Agreement No. CE 18/2002 (EP) Construction of Helipads at Peng Chau and Yung Shue Wan, Lamma Island







Report for
Coral Monitoring Survey
(April 2008)

28th April 2008



Agreement No. CE 18/2002 (EP) Construction of Helipads at Peng Chau and Yung Shue Wan, Lamma Island

Report for Coral Monitoring Survey at Yung Shue Wan in April 2008

Prepared by: miniprojects co. Ltd. Cinotech Consultants Limited

Contents

1	INTRODUCTION	2
	1.1 Project Background	2
2	METHODOLOGY	
	2.1 Impact Monitoring Surveys - Locations	
	2.2 Survey Methods	
	2.3 Coral Monitoring Frequency	
	2.4 Actions on Exceedance of Action & Limit Levels	
3	RESULTS	
	3.1 Impact Monitoring Surveys - April 2008	6
4	SUMMARY AND CONCLUSION	
	4.1 Summary – Monitoring Surveys	
	4.2 Compliance / Event Action Plan	

Appendix

Appendices Ia Photographs of the tagged corals at IMS (26th April 2008) Appendices Ib Photographs of the tagged corals at CMS (26th April 2008)

List of Figures

2.1 Map Showing the Locations of the Impact Monitoring Station (IMS) and Control Monitoring Station (CMS)

List of Tables

- 2.1 Action and Limit Level for Coral Monitoring.
- 3.1 IMS and CMS Physical Conditions.
- 3.2 IMS and CMS Code, Species Name, Area, Percentage of Sedimentation, Bleaching and Mortality of the Tagged Coral Colonies in Initial Coral Survey (21st July 2007), 2 previous (16th February and March 15 2008) and 1 present monitoring surveys (26th April 2008).
- 4.1 Evaluation of Monitoring Results against Action and Limit Levels for Coral Monitoring Surveys.

1 INTRODUCTION

1.1 Project Background


- 1.1.1 Cinotech Consultants Limited has been appointed to formulate a Coral Survey Team to conduct the Marine Ecology Survey for Construction of Helipads at Yung Shue Wan, Lamma Island, Agreement No. CE 18/2002 (EP).
- 1.1.2 miniprojects Company Limited (miniprojects co. Ltd.) have been commissioned by Cinotech Consultants Limited to undertake Coral Monitoring Survey on the tagged hard coral colonies at one Impact Monitoring Station (IMS) and one Control Monitoring Station (CMS).
- 1.1.3 As required by the EM&A manual, frequency of Coral Monitoring Survey is,
 - Twice a week for the first two weeks of works affecting seabed
 - Once a week for the following two weeks if no exceedance is detected
 - Once every two weeks for the 2nd and 3rd months if no exceedance is detected
 - Once a month after the 3rd month until completion of the construction works if not exceedance is detected
- 1.1.4 This is the monthly report presenting the results of the monthly Coral Monitoring Survey (i.e. 15th) conducted in the 8th month (i.e. April 2008) after the commencement of the construction work.

2 METHODOLOGY

2.1 Impact Monitoring Surveys - Locations

2.1.1 The Impact Monitoring Station (IMS) was located at Yung Shue Wan, close to the seabed construction area (Fig. 2.1). In order to identify background environmental perturbations that are not associated with the construction, Sham Wan, which is away from the impact area, was designated as the Control Monitoring Station (CMS; Fig. 2.1). Locations (GPS coordinates) of IMS and CMS, as well as the conditions during monitoring surveys are summarized in Table 3.1.

Fig. 2.1 Map Showing the Locations of the Impact Monitoring Station (IMS) and Control Monitoring Station (CMS)



2.2 Survey Methods

- 2.2.1 At both IMS and CMS, 10 hard coral colonies were tagged for continuous monitoring over the course of construction phase. Dive surveys were conducted to record the health status of the tagged corals, including percentage area of sedimentation, bleaching and partial mortality.
- 2.2.2 The condition of each tagged coral colony was recorded by taking photographs that best represents the entire colony. General physical parameters were recorded for each survey site, including visibility, weather, tidal conditions and water current.
- 2.2.3 The results of the impact monitoring surveys were reviewed with reference to finding of the Initial Coral Survey and the data from CMS collected during the monitoring.

2.3 Coral Monitoring Frequency

- 2.3.1 Monitoring on the tagged corals for degree of sedimentation and area of bleaching shall be conducted at the frequencies indicated below during works affecting the seabed.
 - During the first two weeks of works affecting seabed: twice a week.
 - If no exceedance detected for the first 2 weeks of monitoring: once a week for the following 2 weeks.
 - If no exceedance detected for the first 4 weeks of monitoring: once every two weeks for the 2nd and 3rd months (i.e. October and November 2007, respectively).
 - If no exceedance in the 3rd month of monitoring, coral monitoring shall be conducted once per month (i.e. since December 2007) until completion of the construction works.

2.4 Actions on Exceedance of Action & Limit Levels

2.4.1 Where the coral survey indicates the health conditions of the corals exceed the action and limit levels, the Engineer may direct more frequent monitoring to be carried out until exceedance stops. The action and limit level of coral monitoring is shown in Table 2.1.

Table 2.1. Action and Limit Level for Coral Monitoring

Parameter	Action Level Definition	Limit Level Definition			
Sedimentation	If during Coral Monitoring a 15% increase in the percentage of sediment cover on hard corals occurs at more than 20% of the tagged coral at any one Coral Monitoring Site that is not recorded at the Control Site, then the Action Level is exceeded.	If during Coral Monitoring a 25% increase in the percentage of sediment cover on hard corals occurs at more than 20% of the tagged coral at any one Coral Monitoring Site that is not recorded at the Control Site, then the Limit Level is exceeded.			
Bleaching	If during Coral Monitoring a 15% increase in the percentage of bleaching (bleached white) on hard corals occurs at more than 20% of the tagged coral at any one Coral Monitoring Site that is not recorded at the Control Site, then the Action Level is exceeded.	If during Coral Monitoring a 25% increase in the percentage of bleaching (bleached white) on hard corals occurs at more than 20% of the tagged coral at any one Coral Monitoring Site that is not recorded at the Control Site, then the Limit Level is exceeded.			

- 2.4.2 The Contractor shall take all necessary steps to ensure that the actions of the Contractor are not contributing to the deterioration. These steps shall include, but not be limited to the following:
 - Checking of water quality monitoring data;
 - Checking of all marine plant and equipment; maintenance or replacement of any marine plant or equipment contributing to the deterioration;
 - Checking and maintenance of silt curtains;
 - Review of all working methods; and
 - Reduced construction rate.
- 2.4.3 Upon action level being exceeded and after agreement from the Environmental Specialist and AFCD has been obtained regarding the most appropriate method for reducing the adverse impacts during works affecting the seabed, this mitigated method should then be enacted on the next working day.
- 2.4.4 Upon limit level being exceeded, the Contractor shall suspend all works affecting the seabed until an effective solution is identified. Once the solution has been identified and agreed with the Environmental Specialist and AFCD, construction works affecting seabed may recommence.
- 2.4.5 The Engineer and AFCD shall be kept informed of all steps taken; and written reports and proposals for action shall be passed to the Engineer and AFCD by the Contractor whenever the coral survey shows any adverse impact upon the corals.
- 2.4.6 After the Contractor have implemented the agreed mitigating measures, if the coral surveys indicate the coral condition is unacceptable, additional mitigation measures should be recommended by the Contractor after consulting the Environmental Specialist for the approval of the Engineer and AFCD to rectify the situation. The Engineer can temporarily suspend the site activities until the problem is under control and an acceptable coral condition is restored.
- 2.4.7 In case the Contractor fails to implement the agreed mitigation measures, the Engineer can direct the Contractor to slow down or suspend his work until the Engineer and AFCD is convinced that the mitigation measures have restored the corals to an acceptable condition.
- 2.4.8 The Environmental Specialist shall assess the effectiveness and efficiency of the proposed mitigation measures and/or remedial actions for construction activities affecting the seabed. The performance of the Environmental Monitoring and Audit Programme shall be reviewed and audited by the Environmental Specialist on a quarterly basis. The findings of this review shall be included in the quarterly EM&A summary reports, together with any recommendations to improve the performance of the Environmental Monitoring and Audit Programme.

3 RESULTS

3.1 Monitoring Surveys in April 2008

3.1.1 In April 2008 (i.e. the 8th month after the start of the construction work), both IMS and CMS were surveyed. The date of the survey and physical conditions of each sites are summarized in Table 3.1.

Table 3.1 IMS and CMS – Physical Conditions.

	IMS (Yung Shue Wan)	CMS (Sham Wan)			
GPS Coordinates	N 22°13'28.4	N 22°11'15.0			
GPS Coordinates	E 114°06'30.6	E 114°08'04.0			
Date	26 Apr 08	26 Apr 08			
Sedimentation on	0 to 1	0 to 1			
Rock surfaces (mm)	0 to 1	0 10 1			
Visibility (m)	1 to 1.5	1 to 2			
Weather	Northeast wind; Beaufort force 3;Cloudy	Northeast wind; Beaufort force3;			
weather	Normeast wind, Beautoff force 3, Cloudy	Cloudy			
Tide	Ebb	Ebb			
Current (Knot)	0.5 to 1.0	0.5 to 1.0			
Remark					

3.1.2 Percentages of sedimentation, bleaching and mortality of each tagged colony are presented in Table 3.2. Photographs of each tagged coral in the surveys are illustrated in Appendices Ia and Ib.

IMS

3.1.3 In the current survey, sedimentation on the tagged coral colonies varied from +1% to -3% when compared with the baseline level in July 2007. Increment in sedimentation level was observed in 5 colonies (A04, A06, A07, A09 and A10). Lower sedimentation was found in 1 colony (A05). No bleaching was recorded (Table 3.2; Appendix Ia).

CMS

3.1.4 When compared with the baseline data in July 2007, level of sediment on the colonies was low (Table 3.2). Sedimentation varied from +2% to -1%; decreased in 2 colonies (B06 and B07), and increased in 2 colonies (B04 and B10). No bleaching was recorded. Partial mortality was previously found in 2 colonies (B05 and B06), and no further increase was observed (Table 3.2; Appendix Ib).

Table 3.2 IMS and CMS – Code, Species Name, Area, Percentage of Sedimentation, Bleaching and Mortality of the Tagged Coral Colonies in Initial Coral Survey (21st July 2007), 2 previous (16th February and 15th March 2008) and 1 present monitoring surveys (26th April 2008). "▲" and "▼" indicate increased and decreased in percentage, respectively, when compared with the Initial Coral Survey.

IMS (Yung Shue Wan)

	Coral Species	Area (cm²)	Sedimentation (%)				Bleaching (%)				Mortality (%)			
Code			21 Jul 07 (Baseline)	16 Feb 08	15 Mar 08	26 Apr 08	21 Jul 07 (Baseline)	16 Feb 08	15 Mar 08	26 Apr 08	21 Jul 07 (Baseline)	16 Feb 08	15 Mar 08	26 Apr 08
A01	Favites pentagona	110	1	1	1	1	0	0	0	0	0	0	0	0
A02	Favia rotumana	220	0	1 🛦	0	0	0	0	0	0	0	0	0	0
A03	Platygyra carnosus	400	0	0	0	0	0	0	0	0	0	0	0	0
A04	Favia rotumana	570	0	2 🛦	4 ▲	1 🛦	0	0	0	0	0	0	0	0
A05	Cyphastrea serailia	330	3	0 ▼	2 ▼	0 ▼	0	0	0	0	0	0	0	0
A06	Cyphastrea serailia	190	0	2 🛦	0	2 🛦	0	0	0	0	0	0	0	0
A07	Favites pentagona	200	0	2 🛦	1 🛦	2 🛦	0	0	0	0	0	0	0	0
A08*	Favites pentagona	400	-	-	0	0	-	-	0	0	-	-	0	0
A09	Favites pentagona	300	0	0	0	1 ▲	0	0	0	0	0	0	0	0
A10*	Favites pentagona	1800	-	-	0	1 ▲	-	-	0	0	-	-	0	0

CMS (Sham Wan)

	Coral Species	Area (cm²)	Sedimentation (%)			Bleaching (%)				Mortality (%)				
Code			21 Jul 07 (Baseline)	16 Feb 08	15 Mar 08	26 Apr 08	21 Jul 07 (Baseline)	16 Feb 08	15 Mar 08	26 Apr 08	21 Jul 07 (Baseline)	16 Feb 08	15 Mar 08	26 Apr 08
B01	Favia lizardensis	360	1	0 ▼	0 ▼	1	0	0	0	0	0	0	0	0
B02*	Favites pentagona	750	-	-	0	0	-	-	0	0	-	-	0	0
B03	Psammocora profundacella	440	2	2	5▲	2	0	0	0	0	0	0	0	0
B04	Cyphastrea serailia	220	0	0	0	2 🛦	0	0	0	0	0	0	0	0
B05	Favites abdita	650	2	0 ▼	0 ▼	2	0	0	0	0	0	2 🛦	2 🛦	2 🛦
B06	Leptastrea pruinosa	450	1	0 ▼	0 ▼	0 ▼	0	0	0	0	0	2 🛦	2 🛦	2 🛦
B07	Platygyra acuta	350	1	0 ▼	0 ▼	0	0	0	0	0	0	0	0	0
B08	Leptastrea pruinosa	690	2	1 ▼	2	2	0	0	0	0	0	0	0	0
B09	Leptastrea pruinosa	400	2	0 ▼	2	1 ▼	0	0	0	0	0	0	0	0
B10	Favites pentagona	130	0	1 🛦	0	2 🛦	0	0	0	0	0	0	0	0

^{*}Newly tagged colony in March 2008 survey.

4 SUMMARY AND CONCLUSION

4.1 Summary – Monitoring Surveys

- 4.1.1 In the monitoring surveys conducted in April 2008, the increase of sedimentation level was ≤2% compared to the baseline levels in July 2007 in both IMS and CMS. Bleaching was not recorded in both IMS and CMS. Partial mortality which was previously recorded in 2 colonies (B05 and B06) in CMS did not further increase (Table 3.2).
- 4.1.2 The data from the monitoring surveys showed no significant enhancement in sedimentation, bleaching or mortality in IMS when compared with the CMS.
- 4.1.3 Hence, no adverse impact by the construction activity on the coral community was evidenced.

4.2 Compliance / Event Action Plan

- 4.2.1 The monitoring results were evaluated against the Action and Limit Levels as defined in the EM&A manual (Table 2.1), and is summarized in Table 4.1
- 4.2.2 Overall, the healthy status of the tagged coral colonies was normal, with low levels of sedimentation. No bleaching was observed in both Monitoring and Control Sites. Low levels of morality were observed in Control Sites. Neither action/limit level of sedimentation, bleaching or mortality was exceeded in both monitoring survey conducted in April 2008.

Table 4.1 Evaluation of Monitoring Results against Action and Limit Level for Coral Monitoring Surveys. Note Definition of Action/Limit levels are listed in Table 2.1. "No" indicates NO exceedance.

26th April 2008

Exceedance	Sedimer	ntation	Bleac	hing	Mortality		
Site	Action Level	Limit Level	Action Level	Limit Level	Action Level	Limit Level	
IMS	No	No	No	No	No	No	
CMS	No	No	No	No	No	No	

APPENDIX

Appendices Ia Photographs of the tagged corals at IMS (26th April 2008)

Appendices Ib Photographs of the tagged corals at CMS (26th April 2008)





