

APPENDIX 3A

DETAILS OF CONSTRUCTION NOISE IMPACT ASSESSMENT

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY
 APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT
 Table 3.1.1 Construction Programme

Packages	Description	Year																						
		Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
WA11	Demolition of Buildings - Carpark																							
WA12	Demolition of Buildings - Terminal Bldg																							
WA13	Kai Tak Nullah Stage 1																							
WA14	Road D5 Stage 1																							
WA15	Bridges Over Prince Edward Road - Area 1/ Demolition of Existing Ramps																							
WA16	Bridges Over Prince Edward Road - Area 2																							
WA17	Roads & Drains - Area 1																							
WA18	Roads & Drains - Area 2																							
WA19	Sewerage Connection to TKWPTW																							
WA20	Sewerage Pumping Station in Area 1																							
WA21	Sewerage Pumping Station in Area 2																							
WA22	Hinterland Junction Improvement																							
WB11	Reclamation at Kai Tak Approach Channel																							
WB12	Reclamation of Kwun Tong Typhoon Shelter																							
WB13	Reclamation at Cha Kwo Ling PCWA	x	x	x	x	x	x	x	x	x	x	x												
WB14	Kai Tak Nullah Stage 2																							
WB15	Trunk Drains in Area 4 and 5																							
WB16	Trunk Drains in Area 5 and 6																							
WB17	Relocation of Typhoon Shelter-Bikwater in KTTS																							
WB18	Temporary Relocation of PCWA																							
WB19	Permanent Relocation of PCWA																							
WB20	Reprovision of Vehicular Ferry Pier	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	
WB21	Provision of Tourist Excursion Pier	x	x	x	x	x	x	x	x	x	x	x												
WC11	Drainage Improvement at Hinterland/ Culvert F & Associated TTM/ Culverts A, B, C & D																							
WC12	Trunk Road T2/ Adjacent to Kai Fuk Road/ Underground Portion/ Viaduct in Reclamation																							
WC13	Road D4 - Stage 1																							
WC14	Road D5 - Stage 2																							
WC15	Roads & Drains in Area 4 and 5																							
WC16	Roads & Drains in Area 5 and 6/ Travellator Subway to Ngau Tau kok MTR Station																							
WC17	Roads & Drains at Area 6C/ Hoi Bun Road/ Bridge over outfall U/ Remaining Roadworks in Cha Kwo Ling	x	x	x	x	x	x	x	x	x	x													
WC18	Sewerage Pumping Station in Area 4 and 5																							
WC19	Sewerage Pumping Station in Area 5 and 6																							
WC20	Hinterland Junction Improvement																							
WC21	CKR/T2 Interchange																							
WD11	Reclamation at Kowloon Bay Stage 1/ Earth Bund at Hoi Sum/ Temporary Drain Diversion/ Main Reclamation																							
WD12	Reclamation at Kowloon Bay Stage 2/ Temporary Drain Diversion/ Main Reclamation																							
WD13	Kai Tak Nullah Stage 3																							
WD14	Trunk Drain Area 3 Stage 1/ Culvert S/ Culvert Q/ Culvert P2 on Earth Bund/ Upstream of Culvert P2																							
WD15	Trunk Drain Area 3 Stage 2																							
WD16	Provision of Public Pier																							
WD17	Reprovision of Buoys																							
WD18	Drainage Improvement at Hinterland																							
WD19	Road D4 Stage 2																							
WD20	Roads & Drains at Area 3 - Stage 1																							
WD21	Roads & Drains at Area 3 - Stage 2/ Travellator Subway to Ma Tau Wai Station/ Roads & Drains at Area 3 - Stage 2	x	x	x	x	x	x	x	x															
WD22	Sewerage Pumping Station in Area 3 Stage 1	x	x	x	x	x	x	x	x															

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY
 APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT
 Table 3.1.1 Construction Programme

Packages	Description	2014												2015											
		Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec		
WD23	Sewerage Pumping Station in Area 3 Stage 2	x	x	x	x	x	x	x	x																
WD24	Hinterland Junctions Improvement																								
Future NSR in SEKD (expected occupied date)																									
1A	2005	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
1B	2005	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
1C	2005	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
1D	2005	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
1E	2015																								
1K	2014	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
2A	2015																								
2B	2006	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
2C	2008	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
2D	2007	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
2E	2006	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
2F	2006	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
4A	2012	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
4B2	2012	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
4C	2012	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
4D	2012	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
4E	2012	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
4F	2012	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
4G	2014	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
4H	2014	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
4J	2016																								
4K2	2012	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
4S	2012	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
4L	2012	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
4M	2012	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
4R	2012	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
5A	2014	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
5C	2017																								
5E	2014	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
5G	2015																								
5H	2014	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
5J	2014	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
5K	2015																								
1G	2005	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
1L	2012	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
1Q	2006	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
5L	2014	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
6A	2013	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
1A(S)	2005	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
1C(S)	2005	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
1E(S)	2013	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
1L(S)	2013	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
1P(S)	2009	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
2A(s)	2014	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
2B(S)	2006	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
4E(S)	2012	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
4L(S)	2012	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
4N(S)	2012	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
5J(S)	2014	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			
5L(S)	2014	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x			

Note:
 NSRs in Hoi Sham Areas (Area 3) are the last stages of popu

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT
 APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.2a Coordinates and Assessment Points of Existing Noise Sensitive Receivers

Existing Noise Sensitive Receivers	Assessment Points (Construction Noise/Traffic Noise)	Easting	Northing
Rhythm Gardens	E1/9305	838944	821830
Choi Hung Estate	E2/9309	839195	821775
Richlands Gardens	E3/9315	839218	821311
San Po Kong Area	E4/9504	838154	821425
	E5/9507	838207	821491
Kowloon City Area	E6/9204	837874	821128
	E7/9211	837537	820921
	E8/9216	837526	820600
Mok Cheong St.	E9/9118	837917	820291
Wylor Garden	E10/9111	837944	819871
	E11/9123	837927	819675
To Kwa Wan Area	E12/9120	837605	819418
Laguna City	E13/9401	841281	818570
Cha Kwo Ling	E14/9406	841585	818083
Laguna Verde	E15/9128	837877	818916

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT
 APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.2b Coordinates and Assessment Points of Future Noise Sensitive Receivers

Future Noise Sensitive Receivers	Assessment Points (Construction Noise/Traffic Noise)	Easting	Northing
4C & 4E	F1/8109	839008	819817
4C & 4E	F2/8153	839004	820021
4F & 4L	F3/8202	839208	819858
4F & 4L	F4/8295	839181	819642
4K	F5/8272	839231	819587
4M	F6/8304	839331	819746
4R	F7/8336	839500	819589
5J	F8/8672	840069	819175
5J	F9/8654	839948	819301
4S	F10/8369	839443	819386
4H	F11/8232	839109	819493
4G	F12/8212	839092	819599
4D	F13/8129	838890	819689
4A	F14/8001	838564	820124
4J	F15/8252	839383	819322
5A	F16/8404	839532	819208
5E	F17/8510	839674	819274
5G	F18/8568	839743	819112
5C	F19/8471	839765	818802
5C	F20/8434	839665	819013
4E(S)	F21/7001	839118	820134
5J(S)	F22/7304	839866	819368
5L(S)	F23/7404	840051	819554
4L(S)	F24/7102	839319	819941
4N(S)	F25/7207	839505	819760
5K	F26/8702	839795	819590
5K	F27/8731	839941	819607
1E	F28/8454	838616	821436
1E	F29/8401	838399	821293
1E(S)	F30/7311	838525	821565
1C(S)	F31/7102	838935	820992
2A	F32/8612	838117	821100
2A	F33/8667	837782	820794
2B	F34/8768	838158	820800
2C	F35/8808	838227	820488
2F	F36/8973	837971	820573
2E	F37/8932	838191	820468
2D	F38/8903	838750	820122
1K	F39/8532	838326	821225
1K	F40/8510	838221	821053
1K	F41/8505	838205	821102
2A(S)	F42/7602	837827	820860
2A(S)	F43/7611	837987	820994
2B(S)	F44/7707	838158	820655
1L(S)	F45/7401	838378	821056
1P(S)	F46/7509	838647	820488

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT

APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.3 Construction Noise Assessment - Coordinates of Notional Noise Sources (NNS)

Work Packages	Easting	Northing
WA11-1	837977	821210
WA11-2	838001	821146
WA13-1	838271	821335
WA13-2	838469	821128
WA13-3	838767	820819
WA13-4	838489	820122
WA13-5	838639	821033
WA13-6	838294	821294
WA14-1	838713	820958
WA14-2	838786	821411
WA14-3	838777	821721
WA15-1	838780	821925
WA15-2	838815	821622
WA16-1	838195	821360
WA16-2	838052	821328
WA16-3	837860	821012
WA17-1	839144	821274
WA17-2	839039	820923
WA17-3	838767	821085
WA17-4	838898	821405
WA17-5	839109	821695
WA17-6	838569	821622
WA17-7	838333	821443
WA17-8	837678	820846
WA17-9	838770	821428
WA18-1	838109	820578
WA18-2	837927	820638
WA18-3	838160	820884
WA18-4	838467	821252
WA18-5	838799	821529
WA18-6	838550	820562
WA20-1	838352	821351
WA20-2	839131	820980
WA21-1	837809	820926
WA21-2	837889	820520
WA21-3	838738	820616
WB11-1	838915	820045
WB11-2	839215	819757
WB11-3	839534	819450
WB12-1	840141	819400
WB12-2	840573	818994
WB13-1	840854	818619
WB13-2	841172	818225
WB14-1	838778	820063
WB15-1	839215	819913
WB15-2	839022	819725
WB-16	839841	819225
WB17-1	840741	818413
WB17-2	840916	818182
WB17-3	841067	817981
WB18,19-1	839827	818703
WB18,19-2	840112	818445
WB21	839828	818625
WC11-1	840678	818790
WC11-2	840142	819593
WC12-1	839067	820302
WC12-2	839325	820044
WC12-3	839565	819792
WC12-4	840032	819593
WC12-5	840287	819350
WC12-6	840543	819060
WC12-7	840727	818795
WC12-8	841036	818430
WC13-1	838876	819878
WC13-2	839103	819654
WC13-3	839333	819437
WC13-4	839573	819203
WC13-5	839754	819027
WC14-1	839103	820202
WC14-2	839384	819922

**AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT
APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT**

Table 3.1.3 Construction Noise Assessment - Coordinates of Notional Noise Sources (NNS)

WC14-3	839652	819669
WC14-4	839851	819707
WC15-1	839110	819891
WC15-2	839305	819733
WC15-3	839486	819539
WC15-4	839629	820003
WC15-5	839744	819634
WC15-6	839361	820133
WC16-1	839864	819417
WC16-2	839716	819259
WC16-3	840025	819310
WC16-4	840030	819050
WC16-5	840060	818757
WC16-6	839840	819219
WC17-1	840951	818777
WC17-2	840734	818920
WC17-3	840540	819182
WC-18	839207	820039
WC19-1	840259	819333
WC19-2	840050	818914
WC21-1	838734	820362
WC21-2	838772	820388
WC21-3	838966	820630
WC21-4	839027	820426
WC21-5	839142	820350
WD11-1	838271	819405
WD11-2	838593	819600
WD11-3	838098	819777
WD12-1	838094	819132
WD12-2	838221	819060
WD13	838739	819637
WD14-1	838217	820256
WD14-2	838288	820094
WD14-3	838227	819740
WD14-4	838367	819480
WD14-5	838852	819562
WD14-6	838135	819320
WD14-7	837955	819443
WD14-8	838172	820056
WD15-1	837928	818917
WD15-2	837825	819104
WD16	838534	819510
WD17	838705	819070
WD18-1	837770	819132
WD18-2	837726	819265
WD18-3	837934	819702
WD18-4	837995	819821
WD19-1	838453	819917
WD19-2	838310	819736
WD19-3	838050	819647
WD20-1	838364	819627
WD20-2	838115	819429
WD20-3	837961	819163
WD20-4	838135	820310
WD20-5	838128	820026
WD20-6	838029	819819
WD20-7	837934	819586
WD20-8	837781	819463
WD20-9	837978	819805
WD20-10	837924	819655
WD20-11	838106	819750
WD20-12	837678	819286
WD21-1	838022	818947
WD21-2	837556	819562
WD22	837965	819514
WD23	837866	819203

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT
 APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List		CNP No.	SWL	Ref. No.	SWL	SWL	Number working simultaneously in 30min	Predicted Noise Level			Max. Noise Level for Work Package				
Package	Description	Construction Equipment	Unmitigated	Level 1 Mitigation	Level 2 Mitigation	Unmit.		L1 Mit.	L2 Mit.	Unmit.	L1 Mit.	L2 Mit.			
WA11	Carpark demolition														
	<i>Q1 temporary works</i>														
	Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1	123	115	110					
	Generator, silenced, 75dB(A) at 7m	102	100	102	100	90	1								
	Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	1								
	Breaker, hand-held (pneumatic)	023	117	BS5228: T.6-10	110	105	2								
	Lorry	141	112	BS5228: T.7-59	105	105	1								
	Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	1								
	Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	2								
	<i>Q3 demolition of structures</i>														
	Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	2	129	121	117					
	Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1								
	Lorry	141	112	BS5228: T.7-59	105	105	1								
	Breaker, hand-held (pneumatic)	023	117	BS5228: T.6-10	110	105	4								
	Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	3								
	Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-13	110	105	3								
	Dump truck	067	117	BS5228: T.7-60	110	110	2								
	<i>Temp road to Terminal building</i>														
	<i>Q3 Road formation/Services Excavation</i>														
	Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	1	124	114	112					
	Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-13	110	105	1								
	Dump truck	067	117	BS5228: T.7-60	110	110	1								
	<i>Q4 Surfacing</i>														
	Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	1	117	113	108					
	Lorry	141	112	BS5228: T.7-59	105	105	1								
	Roller, vibratory	186	108	BS5228: T.7-116	106	101	1								
	Asphalt paver	004	109	BS5228: T.11-26	108	103	1								
	<i>Q5 Footway</i>														
	Lorry	141	112	BS5228: T.7-59	105	105	1	118	109	105					
	Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	1								
	Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	1								
	Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	2								
WA12	Demolition of Kai Tak Terminal building (and associated services)														
	<i>Q1 temporary works</i>														
	Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1	123	115	112					
	Generator, silenced, 75dB(A) at 7m	102	100	102	100	90	1								
	Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	1								
	Breaker, hand-held (pneumatic)	023	117	BS5228: T.6-10	110	105	2								
	Lorry	141	112	BS5228: T.7-59	105	105	2								
	Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	1								
	Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	102	2								
	<i>Q2 demolition of structures</i>														
	Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	2	130	121	118					
	Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1								
	Lorry	141	112	BS5228: T.7-59	105	105	1								
	Breaker, hand-held (pneumatic)	023	117	BS5228: T.6-10	110	105	4								
	Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	4								
	Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-13	110	105	4								
	Dump truck	067	117	BS5228: T.7-60	110	110	2								
WA13	Trunk Drain - Kai Tak Nullah - Stage 1 Culvert R construction														
	<i>Q1 Excavation and Formation for Culvert R</i>														
	Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	2	128	119	116					
	Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-13	110	105	3								
	Dump truck	067	117	BS5228: T.7-60	110	110	2								
	Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	12								
	Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2								
	Lorry	141	112	BS5228: T.7-59	105	105	2								
	<i>Q2. Concreting for Culvert R</i>														
	Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2	124	116	111					
	Lorry	141	112	BS5228: T.7-59	105	105	1								
	Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	1								
	Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	2								
	Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	10								
	Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	3								
	Concrete pump, stationary/lorry mounted	047	109	BS5228: T.9-36	106	101	3								
	<i>Q3. Surfacing /Services for Culvert R</i>														
	Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	3	127	119	117					
	Lorry	141	112	BS5228: T.7-59	105	105	3								
	Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	3								
	Dump truck	067	117	BS5228: T.7-60	110	110	3								
	Roller, vibratory	186	108	BS5228: T.7-116	106	101	3								
	Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	3								
	Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	3								
	Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	6								
	<i>Q4 temporary works for demolition of existing nullah</i>														
	Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2	115	106	98					
	Generator, silenced, 75dB(A) at 7m	102	100	102	100	90	2								
	Sheet Piling Plant	0	0	0	0	0	2								
	<i>Q5 demolition of Nullah</i>														
	Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	2	128	121	117					
	Breaker, hand-held (pneumatic)	023	117	BS5228: T.6-10	110	105	8								
	Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	1								
	Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-13	110	105	1								
	Dump truck	067	117	BS5228: T.7-60	110	110	2								
	<i>Q6 demolition of Seawall</i>														
	Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	2	127	119	117					
	Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-13	110	105	2								
	Derrick Barge	061	104	061	104	99	2								

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT

APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List			CNP No.	SWL	Ref. No.	SWL	SWL	Number working simultaneously in 30min	Predicted Noise Level			Max. Noise Level for Work Package		
Package	Description	Construction Equipment	Unmitigated		Level 1 Mitigation		Level 2 Mitigation		Unmit.	L1 Mit.	L2 Mit.	Unmit.	L1 Mit.	L2 Mit.
		Tug Boat	221	110	221		110	2						
		Dump truck	067	117	BSS228: T 7-60		110	2						
	Q7. DSD depot													
		i. excavation												
		Excavator/loader, wheeled/tracked	081	112	BSS228: T 7-24		108	1	118	112	111			
		Dump truck	067	117	BSS228: T 7-60		110	1						
		ii. placing concrete												
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T 10-118		99	1	121	110	104			
		Concrete lorry mixer	044	109	BSS228: T 9-33		96	2						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BSS228: T 7-101		100	1						
		Poker, vibratory, hand-held	170	113	BSS228: T 9-20		102	4						
WA14	Road D5 Stage 1													
	Q1. Diaphragm Walling Works for Road D5 tunnel section													
		i. excavation												
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T 10-118		99	1	124	115	112			
		Piling, diaphragm wall, bentonite filtering plant	162	105	162		105	2						
		Piling, diaphragm wall, hydraulic extractor	163	90	163		90	2						
		Excavator/loader, wheeled/tracked	081	112	BSS228: T 7-24		108	1						
		Breaker, excavator mounted (hydraulic)	028	122	BSS228: T 13-13		119	1						
		Dump truck	067	117	BSS228: T 7-60		110	1						
		ii. placing concrete												
		Piling, diaphragm wall, bentonite filtering plant	162	105	162		105	2	117	111	106			
		Concrete lorry mixer	044	109	BSS228: T 9-33		96	5						
		Concrete pump, stationary/lorry mounted	047	109	BSS228: T 9-36		106	1						
	Q2. Excavation and Strutting													
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T 10-118		99	1	126	119	119			
		Lorry	141	112	BSS228: T 7-59		105	2						
		Water Pump (petrol)	282	103	BSS228: T 7-86		100	4						
		Excavator/loader, wheeled/tracked	081	112	BSS228: T 7-24		108	2						
		Dump truck	067	117	BSS228: T 7-60		110	6						
	Q3. Box Tunnel Construction for D5													
		i. Base Preparation												
		Lorry	141	112	BSS228: T 7-59		105	2	119	115	111			
		Excavator/loader, wheeled/tracked	081	112	BSS228: T 7-24		108	2						
		Compactor, vibratory	050	105	050		105	2						
		Water Pump (petrol)	282	103	BSS228: T 7-86		100	4						
		ii. placing concrete												
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T 10-118		99	1	123	113	107			
		Concrete lorry mixer	044	109	BSS228: T 9-33		96	8						
		Air compressor, standard	001	109	BSS228: T 7-101		100	2						
		Poker, vibratory, hand-held	170	113	BSS228: T 9-20		102	4						
		Water Pump (petrol)	282	103	BSS228: T 7-86		100	4						
		Concrete pump, stationary/lorry mounted	047	109	BSS228: T 9-36		106	1						
	Q4. PIP Tunnel													
		i. Grouting under Kai Tak												
		Grout Mixer	BSS228: T 9-13	108	N/A		108	1	111	111	101			
		Grout Pump	BSS228: T 9-13	108	N/A		108	1						
		ii. Pipe Pile Construction (D5)												
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T 9-18		109	1	119	115	110			
		Lorry	141	112	BSS228: T 7-59		105	2						
		Grout Mixer	BSS228: T 9-13	108	N/A		108	1						
		Grout Pump	BSS228: T 9-13	108	N/A		108	1						
		Water Pump (petrol)	282	103	BSS228: T 7-86		100	8						
	Q5. Backfilling/Surfacing (Services for D5 Tunnel)													
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T 10-118		99	1	125	118	116			
		Lorry	141	112	BSS228: T 7-59		105	2						
		Water Pump (petrol)	282	103	BSS228: T 7-86		100	4						
		Excavator/loader, wheeled/tracked	081	112	BSS228: T 7-24		108	2						
		Dump truck	067	117	BSS228: T 7-60		110	3						
		Roller, vibratory	186	108	BSS228: T 7-116		106	1						
		Concrete lorry mixer	044	109	BSS228: T 9-33		96	2						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BSS228: T 7-101		100	1						
		Poker, vibratory, hand-held	170	113	BSS228: T 9-20		102	4						
	Q6. Piling Works for noise barrier													
		i. Piling												
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T 10-118		99	1	112	103	95			
		Small diameter bored, reverse circulation drilling rig	166	100	N/A		100	1						
		ii. Grouting												
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T 9-18		109	1	115	113	106			
		Grout Mixer	BSS228: T 9-13	108	N/A		108	1						
		Grout Pump	BSS228: T 9-13	108	N/A		108	1						
	Q7. Pile Cap Construction for noise barrier													
		i. excavation												
		Air compressor, standard	001	109	BSS228: T 7-101		100	1	123	116	113			
		Breaker, hand-held (pneumatic)	023	117	BSS228: T 6-10		110	2						
		Excavator/loader, wheeled/tracked	081	112	BSS228: T 7-24		108	1						
		Dump truck	067	117	BSS228: T 7-60		110	1						
		Water Pump (petrol)	282	103	BSS228: T 7-86		100	2						
		ii. placing concrete												
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T 10-118		99	1	121	111	105			
		Concrete lorry mixer	044	109	BSS228: T 9-33		96	5						
		Air compressor, standard	001	109	BSS228: T 7-101		100	1						
		Poker, vibratory, hand-held	170	113	BSS228: T 9-20		102	4						
		Water Pump (petrol)	282	103	BSS228: T 7-86		100	2						
	Q8. Noise Barrier Stem													
		i. Noise Barrier Erection												
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T 10-118		99	1	115	106	105			
		Lorry	141	112	BSS228: T 7-59		105	1						

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT

APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List		CNP No.	SWL	Ref. No.	SWL	SWL	Number working simultaneously in 30min	Predicted Noise Level			Max. Noise Level for Work Package			
Package	Description	Construction Equipment	Unmitigated	Level 1 Mitigation	Level 2 Mitigation	Unmit.		L1 Mit.	L2 Mit.	Unmit.	L1 Mit.	L2 Mit.		
		ii. placing concrete							119	108	102			
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	1						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91	2						
		Air compressor, standard	001	109	BSS228: T.7-101	100	90	1						
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97	2						
	Q9. Road Paving								115	111	108			
		Road roller	185	108	BSS228: T.11-27	104	99	1						
		Asphalt paver	004	107	BSS228: T.11-26	108	103	1						
		Lorry	141	112	BSS228: T.7-59	105	105	1						
WA15 Bridge over Prince Edward Road - Area 1 (Bridge B1, B2, FB1 and FB7)												127	122	117
	Q1. Piling Works (Bridge B1, B2, FB1 and FB7)													
		i. Piling							125	122	117			
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.9-18	109	104	3						
		Piling, large diameter bored	164/165	115	N/A	115	105	3						
		Excavator/loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103	3						
		Dump truck	067	117	BSS228: T.7-60	110	110	2						
		ii. placing concrete							120	112	107			
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	3						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91	3						
		Concrete pump, stationary/lorry mounted	047	109	BSS228: T.9-36	106	101	3						
	Q2. Pile Cap Construction								127	121	117			
		i. excavation												
		Air compressor, standard	001	109	BSS228: T.7-101	100	90	3						
		Breaker, hand-held (pneumatic)	023	117	BSS228: T.6-10	110	105	6						
		Excavator/loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103	3						
		Dump truck	067	117	BSS228: T.7-60	110	110	3						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90	3						
		ii. placing concrete							122	112	105			
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	3						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91	3						
		Air compressor, standard	001	109	BSS228: T.7-101	100	90	3						
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97	3						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90	3						
	Q3. Bridge Pier Construction								117	104	99			
		i. temporary works												
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	3						
		ii. placing concrete							123	114	108			
		Concrete pump, stationary/lorry mounted	047	109	BSS228: T.9-36	106	101	3						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91	3						
		Air compressor, standard	001	109	BSS228: T.7-101	100	90	3						
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97	3						
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	3						
	Q4. Superstructure Construction								117	104	99			
		i. temporary works												
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	3						
		ii. placing concrete							124	115	109			
		Concrete pump, stationary/lorry mounted	047	109	BSS228: T.9-36	106	101	3						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91	6						
		Air compressor, standard	001	109	BSS228: T.7-101	100	90	3						
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97	6						
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	3						
	Q5. Carriageway Construction								118	114	111			
		i. placing asphalt												
		Road roller	185	108	BSS228: T.11-27	104	99	2						
		Asphalt paver	004	107	BSS228: T.11-26	108	103	2						
		Lorry	141	112	BSS228: T.7-59	105	105	2						
		ii. Noise Barrier Erection							118	109	108			
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	2						
		Lorry	141	112	BSS228: T.7-59	105	105	2						
	Q6. Road formation/Services Excavation for Road drain, sewer and water supply pipeworks at road D3 under bridges								124	114	112			
		Excavator/loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103	1						
		Breaker, excavator mounted (hydraulic)	028	112	BSS228: T.11-13	110	105	1						
		Dump truck	067	117	BSS228: T.7-60	110	110	1						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90	1						
	Q7. Laying of Drains and Services for Road drain, sewer and water supply pipeworks at road D3 under bridges								120	112	108			
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	1						
		Lorry	141	112	BSS228: T.7-59	105	105	1						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91	1						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90	1						
		Air compressor, standard	001	109	BSS228: T.7-101	100	90	1						
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97	2						
		Compactor/vibratory	050	105	050	105	100	2						
WA16 Bridge over Prince Edward Road - Area 2 (Bridge D3/E, FB2 and D3W)												124	116	114
	Q1. Piling Works													
		i. excavation							114	115	114			
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	2						
		Piling, large diameter bored	164/165	115	N/A	115	105	2						
		Excavator/loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103	3						
		Dump truck	067	117	BSS228: T.7-60	110	110	2						
		ii. placing concrete							118	110	105			
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	2						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91	2						
		Concrete pump, stationary/lorry mounted	047	109	BSS228: T.9-36	106	101	2						
	Q2. Pile Cap Construction								123	116	113			
		i. excavation												
		Air compressor, standard	001	109	BSS228: T.7-101	100	90	2						
		Breaker, hand-held (pneumatic)	023	117	BSS228: T.6-10	110	105	2						
		Excavator/loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103	1						
		Dump truck	067	117	BSS228: T.7-60	110	110	1						

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT
 APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List		CNP No.	SWL	Ref. No.	SWL	SWL	Number working simultaneously in 30min	Predicted Noise Level			Max. Noise Level for Work Package			
Package	Description	Construction Equipment	Unmitigated	Level 1 Mitigation	Level 2 Mitigation	Unmit.		L1 Mit.	L2 Mit.	Unmit.	L1 Mit.	L2 Mit.		
	ii. placing concrete	Water Pump (petrol)	282	103	BS5228: T 7-86	100	90	2						
		Crane, mobile-barge mounted (diesel)	048	112	BS5228: T 10-118	99	94	2	120	110	105			
		Concrete lorry mixer	044	109	BS5228: T 9-33	96	91	2						
		Air compressor, standard	001	109	BS5228: T 7-101	100	90	2						
		Poker, vibratory, hand-held	170	113	BS5228: T 9-20	102	97	2						
		Water Pump (petrol)	282	103	BS5228: T 9-20	102	97	2						
	Q3. Bridge Pier Construction													
	i. temporary works								115	102	97			
		Crane, mobile-barge mounted (diesel)	048	112	BS5228: T 10-118	99	94	2						
	ii. placing concrete								121	112	107			
		Concrete pump, stationary/lorry mounted	047	109	BS5228: T 9-36	106	101	2						
		Concrete lorry mixer	044	109	BS5228: T 9-33	96	91	2						
		Air compressor, standard	001	109	BS5228: T 7-101	100	90	2						
		Poker, vibratory, hand-held	170	113	BS5228: T 9-20	102	97	2						
		Crane, mobile-barge mounted (diesel)	048	112	BS5228: T 10-118	99	94	2						
	Q4. Superstructure Construction													
	i. temporary works								115	102	97			
		Crane, mobile-barge mounted (diesel)	048	112	BS5228: T 10-118	99	94	2						
	ii. placing concrete													
		Concrete pump, stationary/lorry mounted	047	109	BS5228: T 9-36	106	101	2						
		Concrete lorry mixer	044	109	BS5228: T 9-33	96	91	4						
		Air compressor, standard	001	109	BS5228: T 7-101	100	90	2						
		Poker, vibratory, hand-held	170	113	BS5228: T 9-20	102	97	4						
		Crane, mobile-barge mounted (diesel)	048	112	BS5228: T 10-118	99	94	2						
	Q5. Carriageway Construction													
	i. placing asphalt								118	114	111			
		Road roller	185	108	BS5228: T 11-27	104	99	2						
		Asphalt paver	004	109	BS5228: T 11-26	108	103	2						
		Lorry	141	112	BS5228: T 7-59	105	105	2						
SWA17	Road and Drains at Area 1								120	121	118			
	Q1. Excavation and Formation for culvert V1, V1-V2 and V2								129	120	117			
		Excavator/loader, wheeled/tracked	081	112	BS5228: T 7-24	108	103	3						
		Breaker, excavator mounted (hydraulic)	028	122	BS5228: T 11-13	110	105	3						
		Dump truck	067	117	BS5228: T 7-60	110	110	3						
		Water Pump (petrol)	282	103	BS5228: T 7-86	100	90	12						
		Crane, mobile-barge mounted (diesel)	048	112	BS5228: T 10-118	99	94	3						
		Lorry	141	112	BS5228: T 7-59	105	105	1						
	Q2. Concreting for culvert V1, V1-V2 and V2								124	117	113			
		Crane, mobile-barge mounted (diesel)	048	112	BS5228: T 10-118	99	94	3						
		Lorry	141	112	BS5228: T 7-59	105	105	3						
		Concrete lorry mixer	044	109	BS5228: T 9-33	96	91	9						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T 7-101	100	90	2						
		Water Pump (petrol)	282	103	BS5228: T 7-86	100	90	12						
		Poker, vibratory, hand-held	170	113	BS5228: T 9-20	102	97	2						
		Concrete pump, stationary/lorry mounted	047	109	BS5228: T 9-36	106	101	2						
	Q3. Surfacing /Services for culvert V1, V1-V2 and V2								126	119	116			
		Crane, mobile-barge mounted (diesel)	048	112	BS5228: T 10-118	99	94	2						
		Lorry	141	112	BS5228: T 7-59	105	105	2						
		Excavator/loader, wheeled/tracked	081	112	BS5228: T 7-24	108	103	2						
		Dump truck	067	117	BS5228: T 7-60	110	110	2						
		Roller, vibratory	186	108	BS5228: T 7-116	106	101	2						
		Concrete lorry mixer	044	109	BS5228: T 9-33	96	91	3						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T 7-101	100	90	2						
		Poker, vibratory, hand-held	170	113	BS5228: T 9-20	102	97	8						
	Q4. Road formation/Services Excavation for D1, D2 and D3, etc.								130	121	118			
		Excavator/loader, wheeled/tracked	081	112	BS5228: T 7-24	108	103	4						
		Breaker, excavator mounted (hydraulic)	028	122	BS5228: T 11-13	110	105	4						
		Dump truck	067	117	BS5228: T 7-60	110	110	4						
		Water Pump (petrol)	282	103	BS5228: T 7-86	100	90	8						
	Q5. Laying of Drains and Services D1, D2 and D3, etc.								127	118	114			
		Crane, mobile-barge mounted (diesel)	048	112	BS5228: T 10-118	99	94	4						
		Lorry	141	112	BS5228: T 7-59	105	105	4						
		Concrete lorry mixer	044	109	BS5228: T 9-33	96	91	4						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T 7-101	100	90	4						
		Water Pump (petrol)	282	103	BS5228: T 7-86	100	90	4						
		Poker, vibratory, hand-held	170	113	BS5228: T 9-20	102	97	16						
		Compactor, vibratory	050	105	050	105	100	4						
	Q6. Surfacing D1, D2 and D3, etc.								123	119	115			
		Excavator/loader, wheeled/tracked	081	112	BS5228: T 7-24	108	103	4						
		Lorry	141	112	BS5228: T 7-59	105	105	4						
		Roller, vibratory	186	108	BS5228: T 7-116	106	101	4						
		Asphalt paver	004	109	BS5228: T 11-26	108	102	4						
	Q7. Footway D1, D2 and D3, etc.								125	115	113			
		Crane, mobile-barge mounted (diesel)	048	112	BS5228: T 10-118	99	94	4						
		Lorry	141	112	BS5228: T 7-59	105	105	4						
		Concrete lorry mixer	044	109	BS5228: T 9-33	96	91	4						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T 7-101	100	90	4						
		Poker, vibratory, hand-held	170	113	BS5228: T 9-20	102	97	8						
	Q8. Excavation and Formation for SW2 and SW3								127	119	116			
		Excavator/loader, wheeled/tracked	081	112	BS5228: T 7-24	108	103	2						
		Breaker, excavator mounted (hydraulic)	028	122	BS5228: T 11-13	110	105	2						

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT
 APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List		CNP No.	SWL	Ref. No.	SWL	SWL	Number working simultaneously in 30min	Predicted Noise Level			Max. Noise Level for Work Package			
Package	Description	Construction Equipment	Unmitigated	Level 1 Mitigation	Level 2 Mitigation	Unmit.		L1 Mit.	L2 Mit.	Unmit.	L1 Mit.	L2 Mit.		
		Dump truck	067	117	BSS228: T.7-60	110	110	2						
		Water Pump (petrol)	282	102	BSS228: T.7-86	100	90	4						
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.9-18	109	104	2						
		Lorry	141	112	BSS228: T.7-59	105	105	2						
	Q9. Concreting for SW2 and SW3								123	114	110			
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	2						
		Lorry	141	112	BSS228: T.7-59	105	105	2						
		Concrete lorry mixer	044	109	BSS228: T.9-32	96	91	4						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BSS228: T.7-101	100	90	2						
		Water Pump (petrol)	282	102	BSS228: T.7-86	100	90	8						
		Poker, vibratory, hand-held	170	112	BSS228: T.9-20	102	97	4						
	Q10. Surfacing /Services for SW2 and SW3								125	118	116			
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	2						
		Lorry	141	112	BSS228: T.7-59	105	105	2						
		Excavator/loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103	2						
		Dump truck	067	117	BSS228: T.7-60	110	110	2						
		Roller, vibratory	186	108	BSS228: T.7-116	106	101	2						
		Concrete lorry mixer	044	109	BSS228: T.9-32	96	91	4						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BSS228: T.7-101	100	90	2						
		Poker, vibratory, hand-held	170	112	BSS228: T.9-20	102	97	4						
	Q11. E&M, Finish for SW2 and SW3								118	109	108			
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	2						
		Lorry	141	112	BSS228: T.7-59	105	105	2						
	Q12. Piling Works for noise barrier								118	109	101			
	i. Piling													
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	4						
		Small diameter bored, reverse circulation drilling r	166	100	N/A	100	90	4						
	ii. placing concrete								121	119	112			
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.9-18	109	104	4						
		Grout Mixer	BSS228: T.9-13	108	N/A	108	98	4						
		Grout Pump	BSS228: T.9-13	108	N/A	108	98	4						
	Q13. Pile Cap Construction for noise barrier								125	119	116			
	i. excavation													
		Air compressor, standard	001	100	BSS228: T.7-101	100	90	2						
		Breaker, hand-held (pneumatic)	023	117	BSS228: T.6-10	110	105	4						
		Excavator/loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103	2						
		Dump truck	067	117	BSS228: T.7-60	110	110	2						
		Water Pump (petrol)	282	102	BSS228: T.7-86	100	90	2						
	ii. placing concrete								122	111	105			
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	2						
		Concrete lorry mixer	044	109	BSS228: T.9-32	96	91	2						
		Air compressor, standard	001	100	BSS228: T.7-101	100	90	2						
		Poker, vibratory, hand-held	170	112	BSS228: T.9-20	102	97	4						
		Water Pump (petrol)	282	102	BSS228: T.7-86	100	90	2						
	Q14. Noise Barrier Stem								118	109	108			
	i. Noise Barrier Erection													
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	2						
		Lorry	141	112	BSS228: T.7-59	105	105	2						
	ii. placing concrete								122	110	105			
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	2						
		Concrete lorry mixer	044	109	BSS228: T.9-32	96	91	2						
		Air compressor, standard	001	100	BSS228: T.7-101	100	90	2						
		Poker, vibratory, hand-held	170	112	BSS228: T.9-20	102	97	4						
		Water Pump (petrol)	282	102	BSS228: T.7-86	100	90	2						
	Q15. Low Noise Road Surfacing to Prince Edward Road East								117	116	108			
		Road planer or miller	184	111	184	111	96	2						
		Road Roller	185	108	BSS228: T.11-27	104	99	2						
		Asphalt paver	004	100	BSS228: T.11-26	108	103	2						
WA18	Roads and Drains at Area 2								130	121	118			
	Q1. Excavation and Formation for culvert V4								128	119	117			
		Excavator/loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103	2						
		Breaker, excavator mounted (hydraulic)	028	122	BSS228: T.11-32	110	105	2						
		Dump truck	067	117	BSS228: T.7-60	110	110	4						
		Water Pump (petrol)	282	102	BSS228: T.7-86	100	90	4						
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	1						
		Lorry	141	112	BSS228: T.7-59	105	105	1						
	Q2. Concreting for culvert V4								122	114	109			
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	1						
		Lorry	141	112	BSS228: T.7-59	105	105	1						
		Concrete lorry mixer	044	109	BSS228: T.9-32	96	91	3						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BSS228: T.7-101	100	90	1						
		Water Pump (petrol)	282	102	BSS228: T.7-86	100	90	8						
		Poker, vibratory, hand-held	170	112	BSS228: T.9-20	102	97	4						
		Concrete pump, stationary lorry mounted	047	109	BSS228: T.9-36	106	101	1						
	Q3. Surfacing /Services for culvert V4								123	115	113			
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	1						
		Lorry	141	112	BSS228: T.7-59	105	105	1						
		Excavator/loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103	1						
		Dump truck	067	117	BSS228: T.7-60	110	110	1						
		Roller, vibratory	186	108	BSS228: T.7-116	106	101	1						
		Concrete lorry mixer	044	109	BSS228: T.9-32	96	91	1						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BSS228: T.7-101	100	90	1						
		Poker, vibratory, hand-held	170	112	BSS228: T.9-20	102	97	4						
	Q4 Road formation/Services Excavation for D1 and D3, etc.								130	121	118			
		Excavator/loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103	4						
		Breaker, excavator mounted (hydraulic)	028	122	BSS228: T.11-32	110	105	4						
		Dump truck	067	117	BSS228: T.7-60	110	110	4						
		Water Pump (petrol)	282	102	BSS228: T.7-86	100	90	8						

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT
 APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List			CNP No.	SWL	Ref. No.	SWL	SWL	Number working simultaneously in 30min	Predicted Noise Level			Max. Noise Level for Work Package			
Package	Description	Construction Equipment	Unmitigated	Level 1 Mitigation	Level 2 Mitigation	Unmit.	L1 Mit.		L2 Mit.	Unmit.	L1 Mit.	L2 Mit.			
Q5. Laying of Drains and Services for D1 and D3, etc.													125	117	114
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	4							
		Lorry	141	112	BS5228: T.7-59	105	105	4							
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	4							
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	4							
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	4							
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	8							
		Compactor, vibratory	050	105	050	105	100	4							
Q6. Surfacing for D1 and D3, etc.													123	119	115
		Excavator loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	4							
		Lorry	141	112	BS5228: T.7-59	105	105	4							
		Roller, vibratory	186	108	BS5228: T.7-116	106	101	4							
		Asphalt paver	004	109	BS5228: T.11-26	108	103	4							
Q7. Footway for D1 and D3, etc.													125	115	113
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	4							
		Lorry	141	112	BS5228: T.7-59	105	105	4							
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	4							
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	4							
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	8							
Q8. Excavation and Formation for subway extension													124	115	113
		Excavator loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	1							
		Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-13	110	105	1							
		Dump truck	067	117	BS5228: T.7-60	110	110	1							
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	4							
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1							
		Lorry	141	112	BS5228: T.7-59	105	105	1							
Q9. Concreting for subway extension													122	112	108
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1							
		Lorry	141	112	BS5228: T.7-59	105	105	1							
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	4							
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	1							
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	4							
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	4							
Q10. Surfacing/Services for subway extension													122	115	113
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1							
		Lorry	141	112	BS5228: T.7-59	105	105	1							
		Excavator loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	1							
		Dump truck	067	117	BS5228: T.7-60	110	110	1							
		Roller, vibratory	186	108	BS5228: T.7-116	106	101	1							
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	2							
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	1							
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	2							
Q11. E&M/Finish for subway extension													115	106	105
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1							
		Lorry	141	112	BS5228: T.7-59	105	105	1							
Q12. Piling Works for noise barrier													117	107	100
i. Piling															
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	3							
		Small diameter bored, reverse circulation drilling rig	166	100	N/A	100	90	3							
ii. placing concrete													119	116	107
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	3							
		Grout Mixer	BS5228: T.9-13	108	N/A	108	98	3							
		Grout Pump	BS5228: T.9-13	108	N/A	108	98	3							
Q13. Pile Cap Construction for noise barrier													124	118	114
i. excavation															
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	3							
		Breaker, hand-held (pneumatic)	027	117	BS5228: T.6-10	110	105	3							
		Excavator loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	2							
		Dump truck	067	117	BS5228: T.7-60	110	110	1							
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	2							
ii. placing concrete													121	111	105
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2							
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	3							
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	3							
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	3							
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	3							
Q14. Noise Barrier Stem													118	107	106
i. Noise Barrier Erection															
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	3							
		Lorry	141	112	BS5228: T.7-59	105	105	1							
ii. placing concrete													121	112	106
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2							
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	3							
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	3							
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	6							
Q15. Low Noise Road Surfacing to Prince Edward Road East													117	116	108
		Road planer or miller	184	111	184	111	96	2							
		Road Roller	185	108	BS5228: T.11-27	104	96	2							
		Asphalt paver	004	109	BS5228: T.11-26	108	103	2							
WA19	Sewerage connection to TKW treatment plant (plants can be at any location along the route)											127	117	115	
Q1. Excavation													127	117	115
		Excavator loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	2							
		Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-13	110	105	2							
		Dump truck	067	117	BS5228: T.7-60	110	110	2							
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	2							
Q2. Laying of Drains and Services													122	113	110
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2							
		Lorry	141	112	BS5228: T.7-59	105	105	2							
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	2							

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT
 APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List		CNP No.	SWL	Ref. No.	SWL	SWL	Number working simultaneously in 30min	Predicted Noise Level			Max. Noise Level for Work Package				
Package	Description	Construction Equipment	Unmitigated	Level 1 Mitigation	Level 2 Mitigation	Unmit.		L1 Mit.	L2 Mit.	Unmit.	L1 Mit.	L2 Mit.			
		Air compressor, standard	001	109	BSS228: T.7-101	100	90	2							
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90	2							
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97	2							
		Compactor, vibratory	050	105	050	105	100	2							
	Q3. Surfacing								120	116	112				
		Excavator-loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103	2							
		Lorry	141	112	BSS228: T.7-59	105	105	2							
		Roller, vibratory	186	108	BSS228: T.7-116	106	101	2							
		Asphalt paver	004	109	BSS228: T.11-26	108	103	2							
WA20.21	Sewerage pumping station														
	<i>(Plants listed are per pumping station)</i>														
	Q1. temporary works								112	99	94		123	117	113
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	1							
		Sheet Piling Plant		0		0	0	1							
	Q2. Piling Works														
	i. excavation								121	117	112				
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	1							
		Preboring, oscillatory	165	115	N/A	115	105	1							
		Excavator-loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103	1							
		Dump truck	067	117	BSS228: T.7-60	110	110	1							
	ii. placing grout								112	99	94				
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	1							
		Grout Mixer	BSS228: T.9-13	108	N/A	108	98								
		Grout Pump	BSS228: T.9-12	108	N/A	108	98								
	Q3. Pile Cap Construction														
	i. excavation								123	116	113				
		Air compressor, standard	001	109	BSS228: T.7-101	100	90	1							
		Breaker, hand-held (pneumatic)	023	117	BSS228: T.6-10	110	105	2							
		Excavator-loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103	1							
		Dump truck	067	117	BSS228: T.7-60	110	110	1							
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	1							
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90	4							
	ii. placing concrete								120	111	105				
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	1							
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91	2							
		Air compressor, standard	001	109	BSS228: T.7-101	100	90	1							
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97	2							
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90	2							
		Concrete pump, stationary/lorry mounted	047	109	BSS228: T.9-26	106	101	1							
	Q4. Superstructure Construction														
	i. temporary works								112	99	94				
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	1							
	ii. placing concrete								119	110	105				
		Concrete pump, stationary/lorry mounted	047	109	BSS228: T.9-26	106	101	1							
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91	2							
		Air compressor, standard	001	109	BSS228: T.7-101	100	90	1							
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97	2							
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	1							
WA22	Hinterland Junctions Improvement														
	<i>(Plants listed are per junction)</i>														
	Q1. Road Excavation								124	114	107				
		Excavator-loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103	1							
		Breaker, excavator mounted (hydraulic)	028	122	BSS228: T.11-13	110	105	1							
		Dump truck	067	117	BSS228: T.7-60	110	90	1							
	Q2. Surfacing								115	111	108				
		Lorry	141	112	BSS228: T.7-59	105	105	1							
		Roller, vibratory	186	108	BSS228: T.7-116	106	101	1							
		Asphalt paver	004	109	BSS228: T.11-26	108	103	1							
	Q3. Footway								118	109	106				
		Lorry	141	112	BSS228: T.7-59	105	105	1							
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91	1							
		Air compressor, silenced, 75dB(A) at 7m	002	100	BSS228: T.7-101	100	90	1							
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97	2							

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT
 APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List	CNP No.	SPL	Ref. No.	SPL	SPL	Number working simultaneously in 30min	Predicted Noise Level			Max. Noise Level for Work Package		
							Unmitigated	Level 1 Mitigation	Level 2 Mitigation	Unmit.	L1 Mit.	L2 Mit.
Package	Description	Construction Equipment	dB(A)	dB(A)	dB(A)		dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)
WB11	Reclamation at Kai Tak Approach channel											
	Q1 demolition of structures											
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	126	118	114		
		Breaker, hand-held (pneumatic)	022	117	BS5228: T.6-10	110	105					
		Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103					
		Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-12	110	105					
		Dump truck	067	117	BS5228: T.7-60	110	110					
								126	118	115		
		Q2 demolition of taxiway bridges										
		Air compressor, standard	004	109	BS5228: T.7-101	100	90					
		Breaker, hand-held (pneumatic)	022	117	BS5228: T.6-10	110	105					
		Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-12	110	105					
		Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103					
		Dump truck	067	117	BS5228: T.7-60	110	110					
		Q3 demolition of armour rack										
		Derrick barge	061	104	061	104	99	111	111	110		
		Tug Boat	221	110	221	110	110					
		Q4 Temporary Drain Diversion to R and S										
		Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	124	117	115		
		Dump truck	067	117	BS5228: T.7-60	110	110					
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91					
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90					
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90					
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97					
		Concrete pump, stationary/lorry mounted	047	109	BS5228: T.9-36	106	101					
		Q5. Reclamation at Kai Tak Approach Channel										
		Derrick barge	061	104	061	104	99	128	122	121		
		Tug Boat	221	110	221	110	110					
		Split Barge	061	104	061	104	99					
		Dump truck	067	117	BS5228: T.7-60	110	110					
		Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103					
		Roller, Vibratory	186	108	BS5228: T.7-116	106	101					
WB12	Reclamation at Kwun Tong Typhoon shelter											
	Q1 demolition of structures											
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	128	120	116		
		Breaker, hand-held (pneumatic)	022	117	BS5228: T.6-10	110	105					
		Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103					
		Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-12	110	105					
		Dump truck	067	117	BS5228: T.7-60	110	110					
		Q2 demolition of armour rack										
		Derrick barge	061	104	061	104	99	111	111	110		
		Tug Boat	221	110	221	110	110					
		Q3. Reclamation										
		Derrick barge	061	104	061	104	99	128	122	121		
		Tug Boat	221	110	221	110	110					
		Split Barge	061	104	061	104	99					
		Dump truck	067	117	BS5228: T.7-60	110	110					
		Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103					
		Roller, Vibratory	186	108	BS5228: T.7-116	106	101					
		Q4 Excavation and Foundation for Culvert T construction										
		Percussive Piling Plant	??	0	0	0	0	127	119	116		
		Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103					
		Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-12	110	105					
		Dump truck	067	117	BS5228: T.7-60	110	110					
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90					
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94					
		Lorry	141	112	BS5228: T.7-59	105	105					
		Q5. Concreting for Culvert T construction										
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	122	116	111		
		Lorry	141	112	BS5228: T.7-59	105	105					
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91					
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90					
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90					
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97					
		Concrete pump, stationary/lorry mounted	047	109	BS5228: T.9-36	106	101					
		Q6. Surfacing/Services for Culvert T construction										
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	123	115	113		
		Lorry	141	112	BS5228: T.7-59	105	105					
		Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103					
		Dump truck	067	117	BS5228: T.7-60	110	110					
		Roller, vibratory	186	108	BS5228: T.7-116	106	101					
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91					
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90					
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97					
WB13	Reclamation at Cha Kwo Ling Public Cargo working Area											
	Q1 demolition of structures											
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	127	119	116		
		Breaker, hand-held (pneumatic)	022	117	BS5228: T.6-10	110	105					
		Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103					
		Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-12	110	105					
		Dump truck	067	117	BS5228: T.7-60	110	110					
		Q2. Reclamation for RTS, PFBP and Cha Kwo Ling Area										
		Derrick barge	061	104	061	104	99	128	122	121		
		Tug Boat	221	110	221	110	110					
		Split Barge	061	104	061	104	99					
		Dump truck	067	117	BS5228: T.7-60	110	110					
		Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103					
		Roller, Vibratory	186	108	BS5228: T.7-116	106	101					
		Q3. Laying of Drains and Services to new seawall position										
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	123	115	113		
		Lorry	141	112	BS5228: T.7-59	105	105					
		Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103					

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List			CNP No.	SPL	Ref. No.	SPL	SPL	Predicted Noise Level	Max. Noise Level for Work Package				
Package	Description	Construction Equipment	Unmitigated	Level 1 Mitigation	Level 2 Mitigation	Number working simultaneously in 30min	Unmit.		L1 Mit.	L2 Mit.	Unmit.	L1 Mit.	L2 Mit.
		Pump truck	067	117	BSS228: T.7-60	110	110						
		Roller, vibratory	186	108	BSS228: T.7-116	106	101						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BSS228: T.7-101	100	90						
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97						
WB14	Trunk Drains R - Stage 2										120	120	117
	Q1. Diaphragm Walling Works												
	i. excavation												
		Crane, mobile-barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	127	118	115			
		Piling, diaphragm wall/bentonite filtering plant	162	105	162	105	100						
		Piling, diaphragm wall/hydraulic extractor	163	90	163	90	85						
		Excavator/loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Breaker, excavator mounted (hydraulic)	028	122	BSS228: T.11-13	110	105						
		Dump truck	067	117	BSS228: T.7-60	110	110						
	ii. placing concrete												
		Piling, diaphragm wall/bentonite filtering plant	162	105	162	105	100	116	111	106			
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91						
		Concrete pump, stationary/lorry mounted	047	109	BSS228: T.9-36	106	101						
	Q2 Excavation and Strutting												
		Crane, mobile-barge mounted (diesel)	048	112	BSS228: T.10-118	99	94						
		Lorry	141	112	BSS228: T.7-59	105	105						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
		Excavator/loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Dump truck	067	117	BSS228: T.7-60	110	110						
	Q3. Box Tunnel Construction												
	i. Base Preparation												
		Lorry	141	112	BSS228: T.7-59	105	105	119	115	111			
		Excavator/loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Compactor, vibratory	050	105	050	105	100						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
	ii. placing concrete												
		Crane, mobile-barge mounted (diesel)	048	112	BSS228: T.10-118	99	94						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91						
		Air compressor, standard	001	109	BSS228: T.7-101	100	90						
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
		Concrete pump, stationary/lorry mounted	047	109	BSS228: T.9-36	106	101						
	Q4 Excavation and Foundation for culvert construction												
		Percussive Piling Plant	22	0	22	0	0						
		Excavator/loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Breaker, excavator mounted (hydraulic)	028	122	BSS228: T.11-13	110	105						
		Dump truck	067	117	BSS228: T.7-60	110	110						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
		Crane, mobile-barge mounted (diesel)	048	112	BSS228: T.10-118	99	94						
		Lorry	141	112	BSS228: T.7-59	105	105						
	Q5. Concreting for culvert construction												
		Crane, mobile-barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	123	115	110			
		Lorry	141	112	BSS228: T.7-59	105	105						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BSS228: T.7-101	100	90						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97						
		Concrete pump, stationary/lorry mounted	047	109	BSS228: T.9-36	106	101						
	Q6. Surfacing /Services for culvert construction												
		Crane, mobile-barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	123	116	114			
		Lorry	141	112	BSS228: T.7-59	105	105						
		Excavator/loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Dump truck	067	117	BSS228: T.7-60	110	110						
		Roller, vibratory	186	108	BSS228: T.7-116	106	101						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BSS228: T.7-101	100	90						
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97						
	Q7. Backfilling to temporary open channel and reinstate the upstream connection												
		Air compressor, standard	001	109	BSS228: T.7-101	100	90	125	119	117			
		Breaker, hand-held (pneumatic)	028	117	BSS228: T.6-10	110	105						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
		Excavator/loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Dump truck	067	117	BSS228: T.7-60	110	110						
		Roller, vibratory	186	108	BSS228: T.7-116	106	101						
WB15	Trunk Drains in Area 4 and 5										126	118	117
	Q1. Diaphragm Walling Works for Advance work of Road D4 Tunnel												
	i. excavation												
		Crane, mobile-barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	124	115	112			
		Piling, diaphragm wall/bentonite filtering plant	162	105	162	105	100						
		Piling, diaphragm wall/hydraulic extractor	163	90	163	90	85						
		Excavator/loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Breaker, excavator mounted (hydraulic)	028	122	BSS228: T.11-13	110	105						
		Dump truck	067	117	BSS228: T.7-60	110	110						
	ii. placing concrete												
		Piling, diaphragm wall/bentonite filtering plant	162	105	162	105	100	117	110	105			
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91						
		Concrete pump, stationary/lorry mounted	047	109	BSS228: T.9-36	106	101						
	Q2 Excavation and Strutting												
		Crane, mobile-barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	123	117	116			
		Lorry	141	112	BSS228: T.7-59	105	105						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
		Excavator/loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Dump truck	067	117	BSS228: T.7-60	110	110						
	Q3. Box Tunnel Construction for Advance work of Road D4 Tunnel												
	i. Base Preparation												
		Lorry	141	112	BSS228: T.7-59	105	105	118	114	110			
		Excavator/loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Compactor, vibratory	050	105	050	105	100						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
	ii. placing concrete												
		Crane, mobile-barge mounted (diesel)	048	112	BSS228: T.10-118	99	94	122	113	107			

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT
 APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List		CNP No.	SPL	Ref. No.	SPL	SPL	Number working simultaneously in 30min	Predicted Noise Level			Max. Noise Level for Work Package		
Package	Description	Construction Equipment	Unmitigated	Level 1 Mitigation	Level 2 Mitigation	Unmit.		L1 Mit.	L2 Mit.	Unmit.	L1 Mit.	L2 Mit.	
		Concrete lorry mixer	044	109	BS5228: T 9-33	96	91	5					
		Air compressor, standard	001	109	BS5228: T 7-101	100	90	2					
		Poker, vibratory, hand-held	170	113	BS5228: T 9-20	102	97	4					
		Water Pump (petrol)	282	103	BS5228: T 7-86	100	90	4					
		Concrete pump, stationary lorry mounted	047	109	BS5228: T 9-36	106	101	1					
		Q4 Excavation and Foundation for multicells box culvert S through KTAC and runway							128	119	117		
		Percussive Piling Plant	27	0	0	0	0	2					
		Excavator/loader, wheeled/tracked	081	112	BS5228: T 7-24	108	103	2					
		Breaker, excavator mounted (hydraulic)	028	122	BS5228: T 11-13	110	105	2					
		Dump truck	067	117	BS5228: T 7-60	110	110	3					
		Water Pump (petrol)	282	103	BS5228: T 7-86	100	90	16					
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T 10-118	99	94	2					
		Lorry	141	112	BS5228: T 7-59	105	105	1					
		Q5. Concreting for multicells box culvert S through KTAC and runway							123	115	111		
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T 10-118	99	94	2					
		Lorry	141	112	BS5228: T 7-59	105	105	2					
		Concrete lorry mixer	044	109	BS5228: T 9-33	96	91	4					
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T 7-101	100	90	2					
		Water Pump (petrol)	282	103	BS5228: T 7-86	100	90	8					
		Poker, vibratory, hand-held	170	113	BS5228: T 9-20	102	97	2					
		Concrete pump, stationary lorry mounted	047	109	BS5228: T 9-36	106	101	2					
		Q6. Surfacing /Services for multicells box culvert S through KTAC and runway							123	115	113		
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T 10-118	99	94	1					
		Lorry	141	112	BS5228: T 7-59	105	105	1					
		Excavator/loader, wheeled/tracked	081	112	BS5228: T 7-24	108	103	1					
		Dump truck	067	117	BS5228: T 7-60	110	110	1					
		Roller, vibratory	186	108	BS5228: T 7-116	106	101	1					
		Concrete lorry mixer	044	109	BS5228: T 9-33	96	91	1					
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T 7-101	100	90	1					
		Poker, vibratory, hand-held	170	113	BS5228: T 9-20	102	97	4					
		Q7. Backfilling to temporary open channel and reinstatement							124	119	115		
		Air compressor, standard	001	109	BS5228: T 7-101	100	90	1					
		Breaker, hand-held (pneumatic)	023	117	BS5228: T 6-10	110	105	2					
		Water Pump (petrol)	282	103	BS5228: T 7-86	100	90	4					
		Excavator/loader, wheeled/tracked	081	112	BS5228: T 7-24	108	103	3					
		Dump truck	067	117	BS5228: T 7-60	110	110	2					
		Roller, vibratory	186	108	BS5228: T 7-116	106	101	2					
		WB16 Trunk Drains in Area 2 and 6							129	120	118		
		Q1 Excavation and Foundation for box culvert							129	120	118		
		Percussive Piling Plant	27	0	27	0	0	1					
		Excavator/loader, wheeled/tracked	081	112	BS5228: T 7-24	108	103	3					
		Breaker, excavator mounted (hydraulic)	028	122	BS5228: T 11-13	110	105	3					
		Dump truck	067	117	BS5228: T 7-60	110	110	5					
		Water Pump (petrol)	282	103	BS5228: T 7-86	100	90	12					
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T 10-118	99	94	3					
		Lorry	141	112	BS5228: T 7-59	105	105	3					
		Q2. Concreting for box culvert							124	117	113		
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T 10-118	99	94	3					
		Lorry	141	112	BS5228: T 7-59	105	105	3					
		Concrete lorry mixer	044	109	BS5228: T 9-33	96	91	6					
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T 7-101	100	90	3					
		Water Pump (petrol)	282	103	BS5228: T 7-86	100	90	10					
		Poker, vibratory, hand-held	170	113	BS5228: T 9-20	102	97	4					
		Concrete pump, stationary lorry mounted	047	109	BS5228: T 9-36	106	101	3					
		Q3. Surfacing /Services for box culvert							123	115	113		
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T 10-118	99	94	1					
		Lorry	141	112	BS5228: T 7-59	105	105	1					
		Excavator/loader, wheeled/tracked	081	112	BS5228: T 7-24	108	103	1					
		Dump truck	067	117	BS5228: T 7-60	110	110	1					
		Roller, vibratory	186	108	BS5228: T 7-116	106	101	1					
		Concrete lorry mixer	044	109	BS5228: T 9-33	96	91	1					
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T 7-101	100	90	1					
		Poker, vibratory, hand-held	170	113	BS5228: T 9-20	102	97	4					
		WB17 Relocation of Typhoon Shelter Drainwater in KTFS (Area 5B)							113	113	111		
		Derrick barge	061	104	061	104	99	4					
		Tug Boat	201	110	201	110	110	1					
		WB18 Temporary relocation of Public Cargo Working Area							116	108	103		
		Marine piling							116	108	103		
		Derrick Barge	061	104	061	104	99	2					
		Percussive Piling Plant (land)	27	0	27	0	0	2					
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T 10-118	99	94	2					
		Deck Construction							123	115	110		
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T 10-118	99	94	2					
		Lorry	141	112	BS5228: T 7-59	105	105	1					
		Concrete lorry mixer	044	109	BS5228: T 9-33	96	91	5					
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T 7-101	100	90	3					
		Poker, vibratory, hand-held	170	113	BS5228: T 9-20	102	97	4					
		Concrete pump, stationary lorry mounted	047	109	BS5228: T 9-36	106	101	3					
		Temporary road construction							124	114	112		
		Q1 Road formation/Services Excavation							124	114	112		
		Excavator/loader, wheeled/tracked	081	112	BS5228: T 7-24	108	103	1					
		Breaker, excavator mounted (hydraulic)	028	122	BS5228: T 11-13	110	105	1					
		Dump truck	067	117	BS5228: T 7-60	110	110	1					
		Q2. Laying of Drains and Services							121	113	109		
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T 10-118	99	94	1					
		Lorry	141	112	BS5228: T 7-59	105	105	1					
		Concrete lorry mixer	044	109	BS5228: T 9-33	96	91	1					
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T 7-101	100	90	1					
		Poker, vibratory, hand-held	170	113	BS5228: T 9-20	102	97	4					
		Compressor/vibratory	050	105	050	105	100	2					
		Q3. Surfacing							117	113	109		
		Excavator/loader, wheeled/tracked	081	112	BS5228: T 7-24	108	103	1					

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT

APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List		CNP No.	SPL	Ref. No.	SPL	SPL	Number working simultaneously in 30min	Predicted Noise Level			Max. Noise Level for Work Package			
Package	Description	Construction Equipment	Unmitigated	Level 1 Mitigation	Level 2 Mitigation	Unmit.		L1 Mit.	L2 Mit.	Unmit.	L1 Mit.	L2 Mit.		
		Lorry	141	112	BS5228: T.7-59	105	105	1						
		Roller, vibratory	186	108	BS5228: T.7-116	106	101	1						
		Asphalt paver	104	109	BS5228: T.11-26	108	103	1						
	Q4. Footway								119	109	107			
		Crane, mobile/berge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1						
		Lorry	141	112	BS5228: T.7-59	105	105	1						
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	1						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	1						
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	2						
WB19	Permanent relocation of Public Cargo Working Area											128	120	116
	Demolition of temporary decking and foundation													
	<i>Demolition of temporary decking and foundation</i>													
		Crane, mobile/berge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2	128	120	116			
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	2						
		Breaker, hand-held (pneumatic)	023	117	BS5228: T.6-40	110	105	4						
		Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	2						
		Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-13	110	105	2						
		Dump truck	067	117	BS5228: T.7-60	110	110	2						
	Reinstate the existing sloping seawall													
		Derrick barge	061	104	061	104	89	2	112	112	111			
		Tide Boat	221	110	221	110	110	1						
WB20	Reparation of Vehicular Ferry Pier													
	REFER WB21 BELOW													
WB21	Provision of Tourist Excursion Pier Activities											124	114	112
	Marine piling													
		Derrick Barge	061	104	061	104	89	2	117	110	105			
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	2						
		Concrete pump, stationary/lorry mounted	047	109	BS5228: T.9-36	106	101	1						
		Crane, mobile/berge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1						
	Construction of Tourist Excursion Pier													
	Q1. Excavation and Formation													
		Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	1	124	114	112			
		Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-13	110	105	1						
		Dump truck	067	117	BS5228: T.7-60	110	110	1						
	Q2. Concreting													
		Crane, mobile/berge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1						
		Lorry	141	112	BS5228: T.7-59	105	105	1						
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	4						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	1						
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	4						
		Concrete pump, stationary/lorry mounted	047	109	BS5228: T.9-36	106	101	1						
	Q3. Surfacing/Services													
		Crane, mobile/berge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1	122	115	113			
		Lorry	141	112	BS5228: T.7-59	105	105	1						
		Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	1						
		Dump truck	067	117	BS5228: T.7-60	110	110	1						
		Roller, vibratory	186	108	BS5228: T.7-116	106	101	1						
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	1						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	1						
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	2						
	Q4. Road formation for road to pier													
		Excavator/loader, wheeled/tracked			BS5228: T.7-24	108	103	1	123	115	112			
		Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-13	110	105	1						
		Dump truck	067	117	BS5228: T.7-60	110	110	1						
		Roller, vibratory	186	108	BS5228: T.7-116	106	101	1						
	Q5. Laying of Drains and Services for road to pier													
		Crane, mobile/berge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1						
		Lorry	141	112	BS5228: T.7-59	105	105	1						
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	1						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	1						
		Water Pump (petrol)	282	103	BS5228: T.8-86	100	90	1						
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	2						
		Compactor, vibratory	050	105	050	105	100	1						
	Q6. Surfacing for road to pier													
		Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	1	117	113	109			
		Lorry	141	112	BS5228: T.7-59	105	105	1						
		Roller, vibratory	186	108	BS5228: T.7-116	106	101	1						
		Asphalt paver	104	109	BS5228: T.11-26	108	103	1						
	Q7. Footway for road to pier													
		Crane, mobile/berge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1	119	109	107			
		Lorry	141	112	BS5228: T.7-59	105	105	1						
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	1						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	1						
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	2						

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT

APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List		CNP No.	SWL	Ref. No.	SWL	SWL	Number working simultaneously in 30min	Predicted Noise Level			Max. Noise Level for Work Package		
Package	Description	Unmitigated	Level 1 Mitigation	Level 2 Mitigation	Unmit.	L1 Mit.		L2 Mit.	Unmit.	L1 Mit.	L2 Mit.		
	Construction Equipment												
	Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	4						
	Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	8						
	Concrete pump, stationary/lorry-mounted	047	109	BS5228: T.9-36	106	101	1						
Q8. Backfilling/Surfacing /Services for T2 tunnel box								125	118	116			
	Crane, mobile-barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2						
	Lorry	141	112	BS5228: T.7-59	105	105	2						
	Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	8						
	Excavator-loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	2						
	Dump truck	067	117	BS5228: T.7-60	110	110	2						
	Roller, vibratory	186	108	BS5228: T.7-116	106	101	2						
	Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	2						
	Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	2						
	Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	3						
Q9. Piling Works for noise barrier								112	103	95			
i. Piling													
	Crane, mobile-barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1						
	Small diameter bored, reverse circulation drilling rig	166	100	N/A	100	90	1						
ii. Grouting								115	111	102			
	Crane, mobile-barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1						
	Grout Mixer	BS5228: T.9-13	108	N/A	108	98	1						
	Grout Pump	BS5224: T.9-13	108	N/A	108	98	1						
Q10. Pile Cap Construction for noise barrier								123	116	113			
i. excavation													
	Air compressor, standard	001	109	BS5228: T.7-101	100	90	1						
	Breaker, hand-held (pneumatic)	023	117	BS5228: T.6-10	110	105	2						
	Excavator-loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	1						
	Dump truck	067	117	BS5228: T.7-60	110	110	1						
	Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	2						
ii. placing concrete								119	109	103			
	Crane, mobile-barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1						
	Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	2						
	Air compressor, standard	001	109	BS5228: T.7-101	100	90	1						
	Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	2						
	Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	2						
Q11. Noise Barrier Stem/Decking								115	106	105			
i. Noise Barrier Erection													
	Crane, mobile-barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1						
	Lorry	141	112	BS5228: T.7-59	105	105	1						
ii. placing concrete								122	111	108			
	Crane, mobile-barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2						
	Lorry	141	112	BS5228: T.7-59	105	105	1						
	Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	2						
	Air compressor, standard	001	109	BS5228: T.7-101	100	90	2						
	Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	4						
Q12. Road Paving								115	111	108			
	Road roller	185	108	BS5228: T.11-27	104	99	1						
	Asphalt paver	064	109	BS5228: T.11-26	108	103	1						
	Lorry	141	112	BS5228: T.7-59	105	105	1						
WC13	Road D4 Tunnel - Stage 1							127	119	116			
Q1. Diaphragm Walling Works for D4 tunnel box								127	118	115			
i. excavation													
	Crane, mobile-barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2						
	Piling, diaphragm wall, bentonite filtering plant	162	105	162	105	100	2						
	Piling, diaphragm wall, hydraulic excavator	162	90	162	90	85	2						
	Excavator-loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	2						
	Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-13	110	105	2						
	Dump truck	067	117	BS5228: T.7-60	110	110	2						
ii. placing concrete								118	112	107			
	Piling, diaphragm wall, bentonite filtering plant	162	105	162	105	100	2						
	Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	5						
	Concrete pump, stationary/lorry-mounted	047	109	BS5228: T.9-36	106	101	2						
Q2. Excavation and Strutting for tunnel box								124	118	116			
	Crane, mobile-barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2						
	Lorry	141	112	BS5228: T.7-59	105	105	2						
	Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	8						
	Excavator-loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	2						
	Dump truck	067	117	BS5228: T.7-60	110	110	2						
Q3. Box Tunnel Construction for tunnel box								119	115	111			
i. Base Preparation													
	Lorry	141	112	BS5228: T.7-59	105	105	2						
	Excavator-loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	2						
	Compactor, vibratory	050	105	050	105	100	2						
	Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	8						
ii. placing concrete								123	114	107			
	Crane, mobile-barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2						
	Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	5						
	Air compressor, standard	001	109	BS5228: T.7-101	100	90	1						
	Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	4						
	Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	8						
	Concrete pump, stationary/lorry-mounted	047	109	BS5228: T.9-36	106	101	1						
Q4. Backfilling/Surfacing /Services for tunnel box								125	118	116			
	Crane, mobile-barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2						
	Lorry	141	112	BS5228: T.7-59	105	105	2						
	Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	8						
	Excavator-loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	2						
	Dump truck	067	117	BS5228: T.7-60	110	110	2						
	Roller, vibratory	186	108	BS5228: T.7-116	106	101	2						
	Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	2						
	Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	1						
	Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	4						
Q5. LRT/Trolley Bus Deck													

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT
 APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List			CNP No.	SWL	Ref. No.	SWL	SWL	Number working simultaneously in 30min	Predicted Noise Level			Max. Noise Level for Work Package			
Package	Description	Construction Equipment	Unmitigated	Level 1 Mitigation	Level 2 Mitigation	Level 2 Mitigation	Unmit.		L1 Mit.	L2 Mit.	Unmit.	L1 Mit.	L2 Mit.		
Foundation															
i. Piling													121	117	112
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1							
		Piling, large diameter bored	164/165	115	N/A	115	105	1							
		Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	1							
		Dump truck	067	117	BS5228: T.7-60	110	110	1							
ii. placing concrete													116	107	102
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1							
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	2							
		Concrete pump, stationary/lorry mounted	047	109	BS5228: T.9-36	106	101	1							
Pile Cap Construction															
i. excavation													122	116	113
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	1							
		Breaker, hand-held (pneumatic)	022	117	BS5228: T.6-40	110	105	2							
		Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	1							
		Dump truck	067	117	BS5228: T.7-60	110	110	1							
		Water Pump (petrol)	242	103	BS5228: T.7-86	100	90	1							
ii. placing concrete													119	108	102
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1							
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	2							
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	1							
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	2							
		Water Pump (petrol)	242	103	BS5228: T.7-86	100	90	1							
Bridge Pier Construction															
i. temporary works													112	99	94
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1							
ii. placing concrete													119	114	113
		Concrete pump, stationary/lorry mounted	047	109	BS5228: T.9-36	106	101	1							
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	2							
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	1							
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	2							
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1							
Superstructure Construction															
i. temporary works													112	99	94
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1							
ii. placing concrete													120	111	105
		Concrete pump, stationary/lorry mounted	047	109	BS5228: T.9-36	106	101	1							
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	2							
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	1							
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	2							
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1							
Q6. Road Paving													115	111	108
		Road roller	185	108	BS5228: T.11-27	104	99	1							
		Asphalt paver	304	109	BS5228: T.11-26	108	103	1							
		Lorry	141	112	BS5228: T.7-59	105	105	1							
WC14 Road D5 - Stage 1													126	116	115
Q1. Diaphragm Walling Works for Road D5 tunnel															
i. excavation													124	115	112
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1							
		Piling, diaphragm wall, bentonite filtering plant	162	105	162	105	100	2							
		Piling, diaphragm wall, hydraulic extractor	163	90	163	90	85	2							
		Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	1							
		Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-13	110	105	1							
		Dump truck	067	117	BS5228: T.7-60	110	110	1							
ii. placing concrete													117	111	106
		Piling, diaphragm wall, bentonite filtering plant	162	105	162	105	100	2							
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	5							
		Concrete pump, stationary/lorry mounted	047	109	BS5228: T.9-36	106	101	1							
Q2 Excavation and Strutting for Road D5 tunnel													123	116	115
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1							
		Lorry	141	112	BS5228: T.7-59	105	105	2							
		Water Pump (petrol)	242	103	BS5228: T.7-86	100	90	4							
		Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	2							
		Dump truck	067	117	BS5228: T.7-60	110	110	2							
Q3. Box Tunnel Construction for Road D5 tunnel													116	112	108
i. Base Preparation															
		Lorry	141	112	BS5228: T.7-59	105	105	1							
		Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	1							
		Compactor, vibratory	050	105	050	105	100	1							
		Water Pump (petrol)	242	103	BS5228: T.7-86	100	90	4							
ii. placing concrete													121	112	106
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1							
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	5							
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	1							
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	3							
		Water Pump (petrol)	242	103	BS5228: T.7-86	100	90	4							
		Concrete pump, stationary/lorry mounted	047	109	BS5228: T.9-36	106	101	1							
Q4 Backfilling/Surfacing Services for Road D5 tunnel													123	116	115
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1							
		Lorry	141	112	BS5228: T.7-59	105	105	1							
		Water Pump (petrol)	242	103	BS5228: T.7-86	100	90	4							
		Excavator/loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	1							
		Dump truck	067	117	BS5228: T.7-60	110	110	2							
		Roller, vibratory	186	108	BS5228: T.7-16	106	101	1							
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	2							
		Air compressor, silenced, 25dB(A) at 7m	002	106	BS5228: T.7-101	100	90	1							
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	2							
Q5. Piling Works for noise barrier													112	103	95
i. Piling															
		Crane, mobile barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1							
		Small diameter bored, reverse circulation drilling rig	166	104	N/A	106	99	1							
ii. Grouting													115	111	102
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1							
		Grout Mixer	BS5228: T.9-13	108	N/A	108	98	1							
		Grout Pump	BS5228: T.9-13	108	N/A	108	98	1							
Q6. Pile Cap Construction for noise barrier													123	116	113
i. excavation															

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT
 APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List			CNP No.	SWL	Ref. No.	SWL	SWL	Number working simultaneously in 30min	Predicted Noise Level			Max. Noise Level for Work Package		
Package	Description	Construction Equipment	Unmitigated	Level 1 Mitigation	Level 2 Mitigation	Unmit.	L1 Mit.		L2 Mit.	Unmit.	L1 Mit.	L2 Mit.		
		Air compressor, standard	901	109	BS5228: T.7-101	100	90	1						
		Breaker, hand-held (pneumatic)	923	117	BS5228: T.6-10	110	105	2						
		Excavator/loader, wheeled/tracked	981	112	BS5228: T.7-24	108	103	1						
		Dump truck	967	117	BS5228: T.7-60	110	110	1						
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	2						
	ii. placing concrete								119	109	103			
		Crane, mobile/barge mounted (diesel)	948	112	BS5228: T.10-118	99	94	1						
		Concrete lorry mixer	944	109	BS5228: T.9-33	96	91	2						
		Air compressor, standard	901	109	BS5228: T.7-101	100	90	1						
		Poker, vibratory, hand-held	179	113	BS5228: T.9-20	102	97	2						
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	2						
	Q7. Noise Barrier Stem													
	i. Noise Barrier Erection								115	106	105			
		Crane, mobile/barge mounted (diesel)	948	112	BS5228: T.10-118	99	94	1						
		Lorry	141	112	BS5228: T.7-59	105	105	1						
	ii. placing concrete								119	107	102			
		Crane, mobile/barge mounted (diesel)	948	112	BS5228: T.10-118	99	94	1						
		Concrete lorry mixer	944	109	BS5228: T.9-33	96	91	1						
		Air compressor, standard	901	109	BS5228: T.7-101	100	90	1						
		Poker, vibratory, hand-held	179	113	BS5228: T.9-20	102	97	2						
	Q8 Road formation/Services Excavation for D5 at grade road								126	116	113			
		Excavator/loader, wheeled/tracked	981	112	BS5228: T.7-24	108	103	2						
		Breaker, excavator mounted (hydraulic)	928	122	BS5228: T.11-13	110	105	2						
		Dump truck	967	117	BS5228: T.7-60	110	110	1						
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	2						
	Q9. Laying of Drains and Services for D5 at grade road								121	113	109			
		Crane, mobile/barge mounted (diesel)	948	112	BS5228: T.10-118	99	94	2						
		Lorry	141	112	BS5228: T.7-59	105	105	1						
		Concrete lorry mixer	944	109	BS5228: T.9-33	96	91	2						
		Air compressor, standard	901	109	BS5228: T.7-101	100	90	2						
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	2						
		Poker, vibratory, hand-held	179	113	BS5228: T.9-20	102	97	2						
		Compactor, vibratory	950	105	950	105	100	2						
	Q10. Surfacing for D5 at grade road								119	116	111			
		Excavator/loader, wheeled/tracked	981	112	BS5228: T.7-24	108	103	2						
		Lorry	141	112	BS5228: T.7-59	105	105	1						
		Roller, vibratory	186	108	BS5228: T.7-116	106	101	2						
		Asphalt paver	904	109	BS5228: T.11-26	108	102	2						
	Q11. Footway for D5 at grade road								121	111	109			
		Crane, mobile/barge mounted (diesel)	948	112	BS5228: T.10-118	99	94	2						
		Lorry	141	112	BS5228: T.7-59	105	105	2						
		Concrete lorry mixer	944	109	BS5228: T.9-33	96	91	2						
		Air compressor, standard	901	109	BS5228: T.7-101	100	90	2						
		Poker, vibratory, hand-held	179	113	BS5228: T.9-20	102	97	2						
WC15	Roads and Drains at area 4 and 5											126	120	115
	Q1 Road formation/Services Excavation for Road L9 and L12								126	116	113			
		Excavator/loader, wheeled/tracked	981	112	BS5228: T.7-24	108	103	2						
		Breaker, excavator mounted (hydraulic)	928	122	BS5228: T.11-13	110	105	2						
		Dump truck	967	117	BS5228: T.7-60	110	110	1						
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	2						
	Q2. Laying of Drains and Services for Road L9 and L12								121	113	109			
		Crane, mobile/barge mounted (diesel)	948	112	BS5228: T.10-118	99	94	2						
		Lorry	141	112	BS5228: T.7-59	105	105	1						
		Concrete lorry mixer	944	109	BS5228: T.9-33	96	91	2						
		Air compressor, standard	901	109	BS5228: T.7-101	100	90	2						
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	2						
		Poker, vibratory, hand-held	179	113	BS5228: T.9-20	102	97	2						
		Compactor, vibratory	950	105	950	105	100	2						
	Q3. Surfacing for Road L9 and L12								119	116	111			
		Excavator/loader, wheeled/tracked	981	112	BS5228: T.7-24	108	103	2						
		Lorry	141	112	BS5228: T.7-59	105	105	1						
		Roller, vibratory	186	108	BS5228: T.7-116	106	101	2						
		Asphalt paver	904	109	BS5228: T.11-26	108	102	2						
	Q4. Footway for Road L9 and L12								121	110	107			
		Crane, mobile/barge mounted (diesel)	948	112	BS5228: T.10-118	99	94	2						
		Lorry	141	112	BS5228: T.7-59	105	105	1						
		Concrete lorry mixer	944	109	BS5228: T.9-33	96	91	2						
		Air compressor, standard	901	109	BS5228: T.7-101	100	90	2						
		Poker, vibratory, hand-held	179	113	BS5228: T.9-20	102	97	2						
	Group 1. Bridge Construction for FB17, FB18 and FB23													
	Q5. Piling Works								124	120	115			
	i. excavation													
		Crane, mobile/barge mounted (diesel)	948	112	BS5228: T.10-118	99	94	2						
		Piling, large diameter bored	164/165	115	N/A	115	105	2						
		Excavator/loader, wheeled/tracked	981	112	BS5228: T.7-24	108	103	2						
		Dump truck	967	117	BS5228: T.7-60	110	110	2						
	ii. placing concrete								119	110	105			
		Crane, mobile/barge mounted (diesel)	948	112	BS5228: T.10-118	99	94	2						
		Concrete lorry mixer	944	109	BS5228: T.9-33	96	91	2						
		Concrete pump, stationary/lorry mounted	947	109	BS5228: T.9-36	106	101	2						
	Q6. Pile Cap Construction								125	118	115			
	i. excavation													
		Air compressor, standard	901	109	BS5228: T.7-101	100	90	2						
		Breaker, hand-held (pneumatic)	923	117	BS5228: T.6-10	110	105	2						
		Excavator/loader, wheeled/tracked	981	112	BS5228: T.7-24	108	103	2						
		Dump truck	967	117	BS5228: T.7-60	110	110	2						
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	2						
	ii. placing concrete								121	111	105			
		Crane, mobile/barge mounted (diesel)	948	112	BS5228: T.10-118	99	94	2						
		Concrete lorry mixer	944	109	BS5228: T.9-33	96	91	2						
		Air compressor, standard	901	109	BS5228: T.7-101	100	90	2						
		Poker, vibratory, hand-held	179	113	BS5228: T.9-20	102	97	2						

AGREEMENT NO. CE.32/89 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT

APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List			CNP No.	SWL	Ref. No.	SWL	SWL	Number working simultaneously in 30min	Predicted Noise Level			Max. Noise Level for Work Package		
Package	Description	Construction Equipment	Unmitigated		Level 1 Mitigation	Level 2 Mitigation	Unmit.		L1 Mit.	L2 Mit.	Unmit.	L1 Mit.	L2 Mit.	
		Water Pump (petrol)	282	102	BS5228: T.7-86	100	90	4						
Q7. Bridge Pier Construction														
i. temporary works														
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2	115	102	97			
ii. placing concrete														
		Concrete pump, stationary/lorry mounted	047	109	BS5228: T.9-36	106	101	2						
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	3						
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	2						
		Poker, vibratory, hand-held	170	112	BS5228: T.9-20	102	97	3						
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2						
Q8. Superstructure Construction														
i. temporary works														
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2	115	102	97			
ii. placing concrete														
		Concrete pump, stationary/lorry mounted	047	109	BS5228: T.9-36	106	101	2						
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	4						
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	2						
		Poker, vibratory, hand-held	170	112	BS5228: T.9-20	102	97	4						
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2						
WC16 Road and Drains at area 5 and 6														
Group 3. Road Works D4, D5 and L10														
Q1. Road formation/Services Excavation														
		Excavator-loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	2	126	117	113			
		Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-13	110	105	2						
		Dump truck	067	117	BS5228: T.7-60	110	110	1						
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	3						
Q2. Laying of Drains and Services														
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2	122	113	108			
		Lorry	141	112	BS5228: T.7-59	105	105	1						
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	2						
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	2						
		Water Pump (petrol)	282	102	BS5228: T.7-86	100	90	3						
		Poker, vibratory, hand-held	170	112	BS5228: T.9-20	102	97	3						
		Compactor, vibratory	050	105	050	105	100	1						
Q3. Surfacing														
		Excavator-loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	2	119	116	111			
		Lorry	141	112	BS5228: T.7-59	105	105	1						
		Roller, vibratory	186	108	BS5228: T.7-116	106	101	2						
		Asphalt paver	004	109	BS5228: T.11-26	108	103	2						
Q4. Footway														
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2	121	111	107			
		Lorry	141	112	BS5228: T.7-59	105	105	1						
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	2						
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	2						
		Poker, vibratory, hand-held	170	112	BS5228: T.9-20	102	97	2						
Bridge Construction for FB22, FB24 and also traveller to Ngan Tau Kok MTR station														
Q5. Piling Works														
i. excavation														
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2	122	119	113			
		Piling, large diameter bored	164-165	115	N/A	115	105	2						
		Excavator-loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	2						
		Dump truck	067	117	BS5228: T.7-60	110	110	1						
ii. placing concrete														
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2	118	110	105			
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	2						
		Concrete pump, stationary/lorry mounted	047	109	BS5228: T.9-36	106	101	2						
Q6. Pile Cap Construction														
i. excavation														
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	2	123	117	113			
		Breaker, hand-held (pneumatic)	023	117	BS5228: T.6-10	110	105	2						
		Excavator-loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	2						
		Dump truck	067	117	BS5228: T.7-60	110	110	1						
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	2						
ii. placing concrete														
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2	120	110	103			
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	2						
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	2						
		Poker, vibratory, hand-held	170	112	BS5228: T.9-20	102	97	2						
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	2						
Q7. Bridge Pier Construction														
i. temporary works														
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2	115	102	97			
ii. placing concrete														
		Concrete pump, stationary/lorry mounted	047	109	BS5228: T.9-36	106	101	2	121	112	107			
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	2						
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	2						
		Poker, vibratory, hand-held	170	112	BS5228: T.9-20	102	97	2						
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2						
Q8. Superstructure Construction														
i. temporary works														
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2	115	102	97			
ii. placing concrete														
		Concrete pump, stationary/lorry mounted	047	109	BS5228: T.9-36	106	101	2	122	112	107			
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	2						
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	2						
		Poker, vibratory, hand-held	170	112	BS5228: T.9-20	102	97	2						
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	2						
Q9. Traveller Subway														
Excavation and Formation														
		Excavator-loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	1	124	116	113			
		Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-13	110	105	1						
		Dump truck	067	117	BS5228: T.7-60	110	110	1						
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	8						
		Crane, mobile/barge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1						
		Lorry	141	112	BS5228: T.7-59	105	105	1						

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT

APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List			CNP No.	SWL	Ref. No.	SWL	SWL	Number working simultaneously in 30min	Predicted Noise Level			Max. Noise Level for Work Package			
Package	Description	Construction Equipment	Unmitigated	Level 1 Mitigation	Level 2 Mitigation	Unmit.	L1 Mit.		L2 Mit.	Unmit.	L1 Mit.	L2 Mit.			
Pipe Pile Tunnel Construction													119	114	108
#NAME?	Crane, mobile/barge mounted (diesel)		048	112	BS5228: T.10-118	99	94	2							
	Lorry		141	112	BS5228: T.7-59	105	105	1							
	Crane Mixer		BS5228: T.9-13	108	N/A	108	98	1							
	Crane Pump		BS5228: T.9-13	108	N/A	108	98	1							
	Water Pump (petrol)		282	103	BS5228: T.7-86	100	90	8							
Bored Pile Wall													119	112	111
i. Piling															
	Crane, mobile/barge mounted (diesel)		048	112	BS5228: T.10-118	99	94	1							
	Bored piling, reverse circulation		166	100		0	0	1							
	Excavator/loader, wheeled/tracked		081	112	BS5228: T.7-24	108	103	1							
	Dump truck		067	117	BS5228: T.7-60	110	110	1							
ii. placing concrete													115	107	102
	Crane, mobile/barge mounted (diesel)		048	112	BS5228: T.10-118	99	94	1							
	Concrete lorry mixer		044	109	BS5228: T.9-33	96	91	1							
	Concrete pump, stationary/lorry mounted		047	109	BS5228: T.9-36	106	101	1							
Concreting													121	112	108
	Crane, mobile/barge mounted (diesel)		048	112	BS5228: T.10-118	99	94	1							
	Lorry		141	112	BS5228: T.7-59	105	105	1							
	Concrete lorry mixer		044	109	BS5228: T.9-33	96	91	1							
	Air compressor, silenced, 75dB(A) at 7m		002	100	BS5228: T.7-101	100	90	1							
	Water Pump (petrol)		282	103	BS5228: T.7-86	100	90	4							
	Poker, vibratory, hand-held		170	113	BS5228: T.9-20	102	97	4							
Surfacing /Services													122	115	113
	Crane, mobile/barge mounted (diesel)		048	112	BS5228: T.10-118	99	94	1							
	Lorry		141	112	BS5228: T.7-59	105	105	1							
	Excavator/loader, wheeled/tracked		081	112	BS5228: T.7-24	108	103	1							
	Dump truck		067	117	BS5228: T.7-60	110	110	1							
	Roller, vibratory		186	108	BS5228: T.7-116	106	101	1							
	Concrete lorry mixer		044	109	BS5228: T.9-33	96	91	1							
	Air compressor, silenced, 75dB(A) at 7m		002	100	BS5228: T.7-101	100	90	1							
	Poker, vibratory, hand-held		170	113	BS5228: T.9-20	102	97	2							
E&M:Finishing													115	106	105
	Crane, mobile/barge mounted (diesel)		048	112	BS5228: T.10-118	99	94	1							
	Lorry		141	112	BS5228: T.7-59	105	105	1							
WC17 Roads and Drains at Area 6C													126	118	115
Bridge Construction over existing Nullah and Footbridge FB27															
Q1. Piling Works															
i. excavation													124	115	114
	Crane, mobile/barge mounted (diesel)		048	112	BS5228: T.10-118	99	94	2							
	Piling, large diameter bored		164/165	115		0	0	2							
	Excavator/loader, wheeled/tracked		081	112	BS5228: T.7-24	108	103	2							
	Dump truck		067	117	BS5228: T.7-60	110	110	2							
ii. placing concrete													118	110	105
	Crane, mobile/barge mounted (diesel)		048	112	BS5228: T.10-118	99	94	2							
	Concrete lorry mixer		044	109	BS5228: T.9-33	96	91	2							
	Concrete pump, stationary/lorry mounted		047	109	BS5228: T.9-36	106	101	2							
Q2. Pile Cap Construction													124	118	115
i. excavation															
	Air compressor, standard		001	109	BS5228: T.7-101	100	90	2							
	Breaker, hand-held (pneumatic)		023	117	BS5228: T.6-10	110	105	2							
	Excavator/loader, wheeled/tracked		081	112	BS5228: T.7-24	108	103	2							
	Dump truck		067	117	BS5228: T.7-60	110	110	2							
	Water Pump (petrol)		282	103	BS5228: T.7-86	100	90	2							
ii. placing concrete													120	110	111
	Crane, mobile/barge mounted (diesel)		048	112	BS5228: T.10-118	99	94	2							
	Concrete lorry mixer		044	109	BS5228: T.9-33	96	91	2							
	Air compressor, standard		001	109	BS5228: T.7-101	100	90	2							
	Poker, vibratory, hand-held		170	113	BS5228: T.9-20	102	97	2							
	Water Pump (petrol)		282	103	BS5228: T.7-86	100	90	2							
Q3. Bridge Pier Construction													115	102	97
i. temporary works															
	Crane, mobile/barge mounted (diesel)		048	112	BS5228: T.10-118	99	94	2							
ii. placing concrete													121	112	107
	Concrete pump, stationary/lorry mounted		047	109	BS5228: T.9-36	106	101	2							
	Concrete lorry mixer		044	109	BS5228: T.9-33	96	91	2							
	Air compressor, standard		001	109	BS5228: T.7-101	100	90	2							
	Poker, vibratory, hand-held		170	113	BS5228: T.9-20	102	97	2							
	Crane, mobile/barge mounted (diesel)		048	112	BS5228: T.10-118	99	94	2							
Q4. Superstructure Construction													115	102	97
i. temporary works															
	Crane, mobile/barge mounted (diesel)		048	112	BS5228: T.10-118	99	94	2							
ii. placing concrete													122	112	107
	Concrete pump, stationary/lorry mounted		047	109	BS5228: T.9-36	106	101	2							
	Concrete lorry mixer		044	109	BS5228: T.9-33	96	91	3							
	Air compressor, standard		001	109	BS5228: T.7-101	100	90	2							
	Poker, vibratory, hand-held		170	113	BS5228: T.9-20	102	97	3							
	Crane, mobile/barge mounted (diesel)		048	112	BS5228: T.10-118	99	94	2							
Q5. Carriageway Construction													115	114	113
i. placing asphalt															
	Road roller		185	108	BS5228: T.11-27	104	99	1							
	Asphalt paver		054	109	BS5228: T.11-26	108	103	1							
	Lorry		141	112	141	112	112	1							
Road Works for local roads linking to Hoi Bun Road and Wai Yip street													126	116	113
Q6. Road formation/Services Excavation															
	Excavator/loader, wheeled/tracked		081	112	BS5228: T.7-24	108	103	2							
	Breaker, excavator mounted (hydraulic)		028	122	BS5228: T.11-17	110	105	2							
	Dump truck		067	117	BS5228: T.7-60	110	110	1							
	Water Pump (petrol)		282	103	BS5228: T.7-86	100	90	2							
Q7. Laying of Drains and Services													122	113	109
	Crane, mobile/barge mounted (diesel)		048	112	BS5228: T.10-118	99	94	2							
	Lorry		141	112	BS5228: T.7-59	105	105	1							
	Concrete lorry mixer		044	109	BS5228: T.9-33	96	91	2							
	Air compressor, standard		001	109	BS5228: T.7-101	100	90	2							
	Water Pump (petrol)		282	103	BS5228: T.7-86	100	90	2							
	Poker, vibratory, hand-held		170	113	BS5228: T.9-20	102	97	2							
	Compactor, vibratory		080	105	080	105	100	2							

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT
 APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List			CNP No.	SWL	Ref. No.	SWL	SWL	Number working simultaneously in 30min	Predicted Noise Level			Max. Noise Level for Work Package			
Package	Description	Construction Equipment	Unmitigated	Level 1 Mitigation	Level 2 Mitigation	Unmit.	L1 Mit.		L2 Mit.	Unmit.	L1 Mit.	L2 Mit.			
Q8. Surfacing													119	115	111
		Excavator/loader, wheeled/tracked	081	112	BSS228: T 7-24	108	102	2							
		Lorry	141	112	BSS228: T 7-59	105	105	1							
		Roller, vibratory	186	108	BSS228: T 11-27	104	99	2							
		Asphalt paver	004	109	BSS228: T 11-26	108	102	2							
Q9. Footway													121	111	107
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T 10-118	99	94	2							
		Lorry	141	112	BSS228: T 7-59	105	105	1							
		Concrete lorry mixer	044	109	BSS228: T 9-33	96	91	2							
		Air compressor, standard	001	109	BSS228: T 7-101	100	90	2							
		Poker, vibratory, hand-held	170	113	BSS228: T 9-20	102	97	3							
WC18 Sewerage pumping station in Area 4 and 5													123	117	113
<i>(Plans listed are per pumping station)</i>															
Q1. temporary works													112	99	94
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T 10-118	99	94	1							
Q2. Piling Works													121	117	112
i. excavation															
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T 10-118	99	94	1							
		Preboring, oscillatory	165	115	N/A	115	105	1							
		Excavator/loader, wheeled/tracked	081	112	BSS228: T 7-24	108	102	1							
		Dump truck	067	117	BSS228: T 7-60	110	110	1							
ii. placing grout													115	111	102
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T 10-118	99	94	1							
		Grout Mixer	BSS228: T 9-13	108	N/A	108	98	1							
		Grout Pump	BSS228: T 9-13	108	N/A	108	98	1							
Q3. Pile Cap Construction													123	116	113
i. excavation															
		Air compressor, standard	001	109	BSS228: T 7-101	100	90	1							
		Breaker, hand-held (pneumatic)	023	117	BSS228: T 6-10	110	105	2							
		Excavator/loader, wheeled/tracked	081	112	BSS228: T 7-24	108	102	1							
		Dump truck	067	117	BSS228: T 7-60	110	110	1							
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T 10-118	99	94	1							
		Water Pump (petrol)	282	103	BSS228: T 7-86	100	90	2							
ii. placing concrete													120	111	105
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T 10-118	99	94	1							
		Concrete lorry mixer	044	109	BSS228: T 9-33	96	91	2							
		Air compressor, standard	001	109	BSS228: T 7-101	100	90	1							
		Poker, vibratory, hand-held	170	113	BSS228: T 9-20	102	97	2							
		Water Pump (petrol)	282	103	BSS228: T 7-86	100	90	2							
		Concrete pump, stationary lorry mounted	047	109	BSS228: T 9-36	106	101	1							
Q4. Superstructure Construction													112	99	94
i. temporary works															
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T 10-118	99	94	1							
ii. placing concrete													119	110	105
		Concrete pump, stationary lorry mounted	047	109	BSS228: T 9-36	106	101	1							
		Concrete lorry mixer	044	109	BSS228: T 9-33	96	91	2							
		Air compressor, standard	001	109	BSS228: T 7-101	100	90	1							
		Poker, vibratory, hand-held	170	113	BSS228: T 9-20	102	97	2							
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T 10-118	99	94	1							
WC19 Sewerage pumping station in Area 5 and 6															
<i>(Similar to WC18 above)</i>															
WC20 Riverland Junctions Improvement															
<i>(Similar to WC18)</i>															

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT

APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List		CNP No.	SWL	Ref. No.	SWL	SWL	Predicted Noise Level			Max. Noise Level for Work Package			
Package	Description	Construction Equipment	Unmitigated	Level 1 Mitigation	Level 2 Mitigation	Number working simultaneously in 30min	Unmit.	L1 Mit.	L2 Mit.	Unmit.	L1 Mit.	L2 Mit.	
			dB(A)	dB(A)	dB(A)		dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	
WD11	Reclamation at Kowloon Bay - Stage 1												
	Q1 Demolition of structures												
		Air compressor, silenced, 75dB(A) at 7m	002	100	BSS228: T.7-101	100	90				128	119	116
		Breaker, hand-held (pneumatic)	022	117	BSS228: T.6-10	110	105						
		Excavator loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Breaker, excavator mounted (hydraulic)	028	122	BSS228: T.11-13	110	105						
		Dump truck	067	117	BSS228: T.7-60	110	110						
	Q2 Demolition of armour rock												
		Derrick barge	061	104	061	104	99				111	111	110
		Tug Boat	221	110	221	110	110						
	Q3 Temporary Drain Diversion												
		Excavator loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103				123	116	112
		Dump truck	067	117	BSS228: T.7-60	110	110						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BSS228: T.7-101	100	90						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97						
		Concrete pump, stationary lorry mounted	047	109	BSS228: T.9-36	106	101						
	Q4 Reclamation/Advance Earth Bund												
		Derrick barge	061	104	061	104	99				125	119	118
		Tug Boat	221	110	221	110	110						
		Split Barge	061	104	061	104	99						
		Dump truck	067	117	BSS228: T.7-60	110	110						
		Excavator loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Roller, Vibratory	186	108	BSS228: T.7-116	106	101						
WD12	Reclamation at Kowloon Bay - Stage 2												
	Q1 Demolition of structures												
		Air compressor, silenced, 75dB(A) at 7m	002	100	BSS228: T.7-101	100	90				125	117	113
		Breaker, hand-held (pneumatic)	022	117	BSS228: T.6-10	110	105						
		Excavator loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Breaker, excavator mounted (hydraulic)	028	122	BSS228: T.11-13	110	105						
		Dump truck	067	117	BSS228: T.7-60	110	110						
	Q2 Temporary Drain Diversion												
		Excavator loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103				121	114	112
		Dump truck	067	117	BSS228: T.7-60	110	110						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BSS228: T.7-101	100	90						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97						
		Concrete pump, stationary lorry mounted	047	109	BSS228: T.9-36	106	101						
	Q3 Reclamation												
		Derrick barge	061	104	061	104	99				125	119	118
		Tug Boat	221	110	221	110	110						
		Split Barge	061	104	061	104	99						
		Dump truck	067	117	BSS228: T.7-60	110	110						
		Excavator loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Roller, Vibratory	186	108	BSS228: T.7-116	106	101						
WD13	Trunk Drain R - Stage 3												
	Q1 Excavation and Foundation for culvert construction												
		Excavator loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103				127	119	116
		Breaker, excavator mounted (hydraulic)	028	122	BSS228: T.11-13	110	105						
		Dump truck	067	117	BSS228: T.7-60	110	110						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94						
		Lorry	141	112	BSS228: T.7-59	105	105						
	Q2. Concreting for culvert construction												
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94				123	113	109
		Lorry	141	112	BSS228: T.7-59	105	105						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BSS228: T.7-101	100	90						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97						
		Concrete pump, stationary lorry mounted	047	109	BSS228: T.9-36	106	101						
	Q2. Surfacing /Services for culvert construction												
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94				122	115	113
		Lorry	141	112	BSS228: T.7-59	105	105						
		Excavator loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Dump truck	067	117	BSS228: T.7-60	110	110						
		Roller, vibratory	186	108	BSS228: T.7-116	106	101						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BSS228: T.7-101	100	90						
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97						
WD14	Trunk Drains in Area 3 Stage 1												
	!!Plants listed are for culvert S only; other culverts are similar!!												
	!!3 separate set of plants for culverts Q, P2 on earth bund and upstream of P2 are required!!												
	Q1 Excavation and Foundation for multicells box culvert S												
		Excavator loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103				125	116	111
		Breaker, excavator mounted (hydraulic)	028	122	BSS228: T.11-13	110	105						
		Dump truck	067	117	BSS228: T.7-60	110	110						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94						
		Lorry	141	112	BSS228: T.7-59	105	105						
	Q2. Concreting for multicells box culvert S												
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94				122	114	109
		Lorry	141	112	BSS228: T.7-59	105	105						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BSS228: T.7-101	100	90						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97						
		Concrete pump, stationary lorry mounted	047	109	BSS228: T.9-36	106	101						
	Q3. Surfacing /Services for multicells box culvert S												
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94				122	115	113
		Lorry	141	112	BSS228: T.7-59	105	105						
		Excavator loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Dump truck	067	117	BSS228: T.7-60	110	110						
		Roller, vibratory	186	108	BSS228: T.7-116	106	101						

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT

APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List		CNP No.	SWL	Ref. No.	SWL	SWL	Predicted Noise Level			Max. Noise Level for Work Package			
Package	Description	Construction Equipment	Unmitigated	Level 1 Mitigation	Level 2 Mitigation	Number working simultaneously in 30min	Unmit.	L1 Mit.	L2 Mit.	Unmit.	L1 Mit.	L2 Mit.	
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91						
		Air compressor, silenced, 75dB(A) at 7m	001	109	BSS228: T.7-101	100	90						
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97						
	Q4. Backfilling to temporary open channel and reinstatement							124	117	112			
		Air compressor, standard	001	109	BSS228: T.7-101	100	90						
		Breaker, hand-held (pneumatic)	023	117	BSS228: T.6-10	110	105						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
		Excavator loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Dump truck	067	117	BSS228: T.7-60	110	105						
		Roller, vibratory	186	108	BSS228: T.7-116	106	101						
WD15	Trunk Drain in Area 3 Stage 2												
	<i>(Same as WD14 above)</i>												
WD16	Provision of Public Pier												
	<i>(Same as WB20, 21)</i>												
WD17	Reprovision of Buoys												
		Derrick Barge	061	104	061	104	99	111	111	110	124	118	113
		Tug Boat	221	110	221	110	110						
	Q1. Excavation and Formation							124	115	113			
		Excavator loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Breaker, excavator mounted (hydraulic)	028	122	BSS228: T.11-13	110	105						
		Dump truck	067	117	BSS228: T.7-60	110	110						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94						
		Lorry	141	112	BSS228: T.7-59	105	105						
	Q2. Concreting							120	112	108			
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94						
		Lorry	141	112	BSS228: T.7-59	105	105						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91						
		Air compressor, standard	001	109	BSS228: T.7-101	100	90						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97						
		Concrete pump, stationary/lorry mounted	047	109	BSS228: T.9-36	106	101						
	Q3. Surfacing /Services							122	115	113			
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94						
		Lorry	141	112	BSS228: T.7-59	105	105						
		Excavator loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Dump truck	067	117	BSS228: T.7-60	110	110						
		Roller, vibratory	186	108	BSS228: T.7-116	106	101						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91						
		Air compressor, standard	001	109	BSS228: T.7-101	100	90						
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97						
WD18	Drainage Improvement at hinterland												
	<i>(List of plants listed as follow at each culvert location)</i>												
	Q1. Excavation and Formation							122	112	107			
		Excavator loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Breaker, excavator mounted (hydraulic)	028	122	BSS228: T.11-13	110	105						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
	Q2. Concreting							118	108	102			
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91						
		Air compressor, standard	001	109	BSS228: T.7-101	100	90						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97						
	Q3. Surfacing /Services							118	111	106			
		Excavator loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Roller, vibratory	186	108	BSS228: T.7-116	106	101						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91						
		Air compressor, standard	001	109	BSS228: T.7-101	100	90						
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97						
WD19	Road D4 - Stage 2												
	Q1. Diaphragm Walling Works for D4 tunnel box										127	118	115
	i. excavation												
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94						
		Piling, diaphragm wall, bentonite filtering plant	162	105	162	105	100						
		Piling, diaphragm wall, hydraulic extractor	162	90	163	90	85						
		Excavator loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Breaker, excavator mounted (hydraulic)	028	122	BSS228: T.11-13	110	105						
		Dump truck	067	117	BSS228: T.7-60	110	110						
	ii. placing concrete							117	112	107			
		Piling, diaphragm wall, bentonite filtering plant	162	105	162	105	100						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91						
		Concrete pump, stationary/lorry mounted	047	109	BSS228: T.9-36	106	101						
	Q2. Excavation and Strutting for tunnel box							123	116	114			
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94						
		Lorry	141	112	BSS228: T.7-59	105	105						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
		Excavator loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Dump truck	067	117	BSS228: T.7-60	110	110						
	Q3. Box Tunnel Construction for tunnel box												
	i. Base Preparation							118	114	110			
		Lorry	141	112	BSS228: T.7-59	105	105						
		Excavator loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Computer/vibratory	050	105	050	105	100						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
	ii. placing concrete							122	113	107			
		Crane, mobile/barge mounted (diesel)	048	112	BSS228: T.10-118	99	94						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91						

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT
 APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List			CNP No.	SWL	Ref. No.	SWL	SWL	Predicted Noise Level			Max. Noise Level for Work Package			
Package	Description	Construction Equipment	Unmitigated	Level 1 Mitigation	Level 2 Mitigation	Level 2 Mitigation	Number working simultaneously in 30min	Unmit.	L1 Mit.	L2 Mit.	Unmit.	L1 Mit.	L2 Mit.	
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	2						
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	3						
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	4						
		Concrete pump, stationary lorry mounted	047	109	BS5228: T.9-36	106	101	2						
	Q4. Backfilling/Surfacing /Services for tunnel box										124	117	116	
		Crane, mobile/berge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1						
		Lorry	141	112	BS5228: T.7-59	105	105	1						
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	4						
		Excavator loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	1						
		Dump truck	067	117	BS5228: T.7-60	110	110	3						
		Roller, vibratory	186	108	BS5228: T.7-116	106	101	1						
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	1						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BS5228: T.7-101	100	90	1						
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	2						
	Q5 Road formation/Services Excavation										124	114	112	
		Excavator loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	1						
		Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-12	110	105	1						
		Dump truck	067	117	BS5228: T.7-60	110	110	1						
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	1						
	Q6. Laying of Drains and Services										120	111	108	
		Crane, mobile/berge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1						
		Lorry	141	112	BS5228: T.7-59	105	105	1						
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	1						
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	1						
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	1						
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	2						
		Compactor, vibratory	050	105	050	105	100	1						
	Q7. Surfacing for Road										117	113	109	
		Excavator loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	1						
		Lorry	141	112	BS5228: T.7-59	105	105	1						
		Roller, vibratory	186	108	BS5228: T.7-116	106	101	1						
		Asphalt paver	004	109	BS5228: T.11-26	108	103	1						
	Q8. Footway for Road										118	105	106	
		Crane, mobile/berge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1						
		Lorry	141	112	BS5228: T.7-59	105	105	1						
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	1						
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	1						
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	1						
	Q9. Piling Works for noise barrier										103	110	104	
	i. Piling													
		Crane, mobile/berge mounted (diesel)	BS5228: T.10-118	99	94	109	104	1						
		Small diameter bored, reverse circulation drilling rig	166	100	N/A	100	93	1						
	ii. Grouting										115	113	106	
		Crane, mobile/berge mounted (diesel)	048	112	BS5228: T.9-18	109	104	1						
		Grout Mixer	BS5228: T.9-13	108	N/A	108	98	1						
		Grout Pump	BS5228: T.9-13	108	N/A	108	98	1						
	Q10. Pile Cap Construction for noise barrier										121	115	112	
	i. excavation													
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	1						
		Breaker, hand-held (pneumatic)	023	117	BS5228: T.6-10	110	105	1						
		Excavator loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	1						
		Dump truck	067	117	BS5228: T.7-60	110	110	1						
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	1						
	ii. placing concrete										119	109	103	
		Crane, mobile/berge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1						
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	2						
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	1						
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	2						
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	2						
	Q11. Noise Barrier Stem/Decking										115	106	105	
	i. Noise Barrier Erection													
		Crane, mobile/berge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1						
		Lorry	141	112	BS5228: T.7-59	105	105	1						
	ii. placing concrete										119	109	107	
		Crane, mobile/berge mounted (diesel)	048	112	BS5228: T.10-118	99	94	1						
		Lorry	141	112	BS5228: T.7-59	105	105	1						
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	1						
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	1						
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	2						
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	2						
WD20	Roads and drains at Area 3 - Stage 1											122	116	107
	Q1 Road formation/Services Excavation for Road D1, L7 L15										122	112	107	
		Excavator loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	1						
		Breaker, excavator mounted (hydraulic)	028	122	BS5228: T.11-12	110	105	1						
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	1						
	Q2. Laying of Drains and Services										116	109	103	
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	1						
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	1						
		Water Pump (petrol)	282	103	BS5228: T.7-86	100	90	1						
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	1						
		Compactor, vibratory	050	105	050	105	100	1						
	Q3. Surfacing										115	112	107	
		Excavator loader, wheeled/tracked	081	112	BS5228: T.7-24	108	103	1						
		Roller, vibratory	186	108	BS5228: T.7-116	106	101	1						
		Asphalt paver	004	109	BS5228: T.11-26	108	103	1						
	Q4. Footway										116	105	99	
		Concrete lorry mixer	044	109	BS5228: T.9-33	96	91	1						
		Air compressor, standard	001	109	BS5228: T.7-101	100	90	1						
		Poker, vibratory, hand-held	170	113	BS5228: T.9-20	102	97	1						
	Bridge Construction for FB13 and FB14													

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT

APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List			CNP No.	SWL	Ref. No.	SWL	SWL	Predicted Noise Level			Max. Noise Level for Work Package		
Package	Description	Construction Equipment	Unmitigated	Level 1 Mitigation	Level 2 Mitigation	Number working simultaneously in 30min	Unmit.	L1 Mit.	L2 Mit.	Unmit.	L1 Mit.	L2 Mit.	
Q5. Piling Works													
i. excavation													
		Piling, large diameter bored	164-165	115	N/A	1	105				117	116	107
		Excavator/loader, wheeled/tracked	081	112	B85228: T 7-24	1	108	103					
ii. placing concrete													
		Concrete lorry mixer	044	109	B85228: T 9-33	1	96	91			112	106	101
		Concrete pump, stationary/lorry mounted	047	109	B85228: T 9-36	1	106	101					
Q6. Pile Cap Construction													
i. excavation													
		Air compressor, standard	001	109	B85228: T 7-101	1	100	90			119	113	107
		Breaker, hand-held (pneumatic)	023	117	B85228: T 6-19	1	110	105					
		Excavator/loader, wheeled/tracked	081	112	B85228: T 7-24	1	108	103					
		Water Pump (petrol)	282	103	B85228: T 7-86	1	100	90					
ii. placing concrete													
		Concrete lorry mixer	044	109	B85228: T 9-33	1	96	91			116	106	99
		Air compressor, standard	001	109	B85228: T 7-101	1	100	90					
		Poker, vibratory, hand-held	170	113	B85228: T 9-20	1	102	97					
		Water Pump (petrol)	282	103	B85228: T 7-86	1	100	90					
Q7. Bridge Pier Construction													
i. temporary works													
		Crane, mobile/large mounted (diesel)	048	112	B85228: T 10-118	1	99	94			112	99	94
ii. placing concrete													
		Concrete pump, stationary/lorry mounted	047	109	B85228: T 9-36	1	106	101			116	108	103
		Concrete lorry mixer	044	109	B85228: T 9-33	1	96	91					
		Air compressor, standard	001	109	B85228: T 7-101	1	100	90					
		Poker, vibratory, hand-held	170	113	B85228: T 9-20	1	102	97					
Q8. Superstructure Construction													
i. temporary works													
		Crane, mobile/large mounted (diesel)	048	112	B85228: T 10-118	1	99	94			112	99	94
ii. placing concrete													
		Concrete pump, stationary/lorry mounted	047	109	B85228: T 9-36	1	106	101			116	108	103
		Concrete lorry mixer	044	109	B85228: T 9-33	1	96	91					
		Air compressor, standard	001	109	B85228: T 7-101	1	100	90					
		Poker, vibratory, hand-held	170	113	B85228: T 9-20	1	102	97					
Q9. Travellator Subway													
Excavation and Formation													
		Excavator/loader, wheeled/tracked	081	112	B85228: T 7-24	1	108	103			122	112	107
		Breaker, excavator mounted (hydraulic)	028	122	B85228: T 11-13	1	110	105					
		Water Pump (petrol)	282	103	B85228: T 7-86	1	100	90					
Pipe Pile Tunnel Construction													
		Grout Mixer	B85228: T 9-13	108	N/A	1	108	98			112	111	101
		Grout Pump	B85228: T 9-13	108	N/A	1	108	98					
		Water Pump (petrol)	282	103	B85228: T 7-86	1	100	90					
Bored Pile Wall													
i. Piling													
		Bored piling, reverse circulation	166	109	N/A	1	100	90			112	109	103
		Excavator/loader, wheeled/tracked	081	112	B85228: T 7-24	1	108	103					
ii. placing concrete													
		Concrete lorry mixer	044	109	B85228: T 9-33	1	96	91					
		Concrete pump, stationary/lorry mounted	047	109	B85228: T 9-36	1	106	101					
Concreting													
		Concrete lorry mixer	044	109	B85228: T 9-33	1	96	91			115	106	99
		Air compressor, silenced, 75dB(A) at 7m	002	100	B85228: T 7-101	1	100	90					
		Water Pump (petrol)	282	103	B85228: T 7-86	1	100	90					
		Poker, vibratory, hand-held	170	113	B85228: T 9-20	1	102	97					
Surfacing/Services													
		Excavator/loader, wheeled/tracked	081	112	B85228: T 7-24	1	108	103			117	111	106
		Roller, vibratory	186	108	B85228: T 7-116	1	106	101					
		Concrete lorry mixer	044	109	B85228: T 9-33	1	96	91					
		Air compressor, silenced, 75dB(A) at 7m	002	100	B85228: T 7-101	1	100	90					
		Poker, vibratory, hand-held	170	113	B85228: T 9-20	1	102	97					
WD21 Roads and Drains at Area 3 - Stage 2													
Q1 Road formation/Services Excavation for Road D1, L7 L13(include roadwork above travellator)													
		Excavator loader, wheeled-tracked	081	112	B85228: T 7-24	2	108	103			127	117	115
		Breaker, excavator mounted (hydraulic)	028	122	B85228: T 11-13	2	110	105					
		Dump truck	067	117	B85228: T 7-60	2	110	110					
		Water Pump (petrol)	282	103	B85228: T 7-86	2	100	90					
Q2. Laying of Drains and Services(include temporary diversion at travellator)													
		Crane, mobile/large mounted (diesel)	048	112	B85228: T 10-118	2	99	94			121	113	109
		Lorry	141	112	B85228: T 7-59	1	105	105					
		Concrete lorry mixer	044	109	B85228: T 9-33	2	96	91					
		Air compressor, standard	001	109	B85228: T 7-101	2	100	90					
		Water Pump (petrol)	282	103	B85228: T 7-86	3	100	90					
		Poker, vibratory, hand-held	170	113	B85228: T 9-20	2	102	97					
		Compactor, vibratory	050	105	050	2	105	100					
Q3. Surfacing(include roadwork above travellator)													
		Excavator/loader, wheeled-tracked	081	112	B85228: T 7-24	2	108	103			119	116	111
		Lorry	141	112	B85228: T 7-59	1	105	105					
		Roller, vibratory	186	108	B85228: T 7-116	2	106	101					
		Asphalt paver	064	109	B85228: T 11-26	2	108	102					
Q4. Footway(include footway construction above travellator)													
		Crane, mobile/large mounted (diesel)	048	112	B85228: T 10-118	2	99	94			121	111	107
		Lorry	141	112	B85228: T 7-59	1	105	105					
		Concrete lorry mixer	044	109	B85228: T 9-33	2	96	91					
		Air compressor, standard	001	109	B85228: T 7-101	2	100	90					
		Poker, vibratory, hand-held	170	113	B85228: T 9-20	3	102	97					
Q5. Travellator Subway													
Excavation and Formation													
		Excavator/loader, wheeled-tracked	081	112	B85228: T 7-24	2	108	103			126	118	116
		Breaker, excavator mounted (hydraulic)	028	122	B85228: T 11-13	2	110	105					
		Dump truck	067	117	B85228: T 7-60	1	110	110					
		Water Pump (petrol)	282	103	B85228: T 7-86	8	100	90					
		Crane, mobile/large mounted (diesel)	048	112	B85228: T 10-118	1	99	94					
		Lorry	141	112	B85228: T 7-59	1	105	105					

AGREEMENT NO. CE.32/99 COMPREHENSIVE FEASIBILITY STUDY FOR THE REVISED SCHEME OF SOUTH EAST KOWLOON DEVELOPMENT
 APPENDIX 3.1 CONSTRUCTION NOISE ASSESSMENT

Table 3.1.4 Construction Noise Assessment - Equipment Lists and Predicted Noise Levels of Work Packages

SWL = Sound Power Level
 PNL = Predicted Noise Level
 Level 1 Mitigation = Use of Quiet Plants
 Level 2 Mitigation = Use of Quiet Plants with Acoustic Barriers

Construction Equipment List			CNP No.	SWL	Ref. No.	SWL	SWL	Predicted Noise Level			Max. Noise Level for Work Package		
Package	Description	Construction Equipment	Unmitigated	Level 1 Mitigation	Level 2 Mitigation	Number working simultaneously in 30min	Unmit.	L1 Mit.	L2 Mit.	Unmit.	L1 Mit.	L2 Mit.	
Pipe Pile Tunnel Construction													
		Crane, mobile-barge mounted (diesel)	048	112	BSS228: T.10-118	99	94						
		Lorry	141	112	BSS228: T.7-59	105	105						
		Grout Mixer	BSS228: T.9-13	108	N/A	108	93						
		Grout Pump	BSS228: T.9-12	108	N/A	108	93						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
Bored Pile Wall													
i. Piling													
		Crane, mobile-barge mounted (diesel)	048	112	BSS228: T.10-118	99	94						
		Bored piling, reverse circulation	166	100	N/A	100	90						
		Excavator/loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Dump truck	067	117	BSS228: T.7-60	110	110						
ii. placing concrete													
		Crane, mobile-barge mounted (diesel)	048	112	BSS228: T.10-118	99	94						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91						
		Concrete pump, stationary/lorry mounted	047	109	BSS228: T.9-36	106	101						
Concreting													
		Crane, mobile-barge mounted (diesel)	048	112	BSS228: T.10-118	99	94						
		Lorry	141	112	BSS228: T.7-59	105	105						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BSS228: T.7-101	100	90						
		Water Pump (petrol)	282	103	BSS228: T.7-86	100	90						
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97						
Surfacing /Services													
		Crane, mobile-barge mounted (diesel)	048	112	BSS228: T.10-118	99	94						
		Lorry	141	112	BSS228: T.7-59	105	105						
		Excavator/loader, wheeled/tracked	081	112	BSS228: T.7-24	108	103						
		Dump truck	067	117	BSS228: T.7-60	110	110						
		Roller, vibratory	186	108	BSS228: T.7-116	106	101						
		Concrete lorry mixer	044	109	BSS228: T.9-33	96	91						
		Air compressor, silenced, 75dB(A) at 7m	002	100	BSS228: T.7-101	100	90						
		Poker, vibratory, hand-held	170	113	BSS228: T.9-20	102	97						
E&M: Finishing													
		Crane, mobile-barge mounted (diesel)	048	112	BSS228: T.10-118	99	94						
		Lorry	141	112	BSS228: T.7-59	105	105						
WD22	Sewerage pumping station in Area 3 - stage 1 (Similar to WC180 plants for laying of rising mains included in WD20)												
WD23	Sewerage pumping station in Area 3 - stage 2 (Similar to WC180 plants for laying of rising mains included in WD21)												
WD24	Hinterland Junctions Improvement (Similar to WA221)												

AGREEMENT NO. CE.32/99 C

APPENDIX 3.1 CONSTRU

Table 3.1.11 - Construction Noise Assessment

Unmitigated Scenario

Receivers	Points (APs)	2014											
		Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Existing NSRs													
Rhythm Gardens	E1	65	65	65	65	65	65	65	65	65	65	62	62
Choi Hung Estate	F2	65	65	65	65	65	65	65	65	65	65	64	64
Richlands Gardens	E3	65	65	65	65	65	65	65	65	65	65	64	64
San Po Kong Area	E4	65	65	65	65	65	65	65	65	65	65	60	60
	E5	65	65	65	65	65	65	65	65	65	65	61	61
Kowloon City Area	E6	65	65	65	65	65	65	65	65	65	65	60	60
	F7	64	64	64	64	64	64	64	64	64	64	59	59
	E8	64	64	64	64	64	64	64	64	64	64	59	59
Mok Cheong St.	E9	65	65	65	65	65	65	65	65	65	65	60	60
Wyler Garden	F10	65	65	65	65	65	65	65	65	65	65	60	60
	E11	65	65	65	65	65	65	65	65	65	65	60	60
To Kwa Wan Area	E12	64	64	64	64	64	64	64	64	64	64	60	60
Laguna City	E13	78	78	78	78	78	78	78	78	78	78	78	78
Cha Kwo Ling	E14	71	71	71	71	71	71	71	71	71	71	71	71
Laguna Verde	E15	79	79	79	79	79	79	79	79	79	79	69	69
Future NSRs													
4C & 4E	F1	65	65	65	65	65	65	65	65	65	65	63	63
4C & 4E	F2	65	65	65	65	65	65	65	65	65	65	63	63
4F & 4L	F3	65	65	65	65	65	65	65	65	65	65	64	64
4F & 4L	F4	65	65	65	65	65	65	65	65	65	65	63	63
4K	F5	65	65	65	65	65	65	65	65	65	65	64	64
4M	F6	65	65	65	65	65	65	65	65	65	65	64	64
4R	F7	66	66	66	66	66	66	66	66	66	66	65	65
5J	F8	68	68	68	68	68	68	68	68	68	68	67	67
5J	F9	67	67	67	67	67	67	67	67	67	67	67	67
4S	F10	66	66	66	66	66	66	66	66	66	66	65	65
4H	F11	65	65	65	65	65	65	65	65	65	65	63	63
4G	F12	65	65	65	65	65	65	65	65	65	65	60	60
4D	F13	64	64	64	64	64	64	64	64	64	64	62	62
4A	F14	63	63	63	63	63	63	63	63	63	63	61	61
4J	F15	66	66	66	66	66	66	66	66	66	66	65	65
5A	F16	66	66	66	66	66	66	66	66	66	66	65	65
5E	F17	67	67	67	67	67	67	67	67	67	67	66	66
5G	F18	67	67	67	67	67	67	67	67	67	67	66	66
5C	F19	67	67	67	67	67	67	67	67	67	67	66	66
5C	F20	67	67	67	67	67	67	67	67	67	67	66	66
4E(S)	F21	65	65	65	65	65	65	65	65	65	65	63	63
5J(S)	F22	67	67	67	67	67	67	67	67	67	67	67	67
5L(S)	F23	67	67	67	67	67	67	67	67	67	67	67	67
4L(S)	F24	65	65	65	65	65	65	65	65	65	65	64	64
4N(S)	F25	66	66	66	66	66	66	66	66	66	66	65	65
5K	F26	67	67	67	67	67	67	67	67	67	67	66	66
5K	F27	67	67	67	67	67	67	67	67	67	67	66	66
1F	F28	65	65	65	65	65	65	65	65	65	65	63	63
1E	F29	65	65	65	65	65	65	65	65	65	65	63	63
1E(S)	F30	65	65	65	65	65	65	65	65	65	65	61	61
1C(S)	F31	64	64	64	64	64	64	64	64	64	64	62	62
2A	F32	65	65	65	65	65	65	65	65	65	65	60	60
2A	F33	65	65	65	65	65	65	65	65	65	65	60	60
2B	F34	65	65	65	65	65	65	65	65	65	65	60	60
2C	F35	65	65	65	65	65	65	65	65	65	65	61	61
2F	F36	65	65	65	65	65	65	65	65	65	65	60	60
2E	F37	65	65	65	65	65	65	65	65	65	65	61	61
2D	F38	65	65	65	65	65	65	65	65	65	65	61	61
1K	F39	65	65	65	65	65	65	65	65	65	65	61	61
1K	F40	65	65	65	65	65	65	65	65	65	65	61	61
1K	F41	65	65	65	65	65	65	65	65	65	65	61	61
2A(S)	F42	65	65	65	65	65	65	65	65	65	65	60	60
2A(S)	F43	65	65	65	65	65	65	65	65	65	65	60	60
2B(S)	F44	65	65	65	65	65	65	65	65	65	65	60	60
1L(S)	F45	65	65	65	65	65	65	65	65	65	65	61	61
1P(S)	F46	65	65	65	65	65	65	65	65	65	65	61	61

AGREEMENT NO. CE.32/99 CC
APPENDIX 3.1 CONSTRUCTION

Table 3.1.11 - Construction Noise Assessment

Level 1 Mitigated Scenario

Receivers	Points (APs)	Month					
		Jul	Aug	Sep	Oct	Nov	Dec
Existing NSRs							
Rhythm Gardens	E1	57	57	57	57	55	55
Choi Hung Estate	E2	57	57	57	57	56	56
Richlands Gardens	E3	57	57	57	57	56	56
San Po Kong Area	E4	58	58	58	58	54	54
	E5	58	58	58	58	54	54
Kowloon City Area	E6	58	58	58	58	53	53
	E7	57	57	57	57	57	57
	E8	57	57	57	57	53	53
Mok Cheong St	E9	58	58	58	58	52	52
Wylar Garden	E10	58	58	58	58	54	54
	E11	58	58	58	58	54	54
To Kwa Wan Area	E12	57	57	57	57	53	53
Laguna City	E13	72	72	72	72	72	72
Cha Kwo Ling	E14	64	64	64	64	64	64
Laguna Verde	E15	71	71	71	71	63	63
Future NSRs							
4C & 4E	F1	57	57	57	57	55	55
4C & 4E	F2	57	57	57	57	55	55
4F & 4L	F3	57	57	57	57	56	56
4F & 4L	F4	57	57	57	57	56	56
4K	F5	58	58	58	58	56	56
4M	F6	58	58	58	58	57	57
4R	F7	58	58	58	58	58	58
5J	F8	60	60	60	60	60	60
5J	F9	60	60	60	60	60	60
4S	F10	58	58	58	58	57	57
4H	F11	57	57	57	57	56	56
4G	F12	58	58	58	58	54	54
4D	F13	57	57	57	57	55	55
4A	F14	57	57	57	57	54	54
4J	F15	58	58	58	58	57	57
5A	F16	59	59	59	59	58	58
5E	F17	59	59	59	59	59	59
5G	F18	58	58	58	58	58	58
5C	F19	58	58	58	58	58	58
5C	F20	58	58	58	58	58	58
4E(S)	F21	57	57	57	57	56	56
5J(S)	F22	60	60	60	60	59	59
5L(S)	F23	60	60	60	60	60	60
4L(S)	F24	58	58	58	58	57	57
4N(S)	F25	58	58	58	58	58	58
5K	F26	58	58	58	58	58	58
5K	F27	58	58	58	58	58	58
1E	F28	57	57	57	57	56	56
1E	F29	57	57	57	57	56	56
1E(S)	F30	57	57	57	57	54	54
1C(S)	F31	57	57	57	57	55	55
2A	F32	58	58	58	58	54	54
2A	F33	58	58	58	58	54	54
2B	F34	58	58	58	58	54	54
2C	F35	58	58	58	58	54	54
2F	F36	58	58	58	58	54	54
2E	F37	58	58	58	58	54	54
2D	F38	57	57	57	57	54	54
1K	F39	58	58	58	58	54	54
1K	F40	58	58	58	58	54	54
1K	F41	58	58	58	58	54	54
2A(S)	F42	58	58	58	58	53	53
2A(S)	F43	58	58	58	58	54	54
2B(S)	F44	58	58	58	58	54	54
1I(S)	F45	57	57	57	57	54	54
1P(S)	F46	57	57	57	57	54	54

AGREEMENT NO. CE.32/99 CC

APPENDIX 3.1 CONSTRUCTION

Table 3.1.11 - Construction Noise Assessment

Level 2 Mitigated Scenario

Receivers	Points (APs)	Points (APs)					
		Jul	Aug	Sep	Oct	Nov	Dec
<u>Existing NSRs</u>							
Rhythm Gardens	F1	64	64	64	64	64	64
Choi Hung Estate	E2	55	55	55	55	54	54
Richlands Gardens	E3	55	55	55	55	54	54
San Po Kong Area	F4	55	55	55	55	51	51
	E5	55	55	55	55	51	51
Kowloon City Area	E6	55	55	55	55	51	51
	E7	54	54	54	54	50	50
	F8	54	54	54	54	50	50
Mok Cheong St	E9	55	55	55	55	51	51
Wylar Garden	E10	55	55	55	55	51	51
	E11	55	55	55	55	51	51
To Kwa Wan Area	E12	54	54	54	54	50	50
Laguna City	E13	71	71	71	71	71	71
Cha Kwo Ling	E14	64	64	64	64	64	64
Laguna Verde	E15	68	68	68	68	59	59
<u>Future NSRs</u>							
4C & 4E	F1	55	55	55	55	53	53
4C & 4E	F2	55	55	55	55	53	53
4F & 4L	F3	55	55	55	55	54	54
4F & 4L	F4	55	55	55	55	54	54
4K	F5	55	55	55	55	54	54
4M	F6	56	56	56	56	55	55
4R	F7	57	57	57	57	56	56
5J	F8	59	59	59	59	59	59
5J	F9	58	58	58	58	58	58
4S	F10	56	56	56	56	56	56
4H	F11	55	55	55	55	54	54
4G	F12	55	55	55	55	51	51
4D	F13	55	55	55	55	52	52
4A	F14	55	55	55	55	52	52
4J	F15	56	56	56	56	55	55
5A	F16	57	57	57	57	56	56
5E	F17	57	57	57	57	57	57
5G	F18	57	57	57	57	57	57
5C	F19	57	57	57	57	57	57
5C	F20	57	57	57	57	57	57
4E(S)	F21	55	55	55	55	54	54
5J(S)	F22	58	58	58	58	58	58
5I(S)	F23	59	59	59	59	58	58
4L(S)	F24	56	56	56	56	55	55
4N(S)	F25	57	57	57	57	56	56
5K	F26	57	57	57	57	57	57
5K	F27	57	57	57	57	57	57
1E	F28	55	55	55	55	52	52
1E	F29	57	57	57	57	57	57
1E(S)	F30	55	55	55	55	52	52
1C(S)	F31	55	55	55	55	53	53
2A	F32	55	55	55	55	53	53
2A	F33	55	55	55	55	53	53
2B	F34	55	55	55	55	51	51
2C	F35	55	55	55	55	51	51
2F	F36	55	55	55	55	51	51
2E	F37	55	55	55	55	51	51
2D	F38	55	55	55	55	52	52
1K	F39	55	55	55	55	51	51
1K	F40	55	55	55	55	51	51
1K	F41	55	55	55	55	51	51
2A(S)	F42	55	55	55	55	51	51
2A(S)	F43	55	55	55	55	51	51
2B(S)	F44	55	55	55	55	51	51
1L(S)	F45	55	55	55	55	52	52
1P(S)	F46	55	55	55	55	52	52