

N5 Kar Fu Building

		Distance m	SWL dB(A)	2009												2010																							
				1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12												
North Point	P1a, upper shaft, Diaphragm wall at shaft	208	114		63	63	63	63	63	63	63	63	63	63																									
PTW drop shaft	P1a, upper shaft, Excavation at shaft	208	109													58	58	58																					
	Phase 1b, lower shaft	208	114																																				
	Phase II, upgrading	180	111																	63	63	63	63	63	63														
	Phase III, drop shaft finishing works	192	108																																				
	Phase III, PTW upgrading	192	114																																				
North Point	upper shaft, Diaphragm wall at shaft	108	114		68	68	68	68	68	68	68	68																											
Production Shaft	upper shaft, Excavation at shaft	108	109												63	63																							
	lower shaft	108	114																																				
	tunnel construction	108	106													68	68	68	68																				
Barging Point	Construction of Ramp and Tipping Hall	155	120		71	71	71	71	71	71																													
Barging Point	Barging Activities	155	119													70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70			
Predicted Construction Noise Levels, dB(A)(with Façade Effect)					73	73	73	73	73	73	73	73	72	72	73	73	73	73	70	70	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	

		Distance m	SWL dB(A)	2011												2012																						
				1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12											
North Point	P1a, upper shaft, Diaphragm wall at shaft	208	114																																			
PTW drop shaft	P1a, upper shaft, Excavation at shaft	208	109																																			
	Phase 1b, lower shaft	208	114																																			
	Phase II, upgrading	180	111	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	
	Phase III, drop shaft finishing works	192	108																																			
	Phase III, PTW upgrading	192	114																																			
North Point	upper shaft, Diaphragm wall at shaft	108	114																																			
Production Shaft	upper shaft, Excavation at shaft	108	109																																			
	lower shaft	108	114																																			
	tunnel construction	108	106	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	
Barging Point	Construction of Ramp and Tipping Hall	155	120																																			
Barging Point	Barging Activities	155	119	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	
Predicted Construction Noise Levels, dB(A)(with Façade Effect)					71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71	71

		Distance m	SWL dB(A)	2013												
				1	2	3	4	5	6	7	8	9	10	11	12	
North Point	P1a, upper shaft, Diaphragm wall at shaft	208	114													
PTW drop shaft	P1a, upper shaft, Excavation at shaft	208	109													
	Phase 1b, lower shaft	208	114													
	Phase II, upgrading	180	111													
	Phase III, drop shaft finishing works	192	108	57	57	57	57	57	57							
	Phase III, PTW upgrading	192	114	63	63	63	63	63	63	63	63	63	63	63		
North Point	upper shaft, Diaphragm wall at shaft	108	114													
Production Shaft	upper shaft, Excavation at shaft	108	109													
	lower shaft	108	114													
	tunnel construction	108	106	60	60	60	60	60	60	60	60					
Barging Point	Construction of Ramp and Tipping Hall	155	120													
Barging Point	Barging Activities	155	119	70	70	70	70	70	70	70	70					
Predicted Construction Noise Levels, dB(A)(with Façade Effect)					72	72	72	72	72	72	71	71	71	63	63	63

N15b Block B, The Duchess of Kent Children's Hospital

		Distance (m)	SWL dB(A)	2009												2010											
				1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Sandy Bay	upper shaft, Diaphragm wall at shaft	70	114						72	72	72	72	72	72													
Production shaft /	upper shaft,Excavation at shaft	70	109												67	67											
Drop / Riser Shaft	lower shaft	70	114														72	72	72								
	tunnel construction	70	106																	64	64	64	64	64	64	64	
	Conversion to Drop / Riser Shaft	70	109																								
	PTW Upgarding	65	111																				70	70	70	70	
Production shaft	upper shaft, Diaphragm wall at shaft	70	114						72	72	72	72	72	72													
	upper shaft,Excavation at shaft	70	109												67	67											
	lower shaft	70	114														72	72	72								
	tunnel construction	70	106																	64	64	64	64	64	64	64	
Predicted Construction Noise Levels, dB(A)(with Façade Effect)									75	75	75	75	75	75	75	70	70	75	75	75	67	67	67	72	72	72	72

		Distance (m)	SWL dB(A)	2011												2012											
				1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Sandy Bay	upper shaft, Diaphragm wall at shaft	70	114																								
Production shaft /	upper shaft,Excavation at shaft	70	109																								
Drop / Riser Shaft	lower shaft	70	114																								
	tunnel construction	70	106	64	64	64	64	64	64	64	64	64	64	64	64	64	64	64	64	64	64	64	64	64	64	64	
	Conversion to Drop / Riser Shaft	70	109																								
	PTW Upgarding	65	111	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	
Production shaft	upper shaft, Diaphragm wall at shaft	70	114																								
	upper shaft,Excavation at shaft	70	109																								
	lower shaft	70	114																								
	tunnel construction	70	106	64	64	64	64	64	64	64	64	64	64	64	64	64	64	64	64	64	64	64	64	64	64	64	
Predicted Construction Noise Levels, dB(A)(with Façade Effect)									72	72	72	72	72	72	72	72	72	72	72	72	72	72	72	72	72	72	72

		Distance (m)	SWL dB(A)	2013																						
				1	2	3	4	5	6	7	8	9	10	11	12											
Sandy Bay	upper shaft, Diaphragm wall at shaft	70	114																							
Production shaft /	upper shaft,Excavation at shaft	70	109																							
Drop / Riser Shaft	lower shaft	70	114																							
	tunnel construction	70	106																							
	Conversion to Drop / Riser Shaft	70	109	67	67	67	67	67	67	67	67	67	67													
	PTW Upgarding	65	111	70	70	70	70	70	70	70	70	70	70	70	70	70										
Production shaft	upper shaft, Diaphragm wall at shaft	70	114																							
	upper shaft,Excavation at shaft	70	109																							
	lower shaft	70	114																							
	tunnel construction	70	106	64	64	64	64	64	64	64	64	64	64													
Predicted Construction Noise Levels, dB(A)(with Façade Effect)									72	72	72	72	72	72	72	72	70	70	70							

N16 Point Breeze

		Distance		2009												2010											
		(m)	SWL dB(A)	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Cyberport	upper shaft, Install pipe pile wall	240	112						59	59	59	59	59	59	59												
Production Shaft /	upper shaft, Excavation at shaft	240	110													57	57										
Drop / Riser Shaft	lower shaft	240	114															61	61	61	61						
	tunnel construction	240	106																		53	53	53	53	53	53	
	Conversion to Drop / Riser Shaft - Finishing Works	240	109																								
	PTW Upgrading	220	111																								
	Demolition of Existing CEPT Colmpex	220	110																								
Predicted Construction Noise Levels from concurrent project(HK West Drainage Tunnel TBM support)		175	115						65	65	65	65	65	65	65	65	65	65	65	65	65	65	65	65	65	65	
Predicted Construction Noise Levels from concurrent project(Finalized stage-General works)		175	108																								
Predicted Construction Noise Levels from concurrent project(Finalized stage-Concreting)		175	106																								
Predicted Construction Noise Levels from concurrent project(Finalized stage-Marine Transport)		175	112																								
Predicted Construction Noise Levels with concurrent project, dB(A)(with Façade Effect)									66	66	66	66	66	66	66	65	65	66	66	66	66	66	65	65	65	65	

		Distance		2011												2012											
		(m)	SWL dB(A)	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Cyberport	upper shaft, Install pipe pile wall	240	112																								
Production Shaft /	upper shaft, Excavation at shaft	240	110																								
Drop / Riser Shaft	lower shaft	240	114																								
	tunnel construction	240	106	53	53	53	53	53	53	53	53	53	53	53	53	53	53	53	53	53	53	53	53	53	53	53	
	Conversion to Drop / Riser Shaft - Finishing Works	240	109																								
	PTW Upgrading	220	111			59	59	59	59	59	59	59	59	59	59	59	59	59	59	59	59	59	59	59	59	59	
	Demolition of Existing CEPT Colmpex	220	110																								
Predicted Construction Noise Levels from concurrent project(HK West Drainage Tunnel TBM support)		175	115	65	65	65	65	65	65																		
Predicted Construction Noise Levels from concurrent project(Finalized stage-General works)		175	108						58	58	58	58	58	58	58												
Predicted Construction Noise Levels from concurrent project(Finalized stage-Concreting)		175	106						56	56	56	56	56	56	56												
Predicted Construction Noise Levels from concurrent project(Finalized stage-Marine Transport)		175	112						62	62	62	62	62	62	62												
Predicted Construction Noise Levels with concurrent project, dB(A)(with Façade Effect)				65	65	66	68	68	68	66	66	66	66	66	66	60	60	60	60	60	60	60	60	60	60	60	

		Distance		2013												2014											
		(m)	SWL dB(A)	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Cyberport	upper shaft, Install pipe pile wall	240	112																								
Production Shaft /	upper shaft, Excavation at shaft	240	110																								
Drop / Riser Shaft	lower shaft	240	114																								
	tunnel construction	240	106																								
	Conversion to Drop / Riser Shaft - Finishing Works	240	109	56	56	56	56	56	56	56	56	56	56														
	PTW Upgrading	220	111	59	59	59	59	59	59	59	59	59	59	59	59												
	Demolition of Existing CEPT Colmpex	220	110																		58	58	58	58	58	58	
Predicted Construction Noise Levels from concurrent project(HK West Drainage Tunnel TBM support)		175	115																								
Predicted Construction Noise Levels from concurrent project(Finalized stage-General works)		175	108																								
Predicted Construction Noise Levels from concurrent project(Finalized stage-Concreting)		175	106																								
Predicted Construction Noise Levels from concurrent project(Finalized stage-Marine Transport)		175	112																								
Predicted Construction Noise Levels with concurrent project, dB(A)(with Façade Effect)				61	61	61	61	61	61	61	61	61	61	59	59	59					58	58	58	58	58	58	

