



Equipment Schedule for the Construction and Operation of Concrete Batching Plant at Cybperort

(Extracted from Appendix 5.2 of the EIA report for the Concrete Batching Plant)

Construction Stage				
Equipment	Quantity	TM reference	SWL per Piece dB(A)	Sub-Total SWL dB(A)
Generator Set	2	CNP 101	108	111
Excavator	1	CNP 081	112	112
150T Mobile Crane	2	CNP 048	112	115
Service Truck	2	CNP 067	117	120
Vibration Poker	2	CNP 170	113	116
Pneumatic Breaker	1	CNP 026	114	114
Compressor	1	CNP 003	104	104
Concrete Mixer Truck	2	CNP 044	109	112
Total SWL in dB(A)				124
Operation Stage 1				
Equipment	Quantity	TM reference	SWL per Piece dB(A)	Sub-Total SWL dB(A)
Wheel Loader	1	CNP 081	112	112
Concrete Recycle Machine	1	CNP 045	96	96
Generator	1	CNP 101	108	108
Cement Blower	1	CNP 047	109	109
Concrete Wet Mixer	1	CNP 045	96	96
Tipper Truck	1	CNP 067	117	117
Cement Tanker	1	CNP 141	112	112
Concrete Mixer Truck	3	CNP 044	109	114
Batching Plant	1	CNP 022	108	108
Compressor	2	CNP 003	104	107
Total SWL in dB(A)				121
Operation Stage 2				
Equipment	Quantity	TM reference	SWL per Piece dB(A)	Sub-Total SWL dB(A)
Wheel Loader	1	CNP 081	112	112
Concrete Recycle Machine	1	CNP 045	96	96
Generator	4	CNP 101	108	114
Cement Blower	3	CNP 047	109	114
Concrete Wet Mixer	3	CNP 045	96	101
Tipper Truck	1	CNP 067	117	117
bargo	3	CNP 061	104	109
Concrete Mixer Truck	8	CNP 044	109	118
Batching Plant	1	CNP 022	108	108
Compressor	5	CNP 003	104	111
Total SWL in dB(A)				123