Contract No. : EP/SP/52/06 Development of EcoPark in Tuen Mun Area 38

ENVIRONMENTAL MONITORING AND AUDIT MONTHLY EM&A REPORT for

May 2008

8/F, Chaiwan Industrial Centre Building 20 Lee Chung Street, Chaiwan, Hong Kong Tel: 2889 0569 Fax: 2856 2010

1

APPROVAL SHEET

(Environmental Pioneers & Solutions Limited)
Date:
Date:

TABLE OF CONTENTS

EXI	ECUTIVE SUMMARY	4
1.	BASIC PROJECT INFORMATION	6
2.	SUMMARY OF WORK ACTIVITIES AND CONSTRUCTION STATUS	8
3.	STATUS OF ENVIRONMENTAL PROTECTION AND SITE INSPECTIONS.	10
4.	SUMMARY OF ENVIRONMENTAL PERMIT AND LICENCES	15
5.	CUMULATIVE LOG OF COMPLAINTS AND REMEDIAL ACTION	15
6.	CUMULATIVE LOG OF NOTIFICATION OF SUMMONS AND	
PRO	OSECUTIONS	15
7.	CONCLUSION	15
APF	PENDIX 1 - SITE LAYOUT PLAN	17
APF	PENDIX 2 - THE CONTACT PERSONS, TELEPHONE NUMBERS OF KEY	
PER	RSONNEL FOR DEVELOPMENT OF ECOPARK IN TUEN MUN AREA 38	18
APF	PENDIX 3 – REVISED SITE LAYOUT PLAN FOR REFUSE COLLECTION	
POI	NTS	19
APF	PENDIX 4 - ORIGINAL LANDFILL GAS FIELD MEASUREMENT	
REC	CORDING SHEETS	20
APF	PENDIX 5 – CUMULATIVE LOG OF COMPLAINTS	24

EXECUTIVE SUMMARY

This is the twenty-third monthly Environmental Monitoring and Audit (EM&A) Report for the Environmental Protection Department Contract No. EP/SP/52/06 entitled "Development of EcoPark in Tuen Mun Area 38". (Environmental Permit No. EP-226/2005)

This report contains the results and findings of site inspection activities and EM&A works carried out by the Environmental Team (ET) of the Works Contractor as required in the contract during May 2008.

The site activities in the reporting period mainly consisted of landscaping works and finishing works, fitting outs and building services installation for administration building and marine frontage management office.

Insufficient cover to stockpile of planting soil found beside Site Office was observed. The Contractor was reminded to properly cover stockpile of planting soil with tarpaulin sheet for better dust mitigation. Accumulated water found at the bottom of oil and chemical storage cabinet should be removed. Pest control measures on site are needed as ant colonies had been found in gardening.

No substantial noise impact was noted by ET during weekly environmental site walks.

The Contractor has used the temporary storage tank to store the effluent of aerobic wastewater treatment system and the stored effluent was pumped away regularly. As checked by the ET, there was no effluent discharge into the stormwater drain.

Landfill gas monitoring was carried out at site; measurement results were within the Action and Limit Levels in accordance with the EM&A Manual. The kit would be taken for calibration after all excavation works are completed.

There were no notifications of summons or successful prosecution during May 2008.

The planned activities for May 2008 with regard to development of EcoPark consist of:

- 1) Finishing Works, Fitting Outs and Building Services Installation for Administration Building and Marine Frontage Management Office
- 2) Landscaping Works

1. BASIC PROJECT INFORMATION

1.1 Introduction

This is the twenty-third monthly Environmental Monitoring and Audit (EM&A) Report for the Environmental Protection Department Contract No. EP/SP/52/06 entitled "Development of EcoPark in Tuen Mun Area 38". The site layout plan is shown in Appendix 1. The report was prepared by the Environmental Team, Environmental Pioneers & Solutions Limited, of the Works Contractor, Kaden Construction Limited. The report is to be submitted to the Works Contractor, the Engineer and the Environmental Protection Department for the project.

This report presents the results of the environmental monitoring of the project activities conducted during the month of May 2008. This included regular site inspections once per week for verification of implementation of the mitigation measures as recommended in the EM&A Manual and the Contractor's Environmental Management Plan (EMP).


Phase 1 of the construction works has already commenced in July 2006 and is anticipated to complete in July 2008.

The contact person and telephone number of key personnel for the captioned project are shown in Appendix 2.

1.2 Project Organization and Management

The Works Contractor has commissioned Environmental Pioneers & Solutions Limited as the Environmental Team, which comprises the environmental team leader and the environmental technicians to undertake the environmental monitoring and audit work for this project. The project Organization Chart of Environmental Team is shown in Figure 1.1.

Figure 1.1 Organization Chart of Environmental Team



2. SUMMARY OF WORK ACTIVITIES AND CONSTRUCTION STATUS

2.1 Works Undertaken during the Month

A summary of the site installation works in this month, with the information of locations, activities, equipment/materials and dates of occurrence, is provided by the Contractor, as shown in Table 2.1.

Table	Table 2.1 Work Activities for May 2008								
Item Work Activities & Location Date of Occu									
1	Landscaping works	1May 2008 – 31 May 2008							
2	Finishing works, fitting outs & building services installation for administration building & marine frontage management office	1May 2008 – 31 May 2008							

	Machineries					
	Equipment/ Plant	Quantity				
1	Mobile Crane	1				
2	Excavator	3				
3	Generator	2				
4	Air Compressor	2				
5	Roller	4				
6	Loader	1				
7	Grab Lorry	1				
8	Crane Lorry	2				
9	Water Truck	1				
10	Dump Truck	1				

Remarks:

- As informed by the Contractor, most equipment are mobile at site subject to work progress.
- Refer to Appendix 1 Site layout plan for location of construction activities.

2.2 Future Key Issues

The Contractor has provided an updated construction program in Table 2.2 to show the planned activities for the coming month (June 2008). The anticipated environmental issues are summarized as follow:

Table	Table 2.2 Construction Program and Anticipated Environmental Issues						
Item	Works	Anticipated Environmental Issues					
1	Finishing works, fitting outs & building services installation for administration building & marine frontage management office	- Generation of waste from packaging materials and C&D wastes					
2	Landscaping Works	 Dust may be generated; the wheel washing should be in operation Stagnant water should be removed Mosquito mitigation measures should be implemented Stockpiles of excavated material should be covered with tarpaulin sheet 					

The site inspection schedule for the next month (June 2008) is designated on 4, 11, 18, 25 June 2008.

3. STATUS OF ENVIRONMENTAL PROTECTION AND SITE INSPECTIONS

3.1 Environmental Site Inspections

Environmental site inspections are required to inspect the construction activities of the Development of EcoPark in order to ensure that appropriate environmental protection and pollution control mitigation measures are properly implemented.

Site inspections were conducted on 6, 14, 21, and 29 May 2008

A detailed checklist of each site inspection together with comments, relevant photos and maps have been filed and kept.

The findings and results of site inspections are provided in Table 3.1:

Table 3.1 Sum	Table 3.1 Summary of Site Inspections							
Date	Observations	Advice from ET	Outcome	Closing Date				
14 May 08	Not enough labeling shown on chemical storage tank.	Proper safety labels are required	To be observed in the next reporting period					
14 May 08	Idle chemical storage tanks found	Idle chemical storage tanks could be removed from the site	To be observed in the next reporting period	1				
21, 29 May 08	Mosquito breeding problems found on site	Water in artificial ponds and ditch in the interior garden of the administration building could be drained away to prevent mosquito breeding. Anti-malaria oil can be applied on site when situation get worse in summer	To be observed in the next reporting period					
14, 21,29 May 08	Full-filled rubbish bin and industrial waste found inside the administration hall	Has to be cleared away to prevent mosquitoes breeding	Action taken as advised by ET	29 May 08				
29 May 08	Ant colonies had been observed in gardening area in front of the administration hall main entrance		To be observed in the next reporting period					

3.2 Air Dust

Excavation work at Road F near site office was finished and the site exit at Road F was closed. The site exit at Road A remained and manual wheel washing was used.

Insufficient cover to stockpile of planting soil found beside Site Office was observed. The Contractor was reminded to properly cover stockpile of planting soil with tarpaulin sheet for better dust mitigation.

3.3 Noise

The major noise source was vehicle movement, machinery and rock excavation in the EcoPark. Since the nearby NSRs were remote, the noise impact was minimal. There was no specific observation noted regarding noise issue. The Contractor has obtained the Construction Noise Permit on 07 August 2007.

3.4 Surface Water Quality

Since there was no water discharge at manhole, the Contractor removed the silt curtain installed at discharge point on 4 April 2007, as agreed by the Engineer's Representative. No muddy water was observed at discharge point.

Chemical toilets (3 nos.) have been provided by a licensed contractor, of which sewage generated is collected every three to five days without causing contamination on surface water. The Effluent Discharge License was issued to the Contractor on 20 November 2006.

The temporary storage tank was used to store the effluent of aerobic wastewater treatment system and the stored effluent was pumped away regularly. As checked by the ET, there was no effluent discharge into the storm water drain.

3.5 Visual and Landscape Impact

Hoarding was erected at the site egress and aligned along the site boundary along Lung Mun Road. Hoardings were specially designed to be movable for future re-use in other locations.

During site clearance, trees were relocated and to be replanted for landscaping in the future in EcoPark.

3.6 Waste / Chemical Waste

The Contractor implemented visual inspection and distributed flyers/ notices to ensure all dump trucks have mechanical covers closed when leaving EcoPark site.

Separate waste collection bins were made available for collecting aluminum cans, waste paper and plastic bottles etc. The Contractor has provided the revised site layout plan for refuse collection points as shown in Appendix 3.

Waste dumpers were used for the collection and storage of general waste. Temporary storage areas for waste metals and waste tyres were established.

The Contractor has provided sufficient drip trays for all temporary electricity generators at site. These drip trays should be covered by tarpaulin sheet to minimize rainfall accumulation.

Excavated materials are reused as back-fill material to balance cut and fill and hence reduce the generation of materials. Surplus materials are returned to stock in centralized area with suitable protective measures. The Contractor was reminded to comply with the requirements and conditions for disposal at public fill facility and all oversized aggregates should be crushed to less than 250mm before delivering to the public fill.

Materials are recycled and re-used at site as much as practicable to minimize waste generation. Timbers are recycled to make temporary tools and assess ladders etc. Excavated rocks, concrete and asphalts are stored for future re-use in land formation and structural construction etc.

Registered waste collectors will be arranged to collect and transport the wastes whenever necessary.

Table 3.4 provides a summary table of waste disposal in May 2008. The Contractor has been reminded to keep good record at site in order to have a clear presentation of waste disposal.

Table 3.4 Summary of Waste Disposal in May 2008								
Type of Waste	Disposal Site	Quantity	Remarks					
General Waste	WENT Landfill	0 tonnes	-					
Inert C&D Material	Public Fill Facility	0 tonnes	-					

3.7 Landfill Gas

Landfill gas (LFG) monitoring was carried out on site at three (3) locations, as instructed by the Engineer's Representative. LFG measurements on 6, 14, 21 and 29 May 2008 are summarized in Table 3.5, and original field measurement sheets with measurement locations are appended in Appendix 4. Measurement results are within the Action / Limit Levels in accordance with the EM&A Manual, as shown in Table 3.6.

Table 3.5 Summary of LFG Measurement for the reporting month											
Sampling											
Location	Measurement	Time	Condition	(CH ₄) %LEL	(CO ₂) %LEL						
Point A	6 May 08	1131		0	0	20.9%					
Point J	6 May 08	1133	Drizzle	0	0	20.9%					
Point K	6 May 08	1135		0	0	20.9%					
Point A	14 May 08	1509		0	0	20.9%					
Point J	14 May 08	1511	Sunny	0	0	20.9%					
Point K	14 May 08	1513		0	0	20.9%					
Point A	21 May 08	1410		0	0	20.9%					
Point J	21 May 08	1412	Sunny	0	0	20.9%					
Point K	21 May 08	1415		0	0	20.9%					
Point A	29 May 08	1510		0	0	20.9%					
Point J	29 May 08	1512	Rain	0	0	20.9%					
Point K	29 May 08	1514		0	0	20.9%					

I	Table 3.5	Summary of	of LFG	Measurement	for the	reporting	month

Sampling	Date of	Sampling	Weather	Methane	Carbon Dioxide	Overgon (O)
Location	Measurement	Time	Condition	(CH ₄) %LEL	(CO ₂) %LEL	Oxygen (O ₂)

Remarks:

¹⁾ As instructed by the Engineer's Representative, the landfill gas measurements were carried out with two instruments: one for the measurements of methane and carbon dioxide, another for the measurement of oxygen.

T 11 0 6 4		I.E					
Table 3.6 Action Levels, Limit Levels and Event and Action Plan for LFG (From							
EM&A Mar							
Parameter	Level	Action					
Oxygen	Action Level < 19% O ₂	Ventilate trench/ void to restore O ₂ to >					
		19%					
	Limit Level < 18% O ₂	Stop works					
		Evacuate personnel/prohibit entry					
		Increase ventilation to restore O_2 to > 19%					
Methane	Action Level >10% LEL	Post "No Smoking" signs					
(CH_4)		Prohibit hot works					
		Increase ventilation to restore CH ₄ to <10%					
		LEL					
	Limit Level >20% LEL	Stop works					
		Evacuate personnel/prohibit entry					
		Increase ventilation to restore CH ₄ to <10%					
		LEL					
Carbon	Action Level >0.5% CO ₂	Ventilate to restore CO ₂ to < 0.5%					
Dioxide							
(CO_2)	Limit Level >1.5% CO ₂	Stop works					
		Evacuate personnel/prohibit entry					
		Increase ventilation to restore CO ₂ to <					
		0.5%					

4. SUMMARY OF ENVIRONMENTAL PERMIT AND LICENCES

ET has checked with the Contractor for the status of all environmental permits and licenses for this project as at May 2008, which is summarized in Table 4.1. ET will follow the application process of the outstanding permits / licenses and will provide suitable assistance whenever appropriate.

Table 4.1 Summary of Environmental Permits/ Licences								
Description	License / Permit	Date of	Date of	Status/Remarks				
	No.#	Issue	Expiry					
Environmental Permit	EP-226/2005	9-Sept-2005		Issued				
Registration of Waste Producer	5111-421-K2869-02	27-Jul-2006		Issued				
Construction Noise Permit	GW-RW0402-07	07-Aug-2007	28-Feb-2008	Expired				
Effluent Discharge Licence	EP760/421/011762/I	20-Nov-2006	1-Dec-2011	Issued				

5. CUMULATIVE LOG OF COMPLAINTS AND REMEDIAL ACTION

The cumulative log of complaints is referred in Appendix 5.

6. CUMULATIVE LOG OF NOTIFICATION OF SUMMONS AND PROSECUTIONS

No notification of summons and no prosecutions occurred during May 2008.

7. CONCLUSION

There is no summon nor prosecutions reported during May 2008.

Effluent of aerobic wastewater treatment system was temporarily stored in the storage tank and pumped away. As checked by the ET, there was no effluent discharge into the stormwater drain.

Accumulated mixture of oil and water was found at the bottom of oil and chemical waste storage cabinet in May because of summer rainy period. However, dust and mud was not observed on floor in certain areas.

An ant colony was found in the gardening area where in front of the main entrance of administration hall.

Some industrial wastes for example used ceiling paper and rubbishes had been found inside the administration hall. Contractor had already taken action to clear them away.


The Contractor has been using the waste management and record system including allocation of waste storage areas and the trip ticket system as proposed in the Environmental Management Plan.

In addition to the daily landfill gas monitoring carried out by the Contractor on site, weekly landfill gas monitoring was also carried out by the ET on site. The measurement results from ET shown in Table 3.5 were within Action and Limit levels in accordance with EM&A Manual.

The GEM2000 had been agreed that would be calibrated after all excavation works are completed.

As summer is approaching, water accumulated in ditch, artificial ponds and manhole covers has to be drained away to avoid mosquito breeding. Furthermore, pest control measures must be taken to avoid mosquito and ant problems on site.


APPENDIX 1 - SITE LAYOUT PLAN



APPENDIX 2 - THE CONTACT PERSONS, TELEPHONE NUMBERS OF KEY PERSONNEL FOR DEVELOPMENT OF ECOPARK IN TUEN MUN AREA 38

Company/Department	Name	Position	Telephone
Scott Wilson Ltd.	Mike Bains	Independent Environmental Checker	
Scott Wilson Ltd.	Mr. Michael Lo	Senior Resident Engineer	6290 8860
Scott Wilson Ltd.	Mr. Andy Cheung	Resident Engineer	6111 9703
Scott Wilson Ltd.	Mr. C S Lam	Senior Inspector of Works	9861 8011
Kaden Construction Limited	Mr. K M Book	Project Manager	9193 8680
Kaden Construction Limited	Mr. Stephen Leung	Section Agent	9071 7657
Environmental Pioneers & Solutions Limited	Miss. Patricia Chung	Environmental Team Leader	2185 0123
Environmental Pioneers & Solutions Limited	Mr. Harvey Yung	Environmental Technician	2185 0172
Environmental Pioneers & Solutions Limited	Mr. Lam Ho Chun	Environmental Technician	2185 0154

APPENDIX 3 – REVISED SITE LAYOUT PLAN FOR REFUSE COLLECTION POINTS



APPENDIX 4 - ORIGINAL LANDFILL GAS FIELD MEASUREMENT RECORDING SHEETS

Kaden 基

Kaden Construction Limited

EPD Contract No. EP/SP/52/06

Job No. K0603

Development of EcoPark in Tuen Mun Area 38


Daily Air Monitoring 每日空氣監測記錄

	Model 型號:	GEM 2000	Last calibration 上次檢測:	03 Apr. 07
測試器	S/N 編號:	GM-08793	Next calibration 下次檢測:	02 Apr. 08

Date of Monitor 監測日期: 6	May 2	100 f		Perform	ed by: Ziill	ian WONG
Location	Time 時間	Result 結果				
位置	(hrs)	CH ₄ (%)	, CO ₂ (%)	O ₂ (%)	Bal. Gas (%)	Baro. Pressure ("Hg)
Point A	(1=3)	D	٥	20.9	fs.0	30.50
Point J (Lung Mun Road)	11= 33	0	0	20.9	86.0	30.50
Point K (Lung Mun Road nr production Gallery)	11-35	0	0	20.9	85.0	30.50

Instrument for O2 measurement: GasAlert MicroClip GAMIC-4-DL2 Serial no.: S103-13348

Site layout





Kaden Construction Limited


EPD Contract No. EP/SP/52/06 Job No. K0603 Development of EcoPark in Tuen Mun Area 38

Daily Air Monitoring 每日空氣鹽	監測記錄
----------------------------	------

Detector: Model 型號: GEM 2	2000		t calibration			Apr. 07	
測試器 S/N 編號: GM-08	Nex	ct calibratio	n 下次檢	測: 02.	Apr. 08		
Date of Monitor 監測日期: 以			Performe	ed by: 人行	lliam Long		
Location	Time 時間		Result 結果				
位置	(hrs)	CH ₄	, CO ₂	O ₂	Bal. Gas	Baro. Pressure	
	(/	(%)	(%)	(%)	(%)	("Hg)	
Point A	1509	0	0	20.9	85.1	29.77	
Point J (Lung Mun Road)	1511	С	0	20.9	851	29.77	
Point K (Lung Mun Road nr production Gallery)	1313	O.	0	20.9	85,2	29.77	

Instrument for O2 measurement: GasAlert MicroClip GAMIC-4-DL2 Serial no.: S103-13348

Site layout





Kaden Construction Limited


EPD Contract No. EP/SP/52/06 Job No. K0603 Development of EcoPark in Tuen Mun Area 38

Daily Air Monitoring 每日空氣監測記錄

Detector: Model 型號: GEM 2 測試器 S/N 編號: GM-08		t calibratio ct calibratio			Apr. 07 Apr. 08	
Date of Monitor 監測日期: 2	-5-	08		Performe	ed by: //	Ilian Won
Location	Time 時間			Result	結果	
位置	(hrs)	CH ₄ (%)	, CO ₂ (%)	O ₂ (%)	Bal. Gas (%)	Baro. Pressure ("Hg)
Point A	1410	0	O	20.9	84.8	29.71
Point J (Lung Mun Road)	1412	\circ	O	20.9	84.9	29,71
Point K (Lung Mun Road nr production Gallery)	1415	0	0	20.9	84,8	29.7)

Instrument for O2 measurement: GasAlert MicroClip GAMIC-4-DL2 Serial no.: S103-13348

Site layout





Kaden Construction Limited

EPD Contract No. EP/SP/52/06 Job No. K0603


Development of EcoPark in Tuen Mun Area 38

	Daily Air Monitoring						瓦監測	己錄		
	lel 型號 :	GEM 2	000		Las	t calibratio	n 上次檢	測: 0:	3 Apr. 07	
測試器 S/N	編號:	GM-08	793		Nex	t calibratio	on 下次檢	测: 0	2 Apr. 08	
Date of Monito	r 監測日期	: 20	1- Z	-08			Perform	ed by:	Villiam	Long
I	cation		Time	時間			Result	結果)
1	位置		(hr		CH ₄	CO ₂	O ₂	Bal. Gas	s Baro. P	ressure

Location	Time 時間	Result 結果				
位置	(hrs)	CH ₄ (%)	. CO ₂ (%)	O ₂ (%)	Bal. Gas	Baro. Pressure ("Hg)
Point A	15/0	0	Ô	20.9	84.7	29.55
Point J (Lung Mun Road)	1512	0	٥	209	850	29, 35
Point K (Lung Mun Road nr production Gallery)	1514	0	0	20.9	85	29.55

Instrument for O2 measurement: GasAlert MicroClip GAMIC-4-DL2 Serial no.: S103-13348

Site layout



APPENDIX 5 – CUMULATIVE LOG OF COMPLAINTS

CUMULATIVE LOG OF COMPLAINTS

Environmental	No. of Outstanding	No. of complaints received in May 2008	Cumulative no. of complaints received since the
Parameters	Complaints		commencement of project
Air	0	0	2
Noise	0	0	0
Water	0	0	0
Waste	0	0	0
Total	0	0	2

DETAILS OF COMPLAINTS AND REMEDIAL ACTIONS

Log Ref.	Date of Compliant received	Location	Complainant /Date	Details of Complaint	Investigation /Mitigation Action	Investigated by/ Date
-	-	-	-	-	-	-