#### **EXECUTIVE SUMMARY**

ANNEX C

ANNEX D

1	INTRODUCTIO	N
1.1	BACKGROU	VND
1.2	<b>ORGANISA</b>	TION OF THE REPORT
2	AIR QUALITY	
2.1	MONITORI	NG METHODOLOGY
2.2	CALIBRATI	ON REQUIREMENTS
2.3	MONITORI	NG PROCEDURES
2.4	MONITORI	NG RESULTS
3	NOISE	
3.1	MONITORI	NG METHODOLOGY
3.2	CALIBRATI	ON REQUIREMENTS
3.3	MONITORI	NG RESULTS
4	CONCLUSION	
4.1	BASELINE	LEVELS
4.2	ACTION AN	D TARGET LEVELS
AN	NEX A	TSP Baseline Measurements
AN	NEX B	Noise Baseline Measurements

EPD Approval Letter

Calibration Certificates for Monitoring Equipment

#### EXECUTIVE SUMMARY

#### Background

MTR Corporation Limited (MTRCL) proposes to build a new railway line, the West Island Line (WIL) which is an extension of the Island Line to the Western District. The route length of the fully underground WIL is approximately 3 km with three new underground stations namely Sai Ying Pun Station (SYP), University Station (UNI) and Kennedy Town Station (KET).

#### Impact Assessment and Baseline Monitoring

With the development of the Environmental Monitoring and Audit Manual (EM&A Manual) in accordance with the guideline set out in the Environmental Impact Assessment (EIA) report prepared by ENSR Asia (HK) Limited in October 2008, Baseline Monitoring (Part 8) have been conducted for both dust and noise at the proposed monitoring locations in the vicinity of Works Area A to establish baseline levels for both dust and noise for the civil construction work within Works Area A.

#### Results and Conclusions

Baseline monitoring (Part 8) had been carried out in accordance with the recommendations contained in the Technical Memoranda associated with EIAO, Air Pollution Control Ordinance and Noise Control Ordinance, where applicable. Results and Conclusions of the report were presented in the subsequent sections of the Baseline Monitoring Report.

#### 1 INTRODUCTION

#### 1.1 BACKGROUND

The West Island Line Project

MTR Corporation Limited (MTRCL) proposes to build a new railway line, the West Island Line (WIL) which is an extension of the Island Line to the Western District. The route length of the fully underground WIL is approximately 3 km with three new underground stations namely Sai Ying Pun (SYP), University (UNI) and Kennedy Town (KET).

The location of works areas is shown in Figure 1.

- 1.1.1 An EIA study (refer to EIA Report dated October 2008) has been conducted by ENSR Asia (HK) Limited for the proposed WIL Project. An EM&A Manual has provided guidelines in the preparation of this baseline monitoring report.
- 1.1.2 Baseline levels have been established for both dust and noise, by which the performance of the construction Contractor may be measured in meeting the required environmental protection standards and requirements under the Environmental Permit, during the course of the construction work. These are presented in subsequent sections of this report.
- 1.1.3 This Baseline Monitoring Report (Part 8) presents the results for the baseline monitorings conducted for both dust and noise at the proposed monitoring locations in the vicinity of Works Area A and establishes baseline levels for both dust and noise for the civil construction work within Works Area A. Baseline monitorings for other works areas are to be conducted subsequently and the baseline monitoring reports for these works areas will be submitted accordingly.

#### 1.2 ORGANISATION OF THE REPORT

Following the introduction, the remainder of this Report is arranged as follows:

_	Section 2	describes the air quality monitoring methodology and analyses the monitoring results;
_	Section 3	describes the noise quality monitoring methodology and analyses the monitoring results.
_	Section 4	Conclusions

#### 2 AIR QUALITY

#### 2.1 MONITORING METHODOLOGY

Monitoring was undertaken by the Environmental Team to establish baseline levels for both 1-hour and 24-hour Total Suspended Particulates (TSP) in the vicinity of the major works areas along WIL, namely the construction sites for stations/entrances and associated structures. This provides data against which any environmental impacts due to construction activities can be compared. During the construction period impact monitoring will only be conducted for 24-hour TSP, although 1-hour TSP monitoring may also be conducted and used in following up on complaints or exceedances, in order to provide a more rapid indication of the source of the problem at hand.

Baseline monitoring station (AM3a) which is approved as an alternative monitoring location to the original monitoring station (AM3) as specified in the EM&A Manual for both 1-hour and 24-hour TSP measurements has been established at Hong Kong Institute of Vocational Education (Tsing Yi) Kennedy Town Centre, see figure 2. The approval letter by EPD is attached in Annex D.

Three separate 1-hour TSP measurements daily for a period of at least 14 days were made at the monitoring stations to establish the ambient 1-hour TSP levels.

24-hour TSP measurements were carried out over a period of at least 14 days at the monitoring stations to establish the ambient 24-hour TSP levels.

24-hour samples were collected by High Volume Sampler (Graseby-Andersen) following United Sates Environmental Protection Agency regulations and 1-hour TSP levels were measured by real time dust monitor (MIE - DataRam).

#### 2.2 CALIBRATION REQUIREMENTS

The flow rate of the high volume sampler with mass flow controller will be calibrated using an orifice calibrator. Initial calibration (five points) will be conducted upon installation and prior to commissioning. Calibration will be carried out every six months by Science International Corporation. Calibration certificate is attached in Annex C.

The sensing system of MIE is calibrated by clean filtered air passing through the flow-sensing system, providing a controlled check of the zero-concentration condition. Calibration of the MIE by certified laboratory or manufacturer shall be carried out every two years by ThermoFisher Scientific and properly documented. Calibration certificate is attached in Annex C. The samplers shall be properly maintained. Prior to dust monitoring commencing, appropriate checks shall be made to ensure that all equipment and necessary power supply are in good working condition.

#### 2.3 **MONITORING PROCEDURES**

#### 1-Hour TSP Levels Monitoring

TSP is sampled by drawing air into the MIE where particulate concentrations are measured instantaneously with an in-built silicon detector sensing light scattered by the particles in the sampled air (optical sensing stage). Continuous TSP levels are indicated on the MIE along with a 'Time Weighted Average' value.

#### 24-Hour TSP Levels Monitoring

The sampling procedure follows to that described in the App. B of Pt 50 in 40CFR Ch.1 (U.S. Environmental Protection Agency). TSP is sampled by drawing air through a conditioned, pre-weighed filter paper inside the high volume sampler at a controlled rate. After 24-hour sampling the filter paper with retained particles shall be collected and returned to the laboratory for drying in a desiccator followed by accurate weighing. TSP levels are calculated from the ratio of the mass of particulate retained on the filter paper to the total volume of air sampled.

#### 2.4 **MONITORING RESULTS**

1-Hour TSP baseline monitoring was conducted at the monitoring station 2.4.1 between 10 December 2009 and 23 December 2009. The average 1-hour TSP baseline levels have been established from the baseline data listed in Annex A, and are shown in Table 2.4a below.

Weather conditions throughout the monitoring period were mild and relatively dry, with light wind normally from the north for the majority of the time, with some days from the northeast.

#### 1-hour TSP Baseline Level Table 2.4a

### **Monitoring Location** Average 1-h TSP Level (µg/m<sup>3</sup>) Hong Kong Institute of Vocational 50 Education (Tsing Yi) Kennedy Town Centre (AM3a)

Note: TSP levels are to the nearest whole number, with values of 0.5 rounded up It was noted that there was no construction work with dust generating activities in the vicinity as well as in Works Area A during the monitoring period. Road traffic was observed around the area along Ka Wai Man Road. The dust particulates from the exhaust fumes from the road traffic around the area contribute to the background TSP levels.

#### Action and Limit Levels

To provide an early indication of any deterioration in the Contractor's environmental performance, action levels were derived based on the measured baseline levels. Limit level is set at  $500\mu g/m^3$  for the 1-hour TSP level as recommended for consideration in the EIAO-TM.

For 1-hour TSP the action level for baseline smaller than or equal to  $384\mu g/m^3$  is the average of 130% of the baseline and the limit level. For baseline greater than  $384\mu g/m^3$  the action level is  $500\mu g/m^3$ . The derived level for the monitoring station is shown in *Table 2.4b* below.

Table 2.4b Baseline, Action and Limit Levels for 1-hour TSP

Monitoring Location	Baseline Level (µg/m3)	Action Level (µg/m3)	Limit Level (μg/m3)
Hong Kong Institute of Vocational Education (Tsing Yi) Kennedy Town Centre (AM3a)	50	283	500 <sup>(1)</sup>

<sup>(1) - 1-</sup>hour TSP criterion recommended in the EIAO-TM
Note: TSP levels are to the nearest whole number, with values of 0.5 rounded up

This baseline level can be expected to vary throughout the year, particularly with the weather changes between the wet and dry season, and changes in other construction works in the locality.

It is therefore recommended that baseline level be checked every six months, preferably when there are no MTRCL construction activities ongoing in the vicinity.

#### 2.4.2 24-hour TSP

24-hour TSP baseline monitoring was conducted at the monitoring station between 10 December 2009 and 23 December 2009.

Weather conditions throughout 24hour-TSP monitoring period were mild and relatively dry, with light wind normally from the north for the majority of the time, with some days from the northeast.

The averaged 24-hour TSP baseline level has been established from the baseline data listed in *Annex A*, and are shown in *Table 2.4c* below.

*Table 2.4c* 

#### 24-hour TSP Baseline Levels

#### **Monitoring Location**

Average 24-h TSP Level (µg/m³)

Hong Kong Institute of Vocational Education (Tsing Yi) Kennedy Town Centre (AM3a) 38

Note: TSP levels are to the nearest whole number, with values of 0.5 rounded up

It was noted that there was no construction work with dust generating activities in the vicinity as well as in Works Area A during the monitoring period. Road traffic was observed around the area along Ka Wai Man Road. The dust particulates generated from the exhaust fumes from the road traffic around the area contribute to the background TSP levels.

#### Action and Limit Levels

To provide an early indication of any deterioration in the Contractor's environmental performance, action levels were derived based on the measured baseline levels. The Air Quality Objective limit level for 24-hour TSP is set at  $260\mu g/m^3$ .

For 24-hour TSP the action level for baseline smaller than or equal to  $200\mu g/m^3$  is the average of 130% of the baseline and the limit level. For baseline greater than  $200\mu g/m^3$  the action level is  $260\mu g/m^3$ . The derived levels for each monitoring station are shown in *Table 2.4d* below.

Table 2.4d Baseline, Action and Limit Levels for 24-hour TSP

Monitoring Location	Baseline Level (µg/m³)	Action Level (μg/m³)	Limit Level (μg/m³)
Hong Kong Institute of Vocational Education (Tsing Yi) Kennedy Town Centre (AM3a)	38	155	260

Note: TSP levels are to the nearest whole number, with values of 0.5 rounded up

This baseline level can be expected to vary throughout the year, particularly with the weather changes between the wet and dry season, and changes in other construction works in the locality.

It is therefore recommended that baseline level be checked every six months, preferably when there are no MTRC construction activities ongoing in the vicinity.

#### 3 NOISE

#### 3.1 MONITORING METHODOLOGY

Monitoring was undertaken by the Environmental Team to establish noise baseline levels in the vicinity of the Works Area A, to provide data against which any environmental impacts due to construction activities can be compared.

The baseline monitoring station as specified in the EM&A Manual were established at the following location, see Figure 2:

## CN2 - Hong Kong Institute of Vocational Education (Tsing Yi) Kennedy Town Centre

Consecutive noise measurements were undertaken over a period of at least 14 days to establish the ambient noise levels at representative nearest sensitive receivers. Continuous 5 minute A-weighted noise levels were recorded throughout the daytime, evening and night-time on weekdays (Monday to Saturday) and also on Sundays. The noise levels were presented for weekdays over each 30 minute period between 0700 and 1900hr to produce the baseline conditions.

Monitoring was conducted using B&K sound analysis equipment – B&K SLM 2236. Microphones were extended 1.2 metres from building facades and oriented towards the works area.

Weather conditions throughout the monitoring period were mild and relatively dry, with light wind normally from the north, with some days from the northeast.

#### 3.2 CALIBRATION REQUIREMENTS

B&K 2236 sound level meters which complied with the International Electrotechnical Commission Publication 651:1979 (Type 1) and 804:1985 (Type 1), specification as referred to in the Technical Memoranda to the NCO were used for the baseline monitoring. The B&K sound level meters and B&K 4231 calibrator are verified by the certified laboratory or manufacturer once every two years by MaxLab Calibration Centre Limited to ensure they perform to the same level of accuracy as stated in the manufacturer's specifications. Calibration certificates are attached in Annex C.

Immediately prior to and following each set of measurements at any NSR, the accuracy of the sound level meter was checked using an acoustic calibrator generating a known sound pressure level at a known frequency. If the calibration levels before and after the measurement differ by more than 1.0dB the measurement shall be repeated to obtain a reliable result (note: maximum deviation during this initial baseline monitoring period was 0.3dB). Periods of prolonged or repeated overloading of the sound level meter detector were avoided by setting the meter with adequate headroom prior to commencing measurements. Measurements were recorded to the nearest 0.1 dB, with values of 0.05 being rounded up.

Limit levels for these locations are shown in *Table 3.3a*.

Table 3.3a Limit Levels for Construction Noise

Time Period	Noise Level (dl	B) for NSR around Works Area A
Daytime (0700-1900), M through Saturday exc Public Holidays	•	L <sub>Aeq 30mins</sub> 70 <sup>(1)</sup>
All evenings (1900-2300)	)	Subject to control under the Noise Control Ordinance
General Holidays (include Sundays) during the dand evening (0700-2300)	aytime	Subject to control under the Noise Control Ordinance
All night time periods 0700)	(2300-	Subject to control under the Noise Control Ordinance

<sup>(1)</sup> Limit level guideline, for educational establishments the limit level shall be 70, reduced to 65 during examination periods.

#### 3.3 MONITORING RESULTS

Noise baseline monitoring was conducted at the monitoring station CN2 between 10 December 2009 and 23 December 2009.

5 minute, "fast" detector response, levels were recorded in the following indices,  $L_{Aeq}$ ,  $L_{A10}$ ,  $L_{A90}$ . The baseline data was initially downloaded into a spreadsheet, directly from the noise loggers in ASCII format for checking, and then imported into the database. The  $L_{Aeq}$ , results for each 5 minute period of weekday were averaged. An average of two 24 hour Sunday periods was covered in the monitoring periods. 'Time Slot Averaged', 'Noise Control Period Averaged' baseline noise levels are presented for the monitoring location in *Annex B*.

At the monitoring station CN2, it was observed that the ambient noise and the vehicular traffic along Ka Wai Man Road contributed to the background noise.

#### 4 CONCLUSION

#### 4.1 BASELINE LEVEL

#### 4.1.1 Air

1-hour TSP

1-hour TSP baseline monitoring was conducted at the monitoring station, namely Hong Kong Institute of Vocational Education (Tsing Yi) Kennedy Town Centre (AM3a) between 10 December 2009 and 23 December 2009. Baseline TSP levels were recorded in the range of 32 µg/m<sup>3</sup> and 67 µg/m<sup>3</sup>.

24-hour TSP

24-hour TSP baseline monitoring was conducted at the monitoring station at Hong Kong Institute of Vocational Education (Tsing Yi) Kennedy Town Centre (AM3a) between 10 December 2009 and 23 December 2009. Baseline TSP results between  $18 \mu g/m^3$  and  $62 \mu g/m^3$  had been recorded.

#### 4.1.2 *Noise*

Baseline monitorings were conducted at the monitoring station, namely Hong Kong Institute of Vocational Education (Tsing Yi) Kennedy Town Centre (CN2) from 10 December 2009 to 23 December 2009. Baseline noise levels have been established for weekday and Sunday periods.

Baseline noise levels between 56 and 59 dB(A) had been recorded at the monitoring station CN2 from 0700 - 1900hr for the monitoring station.

The noise sources noticed at the monitoring station CN2 were the vehicular traffic along Ka Wai Man Road in the vicinity.

#### 4.2 ACTION AND TARGET LEVELS

#### 4.2.1 Air

1-hour TSP

The 1-hour TSP action level have been calculated from baseline levels and presented in Table 2.4b. Limit level is set at  $500 \,\mu\text{g/m}^3$  for the 1-hour TSP limit suggested in the EIAO-TM. The 1-hour TSP monitoring is intended to use in following up on complaints or exceedances, in order to provide a more rapid indication of the source of the problem at hand.

#### 24-hour TSP

24-hour TSP action levels have been calculated from baseline levels and are presented in Table 2.4d. The Air Quality Objective limit level for 24-hour TSP is set at 260  $\mu g/m^3.$ 

#### 4.2.2 *Noise*

Action level exceedance occurs when one or more documented complaints are received.

Limit level is set at  $L_{Aeq\ 30mins}70^{(1)}$  for normal working hours (i.e. 0700-1900 hours on any day not being a Sunday or general holiday), as suggested in EIAO-TM and the Practice Note for Professional Persons ProPECC PN2/93. For restricted hours (i.e. 1900-0700 hours for weekdays and all day on Sundays and general holidays), limit level shall be subjected to control under the Noise Control Ordinance (NCO).

<sup>&</sup>lt;sup>(1)</sup>Limit level guideline, for educational establishments the limit level shall be 70, reduced to 65 during examination periods.

# ANNEX A TSP Baseline Measurements

Project: West Island Line

Report for Location: Hong Kong Institute of Vocational Education (Tsing Yi) Kennedy Town Centre (AM3a)

Samples between: 10/12/2009 and 23/12/2009

Report Date 08/04/2010

Sample Code	<u>Date</u>	<b>Start Time</b>	<b>Parameter</b>	<b>Value</b>	<u>Unit</u>
AM3a/001	10/12/2009	13:00	Total Suspended Particulate (1 hr)	53.5	μg/cu.m
AM3a/002	11/12/2009	13:30	Total Suspended Particulate (1 hr)	50.6	μg/cu.m
AM3a/003	12/12/2009	13:45	Total Suspended Particulate (1 hr)	44.8	μg/cu.m
AM3a/004	13/12/2009	13:15	Total Suspended Particulate (1 hr)	38.4	μg/cu.m
AM3a/005	14/12/2009	14:35	Total Suspended Particulate (1 hr)	51.9	μg/cu.m
AM3a/006	15/12/2009	14:15	Total Suspended Particulate (1 hr)	61.0	μg/cu.m
AM3a/007	16/12/2009	13:00	Total Suspended Particulate (1 hr)	56.2	μg/cu.m
AM3a/008	17/12/2009	14:15	Total Suspended Particulate (1 hr)	50.5	μg/cu.m
AM3a/009	18/12/2009	14:15	Total Suspended Particulate (1 hr)	32.1	μg/cu.m
AM3a/010	19/12/2009	13:30	Total Suspended Particulate (1 hr)	66.3	μg/cu.m
AM3a/011	20/12/2009	13:15	Total Suspended Particulate (1 hr)	67.3	μg/cu.m
AM3a/012	21/12/2009	13:45	Total Suspended Particulate (1 hr)	47.8	μg/cu.m
AM3a/013	22/12/2009	14:00	Total Suspended Particulate (1 hr)	39.0	μg/cu.m
AM3a/014	23/12/2009	13:15	Total Suspended Particulate (1 hr)	42.5	μg/cu.m

Note: The figures are the average of 3 separate 1-hour TSP measurements obtained daily

Project: West Island Line

Report for Location: Hong Kong Institute of Vocational Education (Tsing Yi) Kennedy Town Centre (AM3a)

Samples between: 10/12/2009 and 23/12/2009

Report Date 08/04/2010

Sample Code	<u>Date</u>	<u>Parameter</u>	<u>Value</u> <u>Unit</u>
AM3a/001	10/12/2009	Total Suspended Particulate (24 hr)	43.5 µg/cu.m
AM3a/002	11/12/2009	Total Suspended Particulate (24 hr)	37.9 μg/cu.m
AM3a/003	12/12/2009	Total Suspended Particulate (24 hr)	33.5 µg/cu.m
AM3a/004	13/12/2009	Total Suspended Particulate (24 hr)	27.6 µg/cu.m
AM3a/005	14/12/2009	Total Suspended Particulate (24 hr)	37.9 μg/cu.m
AM3a/006	15/12/2009	Total Suspended Particulate (24 hr)	45.4 µg/cu.m
AM3a/007	16/12/2009	Total Suspended Particulate (24 hr)	39.9 μg/cu.m
AM3a/008	17/12/2009	Total Suspended Particulate (24 hr)	42.0 µg/cu.m
AM3a/009	18/12/2009	Total Suspended Particulate (24 hr)	18.1 μg/cu.m
AM3a/010	19/12/2009	Total Suspended Particulate (24 hr)	52.6 μg/cu.m
AM3a/011	20/12/2009	Total Suspended Particulate (24 hr)	61.8 µg/cu.m
AM3a/012	21/12/2009	Total Suspended Particulate (24 hr)	31.4 µg/cu.m
AM3a/013	22/12/2009	Total Suspended Particulate (24 hr)	29.1 μg/cu.m
AM3a/014	23/12/2009	Total Suspended Particulate (24 hr)	34.7 µg/cu.m

Note: 1. The air sampler is operated in constant flow rate

# ANNEX B Noise Baseline Measurements

#### **Noise Baseline Report**

Project: West Island Line

Report for Location: Hong Kong Institute of Vocational Education (Tsing Yi) Kennedy Town Centre (CN2)

Baseline between: 10/12/2009 - 23/12/2009

Report date: 08/04/2010

Parameter: Leq

Time Slot Averaged Baselines
Weekdays Noise Level, dB(A)

Weekdays Noise Le	evel, ub(A)		
	LAeq,30min	L10	L90
07:00-07:30	56.4	57.4	54.7
07:30-08:00	57.1	58.1	55.5
08:00-08:30	57.2	58.2	55.7
08:30-09:00	57.7	58.8	56.0
09:00-09:30	57.8	58.8	56.2
09:30-10:00	57.7	58.9	55.9
10:00-10:30	58.0	59.2	55.9
10:30-11:00	58.0	59.5	55.6
11:00-11:30	57.9	59.2	56.0
11:30-12:00	58.7	59.8	56.3
12:00-12:30	56.5	57.8	54.7
12:30-13:00	57.1	57.8	54.6
13:00-13:30	57.8	59.5	55.4
13:30-14:00	57.4	58.6	55.3
14:00-14:30	57.3	58.5	55.1
14:30-15:00	57.1	58.2	54.9
15:00-15:30	57.0	58.2	54.9
15:30-16:00	57.0	58.4	54.9
16:00-16:30	57.0	58.2	54.8
16:30-17:00	57.3	58.4	54.5
17:00-17:30	56.4	57.8	54.0
17:30-18:00	56.4	57.9	53.9
18:00-18:30	56.1	57.6	53.7
18:30-19:00	55.9	57.5	53.2
Noise Control Peri	od Averaged Baselines		
Weekdays Noise Le	evel, dB(A)		
	LAeq,30min	L10	L90
07:00-19:00	57.3	58.5	55.1

	LAeq,30min	L10	L90
07:00-19:00	57.3	58.5	55.1
	LAeq,5min	L10	L90
19:00-23:00	55.1	56.5	52.4
23:00-07:00	55.4	56.4	51.8

#### Sundays/General Holidays Noise Level, dB(A)

	LAeq,5min	L10	L90
07:00-19:00	57.3	58.5	55.2
19:00-23:00	55.1	56.8	52.2
23:00-07:00	54.2	55.3	51.3

Logarithmic Averaging is being used.

## ANNEX C

Calibration Certificates for Monitoring Equipment



#### **ThermoFisher**

S C I E N T I F I C 27 FORGE PARKWAY FRANKLIN MA 02038

TOLL FREE: 866-282-0430

TEL: 508-553-6949 FAX: 508-541-8366 www.thermo.com/agi

### **DR2000 CALIBRATION CERTIFICATE**

This calibration is traceable to the National Institute of Standards and Testing

SERIAL NUMBER:	<u>2003</u>
CALIBRATION RATIO:	<u>0.991</u>
AVG. DR CONCENTRATION:	2.47 mg/m3
_MASTER AVG CONCENTRATION:	2.04 mg/m3
PDR BACKROUND CONCENTRATION:	0.332 mg/m3

**TEMPERATURE:** 73 F RH: 39 %

CALIBRATION MASTER: D187 LAST CALIBRATED: 5/1/2009

TECHNICIAN: \_\_\_\_ KL DATE: \_\_\_\_ 5/19/2009



#### ANDERSEN INSTRUMENTS INC.

#### GS2310 Series Sampler Calibration

#### (Dickson Recorder)

61	וייו
- ` \	ır

			SITE						
Location -	> HK IVE	(TSING Y	I) KENN	EDY TOWN CENT	RE Date -	> 29-Ju1-09			
	-> 694-066				h -> Chan Kin Fu	ng			
CONDITIONS									
Sea Level Pressure	(hpa)	1003		Sampler Elevation	(feet)	200			
Sea Level Pressure	(in Hg)	29.62		Corrected Pressure	(mm Hg)	747.20			
Temperature	(deg C)	32		Temperature	(deg K)	305.00			
Seasonal SL Pressure	` • ·	29.62		Corrected Seasonal	(mm Hg)	747.20			
Seasonal Temperatur	`	32.00		Seasonal Temperati	ıre(deg K)	305.00			
		CALIBR	ATION	ORIFICE					
Make ->	Anderse	en Instrumer	nts Inc.		Qstd Slope -				
Model ->	25A				Qstd Intercept -	> -0.014012			
Serial# ->	5303				Date Certified -	>			
		CA	LIBRAT	ION					
Plate or	$H_2O$	Qstd	I	IC	LINEAR				
Test #	(in)	$(M^3/min)$	(chart)	(corrected)	REGRESSIC				
1 18	12.4	1.741	59	57.826	Slope				
2 13	10.1	1.572	53	51.945	Intercept				
3 10	7.7	1.374	45	44.104	Corr. Coeff.	= 0.9930			
4 7	4.9	1.097	35	34.303					

Calculations

 $Qstd = 1/m [Sqrt (H_2O (Pa/Pstd) (Tstd/Ta)) - b]$ 

0.860

IC = I [Sqrt (Pa/Pstd) (Tstd/Ta)]

Ostd = standard flow rate

IC = corrected chart response

I = actual chart response

m = calibrator Qstd slope

b = calibrator Qstd intercept

Ta = actual temperature during calibration (deg K)

Pa = actual pressure during calibration (mm Hg)

Tstd = 298 deg K

Pstd = 760 mm Hg

For subsequent calculation of sampler flow:

1/m ((I) [Sqrt (298/Tav) (Pav/760)] - b)



m = sampler slope

b = sampler intercept

I = chart response

Tay = daily average temperature

Pav = daily average pressure

This is to certify that the above equipment has been calibrated in accordance with manufacturer's procedure.



#### Balance Calibration Report Tested to MTRC Method WI/707M/01

Laboratory Equipment Identification Number				BA0011	
Manufacturer	Sartorius	Model	A200S-**DIB	Serial No.	1065989
Capacity	120g Discrimination		0.1mg	Туре	Top Loading
Location	Concrete Testing Area		Temperature	25℃	

Reference Mass Set U	Jsed (Equip. ID. No.)	RM001		
Manufacturer	Troemner	OIML Classification	F1	
Last Calibration Date	29-04-2002	Calibrated By	South China National Centre of Metrology	

(1) Repeatability of Reading

Reference Mass (g)	Standard Deviation of Balance Reading (g)	Maximum Difference Between Successive Readings (g)
10	0.000071	0.0002
60	0.0001333	0.0002
120	0.0001287	0.0003

Standard Deviation of the Balance = 0.0001333

#### (2) Departure from Nominal Value

Reading (g)	Correction (g)	Uncertainty (g)
10.0001	-0.0001	
20.0001	-0.00005	
30.0001	-0.00005	-
40.0001	0.00003	
50.0002	-0.00028	±0.000361
60.0001	-0.00018	
70.000	0.00002	
80.0001	-0.00008	
90.0000	0.00005	•
100.0001	-0.00025	

Maximum Correction = -0.00028

#### MTR Corporation Internal Calibration



#### (3) Off-Centre Loading

A mass of approximately 60 was moved to various position on the balance pan. The balance readings obtained at different position are given in the table.

Centre	Front	Back	Left	Right
60.0001	60.0001	60.0004	59.9997	59.9997

#### Maximum Difference = 0.0007

#### (4) Hysteresis

Load	Hysteresis
(g)	(g)
50	-0.0001333

#### (5) Limit of Performance of the Balance = $\pm 0.000680$

Checked by :	Kenny Li	Certified by:	(dy #0
Date :	13-02-2009	Date :	16 /2/2009

#### Notes:

- 1. The balance has been tested according to the specifications laid down in Chapter 6 of the CSIRO Publication "The Calibration of Balances by David B. Prowse".
- 2.Uncertainties quoted in this report have been estimated on the basis of there being not more than one chance in one hundred that any value differs from the true value by more than the stated uncertainty.
- 3. The Limit of Performance is the tolerance band within which all readings of the balance will fall.

Calibration Certificates for Sound Level Meter and Calibrator



#### **IAXLAB CERTIFICATE** CALIBRATION

#### Certificate Information

Date of Issue

30th December, 2008

Certificate Number

MLCN081194S

#### **Customer Information**

Company Name

Address

MTR Corporation Limited

MTR Tower, Telford Plaza,

33 Wai Yip St., Kowloon Bay,

Kowloon, Hong Kong

#### Unit Under Test (UUT)

Description

Precision Integrating Sound Level Meter

Manufacturer

Brüel & Kjær

Model Number

Type 2236

Serial Number

1794284

**Equipment Number** 

#### Calibration Result

- The UUT range indication was found defective, but range selection and measurement were
- \* All calibration results are within the manufacturer's specification.
- \* Calibration data are detailed on the attached sheet(s).

#### Approved By

Laboratory Manager

- Calibration equipment used for this calibration are traceable to national / international standards.
- The results on this Calibration Certificate only relate to the values measured at the time of the calibration and the uncertainties quoted will not include allowance for the UUT long term drift, variation with environmental changes, vibration and shock during transportation, overloading, mishandling, misuse, and the capacity of any other laboratory to repeat the measurement.
- MaxLab Calibration Centre Limited shall not be liable for any loss or damage resulting from the use of the UUT.

  The copy of this Certificate is owned by MaxLab Calibration Centre Limited. No part of this Certificate may be reproduced without the prior written approval of MaxLab Calibration Centre Limited.

Page 1 of 2



## **//AXLAB**

### **CALIBRATION CERTIFICATE**

Certificate Information

Date of Issue

30<sup>th</sup> December, 2008

Certificate Number

MLCN081194S

Calibration Status

Date of Calibration

Calibration Equipment Used

Calibration Procedure

Calibration Uncertainty

30<sup>th</sup> December, 2008

4231 (MLTE008)/ CA0801167/ 24th Feb 2010

MLCG00 & MLCG15.

±0.2 dB

Calibration Condition

Lab

UUT

**Temperature** 

Relative Humidity

Stabilizing Time

Warm-up Time Supply Voltage 23 °C ± 5 °C

 $55\% \pm 25\%$ 

24 hours

10 minutes

Not applicable

Calibration Data																
UUT Setting									THE P.							
Frequency Wt.	Parameter	Response	Range (dB)	UUT Rdg		UUT Rdg		UUT Rdg		UUT Rdg		Std Rdg	;	UUT E	rror	UUT Error Limit
A	SPL	F	20 - 100	93.9	dB	94	dΒ	-0.1	dB	0.7 dB						
(1 kHz Input)		S		93.9	dB	94	dB	-0.1	dB	0.7 dB						
		I		93.9	dB	94	dΒ	-0.1	ďΒ	0.7 dB						
С		F	20 - 100	93.9	dB	94	dΒ	-0.1	dB	0.7 dB						
(1 kHz Input)		S		93.9	dΒ	94	dΒ	-0.1	dB	0.7 dB						
		I		93.9	dΒ	94	dΒ	-0.1	dB	0.7 dB						
. L		F	20 - 100	94.0	dB	94	dВ	0.0	dB	0.7 dB						
(1 kHz Input)		S		94.0	dB	94	dB	0.0	dB	0.7 dB						
		I		94.0	dB	94	dB	0.0	dB	0.7 dB						
Α		F	40 - 120	113.9	dB	114	dB	0.1	dB	0.7 dB						
(1 kHz Input)		·S		113.9	dB	114	dB	-0.1	dB	0.7 dB						
		I		113.9	dB	114	dB	-0.1	dB	0.7 dB						



## MAXLAB CALIBRATION CERTIFICATE

#### Certificate Information

Date of Issue

6<sup>th</sup> November, 2008

Certificate Number

MLCN080969S

#### **Customer Information**

Company Name

Address

MTR Corporation Limited MTR Tower, Telford Plaza,

33 Wai Yip St., Kowloon Bay,

Kowloon, Hong Kong

#### Unit Under Test (UUT)

Description

Sound Level Calibrator

Manufacturer

Brüel & Kjær

Model Number

4231

Serial Number

1795385

Equipment Number

\_

#### Calibration Result

- \* All calibration results within the manufacturer's specification.
- \* Calibration data are detailed on the attached sheet(s).

#### Approved By

1

Laboratory Manager

- \* Calibration equipment used for this calibration are traceable to national / international standards.
- \* The results on this Calibration Certificate only relate to the values measured at the time of the calibration and the uncertainties quoted will not include allowance for the UUT long term drift, variation with environmental changes, vibration and shock during transportation, overloading, mishandling, misuse, and the capacity of any other laboratory to repeat the measurement.
- \* MaxLab Calibration Centre Limited shall not be liable for any loss or damage resulting from the use of the UUT.
- \* The copy of this Certificate is owned by MaxLab Calibration Centre Limited. No part of this Certificate may be reproduced without the prior written approval of MaxLab Calibration Centre Limited.

Page 1 of 2



# MAXLAB CALIBRATION CERTIFICATE

Certificate Information

Date of Issue

6<sup>th</sup> November, 2008

Lab

Certificate Number

MLCN080969S

Calibration Status

Date of Calibration

6th November, 2008

Calibration Equipment Used

4231 (Spec) (MLTE008)/ CA0801167/ 24<sup>th</sup> Feb 2008 1351 (MLTE049)/ MLEC08/06/02/ 14<sup>th</sup> Jun 2009

MLCG00 & MLCG15.

Calibration Procedure
Calibration Uncertainty

± 0.1 dB

Calibration Condition

**Temperature** 

23 °C ± 5 °C

Relative Humidity

55% ± 25%

UUT Stabilizing Time

24 hours

Warm-up Time

Not applicable

Supply Voltage

Not applicable

Cal	ibration Dat	a			
1	UUT Setting		STD Rdg	UUT Error	UUT Error Limit
	94	dB	94.0 dB	0.0 dB	0.2 dB
	114	dB	114.0 dB	0.0 dB	0.2 dB

# ANNEX D EPD Approval Letter

YOUR REF: 促血原 TEL NO: 202

TEL. NO.: 2835 1142 廣文傳送

FAX NO.: 2591 0558 设计例件 E-MAIL:

例 业 HOMEPAGE: http://www.epd.gov.hk Environmental Protection Department Branch Office

> 28th Floor, Southorn Centre, 130 Hennessy Road, Wan Chai, Hong Kong.



環境保護署分處 香港別任 軒尼詩道 一百三十號 修慎中心作八樓

10 August 2009

By Post & Fax: 2798 8822

(Total 1 page)

MTR Corporation Limited, MTR Headquarters Building, Telford Plaza, Kowloon Bay, Kowloon, Hong Kong.

(Attn.: Dr. Glenn Frommer, Head of Sustainability Development)

Dear Sir,

# Environmental Impact Assessment (EIA) Ordinance, Cap.499, West Island Line (WIL) (Environmental Permit no. EP-313/2008/B)

# EP Conditions 6.1: Change to Environmental Monitoring & Audit (EM&A) Programme Proposal for 3 Alternative Construction Air Quality Monitoring Stations AM3a, AM6a & AM7a

We refer to your letter dated 23 July 2009, enclosing the above proposal, duly certified and verified by ET Leader and IEC respectively, for our approval as required under Condition 6.1 of EP-313/2008/B.

Having carefully reviewed the submission, the above proposal for 3 Alternative Construction Air Quality Monitoring Stations AM3a, AM6a & AM7a to replace the original stations AM3, AM6 & AM7 satisfies the 3 criteria for alternative monitoring locations as stipulated in the approved EM&A Manual section 9.13 and is considered generally in order and is approved. The proposal will be placed on the EIAO Register.

If you have any queries, please contact our Mr. Steve Li at 2835 1142.

Sustainability Development
Department

SP#

Rec'd On: 1 | AUG ZUU9 Encl |

Copy To:

Cir To: File Ref:

Yours sincerely,

(Victor W.1. YEUNG)

Senior Environmental Protection Officer for Director of Environmental Protection

internal

EO(EA) – please place softcopy & hardcopy of submission at  $f_{*}(3)$  on EIAO Register & website. S(RS)1 – with copy of MTRCL letter + encl. dated 23-7-09 at  $f_{*}(3)$ .

HKI Projects WIL EIAO Resubl09Aug07Lt - alternative air stations AM3,6,7 .doc

"一个大型"的"A"。这个人的

TOTAL P.01 P.01