MITIGATION MEASURES LEGEND

MM1	MINIMISING TOPOGRAPHICAL CHANGE
MM2	DETAILED DESIGN - VISUAL *
MM3	OPEN SPACE PROVISION
MM4	TREE PROTECTION AND PRESERVATION
MM5	TREE TRANSPLANTATION
MM6	SLOPE LANDSCAPING
MM7	COMPENSATORY PLANTING
MM8	WOODLAND COMPENSATORY PLANTING
MM9	VERTICAL GREENING
MM10	GREEN ROOF
MM11	SCREEN PLANTING
MM12	ROAD GREENING
MM13	MARSH/ WETLAND COMPENSATION
MM14.1	WATERCOURSE IMPACT MITIGATION - REPROVISION OF NATURAL STREAM
MM14.2	WATERCOURSE IMPACT MITIGATION - STREAM BUFFER PLANTING
MM14.3	WATERCOURSE IMPACT MITIGATION - ENHANCEMENT PLANTING ALONG EMBANKMENT
MM14.4	WATERCOURSE IMPACT MITIGATION - AVOID AFFECTING WATERCOURSES
MM15	POND REPLACEMENT
MM16	SCREEN HOARDING *
MM17	LIGHT CONTROL *

* Mitigation Measure(s) (MM) does/ do not include in this plan is/are considered good practice throughout the NDA.

N

0 50 100 (metres) 200

1:2500 @ A3

FUNG KONG SHAN

3m HIGH VERTICAL NOISE BARRIER (ABSORPTIVE) MM2, MM9

MM7, MM11

5m HIGH + 3m INCLINED CANOPY NOISE BARRIER (ABSORPTIVE) MM2, MM9

DP 4 ROAD D4

FUNG KONG GARDEN

KWU TUNG NORTH NDA BOUNDARY

5m HIGH + 3m INCLINED CANOPY NOISE BARRIER (ABSORPTIVE) MM2, MM9

MM4

MM5, MM6

DP 3 KTN NEW DISTRIBUTOR RD. P1 AND ASSOCIATED INTERCHANGE

MM1, MM7, MM11 MM12

5m HIGH + 3m INCLINED CANOPY NOISE BARRIER (ABSORPTIVE) MM2, MM9

MM11, MM12

DP 4 ROAD D3

3m HIGH VERTICAL NOISE BARRIER (ABSORPTIVE) MM2, MM9

3m HIGH VERTICAL NOISE BARRIER (ABSORPTIVE) MM2, MM9

LEGEND

PRIMARY DISTRIBUTOR - ROAD P1

DISTRICT DISTRIBUTOR - ROAD D3/D4

ROAD

GREEN ROOF (MM10)

CYCLE TRACK / FOOTPATH

MM8 BOUNDARY

ENCLOSURE (SEMI / FULL)

WATER POND/ FEATURE

CEDD 土木工程拓展署 CIVIL ENGINEERING AND DEVELOPMENT DEPARTMENT

規劃署 PLANNING DEPARTMENT

ARUP

Job Title: Agreement No. CE 61/2007 (CE) North East New Territories New Development Areas Planning and Engineering Study - Investigation

Drawing Title: **KTN NDA LANDSCAPE MITIGATION PLAN (ZOOM C)**

Rev	Description	Date
-		29/01/13

Drawn: LM | Date: 29/01/13 | Checked: LFM | Approved: EC | Scale:

Drawing No.: **Figure 12.52.53** Rev.