ISO A1 594mm x 841mm

Approved:

Checked:

Designer:

Project Management Initials:

NOTE:

1. THIS DRAWING TO BE READ IN CONJUNCTION WITH DRAWING NOS. 60662428/C16/FIGURE 3.18.1 AND FIGURE 3.18.2.

LEGEND:

- SITE BOUNDARY
- 500m ASSESSMENT AREA
- RECLAMATION WORKS EXTENT
- N1 — 5.5m HIGH NOISE BARRIER WITH 3.5m CANTILEVER (45 DEGREE)
- N2 — 5.5m HIGH NOISE BARRIER WITH 3.5m CANTILEVER (45 DEGREE)
- N3 — 5m HIGH NOISE BARRIER WITH 1m CANTILEVER(45 DEGREE)
- N4 — 3.5m HIGH NOISE BARRIER WITH 1m CANTILEVER(45 DEGREE)
- N5 — 5m HIGH NOISE BARRIER (VERTICAL)
- N6 — 5m HIGH NOISE BARRIER (VERTICAL)
- N7 — 6m HIGH NOISE BARRIER (VERTICAL)
- SEMI ENCLOSURE WITH ENCLOSED SIDE COLORED RED
- A1 — REPRESENTATIVE AIR SENSITIVE RECEIVERS
- 30 — CONTOUR
- (19,31) — PATH GRIDS

N

816000 E

817500 E

819000 N

817500 N

CUT LINE A-A
SEE DRAWING NO. 60662428/C16/FIGURE 3.18.2

Proposed Limit of Reclamation

TSZ KAN CHAU 匙羹洲

TAI HO WAN 大蠔灣

LAU FA TUNG 榴花峒

LO FU TAU 老虎頭

SHUN LONG ROAD 順朗路

CHEUNG TUNG ROAD 大嶼山公路

SIU HO WAN 小蠔灣

NGAU TAU WAN 牛頭灣

Sham Shui Kok 深水

Tung Yip Hang 東業坑

Sewage Treatment Works 污水處理廠

Water Treatment Works 濾水廠

Railway Depot 鐵路車廠

Lookout 瞭望台

Pak Mong

Tunnel

AQOs CONCENTRATION LIMIT

NO2	19TH HOURLY	200	μg/m³
	10TH DAILY	120	μg/m³
	ANNUAL	40	μg/m³
RSP	10TH DAILY	75	μg/m³
	ANNUAL	30	μg/m³
FSP	19TH DAILY	37.5	μg/m³
	ANNUAL	15	μg/m³

V:\BAKU\S95-BAKUCSWP\plotdrv\Create Plt file\newVCSWP-75(color).pltPlot File by: haiquan.zhaoPATH: P:\PROJECTS\60662428\DRAWING\REPORT\C16\C16_980.dgn6/6/2025

This drawing has been prepared for the use of AECOM's client. It may not be used, modified, reproduced or relied upon by third parties, except as agreed by AECOM or as required by law. AECOM accepts no responsibility, and denies any liability whatsoever to any party that uses or relies on this drawing without AECOM's express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.

AECOM

PROJECT 項目

ROAD P1 (TAI HO - SUNNY BAY SECTION), LANTAU - INVESTIGATION

CLIENT 業主

土木工程拓展署
Civil Engineering and Development Department

CONSULTANT 工程顧問公司

AECOM Asia Company Ltd.
www.aecom.com

SUB-CONSULTANTS 分判工程顧問公司

ISSUE/REVISION 修訂

I/R 修訂	DATE 日期	DESCRIPTION 內容摘要	CHK. 核對

STATUS 階段

SCALE 比例
A3 1 : 15000

DIMENSION UNIT 尺寸單位
METRES

KEY PLAN 索引圖 A3 1 : 450000



PROJECT NO. 項目編號
60662428

AGREEMENT NO. 協議編號
CE 75/2020(HY)

SHEET TITLE 圖紙名稱
CONTOURS OF CUMULATIVE 10th HIGHEST DAILY AVERAGED NO2 CONCENTRATION AT 5mAG DURING OPERATION PHASE
SHEET 1 OF 2

SHEET NUMBER 圖紙編號
60662428/C16/FIGURE 3.19.1