

東業德勤測試顧問有限公司
ETS-TESTCONSULT LIMITED

8/F, Block B, Veristrong Industrial Centre, 34-36 Au Pui Wan Street, Fotan, Hong Kong

Tel : 2695 8318

E-mail : etl@ets-testconsult.com

Fax : 2695 3944

Web site : www.ets-testconsult.com

TEST REPORT

WO HING – PENTA-OCEAN JOINT VENTURE

**CONTRACT NO. 9/WSD/08
LAYING OF WESTERN CROSS
HARBOUR MAIN AND ASSOCIATED
LAND MAINS FROM WEST
KOWLOON TO SAI YING PUN
MONTHLY EM&A REPORT
NO.7**

(NOVEMBER 2010)

Prepared by:

LAW, Sau Yee
Senior Environmental Officer

Checked by:

LAU, Chi Leung
Environmental Team Leader

Issued Date: 08 December 2010

Report No.: ENA01144

ENVIRON

Ref.: WSDWHCMSEI00_0_0116L.10

14th Dec, 2010

Water Supplies Department
Sha Tin Office
6/F Sha Tin Government Offices
1 Sheung Wo Che Road
Sha Tin, NT

By Post

Attention: Ms. Candy Wong

Dear Ms. Wong


Re: Contact No. 9/WSD/08
Laying of Western Cross Harbour Main and Associated Land Mains from West Kowloon to Sai Ying Pun
Monthly Environmental Monitoring and Audit Report No. 7

Reference is made to Environment Team's submission of the Environmental Monitoring and Audit Report No. 7 by Email on 8th Dec 2010 (entitled "9/WSD/08 - Draft Monthly Report (November 10)") and the subsequent revision of the report by Email on 12th Dec 2010.

We are pleased to inform you that we have no comment on the revised captioned report.

Thank you very much for your kind attention and please do not hesitate to contact the undersigned should you have any queries.

Yours sincerely,



David Yeung
Independent Environmental Checker

c.c.	Mott MacDonald Hong Kong Limited	Mr. Kelvin Ho	Fax: 2377 2900
	Wo Hing – Penta-Ocean Joint Venture	Mr. Danny Ho	Fax: 2572 4080
	ETS-TESTCONSULT LIMITED	Mr. C.L. Lau	Fax: 2695 3944

Q:\Projects\WSDWHCMSEI00\Corr\Out\WSDWHCMSEI00_0_0116L.10.doc



TABLE OF CONTENTS

EXECUTIVE SUMMARY

1.0	INTRODUCTION	1
2.0	PROJECT INFORMATION	
	2.1 Scope of the Project	1
	2.2 Work Programme	1
	2.3 Project Organization and Management Structure	1
	2.4 Contact Details of Key Personnel	1
3.0	WORK PROGRESS IN THIS REPORTING MONTH	1
4.0	NOISE MONITORING	
	4.1 Monitoring Requirements	2
	4.2 Monitoring Equipment	2
	4.3 Monitoring Parameters, Duration and Frequency	2
	4.4 Monitoring Locations	2 – 3
	4.5 Monitoring Methodology	3 – 4
	4.6 Action and Limit levels	4
	4.7 Event-Action Plans	4
	4.8 Results	4 – 7
5.0	WATER QUALITY MONITORING	
	5.1 Monitoring Requirements	7
	5.2 Monitoring Locations	7
	5.3 Monitoring Parameters	8
	5.4 Monitoring Frequency	8
	5.5 Monitoring Methodology and Equipment Used	8 – 9
	5.6 Details of site Equipment used for In-situ Measurement	9
	5.7 Quality Assurance (QA) / Quality Control (QC) results and Determination Limits	10
	5.8 Action and Limit Level	10
	5.9 Event and Action Plan	10
	5.10 Monitoring Duration and Period In this reporting month	10 – 11
	5.11 Results	11
6.0	SITE INSPECTION	11
	6.1 Summary of the ET weekly site inspection findings	11
	6.2 Recommendations on site inspection findings in Site Inspections of this month	12
7.0	STATUS OF ENVIRONMENTAL PERMITS	12
8.0	WASTE MANAGEMENT	
	8.1 Monthly Waste Summary	12 – 13
	8.2 Advice on the Solid and Liquid Waste Management Status	13
9.0	ENVIRONMENTAL NON-CONFORMANCE	
	9.1 Summary of Noise and Water Quality	13
	9.2 Summary of Environmental Complaints	13
	9.3 Summary of Notification of Summons and Prosecution	14
10.0	IMPLEMENTATION STATUS	
	10.1 Implementation Status of Environmental Mitigation Measures	14
	10.2 Implementation Status of Event and Action Plan	14
	10.3 Implementation Status of Environmental Complaint, Notifications of Summons and Successful Prosecutions Handling	14
11.0	CONCLUSION AND RECOMMENDATIONS	14 – 15
12.0	FUTURE KEY ISSUE	
	12.1 Work Programme for the Coming Month	15
	12.2 Key Issues for the Coming Month	15 – 16
	12.3 Monitoring Schedule for the Coming Month	16



APPENDIX

A	Organization Chart and Lines of Communication
B1	Calibration Certificates for Impact Noise Monitoring Equipment
B2	Impact Noise Monitoring Results
B3	Graphical Plots of Impact Noise Monitoring Data
C1	Calibration Certificates for Impact Water Quality Monitoring Equipment
C2	Impact Water Quality Monitoring Results
C3	Graphical Plots of Impact Water Quality Monitoring Data
C4	QA/QC Results of Laboratory Analysis for Water Samples
D	Event-Action Plans
E	Work Programme
F	ET Weekly Site Inspection Records
G	Implementation Schedule of Mitigation Measures
H	Site General Layout Plan
I	Monitoring Schedule for this month and Coming Month
J	Daily dredging Summary
K	Details of Interim Notifications of Exceedance (NOEs) in this report month
L	Contractor's Follow up Actions to ET Weekly Site Inspections

Figures

Figure 1	Location of Noise Monitoring Station at West Kowloon
Figure 2	Location of Noise Monitoring Stations at Sai Yung Pun
Figure 3	Locations of Water Quality Monitoring Stations
Figure 1.2a	Locations of Water Sensitive Receivers and stormwater outfalls at Western Harbour
Figure 1.2b	Locations of Noise Sensitive Receivers at Sai Ying Pun
Figure 1.2c	Locations of Noise Sensitive Receivers at West Kowloon

Tables

2.1	Contact Details of Key Personnel
4.1	Noise Monitoring Equipment
4.2	Duration, Frequency and Parameters of Noise Monitoring
4.3	Noise Monitoring Stations
4.4	Action and Limit levels for Noise Monitoring
4.5	Summary of Noise Daytime Monitoring Results
5.1	Water Quality Monitoring Stations
5.2	Water Quality Monitoring Parameters
5.3	Other relevant water quality parameters
5.4	Monitoring Frequency of Impact Water Quality Monitoring
5.5	Details of Monitoring Equipment (In-situ measurement)
5.6	Summary of test method
5.7	Water Quality Action and Limit Levels
5.8	Schedule for Impact Water Quality Monitoring
5.9	Summary of Impact Marine Water Quality Exceedances in this reporting month
6.1	Summary of Site Inspection Findings
7.1	Summary of Environmental Licensing and Permit valid in this reporting month
8.1	Summary of Quantities of Waste for Disposal in this reporting month
10.1	Summary of Environmental Complaints and Prosecutions



EXECUTIVE SUMMARY

Under the requirements of "Environmental Monitoring & Audit Manual – Agreement No. CE42/2005(W/S) Laying of Western Cross Harbour Main and Associated Land Main from West Kowloon to Sai Ying Pun" (the EM&A Manual), impact noise monitoring and water quality monitoring is required to be implemented for the "Contract No. 9/WSD/08 Laying of Western Cross Harbour Main and Associated Land Main from West Kowloon to Sai Ying Pun" (the Project).

This monthly Environmental Monitoring and Audit (EM&A) report No.7 was prepared by ETS-Testconsult Ltd (ET) for the Project. This report documented the findings of EM&A Works conducted during the Project in November 2010.

Site Activities

As informed by the Contractor, the site activities in this reporting month were as below:

- *Dredging of Type 1 marine sediment (between CH0 and CH1560 at Portion I);*
- *Drilling of pipe piles (Portion J);*
- *Preparation of construction joint of the coated and lined pipe (Portion H1 & H2); and*
- *Outfitting of the launching barge (Portion H1 & H2).*

Environmental Monitoring Progress

The summary of the monitoring activities in this monitoring month is listed below:

- *Day-time Noise Monitoring (0700-1900 on normal weekday): 4 Occasions at KS6 and 5 Occasions at CGa, RWM and KY3*
- *Evening-time Noise Monitoring (1900-2300): 3 Occasions at KS6, CGa, RWM and KY3*
- *Night-time Noise Monitoring (2300-0700 of next day): 2 Occasions at KS6, CGa, RWM and KY3*
- *Holiday-time Noise Monitoring (0700-1900 on Holiday): 3 Occasions at KS6, CGa, RWM and KY3*
- *Marine Water Quality Monitoring: 13 Occasions at 9 monitoring stations and 4 control stations*
- *Weekly-site inspection: 5 Occasions*

Noise Monitoring

No exceedances of Action Level of noise monitoring were recorded in this reporting month since no complaint on noise issue was received.

Twenty-one exceedances in Limit Level were recorded according to the results from night-time noise monitoring on 20 and 27 November 2010 at CGa, RWM and KY3, 21 November 2010 at KS6. However, all of the exceedances were considered to be invalid (not project related) and no further actions were required. Interim notifications of exceedance (NOEs) for all exceedances were issued to EPD, ER, IEC and the Contractor by ET. The details of NOEs present in Appendix K.

Water Quality Monitoring

No exceedances of Action and Limit levels were recorded for water quality monitoring in the reporting month.

Site Inspection

Environmental site inspections conducted in this reporting month are presented as follows:

<u>Concerned Parties</u>	<u>Dates of Audit / Inspection</u>
<i>ET Weekly site inspection</i>	<i>02, 10, 17, 24 and 29 November 2010</i>
<i>Monthly Joint site inspection</i>	<i>24 November 2010</i>

In general, performance on environmental mitigation measures implemented was found to be satisfactory in this reporting month. The major findings observed during site inspections are presented in the Section 6.0.

Environmental Complaints, Notification of summons and successful prosecutions

No complaints, notification of summons and prosecutions with respect to environmental issues were received in this reporting month.

Change in Environmental Aspect in this Reporting Month

No change on environmental aspect was reported in this reporting month.



Future Key Issues

Based on the forecast of engineering works in the coming month, key issues to be considered are as follows:

- *Noise and dust impact due to construction works;*
- *Use and maintain silt curtain and silt screen properly;*
- *Clean up the fill material along the barge frequently;*
- *Implement all necessary preventive measures to avoid oil leakage. In the event an oil leakage happens, the Contractor should properly remove the leaked oil and handle the contaminated soil and all materials using for this cleaning works as chemical waste; and*
- *Maintain good site practice to minimize environmental impacts at the site.*



1.0 INTRODUCTION

Wo Hing – Penta-Ocean Joint Venture (WHPOJV) appointed Environmental Team of ETS-Testconsult Limited (ETL) to undertake the Environmental Impact Monitoring for “Contract No. 9/WSD/08 Laying of Western Cross Harbour Main and Associated Land Main from West Kowloon to Sai Ying Pun” (the Project) under the requirements of “Environmental Monitoring & Audit Manual – Agreement No. CE42/2005(W.S) Laying of Western Cross Harbour Main and Associated Land Main from West Kowloon to Sai Ying Pun” (the EM&A Manual).

This report documented the findings of EM&A Works conducted in November 2010.

2.0 PROJECT INFORMATION

2.1 Scope of the Project

The construction works of the Project are located in West Kowloon, across the Victoria Harbour and in Sai Ying Pun.

The construction works under this Project are briefly described, without limitation, as follow:

- Laying of about 1.5km of 1200mm diameter steel fresh water mains at West Kowloon;
- Laying of about 2.1km of 1200mm diameter steel submarine pipeline from West Kowloon to Sai Ying Pun including dredging, cathodic protection system and other associated works;
- Laying of about 0.4km of 1200mm diameter steel fresh water main at Sai Ying Pun;
- Laying of about 0.5km of 800mm diameter steel salt water main at West Kowloon;
- Construction of motorized butterfly valve (MBV) and the associated facilities in the vicinity of Sun Yat Sen Memorial Park at Sai Ying Pun;
- Construction of all chambers associated with pipeworks;
- Making service connections;
- Ancillary works including but not limited to reinstatement of roads, landscaping works.

Areas of the Project present in Appendix H. Locations of environmental monitoring stations and sensitive receivers are shown in Figures 1, 2, 3, 1.2a, 1.2b and 1.2c

2.2 Work Programme

Details of work programme are shown in Appendix E.

2.3 Project Organization and Management Structure

The organization chart and lines of communication with respect to the on-site environmental management and monitoring program are shown in Appendix A.

2.4 Contact Details of Key Personnel

The key personnel contact names and telephone numbers are shown in Table 2.1.

Table 2.1 Contact Details of Key Personnel

<i>Project Role</i>	<i>Organization</i>	<i>Name of Key Staff</i>	<i>Tel. No.</i>	<i>Fax No.</i>
<i>Engineer's Representative</i>	<i>Mott MacDonald</i>	<i>Mr. Kelvin HO</i>	<i>2377 2823</i>	<i>2377 2900</i>
<i>IEC</i>	<i>Environ</i>	<i>Mr David Yeung</i>	<i>3743 0788</i>	<i>3548 6988</i>
<i>Contractor's Agent</i>	<i>WHPOJV</i>	<i>Mr. Danny HO</i>	<i>2695 8318</i>	<i>2957 8213</i>
<i>ET Leader</i>	<i>ET (ETL)</i>	<i>Mr C. L. Lau</i>	<i>2946 7791</i>	<i>2695 3944</i>

3.0 WORK PROGRESS IN THIS REPORTING MONTH

As informed by the Contractor, the activities in the reporting month include:

- *Dredging of Type 1 marine sediment (between CH0 and CH1560 at Portion I);*
- *Drilling of pipe piles (Portion J);*
- *Preparation of construction joint of the coated and lined pipe (Portion H1 & H2); and*
- *Outfitting of the launching barge (Portion H1 & H2).*

Appendix J shows the details of works daily dredging of this reporting month.



4.0 IMPACT NOISE MONITORING

4.1 Monitoring Requirements

As the requirement in the EM&A Manual, impact noise monitoring was conducted for a weekly basis at designated monitoring locations.

4.2 Monitoring Equipment

Integrating Sound Level Meters used for impact noise monitoring were Type 1 sound level meters capable of giving a continuous readout of the noise level reading including equivalent continuous sound pressure level (L_{eq}) and percentile sound pressure level (L_x). They complied with International Electro technical Commission Publications 651:1979 (Type1) and speed in m/s was used to monitor the wind speed. Table 4.1 summarized the noise monitoring equipment model used during the impact monitoring. Copies of calibration certificates and Calibration Summary for noise meters and calibrators used are attached in Appendix B1.

Table 4.1 Noise Monitoring Equipment

Equipment	Model	Equipment No.	Serial No.	Calibration Date.	Expired Date
Sound Level Meter	Rion NL-31 Sound Level Meter	ET/EN/003/13	00593620	14/09/10	13/09/11
		ET/EN/003/10	00531142	09/06/10	08/06/11
Sound Level Calibrator	Castle GA607	ET/EN/002/07	038641	22/04/10	21/04/11
Anemometer	AZ Instrument AZ 8908	EN/001/03	9101259	11/11/09	10/11/10
		EN/001/04	9101231	10/11/10	09/11/11

4.3 Monitoring Parameters, Duration and Frequency

Impact noise monitoring for the A-weighted levels L_{eq} , L_{10} and L_{90} were recorded once per week. Data obtained from impact noise monitoring was processed and presented as below:

- Daytime: three sets of 30-minute noise level monitored between 0700-1900 hrs on normal weekdays;
 - Evening-time*: three sets of 5-minute noise level monitored between 1900-2300 hrs ;
 - Night-time*: three sets of 5-minute noise level monitored between 2300-0700 hrs of next day; and
 - Holiday*: three sets of 5-minute noise level monitored between 0700-1900 hrs on holiday.
- (*): Noise monitoring to be conducted only when there is construction work.

Duration, frequencies and parameters of noise measurement are presented in Table 4.2.

Table 4.2 Duration, Frequencies and Parameters of Noise Monitoring

Time period	Duration/min	No. of Set(s)	Parameters
Day-time: 0700-1900 hrs on normal weekday	30	1	L_{eq} , L_{10} , L_{90}
Evening-time: 1900-2300 hrs	5	3	L_{eq} , L_{10} , L_{90}
Night-time: 2300-0700 hrs of next day	5	3	L_{eq} , L_{10} , L_{90}
Holiday-time: 0700-1900 hrs on holiday	5	3	L_{eq} , L_{10} , L_{90}

4.4 Monitoring Locations

In accordance with the EM&A Manual, the proposed noise monitoring station at the Harbourside (KS4) was cancelled since the owner of the Harbourside and nearby NSRs rejected to perform baseline and impact noise monitoring at their property. As a result, there was one noise monitoring location KS6 (The Cullinan) selected at West Kowloon to conduct impact environmental monitoring.



At Sai Yung Pun, the location at the noise station CG (Connaught Garden) was unavailable for impact noise measurement because the building repairing and maintenance works was carrying out in the Connaught Garden and will be finished in May 2011. Hence, noise monitoring at noise station CG was moved to another noise station CGa (pavement in front of Connaught Garden) temporarily until the completion of repairing and maintenance works at Connaught Garden) since CGa locates close to the major site activities which are likely to have noise impacts and low disturbance to the occupants was observed during the noise monitoring. As a result, there were three noise monitoring locations, CGa (Pavement in front of Connaught Garden), RWM (Roof at Richwealth Mansion) and KY3 (Roof at Kwan Yik Building Phase 3) selected to conduct impact environmental monitoring.

Beside, the locations at the noise stations, RWM (Roof at Richwealth Mansion) and KY3 (Roof at Kwan Yik Building Phase 3), were unavailable for impact evening-time and night-time noise measurement because the building owners reject ET to carry out noise monitoring during such two periods due to security. Hence, evening-time and night-time noise monitoring at noise stations, RWM and KY3 were moved to pavement in front of Richwealth Mansion and Kwan Yik Building Phase 3. The details of noise monitoring stations are summarized in Table 4.3.

Table 4.3 Noise Monitoring Stations

<i>Daytime and Holiday-time Noise monitoring station</i>	<i>Description of location</i>	<i>Type of Measurement</i>
KS6	Podium at the Culliman	Façade
CGa	Pavement in front of Connaught Garden	Façade
RWM	Roof at Richwealth Mansion	Free Field
KY3	Roof at Kwan Yik Building Phase 3	Free Field
<i>Evening-time and Night-time Noise monitoring station</i>	<i>Description of location</i>	<i>Type of Measurement</i>
KS6	Podium at the Culliman	Façade
CGa	Pavement in front of Connaught Garden	Façade
RWM	Pavement at Richwealth Mansion	Façade
KY3	Pavement at Kwan Yik Building Phase 3	Façade

4.5 Monitoring Methodology

Instrumentation

Integrating Sound Level Meters were employed for noise monitoring.

Operation/Analysis Procedures

- Sound Level Meter was set on a tripod at a height of 1.2m above the ground;
- For free field measurement, the meter was positioned away from any nearby reflective surfaces.
- The battery condition was checked to ensure the correct functioning of the meter;
- Parameters such as frequency weighting, the time weighting and the measurement time were set as follows:
 - Frequency weighting : A
 - Time weighting : Fast
 - Time measurement : 30 mins
- Prior to and after each noise measurement, the meter was calibrated using a Calibrator for 94 dB at 1000HZ. If the difference in the calibration level before and after measurement was more than 1.0 dB(A), the measurement would be considered invalid and repeat measurement would be required after re-calibration or repair of the equipment;
- During the monitoring period, the L_{eq} , L_{10} and L_{90} were recorded. In addition, site conditions and noise sources were recorded on a standard record sheet;
- 3dB(A) correction had been added to the results if noise measurements were free-field;
- Noise measurement may be paused during periods of high intrusive noise (e.g. dog barking directly towards the receiver of noise level meter). If noise measurement was paused during high intrusive noise, the noise level meter would be resumed and continued the noise measurement and the observations would also be recorded. Any pause intervals were not included in the measurement time; and



- Noise monitoring would be cancelled in the presence of fog, rain, storm, wind with a steady speed exceeding 5m/s, or wind gusts exceeding 10m/s.

Maintenance and Calibration

- The microphone head of the sound level meter and calibrator are cleaned with soft cloth at quarterly intervals; and
- The meters are sent to supplier or HOKLAS laboratory to check and calibrated at yearly intervals.

4.6 Actions and Limit Levels

The Action and Limit Levels (AL Levels) were established in accordance to the Table 4.2 of the EM&A Manual. Table 4.4 presents the AL levels for noise monitoring.

Table 4.4 Action and Limit Levels for Noise Monitoring

Time Period	Action	Limit
0700 –1900 hrs on normal weekday (Day-time)	When one documented complaint is received	75 dB(A) *
1900-2300 hrs (Evening-time)		70 dB(A)
0700-1900 hrs on Holiday (Holiday-time)		70 dB(A)
Restricted hours (2300-0700 hrs of next day) (Night-time)		55 dB(A)

* reduce to 70dB(A) for school and 65dB(A) during school examination periods

4.7 Event-Action Plans

Should the results of the monitoring parameters at any designated monitoring stations indicate that the noise level criteria are exceeded, the actions in accordance with the Event and Action Plan that summarized in Appendix D should be carried out.

4.8 Results

Totally 4 occasions at KS6 and 5 occasions at CGa, RWM and KY3 of day-time noise monitoring, 3 occasions of evening-time noise monitoring, 2 occasions of night-time noise monitoring and 3 occasions of holiday-time noise monitoring at all four noise monitoring stations (KS6, CGa, RWM and KY3) were carried out in this reporting month.

No exceedances of Action Level of noise monitoring were recorded in this reporting month since no complaint on noise issue was received.

Twenty-one exceedances in Limit Level were recorded according to the results from night-time noise monitoring on 20 and 27 November 2010 at CGa, RWM and KY3, 21 November 2010 at KS6. However, all of the exceedances were considered to be invalid (not project related) and no further actions were required. Interim notifications of exceedance (NOEs) for all exceedances were issued to EPD, ER, IEC and the Contractor by ET. The details of NOEs present in Appendix K.

Table 4.5 summaries the noise daytime monitoring results in the reporting period.



Table 4.5 Summary of Noise Daytime Monitoring Results

Monitoring Parameter	Date	KS6		
		Time	Result	Exceed*
Daytime	05/11/10	15:30	61.2	X
	10/11/10	17:40	62.7	X
	19/11/10	15:40	61.7	X
	26/11/10	13:55	65.3	X
Evening-time	06/11/10	20:25	60.5	X
	06/11/10	20:30	60.7	X
	06/11/10	20:35	60.4	X
	20/11/10	20:55	60.5	X
	20/11/10	21:00	59.3	X
	20/11/10	21:05	59.7	X
	27/11/10	20:45	59.6	X
	27/11/10	20:50	60.8	X
	27/11/10	20:55	60.2	X
Night-time	21/11/10	00:10	58.7	L
	21/11/10	00:15	57.9	L
	21/11/10	00:20	57.7	L
	28/11/10	00:50	55.0	X
	28/11/10	00:55	54.9	X
	28/11/10	01:00	54.7	X
Holiday-time	07/11/10	13:05	59.7	X
	07/11/10	13:10	60.1	X
	07/11/10	13:15	60.5	X
	21/11/10	09:20	61.6	X
	21/11/10	09:25	61.9	X
	21/11/10	09:30	63.3	X
	28/11/10	14:50	61.0	X
	28/11/10	14:55	60.3	X
28/11/10	15:00	61.3	X	
Monitoring Parameter	Date	CGa		
		Time	Result	Exceed*
Daytime	05/11/10	11:05	71.7	X
	08/11/10	13:30	70.1	X
	15/11/10	10:00	72.6	X
	22/11/10	09:15	71.2	X
	29/11/10	10:05	70.8	X
Evening-time	06/11/10	22:00	62.9	X
	06/11/10	22:05	62.9	X
	06/11/10	22:10	63.3	X
	20/11/10	21:50	66.7	X
	20/11/10	21:55	66.9	X
	20/11/10	22:00	67.5	X
	27/11/10	21:20	68.5	X
	27/11/10	21:25	68.8	X
27/11/10	21:30	68.3	X	
Night-time	20/11/10	23:00	61.4	L
	20/11/10	23:05	60.9	L
	20/11/10	23:10	61.7	L
	27/11/10	23:00	62.1	L
	27/11/10	23:05	61.9	L
	27/11/10	23:10	61.7	L
Holiday-time	07/11/10	11:30	69.7	X
	07/11/10	11:35	69.9	X
	07/11/10	11:40	69.4	X
	21/11/10	10:20	68.1	X
	21/11/10	10:25	67.7	X
	21/11/10	10:30	67.9	X
	28/11/10	12:45	70.0	X
	28/11/10	12:50	69.8	X
28/11/10	12:55	70.0	X	



Contract No. 9/WSD/08
Laying of Western Cross Harbour Main and Associated Land Mains
From West Kowloon to Sai Ying Pun

ENA01144
Monthly EM&A Report No.7

Monitoring Parameter	Date	RWM		
		Time	Result	Exceed*
Daytime	05/11/10	11:40	63.5	X
	08/11/10	14:05	62.3	X
	15/11/10	10:35	64.1	X
	22/11/10	09:50	60.8	X
	29/11/10	10:40	62.1	X
Evening-time	06/11/10	22:17	62.9	X
	06/11/10	22:22	63.1	X
	06/11/10	22:27	63.3	X
	20/11/10	22:10	68.1	X
	20/11/10	22:15	68.4	X
	20/11/10	22:20	67.9	X
	27/11/10	21:40	68.3	X
	27/11/10	21:45	67.5	X
Night-time	27/11/10	21:50	67.8	X
	20/11/10	23:20	59.9	L
	20/11/10	23:25	60.3	L
	20/11/10	23:30	60.9	L
	27/11/10	23:15	61.8	L
	27/11/10	23:20	61.4	L
Holiday-time	27/11/10	23:25	60.6	L
	07/11/10	11:50	62.5	X
	07/11/10	11:55	62.2	X
	07/11/10	12:00	62.6	X
	21/11/10	10:40	62.1	X
	21/11/10	10:45	61.7	X
	21/11/10	10:50	61.9	X
	28/11/10	13:10	64.7	X
28/11/10	13:15	65.2	X	
28/11/10	13:20	65.0	X	
Monitoring Parameter	Date	KY3		
		Time	Result	Exceed*
Daytime	05/11/10	13:00	64.0	X
	08/11/10	14:40	61.9	X
	15/11/10	11:15	62.4	X
	22/11/10	10:25	61.1	X
	29/11/10	11:15	61.8	X
Evening-time	06/11/10	22:35	62.1	X
	06/11/10	22:40	62.2	X
	06/11/10	22:45	62.5	X
	20/11/10	22:30	67.3	X
	20/11/10	22:35	67.9	X
	20/11/10	22:40	68.2	X
	27/11/10	22:00	65.3	X
	27/11/10	22:05	65.2	X
Night-time	27/11/10	22:10	64.5	X
	20/11/10	23:40	60.6	L
	20/11/10	23:45	60.3	L
	20/11/10	23:50	61.0	L
	27/11/10	23:35	59.8	L
	27/11/10	23:40	60.2	L
27/11/10	23:45	59.9	L	



Monitoring Parameter	Date	KY3		
		Time	Result	Exceed*
Holiday-time	07/11/10	12:15	60.9	X
	07/11/10	12:20	60.7	X
	07/11/10	12:25	60.6	X
	21/11/10	11:00	61.1	X
	21/11/10	11:05	61.4	X
	21/11/10	11:10	62.0	X
	28/11/10	13:35	63.5	X
	28/11/10	13:40	63.8	X
	28/11/10	13:45	63.1	X

Remark (*): L = Limit Level exceedance, A = Action Level exceedance and X = not an Exceedance
(†): Since daytime and holiday-time noise measurements at monitoring stations RWM and KY3 were free-field, 3dB(A) correction had been added to the results.

The summary of noise exceedances is shown in Table 4.6.

Table 4.6 Summary of Impact Noise Exceedances in this reporting month

Exceedance Level	Daytime	Evening-time	Night-time	Holiday-time
Action	0	0	0	0
Cumulative	0	0	0	0
Limit	0	0	21	0
Cumulative	0	0	119	0

5.0 WATER QUALITY MONITORING

5.1 Monitoring Requirements

In accordance with the EM&A Manual, impact water quality monitoring was conducted three days per week during the course of the marine construction works.

5.2 Monitoring Locations

In accordance with the EM&A Manual, the proposed water quality monitoring station R8 – Macau Ferry Terminal was cancelled since it is located inside the restricted area. Another monitoring location R8a was proposed to replace R8 for impact water quality monitoring. As a result, totally four control stations and nine impact stations were selected to conduct impact water quality monitoring for the Project. Table 5.1 shows the water quality monitoring stations of the Project.

Table 5.1 Water Quality Monitoring Stations

ID	Station	Easting	Northing
R5	Green Island	830 175.979	816 179.217
R6	Prince Philip Dental Hospital	833 437.625	816 747.640
R7	Tsan Yuk Hospital	833 461.092	816 744.773
R8a	Macau Ferry Terminal	833 573	816 885
R15 *	Kowloon South Pumping Station	833 982.630	818 282.101
R16	Kowloon Government Offices Building	834 335.800	817 769.145
R17	Canton Road Government Offices Building	834 364.658	817 802.847
R28	WSD Kennedy Town Salt Water Pumping Station	830 707	815 983
R29	WSD Sheung Wan Salt Water Pumping Station	833 414	816 745
C1	Control Station	830 797.729	819 163.377
C2	Control Station	836 350.628	817 135.218
C3	Control Station	829 495.126	817 228.312
C4	Control Station	836 638.773	816 686.030

Remark (*): Station R15 = WSD Seawater Intake

Control stations, C2 and C4, should be the upstream control station for all impact monitoring stations at mid-flood and Control Stations, C1 and C3, should be the upstream control station for all monitoring stations at mid-ebb.



5.3 Monitoring Parameters

Monitoring parameters listed in Table 5.2 shall be monitored by the ET to ensure that any deteriorating water quality could be readily detected and timely action be taken to rectify the situation. Table 5.3 shows the other relevant water quality data recorded during the impact water quality monitoring.

Table 5.2 Water Quality Monitoring Parameters

<i>In-situ measurement</i>	<i>Laboratory analysis</i>
<i>Dissolved Oxygen (DO) (mg/L)</i>	<i>Suspended solids (SS) (mg/L)</i>
<i>Turbidity (NTU)</i>	

Table 5.3 Other relevant water quality parameters

<i>Water Quality Parameters</i>	
<i>Tidal stages</i>	<i>Water depth (m)</i>
<i>Dissolved Oxygen saturation (%)</i>	<i>Salinity (ppt)</i>
<i>Temperature (°C)</i>	<i>Weather Condition</i>

5.4 Monitoring Frequency

The frequency of impact water quality monitoring of water quality is summarized in Table 5.4.

Table 5.4 Monitoring Frequency of Impact Water Quality Monitoring

<i>Frequency</i>	<i>Monitoring Depth</i>
<i>3 days/week, 2 tides/day</i>	<i>For water depth greater than 6m: Three water depths (1m below Surface, mid-depth and 1m above bottom). For water depth less than 6m but greater than 3m: Two water depths: (1m below Surface and 1m above bottom). For water depth less than 3m: One water depth (Mid-depth)</i>

5.5 Monitoring Methodology and Equipment Used

Refer to the requirement in Appendix D2 "General Technical Requirements of Environmental Monitoring" (TM) in the Environmental Monitoring and Audit Guidelines for Development Projects in Hong Kong published by EPD, water samples for all monitoring parameter were collected, stored, preserved and analysed according to the Standard Method APHA 19ed.. In-situ measurements at monitoring locations including DO, turbidity, salinity and water depth were collected by equipment with the characteristic and functions listed as below:

Location of the monitoring stations

A hand-held digital Global Positioning System (GPS) was used to identify the designated monitoring stations prior to water sampling.

Water Depth measurement

A portable, battery-operated echo sounder was used for the determination of water depth at each designated monitoring station.

In-situ Water Quality Monitoring Equipment

All in-situ monitoring instruments shall be checked, calibrated and certified by a laboratory accredited under HOKLAS or any other international accreditation scheme before use, and subsequently re-calibrated at 3 monthly intervals or sometimes longer throughout all stages of the water quality monitoring. Responses of sensors and electrodes should be checked with certified standard solutions before each use. Wet bulb calibration for a DO meter shall be carried out before measurement at each monitoring location.



Dissolved Oxygen, salinity and temperature measuring equipment

A portable, weatherproof dissolved oxygen & salinity measuring instrument, which complete with cable, sensor and DC power source (e.g. YSI 85 or equivalent) was used for measuring:

- a dissolved oxygen level in the range of 0-20 mg/L and 0-200 % saturation;
- a salinity in range 0-40 ppt; and
- a temperature of 0-45 degree Celsius

A membrane electrode with automatic temperature compensation complete with a cable was installed.

Turbidity Measurement Instrument

A portable, weatherproof turbidity-measuring instrument with DC power source was used. It has a photoelectric sensor capable of measuring turbidity between 0-1000 NTU and be complete with a cable (e.g. HACH model 2100P or equivalent)

Water Sampling and Sample Analysis

In-situ monitoring was carried out at three depths: 1 meter below water surface, at mid-depth and 1 meter above the seabed. If the water depth is less than 6 m, the mid-depth station shall be omitted and if the water depth is below 3 m, only the mid depth station shall be monitored.

A water sampler comprising a transparent PVC cylinder, with a capacity of not less than 2 litres, was lowered into the water body at the predetermined depth. The opening ends of the sampler were then closed accordingly and water samples were collected.

The sample container, made by high-density polythene, was rinsed with a portion of the water sample. The water sample was then transferred to the container, labelled with a unique sample ID and sealed with a screw cap. The water samples were stored in a cool box maintained at 4°C. The water samples were then delivered to Environmental Laboratory of ETS-Testconsult Ltd (HOKLAS Registration No. 022) on the same day for analysis.

5.6 Details of site Equipment used for In-situ Measurement

All in-situ monitoring instruments were checked, calibrated and certified by a laboratory accredited under HOKLAS or any other international accreditation scheme before use, and subsequently re-calibrated at 3 monthly intervals or sometimes longer throughout all stages of the water quality monitoring. Wet bulb calibration for a DO meter was carried out before measurement at each monitoring location.

Table 5.5 shows the equipment used for in-situ monitoring of water quality. The calibration certificates are attached in Appendix C1.

Table 5.5 Details of Monitoring Equipment (In-site measurement)

<i>Parameter</i>	<i>Model</i>	<i>Date of Calibration</i>	<i>Due Date</i>	<i>Equipment No.</i>	<i>Serial No.</i>
<i>Coordinate of Monitoring stations</i>	<i>Magellan GPS Navigator</i>	----	----	<i>ET/EW/005/03</i>	<i>211836B</i>
<i>Dissolved Oxygen (Saturation), Temperature and Salinity</i>	<i>YSI Dissolved Oxygen, Salinity & Temperature Meter, YSI 85</i>	<i>30/09/10</i>	<i>29/12/10</i>	<i>ET/EW/008/003*</i>	<i>08L100716</i>
<i>Turbidity</i>	<i>HACH Model 2100P Turbid Meter</i>	<i>15/10/10</i>	<i>14/01/11</i>	<i>ET/0505/007*</i>	<i>08060C030281</i>
<i>Water Depth</i>	<i>Speedtech Instrument SM-5A</i>	----	----	<i>ET/EW/002/04</i>	<i>56657</i>

Remark:(*) indicates the instrument should be calibrated on use.



5.7 Quality Assurance (QA) / Quality Control (QC) results and Determination Limits

At each measurement/sampling depth, two consecutive measurements of dissolved oxygen (DO), dissolved oxygen saturation (DOS), turbidity and salinity were taken. The probes were retrieved out of the water after the first measurement and then re-deployed for the second measurement. If the difference between the first and second measurement is greater than 25% the reading was discarded and the measurements were repeated.

At the laboratory analysis of water sample, test method of test parameter as required by the EM&A Manual, with the QA/QC results in accordance with the requirement of HOKLAS or international accredited scheme is shown in Table 5.6. For the QA/QC procedures, one QC sample, one duplicate sample and one sample spike of every batch of 20 samples were analysis. The QA/QC results are summarized in Appendix C4

Table 5.6 Summary of test method

Laboratory Analysis	Testing Procedure	Method Detection Limit
Total suspended solids	In house method based on APHA 19 th ed 2540D	1.0 mg/L

5.8 Action and Limit Level

The water quality criteria, namely Action and Limit (AL) levels are presented in the table below.

Table 5.7 Water Quality Action and Limit Levels

Parameter	Action Level	Limit Level
DO (mg/L) (Surface, Middle & Bottom)	<u>Surface, Middle & Bottom</u> WSD Seawater Intakes 2 mg/L (For R15) Other Impact Monitoring Stations 5.65 mg/L (For R5, R6, R7, R8a, R16, R17, R28 and R29)	<u>Surface & Middle</u> WSD Seawater Intakes 2 mg/L (For R15) Other Impact Monitoring Stations 5.51 mg/L (For R5, R6, R7, R8a, R16, R17, R28 and R29) <u>Bottom</u> 5.11 mg/L (For R15, R5, R6, R7, R8a, R16, R17, R28 and R29)
SS (mg/L) (Depth-averaged)	WSD Seawater Intakes 10 mg/L (For R15) Other Impact Monitoring Stations 12.7 mg/L (For R5, R6, R7, R8a, R16, R17, R28 and R29)	WSD Seawater Intakes 10 mg/L (For R15) Other Impact Monitoring Stations 12.7 mg/L (For R5, R6, R7, R8a, R16, R17, R28 and R29)
Turbidity (NTU) (Depth-averaged)	WSD Seawater Intakes 10 NTU Other Impact Monitoring Stations 6.48 NTU (For R5, R6, R7, R8a, R16, R17, R28 and R29)	WSD Seawater Intakes 10 NTU Other Impact Monitoring Stations 6.82 NTU (For R5, R6, R7, R8a, R16, R17, R28 and R29)

- Notes: 1. "depth-averaged" is calculated by taking the arithmetic means of reading of all three depths.
2. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
3. For turbidity and SS, non-compliance of water quality limits occurs when monitoring result is higher than the limits.
4. All the figures given in the table are used for reference only and the EPD may amend the figures whenever it is considered as necessary.

5.9 Event and Action Plan

Please refer to the Appendix D for details.

5.10 Monitoring Duration and Period In this reporting month

Daily water quality monitoring duration are detailed in Appendix C2. Below is the time schedule for the water quality monitoring conducted in this reporting month:



Table 5.8 Schedule for Impact Water Quality Monitoring

November 2010						
Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
	1	2	3	4	5	6
7	8	9	10	11	12	13
14	15	16	17	18	19	20
21	22	23	24	25	26	27
28	29	30				

Remarks: (▼) = Marine water quality monitoring carried out by ET.

5.11 Results

The impact water quality measurement results are detailed in Appendix C2. Appendix C3 presents the water quality monitoring data and graphical presentations of monitoring results respectively.

The summary of marine water quality exceedances is shown in Table 5.9.

Table 5.9 Summary of Impact Marine Water Quality Exceedances in this reporting month

Exceedance Level	DO		Turbidity		SS		Cumulative	
	Flood	Ebb	Flood	Ebb	Flood	Ebb	Flood	Ebb
Action	0	0	0	0	0	0	0	0
Limit	0	0	0	0	0	0	0	0

According to the summary of marine water monitoring results, no exceedances of Action and Limit levels were recorded for this reporting month.

6.0 ENVIRONMENTAL SITE INSPECTION

During this reporting month, weekly site inspections were undertaken on 02, 10, 17, 24, 29 November 2010 by ET. Monthly joint site inspection at 24 November 2010 was carried out by Engineer's Representative, IEC, WHPOJV and ET. A summary of implementation status of mitigation measures on site inspections is presented in Appendix G.

6.1 Summary of the ET weekly site inspection findings

According to the summary of the ET weekly site inspections carried out in November 2010, it indicated that site practices of the Contractor were generally undertaken in an environmentally acceptable manner and the overall site environmental performance was satisfactory. Summary of the site inspection findings in this reporting month is shown in Table 6.1.

Table 6.1 Summary of Site Inspection Findings

Item	Aspect	Finding	Action(s) taken by the Contractor	ET Verification	Status of the finding
1	Chemical	A 200L oil drum was note don the ground at Portion J without drip tray during the weekly site inspection on 02/11/2010. (Photo 101102_001)	<ul style="list-style-type: none"> A drip tray was provided for the oil drum. (Photo Ref. 01 of the Contractor Follow-up Action – 03/11/2010) 	During the subsequently weekly site inspection on 10/11/2010, a drip tray was noted provided for the oil drum at Portion J (Photo 101110_001)	Closed



6.2 Recommendations on site inspection findings in Site Inspections of this month

Based on the site inspection findings, the recommendations are as below:

- Minimize noise and dust impact due to construction works;
- Use and maintain silt curtain and silt screen properly;
- Adequate environmental control measures shall be provided to prevent / avoid dropping of dredged materials into the sea during the transfer;
- Implement all necessary preventive measures to avoid oil leakage. In the event an oil leakage happens, the Contractor should properly remove the leaked oil and handle the contaminated soil and all materials using for this cleaning works as chemical waste; and
- Checking and maintaining all the site machines to prevent black smoke emission;
- Providing briefing to the concerned site staff on remedial actions, such as handling method of chemicals and chemical waste;
- Remove all stagnant water;
- Apply proper treatment facilities to wastewater before discharge; and
- Maintain good waste management at the site.

7.0 STATUS OF ENVIRONMENTAL PERMITS

Permits/licenses valid in this reporting month are summarized in Table 7.1.

Table 7.1 Summary of Environmental Licensing and Permit valid in this reporting month

Description	Permit No.	Valid Period		Remarks
		From	To	
Environmental Permit	EP-273/2007	31/07/07	End of Project	Whole Project
Water Discharge Licence (West Kowloon)	WT00005347-2009	07/01/10	31/01/15	Effluent and all other wastewater arising from the construction site through Screen & Sedimentation Tank
Water Discharge Licence (Sai Yung Pun)	WT00005800-2010	14/01/10	31/01/15	Effluent arising from the construction site through Sedimentation Tank
Chemical Waste Producer	5213-217-W3086-01	13/10/09	End of Project	Spent oil, surplus flammable liquid, surplus paint, soil, rags & containers contaminated with lubricating oil, diesel, flammable liquid & paint, & used batteries
Construction Noise Permit (West Kowloon)	GW-RE0502-10	21/10/10	20/04/11	One Dredger, grab (CNP 063) Two Guard boat One Tug boat (CNP 221) One Generator, standard (CNP 101)
Construction Noise Permit (Sai Ying Pun)	GW-RS0756-10	12/09/10	11/03/11	One dredger, grab (CNP 063) Two Guard boat One Tug boat (CNP 221) Hopper barge
Dumping Licence	EP/MD/11-069	01/10/10	31/03/11	Bulk quantity of material approved for dumping at the South Cheung Chau Spoil Disposal Area denoted "LWCHMALM" within permit validity period: 130000 cu.m. (for Type 1 – Open Sea Disposal)
Notification under APCO	Application had been submitted to EPD on 25/09/09 and approved from 29/09/09.			

8.0 WASTE MANAGEMENT

8.1 Monthly Waste Summary

The quantities of waste generated from the Project in this month are summarized in Table 8.1.



Table 8.1 Summary of Quantities of Waste for Disposal in this reporting month

Type of Waste		Quantity	Disposal Location	Cumulative Quantity
Inert C&D Materials	Total Quantity Generated (in m ³)	1078.66		6576.95
	Broken Concrete (in m ³)	0	---	0
	Reused in the Contract (in m ³)	0	---	0
	Reused in other Projects (in m ³)	0	---	0
	Disposal as Public Fill (in m ³)	1078.66	SENT Landfill	6576.95
C&D Waste	Metals (in kg)	0	---	0
	Paper/Cardboard Packaging (in kg)	0	Collected by recycling company	65
	Plastics (in kg)	0	---	0
	Chemical Waste (in kg)	0	---	0
	Other, e.g. General Refuse (in m ³)	2.24	SENT Landfill	51.74
Dredged Materials*	Type 1 (in m ³)	24100	East Ninepin Mud Disposal Ground	140500
	Type 2 (in m ³)	0	The East Sha Chau	104990

Remark (*): Daily Dredging Summary for this reporting month presents in Appendix J

8.2 Advice on the Solid and Liquid Waste Management Status

The Contractor should provide sufficient preventive measures during equipment maintenance works so as to avoid oil leakage on the ground. In the event of any oil leakage, the Contractor should clean up the polluted soil and handle all the materials used for this cleaning works as chemical waste.

Besides, pre-cast drip trays were provided for oil drums at several areas, such as barge and chemical storage area. The Contractor should collect and dispose of any stagnant water accumulated in the drip trays and handle them as chemical waste.

The Contractor should use suitable containers with proper labels to store chemical wastes in accordance with Code of Practice on the Packaging, Labeling and Storage of Chemical Waste. The Contractor should also advise their workers of the proper procedures in handling the chemical waste.

All the trip tickets for chemical waste disposal were properly kept in the site office. No chemical waste disposal was undertaken in the reporting month.

The Contractor was reminded to increase the frequency of inspection and cleaning of the site drainage system, including desilting facilities. Moreover, the Contractor should apply approved pesticides in the stagnant water.

9.0 ENVIRONMENTAL NON-CONFORMANCE

9.1 Summary of Noise and Water Quality

No exceedances of Action and Limit Level of marine water quality monitoring results were recorded during the reporting month.

No exceedances of Action Level of noise monitoring were recorded in this reporting month since no complaint on noise issue was received.

Twenty-one exceedances in Limit Level were recorded according to the results from night-time noise monitoring on 20 and 27 November 2010 at CGa, RWM and KY3, 21 November 2010 at KS6. However, all of the exceedances were considered to be invalid (not project related) and no further actions were required.

9.2 Summary of Environmental Complaints

There was no complaint received in this reporting month.



9.3 Summary of Notification of Summons and Prosecution

There was no notification of summons respect to environmental issues registered in this reporting month.

10.0 IMPLEMENTATION STATUS

10.1 Implementation Status of Environmental Mitigation Measures

An updated summary of the Environmental Mitigation Implementation Schedule (EMIS) is presented in Appendix G. Most of the necessary mitigation measures were implemented properly. Any deficiencies were noted in the remarks of the schedule.

10.2 Implementation Status of Event and Action Plan

No exceedances of Action and Limit Level of water quality monitoring results were recorded during the reporting month.

Since no documented complaints on noise issue were received in this reporting month, no Action Level exceedances were recorded.

Twenty-one exceedances in Limit Level were recorded according to the results from night-time noise monitoring on 20 and 27 November 2010 at CGa, RWM and KY3, 21 November 2010 at KS6. However, all of the exceedances were considered to be invalid (not project related) and no further actions were required.

10.3 Implementation Status of Environmental Complaint, Notifications of Summons and Successful Prosecutions Handling

No complaints, notifications of summons and successful prosecutions were received in this reporting month. A summary of environmental complaints, notifications of summons and successful prosecutions was given in Table 10.1.

Table 10.1 Summary of Environmental Complaints and Prosecutions

Complaints logged		Summons served		Successful prosecution received	
November 2010	Cumulative	November 2010	Cumulative	November 2010	Cumulative
0	0	0	0	0	0

11.0 CONCLUSIONS AND RECOMMENDATIONS

Conclusions

Impact monitoring of noise and water quality were carried out at designated locations in accordance with the EM&A Manual in this reporting month.

No exceedances of Action and Limit Level of water quality monitoring results were recorded during the reporting month.

No exceedances of Action Level of noise monitoring were recorded in this reporting month since no complaint on noise issue was received.

Twenty-one exceedances in Limit Level were recorded according to the results from night-time noise monitoring on 20 and 27 November 2010 at CGa, RWM and KY3, 21 November 2010 at KS6. However, all of the exceedances were considered to be invalid (not project related) and no further actions were required.

According to the ET weekly site inspections carried out in this reporting month, the Contractor generally implemented sufficient environmental mitigation measures.

No complaints, prosecutions or notifications of summons were received in this reporting month.



Recommendations

According to the environmental site inspections performed in the reporting month, the following recommendations were provided:

Air Quality

- Ensure the frequency of water spraying on unloading areas and stockpiles to be sufficient to suppress the dust sources;
- Provide proper maintenance for the powered mechanical equipment and barges to avoid emission of dark smoke; and
- Implement the dust mitigation measures for the site activities.

Noise

- Conduct noisy activities at a farther location from the NSRs.

Water Quality

- Maintain the drainage system regularly;
- Operate and maintain the silt curtains and silt screen regularly;
- Operate the cleaning vessel regularly;
- Provide proper treatment for the wastewater discharge;
- Clean up the fill material on the barge frequently; and
- Remove the stagnant water or provide approved pesticides for the stagnant water, if any.

Chemical and Waste Management

- Remove waste materials from the site to avoid accumulation regularly;
- Handle and store chemical wastes properly;
- Remove unwanted material in the existing stockpiles and avoid further dumping of such material;
- Provide and maintain sufficient drip trays for diesel drums, chemical containers, chemical waste storage drums and diesel operated generator set;
- Maintain good housekeeping at the works area;
- Avoid soil being polluted during oil filling and equipment maintenance; hence, properly remove and store the contaminated soil, if any.

12.0 FUTURE KEY ISSUES

12.1 Work Programme for the Coming Month

As informed by the Contractor, the activities to be conducted by them in the next month included:

- *Preparation of construction joint of the coated and lined pipe (Portion H1 & H2);*
- *Outfitting of the launching barge (Portion H1 & H2);*
- *Pipe piles installation at Land and Seawall Portion (Portion H1);*
- *Pipe piles installation at Marine and Seawall Portion (Portion J);*
- *Excavation inside the cofferdam (Portion J);*
- *Installation of the strutting system for the cofferdam (Portion J);*
- *Dredging of Type 1 marine sediment between CH0 and CH1960 (Portion I);*
- *Placing rock fill material as bedding layer to the over dredged area (Portion I);*
- *Dismantle existing sloping seawall in West Kowloon for construction of cofferdam (Portion I); and*
- *Drilling of pipe pile (construction of cofferdam) in West Kowloon (Portion I).*

12.2 Key Issues for the Coming Month

Key issues to be considered in the coming month include:

- *Noise and dust impact due to construction works;*
- *Use and maintain silt curtain and silt screen properly;*
- *Adequate environmental control measures shall be provided to prevent / avoid dropping of dredged materials into the sea during the transfer;*
- *Implement all necessary preventive measures to avoid oil leakage. In the event an oil leakage happens, the Contractor should properly remove the leaked oil and handle the contaminated soil and all materials using for this cleaning works as chemical waste; and*
- *Maintain good site practice to minimize environmental impacts at the site.*



Mitigation measures to be required in the coming month:

Air Quality Impact

- To ensure implementation of the dust mitigation measures for the site activities;
- To provide proper maintenance for vehicles and machines on site; and
- To investigate any other dust sources around the air sensitive receivers

Noise

- To switch off equipment if not in use;
- To operate silent equipment;
- To identify the noise sources inside and outside of the site; and
- To re-schedule the work activities in the event of valid noise exceedance.

Water Quality Impact

- To maintain the drainage system;
- To repair, inspect and maintain the silt curtains and site screen regularly;
- To provide covers for the drip trays to avoid stagnant water due to rainfall;
- To provide proper treatment for wastewater from the area;
- To deploy a cleaning vessel to remove floating rubbish;
- To avoid dredged materials on the barge from being washed into the sea; and
- To avoid any stagnant water or provide insecticide to avoid mosquito breeding.

Chemical and Waste Management

- To remove waste from the site regularly;
- To properly store and handle chemical wastes on site;
- To implement trip ticket system for all the imported public fill and general refuse disposal;
- To provide and manage sufficiently sized drip trays for diesel drums or chemical containers;
- To maintain proper housekeeping;
- To remove the oil stains in the event of leakage and handle all materials using for this cleaning works as chemical waste; and
- To identify C&D material by packaging, labeling, storage, transportation and disposal in accordance with statutory regulations.



12.3 Monitoring Schedule for the Coming Month

The proposed EM&A program of the coming month is attached in Appendix I.




Appendix A


Organization Chart and Lines of Communication



Head Office Support Team

Site Team





Project Laying of Western Cross Harbour Main and Associated Land Mains From West Kowloon to Sai Ying Pun - Investigation

Title Project Organization and Line of Communication

Date Dec 2009

Figure 1.3a



Appendix B1

Calibration Certificates for Impact Noise Monitoring Equipment



Calibration Certificate

Certificate No. 01767

Page 1 of 2 Pages

Customer : ETS-Testconsult Limited

Address : 8/F., Block B, Veristrong Industrial Centre, 34-36 Au Pui Wan St., Fotan, Hong Kong.

Order No. : Q00732

Date of receipt : 15-Apr-10

Item Tested

Description : Acoustic Calibrator (ET/ EN/ 002/ 07)

Manufacturer : Castle

Model : GA607

Serial No. : 038641

Test Conditions

Date of Test : 22-Apr-10

Supply Voltage : --

Ambient Temperature : (23 ± 3)°C

Relative Humidity : (50 ± 25) %

Test Specifications

Calibration check.

Ref. Document/Procedure : F06, F20, Z02.

Test Results

All results were within the IEC 942 Class 1 specification.

The results are shown in the attached page(s).

Main Test equipment used:


<u>Equipment No.</u>	<u>Description</u>	<u>Cert. No.</u>	<u>Due Date</u>	<u>Traceable to</u>
S014	Spectrum Analyzer	93091	18-Jun-10	NIM-PRC & SCL-HKSAR
S024	Sound Level Calibrator	93758	16-Jul-10	NIM-PRC & SCL-HKSAR
S041	Universal Counter	94005	6-Aug-10	SCL-HKSAR
S206	Sound Level Meter	93966	5-Aug-10	SCL-HKSAR

The values given in this Calibration Certificate only relate to the values measured at the time of the test and any uncertainties quoted will not include allowance for the equipment long term drift, variations with environmental changes, vibration and shock during transportation, overloading, mis-handling, or the capability of any other laboratory to repeat the measurement. Hong Kong Calibration Ltd. shall not be liable for any loss or damage resulting from the use of the equipment.


The test equipment used for calibration are traceable to International System of Units (SI).

The test results apply to the above Unit-Under-Test only

Calibrated by :


P.F. Wong

Approved by :


Alan Chu

Date: 23-Apr-10

This Certificate is issued by:

Hong Kong Calibration Ltd.

Unit 8B, 24/F., Well Fung Industrial Centre, No. 58-76, Ta Chuen Ping Street, Kwai Chung, NT, Hong Kong.

Tel: 2425 8801 Fax: 2425 8646

The copyright of this certificate is owned by Hong Kong Calibration Ltd.. It may not be reproduced except in full.



Calibration Certificate

Certificate No. 01767

Page 2 of 2 Pages

Results :

1. Level Accuracy

UUT Setting (dB)	Measured Value (dB)	IEC 942 Class 1 Spec.
94	93.88	± 0.3 dB

Uncertainty : ± 0.2 dB

2. Frequency Accuracy

UUT Nominal Value (kHz)	Measured Value (kHz)	IEC 942 Class 1 Spec.
1	1.000	± 2 %

Uncertainty : ± 3.6 x 10⁻⁶

3. Level Stability : 0.0 dB

IEC 942 Class 1 Spec.: ± 1 dB

Uncertainty : ± 0.01 dB

4. Total Harmonic Distortion : < 2.5 %

IEC 942 Class 1 Spec. : < 3 %

Uncertainty : ± 2.3 % of rdg.

Remark : 1. UUT : Unit-Under-Test

2. The above measured values were the mean of 3 measurements.

3. The uncertainty claimed is for a confidence probability of not less than 95%.

4. Atmospheric Pressure : 1 003 hPa.

----- END -----



Calibration Certificate

Certificate No. **02909A**

Page 1 of 4 Pages

Customer : ETS-Testconsult Limited

Address : 8/F., Block B, Veristrong Industrial Centre, 34-36 Au Pui Wan St., Fotan, Hong Kong.

Order No. : Q01152

Date of receipt : 31-May-10

Item Tested

Description : Precision Integrating Sound Level Meter (ET/ EN/ 003/ 10)

Manufacturer : Rion

Model : NL-31

Serial No. : 00531142

Test Conditions

Date of Test : 9-Jun-10

Supply Voltage : --

Ambient Temperature : (23 ± 3)°C

Relative Humidity : (50 ± 25) %

Test Specifications

Calibration check.

Ref. Document/Procedure : Z01.

Test Results

All results were within the IEC 651 Type 1 & IEC 804 Type 1 specification.

The results are shown in the attached page(s).


Main Test equipment used:


<u>Equipment No.</u>	<u>Description</u>	<u>Cert. No.</u>	<u>Due Date</u>	<u>Traceable to</u>
S017	Multi-Function Generator	C101623	25-Mar-11	SCL-HKSAR
S024	Sound Level Calibrator	93758	16-Jul-10	NIM-PRC & SCL-HKSAR

The values given in this Calibration Certificate only relate to the values measured at the time of the test and any uncertainties quoted will not include allowance for the equipment long term drift, variations with environmental changes, vibration and shock during transportation, overloading, mis-handling, or the capability of any other laboratory to repeat the measurement. Hong Kong Calibration Ltd. shall not be liable for any loss or damage resulting from the use of the equipment.

The test equipment used for calibration are traceable to International System of Units (SI).

The test results apply to the above Unit-Under-Test only

Calibrated by : 
Dorothy Cheuk

Approved by : 
Alan Chu

Date: 15-Jun-10

This Certificate is issued by:
Hong Kong Calibration Ltd.

Unit 8B, 24/F., Well Fung Industrial Centre, No. 58-76, Ta Chuen Ping Street, Kwai Chung, NT, Hong Kong.
Tel: 2425 8801 Fax: 2425 8646



Calibration Certificate

Certificate No. 02909A

Page 2 of 4 Pages

Results :

1. SPL Accuracy

UUT Setting			Applied Value (dB)	UUT Reading (dB)
Level Range (dB)	Weight	Response		
20 - 100	L _A	Fast	94.03	93.7
		Slow		93.7
	L _C	Fast		93.7
		L _p		Fast
30 - 120	L _A	Fast	94.03	93.7
		Slow		93.6
	L _C	Fast		93.7
	L _p	Fast		93.7
30 - 120	L _A	Fast	113.97	113.6
		Slow		113.6
	L _C	Fast		113.6
	L _p	Fast		113.6

IEC Type 1 Spec. : ± 0.7 dB

Uncertainty : ± 0.1 dB

2. Level Stability : 0.0 dB

IEC 651 Type 1 Spec. : ± 0.3 dB

Uncertainty : ± 0.1 dB



Calibration Certificate

Certificate No. 02909A

Page 3 of 4 Pages

3. Linearity

3.1 Level Linearity

UUT Range (dB)	Applied Value (dB)	UUT Reading (dB)	Variation (dB)	IEC 651 Type 1 Spec. (Primary Indicator Range)
130	114.0	113.9	+0.2	± 0.7 dB
130	104.0	103.9	+0.2	
120	94.0	93.7 (Ref.)	--	
110	84.0	84.1	+0.4	
100	74.0	73.7	0.0	
90	64.0	63.7	0.0	
80	54.0	53.7	0.0	

Uncertainty : ± 0.1 dB

3.2 Differential level linearity

UUT Range (dB)	Applied Value (dB)	UUT Reading (dB)	Variation (dB)	IEC 651 Type 1 Spec.
120	84.0	83.5	-0.2	± 0.4 dB
	94.0	93.7 (Ref.)	--	
	95.0	94.7	0.0	± 0.2 dB
	104.0	103.8	+0.1	± 0.3 dB
	105.0	104.8	0.0	± 1.0 dB

Uncertainty : ± 0.1 dB

4. Frequency Weighting

A weighting

Frequency	Attenuation (dB)	IEC 651 Type 1 Spec.
31.5 Hz	-40.2	- 39.4 dB, ± 1.5 dB
63 Hz	-26.7	- 26.2 dB, ± 1.5 dB
125 Hz	-16.7	- 16.1 dB, ± 1 dB
250 Hz	-9.1	- 8.6 dB, ± 1 dB
500 Hz	-3.6	- 3.2 dB, ± 1 dB
1 kHz	0.0 (Ref.)	0 dB, ± 1 dB
2 kHz	+1.6	+ 1.2 dB, ± 1 dB
4 kHz	+1.6	+ 1.0 dB, ± 1 dB
8 kHz	-0.5	- 1.1 dB, + 1.5 dB ~ - 3 dB
16 kHz	-6.0	- 6.6 dB, + 3 dB ~ ∞

Uncertainty : ± 0.1 dB



Calibration Certificate

Certificate No. 02909A

Page 4 of 4 Pages

4. Time Averaging

Applied Burst duty Factor	Applied Leq Value (dB)	UUT Reading (dB)	IEC 804 Type 1 Spec.
continuous	40.0	40.0	--
1/10	40.0	39.9	± 0.5 dB
1/10 ²	40.0	40.0	
1/10 ³	40.0	40.0	± 1.0 dB
1/10 ⁴	40.0	39.9	

Uncertainty : ± 0.1 dB

Remark : 1. UUT : Unit-Under-Test

2. The uncertainty claimed is for a confidence probability of not less than 95%.

3. Atmospheric Pressure : 1 002 hPa.

4. This certificate is to supersede our former certificate no. 02909.

----- END -----



Calibration Certificate

Certificate No. **05083**

Page 1 of 3 Pages

Customer : ETS-Testconsult Limited

Address : 8/F., Block B, Veristrong Industrial Centre, 34-36 Au Pui Wan St., Fotan, Hong Kong.

Order No. : Q02020

Date of receipt : 8-Sep-10

Item Tested

Description : Precision Integrating Sound Level Meter (ET/EN/003/13)

Manufacturer : Rion

Model : NL-31

Serial No. : 00593620

Test Conditions

Date of Test : 14-Sep-10

Supply Voltage : --

Ambient Temperature : (23 ± 3)°C

Relative Humidity : (50 ± 25) %

Test Specifications

Calibration check.

Ref. Document/Procedure : Z01.

Test Results

All results were within the IEC 651 Type 1 & IEC 804 Type 1 specification.

The results are shown in the attached page(s).


Main Test equipment used:


<u>Equipment No.</u>	<u>Description</u>	<u>Cert. No.</u>	<u>Traceable to</u>
S017A	Multi-Function Generator	00804	SCL-HKSAR
S024	Sound Level Calibrator	04062	NIM-PRC & SCL-HKSAR

The values given in this Calibration Certificate only relate to the values measured at the time of the test and any uncertainties quoted will not include allowance for the equipment long term drift, variations with environmental changes, vibration and shock during transportation, overloading, mis-handling, or the capability of any other laboratory to repeat the measurement. Hong Kong Calibration Ltd. shall not be liable for any loss or damage resulting from the use of the equipment.

The test equipment used for calibration are traceable to International System of Units (SI).

The test results apply to the above Unit-Under-Test only

Calibrated by : 
P. F. Wong

Approved by : 
Dorothy Cheuk

Date: 14-Sep-10

This Certificate is issued by:
Hong Kong Calibration Ltd.
Unit 8B, 24/F., Well Fung Industrial Centre, No. 56-76, Ta Chuen Ping Street, Kwai Chung, NT, Hong Kong.
Tel: 2425 8801 Fax: 2425 8646



Calibration Certificate

Certificate No. **05083**

Page 2 of 3 Pages

Results :

1. SPL Accuracy

UUT Setting			Applied Value (dB)	UUT Reading (dB)
Level Range (dB)	Weight	Response		
20 – 100	L _A	Fast	94.0	93.7
		Slow		93.7
	L _C	Fast		93.7
		L _p		Fast
30 – 120	L _A	Fast	94.0	93.7
		Slow		93.7
	L _C	Fast		93.7
		L _p		Fast
30 – 120	L _A	Fast	114.0	113.5
		Slow		113.5
	L _C	Fast		113.5
		L _p		Fast

IEC 651 Type 1 Spec. : ± 0.7 dB

Uncertainty : ± 0.1 dB

2. Level Stability : 0.1 dB

IEC 651 Type 1 Spec. : ± 0.3 dB

Uncertainty : ± 0.1 dB

3. Linearity

3.1 Level Linearity

UUT Range (dB)	Applied Value (dB)	UUT Reading (dB)	Variation (dB)	IEC 651 Type 1 Spec. (Primary Indicator Range)
130	114.0	113.9	+0.2	± 0.7 dB
130	104.0	103.9	+0.2	
120	94.0	93.7(Ref.)	--	
110	84.0	83.6	-0.1	
100	74.0	73.7	0.0	
90	64.0	63.7	0.0	
80	54.0	53.7	0.0	

Uncertainty : ± 0.1 dB



Calibration Certificate

Certificate No. **05083**

Page 3 of 3 Pages

3.2 Differential level linearity

UUT Range (dB)	Applied Value (dB)	UUT Reading (dB)	Variation (dB)	IEC 651 Type 1 Spec.
120	84.0	83.6	-0.1	± 0.4 dB
	94.0	93.7 (Ref.)	--	
	95.0	94.7	0.0	± 0.2 dB

Uncertainty : ± 0.1 dB

4. Frequency Weighting

A weighting

Frequency	Attenuation (dB)	IEC 651 Type 1 Spec.
31.5 Hz	-40.2	- 39.4 dB, ± 1.5 dB
63 Hz	-26.8	- 26.2 dB, ± 1.5 dB
125 Hz	-16.7	- 16.1 dB, ± 1 dB
250 Hz	-9.2	- 8.6 dB, ± 1 dB
500 Hz	-3.6	- 3.2 dB, ± 1 dB
1 kHz	0.0 (Ref.)	0 dB, ± 1 dB
2 kHz	+1.5	+ 1.2 dB, ± 1 dB
4 kHz	+1.5	+ 1.0 dB, ± 1 dB
8 kHz	-0.6	- 1.1 dB, + 1.5 dB ~ - 3 dB
16 kHz	-0.6	- 6.6 dB, + 3 dB ~ ∞

Uncertainty : ± 0.1 dB

5. Time Averaging

Applied Burst duty Factor	Applied Leq Value (dB)	UUT Reading (dB)	IEC 804 Type 1 Spec.
continuous	40.0	40.0	--
1/10	40.0	40.0	± 0.5 dB
1/10 ²	40.0	40.1	
1/10 ³	40.0	40.2	± 1.0 dB
1/10 ⁴	40.0	40.2	

Uncertainty : ± 0.1 dB

Remark : 1. UUT : Unit-Under-Test

2. The uncertainty claimed is for a confidence probability of not less than 95%.

3. Atmospheric Pressure : 1 004 hPa.

4. The internal calibration reference of UUT was drifted from 94.0 dB to 94.5 dB

----- END -----



Calibration Certificate

Certificate No. **95694**

Page 1 of 2 Pages

Customer : ETS-Testconsult Limited

Address : 8/F., Block B, Veristrong Industrial Centre, 34-36 Au Pui Wan St., Fotan, Hong Kong.

Order No. : Q92297

Date of receipt : 5-Nov-09

Item Tested

Description : Anemometer (EN/ 001/ 03)

Manufacturer : AZ Instrument

Model : AZ 8908

Serial No. : 9101259

Test Conditions

Date of Test : 11-Nov-09

Supply Voltage : --

Ambient Temperature : (23 ± 3)°C

Relative Humidity : (50 ± 25) %

Test Specifications

Calibration check.

Ref. Document/Procedure: T03, Z04.

Test Results


A correction factor of X 1.1 applied to velocity function is required to bring the meter reading to within manufacturer's specification. The results are shown in the attached page(s).


Main Test equipment used:

<u>Equipment No.</u>	<u>Description</u>	<u>Cert. No.</u>	<u>Due Date</u>	<u>Traceable to</u>
S050A	Std. Temp/R.H. Meter	93193	14-May-10	NIM-PRC, SCS-SWISS
S155	Std. Anemometer	NSC20094046	19-Jan-10	NIM-PRC

The values given in this Calibration Certificate only relate to the values measured at the time of the test and any uncertainties quoted will not include allowance for the equipment long term drift, variations with environmental changes, vibration and shock during transportation, overloading, mis-handling, or the capability of any other laboratory to repeat the measurement. Hong Kong Calibration Ltd. shall not be liable for any loss or damage resulting from the use of the equipment.

The test equipment used for calibration are traceable to International System of Units (SI).
The test results apply to the above Unit-Under-Test only

Calibrated by : 
S.K. Tang

Approved by : 
Steve Kwan

Date: 11-Nov-09

This Certificate is issued by:
Hong Kong Calibration Ltd.
Unit 8B, 24/F., Well Fung Industrial Centre, No. 58-76, Ta Chuen Ping Street, Kwai Chung, NT, Hong Kong.
Tel: 2425 8801 Fax: 2425 8646



Calibration Certificate

Certificate No. 95694

Page 2 of 2 Pages

Results :

1. Velocity

Applied Value (m/s)	UUT Reading (m/s)	Corrected Reading (UUT Reading x 1.1) (m/s)	Mfr's Spec.
2.50	2.2	2.4	± (3 % of reading + 1 dgt)
5.00	4.5	5.0	
10.00	8.8	9.7	
15.00	13.2	14.5	
20.00	17.7	19.5	

2. Temperature

Applied Value (°C)	UUT Reading (°C)	Mfr's Spec.
1.2	2.0	± 1 °C
25.9	25.6	
47.2	46.2	

Remark : 1. UUT: Unit-Under-Test

2. Uncertainty : ± (0.9% + 0.16 m/s) for Velocity, ± 0.3 °C for Temperature, for a confidence probability of not less than 95%.

3. Atmospheric Pressure : 1 002 hPa

----- END -----



Calibration Certificate

Certificate No. **06466**

Page **1** of **2** Pages

Customer : ETS-Testconsult Limited

Address : 8/F., Block B, Veristrong Industrial Centre, 34-36 Au Pui Wan St., Fotan, Hong Kong.

Order No. : Q02516

Date of receipt : 8-Nov-10

Item Tested

Description : Anemometer (EN/001/04)

Manufacturer : AZ Instrument

Model : AZ 8908

Serial No. : 9101231

Test Conditions

Date of Test : 10-Nov-10

Supply Voltage : --

Ambient Temperature : (23 ± 3)°C

Relative Humidity : (50 ± 25) %

Test Specifications

Calibration check.

Ref. Document/Procedure: T03, Z04.

Test Results

All results were within the manufacturer's specification.

The results are shown in the attached page(s).

Main Test equipment used:

<u>Equipment No.</u>	<u>Description</u>	<u>Cert. No.</u>	<u>Traceable to</u>
S223	Std. Thermometer	01631	NIM-PRC
S155	Std. Anemometer	NSC20104025	NIM-PRC

The values given in this Calibration Certificate only relate to the values measured at the time of the test and any uncertainties quoted will not include allowance for the equipment long term drift, variations with environmental changes, vibration and shock during transportation, overloading, mis-handling, or the capability of any other laboratory to repeat the measurement. Hong Kong Calibration Ltd. shall not be liable for any loss or damage resulting from the use of the equipment.

The test equipment used for calibration are traceable to International System of Units (SI).

The test results apply to the above Unit-Under-Test only

Calibrated by : _____

S. K. Tang

Approved by : _____

Alan Chu

This Certificate is issued by:

Hong Kong Calibration Ltd.

Unit 8B, 24/F., Well Fung Industrial Centre, No. 58-76, Ta Chuen Ping Street, Kwai Chung, NT, Hong Kong.

Tel: 2425 8801 Fax: 2425 8846

Date: 10-Nov-10



Calibration Certificate

Certificate No. 06466

Page 2 of 2 Pages

Results :

1. Velocity

Applied Value (m/s)	UUT Reading (m/s)	Mfr's Spec.
2.50	2.5	± 3 % f.s. (f.s. = 35 m/s)
5.00	4.9	
10.00	9.5	
15.00	14.3	
20.00	19.1	

2. Temperature

Applied Value (°C)	UUT Reading (°C)	Mfr's Spec.
3.10	3.0	± 1 °C
23.98	24.0	
48.20	47.8	

Remark : 1. UUT: Unit-Under-Test

2. Uncertainty : ± 1.3 % or ± 0.05 m/s, whichever is greater for Velocity, ± 0.25 °C for Temperature, for a confidence probability of not less than 95%.

3. Atmospheric Pressure : 1 011 hPa

----- END -----



Appendix B2

Impact Noise Monitoring Results



Day-time Noise Monitoring

Monitoring Station: KS6 (Podium at the Culliman)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (30min)	L10	L90	
05/11/10	Drizzle	15:30	16:00	61.2	64.3	57.4	0.8
10/11/10	Fine	17:40	18:10	62.7	63.6	61.6	0.2
19/11/10	Fine	15:40	16:10	61.7	63.8	58.5	1.4
26/11/10	Sunny	13:55	14:25	65.3	66.6	63.7	1.0

Monitoring Station: CGa (Pavement in front of Connaught Garden)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (30min)	L10	L90	
05/11/10	Cloudy	11:05	11:35	71.7	74.2	68.9	0.2
08/11/10	Fine	13:30	14:00	70.1	72.7	67.6	0.9
15/11/10	Sunny	10:00	10:30	72.6	74.9	69.0	0.3
22/11/10	Fine	09:15	09:45	71.2	74.3	67.7	0.8
29/11/10	Fine	10:05	10:35	70.8	72.7	67.3	0.8

Monitoring Station: RWM (Roof at Richwealth Mansion)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (30min)	L10	L90	
05/11/10	Cloudy	11:40	12:10	63.5	64.9	62.2	0.5
08/11/10	Fine	14:05	14:35	62.3	65.4	58.8	1.2
15/11/10	Sunny	10:35	11:05	64.1	66.4	59.3	0.6
22/11/10	Fine	09:50	10:20	60.8	63.5	57.2	1.1
29/11/10	Fine	10:40	11:10	62.1	64.9	57.8	1.4

Monitoring Station: KY3 (Roof at Kwan Yik Building Phase 3)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (30min)	L10	L90	
05/11/10	Cloudy	13:00	13:30	64.0	65.7	62.1	0.5
08/11/10	Fine	14:40	15:10	61.9	64.5	57.9	1.3
15/11/10	Sunny	11:15	11:45	62.4	64.5	58.7	0.8
22/11/10	Fine	10:25	10:55	61.1	63.8	57.9	1.3
29/11/10	Fine	11:15	11:45	61.8	64.4	57.3	1.2



Evening-time Noise Monitoring

Monitoring Station: KS6 (Podium at the Culliman)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (5min)	L10	L90	
06/11/10	Cloudy	20:25	20:30	60.5	62.2	60.0	0.1
06/11/10	Cloudy	20:30	20:35	60.7	62.3	59.4	0.1
06/11/10	Cloudy	20:35	20:40	60.4	62.2	58.9	<0.1
20/11/10	Fine	20:55	21:00	60.5	61.5	57.8	1.4
20/11/10	Fine	21:00	21:05	59.3	60.6	57.5	1.6
20/11/10	Fine	21:05	21:10	59.7	60.5	58.6	1.5
27/11/10	Fine	20:45	20:50	59.6	61.2	57.7	0.7
27/11/10	Fine	20:50	20:55	60.8	62.9	58.5	0.7
27/11/10	Fine	20:55	21:00	60.2	61.5	58.1	0.7

Monitoring Station: CGa (Pavement in front of Connaught Garden)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (5min)	L10	L90	
06/11/10	Cloudy	22:00	22:05	62.9	70.5	61.1	<0.1
06/11/10	Cloudy	22:05	22:10	62.9	70.2	60.5	<0.1
06/11/10	Cloudy	22:10	22:15	63.3	70.4	61.5	<0.1
20/11/10	Fine	21:50	21:55	66.7	69.4	63.0	1.1
20/11/10	Fine	21:55	22:00	66.9	69.8	63.4	1.2
20/11/10	Fine	22:00	22:05	67.5	70.1	63.8	1.4
27/11/10	Fine	21:20	21:25	68.5	70.7	61.9	0.6
27/11/10	Fine	21:25	21:30	68.8	70.8	62.0	0.6
27/11/10	Fine	21:30	21:35	68.3	70.4	61.7	0.6

Monitoring Station: RWM (Roof at Richwealth Mansion)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (5min)	L10	L90	
06/11/10	Cloudy	22:17	22:22	62.9	69.5	60.5	0.1
06/11/10	Cloudy	22:22	22:27	63.1	69.7	60.8	0.1
06/11/10	Cloudy	22:27	22:32	63.3	69.8	60.7	<0.1
20/11/10	Fine	22:10	22:15	68.1	70.5	64.7	1.5
20/11/10	Fine	22:15	22:20	68.4	70.8	65.0	1.4
20/11/10	Fine	22:20	22:25	67.9	70.2	64.4	1.3
27/11/10	Fine	21:40	21:45	68.3	70.4	62.8	0.4
27/11/10	Fine	21:45	21:50	67.5	70.4	62.0	0.4
27/11/10	Fine	21:50	21:55	67.8	70.5	62.2	0.4

Monitoring Station: KY3 (Roof at Kwan Yik Building Phase 3)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (5min)	L10	L90	
06/11/10	Cloudy	22:35	22:40	62.1	68.9	60.0	0.2
06/11/10	Cloudy	22:40	22:45	62.2	69.0	59.7	<0.1
06/11/10	Cloudy	22:45	22:50	62.5	69.0	60.9	<0.1
20/11/10	Fine	22:30	22:35	67.3	70.2	63.9	1.4
20/11/10	Fine	22:35	22:40	67.9	70.6	64.3	1.6
20/11/10	Fine	22:40	22:45	68.2	70.9	64.7	1.5
27/11/10	Fine	22:00	22:05	65.3	68.4	59.6	0.5
27/11/10	Fine	22:05	22:10	65.2	68.0	58.3	0.5
27/11/10	Fine	22:10	22:15	64.5	67.3	59.5	0.5



Night-time Noise Monitoring

Monitoring Station: KS6 (Podium at the Culliman)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (5min)	L10	L90	
21/11/10	Fine	00:10	00:15	58.7	60.1	56.8	1.4
21/11/10	Fine	00:15	00:20	57.9	59.5	56.1	1.5
21/11/10	Fine	00:20	00:25	57.7	58.0	57.3	1.6
28/11/10	Fine	00:50	00:55	55.0	57.7	53.9	0.8
28/11/10	Fine	00:55	01:00	54.9	57.4	53.7	0.8
28/11/10	Fine	01:00	01:05	54.7	57.1	53.5	0.8

Monitoring Station: CGa (Pavement in front of Connaught Garden)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (5min)	L10	L90	
20/11/10	Fine	23:00	23:05	61.4	63.6	57.7	1.2
20/11/10	Fine	23:05	23:10	60.9	63.2	57.4	1.1
20/11/10	Fine	23:10	23:15	61.7	64.0	58.1	1.0
27/11/10	Fine	23:00	23:05	62.1	64.8	58.6	0.4
27/11/10	Fine	23:05	23:10	61.9	64.6	58.5	0.4
27/11/10	Fine	23:10	23:15	61.7	64.1	58.5	0.4

Monitoring Station: RWM (Roof at Richwealth Mansion)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (5min)	L10	L90	
20/11/10	Fine	23:20	23:25	59.9	62.8	56.4	1.3
20/11/10	Fine	23:25	23:30	60.3	63.1	56.8	1.2
20/11/10	Fine	23:30	23:35	60.9	63.7	57.2	1.2
27/11/10	Fine	23:15	23:20	61.8	64.5	58.3	0.2
27/11/10	Fine	23:20	23:25	61.4	63.8	57.6	0.2
27/11/10	Fine	23:25	23:30	60.6	63.6	57.6	0.2

Monitoring Station: KY3 (Roof at Kwan Yik Building Phase 3)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (5min)	L10	L90	
20/11/10	Fine	23:40	23:45	60.6	63.6	57.1	1.4
20/11/10	Fine	23:45	23:50	60.3	63.2	56.7	1.3
20/11/10	Fine	23:50	23:55	61.0	64.0	57.5	1.1
27/11/10	Fine	23:35	23:40	59.8	64.3	57.3	0.3
27/11/10	Fine	23:40	23:45	60.2	64.1	57.0	0.3
27/11/10	Fine	23:45	23:50	59.9	63.8	56.8	0.3



Holiday-time Noise Monitoring

Monitoring Station: KS6 (Podium at the Culliman)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (5min)	L10	L90	
07/11/10	Fine	13:05	13:10	59.7	64.1	59.2	0.4
07/11/10	Fine	13:10	13:15	60.1	64.1	59.6	0.5
07/11/10	Fine	13:15	13:20	60.5	64.4	59.1	0.5
21/11/10	Sunny	09:20	09:25	61.6	64.0	58.9	1.2
21/11/10	Sunny	09:25	09:30	61.9	64.3	59.2	1.4
21/11/10	Sunny	09:30	09:35	63.3	65.4	61.7	1.1
28/11/10	Sunny	14:50	14:55	61.0	62.1	59.4	0.6
28/11/10	Sunny	14:55	15:00	60.3	61.5	59.0	0.6
28/11/10	Sunny	15:00	15:05	61.3	62.9	59.4	0.6

Monitoring Station: CGa (Pavement in front of Connaught Garden)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (5min)	L10	L90	
07/11/10	Fine	11:30	11:35	69.7	71.5	62.9	0.5
07/11/10	Fine	11:35	11:40	69.9	72.0	63.9	0.5
07/11/10	Fine	11:40	11:45	69.4	72.2	64.0	0.2
21/11/10	Sunny	10:20	11:25	68.1	70.5	65.4	0.8
21/11/10	Sunny	10:25	11:30	67.7	70.1	65.1	0.9
21/11/10	Sunny	10:30	11:35	67.9	70.3	65.2	0.7
28/11/10	Sunny	12:45	12:50	70.0	71.8	68.8	0.3
28/11/10	Sunny	12:50	12:55	69.8	71.5	68.6	0.3
28/11/10	Sunny	12:55	13:00	70.0	71.6	68.9	0.3

Monitoring Station: RWM (Roof at Richwealth Mansion)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (5min)	L10	L90	
07/11/10	Fine	11:50	11:55	62.5	66.4	60.5	0.6
07/11/10	Fine	11:55	12:00	62.2	66.0	60.6	0.2
07/11/10	Fine	12:00	12:05	62.6	64.9	61.0	0.4
21/11/10	Sunny	10:40	10:45	62.1	65.0	58.4	1.2
21/11/10	Sunny	10:45	10:50	61.7	64.6	57.9	1.1
21/11/10	Sunny	10:50	10:55	61.9	64.9	58.2	1.0
28/11/10	Sunny	13:10	13:15	64.7	66.2	62.8	0.5
28/11/10	Sunny	13:15	13:20	65.2	66.4	63.4	0.5
28/11/10	Sunny	13:20	13:25	65.0	66.4	63.1	0.5

Monitoring Station: KY3 (Roof at Kwan Yik Building Phase 3)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (5min)	L10	L90	
07/11/10	Fine	12:15	12:20	60.9	61.9	59.4	0.2
07/11/10	Fine	12:20	12:25	60.7	62.5	59.1	0.1
07/11/10	Fine	12:25	12:30	60.6	62.2	59.3	0.5
21/11/10	Sunny	11:00	11:05	61.1	64.2	57.7	1.3
21/11/10	Sunny	11:05	11:10	61.4	64.5	57.9	1.1
21/11/10	Sunny	11:10	11:15	62.0	65.1	58.2	1.2
28/11/10	Sunny	13:35	13:40	63.5	65.2	61.8	0.6
28/11/10	Sunny	13:40	13:45	63.8	65.5	61.8	0.6
28/11/10	Sunny	13:45	13:50	63.1	65.0	61.5	0.6




Appendix B3

Graphical Plots of Impact Noise Monitoring Data




Noise Monitoring (Day-time)


Noise level at KS6 - Podium at the Culliman




Noise level at CGa - Pavement in front of Connaught Garden



Noise level at RWM - Roof of Richwealth Mansion




Noise level at KY3 - Roof of Kwan Yik Building Phase 3






Noise Monitoring (Evening-time)


Noise level at KS6 - Podium at the Culliman




Noise level at CGa - Pavement in front of Connaught Garden



Noise level at RWM - Roof of Richwealth Mansion




Noise level at KY3 - Roof of Kwan Yik Building Phase 3






Noise Monitoring (Night-time)


Noise level at KS6 - Podium at the Culliman




Noise level at CGA - Pavement in front of Connaught Garden



Noise level at RWM - Roof of Richwealth Mansion




Noise level at KY3 - Roof of Kwan Yik Building Phase 3






Noise Monitoring (Holiday-time)


Noise level at KS6 - Podium at the Culliman




Noise level at CGA - Pavement in front of Connaught Garden



Noise level at RWM - Roof of Richwealth Mansion



Noise level at KY3 - Roof of Kwan Yik Building Phase 3





Appendix C1

Calibration Certificates for Impact Water Quality Monitoring Equipments

Performance Check of Turbidimeter

Equipment Ref. No. : ET105051007 Manufacturer : HACH
 Model No. : 2100P Serial No. : 0806 000 30281
 Date of Calibration : 15/10/10 Due Date : 14/1/11

Gelex Vial Std	Theoretical Value (NTU)	Measured Value (NTU)	Difference %
0-10 NTU	5.34	5.49	2.77%
10-100 NTU	52.5	52.1	0.76%
100-1000 NTU	543	529	2.61%

Acceptance Criteria

Difference : <5 %

The salinity meter complies * / ~~does not comply~~ * with the specified requirements and is deemed acceptable * / ~~unacceptable~~ * for use. Measurements are traceable to national standards.

Checked by : Zu Approved by : Inde Lan



Performance Check of Salinity Meter

Equipment Ref. No. : ET1EW1008103 Manufacturer : YSI
Model No. : 85 Serial No. : 084100716
Date of Calibration : 3019110 Due Date : 29112110

Ref. No. of Salinity Standard used (30ppt)

J362

Salinity Standard (ppt)	Measured Salinity (ppt)	Difference %
30	29.5	1.67%

Acceptance Criteria

Difference : <10 %

The salinity meter complies * / ~~does not comply~~ * with the specified requirements and is deemed acceptable * / ~~unacceptable~~ * for use. Measurements are traceable to national standards.

Checked by : *Tm*

Approved by : *[Signature]*



Internal Calibration Report of Dissolved Oxygen Meter

Equipment Ref. No. : ET1EW10081003 Manufacturer : YSI
 Model No. : 85 Serial No. : 08L100716
 Date of Calibration : 30/9/10 Calibration Due Date : 29/12/10

Temperature Verification

Ref. No. of Reference Thermometer : ET10S211001
 Ref. No. of Water Bath : ET10S331001

		Temperature (°C)		
Reference Thermometer reading	Measured	24.1	Corrected	24.2
DO Meter reading	Measured	24.5	Difference	0.3

Standardization of sodium thiosulphate (Na₂S₂O₃) solution

Reagent No. of Na₂S₂O₃ titrant : J392 Reagent No. of 0.025N K₂Cr₂O₇ : J393

	Trial 1	Trial 2
Initial Vol. of Na ₂ S ₂ O ₃ (ml)	0.0	40.0
Final Vol. of Na ₂ S ₂ O ₃ (ml)	40.0	80.0
Vol. of Na ₂ S ₂ O ₃ used (ml)	40.0	40.0
Normality of Na ₂ S ₂ O ₃ solution (N)	0.025	0.025
Average Normality (N) of Na ₂ S ₂ O ₃ solution (N)	0.025	
Acceptance criteria, Deviation	Less than ± 0.001N	

Calculation: Normality of Na₂S₂O₃, N = 1 / ml Na₂S₂O₃ used

Linearity Checking

Determination of dissolved oxygen content by Winkler Titration *

Purging Time (min)	2		5		10	
Trial	1	2	1	2	1	2
Initial Vol. of Na ₂ S ₂ O ₃ (ml)	0	11.80	0	9.30	0	6.75
Final Vol. of Na ₂ S ₂ O ₃ (ml)	11.80	23.65	9.30	18.55	6.75	13.50
Vol. (V) of Na ₂ S ₂ O ₃ used (ml)	11.80	11.85	9.30	9.25	6.75	6.75
Dissolved Oxygen (DO), mg/L	7.92	7.95	6.24	6.21	4.53	4.53
Acceptance criteria, Deviation	Less than + 0.3mg/L		Less than + 0.3mg/L		Less than + 0.3mg/L	

Calculation: DO (mg/L) = V x N x 8000/298

Purging time, min	DO meter reading, mg/L			Winkler Titration result *, mg/L			Difference (%) of DO Content
	1	2	Average	1	2	Average	
2	8.08	8.16	8.12	7.92	7.95	7.94	2.24
5	6.44	6.44	6.44	6.24	6.21	6.23	3.31
10	4.62	4.58	4.60	4.53	4.53	4.53	1.53
Linear regression coefficient							



Internal Calibration Report of Dissolved Oxygen Meter

Zero Point Checking

DO meter reading, mg/L	0.00
------------------------	------

Salinity Checking

Reagent No. of NaCl (10ppt)	J392	Reagent No. of NaCl (30ppt)	J393
-----------------------------	------	-----------------------------	------

Determination of dissolved oxygen content by Winkler Titration **

Salinity (ppt)	10		30	
	1	2	1	2
Initial Vol. of Na ₂ S ₂ O ₃ (ml)	0	11.90	0	11.15
Final Vol. of Na ₂ S ₂ O ₃ (ml)	11.90	23.80	11.15	22.25
Vol. (V) of Na ₂ S ₂ O ₃ used (ml)	11.90	11.90	11.15	11.10
Dissolved Oxygen (DO), mg/L	7.99	7.99	7.48	7.45
Acceptance criteria, Deviation	Less than + 0.3mg/L		Less than + 0.3mg/L	

Calculation: $DO (mg/L) = V \times N \times 8000/298$

Salinity (ppt)	DO meter reading, mg/L			Winkler Titration result**, mg/L			Difference (%) of DO Content
	1	2	Average	1	2	Average	
10	8.17	8.15	8.16	7.99	7.99	7.99	2.11
30	7.55	7.55	7.55	7.48	7.45	7.47	1.07

Acceptance Criteria

- (1) Difference between temperature readings from temperature sensor of DO probe and reference thermometer : < 0.5 °C
- (2) Linear regression coefficient : >0.99
- (3) Zero checking: 0.0mg/L
- (4) Difference (%) of DO content from the meter reading and by winkler titration : within ± 5%

The equipment complies [#] / ~~does not comply~~ [#] with the specified requirements and is deemed acceptable [#] / unacceptable [#] for use.

[#] Delete as appropriate

Calibrated by :

_____ *Tu* _____

Approved by :

_____ *[Signature]* _____



Appendix C2

Impact Water Quality Monitoring Results

Mid-Flood Tide

Monitoring Station : C4

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/11/10	1637-1650	20/Fine	Surface	1.0	27.7	30.0	30.0	5.88	5.88	82.3	82.2	5.10	5.10	5.16	8.4	8.4	8.2
						30.0		5.87		82.1		5.09			8.4		
						30.9		5.82		81.5		5.15			8.2		
04/11/10	1659-1712	22/Drizzle	Middle	8.1	21.6	30.8	30.9	5.80	5.81	81.2	81.4	5.14	5.15	4.32	8.4	8.3	6.7
						30.8		5.80		81.2		5.22			8.0		
						30.8		5.77		80.8		5.25			8.0		
06/11/10	1850-1900	20/Drizzle	Bottom	15.2	21.0	30.8	30.8	5.80	5.79	81.2	81.0	5.22	5.24	5.69	8.4	8.4	8.8
						30.8		5.77		80.8		5.44			8.5		
						31.5		6.14		86.6		4.15			9.6		
09/11/10	1142-1157	25/Fine	Surface	1.0	24.1	30.1	30.1	6.16	6.15	87.4	87.2	4.99	4.95	4.98	8.0	8.1	8.0
						30.1		6.13		87.0		4.91			8.0		
						30.7		6.07		85.5		5.06			8.2		
11/11/10	1317-1330	25/Fine	Middle	7.3	20.5	30.7	30.7	5.87	5.87	83.9	83.9	4.62	4.61	4.71	7.6	7.5	7.7
						30.7		5.86		83.8		4.60			7.4		
						31.5		5.72		81.8		4.79			7.8		
13/11/10	1423-1438	24/Fine	Bottom	14.1	20.0	31.4	31.5	5.74	5.73	82.1	82.0	4.75	4.77	4.37	8.0	7.9	7.2
						31.0		5.90		81.4		4.04			8.0		
						31.0		5.86		82.0		4.13			8.0		
16/11/10	1710-1722	24/Fine	Surface	1.0	23.6	30.5	30.5	5.97	5.96	82.9	82.7	5.17	5.14	5.13	6.5	6.5	8.2
						30.5		5.94		82.5		5.11			8.2		
						31.3		5.83		81.1		4.98			8.2		
18/11/10	1805-1824	24/Sunny	Middle	8.2	23.8	31.4	31.3	5.81	5.81	80.8	80.7	5.69	5.65	5.61	8.4	8.4	8.8
						31.4		5.75		79.9		4.27			9.0		
						31.7		5.67		78.9		4.33			9.4		
20/11/10	1817-1827	22/Cloudy	Bottom	15.8	22.8	32.0	32.0	5.77	5.79	80.2	80.5	4.91	4.94	5.01	8.0	8.0	8.0
						32.0		5.77		80.2		4.91			8.2		
						31.2		5.87		81.5		5.06			8.2		
23/11/10	1108-1120	23/Fine	Surface	1.0	24.4	31.1	31.1	5.83	5.81	81.0	80.7	5.11	5.15	5.32	8.2	8.2	8.4
						31.1		5.78		80.3		5.18			8.2		
						31.7		5.74		79.9		5.26			8.5		
25/11/10	1125-1138	22/Fine	Middle	8.2	23.5	31.8	31.8	5.76	5.75	80.0	80.0	5.38	5.32	5.32	8.2	8.4	8.4
						32.4		5.67		78.8		5.48			8.8		
						32.5		5.67		78.8		5.53			8.8		
27/11/10	1327-1340	22/Fine	Bottom	15.6	22.2	32.1	32.1	5.99	5.98	83.3	83.1	4.93	4.92	5.01	8.0	8.1	8.0
						32.1		5.99		83.3		4.91			8.2		
						30.4		6.06		84.2		5.06			8.0		
30/11/10	1425-1432	23/Fine	Surface	1.0	23.6	30.4	30.5	5.86	5.86	81.5	81.4	5.13	5.15	5.26	8.3	8.2	8.5
						30.4		6.06		84.2		5.09			8.0		
						30.5		5.90		82.0		5.07			8.0		
02/11/10	1637-1650	20/Fine	Surface	1.0	27.7	30.0	30.0	5.88	5.88	82.3	82.2	5.10	5.10	5.16	8.4	8.4	8.2
						30.0		5.87		82.1		5.09			8.4		
						30.9		5.82		81.5		5.15			8.2		
04/11/10	1659-1712	22/Drizzle	Middle	7.4	19.2	31.9	31.8	6.19	6.20	87.0	87.1	4.11	4.19	4.32	6.2	6.4	6.7
						31.9		6.19		87.0		4.11			6.5		
						32.0		6.11		86.9		4.40			7.0		
06/11/10	1850-1900	20/Drizzle	Bottom	14.0	18.0	31.0	31.0	5.99	5.92	85.6	86.0	5.42	5.43	5.69	8.2	8.4	8.8
						31.0		5.85		86.3		5.44			8.5		
						30.1		6.24		90.2		5.92			9.6		
09/11/10	1142-1157	25/Fine	Surface	1.0	24.1	30.1	30.1	6.16	6.15	87.4	87.2	4.99	4.95	4.98	8.0	8.1	8.0
						30.1		6.13		87.0		4.91			8.0		
						30.7		6.07		85.5		5.06			8.2		
11/11/10	1317-1330	25/Fine	Middle	7.3	20.5	30.7	30.7	5.87	5.87	83.9	83.9	4.62	4.61	4.71	7.6	7.5	7.7
						30.7		5.86		83.8		4.60			7.4		
						31.5		5.72		81.8		4.79			7.8		
13/11/10	1423-1438	24/Fine	Bottom	14.1	20.0	31.4	31.5	5.74	5.73	82.1	82.0	4.75	4.77	4.37	8.0	7.9	7.2
						31.0		5.90		81.4		4.04			8.0		
						31.0		5.86		82.0		4.13			8.0		
16/11/10	1710-1722	24/Fine	Surface	1.0	23.6	30.5	30.5	5.97	5.96	82.9	82.7	5.17	5.14	5.13	6.5	6.5	8.2
						30.5		5.94		82.5		5.11			8.2		
						31.3		5.83		81.1		4.98			8.2		
18/11/10	1805-1824	24/Sunny	Middle	8.2	23.8	31.4	31.3	5.81	5.81	80.8	80.7	5.69	5.65	5.61	8.4	8.4	8.8
						31.4		5.75		79.9		4.27			9.0		
						31.7		5.67		78.9		4.33			9.4		
20/11/10	1817-1827	22/Cloudy	Bottom	15.8	22.8	32.0	32.0	5.77	5.79	80.2	80.5	4.91	4.94	5.01	8.0	8.0	8.0
						32.0		5.77		80.2		4.91			8.2		
						31.2		5.87		81.5		5.06			8.2		
23/11/10	1108-1120	23/Fine	Surface	1.0	24.4	31.1	31.1	5.83	5.81	81.0	80.7	5.11	5.15	5.32	8.2	8.2	8.4
						31.1		5.78		80.3		5.18			8.2		
						31.7		5.74		79.9		5.26			8.5		
25/11/10	1125-1138	22/Fine	Middle	8.2	23.5	31.8	31.8	5.76	5.75	80.0	80.0	5.38	5.32	5.32	8.2	8.4	8.4
						32.4		5.67		78.8		5.48			8.8		
						32.5		5.67		78.8		5.53			8.8		
27/11/10	1327-1340	22/Fine	Bottom	15.6	22.2	32.1	32.1	5.99	5.98	83.3	83.1	4.93	4.92	5.01	8.0	8.1	8.0
						32.1		5.99		83.3		4.91			8.2		
						30.4		6.06		84.2		5.06			8.0		
30/11/10	1425-1432	23/Fine	Surface	1.0	23.6	30.4	30.5	5.86	5.86	81.5	81.4	5.13	5.15	5.26	8.3	8.2	8.5
						30.4		6.06		84.2		5.09			8.0		
						30.5		5.90		82.0		5.07			8.0		

Mid-Flood Tide

Monitoring Station : R5

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)		Suspended Solids (mg/L)			
			Surface			Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/11/10	1436-1448	20/Fine	Surface	1.0	22.9	30.6	30.6	6.02	6.02	84.3	84.2	4.80	4.84	4.97	8.0	8.1	8.2
						30.5		6.01		84.1		4.87			8.2		
			Middle	8.5	21.9	30.9	30.9	5.88	5.88	82.3	82.3	4.95	4.96		8.0	8.2	
					30.8	5.87	82.2	4.96	8.4								
			Bottom	16.0	21.0	31.0	31.0	5.84	5.84	81.8	81.7	5.10	5.13		8.2	8.3	
	31.0	5.83		81.6	5.15	8.4											
04/11/10	1515-1525	22/Cloudy	Surface	1.0	19.7	30.9	30.9	6.25	6.23	89.7	84.6	4.17	4.17	4.48	6.8	6.8	7.3
						30.9		6.20		79.5		4.17			6.8		
			Middle	4.5	19.4	31.1	31.3	6.11	6.13	87.0	87.4	4.79	4.75		7.8	7.7	
					31.5	6.14	87.7	4.70	6.8								
			Bottom	7.9	19.1	31.9	31.9	6.11	6.06	85.9	85.9	4.51	4.53		7.5	7.5	
	31.9	6.01		85.9	4.55	7.4											
06/11/10	1655-1705	20/Drizzle	Surface	1.0	19.5	28.4	28.4	6.21	6.21	90.2	90.2	6.22	6.21	6.16	9.5	9.6	9.5
						28.4		6.20		90.2		6.20			9.6		
			Middle	6.0	19.1	28.9	28.9	6.10	6.11	88.0	88.1	6.11	6.18		9.2	9.3	
					28.9	6.11	88.2	6.24	9.4								
			Bottom	11.0	18.4	29.1	29.1	6.00	6.00	85.7	85.6	6.20	6.10		9.6	9.5	
	29.1	5.99		85.5	6.00	9.4											
09/11/10	0742-0753	25/Fine	Surface	1.0	24.1	30.2	30.2	6.22	6.24	86.2	86.4	5.03	5.07	4.96	8.3	8.4	8.0
						30.2		6.25		86.6		5.10			8.4		
			Middle	9.2	23.2	30.8	30.8	6.09	6.09	84.3	84.3	4.87	4.91		7.6	7.7	
					30.8	6.08	84.2	4.94	7.8								
			Bottom	17.9	22.5	31.4	31.4	5.89	5.90	81.6	81.7	4.94	4.91		8.0	7.9	
	31.4	5.90		81.7	4.87	7.8											
11/11/10	0933-0946	25/Fine	Surface	1.0	21.2	30.0	30.0	6.12	6.14	87.5	87.7	5.12	5.13	5.10	8.5	8.4	8.2
						30.0		6.15		87.9		5.13			8.2		
			Middle	6.5	20.7	30.9	30.9	5.96	5.95	85.2	85.1	5.08	5.12		8.0	8.1	
					30.9	5.94	84.9	5.15	8.2								
			Bottom	11.4	20.1	31.3	31.3	5.82	5.83	83.2	83.3	5.04	5.05		8.0	8.0	
	31.3	5.83		83.4	5.05	8.0											
13/11/10	1200-1215	24/Fine	Surface	1.0	24.4	31.0	31.0	5.76	5.78	80.1	80.4	4.28	4.32	4.59	6.8	6.6	7.1
						30.9		5.79		80.6		4.36			6.4		
			Middle	8.7	23.8	31.3	31.3	5.71	5.73	79.4	79.6	4.55	4.57		7.0	6.9	
					31.3	5.74	79.8	4.59	6.8								
			Bottom	16.4	23.0	32.0	32.0	5.68	5.68	78.6	78.6	4.86	4.89		8.0	7.8	
	32.0	5.68		78.6	4.91	7.6											
16/11/10	1512-1524	24/Fine	Surface	1.0	23.8	30.5	30.6	6.09	6.08	84.6	84.4	4.74	4.77	5.21	7.8	7.7	8.5
						30.6		6.06		84.2		4.80			7.5		
			Middle	8.7	23.2	31.4	31.4	5.88	5.86	81.7	81.4	5.34	5.38		8.8	8.7	
					31.4	5.84	81.1	5.42	8.6								
			Bottom	16.4	23.0	31.8	31.8	5.72	5.71	78.9	78.7	5.50	5.49		9.2	9.1	
	31.8	5.69		78.5	5.47	9.0											
18/11/10	1552-1611	24/Sunny	Surface	1.0	24.3	30.9	30.8	5.74	5.76	79.8	79.5	5.89	5.90	6.20	9.2	9.2	9.2
						30.7		5.77		79.2		5.90			9.2		
			Middle	8.6	23.7	31.2	31.1	5.68	5.69	79.0	79.2	6.17	6.18		8.4	8.7	
					31.0	5.70	79.3	6.18	8.9								
			Bottom	16.2	22.7	31.9	31.8	5.66	5.66	78.7	78.7	6.54	6.53		9.6	9.6	
	31.7	5.65		78.6	6.51	9.6											
20/11/10	1619-1630	22/Cloudy	Surface	1.0	23.6	31.0	31.1	6.05	6.03	84.0	83.8	5.21	5.25	5.08	8.8	8.7	8.1
						31.1		6.01		83.5		5.29			8.6		
			Middle	8.7	23.1	31.6	31.7	5.84	5.82	81.1	80.9	4.87	4.86		7.6	7.6	
					31.7	5.80	80.6	4.84	7.5								
			Bottom	16.4	22.8	32.1	32.1	5.75	5.77	79.3	79.5	5.09	5.12		8.0	8.1	
	32.0	5.78		79.7	5.15	8.2											
23/11/10	0915-0930	23/Fine	Surface	1.0	24.3	31.0	31.0	5.76	5.73	80.0	79.6	5.26	5.29	5.50	8.5	8.7	9.0
						31.0		5.70		79.2		5.31			8.8		
			Middle	8.7	23.5	31.6	31.6	5.65	5.66	78.1	78.5	5.51	5.54		9.2	9.1	
					31.6	5.66	78.8	5.56	9.0								
			Bottom	16.4	23.0	32.4	32.5	5.68	5.68	78.9	78.9	5.66	5.68		9.4	9.3	
	32.5	5.67		78.8	5.69	9.2											
25/11/10	0927-0940	20/Fine	Surface	1.0	23.3	30.3	30.4	5.97	5.95	82.9	82.7	5.13	5.12	5.10	8.2	8.1	8.1
						30.4		5.93		82.4		5.10			8.0		
			Middle	8.9	22.7	31.3	31.4	5.87	5.84	81.6	81.2	5.06	5.05		8.0	8.0	
					31.4	5.81	80.8	5.04	7.9								
			Bottom	16.8	22.3	32.2	32.2	5.79	5.78	80.5	80.4	5.14	5.13		8.4	8.3	
	32.1	5.77		80.2	5.11	8.2											
27/11/10	1132-1145	21/Fine	Surface	1.0	22.6	30.3	30.4	6.08	6.07	84.5	84.4	5.06	5.08	5.14	8.0	8.1	8.2
						30.4		6.06		84.2		5.09			8.2		
			Middle	8.9	22.4	31.0	31.1	6.01	5.99	83.5	83.2	5.04	5.06		7.8	7.9	
					31.1	5.97	82.9	5.07	8.0								
			Bottom	16.8	21.6	32.0	32.0	5.94	5.95	82.6	82.7	5.29	5.28		8.6	8.6	
	32.0	5.96		82.8	5.26	8.5											
30/11/10	1229-1242	22/Fine	Surface	1.0	23.5	30.2	30.3	5.96	5.94	82.8	82.5	5.36	5.33	5.34	8.8	8.7	8.7
						30.3		5.91		82.1		5.30			8.6		
			Middle	8.9	22.4	31.3	31.3	6.04	6.05	83.9	84.1	5.48	5.44		9.0	9.1	
					31.2	6.06	84.2	5.40	9.2								
			Bottom	16.8	22.0	32.0	32.0	5.99	5.99	83.3	83.2	5.29	5.25		8.2	8.2	
	32.0	5.98		83.1	5.20	8.2											

Mid-Flood Tide

Monitoring Station : R6

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)			
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average	
02/11/10	1529-1539	20/Fine	Surface	1.0	22.8	30.1	30.1	6.01	6.01	84.1	84.1	5.20	5.19	5.18	8.2	8.2	8.3	
						30.0		6.00		84.0		5.18			8.2			
			Middle	8.0	21.8	30.9	30.9	5.88	5.88	82.3	82.3	5.14	5.15		5.15	8.0		8.2
						30.9		5.88		82.3		5.15			8.4			
			Bottom	15.0	21.2	30.9	30.9	5.87	5.88	82.2	82.3	5.18	5.19		5.19	8.2		8.4
						30.9		5.88		82.3		5.20			8.6			

Mid-Flood Tide

Monitoring Station : R7

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)			
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average	
02/11/10	1542-1606	20/Fine	Surface	1.0	22.7	30.0	30.0	5.99	5.99	83.9	83.8	5.30	5.32	5.27	8.8	8.7	8.6	
				9.1	21.8	31.0		5.87		82.2		5.38			8.6			
			Middle	9.1	21.8	31.0	5.88	82.3	5.39	5.39	9.0	9.0	8.0					
				17.2	21.1	30.9	5.76	80.6	5.10	5.11	8.2							
			Bottom	17.2	21.1	30.8	5.77	80.8	5.12	5.11	8.0							
						30.9	6.00	85.7	4.95	4.97	7.9							
04/11/10	1614-1624	22/Cloudy	Surface	1.0	19.8	30.9	30.9	6.00	6.04	85.7	85.8	4.95		4.97	5.14	8.0	8.0	8.4
				8.1	19.5	31.1		6.00		85.7		5.05				5.08		
			Middle	8.1	19.5	31.1	5.91	84.2	5.11	5.08	8.0							
				15.2	19.1	31.9	5.80	84.0	5.44	5.38	9.0							
			Bottom	15.2	19.1	31.9	5.77	82.2	5.32	5.38	9.0							
						31.9	5.80	84.0	5.44	5.38	9.0							
06/11/10	1755-1805	20/Drizzle	Surface	1.0	19.0	29.1	29.1	6.24	6.22	90.4	90.7	5.97	5.96	5.96	9.6	9.4	9.1	
				7.9	19.1	29.4		6.05		89.0		5.97			5.97			8.6
			Middle	7.9	19.1	29.4	6.07	89.2	5.97	5.97	8.8							
				14.8	18.7	30.0	5.96	85.0	6.00	5.96	9.2							
			Bottom	14.8	18.7	30.0	5.92	84.4	5.92	5.96	9.0							
						30.0	5.92	84.4	5.92	5.96	9.0							
09/11/10	0859-0914	25/Fine	Surface	1.0	24.0	30.1	30.1	6.29	6.30	87.1	87.2	4.90	4.91	4.97	8.0	8.0	8.0	
				8.7	23.1	30.7		6.13		84.9		5.06			5.04			7.8
			Middle	8.7	23.1	30.7	6.14	85.0	5.02	5.04	8.0							
				16.4	22.4	31.4	5.90	81.7	4.92	4.96	8.2							
			Bottom	16.4	22.4	31.4	5.88	81.4	4.99	4.96	8.0							
						31.4	5.88	81.4	4.99	4.96	8.0							
11/11/10	1056-1108	25/Fine	Surface	1.0	21.0	30.0	30.0	6.08	6.09	86.9	87.1	5.11	5.14	5.12	8.1	8.3	8.2	
				6.7	20.5	30.8		5.89		84.2		5.01			5.04			8.0
			Middle	6.7	20.5	30.8	5.92	84.7	5.07	5.04	7.9							
				13.5	19.9	31.2	5.78	82.7	5.15	5.18	8.4							
			Bottom	13.5	19.9	31.3	5.76	82.4	5.20	5.18	8.2							
						31.3	5.76	82.4	5.20	5.18	8.2							
13/11/10	1335-1348	24/Fine	Surface	1.0	24.4	31.1	31.1	5.86	5.83	81.4	81.0	4.08	4.12	4.42	6.4	6.5	6.7	
				9.2	23.7	31.5		5.68		78.9		4.40			4.38			6.5
			Middle	9.2	23.7	31.5	5.72	79.5	4.35	4.38	6.5							
				17.4	22.8	32.1	5.65	78.6	4.73	4.76	7.0							
			Bottom	17.4	22.8	32.1	5.66	78.7	4.78	4.76	7.2							
						32.1	5.66	78.7	4.78	4.76	7.2							
16/11/10	1624-1636	24/Fine	Surface	1.0	23.7	30.6	30.6	5.99	5.97	83.2	83.0	5.15	5.13	5.15	8.2	8.1	8.2	
				9.4	22.9	31.5		5.95		82.7		5.03			5.06			7.9
			Middle	9.4	22.9	31.5	5.98	83.1	5.08	5.06	8.2							
				17.8	22.8	31.8	5.77	79.6	5.27	5.26	8.4							
			Bottom	17.8	22.8	31.7	5.74	79.2	5.24	5.26	8.2							
						31.7	5.74	79.2	5.24	5.26	8.2							
18/11/10	1720-1734	24/Sunny	Surface	1.0	24.3	30.8	30.9	5.89	5.89	81.9	81.8	5.34	5.37	5.61	8.4	8.3	8.8	
				9.1	23.5	31.1		5.71		79.4		5.54			5.57			9.0
			Middle	9.1	23.5	31.1	5.69	79.1	5.59	5.57	8.8							
				17.2	22.8	31.7	5.65	78.4	5.89	5.90	9.0							
			Bottom	17.2	22.8	31.9	5.67	78.7	5.90	5.90	9.4							
						31.9	5.67	78.7	5.90	5.90	9.4							
20/11/10	1733-1743	22/Cloudy	Surface	1.0	23.5	31.2	31.2	5.99	5.97	83.2	83.0	5.02	5.00	5.14	8.0	8.0	8.2	
				9.3	23.0	31.2		5.95		82.7		4.97			5.00			7.9
			Middle	9.3	23.0	31.8	5.71	78.7	5.14	5.12	8.2							
				17.6	22.9	31.9	5.74	79.2	5.10	5.12	8.2							
			Bottom	17.6	22.9	32.0	5.68	78.6	5.29	5.32	8.4							
						32.1	5.66	78.2	5.34	5.32	8.6							
23/11/10	1035-1047	23/Fine	Surface	1.0	24.3	31.1	31.1	5.85	5.83	81.3	81.0	5.12	5.15	5.36	8.0	8.0	8.5	
				9.2	23.5	31.6		5.73		79.8		5.34			5.37			8.4
			Middle	9.2	23.5	31.7	5.75	80.0	5.39	5.37	8.6							
				17.4	22.9	32.5	5.66	78.8	5.52	5.55	9.0							
			Bottom	17.4	22.9	32.6	5.65	78.6	5.58	5.55	8.8							
						32.6	5.65	78.6	5.58	5.55	8.8							
25/11/10	1037-1050	20/Fine	Surface	1.0	23.5	30.5	30.5	5.98	6.01	83.1	83.5	5.01	5.03	5.15	8.0	7.9	8.3	
				9.1	22.6	31.0		6.13		85.2		5.15			5.13			8.0
			Middle	9.1	22.6	31.1	6.10	84.8	5.10	5.13	8.4							
				17.2	22.3	32.2	6.03	83.8	5.31	5.31	8.8							
			Bottom	17.2	22.3	32.1	6.07	84.4	5.30	5.31	8.5							
						32.1	6.07	84.4	5.30	5.31	8.5							
27/11/10	1239-1252	21/Fine	Surface	1.0	22.7	30.2	30.3	5.96	5.95	82.8	82.6	5.08	5.08	5.17	7.9	7.9	8.1	
				9.1	22.2	30.8		5.94		82.6		5.29			5.28			8.2
			Middle	9.1	22.2	30.9	5.91	82.1	5.27	5.28	8.0							
				17.2	21.4	31.9	6.09	84.7	5.13	5.14	8.4							
			Bottom	17.2	21.4	31.8	6.04	83.9	5.15	5.14	8.2							
						31.8	6.04	83.9	5.15	5.14	8.2							
30/11/10	1337-1350	22/Fine	Surface	1.0	23.7	30.6	30.6	6.08	6.09	84.5	84.6	5.45	5.43	5.39	8.9	8.8	8.9	
				9.4	22.7	31.4		5.95		82.7		5.36			5.38			8.8
			Middle	9.4	22.7	31.5	5.92	82.3	5.40	5.38	9.0							
				17.8	22.4	32.0	5.89	81.9	5.39	5.38	8.9							
			Bottom	17.8	22.4	32.1	5.87	81.6	5.36	5.38	9.0							
						32.1	5.87	81.6	5.36	5.38	9.0							

Mid-Flood Tide

Monitoring Station : R28

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)					
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average			
02/11/10	1451-1502	20/Fine	Surface	1.0	22.8	30.5	30.6	6.03	6.04	84.4	84.5	4.88	4.89	5.03	8.0	7.9	8.1			
						30.6		6.04		84.6		4.89			7.8					
			Middle	5.6	21.9	30.8	30.8	5.87	5.87	82.1	82.1	5.03	5.04		5.03	5.04		8.0	8.0	8.0
						30.8		5.87		82.1		5.05			8.0					
			Bottom	10.2	21.3	31.0	31.0	5.84	5.84	81.8	81.7	5.13	5.16		5.13	5.16		8.4	8.3	8.3
						31.0		5.83		81.6		5.18			8.2					
04/11/10	1531-1541	22/Cloudy	Surface	1.0	19.7	30.9	30.9	6.20	6.20	89.5	89.5	4.52	4.56	4.69	7.5	7.5	7.7			
						30.9		6.20		89.5		4.60			7.4					
			Middle	6.2	19.3	31.0	31.0	6.14	6.13	87.7	87.8	4.66	4.64		4.66	4.64		7.5	7.7	7.7
						31.0		6.11		87.9		4.62			7.8					
			Bottom	11.4	19.1	31.9	31.7	6.10	6.09	85.7	85.9	4.69	4.87		4.69	4.87		8.0	8.0	8.0
						31.5		6.08		86.0		5.05			8.0					
06/11/10	1712-1722	20/Drizzle	Surface	1.0	19.5	28.4	28.3	6.20	6.20	90.0	90.0	6.15	6.14	6.05	9.2	9.3	9.1			
						28.1		6.20		90.0		6.12			9.4					
			Middle	7.4	19.1	29.0	29.0	6.15	6.14	89.0	88.9	6.11	6.11		6.11	6.11		9.0	9.0	9.0
						29.0		6.12		88.8		6.11			9.0					
			Bottom	11.8	18.9	29.4	29.4	6.00	6.01	85.7	85.8	5.92	5.91		5.92	5.91		9.2	9.1	9.1
						29.4		6.01		85.9		5.90			9.2					
09/11/10	0759-0810	25/Fine	Surface	1.0	24.2	30.0	30.0	6.31	6.30	87.4	87.3	4.86	4.84	4.95	7.8	7.7	7.9			
						30.0		6.29		87.1		4.82			7.6					
			Middle	7.7	23.3	30.8	30.9	6.12	6.13	84.8	84.9	4.91	4.89		4.91	4.89		7.8	7.9	7.9
						30.9		6.13		84.9		4.87			8.0					
			Bottom	15.2	22.6	31.3	31.3	5.92	5.92	82.0	82.0	5.06	5.11		5.06	5.11		8.2	8.1	8.1
						31.3		5.91		81.9		5.15			8.0					
11/11/10	0953-1004	25/Fine	Surface	1.0	21.0	30.2	30.2	6.09	6.09	87.1	87.0	5.08	5.09	5.08	8.2	8.1	8.1			
						30.2		6.08		86.9		5.09			8.0					
			Middle	6.8	20.6	31.0	31.0	5.92	5.93	84.7	84.8	5.09	5.08		5.09	5.08		8.4	8.2	8.2
						31.0		5.93		84.8		5.07			8.0					
			Bottom	11.5	20.0	31.4	31.4	5.85	5.84	83.7	83.5	5.06	5.08		5.06	5.08		8.0	7.9	7.9
						31.4		5.82		83.2		5.09			7.8					
13/11/10	1220-1235	24/Fine	Surface	1.0	24.4	31.0	31.0	5.87	5.85	81.5	81.3	4.15	4.17	4.32	6.5	6.5	6.6			
						31.0		5.83		81.0		4.19			6.5					
			Middle	5.8	24.0	31.3	31.3	5.85	5.82	81.3	80.8	4.17	4.21		4.17	4.21		6.2	6.3	6.3
						31.3		5.78		80.3		4.24			6.4					
			Bottom	10.6	23.3	31.9	31.9	5.68	5.67	78.9	78.8	4.56	4.59		4.56	4.59		7.0	7.1	7.1
						31.9		5.66		78.6		4.62			7.2					
16/11/10	1531-1542	24/Fine	Surface	1.0	23.9	30.6	30.6	6.04	6.05	83.9	84.1	4.96	4.94	5.15	7.8	7.8	8.3			
						30.5		6.06		84.2		4.91			7.8					
			Middle	6.1	23.1	31.5	31.5	5.79	5.77	79.9	79.6	5.07	5.06		5.07	5.06		8.0	8.1	8.1
						31.4		5.75		79.3		5.04			8.1					
			Bottom	11.2	22.9	31.8	31.8	5.84	5.82	80.5	80.3	5.46	5.45		5.46	5.45		9.0	9.1	9.1
						31.8		5.80		80.0		5.44			9.2					
18/11/10	1614-1627	24/Sunny	Surface	1.0	24.2	30.7	30.8	5.83	5.86	81.0	81.4	5.44	5.47	6.13	9.2	8.7	9.1			
						30.9		5.89		81.9		5.49			8.6					
			Middle	5.7	24.1	30.9	30.9	5.88	5.85	81.7	81.3	5.62	5.62		5.62	5.62		9.2	9.1	9.1
						30.9		5.82		80.9		5.61			9.0					
			Bottom	10.4	23.5	31.4	31.5	5.68	5.69	78.9	79.0	5.84	7.32		5.84	7.32		9.4	9.6	9.6
						31.6		5.69		79.1		8.80			9.8					
20/11/10	1638-1650	22/Cloudy	Surface	1.0	23.6	31.1	31.1	5.96	5.95	82.8	82.7	5.07	5.04	5.14	8.2	8.1	8.3			
						31.1		5.94		82.5		5.01			8.0					
			Middle	5.9	23.0	31.7	31.8	5.76	5.75	79.4	79.2	5.14	5.11		5.14	5.11		8.4	8.5	8.5
						31.8		5.73		79.0		5.07			8.5					
			Bottom	10.8	22.9	32.1	32.1	5.82	5.84	80.8	81.1	5.31	5.29		5.31	5.29		8.2	8.3	8.3
						32.1		5.85		81.3		5.26			8.3					
23/11/10	0934-0949	23/Fine	Surface	1.0	24.4	31.1	31.1	5.98	5.92	83.1	82.3	5.08	5.11	5.27	8.1	8.1	8.3			
						31.1		5.86		81.4		5.14			8.0					
			Middle	5.9	23.8	31.6	31.6	5.70	5.72	79.2	79.5	5.23	5.26		5.23	5.26		8.4	8.3	8.3
						31.5		5.74		79.7		5.28			8.2					
			Bottom	10.8	23.2	32.2	32.2	5.68	5.66	78.8	78.9	5.41	5.44		5.41	5.44		8.8	8.7	8.7
						32.2		5.64		79.0		5.46			8.5					
25/11/10	0947-1000	20/Fine	Surface	1.0	23.4	30.5	30.5	5.99	5.98	83.3	83.1	5.19	5.17	5.08	8.2	8.1	8.1			
						30.4		5.96		82.8		5.15			8.0					
			Middle	6.3	22.6	31.2	31.3	5.76	5.77	80.1	80.2	5.09	5.08		5.09	5.08		8.4	8.3	8.3
						31.3		5.77		80.2		5.06			8.2					
			Bottom	11.6	22.4	32.0	32.0	5.95	5.94	82.7	82.5	4.99	4.98		4.99	4.98		8.0	8.0	8.0
						32.0		5.92		82.3		4.97			7.9					
27/11/10	1152-1205	21/Fine	Surface	1.0	22.5	30.4	30.4	5.94	5.95	82.6	82.7	5.12	5.14	5.21	8.2	8.3	8.3			
						30.3		5.96		82.8		5.15			8.4					
			Middle	6.1	22.3	31.1	31.2	5.94	5.93	82.6	82.4	5.15	5.17		5.15	5.17		8.3	8.2	8.2
						31.2		5.91		82.1		5.19			8.0					
			Bottom	11.2	21.5	32.1	32.1	5.85	5.84	81.3	81.2	5.30	5.32		5.30	5.32		8.5	8.4	8.4
						32.0		5.83		81.0		5.34			8.2					
30/11/10	1249-1302	22/Fine	Surface	1.0	23.6	30.3	30.4	6.03	6.03	83.8	83.8	5.38	5.34	5.36	8.5	8.5	8.5			
						30.4		6.03		83.8		5.30			8.4					
			Middle	6.2	22.5	31.4	31.4	5.94	5.96	82.6	82.9	5.24	5.25		5.24	5.25		8.0	8.1	8.1
						31.4		5.98		83.1		5.26			8.2					
			Bottom	11.4	22.1	32.1	32.2	5.80	5.82	80.6	80.8	5.48	5.49		5.48	5.49		9.0	8.8	8.8
						32.2		5.83		81.0		5.49			8.6					

Mid-Flood Tide

Monitoring Station : R29

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)				
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average		
02/11/10	1506-1519	20/Fine	Surface	1.0	22.8	30.2	30.2	6.02	6.03	84.3	84.4	4.92	4.93	5.07	7.8	7.9	7.9		
				8.6		21.9		30.2		6.03		84.4			4.93			8.0	
			Middle	8.6	21.9	30.9	30.9	5.87	5.88	82.2	82.3	5.10	5.11		5.10	5.11		8.0	7.8
				16.2		21.3		30.8		5.88		82.3			5.12			7.6	
			Bottom	16.2	21.3	30.8	30.8	5.86	5.87	87.9	85.1	5.14	5.16		5.14	5.16		8.2	8.1
				30.8		5.88		82.3		5.18		8.0							
04/11/10	1551-1602	22/Cloudy	Surface	1.0	19.8	30.9	30.9	6.06	6.16	87.0	88.4	5.02	5.03	5.26	8.0	8.1	8.5		
				8.0		19.5		30.9		6.26		89.7			5.04			8.1	
			Middle	8.0	19.5	31.1	31.1	6.11	6.13	87.7	87.8	5.62	5.53		5.62	5.53		9.2	9.1
				15.0		19.1		31.1		6.15		87.9			5.44			9.0	
			Bottom	15.0	19.1	31.9	31.9	6.00	5.95	85.7	85.9	5.26	5.23		5.26	5.23		8.2	8.2
				31.9		5.90		86.0		5.20		8.2							
06/11/10	1732-1742	20/Drizzle	Surface	1.0	19.7	29.0	29.0	6.22	6.23	90.2	90.3	6.12	6.12	6.04	8.6	8.7	9.0		
				8.0		19.1		29.0		6.24		90.4			6.12			8.8	
			Middle	8.0	19.1	29.1	29.1	6.18	6.15	89.1	89.0	6.16	6.08		6.16	6.08		9.0	9.2
				15.0		18.7		29.1		6.12		88.8			6.00			9.2	
			Bottom	15.0	18.7	29.9	29.9	5.99	5.98	85.5	85.3	5.92	5.92		5.92	5.92		9.2	9.2
				29.9		5.96		85.1		5.92		9.2							
09/11/10	0819-0832	25/Fine	Surface	1.0	24.1	30.1	30.1	6.27	6.28	86.8	86.9	5.02	5.07	5.07	8.2	8.1	8.0		
				8.5		23.2		30.1		6.28		87.0			5.11			8.0	
			Middle	8.5	23.2	30.7	30.8	6.10	6.12	84.5	84.7	5.15	5.12		5.15	5.12		8.0	8.1
				15.9		22.5		30.8		6.13		84.9			5.08			8.2	
			Bottom	15.9	22.5	31.3	31.3	5.90	5.89	81.7	81.6	5.03	5.02		5.03	5.02		7.8	7.9
				31.3		5.88		81.4		5.01		8.0							
11/11/10	1013-1027	25/Fine	Surface	1.0	20.9	30.2	30.2	6.11	6.13	87.3	87.6	5.14	5.14	5.12	8.2	8.1	8.1		
				7.4		20.5		30.1		6.14		87.8			5.13			8.0	
			Middle	7.4	20.5	30.8	30.8	5.94	5.95	84.9	85.0	5.02	5.04		5.02	5.04		7.8	7.9
				13.2		20.0		30.8		5.95		85.1			5.06			8.0	
			Bottom	13.2	20.0	31.2	31.2	5.81	5.81	83.1	83.0	5.17	5.18		5.17	5.18		8.4	8.2
				31.2		5.80		82.9		5.19		8.0							
13/11/10	1242-1258	24/Fine	Surface	1.0	24.4	31.0	31.0	5.78	5.78	80.4	80.4	4.38	4.40	4.70	6.8	6.9	7.6		
				8.8		23.7		31.0		5.77		80.3			4.42			7.0	
			Middle	8.8	23.7	31.3	31.4	5.69	5.70	79.1	79.3	4.66	4.68		4.66	4.68		7.5	7.8
				16.6		22.8		31.4		5.71		79.4			4.70			8.0	
			Bottom	16.6	22.8	32.0	32.1	5.66	5.67	78.5	78.7	4.98	5.01		4.98	5.01		8.0	8.2
				32.1		5.68		78.8		5.03		8.4							
16/11/10	1557-1607	24/Fine	Surface	1.0	23.8	30.7	30.7	5.98	6.00	83.1	83.4	5.06	5.04	5.06	8.0	7.8	8.0		
				8.9		23.0		30.6		6.02		83.6			5.01			7.5	
			Middle	8.9	23.0	31.5	31.5	5.64	5.66	77.8	78.0	4.98	4.95		4.98	4.95		7.6	7.8
				16.8		23.0		31.4		5.68		78.2			4.91			8.0	
			Bottom	16.8	23.0	31.8	31.8	5.68	5.67	78.3	78.1	5.15	5.19		5.15	5.19		8.2	8.3
				31.7		5.65		77.9		5.22		8.4							
18/11/10	1634-1648	24/Sunny	Surface	1.0	24.4	30.6	30.7	5.74	5.73	79.8	79.6	5.77	5.78	5.99	9.0	8.9	9.3		
				8.8		24.0		30.7		5.71		79.4			5.79			8.8	
			Middle	8.8	24.0	30.8	30.9	5.69	5.69	79.3	79.2	5.94	5.96		5.94	5.96		9.5	9.5
				16.6		22.7		31.0		5.68		79.1			5.98			9.4	
			Bottom	16.6	22.7	31.7	31.5	5.66	5.67	78.6	78.7	6.21	6.23		6.21	6.23		9.8	9.7
				31.2		5.67		78.8		6.24		9.5							
20/11/10	1705-1716	22/Cloudy	Surface	1.0	23.6	31.1	31.1	6.01	6.03	83.5	83.7	5.15	5.19	5.41	8.0	8.2	8.8		
				8.8		23.1		31.1		6.04		83.9			5.23			8.4	
			Middle	8.8	23.1	31.8	31.8	5.90	5.89	82.0	81.9	5.49	5.46		5.49	5.46		9.0	8.9
				16.6		23.0		31.7		5.88		81.7			5.42			8.8	
			Bottom	16.6	23.0	32.2	32.2	5.74	5.72	79.2	78.9	5.62	5.60		5.62	5.60		9.4	9.3
				32.1		5.70		78.6		5.57		9.2							
23/11/10	0954-1009	23/Fine	Surface	1.0	24.3	31.0	31.1	5.83	5.81	81.6	81.3	5.28	5.32	5.57	8.3	8.3	8.6		
				8.9		23.5		31.1		5.78		80.9			5.35			8.3	
			Middle	8.9	23.5	31.6	31.6	5.74	5.73	79.8	79.7	5.58	5.61		5.58	5.61		8.8	8.7
				16.8		23.0		31.6		5.71		79.5			5.63			8.6	
			Bottom	16.8	23.0	32.5	32.5	5.68	5.68	78.8	78.8	5.76	5.78		5.76	5.78		8.9	8.7
				32.5		5.68		78.8		5.80		8.5							
25/11/10	1004-1017	20/Fine	Surface	1.0	23.3	30.5	30.6	5.86	5.85	81.5	81.4	5.04	5.04	5.19	8.0	8.1	8.2		
				8.6		22.6		30.6		5.84		81.2			5.03			8.2	
			Middle	8.6	22.6	31.1	31.2	6.03	6.03	83.8	83.8	5.19	5.19		5.19	5.19		8.2	8.3
				16.2		22.5		31.2		6.02		83.7			5.18			8.4	
			Bottom	16.2	22.5	32.2	32.2	5.94	5.95	82.6	82.7	5.36	5.34		5.36	5.34		8.5	8.3
				32.1		5.96		82.8		5.32		8.0							
27/11/10	1208-1221	21/Fine	Surface	1.0	22.4	30.2	30.3	5.95	5.94	82.7	82.5	5.27	5.24	5.26	8.4	8.5	8.5		
				8.9		22.2		30.3		5.92		82.2			5.21			8.5	
			Middle	8.9	22.2	30.9	31.0	5.86	5.84	81.5	81.2	5.30	5.31		5.30	5.31		8.8	8.7
				16.8		21.3		31.0		5.82		80.9			5.32			8.5	
			Bottom	16.8	21.3	32.0	32.0	5.88	5.89	81.7	81.8	5.24	5.24		5.24	5.24		8.4	8.3
				32.0		5.89		81.9		5.23		8.2							
30/11/10	1305-1318	22/Fine	Surface	1.0	23.7	30.3	30.3	6.07	6.05	84.4	84.1	5.37	5.34	5.43	8.5	8.5	8.8		
				8.9		22.5		30.2		6.02		83.7			5.31			8.5	
			Middle	8.9	22.5	31.3	31.3	5.86	5.88	81.5	81.7	5.41	5.43		5.41	5.43		8.9	8.8
				16.8		22.3		31.2		5.89		81.9			5.44			8.6	
			Bottom	16.8	22.3	32.0	32.0	5.97	5.95	82.9	82.7	5.56	5.53		5.56	5.53		9.0	9.1
				31.9		5.93		82.4		5.50		9.2							

Mid-Flood Tide

Monitoring Station : C1

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)		Suspended Solids (mg/L)					
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average		
02/11/10	1352-1405	20/Fine	Surface	1.0	22.8	30.6	30.6	6.02	6.02	84.3	84.3	4.87	4.88	4.96	7.8	7.8	7.9		
						30.5		6.02		84.3		4.88			7.8				
			Middle	7.5	20.9	31.3	31.4	5.92	5.93	83.0	83.1	4.92	4.93		4.93	8.0		7.9	7.9
						31.4		5.93		83.2		4.93			7.8				
			Bottom	14.0	20.1	31.2	31.3	5.89	5.90	82.5	82.6	5.07	5.08		5.08	8.2		8.1	8.1
						31.4		5.90		82.6		5.08			8.0				
04/11/10	1435-1446	22/Cloudy	Surface	1.0	19.7	31.2	31.3	6.30	6.31	89.9	90.1	4.04	4.18	4.04	6.4	6.5	6.5		
						31.4		6.31		90.3		4.32			6.6				
			Middle	8.3	19.2	31.6	31.6	6.21	6.21	89.1	89.1	4.01	3.92		3.97	6.8		6.7	6.7
						31.6		6.21		89.1		3.92			6.6				
			Bottom	15.6	19.0	32.2	32.3	6.01	6.03	85.7	85.8	3.99	3.97		3.97	6.2		6.4	6.4
						32.4		6.05		85.9		3.95			6.5				
06/11/10	1610-1624	20/Drizzle	Surface	1.0	19.4	29.5	29.5	6.29	6.30	91.0	91.1	5.90	5.90	5.84	9.4	9.4	9.1		
						29.5		6.30		91.1		5.90			9.4				
			Middle	8.4	19.1	29.9	29.9	6.15	6.15	89.1	89.1	5.99	5.99		5.90	9.0		9.1	9.1
						29.9		6.15		89.1		5.80			9.2				
			Bottom	15.8	18.4	30.5	30.8	6.11	6.11	88.1	88.1	5.77	5.74		5.74	8.6		8.8	8.8
						31.0		6.11		88.1		5.70			9.0				
09/11/10	1032-1047	25/Fine	Surface	1.0	24.2	30.0	30.0	6.30	6.32	89.4	89.7	4.02	4.06	4.49	6.4	6.4	7.2		
						30.0		6.34		90.0		4.10			6.4				
			Middle	6.7	23.4	30.5	30.5	6.10	6.13	86.6	87.0	4.74	4.72		4.72	7.5		7.7	7.7
						30.5		6.15		87.3		4.69			7.8				
			Bottom	12.4	22.6	31.1	31.2	5.96	5.95	84.6	84.4	4.64	4.69		4.69	7.5		7.5	7.5
						31.2		5.93		84.2		4.74			7.5				
11/11/10	1220-1232	25/Fine	Surface	1.0	20.9	30.1	30.1	6.10	6.14	87.2	87.7	4.52	4.56	4.55	7.5	7.7	7.6		
						30.1		6.17		88.2		4.59			7.8				
			Middle	8.2	20.2	30.9	30.9	5.95	5.96	85.1	85.2	4.49	4.48		4.48	7.4		7.5	7.5
						30.9		5.96		85.2		4.47			7.5				
			Bottom	15.6	19.9	31.3	31.3	5.82	5.81	83.2	83.1	4.62	4.61		4.61	7.8		7.8	7.8
						31.3		5.80		82.9		4.60			7.7				
13/11/10	1130-1145	24/Fine	Surface	1.0	24.3	30.9	30.9	5.82	5.84	80.8	81.1	4.04	4.08	4.34	6.6	6.8	7.1		
						30.9		5.86		81.4		4.12			7.0				
			Middle	7.3	23.8	31.3	31.4	5.77	5.78	80.3	80.4	4.31	4.35		4.35	6.8		6.9	6.9
						31.4		5.78		80.4		4.38			7.0				
			Bottom	13.6	23.0	31.9	32.0	5.68	5.68	78.8	78.9	4.57	4.61		4.61	7.4		7.5	7.5
						32.0		5.67		78.9		4.64			7.5				
16/11/10	1430-1442	24/Fine	Surface	1.0	23.8	30.6	30.6	6.01	6.04	83.5	83.9	5.15	5.17	5.13	8.0	8.2	8.2		
						30.6		6.06		84.2		5.19			8.3				
			Middle	7.4	22.9	31.4	31.4	5.93	5.91	82.4	82.1	5.09	5.06		5.06	8.2		8.1	8.1
						31.4		5.89		81.8		5.02			8.0				
			Bottom	13.8	22.9	31.8	31.8	5.85	5.87	81.3	81.5	5.19	5.17		5.17	8.4		8.5	8.5
						31.8		5.88		81.7		5.15			8.5				
18/11/10	1453-1512	24/Sunny	Surface	1.0	24.4	30.7	30.8	5.97	5.96	83.0	82.8	5.35	5.35	5.60	8.4	8.4	8.7		
						30.8		5.94		82.6		5.34			8.4				
			Middle	6.7	23.7	31.0	31.1	5.84	5.85	81.2	81.3	5.56	5.59		5.59	8.8		8.9	8.9
						31.2		5.85		81.3		5.62			9.0				
			Bottom	12.4	23.2	31.7	31.7	5.67	5.68	78.8	78.9	5.87	5.87		5.87	8.6		8.7	8.7
						31.6		5.68		79.0		5.86			8.8				
20/11/10	1529-1540	22/Cloudy	Surface	1.0	23.5	31.0	31.0	6.04	6.06	83.9	84.2	4.87	4.91	4.88	7.9	7.9	7.9		
						31.0		6.08		84.5		4.94			7.8				
			Middle	7.4	22.9	31.6	31.6	5.83	5.81	81.0	80.7	4.74	4.79		4.79	7.5		7.7	7.7
						31.6		5.79		80.4		4.83			7.8				
			Bottom	13.8	22.9	31.9	31.9	5.77	5.76	79.6	79.4	4.97	4.95		4.95	8.0		8.1	8.1
						31.8		5.74		79.2		4.92			8.2				
23/11/10	0832-0846	22/Fine	Surface	1.0	24.3	31.0	31.0	5.89	5.86	81.8	81.3	4.93	4.96	5.23	7.8	7.8	8.2		
						31.0		5.82		80.8		4.99			7.8				
			Middle	7.3	23.6	31.6	31.6	5.70	5.72	79.2	79.5	5.21	5.24		5.24	8.0		8.1	8.1
						31.5		5.74		79.7		5.27			8.2				
			Bottom	13.6	23.0	32.3	32.3	5.66	5.66	78.8	78.8	5.51	5.49		5.49	8.6		8.6	8.6
						32.3		5.65		78.7		5.46			8.5				
25/11/10	0844-0857	19/Fine	Surface	1.0	23.8	30.7	30.8	5.94	5.93	82.6	82.4	5.06	5.05	5.16	8.0	8.0	8.2		
						30.8		5.91		82.1		5.03			8.0				
			Middle	7.7	22.5	31.4	31.5	5.81	5.82	80.8	80.9	5.26	5.27		5.27	8.4		8.3	8.3
						31.5		5.83		81.0		5.27			8.2				
			Bottom	14.4	22.2	32.2	32.2	5.95	5.96	82.7	82.8	5.19	5.16		5.16	8.1		8.2	8.2
						32.1		5.96		82.8		5.13			8.3				
27/11/10	1039-1052	20/Fine	Surface	1.0	22.7	30.2	30.3	5.99	6.01	83.3	83.5	5.10	5.11	5.19	8.0	8.0	8.2		
						30.3		6.02		83.7		5.12			8.0				
			Middle	7.7	22.3	30.7	30.8	5.98	5.98	83.1	83.1	5.26	5.25		5.25	8.4		8.3	8.3
						30.8		5.97		83.0		5.24			8.2				
			Bottom	14.4	21.4	32.1	32.1	5.88	5.87	81.7	81.5	5.20	5.22		5.22	8.5		8.4	8.4
						32.0		5.85		81.3		5.23			8.2				
30/11/10	1136-1149	21/Fine	Surface	1.0	23.5	30.4	30.5	5.96	5.98	82.8	83.1	5.36	5.35	5.42	8.0	8.1	8.6		
						30.5		5.99		83.3		5.33			8.2				
			Middle	7.7	22.4	31.4	31.4	5.83	5.82	81.1	81.0	5.43	5.42		5.42	8.7		8.6	8.6
						31.4		5.81		80.8		5.41			8.5				
			Bottom	14.4	22.0	32.2	32.2	5.79	5.79	80.5	80.4	5.49	5.49		5.49	8.9		9.0	9.0
						32.1		5.78		80.3		5.48			9.0				

Mid-Flood Tide



Monitoring Station : C3

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/11/10	1418-1428	20/Fine	Surface	1.0	22.7	30.6	30.6	6.03	6.03	84.4	84.4	4.86	4.86	4.94	7.8	7.7	7.9
				6.5		20.8		31.4		31.4		5.90			5.91		
			Middle	6.5	20.8	31.4	31.4	5.91	5.91	82.7	82.7	4.91	4.91		7.8		
				12.0		20.0		31.4		31.4		5.89			5.89		
			Bottom	12.0	20.0	31.4	31.4	5.89	5.89	82.5	82.5	5.06	5.06		8.0		
				12.0		20.0		31.4		31.4		5.89			5.89		
04/11/10	1456-1507	22/Cloudy	Surface	1.0	19.7	32.0	32.0	6.30	6.31	90.3	90.4	4.00	4.00	4.04	6.4	6.4	6.4
				8.4		19.3		31.0		31.1		6.15			6.17		
			Middle	8.4	19.3	31.2	31.1	6.18	6.17	87.7	87.6	4.11	4.11		6.4		
				15.8		19.1		31.4		31.4		6.11			6.13		
			Bottom	15.8	19.1	31.4	31.4	6.14	6.13	86.4	86.2	4.01	4.01		6.4		
				15.8		19.1		31.4		31.4		6.11			6.13		
06/11/10	1635-1647	20/Drizzle	Surface	1.0	19.4	29.5	29.5	6.40	6.42	91.9	91.9	5.76	5.76	5.66	9.0	9.1	8.9
				8.0		19.1		29.5		29.7		6.21			6.21		
			Middle	8.0	19.1	29.9	29.7	6.21	6.21	89.9	90.0	5.79	5.79		8.8		
				15.0		18.4		31.0		31.0		6.10			6.13		
			Bottom	15.0	18.4	31.0	31.0	6.15	6.13	88.9	88.5	5.40	5.40		8.6		
				15.0		18.4		31.0		31.0		6.15			6.13		
09/11/10	1056-1109	25/Fine	Surface	1.0	24.1	30.1	30.1	6.20	6.22	88.0	88.3	4.72	4.72	4.98	7.8	7.7	8.1
				7.4		23.3		30.6		30.6		6.03			6.02		
			Middle	7.4	23.3	30.6	30.6	6.01	6.02	85.3	85.5	5.09	5.09		8.0		
				13.8		22.6		31.2		31.2		5.97			5.91		
			Bottom	13.8	22.6	31.2	31.2	5.84	5.91	83.7	83.9	5.22	5.22		8.4		
				13.8		22.6		31.2		31.2		5.84			5.91		
11/11/10	1239-1252	25/Fine	Surface	1.0	21.0	30.0	30.1	6.00	6.02	85.8	86.1	4.76	4.76	4.67	7.6	7.6	7.6
				8.6		20.2		30.9		30.9		5.98			5.97		
			Middle	8.6	20.2	30.8	30.9	5.95	5.97	85.1	85.3	4.56	4.56		7.4		
				16.2		19.7		31.4		31.4		5.78			5.80		
			Bottom	16.2	19.7	31.4	31.4	5.82	5.80	83.2	83.0	4.72	4.72		8.0		
				16.2		19.7		31.4		31.4		5.82			5.80		
13/11/10	1137-1153	24/Fine	Surface	1.0	24.4	30.9	31.0	5.88	5.86	81.7	81.4	4.00	4.00	4.24	6.6	6.7	6.7
				6.7		23.8		31.0		31.0		5.84			5.86		
			Middle	6.7	23.8	31.4	31.4	5.73	5.75	79.6	79.9	4.18	4.18		6.4		
				12.4		23.1		31.4		31.4		5.76			5.75		
			Bottom	12.4	23.1	32.0	32.0	5.67	5.68	78.9	79.0	4.44	4.44		7.0		
				12.4		23.1		32.0		32.0		5.69			5.68		
16/11/10	1445-1457	24/Fine	Surface	1.0	23.8	30.5	30.5	6.04	6.06	83.9	84.2	5.04	5.04	5.21	8.0	8.0	8.3
				6.8		22.9		30.4		30.5		6.08			6.06		
			Middle	6.8	22.9	31.5	31.5	5.88	5.87	81.7	81.5	5.20	5.20		8.5		
				12.6		22.8		31.4		31.9		5.85			5.87		
			Bottom	12.6	22.8	31.8	31.9	5.75	5.77	79.3	79.6	5.37	5.37		8.6		
				12.6		22.8		31.9		31.9		5.79			5.77		
18/11/10	1523-1535	24/Sunny	Surface	1.0	24.1	30.4	30.5	5.86	5.85	81.5	81.4	5.43	5.43	5.68	8.9	9.0	9.3
				6.6		24.2		30.6		30.5		5.84			5.85		
			Middle	6.6	24.2	30.8	30.9	5.81	5.79	80.8	80.5	5.77	5.77		9.4		
				12.2		23.7		30.9		30.9		5.77			5.79		
			Bottom	12.2	23.7	31.4	31.4	5.67	5.68	78.8	79.0	5.86	5.86		9.6		
				12.2		23.7		31.4		31.4		5.69			5.68		
20/11/10	1553-1604	22/Cloudy	Surface	1.0	23.4	31.0	31.1	6.08	6.07	84.5	84.3	5.03	5.03	5.04	8.0	8.1	8.1
				6.7		22.9		31.1		31.1		6.05			6.05		
			Middle	6.7	22.9	31.7	31.7	5.95	5.93	82.7	82.4	4.89	4.89		7.8		
				12.4		23.0		31.7		31.7		5.91			5.93		
			Bottom	12.4	23.0	32.0	32.0	5.87	5.86	81.5	81.3	5.18	5.18		8.4		
				12.4		23.0		32.0		32.0		5.84			5.86		
23/11/10	0853-0908	22/Fine	Surface	1.0	24.2	31.1	31.1	5.98	5.93	83.1	82.3	4.96	4.96	5.24	8.2	8.2	8.5
				6.9		23.6		31.1		31.1		5.87			5.93		
			Middle	6.9	23.6	31.5	31.5	5.71	5.74	79.3	79.7	5.23	5.23		8.4		
				12.8		23.1		31.5		31.5		5.76			5.74		
			Bottom	12.8	23.1	32.3	32.3	5.67	5.66	78.7	78.6	5.46	5.46		8.9		
				12.8		23.1		32.3		32.3		5.65			5.66		
25/11/10	0909-0912	19/Fine	Surface	1.0	23.8	30.7	30.7	6.06	6.07	84.2	84.4	4.99	4.99	5.15	8.0	8.0	8.2
				6.7		22.7		30.6		30.7		6.08			6.07		
			Middle	6.7	22.7	31.4	31.4	5.89	5.91	81.3	81.9	5.13	5.13		8.2		
				12.4		22.3		31.3		31.4		5.93			5.91		
			Bottom	12.4	22.3	32.1	32.1	5.82	5.82	80.9	80.9	5.33	5.33		8.4		
				12.4		22.3		32.0		32.1		5.81			5.82		
27/11/10	1104-1117	20/Fine	Surface	1.0	22.7	30.4	30.4	6.02	6.03	83.7	83.8	5.26	5.26	5.24	8.0	8.1	8.4
				7.0		22.2		30.3		30.4		6.03			6.03		
			Middle	7.0	22.2	30.7	30.7	5.99	5.96	83.3	82.9	5.12	5.12		8.8		
				13.0		21.5		30.6		30.7		5.93			5.96		
			Bottom	13.0	21.5	31.8	31.8	5.90	5.91	82.0	82.1	5.36	5.36		8.6		
				13.0		21.5		31.7		31.8		5.91			5.91		
30/11/10	1201-1214	21/Fine	Surface	1.0	23.4	30.3	30.4	6.06	6.07	84.2	84.3	5.30	5.30	5.50	8.5	8.3	9.0
				6.9		22.5		30.4		30.4		6.07			6.07		
			Middle	6.9	22.5	31.3	31.3	6.09	6.09	84.7	84.6	5.46	5.46		9.4		
				12.8		21.9		31.2		31.3		6.08			6.09		
			Bottom	12.8	21.9	32.1	32.1	5.84	5.82	81.2	80.9	5.71	5.71		9.5		
				12.8		21.9		32.0		32.1		5.80			5.82		

Mid-Ebb Tide

Monitoring Station : C2

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/11/10	1132-1145	20/Fine	Surface	1.0	22.2	30.2	30.2	6.06	6.04	84.8	84.5	4.79	4.78	4.86	7.5	7.6	7.7
						30.1		6.01		84.1		4.77			7.6		
			Middle	7.3	20.7	30.6	30.7	5.86	5.85	82.0	81.9	4.86	4.88		7.8	7.7	
30.7	5.84	81.8				4.89		7.6									
			Bottom	13.6	22.0	31.3	31.3	5.71	5.73	79.9	80.1	4.91	4.94		8.0	7.9	
						31.2		5.74		80.3		4.96			7.8		
			30.9	31.0	5.88	5.86	81.7	81.4	5.77	5.80	8.8						
31.0	5.83	81.0	5.83		8.5												
04/11/10	1215-1230	21/Cloudy	Surface	1.0	24.3	31.5	31.5	5.75	5.73	79.9	79.6	5.96	6.03	5.99	9.0	8.8	8.9
						31.4		5.70		79.2		6.09			8.6		
			Middle	7.4	23.7	31.8	31.9	5.60	5.62	77.8	78.0	6.13	6.16		9.2	9.3	
31.9	5.63	78.2				6.18		9.4									
			Bottom	13.8	23.1	31.8	31.9	5.60	5.62	77.8	78.0	6.13	6.16		8.2	8.1	
						31.6		5.88		82.3		4.99			8.0		
			31.2	31.2	6.05	6.04	84.7	84.5	4.96	4.96	7.5						
29.4	6.02	84.3	4.95		7.8												
06/11/10	1322-1335	19/Rainy	Surface	1.0	20.3	29.3	29.4	6.05	6.04	84.7	84.5	4.96	4.96	4.92	7.5	7.7	7.9
						29.4		6.02		84.3		4.95			7.8		
			Middle	7.5	21.4	30.1	30.1	5.93	5.95	83.0	83.2	4.82	4.83		8.0	7.8	
30.0	5.96	83.4				4.83		7.6									
			Bottom	14.0	22.6	31.5	31.6	5.87	5.88	82.2	82.3	4.99	4.99		8.2	8.1	
						31.6		5.88		82.3		4.99			8.0		
			31.2	31.2	6.02	6.04	83.6	83.8	5.19	5.15	8.5						
31.2	6.05	84.0	5.11		8.6												
09/11/10	1707-1717	20/Fine	Surface	1.0	24.0	32.1	32.1	5.67	5.66	78.2	78.0	5.43	5.46	5.33	9.0	8.9	8.7
						32.1		5.64		77.8		5.48			8.8		
			Middle	8.1	23.2	32.4	32.4	5.54	5.52	76.4	76.2	5.36	5.39		8.4	8.5	
32.4	5.50	75.9				5.41		8.6									
			Bottom	8.1	22.9	31.9	31.9	6.11	6.13	87.8	87.8	5.02	5.02		8.0	8.0	
						31.9		6.14		87.7		5.02			8.0		
			32.1	32.1	6.02	6.02	85.9	86.0	5.10	5.11	8.2						
32.1	6.01	86.0	5.11		8.0												
11/11/10	1912-1922	25/Fine	Surface	1.0	21.2	31.9	31.9	6.11	6.13	87.8	87.8	5.02	5.02	5.04	8.0	8.0	8.0
						31.9		6.14		87.7		5.02			8.0		
			Middle	7.9	21.0	32.1	32.1	6.02	6.02	85.9	86.0	5.10	5.11		8.2	8.1	
32.1	6.01	86.0				5.11		8.0									
			Bottom	14.8	20.7	32.9	32.9	5.96	5.94	85.2	85.2	5.02	4.98		8.0	7.9	
						32.9		5.92		85.2		4.94			7.8		
			30.5	30.6	5.96	5.98	82.8	83.1	5.01	5.02	7.8						
30.6	5.99	83.3	5.03		7.8												
13/11/10	0918-0931	21/Fine	Surface	1.0	21.3	30.5	30.6	5.96	5.98	82.8	83.1	5.01	5.02	5.12	7.8	7.8	8.0
						30.6		5.99		83.3		5.03			7.8		
			Middle	7.3	20.4	30.8	30.6	5.87	5.88	81.6	81.8	5.12	5.12		8.0	7.9	
30.4	5.89	81.9				5.11		7.8									
			Bottom	13.6	20.2	31.9	32.0	5.71	5.72	79.4	79.5	5.23	5.22		8.2	8.3	
						32.0		5.73		79.6		5.21			8.3		
			30.2	30.1	6.04	6.03	84.0	83.6	4.92	4.90	7.5						
29.9	6.02	83.1	4.88		7.9												
16/11/10	1251-1316	23.1/Sunny	Surface	1.0	21.8	30.2	30.1	6.04	6.03	84.0	83.6	4.92	4.86	4.89	8.0	8.1	8.0
						29.9		6.02		83.1		4.88			7.9		
			Middle	7.7	22.3	30.4	30.3	5.94	5.95	82.6	82.7	4.87	4.84		8.0	8.1	
30.2	5.96	82.8				4.84		8.1									
			Bottom	14.2	21.1	31.1	31.0	5.88	5.85	81.7	81.0	4.90	4.92		8.0	8.2	
						30.8		5.82		80.3		4.94			8.4		
			30.8	30.9	5.91	5.89	82.1	81.8	5.41	5.37	9.0						
30.9	5.87	81.5	5.33		9.0												
18/11/10	1210-1225	23/Fine	Surface	1.0	24.4	31.3	30.9	5.78	5.78	80.3	80.0	5.58	5.61	5.63	9.2	9.0	9.2
						31.3		5.74		79.7		5.64			8.8		
			Middle	7.3	23.7	31.9	31.9	5.70	5.68	79.2	78.9	5.87	5.90		9.4	9.5	
31.9	5.66	78.6				5.93		9.5									
			Bottom	13.6	23.2	30.4	30.5	6.00	5.99	83.4	83.2	5.00	5.02		7.8	8.1	8.3
						30.5		5.97		83.0		5.04			8.4		
			30.9	31.0	5.97	5.96	83.0	82.8	5.10	5.11	8.4						
31.0	5.94	82.6	5.12		8.2												
20/11/10	1313-1327	23/Sunny	Surface	1.0	22.9	30.4	30.5	6.00	5.99	83.4	83.2	5.00	5.02	5.12	7.8	8.1	8.3
						30.5		5.97		83.0		5.10			8.4		
			Middle	7.7	22.5	30.9	31.0	5.97	5.96	83.0	82.8	5.10	5.11		8.4	8.3	
31.0	5.94	82.6				5.12		8.2									
			Bottom	15.3	21.8	31.1	31.1	5.82	5.83	80.9	81.1	5.21	5.22		8.6	8.6	
						31.1		5.84		81.2		5.22			8.5		
			30.4	30.6	5.92	5.90	82.3	82.0	5.43	5.44	8.5						
30.7	5.87	81.6	5.45		8.8												
23/11/10	1705-1716	24/Fine	Surface	1.0	24.1	31.2	31.3	5.72	5.73	79.5	79.7	5.60	5.61	5.64	9.0	8.9	8.9
						31.2		5.74		79.7		5.64			8.7		
			Middle	6.8	23.9	31.4	31.3	5.74	5.73	79.8	79.7	5.62	5.61		8.7	9.1	
31.4	5.74	79.8				5.62		8.7									
			Bottom	13.5	23.7	31.7	31.8	5.70	5.68	79.2	79.0	5.84	5.87		9.1	9.1	
						31.8		5.66		78.7		5.90			9.0		
			30.7	30.8	5.91	5.90	82.1	82.0	5.42	5.41	9.0						
30.8	5.89	81.9	5.39		8.6												
25/11/10	1630-1640	24/Fine	Surface	1.0	24.1	31.2	31.3	5.77	5.76	80.2	79.5	5.57	5.59	5.63	9.0	9.1	9.0
						31.4		5.74		78.8		5.60			9.2		
			Middle	6.8	24.1	31.9	31.8	5.70	5.69	79.2	79.1	5.89	5.90		9.4	9.2	
31.7	5.68	79.0				5.90		9.0									
			Bottom	13.5	23.7	31.7	31.8	5.68	5.69	79.0	79.1	5.90	5.90		9.0	9.2	
						31.7		5.68		79.0		5.90			9.0		
			30.9	31.0	5.83	5.81	81.0	80.7	5.57	5.59	9.0						
31.0	5.78	80.3	5.61		9.4												
27/11/10	1915-1930	23/Fine	Surface	1.0	24.2	30.9	31.0	5.83	5.81	81.0	80.7	5.57	5.59	5.84	9.0	9.2	9.5
						31.0		5.78		80.3		5.61			9.4		
			Middle	7.3	23.6	31.7	31.7	5.71	5.71	79.4	79.4	5.86	5.88		9.5	9.5	
31.7	5.71	79.4				5.89		9.5									
			Bottom	13.6	23.0	32.1	32.1	5.67	5.67	78.8	78.8	6.01	6.05		9.8	9.7	
						32.1		5.66		78.7		6.08			9.5		
			30.6	30.6	5.88	5.89	81.7	81.9	5.41	5.41	9.0						
30.5	5.90	82.0	5.40		8.6												
30/11/10	2124-2132	23/Fine	Surface	1.0	23.4	30.6	30.6	5.88	5.89	81.7	81.9	5.41	5.41	5.61	9.0	8.8	9.0
						30.5		5.90		82.0		5.40			8.6		
			Middle	6.9	22.8	30.9	30.9	5.74	5.75	79.8	79.9	5.58	5.59		9.0	9.1	
30.9	5.75	79.9				5.60		9.2									
			Bottom	13.7	22.5	31.1	31.3	5.67	5.67	78.9	78.8	5.80	5.85		9.4	9.2	
						31.4		5.67		78.7		5.89			9.0		

Monitoring Station : C4

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)		Suspended Solids (mg/L)			
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/11/10	1113-1124	20/Fine	Surface	1.0	22.0	30.4	30.4	6.15	6.14	86.1	86.0	5.07	5.06	5.10	8.0	8.1	8.2
						30.3		6.13		85.8		5.04			8.2		
			Middle	8.0	20.8	30.8	30.8	5.99	5.98	83.9	83.7	5.08	5.12	8.2	8.3		
						30.8		5.96		83.4		5.12		8.4			
			Bottom	15.0	22.1	31.4	31.5	5.83	5.85	81.6	81.8	5.14	5.16	8.2	8.1		
						31.5		5.86		82.0		5.16		8.0			
04/11/10	1152-1207	21/Cloudy	Surface	1.0	24.4	31.0	31.0	5.90	5.88	82.0	81.7	5.71	5.74	5.92	8.5	8.5	8.7
						31.0		5.86		81.4		5.76			8.5		
			Middle	7.9	23.8	31.3	31.3	5.78	5.76	80.3	80.0	5.93	5.89	8.8	8.7		
						31.3		5.73		79.6		5.91		8.5			
			Bottom	14.8	23.1	31.9	31.9	5.58	5.56	77.5	77.3	6.07	6.14	9.0	8.9		
						31.9		5.54		77.0		6.11		8.8			
06/11/10	1300-1313	19/Rainy	Surface	1.0	20.5	29.2	29.3	6.18	6.17	86.5	86.3	4.91	4.92	5.03	7.6	7.6	7.8
						29.3		6.15		86.1		4.93			7.6		
			Middle	8.1	21.5	30.0	30.1	6.03	6.04	84.4	84.6	5.06	5.02	7.8	7.7		
						30.1		6.05		84.7		5.04		7.6			
			Bottom	15.2	22.7	31.3	31.4	5.99	5.98	83.9	83.8	5.13	5.11	8.0	8.0		
						31.4		5.97		83.6		5.12		8.0			
09/11/10	1649-1659	20/Fine	Surface	1.0	24.0	31.2	31.2	5.98	5.97	83.1	82.9	5.06	5.10	5.00	7.8	7.9	7.8
						31.2		5.95		82.7		5.14			8.0		
			Middle	8.1	23.3	32.0	32.1	5.80	5.79	80.0	79.8	4.89	4.82	7.8	8.0		
						32.1		5.77		79.6		5.05		8.2			
			Bottom	8.1	23.0	32.4	32.4	5.72	5.74	78.9	79.1	5.01	5.09	7.6	7.6		
						32.3		5.75		79.3		5.05		7.5			
11/11/10	1850-1902	25/Fine	Surface	1.0	21.2	32.0	32.0	6.20	6.16	88.9	88.4	5.11	5.13	5.10	8.2	8.1	8.1
						32.0		6.12		87.9		5.14			8.0		
			Middle	7.9	21.1	32.3	32.3	6.00	6.00	86.0	85.9	5.13	5.12	8.4	8.2		
						32.3		6.00		85.7		5.10		8.0			
			Bottom	17.8	20.8	32.4	32.4	5.92	5.91	85.1	85.1	5.10	5.00	8.2	8.1		
						32.4		5.90		85.1		5.00		8.0			
13/11/10	0857-0910	21/Fine	Surface	1.0	21.4	30.6	30.6	6.07	6.08	84.4	84.6	5.06	5.07	5.12	8.0	8.1	8.3
						30.5		6.09		84.7		5.08			8.2		
			Middle	7.9	20.3	30.9	30.9	5.97	5.96	83.0	82.9	5.13	5.12	8.6	8.6		
						30.8		5.95		82.7		5.10		8.5			
			Bottom	14.8	20.1	31.9	31.9	5.86	5.85	81.5	81.3	5.14	5.17	8.2	8.4		
						31.8		5.83		81.0		5.11		8.5			
16/11/10	1220-1234	23.1/Sunny	Surface	1.0	22.3	29.9	30.2	6.12	6.14	85.1	85.3	4.94	4.93	5.04	7.7	7.9	7.9
						30.4		6.15		85.5		4.92			8.0		
			Middle	8.7	21.3	30.1	30.3	6.04	6.06	83.4	83.9	5.07	5.04	7.9	7.9		
						30.4		6.07		84.4		5.06		7.8			
			Bottom	15.4	20.9	30.9	31.0	5.98	5.97	83.1	83.0	5.13	5.14	8.0	8.0		
						31.1		5.96		82.8		5.14		8.0			
18/11/10	1152-1206	23/Fine	Surface	1.0	24.3	30.9	30.9	5.93	5.92	82.4	82.2	5.38	5.41	5.63	8.0	8.1	8.7
						30.9		5.90		82.0		5.43			8.2		
			Middle	7.9	23.7	31.2	31.3	5.79	5.78	80.4	80.3	5.62	5.68	8.8	8.9		
						31.3		5.77		80.2		5.65		9.0			
			Bottom	14.8	23.2	31.9	31.9	5.68	5.71	78.9	79.3	5.79	5.85	9.2	9.1		
						31.9		5.73		79.6		5.82		9.0			
20/11/10	1252-1304	23/Sunny	Surface	1.0	23.2	30.4	30.6	6.00	6.01	83.4	83.5	5.04	5.02	5.12	8.1	8.1	8.3
						30.8		6.01		83.5		5.00			8.0		
			Middle	7.5	22.5	30.9	31.0	5.98	5.99	83.1	83.2	5.14	5.12	8.4	8.5		
						31.0		5.99		83.3		5.13		8.5			
			Bottom	15.0	22.0	31.2	31.2	5.84	5.85	81.2	81.4	5.20	5.21	8.5	8.5		
						31.2		5.86		81.5		5.21		8.5			
23/11/10	1645-1657	24/Fine	Surface	1.0	24.4	30.7	30.8	5.92	5.93	82.3	82.5	5.40	5.39	5.62	8.5	8.4	8.7
						30.9		5.94		82.6		5.37			8.3		
			Middle	7.4	23.8	31.1	31.2	5.80	5.79	80.6	80.5	5.62	5.68	9.0	8.9		
						31.3		5.78		80.3		5.65		8.8			
			Bottom	14.7	23.2	31.9	31.8	5.74	5.72	79.8	79.5	5.79	5.87	8.9	8.7		
						31.7		5.70		79.2		5.83		8.5			
25/11/10	1611-1622	24/Fine	Surface	1.0	24.2	30.8	30.8	5.92	5.91	82.3	82.2	5.37	5.40	5.61	8.2	8.2	8.7
						30.8		5.90		82.0		5.43			8.2		
			Middle	7.4	23.9	31.1	31.2	5.79	5.79	80.5	80.4	5.61	5.65	8.8	8.7		
						31.2		5.78		80.3		5.63		8.5			
			Bottom	14.7	23.6	31.9	31.9	5.67	5.69	78.8	79.1	5.77	5.84	9.0	9.1		
						31.8		5.71		79.4		5.81		9.2			
27/11/10	1857-1908	23/Fine	Surface	1.0	24.1	30.9	30.9	5.79	5.77	80.4	80.1	5.51	5.53	5.80	9.0	9.1	9.2
						30.9		5.74		79.7		5.55			9.2		
			Middle	7.9	23.5	31.6	31.7	5.68	5.68	78.9	78.9	5.81	5.88	9.5	9.5		
						31.7		5.68		78.9		5.85		9.4			
			Bottom	14.8	23.0	32.1	32.2	5.66	5.67	78.6	78.7	5.98	6.05	9.0	9.0		
						32.2		5.67		78.8		6.02		9.0			
30/11/10	2108-2119	23/Fine	Surface	1.0	23.1	30.7	30.8	5.87	5.89	81.6	81.8	5.44	5.45	5.61	8.2	8.2	8.7
						30.9		5.90		82.0		5.45			8.2		
			Middle	7.6	22.9	30.9	31.0	5.79	5.77	80.5	80.2	5.62	5.67	8.8	8.7		
						31.0		5.74		79.8		5.65		8.5			
			Bottom	15.1	22.7	31.4	31.5	5.67	5.66	78.9	78.7	5.72	5.74	9.0	9.2		
						31.6		5.65		78.5		5.73		9.3			

Mid-Ebb Tide

Monitoring Station : R5

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/11/10	0916-0929	20/Fine	Surface	1.0	22.1	30.1	30.2	6.08	6.07	85.1	85.0	4.92	4.91	5.06	8.0	7.9	8.1
				8.2	20.5	30.2		6.06		84.8		4.90			7.8		
			Bottom	15.4	22.3	30.8	30.9	5.94	5.93	83.2	83.0	6.12	5.08		5.08	8.2	
04/11/10	0949-1004	21/Cloudy	Surface	1.0	24.4	30.9	30.9	5.89	5.87	81.8	81.7	5.94	5.97	6.14	9.0	9.2	9.4
				8.2	23.7	31.3		5.68		78.9		6.12			9.5		
			Bottom	15.4	22.9	31.4	31.4	5.69	5.71	79.1	79.0	6.17	6.15		6.15	9.2	
06/11/10	1102-1115	18/Rainy	Surface	1.0	20.4	29.3	29.3	6.04	6.05	84.6	84.7	4.99	4.97	5.04	8.0	8.0	8.1
				8.4	21.4	30.2		6.01		84.4		5.03			8.2		
			Bottom	15.8	22.7	30.2	30.2	6.03	6.02	84.4	84.3	5.05	5.04		5.04	8.0	
09/11/10	1452-1504	20/Fine	Surface	1.0	24.1	31.2	31.2	5.91	5.89	82.1	81.8	4.87	4.90	4.96	7.5	7.7	8.0
				8.4	23.5	31.8		5.75		79.3		4.99			8.2		
			Bottom	15.8	23.2	31.7	31.8	5.71	5.73	78.7	79.0	4.91	4.95		4.95	8.0	
11/11/10	1652-1702	25/Fine	Surface	1.0	21.2	31.1	31.1	6.20	6.20	88.7	88.7	5.11	5.13	5.62	8.3	8.3	9.0
				6.1	20.9	31.7		6.02		86.0		5.70			9.0		
			Bottom	11.2	20.7	31.9	31.8	6.05	6.04	86.1	86.1	5.67	5.69		5.69	9.5	
13/11/10	0702-0715	20/Fine	Surface	1.0	21.5	30.5	30.6	6.01	6.03	83.5	83.8	4.93	4.92	5.04	8.0	8.0	8.1
				8.2	20.7	31.0		5.94		82.6		5.02			8.2		
			Bottom	15.4	20.3	31.1	31.1	5.95	5.95	82.7	82.7	5.06	5.04		5.04	8.0	
16/11/10	0952-1011	23/Cloudy	Surface	1.0	20.4	30.7	30.7	6.03	6.04	83.8	83.6	4.98	4.99	5.05	8.0	8.0	8.3
				8.2	21.3	31.6		6.00		83.4		5.04			8.4		
			Bottom	15.7	20.4	31.3	31.5	6.01	6.01	83.5	83.5	5.09	5.07		5.07	8.3	
18/11/10	0944-1000	23/Fine	Surface	1.0	24.2	30.8	30.9	5.75	5.76	79.9	80.0	5.88	5.91	6.19	9.5	9.5	9.5
				8.4	23.8	30.9		5.76		80.0		5.93			9.4		
			Bottom	15.8	23.0	31.1	31.1	5.69	5.70	79.0	79.2	6.12	6.15		6.15	9.6	
20/11/10	1046-1059	23/Sunny	Surface	1.0	23.2	30.4	30.5	6.02	6.01	83.7	83.6	4.99	4.99	5.03	8.0	7.9	8.1
				8.4	22.8	30.6		6.00		83.4		4.98			7.8		
			Bottom	15.7	21.4	31.0	31.0	5.99	5.99	83.3	83.2	5.01	5.02		5.02	8.2	
23/11/10	1429-1448	24/Fine	Surface	1.0	24.1	30.4	30.5	5.74	5.73	79.8	79.7	5.89	5.90	6.19	9.5	9.5	9.5
				8.2	23.8	30.6		5.72		79.5		5.90			9.4		
			Bottom	16.4	23.0	30.9	31.0	5.68	5.68	79.0	78.9	6.14	6.16		6.16	9.8	
25/11/10	1408-1426	24/Fine	Surface	1.0	24.0	30.7	30.8	5.82	5.83	80.5	80.7	5.87	5.90	6.13	9.5	9.4	9.5
				8.2	23.8	30.9		5.84		80.8		5.93			9.2		
			Bottom	15.8	23.7	31.2	31.3	5.78	5.79	80.0	80.1	5.99	6.01		6.01	9.6	
27/11/10	1650-1706	23/Fine	Surface	1.0	24.0	31.4	31.0	5.79	5.75	80.2	79.9	6.02	5.96	6.16	9.5	9.4	9.4
				8.2	23.4	31.7		5.68		78.8		6.47			9.2		
			Bottom	15.4	23.0	31.9	31.6	5.67	5.69	78.6	78.9	6.50	6.16		6.16	9.5	
30/11/10	1924-1937	23/Fine	Surface	1.0	23.1	30.4	30.4	5.92	5.93	82.5	82.2	5.87	5.89	6.16	9.5	9.4	9.5
				8.2	22.8	30.3		5.94		81.8		5.90			9.2		
			Bottom	16.3	22.5	30.7	30.7	5.79	5.78	80.8	80.5	6.12	6.13		6.13	9.6	

Mid-Ebb Tide

Monitoring Station : R6

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/11/10	1006-1022	20/Fine	Surface	1.0	22.1	30.3	30.4	6.04	6.03	84.6	84.4	4.81	4.82	4.94	7.8	7.7	7.9
						30.4		6.01		84.1		4.83			7.6		
			Middle	7.7	20.6	30.8	30.9	5.95	5.95	83.3	83.3	4.97	4.96		8.0	7.9	
						30.9		5.94		83.2		4.95			7.8		
			Bottom	14.4	21.9	31.1	31.2	5.84	5.83	81.8	81.7	5.03	5.05		8.2	8.1	
						31.2		5.82		81.5		5.06			8.0		
04/11/10	1047-1102	21/Cloudy	Surface	1.0	24.3	30.9	31.0	5.81	5.84	80.9	81.3	6.01	6.05	6.21	9.0	9.1	9.3
						31.0		5.86		81.6		6.08			9.2		
			Middle	7.7	23.7	31.3	31.3	5.74	5.76	79.8	80.1	6.17	6.19		9.4	9.2	
						31.3		5.77		80.4		6.21			9.0		
			Bottom	14.4	22.9	31.8	31.8	5.68	5.69	78.8	78.9	6.38	6.40		9.5	9.6	
						31.8		5.70		79.0		6.41			9.6		
06/11/10	1156-1209	18/Rainy	Surface	1.0	20.4	29.4	29.4	6.02	6.05	84.3	84.7	5.07	5.05	5.12	8.2	8.2	8.2
						29.3		6.08		85.1		5.03			8.2		
			Middle	7.9	21.7	30.3	30.3	5.94	5.95	83.2	83.3	5.11	5.14		8.0	8.0	
						30.2		5.95		83.3		5.16			8.0		
			Bottom	14.8	22.8	31.4	31.5	5.81	5.81	81.3	81.3	5.17	5.18		8.6	8.5	
						31.5		5.80		81.2		5.19			8.4		
09/11/10	1550-1602	20/Fine	Surface	1.0	24.2	31.2	31.2	6.09	6.07	84.6	84.3	5.23	5.25	5.41	8.6	8.5	8.8
						31.2		6.05		84.0		5.27			8.4		
			Middle	8.1	23.3	32.0	32.1	5.88	5.86	81.7	81.4	5.45	5.42		9.0	8.9	
						32.1		5.84		81.1		5.39			8.8		
			Bottom	15.2	23.1	32.4	32.4	5.70	5.73	78.6	79.0	5.58	5.55		9.2	9.1	
						32.3		5.75		79.3		5.51			9.0		
11/11/10	1746-1759	25/Fine	Surface	1.0	21.2	31.7	31.7	6.11	6.11	86.6	86.6	5.02	5.06	5.63	8.0	8.0	8.9
						31.7		6.11		86.6		5.09			7.9		
			Middle	7.3	20.9	31.9	31.9	6.00	6.00	85.7	85.7	5.77	5.87		9.2	9.3	
						31.9		6.00		85.7		5.97			9.4		
			Bottom	13.6	20.7	32.3	32.2	5.88	5.83	83.9	83.1	5.99	5.98		9.6	9.6	
						32.1		5.77		82.2		5.96			9.5		
13/11/10	0754-0807	20/Fine	Surface	1.0	21.5	30.5	30.6	6.08	6.09	84.5	84.6	5.06	5.07	5.13	8.0	8.0	8.1
						30.6		6.09		84.7		5.08			8.0		
			Middle	7.7	20.6	31.2	31.2	5.89	5.88	81.9	81.7	5.16	5.15		8.2	8.3	
						31.1		5.86		81.5		5.14			8.4		
			Bottom	14.4	20.4	32.0	32.1	5.97	5.96	83.0	82.9	5.19	5.18		8.1	8.1	
						32.1		5.95		82.7		5.16			8.1		
16/11/10	1109-1124	23/Cloudy	Surface	1.0	22.6	30.1	30.3	6.04	6.03	84.0	83.9	5.04	5.05	5.13	8.2	8.3	8.3
						30.4		6.02		83.7		5.05			8.4		
			Middle	7.8	21.9	30.6	30.6	5.99	5.98	83.3	83.1	5.12	5.15		8.0	8.1	
						30.6		5.96		82.8		5.17			8.1		
			Bottom	14.2	20.9	30.9	31.2	5.87	5.86	81.5	81.1	5.17	5.19		8.6	8.6	
						31.4		5.84		80.6		5.20			8.6		
18/11/10	1045-1100	23/Fine	Surface	1.0	24.4	30.8	30.8	5.86	5.84	81.4	81.1	5.51	5.49	5.65	9.0	8.8	9.0
						30.8		5.82		80.8		5.47			8.6		
			Middle	7.7	23.8	31.0	31.1	5.73	5.74	79.6	79.8	5.60	5.63		8.8	8.9	
						31.1		5.75		79.9		5.66			8.9		
			Bottom	14.4	23.0	31.8	31.8	5.66	5.67	78.7	78.9	5.86	5.82		9.5	9.5	
						31.8		5.68		79.0		5.78			9.4		
20/11/10	1147-1200	23/Sunny	Surface	1.0	23.2	30.5	30.6	6.00	6.02	83.4	83.7	5.02	5.02	5.12	7.8	7.9	8.2
						30.6		6.04		84.0		5.01			8.0		
			Middle	7.5	22.8	31.2	31.4	5.98	5.98	83.1	83.1	5.11	5.11		8.2	8.1	
						31.5		5.97		83.0		5.10			8.0		
			Bottom	14.9	21.4	31.7	31.5	5.83	5.85	81.0	81.3	5.24	5.24		8.5	8.5	
						31.2		5.86		81.5		5.23			8.4		
23/11/10	1538-1549	24/Fine	Surface	1.0	24.3	30.7	30.7	5.84	5.85	81.2	81.4	5.52	5.50	5.66	9.0	8.8	9.0
						30.7		5.86		81.5		5.47			8.6		
			Middle	7.2	24.0	31.0	31.1	5.72	5.73	79.5	79.7	5.60	5.61		8.8	8.9	
						31.2		5.74		79.8		5.62			9.0		
			Bottom	14.3	23.6	31.9	31.9	5.66	5.67	78.6	78.7	5.87	5.88		9.2	9.3	
						31.8		5.67		78.8		5.88			9.4		
25/11/10	1517-1527	24/Fine	Surface	1.0	24.2	30.9	30.9	5.85	5.85	81.3	81.3	5.50	5.49	5.65	9.0	9.1	9.2
						30.8		5.84		81.2		5.48			9.2		
			Middle	7.2	23.9	31.0	31.0	5.74	5.75	79.8	80.0	5.62	5.64		8.9	9.1	
						31.0		5.76		80.1		5.65			9.2		
			Bottom	14.4	23.7	31.2	31.2	5.68	5.68	78.8	78.8	5.82	5.81		9.4	9.3	
						31.1		5.68		78.8		5.80			9.2		
27/11/10	1755-1811	23/Fine	Surface	1.0	24.0	30.9	31.0	5.82	5.84	80.8	81.1	5.55	5.58	5.78	9.0	8.8	9.1
						31.0		5.86		81.4		5.60			8.6		
			Middle	7.7	23.4	31.7	31.7	5.75	5.73	79.9	79.6	5.83	5.85		8.8	9.0	
						31.7		5.70		79.2		5.87			9.2		
			Bottom	14.4	23.0	32.2	32.2	5.66	5.66	78.6	78.6	5.90	5.93		9.4	9.4	
						32.2		5.66		78.6		5.95			9.4		
30/11/10	2021-2031	23/Fine	Surface	1.0	23.1	30.7	30.7	5.87	5.86	81.6	81.5	5.52	5.55	5.65	9.0	9.1	9.2
						30.6		5.85		81.3		5.57			9.2		
			Middle	7.6	22.8	30.9	31.0	5.74	5.73	79.8	79.7	5.66	5.67		8.9	9.1	
						31.1		5.72		79.5		5.68			9.2		
			Bottom	15.2	22.5	31.1	31.1	5.66	5.67	78.8	79.0	5.75	5.75		9.4	9.3	
						31.1		5.68		79.1		5.74			9.2		

Mid-Ebb Tide

Monitoring Station : R7

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/11/10	1025-1038	20/Fine	Surface	1.0	22.2	30.4	30.5	6.12	6.11	85.7	85.6	4.94	4.93	5.03	7.8	7.7	8.0
						30.5		6.10		85.4		4.92			7.6		
			Middle	8.7	20.5	30.7	30.8	6.03	6.03	84.4	84.4	5.03	5.06		5.05	8.2	
04/11/10	1109-1125	21/Cloudy	Surface	1.0	24.4	31.0	31.0	5.87	5.86	81.5	81.3	5.87	5.89	6.07	8.8	8.9	9.1
						31.0		5.84		81.1		5.91			9.0		
			Middle	8.8	23.7	31.4	31.5	5.79	5.78	80.4	80.2	6.06	6.13		6.10	9.2	
06/11/10	1212-1225	18/Rainy	Surface	1.0	20.5	29.5	29.5	5.97	5.95	83.6	83.3	5.12	5.15	5.14	8.0	7.9	8.1
						29.4		5.93		83.0		5.17			7.8		
			Middle	8.9	21.6	30.2	30.2	5.86	5.84	82.0	81.8	5.06	5.06		5.06	8.2	
09/11/10	1605-1617	20/Fine	Surface	1.0	24.2	31.3	31.3	6.02	6.04	83.6	83.8	5.11	5.09	5.07	8.2	8.1	8.1
						31.3		6.05		84.0		5.07			8.0		
			Middle	8.9	23.3	32.0	32.0	5.90	5.92	82.0	82.3	5.21	5.18		5.20	8.4	
11/11/10	1800-1815	25/Fine	Surface	1.0	21.4	32.2	32.1	6.10	6.10	87.2	87.2	5.09	5.06	5.69	8.2	8.1	9.0
						32.0		6.10		87.2		5.02			8.0		
			Middle	7.5	21.1	31.9	32.0	5.99	5.99	85.5	85.6	5.62	6.06		5.84	9.0	
13/11/10	0810-0823	20/Fine	Surface	1.0	21.6	30.6	30.6	6.02	6.04	83.7	83.9	5.12	5.13	5.21	8.3	8.4	8.4
						30.5		6.05		84.1		5.14			8.5		
			Middle	8.7	20.6	31.0	31.1	5.92	5.94	82.3	82.6	5.20	5.22		5.22	8.6	
16/11/10	1128-1142	23/Cloudy	Surface	1.0	22.8	30.7	30.7	5.94	5.93	82.6	82.5	5.11	5.11	5.13	7.9	8.0	8.2
						30.7		5.92		82.3		5.10			8.1		
			Middle	8.7	22.5	30.9	30.9	5.87	5.86	81.0	81.1	5.09	5.07		5.08	8.1	
18/11/10	1108-1125	23/Fine	Surface	1.0	24.3	30.9	30.9	5.91	5.89	82.1	81.8	5.36	5.38	5.61	8.5	8.5	8.9
						30.8		5.86		81.4		5.39			8.4		
			Middle	8.8	23.7	31.1	31.1	5.71	5.72	79.4	79.5	5.53	5.58		5.56	9.0	
20/11/10	1204-1217	23/Sunny	Surface	1.0	23.3	30.6	30.6	6.02	6.03	83.7	83.9	5.02	5.01	5.10	7.6	7.8	8.0
						30.5		6.04		84.0		5.00			8.0		
			Middle	8.5	22.9	31.4	31.6	5.97	5.96	83.0	82.9	5.10	5.08		5.09	8.2	
23/11/10	1559-1614	24/Fine	Surface	1.0	24.1	30.9	30.9	5.92	5.91	82.3	82.2	5.37	5.38	5.60	8.6	8.4	8.8
						30.8		5.90		82.0		5.39			8.2		
			Middle	8.3	24.0	31.1	31.2	5.67	5.69	78.8	79.0	5.54	5.55		5.55	8.8	
25/11/10	1538-1552	24/Fine	Surface	1.0	24.3	30.4	30.7	5.92	5.92	82.3	82.3	5.35	5.37	5.61	8.6	8.7	9.0
						30.9		5.92		82.3		5.39			8.8		
			Middle	8.3	23.8	30.9	31.0	5.79	5.80	80.4	80.6	5.54	5.58		5.56	9.0	
27/11/10	1815-1830	23/Fine	Surface	1.0	24.0	31.2	31.2	5.60	5.64	78.8	78.9	5.89	5.90	5.84	9.4	9.4	9.1
						31.2		5.67		78.9		5.90			9.4		
			Middle	8.7	23.4	31.7	31.7	5.76	5.78	80.1	80.4	5.85	5.91		5.88	8.9	
30/11/10	2036-2047	23/Fine	Surface	1.0	23.1	30.9	30.9	5.87	5.86	81.5	81.4	5.58	5.61	5.72	9.0	9.1	9.0
						30.9		5.85		81.3		5.63			9.1		
			Middle	8.5	23.3	31.0	31.1	5.74	5.76	79.8	80.0	5.72	5.77		5.75	8.8	
30/11/10	2036-2047	23/Fine	Surface	1.0	23.1	30.7	30.6	5.82	5.84	80.9	81.1	5.59	5.61	5.72	8.6	8.7	9.0
						30.5		5.85		81.3		5.62			8.8		
			Middle	8.5	23.3	31.0	31.1	5.74	5.76	79.8	80.0	5.72	5.77		5.75	9.0	
30/11/10	2036-2047	23/Fine	Surface	1.0	23.1	31.1	31.1	5.77	5.76	80.2	80.0	5.77	5.75	5.72	8.8	8.9	9.0
						31.1		5.77		80.2		5.77			8.8		
			Bottom	17.0	22.8	31.2	31.3	5.69	5.69	79.1	79.1	5.80	5.82		5.82	9.4	

Mid-Ebb Tide



Monitoring Station : R8a

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)			
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average	
02/11/10	1045-1058	20/Fine	Surface	1.0	22.0	30.2	30.3	6.07	6.05	84.0	84.2	4.96	4.95	5.03	8.0	8.0	8.1	
						30.3		6.03		84.4		4.93			8.0			
			Middle	6.1	20.7	30.7	30.8	5.96	5.97	83.4	83.6	5.04	5.04	5.04	8.0	8.1		8.1
						30.8		5.98		83.7		5.03		8.2				
			Bottom	11.2	22.3	31.3	31.4	5.84	5.83	81.8	81.6	5.13	5.12	5.12	8.4	8.3		
						31.4		5.81		81.3		5.11		8.2				
04/11/10	1130-1145	21/Cloudy	Surface	1.0	24.4	30.9	31.0	5.80	5.79	80.6	80.5	5.77	5.79	6.01	8.8	8.7	9.1	
						31.0		5.78		80.3		5.81			8.5			
			Middle	6.2	23.8	31.3	31.3	5.69	5.71	79.0	79.3	5.94	5.97	5.97	9.0	9.1		
						31.3		5.72		79.5		5.99		9.2				
			Bottom	11.4	23.3	31.8	31.8	5.65	5.67	78.6	78.8	6.26	6.28	6.26	9.5	9.5		
						31.8		5.68		78.9		6.29		9.5				
06/11/10	1232-1245	19/Rainy	Surface	1.0	20.5	29.2	29.2	6.12	6.15	85.7	86.1	4.87	4.88	4.96	7.6	7.8	7.9	
						29.1		6.17		86.4		4.89			8.0			
			Middle	6.3	21.6	30.1	30.2	6.08	6.05	85.1	84.7	4.96	4.95	4.95	8.0	7.9		
						30.2		6.02		84.3		4.93		7.8				
			Bottom	11.6	22.8	31.4	31.5	5.94	5.93	83.2	83.0	5.04	5.05	5.05	8.2	8.1		
						31.5		5.91		82.7		5.05		8.0				
09/11/10	1624-1634	20/Fine	Surface	1.0	24.1	31.1	31.1	6.06	6.05	84.2	84.1	5.15	5.12	4.93	8.2	8.1	7.9	
						31.1		6.04		83.9		5.09			8.0			
			Middle	6.4	23.4	31.9	32.0	5.73	5.72	79.0	78.8	4.90	4.94	4.94	7.8	7.8		
						32.0		5.70		78.6		4.98		7.8				
			Bottom	11.8	23.0	32.4	32.4	5.69	5.67	78.5	78.2	4.75	4.72	4.72	7.5	7.7		
						32.3		5.65		77.9		4.69		7.8				
11/11/10	1819-1830	25/Fine	Surface	1.0	21.9	31.2	31.2	6.11	6.13	87.2	87.3	5.00	5.06	5.40	7.8	8.0	8.6	
						31.2		6.15		87.3		5.11			8.2			
			Middle	8.0	21.2	31.5	31.6	6.00	6.01	85.7	85.7	5.22	5.19	5.19	8.5	8.5		
						31.7		6.02		85.7		5.16		8.4				
			Bottom	15.0	21.0	32.2	32.4	5.92	5.92	85.0	85.0	6.01	5.97	5.97	9.4	9.4		
						32.5		5.91		85.0		5.92		9.4				
13/11/10	0830-0843	21/Fine	Surface	1.0	21.3	30.4	30.5	6.01	6.02	83.5	83.6	5.14	5.14	5.23	8.2	8.1	8.3	
						30.5		6.02		83.7		5.13			8.0			
			Middle	6.1	20.4	30.8	30.9	5.96	5.96	82.8	82.8	5.20	5.21	5.21	8.5	8.4		
						30.9		5.95		82.7		5.21		8.2				
			Bottom	11.2	20.3	31.8	31.8	5.85	5.87	81.3	81.5	5.32	5.35	5.32	8.5	8.5		
						31.7		5.88		81.7		5.37		8.5				
16/11/10	1150-1204	23.1/Sunny	Surface	1.0	22.4	30.2	30.2	6.17	6.17	85.8	85.7	4.82	4.83	4.94	7.7	7.9	8.0	
						30.1		6.16		85.6		4.84			8.0			
			Middle	6.2	21.4	30.7	30.6	6.09	6.08	84.7	84.6	4.97	4.96	4.96	8.0	8.0		
						30.5		6.07		84.4		4.95		7.9				
			Bottom	11.7	21.1	30.7	30.8	5.97	5.95	82.4	82.4	5.02	5.02	5.02	8.2	8.2		
						30.9		5.92		82.3		5.01		8.2				
18/11/10	1130-1145	23/Fine	Surface	1.0	24.3	30.9	30.9	5.86	5.83	81.4	81.0	5.31	5.29	5.54	8.2	8.3	8.9	
						30.9		5.80		80.6		5.26			8.3			
			Middle	6.2	23.8	31.0	31.1	5.72	5.74	79.5	79.7	5.57	5.54	5.54	9.0	9.0		
						31.1		5.75		79.9		5.51		9.0				
			Bottom	11.4	23.2	31.6	31.6	5.68	5.68	78.8	78.8	5.77	5.79	5.77	9.2	9.3		
						31.6		5.68		78.8		5.81		9.4				
20/11/10	1224-1237	23/Sunny	Surface	1.0	23.1	31.0	31.0	6.02	6.03	83.7	83.9	5.02	5.01	5.13	8.2	8.1	8.2	
						31.0		6.04		84.0		5.00			8.0			
			Middle	5.8	22.5	30.9	30.9	6.00	5.97	83.4	83.0	5.12	5.14	5.14	8.2	8.3		
						30.8		5.94		82.6		5.15		8.3				
			Bottom	11.5	21.9	31.2	31.3	5.87	5.88	81.6	81.7	5.22	5.23	5.22	8.5	8.4		
						31.4		5.88		81.7		5.24		8.2				
23/11/10	1620-1633	24/Fine	Surface	1.0	24.1	30.7	30.8	5.84	5.85	81.2	81.3	5.35	5.31	5.55	8.2	8.2	8.7	
						30.9		5.85		81.3		5.27			8.2			
			Middle	5.7	23.9	31.0	31.1	5.72	5.73	79.5	79.7	5.56	5.57	5.56	8.8	8.7		
						31.2		5.74		79.8		5.58		8.5				
			Bottom	11.4	23.4	31.7	31.7	5.67	5.68	78.7	78.8	5.76	5.78	5.76	9.2	9.1		
						31.6		5.68		78.8		5.80		9.0				
25/11/10	1558-1607	24/Fine	Surface	1.0	24.1	30.9	30.9	5.85	5.83	81.3	81.0	5.31	5.29	5.54	8.2	8.4	8.8	
						30.8		5.80		80.6		5.26			8.5			
			Middle	5.7	23.9	31.0	31.0	5.72	5.73	79.5	79.7	5.56	5.56	5.56	9.0	8.8		
						30.9		5.74		79.8		5.55		8.6				
			Bottom	11.4	23.7	31.7	31.8	5.67	5.67	78.8	78.8	5.77	5.79	5.77	9.4	9.3		
						31.8		5.67		78.7		5.81		9.2				
27/11/10	1835-1850	23/Fine	Surface	1.0	24.0	31.0	31.0	5.97	5.95	83.0	82.6	5.63	5.61	5.78	9.2	9.1	9.3	
						31.0		5.92		82.2		5.58			9.0			
			Middle	6.1	23.5	31.5	31.6	5.81	5.83	80.8	81.2	5.78	5.81	5.78	9.5	9.4		
						31.6		5.85		81.5		5.83		9.3				
			Bottom	11.2	23.1	31.9	32.0	5.67	5.67	78.8	78.4	5.90	5.93	5.90	9.5	9.5		
						32.0		5.66		78.0		5.95		9.5				
30/11/10	2052-2102	23/Fine	Surface	1.0	23.2	30.8	30.9	5.82	5.84	80.9	81.1	5.52	5.53	5.74	8.2	8.4	8.8	
						30.9		5.85		81.3		5.54			8.5			
			Middle	6.1	23.0	31.0	31.1	5.70	5.72	79.2	79.4	5.78	5.79	5.78	9.0	8.8		
						31.1		5.74		79.5		5.79		8.6				
			Bottom	12.2	22.7	31.2	31.3	5.68	5.67	78.9	78.8	5.91	5.91	5.91	9.4	9.3		
						31.3		5.66		78.7		5.91		9.2				

Monitoring Station : R15

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)			
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average	
02/11/10	0754-0807	19/Fine	Surface	1.0	21.9	30.2	30.2	6.08	6.08	85.1	85.1	5.02	5.03	5.13	8.0	8.1	8.3	
						30.1		6.07		85.0		5.04			8.2			
			Middle	5.2	20.9	30.6	30.7	5.86	5.84	82.0	81.8	5.12	5.13		8.4			8.2
						30.7		5.82		81.5		5.14			8.0			
			Bottom	9.4	21.9	31.1	31.2	5.74	5.76	80.4	80.7	5.23	5.22		8.4			8.5
						31.2		5.78		80.9		5.21			8.6			
04/11/10	0839-0855	20/Cloudy	Surface	1.0	24.2	30.9	30.9	5.69	5.68	79.0	78.8	6.24	6.26	6.42	9.2	9.3	9.4	
						30.8		5.66		78.6		6.28			9.4			
			Middle	5.4	23.9	31.1	31.1	5.53	5.55	76.8	77.0	6.21	6.26		9.0			9.2
						31.1		5.56		77.2		6.30			9.4			
			Bottom	9.8	23.2	31.5	31.5	5.28	5.30	73.3	73.6	6.75	6.73		9.8			9.7
						31.5		5.31		73.8		6.71			9.5			
06/11/10	0939-0952	18/Rainy	Surface	1.0	20.6	29.1	29.1	5.96	5.96	83.4	83.4	5.16	5.17	5.26	8.4	8.2	8.3	
						29.0		5.95		83.3		5.18			8.0			
			Middle	5.4	21.4	30.2	30.2	5.84	5.86	81.8	82.0	5.31	5.34		8.0			8.1
						30.1		5.87		82.2		5.36			8.2			
			Bottom	9.8	22.6	31.9	32.0	5.79	5.75	81.1	80.5	5.29	5.27		8.6			8.5
						32.0		5.71		79.9		5.25			8.4			
09/11/10	1334-1345	20/Fine	Surface	1.0	23.8	30.9	31.0	5.86	5.85	81.4	81.3	5.15	5.13	5.15	7.8	7.8	8.1	
						31.0		5.84		81.1		5.11			7.8			
			Middle	6.4	23.1	31.9	31.9	5.64	5.62	77.8	77.5	5.07	5.10		8.6			8.5
						31.8		5.60		77.2		5.12			8.4			
			Bottom	11.8	22.9	32.3	32.4	5.57	5.56	76.8	76.6	5.26	5.24		8.2			8.1
						32.4		5.54		76.4		5.21			8.0			
11/11/10	1545-1555	25/Fine	Surface	1.0	21.0	30.9	30.9	5.99	6.02	85.6	85.9	5.14	5.54	6.05	9.0	9.1	9.3	
						30.9		6.05		86.2		5.94			9.2			
			Middle	4.4	20.7	31.0	31.0	5.90	5.89	84.3	84.5	6.01	6.42		9.6			9.6
						31.0		5.87		84.7		6.82			9.6			
			Bottom	7.8	20.1	31.2	31.2	5.79	5.78	82.9	82.6	6.11	6.18		9.4			9.3
						31.1		5.77		82.3		6.25			9.2			
13/11/10	0539-0552	20/Fine	Surface	1.0	21.4	30.6	30.6	6.02	6.02	83.7	83.6	5.06	5.08	5.20	8.2	8.3	8.5	
						30.5		6.01		83.5		5.09			8.4			
			Middle	5.2	20.4	31.2	31.3	5.90	5.92	82.0	82.3	5.21	5.23		8.5			8.5
						31.3		5.94		82.6		5.24			8.4			
			Bottom	9.4	20.7	32.0	32.1	5.89	5.88	81.9	81.8	5.32	5.31		8.8			8.7
						32.1		5.87		81.6		5.30			8.5			
16/11/10	0829-0841	22.8/Rainy	Surface	1.0	20.9	29.4	29.5	5.98	5.98	83.1	83.1	5.16	5.17	5.26	8.3	8.2	8.3	
						29.5		5.97		83.0		5.18			8.1			
			Middle	5.9	21.3	30.7	30.6	5.85	5.86	81.8	81.7	5.32	5.34		8.1			8.2
						30.5		5.87		81.5		5.35			8.3			
			Bottom	9.7	20.5	31.8	31.8	5.77	5.77	80.2	80.2	5.29	5.29		8.5			8.4
						31.7		5.76		80.1		5.28			8.3			
18/11/10	0832-0848	22/Cloudy	Surface	1.0	24.3	30.6	30.6	5.75	5.73	79.9	79.6	6.01	6.04	6.34	9.5	9.4	9.5	
						30.6		5.71		79.3		6.07			9.3			
			Middle	5.4	24.1	30.8	30.9	5.66	5.67	78.6	78.7	6.32	6.35		9.6			9.7
						30.9		5.68		78.8		6.38			9.8			
			Bottom	9.8	23.5	31.4	31.4	5.66	5.66	78.7	78.6	6.60	6.64		9.5			9.5
						31.4		5.65		78.5		6.68			9.4			
20/11/10	0912-0925	23/Sunny	Surface	1.0	23.1	30.7	30.8	6.00	6.01	83.4	83.6	5.10	5.10	5.13	8.3	8.4	8.3	
						30.8		6.02		83.7		5.10			8.5			
			Middle	5.0	22.8	30.8	30.9	5.98	5.98	83.1	83.1	5.09	5.09		8.1			8.2
						31.0		5.97		83.0		5.08			8.2			
			Bottom	9.9	22.1	31.2	31.2	5.88	5.85	81.7	81.3	5.21	5.21		8.4			8.3
						31.1		5.81		80.8		5.20			8.2			
23/11/10	1314-1325	24/Fine	Surface	1.0	24.1	30.7	30.7	5.87	5.87	81.6	81.6	5.43	5.47	5.69	9.0	8.8	9.0	
						30.6		5.86		81.5		5.50			8.6			
			Middle	5.0	23.4	30.9	31.1	5.79	5.80	80.5	80.7	5.71	5.71		8.8			9.0
						31.2		5.81		80.8		5.70			9.2			
			Bottom	9.9	23.0	31.2	31.3	5.67	5.67	78.8	78.8	5.87	5.91		9.4			9.3
						31.3		5.66		78.7		5.94			9.2			
25/11/10	1249-1301	24/Fine	Surface	1.0	24.0	30.5	30.6	5.84	5.83	81.8	81.7	5.32	5.35	5.58	9.5	9.3	9.1	
						30.7		5.82		81.5		5.37			9.0			
			Middle	4.8	24.1	30.9	30.9	5.76	5.76	80.7	80.6	5.55	5.58		8.8			8.9
						30.9		5.75		80.5		5.60			9.0			
			Bottom	9.6	23.6	31.2	31.3	5.66	5.67	78.8	78.9	5.82	5.83		9.0			9.1
						31.4		5.67		78.9		5.84			9.1			
27/11/10	1540-1556	23/Fine	Surface	1.0	24.0	30.9	30.9	5.91	5.90	81.8	81.8	5.89	5.93	6.08	9.0	9.1	9.2	
						30.9		5.88		81.7		5.97			9.2			
			Middle	5.3	23.8	31.4	31.4	5.80	5.79	80.8	80.6	6.03	6.06		9.5			9.5
						31.4		5.77		80.4		6.08			9.4			
			Bottom	9.6	23.2	31.9	32.0	5.68	5.68	79.0	78.9	6.23	6.26		9.0			9.1
						32.0		5.67		78.8		6.28			9.2			
30/11/10	1818-1830	23/Fine	Surface	1.0	24.0	30.6	30.7	5.88	5.89	81.7	81.8	5.41	5.46	5.69	9.5	8.9	9.1	
						30.7		5.89		81.9		5.50			9.2			
			Middle	5.1	23.5	30.9	31.0	5.74	5.75	79.8	79.9	5.72	5.72		9.0			8.9
						31.0		5.75		79.9		5.71			8.8			
			Bottom	10.1	23.2	31.1	31.1	5.67	5.66	78.8	78.7	5.90	5.90		9.0			9.0
						31.0		5.65		78.5		5.89			9.0			

Mid-Ebb Tide

Monitoring Station : R16

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)					
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average			
02/11/10	0916-0929	20/Fine	Surface	1.0	22.1	30.1	30.2	6.08	6.07	85.1	85.0	4.92	4.91	5.06	8.0	7.9	8.1			
						30.2		6.06		84.8		4.90			7.8					
			Middle	8.2	20.5	30.8	30.9	5.94	5.94	83.2	83.1	5.08	5.08		5.07	5.08		8.2	8.1	8.1
						30.9		5.93		83.0		5.07			8.0					
			Bottom	15.4	22.3	31.3	31.3	5.81	5.81	81.3	81.3	5.17	5.18		5.17	5.18		8.4	8.3	
						31.2		5.80		81.2		5.19			8.2					
04/11/10	0819-0835	20/Cloudy	Surface	1.0	24.2	30.9	30.9	5.90	5.88	82.0	81.7	5.78	5.81	5.99	8.8	8.9	9.1			
						30.9		5.86		81.4		5.83			9.0					
			Middle	6.3	23.8	31.2	31.2	5.81	5.83	80.7	80.9	5.96	5.99		6.01	5.99		9.0	9.1	9.1
						31.2		5.84		81.1		6.01			9.2					
			Bottom	11.6	23.1	31.7	31.7	5.73	5.75	79.6	79.8	6.15	6.17		6.15	6.17		9.4	9.2	
						31.7		5.76		80.0		6.19			9.0					
06/11/10	0916-0929	18/Rainy	Surface	1.0	20.7	28.8	31.0	6.06	6.05	84.8	84.6	5.12	5.12	5.14	8.2	8.2	8.2			
						28.9		6.03		84.4		5.11			8.2					
			Middle	6.0	21.5	30.0	30.1	5.99	5.98	83.9	83.7	5.08	5.06		5.04	5.06		8.0	7.9	8.2
						30.1		5.96		83.4		5.04			7.8					
			Bottom	11.0	22.7	31.8	31.9	5.83	5.86	81.6	82.1	5.24	5.23		5.24	5.23		8.6	8.6	
						31.9		5.89		82.5		5.22			8.6					
09/11/10	1315-1326	20/Fine	Surface	1.0	23.8	31.0	31.1	5.90	5.92	82.0	81.9	5.03	5.06	5.24	8.0	8.1	8.5			
						31.1		5.93		81.8		5.09			8.2					
			Middle	6.3	23.1	31.8	31.9	5.70	5.69	78.6	78.4	5.43	5.40		5.43	5.40		9.0	8.9	8.5
						31.9		5.67		78.2		5.37			8.8					
			Bottom	11.6	22.9	32.1	32.2	5.81	5.80	80.1	79.9	5.30	5.27		5.23	5.27		8.6	8.6	
						32.2		5.78		79.7		5.23			8.5					
11/11/10	1533-1543	25/Fine	Surface	1.0	21.2	31.1	31.1	6.18	6.17	87.9	88.1	5.75	5.74	5.73	8.8	9.0	9.2			
						31.1		6.16		88.2		5.72			9.2					
			Middle	4.5	20.8	31.4	31.4	5.99	6.02	85.7	85.9	5.71	5.71		5.71	5.71		9.4	9.2	9.2
						31.4		6.04		86.0		5.70			9.0					
			Bottom	8.0	20.5	31.9	31.9	5.90	5.89	84.3	84.2	5.70	5.74		5.70	5.74		9.2	9.4	
						31.9		5.88		84.0		5.77			9.5					
13/11/10	0516-0529	20/Fine	Surface	1.0	21.4	30.5	30.5	6.02	6.03	83.7	83.8	5.02	5.04	5.15	7.8	7.9	8.3			
						30.5		6.03		83.8		5.06			8.0					
			Middle	6.1	20.4	31.1	31.2	5.91	5.92	82.7	82.9	5.14	5.15		5.14	5.15		8.4	8.3	8.3
						31.2		5.93		83.0		5.16			8.2					
			Bottom	11.2	20.8	32.1	32.1	5.87	5.88	81.6	81.7	5.29	5.27		5.29	5.27		8.5	8.6	
						32.0		5.88		81.7		5.25			8.6					
16/11/10	0805-0817	22.8/Rainy	Surface	1.0	21.7	28.8	28.9	6.10	6.10	84.8	84.8	5.11	5.13	5.15	8.4	8.4	8.3			
						28.9		6.09		84.7		5.14			8.3					
			Middle	6.0	21.3	30.2	30.2	5.98	5.99	83.1	83.2	5.09	5.09		5.09	5.09		8.0	8.0	8.3
						30.1		5.99		83.3		5.08			8.0					
			Bottom	11.0	20.1	31.9	31.9	5.84	5.85	81.2	81.1	5.22	5.23		5.22	5.23		8.5	8.6	
						31.8		5.86		80.9		5.23			8.7					
18/11/10	0809-0825	22/Cloudy	Surface	1.0	24.2	30.6	30.6	5.93	5.90	82.4	82.0	5.51	5.54	5.75	9.0	8.9	9.0			
						30.6		5.87		81.5		5.57			8.8					
			Middle	6.2	24.0	30.9	30.9	5.79	5.81	80.4	80.7	5.72	5.75		5.72	5.75		9.2	9.1	9.0
						30.8		5.83		81.0		5.77			9.0					
			Bottom	11.4	23.5	31.5	31.5	5.68	5.68	78.8	78.9	5.93	5.96		5.93	5.96		9.0	8.9	9.0
						31.5		5.68		78.9		5.98			8.8					
20/11/10	0848-0902	23/Sunny	Surface	1.0	23.2	30.9	30.9	6.04	6.04	84.0	83.9	5.11	5.12	5.14	8.3	8.2	8.3			
						30.8		6.03		83.8		5.13			8.0					
			Middle	5.7	22.7	30.9	31.0	5.99	6.00	83.3	83.4	5.07	5.08		5.07	5.08		8.0	8.1	8.3
						31.1		6.01		83.5		5.08			8.2					
			Bottom	11.4	22.2	31.4	31.5	5.84	5.87	81.2	81.6	5.22	5.22		5.22	5.22		8.5	8.6	
						31.5		5.89		81.9		5.21			8.6					
23/11/10	1254-1302	24/Fine	Surface	1.0	24.2	30.8	30.7	5.88	5.88	81.7	81.7	5.57	5.58	5.74	9.0	9.0	9.3			
						30.5		5.87		81.6		5.59			9.0					
			Middle	5.7	23.2	30.8	31.1	5.74	5.75	79.8	80.0	5.70	5.71		5.70	5.71		9.4	9.5	9.3
						31.3		5.76		80.1		5.71			9.5					
			Bottom	11.4	23.1	31.4	31.5	5.68	5.67	79.0	78.8	5.92	5.93		5.92	5.93		9.6	9.4	
						31.6		5.65		78.5		5.93			9.2					
25/11/10	1227-1237	24/Fine	Surface	1.0	24.1	30.5	30.6	5.92	5.89	82.3	81.9	5.51	5.54	5.74	9.1	9.4	9.4			
						30.6		5.86		81.5		5.56			9.6					
			Middle	5.7	23.7	30.9	30.9	5.79	5.80	80.5	80.6	5.73	5.75		5.73	5.75		9.4	9.5	9.4
						30.8		5.80		80.6		5.77			9.5					
			Bottom	11.3	23.6	31.4	31.3	5.68	5.68	78.9	78.9	5.92	5.95		5.92	5.95		9.2	9.3	
						31.2		5.67		78.8		5.97			9.4					
27/11/10	1517-1532	23/Fine	Surface	1.0	24.0	30.9	31.0	5.99	5.95	83.2	82.7	5.64	5.62	5.81	9.0	8.9	8.9			
						31.0		5.91		82.1		5.60			8.8					
			Middle	6.1	23.8	31.5	31.5	5.86	5.84	81.4	81.1	5.81	5.84		5.81	5.84		9.0	9.0	8.9
						31.5		5.81		80.7		5.87			9.0					
			Bottom	11.2	23.2	32.1	32.1	5.75	5.73	79.9	79.6	5.95	5.97		5.95	5.97		8.8	8.9	
						32.1		5.70		79.2		5.99			9.0					
30/11/10	1754-1806	23/Fine	Surface	1.0	23.6	30.2	30.3	5.87	5.88	81.6	81.7	5.52	5.54	5.72	9.1	9.4	9.4			
						30.3		5.88		81.7		5.55			9.6					
			Middle		23.3	30.4	30.5	5.74	5.75	79.8	79.9	5.69	5.70		5.69	5.70		9.4	9.5	9.4
						30.5		5.75		79.9		5.70			9.5					
			Bottom	12.5	23.1	31.0	31.0	5.67	5.66	78.8	78.7	5.92	5.93		5.92	5.93		9.2	9.3	
						30.9		5.65		78.5		5.93			9.4					

Mid-Ebb Tide

Monitoring Station : R17

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)			
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average	
02/11/10	0715-0728	19/Fine	Surface	1.0	21.8	30.2	30.2	6.12	6.11	85.7	85.6	4.96	4.95	5.05	8.0	8.0	8.1	
						30.1		6.10		85.4		4.94			8.0			
			Middle	5.5	20.6	30.7	30.8	6.02	6.03	84.3	84.5	5.06	5.08		5.08	8.2		8.1
						30.8		6.04		84.6		5.09			8.0			
			Bottom	10.0	22.3	31.2	31.2	5.94	5.95	83.2	83.3	5.12	5.14		5.14	8.0		8.1
						31.1		5.96		83.4		5.15			8.2			
04/11/10	0800-0815	20/Cloudy	Surface	1.0	24.2	30.8	30.9	5.89	5.91	81.8	82.1	5.81	5.84	5.98	8.6	8.7	9.0	
						30.9		5.93		82.4		5.86			8.8			
			Middle	5.6	23.9	31.2	31.2	5.80	5.82	80.6	80.8	5.93	5.96		5.96	9.2		9.0
						31.2		5.83		81.0		5.98			8.8			
			Bottom	10.2	23.2	31.6	31.7	5.71	5.73	79.3	79.6	6.11	6.14		6.14	9.5		9.4
						31.7		5.75		79.9		6.16			9.3			
06/11/10	0900-0913	18/Rainy	Surface	1.0	20.7	28.9	28.9	6.01	6.04	84.1	84.6	5.07	5.05	5.14	7.8	7.8	8.1	
						28.8		6.07		85.0		5.03			7.8			
			Middle	5.7	21.4	29.9	30.0	5.96	5.97	83.4	83.5	5.14	5.17		5.17	8.0		8.0
						30.0		5.97		83.6		5.19			8.0			
			Bottom	10.4	22.8	31.7	31.8	5.81	5.83	81.3	81.6	5.20	5.21		5.21	8.5		8.6
						31.8		5.84		81.8		5.22			8.6			
09/11/10	1300-1312	20/Fine	Surface	1.0	23.9	30.8	30.9	5.97	5.98	82.9	83.1	4.76	4.74	5.23	7.6	7.7	8.3	
						30.9		5.99		83.2		4.71			7.8			
			Middle	6.1	23.2	31.7	31.7	5.67	5.65	78.2	77.9	5.29	5.25		5.25	8.4		8.3
						31.6		5.62		77.5		5.21			8.2			
			Bottom	11.2	23.2	31.9	32.0	5.69	5.68	78.6	78.4	5.66	5.70		5.70	9.0		9.0
						32.0		5.66		78.1		5.73			9.0			
11/11/10	1520-1532	25/Fine	Surface	1.0	21.2	31.1	31.1	6.14	6.14	87.8	87.8	5.92	5.91	5.96	9.6	9.4	9.5	
						31.1		6.14		87.8		5.90			9.2			
			Middle	4.5	20.9	31.7	31.7	6.00	6.01	85.7	85.8	5.99	5.99		5.99	9.5		9.5
						31.7		6.01		85.9		5.99			9.5			
			Bottom	8.0	20.4	32.0	32.0	5.90	5.91	84.3	84.3	5.97	5.97		5.97	9.5		9.5
						32.0		5.92		84.3		5.97			9.4			
13/11/10	0500-0513	20/Fine	Surface	1.0	21.3	30.6	30.6	6.10	6.10	84.8	84.8	5.14	5.15	5.24	8.0	8.0	8.3	
						30.5		6.09		84.7		5.16			8.0			
			Middle	5.5	20.4	31.2	31.2	5.94	5.96	83.2	83.5	5.27	5.26		5.26	8.4		8.3
						31.1		5.98		83.7		5.25			8.2			
			Bottom	10.0	20.8	32.0	32.1	5.86	5.84	81.5	81.2	5.34	5.32		5.32	8.5		8.5
						32.1		5.82		80.9		5.30			8.4			
16/11/10	0745-0758	22.8/Rainy	Surface	1.0	21.8	28.7	28.8	5.94	5.95	82.6	82.4	5.09	5.07	5.15	7.7	7.9	8.1	
						28.8		5.96		82.2		5.04			8.0			
			Middle	5.6	21.5	29.2	29.0	5.92	5.91	82.3	82.2	5.17	5.17		5.17	8.0		8.1
						28.8		5.90		82.0		5.16			8.2			
			Bottom	10.3	20.3	30.7	30.8	5.87	5.88	81.6	81.4	5.22	5.22		5.22	8.5		8.5
						30.9		5.88		81.1		5.21			8.4			
18/11/10	0750-0805	22/Cloudy	Surface	1.0	24.2	30.6	30.6	5.86	5.88	81.4	81.6	5.56	5.59	5.74	8.9	8.7	9.0	
						30.5		5.89		81.8		5.61			8.5			
			Middle	5.7	24.1	30.8	30.8	5.80	5.78	80.6	80.3	5.68	5.72		5.72	8.8		8.9
						30.8		5.75		79.9		5.75			9.0			
			Bottom	10.4	23.6	31.4	31.5	5.67	5.68	78.9	79.0	5.90	5.92		5.92	9.5		9.4
						31.5		5.68		79.0		5.94			9.3			
20/11/10	0830-0844	23/Sunny	Surface	1.0	23.1	31.0	31.0	6.00	6.02	83.4	83.7	5.04	5.04	5.14	7.9	8.0	8.2	
						31.0		6.04		84.0		5.03			8.0			
			Middle	5.3	22.5	30.9	31.0	5.94	5.93	82.6	82.5	5.17	5.18		5.18	8.2		8.1
						31.1		5.92		82.3		5.19			8.0			
			Bottom	10.5	22.0	31.2	31.3	5.84	5.85	81.2	81.3	5.22	5.22		5.22	8.5		8.7
						31.3		5.85		81.3		5.21			8.8			
23/11/10	1240-1250	24/Fine	Surface	1.0	24.2	30.9	30.9	5.84	5.87	81.2	81.6	5.57	5.58	5.73	9.0	8.9	9.0	
						30.9		5.89		81.9		5.58			8.8			
			Middle	5.2	24.1	31.5	31.5	5.90	5.88	82.0	81.8	5.69	5.70		5.70	8.5		8.5
						31.4		5.86		81.5		5.70			8.5			
			Bottom	10.3	23.6	32.4	32.5	5.78	5.78	80.3	80.3	5.90	5.92		5.92	9.5		9.5
						32.6		5.77		80.2		5.94			9.4			
25/11/10	1210-1223	24/Fine	Surface	1.0	23.9	30.4	30.5	5.87	5.87	81.6	81.6	5.56	5.59	5.74	9.0	8.9	8.9	
						30.5		5.86		81.5		5.62			8.8			
			Middle	5.2	23.8	30.7	30.7	5.80	5.77	80.6	80.2	5.68	5.72		5.72	8.6		8.7
						30.6		5.74		79.8		5.75			8.8			
			Bottom	10.3	23.6	31.0	31.0	5.68	5.69	78.9	79.0	5.90	5.90		5.90	9.0		9.0
						31.0		5.69		79.0		5.90			9.0			
27/11/10	1455-1510	23/Fine	Surface	1.0	24.0	30.9	30.9	5.89	5.93	81.8	82.4	5.61	5.64	5.80	9.2	9.1	9.3	
						30.9		5.97		82.9		5.67			8.9			
			Middle	5.6	23.9	31.4	31.5	5.80	5.82	80.6	80.9	5.79	5.82		5.82	9.4		9.3
						31.5		5.84		81.1		5.84			9.2			
			Bottom	10.2	23.2	32.0	32.0	5.72	5.75	79.5	79.9	5.93	5.96		5.96	9.5		9.4
						32.0		5.77		80.2		5.98			9.3			
30/11/10	1739-1749	23/Fine	Surface	1.0	23.1	30.5	30.5	5.86	5.83	81.5	81.1	5.57	5.58	5.71	9.0	8.9	8.9	
						30.4		5.80		80.6		5.59			8.8			
			Middle	5.5	23.0	30.5	30.6	5.81	5.80	80.8	80.7	5.62	5.65		5.65	8.6		8.7
						30.6		5.79		80.5		5.68			8.8			
			Bottom	11.0	22.9	30.8	30.9	5.72	5.71	79.5	79.4	5.90	5.91		5.91	9.0		9.0
						31.0		5.70		79.2		5.92			9.0			

Mid-Ebb Tide

Monitoring Station : R28

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/11/10	0936-0949	20/Fine	Surface	1.0	21.9	30.3	30.3	6.12	6.15	85.7	86.1	4.86	4.84	4.95	7.6	7.7	8.0
				5.1		30.2		6.01		84.1		4.81			8.0		
			9.2	22.2	30.8	6.02	84.3	4.96	8.2								
04/11/10	1008-1023	21/Cloudy	Surface	1.0	24.3	30.9	30.9	5.86	5.84	81.4	84.1	5.76	5.78	5.92	8.6	8.7	8.9
				5.2		30.9		5.82		86.8		5.80			8.8		
			9.4	23.2	31.0	5.77	80.2	5.88	9.0								
06/11/10	1122-1135	18/Rainy	Surface	1.0	20.5	29.3	29.3	6.02	6.05	84.3	84.7	5.09	5.07	5.16	8.2	8.1	8.3
				5.3		30.1		5.94		83.2		5.16			8.4		
			9.6	22.8	30.2	5.95	83.3	5.13	8.4								
09/11/10	1511-1522	20/Fine	Surface	1.0	24.2	31.3	31.3	5.99	5.97	83.2	83.0	5.10	5.08	5.17	8.2	8.1	8.3
				5.7		31.9		5.84		82.7		5.05			8.0		
			10.4	23.0	32.0	5.80	81.1	5.02	8.2								
11/11/10	1709-1720	25/Fine	Surface	1.0	21.2	31.7	31.6	6.22	6.20	88.8	88.8	5.14	5.17	5.65	8.2	8.2	8.8
				6.5		31.5		6.18		88.7		5.19			9.4		
			12.0	20.7	31.9	6.07	86.6	5.92	9.4								
13/11/10	0722-0735	20/Fine	Surface	1.0	21.6	30.6	30.6	6.14	6.13	85.3	85.2	5.04	5.06	5.13	8.0	8.0	8.2
				5.1		30.5		6.12		85.1		5.08			8.0		
			9.2	20.4	31.1	6.07	84.4	5.14	8.2								
16/11/10	1028-1042	23/Cloudy	Surface	1.0	22.3	30.4	30.3	6.04	6.03	84.0	83.6	5.04	5.07	5.16	8.0	8.1	8.2
				5.2		30.2		6.02		83.1		5.09			8.1		
			9.8	21.2	30.7	5.99	83.7	5.17	8.3								
18/11/10	1004-1020	23/Fine	Surface	1.0	24.3	30.8	30.8	5.82	5.85	80.8	81.2	5.42	5.45	5.65	8.6	8.7	9.1
				5.3		30.8		5.87		81.5		5.48			8.8		
			9.6	23.4	30.9	5.84	81.1	5.67	9.2								
20/11/10	1108-1122	23/Sunny	Surface	1.0	23.1	30.5	30.6	6.04	6.04	84.0	83.9	4.99	5.00	5.05	7.8	7.9	8.2
				5.3		30.7		6.03		83.8		5.00			8.0		
			9.6	21.5	31.0	5.98	83.1	5.04	8.2								
23/11/10	1452-1505	24/Fine	Surface	1.0	24.1	30.9	30.8	5.87	5.87	81.6	81.6	5.44	5.46	5.65	8.9	8.9	9.2
				4.8		30.7		5.86		81.5		5.47			8.8		
			9.5	23.5	30.8	5.84	81.2	5.62	9.2								
25/11/10	1431-1445	24/Fine	Surface	1.0	23.9	30.7	30.8	5.84	5.86	81.2	81.4	5.43	5.45	5.64	8.9	9.1	9.3
				4.8		30.9		5.87		81.6		5.47			9.2		
			9.5	23.5	30.8	5.84	81.2	5.60	9.5								
27/11/10	1710-1726	23/Fine	Surface	1.0	24.0	31.0	31.0	5.84	5.82	81.1	80.9	5.53	5.56	5.75	9.0	9.0	8.9
				5.2		31.0		5.80		80.6		5.58			8.9		
			9.4	23.3	31.5	5.82	80.8	5.71	8.6								
30/11/10	1944-1956	23/Fine	Surface	1.0	23.6	30.9	30.8	5.87	5.87	81.6	81.6	5.45	5.46	5.65	8.9	9.1	9.3
				5.2		30.7		5.86		81.5		5.46			9.2		
			10.3	22.7	30.7	5.84	81.2	5.64	9.5								

Mid-Ebb Tide

Monitoring Station : R29

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
			Surface			Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/11/10	0952-1005	20/Fine	Surface	1.0	22.2	30.4	30.5	6.06	6.08	84.8	85.1	4.84	4.83	4.95	7.8	7.9	8.1
				8.4		20.7		30.7		5.93		83.0			83.0		
			Bottom	15.8	22.0	30.8	5.92	82.9	82.0	4.96	8.0						
04/11/10	1028-1043	21/Cloudy	Surface	1.0	24.3	31.3	31.0	5.84	5.84	80.8	80.6	5.92	5.95	6.14	8.8	8.9	9.2
				8.4		23.6		31.3		5.76		80.2			80.3		
			Bottom	15.8	22.8	31.9	5.65	78.6	78.7	6.27	9.5						
06/11/10	1138-1153	18/Rainy	Surface	1.0	20.3	29.3	29.4	5.94	5.95	83.2	83.3	5.12	5.13	5.15	8.2	8.2	8.2
				8.6		21.6		29.4		5.96		83.4			84.7		
			Bottom	16.2	22.7	30.2	6.02	85.0	82.2	5.06	8.6						
09/11/10	1536-1547	20/Fine	Surface	1.0	24.2	31.3	31.3	6.03	6.05	83.8	84.1	4.94	4.92	5.08	7.9	8.0	8.1
				8.6		23.4		31.9		5.92		82.2			81.9		
			Bottom	16.2	23.0	31.9	5.87	81.5	79.0	5.16	8.2						
11/11/10	1735-1745	25/Fine	Surface	1.0	21.4	31.7	31.7	6.11	6.12	86.9	86.9	5.19	5.20	5.40	8.2	8.3	8.7
				7.3		20.8		31.9		6.00		85.7			85.7		
			Bottom	13.5	20.3	31.9	5.99	85.6	83.9	5.14	8.4						
13/11/10	0738-0751	20/Fine	Surface	1.0	21.5	30.5	30.5	6.12	6.13	85.1	85.2	5.12	5.14	5.19	8.5	8.5	8.4
				8.4		20.5		30.4		6.14		85.3			83.8		
			Bottom	15.8	20.3	31.0	6.03	83.7	81.6	5.26	8.2						
16/11/10	1049-1102	23/Cloudy	Surface	1.0	22.3	30.2	30.3	5.82	5.83	80.9	81.1	5.11	5.13	5.15	8.2	8.2	8.3
				8.7		21.9		30.4		5.84		81.2			83.0		
			Bottom	16.4	20.9	30.7	5.97	83.3	81.4	5.09	8.6						
18/11/10	1026-1041	23/Fine	Surface	1.0	24.4	30.8	30.8	5.77	5.75	80.2	79.9	5.73	5.76	5.99	9.0	9.1	9.3
				8.4		23.8		31.0		5.68		79.6			78.9		
			Bottom	15.8	22.9	31.0	5.68	78.9	78.9	5.99	9.5						
20/11/10	1128-1142	23/Sunny	Surface	1.0	23.3	30.4	30.7	6.02	6.03	83.7	83.8	5.01	5.02	5.11	7.9	7.9	8.1
				8.2		22.8		30.9		5.99		83.8			83.2		
			Bottom	16.4	21.5	31.0	5.99	83.3	81.1	5.10	8.2						
23/11/10	1513-1527	24/Fine	Surface	1.0	24.2	30.8	30.9	5.77	5.77	80.2	80.2	5.74	5.73	5.95	8.8	8.7	9.1
				7.9		24.1		30.9		5.76		80.1			79.6		
			Bottom	15.7	23.9	31.2	5.74	79.8	78.6	5.92	9.2						
25/11/10	1452-1506	24/Fine	Surface	1.0	24.1	30.8	30.7	5.88	5.87	81.8	81.8	5.74	5.75	5.97	9.8	9.7	9.4
				7.9		23.9		30.6		5.86		81.7			80.6		
			Bottom	15.7	23.4	31.0	5.74	80.9	78.8	5.92	8.9						
27/11/10	1730-1746	23/Fine	Surface	1.0	24.1	31.1	31.1	5.95	5.93	82.9	82.4	5.91	5.94	6.13	9.5	9.5	9.4
				8.3		23.5		31.0		5.90		81.8			80.1		
			Bottom	15.6	23.0	31.7	5.78	80.4	78.5	6.11	9.6						
30/11/10	2004-2016	23/Fine	Surface	1.0	23.1	30.8	30.8	5.80	5.80	80.6	80.6	5.72	5.73	5.85	9.8	9.7	9.4
				8.2		23.1		30.7		5.79		80.5			79.2		
			Bottom	16.4	22.7	31.0	5.71	79.4	78.7	5.86	8.9						

Monitoring Station : C1

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)				
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average		
02/11/10	0824-0837	19/Fine	Surface	1.0	21.8	30.3	30.3	6.12	6.13	85.7	85.9	4.96	4.95	5.03	8.0	8.0	8.1		
						30.2		6.14		86.0		4.94			8.0				
			Middle	7.0	20.8	30.7	30.8	6.04	6.06	84.6	84.8	5.04	5.03		5.01	5.03		8.0	8.1
						30.8		6.07		85.0		5.01			8.2				
			Bottom	13.0	21.9	31.2	31.3	5.91	5.92	82.7	82.9	5.10	5.12		5.12	5.12		8.4	8.2
						31.3		5.93		83.0		5.13			8.0				
04/11/10	0903-0918	20/Cloudy	Surface	1.0	24.3	30.9	30.9	5.93	5.91	82.4	82.1	5.80	5.83	5.96	8.5	8.7	8.9		
						30.9		5.88		81.7		5.85			8.8				
			Middle	6.9	23.8	31.2	31.2	5.79	5.82	86.4	83.9	5.91	5.94		5.97	5.94		9.0	8.9
						31.2		5.85		81.3		5.97			8.8				
			Bottom	12.8	23.1	31.6	31.6	5.69	5.73	79.0	79.5	6.08	6.10		6.12	6.10		9.1	9.1
						31.6		5.77		80.0		6.12			9.0				
06/11/10	1009-1022	18/Rainy	Surface	1.0	20.6	29.0	29.1	5.98	6.00	83.7	83.9	5.02	5.03	5.13	7.8	7.9	8.1		
						29.1		6.01		84.1		5.03			8.0				
			Middle	7.1	21.4	30.2	30.2	5.88	5.87	82.3	82.1	5.11	5.13		5.14	5.13		8.2	8.3
						30.1		5.85		81.9		5.14			8.4				
			Bottom	13.2	22.5	31.8	31.9	5.94	5.95	83.2	83.3	5.24	5.23		5.22	5.23		8.0	8.0
						31.9		5.96		83.4		5.22			8.0				
09/11/10	1400-1412	20/Fine	Surface	1.0	24.0	31.1	31.2	6.01	6.03	83.5	83.8	4.98	4.96	5.06	7.9	8.0	8.1		
						31.2		6.05		84.0		4.93			8.0				
			Middle	7.1	23.2	31.9	31.9	5.83	5.80	81.0	80.6	5.09	5.05		5.01	5.05		8.2	8.1
						31.9		5.77		80.2		5.01			8.0				
			Bottom	13.2	23.0	32.4	32.4	5.70	5.72	78.6	78.9	5.18	5.17		5.15	5.17		8.4	8.4
						32.4		5.74		79.2		5.15			8.3				
11/11/10	1610-1622	25/Fine	Surface	1.0	20.9	32.2	32.2	6.22	6.24	89.0	89.1	5.16	5.14	5.16	8.4	8.4	8.3		
						32.2		6.25		89.2		5.12			8.4				
			Middle	7.2	20.7	32.5	32.5	6.05	6.07	86.4	86.7	5.10	5.15		5.19	5.15		8.0	8.1
						32.5		6.08		87.0		5.19			8.2				
			Bottom	13.4	20.4	32.9	32.9	6.00	5.96	85.7	84.9	5.22	5.18		5.14	5.18		8.4	8.3
						32.9		5.92		84.0		5.14			8.2				
13/11/10	0609-0622	20/Fine	Surface	1.0	21.5	30.5	30.5	6.14	6.13	85.3	85.2	5.04	5.06	5.14	7.8	7.9	8.2		
						30.4		6.12		85.1		5.07			8.0				
			Middle	6.9	20.5	31.3	31.3	6.02	6.03	83.7	83.8	5.16	5.15		5.14	5.15		8.4	8.3
						31.2		6.03		83.8		5.14			8.2				
			Bottom	12.8	20.7	32.1	32.2	5.93	5.94	82.4	82.5	5.21	5.22		5.22	5.22		8.5	8.5
						32.2		5.94		82.6		5.22			8.5				
16/11/10	0901-0915	22.8/Rainy	Surface	1.0	21.3	29.2	29.1	5.97	5.98	83.0	83.1	5.02	5.03	5.13	7.8	7.9	8.0		
						29.0		5.98		83.1		5.04			8.0				
			Middle	7.5	20.3	30.0	30.1	5.82	5.84	80.9	81.1	5.10	5.12		5.14	5.12		8.0	8.1
						30.2		5.85		81.3		5.14			8.2				
			Bottom	13.5	20.3	31.8	31.8	5.94	5.95	82.6	82.4	5.22	5.24		5.24	5.24		8.2	8.1
						31.8		5.95		82.1		5.25			8.0				
18/11/10	0856-0912	22/Cloudy	Surface	1.0	24.2	30.6	30.7	5.96	5.93	82.8	82.4	5.36	5.33	5.58	8.5	8.5	8.9		
						30.7		5.90		82.0		5.30			8.5				
			Middle	9.6	23.8	31.0	31.0	5.80	5.82	80.6	80.9	5.55	5.58		5.60	5.58		9.0	9.1
						31.0		5.84		81.1		5.60			9.2				
			Bottom	12.8	23.3	31.6	31.6	5.66	5.67	78.6	78.7	5.81	5.84		5.87	5.84		9.0	9.0
						31.6		5.68		78.8		5.81			9.0				
20/11/10	0943-0958	23/Sunny	Surface	1.0	23.0	30.8	30.8	6.02	6.02	83.7	83.6	5.11	5.12	5.15	8.0	8.0	8.3		
						30.7		6.01		83.5		5.12			8.0				
			Middle	6.6	22.8	30.9	31.2	5.99	5.98	83.3	83.2	5.09	5.12		5.14	5.12		8.2	8.4
						31.4		5.97		83.0		5.14			8.5				
			Bottom	13.1	22.0	31.2	31.2	5.86	5.86	81.5	81.5	5.22	5.23		5.24	5.23		8.8	8.7
						31.1		5.86		81.5		5.24			8.5				
23/11/10	1335-1355	24/Fine	Surface	1.0	24.0	30.2	30.3	5.89	5.88	81.9	81.7	5.72	5.76	5.97	9.2	9.1	9.3		
						30.4		5.86		81.5		5.80			9.0				
			Middle	6.4	23.9	31.0	31.2	5.74	5.72	79.8	79.5	5.94	5.96		5.98	5.96		9.4	9.3
						31.4		5.70		79.2		5.98			9.2				
			Bottom	12.7	23.3	31.2	31.4	5.68	5.68	78.9	78.9	6.12	6.18		6.12	6.18		9.5	9.5
						31.6		5.68		78.8		6.24			9.5				
25/11/10	1311-1331	24/Fine	Surface	1.0	24.1	30.2	30.3	5.94	5.95	82.6	82.7	5.32	5.33	5.57	8.6	8.5	9.0		
						30.4		5.95		82.7		5.34			8.4				
			Middle	5.9	23.8	31.2	31.2	5.84	5.83	81.2	81.1	5.54	5.57		5.60	5.57		9.0	8.9
						31.1		5.82		80.9		5.60			8.8				
			Bottom	11.7	23.2	31.7	31.7	5.66	5.67	78.7	78.8	5.82	5.82		5.81	5.82		9.4	9.5
						31.6		5.67		78.8		5.81			9.5				
27/11/10	1604-1619	23/Fine	Surface	1.0	24.0	30.9	31.0	5.90	5.88	82.0	81.7	5.63	5.66	5.84	9.0	9.0	9.1		
						31.0		5.85		81.3		5.68			9.0				
			Middle	6.9	23.7	31.5	31.6	5.78	5.75	80.3	79.9	5.85	5.88		5.90	5.88		9.4	9.3
						31.6		5.72		79.5		5.90			9.2				
			Bottom	12.8	23.2	32.1	32.1	5.66	5.67	78.6	78.7	5.92	5.98		6.03	5.98		9.0	8.9
						32.1		5.67		78.8		6.03			8.8				
30/11/10	1840-1852	23/Fine	Surface	1.0	23.9	30.1	30.2	5.88	5.88	81.7	81.7	5.74	5.77	5.90	8.6	8.5	9.0		
						30.2		5.87		81.6		5.80			8.4				
			Middle	6.4	23.3	30.8	30.9	5.72	5.73	79.5	79.7	5.92	5.93		5.94	5.93		9.0	8.9
						30.9		5.74		79.8		5.94			8.8				
			Bottom	12.7	23.3	31.0	31.0	5.67	5.68	78.8	78.9	5.98	5.99		6.00	5.99		9.4	9.5
						30.9		5.69		79.0		6.00			9.5				

Monitoring Station : C3

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)			
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average	
02/11/10	0849-0901	19/Fine	Surface	1.0	21.9	30.4	30.4	6.10	6.08	85.4	85.1	4.87	4.88	4.98	7.6	7.6	7.9	
						30.3		6.06		84.8		4.89			7.6			
			Middle	6.3	20.9	30.9	30.9	5.95	5.94	83.3	83.1	4.99	4.98		7.5	7.9		8.0
						30.8		5.92		82.9		4.98			8.0			
			Bottom	11.6	21.7	31.1	31.2	5.84	5.85	81.8	81.9	5.09	5.06		8.2	8.1		8.0
						31.2		5.86		82.0		5.06			8.0			
04/11/10	0926-0940	20/Cloudy	Surface	1.0	24.3	31.0	31.0	5.81	5.83	80.7	81.0	5.77	5.81	5.99	8.6	8.7	9.1	
						31.0		5.85		81.3		5.84			8.8			
			Middle	6.3	23.7	31.3	31.3	5.78	5.76	80.3	80.0	5.99	6.05		9.0	9.1		9.2
						31.3		5.74		79.7		6.05			9.2			
			Bottom	11.6	23.2	31.7	31.7	5.66	5.67	78.6	78.5	6.11	6.15		9.4	9.4		9.4
						31.7		5.68		78.3		6.15			9.4			
06/11/10	1034-1047	18/Rainy	Surface	1.0	20.5	29.2	29.2	5.99	5.98	83.9	83.7	4.97	4.95	5.07	8.0	7.9	8.1	
						29.1		5.96		83.4		4.93			7.8			
			Middle	6.5	21.5	30.1	30.1	5.85	5.83	81.9	81.6	5.04	5.03		8.2	8.1		8.0
						30.0		5.81		81.3		5.03			8.0			
			Bottom	12.0	22.6	31.8	31.8	5.80	5.81	81.2	81.4	5.21	5.24		8.4	8.4		8.4
						31.7		5.82		81.5		5.24			8.4			
09/11/10	1425-1437	20/Fine	Surface	1.0	24.0	31.1	31.1	5.95	5.93	82.7	82.4	5.18	5.16	5.27	8.2	8.2	8.4	
						31.1		5.91		82.1		5.14			8.2			
			Middle	6.4	23.3	31.9	31.9	5.68	5.66	78.3	78.1	5.27	5.21		8.4	8.2		8.0
						31.8		5.64		77.8		5.21			8.0			
			Bottom	11.8	23.3	32.4	32.4	5.70	5.72	78.6	79.1	5.43	5.38		9.0	8.9		8.8
						32.3		5.73		79.6		5.38			8.8			
11/11/10	1632-1644	25/Fine	Surface	1.0	20.9	32.5	32.5	6.15	6.17	88.7	88.4	5.10	5.11	5.14	8.3	8.3	8.2	
						32.5		6.18		88.0		5.11			8.2			
			Middle	7.3	20.7	32.2	32.6	6.11	6.06	87.8	86.9	5.12	5.12		8.0	8.0		8.0
						32.9		6.01		86.0		5.12			8.0			
			Bottom	13.6	20.1	32.9	33.0	6.00	5.98	85.7	85.1	5.19	5.22		8.4	8.3		8.2
						33.0		5.95		84.4		5.22			8.2			
13/11/10	0634-0647	20/Fine	Surface	1.0	21.5	30.6	30.6	6.03	6.02	83.8	83.7	4.97	4.96	5.05	8.0	8.0	8.1	
						30.5		6.01		83.5		4.95			7.9			
			Middle	6.3	20.6	31.2	31.2	5.96	5.94	82.8	82.6	5.06	5.03		8.2	8.1		8.0
						31.1		5.92		82.3		5.03			8.0			
			Bottom	11.6	20.4	32.2	32.2	5.84	5.86	81.2	81.4	5.16	5.11		8.4	8.3		8.2
						32.1		5.87		81.6		5.11			8.2			
16/11/10	0927-0941	22.8/Rainy	Surface	1.0	21.8	29.1	29.1	5.98	5.99	83.1	82.9	4.98	4.96	5.07	8.0	8.1	8.3	
						29.1		5.99		82.7		4.94			8.2			
			Middle	6.7	20.9	30.9	30.8	5.84	5.85	81.2	81.4	5.02	5.03		8.4	8.4		8.3
						30.7		5.86		81.5		5.03			8.3			
			Bottom	12.0	20.6	31.7	31.8	5.80	5.80	80.6	80.6	5.22	5.24		8.4	8.4		8.3
						31.8		5.80		80.6		5.24			8.3			
18/11/10	0920-0935	22/Cloudy	Surface	1.0	24.3	30.7	30.7	5.88	5.86	81.7	81.4	5.39	5.42	5.66	8.4	8.5	9.0	
						30.7		5.84		81.1		5.44			8.5			
			Middle	6.3	24.0	30.9	30.9	5.80	5.78	80.6	80.3	5.71	5.66		9.2	9.1		9.0
						30.9		5.76		80.0		5.66			9.0			
			Bottom	11.6	23.5	31.5	31.6	5.68	5.69	78.9	79.0	5.84	5.89		9.4	9.4		9.4
						31.6		5.69		79.1		5.89			9.4			
20/11/10	1012-1026	23/Sunny	Surface	1.0	23.3	30.4	30.6	6.00	6.03	83.4	83.8	5.10	5.12	5.16	8.2	8.2	8.3	
						30.7		6.05		84.1		5.14			8.2			
			Middle	6.1	22.8	30.9	31.0	5.98	5.99	83.1	83.2	5.09	5.12		8.0	8.2		8.4
						31.0		5.99		83.3		5.12			8.4			
			Bottom	12.1	22.1	31.1	31.3	5.84	5.83	81.2	81.1	5.24	5.25		8.5	8.6		8.6
						31.4		5.82		80.9		5.25			8.6			
23/11/10	1405-1416	24/Fine	Surface	1.0	24.1	30.6	30.7	5.89	5.90	81.9	82.0	5.40	5.41	5.65	8.7	8.8	9.1	
						30.7		5.90		82.0		5.42			8.9			
			Middle	5.8	23.8	31.4	31.2	5.80	5.80	80.6	80.6	5.72	5.70		9.2	9.1		9.0
						30.9		5.79		80.5		5.70			9.0			
			Bottom	11.6	23.3	31.7	31.7	5.69	5.69	79.1	79.0	5.80	5.84		9.4	9.3		9.1
						31.6		5.68		78.8		5.88			9.1			
25/11/10	1342-1353	24/Fine	Surface	1.0	24.1	30.1	30.2	5.87	5.87	81.6	81.6	5.40	5.40	5.65	8.8	8.6	8.8	
						30.2		5.86		81.5		5.39			8.4			
			Middle	5.9	24.0	31.1	31.3	5.80	5.77	80.6	80.2	5.72	5.70		8.6	8.6		8.6
						31.4		5.74		79.8		5.70			8.6			
			Bottom	11.7	23.3	31.4	31.6	5.69	5.70	79.1	79.2	5.85	5.86		9.0	9.1		9.2
						31.7		5.70		79.2		5.86			9.2			
27/11/10	1626-1642	23/Fine	Surface	1.0	24.1	31.0	31.0	5.88	5.86	81.7	81.4	5.56	5.58	5.80	9.0	9.1	9.3	
						31.0		5.83		81.0		5.60			9.2			
			Middle	6.3	23.7	31.5	31.5	5.76	5.73	80.0	79.6	5.86	5.83		9.4	9.3		9.2
						31.5		5.70		79.2		5.80			9.2			
			Bottom	11.6	23.2	32.1	32.1	5.68	5.68	78.9	78.8	5.96	6.01		9.5	9.5		9.4
						32.1		5.67		78.7		6.01			9.4			
30/11/10	1900-1911	23/Fine	Surface	1.0	23.8	30.6	30.7	5.87	5.88	81.6	81.7	5.41	5.42	5.63	8.8	8.6	8.8	
						30.7		5.88		81.7		5.42			8.4			
			Middle	6.1	23.7	30.9	31.0	5.81	5.80	80.8	80.7	5.71	5.70		8.6	8.6		8.6
						31.0		5.79		80.5		5.70			8.6			
			Bottom	12.1	23.1	31.2	31.2	5.69	5.69	79.1	79.0	5.78	5.77		9.0	9.1		9.2
						31.2		5.68		78.9		5.77			9.2			




Appendix C3


Graphical Plots of Impact Water Quality Monitoring Data



Dissolved Oxygen (Surface) at Mid-Flood Tide




Dissolved Oxygen (Surface) at Mid-Ebb Tide






Dissolved Oxygen (Middle) at Mid-Flood Tide




Dissolved Oxygen (Middle) at Mid-Ebb Tide






Dissolved Oxygen (Middle) at Mid-Flood Tide




Dissolved Oxygen (Middle) at Mid-Ebb Tide






Dissolved Oxygen (Bottom) at Mid-Flood Tide




Dissolved Oxygen (Bottom) at Mid-Ebb Tide






Dissolved Oxygen (Bottom) at Mid-Flood Tide




Dissolved Oxygen (Bottom) at Mid-Ebb Tide






Turbidity (Depth-average) at Mid-Flood Tide




Turbidity (Depth-average) at Mid-Ebb Tide








Turbidity (Depth-average) of R15 at Mid-Flood Tide




Turbidity (Depth-average) of R15 at Mid-Ebb Tide








Suspended solids (Depth-average) of R15 at Mid-Flood Tide



Suspended Solids (Depth-average) of R15 at Mid-Ebb Tide





Appendix C4

QA/QC Results of Laboratory Analysis for Water Samples



QA/QC Results of Laboratory Analysis of Total Suspended Solids

Sampling Date	QC Sample	Sample Duplicate		Sample Spike	
	% Recovery *	Sample ID	% Error #	Sample ID	% Recovery @
02/11/10	92.0	R5FS	2.47	R8FS	105.9
	98.3	R8FM	6.06	R17FM	103.8
	93.5	R17FB	2.47	C1FB	101.9
	100.8	C2FS	5.13	C4FB	102.0
	92.4	R5ES	0.00	R8ES	102.1
	107.8	R8EM	0.00	R17EM	95.7
	103.9	R17EB	6.45	C1EB	105.9
	98.6	C2ES	6.45	C4EB	93.9
04/11/10	100.8	R5FS	3.77	R8FS	100.0
	94.4	R8FM	2.53	R17FM	94.2
	103.5	R17FB	3.82	C1FB	98.0
	99.6	C2FS	0.00	C4FB	98.0
	98.8	R5ES	2.25	R8ES	101.9
	97.8	R8EM	2.20	R17EM	104.3
	97.4	R17EB	5.41	C1EB	102.1
	103.5	C2ES	2.90	C4EB	96.1
06/11/10	97.9	R5FS	5.41	R8FS	100.0
	98.4	R8FM	2.20	R17FM	102.0
	102.9	R17FB	0.00	C1FB	93.9
	98.3	C2FS	1.06	C4FB	100.0
	97.5	R5ES	2.53	R8ES	106.0
	94.8	R8EM	2.47	R17EM	106.2
	93.9	R17EB	3.47	C1EB	108.3
	99.4	C2ES	6.45	C4EB	102.0
09/11/10	105.6	R5FS	3.08	R8FS	88.5
	102.1	R8FM	2.99	R17FM	107.7
	96.4	R17FB	2.53	C1FB	100.0
	107.0	C2FS	6.06	C4FB	107.5
	102.4	R5ES	1.32	R8ES	112.0
	97.8	R8EM	8.00	R17EM	94.1
	96.7	R17EB	2.20	C1EB	93.7
	107.2	C2ES	0.00	C4EB	107.7
11/11/10	101.6	R5FS	0.00	R8FS	104.2
	98.5	R8FM	1.32	R17FM	100.0
	94.8	R17FB	6.90	C1FB	103.9
	94.9	C2FS	6.45	C4FB	94.3
	99.2	R5ES	2.38	R8ES	101.9
	97.7	R8EM	0.00	R17EM	94.2
	95.2	R17EB	5.41	C1EB	98.1
	94.3	C2ES	1.24	C4EB	91.8
13/11/10	102.0	R5FS	3.64	R8FS	96.1
	95.7	R8FM	1.44	R17FM	104.3
	102.1	R17FB	6.90	C1FB	94.2
	101.0	C2FS	7.41	C4FB	97.9
	104.7	R5ES	2.53	R8ES	94.1
	94.3	R8EM	1.17	R17EM	96.0
	104.7	R17EB	3.59	C1EB	102.0
	104.5	C2ES	3.17	C4EB	106.0

Note: (*) % Recovery of QC sample should be between 80% to 120%.
 (#) % Error of Sample Duplicate should be between -10% to 10%.
 (@) % Recovery of Sample Spike should be between 80% to 120%.



QA/QC Results of Laboratory Analysis of Total Suspended Solids

Sampling Date	QC Sample	Sample Duplicate		Sample Spike	
	% Recovery *	Sample ID	% Error #	Sample ID	% Recovery @
16/11/10	103.8	R5FS	3.17	R8FS	95.8
	102.8	R8FM	2.20	R17FM	102.1
	98.7	R17FB	6.45	C1FB	97.9
	95.6	C2FS	3.08	C4FB	91.7
	96.9	R5ES	2.47	R8ES	100.0
	93.6	R8EM	1.26	R17EM	95.7
	93.5	R17EB	6.06	C1EB	100.0
	102.0	C2ES	6.90	C4EB	94.3
18/11/10	106.7	R5FS	2.67	R8FS	95.8
	100.0	R8FM	2.25	R17FM	94.1
	98.8	R17FB	0.00	C1FB	102.0
	97.1	C2FS	2.20	C4FB	108.3
	104.8	R5ES	3.21	R8ES	103.9
	102.5	R8EM	5.41	R17EM	106.2
	93.3	R17EB	1.06	C1EB	106.1
	92.5	C2ES	4.35	C4EB	106.3
20/11/10	95.5	R5FS	2.82	R8FS	95.7
	104.1	R8FM	96.4	R17FM	102.0
	102.4	R17FB	2.47	C1FB	98.1
	93.7	C2FS	3.68	C4FB	97.9
	92.4	R5ES	2.47	R8ES	96.0
	94.3	R8EM	3.08	R17EM	95.9
	105.0	R17EB	3.59	C1EB	102.0
	103.0	C2ES	2.53	C4EB	98.0
23/11/10	103.4	R5FS	3.47	R8FS	95.9
	101.5	R8FM	3.59	R17FM	94.2
	92.5	R17FB	1.18	C1FB	103.9
	94.8	C2FS	2.99	C4FB	95.8
	103.1	R5ES	3.21	R8ES	96.2
	98.0	R8EM	2.90	R17EM	96.2
	106.8	R17EB	3.21	C1EB	102.1
	96.3	C2ES	1.17	C4EB	98.0
25/11/10	105.5	R5FS	2.99	R8FS	95.9
	103.2	R8FM	2.47	R17FM	104.3
	103.5	R17FB	3.17	C1FB	107.5
	103.5	C2FS	6.06	C4FB	97.9
	97.9	R5ES	3.21	R8ES	93.9
	102.3	R8EM	1.10	R17EM	93.6
	94.8	R17EB	2.20	C1EB	93.6
	98.1	C2ES	4.55	C4EB	107.8
27/11/10	94.0	R5FS	2.47	R8FS	90.4
	105.8	R8FM	1.26	R17FM	98.0
	93.3	R17FB	2.47	C1FB	104.0
	94.6	C2FS	3.59	C4FB	104.1
	104.3	R5ES	3.21	R8ES	93.9
	97.1	R8EM	1.05	R17EM	102.0
	107.8	R17EB	3.21	C1EB	106.0
	97.6	C2ES	4.55	C4EB	98.1

Note: (*) % Recovery of QC sample should be between 80% to 120%.
 (#) % Error of Sample Duplicate should be between -10% to 10%.
 (@) % Recovery of Sample Spike should be between 80% to 120%.



QA/QC Results of Laboratory Analysis of Total Suspended Solids

Sampling Date	QC Sample	Sample Duplicate		Sample Spike	
	% Recovery *	Sample ID	% Error #	Sample ID	% Recovery @
30/11/10	101.2	R5FS	2.43	R8FS	98.0
	105.2	R8FM	1.18	R17FM	106.1
	96.7	R17FB	2.25	C1FB	95.8
	104.4	C2FS	1.24	C4FB	92.3
	102.6	R5ES	3.21	R8ES	103.8
	96.3	R8EM	1.10	R17EM	104.2
	100.8	R17EB	2.20	C1EB	100.0
	92.5	C2ES	4.55	C4EB	98.0

Note: (*) % Recovery of QC sample should be between 80% to 120%.
(#) % Error of Sample Duplicate should be between -10% to 10%.
(@) % Recovery of Sample Spike should be between 80% to 120%.



Appendix D

Event-Action Plans



Event and Action Plan for Construction Noise

Event	Action			
	ET Leader	IEC	ER	Contractor
Action Level	<ol style="list-style-type: none"> 1. Notify IEC and the Contractor. 2. Carry out investigation. 3. Report the results of investigation to IEC and the Contractor. 4. Discuss with the Contractor and formulate remedial measures. 5. Increase monitoring frequency to check mitigation measures. 	<ol style="list-style-type: none"> 1. Review with analysed results submitted by ET. 2. Review the proposed remedial measures by the Contractor and advise ER accordingly. 3. Supervise the implement of remedial measures. 	<ol style="list-style-type: none"> 1. Confirm receipt of notification of exceedance in writing. 2. Notify the Contractor. 3. Require the Contractor to propose remedial measures for the analysed noise problem. 4. Ensure remedial measures are properly implemented. 	<ol style="list-style-type: none"> 1. Submit noise mitigation proposals to IEC. 2. Implement noise mitigation proposals.
Limit Level	<ol style="list-style-type: none"> 1. Identify the source. 2. Notify IEC, ER, EPD and the Contractor. 3. Repeat measurement to confirm findings. 4. Increase monitoring frequency. 5. Carry out analysis of Contractor's working procedures to determine possible mitigation to be implemented. 6. Inform IEC, ER, and EPD the causes & actions taken for the exceedances. 7. Assess effectiveness of the Contractor's remedial actions and keep IEC, EPD and ER informed of the results. 8. If exceedance stops, cease additional monitoring. 	<ol style="list-style-type: none"> 1. Discuss amongst ER, ET Leader and the Contractor on the potential remedial actions. 2. Review the Contractor's remedial actions whenever necessary to assure their effectiveness and advise ER accordingly. 3. Supervise the implementation of remedial measures. 	<ol style="list-style-type: none"> 1. Confirm receipt of notification of exceedance in writing. 2. Notify the Contractor. 3. Require the Contractor to propose remedial measures for the analysed noise problem. 4. Ensure remedial measures are properly implemented. 5. If exceedance continues, consider what activity of the work is responsible and instruct the Contractor to stop that activity of work until the exceedance is abated. 	<ol style="list-style-type: none"> 1. Take immediate action to avoid further exceedance. 2. Submit proposals for remedial actions to IEC within 3 working days of notification. 3. Implement the agreed proposals. 4. Resubmit proposals if problem still not under control. 5. Stop the relevant activity of works as determined by the ER until the exceedance is abated.



Event and Action Plan for Water Quality for Construction Phase

Event	Action			
	ET Leader	IEC	ER	Contractor
Action Level				
Exceedance for one sample	<ol style="list-style-type: none"> 1. Repeat in-situ measurement to confirm finding; 2. Identify source(s) of impact; 3. Inform IEC and Contractor; 4. Check monitoring data, all plant, equipment and Contractor's working methods; 5. Discuss mitigation measures with IEC and Contractor; and 6. Repeat measurement on next day of exceedance. 	<ol style="list-style-type: none"> 1. Discuss with ET and Contractor on the mitigation measures; 2. Review proposals on mitigation measures submitted by Contractor and advise the ER accordingly; and 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Discuss with IEC on the proposed mitigation measures; and 2. Make agreement on the mitigation measures to be implemented. 	<ol style="list-style-type: none"> 1. Inform the ER and confirm notification of the non-compliance in writing; 2. Rectify unacceptable practice; 3. Check all plant and equipment; 4. Consider changes of working methods; 5. Discuss with ET and IEC and propose mitigation measures to IEC and ER; and 6. Implement the agreed mitigation measures.
Exceedance for two or more consecutive samples	<ol style="list-style-type: none"> 1. Repeat in-situ measurement to confirm finding; 2. Identify source(s) of impact; 3. Inform IEC and Contractor; 4. Check monitoring data, all plant, equipment and Contractor's working methods; 5. Discuss mitigation measures with IEC and Contractor; 6. Ensure mitigation measures are implemented; 7. Prepare to increase the monitoring frequency to daily; and 8. Repeat measurement on next day of exceedance. 	<ol style="list-style-type: none"> 1. Discuss with ET and Contractor on the mitigation measures; 2. Review proposals on mitigation measures submitted by Contractor and advise the ER accordingly; and 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Discuss with IEC on the proposed mitigation measures; 2. Make agreement on the mitigation measures to be implemented; and 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Inform the Engineer and confirm notification of the non-compliance in writing; 2. Rectify unacceptable practice; 3. Check all plant and equipment; 4. Consider changes of working methods; 5. Discuss with ET and IEC and propose mitigation measures to IEC and ER within 3 working days; and 6. Implement the agreed mitigation measures.




Event and Action Plan for Water Quality for Construction Phase

Event	Action			
	ET Leader	IEC	ER	Contractor
Limit Level				
Exceedance for one sample	<ol style="list-style-type: none"> 1. Repeat in-situ measurement to confirm finding; 2. Identify source(s) of impact; 3. Inform IEC, Contractor and EPD; 4. Check monitoring data, all plant, equipment and Contractor's working methods; 5. Discuss mitigation measures with IEC, ER and Contractor; 6. Ensure mitigation measures are implemented; and 7. Increase the monitoring frequency to daily until no exceedance of Limit level. 	<ol style="list-style-type: none"> 1. Discuss with ET and Contractor on the mitigation measures; 2. Review proposals on mitigation measures submitted by Contractor and advise the ER accordingly; and 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Discuss with IEC, ET and Contractor on the proposed mitigation measures; and 2. Request Contractor to critically review the working methods; 3. Make agreement on the mitigation measures to be implemented; and 4. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Inform the Engineer and confirm notification of the non-compliance in writing; 2. Rectify unacceptable practice; 3. Check all plant and equipment; 4. Consider changes of working methods; 5. Discuss with ET and IEC and ER and propose mitigation measures to IEC and ER within 3 working days; and 6. Implement the agreed mitigation measures.
Exceedance for two or more consecutive samples	<ol style="list-style-type: none"> 1. Repeat in-situ measurement to confirm finding; 2. Identify source(s) of impact; 3. Inform IEC, Contractor and EPD; 4. Check monitoring data, all plant, equipment and Contractor's working methods; 5. Discuss mitigation measures with IEC, ER and Contractor; 6. Ensure mitigation measures are implemented; and 7. Increase the monitoring frequency to daily until no exceedance of Limit level for two consecutive days. 	<ol style="list-style-type: none"> 1. Discuss with ET and Contractor on the mitigation measures; 2. Review proposals on mitigation measures submitted by Contractor and advise the ER accordingly; and 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Discuss with IEC, ET and Contractor on the proposed mitigation measures; and 2. Request Contractor to critically review the working methods; 3. Make agreement on the mitigation measures to be implemented; 4. Assess the effectiveness of the implemented mitigation measures; and 5. Consider and instruct, if necessary, the Contractor to slow down or to stop all or part of the marine work until no exceedance of Limit Level. 	<ol style="list-style-type: none"> 1. Inform the ER and confirm notification of the non-compliance in writing; 2. Rectify unacceptable practice; 3. Check all plant and equipment; 4. Consider changes of working methods; 5. Discuss with ET and IEC and ER and propose mitigation measures to IEC and ER within 3 working days; 6. Implement the agreed mitigation measures; and 7. As directed by the Engineer, to slow down or to stop all or part of the marine work or construction activities.



Appendix E

Work Programme



3 Months Rolling Program (November 2010)

Task ID	Task Name	Start Date	End Date	Duration (Days)	Start Month	End Month	Start Week	End Week	Task Status	Task Priority
151	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
152	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
153	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
154	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
155	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
156	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
157	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
158	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
159	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
160	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
161	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
162	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
163	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
164	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
165	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
166	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
167	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
168	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
169	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
170	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
171	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
172	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
173	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
174	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
175	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
176	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
177	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
178	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
179	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
180	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
181	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
182	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
183	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
184	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
185	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
186	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
187	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
188	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
189	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
190	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
191	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
192	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
193	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
194	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
195	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
196	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
197	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
198	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
199	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High
200	Final Pipe Trenching	10/22/10	10/29/10	7	10	10	22	29	C	High

Contract No. WQ150000
 Laying of Water Crosses Under Main Road - Associated Level Move from West Rowden to Salway Top

No	Description	Start	Finish	Days	Units	Rate	Value	Start	Finish	Days	Units	Rate	Value	Start	Finish	Days	Units	Rate	Value						
1-149000	T.L.F. F.W.M. Sewer Jacking (CHD 5007.7 (A) & 5007.7 (B))	20/08/10	20/08/10	1	250	175.00	43,750.00	20/08/10	20/08/10	1	250	175.00	43,750.00	20/08/10	20/08/10	1	250	175.00	43,750.00						
1-149001	Preparation & Submission of Risk Assessment Method Statement	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00
1-149002	Preparation & Submission of Method Statement	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00
1-149003	Excavation & Shoring for Jacking PI (A)	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00
1-149004	Excavation & Shoring for Jacking PI (B)	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00
1-149005	Jacking PI Above TL (C)	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00
1-149006	Jacking PI Below TL (C)	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00
1-149007	T.L.F. F.W.M. Sewer Jacking (CHD 5007.7 (A) & 5007.7 (B))	20/08/10	20/08/10	1	250	175.00	43,750.00	20/08/10	20/08/10	1	250	175.00	43,750.00	20/08/10	20/08/10	1	250	175.00	43,750.00	20/08/10	20/08/10	1	250	175.00	43,750.00
1-149008	Preparation & Submission of Risk Assessment Method Statement	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00
1-149009	Preparation & Submission of Method Statement	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00
1-149010	Excavation & Shoring for Jacking PI (A)	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00
1-149011	Excavation & Shoring for Jacking PI (B)	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00
1-149012	Jacking PI Above TL (C)	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00
1-149013	Jacking PI Below TL (C)	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00
1-149014	T.L.F. D.D.S. SWM Pipe Installation (CHD 253.5 (A) & 253.5 (B))	20/08/10	20/08/10	1	250	175.00	43,750.00	20/08/10	20/08/10	1	250	175.00	43,750.00	20/08/10	20/08/10	1	250	175.00	43,750.00	20/08/10	20/08/10	1	250	175.00	43,750.00
1-149015	Preparation & Submission of Risk Assessment Method Statement	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00
1-149016	Preparation & Submission of Method Statement	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00
1-149017	Excavation & Shoring for Jacking PI (A)	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00
1-149018	Excavation & Shoring for Jacking PI (B)	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00
1-149019	Jacking PI Above TL (C)	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00
1-149020	Jacking PI Below TL (C)	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00	20/08/10	20/08/10	1	1	175.00	175.00

3 Months Rolling Program (November 2010)
 Start date: 05/09/10
 Finish date: 04/12/10
 Back date: 1/10/10
 Page number: 3
 © Penta-Ocean Joint Venture



Appendix F

ET Weekly Site Inspection Records

WEEKLY SITE INSPECTION CHECKLIST

Inspection Date	02/11/2010	Inspected by	RE <i>White</i> <i>Revo</i>	IEC	Contractor	ET
Time	09:30	Name	<i>Peter King</i>		<i>Justin Ng</i>	<i>Hide Low</i>

Weather : Sunny / Fine / Cloudy / Drizzle / Rain / Storm / Hazy
 Condition : Calm / (Light) Breeze / Strong
 Temperature : 27 °C
 Humidity : High / Moderate / Low

	Implementation Stages*			Remark
	Yes	No	Not Obs	
Environmental Checklist				
Fugitive Dust Emission				
• Dust control / mitigation measures shall be provided to prevent dust nuisance.	✓			
• Any excavated dusty materials or stockpile of dusty materials should be covered entirely by impervious sheeting or sprayed with water so as to maintain the entire surface wet, and recovered or backfilled or reinstated within 24 hours of the excavation or unloading.	✓			
• The working area of excavation should be sprayed with water immediately before, during and immediately after the operations so as to maintain the entire surface wet.	✓			
• The load of dusty materials carried by vehicle leaving a construction site should be covered entirely by clean impervious sheeting to ensure that the dusty materials do not leak from the vehicle	✓			
• Where a site boundary adjoins a road, streets or other area accessible to the public, hoarding of not less than 2.4m high from ground level should be provided along the entire length except for a site entrance or exit.	✓			
• The area where vehicle washing takes place and the section of the road between the washing facilities and the exit point should be paved with concrete, bituminous materials or hardcores.	✓			✓
• Every main haul road should be sealed with concrete and kept clear of dusty materials or sprayed with water so as to maintain the entire road surface wet.	✓			
• The portion of road leading only to a construction site that is within 30m of a designated vehicle entrance or exit should be kept clear of dusty materials.	✓			
• All dusty materials should be sprayed with water prior to any loading, unloading or transfer operation so as to maintain the dusty material wet.	✓			
• Vehicle speed should be limited to 10 kph except on completed access roads.	✓			
• Every vehicle should be washed to remove any dusty materials from its body and wheels before leaving the construction sites.	✓			✓
• The public road around the site entrance should be kept clean and free from dust.	✓			
• Vehicle and equipment should be switched off while not in use.	✓			
• All plant and equipment should be well maintained e.g. without black smoke emission.	✓			
• Open burning should be prohibited.	✓			

Environmental Checklist		Implementation Stages*			Remark
		Yes	No	Not Obs N/A	
Noise Impact					
▪	The approved method of working, equipment and sound-reducing measures (e.g. use of silenced type of equipment, etc.) shall be adapted.	√			
▪	The constructions works should be scheduled to minimize noise nuisance. Concurrent noisy works should be carried out at different time slots or spread around the construction sites in order to help to reduce the cumulative noise effect produced in the construction process.	√			
▪	Noisy equipment and mobile plant shall always be site away from NSRs.	√			
▪	Machines and plant that may be in intermittent use should be shut down between work periods or should be throttled down to a minimum.	√			
▪	Powered mechanical equipment (PME) should be covered or shielded by appropriate acoustic materials.	√			
▪	Mobile or movable noise barriers should be erected near to the construction plants to reduce the noise levels from stationary items of PME whenever practicable.	√			
▪	Quality Powered mechanical equipment (Quality PME), which are construction plants and equipments that are notably quieter, more environmental friendly and efficiently, recognized by the Noise Control Authority for the purpose of CNP application should be used to reduce the noise generated from the construction plants effectively. The Contractor shall note the required procedures involved in application of the QPME.	√			
▪	Well maintained plant should be operated on-site and plant should be serviced regularly during the construction works.	√			
▪	Air compressors and hand held breakers should have noise labels.	√			
▪	Compressors and generators should operate with door closed.	√			
▪	Material stockpiles and other structures should be effectively utilised, where practicable, to screen noise from on-site construction activities.	√			
Water Quality					
Mitigation Measures for Dredging					
▪	Dredging should be undertaken using one grab dredger only with a maximum production rate of 4,000m ³ per day.	√			
▪	Deployment of frame type silt curtain should be fully enclosed the grab while dredging works are in progress.	√			
▪	Deployment of silt screen should be at the sea water intake at Kowloon South Salt Water Pumping Station while dredging works are in progress	√			
▪	Tight-closing grabs should be used to minimize the loss of sediment to suspension during dredging works. For dredging of any contaminated mud, closed watertight grabs must be used.	√			
▪	All vessels should be sized so that adequate clearance is maintained between vessels and the seabed in all tide conditions, to ensure that undue turbidity is not generated by turbulence from vessel movement or propeller wash	√			
▪	The decks of all vessels should be kept tidy and free of oil or other substances that might be accidentally or otherwise washed overboard	√			
▪	Adequate free board shall be maintained on barges to ensure that decks are not washed by wave action.	√			
▪	All barges used for the transport of dredged materials should be fitted with tight bottom seals to prevent leakage of material during loading and transport	√			
▪	Construction activities should not cause foam, oil, grease, scum, litter or other objectionable matter to be present in the water within the site or dumping grounds	√			
▪	Loading of barges should be controlled to prevent splashing of material into the surrounding waters. Barges should not be filled to a level that would cause the overflow of materials or sediment laden water during loading or transportation	√			
▪	The speed of vessels should be controlled within the works area to prevent propeller wash from stirring up the seabed sediments	√			

Environmental Checklist		Implementation Stages*			Remark
		Yes	No	Not Obs N/A	
Water Quality					
Mitigation Measures for other Construction Activities					
▪	Sedimentation tanks with sufficient capacity, constructed from pre-formed individual cells of approximately 6 to 8 m ³ capacities, are recommended as a general mitigation measure which can be used for settling surface runoff prior to disposal. The system capacity should be flexible and able to handle multiple inputs from a variety of sources and suited to applications where the influent is pumped	✓			
▪	Manholes (including newly constructed ones) should always be adequately covered and temporarily sealed so as to prevent silt, construction materials or debris being washed into the storm runoff being directed into foul sewers	✓			
▪	All vehicles and plant should be cleaned before leaving a construction site to ensure no earth, mud, debris and the like is deposited by them on roads.			✓	
▪	An adequately designed and located wheel washing bay should be provided at every site exit, and wash-water should have sand and silt settled out and removed at least on a weekly basis to ensure the continued efficiency of the process.			✓	
▪	The section of access road leading to, and exiting from, the wheel-wash bay to the public road should be paved with sufficient backfill toward the wheel-wash bay to prevent vehicle tracking of soil and silt water to public roads and drains			✓	
▪	Fuel tanks and storage areas should be provided with locks and be located on sealed areas, within bunds of a capacity equal to 110% of the storage capacity of the largest tank, to prevent spilled fuel oils from reaching the coastal waters of the Victoria Harbour and Western Harbour W CZs	✓			
▪	Portable chemical toilets should be used to handle construction workforce sewage prior to discharge to the existing trunk sewer. Sufficient numbers of portable toilets shall be provided by a licensed contractor to serve the construction workers. The Contractor shall also be responsible for waste disposal and maintenance practices.	✓			
▪	Construction site runoff should be prevented or minimised in accordance with the guidelines stipulated in the EPD's Practice Note for Professional Persons, Construction Site Drainage (ProPECC PN 1794). All discharges from the construction site should be controlled to comply with the standards for effluents discharged into the Victoria Harbour WCZ under the TM-DSS.	✓			
▪	Unnecessary water retained in receptacles and standing water should be avoided to prevent mosquito breeding.	✓			
Waste Management					
C&D Materials					
▪	Excavated materials should be reused on-site as backfilling material and for landscaping works as far as practicable.			✓	
▪	C&D material generated from excavation works should be disposed of at public fill reception facilities for other beneficial uses.			✓	
▪	A recording system for the amount of wastes generated, recycled and disposed (including the disposal sites) should be proposed			✓	
▪	A recording system for the amount of wastes generated, recycled and disposed (including the disposal sites) should be used, e.g. trip ticket system for chemical waste disposal. Quantities could be determined by weighing each load or other suitable methods.			✓	
Chemical Waste					
▪	Good quality containers compatible with the chemical wastes should be used, and incompatible chemicals should be stored separately.	✓			
▪	Appropriate labels should be securely attached on each chemical waste container indicating the corresponding chemical characteristics of the chemical waste, such as explosive, flammable, oxidizing, irritant, toxic, harmful, corrosive, etc.	✓			
▪	The Contractor shall use a licensed collector to transport and dispose of the chemical wastes, to either the approved Chemical Waste Treatment Centre, or another licensed facility.	✓			

Environmental Checklist		Implementation Stages*			Remark
		Yes	No	Not Obs N/A	
Waste Management					
General Refuse					
▪	General refuse should be stored in enclosed bins or compaction units separate from C&D material.	√			
▪	A reputable waste collector should be employed by the contractor to remove general refuse from the site, separately from C&D material.	√			
▪	An enclosed and covered area should be provided to reduce the occurrence of 'wind blown' light material.	√			
Marine Dredged Sediment (During transportation and disposal)					
▪	Bottom opening of barges shall be fitted with tight fitting seals to prevent leakage of material. Excess material shall be cleaned from the decks and exposed fittings of barges and dredgers before the vessel is moved	√			
▪	Monitoring of the barge loading shall be conducted to ensure that loss of material does not take place during transportation. Transport barges or vessels shall be equipped with automatic self-monitoring devices as specified by the EPD	√			
▪	Barges or hopper barges shall not be filled to a level that would cause the overflow of materials or sediment laden water during loading or transportation.	√			
Site Practices					
▪	Nomination of an approved person, such as a site manager, to be responsible for good site practices, arrangements for collection and effective disposal to an appropriate facility, of all wastes generated at the site	√			
▪	Training of site personnel in proper waste management and chemical handling procedures	√			
▪	Provision of sufficient waste disposal points and regular collection of waste	√			
▪	Good site practices should be adopted to clean the rubbish and litter on a regular basis so as to prevent the rubbish and litter from dropping into the nearby environment.	√			
▪	Appropriate measures to minimise windblown litter and dust during transportation of waste by either covering trucks or by transporting wastes in enclosed containers	√			
Waste Reduction Measures					
▪	Sort C&D material from demolition and decommissioning of the existing facilities to recover recyclable portions such as metals	√			
▪	Segregation and storage of different types of waste in different containers, skips or stockpiles to enhance reuse or recycling of materials and their proper disposal	√			
▪	Encourage collection of aluminium cans by providing separate labelled bins to enable this waste to be segregated from other general refuse generated by the work force	√			
▪	Proper storage and site practices to minimise the potential for damage or contamination of construction materials	√			
▪	Plan and stock construction materials carefully to minimise amount of waste generated and avoid unnecessary generation of waste	√			

Implementation Stages*		Remark	
		Yes	No
Environmental Checklist			
Marine Ecology			
Use of one grab dredger only with a maximum production rate of 4,000m ³ per day for dredging.	√		
Deployment of frame type silt curtain to fully enclose the grab while dredging works are in progress.	√		
Deployment of silt screen at the sea water intake at Kowloon South Salt Water Pumping Station while dredging works are in progress.	√		
Good site practices to avoid silt runoff from construction works associated with the construction of the submarine watermain.	√		
Good Site Practices			
The Environmental Permit should be displaced conspicuously on site.	√		
Construction noise permits should be posted at site entrance or available for site inspection.	√		
Chemical storage area provided with lock and located on sealed areas.	√		
All chemicals should be placed at the banded area with adequate bund capacity (>110% of largest tank).	√	√	Item 1
Any unused chemicals or those with remaining functional capacity should be recycled.	√		
All generators, fuel and oil storage are within bunded areas.	√		
Regular cleaning and maintenance programme for waste storage area, drainage systems, silt traps, sumps and oil interceptors.	√		
A collection area should be provided where waste can be stored and loaded prior to removal from site. An enclosed and covered area is preferred to reduce the occurrence of 'wind blown' light material. If an open area is unavoidable for the storage or loading/unloading of wastes, then the area should be bunded and all the polluted surface run-off collected within this area should be diverted into wastewater treatment system.	√		



Summary of the Weekly Site Inspection:


Item	Details of defective works or observations	Status of the item (closed / continue follow-up)	Proposed Follow Up Action (if required)	Photo Ref.	Target Completion Date
1	A 200L oil drum was noted on the ground at Portion J without appropriate label and drip tray.	Continue follow-up	To provide appropriate label for the oil drum and store it in appropriate chemical storage area.	101102_001	09/11/10

Remark

--

Inspected by	Name	Signature	Date
	Linda Law	<i>Linda Law</i>	02 November 2010

Photos



Environmental Checklist	Implementation Stages*			Remark
	Yes	No	Not Obs N/A	
Noise Impact				
<ul style="list-style-type: none"> ▪ The approved method of working, equipment and sound-reducing measures (e.g. use of silenced type of equipment, etc.) shall be adapted. ▪ The constructions works should be scheduled to minimize noise nuisance. Concurrent noisy works should be carried out at different time slots or spread around the construction sites in order to help to reduce the cumulative noise effect produced in the construction process. ▪ Noisy equipment and mobile plant shall always be site away from NSRs. ▪ Machines and plant that may be in intermittent use should be shut down between work periods or should be throttled down to a minimum. ▪ Powered mechanical equipment (PME) should be covered or shielded by appropriate acoustic materials. ▪ Mobile or movable noise barriers should be erected near to the construction plants to reduce the noise levels from stationary items of PME whenever practicable. ▪ Quality Powered mechanical equipment (Quality PME), which are construction plants and equipments that are notably quieter, more environmental friendly and efficiently, recognized by the Noise Control Authority for the purpose of CNP application should be used to reduce the noise generated from the construction plants effectively. The Contractor shall note the required procedures involved in application of the QPME. ▪ Well maintained plant should be operated on-site and plant should be serviced regularly during the construction works. ▪ Air compressors and hand held breakers should have noise labels. ▪ Compressors and generators should operate with door closed. ▪ Material stockpiles and other structures should be effectively utilised, where practicable, to screen noise from on-site construction activities. 	<p>✓</p> <p>✓</p> <p>✓</p> <p>✓</p> <p>✓</p> <p>✓</p> <p>✓</p> <p>✓</p> <p>✓</p> <p>✓</p>			
Water Quality				
Mitigation Measures for Dredging				
<ul style="list-style-type: none"> ▪ Dredging should be undertaken using one grab dredger only with a maximum production rate of 4,000m³ per day. ▪ Deployment of frame type silt curtain should be fully enclosed the grab while dredging works are in progress. ▪ Deployment of silt screen should be at the sea water intake at Kowloon South Salt Water Pumping Station while dredging works are in progress ▪ Tight-closing grabs should be used to minimize the loss of sediment to suspension during dredging works. For dredging of any contaminated mud, closed watertight grabs must be used. ▪ All vessels should be sized so that adequate clearance is maintained between vessels and the seabed in all tide conditions, to ensure that undue turbidity is not generated by turbulence from vessel movement or propeller wash ▪ The decks of all vessels should be kept tidy and free of oil or other substances that might be accidentally or otherwise washed overboard ▪ Adequate free board shall be maintained on barges to ensure that decks are not washed by wave action. ▪ All barges used for the transport of dredged materials should be fitted with tight bottom seals to prevent leakage of material during loading and transport ▪ Construction activities should not cause foam, oil, grease, scurm, litter or other objectionable matter to be present in the water within the site or dumping grounds ▪ Loading of barges should be controlled to prevent splashing of material into the surrounding waters. Barges should not be filled to a level that would cause the overflow of materials or sediment laden water during loading or transportation ▪ The speed of vessels should be controlled within the works area to prevent propeller wash from stirring up the seabed sediments 	<p>✓</p> <p>✓</p> <p>✓</p> <p>✓</p> <p>✓</p> <p>✓</p> <p>✓</p> <p>✓</p> <p>✓</p> <p>✓</p> <p>✓</p>			

Contract No. 9/WSD/08
Laying of Western Cross Harbour Main and Associated Land Mains
From West Kowloon to Sai Ying Pun

Environmental Checklist	Implementation Stages*			Remark
	Yes	No	Not Obs	
Water Quality				
Mitigation Measures for other Construction Activities				
<ul style="list-style-type: none"> Sedimentation tanks with sufficient capacity, constructed from pre-formed individual cells of approximately 6 to 8 m³ capacities, are recommended as a general mitigation measure which can be used for settling surface runoff prior to disposal. The system capacity should be flexible and able to handle multiple inputs from a variety of sources and suited to applications where the influent is pumped. Manholes (including newly constructed ones) should always be adequately covered and temporarily sealed so as to prevent silt, construction materials or debris being washed into the storm runoff being directed into foul sewers. All vehicles and plant should be cleaned before leaving a construction site to ensure no earth, mud, debris and the like is deposited by them on roads. An adequately designed and located wheel washing bay should be provided at every site exit, and wash-water should have sand and silt settled out and removed at least on a weekly basis to ensure the continued efficiency of the process. The section of access road leading to, and exiting from, the wheel-wash bay to the public road should be paved with sufficient backfill toward the wheel-wash bay to prevent vehicle tracking of soil and silty water to public roads and drains. Fuel tanks and storage areas should be provided with locks and be located on sealed areas, within bunds of a capacity equal to 110% of the storage capacity of the largest tank, to prevent spilled fuel oils from reaching the coastal waters of the Victoria Harbour and Western Harbour WCs. Portable chemical toilets should be used to handle construction workforce sewage prior to discharge to the existing trunk sewer. Sufficient numbers of portable toilets shall be provided by a licensed contractor to serve the construction workers. The Contractor shall also be responsible for waste disposal and maintenance practices. Construction site runoff should be prevented or minimised in accordance with the guidelines stipulated in the EPD's Practice Note for Professional Persons, Construction Site Drainage (ProPECC PN 1/94). All discharges from the construction site should be controlled to comply with the standards for effluents discharged into the Victoria Harbour WCZ under the TM-DSS. Unnecessary water retained in receptacles and standing water should be avoided to prevent mosquito breeding. 	√			
Waste Management				
C&D Materials				
<ul style="list-style-type: none"> Excavated materials should be reused on-site as backfilling material and for landscaping works as far as practicable. C&D material generated from excavation works should be disposed of at public fill reception facilities for other beneficial uses. A recording system for the amount of wastes generated, recycled and disposed (including the disposal sites) should be proposed. A recording system for the amount of wastes generated, recycled and disposed (including the disposal sites) should be used, e.g. trip ticket system for chemical waste disposal. Quantities could be determined by weighing each load or other suitable methods. 	√		√	
Chemical Waste				
<ul style="list-style-type: none"> Good quality containers compatible with the chemical wastes should be used, and incompatible chemicals should be stored separately. Appropriate labels should be securely attached on each chemical waste container indicating the corresponding chemical characteristics of the chemical waste, such as explosive, flammable, oxidizing, irritant, toxic, harmful, corrosive, etc. The Contractor shall use a licensed collector to transport and dispose of the chemical wastes, to either the approved Chemical Waste Treatment Centre, or another licensed facility. 	√			

Contract No. 9/WSD/08
Laying of Western Cross Harbour Main and Associated Land Mains
From West Kowloon to Sai Ying Pun

Environmental Checklist	Implementation Stages*			Remark
	Yes	No	Not Obs N/A	
Waste Management				
General Refuse				
General refuse should be stored in enclosed bins or compaction units separate from C&D material.	✓			
A reputable waste collector should be employed by the contractor to remove general refuse from the site, separately from C&D material.	✓			
An enclosed and covered area should be provided to reduce the occurrence of 'wind blown' light material.	✓			
Marine Dredged Sediment (During transportation and disposal)				
Bottom opening of barges shall be fitted with light fitting seals to prevent leakage of material. Excess material shall be cleaned from the decks and exposed fittings of barges and dredgers before the vessel is moved	✓			
Monitoring of the barge loading shall be conducted to ensure that loss of material does not take place during transportation. Transport barges or vessels shall be equipped with automatic self-monitoring devices as specified by the EPD	✓			
Barges or hopper barges shall not be filled to a level that would cause the overflow of materials or sediment laden water during loading or transportation.	✓			
Site Practices				
Nomination of an approved person, such as a site manager, to be responsible for good site practices, arrangements for collection and effective disposal to an appropriate facility, of all wastes generated at the site	✓			
Training of site personnel in proper waste management and chemical handling procedures	✓			
Provision of sufficient waste disposal points and regular collection of waste	✓			
Good site practices should be adopted to clean the rubbish and litter on a regular basis so as to prevent the rubbish and litter from dropping into the nearby environment.	✓			
Appropriate measures to minimise windblown litter and dust during transportation of waste by either covering trucks or by transporting wastes in enclosed containers	✓			
Waste Reduction Measures				
Sort C&D material from demolition and decommissioning of the existing facilities to recover recyclable portions such as metals	✓			
Segregation and storage of different types of waste in different containers, skips or stockpiles to enhance reuse or recycling of materials and their proper disposal	✓			
Encourage collection of aluminium cans by providing separate labelled bins to enable this waste to be segregated from other general refuse generated by the work force	✓			
Proper storage and site practices to minimise the potential for damage or contamination of construction materials	✓			
Plan and stock construction materials carefully to minimise amount of waste generated and avoid unnecessary generation of waste	✓			

Contract No. 9/WSD/08
Laying of Western Cross Harbour Main and Associated Land Mains
From West Kowloon to Sai Ying Pun

Environmental Checklist	Implementation Stages*			Remark
	Yes	No	Not Obs N/A	
Marine Ecology				
▪ Use of one grab dredger only with a maximum production rate of 4,000m ³ per day for dredging.	√			
▪ Deployment of frame type silt curtain to fully enclose the grab while dredging works are in progress.	√			
▪ Deployment of silt screen at the sea water intake at Kowloon South Salt Water Pumping Station while dredging works are in progress.	√			
▪ Good site practices to avoid silt runoff from construction works associated with the construction of the submarine watermain.	√			
Good Site Practices				
▪ The Environmental Permit should be displaced conspicuously on site.	√			
▪ Construction noise permits should be posted at site entrance or available for site inspection.	√			
▪ Chemical storage area provided with lock and located on sealed areas.	√			
▪ All chemicals should be placed at the banded area with adequate band capacity (> 110% of largest tank).	√			
▪ Any unused chemicals or those with remaining functional capacity should be recycled.	√			
▪ All generators, fuel and oil storage are within bundle areas.	√			
▪ Regular cleaning and maintenance programme for waste storage area, drainage systems, silt traps, sumps and oil interceptors.	√			
▪ A collection area should be provided where waste can be stored and loaded prior to removal from site. An enclosed and covered area is preferred to reduce the occurrence of 'wind blown' light material. If an open area is unavoidable for the storage or loading/unloading of wastes, then the area should be bunded and all the polluted surface run-off collected within this area should be diverted into wastewater treatment system.	√			

Contract No. 9/WSD/08
 Laying of Western Cross Harbour Main and Associated Land Mains
 From West Kowloon to Sai Ying Pun



英泰德测试顾问有限公司
 ETS-TESTCONSULT LIMITED

Summary of the Weekly Site Inspection:

Item	Details of defective works or observations	Status of the item (closed / continue follow-up)	Proposed Follow Up Action (if required)	Photo Ref.	Target Completion Date
1	Follow up action to the item 1 on 02/11/10, the 200L oil drum noted on the ground at Portion J was placed inside drip tray and covered properly.	Closed	---	101110_001	--


Remark

No defective observations were found in this weekly site inspection.

Inspected by	Name	Signature	Date
	Linda Law	<i>Linda Law</i>	10 November 2010

Contract No. 9/WSD/08
Laying of Western Cross Harbour Main and Associated Land Mains
From West Kowloon to Sai Ying Pun

Photos



Contract No. 9/WVSD/08
 Laying of Western Cross Harbour Main and Associated Land Mains
 From West Kowloon to Sai Ying Pun

WEEKLY SITE INSPECTION CHECKLIST

Inspection Date	17/11/2010	Inspected by	RE [Signature]	IEC	Contractor	ET
Time	13:30	Name	M. M. K. [Signature]		JHG [Signature]	Under Law

Weather : Sunny / Fine / Cloudy / Drizzle / Rain / Storm / Hazy
 Condition : Calm / Light / Breeze / Strong
 Wind : 26 °C
 Humidity : High / Moderate / Low

Environmental Checklist

Fugitive Dust Emission

Implementation Stages*	Remark		
	Yes	No	N/A
<ul style="list-style-type: none"> Dust control / mitigation measures shall be provided to prevent dust nuisance. 	✓		
<ul style="list-style-type: none"> Any excavated dusty materials or stockpile of dusty materials should be covered entirely by impervious sheeting or sprayed with water so as to maintain the entire surface wet, and recovered or backfilled or reinstated within 24 hours of the excavation or unloading. 	✓		
<ul style="list-style-type: none"> The working area of excavation should be sprayed with water immediately before, during and immediately after the operations so as to maintain the entire surface wet. 	✓		
<ul style="list-style-type: none"> The load of dusty materials carried by vehicle leaving a construction site should be covered entirely by clean impervious sheeting to ensure that the dusty materials do not leak from the vehicle 	✓		
<ul style="list-style-type: none"> Where a site boundary adjoins a road, streets or other area accessible to the public, hoarding of not less than 2.4m high from ground level should be provided along the entire length except for a site entrance or exit. 	✓		
<ul style="list-style-type: none"> The area where vehicle washing takes place and the section of the road between the washing facilities and the exit point should be paved with concrete, bituminous materials or hardcores. 			✓
<ul style="list-style-type: none"> Every main haul road should be sealed with concrete and kept clear of dusty materials or sprayed with water so as to maintain the entire road surface wet. 	✓		
<ul style="list-style-type: none"> The portion of road leading only to a construction site that is within 30m of a designated vehicle entrance or exit should be kept clear of dusty materials. 	✓		
<ul style="list-style-type: none"> All dusty materials should be sprayed with water prior to any loading, unloading or transfer operation so as to maintain the dusty material wet. 	✓		
<ul style="list-style-type: none"> Vehicle speed should be limited to 10 kph except on completed access roads. 	✓		✓
<ul style="list-style-type: none"> Every vehicle should be washed to remove any dusty materials from its body and wheels before leaving the construction sites. 	✓		
<ul style="list-style-type: none"> The public road around the site entrance should be kept clean and free from dust. 	✓		
<ul style="list-style-type: none"> Vehicle and equipment should be switched off while not in use. 	✓		
<ul style="list-style-type: none"> All plant and equipment should be well maintained e.g. without black smoke emission. 	✓		
<ul style="list-style-type: none"> Open burning should be prohibited. 	✓		

Environmental Checklist	Implementation Stages*			Remark
	Yes	No	Not Obs N/A	
Noise Impact				
▪ The approved method of working, equipment and sound-reducing measures (e.g. use of silenced type of equipment, etc.) shall be adapted.	✓			
▪ The constructions works should be scheduled to minimize noise nuisance. Concurrent noisy works should be carried out at different time slots or spread around the construction sites in order to help to reduce the cumulative noise effect produced in the construction process.	✓			
▪ Noisy equipment and mobile plant shall always be site away from NSRs.	✓			
▪ Machines and plant that may be in intermittent use should be shut down between work periods or should be throttled down to a minimum.	✓			
▪ Powered mechanical equipment (PME) should be covered or shielded by appropriate acoustic materials.	✓			
▪ Mobile or movable noise barriers should be erected near to the construction plants to reduce the noise levels from stationary items of PME whenever practicable.	✓			
▪ Quality Powered mechanical equipment (Quality PME), which are construction plants and equipments that are notably quieter, more environmental friendly and efficiently, recognized by the Noise Control Authority for the purpose of CNP application should be used to reduce the noise generated from the construction plants effectively. The Contractor shall note the required procedures involved in application of the QPME.	✓			
▪ Well maintained plant should be operated on-site and plant should be serviced regularly during the construction works.	✓			
▪ Air compressors and hand held breakers should have noise labels.	✓			
▪ Compressors and generators should operate with door closed.	✓			
▪ Material stockpiles and other structures should be effectively utilised, where practicable, to screen noise from on-site construction activities.	✓			
Water Quality				
Mitigation Measures for Dredging				
▪ Dredging should be undertaken using one grab dredger only with a maximum production rate of 4,000m ³ per day.	✓			Maintenance work in progress
▪ Deployment of frame type silt curtain should be fully enclosed the grab while dredging works are in progress.			✓	
▪ Deployment of silt screen should be at the sea water intake at Kowloon South Salt Water Pumping Station while dredging works are in progress	✓			
▪ Tight-closing grabs should be used to minimize the loss of sediment to suspension during dredging works. For dredging of any contaminated mud, closed watertight grabs must be used.	✓			
▪ All vessels should be sized so that adequate clearance is maintained between vessels and the seabed in all tide conditions, to ensure that undue turbidity is not generated by turbulence from vessel movement or propeller wash	✓			
▪ The decks of all vessels should be kept tidy and free of oil or other substances that might be accidentally or otherwise washed overboard	✓			
▪ Adequate free board shall be maintained on barges to ensure that decks are not washed by wave action.	✓			
▪ All barges used for the transport of dredged materials should be fitted with tight bottom seals to prevent leakage of material during loading and transport	✓			
▪ Construction activities should not cause foam, oil, grease, scum, litter or other objectionable matter to be present in the water within the site or dumping grounds	✓			
▪ Loading of barges should be controlled to prevent splashing of material into the surrounding waters. Barges should not be filled to a level that would cause the overflow of materials or sediment laden water during loading or transportation	✓			
▪ The speed of vessels should be controlled within the works area to prevent propeller wash from stirring up the seabed sediments	✓			

Contract No. 9AWS/08
Laying of Western Cross Harbour Main and Associated Land Mains
From West Kowloon to Sai Ying Pun

	Implementation Stages*			Remark
	Yes	No	Not Obs N/A	
Environmental Checklist				
Water Quality				
Mitigation Measures for other Construction Activities				
<ul style="list-style-type: none"> Sedimentation tanks with sufficient capacity, constructed from pre-formed individual cells of approximately 6 to 8 m³ capacities, are recommended as a general mitigation measure which can be used for settling surface runoff prior to disposal. The system capacity should be flexible and able to handle multiple inputs from a variety of sources and suited to applications where the influent is pumped Manholes (including newly constructed ones) should always be adequately covered and temporarily sealed so as to prevent silt, construction materials or debris being washed into the storm runoff being directed into foul sewers All vehicles and plant should be cleaned before leaving a construction site to ensure no earth, mud, debris and the like is deposited by them on roads. An adequately designed and located wheel washing bay should be provided at every site exit, and wash-water should have sand and silt settled out and removed at least on a weekly basis to ensure the continued efficiency of the process. The section of access road leading to, and exiting from, the wheel-wash bay to the public road should be paved with sufficient backfill toward the wheel-wash bay to prevent vehicle tracking of soil and silty water to public roads and drains Fuel tanks and storage areas should be provided with locks and be located on sealed areas, within bunds of a capacity equal to 110% of the storage capacity of the largest tank, to prevent spilled fuel oils from reaching the coastal waters of the Victoria Harbour and Western Harbour WCs Portable chemical toilets should be used to handle construction workforce sewage prior to discharge to the existing trunk sewer. Sufficient numbers of portable toilets shall be provided by a licensed contractor to serve the construction workers. The Contractor shall also be responsible for waste disposal and maintenance practices. Construction site runoff should be prevented or minimised in accordance with the guidelines stipulated in the EPD's Practice Note for Professional Persons, Construction Site Drainage (ProPECC PN 1/94). All discharges from the construction site should be controlled to comply with the standards for effluents discharged into the Victoria Harbour WCZ under the TM-DSS. Unnecessary water retained in receptacles and standing water should be avoided to prevent mosquito breeding. 	√			
Waste Management				
C&D Materials				
<ul style="list-style-type: none"> Excavated materials should be reused on-site as backfilling material and for landscaping works as far as practicable. C&D material generated from excavation works should be disposed of at public fill reception facilities for other beneficial uses. A recording system for the amount of wastes generated, recycled and disposed (including the disposal sites) should be proposed A recording system for the amount of wastes generated, recycled and disposed (including the disposal sites) should be used, e.g. trip ticket system for chemical waste disposal. Quantities could be determined by weighing each load or other suitable methods. 	√		√	
Chemical Waste				
<ul style="list-style-type: none"> Good quality containers compatible with the chemical wastes should be used, and incompatible chemicals should be stored separately. Appropriate labels should be securely attached on each chemical waste container indicating the corresponding chemical characteristics of the chemical waste, such as explosive, flammable, oxidizing, irritant, toxic, harmful, corrosive, etc. The Contractor shall use a licensed collector to transport and dispose of the chemical wastes, to either the approved Chemical Waste Treatment Centre, or another licensed facility. 	√			

Implementation Stages*	Remark		
	Yes	No	Not Obs N/A
Environmental Checklist			
Waste Management			
General Refuse			
General refuse should be stored in enclosed bins or compaction units separate from C&D material.	√		
A reputable waste collector should be employed by the contractor to remove general refuse from the site, separately from C&D material.	√		
An enclosed and covered area should be provided to reduce the occurrence of 'wind blown' light material.	√		
Marine Dredged Sediment (During transportation and disposal)			
Bottom opening of barges shall be fitted with light fitting seals to prevent leakage of material. Excess material shall be cleaned from the decks and exposed fittings of barges and dredgers before the vessel is moved	√		Maintenance work in progress
Monitoring of the barge loading shall be conducted to ensure that loss of material does not take place during transportation. Transport barges or vessels shall be equipped with automatic self-monitoring devices as specified by the EPD	√		Maintenance work in progress
Barges or hopper barges shall not be filled to a level that would cause the overflow of materials or sediment laden water during loading or transportation.	√		Maintenance work in progress
Site Practices			
Nomination of an approved person, such as a site manager, to be responsible for good site practices, arrangements for collection and effective disposal to an appropriate facility, of all wastes generated at the site	√		
Training of site personnel in proper waste management and chemical handling procedures	√		
Provision of sufficient waste disposal points and regular collection of waste	√		
Good site practices should be adopted to clean the rubbish and litter on a regular basis so as to prevent the rubbish and litter from dropping into the nearby environment.	√		
Appropriate measures to minimise windblown litter and dust during transportation of waste by either covering trucks or by transporting wastes in enclosed containers	√		
Waste Reduction Measures			
Sort C&D material from demolition and decommissioning of the existing facilities to recover recyclable portions such as metals	√		
Segregation and storage of different types of waste in different containers, skips or stockpiles to enhance reuse or recycling of materials and their proper disposal	√		
Encourage collection of aluminium cans by providing separate labelled bins to enable this waste to be segregated from other general refuse generated by the work force	√		
Proper storage and site practices to minimise the potential for damage or contamination of construction materials	√		
Plan and stock construction materials carefully to minimise amount of waste generated and avoid unnecessary generation of waste	√		

Environmental Checklist	Implementation Stages*			Remark
	Yes	No	Not Obs	
Marine Ecology				
Use of one grab dredger only with a maximum production rate of 4,000m ³ per day for dredging.			✓	Maintenance work in progress
Deployment of frame type silt curtain to fully enclose the grab while dredging works are in progress.			✓	Maintenance work in progress
Deployment of silt screen at the sea water intake at Kowloon South Salt Water Pumping Station while dredging works are in progress.	✓			
Good site practices to avoid silt runoff from construction works associated with the construction of the submarine watermain.	✓			
Good Site Practices				
The Environmental Permit should be displaced conspicuously on site.	✓			
Construction noise permits should be posted at site entrance or available for site inspection.	✓			
Chemical storage area provided with lock and located on sealed areas.	✓			
All chemicals should be placed at the banded area with adequate band capacity (>110% of largest tank).	✓			
Any unused chemicals or those with remaining functional capacity should be recycled.	✓			
All generators, fuel and oil storage are within bundle areas.	✓			
Regular cleaning and maintenance programme for waste storage area, drainage systems, silt traps, sumps and oil interceptors.	✓			
A collection area should be provided where waste can be stored and loaded prior to removal from site. An enclosed and covered area is preferred to reduce the occurrence of 'wind blown' light material. If an open area is unavoidable for the storage or loading/unloading of wastes, then the area should be bunded and all the polluted surface run-off collected within this area should be diverted into wastewater treatment system.	✓			

Contract No. 9/WSD/08
 Laying of Western Cross Harbour Main and Associated Land Mains
 From West Kowloon to Sai Ying Pun

Summary of the Weekly Site Inspection:

Item	Details of defective works or observations	Status of the item (closed / continue follow-up)	Proposed Follow Up Action (if required)	Photo Ref.	Target Completion Date
---	---	---	---	---	---

Remark

No defective observation was noted during the weekly site inspection.

Inspected by	Name	Signature	Date
	Linda Law	<i>Linda Law</i>	17 November 2010

Contract No. 9/MSD/08
 Laying of Western Cross Harbour Main and Associated Land Mains
 From West Kowloon to Sai Ying Pun

WEEKLY SITE INSPECTION CHECKLIST

Inspection Date	24/11/2010	Inspected by	RE Nelson	IEC	Edmond Chung	Contractor	ET
Time	13:00 - 15:00	Name	Nelson Chau			Joeve	

Weather : Sunny / ~~Clear~~ / Cloudy / Drizzle / Rain / Storm / Hazy
 Condition : Calm / ~~Light~~ / Breeze / Strong
 Wind :
 Temperature : 23 °C
 Humidity : High / Moderate / Low

Environmental Checklist	Implementation Stages*			Remark
	Yes	No	Not Obs / N/A	
Fugitive Dust Emission				
▪ Dust control / mitigation measures shall be provided to prevent dust nuisance.	✓			
▪ Any excavated dusty materials or stockpile of dusty materials should be covered entirely by impervious sheeting or sprayed with water so as to maintain the entire surface wet, and recovered or backfilled or reinstated within 24 hours of the excavation or unloading.	✓			
▪ The working area of excavation should be sprayed with water immediately before, during and immediately after the operations so as to maintain the entire surface wet.	✓			
▪ The load of dusty materials carried by vehicle leaving a construction site should be covered entirely by clean impervious sheeting to ensure that the dusty materials do not leak from the vehicle	✓			
▪ Where a site boundary adjoins a road, streets or other area accessible to the public, hoarding of not less than 2.4m high from ground level should be provided along the entire length except for a site entrance or exit.	✓			
▪ The area where vehicle washing takes place and the section of the road between the washing facilities and the exit point should be paved with concrete, bituminous materials or hardcores.			✓	
▪ Every main haul road should be sealed with concrete and kept clear of dusty materials or sprayed with water so as to maintain the entire road surface wet.	✓			
▪ The portion of road leading only to a construction site that is within 30m of a designated vehicle entrance or exit should be kept clear of dusty materials.	✓			
▪ All dusty materials should be sprayed with water prior to any loading, unloading or transfer operation so as to maintain the dusty material wet.	✓			
▪ Vehicle speed should be limited to 10 kph except on completed access roads.	✓			
▪ Every vehicle should be washed to remove any dusty materials from its body and wheels before leaving the construction sites.			✓	
▪ The public road around the site entrance should be kept clean and free from dust.	✓			
▪ Vehicle and equipment should be switched off while not in use.	✓			
▪ All plant and equipment should be well maintained e.g. without black smoke emission.	✓			
▪ Open burning should be prohibited.	✓			

	Implementation Stages*			Remark
	Yes	No	Not Obs N/A	
Environmental Checklist				
Noise Impact				
▪ The approved method of working, equipment and sound-reducing measures (e.g. use of silenced type of equipment, etc.) shall be adapted.	✓			
▪ The constructions works should be scheduled to minimize noise nuisance. Concurrent noisy works should be carried out at different time slots or spread around the construction sites in order to help to reduce the cumulative noise effect produced in the construction process.	✓			
▪ Noisy equipment and mobile plant shall always be site away from NSRs.	✓			
▪ Machines and plant that may be in intermittent use should be shut down between work periods or should be throttled down to a minimum.	✓			
▪ Powered mechanical equipment (PME) should be covered or shielded by appropriate acoustic materials.	✓			
▪ Mobile or movable noise barriers should be erected near to the construction plants to reduce the noise levels from stationary items of PME whenever practicable.	✓			
▪ Quality Powered mechanical equipment (Quality PME), which are construction plants and equipments that are notably quieter, more environmental friendly and efficiently, recognized by the Noise Control Authority for the purpose of CNP application should be used to reduce the noise generated from the construction plants effectively. The Contractor shall note the required procedures involved in application of the QPME.	✓			
▪ Well maintained plant should be operated on-site and plant should be serviced regularly during the construction works.	✓			
▪ Air compressors and hand held breakers should have noise labels.	✓			
▪ Compressors and generators should operate with door closed.	✓			
▪ Material stockpiles and other structures should be effectively utilised, where practicable, to screen noise from on-site construction activities.	✓			
Water Quality				
Mitigation Measures for Dredging				
▪ Dredging should be undertaken using one grab dredger only with a maximum production rate of 4,000m ³ per day.	✓			
▪ Deployment of frame type silt curtain should be fully enclosed the grab while dredging works are in progress.	✓			
▪ Deployment of silt screen should be at the sea water intake at Kowloon South Salt Water Pumping Station while dredging works are in progress	✓			
▪ Tight-closing grabs should be used to minimize the loss of sediment to suspension during dredging works. For dredging of any contaminated mud, closed watertight grabs must be used.	✓			
▪ All vessels should be sized so that adequate clearance is maintained between vessels and the seabed in all tide conditions, to ensure that undue turbidity is not generated by turbulence from vessel movement or propeller wash	✓			
▪ The decks of all vessels should be kept tidy and free of oil or other substances that might be accidentally or otherwise washed overboard	✓			
▪ Adequate free board shall be maintained on barges to ensure that decks are not washed by wave action.	✓			
▪ All barges used for the transport of dredged materials should be fitted with tight bottom seals to prevent leakage of material during loading and transport	✓			
▪ Construction activities should not cause foam, oil, grease, scum, litter or other objectionable matter to be present in the water within the site or dumping grounds	✓			
▪ Loading of barges should be controlled to prevent splashing of material into the surrounding waters. Barges should not be filled to a level that would cause the overflow of materials or sediment laden water during loading or transportation	✓			
▪ The speed of vessels should be controlled within the works area to prevent propeller wash from stirring up the seabed sediments	✓			

Contract No. 9WSD/08
Laying of Western Cross Harbour Main and Associated Land Mains
From West Kowloon to Sai Ying Pun

Environmental Checklist	Implementation Stages*			Remark
	Yes	No	Not Obs N/A	
Water Quality				
Mitigation Measures for other Construction Activities				
<ul style="list-style-type: none"> Sedimentation tanks with sufficient capacity, constructed from pre-formed individual cells of approximately 6 to 8 m³ capacities, are recommended as a general mitigation measure which can be used for settling surface runoff prior to disposal. The system capacity should be flexible and able to handle multiple inputs from a variety of sources and suited to applications where the influent is pumped Manholes (including newly constructed ones) should always be adequately covered and temporarily sealed so as to prevent silt, construction materials or debris being washed into the storm runoff being directed into foul sewers All vehicles and plant should be cleaned before leaving a construction site to ensure no earth, mud, debris and the like is deposited by them on roads. An adequately designed and located wheel washing bay should be provided at every site exit, and wash-water should have sand and silt settled out and removed at least on a weekly basis to ensure the continued efficiency of the process. The section of access road leading to, and exiting from, the wheel-wash bay to the public road should be paved with sufficient backfill toward the wheel-wash bay to prevent vehicle tracking of soil and silty water to public roads and drains Fuel tanks and storage areas should be provided with locks and be located on sealed areas, within bunds of a capacity equal to 110% of the storage capacity of the largest tank, to prevent spilled fuel oils from reaching the coastal waters of the Victoria Harbour and Western Harbour WQZs Portable chemical toilets should be used to handle construction workforce sewage prior to discharge to the existing trunk sewer. Sufficient numbers of portable toilets shall be provided by a licensed contractor to serve the construction workers. The Contractor shall also be responsible for waste disposal and maintenance practices. Construction site runoff should be prevented or minimised in accordance with the guidelines stipulated in the EPD's Practice Note for Professional Persons, Construction Site Drainage (ProPECC PN 1794). All discharges from the construction site should be controlled to comply with the standards for effluents discharged into the Victoria Harbour WCZ under the TM-DSS. Unnecessary water retained in receptacles and standing water should be avoided to prevent mosquito breeding. 	√			
Waste Management				
C&D Materials				
<ul style="list-style-type: none"> Excavated materials should be reused on-site as backfilling material and for landscaping works as far as practicable. C&D material generated from excavation works should be disposed of at public fill reception facilities for other beneficial uses. A recording system for the amount of wastes generated, recycled and disposed (including the disposal sites) should be proposed A recording system for the amount of wastes generated, recycled and disposed (including the disposal sites) should be used, e.g. trip ticket system for chemical waste disposal. Quantities could be determined by weighing each load or other suitable methods. 	√		√	
Chemical Waste				
<ul style="list-style-type: none"> Good quality containers compatible with the chemical wastes should be used, and incompatible chemicals should be stored separately. Appropriate labels should be securely attached on each chemical waste container indicating the corresponding chemical characteristics of the chemical waste, such as explosive, flammable, oxidizing, irritant, toxic, harmful, corrosive, etc. The Contractor shall use a licensed collector to transport and dispose of the chemical wastes, to either the approved Chemical Waste Treatment Centre, or another licensed facility. 	√			

Environmental Checklist	Implementation Stages*			Remark
	Yes	No	Not Obs N/A	
Waste Management				
General Refuse				
General refuse should be stored in enclosed bins or compaction units separate from C&D material.	✓			
A reputable waste collector should be employed by the contractor to remove general refuse from the site, separately from C&D material.	✓			
An enclosed and covered area should be provided to reduce the occurrence of 'wind blown' light material.	✓			
Marine Dredged Sediment (During transportation and disposal)				
Bottom opening of barges shall be fitted with tight fitting seals to prevent leakage of material. Excess material shall be cleaned from the decks and exposed fittings of barges and dredgers before the vessel is moved	✓			
Monitoring of the barge loading shall be conducted to ensure that loss of material does not take place during transportation. Transport barges or vessels shall be equipped with automatic self-monitoring devices as specified by the EPD	✓			
Barges or hopper barges shall not be filled to a level that would cause the overflow of materials or sediment laden water during loading or transportation.	✓			
Site Practices				
Nomination of an approved person, such as a site manager, to be responsible for good site practices, arrangements for collection and effective disposal to an appropriate facility, of all wastes generated at the site	✓			
Training of site personnel in proper waste management and chemical handling procedures	✓			
Provision of sufficient waste disposal points and regular collection of waste	✓			
Good site practices should be adopted to clean the rubbish and litter on a regular basis so as to prevent the rubbish and litter from dropping into the nearby environment.	✓			
Appropriate measures to minimise windblown litter and dust during transportation of waste by either covering trucks or by transporting wastes in enclosed containers	✓			
Waste Reduction Measures				
Sort C&D material from demolition and decommissioning of the existing facilities to recover recyclable portions such as metals	✓			
Segregation and storage of different types of waste in different containers, skips or stockpiles to enhance reuse or recycling of materials and their proper disposal	✓			
Encourage collection of aluminium cans by providing separate labelled bins to enable this waste to be segregated from other general refuse generated by the work force	✓			
Proper storage and site practices to minimise the potential for damage or contamination of construction materials	✓			
Plan and stock construction materials carefully to minimise amount of waste generated and avoid unnecessary generation of waste	✓			

Contract No. 9/MSD/08
Laying of Western Cross Harbour Main and Associated Land Mains
From West Kowloon to Sai Ying Pun

Environmental Checklist	Implementation Stages*			Remark
	Yes	No	Not Obs N/A	
Marine Ecology				
Use of one grab dredger only with a maximum production rate of 4,000m ³ per day for dredging.	✓			
Deployment of frame type silt curtain to fully enclose the grab while dredging works are in progress.	✓			
Deployment of silt screen at the sea water intake at Kowloon South Salt Water Pumping Station while dredging works are in progress.	✓			
Good site practices to avoid silt runoff from construction works associated with the construction of the submarine watermain.	✓			
Good Site Practices				
The Environmental Permit should be displaced conspicuously on site.	✓			
Construction noise permits should be posted at site entrance or available for site inspection.	✓			
Chemical storage area provided with lock and located on sealed areas.	✓			
All chemicals should be placed at the banded area with adequate band capacity (>110% of largest tank).	✓			
Any unused chemicals or those with remaining functional capacity should be recycled.	✓			
All generators, fuel and oil storage are within bundle areas.	✓			
Regular cleaning and maintenance programme for waste storage area, drainage systems, silt traps, sumps and oil interceptors.	✓			
A collection area should be provided where waste can be stored and loaded prior to removal from site. An enclosed and covered area is preferred to reduce the occurrence of 'wind blown' light material. If an open area is unavoidable for the storage or loading/unloading of wastes, then the area should be banded and all the polluted surface run-off collected within this area should be diverted into wastewater treatment system.	✓			


Contract No. 9/MWD/08
Laying of Western Cross Harbour Main and Associated Land Mains
From West Kowloon to Sai Ying Pun

Summary of the Weekly Site Inspection:

Item	Details of defective works or observations	Status of the item (closed / continue follow-up)	Proposed Follow Up Action (if required)	Photo Ref.	Target Completion Date
---	---	---	---	---	---

Remark

No defective observation was noted during the weekly site inspection.

Inspected by	Name	Signature	Date
	C I Lau		24 November 2010

Contract No. 9AWSD/08
 Laying of Western Cross Harbour Main and Associated Land Mains
 From West Kowloon to Sai Ying Pun

WEEKLY SITE INSPECTION CHECKLIST

Inspection Date	29/11/2010	Inspected by	RE	IEC	Contractor	ET
Time	10:45 - 12:00	Name			Josine So	

Weather : Sunny (Fine) / Cloudy / Drizzle / Rain / Storm / Hazy
 Condition : Calm (Light) / Breeze / Strong
 Wind : 23°C
 Humidity : High / Moderate / Low

	Implementation Stages*			Remark
	Yes	No	Not Obs	
Environmental Checklist				
Fugitive Dust Emission				
▪ Dust control / mitigation measures shall be provided to prevent dust nuisance.	✓			
▪ Any excavated dusty materials or stockpile of dusty materials should be covered entirely by impervious sheeting or sprayed with water so as to maintain the entire surface wet, and recovered or backfilled or reinstated within 24 hours of the excavation or unloading.	✓			
▪ The working area of excavation should be sprayed with water immediately before, during and immediately after the operations so as to maintain the entire surface wet.	✓			
▪ The load of dusty materials carried by vehicle leaving a construction site should be covered entirely by clean impervious sheeting to ensure that the dusty materials do not leak from the vehicle	✓			
▪ Where a site boundary adjoins a road, streets or other area accessible to the public, hoarding of not less than 2.4m high from ground level should be provided along the entire length except for a site entrance or exit.	✓			
▪ The area where vehicle washing takes place and the section of the road between the washing facilities and the exit point should be paved with concrete, bituminous materials or hardcores.			✓	
▪ Every main haul road should be sealed with concrete and kept clear of dusty materials or sprayed with water so as to maintain the entire road surface wet.	✓			
▪ The portion of road leading only to a construction site that is within 30m of a designated vehicle entrance or exit should be kept clear of dusty materials.	✓			
▪ All dusty materials should be sprayed with water prior to any loading, unloading or transfer operation so as to maintain the dusty material wet.	✓			
▪ Vehicle speed should be limited to 10 kph except on completed access roads.	✓			
▪ Every vehicle should be washed to remove any dusty materials from its body and wheels before leaving the construction sites.			✓	
▪ The public road around the site entrance should be kept clean and free from dust.	✓			
▪ Vehicle and equipment should be switched off while not in use.	✓			
▪ All plant and equipment should be well maintained e.g. without black smoke emission.	✓			
▪ Open burning should be prohibited.	✓			

Environmental Checklist

	Implementation Stages*			Remark
	Yes	No	Not Obs N/A	
Noise Impact				
▪ The approved method of working, equipment and sound-reducing measures (e.g. use of silenced type of equipment, etc.) shall be adapted.	✓			
▪ The construction works should be scheduled to minimize noise nuisance. Concurrent noisy works should be carried out at different time slots or spread around the construction sites in order to help to reduce the cumulative noise effect produced in the construction process.	✓			
▪ Noisy equipment and mobile plant shall always be site away from NSRs.	✓			
▪ Machines and plant that may be in intermittent use should be shut down between work periods or should be throttled down to a minimum.	✓			
▪ Powered mechanical equipment (PME) should be covered or shielded by appropriate acoustic materials.	✓			
▪ Mobile or movable noise barriers should be erected near to the construction plants to reduce the noise levels from stationary items of PME whenever practicable.	✓			
▪ Quality Powered mechanical equipment (Quality PME), which are construction plants and equipments that are notably quieter, more environmental friendly and efficiently, recognized by the Noise Control Authority for the purpose of CNP application should be used to reduce the noise generated from the construction plants effectively. The Contractor shall note the required procedures involved in application of the QPME.	✓			
▪ Well maintained plant should be operated on-site and plant should be serviced regularly during the construction works.	✓			
▪ Air compressors and hand held breakers should have noise labels.	✓			
▪ Compressors and generators should operate with door closed.	✓			
▪ Material stockpiles and other structures should be effectively utilised, where practicable, to screen noise from on-site construction activities.	✓			
Water Quality				
Mitigation Measures for Dredging				
▪ Dredging should be undertaken using one grab dredger only with a maximum production rate of 4,000m ³ per day.	✓			
▪ Deployment of frame type silt curtain should be fully enclosed the grab while dredging works are in progress.	✓			
▪ Deployment of silt screen should be at the sea water intake at Kowloon South Salt Water Pumping Station while dredging works are in progress	✓			
▪ Tight-closing grabs should be used to minimize the loss of sediment to suspension during dredging works. For dredging of any contaminated mud, closed watertight grabs must be used.	✓			
▪ All vessels should be sized so that adequate clearance is maintained between vessels and the seabed in all tide conditions, to ensure that undue turbidity is not generated by turbulence from vessel movement or propeller wash	✓			
▪ The decks of all vessels should be kept tidy and free of oil or other substances that might be accidentally or otherwise washed overboard	✓			
▪ Adequate free board shall be maintained on barges to ensure that decks are not washed by wave action.	✓			
▪ All barges used for the transport of dredged materials should be fitted with tight bottom seals to prevent leakage of material during loading and transport	✓			
▪ Construction activities should not cause foam, oil, grease, scum, litter or other objectionable matter to be present in the water within the site or dumping grounds	✓			
▪ Loading of barges should be controlled to prevent splashing of material into the surrounding waters. Barges should not be filled to a level that would cause the overflow of materials or sediment laden water during loading or transportation	✓			
▪ The speed of vessels should be controlled within the works area to prevent propeller wash from stirring up the seabed sediments	✓			

Contract No. 9/WS/D/08
Laying of Western Cross Harbour Main and Associated Land Mains
From West Kowloon to Sai Ying Pun

Environmental Checklist	Implementation Stages*			Remark
	Yes	No	Not Obs N/A	
Water Quality				
Mitigation Measures for other Construction Activities				
<ul style="list-style-type: none"> Sedimentation tanks with sufficient capacity, constructed from pre-formed individual cells of approximately 6 to 8 m³ capacities, are recommended as a general mitigation measure which can be used for settling surface runoff prior to disposal. The system capacity should be flexible and able to handle multiple inputs from a variety of sources and suited to applications where the influent is pumped Manholes (including newly constructed ones) should always be adequately covered and temporarily sealed so as to prevent silt, construction materials or debris being washed into the storm runoff being directed into foul sewers All vehicles and plant should be cleaned before leaving a construction site to ensure no earth, mud, debris and the like is deposited by them on roads. An adequately designed and located wheel washing bay should be provided at every site exit, and wash-water should have sand and silt settled out and removed at least on a weekly basis to ensure the continued efficiency of the process. The section of access road leading to, and exiting from, the wheel-wash bay to the public road should be paved with sufficient backfill toward the wheel-wash bay to prevent vehicle tracking of soil and silt water to public roads and drains Fuel tanks and storage areas should be provided with locks and be located on sealed areas, within bunds of a capacity equal to 110% of the storage capacity of the largest tank, to prevent spilled fuel oils from reaching the coastal waters of the Victoria Harbour and Western Harbour WQZs Portable chemical toilets should be used to handle construction workforce sewage prior to discharge to the existing trunk sewer. Sufficient numbers of portable toilets shall be provided by a licensed contractor to serve the construction workers. The Contractor shall also be responsible for waste disposal and maintenance practices. Construction site runoff should be prevented or minimised in accordance with the guidelines stipulated in the EPD's Practice Note for Professional Persons, Construction Site Drainage (ProPECC PN 1/94). All discharges from the construction site should be controlled to comply with the standards for effluents discharged into the Victoria Harbour WQZ under the TM-DSS. Unnecessary water retained in receptacles and standing water should be avoided to prevent mosquito breeding. 	√			
Waste Management				
C&D Materials				
<ul style="list-style-type: none"> Excavated materials should be reused on-site as backfilling material and for landscaping works as far as practicable. C&D material generated from excavation works should be disposed of at public fill reception facilities for other beneficial uses. A recording system for the amount of wastes generated, recycled and disposed (including the disposal sites) should be proposed A recording system for the amount of wastes generated, recycled and disposed (including the disposal sites) should be used, e.g. trip ticket system for chemical waste disposal. Quantities could be determined by weighing each load or other suitable methods. 	√		√	
Chemical Waste				
<ul style="list-style-type: none"> Good quality containers compatible with the chemical wastes should be used, and incompatible chemicals should be stored separately. Appropriate labels should be securely attached on each chemical waste container indicating the corresponding chemical characteristics of the chemical waste, such as explosive, flammable, oxidizing, irritant, toxic, harmful, corrosive, etc. The Contractor shall use a licensed collector to transport and dispose of the chemical wastes, to either the approved Chemical Waste Treatment Centre, or another licensed facility. 	√			

Environmental Checklist	Implementation Stages*			Remark
	Yes	No	Not Obs N/A	
Waste Management				
General Refuse				
▪ General refuse should be stored in enclosed bins or compaction units separate from C&D material.	✓			
▪ A reputable waste collector should be employed by the contractor to remove general refuse from the site, separately from C&D material.	✓			
▪ An enclosed and covered area should be provided to reduce the occurrence of 'wind blown' light material.	✓			
Marine Dredged Sediment (During transportation and disposal)				
▪ Bottom opening of barges shall be fitted with tight fitting seals to prevent leakage of material. Excess material shall be cleaned from the decks and exposed fittings of barges and dredgers before the vessel is moved	✓			
▪ Monitoring of the barge loading shall be conducted to ensure that loss of material does not take place during transportation. Transport barges or vessels shall be equipped with automatic self-monitoring devices as specified by the EPD	✓			
▪ Barges or hopper barges shall not be filled to a level that would cause the overflow of materials or sediment laden water during loading or transportation.	✓			
Site Practices				
▪ Nomination of an approved person, such as a site manager, to be responsible for good site practices, arrangements for collection and effective disposal to an appropriate facility, of all wastes generated at the site	✓			
▪ Training of site personnel in proper waste management and chemical handling procedures	✓			
▪ Provision of sufficient waste disposal points and regular collection of waste	✓			
▪ Good site practices should be adopted to clean the rubbish and litter on a regular basis so as to prevent the rubbish and litter from dropping into the nearby environment.	✓			
▪ Appropriate measures to minimise windblown litter and dust during transportation of waste by either covering trucks or by transporting wastes in enclosed containers	✓			
Waste Reduction Measures				
▪ Sort C&D material from demolition and decommissioning of the existing facilities to recover recyclable portions such as metals	✓			
▪ Segregation and storage of different types of waste in different containers, skips or stockpiles to enhance reuse or recycling of materials and their proper disposal	✓			
▪ Encourage collection of aluminium cans by providing separate labelled bins to enable this waste to be segregated from other general refuse generated by the work force	✓			
▪ Proper storage and site practices to minimise the potential for damage or contamination of construction materials	✓			
▪ Plan and stock construction materials carefully to minimise amount of waste generated and avoid unnecessary generation of waste	✓			

Contract No. 9/MSD/08
Laying of Western Cross Harbour Main and Associated Land Mains
From West Kowloon to Sai Ying Pun

Environmental Checklist		Implementation Stages*			Remark
		Yes	No	Not Obs N/A	
Marine Ecology					
▪	Use of one grab dredger only with a maximum production rate of 4,000m ³ per day for dredging.	√			
▪	Deployment of frame type silt curtain to fully enclose the grab while dredging works are in progress.	√			
▪	Deployment of silt screen at the sea water intake at Kowloon South Salt Water Pumping Station while dredging works are in progress.	√			
▪	Good site practices to avoid silt runoff from construction works associated with the construction of the submarine watermain.	√			
Good Site Practices					
•	The Environmental Permit should be displaced conspicuously on site.	√			
•	Construction noise permits should be posted at site entrance or available for site inspection.	√			
▪	Chemical storage area provided with lock and located on sealed areas.	√			
▪	All chemicals should be placed at the banded area with adequate band capacity (> 110% of largest tank).	√			
▪	Any unused chemicals or those with remaining functional capacity should be recycled.	√			
▪	All generators, fuel and oil storage are within bundle areas.	√			
▪	Regular cleaning and maintenance programme for waste storage area, drainage systems, silt traps, sumps and oil interceptors.	√			
▪	A collection area should be provided where waste can be stored and loaded prior to removal from site. An enclosed and covered area is preferred to reduce the occurrence of 'wind blown' light material. If an open area is unavoidable for the storage or loading/unloading of wastes, then the area should be bunded and all the polluted surface run-off collected within this area should be diverted into wastewater treatment system.	√			


Contract No. 9/WSD/08
Laying of Western Cross Harbour Main and Associated Land Mains
From West Kowloon to Sai Ying Pun

Summary of the Weekly Site Inspection:

Item	Details of defective works or observations	Status of the item (closed / continue follow-up)	Proposed Follow Up Action (if required)	Photo Ref.	Target Completion Date
---	---	---	---	---	---

Remark

No defective observation was noted during the weekly site inspection.

Name	Signature	Date
Inspected by C L Lau		29 November 2010



Appendix G

Implementation Schedule of Mitigation Measures



Environmental Protection Measures		Location	Implementation Status				
			Implemented	Partially implemented	Not implemented	Not Applicable	
Noise Impact							
<ul style="list-style-type: none"> Well maintained plant should be operated on-site and plant should be serviced regularly during the construction works. Air compressors and hand held breakers should have noise labels. Compressors and generators should operate with door closed. Material stockpiles and other structures should be effectively utilised, where practicable, to screen noise from on-site construction activities. 		All areas All areas All areas All areas	✓ ✓ ✓ ✓				
Water Quality							
Mitigation Measures for Dredging							
<ul style="list-style-type: none"> Dredging should be undertaken using one grab dredger only with a maximum production rate of 4,000m³ per day. Deployment of frame type silt curtain should be fully enclose the grab while dredging works are in progress. Deployment of silt screen should be at the sea water intake at Kowloon South Salt Water Pumping Station while dredging works are in progress. Tight-closing grabs should be used to minimize the loss of sediment to suspension during dredging works. For dredging of any contaminated mud, closed watertight grabs must be used. All vessels should be sized so that adequate clearance is maintained between vessels and the seabed in all tide conditions, to ensure that undue turbidity is not generated by turbulence from vessel movement or propeller wash The decks of all vessels should be kept tidy and free of oil or other substances that might be accidentally or otherwise washed overboard Adequate free board shall be maintained on barges to ensure that decks are not washed by wave action All barges used for the transport of dredged materials should be fitted with tight bottom seals to prevent leakage of material during loading and transport Construction activities should not cause foam, oil, grease, scum, litter or other objectionable matter to be present in the water within the site or dumping grounds Loading of barges should be controlled to prevent splashing of material into the surrounding waters. Barges should not be filled to a level that would cause the overflow of materials or sediment laden water during loading or transportation The speed of vessels should be controlled within the works area to prevent propeller wash from stirring up the seabed sediments 		Marine Marine Marine Marine Marine Marine Marine Marine Marine Marine Marine Marine Marine	✓ ✓ ✓ ✓ ✓ ✓ ✓ ✓ ✓ ✓ ✓ ✓ ✓				
Mitigation Measures for other Construction Activities							
<ul style="list-style-type: none"> Sedimentation tanks with sufficient capacity, constructed from pre-formed individual cells of approximately 6 to 8 m³ capacities, are recommended as a general mitigation measure which can be used for settling surface runoff prior to disposal. The system capacity should be flexible and able to handle multiple inputs from a variety of sources and suited to applications where the influent is pumped Manholes (including newly constructed ones) should always be adequately covered and temporarily sealed so as to prevent silt, construction materials or debris being washed into the storm runoff being directed into foul sewers All vehicles and plant should be cleaned before leaving a construction site to ensure no earth, mud, debris and the like is deposited by them on roads. An adequately designed and located wheel washing bay should be provided at every site exit, and wash-water should have sand and silt settled out and removed at least on a weekly basis to ensure the continued efficiency of the process. The section of access road leading to, and exiting from, the wheel-wash bay to the public road should be paved with sufficient backfill toward the wheel-wash bay to prevent vehicle tracking of soil and silty water to public roads and drains Fuel tanks and storage areas should be provided with locks and be located on sealed areas, within bunds of a capacity equal to 110% of the storage capacity of the largest tank, to prevent spilled fuel oils from reaching the coastal waters of the Victoria Harbour and Western Harbour WCZs 		All areas All areas All areas All areas All areas All areas	✓ ✓ ✓ ✓ ✓ ✓			✓ ✓ ✓ ✓ ✓ ✓	




Environmental Protection Measures		Location	Implementation Status		
			Implemented	Partially Implemented	Not Implemented / Not Applicable
Water Quality					
Mitigation Measures for other Construction Activities					
<ul style="list-style-type: none"> Portable chemical toilets should be used to handle construction workforce sewage prior to discharge to the existing trunk sewer. Sufficient numbers of portable toilets shall be provided by a licensed contractor to serve the construction workers. The Contractor shall also be responsible for waste disposal and maintenance practices. Construction site runoff should be prevented or minimised in accordance with the guidelines stipulated in the EPD's Practice Note for Professional Persons, Construction Site Drainage (ProPECC PN 1/94). All discharges from the construction site should be controlled to comply with the standards for effluents discharged into the Victoria Harbour WCZ under the TM-DSS. Unnecessary water retained in receptacles and standing water should be avoided to prevent mosquito breeding. 	All areas	✓			
Waste Management					
C&D Materials					
<ul style="list-style-type: none"> Excavated materials should be reused on-site as backfilling material and for landscaping works as far as practicable. C&D material generated from excavation works should be disposed of at public fill reception facilities for other beneficial uses. A recording system for the amount of wastes generated, recycled and disposed (including the disposal sites) should be proposed A recording system for the amount of wastes generated, recycled and disposed (including the disposal sites) should be used, e.g. trip ticket system for chemical waste disposal. Quantities could be determined by weighing each load or other suitable methods. 	All areas	✓			✓
Chemical Waste					
<ul style="list-style-type: none"> Good quality containers compatible with the chemical wastes should be used, and incompatible chemicals should be stored separately. Appropriate labels should be securely attached on each chemical waste container indicating the corresponding chemical characteristics of the chemical waste, such as explosive, flammable, oxidizing, irritant, toxic, harmful, corrosive, etc. The Contractor shall use a licensed collector to transport and dispose of the chemical wastes, to either the approved Chemical Waste Treatment Centre, or another licensed facility. 	All areas	✓			
General Refuse					
<ul style="list-style-type: none"> General refuse should be stored in enclosed bins or compaction units separate from C&D material. A reputable waste collector should be employed by the contractor to remove general refuse from the site, separately from C&D material. An enclosed and covered area should be provided to reduce the occurrence of 'wind blown' light material. 	All areas	✓			
Marine Dredged Sediment (During transportation and disposal)					
<ul style="list-style-type: none"> Bottom opening of barges shall be fitted with tight fitting seals to prevent leakage of material. Excess material shall be cleaned from the decks and exposed fittings of barges and dredgers before the vessel is moved Monitoring of the barge loading shall be conducted to ensure that loss of material does not take place during transportation. Transport barges or vessels shall be equipped with automatic self-monitoring devices as specified by the EPD Barges or hopper barges shall not be filled to a level that would cause the overflow of materials or sediment laden water during loading or transportation. 	Marine	✓			
Good Site Practices					
<ul style="list-style-type: none"> Nomination of an approved person, such as a site manager, to be responsible for good site practices, arrangements for collection and effective disposal to an appropriate facility, of all wastes generated at the site Training of site personnel in proper waste management and chemical handling procedures Provision of sufficient waste disposal points and regular collection of waste 	All areas	✓			
	All areas	✓			
	All areas	✓			



Appendix H

Site General Layout plan

MATCH LINE
 SEE SHEET 9/MSD/08
 SHEET NO. 9/MSD/08



NOTES:
 1. THE DRAWING SHALL BE USED IN CONNECTION WITH DRAWING NO. 9/MSD/08/001 TO 004.

LEGEND:

- PROPOSED FRESH WATER MAIN
- PROPOSED SALT WATER MAIN
- PROPOSED WORKS LANE
- EXISTING MAIN
- EXISTING MAIN (SHEET 9/MSD/08/001)
- EXISTING MAIN (SHEET 9/MSD/08/002)
- EXISTING MAIN (SHEET 9/MSD/08/003)
- EXISTING MAIN (SHEET 9/MSD/08/004)
- EXISTING MAIN (SHEET 9/MSD/08/005)
- EXISTING MAIN (SHEET 9/MSD/08/006)
- EXISTING MAIN (SHEET 9/MSD/08/007)
- EXISTING MAIN (SHEET 9/MSD/08/008)
- EXISTING MAIN (SHEET 9/MSD/08/009)
- EXISTING MAIN (SHEET 9/MSD/08/010)
- EXISTING MAIN (SHEET 9/MSD/08/011)
- EXISTING MAIN (SHEET 9/MSD/08/012)
- EXISTING MAIN (SHEET 9/MSD/08/013)
- EXISTING MAIN (SHEET 9/MSD/08/014)
- EXISTING MAIN (SHEET 9/MSD/08/015)
- EXISTING MAIN (SHEET 9/MSD/08/016)
- EXISTING MAIN (SHEET 9/MSD/08/017)
- EXISTING MAIN (SHEET 9/MSD/08/018)
- EXISTING MAIN (SHEET 9/MSD/08/019)
- EXISTING MAIN (SHEET 9/MSD/08/020)

SECTION 1
 SECTION 2
 SECTION 3
 SECTION 4

WORKS AREA WITHIN WHICH THE MAIN TO BE LAYED SHALL BE SUBJECT TO THE PROVISIONS OF THE PUBLIC WORKS ACT AND THE PUBLIC WORKS REGULATIONS. THE MAINS SHALL BE LAYED IN ACCORDANCE WITH THE PROVISIONS OF THE PUBLIC WORKS ACT AND THE PUBLIC WORKS REGULATIONS. THE MAINS SHALL BE LAYED IN ACCORDANCE WITH THE PROVISIONS OF THE PUBLIC WORKS ACT AND THE PUBLIC WORKS REGULATIONS.

Mott MacDonald
 97 WSD/08

THE GOVERNMENT OF THE HONG KONG SPECIAL ADMINISTRATIVE REGION
 WATER SUPPLIES DEPARTMENT

LAYING OF WESTERN CROSS HARBOUR MAIN AND ASSOCIATED LAND MAINS FROM WEST KOWLOON TO SAI YING PUN

POSSESSION OF SITE (SHEET 1 OF 5)

SCALE	1:1000	DATE	24/12/2016	NO.	05
PROJECT	Laying of Western Cross Harbour Main and Associated Land Mains from West Kowloon to Sai Ying Pun	DESIGNER	Mott MacDonald	CLIENT	Water Supplies Department
DRAWN BY	...	CHECKED BY	...	APPROVED BY	...
CHECKED BY	...	DATE	...	SCALE	1:1000
DATE	...	SCALE	1:1000	NO.	05

NOTES

1. THIS DRAWING SHALL BE MADE IN CONFORMANCE WITH DRAWING
2. 241239/6/0301 AND 241239/6/0302
3. THE USER SHALL REFER TO DRAWING NO. 241239/6/0301

01	APR 09	1	TRIGGER APPROVAL NO. 4	1/1	PL
01	MAR 09	1	TRIGGER APPROVAL NO. 3	1/1	SK
01	DEC 08	1	STATE FOR TENDER	1/1	SK
01	DEC 08	1	STATE FOR TENDER	1/1	SK
01	DEC 08	1	STATE FOR TENDER	1/1	SK

Mott MacDonald
 27th Floor
 One World Finance Centre
 120 Robinson Road
 Singapore 068973
 Tel: 65 6337 1133
 Fax: 65 6337 1131
 www.mottmacdonald.com


THE GOVERNMENT OF THE HONG KONG
 SPECIAL ADMINISTRATIVE REGION
 WATER SUPPLIES DEPARTMENT

Project: 9/MSD/08

LAYING OF WESTERN CROSS HARBOUR MAIN
 AND ASSOCIATED LAND MAINS FROM WEST
 KOWLOON TO SAN YING PUN

POSSESSION OF SITE
 (SHEET 2 OF 5)

Version	1.0	Author	SK	Check	SK	Drawn	SK	Scale	1:1000
Issue	1	Issue Date	24/03/09	Issue Description	Final	Project No.	241239	Sheet No.	TEN




© COPYRIGHT RESERVED

Quantities: 1/1044
 This drawing is prepared in accordance with the drawings of the project. The user shall be responsible for the accuracy of the data and the results of the calculations. The user shall be responsible for the accuracy of the data and the results of the calculations. The user shall be responsible for the accuracy of the data and the results of the calculations.

NOTES :

1. THIS DRAWING SHALL BE READ IN CONNECTION WITH DRAWING NO. 241239/G/0301 TO DATE AND CDSK TO CDSK.
2. THE LEGEND SHALL REFER TO DRAWING NO. 241239/G/0301.



DR	DATE	BY	FOR
0	DEC 08	A.	DESIGN FOR TENDER
1			
2			

Mott MacDonald
 25/F, One Asia Building
 111, Queen's Road East
 Hong Kong
 Tel: 852 2511 1111
 Fax: 852 2511 1111
 www.mottmacdonald.com.hk

THE GOVERNMENT OF THE HONG KONG
 SPECIAL ADMINISTRATIVE REGION
 WATER SUPPLIES DEPARTMENT


Project No. 9/WSD/08
 LAYING OF WESTERN CROSS HARBOUR MAIN
 AND ASSOCIATED LAND MAINS FROM WEST
 KOWLOON TO SAN YING PUN

POSSESSION OF SITE
 (SHEET 3 OF 5)

DESIGNER	SCALE	DATE	BY
CHKD BY	DATE	BY	DATE
APPROVED BY	DATE	BY	DATE
PROJECT NO.	241239		
DRAWING NO.	1:1000 0/A1		
TITLE	TEN		

NOTES :

1. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH DRAWING NOS. 241239/C/0301 TO 0303 AND 0305.
2. THE LEGEND SHALL REFER TO DRAWING NO. 241239/C/0301.



01	DATE	01/04/99	REVISION	1	SCALE	AS SHOWN
02	DATE	01/04/99	REVISION	2	SCALE	AS SHOWN
03	DATE	01/04/99	REVISION	3	SCALE	AS SHOWN
04	DATE	01/04/99	REVISION	4	SCALE	AS SHOWN
05	DATE	01/04/99	REVISION	5	SCALE	AS SHOWN
06	DATE	01/04/99	REVISION	6	SCALE	AS SHOWN
07	DATE	01/04/99	REVISION	7	SCALE	AS SHOWN
08	DATE	01/04/99	REVISION	8	SCALE	AS SHOWN
09	DATE	01/04/99	REVISION	9	SCALE	AS SHOWN
10	DATE	01/04/99	REVISION	10	SCALE	AS SHOWN

Mott MacDonald
 THE GOVERNMENT OF THE HONG KONG
 SPECIAL ADMINISTRATIVE REGION
 WATER SUPPLIES DEPARTMENT

9/MSD/08
 LAYING OF WESTERN CROSS HARBOUR MAIN
 AND ASSOCIATED LAND MAINS FROM WEST
 KOWLOON TO SAI YING PUN


POSSESSION OF SITE
 (SHEET 4 OF 5)

PROJECT	NO.	DATE	BY	CHECKED	DATE
11:000 0A1		24/12/98			

Drawing No. 241239/C/0304

NOTES

- THIS DRAWING SHALL BE READ IN CONNECTION WITH DRAWING NOS. 241239/0/0301 TO 0304.
- THE LEGEND SHALL REFER TO DRAWING NO. 241239/0/0301.



Matt MacDonald
 THE GOVERNMENT OF THE HONG KONG
 SPECIAL ADMINISTRATIVE REGION
 WATER SUPPLIES DEPARTMENT

Project: 9/MSD/08
 LAYING OF WESTERN CROSS HARBOUR MAIN AND ASSOCIATED LAND MAINS FROM WEST KOWLOON TO SA YING FUN
 POSSESSION OF SITE (SHEET 5 OF 5)
 Scale: 1:250 @A1
 Drawing No.: 241239/0/0305
 Revision No.: 02

This document is the property of the Water Supplies Department. It is to be used for the purpose for which it is issued and is not to be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written permission of the Water Supplies Department.



Appendix I

Monitoring Schedule for this Month and Coming Month

Contract No. 9/WSD/08

Laying of Western Cross Harbour Main & Associated Land Mains from West Kowloon to Sai Ying Pun
Time Schedule for Impact Marine Water Quality Monitoring (WQM), Noise Monitoring (NM) and Weekly Site Inspection (SI)

December 2010

Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
			01-Dec NM (WK-Daytime) NM (SYP-Daytime)	02-Dec WQM Mid-Ebb 07:00 - 11:30 Mid-Flood 15:00 - 19:30	03-Dec	04-Dec WQM Mid-Ebb 08:00 - 12:30 Mid-Flood 14:00 - 18:30
05-Dec	06-Dec	07-Dec	08-Dec NM (WK-Daytime) NM (SYP-Daytime)	09-Dec WQM Mid-Flood 08:00 - 12:30 Mid-Ebb 13:30 - 17:30	10-Dec	11-Dec WQM Mid-Flood 09:00 - 13:30 Mid-Ebb 15:00 - 19:30
12-Dec	13-Dec	14-Dec	15-Dec NM (WK-Daytime) NM (SYP-Daytime)	16-Dec WQM Mid-Ebb 06:30 - 10:30 Mid-Flood 12:00 - 16:30	17-Dec	18-Dec WQM Mid-Ebb 07:30 - 11:30 Mid-Flood 13:00 - 17:30
19-Dec	20-Dec	21-Dec	22-Dec NM (WK-Daytime) NM (SYP-Daytime)	23-Dec WQM Mid-Flood 07:15 - 11:45 Mid-Ebb 13:00 - 17:30	24-Dec	25-Dec
26-Dec	27-Dec	28-Dec	29-Dec NM (WK-Daytime) NM (SYP-Daytime)	30-Dec WQM Mid-Ebb 11:30 - 16:00 Mid-Flood 17:30 - 21:30	31-Dec	01-Jan

Contract No. 9/WSD/08

Laying of Western Cross Harbour Main & Associated Land Mains from West Kowloon to Sai Ying Pun
 Time Schedule for Impact Marine Water Quality Monitoring (WQM), Noise Monitoring (NM) and Weekly Site Inspection (SI)
 November 2010

Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
	01-Nov	02-Nov	03-Nov	04-Nov	05-Nov	06-Nov
	07-Nov	08-Nov	09-Nov	10-Nov	11-Nov	12-Nov
	14-Nov	15-Nov	16-Nov	17-Nov	18-Nov	19-Nov
	21-Nov	22-Nov	23-Nov	24-Nov	25-Nov	26-Nov
	28-Nov	29-Nov	30-Nov			27-Nov
NM Night-time (West Kowloon)	NM (SYP-Daytime)	WQM Mid-Flood 07:00 - 11:00 Mid-Ebb 12:30 - 17:00	SI	WQM Mid-Flood 07:00 - 11:00 Mid-Ebb 12:00 - 16:00	NM (WK-Daytime)	WQM Mid-Flood 09:30 - 14:00 Mid-Ebb 15:00 - 19:30 NM Evening-time (West Kowloon) (Sai Ying Pun)
NM Night-time (West Kowloon)	NM (SYP-Daytime)	WQM Mid-Ebb 07:00 - 11:30 Mid-Flood 13:00 - 17:30	SI	WQM Mid-Flood 07:30 - 12:00 Mid-Ebb 13:30 - 18:00	NM (WK-Daytime)	WQM Mid-Ebb 09:00 - 13:30 Mid-Flood 14:30 - 19:00 NM Evening-time (West Kowloon) (Sai Ying Pun)
NM Holiday (West Kowloon) (Sai Ying Pun)	NM (SYP-Daytime)	WQM Mid-Ebb 07:00 - 11:30 Mid-Flood 13:00 - 17:30	SI	WQM Mid-Ebb 07:00 - 11:00 Mid-Flood 13:30 - 18:00	NM (WK-Daytime)	WQM Mid-Ebb 09:00 - 13:30 Mid-Flood 14:30 - 19:00 NM Evening-time (West Kowloon) (Sai Ying Pun)
NM Holiday (West Kowloon) (Sai Ying Pun)	NM (SYP-Daytime)	WQM Mid-Flood 07:00 - 11:30 Mid-Ebb 13:00 - 17:00	SI	WQM Mid-Flood 09:00 - 13:30 Mid-Ebb 15:00 - 19:30	NM (WK-Daytime)	WQM Mid-Flood 09:00 - 13:30 Mid-Flood 13:30 - 18:00
NM Night-time (West Kowloon)	NM (SYP-Daytime)	WQM Mid-Ebb 07:00 - 11:30 Mid-Flood 13:00 - 17:30	SI	WQM Mid-Flood 09:00 - 13:30 Mid-Ebb 15:00 - 19:30	NM (WK-Daytime)	WQM Mid-Ebb 09:00 - 13:30 Mid-Flood 14:30 - 19:00 NM Evening-time (West Kowloon) (Sai Ying Pun)
NM Night-time (West Kowloon)	NM (SYP-Daytime)	WQM Mid-Flood 07:00 - 11:00 Mid-Ebb 12:30 - 17:00	SI	WQM Mid-Flood 07:30 - 12:00 Mid-Ebb 13:30 - 18:00	NM (WK-Daytime)	WQM Mid-Flood 09:30 - 14:00 Mid-Ebb 15:00 - 19:30 NM Evening-time (West Kowloon) (Sai Ying Pun)
NM Night-time (West Kowloon)	NM (SYP-Daytime)	WQM Mid-Ebb 07:00 - 11:30 Mid-Flood 13:00 - 17:30	SI	WQM Mid-Flood 09:00 - 13:30 Mid-Ebb 15:00 - 19:30	NM (WK-Daytime)	WQM Mid-Flood 09:30 - 14:00 Mid-Ebb 15:00 - 19:30 NM Evening-time (West Kowloon) (Sai Ying Pun)
NM Night-time (West Kowloon)	NM (SYP-Daytime)	WQM Mid-Flood 07:00 - 11:00 Mid-Ebb 12:30 - 17:00	SI	WQM Mid-Flood 07:30 - 12:00 Mid-Ebb 13:30 - 18:00	NM (WK-Daytime)	WQM Mid-Flood 09:30 - 14:00 Mid-Ebb 15:00 - 19:30 NM Evening-time (West Kowloon) (Sai Ying Pun)
NM Night-time (West Kowloon)	NM (SYP-Daytime)	WQM Mid-Ebb 07:00 - 11:30 Mid-Flood 13:00 - 17:30	SI	WQM Mid-Flood 09:00 - 13:30 Mid-Ebb 15:00 - 19:30	NM (WK-Daytime)	WQM Mid-Flood 09:30 - 14:00 Mid-Ebb 15:00 - 19:30 NM Evening-time (West Kowloon) (Sai Ying Pun)



Appendix J

Daily Dredging Summary

Wo Hing - Penta-Ocean Joint Venture					
Contract no. 9/WSD/08					
Laying of Western Cross Harbour Main & Associated Land Mains from					
West Kowloon to Sai Ying Pun					
Summary of Dumping Qty. of Type 1 Marine Sediment (Dispose to East Ninepin Mud Disposal Ground / South Cheung Chau)					
Date	Dumping qty (m ³)	Barge Load per day	Accumulated Dumping Qty.	Permit No.	Mud Disposal Ground
	(bulk volume)		(bulk volume)		
30-Apr-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
01-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
02-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
03-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
04-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
05-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
06-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
07-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
08-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
09-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
10-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
11-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
12-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
13-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
14-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
15-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
16-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
17-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
18-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
19-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
20-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
21-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
22-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
23-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
24-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
25-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
26-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
27-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
28-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
29-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
30-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
31-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
01-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
02-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
03-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
04-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
05-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
06-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
07-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
08-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
09-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
10-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
11-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
12-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
13-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
14-Jun-2010	1,400	2	1,400	EP/MD/10-085	East Ninepin Mud Disposal Ground
15-Jun-2010	1,400	2	2,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
16-Jun-2010	2,100	3	4,900	EP/MD/10-085	East Ninepin Mud Disposal Ground
17-Jun-2010	2,800	4	7,700	EP/MD/10-085	East Ninepin Mud Disposal Ground
18-Jun-2010	2,100	3	9,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
19-Jun-2010	2,700	4	12,500	EP/MD/10-085	East Ninepin Mud Disposal Ground
20-Jun-2010	2,800	4	15,300	EP/MD/10-085	East Ninepin Mud Disposal Ground
21-Jun-2010	2,100	3	17,400	EP/MD/10-085	East Ninepin Mud Disposal Ground
22-Jun-2010	2,800	4	20,200	EP/MD/10-085	East Ninepin Mud Disposal Ground
23-Jun-2010	2,100	3	22,300	EP/MD/10-085	East Ninepin Mud Disposal Ground
24-Jun-2010	2,100	3	24,400	EP/MD/10-085	East Ninepin Mud Disposal Ground
25-Jun-2010	2,100	3	26,500	EP/MD/10-085	East Ninepin Mud Disposal Ground
26-Jun-2010	2,100	3	28,600	EP/MD/10-085	East Ninepin Mud Disposal Ground

Wo Hing - Penta-Ocean Joint Venture

Contract no. 9/WSD/08

Laying of Western Cross Harbour Main & Associated Land Mains from West Kowloon to Sai Ying Pun

Summary of Dumping Qty. of Type 1 Marine Sediment (Dispose to East Ninepin Mud Disposal Ground / South Cheung Chau)

Date	Dumping qty (m ³)	Barge Load per day	Accumulated Dumping Qty.	Permit No.	Mud Disposal Ground
	(bulk volume)		(bulk volume)		
27-Jun-2010	700	1	29,300	EP/MD/10-085	East Ninepin Mud Disposal Ground
28-Jun-2010	2,100	3	31,400	EP/MD/10-085	East Ninepin Mud Disposal Ground
29-Jun-2010	1,400	2	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
30-Jun-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
01-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
02-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
03-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
04-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
05-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
06-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
07-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
08-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
09-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
10-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
11-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
12-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
13-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
14-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
15-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
16-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
17-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
18-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
19-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
20-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
21-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
22-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
23-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
24-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
25-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
26-Jul-2010	0	0	32,800	EP/MD/11-039	East Ninepin Mud Disposal Ground
27-Jul-2010	0	0	32,800	EP/MD/11-039	East Ninepin Mud Disposal Ground
28-Jul-2010	0	0	32,800	EP/MD/11-039	East Ninepin Mud Disposal Ground
29-Jul-2010	0	0	32,800	EP/MD/11-039	East Ninepin Mud Disposal Ground
30-Jul-2010	700	1	33,500	EP/MD/11-039	East Ninepin Mud Disposal Ground
31-Jul-2010	1,400	2	34,900	EP/MD/11-039	East Ninepin Mud Disposal Ground
01-Aug-2010	2,100	3	37,000	EP/MD/11-039	East Ninepin Mud Disposal Ground
02-Aug-2010	1,400	2	38,400	EP/MD/11-039	East Ninepin Mud Disposal Ground
03-Aug-2010	700	1	39,100	EP/MD/11-039	East Ninepin Mud Disposal Ground
04-Aug-2010	700	1	39,800	EP/MD/11-039	East Ninepin Mud Disposal Ground
05-Aug-2010	700	1	40,500	EP/MD/11-039	East Ninepin Mud Disposal Ground
06-Aug-2010	0	0	40,500	EP/MD/11-039	East Ninepin Mud Disposal Ground
07-Aug-2010	0	0	40,500	EP/MD/11-039	East Ninepin Mud Disposal Ground
08-Aug-2010	0	0	40,500	EP/MD/11-039	East Ninepin Mud Disposal Ground
09-Aug-2010	0	0	40,500	EP/MD/11-039	East Ninepin Mud Disposal Ground
10-Aug-2010	0	0	40,500	EP/MD/11-039	East Ninepin Mud Disposal Ground
11-Aug-2010	0	0	40,500	EP/MD/11-039	East Ninepin Mud Disposal Ground
12-Aug-2010	1,400	2	41,900	EP/MD/11-039	East Ninepin Mud Disposal Ground
13-Aug-2010	1,400	2	43,300	EP/MD/11-039	East Ninepin Mud Disposal Ground
14-Aug-2010	2,100	3	45,400	EP/MD/11-039	East Ninepin Mud Disposal Ground
15-Aug-2010	2,100	3	47,500	EP/MD/11-039	East Ninepin Mud Disposal Ground
16-Aug-2010	2,100	3	49,600	EP/MD/11-039	East Ninepin Mud Disposal Ground
17-Aug-2010	700	1	50,300	EP/MD/11-039	East Ninepin Mud Disposal Ground
18-Aug-2010	1,400	2	51,700	EP/MD/11-039	East Ninepin Mud Disposal Ground
19-Aug-2010	1,400	2	53,100	EP/MD/11-039	East Ninepin Mud Disposal Ground
20-Aug-2010	2,100	3	55,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
21-Aug-2010	1,400	2	56,600	EP/MD/11-039	East Ninepin Mud Disposal Ground

Wo Hing - Penta-Ocean Joint Venture

Contract no. 9/WSD/08

Laying of Western Cross Harbour Main & Associated Land Mains from
West Kowloon to Sai Ying Pun

Summary of Dumping Qty. of Type 1 Marine Sediment (Dispose to East Ninepin Mud Disposal Ground / South Cheung Chau)

Date	Dumping qty (m ³)	Barge Load per day	Accumulated Dumping Qty.	Permit No.	Mud Disposal Ground
	(bulk volume)		(bulk volume)		
22-Aug-2010	700	1	57,300	EP/MD/11-039	East Ninepin Mud Disposal Ground
23-Aug-2010	0	0	57,300	EP/MD/11-039	East Ninepin Mud Disposal Ground
24-Aug-2010	1,400	2	58,700	EP/MD/11-039	East Ninepin Mud Disposal Ground
25-Aug-2010	1,400	2	60,100	EP/MD/11-039	East Ninepin Mud Disposal Ground
26-Aug-2010	2,100	3	62,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
27-Aug-2010	2,100	3	64,300	EP/MD/11-039	East Ninepin Mud Disposal Ground
28-Aug-2010	0	0	64,300	EP/MD/11-039	East Ninepin Mud Disposal Ground
29-Aug-2010	1,400	2	65,700	EP/MD/11-039	East Ninepin Mud Disposal Ground
30-Aug-2010	1,400	2	67,100	EP/MD/11-039	East Ninepin Mud Disposal Ground
31-Aug-2010	2,100	3	69,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
01-Sep-2010	1,400	2	70,600	EP/MD/11-039	East Ninepin Mud Disposal Ground
02-Sep-2010	2,100	3	72,700	EP/MD/11-039	East Ninepin Mud Disposal Ground
03-Sep-2010	2,100	3	74,800	EP/MD/11-039	East Ninepin Mud Disposal Ground
04-Sep-2010	2,800	4	77,600	EP/MD/11-039	East Ninepin Mud Disposal Ground
05-Sep-2010	2,100	3	79,700	EP/MD/11-039	East Ninepin Mud Disposal Ground
06-Sep-2010	1,400	2	81,100	EP/MD/11-039	East Ninepin Mud Disposal Ground
07-Sep-2010	0	0	81,100	EP/MD/11-039	East Ninepin Mud Disposal Ground
08-Sep-2010	700	1	81,800	EP/MD/11-039	East Ninepin Mud Disposal Ground
09-Sep-2010	1,400	2	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
10-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
11-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
12-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
13-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
14-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
15-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
16-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
17-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
18-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
19-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
20-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
21-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
22-Sep-2010	700	1	83,900	EP/MD/11-039	East Ninepin Mud Disposal Ground
23-Sep-2010	0	0	83,900	EP/MD/11-039	East Ninepin Mud Disposal Ground
24-Sep-2010	0	0	83,900	EP/MD/11-039	East Ninepin Mud Disposal Ground
25-Sep-2010	0	0	83,900	EP/MD/11-039	East Ninepin Mud Disposal Ground
26-Sep-2010	0	0	83,900	EP/MD/11-039	East Ninepin Mud Disposal Ground
27-Sep-2010	0	0	83,900	EP/MD/11-039	East Ninepin Mud Disposal Ground
28-Sep-2010	0	0	83,900	EP/MD/11-039	East Ninepin Mud Disposal Ground
29-Sep-2010	0	0	83,900	EP/MD/11-039	East Ninepin Mud Disposal Ground
30-Sep-2010	0	0	83,900	EP/MD/11-039	East Ninepin Mud Disposal Ground
01-Oct-2010	500	1	84,400	EP/MD/11-069	South Cheung Chau
02-Oct-2010	500	1	84,900	EP/MD/11-069	South Cheung Chau
03-Oct-2010	1,000	2	85,900	EP/MD/11-069	South Cheung Chau
04-Oct-2010	1,000	2	86,900	EP/MD/11-069	South Cheung Chau
05-Oct-2010	500	1	87,400	EP/MD/11-069	South Cheung Chau
06-Oct-2010	1,000	2	88,400	EP/MD/11-069	South Cheung Chau
07-Oct-2010	1,500	3	89,900	EP/MD/11-069	South Cheung Chau
08-Oct-2010	1,000	2	90,900	EP/MD/11-069	South Cheung Chau
09-Oct-2010	500	1	91,400	EP/MD/11-069	South Cheung Chau
10-Oct-2010	0	0	91,400	EP/MD/11-069	South Cheung Chau
11-Oct-2010	1,500	3	92,900	EP/MD/11-069	South Cheung Chau
12-Oct-2010	1,000	2	93,900	EP/MD/11-069	South Cheung Chau
13-Oct-2010	2,000	4	95,900	EP/MD/11-069	South Cheung Chau
14-Oct-2010	2,000	4	97,900	EP/MD/11-069	South Cheung Chau
15-Oct-2010	1,500	3	99,400	EP/MD/11-069	South Cheung Chau
16-Oct-2010	2,000	4	101,400	EP/MD/11-069	South Cheung Chau

Wo Hing - Penta-Ocean Joint Venture					
Contract no. 9/WSD/08					
Laying of Western Cross Harbour Main & Associated Land Mains from West Kowloon to Sai Ying Pun					
Summary of Dumping Qty. of Type 1 Marine Sediment (Dispose to East Ninepin Mud Disposal Ground / South Cheung Chau)					
Date	Dumping qty (m ³)	Barge Load per day	Accumulated Dumping Qty.	Permit No.	Mud Disposal Ground
	(bulk volume)		(bulk volume)		
17-Oct-2010	2,000	4	103,400	EP/MD/11-069	South Cheung Chau
18-Oct-2010	2,000	4	105,400	EP/MD/11-069	South Cheung Chau
19-Oct-2010	1,500	3	106,900	EP/MD/11-069	South Cheung Chau
20-Oct-2010	1,000	2	107,900	EP/MD/11-069	South Cheung Chau
21-Oct-2010	0	0	107,900	EP/MD/11-069	South Cheung Chau
22-Oct-2010	0	0	107,900	EP/MD/11-069	South Cheung Chau
23-Oct-2010	500	1	108,400	EP/MD/11-069	South Cheung Chau
24-Oct-2010	2,000	4	110,400	EP/MD/11-069	South Cheung Chau
25-Oct-2010	1,500	3	111,900	EP/MD/11-069	South Cheung Chau
26-Oct-2010	1,000	2	112,900	EP/MD/11-069	South Cheung Chau
27-Oct-2010	1,000	2	113,900	EP/MD/11-069	South Cheung Chau
28-Oct-2010	0	0	113,900	EP/MD/11-069	South Cheung Chau
29-Oct-2010	1,000	2	114,900	EP/MD/11-069	South Cheung Chau
30-Oct-2010	500	1	115,400	EP/MD/11-069	South Cheung Chau
31-Oct-2010	1,000	2	116,400	EP/MD/11-069	South Cheung Chau
01-Nov-2010	1,000	2	117,400	EP/MD/11-069	South Cheung Chau
02-Nov-2010	500	1	117,900	EP/MD/11-069	South Cheung Chau
03-Nov-2010	1,000	2	118,900	EP/MD/11-069	South Cheung Chau
04-Nov-2010	1,000	2	119,900	EP/MD/11-069	South Cheung Chau
05-Nov-2010	500	1	120,400	EP/MD/11-069	South Cheung Chau
06-Nov-2010	500	1	120,900	EP/MD/11-069	South Cheung Chau
07-Nov-2010	500	1	121,400	EP/MD/11-069	South Cheung Chau
08-Nov-2010	0	0	121,400	EP/MD/11-069	South Cheung Chau
09-Nov-2010	500	1	121,900	EP/MD/11-069	South Cheung Chau
10-Nov-2010	300	1	122,200	EP/MD/11-069	South Cheung Chau
11-Nov-2010	0	0	122,200	EP/MD/11-069	South Cheung Chau
12-Nov-2010	0	0	122,200	EP/MD/11-069	South Cheung Chau
13-Nov-2010	0	0	122,200	EP/MD/11-069	South Cheung Chau
14-Nov-2010	0	0	122,200	EP/MD/11-069	South Cheung Chau
15-Nov-2010	0	0	122,200	EP/MD/11-069	South Cheung Chau
16-Nov-2010	0	0	122,200	EP/MD/11-069	South Cheung Chau
17-Nov-2010	0	0	122,200	EP/MD/11-069	South Cheung Chau
18-Nov-2010	1,500	3	123,700	EP/MD/11-069	South Cheung Chau
19-Nov-2010	1,000	2	124,700	EP/MD/11-069	South Cheung Chau
20-Nov-2010	1,500	3	126,200	EP/MD/11-069	South Cheung Chau
21-Nov-2010	1,000	2	127,200	EP/MD/11-069	South Cheung Chau
22-Nov-2010	1,500	3	128,700	EP/MD/11-069	South Cheung Chau
23-Nov-2010	1,000	2	129,700	EP/MD/11-069	South Cheung Chau
24-Nov-2010	2,000	4	131,700	EP/MD/11-069	South Cheung Chau
25-Nov-2010	1,000	2	132,700	EP/MD/11-069	South Cheung Chau
26-Nov-2010	1,800	4	134,500	EP/MD/11-069	South Cheung Chau
27-Nov-2010	1,000	2	135,500	EP/MD/11-069	South Cheung Chau
28-Nov-2010	1,500	3	137,000	EP/MD/11-069	South Cheung Chau
29-Nov-2010	2,000	4	139,000	EP/MD/11-069	South Cheung Chau
30-Nov-2010	1,500	3	140,500	EP/MD/11-069	South Cheung Chau
TOTAL =	116,400	185			

Wo Hing - Penta-Ocean Joint Venture				
Contract no. 9/WSD/08				
Laying of Western Cross Harbour Main & Associated Land Mains from West Kowloon to Sai Ying Pun				
Summary of Dumping Qty. of Type 2 Marine Sediment				
Date	Dumping qty (m³)	Barge Load per day	Accumulated Dumping Qty.	Permit No.
	(bulk volume)		(bulk volume)	
05-May-2010	440	1	440	EP/MD/10-086
06-May-2010	1,280	3	1,720	EP/MD/10-086
07-May-2010	0	0	1,720	EP/MD/10-086
08-May-2010	0	0	1,720	EP/MD/10-086
09-May-2010	1,400	2	3,120	EP/MD/10-086
10-May-2010	1,400	2	4,520	EP/MD/10-086
11-May-2010	1,600	2	5,820	EP/MD/10-086
12-May-2010	1,800	3	7,620	EP/MD/10-086
13-May-2010	1,200	2	8,820	EP/MD/10-086
14-May-2010	0	0	8,820	EP/MD/10-086
15-May-2010	0	0	8,820	EP/MD/10-086
16-May-2010	600	1	9,420	EP/MD/10-086
17-May-2010	1,200	2	10,620	EP/MD/10-086
18-May-2010	700	1	11,320	EP/MD/10-086
19-May-2010	2,000	3	13,320	EP/MD/10-086
20-May-2010	1,400	2	14,720	EP/MD/10-086
21-May-2010	1,400	2	16,120	EP/MD/10-086
22-May-2010	2,100	3	18,220	EP/MD/10-086
23-May-2010	1,400	2	19,620	EP/MD/10-086
24-May-2010	1,400	2	21,020	EP/MD/10-086
25-May-2010	1,600	2	22,320	EP/MD/10-086
26-May-2010	1,400	2	23,720	EP/MD/10-086
27-May-2010	1,300	2	25,020	EP/MD/10-086
28-May-2010	1,400	2	26,420	EP/MD/10-086
29-May-2010	600	1	27,020	EP/MD/10-086
30-May-2010	2,100	3	29,120	EP/MD/11-012
31-May-2010	700	1	29,820	EP/MD/11-012
01-Jun-2010	1,900	3	31,720	EP/MD/11-012
02-Jun-2010	1,220	2	32,940	EP/MD/11-012
03-Jun-2010	1,300	2	34,240	EP/MD/11-012
04-Jun-2010	1,200	2	35,440	EP/MD/11-012
05-Jun-2010	1,400	2	36,840	EP/MD/11-012
06-Jun-2010	600	1	37,440	EP/MD/11-012
07-Jun-2010	0	0	37,440	EP/MD/11-012
08-Jun-2010	500	1	37,940	EP/MD/11-012
09-Jun-2010	0	0	37,940	EP/MD/11-012
10-Jun-2010	600	1	38,540	EP/MD/11-012
11-Jun-2010	1,200	2	39,740	EP/MD/11-012
12-Jun-2010	1,400	2	41,140	EP/MD/11-012
13-Jun-2010	1,400	2	42,540	EP/MD/11-012
14-Jun-2010	0	0	42,540	EP/MD/11-012
15-Jun-2010	0	0	42,540	EP/MD/11-012
16-Jun-2010	0	0	42,540	EP/MD/11-012
17-Jun-2010	0	0	42,540	EP/MD/11-012
18-Jun-2010	0	0	42,540	EP/MD/11-012
19-Jun-2010	0	0	42,540	EP/MD/11-012

Wo Hing - Penta-Ocean Joint Venture

Contract no. 9/WSD/08
 Laying of Western Cross Harbour Main & Associated Land Mains from
 West Kowloon to Sai Ying Pun

Summary of Dumping Qty. of Type 2 Marine Sediment

Date	Dumping qty (m ³)	Barge Load per day	Accumulated Dumping Qty.	Permit No.
	(bulk volume)		(bulk volume)	
20-Jun-2010	0	0	42,540	EP/MD/11-012
21-Jun-2010	0	0	42,540	EP/MD/11-012
22-Jun-2010	0	0	42,540	EP/MD/11-012
23-Jun-2010	0	0	42,540	EP/MD/11-012
24-Jun-2010	0	0	42,540	EP/MD/11-012
25-Jun-2010	0	0	42,540	EP/MD/11-012
26-Jun-2010	0	0	42,540	EP/MD/11-012
27-Jun-2010	0	0	42,540	EP/MD/11-012
28-Jun-2010	0	0	42,540	EP/MD/11-012
29-Jun-2010	0	0	42,540	EP/MD/11-012
30-Jun-2010	1,200	2	43,740	EP/MD/11-024
01-Jul-2010	2,600	4	46,340	EP/MD/11-024
02-Jul-2010	2,800	4	49,140	EP/MD/11-024
03-Jul-2010	1,400	2	50,540	EP/MD/11-024
04-Jul-2010	2,100	3	52,640	EP/MD/11-024
05-Jul-2010	2,850	4	55,490	EP/MD/11-024
06-Jul-2010	1,400	2	56,890	EP/MD/11-024
07-Jul-2010	1,400	2	58,290	EP/MD/11-024
08-Jul-2010	2,700	4	60,990	EP/MD/11-024
09-Jul-2010	2,100	3	63,090	EP/MD/11-024
10-Jul-2010	2,100	3	65,190	EP/MD/11-024
11-Jul-2010	1,400	2	66,590	EP/MD/11-024
12-Jul-2010	2,150	3	68,740	EP/MD/11-024
13-Jul-2010	2,100	3	70,840	EP/MD/11-024
14-Jul-2010	700	1	71,540	EP/MD/11-024
15-Jul-2010	2,100	3	73,640	EP/MD/11-024
16-Jul-2010	2,100	3	75,740	EP/MD/11-024
17-Jul-2010	700	1	76,440	EP/MD/11-024
18-Jul-2010	700	1	77,140	EP/MD/11-024
19-Jul-2010	2,100	3	79,240	EP/MD/11-024
20-Jul-2010 (18 July 2010)	2,100	3	81,340	EP/MD/11-024
21-Jul-2010	700	1	82,040	EP/MD/11-024
22-Jul-2010	600	1	82,640	EP/MD/11-024
23-Jul-2010	1,400	2	84,040	EP/MD/11-024
24-Jul-2010	1,400	2	85,440	EP/MD/11-024
25-Jul-2010	1,400	2	86,840	EP/MD/11-024
26-Jul-2010	1,450	2	88,290	EP/MD/11-024
27-Jul-2010	2,200	3	90,490	EP/MD/11-024
28-Jul-2010	1,450	2	91,940	EP/MD/11-024
29-Jul-2010	1,500	2	93,440	EP/MD/11-024
30-Jul-2010	0	0	93,440	--
31-Jul-2010	0	0	93,440	--
01-Aug-2010	0	0	93,440	--
02-Aug-2010	0	0	93,440	--

Wo Hing - Penta-Ocean Joint Venture

Contract no. 9/WSD/08

Laying of Western Cross Harbour Main & Associated Land Mains from
West Kowloon to Sai Ying Pun

Summary of Dumping Qty. of Type 2 Marine Sediment

Date	Dumping qty (m ³)	Barge Load per day	Accumulated Dumping Qty.	Permit No.
	(bulk volume)		(bulk volume)	
03-Aug-2010	0	0	93,440	
04-Aug-2010	0	0	93,440	
05-Aug-2010	700	1	94,140	
(dump on 06-Aug-10)				
06-Aug-2010	1,500	2	95,640	EP/MD/11-053
07-Aug-2010	700	1	96,340	EP/MD/11-053
08-Aug-2010	2,100	3	98,440	EP/MD/11-053
09-Aug-2010	1,500	2	99,940	EP/MD/11-053
10-Aug-2010	1,500	2	101,440	EP/MD/11-053
11-Aug-2010	700	1	102,140	EP/MD/11-053
12-Aug-2010	0	0	102,140	EP/MD/11-053
13-Aug-2010	0	0	102,140	EP/MD/11-053
14-Aug-2010	0	0	102,140	EP/MD/11-053
15-Aug-2010	0	0	102,140	EP/MD/11-053
16-Aug-2010	0	0	102,140	EP/MD/11-053
17-Aug-2010	0	0	102,140	EP/MD/11-053
18-Aug-2010	0	0	102,140	EP/MD/11-053
19-Aug-2010	0	0	102,140	EP/MD/11-053
20-Aug-2010	0	0	102,140	EP/MD/11-053
21-Aug-2010	0	0	102,140	EP/MD/11-053
22-Aug-2010	0	0	102,140	EP/MD/11-053
23-Aug-2010	0	0	102,140	EP/MD/11-053
24-Aug-2010	0	0	102,140	EP/MD/11-053
25-Aug-2010	0	0	102,140	EP/MD/11-053
26-Aug-2010	0	0	102,140	EP/MD/11-053
27-Aug-2010	0	0	102,140	EP/MD/11-053
28-Aug-2010	1,400	2	103,540	EP/MD/11-053
29-Aug-2010	700	1	104,240	EP/MD/11-053
30-Aug-2010	0	0	104,240	EP/MD/11-053
31-Aug-2010	750	1	104,990	EP/MD/11-053
01-Sep-2010	0	0	104,990	EP/MD/11-053
02-Sep-2010	0	0	104,990	EP/MD/11-053
03-Sep-2010	0	0	104,990	EP/MD/11-053
04-Sep-2010	0	0	104,990	EP/MD/11-053
05-Sep-2010	0	0	104,990	EP/MD/11-053
TOTAL =	104,990	155		

Wo Hing – Penta-Ocean Joint Venture

Contract No. 9/WSD/08
Laying of Western Cross Harbour Main and Associated Land Mains
From West Kowloon to Sai Ying Pun

Dredging Location of GD "Shun Tat 20" during Overtime Hours 19:00 – 07:00 (next day)

Date	Working Hour fm 07:00 to 23:00 or 07:00 to 07:00 (next day)						Working Hour for overtime fm 19:00 to 23:00 or 19:00 to 07:00 (next day)					
	W Hours fm	W Hours to	Chainage fm	Chainage to	Offset fm	Offset to	OT Hours fm	OT Hours to	Chainage fm	Chainage to	Offset fm	Offset to
03-05-2010	-	-	-	-	-	-	-	-	-	-	-	-
04-05-2010	7:00	23:00	1238	1244	0	+17	22:00	23:00	1238	1244	0	+17
05-05-2010	7:00	23:00	1244	1276	0	+17	19:00	23:00	1264	1276	0	+17
06-05-2010	7:00	23:00	1276	1280	0	+17	19:00	23:00	1252	1264	0	-17
			1238	1264	0	-17						
07-05-2010	7:00	19:00	1264	1264	0	-17	19:00	19:00				
08-05-2010	7:00	19:00	1264	1276	0	+17	19:00	19:00				
09-05-2010	7:00	23:00	1276	1304	0	-17	19:00	23:00	1284	1304	0	-17
10-05-2010	7:00	23:00	1304	1316	0	-17	19:00	23:00	1304	1316	0	-17
			1280	1316	0	+17						
11-05-2010	7:00	23:00	1316	1368	0	+17	19:00	23:00	1348	1368	0	+17
12-05-2010	7:00	23:00	1320	1368	0	-17	19:00	23:00	1348	1368	0	-17
13-05-2010	7:00	23:00	1368	1424	0	-17	19:00	23:00	1400	1424	0	-17
14-05-2010	-	-	-	-	-	-	-	-	-	-	-	-
15-05-2010	7:00	23:00	1368	1376	0	+17	19:00	23:00	1368	1376	0	+17
16-05-2010	7:00	23:00	1376	1392	0	+17	19:00	23:00	1380	1392	0	+17
17-05-2010	7:00	23:00	1392	1416	0	+15.5	19:00	23:00	1416	1432	0	-15.5
			1416	1432	0	-15.5						
18-05-2010	7:00	23:00	1432	1468	0	+15	19:00	23:00	1452	1468	0	+15
19-05-2010	7:00	23:00	1424	1484	0	-15	19:00	23:00	1476	1484	0	-15
20-05-2010	7:00	23:00	1480	1500	0	+12.7	19:00	22:00	1480	1486	0	+14.1
			1472	1486	0	+14.1						
21-05-2010	7:00	23:00	1496	1536	0	+12.9	19:00	23:00	1496	1516	0	-12.9
			1496	1516	0	-12.9						
22-05-2010	7:00	23:00	1516	1572	0	-14.0	19:00	23:00	1564	1572	0	-14.0
			1536	1540	0	+13.1			1536	1540	0	+13.1
23-05-2010	7:00	23:00	1540	1592	0	+16.6	19:00	23:00	1580	1592	0	+16.6
24-05-2010	7:00	23:00	1572	1620	0	-17	19:00	23:00	1592	1620	0	-17
25-05-2010	7:00	23:00	1620	1656	0	+17	19:00	23:00	1608	1636	0	-17
			1608	1636	0	-17						
26-05-2010	7:00	23:00	1636	1660	0	-17	19:00	23:00	1664	1680	0	+17
			1656	1680	0	+17						
27-05-2010	7:00	23:00	1660	1708	0	-17	19:00	23:00	1680	1692	0	+16.8
			1680	1692	0	+16.8						
28-05-2010	7:00	23:00	1692	1712	0	+17	19:00	23:00	1716	1736	0	-16
			1708	1736	0	-16						
29-05-2010	7:00	23:00	1712	1752	0	+16	19:00	23:00	1748	1752	0	+16
			1736	1756	0	-16			1736	1756	0	-16
30-05-2010	7:00	23:00	1656	1800	0	-15	19:00	23:00	1752	1780	0	+16
			1752	1760	0	+16						
31-05-2010	7:00	23:00	1780	1820	0	+15	19:00	23:00	1800	1824	0	-15
			1800	1824	0	-15						
01-06-2010	7:00	23:00	1824	1848	0	-14	19:00	23:00	1820	1844	0	+14
			1820	1844	0	+14						
02-06-2010	7:00	23:00	1844	1876	0	+14	19:00	23:00	1848	1864	0	-14
			1848	1864	0	-14						
03-06-2010	7:00	23:00	1872	1908	0	+13	19:00	19:45	1864	1868	0	-13
			1864	1876	0	-13						
04-06-2010	7:00	23:00	1868	1932	0	-13	19:00	23:00	1868	1932	0	-13
05-06-2010	7:00	23:00	1908	1960	0	+12	19:00	23:00	1944	1960	0	+12
06-06-2010	7:00	23:00	1932	1960	0	-12	19:00	21:00	1960	1970	0	+12
			1960	1970	0	+12						
07-06-2010	7:00	23:00	1960	1970	0	-16	19:00	20:00	1974	1980	0	+12
			1970	1980	0	+12						
08-06-2010	7:00	14:40	1250	1300	0	+19	-	-	-	-	-	-
09-06-2010	7:00	23:00	-	-	-	-	-	-	-	-	-	-
10-06-2010	7:00	23:00	1300	1390	+19	-19	19:00	23:00	1300	1390	+4	+19
11-06-2010	7:00	23:00	1390	1530	+16	-16	19:00	23:00	1490	1530	+16	-16
12-06-2010	7:00	23:00	1530	1665	+18	-18	19:00	23:00	1630	1665	+18	-18
13-06-2010	7:00	23:00	1665	1780	+18	-18	19:00	23:00	1750	1780	+18	-18
	23:00	7:00	1130	1142	-4	-21	23:00	7:00	1130	1142	-4	-21
14-06-2010	7:00	7:00	1142	1174	-4.7	-20.7	19:00	7:00	1162	1174	-4.7	-20.7
15-06-2010	7:00	7:00	1130	1162	+4.7	+20.7	19:00	7:00	1142	1162	+4.7	+20.7
16-06-2010	7:00	7:00	1162	1214	+4.7	+20.7	19:00	7:00	1182	1214	+4.7	+20.7
17-06-2010	7:00	7:00	1214	1222	+4.7	+20.7						
			1174	1210	-4.7	-20.7	19:00	7:00	1186	1210	-4.7	-20.7
18-06-2010	7:00	7:00	1130	1190	+8	-8	19:00	7:00	1158	1190	+8	-8
19-06-2010	7:00	7:00	1190	1238	+8.5	-8.5	19:00	7:00	1214	1238	+8.5	-8.5
20-06-2010	7:00	7:00	1266	1210	-4.5	-20.5	19:00	7:00	1222	1210	-4.5	-20.5
			1226	1250	+4.5	+20.5			1226	1250	+4.5	+20.5
21-06-2010	7:00	7:00	1250	1282	+5.5	+20.5						
			1238	1150	+8.5	-8.5	19:00	7:00	1262	1150	+8.5	-8.5
22-06-2010	7:00	7:00	1266	1302	-5.5	-20.5	19:00	7:00	1266	1302	-5.5	-20.5
			1262	1298	+8.5	-8.5			1262	1298	+8.5	-8.5
			1150	1162	+8.5	-8.5			1150	1162	+8.5	-8.5
23-06-2010	7:00	7:00	1282	1326	+5.5	+20.5						
			1298	1338	+8.5	-8.5	19:00	7:00	1324	1338	+8.5	-8.5
			1162	1188	+8.5	-8.5			1162	1188	+8.5	-8.5
24-06-2010	7:00	7:00	1346	1358	-5.5	-20.5						
			1338	1364	+7.5	-7.5	19:00	7:00	1350	1364	+7.5	-7.5
			1188	1208	+8.5	-8.5			1188	1208	+8.5	-8.5

Wo Hing – Penta-Ocean Joint Venture

Contract No. 9/WSD/08
Laying of Western Cross Harbour Main and Associated Land Mains
From West Kowloon to Sai Ying Pun

Dredging Location of GD "Shun Tat 20" during Overtime Hours 19:00 – 07:00 (next day)

Date	Working Hour fm 07:00 to 23:00 or 07:00 to 07:00 (next day)						Working Hour for overtime fm 19:00 to 23:00 or 19:00 to 07:00 (next day)					
	W Hours fm	W Hours to	Chainage fm	Chainage to	Offset fm	Offset to	OT Hours fm	OT Hours to	Chainage fm	Chainage to	Offset fm	Offset to
25-06-2010	7:00	7:00	1364	1412	+7.5	-7.5	19:00	7:00	1392	1412	+7.5	-7.5
26-06-2010	7:00	23:00	1206	1250	+8.5	-8.5	19:00	23:00	1206	1250	+8.5	-8.5
			1306	1400	-7.5	-20.5			1380	1400	-7.5	-20.5
27-06-2010	7:00	23:00	1412	1444	+7.5	-7.5	19:00	23:00	1412	1444	+7.5	-7.5
			1362	1366	+5	+20			1362	1366	+5	+20
28-06-2010	7:00	23:00	1326	1448	+7.5	+20.5	19:00	23:00	1400	1448	+7.5	+20.5
			1400	1436	-7.5	-20.5			1400	1436	-7.5	-20.5
29-06-2010	7:00	23:00	1448	1480	+7.5	+20	19:00	23:00	1448	1480	+7.5	+20
			1444	1468	+7.5	-7.5			1448	1468	+7.5	-7.5
30-06-2010	7:00	7:00	1436	1456	-7.5	-20	23:00	7:00	1436	1456	-7.5	-20
			1456	1500	-7.5	-20			1496	1500	+7.5	-7.5
01-07-2010	7:00	7:00	1468	1500	+7.5	-7.5	19:00	7:00	1076	1100	0	-16
			1076	1100	0	-16			1076	1100	0	-16
02-07-2010	7:00	7:00	1064	1100	0	+16	19:00	7:00	1064	1100	0	+16
			1020	1064	0	+16			1020	1064	0	+16
03-07-2010	7:00	7:00	1032	1048	0	-16	19:00	7:00	1032	1036	0	-16
			1000	1032	0	16			1000	1008	0	16
04-07-2010	7:00	7:00	992	1020	0	+16	19:00	7:00	992	1020	0	+16
			968	992	0	+16			-	-	-	-
05-07-2010	7:00	7:00	944	968	0	+16	19:00	7:00	956	1000	0	-16
			798	850	0	+17			798	850	0	+17
06-07-2010	7:00	7:00	838	850	0	-17	20:50	7:00	838	850	0	-17
			782	838	0	-17			782	826	0	-17
07-07-2010	7:00	7:00	758	782	0	-16	19:00	7:00	758	774	0	-16
			774	798	0	+16			774	798	0	+16
08-07-2010	7:00	7:00	728	774	0	+17	19:00	7:00	696	750	0	-17
			696	750	0	-17			696	750	0	-17
09-07-2010	7:00	7:00	666	710	0	+17	19:00	7:00	666	670	0	+17
			682	710	0	-17			682	710	0	-17
10-07-2010	7:00	7:00	654	682	0	-17	19:00	7:00	654	662	0	-17
			634	666	0	+17			634	666	0	+17
11-07-2010	7:00	7:00	622	654	0	-17	20:55	1:10	622	642	0	-17
			602	622	0	-17			602	626	0	+17
12-07-2010	7:00	7:00	570	602	0	+17	19:00	7:00	570	598	0	+17
			574	602	0	-17			574	582	0	-17
13-07-2010	7:00	7:00	558	570	0	+17	21:00	7:00	558	570	0	+17
			562	574	0	-17			562	574	0	-17
14-07-2010	7:00	7:00	546	562	0	-17	21:15	7:00	530	558	0	+17
			530	558	0	+17			530	558	0	+17
15-07-2010	7:00	7:00	526	546	0	-17	19:00	7:00	526	538	0	-17
			526	536	0	+17			526	530	0	+17
17-07-2010	7:00	19:00	-	-	0	-17	-	-	-	-	-	-
18-07-2010	7:00	23:00	260	300	0	-17	19:00	23:00	260	276	0	-17
19-07-2010	7:00	23:00	248	300	0	+17	19:00	21:15	248	256	0	+17
20-07-2010	7:00	23:00	232	260	0	-15	-	-	-	-	-	-
21-07-2010	7:00	19:00	224	248	0	+15	19:00	23:00	224	236	0	+15
22-07-2010	7:00	19:00	216	232	0	-15	-	-	-	-	-	-
23-07-2010	07:00	23:00	-	-	0	-15	19:00	23:00	-	-	0	+15
			200	216	0	-15			204	224	0	+15
24-07-2010	07:00	23:00	208	224	0	+15	19:00	23:00	204	224	0	+15
			176	200	0	-15			176	184	0	-15
25-07-2010	07:00	23:00	176	184	0	-15	19:00	20:50	176	184	0	-15
			172	176	0	-15			172	176	0	-15
26-07-2010	07:00	23:00	200	204	0	+15	19:00	22:40	200	204	0	+15
			172	192	0	+15			172	192	0	+15
27-07-2010	07:00	23:00	172	200	0	+15	19:20	23:00	152	168	0	+15
			168	172	0	-15			152	168	0	+15
28-07-2010	07:00	23:00	148	172	0	-15	19:00	21:00	128	136	0	+15
			152	168	0	+15			124	128	0	+15
29-07-2010	07:00	23:00	128	152	0	+15	19:00	21:45	124	128	0	+15
			124	148	0	-15			124	136	0	-15
30-07-2010	07:00	23:00	116	124	0	-15	19:00	20:20	116	124	0	-15
			88	116	0	-15			88	100	0	-15
31-07-2010	7:00	23:00	88	100	0	-15	19:00	22:45	1480	1528	+5	+20.5
			1500	1508	+7.5	-7.5			1480	1528	+5	+20.5
20-07-2010	7:00	23:00	1500	1548	-5	-20.5	19:00	22:45	1500	1508	+7.5	-7.5
			1508	1516	+7.5	-7.5			1516	1540	+7.5	-7.5
20-07-2010	7:00	23:00	1516	1540	+7.5	-7.5	19:00	20:45	1516	1540	+7.5	-7.5
			1540	1548	+7.5	-7.5			1540	1548	7.5	-7.5

Wo Hing – Penta-Ocean Joint Venture

Contract No. 9/WSD/08
Laying of Western Cross Harbour Main and Associated Land Mains
From West Kowloon to Sai Ying Pun

Dredging Location of GD "Shun Tai 20" during Overtime Hours 19:00 – 07:00 (next day)

Date	Working Hour fm 07:00 to 23:00 or 07:00 to 07:00 (next day)						Working Hour for overtime fm 19:00 to 23:00 or 19:00 to 07:00 (next day)							
	W Hours fm	W Hours to	Chainage fm	Chainage to	Offset fm	Offset to	OT Hours fm	OT Hours to	Chainage fm	Chainage to	Offset fm	Offset to		
01-08-2010	7:00	23:00	1528	1572	+5	+20.5								
			1548	1568	-5	-20.5								
			1548	1556	+7.5	-7.5								
			1556	1576	7.5	-7.5								
			1556	1576	7.5	-7.5								
02-08-2010	7:00	19:00	1572	1608	+5	+20.5	19:00	23:00	1556	1576	7.5	-7.5		
			1576	1596	+7.5	-7.5								
			1568	1620	-5	-20.5								
03-08-2010	7:00	23:00	1596	1604	-7.5	+7.5	21:10	23:00	1596	1604	-7.5	+7.5		
04-08-2010	7:00	23:00	1604	1612	-7.5	+7.5	19:00	21:40	1604	1612	-7.5	+7.5		
05-08-2010	7:00	19:00	1608	1636	+7.5	+20.5								
06-08-2010	7:00	23:00	112	124	0	+15								
07-08-2010	7:00	23:00	84	112	0	+15	19:00	23:00	84	112	0	+15		
			76	84	0	+15			76	84	0	+15		
			68	76	0	+15			68	76	0	+15		
			60	68	0	+15								
			72	88	0	-15								
08-08-2010	7:00	23:00	56	72	0	-15	19:00	23:00	56	72	0	-15		
			52	56	0	-15			52	56	0	-15		
			36	52	0	-15								
			20	36	0	-15			19:00	23:00	20	36	0	-15
			56	60	0	+15			56	60	0	+15		
09-08-2010	7:00	23:00	54	56	0	+15								
			32	49	0	+15								
			0	32	0	+15	19:00	22:55	0	32	0	+15		
10-08-2010	7:00	19:00	0	20	0	-15	19:00	7:00	0	20	0	-15		
			1118	1130	-5	-20			1118	1130	-5	-20		
			1110	1118	-5	-20								
			1122	1130	+7.5	-7.5			19:00	7:00	1110	1122	+7.5	-7.5
			1122	1130	+5	+20			1122	1130	+5	+20		
11-08-2010	7:00	7:00	1114	1122	+5	+20								
			1086	1114	+5	+20	19:00	7:00	1086	1114	+5	+20		
			1102	1110	+7.5	-7.5								
12-08-2010	7:00	7:00	1098	1110	-5	-20	19:00	21:30	1098	1110	-5	-20		
			1078	1086	-5	-20			1078	1086	-5	-20		
			1078	1102	+7.5	-7.5			23:30	7:00	1078	1102	+7.5	-7.5
			1070	1078	+7.5	-7.5								
			1070	1098	-5	-20			19:00	20:10	1070	1098	-5	-20
13-08-2010	7:00	7:00	1066	1078	+5	+20	20:20	2:30	1066	1078	+5	+20		
			1066	1070	+7.5	-7.5			1066	1070	+7.5	-7.5		
			1058	1066	+7.5	-7.5			3:25	7:00	1058	1066	+7.5	-7.5
			1026	1070	-5	-17.5								
			1046	1058	+7.5	-7.5			21:55	2:30	1046	1058	+7.5	-7.5
14-08-2010	7:00	7:00	1030	1046	-7.5	+7.5	2:30	7:00	1030	1046	-7.5	+7.5		
15-08-2010	7:00	7:00	1026	1036	-7.5	+7.5								
16-08-2010	7:00	7:00	1038	1066	+5	+17.5	19:00	23:05	1038	1066	+5	+17.5		
			1018	1038	+5	+17.5			2:35	7:00	1018	1038	+5	+17.5
			1018	1026	-7.5	+7.5								
			986	1018	+5	+17.5			19:00	20:50	986	1018	+5	+17.5
			1006	1026	-5	-17.5			20:55	2:50	1006	1026	-5	-17.5
17-08-2010	7:00	7:00	1010	1018	-7.5	+7.5	3:25	6:00	1010	1018	-7.5	+7.5		
			1002	1010	-7.5	+7.5			1002	1010	-7.5	+7.5		
			994	1002	+7.5	-7.5								
			978	994	+7.5	-7.5			19:00	7:00	978	994	+7.5	-7.5
			966	1006	-5	-17.5			966	1006	-5	-17.5		
18-08-2010	7:00	7:00	958	986	+5	+17.5								
			970	978	+7.5	-7.5								
			950	970	+7.5	-7.5	19:00	7:00	950	970	+7.5	-7.5		
			942	950	+7.5	-7.5	942	950	+7.5	-7.5				
			938	942	+7.5	-7.5								
19-08-2010	7:00	7:00	942	966	-5	-17.5	19:00	1:35	942	966	-5	-17.5		
			938	958	+5	+17.5			938	958	+5	+17.5		
			-	-										
20-08-2010	7:00	7:00	628	640	+7.5	-7.5								
21-08-2010	7:00	7:00	612	628	-7.5	-7.5	21:10	2:15	612	628	+7.5	-7.5		
			596	620	+7.5	-7.5								
			580	596	+7.5	-7.5			22:10	3:15	572	596	+7.5	-7.5
22-08-2010	7:00	7:00	572	580	+7.5	-7.5	3:35	7:00	572	580	+7.5	-7.5		
			552	572	+7.5	-7.5								
			536	552	+7.5	-7.5			19:55	1:50	536	552	+7.5	-7.5
			528	536	+7.5	-7.5			2:30	7:00	528	536	+7.5	-7.5
			520	528	+7.5	-7.5								
23-08-2010	7:00	7:00	564	572	-20	-5	19:00	0:50	588	620	+7.5	-7.5		
			588	620	+7.5	-7.5								
			564	588	+7.5	-7.5								
			540	564	+7.5	-7.5			0:00	7:00	540	564	+7.5	-7.5
			552	564	-5	-20			552	564	-5	-20		
24-08-2010	7:00	7:00	520	552	-5	-20								
			564	580	+5	+20								
			520	564	+5	+20	19:00	22:20	520	564	+5	+20		
			512	520	-7	+7	22:25	7:00	512	520	-7	+7		
			508	512	-7	+7	508	512	-7	+7				

Wo Hing – Penta-Ocean Joint Venture

Contract No. 9/AWS/D/08
 Laying of Western Cross Harbour Main and Associated Land Mains
 From West Kowloon to Sai Ying Pun

Dredging Location of GD "Shun Tat 20" during Overtime Hours 19:00 – 07:00 (next day)

Date	Working Hour fm 07:00 to 23:00 or 07:00 to 07:00 (next day)						Working Hour for overtime fm 19:00 to 23:00 or 19:00 to 07:00 (next day)					
	W Hours fm	W Hours to	Chainage fm	Chainage to	Offset fm	Offset to	OT Hours fm	OT Hours to	Chainage fm	Chainage to	Offset fm	Offset to
30-08-2010	7:00	7:00	500	508	-7	-5						
			850	870	0	+17.5	19:00	0:50	850	870	0	+17.5
			850	870	0	-17.5			850	870	0	-17.5
31-08-2010	7:00	7:00	914	922	+7.5	-7.5	1:00	6:00	914	922	+7.5	-7.5
			914	938	+5	+17.5	19:00	7:00	914	938	+5	+17.5
			910	914	+5	+17.5			910	914	+5	+17.5
			918	938	+7.5	-7.5			918	938	+7.5	-7.5
			926	938	-5	-17.5			926	938	-5	-17.5
01-09-2010	7:00	7:00	910	926	-5	-17.5	19:00	21:15	910	926	-5	-17.5
			902	918	+7.5	-7.5	22:35	3:45	902	918	+7.5	-7.5
			902	914	+5	-17.5	5:05	7:00	902	914	+5	-17.5
02-09-2010	7:00	7:00	878	902	+5	+17.5						
			902	910	-5	-17.5						
			882	902	-5	-17.5	19:35	1:15	882	902	-5	-17.5
03-09-2010	7:00	7:00	894	902	+7.5	-7.5	4:25	7:00	894	902	+7.5	-7.5
			870	894	+7.5	-7.5						
			850	878	+5	+17.5	19:35	7:00	850	878	+5	+17.5
04-09-2010	7:00	7:00	858	882	-5	-17.5			858	882	-5	-17.5
			846	858	-5	-17.5						
			854	870	+7.5	-7.5	19:00	7:00	854	870	+7.5	-7.5
05-09-2010	7:00	6:00	822	846	-5	-17.5			822	846	-5	-17.5
			834	850	+5	+17.5			834	850	+5	+17.5
			822	834	+5	+17.5						
06-09-2010	7:00	7:00	834	854	+7.5	-7.5	19:00	6:00	834	854	+7.5	-7.5
			814	834	+7.5	-7.5			814	834	+7.5	-7.5
			798	822	-5	-17.5			798	822	-5	-17.5
07-09-2010	7:00	7:00	810	822	+5	+17.5						
			810	814	+5	+17.5	19:00	7:00	810	814	+5	+17.5
			794	814	+7.5	-7.5			794	814	+7.5	-7.5
			778	794	+7.5	-7.5			778	794	+7.5	-7.5
			778	798	-5	-17.5			778	798	-5	-17.5
08-09-2010	7:00	23:00	766	778	+7.5	-7.5						
			778	798	+5	+17.5	19:00	20:55	778	798	+5	+17.5
08-09-2010	7:00	19:00	-	-								
09-09-2010	7:00	19:00	-	-								
10-09-2010	7:00	19:00	-	-								
11-09-2010	7:00	19:00	-	-								
12-09-2010	7:00	19:00	-	-								
13-09-2010	7:00	19:00	-	-								
14-09-2010	7:00	19:00	-	-								
15-09-2010	7:00	19:00	-	-								
16-09-2010	7:00	19:00	-	-								
17-09-2010	7:00	19:00	-	-								
18-09-2010	7:00	19:00	-	-								
19-09-2010	7:00	19:00	-	-								
20-09-2010	7:00	19:00	-	-								
21-09-2010	7:00	7:00	444	452	+7.5	-7.5	20:30	4:30	444	452	+7.5	-7.5
22-09-2010	7:00	19:00	-	-								
23-09-2010	7:00	19:00	-	-								
24-09-2010	7:00	19:00	-	-								
25-09-2010	7:00	19:00	-	-								
26-09-2010	7:00	19:00	-	-								
27-09-2010	7:00	23:00	440	444	+7.5	-7.5	20:35	21:00	440	444	+7.5	-7.5
28-09-2010	7:00	19:00	-	-								
29-09-2010	7:00	23:00	432	444	+7.5	-7.5	19:00	23:00	432	444	+7.5	-7.5
30-09-2010	7:00	19:00	-	-								
01-10-2010	7:00	23:00	429	432	+7.5	-7.5	19:00	23:00	429	432	+7.5	-7.5
02-10-2010	7:00	7:00	440	452	+7.5	-7.5						
			754	778	+17.5	+5	19:00	23:30	754	778	+17.5	+5
			770	778	-17.5	-5	4:35	7:00	770	778	-17.5	-5
03-10-2010	7:00	7:00	746	770	-5	-17.5						
			734	754	+7.5	-7.5	19:00	22:55	734	754	+7.5	-7.5
			742	754	+5	+17.5	4:25	7:00	742	754	+5	+17.5
04-10-2010	7:00	7:00	726	742	+5	+17.5						
			722	734	+7.5	-7.5	0:15	7:00	722	734	+7.5	-7.5
05-10-2010	7:00	7:00	718	722	+7.5	-7.5						
			710	746	-5	-17.5	19:00	7:00	710	746	-5	-17.5
			702	726	+5	+17.5			702	726	+5	+17.5
06-10-2010	7:00	7:00	705	718	+7.5	-7.5						
			698	710	-5	-17.5	19:00	7:00	698	710	-5	-17.5
			690	706	+7.5	-7.5			690	706	+7.5	-7.5
			682	690	+7.5	-7.5			682	690	+7.5	-7.5
			666	702	+17.5	+5			666	702	+17.5	+5
07-10-2010	7:00	7:00	682	698	-5	-17.5			682	698	-5	-17.5
			662	682	-5	-17.5						
			654	682	+7.5	-7.5	19:00	7:00	654	682	+7.5	-7.5
			638	662	-5	-17.5			638	662	-5	-17.5
			646	654	+7.5	-7.5			646	654	+7.5	-7.5
08-10-2010	7:00	23:00	650	666	+5	+17.5			650	666	+5	+17.5
			606	650	+5	+17.5	19:00	21:55	606	650	+5	+17.5
			632	650	+7.5	-7.5	19:00	19:15	632	650	+7.5	-7.5
			572	638	-5	-17.5	19:00	6:00	572	638	-5	-17.5
			602	606	+5	+17.5			602	606	+5	+17.5
11-10-2010	7:00	7:00	580	602	+5	+17.5						
			640	646	+7.5	-7.5						
			512	520	+5	+20						
			496	512	+5	+20	19:00	7:00	496	512	+5	+20
			508	520	-5	-20			508	520	-5	-20

Wo Hing – Penta-Ocean Joint Venture

Contract No. 9/MWD/08
Laying of Western Cross Harbour Main and Associated Land Mains
From West Kowloon to Sai Ying Pun

Dredging Location of GD "Shun Tat 20" during Overtime Hours 19:00 – 07:00 (next day)

Date	Working Hour fm 07:00 to 23:00 or 07:00 to 07:00 (next day)						Working Hour for overtime fm 19:00 to 23:00 or 19:00 to 07:00 (next day)						
	W Hours fm	W Hours to	Chainage fm	Chainage to	Offset fm	Offset to	OT Hours fm	OT Hours to	Chainage fm	Chainage to	Offset fm	Offset to	
12-10-2010	7:00	7:00	500	508	-5	-20							
			492	500	-5	-20	19:00	20:50	492	500	-5	-20	
			492	500	+7.5	-7.5			492	500	+7.5	-7.5	
			480	492	+7.5	-7.5	21:15	4:00	480	492	+7.5	-7.5	
			472	480	-5	-20	4:00	7:00	472	480	-5	-20	
13-10-2010	7:00	7:00	472	498	+5	+20							
			476	480	+7.5	-7.5	19:00	7:00	476	480	+7.5	-7.5	
			460	472	-5	-20			460	472	-5	-20	
			456	460	-5	-20			456	460	-5	-20	
			468	472	+5	+20							
14-10-2010	7:00	7:00	472	476	+7.5	-7.5							
			448	456	-5	-20	19:00	20:50	448	456	-5	-20	
			462	468	+5	+20			462	468	+5	+20	
			452	462	+5	+20	20:55	1:50	452	462	+5	+20	
			448	452	+5	+20	6:30	7:00	448	452	+5	+20	
15-10-2010	7:00	7:00	436	472	+7.5	-7.5							
			424	436	+7.5	-7.5	19:00	23:10	424	436	+7.5	-7.5	
			436	448	-5	-20	23:15	4:15	436	448	-5	-20	
			444	452	+5	+20	4:20	7:00	444	452	+5	+20	
			420	436	-5	-20							
16-10-2010	7:00	7:00	420	432	+20	+5							
			412	420	-5	-20	19:00	6:30	412	420	-5	-20	
			416	424	+7.5	-7.5			416	424	+7.5	-7.5	
			436	444	+20	+5			436	444	+20	+5	
			432	436	+20	+5			432	436	+20	+5	
17-10-2010	7:00	7:00	400	412	+7.5	-7.5							
			404	420	+5	+20							
			392	404	+5	+20	19:00	0:00	392	404	+5	+20	
			404	436	-5	-20			404	436	-5	-20	
			440	460	+7.5	-7.5	0:45	5:15	440	460	+7.5	-7.5	
18-10-2010	7:00	7:00	436	440	+7.5	-7.5	5:25	6:30	436	440	+7.5	-7.5	
			396	400	+7.5	-7.5	7:00	7:00	396	400	+7.5	-7.5	
			376	396	+7.5	-7.5							
			368	392	+20	+5							
			376	404	-5	-20	19:00	23:30	376	404	-5	-20	
19-10-2010	7:00	7:00	436	460	+5	+20	0:10	5:00	436	460	+5	+20	
			372	376	-5	-20	5:30	7:00	372	376	-5	-20	
			360	376	+7.5	-7.5							
			348	360	+7.5	-7.5							
			356	372	-5	-20	19:00	20:05	356	372	-5	-20	
20-10-2010	7:00	23:00	360	368	+5	+20	21:20	2:45	360	368	+5	+20	
			456	480	-5	-20			456	480	-5	-20	
			436	456	-5	-20	2:50	7:00	436	456	-5	-20	
			356	360	+5	+20			356	360	+5	+20	
			340	348	+7.5	-7.5							
21-10-2010	7:00	19:00	336	340	+7.5	-7.5	19:00	21:10	336	340	+7.5	-7.5	
			348	356	+5	+20			348	356	+5	+20	
			340	348	+5	+20	21:20	23:00	340	348	+5	+20	
			-	-	-	-							
			-	-	-	-							
22-10-2010	7:00	19:00	-	-	-	-							
			336	356	-5	-20	19:00	22:40	336	356	-5	-20	
			430	460	+7.5	-7.5	23:30	3:20	430	460	+7.5	-7.5	
			320	334	+5	+20							
			328	336	+7.5	-7.5							
24-10-2010	7:00	7:00	296	320	+20	+5							
			316	336	-5	-17.5	19:00	23:00	316	336	-5	-17.5	
			480	500	-5	-20	0:00	2:00	480	500	-5	-20	
			460	500	+5	+20	2:05	7:00	460	500	+5	+20	
			320	328	+7.5	-7.5			320	328	+7.5	-7.5	
25-10-2010	7:00	23:00	284	316	-5	-17.5							
			284	304	+7.5	-7.5	19:00	23:00	284	304	+7.5	-7.5	
			280	284	+7.5	-7.5			280	284	+7.5	-7.5	
			260	296	+5	+17.5							
			276	280	+7.5	-7.5							
26-10-2010	7:00	23:00	264	276	+7.5	-7.5	19:00	23:00	264	276	+7.5	-7.5	
			260	284	-5	-17.5			260	284	-5	-17.5	
			252	264	+7.5	-7.5			252	264	+7.5	-7.5	
			248	252	+7.5	-7.5			248	252	+7.5	-7.5	
			188	260	+5	+17.5							
27-10-2010	7:00	19:00	240	248	+7.5	-7.5							
			256	260	-5	-17.5							
			240	256	-5	-17.5	19:00	22:00	240	256	-5	-17.5	
			216	240	0	-12.5			216	240	0	-12.5	
			236	240	+12.5	0	22:45	23:00	236	240	+12.5	0	
29-10-2010	7:00	23:00	204	236	0	+12.5							
			180	216	0	-12.5	19:00	22:55	180	216	0	-12.5	
			176	204	+12.5	0	19:00	21:50	176	204	+12.5	0	
			172	180	0	-12.5			172	180	0	-12.5	
			168	172	0	-12.5	22:05	23:00	168	172	0	-12.5	
31-10-2010	7:00	23:00	140	168	0	-12.5	19:00	23:00	140	168	0	-12.5	
			136	176	0	+12.5			136	176	0	+12.5	
			128	136	0	+12.5			128	136	0	+12.5	
			104	128	+12.5	0							
			116	140	0	-12.5	19:00	23:00	116	140	0	-12.5	
02-11-2010	7:00	23:00	112	116	0	-12.5			112	116	0	-12.5	
			80	112	0	-12.5							
			84	104	0	+12.5	19:00	21:55	84	104	0	+12.5	




Wo Hing – Penta-Ocean Joint Venture

Contract No. 9/AWS/08
 Laying of Western Cross Harbour Main and Associated Land Mains
 From West Kowloon to Sai Ying Pun

Dredging Location of GD "Shun Tat 20" during Overtime Hours 19:00 - 07:00 (next day)

Date	Working Hour fm 07:00 to 23:00 or 07:00 to 07:00 (next day)						Working Hour for overtime fm 19:00 to 23:00 or 19:00 to 07:00 (next day)					
	W Hours fm	W Hours to	Chainage fm	Chainage to	Offset fm	Offset to	OT Hours fm	OT Hours to	Chainage fm	Chainage to	Offset fm	Offset to
03-11-2010	7:00	20:30	60	84	+12.5	0						
			60	80	+17.5	+15						
			48	80	0	-12.5	19:00	20:30	48	80	0	-12.5
04-11-2010	7:00	23:00	24	48	0	-12.5	19:00	23:00	24	48	0	-12.5
			48	60	0	+12.5			48	60	0	+12.5
05-11-2010	7:00	23:00	24	48	0	+12.5	19:00	22:45	24	48	0	+12.5
			4	24	0	+12.5			4	24	0	+12.5
06-11-2010	7:00	23:00	6	24	0	-12.5	19:00	23:00	6	24	0	-12.5
			0	4	0	+12.5			0	4	0	+12.5
07-11-2010	7:00	20:00	0	-12	0	+16						
			-12	-18.5	0	+16	19:00	20:00	-12	-18.5	0	+16
08-11-2010	7:00	23:00	240	256	+5	-5	19:00	23:00	240	256	+5	-5
09-11-2010	7:00	23:00	256	280	+5	-5						
			280	308	+5	-5	19:00	23:00	280	308	+5	-5
10-11-2010	7:00	19:00	-	-	-	-	-	-	-	-	-	
11-11-2010	7:00	19:00	-	-	-	-	-	-	-	-	-	
12-11-2010	7:00	19:00	-	-	-	-	-	-	-	-	-	
13-11-2010	7:00	19:00	-	-	-	-	-	-	-	-	-	
14-11-2010	7:00	19:00	-	-	-	-	-	-	-	-	-	
15-11-2010	7:00	19:00	-	-	-	-	-	-	-	-	-	
16-11-2010	7:00	19:00	-	-	-	-	-	-	-	-	-	
17-11-2010	7:00	7:00	504	536	+5	-5	18:30	22:20	504	536	+5	-5
			500	504	+5	-5	0:25	5:30	500	504	+5	-5
			470	500	+15	+5			470	500	+15	+5
18-11-2010	7:00	7:00	476	500	+5	-5			476	500	+5	-5
			444	476	+5	-5						
			396	444	+5	-5	19:00	23:40	396	444	+5	-5
19-11-2010	7:00	7:00	430	470	+15	+5	0:10	4:30	430	470	+15	+5
			392	396	+5	-5	5:55	8:00	392	396	+5	-5
			364	392	+5	-5						
20-11-2010	7:00	7:00	320	364	+5	-5	19:00	22:10	320	364	+5	-5
			460	520	-5	-15	23:20	3:15	460	520	-5	-15
			304	320	+5	-5	5:00	7:00	304	320	+5	-5
21-11-2010	7:00	7:00	620	636	+5	-5						
			636	668	+5	-5	19:00	0:40	636	668	+5	-5
			668	688	+5	-5	2:55	7:00	668	688	+5	-5
22-11-2010	7:00	7:00	688	700	+5	-5						
			700	732	+5	-5	19:00	21:00	700	732	+5	-5
			732	760	+5	-5	21:50	3:00	732	760	+5	-5
23-11-2010	7:00	7:00	760	780	+5	-5	3:35	7:00	760	780	+5	-5
			780	788	+5	-5						
			788	824	+5	-5	19:00	21:40	788	824	+5	-5
24-11-2010	7:00	7:00	824	832	+5	-5	2:35	7:00	824	832	+5	-5
			808	832	+7.5	+15			808	832	+7.5	+15
			832	848	+12.5	-5						
25-11-2010	7:00	7:00	848	888	+12.5	-7.5	19:00	20:50	848	888	+12.5	-7.5
			888	920	+12.5	-7.5	21:30	2:00	888	920	+12.5	-7.5
			920	952	+7.5	-7.5	2:30	6:30	920	952	+7.5	-7.5
26-11-2010	7:00	7:00	952	988	-5	+15						
			988	1012	-7.5	+7.5	19:00	22:25	988	1012	-7.5	+7.5
			1012	1044	-7.5	+5	22:50	2:50	1012	1044	-7.5	+5
27-11-2010	7:00	7:00	1044	1084	+7.5	-7.5						
			1084	1128	+7.5	-5	21:20	2:55	1084	1128	+7.5	-5
			1128	1152	+7.5	-5	3:15	7:00	1128	1152	+7.5	-5
28-11-2010	7:00	7:00	1152	1156	+5	-12.5						
			1156	1180	+5	-12.5	19:00	20:05	1156	1180	+5	-12.5
			1180	1204	+10	-10	20:40	0:45	1180	1204	+10	-10
29-11-2010	7:00	7:00	1204	1224	+10	-10	1:30	7:00	1204	1224	+10	-10
			1224	1244	+10	0						
			1244	1328	-12.5	+7.5	19:00	23:35	1244	1328	-12.5	+7.5
30-11-2010	7:00	7:00	1200	1244	-12.5	-5	2:00	6:00	1200	1244	-12.5	-5
			1328	1340	-12.5	-5	6:45	8:00	1328	1340	-12.5	-5
			1324	1360	+5	-5						
31-11-2010	7:00	7:00	1360	1388	0	-12.5	19:00	21:00	1360	1388	0	-12.5
			1388	1400	0	-12.5	21:50	2:00	1388	1400	0	-12.5
			1150	1200	-10	0			1150	1200	-10	0
30-11-2010	7:00	7:00	1150	1200	+10	0	2:40	7:00	1150	1200	+10	0
			1412	1420	0	+7.5						
			1420	1432	+7.5	0	18:00	7:00	1420	1432	+7.5	0
30-11-2010	7:00	7:00	1432	1452	+5	-5						
			1452	1492	+5	-5						
			1492	1500	+5	-5						
30-11-2010	7:00	7:00	1492	1516	+5	-5						
			1516	1548	+5	-10	19:00	7:00	1516	1548	+5	-10
			1548	1564	+5	-10			1548	1564	+5	-10
			1564	1568	+5	-10			1564	1568	+5	-10

NOTE:
 LOGISTIC OF DREDGING
 STAGE 1 - TYPE 2 MARINE SEDIMENT
 ① -> ② -> ③ -> ④ -> ⑤ -> ⑥ -> ⑦ -> ⑧
 STAGE 2 - TYPE 1 MARINE SEDIMENT
 ⑨ -> ⑩ -> ⑪
 STAGE 3 - TYPE 1 MARINE SEDIMENT
 ⑫ -> ⑬ -> ⑭ -> ⑮ -> ⑯ -> ⑰ -> ⑱ -> ⑲ ->
 STAGE 4 - TYPE 10 MARINE SEDIMENT
 ⑳ -> ㉑
 STAGE 5 - TYPE 1 MARINE SEDIMENT
 ㉒ -> ㉓ -> ㉔ -> ㉕
 IF SIMILAR DISPOSAL SITE IS DEDICATED FOR TYPE 10 AND TYPE 1 MARINE SEDIMENT DREDGING LOGISTIC AT ㉖ WILL BE DELETED AND INCLUDED IN ㉗ AND ㉘



WO HING-PENG OCEAN JOINT VENTURE
 和興洋行聯合有限公司

CONTRACT NO. 9/WSD/08
 合約編號 9/WSD/08

Laying of Western Cross Harbour Main and Associated Land Mains from West Kowloon to Sai Ying Pun
 擬設和興洋行聯合有限公司之西區過海海底水管及與其相關的地下輸管

DRAWING TITLE: DREDGING LOGISTIC

CONTRACTOR: WO HING-PENG OCEAN JOINT VENTURE


CONTRACT NO. 9/WSD/08

Laying of Western Cross Harbour Main and Associated Land Mains from West Kowloon to Sai Ying Pun


DRAWING TITLE: DREDGING LOGISTIC

DRAW BY	TONY TANG	SCALE	N/S
CHECKED BY	STANLEY LAUNG	DWG No.	SK-D-002
DATES	08 Apr 2010	REVISION	D

NOTES :





NO.	DATE	BY	REVISION
1	17 JUN 2018		
2	17 JUN 2018		
3	17 JUN 2018		
4	17 JUN 2018		
5	17 JUN 2018		
6	17 JUN 2018		
7	17 JUN 2018		
8	17 JUN 2018		
9	17 JUN 2018		
10	17 JUN 2018		
11	17 JUN 2018		
12	17 JUN 2018		
13	17 JUN 2018		
14	17 JUN 2018		
15	17 JUN 2018		
16	17 JUN 2018		
17	17 JUN 2018		
18	17 JUN 2018		
19	17 JUN 2018		
20	17 JUN 2018		
21	17 JUN 2018		
22	17 JUN 2018		
23	17 JUN 2018		
24	17 JUN 2018		
25	17 JUN 2018		
26	17 JUN 2018		
27	17 JUN 2018		
28	17 JUN 2018		
29	17 JUN 2018		
30	17 JUN 2018		
31	17 JUN 2018		
32	17 JUN 2018		
33	17 JUN 2018		
34	17 JUN 2018		
35	17 JUN 2018		
36	17 JUN 2018		
37	17 JUN 2018		
38	17 JUN 2018		
39	17 JUN 2018		
40	17 JUN 2018		
41	17 JUN 2018		
42	17 JUN 2018		
43	17 JUN 2018		
44	17 JUN 2018		
45	17 JUN 2018		
46	17 JUN 2018		
47	17 JUN 2018		
48	17 JUN 2018		
49	17 JUN 2018		
50	17 JUN 2018		
51	17 JUN 2018		
52	17 JUN 2018		
53	17 JUN 2018		
54	17 JUN 2018		
55	17 JUN 2018		
56	17 JUN 2018		
57	17 JUN 2018		
58	17 JUN 2018		
59	17 JUN 2018		
60	17 JUN 2018		
61	17 JUN 2018		
62	17 JUN 2018		
63	17 JUN 2018		
64	17 JUN 2018		
65	17 JUN 2018		
66	17 JUN 2018		
67	17 JUN 2018		
68	17 JUN 2018		
69	17 JUN 2018		
70	17 JUN 2018		
71	17 JUN 2018		
72	17 JUN 2018		
73	17 JUN 2018		
74	17 JUN 2018		
75	17 JUN 2018		
76	17 JUN 2018		
77	17 JUN 2018		
78	17 JUN 2018		
79	17 JUN 2018		
80	17 JUN 2018		
81	17 JUN 2018		
82	17 JUN 2018		
83	17 JUN 2018		
84	17 JUN 2018		
85	17 JUN 2018		
86	17 JUN 2018		
87	17 JUN 2018		
88	17 JUN 2018		
89	17 JUN 2018		
90	17 JUN 2018		
91	17 JUN 2018		
92	17 JUN 2018		
93	17 JUN 2018		
94	17 JUN 2018		
95	17 JUN 2018		
96	17 JUN 2018		
97	17 JUN 2018		
98	17 JUN 2018		
99	17 JUN 2018		
100	17 JUN 2018		


**THE GOVERNMENT OF THE HONG KONG
SPECIAL ADMINISTRATIVE REGION
WATER SUPPLIES DEPARTMENT**

CONTRACT TITLE :
 LINES OF WESTERN CROSS SHEDDING LANE
 AND ASSOCIATED DRAINAGE
 PROJECT IN SH 200 (S1)
 (Contract No. S/P200/S1)

TITLE :
 ORIGINAL PLAN OF THE EXTENT
 AND LEVEL OF TYPE 2
 SEGMENT TO BE DREDGED

Consultant

**Mott
Macdonald**
 14th Floor, One Finance Street, Hong Kong, China

Main Contractor

HKB
 40 Wing Lok Street, Kowloon, Hong Kong

Scale : 1:1000
 Date : 17 JUN 2018
 Draw No. : SH-D-011



Appendix K

Details of Interim Notifications of Exceedance (NOEs) in this reporting month

Contract No. 9/WSD/08
Laying of Western Cross Harbour Main & Associated Land Mains from West Kowloon to Sai Ying Pun
Notification of Exceedance (NOE)

Date and Time of Noise Monitoring: 20 November 2010 (2300) to 21 November 2010 (0100) at KS6, KY3, RWM and CGa
Construction Works carried out during the monitoring: Dredging of Type 1 marine sediment at Point I (CH636 to CH668) from 20 November 2010 (2025) to 21 November 2010 (0040)
Corresponding CNP: GW-RE0502-10 (21 October 2010 to 20 April 2011)

Monitoring Location	Measured Value, dB(A)	Action Level	Limit Level, dB(A)	Possible Reason(s) for the Exceedance	Action to be taken	Remark
KS6	58.7	When one documented complaint is received	55	Dredging works were carried out by using one grab dredger (with one split hopper barge) at CH636 to CH668, which fulfill the requirement described in corresponding CNP. Refer to the observation during the monitoring, main source of noise impact was due to local traffic along West Kowloon Highway. According to the summary of baseline noise monitoring, the average and range of background noise level from 0000-0100 * is 58.5dB(A) and between 55.1dB(A) and 62.9dB(A). The impact monitoring results were found within the range of baseline noise level. Hence, the exceedance recorded is considered invalid and no related to the construction works.	Nil	Nil
	57.9					
	57.7					
KY3	60.6	When one documented complaint is received	55	Dredging works were carried out by using one grab dredger (with one split hopper barge) at CH636 to CH668, which fulfill the requirement described in corresponding CNP. Refer to the observation during the monitoring, main source of noise impact was due to local traffic along Connaught Road West and Western Harbour Crossing. According to the summary of baseline noise monitoring, the average and range of background noise level from 2300-0100 * is 58.0dB(A) and between 53.5dB(A) and 62.9dB(A). The impact monitoring results were found within the range of baseline noise level. Hence, the exceedance recorded is considered invalid and no related to the construction works.	Nil	Nil
	60.3					
	61.0					
RWM	59.9	When one documented complaint is received	55	Dredging works were carried out by using one grab dredger (with one split hopper barge) at CH636 to CH668, which fulfill the requirement described in corresponding CNP. Refer to the observation during the monitoring, main source of noise impact was due to local traffic along Connaught Road West and Western Harbour Crossing. According to the summary of baseline noise monitoring, the average and range of background noise level from 2300-0100 * is 59.8dB(A) and between 52.8dB(A) and 67.3dB(A). The impact monitoring results were found within the range of baseline noise level. Hence, the exceedance recorded is considered invalid and no related to the construction works.	Nil	Nil
	60.3					
	60.9					
CGa	61.4	When one documented complaint is received	55	Dredging works were carried out by using one grab dredger (with one split hopper barge) at CH636 to CH668, which fulfill the requirement described in corresponding CNP. Refer to the observation during the monitoring, main source of noise impact was due to local traffic along Connaught Road West and Western Harbour Crossing. According to the summary of baseline noise monitoring, the average and range of background noise level from 2300-0100 * is 62.6dB(A) and between 58.7dB(A) and 66.1dB(A). The impact monitoring results were found below 62.6dB(A) and within the range of baseline noise level. Hence, the exceedance recorded is considered invalid and no related to the construction works.	Nil	Nil
	60.9					
	61.7					

Remark (*): Refer to the baseline data, it shows that the range of noise level during 2300-0700 is very large (around from 52dB(A) to 67dB(A)) and noise from 2300-0100 is in high level (around 60dB(A)) at all monitoring stations. As a result, baseline noise data measured between 2300-0100 at CGa, RWM, KY3 and 0000-0100 at KS6 are more suitable for being as background indicator (instead of 2300-0700 of next day).

Attachment

Night-time Noise monitoring data sheets (20 to 21 November 2010)
Summary of Baseline Noise Monitoring at KS6 (0000-0100), KY3, RWM and CGa (2300-0100)
Location plan shown the construction works carried out on 20 to 21 November 2010 (2025-0040)

Prepared by: _____

Linda Law

(Linda Law) (Senior Environmental Officer)


Date: 22 November 2010

Checked by: _____

C. L. Lau

(C. L. Lau) (Environmental Teamer Leader)

Date: 22 November 2010



Dredging works carried out at
 CH636 to CH668 from 20
 November 2010 (2025) to 21
 November 2010 (0040)



Agreement No. CE 42/2005 (WS)
Laying of Western Cross Harbour Main and Associated Land Mains
From West Kowloon to Sai Ying Pun - Investigation

Impact Noise Monitoring at West Kowloon during 1900-2300 / 2300-0700 / 0700-1900 (Holiday) Data Record Sheet

Date of Monitoring		21/11/10					
Monitoring Location		KS6 - Podium at the Cullinan			KS4b - Footpath of West Kowloon Waterfront Promenade		
Sound Level Meter (Model and Serial No.)		Rion NL-31 (S/N: 00593620)			Rion NL-31 (S/N: 00593620)		
Sound Pressure Calibrator (Model and Serial No.)		Rion NC-73 (S/N: 10196943)			Rion NC-73 (S/N: 10196943)		
Weather Condition		Fine			Fine		
Temperature (°C)		20°C			20°C		
Type of Measurement		Free Field / <u>Façade</u>			<u>Free Field</u> / Façade		
Measurement Period (min)		5			5		
Calibration before Measurement, dB(A)	Before	94.0			94.0		
	After	94.0			94.0		
Measurement Time	From	00:10	00:15	00:20	00:30	00:35	00:40
	To	00:15	00:20	00:25	00:35	00:40	00:45
Wind Strength (m/s)		1.4	1.5	1.6	1.2	1.3	1.1
L _{eq} , dB(A)		58.7	57.9	57.7	56.9	57.4	58.0
L ₁₀ , dB(A)		60.1	59.5	58.0	58.8	59.2	59.7
L ₉₀ , dB(A)		56.8	56.1	57.3	54.6	55.2	55.8
Major Construction Noise Source(s) During Measurement		/			/		
Other Noise Source(s) During Measurement		vehicles passing by			→		
Remarks		The result <u>was</u> not exceeded the Limit Level.			The result <u>was</u> not exceeded the Limit Level.		

Time Period	Action	Limit
0700 - 1900 hrs normal weekdays	When one documented complaint is received	75 dB(A)
1900-2300 hrs on normal weekdays		70 dB(A)
0700-1900 hrs on holiday		70 dB(A)
Restricted hours (2300-0700 hrs)		55 dB(A)

	Name	Signature	Date
Recorded by	Mark Yee Wan	Mark	21/11/10
Checked by	Wanda Lam	Wanda Lam	22/11/10



Agreement No. CE 42/2005 (WS)
Laying of Western Cross Harbour Main and Associated Land Mains
From West Kowloon to Sai Ying Pun - Investigation

Impact Noise Monitoring at Sai Ying Pun during 1900-2300 / 2300-0700 / 0700-1900 (Holiday) Data Record Sheet

Date of Monitoring		20/11/10								
Monitoring Location For 1900-2300		CGa - Pavement at Connaught Garden			RWM - Pavement at Richwealth Mansion			KY3 - Pavement at Kwan Yik Building Phase 3		
Monitoring Location For 2300-0700 and 0700-1900 (Holiday)		CGa - Pavement at Connaught Garden			RWM - Roof at Richwealth Mansion			KY3 - Roof at Kwan Yik Building Phase 3		
Sound Level Meter (Model and Serial No.)		RION NL-31 (S/N: 00593620)			(S/N:)			(S/N:)		
Sound Pressure Calibrator (Model and Serial No.)		RION NC-73 (S/N: 10196943)			(S/N:)			(S/N:)		
Weather Condition		Fine			Fine			Fine		
Temperature (°C)		20°C			20°C			20°C		
Type of Measurement		Free Field / Façade			Free Field / Façade			Free Field / Façade		
Measurement Period (min)		5			5			5		
Calibration before Measurement, dB(A)	Before	94.0			94.0			94.0		
	After	94.0			94.0			94.0		
Measurement Time	From	23:00	23:05	23:10	23:20	23:25	23:30	23:40	23:45	23:50
	To	23:05	23:10	23:15	23:25	23:30	23:35	23:45	23:50	23:55
Wind Strength (m/s)		1.2	1.1	1.0	1.3	1.2	1.2	1.4	1.3	1.1
Leq, dB(A)		61.4	60.9	61.7	59.9	60.3	60.9	60.6	60.3	61.0
L10, dB(A)		63.6	63.2	64.0	62.8	63.1	63.7	63.6	63.2	64.0
L90, dB(A)		57.7	57.4	58.1	56.4	56.8	57.2	57.1	56.7	57.5
Major Construction Noise Source(s) During Measurement		/			/			/		
Other Noise Source(s) During Measurement		vehicles passing by			/			/		
Remarks		The result was not exceeded the Limit Level.			The result was not exceeded the Limit Level.			The result was not exceeded the Limit Level.		

Time Period	Action	Limit
0700-1900 hrs normal weekdays	When one documented complaint is received	75 dB(A)
1900-2300 hrs on normal weekdays		70 dB(A)
0700-1900 hrs on holidays		70 dB(A)
Restricted hrs (2300-0700 hrs)		55 dB(A)

	Name	Signature	Date
Recorded by	Mak Yei Wai	Mak	20/11/10
Checked by	Lo De Lam	Lo De Lam	22/11/10

Summary of Baseline Noise Monitoring (Night-time:0000-0100) - KS6 (The Cullinan)

Date	28/12/09	29/12/09	30/12/09	31/12/09	01/01/10	02/01/10	03/01/10	04/01/10	05/01/10	06/01/10	07/01/10	08/01/10	09/01/10	10/01/10
Daily Average, Leq(5min)	57.0	57.1	62.3	56.8	56.8	59.2	56.6	56.3	60.6	56.7	57.4	60.1	59.0	58.3
Max Leq(5min)	58.5	58.5	63.6	59.5	59.5	60.9	58.3	57.8	61.1	68.2	58.9	61.4	64.7	58.3
Min Leq(5min)	54.7	55.7	60.4	55.2	55.2	57.8	54.2	54.7	59.6	55.1	45.7	59.2	56.0	55.0

Overall Average, Leq(5-min) 58.5 dB(A)
 Max 64.7 dB(A)
 Min 54.2 dB(A)

Summary of Baseline Noise Monitoring (Night-time:2300-0100) - KY3 (Kwan Yik Building Phase 3)

Date	11/01/10	12/01/10	13/01/10	14/01/10	15/01/10	16/01/10	17/01/10	18/01/10	19/01/10	20/01/10	21/01/10	22/01/10	23/01/10	24/01/10
Daily Average, Leq(5min)	57.3	59.9	56.4	60.7	57.9	57.7	56.8	57.2	57.0	59.5	56.8	57.7	57.2	57.0
Max Leq(5min)	60.8	61.5	59.4	62.9	61.7	61.9	60.2	58.4	59.7	61.6	59.1	61.5	58.4	69.5
Min Leq(5min)	54.2	58.5	54.3	58.6	55.1	54.6	53.8	56.0	54.9	57.8	53.7	55.3	54.4	53.5

Overall Average, Leq(5-min) 58.0 dB(A)

Max 62.9 dB(A)

Min 53.5 dB(A)

Summary of Baseline Noise Monitoring (Night-time:2300-0100) - RWM (Richwealth Mansion)

Date	11/01/10	12/01/10	13/01/10	14/01/10	15/01/10	16/01/10	17/01/10	18/01/10	19/01/10	20/01/10	21/01/10	22/01/10	23/01/10	24/01/10
Daily Average, Leq(5min)	60.2	60.6	59.4	63.9	61.0	56.6	55.6	58.1	56.4	57.9	57.3	57.4	62.1	61.3
Max Leq(5min)	62.1	64.1	61.9	67.3	63.1	57.7	57.6	59.3	57.3	59.4	62.1	59.2	64.7	63.6
Min Leq(5min)	56.8	57.0	56.2	57.4	58.9	55.5	52.8	56.9	55.1	55.6	54.8	55.9	59.5	58.0

Overall Average, Leq(5-min) 59.8 dB(A)
 Max 67.3 dB(A)
 Min 52.8 dB(A)

Summary of Baseline Noise Monitoring (Night-time 2300-0100) - CG (Connaught Garden)

Date	11/01/10	12/01/10	13/01/10	14/01/10	15/01/10	16/01/10	17/01/10	18/01/10	19/01/10	20/01/10	21/01/10	22/01/10	23/01/10	24/01/10
Daily Average, Leq(5min)	62.8	62.7	62.6	62.8	63.5	63.5	62.5	62.3	61.7	61.4	60.9	63.6	63.2	62.2
Max Leq(5min)	64.6	64.7	64.4	64.2	65.0	66.1	64.6	63.7	63.6	63.0	63.6	64.7	65.3	64.0
Min Leq(5min)	60.0	59.7	59.7	59.9	61.1	60.8	59.0	60.2	59.5	59.5	58.7	61.2	59.3	59.3

Overall Average, Leq(5-min) 62.6 dB(A)
 Max 66.1 dB(A)
 Min 58.7 dB(A)



Contract No. 9/WSD/08
Laying of Western Cross Harbour Main & Associated Land Mains from West Kowloon to Sai Ying Pun
Notification of Exceedance (NOE)

Date and Time of Noise Monitoring: 27 November 2010 (2300-2400) at KY3, RWM and CGa

Construction Works carried out during the monitoring: Dredging of Type 1 marine sediment at Portion I (CH1200 to CH1328) from 27 November 2010 (1455) to 28 November 2010 (0600)

Corresponding CNP: GW-RE0502-10 (21 October 2010 to 20 April 2011)

Monitoring Location	Measured Value, dB(A)	Action Level	Limit Level, dB(A)	Possible Reason(s) for the Exceedance	Action to be taken	Remark
KY3	59.8 60.2 59.9	When one documented complaint is received	55	Dredging works were carried out by using one grab dredger (with one split hopper barge) at CH1200 to CH1328, which fulfill the requirement described in corresponding CNP. Refer to the observation during the monitoring, main source of noise impact was due to local traffic along Connaught Road West and Western Harbour Crossing. According to the summary of baseline noise monitoring, the average and range of background noise level from 2300-0100 * is 58.0dB(A) and between 53.5dB(A) and 62.9dB(A). The impact monitoring results were found within the range of baseline noise level. Hence, the exceedance recorded is considered invalid and no related to the construction works.	Nil	Nil
RWM	61.8 61.4 60.6	When one documented complaint is received	55	Dredging works were carried out by using one grab dredger (with one split hopper barge) at CH1200 to CH1328, which fulfill the requirement described in corresponding CNP. Refer to the observation during the monitoring, main source of noise impact was due to local traffic along Connaught Road West and Western Harbour Crossing. According to the summary of baseline noise monitoring, the average and range of background noise level from 2300-0100 * is 59.8dB(A) and between 52.8dB(A) and 67.3dB(A). The impact monitoring results were found within the range of baseline noise level. Hence, the exceedance recorded is considered invalid and no related to the construction works.	Nil	Nil
CGa	62.1 61.9 61.7	When one documented complaint is received	55	Dredging works were carried out by using one grab dredger (with one split hopper barge) at CH1200 to CH1328, which fulfill the requirement described in corresponding CNP. Refer to the observation during the monitoring, main source of noise impact was due to local traffic along Connaught Road West and Western Harbour Crossing. According to the summary of baseline noise monitoring, the average and range of background noise level from 2300-0100 * is 62.6dB(A) and between 58.7dB(A) and 66.1dB(A). The impact monitoring results were found below 62.6dB(A) and within the range of baseline noise level. Hence, the exceedance recorded is considered invalid and no related to the construction works.	Nil	Nil

Remark (*): Refer to the baseline data, it shows that the range of noise level during 2300-0700 is very large (around from 52dB(A) to 67dB(A)) and noise from 2300-0100 is in high level (around 60dB(A)) at all monitoring stations. As a result, baseline noise data measured between 2300-0100 at CGa, RWM, KY3 and 0000-0100 at K56 are more suitable for being as background indicator (instead of 2300-0700 of next day).

Attachment

Night-time Noise monitoring data sheets (27 November 2010)
Summary of Baseline Noise Monitoring at KY3, RWM and CGa (2300-0100)
Location plan shown the construction works carried out on 27 to 28 November 2010 (2025-0040)

Prepared by: _____


(C. L. Lau) (Environmental Team Leader)

Date: 29 November 2010

Checked by: _____

(C. L. Lau) (Environmental Team Leader)

Date: 29 November 2010





Agreement No. CE 42/2005 (WS)
Laying of Western Cross Harbour Main and Associated Land Mains
From West Kowloon to Sai Ying Pun - Investigation

Impact Noise Monitoring at Sai Ying Pun during 1900-2300 / 2300-0700 / 0700-1900 (Holiday) Data Record Sheet

Date of Monitoring		27-11-2010									
Monitoring Location For 1900-2300		CGa - Pavement at Connaught Garden			RWM - Pavement at Richwealth Mansion			KY3 - Pavement at Kwan Yik Building Phase 3			
Monitoring Location For 2300-0700 and 0700-1900 (Holiday)		CGa - Pavement at Connaught Garden			RWM - Roof at Richwealth Mansion			KY3 - Roof at Kwan Yik Building Phase 3			
Sound Level Meter (Model and Serial No.)		R10N-NC-31 (S/N: 00773032)			R10N-NC-31 (S/N: 00773032)			R10N-NC-31 (S/N: 00773032)			
Sound Pressure Calibrator (Model and Serial No.)		R10N-NC-73 (S/N: 10196943)			R10N-NC-73 (S/N: 10196943)			R10N-NC-73 (S/N: 10196943)			
Weather Condition		F2NF			F2NF			F2NF			
Temperature (°C)		20			20			20			
Type of Measurement		Free Field / Façade			Free Field / Façade			Free Field / Façade			
Measurement Period (min)		5			5			5			
Calibration before Measurement, dB(A)	Before	94.0			94.0			94.0			
	After	94.0			94.0			94.0			
Measurement Time	From	23:00	23:05	23:10	23:15	23:20	23:25	23:35	23:40	23:45	
	To	23:05	23:10	23:15	23:20	23:25	23:30	23:40	23:45	23:50	
Wind Strength (m/s)		0.4	0.4	0.4	0.2	0.2	0.2	0.3	0.3	0.3	
L _{eq} , dB(A)		62.1	61.9	61.7	61.8	61.4	60.6	59.8	60.2	59.9	
L ₁₀ , dB(A)		64.8	64.6	64.1	64.5	63.8	63.6	64.3	64.1	63.8	
L ₉₀ , dB(A)		58.6	58.5	58.5	58.3	57.6	57.6	57.3	57.0	56.8	
Major Construction Noise Source(s) During Measurement		/			/			/			
Other Noise Source(s) During Measurement		Vehicles passing by			/			/			
Remarks		The result was / was not exceeded the Limit Level.			The result was / was not exceeded the Limit Level.			The result was / was not exceeded the Limit Level.			

Time Period	Action	Limit
0700 - 1900 hrs normal weekdays	When one documented complaint is received	75 dB(A)
1900-2300 hrs on normal weekdays		70 dB(A)
0700-1900 hrs on holidays		70 dB(A)
Restricted hrs (2300-0700 hrs)		55 dB(A)

	Name	Signature	Date
Recorded by	K.M. Kwan		27-11-2010
Checked by	C.L. Lau		28-11-2010

Summary of Baseline Noise Monitoring (Night-time:2300-0100) - KY3 (Kwan Yik Building Phase 3)

Date	11/01/10	12/01/10	13/01/10	14/01/10	15/01/10	16/01/10	17/01/10	18/01/10	19/01/10	20/01/10	21/01/10	22/01/10	23/01/10	24/01/10
Daily Average, Leq(5min)	67.3	59.9	58.4	60.7	57.9	57.7	56.8	57.2	57.0	59.5	58.8	57.7	57.2	57.0
Max Leq(5min)	60.8	61.5	59.4	62.9	61.7	61.9	60.2	58.4	59.7	61.6	59.1	61.5	58.4	59.5
Min Leq(5min)	64.2	58.5	54.3	58.6	55.1	54.6	63.8	56.0	54.9	57.8	53.7	55.3	54.4	53.5

Overall Average, Leq(5-min) 58.0 dB(A)
 Max 62.9 dB(A)
 Min 53.5 dB(A)

Summary of Baseline Noise Monitoring (Night-time:2300-0100) - RWM (Richwealth Mansion)

Date	11/01/10	12/01/10	13/01/10	14/01/10	15/01/10	16/01/10	17/01/10	18/01/10	19/01/10	20/01/10	21/01/10	22/01/10	23/01/10	24/01/10
Daily Average, Leq(5min)	60.2	60.6	59.4	63.9	61.0	56.6	65.6	58.1	56.4	57.9	57.3	57.4	62.1	81.3
Max Leq(5min)	62.1	64.1	61.9	67.3	63.1	57.7	57.6	59.3	57.3	59.4	62.1	59.2	64.7	63.6
Min Leq(5min)	56.8	57.0	56.2	57.4	58.9	55.5	52.8	56.9	55.1	56.6	54.8	55.9	59.5	58.0

Overall Average, Leq(5-min) 59.8 dB(A)

Max 67.3 dB(A)

Min 52.8 dB(A)

Summary of Baseline Noise Monitoring (Night-time 2300-0100) - CG (Connaught Garden)

Date	11/01/10	12/01/10	13/01/10	14/01/10	15/01/10	16/01/10	17/01/10	18/01/10	19/01/10	20/01/10	21/01/10	22/01/10	23/01/10	24/01/10
Daily Average, Leq(5min)	62.8	62.7	62.6	62.3	63.5	63.5	62.5	62.3	61.7	61.4	60.9	63.6	63.2	62.2
Max Leq(5min)	64.6	64.7	64.4	64.2	65.0	66.1	64.6	63.7	63.6	63.0	63.6	64.7	65.3	64.0
Min Leq(5min)	60.0	59.7	59.7	59.9	61.1	60.8	59.0	60.2	59.5	59.5	58.7	61.2	59.3	59.3

Overall Average, Leq(5-min) 62.6 dB(A)
 Max 66.1 dB(A)
 Min 58.7 dB(A)




Appendix L

Contractor's Follow up Actions to ET Weekly Site Inspections

Photo of Follow-up Action




Photo Ref : 01

		 <p>Photo Ref : 01</p>



Figures




Contract No. 9/WSD/08 Laying of Western Cross Harbour Main and Associated Land Mains for West Kowloon to Sai Ying Pun

Figure 1

Location of Noise Monitoring Station at West Kowloon



業業德動測試顧問有限公司
ETS-TESTCONSULT LIMITED



Contract No. 9/WSD/08 Laying of Western Cross Harbour Main and Associated Land Mains for West Kowloon to Sai Ying Pun

Figure 2
Locations of Noise Monitoring Stations at Sai Ying Pun

Project No.	CE42/2005(M)
Scale	1 : 250000/1
Sheet No.	201/53
Revision	
Author	
Checker	
Approver	
Date	


mm Mott MacDonald
 11th Floor, One Connaught Place
 100 Queen's Road East
 Hong Kong
 Tel: 8522 4157
 Fax: 8522 4158
 E-mail: hkk@mm.com

THE GOVERNMENT OF THE HONG KONG
 SPECIAL ADMINISTRATIVE REGION
 WATER SUPPLIES DEPARTMENT

LAYING OF WESTERN CROSS HARBOUR MAIN
 AND ASSOCIATED LAND MAINS FROM WEST
 KOWLOON TO SHI YING PUN - INVESTIGATION

LOCATIONS OF WATER SENSITIVE RECEIVERS
 AND STORMWATER OUTFALLS
 AT WESTERN HARBOUR





Contract No. 9/WSD/08 Laying of Western Cross Harbour Main and Associated Land Mains for West Kowloon to Sai Ying Pun

Figure 3
Locations of Water Quality Monitoring Stations



LEGEND:

- PROPOSED ROUTE OF FRESH WATER MAIN
- NOISE SENSITIVE RECEIVERS
- - - 100m NOISE ASSESSMENT BOUNDARY
- WORKS AREA BOUNDARY

A	DATE/ISS	REV	DESCRIPTION	BY	CHKD
1	03/01/04	1	PRELIMINARY		

Mott
Connell
 14th Floor, 140 Queen's Road East
 Hong Kong
 Tel: 852 2577 8888
 Fax: 852 2577 8887
 Web: www.motc.com

THE GOVERNMENT OF THE HONG KONG
 SPECIAL ADMINISTRATIVE REGION
 WATER SUPPLIES DEPARTMENT

Project No. DE42/2005(NS)

LAYING OF WESTERN CROSS HARBOUR MAIN
 AND ASSOCIATED LAND MAINS FROM WEST
 KOWLOON TO SAU YING PUN - INVESTIGATION

LOCATIONS OF NOISE SENSITIVE
 RECEIVERS IN SAU YING PUN

Project No.	Scale	Sheet No.	Total Sheets
DE42/2005(NS)	1 : 200000	1	1



818500 N

818500 N

835500 E

835500 E


834500 E

834000 E

833500 E

LEGEND:

- PROPOSED ROUTE OF 1200# FRESH WATER MAIN
- NOISE SENSITIVE RECEIVERS
- ▨ TEMPORARY PLATFORM
- 30m NOISE ASSESSMENT BOUNDARY
- WORKS AREA BOUNDARY



A 24/08 1:1K PRELIMINARY 03/11/07
 Date Issue Description
mm Mott
 Cornnell
 4011 Connaught Road East
 100 Queen's Road East
 Hong Kong
 Tel: 8522 0707
 Fax: 8522 1188
 Web: www.mottcornell.com

THE GOVERNMENT OF THE HONG KONG
 SPECIAL ADMINISTRATIVE REGION
 WATER SUPPLIES DEPARTMENT

CE47/2005(HS)
 Project

LAYING OF WESTERN CROSS HARBOUR MAIN
 AND ASSOCIATED LAND MAINS FROM WEST
 KOWLOON TO SHU YING FUN - INVESTIGATION

LOCATION OF NOISE SENSITIVE
 RECEIVERS IN WEST KOWLOON

Project	Fig. No.	Scale	Revision
1 : 40000/1			
Drawn by	Checked by	Approved by	Author

© COPYRIGHT RESERVED
 FIGURE 1.2c
 A

This document should not be relied upon for any purpose other than that for which it was prepared. The user of this document is advised to seek professional advice for any other purpose. The user of this document is advised to seek professional advice for any other purpose.