

東業德勤測試顧問有限公司
ETS-TESTCONSULT LIMITED

8/F., Block B, Veristrong Industrial Centre, 34-36 Au Pui Wan Street, Fotan, Hong Kong
Tel : 2695 8318 E-mail : etl@ets-testconsult.com
Fax : 2695 3944 Web site : www.ets-testconsult.com

TEST REPORT

WO HING – PENTA-OCEAN JOINT VENTURE

**CONTRACT NO. 9/WSD/08
LAYING OF WESTERN CROSS
HARBOUR MAIN AND ASSOCIATED
LAND MAINS FROM WEST
KOWLOON TO SAI YING PUN
MONTHLY EM&A REPORT
NO.12
(APRIL 2011)**

Prepared by:

LAW, Sau Yee
Senior Environmental Officer

Checked by:

LAU, Chi Leung
Environmental Team Leader

Issued Date: 07 May 2011

Report No. IENA10449

ENVIRON

Ref.: WSDWHCMSEI00_0_0157L.11

11th May 2011

Water Supplies Department
Sha Tin Office
6/F Sha Tin Government Offices
1 Sheung Wo Che Road
Sha Tin, NT

By Post

Attention: Ms. Candy Wong

Dear Ms. Wong


Re: Contact No. 9/WSD/08
Laying of Western Cross Harbour Main and Associated Land Mains from West Kowloon to Sai Ying Pun
Monthly Environmental Monitoring and Audit Report No. 12

Reference is made to Environment Team's submission of the Environmental Monitoring and Audit Report No. 12 by Email on 7th May 2011 (entitled "9/WSD/08 - Draft Monthly Report (April 11)") and the subsequent revision of the report by Email on 9th May 2011.

We are pleased to inform you that we have no comment on the revised captioned report.

Thank you very much for your kind attention and please do not hesitate to contact the undersigned should you have any queries.

Yours sincerely,



David Yeung
Independent Environmental Checker

c.c.	Mott MacDonald Hong Kong Limited	Mr. Kelvin Ho	Fax: 2377 2900
	Wo Hing – Penta-Ocean Joint Venture	Mr. Danny Ho	Fax: 2572 4080
	ETS-TESTCONSULT LIMITED	Mr. C.L. Lau	Fax: 2695 3944

Q:\Projects\WSDWHCMSEI00\Corr\Out\WSDWHCMSEI00_0_0157L.11.doc



TABLE OF CONTENTS		Page
EXECUTIVE SUMMARY		
1.0	INTRODUCTION	1
2.0	PROJECT INFORMATION	
	2.1 Scope of the Project	1
	2.2 Work Programme	1
	2.3 Project Organization and Management Structure	1
	2.4 Contact Details of Key Personnel	1
3.0	WORK PROGRESS IN THIS REPORTING MONTH	1 – 2
4.0	NOISE MONITORING	
	4.1 Monitoring Requirements	2
	4.2 Monitoring Equipment	2
	4.3 Monitoring Parameters, Duration and Frequency	2
	4.4 Monitoring Locations	2 – 3
	4.5 Monitoring Methodology	3 – 4
	4.6 Action and Limit levels	4
	4.7 Event-Action Plans	4
	4.8 Results	4 – 5
5.0	WATER QUALITY MONITORING	
	5.1 Monitoring Requirements	6
	5.2 Monitoring Locations	6
	5.3 Monitoring Parameters	6
	5.4 Monitoring Frequency	6 – 7
	5.5 Monitoring Methodology and Equipment Used	7 – 8
	5.6 Details of site Equipment used for In-situ Measurement	8
	5.7 Quality Assurance (QA) / Quality Control (QC) results and Determination Limits	8
	5.8 Action and Limit Level	8 – 9
	5.9 Event and Action Plan	9
	5.10 Monitoring Duration and Period In this reporting month	9
	5.11 Results	9 – 10
6.0	SITE INSPECTION	10
	6.1 Summary of the ET weekly site inspection findings	10
	6.2 Recommendations on site inspection findings in Site Inspections of this month	11
7.0	STATUS OF ENVIRONMENTAL PERMITS	11 – 12
8.0	WASTE MANAGEMENT	
	8.1 Monthly Waste Summary	13
	8.2 Advice on the Solid and Liquid Waste Management Status	13
9.0	ENVIRONMENTAL NON-CONFORMANCE	
	9.1 Summary of Noise and Water Quality	13
	9.2 Summary of Environmental Complaints	13
	9.3 Summary of Notification of Summons and Prosecution	14
10.0	IMPLEMENTATION STATUS	
	10.1 Implementation Status of Environmental Mitigation Measures	14
	10.2 Implementation Status of Event and Action Plan	14
	10.3 Implementation Status of Environmental Complaint, Notifications of Summons and Successful Prosecutions Handling	14
11.0	CONCLUSION AND RECOMMENDATIONS	14 – 15
12.0	FUTURE KEY ISSUE	
	12.1 Work Programme for the Coming Month	15
	12.2 Key Issues for the Coming Month	15 – 16
	12.3 Monitoring Schedule for the Coming Month	16



APPENDIX

A	Organization Chart and Lines of Communication
B1	Calibration Certificates for Impact Noise Monitoring Equipment
B2	Impact Noise Monitoring Results
B3	Graphical Plots of Impact Noise Monitoring Data
C1	Calibration Certificates for Impact Water Quality Monitoring Equipment
C2	Impact Water Quality Monitoring Results
C3	Graphical Plots of Impact Water Quality Monitoring Data
C4	QA/QC Results of Laboratory Analysis for Water Samples
D	Event-Action Plans
E	Work Programme
F	ET Weekly Site Inspection Records
G	Implementation Schedule of Mitigation Measures
H	Site General Layout Plan
I	Monitoring Schedule for this month and Coming Month
J	Daily dredging Summary
K	Details of Interim Notifications of Exceedance (NOEs) in this reporting month
L	Contractor's Follow up Actions to ET Weekly Site Inspections

Figures

Figure 1	Location of Noise Monitoring Station at West Kowloon
Figure 2	Location of Noise Monitoring Stations at Sai Yung Pun
Figure 3	Locations of Water Quality Monitoring Stations
Figure 1.2a	Locations of Water Sensitive Receivers and stormwater outfalls at Western Harbour
Figure 1.2b	Locations of Noise Sensitive Receivers at Sai Ying Pun
Figure 1.2c	Locations of Noise Sensitive Receivers at West Kowloon

Tables

2.1	Contact Details of Key Personnel
4.1	Noise Monitoring Equipment
4.2	Duration, Frequency and Parameters of Noise Monitoring
4.3	Noise Monitoring Stations
4.4	Action and Limit levels for Noise Monitoring
4.5	Summary of Noise Daytime Monitoring Results
5.1	Water Quality Monitoring Stations
5.2	Water Quality Monitoring Parameters
5.3	Other relevant water quality parameters
5.4	Monitoring Frequency of Impact Water Quality Monitoring
5.5	Details of Monitoring Equipment (In-situ measurement)
5.6	Summary of test method
5.7	Water Quality Action and Limit Levels
5.8	Schedule for Impact Water Quality Monitoring
5.9	Summary of Impact Marine Water Quality Exceedances in this reporting month
6.1	Summary of Site Inspection Findings
7.1	Summary of Environmental Licensing and Permit valid in this reporting month
8.1	Summary of Quantities of Waste for Disposal in this reporting month
10.1	Summary of Environmental Complaints and Prosecutions



EXECUTIVE SUMMARY

Under the requirements of "Environmental Monitoring & Audit Manual – Agreement No. CE42/2005(W/S) Laying of Western Cross Harbour Main and Associated Land Main from West Kowloon to Sai Ying Pun" (the EM&A Manual), impact noise monitoring and water quality monitoring is required to be implemented for the "Contract No. 9/WSD/08 Laying of Western Cross Harbour Main and Associated Land Main from West Kowloon to Sai Ying Pun" (the Project).

This monthly Environmental Monitoring and Audit (EM&A) report No.12 was prepared by ETS-Testconsult Ltd (ET) for the Project. This report documented the findings of EM&A Works conducted during the Project in April 2011.

Site Activities

As informed by the Contractor, the site activities in this reporting month were as below:

- Grouting works beneath the seawater intake in West Kowloon (Portion H1 & H2);
- Drilling of pipe pile (Portion H1 & H2);
- Trimming of high spot between CH5 ~ CH10 by derrick lighter (rock fill material) (Portion I);
- Excavation inside the cofferdam (Portion J);
- Installation of the strutting system of the cofferdam (Portion J)
- Concreting of the foundation of turn roller B and back anchor (Portion J);
- Installation of turn roller B (Portion J);
- Placing of precast concrete struts inside the cofferdam (Portion J); and
- Installation of turn rollers A & B and the dry well (Portion J).

Environmental Monitoring Progress

The summary of the monitoring activities in this monitoring month is listed below:

- Day-time Noise Monitoring (0700-1900 on normal weekday): 5 Occasions at KS6 and 5 Occasions at. CGa, RWM and KY3
- Evening-time Noise Monitoring (1900-2300): 0 Occasions at KS6, CGa, RWM and KY3
- Night-time Noise Monitoring (2300-0700 of next day): 0 Occasions at KS6, CGa, RWM and KY3
- Holiday-time Noise Monitoring (0700-1900 on Holiday): 3 Occasions at KS6, CGa, RWM and KY3
- Marine Water Quality Monitoring: 11 Occasions at 9 monitoring stations and 4 control stations
- Weekly-site inspection: 4 Occasions

Noise Monitoring

No exceedances of Action Level of noise monitoring were recorded in this reporting month since no complaint on noise issue was received.

No exceedance in Limit Level were recorded in this reporting month according to the noise monitoring results.

Water Quality Monitoring

No exceedances of Action and Limit levels were recorded for water quality monitoring in the reporting month.

Site Inspection

Environmental site inspections conducted in this reporting month are presented as follows:

<u>Concerned Parties</u>	<u>Dates of Audit / Inspection</u>
ET Weekly site inspection	08, 12, 20 and 28 April 2011
Monthly Joint site inspection	20 April 2011

In general, performance on environmental mitigation measures implemented was found to be satisfactory in this reporting month. The major findings observed during site inspections are presented in the Section 6.0.

Environmental Complaints, Notification of summons and successful prosecutions

No complaints, notification of summons and prosecutions with respect to environmental issues were received in this reporting month.



Change in Environmental Aspect in this Reporting Month

No change on environmental aspect was reported in this reporting month.

Future Key Issues

Based on the forecast of engineering works in the coming month, key issues to be considered are as follows:

- *Noise and dust impact due to construction works;*
- *Use and maintain silt curtain and silt screen properly;*
- *Clean up the fill material along the barge frequently;*
- *Implement all necessary preventive measures to avoid oil leakage. In the event an oil leakage happens, the Contractor should properly remove the leaked oil and handle the contaminated soil and all materials using for this cleaning works as chemical waste; and*
- *Maintain good site practice to minimize environmental impacts at the site.*



1.0 INTRODUCTION

Wo Hing – Penta-Ocean Joint Venture (WHPOJV) appointed Environmental Team of ETS-Testconsult Limited (ETL) to undertake the Environmental Impact Monitoring for “Contract No. 9/WSD/08 Laying of Western Cross Harbour Main and Associated Land Main from West Kowloon to Sai Ying Pun” (the Project) under the requirements of “Environmental Monitoring & Audit Manual – Agreement No. CE42/2005(W/S) Laying of Western Cross Harbour Main and Associated Land Main from West Kowloon to Sai Ying Pun” (the EM&A Manual).

This report documented the findings of EM&A Works conducted in April 2011.

2.0 PROJECT INFORMATION

2.1 Scope of the Project

The construction works of the Project are located in West Kowloon, across the Victoria Harbour and in Sai Ying Pun.

The construction works under this Project are briefly described, without limitation, as follow:

- Laying of about 1.5km of 1200mm diameter steel fresh water mains at West Kowloon;
- Laying of about 2.1km of 1200mm diameter steel submarine pipeline from West Kowloon to Sai Ying Pun including dredging, cathodic protection system and other associated works;
- Laying of about 0.4km of 1200mm diameter steel fresh water main at Sai Ying Pun;
- Laying of about 0.5km of 800mm diameter steel salt water main at West Kowloon;
- Construction of motorized butterfly valve (MBV) and the associated facilities in the vicinity of Sun Yat Sen Memorial Park at Sai Ying Pun;
- Construction of all chambers associated with pipeworks;
- Making service connections;
- Ancillary works including but not limited to reinstatement of roads, landscaping works.

Areas of the Project present in Appendix H. Locations of environmental monitoring stations and sensitive receivers are shown in Figures 1, 2, 3, 1.2a, 1.2b and 1.2c

2.2 Work Programme

Details of work programme are shown in Appendix E.

2.3 Project Organization and Management Structure

The organization chart and lines of communication with respect to the on-site environmental management and monitoring program are shown in Appendix A.

2.4 Contact Details of Key Personnel

The key personnel contact names and telephone numbers are shown in Table 2.1.

Table 2.1 Contact Details of Key Personnel

Project Role	Organization	Name of Key Staff	Tel. No.	Fax No.
Engineer's Representative	Mott MacDonald	Mr. Kelvin Ho	2377 2823	2377 2900
IEC	Environ	Mr David Yeung	3743 0788	3548 6988
Contractor's Agent	WHPOJV	Mr. Danny Ho	2695 8318	2957 8213
ET Leader	ET (ETL)	Mr C. L. Lau	2946 7791	2695 3944

3.0 WORK PROGRESS IN THIS REPORTING MONTH

As informed by the Contractor, the activities in the reporting month include:

- Grouting works beneath the seawater intake in West Kowloon (Portion H1 & H2);
- Drilling of pipe pile (Portion H1 & H2);
- Trimming of high spot between CH5 ~ CH10 by derrick lighter (rock fill material) (Portion I);
- Excavation inside the cofferdam (Portion J);
- Installation of the strutting system of the cofferdam (Portion J)
- Concreting of the foundation of turn roller B and back anchor (Portion J);



- Installation of turn roller B (Portion J);
- Placing of precast concrete struts inside the cofferdam (Portion J); and
- Installation of turn rollers A & B and the dry well (Portion J).

Appendix J shows the details of works daily dredging of this reporting month.

4.0 IMPACT NOISE MONITORING

4.1 Monitoring Requirements

As the requirement in the EM&A Manual, impact noise monitoring was conducted for a weekly basis at designated monitoring locations.

4.2 Monitoring Equipment

Integrating Sound Level Meters used for impact noise monitoring were Type 1 sound level meters capable of giving a continuous readout of the noise level reading including equivalent continuous sound pressure level (L_{eq}) and percentile sound pressure level (L_x). They complied with International Electro technical Commission Publications 651:1979 (Type1) and speed in m/s was used to monitor the wind speed. Table 4.1 summarized the noise monitoring equipment model used during the impact monitoring. Copies of calibration certificates and Calibration Summary for noise meters and calibrators used are attached in Appendix B1.

Table 4.1 Noise Monitoring Equipment

Equipment	Model	Equipment No.	Serial No.	Calibration Date.	Expired Date
Sound Level Meter	Rion NL-31 Sound Level Meter	ET/EN/003/13	00593620	14/09/10	13/09/11
		ET/EN/003/10	00531142	09/06/10	08/06/11
Sound Level Calibrator	Rion NC-73 Sound Level Calibrator	ET/EN/002/01	10196943	12/11/10	11/11/11
Anemometer	AZ Instrument AZ 8908	EN/001/04	9101231	10/11/10	09/11/11

4.3 Monitoring Parameters, Duration and Frequency

Impact noise monitoring for the A-weighted levels L_{eq} , L_{10} and L_{90} were recorded once per week. Data obtained from impact noise monitoring was processed and presented as below:

- Daytime: three sets of 30-minute noise level monitored between 0700-1900 hrs on normal weekdays;
- Evening-time*: three sets of 5-minute noise level monitored between 1900-2300 hrs ;
- Night-time*: three sets of 5-minute noise level monitored between 2300-0700 hrs of next day; and
- Holiday*: three sets of 5-minute noise level monitored between 0700-1900 hrs on holiday.

(*): Noise monitoring to be conducted only when there is construction work.

Duration, frequencies and parameters of noise measurement are presented in Table 4.2.

Table 4.2 Duration, Frequencies and Parameters of Noise Monitoring

Time period	Duration/min	No. of Set(s)	Parameters
Day-time: 0700-1900 hrs on normal weekday	30	1	L_{eq} , L_{10} , L_{90}
Evening-time: 1900-2300 hrs	5	3	L_{eq} , L_{10} , L_{90}
Night-time: 2300-0700 hrs of next day	5	3	L_{eq} , L_{10} , L_{90}
Holiday-time: 0700-1900 hrs on holiday	5	3	L_{eq} , L_{10} , L_{90}

4.4 Monitoring Locations

In accordance with the EM&A Manual, the proposed noise monitoring station at the Harbourside (KS4) was cancelled since the owner of the Harbourside and nearby NSRs rejected to perform baseline and impact noise monitoring at their property. As a result, there was one noise monitoring location KS6 (The Cullinan) selected at West Kowloon to conduct impact environmental monitoring.

At Sai Yung Pun, the location at the noise station CG (Connaught Garden) was unavailable for impact noise measurement because the building repairing and maintenance works was carrying out in the Connaught Garden and will be finished in May 2011. Hence, noise monitoring at noise station CG was moved to another noise station CGa (pavement in front of Connaught Garden) temporarily until the completion of repairing and maintenance works at Connaught Garden since CGa locates close to the major site activities which are likely to have noise impacts and low disturbance to the occupants was observed during the noise monitoring. As a result, there were three noise monitoring locations, CGa (Pavement in front of Connaught Garden), RWM (Roof at Richwealth Mansion) and KY3 (Roof at Kwan Yik Building Phase 3) selected to conduct impact environmental monitoring.

Beside, the locations at the noise stations, RWM (Roof at Richwealth Mansion) and KY3 (Roof at Kwan Yik Building Phase 3), were unavailable for impact evening-time and night-time noise measurement because the building owners reject ET to carry out noise monitoring during such two periods due to security. Hence, evening-time and night-time noise monitoring at noise stations, RWM and KY3 were moved to pavement in front of Richwealth Mansion and Kwan Yik Building Phase 3. The details of noise monitoring stations are summarized in Table 4.3.

Table 4.3 Noise Monitoring Stations

<i>Daytime and Holiday-time Noise monitoring station</i>	<i>Description of location</i>	<i>Type of Measurement</i>
KS6	Podium at the Culliman	Façade
CGa	Pavement in front of Connaught Garden	Façade
RWM	Roof at Richwealth Mansion	Free Field
KY3	Roof at Kwan Yik Building Phase 3	Free Field
<i>Evening-time and Night-time Noise monitoring station</i>	<i>Description of location</i>	<i>Type of Measurement</i>
KS6	Podium at the Culliman	Façade
CGa	Pavement in front of Connaught Garden	Façade
RWM	Pavement at Richwealth Mansion	Façade
KY3	Pavement at Kwan Yik Building Phase 3	Façade

4.5 Monitoring Methodology

Instrumentation

Integrating Sound Level Meters were employed for noise monitoring.

Operation/Analysis Procedures

- Sound Level Meter was set on a tripod at a height of 1.2m above the ground;
- For free field measurement, the meter was positioned away from any nearby reflective surfaces.
- The battery condition was checked to ensure the correct functioning of the meter:
- Parameters such as frequency weighting, the time weighting and the measurement time were set as follows:
 - Frequency weighting : A
 - Time weighting : Fast
 - Time measurement : 30 mins
- Prior to and after each noise measurement, the meter was calibrated using a Calibrator for 94 dB at 1000HZ. If the difference in the calibration level before and after measurement was more than 1.0 dB(A), the measurement would be considered invalid and repeat measurement would be required after re-calibration or repair of the equipment;
- During the monitoring period, the L_{eq} , L_{10} and L_{90} were recorded. In addition, site conditions and noise sources were recorded on a standard record sheet;
- 3dB(A) correction had been added to the results if noise measurements were free-field;
- Noise measurement may be paused during periods of high intrusive noise (e.g. dog barking directly towards the receiver of noise level meter). If noise measurement was paused during high intrusive noise, the noise level meter would be resumed and continued the noise measurement and the observations would also be recorded. Any pause intervals were not included in the measurement time; and

- Noise monitoring would be cancelled in the presence of fog, rain, storm, wind with a steady speed exceeding 5m/s, or wind gusts exceeding 10m/s.

Maintenance and Calibration

- The microphone head of the sound level meter and calibrator are cleaned with soft cloth at quarterly intervals; and
- The meters are sent to supplier or HOKLAS laboratory to check and calibrated at yearly intervals.

4.6 Actions and Limit Levels

The Action and Limit Levels (AL Levels) were established in accordance to the Table 4.2 of the EM&A Manual. Table 4.4 presents the AL levels for noise monitoring.

Table 4.4 Action and Limit Levels for Noise Monitoring

Time Period	Action	Limit
0700 –1900 hrs on normal weekday (Day-time)	When one documented complaint is received	75 dB(A) *
1900-2300 hrs (Evening-time)		70 dB(A)
0700-1900 hrs on Holiday (Holiday-time)		70 dB(A)
Restricted hours (2300-0700 hrs of next day) (Night-time)		55 dB(A)

* reduce to 70dB(A) for school and 65dB(A) during school examination periods

4.7 Event-Action Plans

Should the results of the monitoring parameters at any designated monitoring stations indicate that the noise level criteria are exceeded, the actions in accordance with the Event and Action Plan that summarized in Appendix D should be carried out.

4.8 Results

Totally 5 occasions at KS6 and 5 occasions at CGa, RWM and KY3 of day-time noise monitoring, 0 occasion of evening-time noise monitoring, 0 occasion of night-time noise monitoring and 3 occasions of holiday-time noise monitoring at all four noise monitoring stations (KS6, CGa, RWM and KY3) were carried out in this reporting month.

No exceedances of Action Level of noise monitoring were recorded in this reporting month since no complaint on noise issue was received. Besides, no exceedance in Limit Level were recorded according to the noise monitoring results in this reporting month.

Table 4.5 summaries the noise daytime monitoring results in the reporting period.

Table 4.5 Summary of Noise Daytime Monitoring Results

Monitoring Parameter	Date	KS6		
		Time	Result	Exceed*
Daytime	01/04/11	16:15	68.5	X
	06/04/11	17:35	66.3	X
	15/04/11	09:50	63.9	X
	20/04/11	15:40	66.4	X
	29/04/11	11:30	67.1	X
Holiday-time	03/04/11	11:50	63.4	X
	03/04/11	11:55	63.1	X
	03/04/11	12:00	63.6	X
	10/04/11	08:50	62.9	X
	10/04/11	08:55	59.8	X
	10/04/11	09:00	60.1	X
	17/04/11	14:15	61.5	X
	17/04/11	14:20	60.2	X
	17/04/11	14:25	60.1	X



Monitoring Parameter	Date	CGa		
		Time	Result	Exceed*
Daytime	01/04/11	13:30	74.7	X
	04/04/11	15:25	74.6	X
	11/04/11	13:35	74.0	X
	18/04/11	11:35	74.2	X
	27/04/11	10:25	72.3	X
Holiday-time	03/04/11	10:20	69.8	X
	03/04/11	10:25	69.4	X
	03/04/11	10:30	69.7	X
	10/04/11	10:00	67.7	X
	10/04/11	10:05	68.2	X
	10/04/11	10:10	67.8	X
	17/04/11	16:30	69.8	X
	17/04/11	16:35	69.6	X
	17/04/11	16:40	69.9	X
Monitoring Parameter	Date	RWM		
		Time	Result	Exceed*
Daytime	01/04/11	14:05	64.2	X
	04/04/11	14:50	63.8	X
	11/04/11	13:00	63.4	X
	18/04/11	11:00	62.4	X
	27/04/11	11:00	62.8	X
Holiday-time	03/04/11	10:40	62.1	X
	03/04/11	10:45	62.4	X
	03/04/11	10:50	61.9	X
	10/04/11	10:20	60.2	X
	10/04/11	10:25	59.9	X
	10/04/11	10:30	60.5	X
	17/04/11	16:10	63.3	X
	17/04/11	16:15	63.6	X
	17/04/11	16:20	63.1	X
Monitoring Parameter	Date	KY3		
		Time	Result	Exceed*
Daytime	01/04/11	14:40	62.4	X
	04/04/11	14:15	61.9	X
	11/04/11	11:20	62.3	X
	18/04/11	10:25	59.6	X
	27/04/11	11:35	60.3	X
Holiday-time	03/04/11	11:00	60.5	X
	03/04/11	11:05	60.2	X
	03/04/11	11:10	59.9	X
	10/04/11	10:40	61.0	X
	10/04/11	10:45	60.8	X
	10/04/11	10:50	60.9	X
	17/04/11	15:50	61.1	X
	17/04/11	15:55	60.8	X
	17/04/11	16:00	60.2	X

Remark (*): L = Limit Level exceedance, A = Action Level exceedance and X = not an Exceedance
 (*): Since daytime and holiday-time noise measurements at monitoring stations RWM and KY3 were free-field, 3dB(A) correction had been added to the results

The summary of noise exceedances is shown in Table 4.6.

Table 4.6 Summary of Impact Noise Exceedances in this reporting month

Exceedance Level	Daytime	Evening-time	Night-time	Holiday-time
Action	0	0	0	0
Cumulative	0	0	0	0
Limit	0	0	0	0
Cumulative	0	0	149	0



5.0 WATER QUALITY MONITORING

5.1 Monitoring Requirements

In accordance with the EM&A Manual, impact water quality monitoring was conducted three days per week during the course of the marine construction works.

5.2 Monitoring Locations

In accordance with the EM&A Manual, the proposed water quality monitoring station R8 – Macau Ferry Terminal was cancelled since it is located inside the restricted area. Another monitoring location R8a was proposed to replace R8 for impact water quality monitoring. As a result, totally four control stations and nine impaction stations were selected to conduct impact water quality monitoring for the Project. Table 5.1 shows the water quality monitoring stations of the Project.

Table 5.1 Water Quality Monitoring Stations

ID	Station	Easting	Northing
R5	Green Island	830 175.979	816 179.217
R6	Prince Philip Dental Hospital	833 437.625	816 747.640
R7	Tsan Yuk Hospital	833 461.092	816 744.773
R8a	Macau Ferry Terminal	833 573	816 885
R15 *	Kowloon South Pumping Station	833 982.630	818 282.101
R16	Kowloon Government Offices Building	834 335.800	817 769.145
R17	Canton Road Government Offices Building	834 364.658	817 802.847
R28	WSD Kennedy Town Salt Water Pumping Station	830 707	815 983
R29	WSD Sheung Wan Salt Water Pumping Station	833 414	816 745
C1	Control Station	830 797.729	819 163.377
C2	Control Station	836 350.628	817 135.218
C3	Control Station	829 495.126	817 228.312
C4	Control Station	836 638.773	816 686.030

Remark (*): Station R15 = WSD Seawater Intake

Control stations, C2 and C4, should be the upstream control station for all impact monitoring stations at mid-flood and Control Stations, C1 and C3, should be the upstream control station for all monitoring stations at mid-ebb.

5.3 Monitoring Parameters

Monitoring parameters listed in Table 5.2 shall be monitored by the ET to ensure that any deteriorating water quality could be readily detected and timely action be taken to rectify the situation. Table 5.3 shows the other relevant water quality data recorded during the impact water quality monitoring.

Table 5.2 Water Quality Monitoring Parameters

In-situ measurement	Laboratory analysis
Dissolved Oxygen (DO) (mg/L)	Suspended solids (SS) (mg/L)
Turbidity (NTU)	

Table 5.3 Other relevant water quality parameters

Water Quality Parameters	
Tidal stages	Water depth (m)
Dissolved Oxygen saturation (%)	Salinity (ppt)
Temperature (°C)	Weather Condition

5.4 Monitoring Frequency

The frequency of impact water quality monitoring of water quality is summarized in Table 5.4.



Table 5.4 Monitoring Frequency of Impact Water Quality Monitoring

Frequency	Monitoring Depth
3 days/week, 2 tides/day	For water depth greater than 6m: Three water depths (1m below Surface, mid-depth and 1m above bottom). For water depth less than 6m but greater than 3m: Two water depths: (1m below Surface and 1m above bottom). For water depth less than 3m: One water depth (Mid-depth)

5.5 Monitoring Methodology and Equipment Used

Refer to the requirement in Appendix D2 "General Technical Requirements of Environmental Monitoring" (TM) in the Environmental Monitoring and Audit Guidelines for Development Projects in Hong Kong published by EPD, water samples for all monitoring parameter were collected, stored, preserved and analysed according to the Standard Method APHA 19ed.. In-situ measurements at monitoring locations including DO, turbidity, salinity and water depth were collected by equipment with the characteristic and functions listed as below:

Location of the monitoring stations

A hand-held digital Global Positioning System (GPS) was used to identify the designated monitoring stations prior to water sampling.

Water Depth measurement

A portable, battery-operated echo sounder was used for the determination of water depth at each designated monitoring station.

In-situ Water Quality Monitoring Equipment

All in-situ monitoring instruments shall be checked, calibrated and certified by a laboratory accredited under HOKLAS or any other international accreditation scheme before use, and subsequently re-calibrated at 3 monthly intervals or sometimes longer throughout all stages of the water quality monitoring. Responses of sensors and electrodes should be checked with certified standard solutions before each use. Wet bulb calibration for a DO meter shall be carried out before measurement at each monitoring location.

Dissolved Oxygen, salinity and temperature measuring equipment

A portable, weatherproof dissolved oxygen & salinity measuring instrument, which complete with cable, sensor and DC power source (e.g. YSI 85 or equivalent) was used for measuring:

- a dissolved oxygen level in the range of 0-20 mg/L and 0-200 % saturation;
- a salinity in range 0-40 ppt; and
- a temperature of 0-45 degree Celsius

A membrane electrode with automatic temperature compensation complete with a cable was installed.

Turbidity Measurement Instrument

A portable, weatherproof turbidity-measuring instrument with DC power source was used. It has a photoelectric sensor capable of measuring turbidity between 0-1000 NTU and be complete with a cable (e.g. HACH model 2100P or equivalent)

Water Sampling and Sample Analysis

In-situ monitoring was carried out at three depths: 1 meter below water surface, at mid-depth and 1 meter above the seabed. If the water depth is less than 6 m, the mid-depth station shall be omitted and if the water depth is below 3 m, only the mid depth station shall be monitored.

A water sampler comprising a transparent PVC cylinder, with a capacity of not less than 2 litres, was lowered into the water body at the predetermined depth. The opening ends of the sampler were then closed accordingly and water samples were collected.



The sample container, made by high-density polythene, was rinsed with a portion of the water sample. The water sample was then transferred to the container, labelled with a unique sample ID and sealed with a screw cap. The water samples were stored in a cool box maintained at 4°C. The water samples were then delivered to Environmental Laboratory of ETS-Testconsult Ltd (HOKLAS Registration No. 022) on the same day for analysis.

5.6 Details of site Equipment used for In-situ Measurement

All in-situ monitoring instruments were checked, calibrated and certified by a laboratory accredited under HOKLAS or any other international accreditation scheme before use, and subsequently re-calibrated at 3 monthly intervals or sometimes longer throughout all stages of the water quality monitoring. Wet bulb calibration for a DO meter was carried out before measurement at each monitoring location.

Table 5.5 shows the equipment used for in-situ monitoring of water quality. The calibration certificates are attached in Appendix C1.

Table 5.5 Details of Monitoring Equipment (In-site measurement)

Parameter	Model	Date of Calibration	Due Date	Equipment No.	Serial No.
Coordinate of Monitoring stations	Magellan GPS Navigator	----	----	ET/EW/005/03	211836B
Dissolved Oxygen (Saturation), Temperature and Salinity	YSI Dissolved Oxygen, Salinity & Temperature Meter, YSI 85	22/02/11	21/05/11	ET/EW/008/002*	06C1998AD
Turbidity	HACH Model 2100P Turbid Meter	15/01/11 14/04/11	14/04/11 13/07/11	ET/0505/007*	08060C030281
Water Depth	Speedtech Instrument SM-5A	----	----	ET/EW/002/04	56657

Remark:(*) indicates the instrument should be calibrated on use.

5.7 Quality Assurance (QA) / Quality Control (QC) results and Determination Limits

At each measurement/sampling depth, two consecutive measurements of dissolved oxygen (DO), dissolved oxygen saturation (DOS), turbidity and salinity were taken. The probes were retrieved out of the water after the first measurement and then re-deployed for the second measurement. If the difference between the first and second measurement is greater than 25% the reading was discarded and the measurements were repeated.

At the laboratory analysis of water sample, test method of test parameter as required by the EM&A Manual, with the QA/QC results in accordance with the requirement of HOKLAS or international accredited scheme is shown in Table 5.6. For the QA/QC procedures, one QC sample, one duplicate sample and one sample spike of every batch of 20 samples were analysis. The QA/QC results are summarized in Appendix C4

Table 5.6 Summary of test method

Laboratory Analysis	Testing Procedure	Method Detection Limit
Total suspended solids	In house method based on APHA 19 th ed 2540D	1.0 mg/L

5.8 Action and Limit Level

The water quality criteria, namely Action and Limit (A/L) levels are presented in the table below.



Table 5.7 Water Quality Action and Limit Levels

Parameter	Action Level	Limit Level
DO (mg/L) (Surface, Middle & Bottom)	<u>Surface, Middle & Bottom</u> WSD Seawater Intakes 2 mg/L (For R15) Other Impact Monitoring Stations 5.65 mg/L (For R5, R6, R7, R8a, R16, R17, R28 and R29)	<u>Surface & Middle</u> WSD Seawater Intakes 2 mg/L (For R15) Other Impact Monitoring Stations 5.51 mg/L (For R5, R6, R7, R8a, R16, R17, R28 and R29) <u>Bottom</u> 5.11 mg/L (For R15, R5, R6, R7, R8a, R16, R17, R28 and R29)
SS (mg/L) (Depth-averaged)	WSD Seawater Intakes 10 mg/L (For R15) Other Impact Monitoring Stations 12.7 mg/L (For R5, R6, R7, R8a, R16, R17, R28 and R29)	WSD Seawater Intakes 10 mg/L (For R15) Other Impact Monitoring Stations 12.7 mg/L (For R5, R6, R7, R8a, R16, R17, R28 and R29)
Turbidity (NTU) (Depth-averaged)	WSD Seawater Intakes 10 NTU Other Impact Monitoring Stations 6.48 NTU (For R5, R6, R7, R8a, R16, R17, R28 and R29)	WSD Seawater Intakes 10 NTU Other Impact Monitoring Stations 6.82 NTU (For R5, R6, R7, R8a, R16, R17, R28 and R29)

Notes: 1. "depth-averaged" is calculated by taking the arithmetic means of reading of all three depths.
2. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
3. For turbidity and SS, non-compliance of water quality limits occurs when monitoring result is higher than the limits.
4. All the figures given in the table are used for reference only and the EPD may amend the figures whenever it is considered as necessary.

5.9 Event and Action Plan

Please refer to the Appendix D for details.

5.10 Monitoring Duration and Period In this reporting month

Daily water quality monitoring duration are detailed in Appendix C2. Below is the time schedule for the water quality monitoring conducted in this reporting month:

Table 5.8 Schedule for Impact Water Quality Monitoring

April 2011						
Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
					1	2
3	4	5	6	7	8	9
10	11	12	13	14	15	16
17	18	19	20	21	22	23
24	25	26	27	28	29	30

Remarks: (▼) = Marine water quality monitoring carried out by ET.

5.11 Results

The impact water quality measurement results are detailed in Appendix C2. Appendix C3 presents the water quality monitoring data and graphical presentations of monitoring results respectively. The summary of marine water quality exceedances is shown in Table 5.9.

Table 5.9 Summary of Impact Marine Water Quality Exceedances in this reporting month

Exceedance Level	DO		Turbidity		SS		Cumulative	
	Flood	Ebb	Flood	Ebb	Flood	Ebb	Flood	Ebb
Action	0	0	0	0	0	0	0	0
Limit	0	0	0	0	0	0	0	0

According to the summary of marine water monitoring results, no exceedances of Action and Limit levels were recorded for this reporting month.

6.0 ENVIRONMENTAL SITE INSPECTION

During this reporting month, weekly site inspections were undertaken on 08, 12, 20 and 28 April 2011 by ET. Monthly joint site inspection at 20 April 2011 was carried out by Engineer's Representative, IEC, WHPOJV and ET. A summary of implementation status of mitigation measures on site inspections is presented in Appendix G.

6.1 Summary of the ET weekly site inspection findings

According to the summary of the ET weekly site inspections carried out in April 2011, it indicated that site practices of the Contractor were generally undertaken in an environmentally acceptable manner and the overall site environmental performance was satisfactory. Summary of the site inspection findings in this reporting month is shown in Table 6.1.

Table 6.1 Summary of Site Inspection Findings

Item	Aspect	Finding	Action(s) taken by the Contractor	ET Verification	Status of finding
1	Water	Follow up action to the outstanding finding in the previous month, excavated materials accumulated along the sea-front at Portion J were found removed and steel bundling was provided to prevent the excavated materials dropping into the sea during the weekly site inspection on 12/04/11.	---	---	Closed
2	Water	Follow up action to the outstanding finding in the previous month, silt screen at Portion J was found removed and rubbish was collected during the weekly site inspection on 08/04/11.	---	---	Closed
3	Water	Silt screen at the sea water intake at Kowloon Salt Water Pumping Station was found damaged during the weekly site inspection on 12/04/11 (although no marine works were carried out during the inspection day).	<ul style="list-style-type: none"> Repair the damaged part of silt screen and maintain it properly. (Photo Ref.1 of the Contractor Follow-up Action – 12/04/11) 	During the subsequent weekly site inspection on 20/04/11, silt screen at the sea water intake at Kowloon South Salt Water Pumping Station was found repaired and maintain properly.	Closed
4	Site Practice	Rubbish skip at Portion J was noted full of rubbish during the weekly site inspection on 08/04/11.	<ul style="list-style-type: none"> The rubbish skip at Portion J was covered by the impervious sheet (Photo Ref.2 of the Contractor Follow-up Action – 12/04/11) 	During the subsequent weekly site inspection on 12/04/11, the rubbish skip was removed.	Closed
5	Site Practice	Water leakage was observed from an air-conditioner at Contractor's site office at Portion J during the weekly site inspection on 08/04/11.	<ul style="list-style-type: none"> Water outlet was connected to the container to prevent water leakage to the nearby environment (Photo Ref.2 of the Contractor Follow-up Action – 08/04/11) 	During the subsequent weekly site inspection on 12/04/11, water outlet was connected to the container and hence no leaked water was noted.	Closed



6.2 Recommendations on site inspection findings in Site Inspections of this month

Based on the site inspection findings, the recommendations are as below:

- Minimize noise and dust impact due to construction works;
- Use and maintain silt curtain and silt screen properly;
- Adequate environmental control measures shall be provided to prevent / avoid dropping of dredged materials into the sea during the transfer;
- Implement all necessary preventive measures to avoid oil leakage. In the event an oil leakage happens, the Contractor should properly remove the leaked oil and handle the contaminated soil and all materials using for this cleaning works as chemical waste;
- Checking and maintaining all the site machines to prevent black smoke emission;
- Providing briefing to the concerned site staff on remedial actions, such as handling method of chemicals and chemical waste;
- Remove all stagnant water;
- Apply proper treatment facilities to wastewater before discharge; and
- Maintain good waste management at the site.

7.0 STATUS OF ENVIRONMENTAL PERMITS

Permits/licenses valid in this reporting month are summarized in Table 7.1.

Table 7.1 Summary of Environmental Licensing and Permit valid in this reporting month

Description	Permit No.	Valid Period		Remarks
		From	To	
Environmental Permit	EP-273/2007	31/07/07	End of Project	Whole Project
Water Discharge Licence (West Kowloon)	WT00005347-2009	07/01/10	31/01/15	Effluent and all other wastewater arising from the construction site through Screen & Sedimentation Tank
Water Discharge Licence (Sai Yung Pun)	WT00005800-2010	14/01/10	31/01/15	Effluent arising from the construction site through Sedimentation Tank
Chemical Waste Producer	5213-217-W3086-01	13/10/09	End of Project	Spent oil, surplus flammable liquid, surplus paint, soil, rags & containers contaminated with lubricating oil, diesel, flammable liquid & paint, & used batteries
Construction Noise Permit (West Kowloon)	GW-RE0160-11	18/03/11	14/09/11	Group A One Crane, mobile (diesel) (CNP 048) (Zone A) One Generator, silenced, $\leq 75\text{dB(A)}$ at 7m (Zone A) One Generator, standard (CNP 101) (Zone B) Group B One Crane, mobile (diesel) (CNP 048) (Zone A) One Air compressor, air flow $\leq 10\text{m}^3/\text{min}$ (CNP 001) (Zone B) Two Crane, mobile (diesel) (CNP 048) (Zone B) One Derrick barge (CNP 061) (Zone B) Four Generator, silenced, $\leq 75\text{dB(A)}$ at 7m (Zone B) Six Grinder, hand-held (electric) (CNP065) (Zone B) Two Guard boats (Zone B) Two Poker, vibratory, external (electric) (Zone B) One Tug boat (CNP 221) (Zone B) Group C One Generator, silenced, $\leq 75\text{dB(A)}$ at 7m (Zone A) One Air compressor, air flow $\leq 10\text{m}^3/\text{min}$ (CNP 001) (Zone B) One Grinder, hand-held (electric) (CNP065) (Zone B) Group D One Derrick barge (CNP 061) (Zone B) One dredger, grab (CNP 063) (Zone B) One Generator, standard (CNP 101) (Zone B) Two Guard boats (Zone B) One Tug boat (CNP 221) (Zone B)



Description	Permit No.	Valid Period		Remarks
		From	To	
Construction Noise Permit (West Kowloon)	GW-RE0257-11	19/04/11	04/10/11	<p>Group A One Air Compressor, air flow $\leq 10\text{m}^3/\text{min}$ (CNP 001) (Zone A) One Crane, mobile (diesel) (CNP 048) (Zone A) One Generator, silenced, $\leq 75\text{dB(A)}$ at 7m (Zone A) One Generator, standard (CNP 101) (Zone B)</p> <p>Group B One Concrete lorry mixer (CNP 044) (Zone A) One Crane, mobile (diesel) (CNP 048) (Zone A) One Air compressor, air flow $\leq 10\text{m}^3/\text{min}$ (CNP 001) (Zone B) Two Crane, mobile (diesel) (CNP 048) (Zone B) One Derrick barge (CNP 061) (Zone B) Four Generator, silenced, $\leq 75\text{dB(A)}$ at 7m (Zone B) Six Grinder, hand-held (electric) (CNP065) (Zone B) Two Guard boats (Zone B) Two Poker, vibratory, external (electric) (Zone B) One Tug boat (CNP 221) (Zone B)</p> <p>Group C One Generator, silenced, $\leq 75\text{dB(A)}$ at 7m (Zone A) One Air compressor, air flow $\leq 10\text{m}^3/\text{min}$ (CNP 001) (Zone B) One Grinder, hand-held (electric) (CNP065) (Zone B) One Generator, silenced, $\leq 75\text{dB(A)}$ at 7m (Zone B)</p> <p>Group D One Derrick barge (CNP 061) (Zone B) One dredger, grab (CNP 063) (Zone B) One Generator, standard (CNP 101) (Zone B) Two Guard boats (Zone B) One Tug boat (CNP 221) (Zone B)</p>
Construction Noise Permit (Sai Ying Pun)	GW-RS0352-11	26/04/11	10/10/11	<p>Group A One dredger, grab (CNP 063) Two Guard boats One Tug boats (CNP 221) One Hopper barge One Air compressor with Noise Emission Label showing a sound power level of $\leq 98\text{dB(A)}$ One Generator, silenced, 108dB(A) (CNP 101) One Derrick barge (CNP 061)</p> <p>Group B One Crane, mobile (diesel) (CNP 048) One Air compressor with Noise Emission Label showing a sound power level of $\leq 98\text{dB(A)}$ One Generator, silenced, 108dB(A) (CNP 101)</p> <p>Group C Two Derrick barge (CNP 061) Three Guard boats One Tug boat (CNP 221) One Air compressor with Noise Emission Label showing a sound power level of $\leq 98\text{dB(A)}$ Two Generator, silenced, 108dB(A) (CNP 101)</p> <p>Group D One Derrick barge (CNP 061) Two Guard boats One Tug boat (CNP 221) One Crane, mobile (diesel) (CNP 048) One Air compressor with Noise Emission Label showing a sound power level of $\leq 98\text{dB(A)}$ One Generator, silenced, 108dB(A) (CNP 101)</p> <p>Group E One Derrick barge (CNP 061) Two Guard boats One Tug boat (CNP 221) One Crane, mobile (diesel) (CNP 048) Two Generator, silenced, 108dB(A) (CNP 101) One Winch (electric) (CNP 262)</p> <p>Group F One Air compressor with Noise Emission Label showing a sound power level of $\leq 98\text{dB(A)}$ One Generator, silenced, 108dB(A) (CNP 101)</p>
Notification under APCO	Application had been submitted to EPD on 25/09/09 and approved from 29/09/09.			



8.0 WASTE MANAGEMENT

8.1 Monthly Waste Summary

The quantities of waste generated from the Project in this month are summarized in Table 8.1.

Table 8.1 Summary of Quantities of Waste for Disposal in this reporting month

Type of Waste		Quantity	Disposal Location	Cumulative Quantity
Inert C&D Materials	Total Quantity Generated (in m ³)	701.05		12806.76
	Broken Concrete (in m ³)	0	---	0
	Reused in the Contract (in m ³)	0	---	0
	Reused in other Projects (in m ³)	0	---	0
	Disposal as Public Fill (in m ³)	701.05	SENT Landfill	12806.76
C&D Waste	Metals (in kg)	0	---	0
	Paper/Cardboard Packaging (in kg)	0	Collected by recycling company	104
	Plastics (in kg)	0	---	0
	Chemical Waste (in kg)	0	---	0
	Other, e.g. General Refuse (in m ³)	5.16	SENT Landfill	72.74
Dredged Materials*	Type 1 (in m ³)	0	East Ninepin Mud Disposal Ground	160500
	Type 2 (in m ³)	0	The East Sha Chau	104990

Remark (*): Daily Dredging Summary for this reporting month presents in Appendix J

8.2 Advice on the Solid and Liquid Waste Management Status

The Contractor should provide sufficient preventive measures during equipment maintenance works so as to avoid oil leakage on the ground. In the event of any oil leakage, the Contractor should clean up the polluted soil and handle all the materials used for this cleaning works as chemical waste.

Besides, pre-cast drip trays were provided for oil drums at several areas, such as barge and chemical storage area. The Contractor should collect and dispose of any stagnant water accumulated in the drip trays and handle them as chemical waste.

The Contractor should use suitable containers with proper labels to store chemical wastes in accordance with Code of Practice on the Packaging, Labeling and Storage of Chemical Waste. The Contractor should also advise their workers of the proper procedures in handling the chemical waste.

All the trip tickets for chemical waste disposal were properly kept in the site office. No chemical waste disposal was undertaken in the reporting month.

The Contractor was reminded to increase the frequency of inspection and cleaning of the site drainage system, including desilting facilities. Moreover, the Contractor should apply approved pesticides in the stagnant water.

9.0 ENVIRONMENTAL NON-CONFORMANCE

9.1 Summary of Noise and Water Quality

No exceedances of Action and Limit Level of marine water quality monitoring results were recorded during the reporting month.

No exceedances of Action Level of noise monitoring were recorded in this reporting month since no complaint on noise issue was received. Besides, one exceedance in Limit Level was recorded according to the noise monitoring results in this reporting month.

9.2 Summary of Environmental Complaints

There was no complaint received in this reporting month.



9.3 Summary of Notification of Summons and Prosecution

There was no notification of summons respect to environmental issues registered in this reporting month.

10.0 IMPLEMENTATION STATUS

10.1 Implementation Status of Environmental Mitigation Measures

An updated summary of the Environmental Mitigation Implementation Schedule (EMIS) is presented in Appendix G. Most of the necessary mitigation measures were implemented properly. Any deficiencies were noted in the remarks of the schedule.

10.2 Implementation Status of Event and Action Plan

No exceedances of Action and Limit Level of water quality monitoring results were recorded during the reporting month.

Since no documented complaints on noise issue were received in this reporting month, no Action and Limit Level exceedances were recorded.

10.3 Implementation Status of Environmental Complaint, Notifications of Summons and Successful Prosecutions Handling

No complaints, notifications of summons and successful prosecutions were received in this reporting month. A summary of environmental complaints, notifications of summons and successful prosecutions was given in Table 10.1.

Table 10.1 Summary of Environmental Complaints and Prosecutions

<i>Complaints logged</i>		<i>Summons served</i>		<i>Successful prosecution received</i>	
<i>April 2011</i>	<i>Cumulative</i>	<i>April 2011</i>	<i>Cumulative</i>	<i>April 2011</i>	<i>Cumulative</i>
0	0	0	0	0	0

11.0 CONCLUSIONS AND RECOMMENDATIONS

Conclusions

Impact monitoring of noise and water quality were carried out at designated locations in accordance with the EM&A Manual in this reporting month.

No exceedances of Action and Limit Level of water quality monitoring results were recorded during the reporting month.

Since no documented complaints on noise issue were received in this reporting month, no Action Level exceedances were recorded. Besides, no exceedances in Limit Level were recorded according to the noise monitoring results in this reporting month.

According to the ET weekly site inspections carried out in this reporting month, the Contractor generally implemented sufficient environmental mitigation measures.

No complaints, prosecutions or notifications of summons were received in this reporting month.

Recommendations

According to the environmental site inspections performed in the reporting month, the following recommendations were provided:



Air Quality

- Ensure the frequency of water spraying on unloading areas and stockpiles to be sufficient to suppress the dust sources;
- Provide proper maintenance for the powered mechanical equipment and barges to avoid emission of dark smoke; and
- Implement the dust mitigation measures for the site activities.

Noise

- Conduct noisy activities at a farther location from the NSRs.

Water Quality

- Maintain the drainage system regularly;
- Operate and maintain the silt curtains and silt screen regularly;
- Operate the cleaning vessel regularly;
- Provide proper treatment for the wastewater discharge;
- Clean up the fill material on the barge frequently; and
- Remove the stagnant water or provide approved pesticides for the stagnant water, if any.

Chemical and Waste Management

- Remove waste materials from the site to avoid accumulation regularly;
- Handle and store chemical wastes properly;
- Remove unwanted material in the existing stockpiles and avoid further dumping of such material;
- Provide and maintain sufficient drip trays for diesel drums, chemical containers, chemical waste storage drums and diesel operated generator set;
- Maintain good housekeeping at the works area;
- Avoid soil being polluted during oil filling and equipment maintenance; hence, properly remove and store the contaminated soil, if any.

12.0 FUTURE KEY ISSUES

12.1 Work Programme for the Coming Month

As informed by the Contractor, the activities to be conducted by them in the next month included:

- *Move the coated pipe to Portion "I" for pipe pulling (Portion H1& H2);*
- *Drilling of pipe piles (Portion I);*
- *Laying pulling wire for pipe pulling (Portion I);*
- *Pipe pulling (Portion I);*
- *Laying pulling wire for pipe pulling (Portion J); and*
- *Pipe pulling (Portion J).*

12.2 Key Issues for the Coming Month

Key issues to be considered in the coming month include:

- *Noise and dust impact due to construction works;*
- *Use and maintain silt curtain and silt screen properly;*
- *Adequate environmental control measures shall be provided to prevent / avoid dropping of dredged materials into the sea during the transfer;*
- *Implement all necessary preventive measures to avoid oil leakage. In the event an oil leakage happens, the Contractor should properly remove the leaked oil and handle the contaminated soil and all materials using for this cleaning works as chemical waste; and*
- *Maintain good site practice to minimize environmental impacts at the site.*

Mitigation measures to be required in the coming month:

Air Quality Impact

- To ensure implementation of the dust mitigation measures for the site activities;
- To provide proper maintenance for vehicles and machines on site; and
- To investigate any other dust sources around the air sensitive receivers



Noise

- To switch off equipment if not in use;
- To operate silent equipment;
- To identify the noise sources inside and outside of the site; and
- To re-schedule the work activities in the event of valid noise exceedance.

Water Quality Impact

- To maintain the drainage system;
- To repair, inspect and maintain the silt curtains and site screen regularly;
- To provide covers for the drip trays to avoid stagnant water due to rainfall;
- To provide proper treatment for wastewater from the area;
- To deploy a cleaning vessel to remove floating rubbish;
- To avoid dredged materials on the barge from being washed into the sea; and
- To avoid any stagnant water or provide insecticide to avoid mosquito breeding.

Chemical and Waste Management

- To remove waste from the site regularly;
- To properly store and handle chemical wastes on site;
- To implement trip ticket system for all the imported public fill and general refuse disposal;
- To provide and manage sufficiently sized drip trays for diesel drums or chemical containers;
- To maintain proper housekeeping;
- To remove the oil stains in the event of leakage and handle all materials using for this cleaning works as chemical waste; and
- To identify C&D material by packaging, labeling, storage, transportation and disposal in accordance with statutory regulations.


12.3 Monitoring Schedule for the Coming Month

The proposed EM&A program of the coming month is attached in Appendix I.



Appendix A

Organization Chart and Lines of Communication



Project	Laying of Western Cross Harbour Main and Associated Land Mains From West Kowloon to Sai Ying Pun - Investigation
Title	Project Organization and Line of Communication
Date Dec 2009	

Figure 1.3a



東業德勤測試顧問有限公司
ETS-TESTCONSULT LIMITED

Appendix B1

Calibration Certificates for Impact Noise Monitoring Equipment



Calibration Certificate

Certificate No. 06467

Page 1 of 2 Pages

Customer : ETS-Testconsult Limited

Address : 8/F., Block B, Veristrong Industrial Centre, 34-36 Au Pui Wan St., Fotan, Hong Kong.

Order No. : Q02516

Date of receipt : 8-Nov-10

Item Tested

Description : Sound Level Calibrator (ET/EN/002/01)

Manufacturer : Rion

Model : NC-73

Serial No. : 10196943

Test Conditions

Date of Test : 12-Nov-10

Supply Voltage : --

Ambient Temperature : (23 ± 3)°C

Relative Humidity : (50 ± 25) %

Test Specifications

Calibration check.

Ref. Document/Procedure : F21, Z02.

Test Results

All results were within the manufacturer's specification.

The results are shown in the attached page(s).

Main Test equipment used:


<u>Equipment No.</u>	<u>Description</u>	<u>Cert. No.</u>	<u>Traceable to</u>
S014	Spectrum Analyzer	03926	NIM-PRC & SCL-HKSAR
S024	Sound Level Calibrator	04062	NIM-PRC & SCL-HKSAR
S041	Universal Counter	04461	SCL-HKSAR
S206	Sound Level Meter	04462	SCL-HKSAR

The values given in this Calibration Certificate only relate to the values measured at the time of the test and any uncertainties quoted will not include allowance for the equipment long term drift, variations with environmental changes, vibration and shock during transportation, overloading, mis-handling, or the capability of any other laboratory to repeat the measurement. Hong Kong Calibration Ltd. shall not be liable for any loss or damage resulting from the use of the equipment.

The test equipment used for calibration are traceable to International System of Units (SI).

The test results apply to the above Unit-Under-Test only

Calibrated by : 
P. F. Wong

Approved by : 
Dorothy Cheuk

Date: 15-Nov-10



Calibration Certificate

Certificate No. 06467

Page 2 of 2 Pages

Results :

1. Level Accuracy (at 1 kHz)

UUT Nominal Value	Measured Value		Mfr's Spec.
	Before Adjust.	After Adjust.	
94 dB	93.52 dB	93.82 dB	± 1 dB

Uncertainty : ± 0.1 dB

2. Frequency Accuracy

UUT Nominal Value	Measured Value	Mfr's Spec.
1 kHz	0.988 kHz	± 2 %

Uncertainty : ± 0.1 %

3. Level Stability : 0.0 dB

Uncertainty : ± 0.01 dB

4. Total Harmonic Distortion : < 0.3 %

Mfr's Spec. : < 3 %

Uncertainty : ± 2.3 % of reading

Remark : 1. UUT : Unit-Under-Test

2. The uncertainty claimed is for a confidence probability of not less than 95%.

3. Atmospheric Pressure : 1 006 hPa

----- END -----



Calibration Certificate

Certificate No. 05083

Page 1 of 3 Pages

Customer : ETS-Testconsult Limited

Address : 8/F., Block B, Veristrong Industrial Centre, 34-36 Au Pui Wan St., Fotan, Hong Kong.

Order No. : Q02020

Date of receipt : 8-Sep-10

Item Tested

Description : Precision Integrating Sound Level Meter (ET/EN/003/13)

Manufacturer : Rion

Model : NL-31

Serial No. : 00593620

Test Conditions

Date of Test : 14-Sep-10

Supply Voltage : --

Ambient Temperature : (23 ± 3)°C

Relative Humidity : (50 ± 25) %

Test Specifications

Calibration check.

Ref. Document/Procedure : Z01.

Test Results

All results were within the IEC 651 Type 1 & IEC 804 Type 1 specification.

The results are shown in the attached page(s).

Main Test equipment used:


<u>Equipment No.</u>	<u>Description</u>	<u>Cert. No.</u>	<u>Traceable to</u>
S017A	Multi-Function Generator	00804	SCL-HKSAR
S024	Sound Level Calibrator	04062	NIM-PRC & SCL-HKSAR

The values given in this Calibration Certificate only relate to the values measured at the time of the test and any uncertainties quoted will not include allowance for the equipment long term drift, variations with environmental changes, vibration and shock during transportation, overloading, mis-handling, or the capability of any other laboratory to repeat the measurement. Hong Kong Calibration Ltd. shall not be liable for any loss or damage resulting from the use of the equipment.

The test equipment used for calibration are traceable to International System of Units (SI).

The test results apply to the above Unit-Under-Test only

Calibrated by : 
P. F. Wong

Approved by : 
Dorothy Cheuk

Date: 14-Sep-10

This Certificate is issued by:
Hong Kong Calibration Ltd.
Unit 8B, 24/F., Well Fung Industrial Centre, No. 58-76, Ta Chuen Ping Street, Kwai Chung, NT, Hong Kong.
Tel: 2425 8801 Fax: 2425 8646

The copyright of this certificate is owned by Hong Kong Calibration Ltd.. It may not be reproduced except in full.



Calibration Certificate

Certificate No. **05083**

Page 2 of 3 Pages

Results :

1. SPL Accuracy

UUT Setting			Applied Value (dB)	UUT Reading (dB)
Level Range (dB)	Weight	Response		
20 – 100	L _A	Fast	94.0	93.7
		Slow		93.7
	L _C	Fast		93.7
		L _p		Fast
30 – 120	L _A	Fast	94.0	93.7
		Slow		93.7
	L _C	Fast		93.7
	L _p	Fast		93.7
30 – 120	L _A	Fast	114.0	113.5
		Slow		113.5
	L _C	Fast		113.5
	L _p	Fast		113.5

IEC 651 Type 1 Spec. : ± 0.7 dB

Uncertainty : ± 0.1 dB

2. Level Stability : 0.1 dB

IEC 651 Type 1 Spec. : ± 0.3 dB

Uncertainty : ± 0.1 dB

3. Linearity

3.1 Level Linearity

UUT Range (dB)	Applied Value (dB)	UUT Reading (dB)	Variation (dB)	IEC 651 Type 1 Spec. (Primary Indicator Range)
130	114.0	113.9	+0.2	± 0.7 dB
130	104.0	103.9	+0.2	
120	94.0	93.7(Ref.)	--	
110	84.0	83.6	-0.1	
100	74.0	73.7	0.0	
90	64.0	63.7	0.0	
80	54.0	53.7	0.0	

Uncertainty : ± 0.1 dB



Calibration Certificate

Certificate No. **05083**

Page 3 of 3 Pages

3.2 Differential level linearity

UUT Range (dB)	Applied Value (dB)	UUT Reading (dB)	Variation (dB)	IEC 651 Type 1 Spec.
120	84.0	83.6	-0.1	± 0.4 dB
	94.0	93.7 (Ref.)	--	
	95.0	94.7	0.0	± 0.2 dB

Uncertainty : ± 0.1 dB

4. Frequency Weighting

A weighting

Frequency	Attenuation (dB)	IEC 651 Type 1 Spec.
31.5 Hz	-40.2	- 39.4 dB, ± 1.5 dB
63 Hz	-26.8	- 26.2 dB, ± 1.5 dB
125 Hz	-16.7	- 16.1 dB, ± 1 dB
250 Hz	-9.2	- 8.6 dB, ± 1 dB
500 Hz	-3.6	- 3.2 dB, ± 1 dB
1 kHz	0.0 (Ref.)	0 dB, ± 1 dB
2 kHz	+1.5	+ 1.2 dB, ± 1 dB
4 kHz	+1.5	+ 1.0 dB, ± 1 dB
8 kHz	-0.6	- 1.1 dB, + 1.5 dB ~ - 3 dB
16 kHz	-0.6	- 6.6 dB, + 3 dB ~ ∞

Uncertainty : ± 0.1 dB

5. Time Averaging

Applied Burst duty Factor	Applied Leq Value (dB)	UUT Reading (dB)	IEC 804 Type 1 Spec.
continuous	40.0	40.0	--
1/10	40.0	40.0	± 0.5 dB
1/10 ²	40.0	40.1	
1/10 ³	40.0	40.2	± 1.0 dB
1/10 ⁴	40.0	40.2	

Uncertainty : ± 0.1 dB

Remark : 1. UUT : Unit-Under-Test

2. The uncertainty claimed is for a confidence probability of not less than 95%.

3. Atmospheric Pressure : 1 004 hPa.

4. The internal calibration reference of UUT was drifted from 94.0 dB to 94.5 dB

----- END -----



Calibration Certificate

Certificate No. **02909A**

Page **1** of **4** Pages

Customer : ETS-Testconsult Limited

Address : 8/F., Block B, Veristrong Industrial Centre, 34-36 Au Pui Wan St., Fotan, Hong Kong.

Order No. : Q01152

Date of receipt : 31-May-10

Item Tested

Description : Precision Integrating Sound Level Meter (ET/ EN/ 003/ 10)

Manufacturer : Rion

Model : NL-31

Serial No. : 00531142

Test Conditions

Date of Test : 9-Jun-10

Supply Voltage : --

Ambient Temperature : (23 ± 3)°C

Relative Humidity : (50 ± 25) %

Test Specifications

Calibration check.

Ref. Document/Procedure : Z01.

Test Results

All results were within the IEC 651 Type 1 & IEC 804 Type 1 specification.

The results are shown in the attached page(s).


Main Test equipment used:


<u>Equipment No.</u>	<u>Description</u>	<u>Cert. No.</u>	<u>Due Date</u>	<u>Traceable to</u>
S017	Multi-Function Generator	C101623	25-Mar-11	SCL-HKSAR
S024	Sound Level Calibrator	93758	16-Jul-10	NIM-PRC & SCL-HKSAR

The values given in this Calibration Certificate only relate to the values measured at the time of the test and any uncertainties quoted will not include allowance for the equipment long term drift, variations with environmental changes, vibration and shock during transportation, overloading, mis-handling, or the capability of any other laboratory to repeat the measurement. Hong Kong Calibration Ltd. shall not be liable for any loss or damage resulting from the use of the equipment.

The test equipment used for calibration are traceable to International System of Units (SI).

The test results apply to the above Unit-Under-Test only

Calibrated by : 
Dorothy Cheuk

Approved by : 
Alan Chu

Date: 15-Jun-10

This Certificate is issued by:
Hong Kong Calibration Ltd.
Unit 8B, 24/F., Well Fung Industrial Centre, No. 58-76, Ta Chuen Ping Street, Kwai Chung, NT, Hong Kong.
Tel: 2425 8801 Fax: 2425 8846

The copyright of this certificate is owned by Hong Kong Calibration Ltd.. It may not be reproduced except in full.



Calibration Certificate

Certificate No. 02909A

Page 2 of 4 Pages

Results :

1. SPL Accuracy

UUT Setting			Applied Value (dB)	UUT Reading (dB)
Level Range (dB)	Weight	Response		
20 - 100	L _A	Fast	94.03	93.7
		Slow		93.7
	L _C L _p	Fast		93.7
		Fast		93.7
30 - 120	L _A	Fast	94.03	93.7
		Slow		93.6
	L _C L _p	Fast		93.7
		Fast		93.7
30 - 120	L _A	Fast	113.97	113.6
		Slow		113.6
	L _C L _p	Fast		113.6
		Fast		113.6

IEC Type 1 Spec. : ± 0.7 dB

Uncertainty : ± 0.1 dB

2. Level Stability : 0.0 dB

IEC 651 Type 1 Spec. : ± 0.3 dB

Uncertainty : ± 0.1 dB



Calibration Certificate

Certificate No. 02909A

Page 3 of 4 Pages

3. Linearity

3.1 Level Linearity

UUT Range (dB)	Applied Value (dB)	UUT Reading (dB)	Variation (dB)	IEC 651 Type 1 Spec. (Primary Indicator Range)
130	114.0	113.9	+0.2	± 0.7 dB
130	104.0	103.9	+0.2	
120	94.0	93.7 (Ref.)	--	
110	84.0	84.1	+0.4	
100	74.0	73.7	0.0	
90	64.0	63.7	0.0	
80	54.0	53.7	0.0	

Uncertainty : ± 0.1 dB

3.2 Differential level linearity

UUT Range (dB)	Applied Value (dB)	UUT Reading (dB)	Variation (dB)	IEC 651 Type 1 Spec.
120	84.0	83.5	-0.2	± 0.4 dB
	94.0	93.7 (Ref.)	--	
	95.0	94.7	0.0	± 0.2 dB
	104.0	103.8	+0.1	± 0.3 dB
	105.0	104.8	0.0	± 1.0 dB

Uncertainty : ± 0.1 dB

4. Frequency Weighting

A weighting

Frequency	Attenuation (dB)	IEC 651 Type 1 Spec.
31.5 Hz	-40.2	- 39.4 dB, ± 1.5 dB
63 Hz	-26.7	- 26.2 dB, ± 1.5 dB
125 Hz	-16.7	- 16.1 dB, ± 1 dB
250 Hz	-9.1	- 8.6 dB, ± 1 dB
500 Hz	-3.6	- 3.2 dB, ± 1 dB
1 kHz	0.0 (Ref.)	0 dB, ± 1 dB
2 kHz	+1.6	+ 1.2 dB, ± 1 dB
4 kHz	+1.6	+ 1.0 dB, ± 1 dB
8 kHz	-0.5	- 1.1 dB, + 1.5 dB ~ - 3 dB
16 kHz	-6.0	- 6.6 dB, + 3 dB ~ ∞

Uncertainty : ± 0.1 dB



Calibration Certificate

Certificate No. 02909A

Page 4 of 4 Pages

4. Time Averaging

Applied Burst duty Factor	Applied Leq Value (dB)	UUT Reading (dB)	IEC 804 Type 1 Spec.
continuous	40.0	40.0	--
1/10	40.0	39.9	± 0.5 dB
1/10 ²	40.0	40.0	
1/10 ³	40.0	40.0	± 1.0 dB
1/10 ⁴	40.0	39.9	

Uncertainty : ± 0.1 dB

Remark : 1. UUT : Unit-Under-Test

2. The uncertainty claimed is for a confidence probability of not less than 95%.
3. Atmospheric Pressure : 1 002 hPa.
4. This certificate is to supersede our former certificate no. 02909.

----- END -----



Calibration Certificate

Certificate No. **06466**

Page **1** of **2** Pages

Customer : ETS-Testconsult Limited

Address : 8/F., Block B, Veristrong Industrial Centre, 34-36 Au Pui Wan St., Fotan, Hong Kong.

Order No. : Q02516

Date of receipt : 8-Nov-10

Item Tested

Description : Anemometer (EN/001/04)

Manufacturer : AZ Instrument

Model : AZ 8908

Serial No. : 9101231

Test Conditions

Date of Test : 10-Nov-10

Supply Voltage : -

Ambient Temperature : (23 ± 3)°C

Relative Humidity : (50 ± 25) %

Test Specifications

Calibration check.

Ref. Document/Procedure: T03, Z04.

Test Results

All results were within the manufacturer's specification.

The results are shown in the attached page(s).

Main Test equipment used:

<u>Equipment No.</u>	<u>Description</u>	<u>Cert. No.</u>	<u>Traceable to</u>
S223	Std. Thermometer	01631	NIM-PRC
S155	Std. Anemometer	NSC20104025	NIM-PRC

The values given in this Calibration Certificate only relate to the values measured at the time of the test and any uncertainties quoted will not include allowance for the equipment long term drift, variations with environmental changes, vibration and shock during transportation, overloading, mis-handling, or the capability of any other laboratory to repeat the measurement. Hong Kong Calibration Ltd. shall not be liable for any loss or damage resulting from the use of the equipment.

The test equipment used for calibration are traceable to International System of Units (SI).

The test results apply to the above Unit-Under-Test only

Calibrated by : 

S. K. Tang

Approved by : 

Alan Chu

Date: 10-Nov-10

This Certificate is issued by:

Hong Kong Calibration Ltd.

Unit 8B, 24/F., Well Fung Industrial Centre, No. 58-76, Ta Chuen Ping Street, Kwai Chung, NT, Hong Kong.

Tel: 2425 8801 Fax: 2425 8648

The copyright of this certificate is owned by Hong Kong Calibration Ltd.. It may not be reproduced except in full.



Calibration Certificate

Certificate No. 06466

Page 2 of 2 Pages

Results :

1. Velocity

Applied Value (m/s)	UUT Reading (m/s)	Mfr's Spec.
2.50	2.5	± 3 % f.s. (f.s. = 35 m/s)
5.00	4.9	
10.00	9.5	
15.00	14.3	
20.00	19.1	

2. Temperature

Applied Value (°C)	UUT Reading (°C)	Mfr's Spec.
3.10	3.0	± 1 °C
23.98	24.0	
48.20	47.8	

Remark : 1. UUT: Unit-Under-Test

2. Uncertainty : ± 1.3 % or ± 0.05 m/s, whichever is greater for Velocity, ± 0.25 °C for Temperature, for a confidence probability of not less than 95%.

3. Atmospheric Pressure : 1 011 hPa

----- END -----



Appendix B2

Impact Noise Monitoring Results



Day-time Noise Monitoring

Monitoring Station: KS6 (Podium at the Culliman)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (30min)	L10	L90	
01/04/11	Sunny	16:15	16:45	68.5	71.3	64.4	0.3
06/04/11	Cloudy	17:35	18:05	66.3	67.5	63.6	0.6
15/04/11	Fine	09:50	10:20	63.9	65.2	62.3	0.2
20/04/11	Sunny	15:40	16:10	66.4	68.3	62.3	0.8
29/04/11	Drizzle	11:30	12:00	67.1	68.8	64.3	1.2

Monitoring Station: CGa (Pavement in front of Connaught Garden)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (30min)	L10	L90	
01/04/11	Sunny	13:30	14:00	74.7	76.8	69.2	0.2
04/04/11	Cloudy	15:25	15:55	74.6	76.5	68.5	0.1
11/04/11	Sunny	13:35	14:05	74.0	77.1	66.2	0.1
18/04/11	Fine	11:35	12:05	74.2	77.0	66.7	0.1
27/04/11	Sunny	10:25	10:55	72.3	75.1	67.0	0.2

Monitoring Station: RWM (Roof at Richwealth Mansion)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (30min)	L10	L90	
01/04/11	Sunny	14:05	14:35	64.2	65.6	62.0	0.4
04/04/11	Cloudy	14:50	15:20	63.8	65.5	59.8	0.1
11/04/11	Sunny	13:00	13:30	63.4	64.8	59.2	0.1
18/04/11	Fine	11:00	11:30	62.4	64.8	60.1	0.2
27/04/11	Sunny	11:00	11:30	62.8	65.1	60.5	0.3

Monitoring Station: KY3 (Roof at Kwan Yik Building Phase 3)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (30min)	L10	L90	
01/04/11	Sunny	14:40	15:10	62.4	63.8	60.3	0.4
04/04/11	Cloudy	14:15	14:45	61.9	63.2	59.2	0.3
11/04/11	Sunny	11:20	11:50	62.3	64.0	58.7	0.2
18/04/11	Fine	10:25	10:55	59.6	61.9	56.3	0.2
27/04/11	Sunny	11:35	12:05	60.3	62.6	57.3	0.3



Holiday-time Noise Monitoring

Monitoring Station: KS6 (Podium at the Culliman)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (5min)	L10	L90	
03/04/11	Sunny	11:50	11:55	63.4	64.5	60.7	0.3
03/04/11	Sunny	11:55	12:00	63.1	64.2	60.4	0.3
03/04/11	Sunny	12:00	12:02	63.6	64.8	60.8	0.3
10/04/11	Cloudy	08:50	08:55	62.9	65.2	58.8	1.2
10/04/11	Cloudy	08:55	09:00	59.8	61.5	58.1	1.1
10/04/11	Cloudy	09:00	09:05	60.1	61.5	58.4	1.3
17/04/11	Cloudy	14:15	14:20	61.5	62.4	59.1	0.3
17/04/11	Cloudy	14:20	14:25	60.2	61.4	58.8	0.3
17/04/11	Cloudy	14:25	14:30	60.1	61.2	58.5	0.3

Monitoring Station: CGa (Pavement in front of Connaught Garden)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (5min)	L10	L90	
03/04/11	Sunny	10:20	10:25	69.8	73.7	63.3	0.2
03/04/11	Sunny	10:25	10:30	69.4	73.2	62.7	0.2
03/04/11	Sunny	10:30	10:35	69.7	73.4	63.0	0.2
10/04/11	Cloudy	10:00	10:05	67.7	69.8	63.2	0.7
10/04/11	Cloudy	10:05	10:10	68.2	70.1	63.9	0.8
10/04/11	Cloudy	10:10	10:15	67.8	69.9	63.5	0.7
17/04/11	Cloudy	16:30	16:35	69.8	73.1	65.8	0.1
17/04/11	Cloudy	16:35	16:40	69.6	73.0	65.2	0.1
17/04/11	Cloudy	16:40	16:45	69.9	73.6	65.4	0.1

Monitoring Station: RWM (Roof at Richwealth Mansion)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (5min)	L10	L90	
03/04/11	Sunny	10:40	10:45	62.1	63.8	60.2	0.3
03/04/11	Sunny	10:45	10:50	62.4	63.9	60.6	0.3
03/04/11	Sunny	10:50	10:55	61.9	63.3	59.8	0.3
10/04/11	Cloudy	10:20	10:25	60.2	61.7	56.4	1.0
10/04/11	Cloudy	10:25	10:30	59.9	61.4	56.0	1.2
10/04/11	Cloudy	10:30	10:35	60.5	61.5	56.6	1.1
17/04/11	Cloudy	16:10	16:15	63.3	64.7	59.4	0.1
17/04/11	Cloudy	16:15	16:20	63.6	65.0	59.6	0.1
17/04/11	Cloudy	16:20	16:25	63.1	64.8	59.3	0.1

Monitoring Station: KY3 (Roof at Kwan Yik Building Phase 3)

Date	Weather Condition	Start Time (hh:mm)	End Time (hh:mm)	Noise Level at the monitoring point, dB (A)			Wind Speed (m/s)
				Leq (5min)	L10	L90	
03/04/11	Sunny	11:00	11:05	60.5	61.8	58.4	0.3
03/04/11	Sunny	11:05	11:10	60.2	61.5	58.1	0.3
03/04/11	Sunny	11:10	11:15	59.9	61.1	58.0	0.3
10/04/11	Cloudy	10:40	10:45	61.0	62.1	57.4	1.3
10/04/11	Cloudy	10:45	10:50	60.8	61.8	56.9	1.2
10/04/11	Cloudy	10:50	10:55	60.9	62.0	57.1	1.4
17/04/11	Cloudy	15:50	15:55	61.1	62.2	58.7	0.2
17/04/11	Cloudy	15:55	16:00	60.8	61.9	58.3	0.2
17/04/11	Cloudy	16:00	16:05	60.2	61.0	58.1	0.2




Appendix B3

Graphical Plots of Impact Noise Monitoring Data




Noise Monitoring (Day-time)


Noise level at KS6 - Podium at the Culliman




Noise level at CGa - Pavement in front of Connaught Garden



Noise level at RWM - Roof of Richwealth Mansion




Noise level at KY3 - Roof of Kwan Yik Building Phase 3






Noise Monitoring (Evening-time)


Noise level at KS6 - Podium at the Culliman




Noise level at CGa - Pavement in front of Connaught Garden



Noise level at RWM - Roof of Richwealth Mansion




Noise level at KY3 - Roof of Kwan Yik Building Phase 3






Noise Monitoring (Night-time)


Noise level at KS6 - Podium at the Cullinan




Noise level at CGa - Pavement in front of Connaught Garden



Noise level at RWM - Roof of Richwealth Mansion




Noise level at KY3 - Roof of Kwan Yik Building Phase 3






Noise Monitoring (Holiday-time)


Noise level at KS6 - Podium at the Culliman




Noise level at CGa - Pavement in front of Connaught Garden



Noise level at RWM - Roof of Richwealth Mansion



Noise level at KY3 - Roof of Kwan Yik Building Phase 3





東業德勤測試顧問有限公司
ETS-TESTCONSULT LIMITED

Appendix C1

Calibration Certificates for Impact Water Quality Monitoring Equipments



Performance Check of Turbidimeter



Equipment Ref. No. : ET105051007 Manufacturer : HAACH
Model No. : 2100P Serial No. : 0806 000 30281
Date of Calibration : 15/1/11 Due Date : 14/4/11

Gelex Vial Std	Theoretical Value (NTU)	Measured Value (NTU)	Difference %
0-10 NTU	5.34	5.40	1.12%
10-100 NTU	52.5	52.8	0.57%
100-1000 NTU	543	531	2.21%

Acceptance Criteria

Difference : <5 %

The salinity meter complies * / ~~does not comply~~ * with the specified requirements and is deemed acceptable * / ~~unacceptable~~ * for use. Measurements are traceable to national standards.

Checked by :  Approved by : 



Performance Check of Salinity Meter

Equipment Ref. No. : ET/EW/008/002 Manufacturer : YSI
Model No. : 85 Serial No. : 060 1998 AD
Date of Calibration : 22/2/11 Due Date : 21/2/11

Ref. No. of Salinity Standard used (30ppt)


7410


Salinity Standard (ppt)	Measured Salinity (ppt)	Difference %
30	30.2	0.67%

Acceptance Criteria

Difference : <10 %

The salinity meter complies * / ~~does not comply~~ * with the specified requirements and is deemed acceptable * / ~~unacceptable~~ * for use. Measurements are traceable to national standards.

Checked by : 

Approved by : 



Internal Calibration Report of Dissolved Oxygen Meter

Equipment Ref. No. : ET1EW10081002 Manufacturer : YSI
 Model No. : 85 Serial No. : 0601998AD
 Date of Calibration : 22/2/11 Calibration Due Date : 2/1/5/11

Temperature Verification

Ref. No. of Reference Thermometer : ET105211001
 Ref. No. of Water Bath : ET103331001

		Temperature (°C)		
Reference Thermometer reading	Measured	20.0	Corrected	20.1
DO Meter reading	Measured	20.4	Difference	0.3

Standardization of sodium thiosulphate (Na₂S₂O₃) solution

Reagent No. of Na₂S₂O₃ titrant : J418 Reagent No. of 0.025N K₂Cr₂O₇ : J419

	Trial 1	Trial 2
Initial Vol. of Na ₂ S ₂ O ₃ (ml)	0	0
Final Vol. of Na ₂ S ₂ O ₃ (ml)	40.1	40.2
Vol. of Na ₂ S ₂ O ₃ used (ml)	40.1	40.2
Normality of Na ₂ S ₂ O ₃ solution (N)	0.02494	0.02488
Average Normality (N) of Na ₂ S ₂ O ₃ solution (N)	0.02491	
Acceptance criteria, Deviation	Less than ± 0.001N	

Calculation: Normality of Na₂S₂O₃, N = 1 / ml Na₂S₂O₃ used

Linearity Checking

Determination of dissolved oxygen content by Winkler Titration *

Purging Time (min)	2		5		10	
Trial	1	2	1	2	1	2
Initial Vol. of Na ₂ S ₂ O ₃ (ml)	0	11.75	0	9.80	0	6.55
Final Vol. of Na ₂ S ₂ O ₃ (ml)	11.75	23.55	9.80	19.50	6.55	13.05
Vol. (V) of Na ₂ S ₂ O ₃ used (ml)	11.75	11.80	9.80	9.70	6.55	6.50
Dissolved Oxygen (DO), mg/L	7.86	7.87	6.55	6.47	4.38	4.35
Acceptance criteria, Deviation	Less than + 0.3mg/L		Less than + 0.3mg/L		Less than + 0.3mg/L	

Calculation: DO (mg/L) = V x N x 8000/298

Purging time, min	DO meter reading, mg/L			Winkler Titration result *, mg/L			Difference (%) of DO Content
	1	2	Average	1	2	Average	
2	7.98	7.98	7.98	7.86	7.87	7.87	1.39
5	6.60	6.44	6.52	6.55	6.47	6.51	0.15
10	4.48	4.40	4.44	4.38	4.35	4.37	1.55
Linear regression coefficient				0.9993			



Internal Calibration Report of Dissolved Oxygen Meter

Zero Point Checking

DO meter reading, mg/L	0.00
------------------------	------

Salinity Checking

Reagent No. of NaCl (10ppt)	J417	Reagent No. of NaCl (30ppt)	J416
-----------------------------	------	-----------------------------	------

Determination of dissolved oxygen content by Winkler Titration **

Salinity (ppt)	10		30	
	1	2	1	2
Initial Vol. of Na ₂ S ₂ O ₃ (ml)	0	11.60	0	11.05
Final Vol. of Na ₂ S ₂ O ₃ (ml)	11.60	23.20	11.05	22.05
Vol. (V) of Na ₂ S ₂ O ₃ used (ml)	11.60	11.60	11.05	11.00
Dissolved Oxygen (DO), mg/L	7.74	7.74	7.39	7.36
Acceptance criteria, Deviation	Less than + 0.3mg/L		Less than + 0.3mg/L	

Calculation: $DO (mg/L) = V \times N \times 8000/298$

Salinity (ppt)	DO meter reading, mg/L			Winkler Titration result**, mg/L			Difference (%) of DO Content
	1	2	Average	1	2	Average	
10	7.83	7.77	7.80	7.74	7.74	7.74	0.77
30	7.30	7.28	7.29	7.39	7.36	7.38	1.23

Acceptance Criteria

- (1) Difference between temperature readings from temperature sensor of DO probe and reference thermometer : < 0.5 °C
- (2) Linear regression coefficient : >0.99
- (3) Zero checking: 0.0mg/L
- (4) Difference (%) of DO content from the meter reading and by winkler titration : within ± 5%

The equipment complies # / does not comply # with the specified requirements and is deemed acceptable # / unacceptable # for use.

Delete as appropriate

Calibrated by : _____

Approved by : _____



Appendix C2

Impact Water Quality Monitoring Results

Mid-Flood Tide

Monitoring Station : C2

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)		Suspended Solids (mg/L)					
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average		
02/04/11	1848-1901	27/Sunny	Surface	1.0	18.8	30.6	30.6	6.11	6.14	83.7	84.1	5.15	5.17	5.29	7.7	7.9	8.2		
						30.5		6.16		84.4		5.19			8.0				
						31.5		6.03		83.2		5.32			8.5				
			Middle	8.2	19.6	31.5	31.5	6.00	6.02	82.8	83.0	5.28	5.30		5.30	5.30		8.2	8.4
						32.3		5.91		81.6		5.39			8.6				
						32.3		5.87		81.0		5.43			8.4				
			Bottom	15.4	20.4	30.8	30.8	6.26	6.28	88.8	89.1	5.08	5.11		5.08	5.11		8.2	8.3
						30.7		6.30		89.4		5.13			8.3				
						31.5		6.21		88.1		5.25			8.1				
07/04/11	2209-2220	29/Fine	Surface	1.0	19.2	30.8	30.8	6.26	6.28	88.8	89.1	5.08	5.11	5.24	8.2	8.3	8.2		
						30.7		6.30		89.4		5.13			8.3				
						31.5		6.21		88.1		5.25			8.1				
			Middle	8.4	18.8	31.5	31.5	6.18	6.20	87.7	87.9	5.20	5.23		5.23	5.23		8.0	8.1
						31.9		6.03		85.6		5.37			8.4				
						31.9		5.97		84.7		5.42			8.2				
			Bottom	15.8	18.2	31.9	31.9	6.03	6.00	85.6	85.2	5.37	5.40		5.40	5.40		8.4	8.3
						32.0		5.73		80.2		5.44			8.7				
						32.0		5.78		80.9		5.48			9.0				
09/04/11	1110-1123	22/Fine	Surface	1.0	20.8	31.2	31.2	5.99	5.98	83.9	83.7	5.23	5.24	5.36	8.0	8.1	8.5		
						31.1		5.96		83.4		5.25			8.2				
						31.8		5.79		81.1		5.37			8.6				
			Middle	8.1	20.4	31.9	31.9	5.82	5.81	81.5	81.3	5.39	5.38		5.38	5.38		8.4	8.5
						32.1		5.73		80.2		5.44			8.7				
						32.0		5.78		80.9		5.48			9.0				
			Bottom	15.2	19.5	32.1	32.1	5.73	5.78	80.2	80.6	5.44	5.46		5.46	5.46		8.9	8.9
						32.0		5.78		80.9		5.48			9.0				
						32.0		5.78		80.9		5.48			9.0				
12/04/11	1356-1408	25/Cloudy	Surface	1.0	18.6	30.6	30.6	6.13	6.14	87.0	87.2	5.21	5.18	5.28	8.2	8.1	8.5		
						30.6		6.15		87.3		5.14			8.0				
						31.3		6.05		85.9		5.26			8.4				
			Middle	8.3	18.9	31.2	31.3	6.07	6.06	86.2	86.1	5.30	5.28		5.28	5.28		8.3	8.4
						31.7		5.98		84.3		5.38			8.8				
						31.7		5.95		83.9		5.41			9.0				
			Bottom	15.6	19.2	31.7	31.7	5.95	5.97	83.9	84.1	5.41	5.40		5.40	5.40		8.9	8.9
						30.4		6.16		86.2		5.11			8.0				
						30.5		6.21		86.9		5.16			7.8				
14/04/11	1754-1807	29/Sunny	Surface	1.0	19.8	30.4	30.5	6.16	6.19	86.2	86.6	5.11	5.14	5.25	8.0	7.9	8.4		
						30.5		6.21		86.9		5.16			7.8				
						31.2		6.02		84.3		5.23			8.5				
			Middle	8.2	19.4	31.2	31.2	6.06	6.04	84.8	84.6	5.27	5.25		5.25	5.25		8.5	8.5
						32.0		5.86		82.0		5.35			8.7				
						31.9		5.89		82.5		5.38			8.6				
			Bottom	15.4	18.7	31.9	32.0	5.89	5.88	82.5	82.3	5.38	5.37		5.37	5.37		8.7	8.7
						30.7		6.19		87.2		4.90			7.5				
						30.8		6.24		87.9		4.96			8.0				
16/04/11	1805-1820	27/Cloudy	Surface	1.0	21.0	30.7	30.8	6.19	6.22	87.2	87.6	4.90	4.93	5.13	7.5	7.8	8.1		
						30.8		6.24		87.9		4.96			8.0				
						31.5		6.10		86.0		5.12			8.1				
			Middle	8.4	20.3	31.4	31.5	6.13	6.12	86.4	86.2	5.17	5.15		5.15	5.15		8.0	8.1
						32.0		5.97		84.1		5.30			8.5				
						32.0		5.93		83.6		5.35			8.5				
			Bottom	15.8	19.7	32.0	32.0	5.93	5.95	83.6	83.9	5.35	5.33		5.33	5.33		8.5	8.5
						30.8		5.99		80.9		5.07			7.7				
						30.9		5.91		79.8		5.11			7.8				
19/04/11	2027-2040	26/Fine	Surface	1.0	20.9	30.8	30.9	5.99	5.95	80.9	80.4	5.07	5.09	5.24	7.7	7.8	8.1		
						30.9		5.91		79.8		5.11			7.8				
						31.8		5.84		78.8		5.29			7.9				
			Middle	8.2	19.9	31.9	31.9	5.86	5.85	79.1	79.0	5.20	5.25		5.25	5.25		8.2	8.1
						32.2		5.72		77.2		5.37			8.6				
						32.1		5.75		77.6		5.42			8.3				
			Bottom	15.4	19.3	32.1	32.2	5.75	5.74	77.2	77.4	5.37	5.40		5.40	5.40		8.5	8.5
						32.0		5.70		76.9		5.41			8.5				
						32.0		5.70		76.9		5.41			8.5				
21/04/11	1054-1105	24/Fine	Surface	1.0	22.1	31.0	31.1	6.12	6.11	82.6	82.5	5.02	5.02	5.24	8.0	8.0	8.4		
						31.1		6.10		82.4		5.01			8.0				
						31.6		5.92		79.9		5.29			8.4				
			Middle	8.1	20.5	31.7	31.7	5.89	5.91	79.5	79.7	5.32	5.31		5.31	5.31		8.5	8.5
						32.0		5.72		77.2		5.39			8.7				
						32.0		5.70		76.9		5.41			8.5				
			Bottom	15.2	20.0	32.0	32.0	5.72	5.71	77.2	77.1	5.39	5.40		5.40	5.40		8.6	8.6
						30.7		6.17		87.0		5.19			8.2				
						30.7		6.19		87.3		5.15			8.4				
26/04/11	1340-1352	26/Sunny	Surface	1.0	21.2	30.7	30.7	6.17	6.18	87.0	87.2	5.19	5.17	5.27	8.2	8.3	8.5		
						30.7		6.19		87.3		5.15			8.4				
						31.3		6.05		85.3		5.28			8.5				
			Middle	8.2	20.8	31.5	31.4	6.09	6.07	85.9	85.6	5.23	5.26		5.26	5.26		8.2	8.4
						31.8		5.96		84.0		5.42			8.7				
						31.7		5.93		83.6		5.36			8.9				
			Bottom	15.4	20.5	31.8	31.8	5.96	5.95	84.0	83.8	5.42	5.39		5.39	5.39		8.8	8.8
						30.7		6.22		87.1		4.99			7.6				
						30.7		6.22		87.1		4.99			7.6				
28/04/11	1723-1737	27/Rainy	Surface	1.0	23.4	30.8	30.8	6.20	6.18	88.0	87.8	5.07	5.09	5.21	7.8	7.9	8.3		
						30.7		6.16		87.5		5.11			8.0				
						31.4		6.08		86.3		5.24			8.4				
			Middle	8.2	22.9	31.3	31.4	6.05	6.07	85.9	86.1	5.20	5.22		5.22	5.22		8.6	8.5
						32.0		5.90		83.2		5.31			8.5				
						32.0		5.94		83.8		5.35			8.2				
			Bottom	15.4	22.7	32.0	32.0	5.94	5.92	83.2	83.5	5.31	5.33		5.33	5.33		8.4	8.4
						30.6		6.19		86.7		4.93			7.5				
						30.7		6.22		87.1		4.99			7.6				
30/04/11	1812-1823	26/Cloudy	Surface	1.0	21.8	30.6	30.7	6.19	6.21	86.7	86.9	4.93	4.96	5.07	7.5	7.6	8.0		
						30.7		6.22		87.1		4.99			7.6				
						31.4		6.10		85.4		5.17			8.3				
			Middle	8.2	21.5	31.5	31.5	6.08	6.09	85.1	85.3	5.13	5.15		5.15	5.15		8.0	8.2
						31.9		5.99		83.9		5.06			8.1				
						31.9		5.97		83.6		5.13			8.2				
			Bottom	15.4	21.2	31.9	31.9	5.97	5.98	83.6	83.8	5.13	5.10		5.10	5.10		8.2	8.2

Mid-Flood Tide



Monitoring Station : C4

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/04/11	1826-1839	27/Sunny	Surface	1.0	18.9	30.7	30.7	6.20	6.19	85.6	85.4	5.13	5.15	5.27	8.1	8.1	8.3
						30.7		6.17		85.1		5.16			8.0		
			Middle	8.3	19.6	31.5	31.5	6.10	6.09	84.2	84.1	5.29	5.27		8.2	8.2	
						31.4		6.08		83.9		5.25			8.2		
			Bottom	15.6	20.4	32.4	32.4	5.95	5.97	82.1	82.3	5.37	5.39		8.7	8.6	
						32.3		5.98		82.5		5.40			8.5		
07/04/11	2151-2205	21/Fine	Surface	1.0	19.2	30.8	30.8	6.22	6.25	88.2	88.6	5.12	5.14	5.26	8.2	8.3	8.5
						30.8		6.27		89.0		5.16			8.3		
			Middle	8.3	18.7	31.5	31.5	6.19	6.17	87.8	87.5	5.23	5.26		8.5	8.4	
						31.5		6.14		87.1		5.28			8.3		
			Bottom	15.6	18.2	31.9	31.9	6.00	6.02	85.2	85.5	5.36	5.38		8.9	8.9	
						31.9		6.04		85.7		5.40			8.8		
09/04/11	1050-1103	22/Fine	Surface	1.0	20.8	31.1	31.2	5.94	5.94	83.2	83.1	5.12	5.14	5.26	8.2	8.1	8.4
						31.2		5.93		83.0		5.16			8.0		
			Middle	8.4	20.5	31.7	31.7	5.84	5.83	81.8	81.6	5.26	5.24		8.5	8.4	
						31.6		5.81		81.3		5.22			8.3		
			Bottom	15.8	19.4	32.0	32.1	5.78	5.74	80.6	80.3	5.39	5.41		8.6	8.6	
						32.1		5.71		79.9		5.42			8.5		
12/04/11	1338-1349	25/Cloudy	Surface	1.0	18.6	30.6	30.7	6.17	6.16	87.6	87.4	5.19	5.22	5.31	8.2	8.1	8.6
						30.7		6.14		87.2		5.24			8.0		
			Middle	8.2	18.9	31.2	31.3	6.08	6.07	86.3	86.1	5.27	5.30		8.5	8.4	
						31.3		6.05		85.9		5.33			8.3		
			Bottom	15.4	19.2	31.6	31.6	5.96	5.97	84.0	84.2	5.43	5.41		9.2	9.3	
						31.6		5.98		84.3		5.39			9.3		
14/04/11	1731-1744	29/Sunny	Surface	1.0	19.9	30.4	30.5	6.18	6.20	86.5	86.7	5.12	5.14	5.26	8.1	8.1	8.5
						30.5		6.21		86.9		5.15			8.1		
			Middle	8.1	19.4	31.2	31.1	6.05	6.07	84.7	85.0	5.27	5.26		8.4	8.3	
						31.0		6.09		85.3		5.25			8.2		
			Bottom	15.2	18.7	31.9	32.0	5.95	5.94	83.3	83.1	5.36	5.38		8.9	9.0	
						32.0		5.92		82.9		5.40			9.0		
16/04/11	1744-1800	27/Cloudy	Surface	1.0	21.0	30.7	30.7	6.21	6.23	87.5	87.8	4.97	4.99	5.14	7.8	7.9	8.2
						30.7		6.25		88.1		5.01			8.0		
			Middle	8.4	20.3	31.4	31.4	6.11	6.10	86.1	85.9	5.10	5.12		8.3	8.2	
						31.4		6.08		85.7		5.14			8.1		
			Bottom	15.8	19.8	31.9	32.0	5.91	5.93	83.3	83.5	5.29	5.31		8.5	8.4	
						32.0		5.94		83.7		5.33			8.2		
19/04/11	2010-2022	26/Fine	Surface	1.0	21.0	30.9	30.9	6.02	6.02	81.3	81.2	5.26	5.25	5.37	8.2	8.3	8.5
						30.9		6.01		81.1		5.23			8.4		
			Middle	8.4	20.0	31.9	31.9	5.89	5.91	79.5	79.8	5.35	5.37		8.6	8.5	
						31.8		5.93		80.1		5.39			8.4		
			Bottom	15.8	19.2	32.1	32.1	5.86	5.88	79.1	79.3	5.53	5.51		9.0	8.8	
						32.0		5.89		79.5		5.48			8.5		
21/04/11	1032-1045	24/Fine	Surface	1.0	22.3	31.2	31.2	5.99	5.97	80.9	80.6	5.20	5.18	5.32	8.4	8.6	8.9
						31.2		5.95		80.3		5.15			8.7		
			Middle	8.3	20.5	31.5	31.5	5.97	5.95	80.6	80.4	5.40	5.38		9.3	9.2	
						31.4		5.93		80.1		5.35			9.1		
			Bottom	15.6	20.0	32.2	32.2	5.78	5.78	78.0	78.0	5.42	5.40		8.9	9.0	
						32.1		5.77		77.9		5.38			9.0		
26/04/11	1321-1332	26/Sunny	Surface	1.0	21.2	30.8	30.8	6.15	6.14	86.7	86.6	5.12	5.15	5.25	8.0	7.9	8.2
						30.8		6.13		86.4		5.18			7.8		
			Middle	8.3	20.9	31.5	31.5	6.07	6.06	85.6	85.5	5.22	5.24		8.1	8.1	
						31.4		6.05		85.3		5.26			8.0		
			Bottom	15.6	20.6	31.7	31.7	5.95	5.97	83.3	83.6	5.39	5.36		8.5	8.7	
						31.7		5.99		83.9		5.32			8.8		
28/04/11	1700-1713	27/Rainy	Surface	1.0	23.4	30.6	30.7	6.14	6.16	87.2	87.5	5.15	5.14	5.24	8.1	8.1	8.3
						30.7		6.18		87.8		5.13			8.0		
			Middle	8.2	22.9	31.4	31.4	6.06	6.05	86.1	85.9	5.22	5.24		8.4	8.4	
						31.4		6.03		85.6		5.25			8.3		
			Bottom	15.4	22.7	31.9	32.0	5.92	5.90	83.5	83.2	5.38	5.35		8.6	8.6	
						32.0		5.88		82.9		5.32			8.5		
30/04/11	1750-1800	26/Cloudy	Surface	1.0	21.9	30.7	30.7	6.08	6.11	85.1	85.5	5.42	5.44	5.34	9.2	9.1	8.6
						30.7		6.13		85.8		5.46			9.0		
			Middle	8.4	21.4	31.6	31.6	6.04	6.05	84.6	84.7	5.27	5.32		8.5	8.5	
						31.5		6.05		84.7		5.36			8.5		
			Bottom	15.8	21.3	31.9	31.9	5.94	5.95	83.2	83.3	5.26	5.28		8.2	8.1	
						31.8		5.96		83.4		5.29			8.0		

Monitoring Station : R5

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)				
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average		
02/04/11	1629-1642	27/Sunny	Surface	1.0	18.9	30.7	30.7	6.12	6.10	83.8	83.6	5.12	5.10	5.20	8.2	8.2	8.4		
						30.6		6.08		83.3		5.08			8.2				
			Middle	8.8	19.5	31.4	31.4	6.02	6.00	83.7	83.4	5.18	5.20		5.20	5.20		8.4	8.5
						31.3		5.97		83.0		5.21			8.5				
			Bottom	16.8	20.3	32.2	32.2	5.83	5.85	80.5	80.8	5.27	5.29		5.29	5.29		8.3	8.4
						32.2		5.87		81.0		5.31			8.5				
07/04/11	1951-2006	22/Fine	Surface	1.0	19.3	30.7	30.8	6.04	6.06	85.7	86.0	5.31	5.34	5.47	8.5	8.6	9.0		
						30.8		6.08		86.3		5.37			8.6				
			Middle	8.8	18.8	31.4	31.5	5.92	5.94	84.0	84.2	5.44	5.46		5.46	5.46		9.2	9.1
						31.5		5.95		84.4		5.48			9.0				
			Bottom	16.6	18.2	31.9	31.9	5.81	5.83	82.5	82.7	5.60	5.62		5.62	5.62		9.3	9.4
						31.9		5.84		82.9		5.64			9.5				
09/04/11	0858-0910	21/Fine	Surface	1.0	20.8	31.2	31.2	5.97	5.98	83.6	83.8	5.13	5.12	5.27	8.2	8.3	8.5		
						31.1		5.99		83.9		5.10			8.3				
			Middle	8.8	20.3	31.7	31.8	5.88	5.90	82.3	82.5	5.23	5.26		5.26	5.26		8.5	8.4
						31.8		5.91		82.7		5.28			8.3				
			Bottom	16.6	19.6	32.0	32.1	5.78	5.77	80.9	80.7	5.47	5.45		5.45	5.45		8.8	8.9
						32.1		5.75		80.5		5.42			9.0				
12/04/11	1145-1157	23/Cloudy	Surface	1.0	18.5	30.8	30.8	5.93	5.95	84.2	84.4	5.27	5.25	5.37	8.5	8.4	8.7		
						30.7		5.96		84.6		5.22			8.2				
			Middle	8.8	18.9	31.3	31.3	5.82	5.84	82.1	82.3	5.38	5.36		5.36	5.36		8.6	8.7
						31.3		5.85		82.5		5.34			8.8				
			Bottom	16.6	19.2	31.6	31.6	5.74	5.73	80.9	80.8	5.46	5.49		5.49	5.49		9.0	9.0
						31.6		5.72		80.7		5.52			8.9				
14/04/11	1530-1542	29/Sunny	Surface	1.0	19.8	30.4	30.5	6.10	6.08	85.4	85.1	5.20	5.22	5.33	8.5	8.5	8.7		
						30.5		6.06		84.8		5.24			8.4				
			Middle	8.9	19.3	31.2	31.2	5.93	5.91	83.0	82.7	5.32	5.34		5.34	5.34		8.6	8.7
						31.1		5.88		82.3		5.35			8.8				
			Bottom	16.8	18.7	32.0	32.0	5.75	5.77	80.5	80.7	5.41	5.43		5.43	5.43		9.0	9.0
						31.9		5.78		80.9		5.44			9.0				
16/04/11	1544-1559	28/Cloudy	Surface	1.0	20.9	30.7	30.8	6.03	6.00	85.0	84.6	5.29	5.32	5.45	8.3	8.3	8.9		
						30.8		5.97		84.1		5.35			8.3				
			Middle	8.6	20.3	31.6	31.6	5.90	5.89	83.1	82.9	5.44	5.47		5.47	5.47		9.0	9.1
						31.6		5.87		82.7		5.49			9.2				
			Bottom	16.2	19.7	31.9	32.0	5.77	5.79	81.3	81.5	5.55	5.58		5.58	5.58		9.3	9.2
						32.0		5.80		81.7		5.60			9.1				
19/04/11	1825-1836	27/Fine	Surface	1.0	20.9	30.8	30.9	6.03	6.04	81.4	81.5	5.47	5.44	5.45	9.0	9.0	8.8		
						30.9		6.04		81.5		5.40			8.9				
			Middle	8.9	20.0	31.7	31.8	5.92	5.91	79.9	80.1	5.33	5.36		5.36	5.36		8.5	8.6
						31.8		5.90		80.2		5.39			8.6				
			Bottom	16.8	19.2	32.0	32.1	5.77	5.78	78.5	78.6	5.53	5.56		5.56	5.56		9.0	9.0
						32.1		5.79		78.7		5.58			9.0				
21/04/11	0851-0904	24/Fine	Surface	1.0	21.9	31.1	31.1	6.09	6.11	82.2	82.4	5.02	5.04	5.21	8.0	7.9	8.3		
						31.0		6.12		82.6		5.05			7.8				
			Middle	8.9	20.5	31.7	31.8	5.93	5.96	80.1	80.5	5.16	5.16		5.16	5.16		8.2	8.1
						31.8		5.99		80.9		5.15			8.0				
			Bottom	16.8	20.1	32.1	32.2	5.87	5.86	79.2	79.1	5.42	5.44		5.44	5.44		8.7	8.9
						32.2		5.85		78.9		5.46			9.0				
26/04/11	1122-1134	25/Sunny	Surface	1.0	21.2	30.6	30.6	5.96	5.95	84.0	83.9	5.22	5.25	5.36	8.5	8.4	8.7		
						30.6		5.94		83.8		5.28			8.3				
			Middle	8.8	20.9	31.4	31.4	5.87	5.85	82.8	82.5	5.38	5.36		5.36	5.36		8.6	8.6
						31.3		5.83		82.2		5.33			8.5				
			Bottom	16.6	20.5	31.7	31.8	5.74	5.76	80.4	80.6	5.51	5.48		5.48	5.48		9.1	9.2
						31.8		5.77		80.8		5.45			9.2				
28/04/11	1459-1512	27/Rainy	Surface	1.0	23.5	30.8	30.8	6.10	6.12	86.6	86.8	5.17	5.19	5.30	7.5	7.7	8.2		
						30.7		6.13		87.0		5.21			7.9				
			Middle	8.8	22.8	31.4	31.5	6.01	5.99	85.3	85.1	5.33	5.31		5.31	5.31		8.2	8.4
						31.5		5.97		84.8		5.29			8.5				
			Bottom	16.6	22.6	32.0	32.0	5.84	5.87	82.9	83.3	5.42	5.40		5.40	5.40		8.7	8.6
						32.0		5.89		83.6		5.38			8.5				
30/04/11	1604-1617	26/Cloudy	Surface	1.0	21.8	30.7	30.7	5.98	5.97	83.7	83.5	5.10	5.13	5.33	8.0	8.1	8.5		
						30.7		5.95		83.3		5.16			8.1				
			Middle	8.9	21.6	31.4	31.5	6.02	6.02	84.3	84.2	5.36	5.36		5.36	5.36		8.7	8.6
						31.5		6.01		84.1		5.35			8.5				
			Bottom	16.8	20.9	31.9	32.0	5.88	5.87	82.3	82.2	5.49	5.51		5.51	5.51		9.0	8.9
						32.0		5.86		82.0		5.53			8.7				

Mid-Flood Tide



Monitoring Station : R6

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)		Suspended Solids (mg/L)							
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average				
02/04/11	1724-1737	27/Sunny	Surface	1.0	18.8	30.5	30.6	6.14	6.16	84.7	84.9	5.11	5.13	5.23	8.0	8.1	8.3				
				8.3	19.5	31.4		6.03		83.2		5.19			8.1						
			Middle	8.3	19.5	31.3	31.4	6.06	6.05	83.6	83.4	5.23	5.21		8.1	8.1					
				Bottom	15.6	20.3	32.2	32.2	5.91	5.90	81.0	80.8	5.32		5.34	8.7		8.6			
			Surface		1.0	19.3	30.7	30.7	6.23	6.25	88.4	88.7	5.23		5.25	8.4		8.5	5.39	8.5	8.6
				8.2	18.8	31.5	6.10		86.6		5.38		8.7								
Middle	8.2	18.8	31.4	31.5	6.14	6.12	87.1	86.9	5.41	5.40	8.5	8.6									
	Bottom	15.4	18.2	31.9	31.9	6.05	6.07	85.9	86.1	5.50	5.53	9.0	9.0								
Surface		1.0	20.7	31.0	31.1	6.09	6.05	85.3	84.7	5.36	5.32	8.7	8.6	5.45	8.5	9.0	8.9				
	8.4	20.4	31.7	5.73		80.2		5.42		8.9											
Middle	8.4	20.4	31.8	31.8	5.79	5.76	81.1	80.7	5.44	5.43	9.0	9.0									
	Bottom	15.8	19.5	32.0	32.1	5.77	5.79	80.8	81.0	5.60	5.61	9.3	9.2								
Surface		1.0	18.5	30.6	30.7	6.13	6.15	87.0	87.3	5.17	5.19	8.2	8.1		5.31	8.0		8.5	8.5		
	8.4	18.8	31.4	6.02		84.9		5.26		8.5											
Middle	8.4	18.8	31.3	31.4	6.04	6.03	85.2	85.1	5.34	5.30	8.5	8.5									
	Bottom	15.8	19.1	31.7	31.7	5.96	5.97	84.0	84.1	5.46	5.44	8.9	8.8								
Surface		1.0	19.8	30.5	30.5	6.22	6.20	87.1	86.8	5.19	5.17	8.1	8.1	5.29		8.0	8.3	8.3			
	8.5	19.3	31.2	6.07		85.0		5.28		8.4											
Middle	8.5	19.3	31.1	31.2	6.11	6.09	85.5	85.3	5.31	5.30	8.2	8.3									
	Bottom	16.0	18.7	31.9	31.9	5.87	5.89	82.2	82.4	5.39	5.41	8.5	8.4								
Surface		1.0	21.0	30.8	30.8	6.26	6.28	88.2	88.5	4.96	4.98	7.8	7.9		5.22	8.0	8.2		8.4		
	8.3	20.4	31.5	6.18		87.1		5.23		8.3											
Middle	8.3	20.4	31.5	31.5	6.14	6.16	86.5	86.8	5.27	5.25	8.1	8.2									
	Bottom	15.6	19.8	31.9	32.0	5.99	5.97	84.4	84.1	5.40	5.43	9.0	9.0								
Surface		1.0	20.9	30.8	30.8	5.98	5.97	80.7	80.5	5.32	5.31	8.7	8.6	5.31		8.5	8.1	8.6			
	8.4	20.0	31.8	5.88		79.4		5.18		8.2											
Middle	8.4	20.0	31.7	31.8	5.84	5.86	78.8	79.1	5.24	5.21	8.0	8.1									
	Bottom	15.8	19.2	32.1	32.2	5.79	5.77	78.2	77.9	5.42	5.42	8.9	9.0								
Surface		1.0	21.9	31.0	31.1	5.94	5.93	80.2	80.0	5.14	5.17	7.9	8.0		5.30	8.3	8.4		8.4		
	8.4	20.5	31.7	5.77		77.9		5.29		8.5											
Middle	8.4	20.5	31.8	31.8	5.79	5.78	78.2	78.1	5.27	5.28	8.3	8.4									
	Bottom	15.8	20.0	32.0	32.1	5.73	5.75	77.4	77.7	5.48	5.46	8.9	8.8								
Surface		1.0	21.2	30.8	30.8	6.15	6.14	86.1	85.9	5.24	5.26	8.2	8.2	5.36		8.2	8.7	8.7			
	8.2	20.9	31.3	6.07		85.0		5.33		8.8											
Middle	8.2	20.9	31.4	31.4	6.03	6.05	84.4	84.7	5.39	5.36	8.5	8.7									
	Bottom	15.4	20.6	31.7	31.7	5.92	5.94	82.9	83.1	5.49	5.47	9.2	9.1								
Surface		1.0	23.5	30.7	30.7	6.17	6.19	87.6	87.9	5.09	5.11	8.1	8.2		5.23	8.1	8.5		8.3		
	8.4	22.8	31.5	6.10		88.2		5.13		8.2											
Middle	8.4	22.8	31.4	31.5	6.06	6.08	86.6	86.4	5.20	5.22	8.5	8.4									
	Bottom	15.8	22.7	31.9	31.9	5.92	5.91	84.1	83.9	5.33	5.35	8.6	8.5								
Surface		1.0	21.8	30.7	30.8	6.11	6.14	85.5	86.0	5.12	5.13	8.1	8.1	5.27		8.1	8.4	8.4			
	8.4	21.5	31.4	5.96		83.4		5.22		8.3											
Middle	8.4	21.5	31.3	31.4	5.95	5.96	83.3	83.4	5.29	5.26	8.5	8.4									
	Bottom	15.8	21.0	31.9	31.9	5.84	5.82	81.8	81.5	5.44	5.44	8.8	8.7								
Surface		1.0	21.8	30.7	30.8	6.11	6.14	85.5	86.0	5.12	5.13	8.1	8.1		5.27	8.1	8.4		8.4		
	8.4	21.5	31.4	5.96		83.4		5.22		8.3											
Middle	8.4	21.5	31.3	31.4	5.95	5.96	83.3	83.4	5.29	5.26	8.5	8.4									
	Bottom	15.8	21.0	31.9	31.9	5.84	5.82	81.8	81.5	5.44	5.44	8.8	8.7								

Mid-Flood Tide

Monitoring Station : R7

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/04/11	1744-1757	27/Sunny	Surface	1.0	18.9	30.6	30.6	6.22	6.21	85.8	85.6	5.18	5.16	5.25	8.2	8.2	8.5
						30.6		6.19		85.4		5.13			8.2		
			Middle	9.3	19.6	31.5	31.5	6.13	6.11	85.2	85.0	5.21	5.24		8.4	8.5	
						31.4		6.09		84.7		5.26			8.5		
			Bottom	17.6	20.4	32.3	32.3	5.99	6.00	82.1	82.2	5.38	5.37		8.8	8.7	
						32.2		6.00		82.2		5.36			8.6		
07/04/11	2111-2126	22/Fine	Surface	1.0	19.3	30.7	30.7	6.21	6.23	88.1	88.4	5.18	5.21	5.39	8.1	8.3	8.8
						30.7		6.25		88.7		5.24			8.4		
			Middle	9.4	18.8	31.5	31.5	6.15	6.13	87.3	87.0	5.40	5.42		8.8	8.9	
						31.5		6.11		86.7		5.43			9.0		
			Bottom	17.8	18.1	31.9	31.9	6.02	6.00	85.4	85.2	5.52	5.54		9.2	9.1	
						31.9		5.98		84.9		5.56			9.0		
09/04/11	1003-1015	21/Fine	Surface	1.0	20.8	31.1	31.2	6.04	6.04	84.6	84.5	5.14	5.16	5.36	8.3	8.2	8.6
						31.2		6.03		84.4		5.18			8.1		
			Middle	9.1	20.5	31.8	31.8	5.80	5.81	81.2	81.4	5.36	5.38		8.5	8.5	
						31.8		5.82		81.5		5.39			8.5		
			Bottom	17.2	19.4	32.1	32.1	5.75	5.74	80.5	80.4	5.53	5.54		9.2	9.1	
						32.0		5.73		80.2		5.55			9.0		
12/04/11	1255-1307	23/Cloudy	Surface	1.0	18.6	30.8	30.8	6.19	6.19	87.9	87.9	5.15	5.14	5.24	8.1	8.1	8.4
						30.7		6.18		87.8		5.12			8.0		
			Middle	9.3	18.9	31.4	31.4	6.06	6.07	86.1	86.2	5.24	5.22		8.3	8.4	
						31.4		6.07		86.2		5.20			8.5		
			Bottom	17.6	19.2	31.7	31.8	5.96	5.98	84.0	84.3	5.32	5.35		8.6	8.6	
						31.8		5.99		84.5		5.38			8.6		
14/04/11	1646-1700	29/Sunny	Surface	1.0	19.8	30.4	30.4	6.16	6.16	86.2	86.2	5.16	5.15	5.28	8.0	7.9	8.4
						30.4		6.15		86.1		5.14			7.8		
			Middle	9.3	19.4	31.2	31.2	6.06	6.04	84.8	84.5	5.25	5.28		8.2	8.4	
						31.2		6.01		84.1		5.30			8.5		
			Bottom	17.6	18.7	32.0	32.0	5.83	5.85	81.6	81.8	5.42	5.41		8.9	9.0	
						32.0		5.86		82.0		5.39			9.0		
16/04/11	1702-1715	28/Cloudy	Surface	1.0	21.0	30.9	30.9	6.31	6.33	88.9	89.1	4.92	4.95	5.20	7.9	7.9	8.3
						30.8		6.34		89.3		4.97			7.8		
			Middle	9.2	20.3	31.6	31.6	6.20	6.18	87.4	87.1	5.18	5.20		8.2	8.1	
						31.5		6.15		86.7		5.21			8.0		
			Bottom	17.4	19.7	32.0	32.0	6.03	6.00	85.0	84.6	5.44	5.47		8.9	9.0	
						32.0		5.97		84.1		5.49			9.0		
19/04/11	1928-1940	27/Fine	Surface	1.0	20.9	30.5	30.5	5.86	5.88	79.1	79.3	5.28	5.26	5.39	8.1	8.1	8.4
						30.4		5.89		79.5		5.24			8.0		
			Middle	9.3	19.9	31.7	31.8	5.80	5.80	78.3	78.3	5.40	5.38		8.5	8.5	
						31.8		5.79		78.2		5.35			8.4		
			Bottom	17.6	19.3	32.0	32.1	5.72	5.71	77.2	77.1	5.50	5.52		8.9	8.8	
						32.1		5.70		76.9		5.54			8.6		
21/04/11	0955-1001	24/Fine	Surface	1.0	21.9	31.2	31.2	5.90	5.92	79.7	79.9	5.23	5.20	5.31	8.4	8.3	8.6
						31.1		5.93		80.1		5.17			8.2		
			Middle	9.0	20.6	31.6	31.7	5.88	5.89	79.4	79.5	5.30	5.29		8.5	8.5	
						31.7		5.89		79.5		5.27			8.5		
			Bottom	17.0	20.0	32.1	32.1	5.79	5.79	78.2	78.1	5.50	5.46		9.2	9.1	
						32.0		5.78		78.0		5.41			9.0		
26/04/11	1235-1247	25/Sunny	Surface	1.0	21.2	30.7	30.8	6.16	6.17	86.9	87.0	5.25	5.22	5.32	8.2	8.1	8.5
						30.8		6.18		87.1		5.19			8.0		
			Middle	9.2	20.9	31.3	31.4	6.06	6.08	85.4	85.7	5.32	5.31		8.7	8.6	
						31.4		6.09		85.9		5.29			8.5		
			Bottom	17.4	20.6	31.7	31.8	5.98	5.97	83.7	83.6	5.40	5.42		8.8	8.9	
						31.9		5.96		83.4		5.44			8.9		
28/04/11	1614-1628	27/Rainy	Surface	1.0	23.4	30.7	30.8	6.20	6.21	88.0	88.1	5.15	5.14	5.27	8.0	8.1	8.5
						30.8		6.21		88.2		5.12			8.2		
			Middle	9.3	22.9	31.5	31.5	6.12	6.11	86.9	86.7	5.29	5.28		8.5	8.4	
						31.5		6.09		86.5		5.26			8.3		
			Bottom	17.6	22.7	32.2	32.2	5.82	5.84	82.6	82.9	5.43	5.41		8.8	8.9	
						32.1		5.86		83.2		5.38			9.0		
30/04/11	1706-1719	26/Cloudy	Surface	1.0	21.8	30.6	30.7	5.92	5.96	82.9	83.4	5.09	5.11	5.24	8.0	7.9	8.2
						30.7		5.99		83.9		5.13			7.8		
			Middle	9.1	21.5	31.4	31.5	5.87	5.89	82.2	82.4	5.19	5.23		8.2	8.3	
						31.5		5.90		82.6		5.26			8.4		
			Bottom	17.2	20.9	31.8	31.9	5.82	5.85	81.5	81.9	5.35	5.39		8.5	8.5	
						31.9		5.88		82.3		5.42			8.4		

Mid-Flood Tide

Monitoring Station : R8a

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/04/11	1806-1818	27/Sunny	Surface	1.0	18.8	30.5	30.6	6.13	6.14	84.6	84.8	5.18	5.16	5.26	8.2	8.2	8.4
						30.6		6.15		84.9		5.14			8.2		
			Middle	6.9	19.6	31.3	31.4	6.04	6.06	84.0	84.2	5.23	5.25		8.5	8.6	
						31.4		6.07		84.4		5.27			8.7		
			Bottom	12.8	20.3	32.2	32.2	5.92	5.94	82.3	82.6	5.35	5.37		8.6	8.5	
						32.2		5.96		82.8		5.38			8.4		
07/04/11	2132-2147	29/Fine	Surface	1.0	19.3	30.7	30.8	6.24	6.27	88.6	89.0	5.06	5.08	5.20	7.8	7.9	8.2
						30.8		6.29		89.3		5.09			8.0		
			Middle	6.7	19.0	31.3	31.3	6.17	6.15	87.6	87.3	5.16	5.17		8.0	8.1	
						31.3		6.13		87.0		5.18			8.2		
			Bottom	12.4	18.5	31.7	31.7	6.02	6.04	85.4	85.7	5.33	5.36		8.5	8.5	
						31.6		6.06		86.0		5.38			8.4		
09/04/11	1023-1035	22/Fine	Surface	1.0	20.9	31.0	31.1	6.07	6.05	84.9	84.6	5.01	5.04	5.24	8.0	7.9	8.3
						31.1		6.02		84.3		5.07			7.7		
			Middle	6.6	20.4	31.8	31.8	5.89	5.85	82.5	81.9	5.23	5.27		8.5	8.6	
						31.7		5.80		81.2		5.30			8.6		
			Bottom	12.2	19.5	32.1	31.7	5.74	5.73	80.4	80.3	5.41	5.42		8.7	8.6	
						31.2		5.72		80.1		5.43			8.5		
12/04/11	1313-1325	25/Cloudy	Surface	1.0	18.6	30.8	30.8	6.11	6.13	86.8	87.0	5.16	5.19	5.31	8.0	7.9	8.6
						30.8		6.14		87.2		5.22			7.7		
			Middle	6.7	18.8	31.3	31.3	6.02	6.03	85.5	85.6	5.35	5.32		8.8	8.8	
						31.3		6.03		85.6		5.29			8.8		
			Bottom	12.4	19.2	31.7	31.7	5.94	5.93	83.8	83.7	5.40	5.43		9.0	9.1	
						31.6		5.92		83.5		5.45			9.2		
14/04/11	1709-1722	29/Sunny	Surface	1.0	19.8	30.3	30.3	6.24	6.22	87.4	87.1	5.13	5.15	5.26	8.2	8.2	8.5
						30.3		6.20		86.8		5.17			8.2		
			Middle	6.9	19.3	31.0	31.0	6.13	6.11	85.3	85.2	5.24	5.26		8.8	8.8	
						30.9		6.08		85.1		5.28			8.7		
			Bottom	12.8	18.6	31.8	31.8	5.93	5.95	83.0	83.3	5.37	5.36		8.4	8.4	
						31.7		5.97		83.6		5.35			8.4		
16/04/11	1720-1735	27/Cloudy	Surface	1.0	21.0	30.8	30.8	6.23	6.25	87.8	88.1	4.90	4.92	5.07	8.3	8.3	8.4
						30.7		6.27		88.4		4.94			8.2		
			Middle	6.6	20.6	31.4	31.5	6.18	6.16	87.1	86.8	5.01	5.04		8.5	8.7	
						31.5		6.14		86.5		5.07			8.8		
			Bottom	12.2	20.0	31.9	31.9	6.05	6.03	85.3	85.0	5.21	5.24		8.4	8.4	
						31.9		6.00		84.6		5.26			8.4		
19/04/11	1945-1958	26/Fine	Surface	1.0	21.0	30.7	30.8	6.12	6.09	82.0	81.1	5.13	5.16	5.29	8.1	8.1	8.4
						30.8		6.05		80.1		5.19			8.0		
			Middle	6.7	19.9	31.7	31.7	5.84	5.82	78.8	78.6	5.28	5.30		8.5	8.5	
						31.6		5.80		78.3		5.31			8.4		
			Bottom	12.4	19.1	31.9	32.0	5.73	5.75	77.4	77.7	5.42	5.41		8.9	8.8	
						32.0		5.77		77.9		5.40			8.6		
21/04/11	1011-1023	24/Fine	Surface	1.0	22.1	31.2	31.2	5.97	5.94	80.6	80.2	5.19	5.21	5.40	8.1	8.1	8.6
						31.1		5.91		79.8		5.23			8.0		
			Middle	6.7	20.6	31.4	31.5	5.84	5.82	78.8	78.6	5.36	5.38		8.5	8.6	
						31.5		5.80		78.3		5.39			8.6		
			Bottom	12.4	20.1	32.0	32.1	5.72	5.74	77.2	77.4	5.59	5.61		9.3	9.2	
						32.1		5.75		77.6		5.62			9.0		
26/04/11	1254-1306	26/Sunny	Surface	1.0	21.1	30.7	30.7	6.17	6.19	87.0	87.3	5.21	5.19	5.30	8.1	8.1	8.4
						30.6		6.21		87.6		5.17			8.0		
			Middle	6.9	20.8	31.3	31.3	6.12	6.11	85.7	85.5	5.33	5.30		8.5	8.7	
						31.3		6.09		85.3		5.27			8.8		
			Bottom	12.8	20.6	31.8	31.8	6.01	5.99	84.1	83.9	5.38	5.40		8.6	8.5	
						31.7		5.97		83.6		5.41			8.4		
28/04/11	1637-1649	27/Rainy	Surface	1.0	23.4	30.7	30.7	6.17	6.20	87.6	88.0	5.12	5.11	5.19	8.0	7.9	8.2
						30.7		6.22		88.3		5.09			7.7		
			Middle	6.9	22.8	31.3	31.4	6.11	6.09	86.8	86.5	5.16	5.18		8.5	8.6	
						31.4		6.07		86.2		5.20			8.6		
			Bottom	12.8	22.4	31.8	31.9	5.96	5.98	84.0	84.3	5.27	5.29		8.3	8.3	
						31.9		5.99		84.5		5.30			8.2		
30/04/11	1729-1738	26/Cloudy	Surface	1.0	21.7	30.6	30.7	6.12	6.15	85.7	86.1	5.23	5.26	5.27	8.7	8.6	8.6
						30.7		6.17		86.4		5.28			8.5		
			Middle	6.7	21.5	31.5	31.6	6.02	6.00	84.3	84.0	5.12	5.11		8.2	8.3	
						31.6		5.97		83.6		5.09			8.3		
			Bottom	12.4	21.1	32.0	32.0	5.82	5.84	81.5	81.8	5.47	5.46		8.9	9.0	
						31.9		5.86		82.0		5.45			9.0		

Mid-Flood Tide



東業德動測試顧問有限公司
ETS-TESTCONSULT LIMITED

Monitoring Station : R15

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)		Suspended Solids (mg/L)			
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/04/11	1534-1546	27/Sunny	Surface	1.0	18.8	30.7	30.7	6.10	6.08	84.8	84.5	5.18	5.20	5.27	8.1	8.3	8.3
				5.9	19.4	30.6		6.06		84.2		5.22			8.4		
			Middle	5.9	19.4	31.3	31.4	5.98	5.97	82.5	82.3	5.28	5.26		8.3	8.2	
				10.8	20.1	31.4		5.95		82.1		5.24			8.1		
			Bottom	10.8	20.1	32.1	32.1	5.84	5.86	80.6	80.8	5.33	5.35		8.5	8.6	
				10.8	20.1	32.1		5.87		81.0		5.36			8.6		
07/04/11	1851-1906	22/Fine	Surface	1.0	19.4	30.7	30.8	6.08	6.10	86.3	86.6	5.32	5.31	5.47	8.5	8.4	8.8
				5.7	19.2	30.8		6.12		86.9		5.29			8.2		
			Middle	5.7	19.2	31.2	31.2	6.01	5.99	85.3	85.0	5.46	5.46		8.9	9.0	
				10.4	18.5	31.1		5.97		84.7		5.45			9.1		
			Bottom	10.4	18.5	31.6	31.7	5.88	5.87	83.4	83.2	5.61	5.64		8.8	8.9	
				10.4	18.5	31.7		5.85		83.0		5.66			9.0		
09/04/11	0738-0750	20/Fine	Surface	1.0	20.8	31.1	31.1	5.95	5.93	83.3	83.0	5.19	5.18	5.28	8.1	8.2	8.6
				5.6	20.4	31.0		5.91		82.7		5.16			8.3		
			Middle	5.6	20.4	31.6	31.7	5.78	5.77	80.9	80.8	5.22	5.24		8.4	8.5	
				10.2	19.7	31.7		5.76		80.6		5.26			8.6		
			Bottom	10.2	19.7	32.2	32.2	5.81	5.80	81.3	81.2	5.42	5.41		8.9	9.0	
				10.2	19.7	32.1		5.79		81.1		5.40			9.0		
12/04/11	1033-1044	21/Cloudy	Surface	1.0	18.6	30.7	30.8	5.98	5.99	84.9	85.0	5.25	5.27	5.38	8.4	8.3	8.6
				5.9	18.9	30.8		5.99		85.1		5.29			8.2		
			Middle	5.9	18.9	31.4	31.4	5.86	5.85	82.6	82.5	5.36	5.39		8.5	8.5	
				10.8	19.1	31.3		5.84		82.3		5.41			8.5		
			Bottom	10.8	19.1	31.8	31.8	5.77	5.76	81.4	81.3	5.51	5.49		9.0	9.0	
				10.8	19.1	31.7		5.75		81.1		5.46			8.9		
14/04/11	1434-1446	29/Fine	Surface	1.0	19.8	30.5	30.5	6.12	6.11	85.7	85.5	5.18	5.20	5.32	8.0	8.2	8.6
				5.9	19.2	30.4		6.09		85.3		5.22			8.3		
			Middle	5.9	19.2	31.2	31.2	6.01	5.99	84.1	83.9	5.31	5.32		8.7	8.6	
				10.8	18.6	31.1		5.97		83.6		5.34			8.5		
			Bottom	10.8	18.6	31.9	31.9	5.88	5.90	82.3	82.5	5.43	5.45		9.0	9.1	
				10.8	18.6	31.8		5.91		82.7		5.46			9.2		
16/04/11	1440-1454	28/Cloudy	Surface	1.0	20.8	30.8	30.8	5.98	5.96	84.3	84.0	5.19	5.22	5.39	8.1	8.1	8.5
				5.9	20.5	30.8		5.93		83.6		5.24			8.0		
			Middle	5.9	20.5	31.4	31.4	5.95	5.93	83.8	83.5	5.37	5.39		8.6	8.5	
				10.8	20.0	31.4		5.90		83.1		5.41			8.4		
			Bottom	10.8	20.0	31.7	31.8	5.81	5.83	81.9	82.1	5.57	5.55		9.0	9.1	
				10.8	20.0	31.8		5.84		82.3		5.53			9.1		
19/04/11	1709-1722	26/Fine	Surface	1.0	20.9	31.0	31.1	6.08	6.10	82.1	82.3	5.19	5.21	5.29	8.0	8.0	8.4
				5.9	19.8	31.1		6.11		82.5		5.22			8.0		
			Middle	5.9	19.8	31.8	31.8	6.01	5.99	81.1	80.9	5.30	5.34		8.4	8.3	
				10.8	19.0	31.8		5.97		80.6		5.37			8.2		
			Bottom	10.8	19.0	32.0	32.1	5.96	5.95	80.5	80.3	5.36	5.34		8.8	8.9	
				10.8	19.0	32.1		5.93		80.1		5.31			9.0		
21/04/11	0738-0750	23/Fine	Surface	1.0	21.9	31.0	31.1	6.01	6.02	81.1	81.3	5.06	5.08	5.23	8.0	8.0	8.4
				5.9	20.5	31.1		6.03		81.4		5.09			7.9		
			Middle	5.9	20.5	31.8	31.9	5.87	5.88	79.2	79.4	5.17	5.19		8.2	8.3	
				10.8	19.9	31.9		5.89		79.5		5.21			8.3		
			Bottom	10.8	19.9	32.1	32.1	5.82	5.81	78.6	78.4	5.44	5.43		8.9	8.9	
				10.8	19.9	32.0		5.79		78.2		5.42			8.8		
26/04/11	1004-1015	24/Sunny	Surface	1.0	21.1	30.7	30.7	5.98	5.97	84.3	84.1	5.33	5.35	5.46	8.4	8.6	8.9
				5.7	20.7	30.7		5.95		83.9		5.37			8.7		
			Middle	5.7	20.7	31.3	31.4	5.81	5.83	81.9	82.1	5.48	5.46		9.0	8.9	
				10.4	20.5	31.4		5.84		82.3		5.43			8.8		
			Bottom	10.4	20.5	31.7	31.8	5.73	5.74	80.8	81.0	5.58	5.56		9.3	9.3	
				10.4	20.5	31.8		5.75		81.1		5.54			9.2		
28/04/11	1404-1416	27/Rainy	Surface	1.0	23.5	30.7	30.7	6.08	6.10	85.7	86.0	5.24	5.23	5.31	8.3	8.3	8.4
				5.9	22.8	30.6		6.12		86.3		5.21			8.3		
			Middle	5.9	22.8	31.5	31.5	6.00	5.98	84.6	84.3	5.32	5.31		8.6	8.4	
				10.8	22.5	31.5		5.96		84.0		5.30			8.2		
			Bottom	10.8	22.5	31.9	31.9	5.84	5.86	82.3	82.6	5.38	5.40		8.5	8.5	
				10.8	22.5	31.8		5.88		82.9		5.41			8.5		
30/04/11	1448-1500	27/Cloudy	Surface	1.0	21.7	30.7	30.7	6.17	6.17	86.4	86.3	5.19	5.15	5.17	8.3	8.2	8.6
				5.8	21.5	30.6		6.16		86.2		5.11			8.0		
			Middle	5.8	21.5	31.2	31.3	5.82	5.86	81.5	82.1	5.29	5.26		8.4	8.5	
				10.6	20.9	31.3		5.90		82.6		5.22			8.6		
			Bottom	10.6	20.9	31.8	31.8	5.80	5.77	81.2	80.7	5.12	5.11		9.3	9.2	
				10.6	20.9	31.7		5.73		80.2		5.09			9.0		

Mid-Flood Tide



Monitoring Station : R16

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/04/11	1516-1527	27/Sunny	Surface	1.0	18.9	30.6	30.6	6.14	6.15	84.7	84.9	5.13	5.11	5.18	8.2	8.1	8.2
						30.5		6.16		85.0		5.09			8.0		
			Middle	6.8	19.5	31.4	31.4	6.11	6.10	84.9	84.8	5.15	5.17		8.2	8.2	
						31.3		6.09		84.7		5.19			8.2		
			Bottom	12.6	20.2	32.1	32.1	6.03	6.00	83.8	83.4	5.24	5.25		8.5	8.4	
						32.0		5.97		83.0		5.26			8.3		
07/04/11	1832-1846	22/Fine	Surface	1.0	19.4	30.7	30.7	6.33	6.35	89.8	90.1	5.12	5.14	5.27	8.1	8.1	8.4
						30.7		6.37		90.4		5.16			8.0		
			Middle	6.6	19.0	31.3	31.3	6.25	6.23	88.7	88.4	5.23	5.26		8.4	8.3	
						31.3		6.21		88.1		5.28			8.2		
			Bottom	12.2	18.3	31.7	31.8	6.13	6.12	87.0	86.8	5.40	5.43		8.9	9.0	
						31.8		6.10		86.6		5.45			9.0		
09/04/11	0719-0729	20/Fine	Surface	1.0	20.8	30.9	30.9	6.03	6.05	84.4	84.6	5.21	5.23	5.37	8.3	8.4	8.8
						30.9		6.06		84.8		5.24			8.5		
			Middle	6.5	20.4	31.7	31.7	5.88	5.89	82.3	82.4	5.46	5.45		9.0	9.2	
						31.6		5.89		82.5		5.44			9.3		
			Bottom	12.0	19.8	32.0	32.1	5.70	5.72	79.8	80.1	5.43	5.44		8.7	8.9	
						32.1		5.74		80.4		5.45			9.0		
12/04/11	1015-1026	21/Cloudy	Surface	1.0	18.5	30.7	30.7	6.15	6.14	87.3	87.1	5.18	5.15	5.26	8.1	8.1	8.4
						30.7		6.12		86.9		5.12			8.0		
			Middle	6.7	18.8	31.2	31.3	6.04	6.06	85.8	86.0	5.27	5.26		8.4	8.5	
						31.3		6.07		86.2		5.24			8.5		
			Bottom	12.4	19.1	31.7	31.7	5.95	5.94	83.9	83.8	5.35	5.38		8.8	8.7	
						31.6		5.93		83.6		5.40			8.6		
14/04/11	1416-1427	29/Fine	Surface	1.0	19.8	30.3	30.4	6.17	6.19	86.4	86.7	5.09	5.11	5.20	8.0	8.0	8.4
						30.4		6.21		86.9		5.12			8.0		
			Middle	6.9	19.3	31.1	31.1	6.08	6.07	85.1	84.9	5.18	5.20		8.3	8.4	
						31.1		6.05		84.7		5.21			8.5		
			Bottom	12.8	18.6	31.8	31.8	5.92	5.94	82.9	83.2	5.27	5.29		8.9	8.8	
						31.7		5.96		83.4		5.31			8.6		
16/04/11	1420-1435	28/Cloudy	Surface	1.0	20.7	30.7	30.7	6.32	6.31	89.1	88.9	5.04	5.02	5.19	8.0	7.9	8.2
						30.7		6.29		88.6		4.99			7.8		
			Middle	6.5	20.4	31.4	31.5	6.16	6.18	86.8	87.0	5.16	5.18		8.3	8.2	
						31.5		6.19		87.2		5.20			8.1		
			Bottom	12.0	19.8	31.9	31.9	6.05	6.03	85.3	85.0	5.35	5.38		8.7	8.6	
						31.9		6.00		84.6		5.40			8.5		
19/04/11	1646-1659	26/Fine	Surface	1.0	20.8	30.9	31.0	6.03	6.06	81.4	82.1	5.10	5.14	5.30	8.4	8.5	8.6
						31.0		6.09		82.8		5.17			8.6		
			Middle	6.2	19.9	31.7	31.8	5.83	5.82	79.3	78.8	5.26	5.28		8.2	8.2	
						31.8		5.80		78.3		5.30			8.2		
			Bottom	11.4	19.0	32.1	32.1	5.92	5.91	79.9	79.7	5.46	5.48		9.3	9.2	
						32.0		5.89		79.5		5.50			9.0		
21/04/11	0716-0728	23/Fine	Surface	1.0	21.9	31.1	31.1	6.09	6.07	82.2	81.9	5.20	5.23	5.36	8.2	8.4	8.6
						31.1		6.04		81.5		5.26			8.5		
			Middle	6.5	20.4	31.7	31.8	5.94	5.92	80.2	80.0	5.36	5.33		8.4	8.5	
						31.8		5.90		79.7		5.30			8.5		
			Bottom	12.0	20.1	32.2	32.2	5.77	5.79	77.9	78.1	5.55	5.53		9.0	9.0	
						32.1		5.80		78.3		5.51			9.0		
26/04/11	0945-0956	24/Sunny	Surface	1.0	21.0	30.6	30.7	6.11	6.12	86.2	86.3	5.17	5.20	5.31	8.1	8.1	8.4
						30.7		6.13		86.4		5.23			8.0		
			Middle	6.5	20.8	31.3	31.4	6.06	6.05	84.8	84.6	5.27	5.30		8.5	8.4	
						31.5		6.03		84.4		5.32			8.3		
			Bottom	12.0	20.5	31.9	31.9	5.93	5.95	83.0	83.2	5.46	5.43		8.7	8.9	
						31.8		5.96		83.4		5.39			9.0		
28/04/11	1346-1357	27/Rainy	Surface	1.0	23.4	30.6	30.7	6.16	6.18	87.5	87.7	5.05	5.07	5.17	7.8	7.7	8.0
						30.7		6.19		87.9		5.09			7.6		
			Middle	6.8	22.8	31.4	31.5	6.05	6.07	85.3	85.5	5.15	5.17		8.1	8.1	
						31.5		6.08		85.7		5.18			8.0		
			Bottom	12.6	22.5	31.9	31.9	5.92	5.94	83.5	83.7	5.25	5.27		8.3	8.2	
						31.9		5.95		83.9		5.29			8.1		
30/04/11	1423-1437	27/Cloudy	Surface	1.0	21.8	30.6	30.6	6.02	6.06	84.3	84.8	5.20	5.22	5.37	8.5	8.4	8.8
						30.6		6.09		85.3		5.24			8.3		
			Middle	6.5	21.4	31.3	31.4	5.99	6.00	83.9	84.0	5.36	5.38		8.7	8.8	
						31.4		6.01		84.1		5.39			8.8		
			Bottom	12.0	21.0	31.7	31.8	5.72	5.74	80.1	80.4	5.50	5.53		9.2	9.1	
						31.8		5.76		80.6		5.55			9.0		

Mid-Flood Tide

Monitoring Station : R17

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/04/11	1500-1512	27/Sunny	Surface	1.0	18.8	30.5	30.6	6.20	6.19	85.6	85.4	5.06	5.08	5.19	8.0	8.1	8.2
				6.4	19.4	31.4		6.14		85.3		5.17			8.1		
			Middle	6.4	19.4	31.5	31.5	6.08	6.11	84.5	84.9	5.20	5.19		8.0	8.1	
				Bottom	11.8	20.1	32.2	32.2	5.96	5.98	82.8	83.1	5.27		5.29	8.5	
					32.1		5.99		83.3		5.31		8.2				
			07/04/11	1815-1828	22/Fine	Surface	1.0	19.4	30.7	30.8	6.38	6.40	90.5		90.8	5.08	
6.2	19.1	31.2					31.3	6.27	6.25		89.0		88.7	5.20		5.23	8.5
Middle	6.2	19.1				31.3	31.3	6.23	6.13	88.4	87.0	5.25	5.45	8.3	8.8		
	Bottom	11.4				18.3	31.7	31.7	6.11	6.13	86.7	87.0	5.43	5.45	8.7	8.8	
		31.7					6.15		87.3		5.47		8.2				
		30.9					5.99		83.9		5.18		8.2				
		31.0		5.93		83.0		5.20		8.4							
09/04/11	0700-0713	20/Fine	Surface	1.0	20.7	30.9	31.0	5.99	5.96	83.9	83.5	5.18	5.19	5.34	8.2	8.3	8.6
				6.4	20.3	31.8		31.8		6.01		6.04			84.1		
			Middle	6.4	20.3	31.7	31.8	6.07	6.04	84.9	84.5	5.33	5.32		8.2	8.4	
				Bottom	11.8	19.7	32.0	32.1	5.89	5.87	82.5	82.2	5.49		5.50	9.0	
					32.1		5.85		81.9		5.50		9.0				
			12/04/11	1000-1012	21/Cloudy	Surface	1.0	18.6	30.8	30.8	6.13	6.12	87.0		86.9	5.18	
6.4	18.8	31.4					31.4	6.03	6.04		85.6		85.7	5.34		5.31	8.0
Middle	6.4	18.8				31.4	31.4	6.04	6.04	85.8	85.7	5.28	5.31	8.7	8.6		
	Bottom	11.8				19.1	31.6	31.7	5.94	5.96	83.8	84.0	5.45	5.43	9.3	9.3	
		31.7					5.97		84.2		5.41		9.2				
14/04/11	1400-1412	29/Fine				Surface	1.0	19.7	30.3	30.4	6.24	6.22	87.4	87.1	5.13	5.15	5.26
			6.4	19.2	30.4		31.1	6.15	6.14		86.1		85.9		5.25		
			Middle	6.4	19.2	31.0	31.1	6.12	6.14	85.7	85.9	5.28	5.27	8.3	8.4		
				Bottom	11.8	18.6	31.7	31.7	6.03	6.01	84.4	84.1	5.34	5.36	9.0	9.0	
					31.7		5.98		83.7		5.37		9.0				
					30.7		6.26		88.2		5.02		8.0				
		30.8		6.30		88.8		5.06		8.0							
16/04/11	1400-1415	28/Cloudy	Surface	1.0	20.8	30.7	30.8	6.26	6.28	88.2	88.5	5.02	5.04	5.18	8.0	8.0	8.3
				6.4	20.3	31.4		31.4		6.12		6.14			86.2		
			Middle	6.4	20.3	31.4	31.4	6.15	6.14	86.7	86.5	5.19	5.16		8.0	8.1	
				Bottom	11.8	19.8	31.8	31.9	6.01	5.99	84.7	84.4	5.32		5.35	8.8	
					31.9		5.97		84.1		5.37		8.7				
			19/04/11	1630-1643	26/Fine	Surface	1.0	20.9	31.0	31.1	6.18	6.14	83.4		82.9	5.36	
6.1	20.0	31.1					31.9	6.10	6.14		82.4		80.2	5.33		5.35	9.0
Middle	6.1	20.0				31.8	31.9	5.89	5.92	80.1	80.2	5.27	5.30	8.1	8.2		
	Bottom	11.2				19.2	31.9	32.0	5.94	5.83	80.2	80.2	5.32	5.30	8.2	8.2	
		32.0					5.81		78.4		5.48		9.3				
		32.0					5.84		78.8		5.44		9.2				
21/04/11	0700-0713	23/Fine	Surface	1.0	21.8	31.0	31.1	6.10	6.14	82.4	82.9	5.12	5.15	5.27	8.2	8.1	8.7
				6.4	20.3	31.1		31.8		6.18		6.14			83.4		
			Middle	6.4	20.3	31.8	31.8	5.92	5.95	79.9	80.3	5.22	5.25		8.5	8.5	
				Bottom	11.8	20.0	31.7	32.1	5.97	5.82	80.6	80.3	5.28		5.25	8.5	
					32.0		5.80		78.3		5.41		9.5				
					32.1		5.84		78.8		5.40		9.2				
26/04/11	0930-0942	24/Sunny	Surface	1.0	21.1	30.7	30.8	6.12	6.14	86.3	86.6	5.21	5.24	5.35	8.2	8.4	8.7
				6.3	20.8	30.8		31.5		6.16		6.04			86.9		
			Middle	6.3	20.8	31.5	31.5	6.03	6.04	85.0	85.2	5.36	5.34		8.7	8.6	
				Bottom	11.6	20.4	31.4	31.8	6.05	5.93	85.3	83.0	5.32		5.47	8.5	
					31.8		5.94		83.2		5.50		9.0				
					31.8		5.91		82.7		5.44		9.2				
		31.8		5.94		83.2		5.48		8.8							
		31.9		5.97		84.2		5.31		8.8							
28/04/11	1330-1342	27/Rainy	Surface	1.0	23.5	30.7	30.7	6.18	6.21	87.8	88.2	5.12	5.10	5.19	8.1	8.0	8.2
				6.4	22.9	30.7		31.5		6.23		6.09			88.5		
			Middle	6.4	22.9	31.5	31.5	6.10	6.09	86.0	85.8	5.17	5.19		8.2	8.1	
				Bottom	11.8	22.7	31.5	32.0	6.07	5.96	85.6	84.1	5.20		5.29	8.0	
					31.9		5.95		83.9		5.27		8.5				
					32.0		5.97		84.2		5.31		8.8				
30/04/11	1400-1413	27/Cloudy	Surface	1.0	21.8	30.6	30.7	6.07	6.04	84.9	84.5	5.13	5.15	5.29	8.2	8.2	8.5
				6.3	21.5	30.7		31.4		6.01		5.96			84.1		
			Middle	6.3	21.5	31.4	31.4	5.94	5.96	83.2	83.4	5.24	5.27		8.2	8.3	
				Bottom	11.6	21.0	31.3	31.9	5.97	5.92	83.6	82.8	5.30		5.45	8.5	
					31.8		5.90		82.6		5.42		9.0				
					31.9		5.93		83.0		5.48		8.8				

Mid-Flood Tide

Monitoring Station : R28

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/04/11	1648-1700	27/Sunny	Surface	1.0	18.8	30.6	30.6	6.21	6.20	85.7	85.5	5.16	5.18	5.26	8.1	8.1	8.2
				5.9	19.4	31.3		6.10		84.8		5.27			8.0		
			10.8	20.2	31.4	6.08	84.5	5.24	8.3								
07/04/11	2013-2028	22/Fine	Surface	1.0	19.4	30.7	30.7	6.22	6.25	88.3	88.7	5.28	5.28	5.37	8.3	8.2	8.6
				5.8	19.3	30.7		6.15		87.3		5.34			8.1		
			10.6	18.8	30.8	6.19	87.8	5.36	8.5								
09/04/11	0917-0930	21/Fine	Surface	1.0	20.7	31.3	31.3	6.07	6.09	84.9	85.2	5.21	5.23	5.37	8.4	8.3	8.6
				6.2	20.2	31.2		6.10		85.4		5.24			8.2		
			11.4	19.5	31.8	6.02	83.7	5.37	8.6								
12/04/11	1203-1214	23/Cloudy	Surface	1.0	18.6	31.6	31.6	5.97	5.98	82.3	82.1	5.46	5.50	5.28	8.9	8.8	8.3
				5.8	18.9	31.7		5.98		84.3		5.37			8.6		
			10.6	19.1	31.3	6.06	86.1	5.25	8.0								
14/04/11	1549-1601	29/Sunny	Surface	1.0	19.8	30.3	30.3	6.17	6.19	86.4	86.7	5.06	5.08	5.19	7.9	7.9	8.2
				5.8	19.3	30.3		6.21		86.9		5.10			7.9		
			10.6	18.6	31.0	6.06	84.8	5.21	8.5								
16/04/11	1605-1619	28/Cloudy	Surface	1.0	20.9	31.1	31.1	6.09	6.08	85.3	85.1	5.18	5.20	5.10	8.3	8.4	8.1
				5.9	20.5	31.7		5.94		83.2		5.28			8.4		
			10.8	20.0	31.7	5.92	82.9	5.32	8.2								
19/04/11	1843-1855	27/Fine	Surface	1.0	20.9	30.8	30.8	6.15	6.13	87.4	87.7	5.01	4.99	5.30	8.0	7.9	8.5
				6.3	20.0	30.8		6.20		87.9		4.96			7.7		
			11.6	19.1	31.1	6.13	86.4	5.05	8.2								
21/04/11	0909-0920	24/Fine	Surface	1.0	21.8	31.6	31.6	5.87	5.87	83.6	83.0	5.17	5.14	5.24	8.2	8.2	8.4
				6.2	20.6	31.7		5.86		79.7		5.31			8.5		
			11.4	19.9	31.1	6.03	81.4	5.16	8.1								
26/04/11	1141-1152	25/Sunny	Surface	1.0	21.2	31.2	31.2	6.01	6.02	81.1	81.3	5.17	5.17	5.27	8.4	8.3	8.2
				6.0	20.8	31.9		5.86		79.1		5.25			8.2		
			11.0	20.6	31.8	5.88	79.4	5.27	8.6								
28/04/11	1518-1530	27/Rainy	Surface	1.0	23.3	31.9	31.9	5.97	5.96	83.6	83.5	5.35	5.37	5.20	8.5	8.4	8.2
				5.9	22.7	31.8		5.95		83.3		5.39			8.2		
			10.8	22.5	30.6	6.18	87.8	5.10	8.1								
30/04/11	1622-1633	26/Cloudy	Surface	1.0	21.7	30.7	30.7	6.30	6.28	88.2	87.9	5.22	5.25	5.38	8.3	8.5	8.6
				6.3	21.5	30.7		6.25		87.5		5.27			8.6		
			11.6	20.9	31.4	6.17	86.4	5.33	8.5								

Mid-Flood Tide



Monitoring Station : R29

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)		Suspended Solids (mg/L)					
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average		
02/04/11	1704-1718	27/Sunny	Surface	1.0	18.9	30.6	30.7	6.16	6.18	85.6	85.9	5.14	5.16	5.25	8.2	8.2	8.4		
						30.7		6.20		86.2		5.17			8.2				
			Middle	8.9	19.6	31.5	31.5	6.07	6.08	84.4	84.6	5.22	5.24		5.25	5.24		8.4	8.5
						31.5		6.09		84.7		5.25			8.6				
			Bottom	16.8	20.3	32.2	32.3	5.97	5.96	82.4	82.2	5.34	5.37		5.34	5.37		8.5	8.5
						32.3		5.94		82.0		5.39			8.4				
07/04/11	2032-2047	22/Fine	Surface	1.0	19.3	30.7	30.8	6.05	6.08	85.9	86.3	5.36	5.38	5.52	8.6	8.8	9.1		
						30.8		6.10		86.6		5.40			8.9				
			Middle	8.9	18.8	31.5	31.5	5.98	5.95	84.9	84.5	5.50	5.52		5.50	5.52		9.0	9.1
						31.5		5.92		84.0		5.53			9.2				
			Bottom	16.8	18.2	31.9	31.9	5.85	5.83	83.0	82.7	5.65	5.67		5.65	5.67		9.5	9.5
						31.9		5.80		82.3		5.69			9.5				
09/04/11	0933-0945	21/Fine	Surface	1.0	20.8	31.2	31.2	6.12	6.11	85.7	85.6	5.16	5.14	5.31	8.2	8.1	8.5		
						31.1		6.10		85.4		5.11			8.0				
			Middle	8.9	20.3	31.9	31.9	5.87	5.85	82.2	81.9	5.28	5.30		5.28	5.30		8.4	8.4
						31.8		5.82		81.5		5.31			8.3				
			Bottom	16.8	19.6	32.2	32.2	5.72	5.71	80.1	80.0	5.49	5.50		5.49	5.50		9.0	9.0
						32.1		5.70		79.8		5.51			9.0				
12/04/11	1226-1237	23/Cloudy	Surface	1.0	18.5	30.7	30.7	5.95	5.95	84.5	84.4	5.24	5.27	5.36	8.8	8.7	8.8		
						30.7		5.94		84.3		5.30			8.6				
			Middle	8.7	18.8	31.3	31.4	5.87	5.86	82.8	82.7	5.38	5.36		5.38	5.36		8.5	8.4
						31.4		5.85		82.5		5.33			8.3				
			Bottom	16.4	19.1	31.7	31.7	5.77	5.78	81.4	81.5	5.44	5.46		5.44	5.46		9.0	9.2
						31.6		5.78		81.5		5.47			9.3				
14/04/11	1606-1619	29/Sunny	Surface	1.0	19.9	30.4	30.4	6.14	6.15	86.0	86.1	5.13	5.15	5.27	8.0	8.0	8.2		
						30.3		6.16		86.2		5.17			8.0				
			Middle	8.9	19.4	31.1	31.1	6.02	6.00	84.3	84.0	5.29	5.28		5.29	5.28		8.6	8.5
						31.1		5.97		83.6		5.27			8.4				
			Bottom	16.8	18.7	31.8	31.9	5.85	5.83	81.9	81.6	5.37	5.39		5.37	5.39		8.2	8.2
						31.9		5.81		81.3		5.40			8.2				
16/04/11	1627-1640	28/Cloudy	Surface	1.0	21.0	30.8	30.9	6.01	6.03	84.7	85.0	5.26	5.28	5.48	8.6	8.5	8.9		
						30.9		6.05		85.3		5.30			8.4				
			Middle	8.9	20.3	31.5	31.6	5.93	5.89	83.6	83.0	5.47	5.49		5.47	5.49		8.9	9.0
						31.6		5.85		82.4		5.51			9.0				
			Bottom	16.8	19.7	32.0	32.0	5.78	5.76	81.4	81.1	5.63	5.66		5.63	5.66		9.4	9.3
						32.0		5.73		80.7		5.68			9.2				
19/04/11	1858-1910	27/Fine	Surface	1.0	21.0	30.8	30.8	6.09	6.05	82.2	81.7	5.01	5.05	5.27	7.8	7.9	8.4		
						30.8		6.01		81.1		5.08			8.0				
			Middle	9.0	19.9	31.9	31.9	5.98	5.96	81.3	80.8	5.20	5.22		5.20	5.22		8.3	8.2
						31.8		5.94		80.2		5.24			8.0				
			Bottom	17.0	19.2	32.1	32.1	5.78	5.81	78.0	78.4	5.56	5.54		5.56	5.54		9.1	9.1
						32.0		5.83		78.7		5.51			9.1				
21/04/11	0923-0936	24/Fine	Surface	1.0	22.0	31.0	31.1	6.08	6.09	82.1	82.3	5.08	5.11	5.19	8.0	8.0	8.2		
						31.1		6.10		82.4		5.13			8.0				
			Middle	8.8	20.5	31.7	31.8	5.92	5.92	79.9	79.9	5.20	5.19		5.20	5.19		8.4	8.3
						31.8		5.91		79.8		5.18			8.1				
			Bottom	16.6	19.8	32.2	32.2	5.70	5.71	77.0	77.1	5.27	5.27		5.27	5.27		8.2	8.2
						32.1		5.71		77.1		5.26			8.2				
26/04/11	1206-1217	25/Sunny	Surface	1.0	21.1	30.8	30.8	5.92	5.93	83.5	83.7	5.36	5.34	5.45	8.4	8.5	8.5		
						30.7		5.94		83.8		5.31			8.5				
			Middle	8.9	20.8	31.4	31.4	5.83	5.84	82.2	82.4	5.42	5.44		5.42	5.44		8.9	8.7
						31.4		5.85		82.5		5.46			8.5				
			Bottom	16.8	20.5	31.8	31.8	5.72	5.74	80.7	80.9	5.60	5.57		5.60	5.57		8.5	8.4
						31.7		5.75		81.1		5.53			8.2				
28/04/11	1534-1548	27/Rainy	Surface	1.0	23.4	30.7	30.7	6.20	6.18	88.0	87.8	5.17	5.16	5.26	8.1	8.1	8.3		
						30.6		6.16		87.5		5.14			8.0				
			Middle	8.9	22.9	31.4	31.5	6.05	6.07	85.9	86.2	5.26	5.25		5.26	5.25		8.4	8.3
						31.5		6.09		86.5		5.23			8.2				
			Bottom	16.8	22.7	32.0	32.1	5.91	5.89	83.9	83.7	5.36	5.38		5.36	5.38		8.7	8.6
						32.1		5.87		83.4		5.40			8.5				
30/04/11	1636-1650	26/Cloudy	Surface	1.0	21.7	30.6	30.7	6.02	6.06	84.3	84.9	5.05	5.08	5.19	8.0	8.1	8.1		
						30.7		6.10		85.4		5.10			8.1				
			Middle	9.0	21.6	31.3	31.3	6.23	6.21	87.2	87.0	5.09	5.12		5.09	5.12		7.8	7.8
						31.3		6.19		86.7		5.14			7.8				
			Bottom	17.0	20.9	31.9	31.9	6.06	6.04	84.8	84.6	5.36	5.37		5.36	5.37		8.3	8.5
						31.8		6.02		84.3		5.37			8.6				

Mid-Flood Tide

Monitoring Station : C1

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/04/11	1553-1604	27/Sunny	Surface	1.0	18.9	30.7	30.7	6.22	6.20	85.2	85.0	5.16	5.18	5.26	8.0	8.0	8.3
						30.7		6.18		84.7		5.19			8.0		
			Middle	7.4	19.5	31.4	31.5	6.12	6.10	83.8	83.5	5.23	5.25		8.2	8.3	
						31.5		6.07		83.2		5.27			8.4		
			Bottom	13.8	20.2	32.2	32.2	5.92	5.94	81.7	82.0	5.38	5.37		8.6	8.7	
						32.2		5.96		82.2		5.35			8.8		
07/04/11	1910-1925	22/Fine	Surface	1.0	19.3	30.7	30.7	6.27	6.29	89.0	89.2	5.14	5.17	5.29	8.0	8.2	8.5
						30.7		6.30		89.4		5.20			8.3		
			Middle	7.3	19.0	31.3	31.3	6.19	6.18	87.8	87.6	5.32	5.30		8.5	8.5	
						31.3		6.16		87.4		5.28			8.5		
			Bottom	13.6	18.3	31.7	31.8	6.08	6.09	86.3	86.5	5.41	5.40		8.9	8.9	
						31.8		6.10		86.6		5.39			8.8		
09/04/11	0806-0819	20/Fine	Surface	1.0	20.7	31.1	31.2	5.98	6.01	83.7	84.1	5.13	5.12	5.32	8.2	8.2	8.7
						31.2		6.03		84.4		5.10			8.1		
			Middle	7.7	20.3	31.8	31.8	5.85	5.83	81.9	81.6	5.32	5.35		8.6	8.7	
						31.7		5.81		81.3		5.37			8.8		
			Bottom	14.4	19.6	32.0	32.1	5.73	5.72	80.2	80.0	5.50	5.49		9.2	9.1	
						32.1		5.70		79.8		5.47			9.0		
12/04/11	1057-1109	21/Cloudy	Surface	1.0	18.5	30.6	30.7	6.18	6.17	87.8	87.6	5.19	5.17	5.27	8.3	8.2	8.6
						30.7		6.15		87.3		5.14			8.1		
			Middle	7.3	18.8	31.3	31.3	6.07	6.08	86.2	86.4	5.28	5.26		8.5	8.6	
						31.3		6.09		86.5		5.24			8.6		
			Bottom	13.6	19.0	31.6	31.6	5.96	5.97	84.0	84.2	5.36	5.39		9.0	9.2	
						31.6		5.98		84.3		5.42			9.3		
14/04/11	1453-1505	29/Fine	Surface	1.0	19.9	30.4	30.4	6.13	6.15	85.8	86.1	5.16	5.14	5.26	8.3	8.5	8.5
						30.4		6.17		86.4		5.12			8.6		
			Middle	7.3	19.3	31.2	31.2	6.04	6.02	84.6	84.3	5.24	5.26		8.4	8.4	
						31.2		6.00		84.0		5.28			8.4		
			Bottom	13.6	18.7	31.9	32.0	5.90	5.88	82.6	82.3	5.39	5.37		8.7	8.8	
						32.0		5.86		82.0		5.34			8.8		
16/04/11	1501-1515	28/Cloudy	Surface	1.0	20.8	30.8	30.8	6.27	6.25	88.4	88.1	5.01	5.04	5.22	7.9	8.0	8.3
						30.7		6.22		87.7		5.06			8.0		
			Middle	7.3	20.2	31.5	31.6	6.15	6.13	86.7	86.4	5.19	5.21		8.2	8.2	
						31.6		6.10		86.0		5.23			8.2		
			Bottom	13.6	19.7	31.8	31.8	6.04	6.01	85.1	84.6	5.38	5.41		8.7	8.9	
						31.7		5.97		84.1		5.44			9.0		
19/04/11	1737-1750	26/Fine	Surface	1.0	20.9	31.1	31.2	5.94	5.95	80.2	80.0	5.32	5.31	5.47	8.6	8.5	8.8
						31.2		5.96		79.7		5.30			8.4		
			Middle	7.8	19.9	31.9	31.9	5.80	5.82	78.3	77.1	5.40	5.42		8.8	8.9	
						31.8		5.84		75.9		5.43			9.0		
			Bottom	14.6	19.0	32.1	32.2	5.76	5.78	78.2	79.1	5.49	5.68		9.1	9.0	
						32.2		5.79		79.9		5.67			8.8		
21/04/11	0802-0815	23/Fine	Surface	1.0	21.9	31.1	31.1	6.12	6.12	82.6	82.6	5.21	5.25	5.35	8.8	8.7	8.6
						31.1		6.11		82.5		5.28			8.6		
			Middle	7.8	20.4	31.9	31.9	5.99	6.01	80.9	81.1	5.47	5.46		8.9	9.1	
						31.8		6.02		81.3		5.45			9.2		
			Bottom	14.6	20.0	32.0	32.1	5.72	5.75	77.2	77.6	5.32	5.35		8.3	8.2	
						32.1		5.78		78.0		5.37			8.0		
26/04/11	1030-1042	24/Sunny	Surface	1.0	21.1	30.8	30.8	6.16	6.18	86.9	87.2	5.19	5.16	5.28	7.7	7.9	8.3
						30.7		6.20		87.4		5.13			8.0		
			Middle	7.4	20.9	31.5	31.5	6.04	6.06	84.6	84.9	5.29	5.27		8.6	8.5	
						31.5		6.08		85.1		5.25			8.3		
			Bottom	13.8	20.6	31.8	31.9	5.99	5.98	83.9	83.8	5.37	5.40		8.5	8.5	
						31.9		5.97		83.6		5.42			8.5		
28/04/11	1423-1434	27/Rainy	Surface	1.0	23.4	30.8	30.8	6.19	6.17	87.9	87.6	5.14	5.12	5.22	8.2	8.1	8.4
						30.7		6.15		87.3		5.10			8.0		
			Middle	7.3	22.7	31.4	31.5	6.03	6.05	85.6	85.9	5.19	5.21		8.3	8.4	
						31.5		6.07		86.2		5.22			8.5		
			Bottom	13.6	22.7	32.0	32.1	5.91	5.90	83.3	83.2	5.35	5.34		8.7	8.8	
						32.1		5.89		83.0		5.32			8.8		
30/04/11	1513-1526	27/Cloudy	Surface	1.0	21.7	30.7	30.7	6.20	6.17	86.8	86.3	5.30	5.31	5.35	8.9	8.9	8.8
						30.7		6.13		85.8		5.32			8.8		
			Middle	7.7	21.4	31.3	31.4	5.97	5.98	83.6	83.7	5.21	5.21		8.4	8.5	
						31.4		5.98		83.7		5.20			8.5		
			Bottom	14.4	21.1	31.7	31.8	5.92	5.93	82.8	83.0	5.57	5.54		9.1	9.1	
						31.8		5.94		83.2		5.51			9.0		

Mid-Flood Tide

Monitoring Station : C3

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/04/11	1610-1622	27/Sunny	Surface	1.0	18.8	30.6	30.6	6.12	6.15	84.5	84.8	5.17	5.20	5.28	8.0	8.1	8.4
				6.8	19.5	30.5		6.17		85.1		5.23			8.2		
			Middle	31.4	31.4	6.05	6.03	84.1	83.8	5.29	5.28	8.4	8.5				
				12.6		20.1		31.4		6.01		83.5			5.26	8.5	
			Bottom	32.0	32.1	5.87	5.90	81.0	81.4	5.34	5.37	8.7	8.6				
				32.1		5.92		81.7		5.39		8.5					
07/04/11	1930-1945	22/Fine	Surface	1.0	19.3	30.7	30.8	6.22	6.24	88.3	88.6	5.22	5.24	5.35	8.4	8.4	8.7
				6.9	19.0	30.8		6.26		88.8		5.26			8.3		
			Middle	31.3	31.3	6.17	6.16	87.6	87.3	5.34	5.36	8.6	8.7				
				12.8		18.3		31.2		6.14		87.0			5.38	8.7	
			Bottom	31.7	31.7	6.02	6.04	88.0	87.0	5.42	5.45	9.0	9.1				
				31.7		6.06		86.0		5.47		9.2					
09/04/11	0830-0842	20/Fine	Surface	1.0	20.7	31.1	31.2	6.01	6.04	84.1	84.5	5.26	5.25	5.37	8.2	8.2	8.5
				6.8	20.4	31.2		6.07		84.9		5.23			8.2		
			Middle	31.8	31.8	5.96	5.95	83.4	83.3	5.39	5.42	8.6	8.7				
				12.6		19.5		31.8		5.94		83.2			5.44	8.8	
			Bottom	32.1	32.1	5.89	5.85	82.5	81.9	5.41	5.46	8.5	8.6				
				32.0		5.81		81.3		5.50		8.7					
12/04/11	1120-1132	21/Cloudy	Surface	1.0	18.6	30.8	30.8	6.12	6.13	86.9	87.0	5.20	5.18	5.28	8.5	8.4	8.6
				6.6	18.9	30.8		6.13		87.0		5.16			8.2		
			Middle	31.3	31.4	6.05	6.04	85.3	85.1	5.25	5.28	8.6	8.5				
				12.2		19.2		31.4		6.02		84.9			5.31	8.4	
			Bottom	31.7	31.8	5.93	5.94	83.6	83.7	5.40	5.39	9.0	9.0				
				31.8		5.94		83.8		5.37		9.0					
14/04/11	1511-1523	29/Fine	Surface	1.0	19.8	30.4	30.4	6.18	6.17	86.5	86.3	5.14	5.16	5.26	8.2	8.1	8.4
				6.9	19.3	30.3		6.15		86.1		5.17			8.0		
			Middle	31.0	31.1	6.06	6.05	84.8	84.6	5.26	5.25	8.4	8.5				
				12.8		18.6		31.1		6.03		84.4			5.23	8.5	
			Bottom	31.7	31.8	5.95	5.94	83.3	83.1	5.35	5.37	8.7	8.8				
				31.8		5.92		82.9		5.38		8.8					
16/04/11	1523-1535	28/Cloudy	Surface	1.0	20.8	30.7	30.7	6.30	6.28	88.8	88.5	5.00	5.03	5.20	8.0	8.1	8.5
				6.9	20.3	30.7		6.25		88.1		5.05			8.2		
			Middle	31.5	31.5	6.13	6.11	86.4	86.1	5.21	5.19	8.5	8.4				
				12.8		19.8		31.5		6.09		85.8			5.17	8.2	
			Bottom	31.8	31.8	5.98	5.95	84.3	83.9	5.40	5.38	8.9	9.0				
				31.8		5.92		83.4		5.35		9.0					
19/04/11	1800-1813	26/Fine	Surface	1.0	20.8	31.0	31.1	6.02	6.05	81.3	81.6	5.19	5.17	5.30	8.1	8.1	8.6
				6.9	19.9	31.1		6.07		81.9		5.14			8.1		
			Middle	31.8	31.9	5.99	5.95	80.9	80.4	5.26	5.28	8.5	8.6				
				12.8		18.9		31.9		5.91		79.8			5.30	8.6	
			Bottom	32.0	32.0	5.84	5.86	78.8	79.0	5.49	5.45	9.3	9.2				
				31.9		5.87		79.2		5.41		9.0					
21/04/11	0826-0839	23/Fine	Surface	1.0	21.9	31.0	31.1	6.08	6.07	82.1	82.0	5.14	5.16	5.33	8.3	8.2	8.5
				6.8	20.6	31.1		6.06		81.8		5.17			8.1		
			Middle	31.7	31.8	5.95	5.93	80.3	80.1	5.33	5.36	8.5	8.5				
				12.6		20.1		31.8		5.91		79.8			5.38	8.5	
			Bottom	32.1	32.1	5.74	5.73	77.5	77.4	5.48	5.49	8.8	8.8				
				32.1		5.72		77.2		5.49		8.8					
26/04/11	1055-1107	24/Sunny	Surface	1.0	21.1	30.8	30.7	6.15	6.17	86.1	86.3	5.16	5.18	5.29	8.0	8.0	8.4
				6.8	20.8	30.6		6.18		86.5		5.20			8.0		
			Middle	31.5	31.5	6.06	6.05	84.8	84.7	5.26	5.29	8.6	8.4				
				12.6		20.5		31.4		6.04		84.6			5.31	8.2	
			Bottom	31.9	31.9	5.91	5.93	82.7	83.0	5.43	5.41	8.7	8.9				
				31.9		5.95		83.3		5.39		9.0					
28/04/11	1440-1452	27/Rainy	Surface	1.0	23.5	30.7	30.7	6.21	6.19	88.2	87.9	5.07	5.09	5.18	8.0	8.0	8.1
				6.9	22.9	30.7		6.17		87.6		5.11			8.0		
			Middle	31.5	31.5	6.11	6.10	86.8	86.6	5.16	5.18	8.2	8.1				
				12.8		22.6		31.4		6.08		86.3			5.19	8.0	
			Bottom	32.0	32.0	5.90	5.93	83.2	83.6	5.26	5.27	8.3	8.2				
				31.9		5.95		83.9		5.28		8.1					
30/04/11	1539-1552	27/Cloudy	Surface	1.0	21.8	30.6	30.7	6.02	6.05	84.3	84.6	5.47	5.44	5.40	8.8	8.8	8.6
				6.9	21.4	30.7		6.07		84.9		5.41			8.7		
			Middle	31.2	31.3	5.93	5.92	83.0	82.9	5.35	5.34	8.3	8.4				
				12.8		21.0		31.3		5.91		82.7			5.33	8.5	
			Bottom	31.8	31.9	5.78	5.82	80.9	81.5	5.44	5.42	8.6	8.7				
				31.9		5.86		82.0		5.40		8.8					

Monitoring Station : C2

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)		Suspended Solids (mg/L)					
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average		
02/04/11	1340-1352	27/Sunny	Surface	1.0	18.9	30.5	30.5	6.19	6.20	86.0	86.2	5.23	5.20	5.31	8.0	8.2	8.5		
						30.5		6.21		86.3		5.16			8.3				
			Middle	7.9	19.4	31.5	31.5	6.09	6.11	84.7	84.9	5.33	5.30		5.33	5.30		8.5	8.6
						31.4		6.12		85.1		5.26			8.7				
			Bottom	14.8	20.0	31.8	31.9	5.96	5.96	82.2	82.2	5.41	5.44		5.41	5.44		8.8	8.7
						31.9		5.95		82.1		5.47			8.5				
07/04/11	1720-1735	23/Fine	Surface	1.0	19.4	30.4	30.4	6.06	6.08	84.8	85.1	5.26	5.28	5.39	8.2	8.4	8.7		
						30.3		6.09		85.3		5.30			8.5				
			Middle	8.0	19.4	31.3	31.4	5.91	5.93	82.7	83.0	5.41	5.42		5.41	5.42		8.7	8.9
						31.4		5.95		83.3		5.43			9.0				
			Bottom	15.0	18.3	31.6	31.7	5.84	5.83	81.8	81.7	5.49	5.47		5.49	5.47		8.9	9.0
						31.7		5.82		81.5		5.44			9.0				
09/04/11	1710-1722	23/Fine	Surface	1.0	21.3	31.3	31.4	6.29	6.27	89.3	89.0	5.27	5.30	5.35	8.8	8.9	8.8		
						31.4		6.25		88.7		5.33			9.0				
			Middle	8.4	20.3	31.9	31.9	6.10	6.08	86.6	86.3	5.44	5.41		5.44	5.41		8.8	8.9
						31.8		6.06		86.0		5.37			8.5				
			Bottom	15.8	20.1	32.0	32.1	6.01	6.03	84.7	84.9	5.38	5.34		5.38	5.34		8.7	8.6
						32.1		6.04		85.1		5.30			8.7				
12/04/11	1919-1931	25/Cloudy	Surface	1.0	18.6	30.6	30.6	6.21	6.22	88.8	89.0	5.20	5.18	5.28	8.0	8.1	8.3		
						30.5		6.23		89.1		5.16			8.1				
			Middle	8.1	19.0	31.3	31.4	6.12	6.11	86.9	86.7	5.28	5.30		5.28	5.30		8.3	8.4
						31.4		6.09		86.5		5.31			8.4				
			Bottom	15.2	19.6	31.9	32.0	5.96	5.94	85.2	84.9	5.39	5.37		5.39	5.37		8.6	8.5
						32.0		5.91		84.5		5.35			8.4				
14/04/11	1158-1210	25/Fine	Surface	1.0	19.8	30.7	30.8	6.33	6.31	88.6	86.9	4.81	4.84	5.00	7.7	7.9	7.9		
						30.8		6.28		85.1		4.86			8.1				
			Middle	7.4	19.4	31.3	31.3	6.19	6.17	86.6	86.3	4.96	4.98		4.96	4.98		7.9	7.8
						31.3		6.14		85.9		5.00			7.7				
			Bottom	13.8	18.9	31.9	31.9	6.05	6.03	84.7	84.4	5.16	5.18		5.16	5.18		8.2	8.1
						31.9		6.00		84.0		5.20			8.0				
16/04/11	1226-1238	29/Cloudy	Surface	1.0	20.2	30.6	30.7	6.12	6.14	86.9	87.1	5.23	5.19	5.32	8.2	8.2	8.5		
						30.7		6.15		87.3		5.15			8.2				
			Middle	8.0	19.9	31.2	31.3	6.06	6.05	85.4	85.2	5.29	5.32		5.29	5.32		8.4	8.5
						31.4		6.03		85.0		5.34			8.5				
			Bottom	15.0	19.7	31.7	31.7	5.94	5.95	83.8	83.9	5.48	5.45		5.48	5.45		8.9	8.8
						31.7		5.95		83.9		5.42			8.6				
19/04/11	1432-1445	26/Fine	Surface	1.0	20.8	30.6	30.7	6.22	6.24	87.1	87.3	4.88	4.92	5.10	7.7	7.8	8.1		
						30.7		6.25		87.5		4.95			7.8				
			Middle	8.0	20.4	31.6	31.6	6.06	6.08	84.8	85.1	5.08	5.11		5.08	5.11		8.0	8.1
						31.6		6.10		85.4		5.13			8.2				
			Bottom	15.0	19.7	32.0	32.0	5.96	5.93	83.4	83.0	5.27	5.29		5.27	5.29		8.4	8.5
						32.0		5.90		82.6		5.30			8.6				
21/04/11	1628-1638	24/Fine	Surface	1.0	22.8	31.2	31.2	6.27	6.25	89.0	88.7	5.02	5.04	5.19	8.0	8.0	8.3		
						31.2		6.23		88.4		5.05			7.9				
			Middle	8.4	21.0	31.9	32.0	6.04	6.03	85.7	85.6	5.20	5.24		5.20	5.24		8.4	8.4
						32.0		6.02		85.4		5.27			8.3				
			Bottom	15.8	20.8	32.2	32.3	5.91	5.89	83.3	83.0	5.34	5.31		5.34	5.31		8.5	8.6
						32.3		5.87		82.7		5.27			8.7				
26/04/11	1917-1932	27/Fine	Surface	1.0	21.4	30.7	30.7	6.12	6.09	85.7	85.2	5.27	5.24	5.26	8.8	8.7	8.4		
						30.6		6.05		84.7		5.20			8.5				
			Middle	7.4	20.9	31.3	31.4	5.91	5.90	82.7	82.6	5.36	5.34		5.36	5.34		8.6	8.6
						31.4		5.89		82.5		5.32			8.6				
			Bottom	13.8	20.5	31.8	31.9	5.82	5.81	81.5	81.4	5.17	5.20		5.17	5.20		8.0	7.9
						31.9		5.80		81.2		5.23			7.8				
28/04/11	1156-1208	27/Cloudy	Surface	1.0	23.2	30.7	30.7	6.18	6.19	87.8	87.9	5.18	5.21	5.29	8.0	8.0	8.2		
						30.7		6.20		88.0		5.23			8.0				
			Middle	8.2	22.9	31.4	31.5	6.09	6.09	85.9	85.8	5.29	5.28		5.29	5.28		8.2	8.1
						31.5		6.08		85.7		5.26			8.0				
			Bottom	15.4	22.7	31.8	31.8	5.95	5.96	83.9	84.1	5.35	5.39		5.35	5.39		8.6	8.5
						31.8		5.97		84.2		5.42			8.4				
30/04/11	1234-1246	26/Cloudy	Surface	1.0	22.3	30.6	30.6	6.21	6.19	87.6	87.3	5.15	5.18	5.27	8.0	8.2	8.4		
						30.6		6.16		86.9		5.20			8.3				
			Middle	8.3	21.9	31.4	31.4	6.07	6.08	85.0	85.2	5.27	5.26		5.27	5.26		8.5	8.4
						31.4		6.09		85.3		5.24			8.2				
			Bottom	15.6	21.3	31.7	31.8	5.96	5.97	83.4	83.6	5.34	5.38		5.34	5.38		8.7	8.8
						31.8		5.98		83.7		5.42			8.9				

Mid-Ebb Tide

Monitoring Station : C4

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)			
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average	
02/04/11	1321-1332	27/Sunny	Surface	1.0	18.9	30.7	30.7	6.14	6.16	85.3	85.6	5.19	5.16	5.28	7.8	7.9	8.4	
						30.6		6.17		85.8		5.13			8.0			
			Middle	8.0	19.5	31.4	31.5	6.07	6.05	84.4	84.1	5.24	5.27		5.30	8.2		8.1
						31.5		6.03		83.8		5.30			8.0			
			Bottom	15.0	19.9	31.9	31.9	5.93	5.95	81.8	82.0	5.43	5.41		5.38	9.0		9.2
						31.9		5.96		82.2		5.38			9.3			
07/04/11	1700-1713	23/Fine	Surface	1.0	19.5	30.6	30.6	6.07	6.05	84.9	84.6	5.40	5.38	5.44	8.9	8.8	9.0	
						30.5		6.02		84.3		5.36			8.6			
			Middle	8.1	19.1	31.2	31.3	5.99	5.98	83.9	83.8	5.43	5.46		5.48	9.0		9.0
						31.3		5.97		83.6		5.48			9.0			
			Bottom	15.2	18.4	31.8	31.8	5.86	5.83	82.0	81.6	5.47	5.49		5.51	9.2		9.1
						31.7		5.80		81.2		5.51			9.0			
09/04/11	1651-1702	23/Fine	Surface	1.0	21.4	31.4	31.4	6.27	6.26	89.0	88.8	5.15	5.13	5.22	8.3	8.3	8.4	
						31.4		6.24		88.6		5.10			8.2			
			Middle	8.4	20.4	31.7	31.8	6.07	6.06	86.1	85.9	5.32	5.30		5.27	8.6		8.5
						31.8		6.04		85.7		5.27			8.4			
			Bottom	15.8	20.0	32.0	32.0	6.09	6.07	86.4	86.2	5.27	5.24		5.20	8.5		8.5
						32.0		6.05		85.9		5.20			8.5			
12/04/11	1855-1909	25/Cloudy	Surface	1.0	18.6	30.5	30.5	6.14	6.15	87.8	88.0	5.17	5.16	5.27	8.0	7.9	8.2	
						30.5		6.16		88.1		5.14			7.8			
			Middle	7.7	19.0	31.3	31.3	6.03	6.05	85.6	85.9	5.25	5.27		5.28	8.2		8.1
						31.3		6.06		86.1		5.28			8.0			
			Bottom	14.4	19.5	31.8	31.9	5.93	5.91	84.2	83.9	5.36	5.38		5.40	8.4		8.5
						31.9		5.89		83.6		5.40			8.5			
14/04/11	1139-1154	25/Fine	Surface	1.0	19.8	30.7	30.7	6.30	6.28	88.2	87.9	4.87	4.89	5.03	7.5	7.7	7.9	
						30.7		6.25		87.5		4.91			7.8			
			Middle	7.9	19.3	31.3	31.3	6.16	6.13	86.2	85.8	5.01	5.04		5.08	8.0		8.0
						31.3		6.10		85.4		5.08			8.0			
			Bottom	14.8	18.8	31.9	32.0	6.03	5.99	84.4	83.8	5.13	5.16		5.18	8.2		8.1
						32.0		5.94		83.1		5.18			8.0			
16/04/11	1208-1219	29/Cloudy	Surface	1.0	20.2	30.6	30.6	6.19	6.18	87.9	87.8	5.19	5.16	5.29	7.8	7.9	8.3	
						30.6		6.17		87.6		5.13			8.0			
			Middle	8.2	20.0	31.4	31.4	6.09	6.09	86.5	86.4	5.26	5.30		5.33	8.3		8.2
						31.3		6.08		86.3		5.33			8.1			
			Bottom	15.4	19.6	31.8	31.8	5.93	5.95	83.6	83.9	5.44	5.41		5.38	8.7		8.9
						31.8		5.97		84.2		5.38			9.0			
19/04/11	1415-1428	26/Fine	Surface	1.0	20.8	30.7	30.7	6.21	6.24	86.9	87.3	4.86	4.89	5.08	8.0	8.0	8.2	
						30.7		6.26		87.6		4.91			8.0			
			Middle	8.2	20.3	31.6	31.6	6.13	6.11	85.8	85.5	5.06	5.09		5.11	8.1		8.2
						31.5		6.08		85.1		5.11			8.2			
			Bottom	12.4	19.7	32.1	32.1	5.88	5.90	82.3	82.6	5.23	5.26		5.28	8.5		8.5
						32.0		5.92		82.8		5.28			8.5			
21/04/11	1611-1621	24/Fine	Surface	1.0	22.8	31.0	31.1	6.23	6.22	88.4	88.2	4.98	4.95	5.10	8.0	8.0	8.2	
						31.1		6.20		88.0		4.91			8.0			
			Middle	8.4	21.1	31.9	31.9	6.01	6.03	85.3	85.5	5.21	5.20		5.18	8.3		8.4
						31.8		6.04		85.7		5.18			8.5			
			Bottom	15.8	20.7	32.3	32.3	5.90	5.92	83.1	83.4	5.18	5.15		5.11	8.1		8.1
						32.3		5.94		83.7		5.11			8.0			
26/04/11	1859-1911	27/Fine	Surface	1.0	21.4	30.8	30.8	6.09	6.08	85.3	85.1	5.36	5.33	5.27	8.1	8.3	8.3	
						30.7		6.06		84.8		5.30			8.4			
			Middle	8.2	20.8	31.2	31.3	5.86	5.88	82.0	82.3	5.16	5.17		5.17	8.2		8.2
						31.3		5.89		82.5		5.17			8.2			
			Bottom	15.4	20.4	32.0	32.0	5.78	5.79	80.9	81.1	5.29	5.31		5.32	8.5		8.4
						31.9		5.80		81.2		5.32			8.2			
28/04/11	1138-1149	27/Cloudy	Surface	1.0	23.3	30.6	30.7	6.15	6.17	87.3	87.6	5.35	5.32	5.44	8.4	8.4	8.8	
						30.8		6.19		87.9		5.28			8.4			
			Middle	8.1	23.0	31.4	31.4	6.03	6.05	85.0	85.2	5.41	5.45		5.49	9.0		8.9
						31.4		6.06		85.4		5.49			8.8			
			Bottom	15.2	22.6	31.9	31.9	5.98	5.96	84.3	84.0	5.59	5.57		5.54	9.2		9.1
						31.9		5.93		83.6		5.54			9.0			
30/04/11	1215-1226	26/Cloudy	Surface	1.0	22.4	30.8	30.8	6.12	6.15	86.3	86.7	5.13	5.15	5.24	8.1	8.1	8.3	
						30.7		6.18		87.1		5.16			8.0			
			Middle	8.2	21.9	31.5	31.5	6.05	6.04	85.3	85.1	5.28	5.25		5.21	8.2		8.2
						31.4		6.02		84.9		5.21			8.2			
			Bottom	15.4	21.3	31.6	31.6	5.92	5.95	82.9	83.3	5.31	5.34		5.37	8.6		8.6
						31.6		5.97		83.6		5.37			8.5			

Monitoring Station : R5

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/04/11	1122-1134	23/Sunny	Surface	1.0	18.8	30.7	30.7	5.94	5.94	82.6	82.5	5.30	5.27	5.37	8.5	8.7	8.8
						30.6		5.93		82.4		5.24			8.8		
			Middle	8.2	19.4	31.5	31.5	5.84	5.86	80.6	80.8	5.34	5.36		8.4	8.5	
						31.5		5.87		81.0		5.38			8.6		
			Bottom	15.4	19.8	32.0	32.0	5.76	5.78	79.5	79.7	5.51	5.48		9.2	9.1	
						31.9		5.79		79.9		5.45			9.0		
07/04/11	1505-1520	24/Fine	Surface	1.0	19.8	30.5	30.6	6.09	6.07	85.3	85.0	5.42	5.45	5.94	9.0	9.0	9.4
						30.6		6.05		84.7		5.48			9.0		
			Middle	8.4	19.4	31.8	31.8	5.81	5.84	81.3	81.7	5.66	5.63		9.6	9.5	
						31.7		5.86		82.0		5.60			9.4		
			Bottom	15.8	18.7	32.0	32.1	5.74	5.74	80.4	80.3	5.76	6.75		9.7	9.6	
						32.1		5.73		80.2		7.74			9.5		
09/04/11	1452-1504	23/Fine	Surface	1.0	21.1	31.2	31.3	6.30	6.32	89.4	89.7	4.89	4.93	5.05	7.8	7.9	8.1
						31.3		6.34		90.0		4.96			8.0		
			Middle	8.4	20.5	31.7	31.7	6.11	6.09	86.7	86.4	5.07	5.04		8.2	8.3	
						31.7		6.07		86.1		5.01			8.3		
			Bottom	15.8	20.0	32.0	32.0	6.02	6.04	85.4	85.7	5.15	5.17		8.0	8.0	
						32.0		6.05		85.9		5.19			8.0		
12/04/11	1700-1712	25/Cloudy	Surface	1.0	18.5	30.6	30.6	6.11	6.13	86.2	86.5	5.23	5.21	5.30	8.5	8.4	8.3
						30.5		6.15		86.7		5.19			8.3		
			Middle	8.1	18.9	31.4	31.4	6.05	6.04	85.9	85.8	5.27	5.29		8.1	8.1	
						31.3		6.03		85.6		5.31			8.0		
			Bottom	15.2	19.6	32.0	32.0	5.88	5.91	84.1	84.5	5.36	5.39		8.3	8.4	
						31.9		5.93		84.8		5.41			8.4		
14/04/11	0940-0955	25/Fine	Surface	1.0	19.7	30.8	30.8	6.03	6.05	84.4	84.7	5.12	5.14	5.29	8.0	8.1	8.5
						30.7		6.07		84.9		5.16			8.2		
			Middle	8.3	19.2	31.3	31.4	5.92	5.90	82.8	82.6	5.28	5.30		8.3	8.3	
						31.4		5.88		82.3		5.31			8.3		
			Bottom	15.6	18.7	31.9	32.0	5.89	5.71	79.9	79.6	5.41	5.44		8.9	9.0	
						32.0		5.73		80.3		5.46			9.0		
16/04/11	1015-1027	26/Cloudy	Surface	1.0	20.2	30.8	30.8	5.94	5.93	84.3	84.1	5.32	5.29	5.40	8.8	8.9	8.8
						30.7		5.91		83.9		5.26			9.0		
			Middle	8.3	19.9	31.3	31.4	5.83	5.85	82.2	82.4	5.36	5.39		8.6	8.5	
						31.4		5.86		82.6		5.41			8.4		
			Bottom	15.6	19.6	31.8	31.8	5.73	5.75	80.8	81.1	5.55	5.52		9.1	9.1	
						31.8		5.77		81.4		5.48			9.0		
19/04/11	1215-1228	26/Fine	Surface	1.0	20.6	30.7	30.7	6.06	6.04	84.8	84.5	5.12	5.14	5.30	8.0	8.0	8.4
						30.7		6.02		84.2		5.16			8.0		
			Middle	8.2	20.2	31.6	31.6	5.94	5.92	83.1	82.9	5.28	5.31		8.4	8.3	
						31.5		5.90		82.6		5.33			8.2		
			Bottom	15.4	19.8	32.0	32.0	5.82	5.84	81.4	81.7	5.45	5.47		8.9	8.8	
						32.0		5.85		81.9		5.48			8.7		
21/04/11	1412-1424	24/Fine	Surface	1.0	22.9	31.2	31.3	6.11	6.09	86.1	85.8	5.25	5.23	5.37	8.5	8.5	8.8
						31.3		6.06		85.4		5.21			8.4		
			Middle	8.4	20.9	31.8	31.9	6.01	6.03	84.7	84.9	5.57	5.54		9.2	9.2	
						31.9		6.04		85.1		5.50			9.2		
			Bottom	15.8	20.6	32.3	32.4	5.95	5.97	83.8	84.1	5.39	5.35		8.7	8.6	
						32.4		5.98		84.3		5.31			8.5		
26/04/11	1723-1736	27/Fine	Surface	1.0	21.4	30.6	30.7	6.04	6.07	84.6	85.0	5.19	5.22	5.29	7.8	8.0	8.3
						30.7		6.10		85.4		5.24			8.1		
			Middle	8.4	21.0	31.3	31.4	6.01	5.98	84.1	83.7	5.29	5.33		8.6	8.5	
						31.4		5.94		83.2		5.36			8.3		
			Bottom	15.8	20.6	31.8	31.8	5.90	5.89	82.6	82.4	5.34	5.32		8.5	8.5	
						31.7		5.87		82.2		5.30			8.4		
28/04/11	0945-0957	26/Cloudy	Surface	1.0	23.2	30.6	30.6	5.97	5.98	84.2	84.4	5.35	5.33	5.44	8.5	8.4	8.9
						30.6		5.99		84.5		5.31			8.2		
			Middle	8.3	22.9	31.5	31.5	5.85	5.87	82.5	82.7	5.48	5.45		9.0	9.1	
						31.4		5.88		82.9		5.42			9.2		
			Bottom	15.6	22.6	31.8	31.8	5.77	5.77	81.4	81.3	5.53	5.55		9.3	9.2	
						31.8		5.76		81.2		5.56			9.1		
30/04/11	1018-1030	26/Cloudy	Surface	1.0	22.3	30.6	30.7	5.94	5.93	83.2	83.1	5.33	5.36	5.47	8.8	8.7	9.1
						30.7		5.92		82.9		5.39			8.6		
			Middle	8.2	21.8	31.4	31.5	5.87	5.85	82.2	81.9	5.49	5.47		9.3	9.2	
						31.5		5.83		81.6		5.44			9.0		
			Bottom	15.4	21.2	31.8	31.8	5.73	5.75	80.2	80.4	5.63	5.59		9.5	9.4	
						31.8		5.76		80.6		5.55			9.3		

Mid-Ebb Tide

Monitoring Station : R6

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/04/11	1220-1232	23/Sunny	Surface	1.0	18.8	30.7	30.7	6.18	6.17	85.9	85.8	5.20	5.18	5.28	8.4	8.3	8.5
						30.7		6.16		85.6		5.16			8.2		
			Middle	8.3	19.4	31.4	31.5	6.08	6.07	83.9	83.7	5.24	5.28		8.3	8.3	
						31.5		6.05		83.5		5.31			8.3		
			Bottom	15.6	20.0	31.9	32.0	5.94	5.96	82.0	82.2	5.41	5.39		8.7	8.9	
						32.0		5.97		82.4		5.36			9.0		
07/04/11	1558-1610	24/Fine	Surface	1.0	19.8	30.4	30.5	5.98	5.97	83.7	83.6	5.36	5.33	5.52	8.4	8.5	9.0
						30.5		5.96		83.4		5.30			8.6		
			Middle	7.9	19.3	31.6	31.7	5.82	5.81	81.5	81.4	5.56	5.58		9.0	9.1	
						31.7		5.80		81.2		5.59			9.2		
			Bottom	14.8	18.7	32.3	32.3	5.88	5.89	82.3	82.4	5.67	5.67		9.4	9.4	
						32.2		5.89		82.5		5.66			9.4		
09/04/11	1550-1602	23/Fine	Surface	1.0	21.3	31.3	31.3	6.25	6.23	88.7	88.4	5.09	5.07	5.29	8.1	8.1	8.5
						31.3		6.21		88.1		5.05			8.0		
			Middle	8.2	20.4	31.8	31.8	6.01	6.03	85.3	85.5	5.39	5.42		8.5	8.6	
						31.7		6.04		85.7		5.44			8.7		
			Bottom	15.4	19.9	32.0	32.0	6.03	6.05	85.6	85.9	5.41	5.39		9.0	8.9	
						31.9		6.07		86.1		5.37			8.8		
12/04/11	1754-1807	25/Cloudy	Surface	1.0	18.6	30.7	30.6	6.13	6.15	86.4	86.7	5.19	5.18	5.23	8.2	8.1	8.2
						30.5		6.16		86.9		5.16			8.0		
			Middle	7.8	19.0	31.3	31.4	6.02	6.04	84.9	85.2	5.20	5.22		8.6	8.5	
						31.4		6.06		85.4		5.23			8.4		
			Bottom	14.6	19.5	32.0	32.0	5.84	5.83	82.3	82.2	5.29	5.31		8.2	8.1	
						32.0		5.82		82.1		5.32			8.0		
14/04/11	1039-1055	25/Fine	Surface	1.0	19.8	30.7	30.8	6.28	6.26	87.9	87.6	5.03	5.00	5.16	7.8	7.9	8.2
						30.8		6.24		87.3		4.97			8.0		
			Middle	7.8	19.3	31.3	31.3	6.13	6.15	85.8	86.0	5.11	5.14		8.2	8.1	
						31.3		6.16		86.2		5.17			8.0		
			Bottom	14.6	18.8	31.9	31.9	5.97	5.95	83.5	83.2	5.32	5.34		8.5	8.5	
						31.8		5.92		82.8		5.36			8.5		
16/04/11	1110-1122	26/Cloudy	Surface	1.0	20.2	30.6	30.7	6.14	6.12	87.2	86.9	5.18	5.15	5.27	8.3	8.2	8.4
						30.7		6.10		86.6		5.12			8.0		
			Middle	8.1	19.8	31.3	31.3	6.03	6.04	85.0	85.2	5.26	5.28		8.5	8.4	
						31.3		6.05		85.3		5.30			8.2		
			Bottom	15.2	19.5	31.6	31.7	5.93	5.94	83.6	83.8	5.35	5.39		8.7	8.6	
						31.8		5.95		83.9		5.42			8.5		
19/04/11	1313-1327	26/Fine	Surface	1.0	20.7	30.7	30.7	6.24	6.27	87.3	87.7	4.81	4.84	5.02	7.6	7.7	7.9
						30.7		6.29		88.1		4.86			7.8		
			Middle	7.9	20.3	31.6	31.7	6.13	6.15	85.8	86.0	4.97	5.01		8.0	8.0	
						31.7		6.16		86.2		5.05			7.9		
			Bottom	14.8	19.8	32.0	32.1	5.92	5.94	82.8	83.1	5.18	5.21		8.2	8.1	
						32.1		5.95		83.3		5.23			8.0		
21/04/11	1510-1522	24/Fine	Surface	1.0	22.8	31.2	31.2	6.29	6.28	89.3	89.2	5.43	5.40	5.27	8.9	8.8	8.4
						31.1		6.27		89.0		5.37			8.6		
			Middle	8.2	20.9	32.0	32.0	6.04	6.06	85.7	86.0	5.21	5.19		8.4	8.3	
						32.0		6.08		86.3		5.16			8.2		
			Bottom	15.4	20.7	32.3	32.3	5.84	5.82	82.3	82.0	5.19	5.22		8.1	8.2	
						32.2		5.80		81.7		5.25			8.2		
26/04/11	1813-1822	27/Fine	Surface	1.0	21.5	30.7	30.8	6.09	6.11	85.3	85.5	5.13	5.17	5.21	8.2	8.2	8.2
						30.8		6.12		85.7		5.20			8.2		
			Middle	7.9	21.1	31.4	31.4	5.93	5.92	83.0	82.9	5.19	5.18		8.0	8.0	
						31.3		5.91		82.7		5.17			8.0		
			Bottom	14.8	20.5	31.9	31.9	5.78	5.80	80.9	81.1	5.26	5.29		8.4	8.5	
						31.8		5.81		81.3		5.31			8.6		
28/04/11	1040-1052	26/Cloudy	Surface	1.0	23.2	30.8	30.8	6.14	6.15	87.2	87.4	5.23	5.25	5.35	8.2	8.2	8.6
						30.8		6.16		87.5		5.26			8.2		
			Middle	8.2	22.8	31.4	31.5	6.05	6.07	85.3	85.5	5.39	5.36		8.4	8.6	
						31.5		6.08		85.7		5.33			8.7		
			Bottom	15.4	22.5	31.8	31.9	5.97	5.95	84.2	83.9	5.43	5.46		8.9	9.0	
						31.9		5.93		83.6		5.48			9.0		
30/04/11	1115-1127	26/Cloudy	Surface	1.0	22.3	30.8	30.7	6.15	6.13	86.7	86.5	5.26	5.29	5.38	8.2	8.1	8.6
						30.6		6.11		86.2		5.32			8.0		
			Middle	8.1	21.8	31.5	31.5	6.04	6.06	84.6	84.8	5.39	5.38		8.7	8.6	
						31.5		6.07		85.0		5.36			8.5		
			Bottom	15.2	21.2	31.8	31.8	5.98	5.97	83.7	83.5	5.45	5.48		9.0	9.0	
						31.8		5.95		83.3		5.50			8.9		

Monitoring Station : R7

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)		Suspended Solids (mg/L)					
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average		
02/04/11	1235-1247	23/Sunny	Surface	1.0	18.9	30.6	30.6	6.13	6.14	85.2	85.4	5.24	5.21	5.32	8.3	8.2	8.3		
						30.5		6.15		85.5		5.18			8.1				
			Middle	8.7	19.5	31.5	31.5	6.06	6.04	83.6	83.4	5.33	5.31		5.33	5.31		8.6	8.5
						31.5		6.02		83.1		5.28			8.4				
			Bottom	16.4	20.0	31.9	31.9	5.95	5.94	82.1	82.0	5.40	5.43		5.40	5.43		8.2	8.1
						31.8		5.93		81.8		5.46			8.0				
07/04/11	1613-1627	24/Fine	Surface	1.0	19.7	30.5	30.6	5.90	5.92	82.6	82.9	5.41	5.45	5.58	8.8	8.9	9.0		
						30.6		5.94		83.2		5.48			8.9				
			Middle	9.0	19.4	31.5	31.6	5.89	5.91	82.5	82.7	5.56	5.57		5.56	5.57		9.1	9.1
						31.6		5.92		82.9		5.57			9.0				
			Bottom	17.0	18.8	32.4	32.4	5.74	5.76	80.4	80.6	5.70	5.74		5.70	5.74		9.3	9.2
						32.3		5.77		80.8		5.77			9.1				
09/04/11	1605-1617	23/Fine	Surface	1.0	21.3	31.3	31.4	6.35	6.33	90.1	89.9	5.25	5.29	5.13	8.3	8.2	8.0		
						31.4		6.31		89.6		5.32			8.1				
			Middle	8.9	20.4	31.8	31.8	6.10	6.09	86.6	86.4	5.15	5.18		5.15	5.18		8.0	8.1
						31.8		6.07		86.1		5.21			8.2				
			Bottom	16.8	20.0	31.9	32.0	6.04	6.06	85.7	86.0	4.89	4.92		4.89	4.92		7.6	7.6
						32.0		6.08		86.3		4.94			7.5				
12/04/11	1814-1825	25/Cloudy	Surface	1.0	18.6	30.6	30.6	6.20	6.18	88.0	87.8	5.13	5.15	5.25	8.1	8.1	8.4		
						30.6		6.16		87.5		5.17			8.0				
			Middle	8.6	19.0	31.4	31.4	6.04	6.07	86.4	86.8	5.22	5.24		5.22	5.24		8.6	8.5
						31.4		6.09		87.1		5.26			8.3				
			Bottom	16.2	19.6	32.0	32.1	5.87	5.84	83.4	83.0	5.33	5.37		5.33	5.37		8.7	8.8
						32.1		5.81		82.5		5.40			8.8				
14/04/11	1100-1115	25/Fine	Surface	1.0	19.8	30.7	30.7	6.30	6.28	88.2	87.9	4.91	4.93	5.12	7.9	8.0	8.2		
						30.7		6.26		87.6		4.95			8.0				
			Middle	8.8	19.4	31.3	31.4	6.15	6.13	86.1	85.8	5.10	5.13		5.10	5.13		8.2	8.1
						31.4		6.11		85.5		5.15			8.0				
			Bottom	16.6	18.6	31.9	32.0	5.96	5.93	83.4	83.0	5.29	5.31		5.29	5.31		8.3	8.4
						32.0		5.90		82.6		5.33			8.5				
16/04/11	1125-1137	26/Cloudy	Surface	1.0	20.2	30.8	30.8	6.15	6.16	87.3	87.5	5.15	5.17	5.30	8.0	8.0	8.4		
						30.8		6.17		87.6		5.19			8.0				
			Middle	8.8	19.9	31.2	31.3	6.09	6.08	85.9	85.7	5.25	5.29		5.25	5.29		8.4	8.3
						31.3		6.06		85.4		5.33			8.2				
			Bottom	16.6	19.7	31.7	31.7	5.98	5.97	84.3	84.2	5.44	5.43		5.44	5.43		8.9	9.0
						31.7		5.96		84.0		5.41			9.0				
19/04/11	1331-1346	26/Fine	Surface	1.0	20.7	30.7	30.8	6.20	6.23	86.8	87.2	4.89	4.91	5.09	7.5	7.7	8.0		
						30.8		6.26		87.6		4.93			7.8				
			Middle	8.8	20.3	31.7	31.7	6.12	6.10	85.6	85.3	5.07	5.10		5.07	5.10		8.1	8.0
						31.7		6.07		84.9		5.13			7.8				
			Bottom	16.6	19.7	32.1	32.1	5.93	5.90	83.0	82.6	5.24	5.26		5.24	5.26		8.5	8.4
						32.1		5.87		82.1		5.28			8.3				
21/04/11	1525-1537	24/Fine	Surface	1.0	22.8	31.2	31.2	6.21	6.23	88.1	88.4	5.27	5.24	5.27	8.3	8.3	8.4		
						31.2		6.24		88.6		5.21			8.3				
			Middle	8.9	21.0	31.9	31.9	6.07	6.06	86.1	86.0	5.44	5.47		5.44	5.47		8.9	9.0
						31.8		6.05		85.9		5.49			9.0				
			Bottom	16.8	20.7	32.4	32.4	5.90	5.92	83.1	83.4	5.06	5.11		5.06	5.11		8.1	8.1
						32.4		5.93		83.6		5.15			8.0				
26/04/11	1825-1838	27/Fine	Surface	1.0	21.4	30.8	30.9	6.12	6.15	85.7	86.1	5.24	5.23	5.36	8.4	8.5	8.8		
						30.9		6.17		86.4		5.22			8.5				
			Middle	8.9	21.0	31.4	31.4	6.03	6.05	84.4	84.7	5.37	5.35		5.37	5.35		8.9	8.8
						31.3		6.07		84.9		5.33			8.6				
			Bottom	16.8	20.6	31.8	31.8	5.93	5.92	83.0	82.8	5.50	5.50		5.50	5.50		9.3	9.3
						31.7		5.90		82.6		5.49			9.3				
28/04/11	1055-1107	26/Cloudy	Surface	1.0	23.3	30.7	30.7	6.18	6.16	87.8	87.5	5.13	5.15	5.27	8.2	8.1	8.5		
						30.7		6.14		87.2		5.17			8.0				
			Middle	8.7	22.9	31.4	31.4	6.07	6.05	86.2	85.9	5.29	5.26		5.29	5.26		8.4	8.3
						31.4		6.02		85.5		5.22			8.1				
			Bottom	16.4	22.5	31.7	31.8	5.91	5.93	83.3	83.6	5.43	5.40		5.43	5.40		9.0	9.0
						31.9		5.95		83.9		5.37			9.0				
30/04/11	1130-1142	26/Cloudy	Surface	1.0	22.4	30.6	30.7	6.14	6.17	86.6	87.0	5.21	5.19	5.30	8.3	8.2	8.5		
						30.7		6.19		87.3		5.17			8.1				
			Middle	8.8	21.8	31.5	31.5	6.09	6.07	85.9	85.6	5.26	5.30		5.26	5.30		8.5	8.5
						31.4		6.05		85.3		5.34			8.4				
			Bottom	16.6	21.3	31.8	31.8	5.90	5.93	82.6	83.0	5.44	5.41		5.44	5.41		8.9	9.0
						31.7		5.96		83.4		5.37			9.0				

Monitoring Station : R8a

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/04/11	1254-1306	27/Sunny	Surface	1.0	18.9	30.6	30.6	6.16	6.18	85.6	85.8	5.12	5.15	5.26	8.2	8.1	8.3
				6.3		19.5		31.3		6.06		84.2			5.29		
			Middle	6.3	19.5	31.4	6.08	84.5	5.22	8.3							
				11.6		20.0	31.9	5.98	82.5	5.35	8.6						
			Bottom	11.6	20.0	31.9	5.95	82.1	5.39	8.4							
				31.9		5.95	82.1	5.39	8.4								
07/04/11	1634-1647	23/Fine	Surface	1.0	19.6	30.6	30.6	6.09	6.07	85.3	85.0	5.67	5.65	5.75	9.3	9.2	9.3
				6.3		19.2		31.4		5.94		83.2			5.71		
			Middle	6.3	19.2	31.5	5.91	82.7	5.79	9.2							
				11.8		18.6	31.9	5.82	81.5	5.88	9.5						
			Bottom	11.8	18.6	31.8	5.80	81.2	5.81	9.3							
				31.8		5.80	81.2	5.81	9.3								
09/04/11	1624-1636	23/Fine	Surface	1.0	21.3	31.3	31.4	6.21	6.24	88.1	88.6	5.34	5.38	5.45	8.5	8.7	8.9
				6.3		20.6		31.8		6.01		85.3			5.43		
			Middle	6.3	20.6	31.8	6.04	85.7	5.37	8.6							
				11.8		19.9	32.0	5.95	83.8	5.60	9.3						
			Bottom	11.8	19.9	32.1	5.98	84.3	5.52	9.3							
				32.1		5.98	84.3	5.52	9.3								
12/04/11	1835-1847	25/Cloudy	Surface	1.0	18.5	30.5	30.6	6.22	6.20	88.9	88.7	5.12	5.14	5.23	7.8	7.9	8.3
				6.3		18.9		31.2		6.10		86.6			5.21		
			Middle	6.3	18.9	31.3	6.07	86.2	5.24	8.3							
				12.2		19.4	31.8	5.95	84.5	5.31	8.7						
			Bottom	12.2	19.4	31.7	5.99	85.1	5.33	8.5							
				31.7		5.99	85.1	5.33	8.5								
14/04/11	1121-1135	25/Fine	Surface	1.0	19.8	30.7	30.8	6.22	6.25	87.0	87.4	4.83	4.86	4.97	7.6	7.7	7.9
				6.2		19.4		31.3		6.15		86.1			4.95		
			Middle	6.2	19.4	31.4	6.12	85.6	4.99	8.0							
				11.4		19.0	31.8	6.08	85.1	5.06	8.1						
			Bottom	11.4	19.0	31.8	6.01	84.1	5.10	8.0							
				31.8		6.01	84.1	5.10	8.0								
16/04/11	1143-1155	29/Cloudy	Surface	1.0	20.2	30.8	30.7	6.13	6.13	87.0	87.0	5.18	5.22	5.33	8.1	8.1	8.6
				6.3		19.9		30.6		6.12		86.9			5.25		
			Middle	6.3	19.9	31.4	6.03	85.0	5.34	8.8							
				11.8		19.5	31.4	6.04	85.2	5.30	8.7						
			Bottom	11.8	19.5	31.6	5.95	83.9	5.49	9.0							
				31.7		5.92	83.5	5.41	8.8								
19/04/11	1353-1407	26/Fine	Surface	1.0	20.8	30.7	30.8	6.25	6.27	87.5	87.8	4.81	4.84	4.87	7.9	7.8	7.8
				6.3		20.4		31.5		6.20		86.8			4.73		
			Middle	6.3	20.4	31.4	6.14	85.9	4.84	8.1							
				11.6		19.8	31.8	6.03	84.4	4.95	7.4						
			Bottom	11.6	19.8	31.9	6.00	84.0	5.01	7.6							
				31.9		6.00	84.0	5.01	7.6								
21/04/11	1544-1556	24/Fine	Surface	1.0	22.7	31.1	31.2	6.19	6.17	87.8	87.6	4.94	4.91	5.30	7.8	7.8	8.2
				6.3		21.0		31.9		6.03		85.6			5.43		
			Middle	6.3	21.0	32.0	6.07	86.1	5.38	7.9							
				11.8		20.9	32.1	5.85	82.4	5.55	9.3						
			Bottom	11.8	20.9	32.2	5.88	82.9	5.62	9.1							
				32.2		5.88	82.9	5.62	9.1								
26/04/11	1838-1850	27/Fine	Surface	1.0	21.4	30.7	30.7	6.17	6.16	86.4	86.3	5.09	5.13	5.24	8.1	8.1	8.3
				6.1		20.9		31.3		5.95		83.3			5.36		
			Middle	6.1	20.9	31.4	6.02	84.3	5.33	8.8							
				11.2		20.5	31.9	5.82	81.5	5.29	8.1						
			Bottom	11.2	20.5	31.8	5.84	81.8	5.20	8.0							
				31.8		5.84	81.8	5.20	8.0								
28/04/11	1113-1125	27/Cloudy	Surface	1.0	23.3	30.7	30.8	6.16	6.15	87.5	87.3	5.22	5.19	5.29	8.5	8.4	8.6
				6.3		22.9		31.4		6.03		85.6			5.31		
			Middle	6.3	22.9	31.3	6.04	85.8	5.26	8.6							
				11.6		22.7	31.7	5.97	84.8	5.38	8.5						
			Bottom	11.6	22.7	31.8	5.94	84.3	5.41	8.7							
				31.8		5.94	84.3	5.41	8.7								
30/04/11	1149-1201	26/Cloudy	Surface	1.0	22.4	30.7	30.7	6.16	6.15	86.9	86.7	5.25	5.22	5.34	8.6	8.6	8.5
				6.2		21.9		31.3		6.01		84.7			5.32		
			Middle	6.2	21.9	31.4	6.07	85.6	5.38	8.0							
				11.4		21.2	31.7	5.93	83.6	5.47	8.9						
			Bottom	11.4	21.2	31.8	5.89	83.0	5.42	8.7							
				31.8		5.89	83.0	5.42	8.7								

Monitoring Station : R15

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)				
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average		
02/04/11	1004-1015	20/Sunny	Surface	1.0	18.9	30.6	30.7	5.96	5.97	82.8	83.0	5.26	5.24	5.35	8.4	8.4	8.7		
						30.7		5.98		83.1		5.22			8.3				
			Middle	5.7	19.4	31.4	31.4	5.87	5.86	81.6	81.5	5.36	5.34		5.36	5.34		8.5	8.6
						31.4		5.85		81.3		5.31			8.7				
			Bottom	10.4	19.9	31.9	31.9	5.76	5.77	79.5	79.7	5.48	5.46		5.48	5.46		9.0	9.1
						31.9		5.78		79.8		5.44			9.1				
07/04/11	1354-1406	24/Fine	Surface	1.0	19.8	30.4	30.5	6.19	6.18	86.7	86.6	5.36	5.34	5.55	8.7	8.6	8.9		
						30.5		6.17		86.4		5.31			8.5				
			Middle	5.4	19.3	31.5	31.6	6.10	6.06	85.4	84.9	5.45	5.43		5.45	5.43		9.0	8.9
						31.6		6.02		84.3		5.40			8.8				
			Bottom	9.8	18.5	32.1	32.2	5.94	5.92	83.2	82.9	5.87	5.88		5.87	5.88		9.3	9.2
						32.2		5.90		82.6		5.89			9.1				
09/04/11	1334-1345	23/Fine	Surface	1.0	21.2	31.2	31.2	6.19	6.17	87.8	87.6	5.09	5.05	5.05	8.0	8.1	8.0		
						31.1		6.15		87.3		5.01			8.2				
			Middle	5.6	20.2	31.6	31.7	6.11	6.09	86.7	86.4	4.98	5.02		4.98	5.02		7.6	7.7
						31.7		6.07		86.1		5.05			7.8				
			Bottom	10.4	20.0	32.0	32.0	6.03	6.05	85.6	85.9	5.12	5.10		5.12	5.10		8.2	8.2
						31.9		6.07		86.1		5.07			8.2				
12/04/11	1604-1616	25/Cloudy	Surface	1.0	18.5	30.5	30.5	6.13	6.15	87.7	87.9	5.22	5.20	5.30	7.9	8.0	8.3		
						30.5		6.16		88.1		5.18			8.0				
			Middle	5.6	18.9	31.2	31.3	6.04	6.03	85.8	85.6	5.27	5.29		5.27	5.29		8.4	8.3
						31.3		6.01		85.3		5.31			8.2				
			Bottom	10.2	19.5	31.8	31.8	5.86	5.89	83.2	83.6	5.38	5.40		5.38	5.40		8.7	8.6
						31.7		5.91		83.9		5.42			8.5				
14/04/11	0842-0856	24/Fine	Surface	1.0	19.6	30.8	30.8	6.08	6.06	85.1	84.8	5.02	5.05	5.20	8.0	8.0	8.2		
						30.8		6.04		84.5		5.07			8.0				
			Middle	5.3	19.4	31.0	31.1	6.12	6.09	85.6	85.2	5.15	5.18		5.15	5.18		8.0	8.1
						31.1		6.06		84.8		5.21			8.2				
			Bottom	9.6	19.0	31.6	31.6	5.89	5.87	82.4	82.1	5.34	5.37		5.34	5.37		8.5	8.6
						31.5		5.84		81.7		5.40			8.7				
16/04/11	0903-0914	24/Cloudy	Surface	1.0	20.2	30.8	30.8	5.92	5.94	84.1	84.4	5.24	5.26	5.37	8.3	8.2	8.6		
						30.7		5.96		84.6		5.28			8.1				
			Middle	5.6	19.8	31.3	31.3	5.84	5.83	82.9	82.8	5.33	5.36		5.33	5.36		8.5	8.5
						31.3		5.82		82.6		5.39			8.5				
			Bottom	10.2	19.6	31.6	31.7	5.72	5.74	80.7	80.9	5.53	5.50		5.53	5.50		9.3	9.2
						31.7		5.75		81.1		5.46			9.0				
19/04/11	1109-1123	25/Fine	Surface	1.0	20.5	30.6	30.7	6.08	6.05	85.1	84.7	4.99	4.97	5.19	7.8	7.9	8.4		
						30.7		6.02		84.2		4.95			8.0				
			Middle	5.6	20.2	31.1	31.2	5.92	5.94	82.8	83.1	5.16	5.18		5.16	5.18		8.4	8.4
						31.2		5.96		83.4		5.20			8.3				
			Bottom	10.2	19.8	31.6	31.7	5.83	5.82	81.6	81.4	5.41	5.43		5.41	5.43		8.7	8.9
						31.7		5.80		81.2		5.45			9.0				
21/04/11	1304-1315	24/Fine	Surface	1.0	22.9	31.1	31.2	6.19	6.17	87.8	87.5	5.21	5.19	5.09	8.4	8.3	8.1		
						31.2		6.14		87.1		5.17			8.2				
			Middle	5.7	21.0	31.9	31.9	6.10	6.12	86.6	86.9	5.01	5.05		5.01	5.05		8.0	8.1
						31.9		6.14		87.1		5.09			8.1				
			Bottom	10.4	20.7	32.0	32.1	5.79	5.81	81.6	81.9	4.99	5.03		4.99	5.03		8.0	7.9
						32.2		5.83		82.2		5.06			7.7				
26/04/11	1616-1627	28/Fine	Surface	1.0	21.6	30.5	30.6	6.19	6.20	86.7	86.8	5.27	5.27	5.38	8.4	8.3	8.5		
						30.6		6.21		86.9		5.28			8.1				
			Middle	5.4	21.0	31.3	31.4	5.97	5.96	83.6	83.4	5.40	5.37		5.40	5.37		8.2	8.2
						31.4		5.94		83.2		5.33			8.2				
			Bottom	9.8	20.4	31.7	31.8	5.72	5.75	80.1	80.5	5.52	5.50		5.52	5.50		9.0	8.9
						31.8		5.77		80.8		5.48			8.8				
28/04/11	0833-0844	26/Cloudy	Surface	1.0	23.2	30.8	30.8	5.94	5.93	84.3	84.1	5.41	5.38	5.47	8.9	9.0	9.0		
						30.7		5.91		83.9		5.35			9.0				
			Middle	5.7	22.7	31.4	31.5	5.84	5.85	82.9	83.1	5.48	5.46		5.48	5.46		9.2	9.1
						31.5		5.86		83.2		5.44			9.0				
			Bottom	10.4	22.5	31.9	31.9	5.76	5.77	81.8	82.0	5.54	5.58		5.54	5.58		8.8	8.9
						31.9		5.78		82.1		5.61			8.9				
30/04/11	0904-0915	25/Cloudy	Surface	1.0	22.3	30.7	30.8	5.92	5.95	83.5	83.9	6.31	5.34	5.45	8.7	8.7	9.1		
						30.8		5.98		84.3		5.36			8.6				
			Middle	5.6	21.7	31.4	31.4	5.85	5.83	82.5	82.2	5.48	5.44		5.48	5.44		9.2	9.2
						31.4		5.81		81.9		5.40			9.2				
			Bottom	10.2	21.2	31.8	31.8	5.74	5.73	80.9	80.8	5.55	5.57		5.55	5.57		9.5	9.4
						31.7		5.72		80.7		5.59			9.3				

Monitoring Station : R16

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)				
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average		
02/04/11	0945-0956	20/Sunny	Surface	1.0	18.8	30.6	30.6	6.12	6.14	85.1	85.3	5.18	5.16	5.26	8.1	8.1	8.5		
						30.6		6.15		85.5		5.13			8.0				
			Middle	6.2	19.4	31.5	31.5	6.06	6.07	83.6	83.7	5.22	5.25		5.28	5.38		8.4	8.3
						31.4		6.07		83.8		5.28			8.2				
			Bottom	11.4	20.0	31.9	32.0	5.97	5.95	82.4	82.1	5.41	5.35		5.38	5.38		9.3	9.2
						32.0		5.93		81.8		5.35			9.0				
07/04/11	1331-1344	24/Fine	Surface	1.0	19.7	30.3	30.4	6.13	6.12	85.8	85.6	5.49	5.47	5.62	8.9	8.8	9.2		
						30.4		6.10		85.4		5.44			8.7				
			Middle	6.2	19.4	31.6	31.7	6.07	6.06	84.9	84.8	5.60	5.61		5.62	5.78		9.4	9.3
						31.7		6.05		84.7		5.62			9.2				
			Bottom	11.4	18.6	32.0	32.0	5.83	5.85	81.7	82.0	5.75	5.80		5.78	5.78		9.5	9.5
						32.0		5.87		82.2		5.80			9.5				
09/04/11	1315-1326	23/Fine	Surface	1.0	21.1	31.1	31.2	6.22	6.20	88.3	88.0	5.15	5.12	5.30	8.3	8.2	8.5		
						31.2		6.17		87.6		5.08			8.1				
			Middle	6.3	20.3	31.5	31.6	6.09	6.07	86.4	86.2	5.37	5.41		5.44	5.38		8.7	8.6
						31.6		6.05		85.9		5.44			8.5				
			Bottom	11.6	20.1	31.9	32.0	6.01	6.03	85.3	85.5	5.41	5.35		5.38	5.38		9.0	8.8
						32.0		6.04		85.7		5.35			8.6				
12/04/11	1546-1557	25/Cloudy	Surface	1.0	18.6	30.6	30.6	6.13	6.16	87.0	87.4	5.13	5.15	5.24	8.1	8.1	8.5		
						30.5		6.18		87.8		5.17			8.1				
			Middle	6.2	19.0	31.3	31.3	6.03	6.05	86.2	86.5	5.21	5.23		5.25	5.33		8.6	8.5
						31.2		6.06		86.7		5.25			8.4				
			Bottom	11.4	19.5	31.7	31.8	5.91	5.93	83.9	84.2	5.31	5.34		5.33	5.33		8.9	8.9
						31.8		5.95		84.5		5.34			8.9				
14/04/11	0820-0835	24/Fine	Surface	1.0	19.5	30.8	30.9	6.25	6.24	87.5	87.3	4.94	4.97	5.12	7.9	8.0	8.1		
						30.9		6.22		87.0		4.99			8.0				
			Middle	6.2	19.3	31.1	31.2	6.15	6.13	86.1	85.8	5.08	5.10		5.12	5.28		8.1	8.1
						31.2		6.11		85.5		5.12			8.0				
			Bottom	11.4	19.0	31.7	31.7	6.01	6.03	84.1	84.4	5.25	5.31		5.28	5.28		8.3	8.2
						31.7		6.05		84.7		5.31			8.1				
16/04/11	0845-0856	24/Cloudy	Surface	1.0	20.1	30.7	30.7	6.14	6.15	87.2	87.4	5.22	5.19	5.30	8.4	8.3	8.4		
						30.6		6.16		87.5		5.16			8.2				
			Middle	6.3	19.8	31.3	31.4	6.05	6.07	85.9	86.1	5.32	5.31		5.31	5.39		8.6	8.6
						31.4		6.08		86.3		5.29			8.5				
			Bottom	11.6	19.5	31.8	31.8	5.96	5.95	84.0	83.9	5.37	5.41		5.39	5.39		8.4	8.3
						31.7		5.94		83.8		5.41			8.2				
19/04/11	1049-1103	25/Fine	Surface	1.0	20.4	30.7	30.7	6.25	6.27	87.5	87.8	4.87	4.90	5.07	8.0	7.9	8.1		
						30.7		6.29		88.0		4.92			7.7				
			Middle	5.8	20.1	31.3	31.4	6.18	6.16	86.5	86.2	4.99	5.02		5.05	5.29		8.0	8.1
						31.4		6.13		85.8		5.05			8.2				
			Bottom	10.6	19.6	31.8	31.8	6.02	6.04	84.2	84.5	5.26	5.31		5.29	5.29		8.3	8.3
						31.8		6.06		84.8		5.31			8.3				
21/04/11	1245-1256	24/Fine	Surface	1.0	22.9	31.0	31.1	6.17	6.16	87.6	87.4	4.74	4.79	5.09	7.6	7.7	8.1		
						31.1		6.14		87.1		4.83			7.8				
			Middle	6.3	20.9	31.8	31.8	6.05	6.07	85.3	85.5	5.17	5.14		5.10	5.35		8.2	8.1
						31.7		6.08		85.7		5.10			8.0				
			Bottom	11.6	20.7	32.2	32.2	5.85	5.87	82.4	82.7	5.38	5.31		5.35	5.35		8.4	8.5
						32.1		5.89		83.0		5.31			8.5				
26/04/11	1552-1605	28/Fine	Surface	1.0	21.5	30.6	30.7	6.11	6.13	85.5	85.8	5.16	5.16	5.32	8.1	8.1	8.4		
						30.7		6.15		86.1		5.15			8.0				
			Middle	6.1	21.0	31.4	31.4	5.99	6.00	83.9	84.0	5.26	5.29		5.29	5.52		8.3	8.2
						31.3		6.01		84.1		5.31			8.1				
			Bottom	11.2	20.5	31.9	31.9	5.89	5.87	82.5	82.2	5.49	5.54		5.52	5.52		8.8	9.0
						31.8		5.85		81.9		5.54			9.1				
28/04/11	0815-0826	26/Cloudy	Surface	1.0	23.2	30.7	30.7	6.17	6.16	87.6	87.5	5.26	5.24	5.33	8.1	8.1	8.4		
						30.6		6.15		87.3		5.22			8.0				
			Middle	6.2	22.9	31.3	31.4	6.05	6.07	85.3	85.6	5.32	5.34		5.34	5.42		8.5	8.4
						31.4		6.09		85.9		5.35			8.2				
			Bottom	11.4	22.6	31.7	31.7	5.98	5.97	84.3	84.1	5.45	5.39		5.42	5.42		8.7	8.8
						31.7		5.95		83.9		5.39			8.8				
30/04/11	0845-0856	25/Cloudy	Surface	1.0	22.3	30.6	30.6	6.12	6.14	86.3	86.5	5.21	5.20	5.30	7.9	8.0	8.3		
						30.6		6.15		86.7		5.18			8.0				
			Middle	6.3	21.8	31.3	31.4	6.08	6.05	85.1	84.7	5.33	5.30		5.30	5.40		8.4	8.5
						31.5		6.02		84.3		5.27			8.6				
			Bottom	11.6	21.3	31.7	31.8	5.91	5.93	82.7	83.0	5.37	5.42		5.40	5.40		8.7	8.6
						31.8		5.95		83.3		5.42			8.4				

Monitoring Station : R17

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/04/11	0930-0942	20/Sunny	Surface	1.0	18.8	30.6	30.6	6.22	6.21	86.5	86.4	5.11	5.13	5.24	8.1	8.1	8.2
						30.5		6.20		86.2		5.15			8.0		
			Middle	6.0	19.4	31.3	31.4	6.07	6.06	83.8	83.6	5.26	5.23		8.3	8.2	
						31.4		6.04		83.4		5.20			8.0		
			Bottom	11.0	19.9	31.9	31.9	5.96	5.98	82.2	82.5	5.34	5.37		8.5	8.5	
						31.8		5.99		82.7		5.39			8.4		
07/04/11	1315-1328	24/Fine	Surface	1.0	19.8	30.4	30.5	6.20	6.19	86.8	86.6	5.39	5.41	5.57	8.4	8.5	8.9
						30.5		6.17		86.4		5.42			8.6		
			Middle	5.9	19.3	31.7	31.7	6.01	6.02	84.1	84.3	5.54	5.56		8.9	8.9	
						31.6		6.03		84.4		5.57			8.8		
			Bottom	10.8	18.5	32.1	32.1	5.95	5.97	83.3	83.6	5.79	5.75		9.5	9.4	
						32.0		5.99		83.9		5.71			9.2		
09/04/11	1300-1312	23/Fine	Surface	1.0	21.0	31.1	31.1	6.17	6.16	87.6	87.4	5.07	5.11	5.21	8.0	8.0	8.1
						31.0		6.14		87.1		5.14			7.9		
			Middle	5.9	20.4	31.6	31.7	6.02	6.04	85.4	85.7	5.25	5.23		8.3	8.2	
						31.7		6.05		85.9		5.21			8.0		
			Bottom	10.8	20.0	31.8	31.9	5.99	6.01	84.4	84.6	5.33	5.30		8.2	8.3	
						31.9		6.02		84.8		5.27			8.4		
12/04/11	1530-1542	25/Cloudy	Surface	1.0	18.6	30.7	30.7	6.21	6.19	86.2	87.9	5.15	5.17	5.26	8.0	8.1	8.4
						30.6		6.17		87.6		5.18			8.2		
			Middle	5.9	18.9	31.2	31.2	6.10	6.08	87.2	86.9	5.24	5.26		8.4	8.3	
						31.2		6.05		86.5		5.27			8.2		
			Bottom	10.8	19.5	31.8	31.8	5.94	5.96	84.3	84.6	5.33	5.35		8.8	8.9	
						31.8		5.97		84.8		5.36			9.0		
14/04/11	0800-0815	24/Fine	Surface	1.0	19.6	30.9	30.9	6.28	6.26	87.9	87.6	4.91	4.94	5.08	7.8	7.9	8.1
						30.9		6.24		87.3		4.96			8.0		
			Middle	5.8	19.3	31.2	31.3	6.20	6.18	86.8	86.5	5.05	5.07		8.1	8.1	
						31.3		6.16		86.2		5.09			8.0		
			Bottom	10.6	19.0	31.6	31.7	6.03	6.05	84.4	84.7	5.20	5.23		8.3	8.3	
						31.7		6.07		84.9		5.26			8.3		
16/04/11	0830-0842	24/Cloudy	Surface	1.0	20.2	30.7	30.7	6.21	6.20	88.2	88.0	5.13	5.15	5.27	8.1	8.1	8.4
						30.7		6.18		87.8		5.17			8.0		
			Middle	6.2	19.8	31.3	31.3	6.04	6.05	85.2	85.3	5.30	5.27		8.7	8.6	
						31.2		6.06		85.4		5.23			8.5		
			Bottom	11.4	19.5	31.7	31.8	5.93	5.96	83.6	84.0	5.38	5.41		8.2	8.4	
						31.8		5.98		84.3		5.43			8.6		
19/04/11	1030-1044	25/Fine	Surface	1.0	20.5	30.6	30.7	6.18	6.20	86.5	86.8	4.84	4.87	5.04	7.6	7.6	8.0
						30.7		6.22		87.0		4.89			7.5		
			Middle	6.0	20.1	31.3	31.3	6.11	6.10	85.5	85.3	4.96	4.99		7.9	8.0	
						31.3		6.08		85.1		5.01			8.0		
			Bottom	11.0	19.7	31.8	31.8	5.90	5.92	82.6	82.9	5.23	5.26		8.5	8.4	
						31.7		5.94		83.1		5.28			8.2		
21/04/11	1230-1242	24/Fine	Surface	1.0	22.8	30.9	31.0	6.20	6.18	88.0	87.7	4.90	4.92	5.23	7.7	7.8	8.5
						31.0		6.15		87.3		4.94			7.8		
			Middle	5.9	20.9	31.8	31.8	6.04	6.06	85.1	85.3	5.24	5.21		8.4	8.3	
						31.8		6.07		85.5		5.17			8.2		
			Bottom	10.8	20.6	32.1	32.1	5.94	5.92	83.7	83.4	5.60	5.58		9.5	9.4	
						32.1		5.89		83.0		5.55			9.2		
26/04/11	1530-1542	28/Fine	Surface	1.0	21.5	30.5	30.6	6.07	6.06	84.9	84.8	5.23	5.22	5.35	8.7	8.6	8.6
						30.6		6.04		84.6		5.20			8.5		
			Middle	5.7	20.9	31.4	31.5	5.94	5.94	83.2	83.1	5.42	5.40		8.2	8.4	
						31.5		5.93		83.0		5.38			8.5		
			Bottom	10.4	20.5	31.8	31.8	5.78	5.77	80.9	80.8	5.44	5.42		9.0	9.0	
						31.8		5.76		80.6		5.40			8.9		
28/04/11	0800-0812	26/Cloudy	Surface	1.0	23.2	30.8	30.8	6.11	6.13	86.8	87.0	5.19	5.17	5.28	8.1	8.1	8.3
						30.8		6.14		87.2		5.14			8.0		
			Middle	6.0	22.8	31.4	31.4	6.03	6.03	85.0	85.0	5.30	5.27		8.6	8.4	
						31.4		6.02		84.9		5.23			8.2		
			Bottom	11.0	22.5	31.8	31.8	5.96	5.94	84.0	83.8	5.38	5.41		8.5	8.4	
						31.7		5.92		83.5		5.43			8.3		
30/04/11	0830-0842	25/Cloudy	Surface	1.0	22.3	30.7	30.7	6.18	6.16	87.1	86.8	5.29	5.26	5.37	8.6	8.6	8.9
						30.6		6.13		86.4		5.23			8.6		
			Middle	6.2	21.8	31.4	31.4	6.03	6.05	85.0	85.2	5.34	5.36		8.8	8.7	
						31.3		6.06		85.4		5.38			8.5		
			Bottom	11.4	21.2	31.7	31.7	5.94	5.96	83.8	84.0	5.53	5.50		9.5	9.3	
						31.7		5.97		84.2		5.46			9.1		

Monitoring Station : R28

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)			
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average	
02/04/11	1141-1152	23/Sunny	Surface	1.0	18.8	30.6	30.6	6.13	6.15	85.2	85.4	5.19	5.21	5.32	8.3	8.2	8.6	
				5.6	19.3	31.4	31.4	6.09	6.08	84.7	84.6	5.35	5.32		8.7			
			Middle	10.2	19.9	31.8	31.8	5.96	5.97	82.2	82.4	5.46	5.44		8.9			9.0
				19.3	19.3	31.6	31.7	5.93	5.95	83.0	83.2	5.64	5.67		9.0			9.0
			Bottom	1.0	19.7	30.4	30.5	6.01	6.03	84.1	84.4	5.50	5.53		9.4			9.3
				5.4	19.3	31.7	31.7	5.96	5.95	83.4	83.2	5.69	5.67		9.2			9.3
07/04/11	1527-1540	24/Fine	Surface	1.0	19.7	30.4	30.5	6.01	6.03	84.1	84.4	5.50	5.53	5.67	9.0	8.9	9.2	
				5.4	19.3	31.7	31.7	5.96	5.95	83.4	83.2	5.69	5.67		9.4			
			Middle	9.8	18.7	32.1	32.2	5.95	5.97	83.3	83.6	5.80	5.83		9.5			9.4
				10.2	18.7	32.2	32.2	5.99	5.97	83.9	83.6	5.85	5.83		9.2			9.4
			Bottom	1.0	21.3	31.3	31.3	6.22	6.20	88.3	88.0	5.01	5.04		8.0			8.1
				5.6	20.4	31.6	31.7	6.07	6.06	86.1	85.9	5.49	5.52		8.9			9.0
09/04/11	1511-1522	23/Fine	Surface	1.0	21.3	31.3	31.3	6.22	6.20	88.3	88.0	5.01	5.04	5.17	8.2	8.1	8.6	
				5.6	20.4	31.6	31.7	6.07	6.06	86.1	85.9	5.49	5.52		9.1			
			Middle	10.2	20.1	32.0	32.0	5.97	5.96	84.1	83.9	4.97	4.94		8.5			8.6
				19.3	20.1	31.9	32.0	5.94	5.96	83.7	83.9	4.91	4.94		8.7			8.6
			Bottom	1.0	18.6	30.7	30.7	6.22	6.21	87.7	87.5	5.17	5.16		8.2			8.2
				5.3	19.0	31.2	31.3	6.12	6.11	86.9	86.7	5.24	5.26		8.7			8.8
12/04/11	1718-1730	25/Cloudy	Surface	1.0	18.6	30.7	30.7	6.22	6.21	87.7	87.5	5.17	5.16	5.26	8.2	8.2	8.5	
				5.3	19.0	31.2	31.3	6.12	6.11	86.9	86.7	5.24	5.26		8.7			
			Middle	9.6	19.5	31.8	31.9	5.94	5.96	84.9	85.2	5.37	5.36		8.4			8.4
				10.2	19.5	31.9	31.9	5.97	5.96	85.4	85.2	5.34	5.36		8.4			8.4
			Bottom	1.0	19.8	30.8	30.8	6.22	6.24	87.1	87.3	4.88	4.91		7.7			7.9
				5.4	19.6	31.0	31.1	6.18	6.17	86.5	86.3	5.02	5.04		8.2			8.2
14/04/11	1001-1015	25/Fine	Surface	1.0	19.8	30.8	30.8	6.22	6.24	87.1	87.3	4.88	4.91	5.03	8.0	8.0	8.0	
				5.4	19.6	31.0	31.1	6.18	6.17	86.5	86.3	5.02	5.04		8.2			
			Middle	9.8	19.2	31.5	31.6	6.02	6.05	84.2	84.6	5.13	5.15		8.1			8.1
				10.2	19.2	31.6	31.6	6.07	6.05	84.9	84.6	5.17	5.15		8.2			8.1
			Bottom	1.0	20.2	30.7	30.7	6.16	6.17	87.5	87.7	5.20	5.18		8.0			8.4
				5.8	19.9	31.2	31.3	6.08	6.06	86.3	86.1	5.29	5.27		8.2			8.2
16/04/11	1033-1044	26/Cloudy	Surface	1.0	20.2	30.7	30.7	6.16	6.17	87.5	87.7	5.20	5.18	5.28	8.4	8.4	8.4	
				5.8	19.9	31.2	31.3	6.08	6.06	86.3	86.1	5.29	5.27		8.2			
			Middle	10.6	19.6	31.7	31.7	5.95	5.97	83.9	84.1	5.36	5.40		8.4			8.6
				19.6	19.6	31.6	31.7	5.98	5.97	84.3	84.1	5.44	5.40		8.7			8.6
			Bottom	1.0	20.5	30.7	30.7	6.24	6.27	87.3	87.8	4.86	4.87		7.6			7.7
				5.6	20.3	30.9	31.0	6.20	6.18	86.8	86.5	4.95	4.93		7.8			7.9
19/04/11	1233-1246	26/Fine	Surface	1.0	20.5	30.7	30.7	6.24	6.27	87.3	87.8	4.86	4.87	4.98	8.0	8.0	8.0	
				5.6	20.3	30.9	31.0	6.20	6.18	86.8	86.5	4.95	4.93		8.0			
			Middle	10.2	19.9	31.6	31.6	6.06	6.08	84.8	85.0	5.13	5.15		8.3			8.5
				19.9	19.9	31.6	31.6	6.09	6.08	85.2	85.0	5.17	5.15		8.6			8.5
			Bottom	1.0	22.8	31.3	31.3	6.17	6.16	87.6	87.4	5.17	5.20		8.1			8.1
				5.7	21.0	32.0	32.0	5.98	5.97	84.3	84.1	5.09	5.05		7.8			7.8
21/04/11	1431-1442	24/Fine	Surface	1.0	22.8	31.3	31.3	6.17	6.16	87.6	87.4	5.17	5.20	5.11	8.1	8.1	8.1	
				5.7	21.0	32.0	32.0	5.98	5.97	84.3	84.1	5.09	5.05		7.8			
			Middle	10.4	20.8	32.4	32.4	5.81	5.83	81.9	82.2	5.11	5.09		8.4			8.3
				19.9	20.8	32.4	32.4	5.85	5.83	82.4	82.2	5.07	5.09		8.2			8.3
			Bottom	1.0	21.4	30.8	30.8	6.12	6.15	85.7	86.1	5.10	5.07		8.0			7.9
				5.4	20.9	31.4	31.5	6.07	6.05	84.9	84.6	5.12	5.14		7.7			7.9
26/04/11	1741-1753	27/Fine	Surface	1.0	21.4	30.8	30.8	6.12	6.15	85.7	86.1	5.10	5.07	5.15	8.1	8.1	8.1	
				5.4	20.9	31.4	31.5	6.07	6.05	84.9	84.6	5.12	5.14		8.2			
			Middle	9.8	20.6	31.9	31.9	5.93	5.95	83.0	83.2	5.26	5.25		8.4			8.5
				10.2	20.6	31.8	31.9	5.96	5.95	83.4	83.2	5.24	5.25		8.5			8.5
			Bottom	1.0	23.2	30.8	30.8	6.15	6.13	87.3	87.1	5.33	5.30		8.7			8.6
				5.6	22.8	31.5	31.5	6.02	6.03	85.5	85.7	5.36	5.38		8.4			8.5
28/04/11	1003-1014	26/Cloudy	Surface	1.0	23.2	30.8	30.8	6.15	6.13	87.3	87.1	5.33	5.30	5.39	8.5	8.5	8.7	
				5.6	22.8	31.5	31.5	6.02	6.03	85.5	85.7	5.36	5.38		8.5			
			Middle	10.2	22.6	31.7	31.8	5.89	5.91	83.6	83.9	5.52	5.50		9.1			9.1
				19.9	22.6	31.8	31.8	5.92	5.91	84.1	83.9	5.47	5.50		9.0			9.1
			Bottom	1.0	22.3	30.8	30.8	6.14	6.16	86.0	86.2	5.27	5.25		8.1			8.3
				5.8	21.9	31.3	31.3	6.06	6.04	84.8	84.5	5.31	5.35		8.4			8.5
30/04/11	1037-1048	26/Cloudy	Surface	1.0	22.3	30.8	30.8	6.14	6.16	86.0	86.2	5.27	5.25	5.35	8.3	8.3	8.6	
				5.8	21.9	31.3	31.3	6.06	6.04	84.8	84.5	5.31	5.35		8.6			
			Middle	10.6	21.3	31.6	31.7	5.94	5.93	83.2	83.0	5.46	5.45		8.3			8.5
				19.9	21.3	31.6	31.7	5.91	5.93	82.7	83.0	5.43	5.45		9.0			9.1
			Bottom	1.0	21.3	31.8	31.7	5.91	5.93	82.7	83.0	5.43	5.45		9.2			9.1
				10.6	21.3	31.8	31.7	5.91	5.93	82.7	83.0	5.43	5.45		9.2			9.1

Mid-Ebb Tide

Monitoring Station : R29

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/04/11	1206-1217	23/Sunny	Surface	1.0	18.9	30.6	30.7	5.95	5.94	82.7	82.6	5.26	5.29	5.39	8.2	8.3	8.6
						30.7		5.93		82.4		5.31			8.4		
			Middle	8.6	19.4	31.3	31.4	5.83	5.84	80.5	80.6	5.40	5.37		8.8	8.7	
						31.5		5.85		80.7		5.34			8.6		
			Bottom	16.2	20.0	31.8	31.9	5.77	5.75	79.6	79.4	5.48	5.51		8.7	8.9	
						31.9		5.73		79.1		5.53			9.0		
07/04/11	1543-1555	24/Fine	Surface	1.0	19.8	30.5	30.6	5.91	5.93	82.7	83.0	5.37	5.34	5.68	8.3	8.3	9.0
						30.6		5.94		83.2		5.31			8.3		
			Middle	8.6	19.4	31.7	31.8	5.86	5.84	82.0	81.8	5.72	5.73		9.0	9.1	
						31.8		5.82		81.5		5.74			9.2		
			Bottom	16.2	18.6	32.2	32.3	5.91	5.93	82.7	83.0	5.98	5.96		9.6	9.5	
						32.3		5.94		83.2		5.94			9.4		
09/04/11	1536-1547	23/Fine	Surface	1.0	21.3	31.3	31.3	6.19	6.17	87.8	87.6	5.17	5.20	5.05	8.2	8.3	8.0
						31.2		6.15		87.3		5.22			8.4		
			Middle	8.4	20.3	31.7	31.7	6.09	6.08	86.4	86.2	5.01	5.04		8.0	8.0	
						31.7		6.06		86.0		5.07			8.0		
			Bottom	15.8	20.0	31.9	31.9	6.05	6.07	85.9	86.1	4.90	4.93		7.6	7.8	
						31.8		6.08		86.3		4.95			7.9		
12/04/11	1734-1748	25/Cloudy	Surface	1.0	18.5	30.5	30.6	6.17	6.19	87.6	87.9	5.14	5.16	5.26	8.1	8.1	8.5
						30.6		6.21		88.2		5.18			8.0		
			Middle	8.1	19.0	31.4	31.4	6.07	6.09	86.2	86.4	5.27	5.26		8.4	8.5	
						31.3		6.10		86.6		5.25			8.6		
			Bottom	15.2	19.6	31.9	32.0	5.91	5.89	84.5	84.2	5.35	5.37		8.9	9.0	
						32.0		5.86		83.8		5.38			9.0		
14/04/11	1019-1035	25/Fine	Surface	1.0	19.7	30.8	30.8	6.10	6.08	85.4	85.1	5.14	5.17	5.33	8.2	8.3	8.7
						30.8		6.05		84.7		5.20			8.4		
			Middle	8.2	19.2	31.2	31.3	5.89	5.87	82.4	82.1	5.32	5.34		8.5	8.5	
						31.3		5.84		81.7		5.36			8.5		
			Bottom	15.4	18.7	31.9	31.9	5.70	5.73	79.8	80.2	5.45	5.47		9.3	9.2	
						31.9		5.75		80.5		5.49			9.0		
16/04/11	1056-1107	26/Cloudy	Surface	1.0	20.1	30.7	30.8	5.93	5.95	84.2	84.4	5.23	5.26	5.38	8.5	8.5	8.9
						30.8		5.96		84.6		5.29			8.5		
			Middle	8.7	19.8	31.4	31.4	5.84	5.86	82.9	83.2	5.40	5.39		8.9	9.0	
						31.4		5.88		83.5		5.37			9.1		
			Bottom	16.4	19.5	31.8	31.8	5.74	5.73	80.9	80.8	5.51	5.49		9.2	9.2	
						31.7		5.72		80.7		5.46			9.2		
19/04/11	1255-1309	26/Fine	Surface	1.0	20.6	30.6	30.7	6.08	6.11	85.1	85.5	5.06	5.08	5.26	8.0	8.0	8.1
						30.7		6.14		85.9		5.10			8.0		
			Middle	8.7	20.2	31.6	31.6	6.00	5.97	84.0	83.6	5.26	5.28		8.2	8.1	
						31.6		5.94		83.1		5.29			8.0		
			Bottom	16.4	19.7	32.0	32.1	5.81	5.83	81.3	81.5	5.40	5.43		8.1	8.1	
						32.1		5.84		81.7		5.46			8.0		
21/04/11	1456-1507	24/Fine	Surface	1.0	22.9	31.3	31.3	6.25	6.23	88.7	88.4	5.09	5.05	5.13	8.0	8.0	8.3
						31.2		6.21		88.1		5.01			8.0		
			Middle	8.4	21.0	31.9	32.0	6.10	6.07	86.6	86.2	5.02	5.06		8.3	8.3	
						32.0		6.04		85.7		5.09			8.2		
			Bottom	15.8	20.7	32.3	32.4	5.98	5.96	84.9	84.6	5.33	5.29		8.5	8.6	
						32.4		5.94		84.3		5.24			8.6		
26/04/11	1756-1810	27/Fine	Surface	1.0	21.3	30.6	30.7	6.01	6.05	84.1	84.6	5.28	5.25	5.40	8.1	8.1	8.6
						30.7		6.08		85.1		5.21			8.1		
			Middle	8.6	21.0	31.3	31.3	6.04	6.05	84.5	84.6	5.38	5.41		8.7	8.6	
						31.2		6.05		84.7		5.43			8.5		
			Bottom	16.2	20.5	31.9	31.9	5.88	5.85	82.3	81.9	5.57	5.55		9.3	9.2	
						31.8		5.82		81.5		5.52			9.0		
28/04/11	1026-1037	26/Cloudy	Surface	1.0	23.3	30.6	30.7	5.92	5.94	84.1	84.3	5.42	5.40	5.50	8.7	8.8	8.9
						30.7		5.95		84.5		5.37			8.9		
			Middle	8.5	22.9	31.5	31.4	5.84	5.83	82.9	82.8	5.46	5.50		8.8	8.7	
						31.3		5.82		82.6		5.54			8.6		
			Bottom	16.0	22.6	31.9	31.9	5.73	5.74	81.4	81.6	5.59	5.61		9.1	9.2	
						31.8		5.75		81.7		5.63			9.2		
30/04/11	1101-1112	26/Cloudy	Surface	1.0	22.4	30.7	30.7	5.93	5.96	83.6	84.1	5.42	5.39	5.50	8.7	8.9	9.0
						30.7		5.99		84.5		5.35			9.0		
			Middle	8.6	21.9	31.3	31.4	5.83	5.84	82.2	82.4	5.48	5.50		8.8	8.9	
						31.4		5.85		82.5		5.52			8.9		
			Bottom	16.2	21.3	31.7	31.8	5.78	5.76	81.5	81.2	5.65	5.62		9.4	9.3	
						31.8		5.74		80.9		5.59			9.2		

Monitoring Station : C1

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/04/11	1030-1042	20/Sunny	Surface	1.0	18.8	30.5	30.6	6.17	6.16	85.8	86.7	5.15	5.18	5.28	8.2	8.3	8.6
				7.1	19.5	30.6		6.15		85.5		5.21			8.4		
			Middle	31.3	31.4	6.05	6.07	83.5	83.7	5.30	5.27	8.5	8.4				
				31.4		6.08		83.9		5.24		8.2					
			Bottom	13.2	20.0	31.8	31.9	5.99	5.98	82.7	82.6	5.36	5.38		9.0	9.0	
				31.9	5.97	82.4		5.40		9.0							
07/04/11	1420-1433	24/Fine	Surface	1.0	19.9	30.3	30.3	6.15	6.17	86.1	86.3	5.38	5.42	5.59	8.7	8.8	9.1
				7.1	19.4	30.3		6.18		86.5		5.46			8.9		
			Middle	31.7	31.7	5.97	5.97	83.6	83.5	5.59	5.61	9.0	9.1				
				31.7		5.96		83.4		5.63		9.2					
			Bottom	12.8	18.6	32.0	32.1	5.81	5.85	81.3	81.8	5.73	5.74		9.4	9.5	
				32.1	5.88	82.3		5.74		9.5							
09/04/11	1400-1412	23/Fine	Surface	1.0	21.2	31.2	31.2	6.15	6.13	87.3	87.0	5.21	5.26	5.27	8.5	8.4	8.4
				7.1	20.3	31.2		6.11		86.7		5.30			8.3		
			Middle	31.7	31.7	6.01	6.03	85.3	85.5	5.34	5.31	8.6	8.7				
				31.6		6.04		85.7		5.27		8.8					
			Bottom	12.8	19.9	32.0	32.0	5.95	5.93	83.8	83.6	5.27	5.24		8.3	8.2	
				32.0	5.91	83.3		5.21		8.0							
12/04/11	1623-1634	25/Cloudy	Surface	1.0	18.5	30.6	30.7	6.12	6.14	87.5	87.7	5.20	5.18	5.26	8.1	8.1	8.5
				7.1	19.0	30.7		6.15		87.9		5.16			8.0		
			Middle	31.3	31.3	6.04	6.06	86.4	86.6	5.27	5.26	8.4	8.5				
				31.3		6.07		86.8		5.24		8.6					
			Bottom	12.6	19.6	31.9	32.0	5.95	5.93	84.5	84.2	5.30	5.34		8.9	9.0	
				32.0	5.90	83.8		5.37		9.0							
14/04/11	0901-0915	24/Fine	Surface	1.0	19.6	30.8	30.9	6.28	6.26	87.9	87.6	4.95	4.94	5.13	7.9	7.9	8.1
				7.1	19.2	30.9		6.23		87.2		4.92			7.8		
			Middle	31.2	31.3	6.12	6.15	85.7	86.0	5.11	5.13	8.2	8.1				
				31.3		6.17		86.3		5.15		8.0					
			Bottom	12.8	18.8	31.7	31.8	6.02	6.04	84.2	84.5	5.28	5.31		8.4	8.3	
				31.8	6.06	84.8		5.34		8.2							
16/04/11	0927-0939	24/Cloudy	Surface	1.0	20.1	30.8	30.7	6.16	6.14	87.5	87.2	5.11	5.14	5.25	8.4	8.5	8.5
				7.1	19.9	30.6		6.11		86.8		5.16			8.5		
			Middle	31.4	31.4	6.04	6.06	85.2	85.4	5.28	5.25	8.6	8.5				
				31.3		6.07		85.6		5.22		8.4					
			Bottom	12.8	19.5	31.7	31.7	5.95	5.97	83.9	84.2	5.39	5.38		8.7	8.6	
				31.7	5.99	84.5		5.36		8.5							
19/04/11	1131-1145	25/Fine	Surface	1.0	20.5	30.7	30.7	6.26	6.28	87.6	87.9	4.86	4.88	5.03	7.7	7.8	8.1
				7.1	20.1	30.7		6.30		88.2		4.89			7.9		
			Middle	31.2	31.3	6.18	6.15	86.5	86.1	4.97	5.00	8.0	8.1				
				31.3		6.12		85.6		5.03		8.1					
			Bottom	12.8	19.7	31.8	31.9	6.04	6.01	84.5	84.1	5.18	5.21		8.4	8.4	
				31.9	5.98	83.7		5.24		8.3							
21/04/11	1330-1342	24/Fine	Surface	1.0	23.0	31.2	31.2	6.30	6.32	89.4	89.7	5.37	5.34	5.42	8.7	8.6	8.7
				7.1	21.0	31.1		6.34		90.0		5.30			8.4		
			Middle	31.9	31.9	6.14	6.16	87.1	87.4	5.60	5.64	9.2	9.1				
				31.8		6.18		87.7		5.68		9.0					
			Bottom	12.8	20.7	32.1	32.2	5.97	5.96	84.7	84.5	5.33	5.29		8.5	8.5	
				32.2	5.94	84.3		5.25		8.5							
26/04/11	1639-1649	28/Fine	Surface	1.0	21.5	30.7	30.7	6.04	6.07	84.6	85.0	5.08	5.10	5.23	8.0	8.0	8.3
				7.1	20.9	30.6		6.09		85.3		5.11			8.0		
			Middle	31.5	31.5	5.95	5.98	83.3	83.7	5.25	5.24	8.3	8.4				
				31.4		6.01		84.1		5.22		8.5					
			Bottom	13.2	20.5	31.8	31.8	5.92	5.91	82.9	82.8	5.37	5.35		8.6	8.6	
				31.7	5.90	82.6		5.33		8.5							
28/04/11	0857-0909	26/Cloudy	Surface	1.0	23.2	30.7	30.7	6.13	6.14	87.0	87.2	5.16	5.18	5.29	7.9	7.8	8.4
				7.1	22.8	30.7		6.15		87.3		5.19			7.6		
			Middle	31.4	31.4	6.07	6.06	85.6	85.4	5.31	5.28	8.3	8.3				
				31.3		6.04		85.2		5.24		8.2					
			Bottom	13.2	22.6	31.8	31.9	5.94	5.96	83.8	84.1	5.43	5.41		9.2	9.1	
				31.9	5.98	84.3		5.39		9.0							
30/04/11	0929-0940	25/Cloudy	Surface	1.0	22.3	30.8	30.8	6.19	6.18	87.3	87.1	5.16	5.20	5.30	8.1	8.2	8.5
				7.2	21.9	30.7		6.16		86.9		5.23			8.2		
			Middle	31.3	31.4	6.03	6.06	85.0	85.4	5.26	5.29	8.4	8.3				
				31.4		6.08		85.7		5.31		8.1					
			Bottom	13.4	21.3	31.6	31.7	5.94	5.96	83.2	83.5	5.45	5.42		9.0	9.0	
				31.7	5.98	83.7		5.39		9.0							

Monitoring Station : C3

Date	Sampling Duration	Ambient Temp (°C) / Weather Condition	Monitoring Depth (m)		Temp (°C)	Salinity (ppt)		Dissolved Oxygen (mg/L)		Dissolved Oxygen Saturation (%)		Turbidity (NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Depth-average	Value	Average	Depth-average
02/04/11	1055-1107	20/Sunny	Surface	1.0	18.7	30.7	30.7	6.19	6.21	85.0	86.3	5.17	5.20	5.31	8.1	8.1	8.4
				6.3	19.4	31.4		6.06		83.6		5.27			8.4		
			Middle	6.3	19.4	31.5	31.5	6.04	6.05	83.4	83.5	5.33	5.30		8.2	8.3	
				11.6	19.9	31.8		5.95		82.1		5.46			8.9		
			Bottom	11.6	19.9	31.8	31.8	5.92	5.94	81.7	81.9	5.41	5.44		9.0	9.0	
				1.0	19.8	30.4		6.11		85.5		5.35			8.6		
07/04/11	1443-1455	24/Fine	Surface	1.0	19.8	30.5	30.5	6.07	6.09	84.6	85.1	5.32	5.34	5.61	8.3	8.5	9.0
				6.5	19.3	31.7		5.90		82.6		5.61			9.2		
			Middle	6.5	19.3	31.8	31.8	5.91	5.91	82.7	82.7	5.64	5.63		9.0	9.1	
				12.0	18.6	32.1		5.89		82.5		5.89			9.4		
			Bottom	12.0	18.6	32.0	32.1	5.86	5.88	82.0	82.3	5.85	5.87		9.3	9.4	
				1.0	21.2	31.2		6.20		88.0		4.99			8.0		
09/04/11	1425-1437	23/Fine	Surface	1.0	21.2	31.2	31.2	6.24	6.22	88.6	88.3	5.05	5.02	5.19	8.1	8.1	8.3
				6.4	20.2	31.6		6.08		86.3		5.09			8.2		
			Middle	6.4	20.2	31.6	31.6	6.05	6.07	85.9	86.1	5.15	5.12		8.0	8.1	
				11.8	20.0	32.0		5.97		84.1		5.40			8.6		
			Bottom	11.8	20.0	31.9	32.0	5.94	5.96	83.7	83.9	5.45	5.43		8.8	8.7	
				1.0	18.5	30.5		6.17		87.0		5.14			8.0		
12/04/11	1640-1653	25/Cloudy	Surface	1.0	18.5	30.6	30.6	6.22	6.20	87.7	87.4	5.16	5.15	5.24	8.0	8.0	8.3
				6.3	18.9	31.4		6.08		85.7		5.22			8.4		
			Middle	6.3	18.9	31.3	31.4	6.12	6.10	86.3	86.0	5.25	5.24		8.1	8.3	
				11.6	19.5	31.9		6.00		85.2		5.35			8.6		
			Bottom	11.6	19.5	31.9	31.9	5.98	5.99	84.9	85.1	5.32	5.34		8.4	8.5	
				1.0	19.6	30.8		6.31		88.3		4.91			7.9		
14/04/11	0919-0935	24/Fine	Surface	1.0	19.6	30.8	30.8	6.26	6.29	87.6	88.0	4.88	4.90	5.04	8.0	8.0	8.1
				6.2	19.2	31.2		6.19		86.6		5.00			8.2		
			Middle	6.2	19.2	31.2	31.2	6.14	6.17	85.9	86.3	5.06	5.03		8.0	8.1	
				11.4	18.9	31.7		6.05		84.7		5.18			8.3		
			Bottom	11.4	18.9	31.8	31.8	6.00	6.03	84.0	84.4	5.22	5.20		8.1	8.2	
				1.0	20.1	30.6		6.14		87.2		5.14			8.0		
16/04/11	0950-1002	24/Cloudy	Surface	1.0	20.1	30.7	30.7	6.12	6.13	86.9	87.1	5.21	5.18	5.29	8.2	8.1	8.5
				6.4	19.8	31.3		6.02		84.9		5.31			8.5		
			Middle	6.4	19.8	31.2	31.3	6.06	6.04	85.4	85.2	5.27	5.29		8.5	8.5	
				11.8	19.5	31.8		5.97		84.2		5.37			8.7		
			Bottom	11.8	19.5	31.7	31.8	5.96	5.97	84.0	84.1	5.43	5.40		8.8	8.8	
				1.0	20.5	30.6		6.21		86.9		4.90			7.9		
19/04/11	1153-1206	25/Fine	Surface	1.0	20.5	30.7	30.7	6.25	6.23	87.5	87.2	4.97	4.94	5.11	7.9	7.9	8.2
				6.4	20.1	31.2		6.14		85.9		5.08			8.2		
			Middle	6.4	20.1	31.2	31.2	6.10	6.12	85.4	85.7	5.13	5.11		8.0	8.1	
				11.8	19.8	31.8		5.92		82.8		5.26			8.6		
			Bottom	11.8	19.8	31.8	31.8	5.97	5.95	83.5	83.2	5.30	5.28		8.5	8.6	
				1.0	22.9	31.1		6.21		88.1		5.07			8.0		
21/04/11	1345-1357	24/Fine	Surface	1.0	22.9	31.1	31.1	6.17	6.19	87.6	87.9	5.13	5.10	5.15	8.3	8.2	8.3
				6.4	20.9	31.9		6.09		86.4		5.21			8.5		
			Middle	6.4	20.9	32.0	32.0	6.06	6.08	86.0	86.2	5.27	5.24		8.6	8.6	
				11.8	20.6	32.2		5.88		82.9		5.09			8.0		
			Bottom	11.8	20.6	32.1	32.2	5.93	5.91	83.6	83.3	5.15	5.12		8.2	8.1	
				1.0	21.5	30.5		6.16		86.2		5.20			8.5		
26/04/11	1658-1710	28/Fine	Surface	1.0	21.5	30.6	30.6	6.11	6.14	85.5	85.9	5.24	5.22	5.36	8.4	8.5	8.7
				6.4	21.1	31.4		6.07		84.9		5.36			8.7		
			Middle	6.4	21.1	31.4	31.4	6.09	6.08	85.3	85.1	5.39	5.38		8.5	8.6	
				11.8	20.6	31.7		5.83		81.6		5.50			9.0		
			Bottom	11.8	20.6	31.8	31.8	5.81	5.82	81.3	81.5	5.49	5.50		9.0	9.0	
				1.0	23.1	30.6		6.22		88.3		5.29			8.2		
28/04/11	0920-0932	26/Cloudy	Surface	1.0	23.1	30.7	30.7	6.17	6.20	87.6	88.0	5.24	5.27	5.37	8.0	8.1	8.5
				6.3	22.8	31.3		6.09		85.9		5.33			8.5		
			Middle	6.3	22.8	31.3	31.3	6.07	6.08	85.6	85.8	5.38	5.36		8.3	8.4	
				11.6	22.5	31.8		5.96		84.0		5.51			9.0		
			Bottom	11.6	22.5	31.7	31.8	5.94	5.95	83.8	83.9	5.44	5.48		8.7	8.9	
				1.0	22.2	30.8		6.15		86.7		5.28			8.4		
30/04/11	0952-1004	25/Cloudy	Surface	1.0	22.2	30.8	30.8	6.20	6.18	87.4	87.1	5.24	5.26	5.37	8.1	8.3	8.6
				6.4	21.8	31.5		6.09		85.3		5.39			8.5		
			Middle	6.4	21.8	31.4	31.5	6.12	6.11	85.7	85.5	5.36	5.38		8.8	8.7	
				11.8	21.3	31.7		5.96		83.4		5.45			8.9		
			Bottom	11.8	21.3	31.7	31.7	5.92	5.94	82.9	83.2	5.51	5.48		9.0	9.0	




Appendix C3


Graphical Plots of Impact Water Quality Monitoring Data



Dissolved Oxygen (Surface) at Mid-Flood Tide




Dissolved Oxygen (Surface) at Mid-Ebb Tide






Dissolved Oxygen (Middle) at Mid-Flood Tide




Dissolved Oxygen (Middle) at Mid-Ebb Tide






Dissolved Oxygen (Middle) at Mid-Flood Tide




Dissolved Oxygen (Middle) at Mid-Ebb Tide






Dissolved Oxygen (Bottom) at Mid-Flood Tide




Dissolved Oxygen (Bottom) at Mid-Ebb Tide






Dissolved Oxygen (Bottom) at Mid-Flood Tide



△ R15

— Action and Limit Level

Dissolved Oxygen (Bottom) at Mid-Ebb Tide




△ R15


— Action and Limit Level



Turbidity (Depth-average) of R15 at Mid-Flood Tide




Turbidity (Depth-average) of R15 at Mid-Ebb Tide






Suspended solids (Depth-average) of R15 at Mid-Flood Tide



Suspended Solids (Depth-average) of R15 at Mid-Ebb Tide





Appendix C4

QA/QC Results of Laboratory Analysis for Water Samples



QA/QC Results of Laboratory Analysis of Total Suspended Solids

Sampling Date	QC Sample	Sample Duplicate		Sample Spike	
	% Recovery *	Sample ID	% Error #	Sample ID	% Recovery @
02/04/11	92.9	R5FS	3.1	R8FS	95.9
	96.2	R8FM	0.0	R17FM	98.1
	96.0	R17FB	3.0	C1FB	100.0
	100.8	C2FS	3.2	C4FB	98.1
	97.3	R5ES	2.9	R8ES	102.1
	94.2	R8EM	3.1	R17EM	105.7
	103.7	R17EB	3.0	C1EB	104.0
	96.9	C2ES	3.1	C4EB	95.9
07/04/11	106.4	R5FS	2.9	R8FS	100.0
	98.2	R8FM	3.1	R17FM	98.0
	107.7	R17FB	2.8	C1FB	101.9
	98.1	C2FS	3.0	C4FB	102.0
	94.8	R5ES	2.7	R8ES	101.9
	94.8	R8EM	2.7	R17EM	101.9
	102.5	R17EB	2.7	C1EB	102.0
	98.0	C2ES	0.0	C4EB	98.0
09/04/11	93.4	R5FS	3.1	R8FS	100.0
	104.0	R8FM	3.0	R17FM	108.3
	104.8	R17FB	2.7	C1FB	95.8
	107.3	C2FS	6.1	C4FB	98.1
	105.6	R5ES	3.2	R8ES	86.5
	96.8	R8EM	2.8	R17EM	107.7
	94.5	R17EB	0.0	C1EB	105.7
	100.4	C2ES	2.8	C4EB	94.3
12/04/11	95.9	R5FS	3.0	R8FS	104.3
	96.5	R8FM	2.8	R17FM	96.0
	101.9	R17FB	2.7	C1FB	94.0
	95.2	C2FS	3.1	C4FB	91.8
	106.0	R5ES	0.0	R8ES	102.1
	100.2	R8EM	3.1	R17EM	103.8
	97.1	R17EB	2.8	C1EB	106.1
	98.2	C2ES	6.1	C4EB	98.0
14/04/11	97.9	R5FS	2.9	R8FS	94.0
	95.5	R8FM	2.8	R17FM	106.2
	103.9	R17FB	2.7	C1FB	103.9
	99.4	C2FS	3.2	C4FB	106.0
	100.0	R5ES	0.0	R8ES	96.1
	92.4	R8EM	3.2	R17EM	112.0
	101.8	R17EB	6.3	C1EB	114.6
	97.7	C2ES	3.2	C4EB	106.1
16/04/11	92.7	R5FS	3.1	R8FS	94.0
	106.9	R8FM	5.7	R17FM	94.2
	105.3	R17FB	2.9	C1FB	92.2
	101.7	C2FS	3.3	C4FB	102.0
	93.1	R5ES	2.8	R8ES	102.1
	101.2	R8EM	2.8	R17EM	110.2
	100.8	R17EB	3.0	C1EB	105.9
	97.5	C2ES	3.1	C4EB	98.0

Note: (*)% Recovery of QC sample should be between 80% to 120%.
 (#) % Error of Sample Duplicate should be between -10% to 10%.
 (@) % Recovery of Sample Spike should be between 80% to 120%.



QA/QC Results of Laboratory Analysis of Total Suspended Solids

Sampling Date	QC Sample	Sample Duplicate		Sample Spike	
	% Recovery *	Sample ID	% Error #	Sample ID	% Recovery @
19/04/11	101.5	R5FS	2.7	R8FS	94.1
	94.7	R8FM	3.0	R17FM	100.0
	95.5	R17FB	2.7	C1FB	94.0
	103.5	C2FS	3.2	C4FB	93.9
	98.0	R5ES	3.1	R8ES	94.2
	92.3	R8EM	0.0	R17EM	109.8
	98.0	R17EB	3.0	C1EB	114.6
	98.2	C2ES	3.3	C4EB	96.2
21/04/11	104.9	R5FS	3.2	R8FS	92.3
	99.8	R8FM	2.9	R17FM	95.8
	92.4	R17FB	2.7	C1FB	104.2
	101.3	C2FS	3.1	C4FB	95.8
	103.5	R5ES	3.0	R8ES	96.1
	99.6	R8EM	6.5	R17EM	103.8
	96.0	R17EB	5.4	C1EB	105.9
	94.7	C2ES	3.1	C4EB	102.0
26/04/11	94.5	R5FS	6.1	R8FS	102.1
	98.8	R8FM	2.9	R17FM	102.0
	97.3	R17FB	5.4	C1FB	92.5
	107.5	C2FS	0.0	C4FB	93.8
	101.1	R5ES	3.2	R8ES	94.1
	92.8	R8EM	3.0	R17EM	112.5
	103.1	R17EB	2.7	C1EB	110.2
	102.2	C2ES	2.8	C4EB	104.1
28/04/11	95.5	R5FS	6.5	R8FS	104.3
	93.0	R8FM	3.0	R17FM	96.2
	104.9	R17FB	2.9	C1FB	98.1
	95.9	C2FS	3.2	C4FB	93.8
	96.3	R5ES	3.0	R8ES	94.0
	101.9	R8EM	2.8	R17EM	105.8
	104.2	R17EB	0.0	C1EB	104.0
	95.6	C2ES	3.1	C4EB	94.1
30/04/11	98.4	R5FS	6.5	R8FS	92.0
	92.7	R8FM	3.1	R17FM	93.6
	104.9	R17FB	2.7	C1FB	102.0
	99.0	C2FS	3.3	C4FB	106.0
	103.1	R5ES	2.8	R8ES	92.0
	99.0	R8EM	3.0	R17EM	114.9
	99.8	R17EB	2.7	C1EB	108.3
	102.0	C2ES	3.1	C4EB	98.0

Note: (*) % Recovery of QC sample should be between 80% to 120%.
 (#) % Error of Sample Duplicate should be between -10% to 10%.
 (@) % Recovery of Sample Spike should be between 80% to 120%.



Appendix D

Event-Action Plans



Event and Action Plan for Construction Noise

Event	Action			
	ET Leader	IEC	ER	Contractor
Action Level	<ol style="list-style-type: none"> 1. Notify IEC and the Contractor. 2. Carry out investigation. 3. Report the results of investigation to IEC and the Contractor. 4. Discuss with the Contractor and formulate remedial measures. 5. Increase monitoring frequency to check mitigation measures. 	<ol style="list-style-type: none"> 1. Review with analysed results submitted by ET. 2. Review the proposed remedial measures by the Contractor and advise ER accordingly. 3. Supervise the implement of remedial measures. 	<ol style="list-style-type: none"> 1. Confirm receipt of notification of exceedance in writing. 2. Notify the Contractor. 3. Require the Contractor to propose remedial measures for the analysed noise problem. 4. Ensure remedial measures are properly implemented. 	<ol style="list-style-type: none"> 1. Submit noise mitigation proposals to IEC. 2. Implement noise mitigation proposals.
Limit Level	<ol style="list-style-type: none"> 1. Identify the source. 2. Notify IEC, ER, EPD and the Contractor. 3. Repeat measurement to confirm findings. 4. Increase monitoring frequency. 5. Carry out analysis of Contractor's working procedures to determine possible mitigation to be implemented. 6. Inform IEC, ER, and EPD the causes & actions taken for the exceedances. 7. Assess effectiveness of the Contractor's remedial actions and keep IEC, EPD and ER informed of the results. 8. If exceedance stops, cease additional monitoring. 	<ol style="list-style-type: none"> 1. Discuss amongst ER, ET Leader and the Contractor on the potential remedial actions. 2. Review the Contractor's remedial actions whenever necessary to assure their effectiveness and advise ER accordingly. 3. Supervise the implementation of remedial measures. 	<ol style="list-style-type: none"> 1. Confirm receipt of notification of exceedance in writing. 2. Notify the Contractor. 3. Require the Contractor to propose remedial measures for the analysed noise problem. 4. Ensure remedial measures are properly implemented. 5. If exceedance continues, consider what activity of the work is responsible and instruct the Contractor to stop that activity of work until the exceedance is abated. 	<ol style="list-style-type: none"> 1. Take immediate action to avoid further exceedance. 2. Submit proposals for remedial actions to IEC within 3 working days of notification. 3. Implement the agreed proposals. 4. Resubmit proposals if problem still not under control. 5. Stop the relevant activity of works as determined by the ER until the exceedance is abated.



Event and Action Plan for Water Quality for Construction Phase

Event	Action			
	ET Leader	IEC	ER	Contractor
Action Level				
Exceedance for one sample	<ol style="list-style-type: none"> 1. Repeat in-situ measurement to confirm finding; 2. Identify source(s) of impact; 3. Inform IEC and Contractor; 4. Check monitoring data, all plant, equipment and Contractor's working methods; 5. Discuss mitigation measures with IEC and Contractor; and 6. Repeat measurement on next day of exceedance. 	<ol style="list-style-type: none"> 1. Discuss with ET and Contractor on the mitigation measures; 2. Review proposals on mitigation measures submitted by Contractor and advise the ER accordingly; and 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Discuss with IEC on the proposed mitigation measures; and 2. Make agreement on the mitigation measures to be implemented. 	<ol style="list-style-type: none"> 1. Inform the ER and confirm notification of the non-compliance in writing; 2. Rectify unacceptable practice; 3. Check all plant and equipment; 4. Consider changes of working methods; 5. Discuss with ET and IEC and propose mitigation measures to IEC and ER; and 6. Implement the agreed mitigation measures.
Exceedance for two or more consecutive samples	<ol style="list-style-type: none"> 1. Repeat in-situ measurement to confirm finding; 2. Identify source(s) of impact; 3. Inform IEC and Contractor; 4. Check monitoring data, all plant, equipment and Contractor's working methods; 5. Discuss mitigation measures with IEC and Contractor; 6. Ensure mitigation measures are implemented; 7. Prepare to increase the monitoring frequency to daily; and 8. Repeat measurement on next day of exceedance. 	<ol style="list-style-type: none"> 1. Discuss with ET and Contractor on the mitigation measures; 2. Review proposals on mitigation measures submitted by Contractor and advise the ER accordingly; and 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Discuss with IEC on the proposed mitigation measures; 2. Make agreement on the mitigation measures to be implemented; and 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Inform the Engineer and confirm notification of the non-compliance in writing; 2. Rectify unacceptable practice; 3. Check all plant and equipment; 4. Consider changes of working methods; 5. Discuss with ET and IEC and propose mitigation measures to IEC and ER within 3 working days; and 6. Implement the agreed mitigation measures.



Event and Action Plan for Water Quality for Construction Phase

Event	Action			
	ET Leader	IEC	ER	Contractor
Limit Level				
Exceedance for one sample	<ol style="list-style-type: none"> 1. Repeat in-situ measurement to confirm finding; 2. Identify source(s) of impact; 3. Inform IEC, Contractor and EPD; 4. Check monitoring data, all plant, equipment and Contractor's working methods; 5. Discuss mitigation measures with IEC, ER and Contractor; 6. Ensure mitigation measures are implemented; and 7. Increase the monitoring frequency to daily until no exceedance of Limit level. 	<ol style="list-style-type: none"> 1. Discuss with ET and Contractor on the mitigation measures; 2. Review proposals on mitigation measures submitted by Contractor and advise the ER accordingly; and 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Discuss with IEC, ET and Contractor on the proposed mitigation measures; and 2. Request Contractor to critically review the working methods; 3. Make agreement on the mitigation measures to be implemented; and 4. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Inform the Engineer and confirm notification of the non-compliance in writing; 2. Rectify unacceptable practice; 3. Check all plant and equipment; 4. Consider changes of working methods; 5. Discuss with ET and IEC and ER and propose mitigation measures to IEC and ER within 3 working days; and 6. Implement the agreed mitigation measures.
Exceedance for two or more consecutive samples	<ol style="list-style-type: none"> 1. Repeat in-situ measurement to confirm finding; 2. Identify source(s) of impact; 3. Inform IEC, Contractor and EPD; 4. Check monitoring data, all plant, equipment and Contractor's working methods; 5. Discuss mitigation measures with IEC, ER and Contractor; 6. Ensure mitigation measures are implemented; and 7. Increase the monitoring frequency to daily until no exceedance of Limit level for two consecutive days. 	<ol style="list-style-type: none"> 1. Discuss with ET and Contractor on the mitigation measures; 2. Review proposals on mitigation measures submitted by Contractor and advise the ER accordingly; and 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Discuss with IEC, ET and Contractor on the proposed mitigation measures; and 2. Request Contractor to critically review the working methods; 3. Make agreement on the mitigation measures to be implemented; 4. Assess the effectiveness of the implemented mitigation measures; and 5. Consider and instruct, if necessary, the Contractor to slow down or to stop all or part of the marine work until no exceedance of Limit Level. 	<ol style="list-style-type: none"> 1. Inform the ER and confirm notification of the non-compliance in writing; 2. Rectify unacceptable practice; 3. Check all plant and equipment; 4. Consider changes of working methods; 5. Discuss with ET and IEC and ER and propose mitigation measures to IEC and ER within 3 working days; 6. Implement the agreed mitigation measures; and 7. As directed by the Engineer, to slow down or to stop all or part of the marine work or construction activities.



Appendix E

Work Programme

Act ID	Description	Qtd	Dly	Early Start	Early Finish	Late Start	Late Finish
General Information							
1156	07SEP09 A	05NOV12	07SEP09 A	05NOV12	07SEP09 A	05NOV12	05NOV12

Key Dates	Contract Commencement Date	07SEP09 A	05NOV12	07SEP09 A	05NOV12
KD-1010	Contract Commencement Date	07SEP09 A	05NOV12	07SEP09 A	05NOV12
KD-1020	Contract Completion	07SEP09 A	05NOV12	07SEP09 A	05NOV12
KD-1030	Works Period of Section 1 Works (791Days)	07SEP09 A	15DEC11	07SEP09 A	15DEC11
KD-1040	Works Period of Section 2 Works (428Days)	07SEP09 A	29NOV10	07SEP09 A	29NOV10
KD-1050	Works Period of Section 4 Works (549Days)	07SEP09 A	05APR11	07SEP09 A	05APR11
KD-1060	Works Period of Section 5 Works (1150Days)	07SEP09 A	05NOV12	07SEP09 A	05NOV12

Preliminaries	07SEP09 A	05NOV12
B1-1000	Mobilization	06DEC09 A
B1-1100	Site Office	16JAN10
B1-1120	Maintenance/Service of Preliminary Items	17JAN10
B1-1130	Clearance & Demobilisation	09AUG12
B1-1140	Environmental Monitoring	10AUG12
B1-1150	Material Approval For Water Mains & Accessories	28DEC09 A
B1-1160	Material Procurement & Delivery Start	18FEB10
B1-1170	Delivery of Valve, Actuators, Flow Meter & E&M	14JUN10
B1-1180	CCTV & Monitoring Of Existing DSD Drainage	19SEP11
B1-1190	Monitoring of Hyd Structure	05NOV11

Section 1	07SEP09 A	15DEC11
830	07SEP09 A	15DEC11

Land Works	07SEP09 A	15DEC11
180	07SEP09 A	05MAR10
120	01DEC09 A	16MAR10
40	08OCT09 A	08OCT09 A
80	07OCT09 A	29NOV09 A
90	07SEP09 A	17FEB10
30	18FEB10	19MAR10
120	05OCT09 A	04MAR10
45	01NOV11	15DEC11
0	15DEC11	15DEC11

General	07SEP09 A	15DEC11
180	07SEP09 A	05MAR10
270	28MAY10	21FEB11
90	24JUN10	21SEP10
40	22FEB10	02APR10
40	22FEB10	02APR10
80	28MAY10	15AUG10
50	17JUL10	04SEP10
10	05SEP10	14SEP10
60	06MAR10	04MAY10
28	17JUL10	13AUG10
28	17JUL10	13AUG10
28	17JUL10	13AUG10
3	31JUL10	02AUG10
15	15SEP10	28SEP10
3	30SEP10	02OCT10
10	03OCT10	12OCT10
3	13OCT10	15OCT10
15	18OCT10	30OCT10
50	05MAY10	23JUN10
10	31OCT10	08NOV10
6	10NOV10	15NOV10

Portion C1	07SEP09 A	15DEC11
160	07SEP09 A	14APR10
270	28MAY10	21FEB11
90	24JUN10	21SEP10
40	22FEB10	02APR10
40	22FEB10	02APR10
80	28MAY10	15AUG10
50	17JUL10	04SEP10
10	05SEP10	14SEP10
60	06MAR10	04MAY10
28	17JUL10	13AUG10
28	17JUL10	13AUG10
28	17JUL10	13AUG10
3	31JUL10	02AUG10
15	15SEP10	28SEP10
3	30SEP10	02OCT10
10	03OCT10	12OCT10
3	13OCT10	15OCT10
15	18OCT10	30OCT10
50	05MAY10	23JUN10
10	31OCT10	08NOV10
6	10NOV10	15NOV10

Start date 07SEP09
Finish date 05NOV12
Data date 04JAN10
Run date 12APR11
Page number 1A
© Primavera Systems, Inc.

3 Months Rolling Program (April 2011)

Legend:
 ■ Early bar
 ■ Progress bar
 ■ Critical bar
 ■ Summary bar
 ■ Start milestone point
 ■ Finish milestone point


Act ID	Description	Orig Dur	Early Start	Early Finish	Late Start	Late Finish
S1-3050B30	Backfilling Of Pipe Trough	5	18NOV10	20NOV10	02JUN11	06JUN11
S1-3050B40	Backfilling & Reinstatement	10	21NOV10	30NOV10	07JUN11	16JUN11
S1-3060	Portion C1 Pipe Works CH290.0-325.5 (O)	83	01DEC10	21FEB11	17JUN11	07SEP11
S1-3070	Area C1 Portional Pipe Testing	30	22FEB11	23MAR11	02OCT11	31OCT11
Portion E1A						
S1-4020	Portion E1A Pipe Works CH387.5-576.9 (O)	180	17MAR10	12SEP10	24AUG10	19FEB11
S1-4020A20	Preparation & Submission Of Risk Assessment	40	03MAR10	11APR10	10AUG10	18SEP10
S1-4020A30	Preparation & Submission Of Method Statement	40	03MAR10	11APR10	10AUG10	18SEP10
S1-4020A40	Preparation & Submission Of Temp. Works	40	03MAR10	11APR10	10AUG10	18SEP10
S1-4020B10	Stage 1 U/D & Trial Pit (CH380-420)	32	03MAY10	11OCT10	10OCT10	30NOV10
S1-4020B20	Fabrication Of Access Shaft	30	12SEP10	11OCT10	18FEB11	20MAR11
S1-4020B30	Excavation & Support for Trenchless Works	45	12OCT10	29NOV10	21MAR11	04MAY11
S1-4020B40	Pipe Laying & Joint Connection	20	28NOV10	19DEC10	05MAY11	24MAY11
S1-4020B50	Backfilling & Reinstatement	7	18NOV10	22DEC10	25MAY11	31MAY11
S1-4020C05	Existing Trees Relocation	4	19AUG10	22AUG10	03JUN11	06JUN11
S1-4020C10	Stage 2 U/D & Trial Pit (CH420-CH480)	10	23AUG10	01SEP10	07JUN11	16JUN11
S1-4020C20	Excavation & Shoring	60	02SEP10	21OCT10	17JUN11	05AUG11
S1-4020C30	Pipe Laying & Connection (Welding)	25	22OCT10	16NOV10	06AUG11	30AUG11
S1-4020C40	Backfilling & Reinstatement	7	18NOV10	22NOV10	01JUN11	06SEP11
S1-4020D10	Stage 3 U/D & Trial Pit (CH480-576.9)	6	01JUN11	06JUN11	01JUN11	06SEP11
S1-4020D20	Excavation & Shoring	92	07JUN11	06SEP11	07JUN11	06SEP11
S1-4020D30	Pipe Laying & Connection (Welding)	29	07SEP11	07OCT11	07SEP11	07OCT11
S1-4020D40	Backfilling & Reinstatement	16	02OCT11	17OCT11	02OCT11	17OCT11
S1-4030	Portion E1A Pipe Works CH576.9-585.9 (TL-B)	108	23FEB11	10JUN11	02JUL11	17OCT11
S1-4030B10	Fabrication Of Access Shaft	35	27SEP10	20NOV10	12MAR11	09MAY11
S1-4030B20	Excavation & Support for Trenchless Works	30	21NOV10	09JAN11	09MAY11	25JUN11
S1-4030B30	Pipe Laying & Joint Connection	15	10JAN11	24JAN11	25JUN11	09JUL11
S1-4030B40	Backfilling & Reinstatement	8	25JAN11	01FEB11	10OCT11	17OCT11
S1-4050	Area E1A Portional Pipe Testing	14	18OCT11	31OCT11	18OCT11	31OCT11
Portion E1B - E2 SWM						
S1-4010	Portion E1B Diversion of Existing Storm Drain	50	15SEP10	01NOV10	05MAY11	24JUN11
S1-4010A10	Trees Transplanting (LCSD Consent Required)	5	08SEP10	13SEP10	28JAN11	30JAN11
S1-4010A20	Temporary Relocation of Irrigation Pipe	60	14SEP10	12NOV10	31JAN11	31MAR11
S1-4010A30	Temporary Relocation of Existing Storm Drain	60	14SEP10	12NOV10	31JAN11	31MAR11
S1-4010A40	Irrigation Pipe Installation	20	11MAR11	30MAR11	24AUG11	12SEP11
S1-4010A50	Excavation for Irrigation Pipe Perm. Diversion	10	31MAR11	09APR11	28SEP11	07OCT11
S1-4010A70	Excavation for Storm Drain Diversion	20	11MAR11	30MAR11	24AUG11	12SEP11
S1-4010A80	Pipe Laying & MH Construction	25	31MAR11	24APR11	13SEP11	07OCT11
S1-4010A90	Backfilling & Reinstatement	10	26APR11	04MAY11	08OCT11	17OCT11
S1-4040	Portion E1B Pipe Works CH585.9-600.5 (O)	115	02NOV10	24FEB11	25JUN11	17OCT11
S1-4040B10	Excavation & Shoring For Pipe Trough (Stage 1)	40	13NOV10	22DEC10	01APR11	10MAY11
S1-4040B20	FWK & Reinforcement for Pipe Trough	15	23DEC10	08JAN11	25JUN11	09JUL11
S1-4040B30	Pipe Laying & Support Casting	25	25JAN11	18FEB11	10JUL11	03AUG11
S1-4040B40	Backfilling & Reinstatement	20	18FEB11	10MAR11	04AUG11	23AUG11
S1-4410	Portion E2 DN600A SWM Works CH7.1-63.7 (UC)	50	05MAR10	23APR10	03SEP10	22OCT10
S1-4410A10	Preparation & Submission Of Risk Assessment	28	18FEB10	18MAR10	27FEB11	28MAR11
S1-4410A20	Preparation & Submission Of Method Statement	28	18FEB10	18MAR10	27FEB11	28MAR11
S1-4410A30	Submission & Approval Of Temp. Work	28	18FEB10	18MAR10	27FEB11	28MAR11
S1-4410B10	Installation & Connection Of DN600A SWM	8	14FEB11	21FEB11	27MAR11	03APR11
S1-4410B20	Support & Fixing Of DN600A SWM	3	22FEB11	24FEB11	04APR11	08APR11
S1-4420	Portion E1B DN600A SWM Works CH0.0-7.1 (O)	30	24APR10	23MAY10	23OCT10	21NOV10
S1-4420B10	Excavation & Shoring	6	26FEB11	03MAY11	10MAR11	12APR11
S1-4420B20	Main Laying & Connection With Trough Portion	8	03MAY11	10MAR11	13APR11	20APR11
S1-4430	Portion E2 DN600A SWM Works CH63.7-67.9 (O)	30	24MAY10	22JUN10	21APR11	23APR11
S1-4430B10	Excavation & Shoring	8	11MAR11	18MAR11	21APR11	23APR11
S1-4430B20	Main Laying & Connection With Trough Portion	4	19MAR11	22MAR11	29APR11	02MAY11
S1-4440	E1B Existing DN600 SWM Diversion & Demolition	30	23JUN10	22JUL10	22DEC10	20JAN11
S1-4440A10	Issuance Of Temp. Water Supply Suspension Notice	14	09MAR11	22MAR11	19APR11	02MAY11

Start date: 07SEP09
 Finish date: 05NOV12
 Data date: 04JAN10
 Run date: 12APR11
 Page number: 2A
 © Primavera Systems, Inc.


3 Months Rolling Program (April 2011)

Legend:
 - Early bar
 - Progress bar
 - Critical bar
 - Summary bar
 - Start milestone point
 - Finish milestone point

Act ID	Description	Orig Dur	Early Start	Early Finish	Lat Start	Lat Finish
S1-4440B10	Shut Off Of Existing DN600 SWM	2	23MAR11	24MAR11	03MAY11	04MAY11
S1-4440B20	DN600A Diversion Main Connect To Existing	2	23MAR11	24MAR11	03MAY11	04MAY11
S1-4440B30	Removal Of Existing DN800 SWM	8	25MAR11	30MAR11	05MAY11	10MAY11
S1-4445B10	Excavation & Shoring For Pipe Trough (Stage 2)	60	24JUN10	22AUG10	11MAY11	19JUN11
S1-4445B20	Excavation & Shoring For Pipe Trough (Stage 2)	45	01FEB11	15FEB11	20JUN11	04JUL11
S1-4450B10	Backfilling & Reinforcement For Pipe Trough	60	11OCT10	09DEC10	11APR11	09JUN11
S1-4450B20	Backfilling & Reinforcement For Pipe Trough	25	16FEB11	12MAR11	05JUL11	29JUL11
S1-4460B10	Portion E1B Pipe Works CH677.4-685.9 (O)	20	13MAR11	01APR11	30JUL11	18AUG11
S1-4460B20	Portion E1B Pipe Works CH677.4-685.9 (O)	30	02FEB11	02APR11	08SEP11	17OCT11
S1-4460B30	Portion E1B Pipe Works CH677.4-685.9 (O)	30	02MAY11	31MAY11	16SEP11	17OCT11
S1-4470B10	Portion E1B Pipe Works CH895.9-898.5 (UC)	20	10DEC10	29DEC10	10JUN11	26JUN11
S1-4470B20	Portion E1B Pipe Works CH895.9-898.5 (UC)	30	02APR11	01MAY11	19AUG11	17SEP11
S1-4480B10	Portion E1B DN600B SWM Works CH0.0-7.1 (O)	30	23JUL10	21AUG10	11FEB11	11MAY11
S1-4480B20	Portion E1B DN600B SWM Works CH0.0-7.1 (O)	30	30APR11	28MAY11	16SEP11	17OCT11
S1-4490B10	Portion E2 DN600B SWM Works CH7.1-63.7 (UC)	50	23JUL10	10SEP10	21JAN11	11MAR11
S1-4490B20	Portion E2 DN600B SWM Works CH7.1-63.7 (UC)	30	31MAR11	29APR11	11MAY11	09JUN11
S1-4500B10	Portion E2 DN600B SWM Works CH7.1-63.7 (O)	30	11SEP10	10OCT10	12MAR11	10APR11
S1-4500B20	Portion E2 DN600B SWM Works CH7.1-63.7 (O)	30	30APR11	19MAY11	10JUN11	29JUN11
S1-4510B10	Area E1B-E2 SWM Portional Pipe Testing	14	03APR11	18APR11	18OCT11	31OCT11
S1-4510B20	Area E1B-E2 SWM Portional Pipe Testing	14	01JUN11	14JUN11	18OCT11	31OCT11
Portion E1C-E1D						
S1-4710	Portion E1C DN300 FWM Works CH0.0-50.0 (UC)	50	05MAR10	23APR10	27SEP10	15NOV10
S1-4710A10	Submission & Approval Of Risk Assessment	28	19FEB10	18MAR10	13SEP10	10OCT10
S1-4710A20	Submission & Approval Of Method Statement	28	19FEB10	18MAR10	13SEP10	10OCT10
S1-4710A30	Submission & Approval Of Temp. Work	28	19FEB10	18MAR10	13SEP10	10OCT10
S1-4710B10	Installation & Connection Of DN300 FWM	50	17MAY10	05JUL10	11OCT10	29NOV10
S1-4710B20	Support & Fixing Of DN300 FWM	40	06JUL10	14AUG10	30NOV10	08JAN11
S1-4720	E1C DN300 FWM Diversion Main Testing	8	24APR10	01MAY10	03APR11	10APR11
S1-4720B10	E1C Exst. DN300 FWM Diversion & Demolition	8	15AUG10	22AUG10	06JAN11	16JAN11
S1-4730	Issuance Of Temp. Water Supply Suspension Notice	30	02MAY10	31MAY10	11APR11	10MAY11
S1-4730A10	Shut Off Existing DN300 FWM	14	22SEP10	05OCT10	16FEB11	01MAY11
S1-4730A20	Shut Off Existing DN300 FWM	2	08OCT10	07OCT10	03MAR11	03MAR11
S1-4730A30	Removal Of Existing DN300 FWM	2	08OCT10	07OCT10	03MAR11	03MAR11
S1-4730B10	Portion E1C DN800 SWM Works CH0.0-52.0 (UC)	80	05NOV10	23JAN11	04MAY11	28JUL11
S1-4740	Portion E1C DN800 SWM Works CH0.0-52.0 (UC)	120	05NOV10	04MAY11	01APR11	28JUL11
S1-4750	Portion E1C DN800 SWM Works CH52.0-90.0 (O)	80	01FEB11	21APR11	30JUL11	17OCT11
S1-4750B10	Portion E1C DN800 SWM Works CH52.0-90.0 (O)	80	05MAR11	23MAY11	30JUL11	17OCT11
S1-4760	Area E1C Portional Pipe Testing	14	22APR11	05MAY11	18OCT11	31OCT11
S1-4760B10	Area E1C Portional Pipe Testing	14	24MAY11	06JUN11	18OCT11	31OCT11
Portion E2						
S1-5010	Portion E2 Marine Dept Advance Notice	90	07OCT09 A	20FEB10	07OCT09 A	20APR10
S1-5020	WHTCL Consent For Works Within Tunnel Area	120	07SEP09 A	20FEB10	07SEP09 A	20APR10
S1-5030	Chamber Modification - 180 Days of Portion E2	65	07JAN10 A	14MAR10 A	07JAN10 A	14MAR10 A
S1-5040	Portion E2 Trial Run	60	09NOV09 A	14NOV09 A	09NOV09 A	14NOV09 A
S1-5050	Portion E2 Trial Pit & Utilities Detection	15	21FEB10	07MAR10	21APR10	05MAY10
S1-5060	Portion E2 Initial & Utilities Survey	15	21FEB10	07MAR10	21APR10	05MAY10
S1-5070	Portion E2 Pipe Works CH698.5-752.5 (UC)	80	27MAR11	14JUN11	30JUN11	17SEP11
S1-5070B10	Portion E2 Pipe Works CH698.5-752.5 (UC)	30	20MAY11	07AUG11	30JUN11	17SEP11
S1-5080A	Portion E2 Pipe Works CH752.5-790.5 (O)	30	16JUL11	14AUG11	18SEP11	17OCT11
S1-5080B	Portion E2 Pipe Works CH752.5-790.5 (O)	30	08AUG11	06SEP11	18SEP11	17OCT11
S1-5090	TL-C FWM Sleeve Jacking CH790.5-977.7	70	26JUL10	03OCT10	28SEP10	08DEC10
S1-5090A10	Preparation & Submission of Risk Assessment	60	06FEB10	03SEP10	03SEP10	03NOV10
S1-5090A20	Preparation & Submission of Method Statement	60	06FEB10	03SEP10	03SEP10	03NOV10
S1-5090A30	Preparation & Submission of Temp. Design	60	06FEB10	03SEP10	03SEP10	03NOV10
S1-5090B10	Excavation & Shoring for Jacking Pit (A3)	40	07APR10	18MAY10	02NOV10	11DEC10
S1-5090B20	Jacking Pit Set-up (TL-C)	10	19AUG10	28AUG10	12DEC10	21DEC10



Start date	07SEP09
Finish date	05NOV12
Data date	04JAN10
Run date	12APR11
Page number	3A




Act ID	Description	Orig Dur	Early Start	Early Finish	Late Start	Late Finish
S1-5090C10	Sleeve Pipe Installation by Jacking	20	29AUG10	17SEP10	22DEC10	10JAN11
S1-5095	TL-C FWM Pipe Installation CH780.5-977.7	40	12MAY11	20JUN11	15JUL11	23AUG11
S1-5095E10	Pipe Laying & Connection	50	02DEC10	20JAN11	07MAR11	25APR11
S1-5095E20	Sleeve Pipe Grouting	10	21JAN11	30JAN11	28APR11	05MAY11
S1-5095E30	Backfilling & Reinstatement	30	31JAN11	01MAR11	08MAY11	04JUN11
S1-51000	Portion E2 Pipe Works CH877.7-985.5 (O)	25	21JUN11	15JUL11	24AUG11	17SEP11
S1-5100A	TL-E SWM Sleeve Jacking CH90.0-225.5 (A1-A4)	120	02MAY11	28MAY11	05JUN11	28JUN11
S1-51010	Preparation & Submission of Risk Assessment	60	06FEB10	09APR10	07DEC10	05APR11
S1-51010A10	Preparation & Submission of Method Statement	60	06FEB10	06APR10	12MAY10	10JUL10
S1-51010A20	Preparation & Submission of Method Statement	60	06FEB10	06APR10	12MAY10	10JUL10
S1-51010B10	Excavation & Shoring for Jacking Pit (A4)	50	07APR10	28MAY10	11JUL10	29AUG10
S1-51010B20	Jacking Pit Set-up (TL-E)	30	30MAY10	02SEP10	01OCT10	01OCT10
S1-51010B30	Sleeve Pipe Installation by Jacking	42	28JUN10	08AUG10	02OCT10	12NOV10
S1-5115	TL-E DN800 SWM Pipe Installation CH225.5-252.0	9	10AUG10	19AUG10	13NOV10	19JUN11
S1-5115B10	Pipe Laying & Connection	25	23MAR11	16APR11	26MAY11	19JUN11
S1-5115B20	Sleeve Pipe Grouting	30	08OCT10	06NOV10	11JAN11	09FEB11
S1-5115B30	Backfilling & Reinstatement of Jacking Pit	10	07NOV10	16NOV10	01APR11	10APR11
S1-5120A	Portion E2 DN800 SWM Works CH225.5-252.0	30	17APR11	11MAY11	20JUN11	14JUL11
S1-5130	TL-F SWM Sleeve Jacking CH252.0-432.0	142	06MAY10	23JUL10	10JAN11	04JUN11
S1-5130A10	Preparation & Submission of Risk Assessment	60	06FEB10	06APR10	08DEC10	23SEP10
S1-5130A20	Preparation & Submission of Method Statement	60	06FEB10	06APR10	08DEC10	05FEB11
S1-5130A30	Preparation & Submission of Temp. Design	60	06FEB10	06APR10	08DEC10	05FEB11
S1-5130B10	Jacking Pit (A3) Modification & Set-up (TL-F)	14	18SEP10	10OCT10	06FEB11	18FEB11
S1-5130C10	Sleeve Pipe Installation by Jacking	30	18SEP10	17OCT10	11JAN11	09FEB11
S1-5135	TL-F DN800 SWM Pipe Installation	50	07FEB11	23MAY11	06APR11	25MAY11
S1-5135B10	Pipe Laying & Connection	25	07NOV10	01DEC10	10FEB11	06MAY11
S1-5135B20	Sleeve Pipe Grouting	10	02DEC10	11DEC10	08AUG11	18AUG11
S1-5135B30	Backfilling & Reinstatement	30	12DEC10	10JAN11	19AUG11	17SEP11
S1-5140	Area E2 Portional Pipe Testing	14	07SEP11	20SEP11	18OCT11	31OCT11
S1-5140B10	Area E2 Portional Pipe Testing	14	01APR11	14APR11	18OCT11	31OCT11
Portion F						
S1-6010	Portion F Pipe Works CH895.5-1240.5 (O)	180	23NOV10	21MAY11	21JAN11	18JUL11
S1-6010B10	Stage 1 Excavation & Shoring CH1060-1240.5	103	24MAR11	01JUL10	02MAR11	09JUN11
S1-6010B20	Formation Trimming	10	02JUL10	11JUL10	10JUN11	16JUN11
S1-6010B30	Pipe Laying & Connection (Welding)	30	12JUL10	10AUG10	20JUN11	19JUL11
S1-6010B40	Backfilling & Reinstatement	50	11AUG10	29SEP10	20JUL11	07SEP11
S1-6010C10	Stage 2 Excavation & Shoring CH895.5-1060	40	02DEC10	10JAN11	08SEP11	17OCT11
S1-6020	Portion F DN800 SWM Works CH432.0-494.7 (O)	120	26JUL10	22NOV10	23SEP10	20JAN11
S1-6020A10	Portion F DN800 SWM Works CH432.0-494.7	120	12NOV10	11MAR11	20JUN11	17OCT11
S1-6020A10	Area F Portional Pipe Testing	14	22MAY11	04JUN11	18OCT11	31OCT11
Portion H1						
S1-7010	Portion H1 Temporary Assess Road	80	28DEC09A	31JAN10	26DEC09A	05MAR10
S1-7020	Portion H1 Pipe Works CH1468.5-1516.5 (O)	40	22MAY11	30JUN10	20JUL10	26AUG11
S1-7030	Portion H1 Pipe Works CH1516.5-1544.7 (O-S)	50	01JUL11	19AUG11	29AUG11	17OCT11
S1-7040	Area H1 Portional Pipe Testing	14	20AUG11	02SEP11	18OCT11	31OCT11
Portion J						
S1-8010	Portion J Pipe Works CH0-46.0 (O-S Wall)	40	28JUL11	06SEP11	08SEP11	17OCT11
S1-8020	Portion J Pipe Works CH46.0-390.0 (O)	300	02OCT10	12NOV10	12NOV10	07SEP11
S1-8020B10	Stage 1 Excavation & Shoring CH250-290 S1	55	22JUN10	16AUG10	28AUG10	23OCT10
S1-8020B20	Pipe Laying & Connection (Welding)	20	16AUG10	04SEP10	23OCT10	11NOV10
S1-8020B30	Associated Chamber Construction	30	05SEP10	04OCT10	12DEC10	11DEC10
S1-8020B40	Backfilling & Reinstatement	15	05OCT10	18OCT10	12DEC10	26DEC10
S1-8020B50	Stage 1 Excavation & Shoring CH250-290 S2	20	27FEB11	18MAR11	08MAY11	25MAY11
S1-8020B60	Associated Chamber Construction	30	19MAR11	17APR11	26MAY11	24JUN11
S1-8020B70	Backfilling & Reinstatement	15	19APR11	02MAY11	25JUN11	06JUL11

3 Months Rolling Program (April 2011)


Wo Hing - Penta-Ocean Joint Venture

Start date: 07SEP09
 Finish date: 05NOV12
 Data date: 04JAN10
 Run date: 12APR11
 Page number: 4A
 © Primavera Systems, Inc.

Legend:
 ■ Early bar
 ■ Progress bar
 ■ Sribal bar
 ■ Summary bar
 ■ Start milestone point
 ■ Finish milestone point





3 Months Rolling Program (April 2011)



Wo Hing - Penta-Ocean Joint Venture

Start date	07SEP09
Finish date	05NOV12
Date date	04JAN10
Run date	12APR11
Page number	5A
© Primavera Systems, Inc.	

Act ID	Description	Orig Dur	Early Start	Early Finish	Late Start	Late Finish
M1009B20	Excavation of Cofferdam	80	28DEC10	17MAR11	07JAN11	27MAR11
M1090	Sai Ying Pun Cofferdam for Landfill (J)	180	21FEB10	19AUG10	10APR10	08OCT10
M2060	Set-up For Pipe Pulling	60	21JUL10	18SEP10	07SEP10	05NOV10
M2090A10	Mobilization of Plants & Machines	8	27JAN11	03FEB11	08FEB11	13FEB11
M2090A20	Set-up For Pipe Pulling	90	04FEB11	04MAY11	14FEB11	14MAY11
M2070	Dredging Works	150	22APR10	18SEP10	09JUN10	05NOV10
M2080	Portion 1 Submarine Pipe Pulling	130	19SEP10	26JAN11	06NOV10	15MAR11
M2090B10	Portion 1 Submarine Pipe Pulling	85	09MAY11	28JUL11	15MAY11	07AUG11
M2090	Portion H1&J Tie-in With Submarine Pipe Line	30	27JAN11	25FEB11	16MAR11	14APR11
M2090A10	Portion H1&J Tie-in With Submarine Pipe Line	20	29JUL11	17AUG11	08AUG11	27AUG11
M2100	Portion 1 Submarine Pipe Pressure Testing &	30	28FEB11	27MAR11	15APR11	14MAY11
M2100A10	Portion H1&J Seawall Reinstatement	20	18AUG11	06SEP11	28AUG11	16SEP11
M2110	Portion H1&J Seawall Reinstatement	120	28MAR11	25JUL11	29MAY11	25SEP11
M2110A10	Portion H1&J Seawall Reinstatement	90	18AUG11	15NOV11	17SEP11	15DEC11
M2120	Portion 1 Submarine Pipeline Backfilling	185	28MAR11	28SEP11	19MAY11	15NOV11
M2120A10	Portion 1 Submarine Pipeline Backfilling	150	30MAY11	28OCT11	19JUL11	15DEC11
M2130	CP Test Box Installation (On Land)	60	28MAR11	26MAY11	02SEP11	31OCT11
M2130A10	CP Test Box Installation (On Land)	60	07SEP11	05NOV11	17SEP11	15NOV11
M2140	CIP Test (Close Interval Potential Survey)	30	29SEP11	28OCT11	16NOV11	15DEC11
M2140A10	CIP Test (Close Interval Potential Survey)	30	08NOV11	05DEC11	16NOV11	15DEC11
M2150	Completion of Section 1 Works	0		15DEC11		15DEC11
*Section 2						
		449	07SEP09 A	28NOV10	07SEP09 A	28NOV10
*Subitem 4						
		576	07SEP09 A	05APR11	07SEP09 A	05APR11
*Subitem 5						
		1156	07SEP09 A	08NOV12	07SEP09 A	08NOV12



3 Months Rolling Program (April 2011)

Wo Hing - Penta-Ocean Joint Venture

Start date	07SEP09
Finish date	08NOV12
Data date	04JAN10
Run date	12APR11
Page number	6A
© Primavera Systems, Inc.	



東業德勤測試顧問有限公司
ETS-TESTCONSULT LIMITED

Appendix F

ET Weekly Site Inspection Records

	Implementation Stages*			Remark
	Yes	No	Not Obs N/A	
Environmental Checklist				
Noise Impact				
▪ The approved method of working, equipment and sound-reducing measures (e.g. use of silenced type of equipment, etc.) shall be adapted.	√			
▪ The constructions works should be scheduled to minimize noise nuisance. Concurrent noisy works should be carried out at different time slots or spread around the construction sites in order to help to reduce the cumulative noise effect produced in the construction process.	√			
▪ Noisy equipment and mobile plant shall always be site away from NSRs.	√			
▪ Machines and plant that may be in intermittent use should be shut down between work periods or should be throttled down to a minimum.	√			
▪ Powered mechanical equipment (PME) should be covered or shielded by appropriate acoustic materials.	√			
▪ Mobile or movable noise barriers should be erected near to the construction plants to reduce the noise levels from stationary items of PME whenever practicable.	√			
▪ Quality Powered mechanical equipment (Quality PME), which are construction plants and equipments that are notably quieter, more environmental friendly and efficiently, recognized by the Noise Control Authority for the purpose of CNP application should be used to reduce the noise generated from the construction plants effectively. The Contractor shall note the required procedures involved in application of the QPME.	√			
▪ Well maintained plant should be operated on-site and plant should be serviced regularly during the construction works.	√			
▪ Air compressors and hand held breakers should have noise labels.	√			
▪ Compressors and generators should operate with door closed.	√			
▪ Material stockpiles and other structures should be effectively utilised, where practicable, to screen noise from on-site construction activities.	√			
Water Quality				
Mitigation Measures for Dredging				
▪ Dredging should be undertaken using one grab dredger only with a maximum production rate of 4,000m ³ per day.			√	No dredging work was observed.
▪ Deployment of frame type silt curtain should be fully enclosed the grab while dredging works are in progress.			√	No dredging work was observed.
▪ Deployment of silt screen should be at the sea water intake at Kowloon South Salt Water Pumping Station while dredging works are in progress	√			
▪ Tight-closing grabs should be used to minimize the loss of sediment to suspension during dredging works. For dredging of any contaminated mud, closed watertight grabs must be used.	√			
▪ All vessels should be sized so that adequate clearance is maintained between vessels and the seabed in all tide conditions, to ensure that undue turbidity is not generated by turbulence from vessel movement or propeller wash	√			
▪ The decks of all vessels should be kept tidy and free of oil or other substances that might be accidentally or otherwise washed overboard	√			
▪ Adequate free board shall be maintained on barges to ensure that decks are not washed by wave action.	√			
▪ All barges used for the transport of dredged materials should be fitted with tight bottom seals to prevent leakage of material during loading and transport	√			
▪ Dredging activities should not cause foam, oil, grease, scurm, litter or other objectionable matter to be present in the water within the site or dumping grounds			√	No dredging work was observed.
▪ Loading of barges should be controlled to prevent splashing of material into the surrounding waters. Barges should not be filled to a level that would cause the overflow of materials or sediment laden water during loading or transportation	√			
▪ The speed of vessels should be controlled within the works area to prevent propeller wash from stirring up the seabed sediments	√			



Environmental Checklist		Implementation Stages*			Remark
		Yes	No	Not Obs N/A	
Water Quality					
Mitigation Measures for other Construction Activities					
▪	Sedimentation tanks with sufficient capacity, constructed from pre-formed individual cells of approximately 6 to 8 m ³ capacities, are recommended as a general mitigation measure which can be used for settling surface runoff prior to disposal. The system capacity should be flexible and able to handle multiple inputs from a variety of sources and suited to applications where the influent is pumped	√			
▪	Manholes (including newly constructed ones) should always be adequately covered and temporarily sealed so as to prevent silt, construction materials or debris being washed into the storm runoff being directed into foul sewers	√			
▪	Construction activities should not cause foam, oil, grease, scum, litter or other objectionable matter to be present in the water within the site or dumping grounds		√		Item 1
▪	Fuel tanks and storage areas should be provided with locks and be located on sealed areas, within bunds of a capacity equal to 110% of the storage capacity of the largest tank, to prevent spilled fuel oils from reaching the coastal waters of the Victoria Harbour and Western Harbour WCs	√			
▪	Portable chemical toilets should be used to handle construction workforce sewage prior to discharge to the existing trunk sewer. Sufficient numbers of portable toilets shall be provided by a licensed contractor to serve the construction workers. The Contractor shall also be responsible for waste disposal and maintenance practices.	√			
▪	Construction site runoff should be prevented or minimised in accordance with the guidelines stipulated in the EPD's Practice Note for Professional Persons, Construction Site Drainage (ProPECC PN 1/94). All discharges from the construction site should be controlled to comply with the standards for effluents discharged into the Victoria Harbour WCZ under the IM-DSS.	√			
▪	Unnecessary water retained in receptacles and standing water should be avoided to prevent mosquito breeding.	√			
▪	An adequately designed and located wheel washing bay should be provided at every site exit, and wash-water should have sand and silt settled out and removed at least on a weekly basis to ensure the continued efficiency of the process.			√	
▪	The section of access road leading to, and exiting from, the wheel-wash bay to the public road should be paved with sufficient backfill toward the wheel-wash bay to prevent vehicle tracking of soil and silty water to public roads and drains			√	
Waste Management					
C&D Materials					
▪	Excavated materials should be reused on-site as backfilling material and for landscaping works as far as practicable.			√	
▪	C&D material generated from excavation works should be disposed of at public fill reception facilities for other beneficial uses.			√	
▪	A recording system for the amount of wastes generated, recycled and disposed (including the disposal sites) should be proposed			√	
▪	A recording system for the amount of wastes generated, recycled and disposed (including the disposal sites) should be used, e.g. trip ticket system for chemical waste disposal. Quantities could be determined by weighing each load or other suitable methods.			√	
Chemical Waste					
▪	Good quality containers compatible with the chemical wastes should be used, and incompatible chemicals should be stored separately.	√			
▪	Appropriate labels should be securely attached on each chemical waste container indicating the corresponding chemical characteristics of the chemical waste, such as explosive, flammable, oxidizing, irritant, toxic, harmful, corrosive, etc.	√			
▪	The Contractor shall use a licensed collector to transport and dispose of the chemical wastes, to either the approved Chemical Waste Treatment Centre, or another licensed facility.	√			

Environmental Checklist		Implementation Stages*			Remark
		Yes	No	Not Obs N/A	
Waste Management					
General Refuse					
▪	General refuse should be stored in enclosed bins or compaction units separate from C&D material.	√			
▪	A reputable waste collector should be employed by the contractor to remove general refuse from the site, separately from C&D material.	√			
▪	An enclosed and covered area should be provided to reduce the occurrence of 'wind blown' light material.	√			
Marine Dredged Sediment (During transportation and disposal)					
▪	Bottom opening of barges shall be fitted with tight fitting seals to prevent leakage of material. Excess material shall be cleaned from the decks and exposed fittings of barges and dredgers before the vessel is moved			√	No dredging work was observed.
▪	Monitoring of the barge loading shall be conducted to ensure that loss of material does not take place during transportation. Transport barges or vessels shall be equipped with automatic self-monitoring devices as specified by the EPD			√	No dredging work was observed.
▪	Barges or hopper barges shall not be filled to a level that would cause the overflow of materials or sediment laden water during loading or transportation.			√	No dredging work was observed.
Site Practices					
▪	Nomination of an approved person, such as a site manager, to be responsible for good site practices, arrangements for collection and effective disposal to an appropriate facility, of all wastes generated at the site	√			
▪	Training of site personnel in proper waste management and chemical handling procedures	√			
▪	Provision of sufficient waste disposal points and regular collection of waste	√			
▪	Good site practices should be adopted to clean the rubbish and litter on a regular basis so as to prevent the rubbish and litter from dropping into the nearby environment.	√			
▪	Appropriate measures to minimise windblown litter and dust during transportation of waste by either covering trucks or by transporting wastes in enclosed containers	√			
Waste Reduction Measures					
▪	Sort C&D material from demolition and decommissioning of the existing facilities to recover recyclable portions such as metals	√			
▪	Segregation and storage of different types of waste in different containers, skips or stockpiles to enhance reuse or recycling of materials and their proper disposal	√			
▪	Encourage collection of aluminium cans by providing separate labelled bins to enable this waste to be segregated from other general refuse generated by the work force	√			
▪	Proper storage and site practices to minimise the potential for damage or contamination of construction materials	√			
▪	Plan and stock construction materials carefully to minimise amount of waste generated and avoid unnecessary generation of waste	√			

Environmental Checklist	Implementation Stages*			Remark
	Yes	No	Not Obs N/A	
Marine Ecology				
• Use of one grab dredger only with a maximum production rate of 4,000m ³ per day for dredging.			√	No dredging work was observed.
• Deployment of frame type silt curtain to fully enclose the grab while dredging works are in progress.			√	No dredging work was observed.
• Deployment of silt screen at the sea water intake at Kowloon South Salt Water Pumping Station while dredging works are in progress.	√			
• Good site practices to avoid silt runoff from construction works associated with the construction of the submarine watermain.	√			
Good Site Practices				
• The Environmental Permit should be displaced conspicuously on site.	√			
• Construction noise permits should be posted at site entrance or available for site inspection.	√			
• Chemical storage area provided with lock and located on sealed areas.	√			
• All chemicals should be placed at the banded area with adequate band capacity (>110% of largest tank).	√			
• Any unused chemicals or those with remaining functional capacity should be recycled.	√			
• All generators, fuel and oil storage are within bundle areas.	√			
• Regular cleaning and maintenance programme for waste storage area, drainage systems, silt traps, sumps and oil interceptors.	√			
• A collection area should be provided where waste can be stored and loaded prior to removal from site. An enclosed and covered area is preferred to reduce the occurrence of 'wind blown' light material. If an open area is unavoidable for the storage or loading/unloading of wastes, then the area should be bunded and all the polluted surface run-off collected within this area should be diverted into wastewater treatment system.		√		Item 3

Summary of the Weekly Site Inspection:

Item	Details of defective works or observations	Status of the item (closed / continue follow-up)	Proposed Follow Up Action (if required)	Photo Ref.	Target Completion Date
1	Follow up action to item 4 on 28/03/11, the previous excavated materials (e.g. rock and mud) noted accumulated along the sea-front at Portion J was removed. Besides, steel bunding was noted improved in order to prevent the excavated materials dropping into the sea. However, the Contractor was still reminded to remove all excavated materials regularly.	Follow-up	To remove all excavated materials regularly	110408_001 110408_002	12/04/11
2	Follow up action to item 5 on 28/03/11, because of no marine work near the Portion J, the silt screen had been removed. The rubbish was trapped between the inner and outer silt screen had been clear.	Closed	---	110408_003	---
3	Rubbish skip at Portion J was noted full of rubbish.	Follow-up	To dispose of the rubbish properly and regularly and provide cover for the rubbish skip.	110408_004	12/04/11
4	Water leakage was observed from an air-conditioner at Contractor's site office at Portion J.	Follow-up	To connect the water outlet of the air-conditioner to an appropriate container in order to prevent water leakage to the nearby environment.	110408_005	12/04/11

Remark

Inspected by	Name	Signature	Date
	Tony Chow	周若然	08 April 2011

Photos




Photo 110408_001 (sea front at Portion J)




Photo 110408_002 (sea front at Portion J)




Photo 110408_003 (Silt screen at Portion J)




Photo 110408_004 (rubbish skip at Portion J)



Photo 110408_005 (Contractor's site office at Portion J)

Contract No. 9/MWSD/08
 Laying of Western Cross Harbour Main and Associated Land Mains
 From West Kowloon to Sai Ying Pun

WEEKLY SITE INSPECTION CHECKLIST

Inspection Date	12/04/11	Inspected by	RE	IEC	Contractor	ET
Time	9:45	Name		/	Salvo	Wada

Weather : Sunny / Fine / Cloudy / Drizzle / Rain / Storm / Hazy
 Condition : Calm / Light / Breeze / Strong
 Wind : 26 °C
 Humidity : High / Moderate / Low

Environmental Checklist	Implementation Stages*			Remark
	Yes	No	Not Obs	
Fugitive Dust Emission				
▪ Dust control / mitigation measures shall be provided to prevent dust nuisance.	√			
▪ Any excavated dusty materials or stockpile of dusty materials should be covered entirely by impervious sheeting or sprayed with water so as to maintain the entire surface wet, and recovered or backfilled or reinstated within 24 hours of the excavation or unloading.	√			
▪ The working area of excavation should be sprayed with water immediately before, during and immediately after the operations so as to maintain the entire surface wet.	√			
▪ The load of dusty materials carried by vehicle leaving a construction site should be covered entirely by clean impervious sheeting to ensure that the dusty materials do not leak from the vehicle	√			
▪ Where a site boundary adjoins a road, streets or other area accessible to the public, hoarding of not less than 2.4m high from ground level should be provided along the entire length except for a site entrance or exit.	√			
▪ The area where vehicle washing takes place and the section of the road between the washing facilities and the exit point should be paved with concrete, bituminous materials or hardcores.	√		√	
▪ Every main haul road should be sealed with concrete and kept clear of dusty materials or sprayed with water so as to maintain the entire road surface wet.	√			
▪ The portion of road leading only to a construction site that is within 30m of a designated vehicle entrance or exit should be kept clear of dusty materials.	√			
▪ All dusty materials should be sprayed with water prior to any loading, unloading or transfer operation so as to maintain the dusty material wet.	√			
▪ Vehicle speed should be limited to 10 kph except on completed access roads.	√			
▪ Every vehicle should be washed to remove any dusty materials from its body and wheels before leaving the construction sites.	√		√	
▪ The public road around the site entrance should be kept clean and free from dust.	√			
▪ Vehicle and equipment should be switched off while not in use.	√			
▪ All plant and equipment should be well maintained e.g. without black smoke emission.	√			
▪ Open burning should be prohibited.	√			

Environmental Checklist	Implementation Stages*			Remark
	Yes	No	Not Obs N/A	
Water Quality				
Mitigation Measures for other Construction Activities				
<ul style="list-style-type: none"> Sedimentation tanks with sufficient capacity, constructed from pre-formed individual cells of approximately 6 to 8 m³ capacities, are recommended as a general mitigation measure which can be used for settling surface runoff prior to disposal. The system capacity should be flexible and able to handle multiple inputs from a variety of sources and suited to applications where the influent is pumped Manholes (including newly constructed ones) should always be adequately covered and temporarily sealed so as to prevent silt, construction materials or debris being washed into the storm runoff being directed into foul sewers Construction activities should not cause foam, oil, grease, scum, litter or other objectionable matter to be present in the water within the site or dumping grounds Fuel tanks and storage areas should be provided with locks and be located on sealed areas, within bunds of a capacity equal to 110% of the storage capacity of the largest tank, to prevent spilled fuel oils from reaching the coastal waters of the Victoria Harbour and Western Harbour WCs Portable chemical toilets should be used to handle construction workforce sewage prior to discharge to the existing trunk sewer. Sufficient numbers of portable toilets shall be provided by a licensed contractor to serve the construction workers. The Contractor shall also be responsible for waste disposal and maintenance practices. Construction site runoff should be prevented or minimised in accordance with the guidelines stipulated in the EPD's Practice Note for Professional Persons, Construction Site Drainage (ProPECC PN 1/94). All discharges from the construction site should be controlled to comply with the standards for effluents discharged into the Victoria Harbour WCZ under the TM-DSS. Unnecessary water retained in receptacles and standing water should be avoided to prevent mosquito breeding. An adequately designed and located wheel washing bay should be provided at every site exit, and wash-water should have sand and silt settled out and removed at least on a weekly basis to ensure the continued efficiency of the process. The section of access road leading to, and exiting from, the wheel-wash bay to the public road should be paved with sufficient backfill toward the wheel-wash bay to prevent vehicle tracking of soil and silty water to public roads and drains 	√			
Waste Management				
C&D Materials				
<ul style="list-style-type: none"> Excavated materials should be reused on-site as backfilling material and for landscaping works as far as practicable. C&D material generated from excavation works should be disposed of at public fill reception facilities for other beneficial uses. A recording system for the amount of wastes generated, recycled and disposed (including the disposal sites) should be proposed A recording system for the amount of wastes generated, recycled and disposed (including the disposal sites) should be used, e.g. trip ticket system for chemical waste disposal. Quantities could be determined by weighing each load or other suitable methods. 	√		√	
Chemical Waste				
<ul style="list-style-type: none"> Good quality containers compatible with the chemical wastes should be used, and incompatible chemicals should be stored separately. Appropriate labels should be securely attached on each chemical waste container indicating the corresponding chemical characteristics of the chemical waste, such as explosive, flammable, oxidizing, irritant, toxic, harmful, corrosive, etc. The Contractor shall use a licensed collector to transport and dispose of the chemical wastes, to either the approved Chemical Waste Treatment Centre, or another licensed facility. 	√			

Implementation Stages*	Remark		
	Yes	No	Not Obs
Environmental Checklist			
Waste Management			
General Refuse			
General refuse should be stored in enclosed bins or compaction units separate from C&D material.	√		
A reputable waste collector should be employed by the contractor to remove general refuse from the site, separately from C&D material.	√		
An enclosed and covered area should be provided to reduce the occurrence of 'wind blown' light material.	√		
Marine Dredged Sediment (During transportation and disposal)			
Bottom opening of barges shall be fitted with tight fitting seals to prevent leakage of material. Excess material shall be cleaned from the decks and exposed fittings of barges and dredgers before the vessel is moved	√		No dredging work was observed.
Monitoring of the barge loading shall be conducted to ensure that loss of material does not take place during transportation. Transport barges or vessels shall be equipped with automatic self-monitoring devices as specified by the EPD	√		No dredging work was observed.
Barges or hopper barges shall not be filled to a level that would cause the overflow of materials or sediment laden water during loading or transportation.	√		No dredging work was observed.
Site Practices			
Nomination of an approved person, such as a site manager, to be responsible for good site practices, arrangements for collection and effective disposal to an appropriate facility, of all wastes generated at the site	√		
Training of site personnel in proper waste management and chemical handling procedures	√		
Provision of sufficient waste disposal points and regular collection of waste	√		
Good site practices should be adopted to clean the rubbish and litter on a regular basis so as to prevent the rubbish and litter from dropping into the nearby environment.	√		
Appropriate measures to minimise windblown litter and dust during transportation of waste by either covering trucks or by transporting wastes in enclosed containers	√		
Waste Reduction Measures			
Sort C&D material from demolition and decommissioning of the existing facilities to recover recyclable portions such as metals	√		
Segregation and storage of different types of waste in different containers, skips or stockpiles to enhance reuse or recycling of materials and their proper disposal	√		
Encourage collection of aluminium cans by providing separate labelled bins to enable this waste to be segregated from other general refuse generated by the work force	√		
Proper storage and site practices to minimise the potential for damage or contamination of construction materials	√		
Plan and stock construction materials carefully to minimise amount of waste generated and avoid unnecessary generation of waste	√		

Environmental Checklist	Implementation Stages*			Remark
	Yes	No	Not Obs N/A	
Marine Ecology				
Use of one grab dredger only with a maximum production rate of 4,000m ³ per day for dredging.			√	No dredging work was observed.
Deployment of frame type silt curtain to fully enclose the grab while dredging works are in progress.			√	No dredging work was observed.
Deployment of silt screen at the sea water intake at Kowloon South Salt Water Pumping Station while dredging works are in progress.		√		Item 4
Good site practices to avoid silt runoff from construction works associated with the construction of the submarine watermain.	√			
Good Site Practices				
The Environmental Permit should be displaced conspicuously on site.	√			
Construction noise permits should be posted at site entrance or available for site inspection.	√			
Chemical storage area provided with lock and located on sealed areas.	√			
All chemicals should be placed at the banded area with adequate band capacity (>110% of largest tank).	√			
Any unused chemicals or those with remaining functional capacity should be recycled.	√			
All generators, fuel and oil storage are within bundle areas.	√			
Regular cleaning and maintenance programme for waste storage area, drainage systems, silt traps, sumps and oil interceptors.	√			
A collection area should be provided where waste can be stored and loaded prior to removal from site. An enclosed and covered area is preferred to reduce the occurrence of 'wind blown' light material. If an open area is unavoidable for the storage or loading/unloading of wastes, then the area should be bunded and all the polluted surface run-off collected within this area should be diverted into wastewater treatment system.	√			

Summary of the Weekly Site Inspection:

Item	Details of defective works or observations	Status of the item (closed / continue follow-up)	Proposed Follow Up Action (if required)	Photo Ref.	Target Completion Date
1	Follow up action to item 3 on 22/03/11, item 4 on 28/03/11 and item 1 on 08/04/11, the most of excavated materials (e.g. rock and mud) noted accumulated along the sea-front at Portion J was removed. Besides, steel bunding was noted improved in order to prevent the excavated materials dropping into the sea.	Closed	--	110412_001 110412_002	--
2	Follow up action to item 3 on 08/04/11, rubbish skip at Portion J was removed.	Closed	--	110412_003	--
3	Follow up action to item 4 on 08/04/11, the water outlet of the air-conditioner at Contractor's site office at Portion J was connect to an appropriate container and no condensed water was noted on the ground.	Closed	--	110412_004	--
4	Silt screen at the sea water intake at Kowloon Salt Water Pumping Station was found damaged (although no marine works were carried out during the inspection day).	Follow-up	To repair the damaged part of the silt screen before the maine works started and also maintain the silt screen properly during any marine works.	110412_005	Before any marine works start

Remark

Inspected by	Name	Signature	Date
	Linda Law	<i>Linda Law</i>	12 April 2011

Photos



Photo 110412_001 (sea front at Portion J)



Photo 110412_002 (sea front at Portion J)




Photo 110412_003 (Portion J)



Photo 110412_004 (Contractor's site office at Portion J)




Photo 110412_005 (Silt screen at the sea water intake at Kowloon South Salt Water Pumping Station)

WEEKLY SITE INSPECTION CHECKLIST

Inspection Date	26/04/11	Inspected by	RE [Signature]	IEC	Contractor	ET
Time	14:00	Name	[Signature]	[Signature]	JNG [Signature]	Wah Lam

Weather Condition : Sunny / Fine / Cloudy / Drizzle / Rain / Storm / Hazy
 Wind : Calm / Light / Breeze / Strong
 Temperature : 28°C
 Humidity : High / Moderate / Low

Environmental Checklist	Implementation Stages*			Remark
	Yes	No	Not Obs / N/A	
Fugitive Dust Emission				
▪ Dust control / mitigation measures shall be provided to prevent dust nuisance.	✓			
▪ Any excavated dusty materials or stockpile of dusty materials should be covered entirely by impervious sheeting or sprayed with water so as to maintain the entire surface wet, and recovered or backfilled or reinstated within 24 hours of the excavation or unloading.	✓			
▪ The working area of excavation should be sprayed with water immediately before, during and immediately after the operations so as to maintain the entire surface wet.	✓			
▪ The load of dusty materials carried by vehicle leaving a construction site should be covered entirely by clean impervious sheeting to ensure that the dusty materials do not leak from the vehicle	✓			
▪ Where a site boundary adjoins a road, streets or other area accessible to the public, hoarding of not less than 2.4m high from ground level should be provided along the entire length except for a site entrance or exit.	✓			
▪ The area where vehicle washing takes place and the section of the road between the washing facilities and the exit point should be paved with concrete, bituminous materials or hardcores.			✓	
▪ Every main haul road should be sealed with concrete and kept clear of dusty materials or sprayed with water so as to maintain the entire road surface wet.	✓			
▪ The portion of road leading only to a construction site that is within 30m of a designated vehicle entrance or exit should be kept clear of dusty materials.	✓			
▪ All dusty materials should be sprayed with water prior to any loading, unloading or transfer operation so as to maintain the dusty material wet.	✓			
▪ Vehicle speed should be limited to 10 kph except on completed access roads.	✓			
▪ Every vehicle should be washed to remove any dusty materials from its body and wheels before leaving the construction sites.			✓	
▪ The public road around the site entrance should be kept clean and free from dust.	✓			
▪ Vehicle and equipment should be switched off while not in use.	✓			
▪ All plant and equipment should be well maintained e.g. without black smoke emission.	✓			
▪ Open burning should be prohibited.	✓			



Environmental Checklist		Implementation Stages*			Remark
		Yes	No	Not Obs	
Water Quality					
Mitigation Measures for other Construction Activities					
▪	Sedimentation tanks with sufficient capacity, constructed from pre-formed individual cells of approximately 6 to 8 m ³ capacities, are recommended as a general mitigation measure which can be used for settling surface runoff prior to disposal. The system capacity should be flexible and able to handle multiple inputs from a variety of sources and suited to applications where the influent is pumped	√			
▪	Manholes (including newly constructed ones) should always be adequately covered and temporarily sealed so as to prevent silt, construction materials or debris being washed into the storm runoff being directed into foul sewers	√			
▪	Construction activities should not cause foam, oil, grease, scum, litter or other objectionable matter to be present in the water within the site or dumping grounds	√			
▪	Fuel tanks and storage areas should be provided with locks and be located on sealed areas, within bunds of a capacity equal to 110% of the storage capacity of the largest tank, to prevent spilled fuel oils from reaching the coastal waters of the Victoria Harbour and Western Harbour WCs	√			
▪	Portable chemical toilets should be used to handle construction workforce sewage prior to discharge to the existing trunk sewer. Sufficient numbers of portable toilets shall be provided by a licensed contractor to serve the construction workers. The Contractor shall also be responsible for waste disposal and maintenance practices.	√			
▪	Construction site runoff should be prevented or minimised in accordance with the guidelines stipulated in the EPD's Practice Note for Professional Persons, Construction Site Drainage (ProPECC PN 1/94). All discharges from the construction site should be controlled to comply with the standards for effluents discharged into the Victoria Harbour WCZ under the TM-DSS.	√			
▪	Unnecessary water retained in receptacles and standing water should be avoided to prevent mosquito breeding.	√			
▪	An adequately designed and located wheel washing bay should be provided at every site exit, and wash-water should have sand and silt settled out and removed at least on a weekly basis to ensure the continued efficiency of the process.				√
▪	The section of access road leading to, and exiting from, the wheel-wash bay to the public road should be paved with sufficient backfill toward the wheel-wash bay to prevent vehicle tracking of soil and silty water to public roads and drains				√
Waste Management					
C&D Materials					
▪	Excavated materials should be reused on-site as backfilling material and for landscaping works as far as practicable.				√
▪	C&D material generated from excavation works should be disposed of at public fill reception facilities for other beneficial uses.				√
▪	A recording system for the amount of wastes generated, recycled and disposed (including the disposal sites) should be proposed				√
▪	A recording system for the amount of wastes generated, recycled and disposed (including the disposal sites) should be used, e.g. trip ticket system for chemical waste disposal. Quantities could be determined by weighing each load or other suitable methods.				√
Chemical Waste					
▪	Good quality containers compatible with the chemical wastes should be used, and incompatible chemicals should be stored separately.	√			
▪	Appropriate labels should be securely attached on each chemical waste container indicating the corresponding chemical characteristics of the chemical waste, such as explosive, flammable, oxidizing, irritant, toxic, harmful, corrosive, etc.	√			
▪	The Contractor shall use a licensed collector to transport and dispose of fine chemical wastes, to either the approved Chemical Waste Treatment Centre, or another licensed facility.	√			

Environmental Checklist	Implementation Stages*			Remark
	Yes	No	Not Obs N/A	
Waste Management				
General Refuse				
General refuse should be stored in enclosed bins or compaction units separate from C&D material.	✓			
A reputable waste collector should be employed by the contractor to remove general refuse from the site, separately from C&D material.	✓			
An enclosed and covered area should be provided to reduce the occurrence of 'wind blown' light material.	✓			
Marine Dredged Sediment (During transportation and disposal)				
Bottom opening of barges shall be fitted with tight fitting seals to prevent leakage of material. Excess material shall be cleaned from the decks and exposed fittings of barges and dredgers before the vessel is moved			✓	No dredging work was observed.
Monitoring of the barge loading shall be conducted to ensure that loss of material does not take place during transportation. Transport barges or vessels shall be equipped with automatic self-monitoring devices as specified by the EPD			✓	No dredging work was observed.
Barges or hopper barges shall not be filled to a level that would cause the overflow of materials or sediment laden water during loading or transportation.			✓	No dredging work was observed.
Site Practices				
Nomination of an approved person, such as a site manager, to be responsible for good site practices, arrangements for collection and effective disposal to an appropriate facility, of all wastes generated at the site	✓			
Training of site personnel in proper waste management and chemical handling procedures	✓			
Provision of sufficient waste disposal points and regular collection of waste	✓			
Good site practices should be adopted to clean the rubbish and litter on a regular basis so as to prevent the rubbish and litter from dropping into the nearby environment.	✓			
Appropriate measures to minimise windblown litter and dust during transportation of waste by either covering trucks or by transporting wastes in enclosed containers	✓			
Waste Reduction Measures				
Sort C&D material from demolition and decommissioning of the existing facilities to recover recyclable portions such as metals	✓			
Segregation and storage of different types of waste in different containers, skips or stockpiles to enhance reuse or recycling of materials and their proper disposal	✓			
Encourage collection of aluminium cans by providing separate labelled bins to enable this waste to be segregated from other general refuse generated by the work force	✓			
Proper storage and site practices to minimise the potential for damage or contamination of construction materials	✓			
Plan and stock construction materials carefully to minimise amount of waste generated and avoid unnecessary generation of waste	✓			

Implementation Stages*		Remark	
		Yes	No
Environmental Checklist			
Marine Ecology			
Use of one grab dredger only with a maximum production rate of 4,000m ³ per day for dredging.	√		No dredging work was observed.
Deployment of frame type silt curtain to fully enclose the grab while dredging works are in progress.	√		No dredging work was observed.
Deployment of silt screen at the sea water intake at Kowloon South Salt Water Pumping Station while dredging works are in progress.	√		
Good site practices to avoid silt runoff from construction works associated with the construction of the submarine watermain.	√		
Good Site Practices			
The Environmental Permit should be displaced conspicuously on site.	√		
Construction noise permits should be posted at site entrance or available for site inspection.	√		
Chemical storage area provided with lock and located on sealed areas.	√		
All chemicals should be placed at the banded area with adequate bund capacity (>110% of largest tank).	√		
Any unused chemicals or those with remaining functional capacity should be recycled.	√		
All generators, fuel and oil storage are within bundle areas.	√		
Regular cleaning and maintenance programme for waste storage area, drainage systems, silt traps, sumps and oil interceptors.	√		
A collection area should be provided where waste can be stored and loaded prior to removal from site. An enclosed and covered area is preferred to reduce the occurrence of 'wind blown' light material. If an open area is unavoidable for the storage or loading/unloading of wastes, then the area should be bunded and all the polluted surface run-off collected within this area should be diverted into wastewater treatment system.	√		



Summary of the Weekly Site Inspection:

Item	Details of defective works or observations	Status of the item (closed / continue follow-up)	Proposed Follow Up Action (if required)	Photo Ref.	Target Completion Date
1	Follow up action to item 4 on 12/04/11, silt screen at the sea water intake at Kowloon Salt Water Pumping Station was repaired and maintained properly	Closed	---	110420_001	--

Remark

No defective observation was recorded in the weekly site inspection.

Inspected by	Name	Signature	Date
	Linda Law		20 April 2011



Photos



Photo 110420_001 (Silt screen at the sea water intake at Kowloon South Salt Water Pumping Station)

Environmental Checklist	Implementation Stages*			Remark
	Yes	No	Not Obs N/A	
Noise Impact				
▪ The approved method of working, equipment and sound-reducing measures (e.g. use of silenced type of equipment, etc.) shall be adapted.	✓			
▪ The constructions works should be scheduled to minimize noise nuisance. Concurrent noisy works should be carried out at different time slots or spread around the construction sites in order to help to reduce the cumulative noise effect produced in the construction process.	✓			
▪ Noisy equipment and mobile plant shall always be site away from NSRs.	✓			
▪ Machines and plant that may be in intermittent use should be shut down between work periods or should be throttled down to a minimum.	✓			
▪ Powered mechanical equipment (PME) should be covered or shielded by appropriate acoustic materials.	✓			
▪ Mobile or movable noise barriers should be erected near to the construction plants to reduce the noise levels from stationary items of PME whenever practicable.	✓			
▪ Quality Powered mechanical equipment (Quality PME), which are construction plants and equipments that are notably quieter, more environmental friendly and efficiently, recognized by the Noise Control Authority for the purpose of CNP application should be used to reduce the noise generated from the construction plants effectively. The Contractor shall note the required procedures involved in application of the QPME.	✓			
▪ Well maintained plant should be operated on-site and plant should be serviced regularly during the construction works.	✓			
▪ Air compressors and hand held breakers should have noise labels.	✓			
▪ Compressors and generators should operate with door closed.	✓			
▪ Material stockpiles and other structures should be effectively utilised, where practicable, to screen noise from on-site construction activities.	✓			
Water Quality				
Mitigation Measures for Dredging				
▪ Dredging should be undertaken using one grab dredger only with a maximum production rate of 4,000m ³ per day.			✓	No dredging work was observed.
▪ Deployment of frame type silt curtain should be fully enclosed the grab while dredging works are in progress.			✓	No dredging work was observed.
▪ Deployment of silt screen should be at the sea water intake at Kowloon South Salt Water Pumping Station while dredging works are in progress	✓			
▪ Tight-closing grabs should be used to minimize the loss of sediment to suspension during dredging works. For dredging of any contaminated mud, closed watertight grabs must be used.	✓			
▪ All vessels should be sized so that adequate clearance is maintained between vessels and the seabed in all tide conditions, to ensure that undue turbidity is not generated by turbulence from vessel movement or propeller wash	✓			
▪ The decks of all vessels should be kept tidy and free of oil or other substances that might be accidentally or otherwise washed overboard	✓			
▪ Adequate free board shall be maintained on barges to ensure that decks are not washed by wave action.	✓			
▪ All barges used for the transport of dredged materials should be fitted with tight bottom seals to prevent leakage of material during loading and transport	✓			
▪ Dredging activities should not cause foam, oil, grease, scum, litter or other objectionable matter to be present in the water within the site or dumping grounds			✓	No dredging work was observed.
▪ Loading of barges should be controlled to prevent splashing of material into the surrounding waters. Barges should not be filled to a level that would cause the overflow of materials or sediment laden water during loading or transportation	✓			
▪ The speed of vessels should be controlled within the works area to prevent propeller wash from stirring up the seabed sediments	✓			

Implementation Stages*		Remark	
		Yes	No
Environmental Checklist			
Waste Management			
General Refuse			
General refuse should be stored in enclosed bins or compaction units separate from C&D material.	√		
A reputable waste collector should be employed by the contractor to remove general refuse from the site, separately from C&D material.	√		
An enclosed and covered area should be provided to reduce the occurrence of 'wind blown' light material.	√		
Marine Dredged Sediment (During transportation and disposal)			
Bottom opening of barges shall be fitted with light fitting seals to prevent leakage of material. Excess material shall be cleaned from the decks and exposed fittings of barges and dredgers before the vessel is moved			√ No dredging work was observed.
Monitoring of the barge loading shall be conducted to ensure that loss of material does not take place during transportation. Transport barges or vessels shall be equipped with automatic self-monitoring devices as specified by the EPD			√ No dredging work was observed.
Barges or hopper barges shall not be filled to a level that would cause the overflow of materials or sediment laden water during loading or transportation.			√ No dredging work was observed.
Site Practices			
Nomination of an approved person, such as a site manager, to be responsible for good site practices, arrangements for collection and effective disposal to an appropriate facility, of all wastes generated at the site	√		
Training of site personnel in proper waste management and chemical handling procedures	√		
Provision of sufficient waste disposal points and regular collection of waste	√		
Good site practices should be adopted to clean the rubbish and litter on a regular basis so as to prevent the rubbish and litter from dropping into the nearby environment.	√		
Appropriate measures to minimise windblown litter and dust during transportation of waste by either covering trucks or by transporting wastes in enclosed containers	√		
Waste Reduction Measures			
Sort C&D material from demolition and decommissioning of the existing facilities to recover recyclable portions such as metals	√		
Segregation and storage of different types of waste in different containers, skips or stockpiles to enhance reuse or recycling of materials and their proper disposal	√		
Encourage collection of aluminium cans by providing separate labelled bins to enable this waste to be segregated from other general refuse generated by the work force	√		
Proper storage and site practices to minimise the potential for damage or contamination of construction materials	√		
Plan and stock construction materials carefully to minimise amount of waste generated and avoid unnecessary generation of waste	√		

Environmental Checklist	Implementation Stages*			Remark
	Yes	No	Not Obs / N/A	
Marine Ecology				
Use of one grab dredger only with a maximum production rate of 4,000m ³ per day for dredging.			✓	No dredging work was observed.
Deployment of frame type silt curtain to fully enclose the grab while dredging works are in progress.			✓	No dredging work was observed.
Deployment of silt screen at the sea water intake at Kowloon South Salt Water Pumping Station while dredging works are in progress.	✓			
Good site practices to avoid silt runoff from construction works associated with the construction of the submarine watermain.	✓			
Good Site Practices				
The Environmental Permit should be displaced conspicuously on site.	✓			
Construction noise permits should be posted at site entrance or available for site inspection.	✓			
Chemical storage area provided with lock and located on sealed areas.	✓			
All chemicals should be placed at the banded area with adequate band capacity (>110% of largest tank).	✓			
Any unused chemicals or those with remaining functional capacity should be recycled.	✓			
All generators, fuel and oil storage are within bundle areas.	✓			
Regular cleaning and maintenance programme for waste storage area, drainage systems, silt traps, sumps and oil interceptors.	✓			
A collection area should be provided where waste can be stored and loaded prior to removal from site. An enclosed and covered area is preferred to reduce the occurrence of 'wind blown' light material. If an open area is unavoidable for the storage or loading/unloading of wastes, then the area should be bunded and all the polluted surface run-off collected within this area should be diverted into wastewater treatment system.	✓			

Summary of the Weekly Site Inspection:

Item	Details of defective works or observations	Status of the item (closed / continue follow-up)	Proposed Follow Up Action (if required)	Photo Ref.	Target Completion Date

Remark

No defective observation was recorded in the weekly site inspection.

Inspected by	Name	Signature	Date
	Linda Law	<i>Linda Law</i>	28 April 2011



Appendix G

Implementation Schedule of Mitigation Measures



Environmental Protection Measures		Location	Implementation Status		
			Implemented	Partially implemented	Not implemented
Noise Impact					
Well maintained plant should be operated on-site and plant should be serviced regularly during the construction works.	All areas	✓			
Air compressors and hand held breakers should have noise labels.	All areas	✓			
Compressors and generators should operate with door closed.	All areas	✓			
Material stockpiles and other structures should be effectively utilised, where practicable, to screen noise from on-site construction activities.	All areas	✓			
Water Quality					
Mitigation Measures for Dredging					
Dredging should be undertaken using one grab dredger only with a maximum production rate of 4,000m ³ per day.	Marine				✓
Deployment of frame type silt curtain should be fully enclose the grab while dredging works are in progress.	Marine				✓
Deployment of silt screen should be at the sea water intake at Kowloon South Salt Water Pumping Station while dredging works are in progress	Marine		✓		
Tight-closing grabs should be used to minimize the loss of sediment to suspension during dredging works. For dredging of any contaminated mud, closed watertight grabs must be used.	Marine				✓
All vessels should be sized so that adequate clearance is maintained between vessels and the seabed in all tide conditions, to ensure that undue turbidity is not generated by turbulence from vessel movement or propeller wash	Marine	✓			
The decks of all vessels should be kept tidy and free of oil or other substances that might be accidentally or otherwise washed overboard	Marine	✓			
Adequate free board shall be maintained on barges to ensure that decks are not washed by wave action.	Marine	✓			
All barges used for the transport of dredged materials should be fitted with tight bottom seals to prevent leakage of material during loading and transport	Marine				✓
Construction activities should not cause foam, oil, grease, scum, litter or other objectionable matter to be present in the water within the site or dumping grounds	Marine	✓			
Loading of barges should be controlled to prevent splashing of material into the surrounding waters. Barges should not be filled to a level that would cause the overflow of materials or sediment laden water during loading or transportation	Marine	✓			
The speed of vessels should be controlled within the works area to prevent propeller wash from stirring up the seabed sediments	Marine	✓			
Mitigation Measures for other Construction Activities					
Sedimentation tanks with sufficient capacity, constructed from pre-formed individual cells of approximately 6 to 8 m ³ capacities, are recommended as a general mitigation measure which can be used for settling surface runoff prior to disposal. The system capacity should be flexible and able to handle multiple inputs from a variety of sources and suited to applications where the influent is pumped	All areas	✓			
Manholes (including newly constructed ones) should always be adequately covered and temporarily sealed so as to prevent silt, construction materials or debris being washed into the storm runoff being directed into foul sewers	All areas	✓			
All vehicles and plant should be cleaned before leaving a construction site to ensure no earth, mud, debris and the like is deposited by them on roads.	All areas				✓
An adequately designed and located wheel washing bay should be provided at every site exit, and wash-water should have sand and silt settled out and removed at least on a weekly basis to ensure the continued efficiency of the process.	All areas				✓
The section of access road leading to, and exiting from, the wheel-wash bay to the public road should be paved with sufficient backfill toward the wheel-wash bay to prevent vehicle tracking of soil and silty water to public roads and drains	All areas				✓
Fuel tanks and storage areas should be provided with locks and be located on sealed areas, within bunds of a capacity equal to 110% of the storage capacity of the largest tank, to prevent spilled fuel oils from reaching the coastal waters of the Victoria Harbour and Western Harbour WCZs	All areas	✓			



Environmental Protection Measures		Location	Implementation Status		
			Implemented	Partially implemented	Not implemented
Water Quality					
Mitigation Measures for other Construction Activities					
<ul style="list-style-type: none"> Portable chemical toilets should be used to handle construction workforce sewage prior to discharge to the existing trunk sewer. Sufficient numbers of portable toilets shall be provided by a licensed contractor to serve the construction workers. The Contractor shall also be responsible for waste disposal and maintenance practices. Construction site runoff should be prevented or minimised in accordance with the guidelines stipulated in the EPD's Practice Note for Professional Persons, Construction Site Drainage (ProPECC PN 1/94). All discharges from the construction site should be controlled to comply with the standards for effluents discharged into the Victoria Harbour WCZ under the TM-DSS. Unnecessary water retained in receptacles and standing water should be avoided to prevent mosquito breeding. 	All areas	√			
Waste Management					
C&D Materials					
<ul style="list-style-type: none"> Excavated materials should be reused on-site as backfilling material and for landscaping works as far as practicable. C&D material generated from excavation works should be disposed of at public fill reception facilities for other beneficial uses. A recording system for the amount of wastes generated, recycled and disposed (including the disposal sites) should be proposed A recording system for the amount of wastes generated, recycled and disposed (including the disposal sites) should be used, e.g. trip ticket system for chemical waste disposal. Quantities could be determined by weighing each load or other suitable methods. 	All areas				√
Chemical Waste					
<ul style="list-style-type: none"> Good quality containers compatible with the chemical wastes should be used, and incompatible chemicals should be stored separately. Appropriate labels should be securely attached on each chemical waste container indicating the corresponding chemical characteristics of the chemical waste, such as explosive, flammable, oxidizing, irritant, toxic, harmful, corrosive, etc. The Contractor shall use a licensed collector to transport and dispose of the chemical wastes, to either the approved Chemical Waste Treatment Centre, or another licensed facility. 	All areas	√			
General Refuse					
<ul style="list-style-type: none"> General refuse should be stored in enclosed bins or compaction units separate from C&D material. A reputable waste collector should be employed by the contractor to remove general refuse from the site, separately from C&D material. An enclosed and covered area should be provided to reduce the occurrence of 'wind blown' light material. 	All areas	√			
Marine Dredged Sediment (During transportation and disposal)					
<ul style="list-style-type: none"> Bottom opening of barges shall be fitted with tight fitting seals to prevent leakage of material. Excess material shall be cleaned from the decks and exposed fittings of barges and dredgers before the vessel is moved Monitoring of the barge loading shall be conducted to ensure that loss of material does not take place during transportation. Transport barges or vessels shall be equipped with automatic self-monitoring devices as specified by the EPD Barges or hopper barges shall not be filled to a level that would cause the overflow of materials or sediment laden water during loading or transportation. 	Marine				√
Good Site Practices					
<ul style="list-style-type: none"> Nomination of an approved person, such as a site manager, to be responsible for good site practices, arrangements for collection and effective disposal to an appropriate facility, of all wastes generated at the site Training of site personnel in proper waste management and chemical handling procedures Provision of sufficient waste disposal points and regular collection of waste 	All areas	√			
	All areas	√			
	All areas	√			



Appendix H

Site General Layout plan

NOTES:
 1. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH DRAWING NOS. 241239/6/0301 TO 0304.

LEGEND:

- PROPOSED FRESH WATER MAIN
- PROPOSED SALT WATER MAIN
- PROPOSED WORKS LANE
- CL / ST
- PORTION A (SECTION 2)
- PORTION C1
- PORTION C (SECTION 4)
- PORTION E1B
- PORTION E1C
- PORTION E1D
- PORTION E2
- PORTION E3
- PORTION E4
- PORTION E5
- PORTION E6
- PORTION E7
- PORTION E8
- PORTION E9
- PORTION E10
- PORTION E11
- PORTION E12
- PORTION E13
- PORTION E14
- PORTION E15
- PORTION E16
- PORTION E17
- PORTION E18
- PORTION E19
- PORTION E20
- PORTION E21
- PORTION E22
- PORTION E23
- PORTION E24
- PORTION E25
- PORTION E26
- PORTION E27
- PORTION E28
- PORTION E29
- PORTION E30
- PORTION E31
- PORTION E32
- PORTION E33
- PORTION E34
- PORTION E35
- PORTION E36
- PORTION E37
- PORTION E38
- PORTION E39
- PORTION E40
- PORTION E41
- PORTION E42
- PORTION E43
- PORTION E44
- PORTION E45
- PORTION E46
- PORTION E47
- PORTION E48
- PORTION E49
- PORTION E50
- PORTION E51
- PORTION E52
- PORTION E53
- PORTION E54
- PORTION E55
- PORTION E56
- PORTION E57
- PORTION E58
- PORTION E59
- PORTION E60
- PORTION E61
- PORTION E62
- PORTION E63
- PORTION E64
- PORTION E65
- PORTION E66
- PORTION E67
- PORTION E68
- PORTION E69
- PORTION E70
- PORTION E71
- PORTION E72
- PORTION E73
- PORTION E74
- PORTION E75
- PORTION E76
- PORTION E77
- PORTION E78
- PORTION E79
- PORTION E80
- PORTION E81
- PORTION E82
- PORTION E83
- PORTION E84
- PORTION E85
- PORTION E86
- PORTION E87
- PORTION E88
- PORTION E89
- PORTION E90
- PORTION E91
- PORTION E92
- PORTION E93
- PORTION E94
- PORTION E95
- PORTION E96
- PORTION E97
- PORTION E98
- PORTION E99
- PORTION E100

Section 1
 Section 2
 Section 4

WORKS AREA A1
 WORKS AREA A2
 WORKS AREA A3
 WORKS AREA A4
 WORKS AREA A5
 WORKS AREA A6
 WORKS AREA A7
 WORKS AREA A8
 WORKS AREA A9
 WORKS AREA A10
 WORKS AREA A11
 WORKS AREA A12
 WORKS AREA A13
 WORKS AREA A14
 WORKS AREA A15
 WORKS AREA A16
 WORKS AREA A17
 WORKS AREA A18
 WORKS AREA A19
 WORKS AREA A20
 WORKS AREA A21
 WORKS AREA A22
 WORKS AREA A23
 WORKS AREA A24
 WORKS AREA A25
 WORKS AREA A26
 WORKS AREA A27
 WORKS AREA A28
 WORKS AREA A29
 WORKS AREA A30
 WORKS AREA A31
 WORKS AREA A32
 WORKS AREA A33
 WORKS AREA A34
 WORKS AREA A35
 WORKS AREA A36
 WORKS AREA A37
 WORKS AREA A38
 WORKS AREA A39
 WORKS AREA A40
 WORKS AREA A41
 WORKS AREA A42
 WORKS AREA A43
 WORKS AREA A44
 WORKS AREA A45
 WORKS AREA A46
 WORKS AREA A47
 WORKS AREA A48
 WORKS AREA A49
 WORKS AREA A50
 WORKS AREA A51
 WORKS AREA A52
 WORKS AREA A53
 WORKS AREA A54
 WORKS AREA A55
 WORKS AREA A56
 WORKS AREA A57
 WORKS AREA A58
 WORKS AREA A59
 WORKS AREA A60
 WORKS AREA A61
 WORKS AREA A62
 WORKS AREA A63
 WORKS AREA A64
 WORKS AREA A65
 WORKS AREA A66
 WORKS AREA A67
 WORKS AREA A68
 WORKS AREA A69
 WORKS AREA A70
 WORKS AREA A71
 WORKS AREA A72
 WORKS AREA A73
 WORKS AREA A74
 WORKS AREA A75
 WORKS AREA A76
 WORKS AREA A77
 WORKS AREA A78
 WORKS AREA A79
 WORKS AREA A80
 WORKS AREA A81
 WORKS AREA A82
 WORKS AREA A83
 WORKS AREA A84
 WORKS AREA A85
 WORKS AREA A86
 WORKS AREA A87
 WORKS AREA A88
 WORKS AREA A89
 WORKS AREA A90
 WORKS AREA A91
 WORKS AREA A92
 WORKS AREA A93
 WORKS AREA A94
 WORKS AREA A95
 WORKS AREA A96
 WORKS AREA A97
 WORKS AREA A98
 WORKS AREA A99
 WORKS AREA A100

NO.	DATE	DESCRIPTION	BY	CHECKED
01	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 1	MM	MM
02	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 2	MM	MM
03	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 3	MM	MM
04	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 4	MM	MM
05	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 5	MM	MM
06	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 6	MM	MM
07	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 7	MM	MM
08	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 8	MM	MM
09	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 9	MM	MM
10	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 10	MM	MM
11	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 11	MM	MM
12	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 12	MM	MM
13	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 13	MM	MM
14	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 14	MM	MM
15	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 15	MM	MM
16	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 16	MM	MM
17	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 17	MM	MM
18	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 18	MM	MM
19	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 19	MM	MM
20	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 20	MM	MM
21	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 21	MM	MM
22	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 22	MM	MM
23	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 23	MM	MM
24	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 24	MM	MM
25	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 25	MM	MM
26	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 26	MM	MM
27	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 27	MM	MM
28	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 28	MM	MM
29	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 29	MM	MM
30	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 30	MM	MM
31	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 31	MM	MM
32	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 32	MM	MM
33	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 33	MM	MM
34	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 34	MM	MM
35	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 35	MM	MM
36	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 36	MM	MM
37	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 37	MM	MM
38	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 38	MM	MM
39	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 39	MM	MM
40	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 40	MM	MM
41	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 41	MM	MM
42	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 42	MM	MM
43	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 43	MM	MM
44	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 44	MM	MM
45	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 45	MM	MM
46	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 46	MM	MM
47	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 47	MM	MM
48	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 48	MM	MM
49	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 49	MM	MM
50	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 50	MM	MM
51	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 51	MM	MM
52	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 52	MM	MM
53	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 53	MM	MM
54	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 54	MM	MM
55	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 55	MM	MM
56	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 56	MM	MM
57	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 57	MM	MM
58	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 58	MM	MM
59	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 59	MM	MM
60	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 60	MM	MM
61	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 61	MM	MM
62	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 62	MM	MM
63	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 63	MM	MM
64	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 64	MM	MM
65	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 65	MM	MM
66	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 66	MM	MM
67	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 67	MM	MM
68	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 68	MM	MM
69	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 69	MM	MM
70	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 70	MM	MM
71	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 71	MM	MM
72	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 72	MM	MM
73	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 73	MM	MM
74	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 74	MM	MM
75	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 75	MM	MM
76	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 76	MM	MM
77	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 77	MM	MM
78	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 78	MM	MM
79	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 79	MM	MM
80	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 80	MM	MM
81	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 81	MM	MM
82	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 82	MM	MM
83	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 83	MM	MM
84	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 84	MM	MM
85	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 85	MM	MM
86	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 86	MM	MM
87	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 87	MM	MM
88	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 88	MM	MM
89	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 89	MM	MM
90	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 90	MM	MM
91	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 91	MM	MM
92	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 92	MM	MM
93	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 93	MM	MM
94	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 94	MM	MM
95	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 95	MM	MM
96	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 96	MM	MM
97	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 97	MM	MM
98	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 98	MM	MM
99	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 99	MM	MM
100	15 MAY 09	ISSUE FOR TENDER APPROVAL NO. 100	MM	MM

Mott MacDonald

THE GOVERNMENT OF THE HONG KONG
 SPECIAL ADMINISTRATIVE REGION
 WATER SUPPLIES DEPARTMENT

9/19SD/08


LAYING OF WESTERN CROSS HARBOUR MAIN
 AND ASSOCIATED LAND MAINS FROM WEST
 KOWLOON TO SHI YING PUN

POSSESSION OF SITE
 (SHEET 1 OF 5)

Scale: 1:1000

Drawing No. 241239/6/0301

Sheet No. 05




MATCH LINE
 TO DRAWING NO. 241239/6/0302

THIS DRAWING IS THE PROPERTY OF MOTT MACDONALD AND SHOULD NOT BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF MOTT MACDONALD.

NOTES :

1. THE WORKING PLAN OF THIS PROJECT IS CONSIDERED WITH DRAWING NO. 24123/6/0304 TO 0306 AND 0308.
2. THE USER SHALL REFER TO DRAWING NO. 24123/6/0301.



DATE OF ISSUE	15/01/08	REVISION NO.	1
DATE OF ISSUE	15/01/08	REVISION NO.	2
DATE OF ISSUE	15/01/08	REVISION NO.	3
DATE OF ISSUE	15/01/08	REVISION NO.	4
DATE OF ISSUE	15/01/08	REVISION NO.	5

Mott MacDonald

THE GOVERNMENT OF THE HONG KONG
SPECIAL ADMINISTRATIVE REGION
WATER SUPPLIES DEPARTMENT



9/WSD/08

LAYING OF WESTERN CROSS HARBOUR MAIN
AND ASSOCIATED LAND MAINS FROM WEST
KOWLOON TO SAI YING PUN

POSSESSION OF SITE
(SHEET 4 OF 5)

SCALE	1:1000	DATE	24/12/07
DRAWN BY	GA1	CHECKED BY	GA1
DESIGNED BY	GA1	APPROVED BY	GA1
PROJECT NO.	24123/6	SHEET NO.	TEN
PROJECT TITLE	LAYING OF WESTERN CROSS HARBOUR MAIN AND ASSOCIATED LAND MAINS FROM WEST KOWLOON TO SAI YING PUN	DATE	02

NOTES

1. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH DRAWING NOS. 241239/03/01 TO 03/04.
2. THE LEGEND SHALL REFER TO DRAWING NO. 241239/03/01.

Q2	FEB 09	2	REVISION	NO. 2	DATE
D1	JAN 08	1	REVISION	NO. 1	DATE
0	DEC 05	1	ISSUE FOR TENDER		

Mott MacDonald
 11th Floor, One Island Plaza
 1101 Eastern Avenue, Suite 1101
 Causeway Bay, Hong Kong
 Tel: 2812 1212
 Fax: 2812 1217
 Email: mottmac@comcast.hk


THE GOVERNMENT OF THE HONG KONG
 SPECIAL ADMINISTRATIVE REGION
 WATER SUPPLIES DEPARTMENT

DATE: 9/19/08

LAYING OF WESTERN CROSS HARBOUR MAIN
 AND ASSOCIATED LAND MAINS FROM WEST
 KOWLOON TO SAN YING PUN

POSSESSION OF SITE
 (SHEET 5 OF 5)

Scale	1:250	Sheet No.	041
Project No.	241239	Drawn By	TEN
Checked By		Reviewed By	
Approved By		Project Manager	
Contract No.	241239/03/0305	Revision	02



© Mott MacDonald Limited
 The information in this drawing is the property of Mott MacDonald Limited. It is to be used only for the project for which it was prepared and for which Mott MacDonald Limited is responsible. It is not to be used for any other project without the prior written consent of Mott MacDonald Limited.



Appendix I

Monitoring Schedule for this Month and Coming Month

Contract No. 9/WSD/08

Laying of Western Cross Harbour Main & Associated Land Mains from West Kowloon to Sai Ying Pun
 Time Schedule for Impact Marine Water Quality Monitoring (WQM), Noise Monitoring (NM) and Weekly Site Inspection (SI)
 April 2011

Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
					01-Apr NM (WK-Daytime) NM (SYP-Daytime)	02-Apr WQM Mid-Ebb 09:30 - 13:30 Mid-Flood 15:00 - 19:00
03-Apr	04-Apr NM (SYP-Daytime)	05-Apr	06-Apr NM (WK-Daytime)	07-Apr	08-Apr	09-Apr
NM Holiday (West Kowloon) (Sai Ying Pun)				WQM Mid-Ebb 13:00 - 17:00 Mid-Flood 18:00 - 22:00		WQM Mid-Flood 07:00 - 11:00 Mid-Ebb 13:00 - 17:00
10-Apr	11-Apr NM (SYP-Daytime)	12-Apr	13-Apr	14-Apr	15-Apr	16-Apr
NM Holiday (West Kowloon) (Sai Ying Pun)		WQM Mid-Flood 10:00 - 14:00 Mid-Ebb 15:30 - 19:30 SI		WQM Mid-Ebb 07:30 - 11:30 Mid-Flood 13:30 - 17:30	SI	WQM Mid-Ebb 08:30 - 12:30 Mid-Flood 14:00 - 18:00
17-Apr	18-Apr NM (SYP-Daytime)	19-Apr	20-Apr NM (WK-Daytime)	21-Apr	22-Apr	23-Apr
NM Holiday (West Kowloon) (Sai Ying Pun)		WQM Mid-Ebb 10:30 - 14:30 Mid-Flood 16:30 - 20:30		WQM Mid-Flood 07:00 - 11:00 Mid-Ebb 12:30 - 16:30		
24-Apr	25-Apr	26-Apr	27-Apr	28-Apr	29-Apr	30-Apr
		WQM Mid-Flood 09:30 - 13:30 Mid-Ebb 15:30 - 19:30	SI	WQM Mid-Ebb 08:00 - 12:00 Mid-Flood 13:30 - 17:30 SI	SI	WQM Mid-Ebb 08:30 - 12:30 Mid-Flood 14:00 - 18:00

Contract No. 9/WSD/08

Laying of Western Cross Harbour Main & Associated Land Mains from West Kowloon to Sai Ying Pun
 Time Schedule for Impact Marine Water Quality Monitoring (WQM), Noise Monitoring (NM) and Weekly Site Inspection (SI)
 May 2011

Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
01-May	02-May	03-May	04-May	05-May	06-May	07-May
		WQM Mid-Ebb 10:00 - 14:00 Mid-Flood 16:00 - 20:00	NM (WK-Daytime) NM (SYP-Daytime)	WQM Mid-Ebb 11:30 - 15:30 Mid-Flood 17:30 - 21:30 SI		WQM Mid-Ebb 12:30 - 16:30 Mid-Flood 18:30 - 22:30
08-May	09-May		11-May	12-May	13-May	14-May
			NM (WK-Daytime) NM (SYP-Daytime)	WQM Mid-Ebb 11:30 - 15:30 Mid-Flood 17:00 - 21:00 SI		WQM Mid-Ebb 08:30 - 12:30 Mid-Flood 14:00 - 18:00
15-May	16-May	17-May	18-May	19-May	20-May	21-May
		WQM Mid-Ebb 10:30 - 14:30 Mid-Flood 16:00 - 20:00 SI	NM (WK-Daytime) NM (SYP-Daytime)	WQM Mid-Flood 12:00 - 16:00 Mid-Ebb 17:30 - 21:30		WQM Mid-Flood 07:00 - 11:00 Mid-Ebb 12:30 - 16:30
22-May	23-May	24-May	25-May	26-May	27-May	28-May
		WQM Mid-Flood 08:30 - 12:30 Mid-Ebb 14:00 - 18:00 SI	NM (WK-Daytime) NM (SYP-Daytime)	WQM Mid-Flood 11:00 - 15:00 Mid-Ebb 16:30 - 20:30		WQM Mid-Ebb 08:30 - 12:30 Mid-Flood 14:00 - 18:00
29-May	30-May	31-May				
		WQM Mid-Ebb 09:00 - 14:00 Mid-Flood 15:30 - 19:30 SI				



Appendix J

Daily Dredging Summary

Wo Hing - Penta-Ocean Joint Venture					
Contract no. 9/WSD/08					
Laying of Western Cross Harbour Main & Associated Land Mains from West Kowloon to Sai Ying Pun					
Summary of Dumping Qty. of Type 1 Marine Sediment (Dispose to East Ninepin Mud Disposal Ground / South Cheung Chau)					
Date	Dumping qty (m ³)	Barge Load per day	Accumulated Dumping Qty.	Permit No.	Mud Disposal Ground
	(bulk volume)		(bulk volume)		
30-Apr-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
01-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
02-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
03-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
04-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
05-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
06-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
07-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
08-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
09-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
10-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
11-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
12-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
13-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
14-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
15-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
16-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
17-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
18-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
19-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
20-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
21-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
22-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
23-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
24-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
25-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
26-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
27-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
28-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
29-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
30-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
31-May-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
01-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
02-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
03-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
04-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
05-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
06-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
07-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
08-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
09-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
10-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
11-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
12-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
13-Jun-2010	0	0	0	EP/MD/10-085	East Ninepin Mud Disposal Ground
14-Jun-2010	1,400	2	1,400	EP/MD/10-085	East Ninepin Mud Disposal Ground
15-Jun-2010	1,400	2	2,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
16-Jun-2010	2,100	3	4,900	EP/MD/10-085	East Ninepin Mud Disposal Ground
17-Jun-2010	2,800	4	7,700	EP/MD/10-085	East Ninepin Mud Disposal Ground
18-Jun-2010	2,100	3	9,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
19-Jun-2010	2,700	4	12,500	EP/MD/10-085	East Ninepin Mud Disposal Ground
20-Jun-2010	2,800	4	15,300	EP/MD/10-085	East Ninepin Mud Disposal Ground
21-Jun-2010	2,100	3	17,400	EP/MD/10-085	East Ninepin Mud Disposal Ground
22-Jun-2010	2,800	4	20,200	EP/MD/10-085	East Ninepin Mud Disposal Ground
23-Jun-2010	2,100	3	22,300	EP/MD/10-085	East Ninepin Mud Disposal Ground
24-Jun-2010	2,100	3	24,400	EP/MD/10-085	East Ninepin Mud Disposal Ground
25-Jun-2010	2,100	3	26,500	EP/MD/10-085	East Ninepin Mud Disposal Ground
26-Jun-2010	2,100	3	28,600	EP/MD/10-085	East Ninepin Mud Disposal Ground
27-Jun-2010	700	1	29,300	EP/MD/10-085	East Ninepin Mud Disposal Ground
28-Jun-2010	2,100	3	31,400	EP/MD/10-085	East Ninepin Mud Disposal Ground
29-Jun-2010	1,200	2	32,600	EP/MD/10-085	East Ninepin Mud Disposal Ground
30-Jun-2010	0	0	32,600	EP/MD/10-085	East Ninepin Mud Disposal Ground
01-Jul-2010	0	0	32,600	EP/MD/10-085	East Ninepin Mud Disposal Ground
02-Jul-2010	0	0	32,600	EP/MD/10-085	East Ninepin Mud Disposal Ground

Wo Hing - Penta-Ocean Joint Venture					
Contract no. 9/WSD/08					
Laying of Western Cross Harbour Main & Associated Land Mains from West Kowloon to Sai Ying Pun					
Summary of Dumping Qty. of Type 1 Marine Sediment (Dispose to East Ninepin Mud Disposal Ground / South Cheung Chau)					
Date	Dumping qty (m ³)	Barge Load per day	Accumulated Dumping Qty.	Permit No.	Mud Disposal Ground
	(bulk volume)		(bulk volume)		
03-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
04-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
05-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
06-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
07-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
08-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
09-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
10-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
11-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
12-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
13-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
14-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
15-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
16-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
17-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
18-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
19-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
20-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
21-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
22-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
23-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
24-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
25-Jul-2010	0	0	32,800	EP/MD/10-085	East Ninepin Mud Disposal Ground
26-Jul-2010	0	0	32,800	EP/MD/11-039	East Ninepin Mud Disposal Ground
27-Jul-2010	0	0	32,800	EP/MD/11-039	East Ninepin Mud Disposal Ground
28-Jul-2010	0	0	32,800	EP/MD/11-039	East Ninepin Mud Disposal Ground
29-Jul-2010	0	0	32,800	EP/MD/11-039	East Ninepin Mud Disposal Ground
30-Jul-2010	700	1	33,500	EP/MD/11-039	East Ninepin Mud Disposal Ground
31-Jul-2010	1,300	2	34,800	EP/MD/11-039	East Ninepin Mud Disposal Ground
01-Aug-2010	2,100	3	37,000	EP/MD/11-039	East Ninepin Mud Disposal Ground
02-Aug-2010	1,400	2	38,400	EP/MD/11-039	East Ninepin Mud Disposal Ground
03-Aug-2010	700	1	39,100	EP/MD/11-039	East Ninepin Mud Disposal Ground
04-Aug-2010	700	1	39,800	EP/MD/11-039	East Ninepin Mud Disposal Ground
05-Aug-2010	700	1	40,500	EP/MD/11-039	East Ninepin Mud Disposal Ground
06-Aug-2010	0	0	40,500	EP/MD/11-039	East Ninepin Mud Disposal Ground
07-Aug-2010	0	0	40,500	EP/MD/11-039	East Ninepin Mud Disposal Ground
08-Aug-2010	0	0	40,500	EP/MD/11-039	East Ninepin Mud Disposal Ground
09-Aug-2010	0	0	40,500	EP/MD/11-039	East Ninepin Mud Disposal Ground
10-Aug-2010	0	0	40,500	EP/MD/11-039	East Ninepin Mud Disposal Ground
11-Aug-2010	1,400	2	41,900	EP/MD/11-039	East Ninepin Mud Disposal Ground
12-Aug-2010	1,400	2	43,300	EP/MD/11-039	East Ninepin Mud Disposal Ground
13-Aug-2010	2,100	3	45,400	EP/MD/11-039	East Ninepin Mud Disposal Ground
14-Aug-2010	2,100	3	47,500	EP/MD/11-039	East Ninepin Mud Disposal Ground
15-Aug-2010	2,100	3	49,600	EP/MD/11-039	East Ninepin Mud Disposal Ground
16-Aug-2010	700	1	50,300	EP/MD/11-039	East Ninepin Mud Disposal Ground
17-Aug-2010	1,400	2	51,700	EP/MD/11-039	East Ninepin Mud Disposal Ground
18-Aug-2010	1,400	2	53,100	EP/MD/11-039	East Ninepin Mud Disposal Ground
19-Aug-2010	1,400	2	54,500	EP/MD/11-039	East Ninepin Mud Disposal Ground
20-Aug-2010	2,100	3	56,600	EP/MD/11-039	East Ninepin Mud Disposal Ground
21-Aug-2010	1,400	2	58,000	EP/MD/11-039	East Ninepin Mud Disposal Ground
22-Aug-2010	700	1	58,700	EP/MD/11-039	East Ninepin Mud Disposal Ground
23-Aug-2010	0	0	58,700	EP/MD/11-039	East Ninepin Mud Disposal Ground
24-Aug-2010	1,400	2	60,100	EP/MD/11-039	East Ninepin Mud Disposal Ground
25-Aug-2010	1,400	2	61,500	EP/MD/11-039	East Ninepin Mud Disposal Ground
26-Aug-2010	2,100	3	63,600	EP/MD/11-039	East Ninepin Mud Disposal Ground
27-Aug-2010	2,100	3	65,700	EP/MD/11-039	East Ninepin Mud Disposal Ground
28-Aug-2010	0	0	65,700	EP/MD/11-039	East Ninepin Mud Disposal Ground
29-Aug-2010	1,400	2	67,100	EP/MD/11-039	East Ninepin Mud Disposal Ground
30-Aug-2010	1,400	2	68,500	EP/MD/11-039	East Ninepin Mud Disposal Ground
31-Aug-2010	2,100	3	70,600	EP/MD/11-039	East Ninepin Mud Disposal Ground
01-Sep-2010	1,400	2	72,000	EP/MD/11-039	East Ninepin Mud Disposal Ground
02-Sep-2010	2,100	3	74,100	EP/MD/11-039	East Ninepin Mud Disposal Ground
03-Sep-2010	2,100	3	76,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
04-Sep-2010	2,800	4	79,000	EP/MD/11-039	East Ninepin Mud Disposal Ground

Wo Hing - Penta-Ocean Joint Venture					
Contract no. 9/WSD/08					
Laying of Western Cross Harbour Main & Associated Land Mains from					
West Kowloon to Sai Ying Pun					
Summary of Dumping Qty. of Type 1 Marine Sediment (Dispose to East Ninepin Mud Disposal Ground / South Cheung Chau)					
Date	Dumping qty (m ³)	Barge Load per day	Accumulated Dumping Qty.	Permit No.	Mud Disposal Ground
	(bulk volume)		(bulk volume)		
05-Sep-2010	2,100	3	79,700	EP/MD/11-039	East Ninepin Mud Disposal Ground
06-Sep-2010	1,400	2	81,100	EP/MD/11-039	East Ninepin Mud Disposal Ground
07-Sep-2010	0	0	81,100	EP/MD/11-039	East Ninepin Mud Disposal Ground
08-Sep-2010	700	1	81,800	EP/MD/11-039	East Ninepin Mud Disposal Ground
09-Sep-2010	1,400	2	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
10-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
11-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
12-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
13-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
14-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
15-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
16-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
17-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
18-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
19-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
20-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
21-Sep-2010	0	0	83,200	EP/MD/11-039	East Ninepin Mud Disposal Ground
22-Sep-2010	700	1	83,900	EP/MD/11-039	East Ninepin Mud Disposal Ground
23-Sep-2010	0	0	83,900	EP/MD/11-039	East Ninepin Mud Disposal Ground
24-Sep-2010	0	0	83,900	EP/MD/11-039	East Ninepin Mud Disposal Ground
25-Sep-2010	0	0	83,900	EP/MD/11-039	East Ninepin Mud Disposal Ground
26-Sep-2010	0	0	83,900	EP/MD/11-039	East Ninepin Mud Disposal Ground
27-Sep-2010	0	0	83,900	EP/MD/11-039	East Ninepin Mud Disposal Ground
28-Sep-2010	0	0	83,900	EP/MD/11-039	East Ninepin Mud Disposal Ground
29-Sep-2010	0	0	83,900	EP/MD/11-039	East Ninepin Mud Disposal Ground
30-Sep-2010	0	0	83,900	EP/MD/11-039	East Ninepin Mud Disposal Ground
01-Oct-2010	500	1	84,400	EP/MD/11-069	South Cheung Chau
02-Oct-2010	500	1	84,900	EP/MD/11-069	South Cheung Chau
03-Oct-2010	1,000	2	85,900	EP/MD/11-069	South Cheung Chau
04-Oct-2010	1,000	2	86,900	EP/MD/11-069	South Cheung Chau
05-Oct-2010	500	1	87,400	EP/MD/11-069	South Cheung Chau
06-Oct-2010	1,000	2	88,400	EP/MD/11-069	South Cheung Chau
07-Oct-2010	1,500	3	89,900	EP/MD/11-069	South Cheung Chau
08-Oct-2010	1,000	2	90,900	EP/MD/11-069	South Cheung Chau
09-Oct-2010	500	1	91,400	EP/MD/11-069	South Cheung Chau
10-Oct-2010	0	0	91,400	EP/MD/11-069	South Cheung Chau
11-Oct-2010	1,500	3	92,900	EP/MD/11-069	South Cheung Chau
12-Oct-2010	1,000	2	93,900	EP/MD/11-069	South Cheung Chau
13-Oct-2010	2,000	4	95,900	EP/MD/11-069	South Cheung Chau
14-Oct-2010	2,000	4	97,900	EP/MD/11-069	South Cheung Chau
15-Oct-2010	1,500	3	99,400	EP/MD/11-069	South Cheung Chau
16-Oct-2010	2,000	4	101,400	EP/MD/11-069	South Cheung Chau
17-Oct-2010	2,000	4	103,400	EP/MD/11-069	South Cheung Chau
18-Oct-2010	2,000	4	105,400	EP/MD/11-069	South Cheung Chau
19-Oct-2010	1,500	3	106,900	EP/MD/11-069	South Cheung Chau
20-Oct-2010	1,000	2	107,900	EP/MD/11-069	South Cheung Chau
21-Oct-2010	0	0	107,900	EP/MD/11-069	South Cheung Chau
22-Oct-2010	0	0	107,900	EP/MD/11-069	South Cheung Chau
23-Oct-2010	500	1	108,400	EP/MD/11-069	South Cheung Chau
24-Oct-2010	2,000	4	110,400	EP/MD/11-069	South Cheung Chau
25-Oct-2010	1,500	3	111,900	EP/MD/11-069	South Cheung Chau
26-Oct-2010	1,000	2	112,900	EP/MD/11-069	South Cheung Chau
27-Oct-2010	1,000	2	113,900	EP/MD/11-069	South Cheung Chau
28-Oct-2010	0	0	113,900	EP/MD/11-069	South Cheung Chau
29-Oct-2010	1,000	2	114,900	EP/MD/11-069	South Cheung Chau
30-Oct-2010	500	1	115,400	EP/MD/11-069	South Cheung Chau
31-Oct-2010	1,000	2	116,400	EP/MD/11-069	South Cheung Chau
01-Nov-2010	1,000	2	117,400	EP/MD/11-069	South Cheung Chau
02-Nov-2010	500	1	117,900	EP/MD/11-069	South Cheung Chau
03-Nov-2010	1,000	2	118,900	EP/MD/11-069	South Cheung Chau
04-Nov-2010	1,000	2	119,900	EP/MD/11-069	South Cheung Chau
05-Nov-2010	500	1	120,400	EP/MD/11-069	South Cheung Chau
06-Nov-2010	500	1	120,900	EP/MD/11-069	South Cheung Chau

Wo Hing - Penta-Ocean Joint Venture					
Contract no. 9/WSD/08					
Laying of Western Cross Harbour Main & Associated Land Mains from					
West Kowloon to Sai Ying Pun					
Summary of Dumping Qty. of Type 1 Marine Sediment (Dispose to East Ninepin Mud Disposal Ground / South Cheung Chau)					
Date	Dumping qty (m ³)	Barge Load per day	Accumulated Dumping Qty.	Permit No.	Mud Disposal Ground
	(bulk volume)		(bulk volume)		
07-Nov-2010	500	1	121,400	EP/MD/11-069	South Cheung Chau
08-Nov-2010	0	0	121,400	EP/MD/11-069	South Cheung Chau
09-Nov-2010	500	1	121,900	EP/MD/11-069	South Cheung Chau
10-Nov-2010	300	1	122,200	EP/MD/11-069	South Cheung Chau
11-Nov-2010	0	0	122,200	EP/MD/11-069	South Cheung Chau
12-Nov-2010	0	0	122,200	EP/MD/11-069	South Cheung Chau
13-Nov-2010	0	0	122,200	EP/MD/11-069	South Cheung Chau
14-Nov-2010	0	0	122,200	EP/MD/11-069	South Cheung Chau
15-Nov-2010	0	0	122,200	EP/MD/11-069	South Cheung Chau
16-Nov-2010	0	0	122,200	EP/MD/11-069	South Cheung Chau
17-Nov-2010	0	0	122,200	EP/MD/11-069	South Cheung Chau
18-Nov-2010	1,500	3	123,700	EP/MD/11-069	South Cheung Chau
19-Nov-2010	1,000	2	124,700	EP/MD/11-069	South Cheung Chau
20-Nov-2010	1,500	3	126,200	EP/MD/11-069	South Cheung Chau
21-Nov-2010	1,000	2	127,200	EP/MD/11-069	South Cheung Chau
22-Nov-2010	1,500	3	128,700	EP/MD/11-069	South Cheung Chau
23-Nov-2010	1,000	2	129,700	EP/MD/11-069	South Cheung Chau
24-Nov-2010	2,000	4	131,700	EP/MD/11-069	South Cheung Chau
25-Nov-2010	1,000	2	132,700	EP/MD/11-069	South Cheung Chau
26-Nov-2010	1,800	4	134,500	EP/MD/11-069	South Cheung Chau
27-Nov-2010	1,000	2	135,500	EP/MD/11-069	South Cheung Chau
28-Nov-2010	1,500	3	137,000	EP/MD/11-069	South Cheung Chau
29-Nov-2010	2,000	4	139,000	EP/MD/11-069	South Cheung Chau
30-Nov-2010	1,500	3	140,500	EP/MD/11-069	South Cheung Chau
01-Dec-2010	1,000	2	141,500	EP/MD/11-069	South Cheung Chau
02-Dec-2010	1,500	3	143,000	EP/MD/11-069	South Cheung Chau
03-Dec-2010	1,000	2	144,000	EP/MD/11-069	South Cheung Chau
04-Dec-2010	1,500	3	145,500	EP/MD/11-069	South Cheung Chau
05-Dec-2010	1,000	2	146,500	EP/MD/11-069	South Cheung Chau
06-Dec-2010	500	1	147,000	EP/MD/11-069	South Cheung Chau
07-Dec-2010	1,500	3	148,500	EP/MD/11-069	South Cheung Chau
08-Dec-2010	1,000	2	149,500	EP/MD/11-069	South Cheung Chau
09-Dec-2010	1,000	2	150,500	EP/MD/11-069	South Cheung Chau
10-Dec-2010	1,500	3	152,000	EP/MD/11-069	South Cheung Chau
11-Dec-2010	500	1	152,500	EP/MD/11-069	South Cheung Chau
12-Dec-2010	1,000	2	153,500	EP/MD/11-069	South Cheung Chau
13-Dec-2010	0	0	153,500	EP/MD/11-069	South Cheung Chau
14-Dec-2010	0	0	153,500	EP/MD/11-069	South Cheung Chau
15-Dec-2010	0	0	153,500	EP/MD/11-069	South Cheung Chau
16-Dec-2010	0	0	153,500	EP/MD/11-069	South Cheung Chau
17-Dec-2010	0	0	153,500	EP/MD/11-069	South Cheung Chau
18-Dec-2010	0	0	153,500	EP/MD/11-069	South Cheung Chau
19-Dec-2010	0	0	153,500	EP/MD/11-069	South Cheung Chau
20-Dec-2010	0	0	153,500	EP/MD/11-069	South Cheung Chau
21-Dec-2010	0	0	153,500	EP/MD/11-069	South Cheung Chau
22-Dec-2010	500	1	154,000	EP/MD/11-069	South Cheung Chau
23-Dec-2010	0	0	154,000	EP/MD/11-069	South Cheung Chau
24-Dec-2010	0	0	154,000	EP/MD/11-069	South Cheung Chau
25-Dec-2010	500	1	154,500	EP/MD/11-069	South Cheung Chau
26-Dec-2010	0	0	154,500	EP/MD/11-069	South Cheung Chau
27-Dec-2010	500	1	155,000	EP/MD/11-069	South Cheung Chau
28-Dec-2010	500	1	155,500	EP/MD/11-069	South Cheung Chau
29-Dec-2010	500	1	156,000	EP/MD/11-069	South Cheung Chau
30-Dec-2010	500	1	156,500	EP/MD/11-069	South Cheung Chau
31-Dec-2010	500	1	157,000	EP/MD/11-069	South Cheung Chau
01-Jan-2011	500	1	157,500	EP/MD/11-069	South Cheung Chau
02-Jan-2011	500	1	158,000	EP/MD/11-069	South Cheung Chau
03-Jan-2011	1,000	2	159,000	EP/MD/11-069	South Cheung Chau
04-Jan-2011	0	0	159,000	EP/MD/11-069	South Cheung Chau
05-Jan-2011	500	1	159,500	EP/MD/11-069	South Cheung Chau
06-Jan-2011	500	1	160,000	EP/MD/11-069	South Cheung Chau
07-Jan-2011	0	0	160,000	EP/MD/11-069	South Cheung Chau
08-Jan-2011	500	1	160,500	EP/MD/11-069	South Cheung Chau

Wo Hing - Penta-Ocean Joint Venture					
Contract no. 9/WSD/08					
Laying of Western Cross Harbour Main & Associated Land Mains from West Kowloon to Sai Ying Pun					
Summary of Dumping Qty. of Type 1 Marine Sediment (Dispose to East Ninepin Mud Disposal Ground / South Cheung Chau)					
Date	Dumping qty (m ³)	Barge Load per day	Accumulated Dumping Qty.	Permit No.	Mud Disposal Ground
	(bulk volume)		(bulk volume)		
09-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
10-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
11-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
12-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
13-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
14-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
15-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
16-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
16-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
17-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
18-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
19-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
20-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
21-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
22-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
23-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
24-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
25-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
26-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
27-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
28-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
29-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
30-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
31-Jan-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
01-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
02-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
03-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
04-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
05-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
06-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
07-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
08-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
09-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
10-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
11-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
12-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
13-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
14-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
15-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
16-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
17-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
18-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
19-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
20-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
21-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
22-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
23-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
24-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
25-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
26-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
27-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
28-Feb-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
01-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
02-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
03-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
04-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
05-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
06-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
07-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
08-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
09-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
10-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
11-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
12-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau

Wo Hing - Penta-Ocean Joint Venture					
Contract no. 9/WSD/08					
Laying of Western Cross Harbour Main & Associated Land Mains from West Kowloon to Sai Ying Pun					
Summary of Dumping Qty. of Type 1 Marine Sediment (Dispose to East Ninepin Mud Disposal Ground / South Cheung Chau)					
Date	Dumping qty (m ³)	Barge Load per day	Accumulated Dumping Qty.	Permit No.	Mud Disposal Ground
	(bulk volume)		(bulk volume)		
13-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
14-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
15-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
16-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
17-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
18-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
19-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
20-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
21-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
22-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
23-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
24-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
25-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
26-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
27-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
28-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
29-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
30-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
31-Mar-2011	0	0	160,500	EP/MD/11-069	South Cheung Chau
01-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
02-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
03-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
04-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
05-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
06-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
07-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
08-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
09-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
10-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
11-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
12-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
13-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
14-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
15-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
16-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
17-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
18-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
19-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
20-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
21-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
22-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
23-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
24-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
25-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
26-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
27-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
28-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
29-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
30-Apr-2011	0	0	160,500	EP/MD/11-160	East Ninepin Mud Disposal Ground
TOTAL =	160,500	274			

Wo Hing - Penta-Ocean Joint Venture				
Contract no. 9/WSD/08				
Laying of Western Cross Harbour Main & Associated Land Mains from West Kowloon to Sai Ying Pun				
Summary of Dumping Qty. of Type 2 Marine Sediment				
Date	Dumping qty (m ³)	Barge Load per day	Accumulated Dumping Qty.	Permit No.
	(bulk volume)		(bulk volume)	
05-May-2010	440	1	440	EP/MD/10-086
06-May-2010	1,280	3	1,720	EP/MD/10-086
07-May-2010	0	0	1,720	EP/MD/10-086
08-May-2010	0	0	1,720	EP/MD/10-086
09-May-2010	1,400	2	3,120	EP/MD/10-086
10-May-2010	1,400	2	4,520	EP/MD/10-086
11-May-2010	1,300	2	5,820	EP/MD/10-086
12-May-2010	1,800	3	7,620	EP/MD/10-086
13-May-2010	1,200	2	8,820	EP/MD/10-086
14-May-2010	0	0	8,820	EP/MD/10-086
15-May-2010	0	0	8,820	EP/MD/10-086
16-May-2010	600	1	9,420	EP/MD/10-086
17-May-2010	1,200	2	10,620	EP/MD/10-086
18-May-2010	700	1	11,320	EP/MD/10-086
19-May-2010	2,000	3	13,320	EP/MD/10-086
20-May-2010	1,400	2	14,720	EP/MD/10-086
21-May-2010	1,400	2	16,120	EP/MD/10-086
22-May-2010	2,100	3	18,220	EP/MD/10-086
23-May-2010	1,400	2	19,620	EP/MD/10-086
24-May-2010	1,400	2	21,020	EP/MD/10-086
25-May-2010	1,300	2	22,320	EP/MD/10-086
26-May-2010	1,400	2	23,720	EP/MD/10-086
27-May-2010	1,300	2	25,020	EP/MD/10-086
28-May-2010	1,400	2	26,420	EP/MD/10-086
29-May-2010	600	1	27,020	EP/MD/10-086
30-May-2010	2,100	3	29,120	EP/MD/11-012
31-May-2010	700	1	29,820	EP/MD/11-012
01-Jun-2010	1,900	3	31,720	EP/MD/11-012
02-Jun-2010	1,220	2	32,940	EP/MD/11-012
03-Jun-2010	1,300	2	34,240	EP/MD/11-012
04-Jun-2010	1,200	2	35,440	EP/MD/11-012
05-Jun-2010	1,400	2	36,840	EP/MD/11-012
06-Jun-2010	600	1	37,440	EP/MD/11-012
07-Jun-2010	0	0	37,440	EP/MD/11-012
08-Jun-2010	500	1	37,940	EP/MD/11-012
09-Jun-2010	0	0	37,940	EP/MD/11-012
10-Jun-2010	600	1	38,540	EP/MD/11-012
11-Jun-2010	1,200	2	39,740	EP/MD/11-012
12-Jun-2010	1,400	2	41,140	EP/MD/11-012
13-Jun-2010	1,400	2	42,540	EP/MD/11-012
14-Jun-2010	0	0	42,540	EP/MD/11-012
15-Jun-2010	0	0	42,540	EP/MD/11-012
16-Jun-2010	0	0	42,540	EP/MD/11-012
17-Jun-2010	0	0	42,540	EP/MD/11-012
18-Jun-2010	0	0	42,540	EP/MD/11-012
19-Jun-2010	0	0	42,540	EP/MD/11-012

Wo Hing - Penta-Ocean Joint Venture				
Contract no. 9/WSD/08				
Laying of Western Cross Harbour Main & Associated Land Mains from West Kowloon to Sai Ying Pun				
Summary of Dumping Qty. of Type 2 Marine Sediment				
Date	Dumping qty (m ³)	Barge Load per day	Accumulated Dumping Qty.	Permit No.
	(bulk volume)		(bulk volume)	
20-Jun-2010	0	0	42,540	EP/MD/11-012
21-Jun-2010	0	0	42,540	EP/MD/11-012
22-Jun-2010	0	0	42,540	EP/MD/11-012
23-Jun-2010	0	0	42,540	EP/MD/11-012
24-Jun-2010	0	0	42,540	EP/MD/11-012
25-Jun-2010	0	0	42,540	EP/MD/11-012
26-Jun-2010	0	0	42,540	EP/MD/11-012
27-Jun-2010	0	0	42,540	EP/MD/11-012
28-Jun-2010	0	0	42,540	EP/MD/11-012
29-Jun-2010	0	0	42,540	EP/MD/11-012
30-Jun-2010	1,200	2	43,740	EP/MD/11-024
01-Jul-2010	2,600	4	46,340	EP/MD/11-024
02-Jul-2010	2,800	4	49,140	EP/MD/11-024
03-Jul-2010	1,400	2	50,540	EP/MD/11-024
04-Jul-2010	2,100	3	52,640	EP/MD/11-024
05-Jul-2010	2,850	4	55,490	EP/MD/11-024
06-Jul-2010	1,400	2	56,890	EP/MD/11-024
07-Jul-2010	1,400	2	58,290	EP/MD/11-024
08-Jul-2010	2,700	4	60,990	EP/MD/11-024
09-Jul-2010	2,100	3	63,090	EP/MD/11-024
10-Jul-2010	2,100	3	65,190	EP/MD/11-024
11-Jul-2010	1,400	2	66,590	EP/MD/11-024
12-Jul-2010	2,150	3	68,740	EP/MD/11-024
13-Jul-2010	2,100	3	70,840	EP/MD/11-024
14-Jul-2010	700	1	71,540	EP/MD/11-024
15-Jul-2010	2,100	3	73,640	EP/MD/11-024
16-Jul-2010	2,100	3	75,740	EP/MD/11-024
17-Jul-2010	700	1	76,440	EP/MD/11-024
18-Jul-2010	700	1	77,140	EP/MD/11-024
19-Jul-2010	2,100	3	79,240	EP/MD/11-024
20-Jul-2010	2,100	3	81,340	EP/MD/11-024
21-Jul-2010	700	1	82,040	EP/MD/11-024
22-Jul-2010	600	1	82,640	EP/MD/11-024
23-Jul-2010	1,400	2	84,040	EP/MD/11-024
24-Jul-2010	1,400	2	85,440	EP/MD/11-024
25-Jul-2010	1,400	2	86,840	EP/MD/11-024
26-Jul-2010	1,450	2	88,290	EP/MD/11-024
27-Jul-2010	2,200	3	90,490	EP/MD/11-024
28-Jul-2010	1,450	2	91,940	EP/MD/11-024
29-Jul-2010	1,500	2	93,440	EP/MD/11-024
30-Jul-2010	0	0	93,440	--
31-Jul-2010	0	0	93,440	--
01-Aug-2010	0	0	93,440	--
02-Aug-2010	0	0	93,440	--

Wo Hing - Penta-Ocean Joint Venture				
Contract no. 9/WSD/08				
Laying of Western Cross Harbour Main & Associated Land Mains from West Kowloon to Sai Ying Pun				
Summary of Dumping Qty. of Type 2 Marine Sediment				
Date	Dumping qty (m ³)	Barge Load per day	Accumulated Dumping Qty.	Permit No.
	(bulk volume)		(bulk volume)	
03-Aug-2010	0	0	93,440	
04-Aug-2010	0	0	93,440	
05-Aug-2010	700	1	94,140	
(dump on 06-Aug-10)				
06-Aug-2010	1,500	2	95,640	EP/MD/11-053
07-Aug-2010	700	1	96,340	EP/MD/11-053
08-Aug-2010	2,100	3	98,440	EP/MD/11-053
09-Aug-2010	1,500	2	99,940	EP/MD/11-053
10-Aug-2010	1,500	2	101,440	EP/MD/11-053
11-Aug-2010	700	1	102,140	EP/MD/11-053
12-Aug-2010	0	0	102,140	EP/MD/11-053
13-Aug-2010	0	0	102,140	EP/MD/11-053
14-Aug-2010	0	0	102,140	EP/MD/11-053
15-Aug-2010	0	0	102,140	EP/MD/11-053
16-Aug-2010	0	0	102,140	EP/MD/11-053
17-Aug-2010	0	0	102,140	EP/MD/11-053
18-Aug-2010	0	0	102,140	EP/MD/11-053
19-Aug-2010	0	0	102,140	EP/MD/11-053
20-Aug-2010	0	0	102,140	EP/MD/11-053
21-Aug-2010	0	0	102,140	EP/MD/11-053
22-Aug-2010	0	0	102,140	EP/MD/11-053
23-Aug-2010	0	0	102,140	EP/MD/11-053
24-Aug-2010	0	0	102,140	EP/MD/11-053
25-Aug-2010	0	0	102,140	EP/MD/11-053
26-Aug-2010	0	0	102,140	EP/MD/11-053
27-Aug-2010	0	0	102,140	EP/MD/11-053
28-Aug-2010	1,400	2	103,540	EP/MD/11-053
29-Aug-2010	700	1	104,240	EP/MD/11-053
30-Aug-2010	0	0	104,240	EP/MD/11-053
31-Aug-2010	750	1	104,990	EP/MD/11-053
01-Sep-2010	0	0	104,990	EP/MD/11-053
02-Sep-2010	0	0	104,990	EP/MD/11-053
03-Sep-2010	0	0	104,990	EP/MD/11-053
04-Sep-2010	0	0	104,990	EP/MD/11-053
05-Sep-2010	0	0	104,990	EP/MD/11-053
TOTAL =	104,990	155		



Appendix K

Details of Interim Notifications of Exceedance (NOEs) in this reporting month



Nil



Appendix L

Contractor's Follow up Actions to ET Weekly Site Inspections

Photo of Follow-up Action

 <p>Photo ref. 1</p>	 <p>Photo ref. 2</p>		

Follow-up Action of the Weekly Site Inspection by the Contractor

Inspection Date : 12 April 2011

Item	Details of defective works or observations	Follow up Action(s) taken	Date of Action taken	Photo Ref.
1	Silt screen at the sea water intake at Kowloon Salt Water Pumping Station was found damaged.	Silt screen at the sea water intake at Kowloon Salt Water Pumping Station was repaired.	19 Apr 2011	1


Photo of Follow-up Action



Photo ref. 1



Figures



LOCATION	Type	Assignment
Wai Yee Tin Trench	Stormwater	81
Wai Yee Tin Trench	Stormwater	82
Wai Yee Tin Trench	Stormwater	83
Wai Yee Tin Trench	Stormwater	84
Wai Yee Tin Trench	Stormwater	85
Wai Yee Tin Trench	Stormwater	86
Wai Yee Tin Trench	Stormwater	87
Wai Yee Tin Trench	Stormwater	88
Wai Yee Tin Trench	Stormwater	89
Wai Yee Tin Trench	Stormwater	90
Wai Yee Tin Trench	Stormwater	91
Wai Yee Tin Trench	Stormwater	92
Wai Yee Tin Trench	Stormwater	93
Wai Yee Tin Trench	Stormwater	94
Wai Yee Tin Trench	Stormwater	95
Wai Yee Tin Trench	Stormwater	96
Wai Yee Tin Trench	Stormwater	97
Wai Yee Tin Trench	Stormwater	98
Wai Yee Tin Trench	Stormwater	99
Wai Yee Tin Trench	Stormwater	100
Wai Yee Tin Trench	Stormwater	101
Wai Yee Tin Trench	Stormwater	102
Wai Yee Tin Trench	Stormwater	103
Wai Yee Tin Trench	Stormwater	104
Wai Yee Tin Trench	Stormwater	105
Wai Yee Tin Trench	Stormwater	106
Wai Yee Tin Trench	Stormwater	107
Wai Yee Tin Trench	Stormwater	108
Wai Yee Tin Trench	Stormwater	109
Wai Yee Tin Trench	Stormwater	110
Wai Yee Tin Trench	Stormwater	111
Wai Yee Tin Trench	Stormwater	112
Wai Yee Tin Trench	Stormwater	113
Wai Yee Tin Trench	Stormwater	114
Wai Yee Tin Trench	Stormwater	115
Wai Yee Tin Trench	Stormwater	116
Wai Yee Tin Trench	Stormwater	117
Wai Yee Tin Trench	Stormwater	118
Wai Yee Tin Trench	Stormwater	119
Wai Yee Tin Trench	Stormwater	120

NO. 10/08	DATE	PRELIMINARY	SCALE	DATE

Mott
 MacDonald
 11th Floor, 111 Des Voeux Road East
 Causeway Bay, Hong Kong
 Tel: 852 2511 2222
 Fax: 852 2511 2227
 E-mail: info@mottmac.com

THE GOVERNMENT OF THE HONG KONG
 SPECIAL ADMINISTRATIVE REGION
 WATER SUPPLIES DEPARTMENT

PROJECT NO. CE42/2005(165)


LAYING OF WESTERN CROSS HARBOUR MAIN
 AND ASSOCIATED LAND MAINS FROM WEST
 KOWLOON TO SAI TING PUN - INVESTIGATION

LOCATIONS OF WATER SENSITIVE RECEIVERS
 AND STORMWATER OUTFALLS
 AT WESTERN HARBOUR

Scale: 1 : 2500000
 Date: 2013

FIGURE 1.2a

This document and its contents are the property of the Water Supplies Department. It is not to be used for any other purpose without the written consent of the Water Supplies Department.



LEGEND:

- PROPOSED ROUTE OF 1200MM FRESH WATER MAIN
- NOISE SENSITIVE RECEIVERS
- 300M NOISE ASSESSMENT BOUNDARY
- - - WORKS AREA BOUNDARY

mMott
 Mott MacDonald
 11th Floor, 111 Des Voeux Road East
 Hong Kong
 Tel: +852 2511 8888
 Fax: +852 2511 8889
 Web: www.mottmac.com

THE GOVERNMENT OF THE HONG KONG
 SPECIAL ADMINISTRATIVE REGION
 WATER SUPPLIES DEPARTMENT

Project: DE42/2005 (NS)


LAYING OF WESTERN CROSS HARBOUR MAIN
 AND ASSOCIATED LAND MAINS FROM WEST
 KOHLOON TO SAI YING PUN - INVESTIGATION

LOCATIONS OF NOISE SENSITIVE
 RECEIVERS IN SAI YING PUN

Project No.	DE42/2005 (NS)
Scale	1 : 200000
Date	2005
Author	
Checker	
Approver	
Project Manager	

FIGURE 1.2b

COPYRIGHT RESERVED



LEGEND:

- PROPOSED ROUTE OF 1200V FIRST WATER MAIN
- NOISE SENSITIVE RECEIVERS
- TEMPORARY PLATFORM
- NOISE ASSESSMENT BOUNDARY
- WORKS AREA BOUNDARY

Mott
 Mott MacDonald
 11/F, 110 Des Voeux Road East
 Hong Kong
 Tel: 852 2511 7777
 Fax: 852 2511 7778
 Web: www.mottmac.com

THE GOVERNMENT OF THE HONG KONG
 SPECIAL ADMINISTRATIVE REGION
 WATER SUPPLIES DEPARTMENT

DE42/2002(NS)


LAYING OF WESTERN CROSS HARBOUR MAIN
 AND ASSOCIATED LAND MARKS FROM WEST
 KOWLOON TO SUI YING PUI - INVESTIGATION

LOCATION OF NOISE SENSITIVE
 RECEIVERS IN WEST KOWLOON

Project No.	DE42/2002(NS)
Scale	1 : 40000A1
Date	
Author	
Checked	
Approved	
Drawn	
Sheet No.	A

© COPYRIGHT RESERVED

This document should not be relied upon for any purpose other than that for which it was prepared and for which Mott MacDonald Ltd
 and its subsidiaries, Mott MacDonald (UK) Limited, Mott MacDonald (USA) Inc. and Mott MacDonald (Canada) Inc. are not liable.




Contract No. 9/WSD/08 Laying of Western Cross Harbour Main and Associated Land Mains for West Kowloon to Sai Ying Pun

Figure 1

Location of Noise Monitoring Station at West Kowloon



東業儀器測試顧問有限公司
ETS-TESTCONSULT LIMITED




Contract No. 9/WSD/08 Laying of Western Cross Harbour Main and Associated Land Mains for West Kowloon to Sai Ying Pun



Figure 2
Locations of Noise Monitoring Stations at Sai Ying Pun

英美儀器測試顧問有限公司
ETS-TESTCONSULT LIMITED



Contract No. 9/WSD/08 Laying of Western Cross Harbour Main and Associated Land Mains for West Kowloon to Sai Ying Pun

Figure 3

Locations of Water Quality Monitoring Stations



東業保測海試顧問有限公司
ETS-TESTCONSULT LIMITED