



LEGEND:

- TREE TO BE PLANTED
- TRANSPLANT TREE
- RETAIN TREE
- RECYCLED PLASTIC RUBBISH BIN
- BENCH
- CONCRETE PAVING REINSTATED / PROVIDED
- EXISTING VEGETATED AREA REINSTATED
- EXISTING TURF AREA REINSTATED
- SLOPE SURFACE HYDROSEEDED WITH EROSION CONTROL MAT OF POLYAMIDE TYPE WITH MINIMUM 20mm THICKNESS

NOTE:
1. THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH DRAWING Nos. 51505/AB/0632 AND 0640 TO 0645.

1. EXISTING TREE SCHEDULE:

TREE No.	SPECIES	TYPE	SIZE	SPACING
T01	ACACIA CONFUSA	RETAIN	10m TALL x 8m CROWN SPREAD (1.25m GIRTH)	N/A
T02	ACACIA CONFUSA	RETAIN	9m TALL x 8m CROWN SPREAD (1.25m GIRTH)	N/A
T03	MACARANGA TANARIUS	TRANSPLANT WITHIN THE SITE	4m TALL x 4m CROWN SPREAD (0.4m GIRTH)	N/A
T90	CRATOXYLUM LIGUSTRINUM	TRANSPLANT WITHIN THE SITE	6m TALL x 3m CROWN SPREAD (0.7m GIRTH)	N/A
T91	BAUHINIA BLAKEANA	RETAIN	5m TALL x 4m CROWN SPREAD (0.4m GIRTH)	N/A
T92	BAUHINIA BLAKEANA	RETAIN	5m TALL x 3m CROWN SPREAD (0.4m GIRTH)	N/A
T93	BAUHINIA BLAKEANA	RETAIN	4m TALL x 3m CROWN SPREAD (0.4m GIRTH)	N/A
T94	BAUHINIA BLAKEANA	RETAIN	5m TALL x 5m CROWN SPREAD (0.45m GIRTH)	N/A
T95	MELALEUCA QUINQUENERVIA	TRANSPLANT WITHIN THE SITE	9m TALL x 4m CROWN SPREAD (0.92m GIRTH)	N/A
T96	CRATOXYLUM LIGUSTRINUM	TRANSPLANT WITHIN THE SITE	6m TALL x 3m CROWN SPREAD (0.49m GIRTH)	N/A
T97	CRATOXYLUM LIGUSTRINUM	TRANSPLANT WITHIN THE SITE	8m TALL x 4m CROWN SPREAD (0.59m GIRTH)	N/A
T98	CELTIS SINENSIS	RETAIN	5m TALL x 3m CROWN SPREAD (0.35m GIRTH)	N/A
T99	CELTIS SINENSIS	RETAIN	7m TALL x 4m CROWN SPREAD (0.45m GIRTH)	N/A
T100	CELTIS SINENSIS	RETAIN	8m TALL x 6m CROWN SPREAD (1.8m GIRTH)	N/A
T101	CELTIS SINENSIS	RETAIN	4m TALL x 4m CROWN SPREAD (0.4m GIRTH)	N/A
T102	CELTIS SINENSIS	TRANSPLANT WITHIN THE SITE	4m TALL x 3m CROWN SPREAD (0.3m GIRTH)	N/A
T103	BRIDEDIA TOMENTOSA	RETAIN	3m TALL x 2m CROWN SPREAD (0.35m GIRTH)	N/A
T104	CELTIS SINENSIS	TRANSPLANT WITHIN THE SITE	3m TALL x 2m CROWN SPREAD (0.3m GIRTH)	N/A
T111	CELTIS SINENSIS	RETAIN	4m TALL x 3m CROWN SPREAD (0.35m GIRTH)	N/A
T200	CARYOTA OCHLANDRA	TRANSPLANT OUTSIDE THE SITE	4m TALL x 3m CROWN SPREAD (0.36m GIRTH)	N/A
T201	CARYOTA OCHLANDRA	TRANSPLANT OUTSIDE THE SITE	6m TALL x 4m CROWN SPREAD (0.4m GIRTH)	N/A
T202	CARYOTA OCHLANDRA	TRANSPLANT OUTSIDE THE SITE	5m TALL x 4m CROWN SPREAD (0.35m GIRTH)	N/A
T203	CARYOTA OCHLANDRA	TRANSPLANT OUTSIDE THE SITE	5m TALL x 4m CROWN SPREAD (0.35m GIRTH)	N/A
T203a	CARYOTA OCHLANDRA	TRANSPLANT OUTSIDE THE SITE	3m TALL x 2m CROWN SPREAD (0.25m GIRTH)	N/A
T204	CARYOTA OCHLANDRA	TRANSPLANT OUTSIDE THE SITE	4m TALL x 3m CROWN SPREAD (0.34m GIRTH)	N/A

2. PROPOSED PLANTING SCHEDULE:

PLANTING No.	SPECIES	TYPE	SIZE	SPACING
1	CARYOTA OCHLANDRA	PROPOSED	3m TALL x 2m SPREAD (MIN. 3 SHOOTS)	AS SHOWN
2		PROPOSED		
3		PROPOSED		
4		PROPOSED		
5		PROPOSED		
6		PROPOSED		
7	MELALEUCA QUINQUENERVIA	PROPOSED	HEAVY STANDARD	AS SHOWN
8		PROPOSED		
9		PROPOSED		
10		PROPOSED		
11	CHRYSALIDOCARPUS LUTESCENS	PROPOSED	CHRYSALIDOCARPUS LUTESCENS: 2m TALL x 1.5m SPREAD (MIN. 3 SHOOTS)	CHRYSALIDOCARPUS LUTESCENS: 1.5m
12		PROPOSED		
13		PROPOSED		
14		PROPOSED		
15		PROPOSED		
16		PROPOSED		
18	FICUS PUMILA	PROPOSED	MINIMUM 300mm LONG	500mm

REV.	DESCRIPTION	DATE	BY	CHECKED	DATE
-	FIRST ISSUE AS-BUILT DRAWING	SFC	JCYC	JLY	SEP 09

CEDD CIVIL ENGINEERING AND DEVELOPMENT DEPARTMENT

CONTRACT No. GE/2005/45
LANDSLIDE PREVENTIVE WORKS
AT PO SHAN ROAD, MID-LEVELS

LANDSCAPE PLAN

SHEET 1 OF 3

AECOM

DRGNO. 51505/AB/0630A

SCALE 1:200(A1)

STATUS AS-BUILT DRAWING

© COPYRIGHT RESERVED

Date: 2011-6-22 Time: 15:51:13