

Drainage Service Department

Monthly Environmental Monitoring & Auditing report for

Contract No.DC/2006/11

Drainage Improvement in Southern Lantau

March 2009

Environmental Pioneers & Solutions Limited

8/F, Chaiwan Industrial Centre Building

20 Lee Chung Street, Chaiwan, Hong Kong

Tel: 2889 0568

Fax: 2856 2010

APPROVAL SHEET

Prepared and Certified by: ET Leader (Environmental Pioneers & Solutions Limited)

Signature: _____
Miss Patricia Chung
(ET* Leader)

Date: _____

Signature: _____
Mr. Vincent Lai
(Ecologist)

Date: _____

* ET – Environmental Team

TABLE of CONTENT

TABLE of CONTENT	ii
EXECUTIVE SUMMARY	iv
1. Introduction	1
2. Project Information	1
2.1 Construction program	1
2.2 Project Organization	1
2.3 Key Personal Contact information chart.....	2
3. Construction Stage	3
3.1 Construction Activities in the reporting month.....	3
3.2 Construction Activities for the coming month.....	3
3.3 Environmental Status	3
4. Noise Monitoring	4
4.1 Monitoring Parameters and Methodology	4
4.2 Monitoring Equipment.....	4
4.3 Monitoring Locations.....	5
4.4 Monitoring Results and Interpretation	7
4.5 Action and Limit level for Construction noise	7
4.6 Noise Mitigation Measures	9
5. Water Monitoring	10
5.1 Water Quality Monitoring Parameters and methodology	10
5.2 Monitoring Equipment.....	10
5.3 Monitoring Locations.....	11
5.4 Monitoring Frequency	13
5.5 Monitoring Results and Interpretation	13
5.6 Action and limit level for Water Quality.....	15
5.7 Water Quality Mitigation Measures	17
5.8 Water Monitoring Schedule for the Next reporting period.....	17
6. Ecology Monitoring	18
6.1 Ecological Monitoring Parameters	18
6.2 Monitoring Equipment and Methodology	19
6.3 Monitoring Locations.....	20
6.4 Monitoring Frequency	23
6.5 Monitoring results	23
6.6 Action and Limit level for Monitoring of White-shouldered Starlings	35

6.7	Ecological monitoring Schedule	35
7.	Action taken in Event of Exceedence	36
8.	Construction waste disposal.....	38
9.	Status of Permits and Licenses obtained.....	39
10.	Complaint Log	39
11.	Site Environmental Audits	40
11.1	Site Inspection.....	40
11.2	Compliance with legal and Contractual requirement.....	42
11.3	Environmental Complaint and follow up actions.....	43
12.	Future key issues.....	43
13.	Conclusions.....	44

APPENDIXES

Appendix A	Construction Programme and location plan
Appendix B	Key Personal Contact information chart
Appendix C	Calibration Certificates for measuring instruments
Appendix D1	Plant species recorded at Pak Ngan Heung River (N)
Appendix D2	Plant species recorded at Pak Ngan Heung River (S)
Appendix D3	Plant species recorded at Luk Tei Tong River
Appendix D4	Ecological Water Monitoring results (on-site measurement)
Appendix D5	Ecological Water Monitoring results (lab-report)
Appendix E	Construction Noise Monitoring Data Sheet
Appendix F1	Water Quality Monitoring Data Sheet
Appendix F2	Water Quality Monitoring Lab report
Appendix G	Monitoring Schedule for March 2009
Appendix H	Implementation status of environmental protection / mitigation measures
Appendix I	Graphical plot of water quality monitoring results (SS, DO, turbidity)
Appendix J	Graphical plot of noise monitoring results

EXECUTIVE SUMMARY

This is the eighth monthly environmental Monitoring and audit (EM&A) report for “Drainage Improvement in Southern Lantau Investigation”. The environmental permit number is “EP-237/2005/A”. The report concludes the impact monitoring for the activities undertaken during the period of 1st March 2009 to 31st March 2009. The major activities in this reporting month include construction works of box culvert at Pak Ngan Heung (PNH) River, construction of bypass channel at Luk Tei Tong (LTT) Marshland, channel widening works at Tai Tei Tong (TTT) River and construction of U-channel at Ling Tsui Tau.

Noise, water quality and ecological monitoring were performed. Results obtained were checked against the previously established Action / Limit (A/L) levels. Additionally, the implementation status of environmental mitigation measures, event/ action plan and environmental complaint handling procedures were inspected during weekly site environmental audit.

In general, waste management was satisfactory during the reporting month.

Impact monitoring for construction noise was conducted in the reporting period. No exceedance of A/L level was reported.

Furthermore, impact monitoring for water quality was conducted. Non-compliance events of water quality criteria were recorded on 2, 3, 4, 6, 16, 17 and 27 March. Exceedances were mainly caused by site water discharge and influx of marine water from silver bay.

During ecological monitoring survey, no White-shouldered Starling was recorded breeding in the watch tower. And there was no sign of disturbance from the Project to the watch tower, though the breeding season of White-shouldered Starling in this year has begun. The watch tower may not be suitable for birds as nesting habitat. In addition, no disturbance on the flora and fauna in the river channels were observed during the ecological monitoring.

Furthermore, there was no complaint, notification of any summons and successful prosecutions against the project received during the reporting period.

Key construction activity in the coming month will be construction of box culvert at PNH and retaining walls at TTT River. It is expected that noise, air and water quality impacts will be resulted from the works. With reference to the EM&A manual and mitigation measure report, mitigation measures are proposed to be taken, if necessary.

The ET will continue to implement the environmental monitoring & audit programme in accordance with the EM&A Manual and Environmental Permit requirement.

1. Introduction

This is the eighth monthly Environmental Monitoring and Audit (EM&A) Report for “Drainage Improvement in Southern Lantau Investigation” project (Environmental Permit No. EP-237/2005/A)

2. Project Information

2.1 Construction program

The “Drainage Improvement in Southern Lantau Investigation” project will be completed by June 2009. The project comprises the following:

- Construction of approximately 80m long gabion with natural bed in Pak Ngan Heung River, approximately 180m of three cells 3m x 2m box culvert and approximately 100m of rectangular channel at Pak Ngan Heung River;
- Construction of approximately 250m of 0.75m wide U-Channel at Ling Tsui Tau Village in Mui Wo;
- Construction of bypass channel of about 350m and 240m long of gabion channels at Luk Tei Tong River respectively; and Widening three existing bottlenecks with gabion lined at Tai Tei Tong River

Appendix A shows the construction program and location plan of the project.

2.2 Project Organization

The Main Contractor, Yick Hing Construction Company Limited, has commissioned Environmental Pioneers & Solutions Limited and Ecosystems Limited as the Environmental Team, which comprises the environmental team leader, the ecologists and the environmental technicians to undertake the environmental monitoring and audit work for this project.

The environmental management structure and is shown in Fig 2.2.1.




Figure. 2.2.1 Environmental Management structure for the project

2.3 Key Personal Contact information chart

Detailed contact of key persons involved in environmental aspect of the project is shown in appendix B.

3. Construction Stage

3.1 Construction Activities in the reporting month

Major activities in the reporting month included the followings:

1. Construction of U-channel and catchpit at Ling Tsui Tau;
2. Concreting works for box culvert (coded BC11) at PNHR;
3. Shuttering formwork and Steel fixing works of box culvert (coded BC12) at PNHR;
4. Rock filling and shuttering to gabion blocks at bottle neck A of TTT River
5. Rock filling and shuttering to gabion blocks at LTT bypass channel;
6. Concreting works of box culvert, mass concrete wall and tree-ring at Luk Tei Tong; and
7. Reinstatement of turf/ topsoil to the bed of LTT bypass channel.

3.2 Construction Activities for the coming month

Key Construction works in the coming month will include:

1. Construction of box culvert at PNH;
2. Construction of gabion wall at Bottleneck B of TTT River; and
3. Construction of retaining wall H at TTT River.

3.3 Environmental Status

Appendix A shows the drawing of the project area.

Locations of the monitoring and control stations with environmental sensitive receivers are presented in Section 4.3, 5.3 and 6.3 for noise, water and ecological monitoring respectively.

4. Noise Monitoring

4.1 Monitoring Parameters and Methodology

The construction noise level was measured in terms of the A-weighted equivalent continuous sound pressure level (L_{eq}). $L_{eq(30minutes)}$ was used as the monitoring parameter for the impact monitoring in the time period between 0700 to 1900 hours on normal weekdays. For all other time period, $L_{eq(5minutes)}$ was employed for comparison with the Noise Control Ordinance (NCO) criteria.

Noise measurement results obtained from each monitoring location were recorded in the Construction Noise Monitoring Data Sheet (Appendix E) immediately after the measurement. As supplementary information for data auditing, statistical results L_{10} and L_{90} were also be recorded for reference.

In case of non-compliance with the construction noise criteria, more frequent monitoring, as specified in the Action plan in table 4.5.2, shall be carried out. This additional monitoring shall be carried out until the recorded noise levels are rectified or proved to be irrelevant to the construction activities.

4.2 Monitoring Equipment

The sound level meters and calibrators comply with the International Electrotechnical Commission Publications 651:1979 (Type 1) and 804:1985 (Type 1) specifications as referred to in the Technical Memorandum (TM) to the Noise Control Ordinance was deployed as monitoring equipment for noise measurement.

Noise measurement was not be made in the presence of fog, rain, wind with a steady speed exceeding $5ms^{-1}$ or wind with gust exceeding $10ms^{-1}$. Thus wind speed was checked by the portable wind speed indicator capable of measuring the wind speed in m/s. Table 4.2.1 summarizes the equipment list for noise monitoring

Table 4.2.1 Equipment List for Noise Monitoring

Equipment	Manufacturer & Model No.	Precision Grade	Qty
Integrated sound level meter	ACO Japan, model 6224	IEC 651 Type 1 IEC 804 Type 1	1
Windscreen	Microtech gefell model W2	N/A	1
Acoustical calibrator	Castle GA 607	IEC 942 Type 1	1
Wind speed indicator	Kestrel K1000	N/A	1
Remarks: Calibration details for the sound level meter is given in Appendix C for reference			

4.3 Monitoring Locations

According to the Baseline Monitoring Report issued in May 2008 for the captioned project, four locations were alternative from the locations proposed in EM&A manual, were designated for baseline noise monitoring. For the data validation, impact noise monitoring was undertaken in the same locations during the construction phase of the project. The proposed monitoring locations are summarized in Table 4.3.1. Figure 4.3.1 shows the Noise Monitoring Locations

Noise measurement in each monitoring locations were taken at a point 1m from the exterior of the selected premises and at a height with no disturbance to the dweller and least obstructed view.

Table 4.3.1 Noise Monitoring Locations during Construction Phase

Identification No.	Noise Monitoring Locations
N1	No. 73, Village House, Ling Tsui Tau Tsuen (ground level)
N2	No. 31, Village House, Ling Tsui Tau Tsuen (ground level)
N3	Fence wall outside No. 5 village house adjacent to Luk Tei Tong River Outlet (ground level)
N4	No. 23, Village House, Tai Tei Tong River (ground level)

In accordance with the requirements in the EM&A manual, weekly impact monitoring was conducted. For the time period between 0700 and 1900 hours on normal weekdays, and noise parameter of $L_{eq(30minutes)}$ was measured. As if the construction works were carried out during restricted period (ie. 1900-2300, 2300-0700 of next day and Sundays / general holiday), impact monitoring that comprises 3 consecutive $L_{eq(5minutes)}$ would be carried out.




Figure 4.3.1 Impact noise monitoring locations

4.4 Monitoring Results and Interpretation

Relevant details of the noise monitoring results are presented in table 4.4.1. The results, ranged between 44.8 dB (A) and 68.4 dB (A), were within the limit levels and therefore, no exceedance was found.

Table 4.4.1 Noise monitoring results

Location	Parameter	Date	Time	L _{Aeq} dB(A)	Limit dB(A)	Exceedance	Weather
N1	L _{eq} 30mins	02/03/09	13:00	44.8	75	N	Sunny
N1	L _{eq} 30mins	09/03/09	15:15	45.2	75	N	Sunny
N1	L _{eq} 30mins	16/03/09	15:20	48.3	75	N	Sunny
N1	L _{eq} 30mins	23/03/09	15:00	46.6	75	N	Sunny
N1	L _{eq} 30mins	30/03/09	13:35	46.7	75	N	Sunny
N2	L _{eq} 30mins	02/03/09	13:35	49.7	75	N	Sunny
N2	L _{eq} 30mins	09/03/09	15:53	57.8	75	N	Sunny
N2	L _{eq} 30mins	16/03/09	14:45	57.9	75	N	Sunny
N2	L _{eq} 30mins	23/03/09	14:25	63.6	75	N	Sunny
N2	L _{eq} 30mins	30/03/09	13:00	58.7	75	N	Sunny
N3*	L _{eq} 30mins	02/03/09	11:15	52.8	75	N	Sunny
N3*	L _{eq} 30mins	09/03/09	14:40	48.1	75	N	Sunny
N3*	L _{eq} 30mins	16/03/09	14:05	54.9	75	N	Sunny
N3*	L _{eq} 30mins	23/03/09	13:50	68.4	75	N	Sunny
N3*	L _{eq} 30mins	30/03/09	10:40	52.4	75	N	Sunny
N4	L _{eq} 30mins	02/03/09	10:40	45.8	75	N	Sunny
N4	L _{eq} 30mins	09/03/09	14:08	49.9	75	N	Sunny
N4	L _{eq} 30mins	16/03/09	13:30	50.4	75	N	Sunny
N4	L _{eq} 30mins	23/03/09	13:15	54.5	75	N	Sunny
N4	L _{eq} 30mins	30/03/09	11:15	50.3	75	N	Sunny

Remarks: Raw datasheet for noise monitoring are attached in appendix E for reference.

Remark*: The equivalent noise level of N3 is corrected by +3 dB from the raw data result due to the fact that free field measurement was carried out in the location.

4.5 Action and Limit level for Construction noise

The Action and Limit (A/L) levels for construction noise are defined in Table 4.5.1. Should non-compliance of the criteria occur, action in accordance with the Action Plan in Table 4.5.2 should be carried out.

There was no recorded exceedance in the reporting month.

Time Period	Action Level	Limit Level
0700 – 1900 hours on normal weekdays	When one documented complaint is received	75dB(A)
Remarks: If works are to be carried out during restricted hours, the conditions stipulated in the construction noise permit issued by the Noise Control Authority have to be followed.		

Table 4.5.2 Event / Action Plan for Construction Noise

EVENT	ACTION			
	ET	IC(E)	ER	Contractor
Action Level	<ol style="list-style-type: none"> 1. Notify IC(E) and Contractor; 2. Carry out investigation; 3. Report the results of investigation to the IC(E), ER and Contractor; 4. Discuss with the Contractor and formulate remedial measures; 5. Increase monitoring frequency to check mitigation effectiveness. 	<ol style="list-style-type: none"> 1. Review the analysed results submitted by the ET; 2. Review the proposed remedial measures by the Contractor and advise ER accordingly; 3. Supervise the implementation of remedial measures. 	<ol style="list-style-type: none"> 1. Confirm receipt of notification of failure in writing; 2. Notify Contractor; 3. Require Contractor to propose remedial measures for the analysed noise problem; 4. Ensure remedial measures are properly implemented. 	<ol style="list-style-type: none"> 1. Submit noise mitigation proposals to IC(E); 2. Implement Noise mitigation proposals.
Limit Level	<ol style="list-style-type: none"> 1. Identify source; 2. Inform IC(E), ER, EPD and Contractor; 3. Repeat measurements to confirm findings; 4. Increase monitoring frequency; 5. Carry out analysis of Contractor's working procedures to determine possible mitigation to be implemented; 6. Inform IC(E), ER and EPD the causes and actions taken for the exceedances; 7. Assess effectiveness of Contractor's remedial actions and keep IC(E), EPD and ER informed of the results 8. If exceedance stops, cease additional monitoring 	<ol style="list-style-type: none"> 1. Discuss amongst ER, ET, and Contractor on the potential remedial actions; 2. Review Contractors remedial actions whenever necessary to assure their effectiveness and advise the ER accordingly; 3. Supervise the implementation of remedial measures. 	<ol style="list-style-type: none"> 1. Confirm receipt of notification of failure in writing; 2. Notify Contractor; 3. Require Contractor to propose remedial measures for the analysed noise problem; 4. Ensure remedial measures properly implemented; 5. If exceedance continues, consider what portion of the work is responsible and instruct the Contractor to stop that portion of work until the exceedance is abated 	<ol style="list-style-type: none"> 1. Take immediate action to avoid further exceedance; 2. Submit proposals for remedial actions to IC(E) within 3 working days of notification; 3. Implement the agreed proposals; 4. Resubmit proposals if problem still not under control; 5. Stop the relevant portion of works as determined by the ER until the exceedance is abated

4.6 Noise Mitigation Measures

The following mitigation measures were observed from the weekly site inspection in the reporting month:

- Use of quiet powered mechanical equipment (PME)
- Implementation of the following good site practices:
 - Only well-maintained and regularly serviced plant should be operated on site;
 - Silencers or mufflers on construction equipment;
 - Mobile plant, if any, should be sited as far from noise sensitive receivers as possible; and
 - Machines and plant (such as trucks) that may be in intermittent use should be shut down between work periods or should be throttled down to a minimum.

5. Water Monitoring

5.1 Water Quality Monitoring Parameters and methodology

Turbidity in Nephelometric Turbidity Unit (NTU), Dissolved Oxygen (DO) in mg/L and Suspended Solids (SS) in mg/L are required to measure in this project. Turbidity, DO was measured in-situ while water samples were delivered to Accredited HOKLAS Laboratory for analysis of SS.

Other relevant data such as monitoring location, time, water depth, temperature, salinity, weather conditions and any other special phenomena and work underway at the construction site were recorded during sampling.

According to the requirement of the EM&A manual, two consecutive measurements for parameters of DO concentration, DO saturation and Turbidity are required to be taken at each monitoring location. When the difference in value between the first and second reading of DO or Turbidity is more than 25%, the reading would be discarded and further reading would be taken.

5.2 Monitoring Equipment

Turbidity, DO, Salinity, pH and temperature was measured by an instrument complied with the following requirements:

The instrument is a portable as well as weatherproof multimeter complete with cable and uses a DC power source. It is capable of measuring:

- A turbidity between 0-800NTU;
- A dissolved Oxygen level in the range of 0-20mg/L and 0-200% saturation;
- A temperature of 0-50°C;
- Salinity in the range of 0-40ppt;
- pH in the range of 0-14.

Suspended solid was determined by the water samples collected from the monitoring locations for further analysis in accredited HOKLAS laboratory. Water samples were contained by polythene bottles, packed in ice (cooled in 4°C without frozen) and delivered to the laboratory for analysis as soon as possible after collection. Duplicate samples from each independent sampling event were undertaken during impact monitoring.

Detailed calibration records of the multimeter were shown in Appendix C for reference.

5.3 Monitoring Locations

Seven locations included a control station in upstream of each stream/ river, a monitoring station at the end of each stream/ river of the works area and a monitoring station at Silver River were proposed for the impact water quality monitoring. Water samples were collected at mid-depth of each proposed monitoring stations for measurements and sample collection. The Location Plan is shown in Figure 5.3.1 for reference.




Figure 5.3.1 Water Quality Monitoring Locations

5.4 Monitoring Frequency

Impact water quality monitoring was undertaken three days per week and at ebb tides during the course of the construction river works. Upon the completion of the construction works, the monitoring exercises at the designated monitoring stations will be continued for four weeks in the same manner as the impact monitoring.

5.5 Monitoring Results and Interpretation

Water quality monitoring was carried out fifteen times during March. Detailed on-site measurements and laboratory analysis reports including QA/QC results are shown in appendix F1 and F2 respectively, while Table 5.5.1 presents consolidated results throughout the reporting month.

Exceedance events on parameters of turbidity and suspended solids were recorded on 2, 3, 4, 6, 16, 17 and 27 March according to the established level. Findings from the investigations showed that exceedance were mainly caused by:

- 1.) Defective mitigation measures and working method of the river based construction work. Site water and surface runoff was found entered the river stream due to insufficient and/or ineffective protective measures in some events.
- 2.) Influx of marine water affected the water quality of Silver River as well as confluence of LTT, TTT and PNH River (i.e. salinity were found extremely high in the monitor locations in some cases).
- 3.) River clearance works carried out at the upper stream area by the other projects in TTT River, as control station C2 was also seriously contaminated by silty water according to the observation and measured results (i.e.: maximum reading obtained in C2 - Turbidity: 329.6 NTU, Suspended Solids: 215.4mg/L).
- 4.) Water quality changes due to heavy rainstorm.

Detailed information of the exceedance events and action taken were presented in Section 7.

Table 5.5.1 Water quality monitoring results in March 2009

	M1			M2			M3			M4		
	MIN	MAX	Ave	MIN	MAX	Ave	MIN	MAX	Ave	MIN	MAX	Ave
Turbidity (NTU)	3.4	25.6	8.6	2.7	15.9	7.3	4.3	16.5	8.1	5.1	17.5	9.0
DO (mg/l)	4.9	10.5	7.7	5.4	10.8	8.3	5.4	9.1	7.0	5.0	8.9	6.8
Suspended Solid (mg/l)	4.1	12.8	7.8	1.0	11.3	4.6	4.9	13.8	8.1	5.2	13.1	9.1

	C1			C2			C3		
	MIN	MAX	Ave	MIN	MAX	Ave	MIN	MAX	Ave
Turbidity (NTU)	0	8.6	2.9	0.0	329.6	25.7	3.7	19.0	9.9
DO (mg/l)	6.24	9.6	7.6	6.3	9.0	7.7	3.7	6.9	5.0
Suspended Solid (mg/l)	1.0	6.2	2.1	1.0	215.4	16.8	7.4	13.0	10.7

* Remarks: Detection limit for Turbidity, DO and SS are 1 NTU, 0.1 mg/L and 1 mg/L respectively.

5.6 Action and limit level for Water Quality

Based on the baseline water quality monitoring data obtained, the A/L levels are shown in Table 5.6.1. If the water quality monitoring results at any impact stations exceeded the criteria, the actions in accordance with the Event and Action Plan in Table 5.6.2 should be taken.

Table 5.6.1 Action and Limit Levels for water quality monitoring

Parameters	Monitoring locations							
	M1		M2		M3		M4	
	Action Level	Limit Level	Action Level	Limit Level	Action Level	Limit Level	Action Level	Limit Level
Turbidity (NTU)	15.2	16.9	5.3	6.5	16.8	26.0	16.2	18.0
DO (mg/L)	5.7	4.0	6.2	4.0	5.9	4.0	5.9	4.0
SS (mg/L)	12.2	12.8	3.1	4.2	12.4	17.7	13.9	15.2

Remarks:

For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits

For SS and turbidity, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.

Table 5.6.2 Event and action Plan for Water Quality

EVENT	ACTION			
	ET	IC(E)	ER	Contractor
Action Level being exceed by one sampling day	<ol style="list-style-type: none"> 1. Repeat in <i>situ</i> measurement to confirm findings; 2. Identify reasons for non-compliance and source(s) of impact; 3. Inform IC(E) and Contractor; 4. Check monitoring data, all plant, equipment and Contractor's working methods; 5. Discuss mitigation measures with IC(E) and Contractor; 6. Repeat measurement on next day of exceedance. 	<ol style="list-style-type: none"> 1. Discuss with ET and Contractor on the mitigation measures; 2. Review proposals in mitigation measures submitted by Contractor and advise the ER accordingly; 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Discuss with IC(E) on the proposed mitigation measures; 2. make agreement on the mitigation measures to be implemented; 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Inform the ER and confirm notification of the non-compliance in writing; 2. Rectify unacceptable practice; 3. Check all plant and equipment; 4. Consider changes of working methods; 5. Discuss with ET and IC(E) and propose mitigation measures to IC(E) and ER; 6. Implement the agreed mitigation measures.
Action level being exceed by more than two consecutive sampling days	<ol style="list-style-type: none"> 1. Repeat in <i>situ</i> measurement to confirm findings; 2. Identify reasons for non-compliance and source(s) of impact; 3. Inform IC(E) and Contractor; 4. Check monitoring data, all plant, equipment and Contractor's working methods; 5. Discuss mitigation measures with IC(E) and Contractor; 6. Ensure mitigation measures are implemented; prepare to increase the monitoring frequency to daily 7. Repeat measurement on next day of exceedance 	<ol style="list-style-type: none"> 1. Discuss with ET and Contractor on the mitigation measures; 2. Review proposals in mitigation measures submitted by Contractor and advise the ER accordingly; 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Discuss with IC(E) on the proposed mitigation measures; 2. make agreement on the mitigation measures to be implemented; 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Inform the ER and confirm notification of the non-compliance in writing; 2. Rectify unacceptable practice; 3. Check all plant and equipment; 4. Consider changes of working methods; 5. Discuss with ET and IC(E) and propose mitigation measures to IC(E) and ER within three working days; 6. Implement the agreed mitigation measures.
Limit level being exceeded by one sampling day	<ol style="list-style-type: none"> 1. Repeat in <i>situ</i> measurement to confirm findings; 2. Identify reasons for non-compliance and source(s) of impact; 3. Inform IC(E) and Contractor; 4. Check monitoring data, all plant, equipment and Contractor's working methods; 5. Discuss mitigation measures with IC(E) and Contractor; 6. Ensure mitigation measures are implemented; 7. Increase the monitoring frequency to daily until no exceedance of Limit Level 	<ol style="list-style-type: none"> 1. Discuss with ET and Contractor on the mitigation measures; 2. Review proposals in mitigation measures submitted by Contractor and advise the ER accordingly; 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Discuss with IC(E) on the proposed mitigation measures; 2. make agreement on the mitigation measures to be implemented; 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Inform the ER and confirm notification of the non-compliance in writing; 2. Rectify unacceptable practice; 3. Check all plant and equipment; 4. Consider changes of working methods; 5. Discuss with ET and IC(E) and propose mitigation measures to IC(E) and ER; 6. Implement the agreed mitigation measures.

5.7 Water Quality Mitigation Measures

Construction Run-off and Drainage

The site practices outlined in ProPECC PN 1/94 ‘Construction Site Drainage’ should be followed as far as practicable during both construction and operation phase of the drainage improvement works in order to minimize surface runoff and the chance of erosion, and also to retain and reduce any suspended solids prior to discharge.

As recommended in the final EM&A manual, attention would be paid specially construction run-off and drainage, general construction activities, sewage discharged from construction workforce and river channel excavation works.

5.8 Water Monitoring Schedule for the Next reporting period

Water monitoring in the next reporting period is scheduled for 1, 2, 6, 8, 9, 14, 15, 17, 20, 22, 24, 27 and 29 April.

6. Ecology Monitoring

6.1 Ecological Monitoring Parameters

According to the Final EM&A Manual, a specific ecological monitoring programme of the improved section of PNH and LTT Rivers is recommended. The monitoring parameters required to measure in this project and survey methodology are described below:

(1) Avifauna species and abundance: Birds will be surveyed quantitatively using transect count method. Birds within the river channel and on the riverbank will be identified and their abundance will be recorded.

(2) Aquatic macroinvertebrate community species composition and abundance: Survey on aquatic fauna will focus on determination of the diversity and abundance of stream aquatic communities. Sampling methods, such as active searching, direct observation, netting, and kick sampling, will be determined according to the site conditions during field survey.

(3) Fish community species composition and abundance: Sampling methods, such as active searching, direct observation, and hand netting, will be determined according to the site conditions during field survey.

(4) Adult odonate community species composition and abundance: Adult dragonfly will be surveyed quantitatively using transect count method. Adult dragonflies within the river channel and on the riverbank will be identified and their abundance will be recorded. Species requiring close examination will be netted.

(5) Aquatic, emergent and riparian vegetation community species composition and abundance: The area will be walked through. Plant species composition and their relative abundance will be recorded.

(6) Surveys of White-shouldered Starling *Sturnus sinensis* will be conducted at the disused watchtowers next to LTT river. Breeding of the White-shouldered Starlings will be determined by checking signs of attempt to breed or sign of breeding which include carrying nesting materials, to-and-fro movement of adults carrying food, presence of recently fledged juveniles, etc. The number of breeding pairs and the site observation will be recorded whenever possible.

Water Quality Monitoring along LTT and PNH River as well as LTT bypass channel was carried out. Water quality monitoring will include Turbidity in Nephelometric Turbidity Unit (NTU), Dissolved Oxygen (DO) in mg/L and Suspended Solids (SS) in mg/L are required to measure in this project. Moreover, additional water monitoring parameters will be taken for the purposes of ecological monitoring of water quality in this project. The added information will include: BOD, Ammonia, Nitrate and Phosphate concentrations. Turbidity, DO, pH and water flow will be measured in-situ while water samples will be delivered to Accredited HOKLAS Laboratory accredited laboratory and the analyses followed the standard methods according to APHA Standard Methods for the Examination of Water and Wastewater, 20th Edition, or equivalent for analysis of SS, BOD, Ammonia, Nitrate and Phosphate concentrations.

Other relevant data such as monitoring location, time, water depth, temperature, salinity, weather conditions and any other special phenomena and work underway at the construction site will be recorded during sampling.

According to the requirement of the EM&A manual, two consecutive measurements for parameters of DO concentration, DO saturation and Turbidity are required to be taken at each monitoring. When the difference in value between the first and second reading of DO or Turbidity is more than 25%, the reading will be discarded and further reading will be taken.

6.2 Monitoring Equipment and Methodology

Turbidity, DO, Salinity, pH and Temperature will be measured by a instrument complied with the following requirements:

The instrument is a portable as well as weatherproof multimeter complete with cable and uses a DC power source. It is capable of measuring:

- A turbidity between 0-800NTU;
- A dissolved Oxygen level in the range of 0-20mg/L and 0-200% saturation;
- A temperature of 0-50°C;
- Salinity in the range of 0-40ppt;
- pH in the range of 0-14.

Suspended solid was determined by the water samples collected from the

monitoring locations for further analysis in accredited HOKLAS laboratory. Water samples were contained by polythene bottles, packed in ice (cooled in 4°C without frozen) and delivered to the laboratory for analysis as soon as possible after collection. Duplicate samples from each independent sampling event were undertaken during impact monitoring.

6.3 Monitoring Locations

According to the Final EM&A Manual, the improved section of the river channels will be divided into 50m long sections, and ecological survey will be carried out in each of the 50m sections. A total of nine sections will be divided for the two rivers which include:

- Two sections for existing upstream of PNH river (i.e. the proposed 80m long trapezoidal channel)
- Two sections for existing downstream of PNH river (i.e. the proposed 100m long rectangular channel)
- Five sections for existing Luk Tei Tong River (i.e. the proposed 240m long trapezoidal channel)

The disused watchtowers are located at the confluence of the three rivers and next to LTT river.

The Location Plan for ecological is shown in Figure 6.1 for reference.

The improved sections of the river channels require to carrying out water quality monitoring for the ecological purpose. The sampling points for impact monitoring was undertaken in the same place as the baseline monitoring proposed, where include:

- Three points for existing of PNH river
- Three points for existing of Luk Tei Tong River

The Location Plan for ecological water monitoring is shown in Figure 6.2 for reference.




Figure 6.1 Ecological Monitoring Locations




Figure 6.2 Ecological Water Quality monitoring locations

6.4 Monitoring Frequency

As proposed, ecological impact monitoring was carried out once for each monitoring location in the reporting month.

6.5 Monitoring results

Pak Ngan Heung Stream N and S sections

Vegetation

Surveys were conducted on 26 March 2009. The north section of Pak Ngan Heung Stream was fairly modified. Part of the west bank was lined with rock gabion bank and occupied by village houses and abandoned agricultural field. The stream channel was wider than the downstream section, but the stream bank was still fairly narrow and steep in gradient. Compared to the south section, the north section was relatively shaded due to presence of more trees with larger canopy.

The walk through survey recorded a total of 69 species, including 24 trees, 10 shrub, 22 herb and 4 grass species (Appendix D1). 53 of the species recorded are natives, while 16 were exotics. The quantitative sampling recorded 23 species at the north section. Large native (e.g. *Celtis sinensis*, *Cleistocalyx operculata*, *Ficus hispida*) and exotic trees (*Acacia confusa*) dominated the transects. Other species recorded include common and typical native pioneer forest and streamside tree species and ruderal species. No species of conservation interest was recorded.

Table 6.5.1 Relative percentage cover of vegetation recorded at Pak Ngan Heung (N) Section

Species	Relative % cover	
	PNH3	PNH4
<i>Acacia confusa</i>		15.70
<i>Acorus graminifolius</i>		0.60
<i>Aporosa dioica</i>		3.29
Bamboo	12.77	
<i>Celtis sinensis</i>	20.28	24.15
<i>Christella parasitca</i>	0.56	1.60
<i>Cleistocalyx operculata</i>	30.23	
<i>Embelia ribes</i>		1.45
<i>Ficus hispida</i>		15.45
<i>Litsea glutinosa</i>		16.30
<i>Macaranga tanarius</i>		12.07
<i>Mallotus paniculatus</i>	15.02	
<i>Microstegium ciliatum</i>		1.21
<i>Mikania micrantha</i>	2.18	1.21
<i>Phyllanthus urinaria</i>	0.45	
<i>Phyllanthus urinaria</i>		1.06
<i>Pueraria phaseoloides</i>	3.19	
<i>Pueraria phaseoloides</i>		0.54
<i>Sageretia thea</i>		4.07
<i>Sporobolus fertilis</i>		1.18
<i>Sterculia lanceolata</i>	1.24	
<i>Syzygium jambos</i>	14.08	
<i>Syzygium jambos</i>		0.12
Total Relative % Cover*	100.0	100.0
Total Transect Length (m)	13	34

*Total Cover rounded up to one decimal place to avoid round-off error.

The south section of Pak Ngan Heung Stream was highly modified. Both banks were lined with rock gabions and were occupied by village houses immediately beyond the channel. The stream channel was lack of riparian zone and vegetation. A total of 19 species recorded, 14 of which were native and 5 were exotic. It was composed of isolated individuals of mangrove (*Kandelia obovata*), backshore species (*Clerodendrum inerme*), native (*Celtis sinensis*) and planted trees (*Acacia confusa*) (Appendix D2). No species of conservation interest was recorded.

Terrestrial Fauna

Surveys were conducted on 20 March 2009.

A total of five species of birds were recorded in the proposed work area of the Pak Ngan Heung River (Table 6.5.2). All are common in Hong Kong.

Table 6.5.2 Avifauna in Pak Ngan Heung

Common names	Latin names	PNH 1	PNH 2	PNH 3	PNH 4	Commonness & distribution
Little Egret	<i>Egretta garzetta</i>		1			CW
Chinese Bulbul	<i>Pycnonotus sinensis</i>	4				CW
Yellow-bellied Prinia	<i>Prinia flaviventris</i>		1			CW
Japanese White-eye	<i>Zosterops japonica</i>				1	CW
Crested Myna	<i>Acridotheres crisatellus</i>		1			CW

CW = common and widespread

Three species of dragonfly was recorded in the proposed work area of the Pak Ngan Heung River in March 2009 (Table 6.5.3). The Yellow-spotted Shadowdamsel *Sinosticta ogatai* is uncommon in Hong Kong.

Table 6.5.3 Dragonfly in Pak Ngan Heung River

Common names	Latin names	PNH 1	PNH 2	PNH 3	PNH 4	Commonness & distribution
Yellow-spotted Shadowdamsel	<i>Sinosticta ogatai</i>				1	UC
Crimson Dropwing	<i>Trithemis aurora</i>	1				A
Indigo Dropwing	<i>Trithemis festiva</i>		3			A

A = abundant, UC = uncommon

Aquatic fauna and fish

8 species of fish and 4 crustacean were recorded in the 4 sections at PNH. All are common and widespread in Hong Kong. Both the species number of aquatic fauna and their abundance recorded in the present monitoring survey were lower than those recorded in previous wet season months, probably due to the lower temperature. As observed on site, the stream flow was very small and the water level was low, and there were algae on the stream bed. This is typical in local streams during dry season. Though Predaceous Chub was observed, the another one fish species of conservation concern reported in the EIA report, i.e. Flagtail *Kuhlia marginata*, was not recorded in PNH during the present monthly monitoring survey.

Table 6.5.4 Aquatic Invertebrates and fish in Pak Ngan Heung

Common names	Scientific names	PNH 1	PNH 2	PNH3	PNH4
Invertebrates					
Atyid shrimp	<i>Caridina elongata</i>				+
Palaemonid shrimp	<i>Macrobrachium hainanensis</i>			+	
Crab	<i>Varuna litterata</i>	+	+		
Mitten Crab	<i>Eriocheir japonica</i>		+		
Fish					
Mosquito fish	<i>Gamusia affinis</i>				+
Barcheek Goby	<i>Rhinogobius giurinus</i>				+
Goby	<i>Rhinogobius duospilus</i>		+		
Swordtail	<i>Xiphophorus hellerii</i>				
Six-banded Barb	<i>Puntius semifasciolatus</i>				
Unidentified Cichlid fish					
Tilapia		++	+++	+	
Predaceous Chub	<i>Parazacco spilurus</i>			++	
Jarua Terapon	<i>Terapon jarbua</i>	++			
Common Silver-biddy	<i>Gerres oyena</i>	+			
Mullet	<i>Mugil cephalus</i>	+++	+++		
Broken-band Hillstream Loach	<i>Liniparhomaloptera disparis</i>				

+ = Occasional, less than 5 individuals were found; ++ = Common, 5 – 20 individuals were found; +++ = Abundant, more than 20 individuals were found.

Luk Tei Tong Stream Section

Vegetation

Surveys were conducted on 26 March 2009. The Luk Tei Tong Stream Section was highly modified. Vegetation only established on isolated muddy patches at the estuary and remaining semi-natural banks of Section 1 and Section 2. Vegetation on the eastern stream bank from the second half of Section 3 to Section 5 were largely cleared while the western bank was still lined with rock gabions or concrete. The whole section appeared to be subject to tidal influence, as mangrove associated or backshore species were recorded along the whole channel.

The walk through survey recorded a total of 26 species, including 11 tree, 6 shrub, 4 grass species (Appendix D3). 21 of the species recorded are natives, while 5 were exotics. The quantitative sampling recorded 10 species at Sections 2 and 3. Section 2 was dominated by *Terminalia catappa* and *Wollastonia biflora*, while Section 3 was dominated by *Hibiscus tiliaceus*. No quantitative survey was carried out on Section 4 due to vegetation clearance on stream banks as part of the site clearance works under the project. .

Due to the patchiness of streamside vegetation, the quantitative data should be interpreted with cautions and used as a reference only.

Table 6.5.5 Relative percentage cover of vegetation recorded at Luk Tei Tong Stream Section

Species	Relative % cover	
	LLT2	LLT3
<i>Acanthus ilicifolius</i>	6.75	31.85
<i>Celtis sinensis</i>	12.98	
<i>Execoecaria agallocha</i>	5.71	
<i>Fimbristylis sp.</i>	6.23	
<i>Kandelia obovata</i>	1.56	31.53
<i>Papalum paspaloides</i>	20.25	
<i>Terminalia catappa</i>	37.38	
<i>Toxocarpus wightianum</i>	0.31	
<i>Wollastonia biflora</i>	8.83	
<i>Hibiscus tiliaceus</i>		36.62
Total Relative % Cover	100.0	100.0
Total Transect Length (m)	11	10

*Total Cover rounded up to one decimal place to avoid round-off error.

Terrestrial Fauna

The proposed work area of Luk Tei Tong River was divided into 5 sections. All recorded avifauna and dragonfly species are common in Hong Kong

Surveys were conducted on 20 March 2009.

A total of ten species of birds were recorded in these sections (Table 6.5.6). All these species are common and widely distributed in Hong Kong.

Table 6.5.6 Avifauna in Luk Tei Tong River

Common names	Latin names	LTT	LTT	LTT	LTT	LTT	Commonness & distribution
		1	2	3	4	5	
Little Egret	<i>Egretta garzetta</i>	2		4		1	CW
Great Egret	<i>Casmerodius albus</i>	1					CL
Common Sandpiper	<i>Actitis hypoleucos</i>	1					CW
Barn Swallow	<i>Hirundo rustica</i>			5			CW
Spotted Dove	<i>Streptopelia chinensis</i>			1			CW
Common Koel	<i>Eudynamis scolopacea</i>	1					CW
Oriental Magpie Robin	<i>Copsychus saularis</i>		1				CW
Dusky Warbler	<i>Phylloscopus fuscatus</i>		1				CL
Crested Myna	<i>Acridotheres cristatellus</i>	6				2	CW
Common Magpie	<i>Pica pica</i>	1					CW

CW = common and widespread, CL = common/uncommon and localised

Three species of dragonfly were recorded in the Luk Tei Tong River (Table 6.5.7) in March 2009. All are common and widespread in Hong Kong.

Table 6.5.7 Dragonfly in Luk Tei Tong River

Common names	Latin names	LTT	LTT	LTT	LTT	LTT	Commonness & distribution
		1	2	3	4	5	
Common Blue Skimmer	<i>Orthetrum glaucum</i>	1					A
Green Skimmer	<i>Orthetrum sabina</i>					1	A
Crimson Dropwing	<i>Trithemis aurora</i>	1					A

A = abundant, C = common

Aquatic invertebrates and fish

4 species of fish, 3 species of crustacean and 4 species of mollusks were recorded in the 5 sections at LTT. All are common and widespread in Hong Kong. The species number of the aquatic fauna, in particular crustacean, and their abundance recorded in the present monitoring survey were lower than those recorded in previous wet season months, probably due to the lower temperature. As observed on site, the stream flow was very small and the water level was low. This is typical in local streams during dry season. The two fish species of conservation concern reported in the EIA report, i.e. Flagtail *Kuhlia marginata* and Predaceous Chub *Parazacco spilurus* were not recorded in LTT during the present monitoring as well as the baseline monitoring survey.

Table 6.5.8 Aquatic invertebrates and fish in Luk Tei Tong River

Common names	Scientific names	LTT1	LTT2	LTT3	LTT4	LTT5
Invertebrates						
Mangrove clam	<i>Geloina erosa</i>					
Rock oyster	<i>Saccostrea cuculata</i>		+++	+		
Snail	<i>Melanoides tuberculata</i>					
Snail	<i>Terebralia</i> sp.			+		
Snail	<i>Nerita</i> sp.		+	+		
Snail	<i>Littoraria articulata</i>		+	+		
Crab	<i>Varuna litterata</i>			+	+	
Fiddler crab	<i>Uca lactea</i>					
Fiddler crab	<i>Uca arcuata</i>					
Fiddler crab	<i>Uca crassipes</i>					
Crab	<i>Perisesarma bidens</i>		+			
Mangrove mud crab	<i>Scylla paramamosain</i>		+	+		
Mitten crab	<i>Eriocheir japonica</i>					
Fish						
Common mudskipper	<i>Periophthalmus cantonensis</i>					
Tilapia		++				
Jarboa terapon	<i>Terapon jarbua</i>		+	+		
Mullet	<i>Mugil cephalus</i>	+++	++	+		
Common Silver-biddy	<i>Gerres oyena</i>			+		
Barcheek Goby	<i>Rhinogobius giurinus</i>					

+ = Occasional, less than 5 individuals were found; ++ = Common, 5 – 20 individuals were found; +++ = Abundant, more than 20 individuals were found.

Disused Watchtowers

Surveys were conducted on 20 March 2009.

There was no sign (e.g., adults carrying food or nesting materials) of use of the watchtower as nesting habitat by White-shouldered Starling. This species was not observed during the March 2009 monitoring.

Since the monitoring surveys commenced in August 2008, no bird was observed entering the watchtower. It seems the birds do not prefer the watchtower as roosting or nesting habitat.

Ecological Water Quality Monitoring (EWQM)

EWQM was conducted on 9 March 2009. Monitoring results are summarized in table 6.9. Detailed on-site measurements and laboratory report are presented in appendix D4 and D5.

Table 6.10 shows the baseline results of Ecological Water Quality Monitoring, from the information given in Baseline Monitoring Report.

To review the results in table 6.9 in general, the measured results were found similar with past months. As land based construction activities were being carried out in the project sites and sites were in enclosed condition, water quality impacts to the rivers should be minimal.

Table 6.9 Summarized Ecological water quality monitoring results (9 March 2009)

Parameters	Limit of detection	WE1	WE2	WE3	WE4	WE5	WE6
Suspended Solid (mg/l)	1	1.15	2.25	4.15	9.50	11.10	1.05
Nitrogen (Ammonia) (mg/l)	0.01	0.28	0.62	0.61	0.47	1.23	0.15
Nitrogen (Nitrate) (mg/l)	0.01	0.18	0.40	0.44	0.25	0.22	0.05
Phosphorous (mg/l)	0.01	0.03	0.13	0.13	0.07	0.15	0.03
BOD ₅ (mg/l)	1	2.00	3.00	3.00	2.00	2.50	2.00
DO (mg/l)	0.01	8.03	8.44	8.09	6.11	7.18	8.49
Turbidity (NTU)	0.01	8.60	5.00	4.50	4.60	5.30	4.40
Temperature (oC)	0.1	16.5	16.7	17.3	18.6	17.8	16.9
pH	0.01	6.41	6.33	7.15	6.84	6.55	6.04
Salinity (ppt)	0.1	0.0	0.5	2.7	16.1	10.7	0.0
Conductivity (ms/m)	0.1	16.0	111.0	517.0	2660.0	1880.0	6500.0
Water Flow (m/s)	N/A	0.053	0.01	0.075	0.01	0.03	0

Table 6.10 Baseline Results of Ecological water quality monitoring

Parameters	WE1	WE2	WE3	WE4	WE5	WE6
Suspended Solid (mg/l)	1.0	2.0	3.0	3.0	<1	<1
Nitrogen (Ammonia) (mg/l)	0.07	0.12	0.11	0.23	0.03	0.02
Nitrogen (Nitrate) (mg/l)	0.12	0.13	0.13	0.31	0.04	0.05
Phosphorous (mg/l)	0.04	0.06	0.06	0.09	0.06	0.05
BOD ₅ (mg/l)	<2	<2	<2	<2	<2	<2
DO (mg/l)	6.58	6.82	6.37	7.61	6.87	5.70
Turbidity (NTU)	4.44	5.12	5.93	6.96	4.65	2.73
pH	6.4	7.1	7.0	6.8	6.6	6.1
Salinity (ppt)	<0.1	0.1	0.3	7.6	0.1	<0.1

6.6 Action and Limit level for Monitoring of White-shouldered Starlings

A simple Event and Action Plan is shown in Table 6.6.1. Should the Event occur, action in accordance with the Action Plan should be carried out.

There was no recorded event in the reporting month.

Table 6.6.1 Event / Action Plan for Monitoring of White-shouldered Starlings

EVENT	ACTION	
	ET Leader	Contractor
Identification of disturbance to breeding White-shouldered Starlings	1. Increase frequency of monitoring to twice weekly	1. Check all construction actions and working methods
	2. Notify Site Engineer	2. Submit proposals for remedial action to prevent abandonment of the breeding site.
	3. Review construction activities of previous week.	3. Implement remedial action.
	4. Identify any changes in construction activities in previous week	4. Liaise with ET regarding effectiveness of remedial actions.
	5. Discuss remedial actions with Site Engineer	

6.7 Ecological monitoring Schedule

The next ecological surveys are scheduled on 9th and 17th April, while ecological water quality monitoring is scheduled on 9th April.

7. Action taken in Event of Exceedence

If the measurements (Noise, Water, Ecology) exceed the action / limit level, exceedance details will be reported and follow-up actions will be taken by relevant parties involved.

During the reporting period there was no exceedance for noise, ecological measurements recorded; therefore no actions were taken.

Non-compliance of water quality limits (turbidity and/or suspended solids) were recorded on 2, 3, 4, 6, 16, 17 and 27 March according to the established level. ET has arranged site investigations for the exceedance events and causes were substantially attributable to:

- Site water discharged into the down stream area from project site (construction of gabion walls at bottleneck A of TTT River);
- Influx of marine water at the confluence of LTT, TTT, PNH River, and Silver River;
- Clearance works to the river channel carried out at the upper stream area of TTT River by the other project; and
- Water quality changes due to rainstorm.

The summary of non-compliance is listed in Table 7.1 for reference.

ET increased the monitoring frequency to daily basis until no exceedance of Limit level; at the mean time contractor was also urged to conduct necessary mitigation measures so as to keep the disturbance on water quality to minimal levels.

Table 7.1 Summary of Non-compliance for Water Quality

Date	Location	Parameter	Level of exceedance	Main cause of exceedance
02/03/2009	M2	Turbidity	Limit Level	Silty water discharged from project site
03/03/2009	M2	Turbidity	Limit Level	Silty water discharged from project site
03/03/2009	M2	D.O.	Action Level	Disturbance of marine water
04/03/2009	M1	D.O.	Action Level	Disturbance of marine water
04/03/2009	M2	Turbidity	Limit Level	Disturbance of marine water
04/03/2009	M2	D.O.	Action Level	Disturbance of marine water
04/03/2009	M3	D.O.	Action Level	Disturbance of marine water
04/03/2009	M4	D.O.	Action Level	Disturbance of marine water
06/03/2009	M1	Turbidity	Limit Level	Heavy rainstorm
06/03/2009	M2	Turbidity	Limit Level	Heavy rainstorm
06/03/2009	M4	Turbidity	Action Level	Heavy rainstorm
16/03/2009	M2	Turbidity	Action Level	Channel clearance works at upper stream area
17/03/2009	M2	Turbidity	Limit Level	Channel clearance works at upper stream area
27/03/2009	M2	Turbidity	Action Level	Silty water discharged from project site

8. Construction waste disposal

It is the contractor's responsibility to ensure that all wastes produced during the construction phase for the drainage improvement works are handled, stored and disposed of in accordance with good waste management practices and EPD's regulation and requirement. Waste materials generated during construction activities, such as construction and demolition (C&D) material, chemical wastes and general refuse, are recommended to be audited at regular intervals to ensure that proper storage, transportation and disposal practices are being implemented.

Contractor has completed the registration of Waste Producer under the Waste Disposal (Chemical Waste)(General) Regulation. The Waste Producer Number, WPN 5213-950-Y2443-03 was assigned by EPD on 12 Aug 2008. The Contractor would be responsible for the implementation of any mitigation measure to minimize waste or redress problems arising from the waste materials.

Table 8.1 is a summary of updated figures of the construction wastes disposal provided by the Contractor.

Table 8.1 Summary of Construction Waste Disposal

Month	Amount of Construction Waste disposed		
	Inert Waste (to Public Fill)	Non-inert Waste (to Landfill)	Chemical Waste (to treatment plant)
1 st March, 09 to 31 st March 09	22.38 (ton)	59.54 (ton)	Nil
Total (from June 08 to March 09)	8878.79 (ton)	64.76 (ton)	0

9. Status of Permits and Licenses obtained

Table 9.1 is the updated status of environmental related permits/ license obtained for the construction activities

Table 9 .1 Status of Permits and Licenses Obtained

Description	License / Permit No.#	Date of Issue	Date of Expiry	Remarks
Environmental Permit	EP-237/2005/A	05 Mar 2008	--	Issued
Registration of C&D Waste Producer	7006521	--	--	Issued
Chemical Waste Producer	5213-950-Y2443-03	12 Aug 2008	--	Issued
Construction Noise Permit	N/A	N/A	N/A	N/A
Effluent Discharge License	EP890/W2/XG032 EP890/W2/XG033 EP890/W2/XG034 EP890/W2/XG035 EP890/W2/XG036 EP890/W2/XG037 EP890/W2/XG038 EP890/W2/XG039 EP890/W2/XG040 EP890/W2/XG041	23 Oct 2008	31 Oct 2013	Issued

The contractor implemented various environmental mitigation measures as recommended in the Environmental Permit and Final Mitigation Measures Report. The implemented schedule is presented in appendix H.

10. Complaint Log

There was no formal complaint received during the reporting month.

	Noise	Water	Ecology	Cultural	Others
March 2009	0	0	0	0	0
Total	0	0	0	0	0

11. Site Environmental Audits

11.1 Site Inspection

With an intention to ensure that appropriate environmental protection and pollution control mitigation measures are properly implemented, regular environmental site inspections have been scheduled.

Within the reporting month, site inspections were conducted on 5, 12, 20 and 26 of March.

A detailed checklist of each site inspection together with comments, relevant photos and maps have been filed and kept. A summary of observation and follow-up action is shown in table 11.1

Date	Observations	Advice from ET	Action taken	Closing Date
26 Feb 09	Construction wastes were found stored outside of the site boundary at LTT	Contractor was advised to assign a waste storage area at LTT bypass channel for waste collection and segregation	Wastes have been removed as advised	5 Mar 09
26 Feb 09	Vehicle was found leaving the site of LTT without washing	Contractor was reminded to always wash their vehicles when leaving site to avoid bringing any earth materials to the public road	Contractor has reminded their drivers for washing their vehicles every time when leaving site	Ongoing
26 Feb 09	General wastes were found trapped in the U-channel at the LTT site entrance	Contractor should remove the wastes in the U-channel and provide a proper covering to avoid blockage of public drain	Wastes trapped in the U-channel were removed as advised	12 Mar 09
5 Mar 09	High jet water sprayer and wheel washing bay were not available at the site entrance of TTT River for vehicle washing	Contractor was advised to provide such facilities as soon as possible	High jet water sprayer was provided in the next inspection	12 Mar 09
5 Mar 09	Muddy water surface runoff was found discharged to the down	Contractor was urged to provide proper mitigation measures and	Coverings with geo-textile have been provided to the earth	20 Mar 09

Table 11.1 Summary of site inspection

Date	Observations	Advice from ET	Action taken	Closing Date
	stream area from site	remedial actions to avoid deterioration of water quality	surfaces exposed to the river stream. Enclosed dry section has been formed for further construction works in the channel	
5 Mar 09	Falling leaves and stagnant water were found accumulated in the wheel washing bay, located at the site entrance of PNH BC9	Contractor was advised to clean up the wheel washing bay regularly (daily cleaning is preferable)	To be follow up	Ongoing
12 Mar 09	General wastes were poorly dumped at the site area of PNH BC9-12	Contractor was reminded to store the waste in the assigned storage area in proper manner	Wastes has been removed by regular cleaning	20 Mar 09
12 Mar 09	Site water was found diverted to the upper ground at TTT bottleneck A for soak-away	Contractor was reminded diverted site water might affect the nearby premises. Soak-away pond should be prevented in that area	Use of soak-away pond has been stopped as advised	20 Mar 09
12 Mar 09	Pile of vegetative wastes were found dumped on top of the retained topsoil stored at LTT	Contractor was advised to removed the vegetative wastes from the turf as soon as possible to avoid mixing up	Wastes has been removed as advised	20 Mar 09
20 Mar 09	Underground water was found accumulated at the excavated site area PNH BC2, 3, 11 and 12	Contractor was advised to remove the stagnant water on site as far as practicable, or provide larvicide for mosquito control	Underground water has been pumped to site surface regularly as dust suppression measures	Ongoing
20 Mar 09	Wood board coverings to the public drainage at the site entrance of PNH were found damaged	Contractor was advised to replace the damaged coverings with durable material (such as steel plates)	Still outstanding. To be follow up	Ongoing
26 Mar 09	Open stockpile and exposed earth surfaces were observed at the bottleneck A of TTT River	Contractor was advised to removed the open stockpile and provided proper coverings to the earth surfaces exposed to river stream	To be follow up	Ongoing

11.2 Compliance with legal and Contractual requirement

ET leader has reviewed the progress and programme of the works to check any relevant environmental laws has not violated.

A non-compliance of working programme that caused discharge of muddy water to the down stream area of TTT River was recorded in this reporting month. River diversion and construction activities carried out at bottleneck A of TTT River might not fully comply with the conditions of “Measures to Mitigate Water Quality Impact” stated in EP.

Following the several exceedance events of water quality criteria recorded at the early of March and the issue of a warning letter to the contractor by EPD regarding their concern on improper containment measures for river-based construction works in TTT River after their inspection on 7th March, an ad-hoc site investigation and meeting were held among representatives of DSD, IEC, Contractor and ET on 9th March to resolve the incident.

As the investigation showed exposed earth surfaces caused surface runoff and soil erosion thus affected the down stream area, contractor was urged to take remedial actions and provide necessary mitigation measures to prevent further deterioration of water quality.

Contractor implemented remedial actions and mitigation measures progressively that include provision of geo-textile materials as coverings to the exposed earth surfaces and temporary river channel, and completion of earth bunds to form an enclosed site area for further works. In addition, silty water on site was pumped to silt retention pond at the upper ground for soak-away.

ET seriously reminded the Contractor to be cautious on the requirements stated in relevant environmental law and documents and manage good site practices so as to minimize impacts to the environment as well as sensitive receivers.

11.3 Environmental Complaint and follow up actions

During this reporting period, there was no documented complaint received. Therefore, follow up actions for the Environmental Complaint is not required

12. Future key issues

Key construction activity in the coming month will include construction of box culvert at PNH River and retaining walls at the bottleneck B of TTT River. It is expected that several impacts on environmental aspects will be generated on-site. With reference to the EM&A manual, mitigation measure report as well as the environmental permit, proper mitigation measures are proposed to be taken, if necessary.

Contractor was reminded to provide proper measures to mitigate water quality impacts to the river channels due to construction works. River based construction activities should be carried out in enclosed as well as dry condition to prevent discharge of site water to the stream; containment measures such as bunds and barriers should be provided as to restrict the carrying out of construction works within enclosed dry area of the river.

Underground water and site water may be accumulated on site. Contractor is recommended to treat the accumulated site water by proper silt removal facilities before discharging to the designated stormwater drainage; also reuse of site water should be considerable.

Contractor was reminded to be cautious on erosion and surface run-off from the stockpiles of earth materials and exposed earth surfaces. Coverings with tarpaulin and/or geo-textile materials should be provided to minimize the concerned impacts.

Dust impact may be resulted by boulder movement, breaking and installation works of gabion blocks, contractor is reminded to provide regular watering to the dusty static site area and stockpile. Meanwhile, size and height of stockpiles should be controlled as such erosion issue could be minimized.

13. Conclusions

In this reporting month, Construction work of box culvert at PNH, excavation and installation works for gabion blocks for LTT bypass channel were carried out.

Regular site meetings and inspection audits led by the seniors for discussing site environmental matters were held among Project Proponent, Contractor and the ET on weekly basis. Also monthly site meeting and inspection audits with the above parties and IEC were carried out at the mid of the reporting month.

For noise level monitoring, all results were within the established A/L limits.

For water quality monitoring, non-compliance events of water quality criteria were recorded on 2, 3, 4, 6, 16, 17 and 27 March. Exceedance were mainly caused by site water discharge and influx of marine water from silver bay. According to the monthly ecological water monitoring results performed on 09 March 2009, measurements recorded in the monitoring locations were found similar with past months.

During ecological monitoring survey, no White-shouldered Starling was recorded breeding in the watch tower. There was no sign of disturbance from the Project to the watch tower. The breeding season of White-shouldered Starling in this year has begun. However, the absence of nesting of White-shouldered Starling in the watch tower did not seem to be related to construction works in Luk Tei Tong River. A bird species nests in village house should be to certain extent disturbance tolerant.

No bird was observed entering the watchtower since the monitoring surveys commenced in August 2008. Also, no breeding was recorded in the baseline survey in September 2007. It appears that the birds do not prefer to roost or nest in the watch tower.

Also, there were not any notifications of summons recorded during the reporting period. Furthermore, there were not any formal prosecution and complaints recorded.

Containment measures for river based construction activities and mitigation measures to control surface runoff and soil erosion were the major concerns in this reporting month. Contractor was urged to enhance their measures provided and improve their site practices in order to minimize impacts to the river streams.

ET has reminded the contractor to provide environmental pollution control measures wherever necessary; and to keep a good environmental management at site practice.

The ET will continue to implement the environmental monitoring & audit programme in accordance with the EM&A Manual and Environmental Permit requirement.

Appendix A

Construction

Programmer and

Location plan

NOTES:

- 1. GRID LINES ARE IN METERS
- 2. ALL LEVELS ARE IN METERS AND REFERRED TO MSL+0.0



DATE	1998
SCALE	1:1
PROJECT	PRELIMINARY
DATE	1998
SCALE	1:1
PROJECT	PRELIMINARY
DATE	1998
SCALE	1:1
PROJECT	PRELIMINARY
DATE	1998
SCALE	1:1
PROJECT	PRELIMINARY

LOCATION PLAN OF THE PROJECT

Mercator & Eddy Ltd
測量師行有限公司



NOTES :

1. ALL LEVELS ARE IN METRES ABOVE P.D.H.K.1.
2. ALL GRIDS REFER TO HONG KONG 1980 GRID.

LEGENDS :

- SITE BOUNDARIES
- ▨ PORTION D1 - PAK NGAM BEIANG
- ▧ PORTION D2 - LING TSUI TAI LAI
- ▩ PORTION D3 - LING TSUI TAI (B)
- PORTION D4 - TAI TEI TONG RIVER
- PORTION D5 - LUK TEI TONG
- ▬ PORTION D6 - FUU O
- ▭ PORTION D7 - LO UK TSEEN
- ▮ PORTION D8 - CHEUNG SHA SHEUNG YEGHEN
- ▯ PORTION D9 - EMERGENCY VEHICULAR ACCESS (EVA) AT 10/10

FOR TENDER PURPOSES ONLY

DESIGNED BY	H. T. CHAN	DATE	12 FEB 2006
DRAWN BY	B. D. CHAN	DATE	23 MAR 2006
CHECKED BY	W. H. CHAN	DATE	10 MAY 2007
VERTICALS BY	T. Y. CHAN	DATE	11 MAY 2007
APPROVED BY			

DESIGNED BY: H. T. CHAN 12 FEB 2006
 DRAWN BY: B. D. CHAN 23 MAR 2006
 CHECKED BY: W. H. CHAN 10 MAY 2007
 VERTICALS BY: T. Y. CHAN 11 MAY 2007



CONTRACT NO: DC/2006/11
 FILE NO: DP/06/4128CD
 PROJECT NO: 128CD
 CONTRACT:

DRAINAGE IMPROVEMENT IN
 SOUTHERN LANTAU

DRAWING TITLE:
 PORTIONS OF SITE
 - SOUTHERN LANTAU

SCALE: 1 : 2000
 SHEET NO: DDN/128CD2/1002A

COPYRIGHT RESERVED
 OFFICE: DRAINAGE PROJECTS DIVISION



Comments: 1. Proposed drainage channel / pipe at 10/10. 2. Proposed drainage channel / pipe at 10/10. 3. Proposed drainage channel / pipe at 10/10. 4. Proposed drainage channel / pipe at 10/10. 5. Proposed drainage channel / pipe at 10/10. 6. Proposed drainage channel / pipe at 10/10. 7. Proposed drainage channel / pipe at 10/10. 8. Proposed drainage channel / pipe at 10/10. 9. Proposed drainage channel / pipe at 10/10. 10. Proposed drainage channel / pipe at 10/10. 11. Proposed drainage channel / pipe at 10/10. 12. Proposed drainage channel / pipe at 10/10. 13. Proposed drainage channel / pipe at 10/10. 14. Proposed drainage channel / pipe at 10/10. 15. Proposed drainage channel / pipe at 10/10. 16. Proposed drainage channel / pipe at 10/10. 17. Proposed drainage channel / pipe at 10/10. 18. Proposed drainage channel / pipe at 10/10. 19. Proposed drainage channel / pipe at 10/10. 20. Proposed drainage channel / pipe at 10/10. 21. Proposed drainage channel / pipe at 10/10. 22. Proposed drainage channel / pipe at 10/10. 23. Proposed drainage channel / pipe at 10/10. 24. Proposed drainage channel / pipe at 10/10. 25. Proposed drainage channel / pipe at 10/10. 26. Proposed drainage channel / pipe at 10/10. 27. Proposed drainage channel / pipe at 10/10. 28. Proposed drainage channel / pipe at 10/10. 29. Proposed drainage channel / pipe at 10/10. 30. Proposed drainage channel / pipe at 10/10. 31. Proposed drainage channel / pipe at 10/10. 32. Proposed drainage channel / pipe at 10/10. 33. Proposed drainage channel / pipe at 10/10. 34. Proposed drainage channel / pipe at 10/10. 35. Proposed drainage channel / pipe at 10/10. 36. Proposed drainage channel / pipe at 10/10. 37. Proposed drainage channel / pipe at 10/10. 38. Proposed drainage channel / pipe at 10/10. 39. Proposed drainage channel / pipe at 10/10. 40. Proposed drainage channel / pipe at 10/10. 41. Proposed drainage channel / pipe at 10/10. 42. Proposed drainage channel / pipe at 10/10. 43. Proposed drainage channel / pipe at 10/10. 44. Proposed drainage channel / pipe at 10/10. 45. Proposed drainage channel / pipe at 10/10. 46. Proposed drainage channel / pipe at 10/10. 47. Proposed drainage channel / pipe at 10/10. 48. Proposed drainage channel / pipe at 10/10. 49. Proposed drainage channel / pipe at 10/10. 50. Proposed drainage channel / pipe at 10/10. 51. Proposed drainage channel / pipe at 10/10. 52. Proposed drainage channel / pipe at 10/10. 53. Proposed drainage channel / pipe at 10/10. 54. Proposed drainage channel / pipe at 10/10. 55. Proposed drainage channel / pipe at 10/10. 56. Proposed drainage channel / pipe at 10/10. 57. Proposed drainage channel / pipe at 10/10. 58. Proposed drainage channel / pipe at 10/10. 59. Proposed drainage channel / pipe at 10/10. 60. Proposed drainage channel / pipe at 10/10. 61. Proposed drainage channel / pipe at 10/10. 62. Proposed drainage channel / pipe at 10/10. 63. Proposed drainage channel / pipe at 10/10. 64. Proposed drainage channel / pipe at 10/10. 65. Proposed drainage channel / pipe at 10/10. 66. Proposed drainage channel / pipe at 10/10. 67. Proposed drainage channel / pipe at 10/10. 68. Proposed drainage channel / pipe at 10/10. 69. Proposed drainage channel / pipe at 10/10. 70. Proposed drainage channel / pipe at 10/10. 71. Proposed drainage channel / pipe at 10/10. 72. Proposed drainage channel / pipe at 10/10. 73. Proposed drainage channel / pipe at 10/10. 74. Proposed drainage channel / pipe at 10/10. 75. Proposed drainage channel / pipe at 10/10. 76. Proposed drainage channel / pipe at 10/10. 77. Proposed drainage channel / pipe at 10/10. 78. Proposed drainage channel / pipe at 10/10. 79. Proposed drainage channel / pipe at 10/10. 80. Proposed drainage channel / pipe at 10/10. 81. Proposed drainage channel / pipe at 10/10. 82. Proposed drainage channel / pipe at 10/10. 83. Proposed drainage channel / pipe at 10/10. 84. Proposed drainage channel / pipe at 10/10. 85. Proposed drainage channel / pipe at 10/10. 86. Proposed drainage channel / pipe at 10/10. 87. Proposed drainage channel / pipe at 10/10. 88. Proposed drainage channel / pipe at 10/10. 89. Proposed drainage channel / pipe at 10/10. 90. Proposed drainage channel / pipe at 10/10. 91. Proposed drainage channel / pipe at 10/10. 92. Proposed drainage channel / pipe at 10/10. 93. Proposed drainage channel / pipe at 10/10. 94. Proposed drainage channel / pipe at 10/10. 95. Proposed drainage channel / pipe at 10/10. 96. Proposed drainage channel / pipe at 10/10. 97. Proposed drainage channel / pipe at 10/10. 98. Proposed drainage channel / pipe at 10/10. 99. Proposed drainage channel / pipe at 10/10. 100. Proposed drainage channel / pipe at 10/10.

Appendix B Key Personal Contact information chart

Organization Name	Role	Title	Name	Telephone	Fax Number
Drainage Service Department	Project Proponent	Engineering Representative	Mr. Chan Wai Hong	2594 7464	2827 8700
Allied Environmental Consultants Limited	Independent Environmental Checker (IEC)	Principal Consultant	Ms. Claudine Lee	2815 7028	2815 5399
Yick-Hing Construction Company Limited	Main Contractor	Senior Project Manager	Mr. Liu Kai Choi	2394 4988	2787 4890
Environmental Pioneers & Solutions Limited	Environmental Team (ET)	Environmental Team Leader	Ms. Patricia Chung	2185 0123	2856 2010

Appendix C

Calibration Certificates for Measuring Equipments



Report for Calibration of Hand-held Water Quality Meter WQC-24

Calibration Reference No. : GCE/CAL/2009/MW/WQM/C1

Client : ENVIRONMENTAL PIONEER AND SOLUTION LIMITED

Equipment No. : WQC-24 Location : Mui Wo Site

Manufacturer : DKK-TOA Serial No.: 617892

Calibration Date : 26 to 28-02-2009 Due Date : 26-05-2009

Criterion: (Repeatability, Linearity)

- pH : Both within ± 0.05 pH
- Dissolved oxygen : Both within ± 0.1 mg/L
- Electric conductivity : Both within $\pm 1\%$ FS
- Turbidity : Repeatability : within $\pm 3\%$ FS
- Temperature : Repeatability $\pm 0.25^\circ\text{C}$; Linearity $\pm 0.5^\circ\text{C}$; (Ambient $5\sim 45^\circ\text{C}$)

Electric Conductivity (Salinity converted from EC):

(Reference : APHA 20ed 2510 B, ISO 7888 - 1985 (E) and DKK-TOA Hand-held Water Quality Meter WQC-24 Instruction Manual)

Concentration of KCl Standard Solution (M)	Reference conductivity value at 25.0 °C	Indicated value by meter	Linearity (R^2)
0	0.0 mS/m*	0.0 mS/m	0.9996
0.001	14.7 mS/m	14.5 mS/m	
0.005	71.8 mS/m	71.2 mS/m	
0.01	0.141 S/m	0.139 S/m	
0.05	0.667 S/m	0.664 S/m	
0.1	1.29 S/m	1.28 S/m	Acceptance Criterion
0.5	5.87 S/m	5.85 S/m	$R^2 > 0.995$
Repeatability	1 st time	0.00 , 5.85 S/m	-
	2 nd time	0.00 , 5.85 S/m	
	3 rd time	0.00 , 5.85 S/m	
	0.00 , 5.85 S/m	0.00 , 0.00	

* 1 S/m = 10^4 $\mu\text{mhos/cm}$ = 10^3 mS/m

Remark: For repeatability, the maximum difference from the average value of 3 measurements was taken.



Dissolved Oxygen:

(Reference : APHA 20ed 4500-O B&C, ISO 5814:1990(E) and DKK-TOA Hand-held Water Quality Meter WQC-24 Instruction Manual)

DO value evaluated by Iodometric Method (mg/L)	Indicated value by meter (mg/L)	Linearity (R^2)	
0.00	0.00	0.9997	
4.21	4.27		
6.42	6.56		
8.77	8.90		
10.52	10.64	Acceptance Criterion	
13.73	13.68	$R^2 > 0.995$	
Repeatability	1 st time	0.00 , 8.90	-
	2 nd time	0.00 , 8.91	
	3 rd time	0.00 , 8.88	
	0.00 , 8.77	0.00 , 0.03	

Remark: For repeatability, the maximum difference from the average value of 3 measurements was taken.

pH Value:

(Reference : APHA 20ed 4500-H⁺ B, ISO 10523:1994(E) and DKK-TOA Hand-held Water Quality Meter WQC-24 Instruction Manual)

Calibration pH buffer (25°C)	Input value (pH buffer) (25°C)	Indicated pH value by meter (25°C)	Linearity (R^2)
pH = 1.67	1.67	1.69	1.0000
pH = 6.86	4.00	4.02	
pH = 7.42	7.00	7.02	
pH = 9.18	10.00	10.05	Acceptance Criterion
pH = 12.45	12.45	12.50	$R^2 > 0.995$
Repeatability	1 st time	4.01 , 10.05	-
	2 nd time	4.01 , 10.05	
	3 rd time	4.01 , 10.04	
	pH 4.00 , 10.00	0.00 , 0.01	

Remark: For repeatability, the maximum difference from the average value of 3 measurements was taken.



Temperature:

(Reference : APHA 20ed 2550 B, In-house method and DKK-TOA Hand-held Water Quality Meter WQC-24 Instruction Manual)

Setting Temperature (°C)	Indicated value by meter (°C)		Linearity
5.0	5.2		R ² = 0.9998 And SD = ± 0.16°C
15.0	15.4		
25.0	25.5		
35.0	35.3		
45.0	45.2		Acceptance Criterion R ² > 0.995 and within ± 5°C
55.0	55.6		
Repeatability	1 st time	5.2 , 55.7	-
	2 nd time	5.2 , 55.6	
	3 rd time	5.1 , 55.5	
	5.0 , 55.0	0.1 , 0.2	

Remark: For repeatability, the maximum difference from the average value of 3 measurements was taken.


Turbidity:

(Reference : APHA 20ed 2130 B and DKK-TOA Hand-held Water Quality Meter WQC-24 Instruction Manual)

Formazin Standards (NTU)	Indicated value by meter (NTU)		Linearity (R ²)
0.0	0.2		1.0000
20.0	19.4		
100.0	102.3		
400.0	403.6		Acceptance Criterion R ² > 0.995
800.0	804.7		
Repeatability	1 st time	0.3 , 805.0	-
	2 nd time	0.3 , 804.7	
	3 rd time	0.3 , 804.6	
	0.0 , 800.0	0.0 , 0.4	

Remark: For repeatability, the maximum difference from the average value of 3 measurements was taken.

Comments : Pass, comply with the criteria.

Tested by : Ho Tin Kau Certified by : 
 Gu Chin
 Chemist

Checked by : Gu Chin Date : 28-2-2009



綜合試驗有限公司
SOILS & MATERIALS ENGINEERING CO., LTD.

G/F, 9/F, 12/F, 13/F. & 20/F, Leader Centre, 37 Wong Chuk Hang Road, Aberdeen, Hong Kong.
香港黃竹坑道37號利達中心地下, 9樓, 12樓, 13樓及20樓
E-mail: smec@cigismec.com Website: www.cigismec.com

Tel : (852) 2873 6860
Fax : (852) 2555 7533



CERTIFICATE OF CALIBRATION

D094

Certificate No.: 09CA0102 01-01 Page 1 of 2

Item tested

Description: Sound Level Meter (Type I) , Microphone
Manufacturer: ACO, Japan , ACO, Japan
Type/Model No.: 6224 , 7146
Serial/Equipment No.: 060166 , 34733
Adaptors used: - , -

Item submitted by

Customer Name: Geotechnics & Concrete Engineering (H.K.) Ltd.
Address of Customer: G/F., 6 Ko Shan Road, Hung Hom, Kowloon, Hong Kong
Request No.: -
Date of request: 30-12-2008

Date of test: 02-01-2009

Reference equipment used in the calibration

Description:	Model:	Serial No.	Expiry Date:	Traceable to:
Multi function sound calibrator	B&K 4226	2288444	11-01-2009	CIGISMEC
Signal generator	DS 360	33873	12-06-2009	CEPREI
Signal generator	DS 360	61227	18-07-2009	CEPREI

Ambient conditions

Temperature: 23 ± 2 °C
Relative humidity: 55 ± 15 %
Air pressure: 1010 ± 15 hPa

Test specifications

- 1, The Sound Level Meter has been calibrated in accordance with the requirements as specified in BS 7580: Part 1: 1997 and the lab calibration procedure SMTP004-CA-152.
- 2, The electrical tests were performed using an electrical signal substituted for the microphone which was removed and replaced by an equivalent capacitance within a tolerance of ±20%.
- 3, The acoustic calibration was performed using an B&K 4226 sound calibrator and corrections was applied for the difference between the free-field and pressure responses of the Sound Level Meter.

Test results

This is to certify that the Sound Level Meter conforms to BS 7580: Part 1: 1997 for the conditions under which the test was performed.

Details of the performed measurements are presented on page 2 of this certificate.


Actual Measurement data are documented on worksheets.

Approved Signatory:

Huang Jian Min/Feng Jun Qi

Date: 02-01-2009

Company Chop:



Comments: The results reported in this certificate refer to the condition of the instrument on the date of calibration and carry no implication regarding the long term stability of the instrument.



CERTIFICATE OF CALIBRATION

(Continuation Page)

D094

Certificate No.: 09CA0102 01-01

Page 2 of 2

1, Electrical Tests

The electrical tests were performed using an equivalent capacitance substituted for the microphone. The results are given in below with test status and the estimated uncertainties. The "Pass" means the result of the test is inside the tolerances stated in the test specifications. The "-" means the result of test is outside these tolerances.

Test:	Subtest:	Status:	Uncertainty (dB) / Coverage Factor	
Self-generated noise	A	Pass	0.3	
	C	Pass	1.0	2.1
	Lin	Pass	1.5	2.2
Linearity range for Leq	At reference range, Step 5 dB at 4 kHz	Pass	0.3	
	Reference SPL on all other ranges	Pass	0.3	
	2 dB below upper limit of each range	Pass	0.3	
	2 dB above lower limit of each range	Pass	0.3	
		Pass	0.3	
Linearity range for SPL	At reference range, Step 5 dB at 4 kHz	Pass	0.3	
	A	Pass	0.3	
	C	Pass	0.3	
Frequency weightings	Lin	Pass	0.3	
	Single Burst Fast	Pass	0.3	
	Single Burst Slow	Pass	0.3	
Time weightings	Single 100µs rectangular pulse	N/A	N/A	
Peak response	Crest factor of 3	Pass	0.3	
R.M.S. accuracy	Single burst 5 ms at 2000 Hz	Pass	0.3	
Time weighting I	Repeated at frequency of 100 Hz	Pass	0.3	
	1 ms burst duty factor 1/10 ³ at 4kHz	Pass	0.3	
Time averaging	1 ms burst duty factor 1/10 ⁴ at 4kHz	Pass	0.3	
	Single burst 10 ms at 4 kHz	Pass	0.4	
Pulse range	Single burst 10 ms at 4 kHz	Pass	0.4	
Sound exposure level	SPL	Pass	0.3	
Overload Indication	Leq	Pass	0.4	

2, Acoustic tests

The complete sound level meter was calibrated on the reference range using a B&K 4226 acoustic calibrator with 1000Hz and SPL 94 dB. The sensitivity of the sound level meter was adjusted. The test result at 125 Hz and 8000 Hz are given in below with test status and the estimated uncertainties.

Test:	Subtest	Status	Uncertainty (dB) / Coverage Factor	
Acoustic response	Weighting A at 125 Hz	Pass	0.3	
	Weighting A at 8000 Hz	Pass	0.5	

3, Response to associated sound calibrator

N/A

The uncertainties have been calculated in accordance with the ISO Publication "Guide to the expression of uncertainty in measurement", and gives an interval estimated to have a level of confidence of 95 %. A coverage factor of 2 is assumed unless explicitly stated.

- End -

Calibrated by: G.Y. Fung
Date: 02-01-2009

Checked by: 
Date: 02-01-2009

The standard(s) and equipment used in the calibration are traceable to national or international recognised standards and are calibrated on a schedule to maintain the required accuracy level.



綜合試驗有限公司
SOILS & MATERIALS ENGINEERING CO., LTD.

G/F, 9/F, 12/F, 13/F. & 20/F, Leader Centre, 37 Wong Chuk Hang Road, Aberdeen, Hong Kong.
香港黃竹坑道37號利達中心地下, 9樓, 12樓, 13樓及20樓
E-mail: smec@cigismec.com Website: www.cigismec.com

Tel : (852) 2873 6860
Fax : (852) 2555 7533



CERTIFICATE OF CALIBRATION

2095

Certificate No.: 09CA0102 01-02 Page: 1 of 2

Item tested

Description: Acoustical Calibrator (Class 1)
Manufacturer: Castle Group Ltd.
Type/Model No.: GA607
Serial/Equipment No.: 039543
Adaptors used: -

Item submitted by

Customer: Geotechnics & Concrete Engineering (H.K.) Ltd.
Address of Customer: G/F., 6 Ko Shan Road, Hung Hom, Kowloon, Hong Kong
Request No.: -
Date of request: 30-12-2008

Date of test: 02-01-2009

Reference equipment used in the calibration

Description:	Model:	Serial No.	Expiry Date:	Traceable to:
Lab standard microphone	B&K 4180	2412857	29-06-2009	SCL
Preamplifier	B&K 2673	2239857	02-12-2009	CEPREI
Measuring amplifier	B&K 2610	2346941	03-12-2009	CEPREI
Signal generator	DS 360	61227	18-07-2009	CEPREI
Digital multi-meter	34401A	US36087050	03-12-2009	CIGISMEC
Audio analyzer	8903B	GB41300350	27-11-2009	CEPREI
Universal counter	53132A	MY40003662	11-07-2009	CEPREI

Ambient conditions



Temperature: 22 ± 1 °C
Relative humidity: 55 ± 10 %
Air pressure: 1010 ± 15 hPa

Test specifications

- The Sound Calibrator has been calibrated in accordance with the requirements as specified in IEC 60942 1997 Annex B and the lab calibration procedure SMTP004-CA-156.
- The calibrator was tested with its axis vertical facing downwards at the specific frequency using insert voltage technique.
- The results are rounded to the nearest 0.01 dB and 0.1 Hz and have not been corrected for variations from a reference pressure of 1013.25 hectoPascals as the maker's information indicates that the instrument is insensitive to pressure changes.

Test results

Details of the performed measurements are presented on page 2 of this certificate.

Approved Signatory:  Date: 02-01-2009 Company Chop: 

Comments: The results reported in this certificate refer to the condition of the instrument on the date of calibration and carry no implication regarding the long-term stability of the instrument.



CERTIFICATE OF CALIBRATION

(Continuation Page)

2095

Certificate No.: 09CA0102 01-02

Page: 2 of 2

1, Measured Sound Pressure Level

The output Sound Pressure Level in the calibrator head was measured at the setting and frequency shown using a calibrated laboratory standard microphone and insert voltage technique. The results are given in below with the estimated uncertainties.

Frequency Shown Hz	Output Sound Pressure Level Setting dB	Measured Output Sound Pressure Level dB	Estimated Uncertainty dB
1000	94.00	94.30	0.1

(Output level in dB re 20 μ Pa)

2, Sound Pressure Level Stability - Short Term Fluctuations

The Short Term Fluctuations was determined by measuring the maximum and minimum of the fast weighted DC output of the B&K 2610 measuring amplifier over a 20 second time interval as required in the standard. The Short Term Fluctuation was found to be:

At 1000 Hz STF = 0.002 dB
Estimated uncertainty 0.005 dB

3, Actual Output Frequency

The determination of actual output frequency was made using a B&K 4180 microphone together with a B&K 2673 preamplifier connected to a B&K 2610 measuring amplifier. The AC output of the B&K 2610 was taken to an universal counter which was used to determine the frequency averaged over 20 second of operation as required by the standard. The actual output frequency at 1 KHz was:

At 1000 Hz Actual Frequency = 1000.0 Hz
Estimated uncertainty 0.1 Hz Coverage factor k = 2.2

4, Total Noise and Distortion

For the Total Noise and Distortion measurement, the unfiltered AC output of the B&K 2610 measuring amplifier was connected to an Agilent Type 8903 B distortion analyser. The TND result at 1 KHz was:

At 1000 Hz TND = 2.1%
Estimated uncertainty 0.7%

The uncertainties have been calculated in accordance with the ISO Publication "Guide to the expression of uncertainty in measurement", and gives an interval estimated to have a level of confidence of 95 %. A coverage factor of 2 is assumed unless explicitly stated.

- End -

Calibrated by: C.Y. Fung
Date: 02-01-2009

Checked by:
Date: 02-01-2009

The standard(s) and equipment used in the calibration are traceable to national or international recognised standards and are calibrated on a schedule to maintain the required accuracy level.

Appendix D1 Plant species recorded at Pak Ngan Heung River (N)

Species	Habit	Native	Relative	Occurrence	
			Abundance	PNH3	PNH4
<i>Acacia confusa</i>	tree	no	occasional		+
<i>Acorus gramineus</i>	herb	yes	scarce		+
<i>Acronychia pedunculata</i>	tree	yes	scarce		
<i>Alangium chinensis</i>	tree	yes	scarce		+
<i>Alocasia macrorrhiza</i>	herb	yes	occasional	+	+
<i>Aporosa dioica</i>	tree	yes	occasional	+	+
<i>Ardisia crenata</i>	shrub	yes	occasional	+	+
<i>Atalantia buxifolia</i>	tree	yes	scarce		+
<i>Bamboo</i>	herb	-	scarce	+	
<i>Bidens pilosa</i>	herb	no	scarce	+	
<i>Bischofia javanica</i>	herb	yes	scarce	+	
<i>Breynia fruticosa</i>	shrub	yes	scarce		+
<i>Bridelia tomentosa</i>	tree	yes	scarce		+
<i>Caryota mitis</i>	herb	yes	scarce		+
<i>Celtis sinensis</i>	tree	yes	occasional	+	+
<i>Celtis timorensis</i>	tree	yes	scarce		+
<i>Christella parasitica</i>	fern	yes	occasional	+	+
<i>Cleistocalyx operculata</i>	tree	yes	occasional	+	+
<i>Commelina sp.</i>	herb	yes	occasional	+	
<i>Conyza canadensis</i>	herb	no	scarce	+	+
<i>Cyperus sp.</i>	herb	-	scarce	+	
<i>Desmos chinensis</i>	shrub	yes	occasional	+	
<i>Dimocarpus longan</i>	tree	no	occasional		+
<i>Embelia ribes</i>	climber	yes	scarce		+
<i>Ficus hispida</i>	tree	yes	common	+	+
<i>Ficus superba</i>	tree	yes	occasional		+
<i>Garcinia oblongifolia</i>	tree	yes	occasional		+
<i>Glochidion puberum</i>	shrub	yes	scarce	+	
<i>Hedychium coronarium</i>	herb	no	scarce		+
<i>Leucaena leucocephala</i>	tree	no	scarce		+
<i>Liriope spicata</i>	herb	yes	scarce		+
<i>Litsea glutinosa</i>	tree	yes	occasional		+

Species	Habit	Native	Relative	Occurrence	
			Abundance	PNH3	PNH4
<i>Litsea rotundifolia</i>	shrub	yes	scarce	+	
<i>Ludwigia perennis</i>	herb	yes	occasional	+	
<i>Lygodium japonicum</i>	fern	yes	scarce	+	
<i>Macaranga tanarius</i>	tree	yes	occasional	+	+
<i>Maesa perlarius</i>	shrub	yes	scarce	+	
<i>Mallotus paniculatus</i>	tree	yes	scarce	+	
<i>Melastoma candidum</i>	shrub	yes	scarce		+
<i>Microcos paniculata</i>	tree	yes	scarce		+
<i>Microstegium ciliatum</i>	grass	yes	common	+	+
<i>Mikania micrantha</i>	climber	no	common	+	+
<i>Millettia nitida</i>	climber	yes	scarce	+	
<i>Mimosa pudica</i>	herb	yes	scarce	+	
<i>Murraya paniculata</i>	shrub	no	scarce	+	
<i>Musa paradisiaca</i>	tree	no	scarce	+	
<i>Oxalis corymbosa</i>	herb	yes	scarce		+
<i>Panicum maximum</i>	grass	no	common		+
<i>Phyllanthus urinaria</i>	herb	yes	scarce	+	+
<i>Plantago major</i>	herb	yes	scarce		+
<i>Pogonatherum crinitum</i>	grass	yes	scarce		+
<i>Polygonum barbatum</i>	herb	yes	scarce	+	
<i>Polygonum chinense</i>	herb	yes	occasional	+	
<i>Polygonum sp.</i>	herb	yes	scarce	+	
<i>Psychotria asiatica</i>	shrub	yes	common	+	+
<i>Pueraria phaseoloides</i>	climber	yes	occasional	+	+
<i>Sageretia thea</i>	climber	yes	occasional		+
<i>Schefflera heptaphylla</i>	tree	yes	scarce	+	+
<i>Sida rhombifolia</i>	herb	yes	scarce	+	+
<i>Solanum nigrum</i>	herb	no	scarce		+
<i>Sporobolus fertilis</i>	grass	yes	scarce		+
<i>Sterculia lanceolata</i>	tree	yes	common	+	+
<i>Syngonium podophyllum</i>	climber	no	occasional	+	
<i>Syzygium jambos</i>	tree	no	common	+	+
<i>Syzygium levinei</i>	tree	yes	scarce	+	
<i>Urena lobata</i>	herb	yes	scarce		+

			Relative	Occurrence	
Species	Habit	Native	Abundance	PNH3	PNH4
<i>Uvaria microcarpa</i>	shrub	yes	occasional		+
<i>Wedelia trilobata</i>	climber	no	scarce	+	
<i>Zanthoxylum avicennae</i>	tree	yes	scarce		+

Appendix D2 Plant species recorded at Pak Ngan Heung River (S)

Species	Habit	Native	Relative	Occurrence	
			Abundance	PNH1	PNH2
<i>Acacia confusa</i>	tree	no	occasional	+	
<i>Acanthus ilicifolius</i>	shrub	yes	scarce	+	
<i>Acrostichum aureum</i>	fern	yes	scarce	+	
<i>Celtis sinensis</i>	tree	yes	occasional	+	
<i>Clerodendrum inerme</i>	shrub	yes	occasional	+	
<i>Dendrotrophe frutescens</i>	climber	yes	scarce	+	
<i>Ficus microcarpa</i>	tree	yes	scarce		+
<i>Ficus superba</i>	tree	yes	occasional		+
<i>Ipomoea cairica</i>	climber	yes	occasional		+
<i>Kandelia obovata</i>	shrub	yes	scarce	+	
<i>Melaleuca quinquenervia</i>	tree	no	common	+	
<i>Morus alba</i>	tree	no	scarce		+
<i>Neyraudia reynaudiana</i>	grass	yes	occasional	+	
<i>Panicum maximum</i>	grass	no	common	+	+
<i>Phragmites karka</i>	grass	yes	occasional	+	
<i>Phyllanthus urinaria</i>	shrub	yes	common	+	+
<i>Sapium sebiferum</i>	tree	yes	occasional		+
<i>Wedelia triloba</i>	climber	no	occasional	+	+
<i>Wollastonia biflora</i>	climber	yes	occasional	+	

Appendix D3 Plant species recorded at Luk Tei Tong River

Species	Habit	Native	Relative	Occurrence				
			Abundance	LLT1	LLT2	LLT3	LLT4	LLT5
<i>Acanthus ilicifolius</i>	shrub	yes	common	+	+			
<i>Aegiceras corniculatum</i>	shrub	yes	scarce	+	+			
<i>Bougainvillea spectabilis</i>	climber	no	scarce	+				
<i>Bridelia tomentosa</i>	tree	yes	occasional		+			
<i>Celtis sinensis</i>	tree	yes	scarce	+	+	+		
<i>Clerodendrum inerme</i>	shrub	yes	abundant	+	+		+	
<i>Cyperus malaccensis</i>	sedge	yes	occasional		+			
<i>Excoecaria agallocha</i>	shrub	yes	common	+	+			
<i>Ficus microcarpa</i>	tree	yes	scarce			+		
<i>Ficus superba</i>	tree	yes	occasional	+				
<i>Fimbristylis ferruginea</i>	sedge	yes	occasional		+		+	
<i>Hibiscus tiliaceus</i>	tree	yes	abundant	+	+		+	
<i>Kandelia obovata</i>	tree	yes	common	+	+			
<i>Leucaena leucocephala</i>	tree	no	occasional	+				
<i>Litsea glutinosa</i>	tree	yes	scarce		+	+		
<i>Neyraudia reynaudiana</i>	grass	yes	occasional	+			+	+
<i>Panicum maximum</i>	grass	no	common	+		+		
<i>Paspalum paspaloides</i>	grass	no	occasional		+			
<i>Premna serratifolia</i>	tree	yes	scarce		+			
<i>Saccharum arundinaceum</i>	grass	yes	scarce	+				
<i>Scolopia chinensis</i>	tree	yes	scarce				+	
<i>Severinia buxifolia</i>	shrub	yes	scarce	+				
<i>Terminalia catappa</i>	tree	no	scarce		+			
<i>Toxocarpus wightianus</i>	climber	yes	scarce		+			
<i>Wikstroemia indica</i>	shrub	yes	scarce				+	
<i>Wollastonia biflora</i>	climber	yes	occasional	+	+			

Appendix D4


Ecological Water Monitoring Results (on-site measurements)

Environmental Pioneers & Solutions Limited
Ecological Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 2009/3/9

Weather Condition: Cloudy

Monitoring Location	WE1			WE2			WE3			WE4			WE5			WE6		
Time (hhmm)	1210			1200			1055			1115			1225			1220		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal		
Water Depth (m)	< 1			< 1			< 1			< 1			< 1			< 1		
pH value	6.41			6.33			7.15			6.84			6.55			6.04		
Temperature (oC)	16.5			16.7			17.3			18.6			17.8			16.9		
Salinity (ppt)	0.00			0.50			2.70			16.10			10.70			0.00		
Conductivity (ms/m)	16.0			111.0			517.0			2660.0			1880.0			6500.0		
Water flow (m/s)	0.053			0.010			0.075			0.010			0.030			0.000		
Turbidity (NTU)	8.6	8.6	Average	5.0	5.0	Average	4.5	4.5	Average	4.6	4.6	Average	5.3	5.3	Average	4.4	4.4	Average
			8.60						5.00						4.50			
DO (mg/l)	8.03	8.03	Average	8.44	8.44	Average	8.09	8.09	Average	6.11	6.11	Average	7.18	7.18	Average	8.49	8.49	Average
			8.03			8.44			8.09			6.11			7.18			8.49
DO Saturation (%)	83	83	Average	88	88	Average	86	86	Average	72	72	Average	77	77	Average	90	90	Average
			83			88			86			72			77			90

Prepared By: Jimmy Cheng  Date: 2009/3/9 remark or observation: _____

Appendix D5

Ecological Water Monitoring Results (lab report)



TEST SUMMARY ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC090300076 Date of Issue : 16-03-2009

Client* : Environmental Pioneers & Solutions Limited Date Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 09-03-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 10-03-2009

GCE Serial No. : WQM032009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	502	495	1.4	26.6
Acceptance Criteria			< 2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ± 5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	WE1	WE1 Duplicate	WE2	WE2 Duplicate	WE3	WE3 Duplicate		
	Sampling Date/Time	09 Mar 2009 / 12:10		09 Mar 2009 / 12:00		09 Mar 2009 / 10:55			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	1.2	1.1	2.3	2.2	4.4	3.9	

TEST RESULTS	Sample ID	WE4	WE4 Duplicate	WE5	WE5 Duplicate	WE6	WE6 Duplicate		
	Sampling Date/Time	09 Mar 2009 / 11:15		09 Mar 2009 / 12:25		09 Mar 2009 / 12:20			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	9.7	9.3	11.3	10.9	< 1.0	1.1	

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : Location M1 & WE3 and Location M3 & WE4 are the same location.

----- End -----

Tested By : K.L FONG

Approved Signatory : 

Checked By : GU CHIN

Name : GU CHIN

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Page 1 of 1

Report No. : GCC090300157

Date of Issue : 28-03-2009

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008
 Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of
 Project* : Mui Wo Village Sewerage Phase 1
 Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 09-03-2009
 W.O. No.* : -- Contract No.* : -- Date Completed : 23-03-2009
 GCE Serial No. : WQM032009 Sampling Date* : 09-03-2009 / 12:10 Sample Type* : River Water
 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE1
 Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	0.28
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.18
Phosphorus mg/L	APHA 20ed 4500-P D	0.03
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	2
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--

* : Information provided by client


Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 March 2009.

REMARKS : Sample Location WE1.

----- End -----

Tested By : T.W. Lam, K.L. Fong

Certified By : 
 Name : Gu Chin

Checked By : Gu Chin

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Page 1 of 1

Report No. : GCC090300165

Date of Issue : 28-03-2009

Client* : Environmental Pioneers & Solutions Limited

Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon.

Date Started : 09-03-2009

W.O. No.* : --

Contract No.* : --

Date Completed : 23-03-2009

GCE Serial No. : WQM032009

Sampling Date* : 09-03-2009 / 12:10

Sample Type* : River Water

GCE Reg. No. : GCE 081096

Test Unit No. : CH 08258

Sample I.D.* : WE1 Duplicate

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	0.27
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.18
Phosphorus mg/L	APHA 20ed 4500-P D	0.03
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	2
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 March 2009.

REMARKS : Sample Location WE1.

----- End -----

Tested By : T.W. Lam, K.L. Fong

Certified By : 

Name : Gu Chin

Checked By : Gu Chin

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Page 1 of 1

Report No. : GCC090300173

Date of Issue : 28-03-2009

Client* : Environmental Pioneers & Solutions Limited

Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon.

Date Started : 09-03-2009

W.O. No.* : --

Contract No.* : --

Date Completed : 23-03-2009

GCE Serial No. : WQM032009

Sampling Date* : 09-03-2009 / 12:00

Sample Type* : River Water

GCE Reg. No. : GCE 081096

Test Unit No. : CH 08258

Sample I.D.* : WE2

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	0.62
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.40
Phosphorus mg/L	APHA 20ed 4500-P D	0.13
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	3
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 March 2009.

REMARKS : Sample Location WE2.

----- End -----

Tested By : T.W. Lam, K.L. Fong

Certified By : 

Name : Gu Chin

Checked By : Gu Chin

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Page 1 of 1

Report No. : GCC090300181

Date of Issue : 28-03-2009

Client* : Environmental Pioneers & Solutions Limited

Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon.

Date Started : 09-03-2009

W.O. No.* : --

Contract No.* : --

Date Completed : 23-03-2009

GCE Serial No. : WQM032009

Sampling Date* : 09-03-2009 / 12:00

Sample Type* : River Water

GCE Reg. No. : GCE 081096

Test Unit No. : CH 08258

Sample I.D.* : WE2 Duplicate

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	0.61
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.40
Phosphorus mg/L	APHA 20ed 4500-P D	0.12
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	3
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 March 2009.

REMARKS : Sample Location WE2.

----- End -----

Tested By : T.W. Lam, K.L. Fong

Certified By : 

Name : Gu Chin

Checked By : Gu Chin

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Page 1 of 1

Report No. : GCC090300199

Date of Issue : 28-03-2009

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 09-03-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 23-03-2009

GCE Serial No. : WQM032009 Sampling Date* : 09-03-2009 / 10:55 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE3

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	0.61
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.44
Phosphorus mg/L	APHA 20ed 4500-P D	0.13
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	3
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 March 2009.

REMARKS : Sample Location WE3.

----- End -----

Tested By : T.W. Lam, K.L. Fong

Certified By : 

Name : Gu Chin

Checked By : Gu Chin

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Page 1 of 1

Report No. : GCC090300204

Date of Issue : 28-03-2009

Client* : Environmental Pioneers & Solutions Limited

Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon.

Date Started : 09-03-2009

W.O. No.* : --

Contract No.* : --

Date Completed : 23-03-2009

GCE Serial No. : WQM032009

Sampling Date* : 09-03-2009 / 10:55

Sample Type* : River Water

GCE Reg. No. : GCE 081096

Test Unit No. : CH 08258

Sample I.D.* : WE3 Duplicate

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	0.60
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.43
Phosphorus mg/L	APHA 20ed 4500-P D	0.13
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	3
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 March 2009.

REMARKS : Sample Location WE3.

----- End -----

Tested By : T.W. Lam, K.L. Fong

Certified By :

Name

Gu Chin

Checked By : Gu Chin

Post

Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Report No. : GCC090300212

Date of Issue : 28-03-2009

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008
 Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of
 Project* : Mui Wo Village Sewerage Phase 1
 Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 09-03-2009
 W.O. No.* : -- Contract No.* : -- Date Completed : 23-03-2009
 GCE Serial No. : WQM032009 Sampling Date* : 09-03-2009 / 11:15 Sample Type* : River Water
 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE4
 Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	0.47
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.24
Phosphorus mg/L	APHA 20ed 4500-P D	0.06
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	2
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--

* : Information provided by client


Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 March 2009.

REMARKS : Sample Location WE4.

----- End -----

Tested By : T.W. Lam, K.L. Fong

Certified By : 
 Name : Gu Chin

Checked By : Gu Chin

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Page 1 of 1

Report No. : GCC090300220

Date of Issue : 28-03-2009

Client* : Environmental Pioneers & Solutions Limited

Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon.

Date Started : 09-03-2009

W.O. No.* : --

Contract No.* : --

Date Completed : 23-03-2009

GCE Serial No. : WQM032009

Sampling Date* : 09-03-2009 / 11:15

Sample Type* : River Water

GCE Reg. No. : GCE 081096

Test Unit No. : CH 08258

Sample I.D.* : WE4 Duplicate

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	0.46
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.25
Phosphorus mg/L	APHA 20ed 4500-P D	0.07
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	2
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 March 2009.

REMARKS : Sample Location WE4.

----- End -----

Tested By : T.W. Lam, K.L. Fong

Certified By : 

Name : Gu Chin

Checked By : Gu Chin

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Page 1 of 1

Report No. : GCC090300238

Date of Issue : 28-03-2009

Client* : Environmental Pioneers & Solutions Limited

Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon.

Date Started : 09-03-2009

W.O. No.* : --

Contract No.* : --

Date Completed : 23-03-2009

GCE Serial No. : WQM032009

Sampling Date* : 09-03-2009 / 12:25

Sample Type* : River Water

GCE Reg. No. : GCE 081096

Test Unit No. : CH 08258

Sample I.D.* : WE5

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	1.22
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.22
Phosphorus mg/L	APHA 20ed 4500-P D	0.15
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	2
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 March 2009.

REMARKS : Sample Location WE5.

----- End -----

Tested By : T.W. Lam, K.L. Fong

Certified By

Name

Gu Chin

Checked By : Gu Chin

Post

Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Page 1 of 1

Report No. : GCC090300246 Date of Issue : 28-03-2009

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 09-03-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 23-03-2009

GCE Serial No. : WQM032009 Sampling Date* : 09-03-2009 / 12:25 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE5 Duplicate

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	1.23
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.22
Phosphorus mg/L	APHA 20ed 4500-P D	0.14
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	3
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--


* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 March 2009.

REMARKS : Sample Location WE5.

----- End -----

Tested By : T.W. Lam, K.L. Fong Certified By : 
 Name : Gu Chin
 Checked By : Gu Chin Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Page 1 of 1

Report No. : GCC090300254 Date of Issue : 28-03-2009

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 09-03-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 23-03-2009

GCE Serial No. : WQM032009 Sampling Date* : 09-03-2009 / 12:20 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE6

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	0.15
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.05
Phosphorus mg/L	APHA 20ed 4500-P D	0.03
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	2
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--


* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 March 2009.

REMARKS : Sample Location WE6.

----- End -----

Tested By : T.W. Lam, K.L. Fong Certified By : 
 Name : Gu Chin
 Checked By : Gu Chin Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Report No. : GCC090300262 Date of Issue : 28-03-2009

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 09-03-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 23-03-2009

GCE Serial No. : WQM032009 Sampling Date* : 09-03-2009 / 12:20 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE6 Duplicate

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	0.15
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.05
Phosphorus mg/L	APHA 20ed 4500-P D	0.03
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	2
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--


* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 March 2009.

REMARKS : Sample Location WE6.

---- End ----

Tested By : T.W. Lam, K.L. Fong Certified By : 
 Name : Gu Chin
 Checked By : Gu Chin Post : Chemist

Appendix E

Construction Noise Monitoring Data Sheet



大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N1	N2
Description of Location		Façade	Façade
Date of Monitoring		2009/3/2	
Measurement Start Time (hhmm)		13:00	13:35
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		SVAN 949	
Calibrator Model/ Identification		SVAN SV 30A	
Wind Speed (m/s)		0.5	0.9
Measurement Results	L90 (dB(A))	38.2	46.6
	L10 (dB(A))	45.9	50.3
	Leq (dB(A))	44.8	49.7
Weather condition:		Sunny	
Major Construction Noise Source(s) During Monitoring		No construction works are being carried out during measurement.	1. House keeping noise 2. Power Generator noise
Other Noise Source(s) During Monitoring			1. Public noise
Remarks			

Name & Designation

Signature

Date:

Prepared by:

Jimmy Cheng

2009/3/2



大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N3	N4
Description of Location		Freefield	Façade
Date of Monitoring		2009/3/2	
Measurement Start Time	(hhmm)	11:15	10:40
Measurement Time Length		30 mins	
Noise Meter Model/ Identification		SVAN 949	
Calibrator Model/ Identification		SVAN SV 30A	
Wind Speed		(m/s)	0.6
Measurement Results	L90	(dB(A))	39.1
	L10	(dB(A))	42.8
	Leq	(dB(A))	52.5
Weather condition:		Sunny	
Major Construction Noise Source(s) During Monitoring		1. Excavator noise	No construction works are being carried out during measurement.
Other Noise Source(s) During Monitoring		1. Public noise 2. Traffic noise (bicycle)	1. Public noise
Remarks			

Name & Designation

Signature

Date:

Prepared by:

Jimmy Cheng

2009/3/2



大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N1	N2
Description of Location		Façade	Façade
Date of Monitoring		2009/3/9	
Measurement Start Time (hhmm)		15:15	15:53
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		SVAN 949	
Calibrator Model/ Identification		SVAN SV 30A	
Wind Speed (m/s)		0.3	1.1
Measurement Results	L90 (dB(A))	38.8	53.3
	L10 (dB(A))	45.9	61.2
	Leq (dB(A))	45.2	57.8
Weather condition:		Sunny	
Major Construction Noise Source(s) During Monitoring		No construction works are being carried out during measurement.	1. Cutting machine noise 2. Power generator noise 3. Hammer noise
Other Noise Source(s) During Monitoring			1. Public noise
Remarks			


Name & Designation

Signature

Date:

Prepared by:

Jimmy Cheng



2009/3/9



大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N3	N4
Description of Location		Freefield	Façade
Date of Monitoring		2009/3/9	
Measurement Start Time (hhmm)		14:40	14:08
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		SVAN 949	
Calibrator Model/ Identification		SVAN SV 30A	
Wind Speed (m/s)		0.9	0.7
Measurement Results	L90 (dB(A))	42.1	41.5
	L10 (dB(A))	47.0	50.5
	Leq (dB(A))	45.1	49.9
Weather condition:		Sunny	
Major Construction Noise Source(s) During Monitoring		No construction works are being carried out during measurement.	No construction works are being carried out during measurement.
Other Noise Source(s) During Monitoring		1. Public noise 2. Traffic noise	1. Helicopter noise 2. Public noise
Remarks			

Name & Designation

Signature

Date:

Prepared by:

Jimmy Cheng

2009/3/9



大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N1	N2
Description of Location		Façade	Façade
Date of Monitoring		2009/3/16	
Measurement Start Time (hhmm)		15:20	14:45
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		SVAN 949	
Calibrator Model/ Identification		SVAN SV 30A	
Wind Speed (m/s)		0.2	0.8
Measurement Results	L90 (dB(A))	42.0	45.8
	L10 (dB(A))	50.2	58.1
	Leq (dB(A))	48.3	57.9
Weather condition:		Sunny	
Major Construction Noise Source(s) During Monitoring		No construction works are being carried out during measurement.	1. Construction truck 2. House keeping 3. Hammer noise
Other Noise Source(s) During Monitoring			1. Public noise
Remarks			

Name & Designation

Signature

Date:

Prepared by:

Jimmy Cheng

2009/3/16



大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N3	N4
Description of Location		Freefield	Façade
Date of Monitoring		2009/3/16	
Measurement Start Time (hhmm)		14:05	13:30
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		SVAN 949	
Calibrator Model/ Identification		SVAN SV 30A	
Wind Speed (m/s)		0.7	0.4
Measurement Results	L90 (dB(A))	44.8	42.9
	L10 (dB(A))	54.4	53.3
	Leq (dB(A))	51.9	50.4
Weather condition:		Sunny	
Major Construction Noise Source(s) During Monitoring		1. Excavator noise	No construction works are being carried out during measurement.
Other Noise Source(s) During Monitoring		1. Public noise 2. Traffic noise (bicycle)	1. Public noise
Remarks			

Name & Designation

Signature

Date:

Prepared by:

Jimmy Cheng



2009/3/16



大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N1	N2
Description of Location		Façade	Façade
Date of Monitoring		2009/3/23	
Measurement Start Time (hhmm)		15:00	14:25
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		SVAN 949	
Calibrator Model/ Identification		SVAN SV 30A	
Wind Speed (m/s)		0.4	0.3
Measurement Results	L90 (dB(A))	42.7	60.6
	L10 (dB(A))	48.9	65.6
	Leq (dB(A))	46.6	63.6
Weather condition:		Sunny	
Major Construction Noise Source(s) During Monitoring		No construction works are being carried out during measurement.	1. Power Generator Noise 2. Water Gum Noise
Other Noise Source(s) During Monitoring			1. Public Noise
Remarks			

Name & Designation

Signature

Date:

Prepared by:

Jimmy Cheng

2009/3/23



大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N3	N4
Description of Location		Freefield	Façade
Date of Monitoring		2009/3/23	
Measurement Start Time (hhmm)		13:50	13:15
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		SVAN 949	
Calibrator Model/ Identification		SVAN SV 30A	
Wind Speed (m/s)		0.8	0.4
Measurement Results	L90 (dB(A))	41.8	46.9
	L10 (dB(A))	52.0	56.1
	Leq (dB(A))	65.4	54.5
Weather condition:		Sunny	
Major Construction Noise Source(s) During Monitoring		1. Excavator noise	No construction works are being carried out during measurement.
Other Noise Source(s) During Monitoring		1. Public noise 2. Traffic noise (bicycle)	1. Public noise
Remarks			

Name & Designation

Signature

Date:

Prepared by:

Jimmy Cheng

2009/3/23



大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N1	N2
Description of Location		Façade	Façade
Date of Monitoring		2009/3/30	
Measurement Start Time (hhmm)		13:35	13:00
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		SVAN 949	
Calibrator Model/ Identification		SVAN SV 30A	
Wind Speed (m/s)		0.5	0.7
Measurement Results	L90 (dB(A))	41.5	49.1
	L10 (dB(A))	48.1	61.0
	Leq (dB(A))	46.7	58.7
Weather condition:		Sunny	
Major Construction Noise Source(s) During Monitoring		1. Excavator noise 2. Shoveling noise	1. Excavator noise 2. Hammer noise 3. Cutting machine noise
Other Noise Source(s) During Monitoring			1. Traffic Noise
Remarks			

Name & Designation

Signature

Date:

Prepared by:

Jimmy Cheng

2009/3/30



大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N3	N4
Description of Location		Freefield	Façade
Date of Monitoring		2009/3/30	
Measurement Start Time (hhmm)		10:40	11:15
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		SVAN 949	
Calibrator Model/ Identification		SVAN SV 30A	
Wind Speed (m/s)		0.9	1.1
Measurement Results	L90 (dB(A))	43.5	45.7
	L10 (dB(A))	52.1	51.5
	Leq (dB(A))	49.4	50.3
Weather condition:		Sunny	
Major Construction Noise Source(s) During Monitoring		No major construction works are being carried out during measurement.	No construction works are being carried out during measurement.
Other Noise Source(s) During Monitoring		1. Public noise 2. Traffic noise (bicycle)	1. Public noise 2. Dog barking noise
Remarks			

Name & Designation

Signature

Date:

Prepared by:

Jimmy Cheng

2009/3/30

Appendix F1

Water Quality

Monitoring Data Sheet

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 09/3/2

Cloudy

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1530			1525			1520			1540			1430			1440			1505		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			<1			<1			<1			<1			<1			<1		
pH value	7.83			7.85			7.75			7.82			6.11			5.86			6.48		
Temperature (oC)	20.5			20.7			20.9			20.5			20.2			20.5			20.7		
Salinity (ppt)	21.9			24.5			25.8			25.6			0.0			0.0			18.4		
Turbidity (NTU)	5.9	5.9	Average	7.7	7.7	Average	5.9	5.9	Average	6.6	6.6	Average	5.1	5.1	Average	3.5	3.5	Average	19.0	19.0	Average
			5.9			7.7			5.9			6.6			5.1			3.5			19.0
DO (mg/l)	7.91	7.91	Average	6.92	6.92	Average	7.38	7.38	Average	6.55	6.55	Average	6.96	6.96	Average	7.42	7.42	Average	5.69	5.69	Average
			7.91			6.92			7.38			6.55			6.96			7.42			5.69
DO Saturation (%)	90	90	Average	76	76	Average	83	83	Average	74	74	Average	77	77	Average	83	83	Average	70	70	Average
			90			76			83			74			77			83			70

Name
Prepared By: Jimmy Cheng

Signature


Date
09/3/2

remark or observation: _____

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 09/3/3

Cloudy

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1600			1550			1540			1610			1510			1520			1530		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	< 1			< 1			< 1			< 1			< 1			< 1			< 1		
pH value	6.23			7.70			7.51			7.79			7.17			6.51			6.98		
Temperature (oC)	20.1			20.4			20.6			20.8			19.7			20.1			20.4		
Salinity (ppt)	22.2			22.3			26.4			25.8			0.2			0.0			17.3		
Turbidity (NTU)	12.9	12.9	Average	11.9	11.9	Average	14.8	14.8	Average	14.9	14.9	Average	2.1	2.1	Average	0.7	0.7	Average	14.9	14.9	Average
			12.9			11.9			14.8			14.9			2.1			0.7			14.9
DO (mg/l)	5.96	5.96	Average	5.97	5.97	Average	5.96	5.96	Average	6.01	6.01	Average	7.97	7.97	Average	8.46	8.46	Average	4.76	4.76	Average
			5.96			5.97			5.96			6.01			7.97			8.46			4.76
DO Saturation (%)	76	76	Average	77	77	Average	77	77	Average	79	79	Average	89	89	Average	94	94	Average	63	63	Average
			76			77			77			79			89			94			63

Name
Prepared By: Jimmy Cheng

Signature


Date
09/3/3

remark or observation: _____

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 2009/3/4

Cloudy

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1715			1700			1705			1650			1635			1625			1610		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	< 1			< 1			< 1			1.7			< 1			< 1			< 1		
pH value	7.62			7.59			7.58			7.63			6.17			7.01			6.78		
Temperature (oC)	19.8			19.9			19.8			20.0			19.5			19.8			20.1		
Salinity (ppt)	25.2			22.4			25.1			26.8			0.0			0.0			21.1		
Turbidity (NTU)	7.1	7.1	Average	15.9	15.9	Average	5.2	5.2	Average	9.1	9.1	Average	3.8	3.8	Average	3.2	3.2	Average	13.3	13.3	Average
			7.1			15.9			5.2			9.1			3.8			3.2			13.3
DO (mg/l)	4.93	4.93	Average	5.44	5.44	Average	5.41	5.41	Average	4.99	4.99	Average	7.21	7.21	Average	7.06	7.06	Average	4.60	4.60	Average
			4.93			5.44			5.41			4.99			7.21			7.06			4.60
DO Saturation (%)	63	63	Average	68	68	Average	68	68	Average	64	64	Average	79	79	Average	78	78	Average	56	56	Average
			63			68			68			64			79			78			56

Name
Prepared By: Jimmy Cheng

Signature


Date
2009/3/4

remark or observation: _____

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 2009/3/6

Cloudy and rainy

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1550			1555			1602			1540						1615					
Tide Mode	flow			flow			flow			flow						flow					
River Condition	normal			normal			normal			normal						normal					
Water Depth (m)	<1			<1			<1			1.8						1.1					
pH value	7.57			7.26			7.78			7.93						7.11					
Temperature (oC)	18.2			18.3			18.9			19.3						18.4					
Salinity (ppt)	7.0			5.9			20.5			23.3						0.0					
Turbidity (NTU)	25.6	25.6	Average 25.6	14.9	14.9	Average 14.9	16.5	16.5	Average 16.5	17.5	17.5	Average 17.5			Average #DIV/0!	2.8	2.8	Average 2.8			Average #DIV/0!
DO (mg/l)	7.45	7.45	Average 7.45	7.53	7.53	Average 7.53	6.35	6.35	Average 6.35	6.23	6.23	Average 6.23			Average #DIV/0!	8.45	8.45	Average 8.45			Average #DIV/0!
DO Saturation (%)	83	83	Average 83	83	83	Average 83	77	77	Average 77	77	77	Average 77			Average #DIV/0!	91	91	Average 91			Average #DIV/0!

Name
Prepared By: Jimmy Cheng

Signature


Date
2009/3/6

remark or observation: _____

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 2009/3/9

Cloudy

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1055			1105			1115			1045			1210			1215			1225		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			<1			<1			1.1			<1			<1			<1		
pH value	7.15			6.80			6.84			7.70			6.42			6.03			6.56		
Temperature (oC)	17.3			17.6			18.6			18.1			16.5			17.8			17.9		
Salinity (ppt)	2.7			0.6			16.1			21.9			0.0			0.0			1.7		
Turbidity (NTU)	4.5	4.5	Average	2.9	2.9	Average	4.6	4.6	Average	5.9	5.9	Average	8.6	8.6	Average	1.1	1.1	Average	9.5	9.5	Average
			4.5			2.9			4.6			5.9			8.6			1.1			9.5
DO (mg/l)	8.09	8.09	Average	8.83	8.83	Average	6.11	6.11	Average	6.48	6.48	Average	8.04	8.04	Average	8.49	8.49	Average	4.34	4.34	Average
			8.09			8.83			6.11			6.48			8.04			8.49			4.34
DO Saturation (%)	86	86	Average	93	93	Average	72	72	Average	79	79	Average	83	83	Average	89	89	Average	44	44	Average
			86			93			72			79			83			89			44

Name
Prepared By: Jimmy Cheng

Signature


Date
2009/3/9

remark or observation: _____

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 2009/3/11

Cloudy

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1555			1548			1350			1309			1608			1615			1633		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	< 1			< 1			< 1			< 1			< 1			< 1			< 1		
pH value	6.93			7.14			6.69			7.53			6.53			6.13			6.27		
Temperature (oC)	20.0			20.1			20.7			19.9			19.1			19.9			20.0		
Salinity (ppt)	2.7			1.4			14.5			22.0			0.2			0.0			4.0		
Turbidity (NTU)	5.4	5.4	Average	2.7	2.7	Average	6.9	6.9	Average	7.2	7.2	Average	0.8	0.8	Average	0.0	0.0	Average	3.7	3.7	Average
			5.4			2.7			6.9			7.2			0.8			0.0			3.7
DO (mg/l)	8.30	8.30	Average	8.90	8.90	Average	6.46	6.46	Average	6.37	6.37	Average	7.13	7.13	Average	9.03	9.03	Average	5.73	5.73	Average
			8.30			8.90			6.46			6.37			7.13			9.03			5.73
DO Saturation (%)	93	93	Average	99	99	Average	78	78	Average	78	78	Average	77	77	Average	99	99	Average	66	66	Average
			93			99			78			78			77			99			66

Name
Prepared By: Jimmy Cheng

Signature


Date
2009/3/11

remark or observation: _____

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 2009/3/13 Sunny

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1330			1335			1345			1320			1350			1405			1420		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			<1			<1			1.1			<1			<1			<1		
pH value	7.34			7.34			6.94			7.69			6.75			6.25			6.38		
Temperature (oC)	22.7			22.8			23.6			22.4			22.7			22.0			23.0		
Salinity (ppt)	8.2			4.0			15.4			21.9			0.4			0.0			3.7		
Turbidity (NTU)	5.5	5.5	Average	4.5	4.5	Average	5.4	5.4	Average	5.1	5.1	Average	0.0	0.0	Average	0.0	0.0	Average	5.4	5.4	Average
			5.5			4.5			5.4			5.1			0.0			0.0			5.4
DO (mg/l)	8.37	8.37	Average	9.70	9.70	Average	7.65	7.65	Average	7.46	7.46	Average	7.63	7.63	Average	8.51	8.51	Average	5.91	5.91	Average
			8.37			9.70			7.65			7.46			7.63			8.51			5.91
DO Saturation (%)	102	102	Average	116	116	Average	98	98	Average	97	97	Average	89	89	Average	97	97	Average	70	70	Average
			102			116			98			97			89			97			70

Name
Prepared By: Jimmy Cheng

Signature


Date
2009/3/13

remark or observation: _____

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 2009/3/16 Sunny

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1627			1650			1645			1700			1540			1600			1615		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			<1			<1			1.2			<1			<1			<1		
pH value	7.55			7.44			6.96			7.96			5.68			5.74			6.47		
Temperature (oC)	23.2			22.8			23.9			22.2			22.6			22.6			21.6		
Salinity (ppt)	3.9			6.7			15.7			28.2			0.0			0.0			2.2		
Turbidity (NTU)	3.4	3.4	Average	6.2	6.2	Average	7.1	7.1	Average	13.0	13.0	Average	0.0	0.0	Average	329.6	329.6	Average	8.4	8.4	Average
			3.4			6.2			7.1			13.0			0.0			329.6			8.4
DO (mg/l)	9.64	9.64	Average	9.20	9.20	Average	7.97	7.97	Average	6.86	6.86	Average	8.02	8.02	Average	7.02	7.02	Average	4.25	4.25	Average
			9.64			9.20			7.97			6.86			8.02			7.02			4.25
DO Saturation (%)	118	118	Average	113	113	Average	106	106	Average	96	96	Average	93	93	Average	81	81	Average	48	48	Average
			118			113			106			96			93			81			48

Name
Prepared By: Jimmy Cheng

Signature


Date
2009/3/16

remark or
observation: _____

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 2009/3/17 Sunny

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1618			1610			1616			1625			1510			1521			1540		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			<1			<1			1.0			<1			<1			<1		
pH value	7.93			7.94			7.52			8.10			5.64			5.87			6.53		
Temperature (oC)	24.7			24.6			25.4			24.6			22.0			22.9			23.9		
Salinity (ppt)	9.9			4.7			18.8			23.6			0.0			0.0			2.8		
Turbidity (NTU)	11.8	11.8	Average	14.3	14.3	Average	9.3	9.3	9.3	9.2	9.2	Average	1.5	1.5	Average	8.5	8.5	Average	10.8	10.8	Average
			11.8			14.3			9.3			9.2			1.5			8.5			10.8
DO (mg/l)	10.01	10.01	Average	10.78	10.78	Average	9.12	9.12	9.12	8.85	8.85	Average	7.89	7.89	Average	6.31	6.31	Average	5.87	5.87	Average
			10.01			10.78			9.12			8.85			7.89			6.31			5.87
DO Saturation (%)	127	127	Average	134	134	Average	125	125	125	122	122	Average	91	91	Average	74	74	Average	72	72	Average
			127			134			125			122			91			74			72

Name
Prepared By: Jimmy Cheng

Signature


Date
2009/3/17

remark or observation: _____

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 2009/3/18 Sunny

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1620			1615			1610			1630			1515			1525			1545		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			<1			<1			1.2			<1			<1			<1		
pH value	7.75			7.21			7.70			8.10			5.39			5.86			6.54		
Temperature (oC)	26.2			26.1			26.1			24.9			22.9			24.6			24.4		
Salinity (ppt)	9.6			0.0			20.5			25.9			0.0			0.0			2.1		
Turbidity (NTU)	11.7	11.7	Average	3.9	3.9	Average	10.7	10.7	Average	7.8	7.8	Average	1.5	1.5	Average	9.8	9.8	Average	12.2	12.2	Average
			11.7			3.9			10.7			7.8			1.5			9.8			12.2
DO (mg/l)	10.54	10.54	Average	9.70	9.70	Average	8.81	8.81	Average	8.49	8.49	Average	9.62	9.62	Average	6.97	6.97	Average	4.78	4.78	Average
			10.54			9.70			8.81			8.49			9.62			6.97			4.78
DO Saturation (%)	137	137	Average	122	122	Average	125	125	Average	120	120	Average	84	84	Average	84	84	Average	58	58	Average
			137			122			125			120			84			84			58

Name
Prepared By: Jimmy Cheng

Signature


Date
2009/3/18

remark or observation: _____

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 2009/3/23 Rainy

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	940			945			950			1000			1015			1025			1040		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			<1			<1			1			<1			<1			<1		
pH value	6.88			6.94			6.63			7.90			6.51			6.16			6.65		
Temperature (oC)	23.7			23.3			23.8			23.4			23.5			23.5			23.9		
Salinity (ppt)	1.2			0.6			9.6			27.0			0.1			0.0			1.3		
Turbidity (NTU)	4.8	4.8	Average	3.8	3.8	Average	7.6	7.6	Average	8.4	8.4	Average	5.5	5.5	Average	1.5	1.5	Average	10.1	10.1	Average
			4.8			3.8			7.6			8.4			5.5			1.5			10.1
DO (mg/l)	6.50	6.50	Average	8.86	8.86	Average	6.67	6.67	Average	6.27	6.27	Average	6.24	6.24	Average	6.91	6.91	Average	3.74	3.74	Average
			6.50			8.86			6.67			6.27			6.24			6.91			3.74
DO Saturation (%)	75	75	Average	107	107	Average	75	75	Average	74	74	Average	73	73	Average	82	82	Average	45	45	Average
			75			107			75			74			73			82			45

Name
Prepared By: Jimmy Cheng

Signature


Date
2009/3/23

remark or observation: _____

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 2009/3/25 Rainy

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1045			1055			1105			1030			1120			1130			1145		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	< 1			< 1			< 1			< 1			< 1			< 1			< 1		
pH value	6.24			6.58			6.83			7.71			6.56			6.01			6.84		
Temperature (oC)	20.1			20.3			20.6			20.9			19.6			20.1			20.3		
Salinity (ppt)	1.4			1.4			12.8			19.1			0.0			0.0			1.5		
Turbidity (NTU)	7.4	7.4	Average	3.4	3.4	Average	4.3	4.3	Average	7.5	7.5	Average	3.7	3.7	Average	8.0	8.0	Average	6.9	6.9	Average
			7.4			3.4			4.3			7.5			3.7			8.0			6.9
DO (mg/l)	5.96	5.96	Average	7.28	7.28	Average	6.15	6.15	Average	6.03	6.03	Average	7.80	7.80	Average	7.47	7.47	Average	4.21	4.21	Average
			5.96			7.28			6.15			6.03			7.80			7.47			4.21
DO Saturation (%)	68	68	Average	80	80	Average	72	72	Average	70	70	Average	84	84	Average	81	81	Average	48	48	Average
			68			80			72			70			84			81			48

Name
Prepared By: Jimmy Cheng

Signature


Date
2009/3/25

remark or observation: _____

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 2009/3/27 Rainy

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1305			1315			1320			1250			1330			1340			1350		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	< 1			< 1			< 1			< 1			< 1			< 1			< 1		
pH value	6.87			6.77			6.63			6.58			6.64			5.74			6.24		
Temperature (oC)	20.1			20.6			20.7			19.1			19.6			20.8			20.6		
Salinity (ppt)	3.5			1.2			8.9			13.2			0.0			0.0			1.4		
Turbidity (NTU)	9.8	9.8	Average	6.6	6.6	Average	7.1	7.1	Average	7.4	7.4	Average	4.3	4.3	Average	7.2	7.2	Average	7.2	7.2	Average
			9.8			6.6			7.1			7.4			4.3			7.2			7.2
DO (mg/l)	7.33	7.33	Average	8.34	8.34	Average	6.23	6.23	Average	7.01	7.01	Average	7.26	7.26	Average	7.60	7.60	Average	4.19	4.19	Average
			7.33			8.34			6.23			7.01			7.26			7.60			4.19
DO Saturation (%)	83	83	Average	97	97	Average	75	75	Average	84	84	Average	81	81	Average	85	85	Average	48	48	Average
			83			97			75			84			81			85			48

Name
Prepared By: Jimmy Cheng

Signature


Date
2009/3/27

remark or observation: _____

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 2009/3/28 Cloudy

Monitoring Location	M1		M2		M3		M4		C1		C2		C3					
Time (hhmm)			1445								1430							
Tide Mode	mid-ebb		mid-ebb		mid-ebb		mid-ebb		mid-ebb		mid-ebb		mid-ebb					
River Condition	normal		normal		normal		normal		normal		normal		normal					
Water Depth (m)	< 1		< 1		< 1		< 1		< 1		< 1		< 1					
pH value			6.38								5.75							
Temperature (oC)			22.9								23.3							
Salinity (ppt)			0.0								0.0							
Turbidity (NTU)			Average	5.1	5.1	Average			Average			Average	4.8	4.8	Average			Average
			#DIV/0!			5.1		#DIV/0!		#DIV/0!		#DIV/0!		4.8		#DIV/0!		
DO (mg/l)			Average	8.38	8.38	Average			Average			Average	8.17	8.17	Average			Average
			#DIV/0!			8.38		#DIV/0!		#DIV/0!		#DIV/0!		8.17		#DIV/0!		
DO Saturation (%)			Average	98	98	Average			Average			Average	96	96	Average			Average
			#DIV/0!			98		#DIV/0!		#DIV/0!		#DIV/0!		96		#DIV/0!		

Name
Prepared By: Jimmy Cheng

Signature


Date
2009/3/28

remark or
observation: _____

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 2009/3/30 Sunny

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1510			1455			1502			1530			1420			1435			1445		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	< 1			< 1			< 1			1.2			< 1			< 1			< 1		
pH value	7.26			6.75			6.92			7.44			5.21			5.53			6.49		
Temperature (oC)	21.8			22.3			22.0			21.8			21.0			22.2			21.9		
Salinity (ppt)	14.6			0.1			17.4			19.4			0.0			0.0			9.9		
Turbidity (NTU)	5.3	5.3	Average	5.1	5.1	Average	7.8	7.8	Average	6.3	6.3	Average	0.5	0.5	Average	4.9	4.9	Average	7.1	7.1	Average
			5.3			5.1			7.8			6.3			0.5			4.9			7.1
DO (mg/l)	7.32	7.32	Average	8.63	8.63	Average	7.33	7.33	Average	7.47	7.47	Average	6.62	6.62	Average	8.03	8.03	Average	6.87	6.87	Average
			7.32			8.63			7.33			7.47			6.62			8.03			6.87
DO Saturation (%)	91	91	Average	100	100	Average	91	91	Average	95	95	Average	74	74	Average	93	93	Average	83	83	Average
			91			100			91			95			74			93			83

Name
Prepared By: Jimmy Cheng

Signature


Date
2009/3/30

remark or observation: _____

Appendix F2

Water Quality

Monitoring Lab report



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC090300018 Date of Issue : 09-03-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 02-03-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 03-03-2009

GCE Serial No. : WQM032009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	492	491	0.2	22.8
Acceptance Criteria			< 2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ± 5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	02 Mar 2009 / 14:30		02 Mar 2009 / 14:40		02 Mar 2009 / 15:05			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	2.5	2.7	< 1.0	< 1.0	13.2	12.7	

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	02 Mar 2009 / 15:30		02 Mar 2009 / 15:25		02 Mar 2009 / 15:20		02 Mar 2009 / 15:40	
	LOD	Units							
Suspended Solids (SS)	1	mg/L	7.1	6.6	5.0	5.4	8.4	8.8	9.6

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : _____

----- End -----

Tested By : K.L. FONG

Approved Signatory : 

Checked By : GU CHIN

Name : GU CHIN
 Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Page 1 of 1

Report No. : GCC090300026 Date of Issue : 09-03-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 04-03-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 05-03-2009

GCE Serial No. : WQM032009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	507	502	1.0	23.1
Acceptance Criteria			<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	03 Mar 2009 / 15:10		03 Mar 2009 / 15:20		03 Mar 2009 / 15:30			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	5.9	6.4	1.1	1.3	8.9	9.2	

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	03 Mar 2009 / 16:00		03 Mar 2009 / 15:50		03 Mar 2009 / 15:40		03 Mar 2009 / 16:10	
	LOD	Units							
Suspended Solids (SS)	1	mg/L	12.9	12.7	9.7	9.6	13.7	13.9	12.9

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : _____

---- End ----

Tested By : K.L. FONG

Approved Signatory : 

Name : GU CHIN

Checked By : GU CHIN

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC090300034 Date of Issue : 09-03-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 05-03-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 06-03-2009

GCE Serial No. : WQM032009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	501	495	1.2	25.6
Acceptance Criteria			< 2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ± 5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID		C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time		04 Mar 2009 / 16:35		04 Mar 2009 / 16:25		04 Mar 2009 / 16:10			
	LOD	Units								
Suspended Solids (SS)	1	mg/L	3.3	3.6	2.4	2.2	8.8	9.3		


TEST RESULTS	Sample ID		M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time		04 Mar 2009 / 17:15		04 Mar 2009 / 17:00		04 Mar 2009 / 17:05		04 Mar 2009 / 16:50	
	LOD	Units								
Suspended Solids (SS)	1	mg/L	9.8	10.2	11.3	11.2	8.9	9.1	9.0	9.4

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : _____

----- End -----

Tested By : K.L. FONG Approved Signatory : 
 Name : GU CHIN
 Checked By : GU CHIN Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Page 1 of 1

Report No. : GCC090300042 Date of Issue : 09-03-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 07-03-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 07-03-2009

GCE Serial No. : WQM032009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	493	497	-0.8	24.1
Acceptance Criteria			< 2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	06 Mar 2009 / 16:15							
	LOD	Units							
Suspended Solids (SS)	1	mg/L			< 1.0	< 1.0			

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	06 Mar 2009 / 17:00							
	LOD	Units							
Suspended Solids (SS)	1	mg/L			9.5	10.0			

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : _____

----- End -----

Tested By : K.L. FONG

Approved Signatory : 

Checked By : GU CHIN

Name : GU CHIN
 Post : Chemist



TEST SUMMARY ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Page 1 of 1

Report No. : GCC090300068 Date of Issue : 16-03-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 09-03-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 10-03-2009

GCE Serial No. : WQM032009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	502	495	1.4	26.6
Acceptance Criteria			< 2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ± 5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	09 Mar 2009 / 12:10		09 Mar 2009 / 12:15		09 Mar 2009 / 12:25			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	1.4	1.4	< 1.0	< 1.0	10.9	10.7	

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate	
	Sampling Date/Time	09 Mar 2009 / 10:55		09 Mar 2009 / 11:05		09 Mar 2009 / 11:15		09 Mar 2009 / 10:45		
	LOD	Units								
Suspended Solids (SS)	1	mg/L	4.4	3.9	1.1	1.4	9.7	9.3	8.0	7.8

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : Location M1 & WE3 and Location M3 & WE4 are the same location.

---- End ----

Tested By : K.L. FONG

Approved Signatory : 

Name : GU CHIN

Checked By : GU CHIN

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Page 1 of 1

Report No. : GCC090300084 Date of Issue : 16-03-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 11-03-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 12-03-2009

GCE Serial No. : WQM032009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	493	495	-0.4	23.7
Acceptance Criteria			< 2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	11 Mar 2009 / 16:08		11 Mar 2009 / 16:15		11 Mar 2009 / 16:33			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	2.1	1.6	< 1.0	< 1.0	9.6	9.9	

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	11 Mar 2009 / 15:55		11 Mar 2009 / 15:48		11 Mar 2009 / 13:50		11 Mar 2009 / 13:09	
	LOD	Units							
Suspended Solids (SS)	1	mg/L	5.3	5.7	1.9	1.6	6.1	6.3	13.1

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : _____

----- End -----

Tested By : K.L. FONG

Approved Signatory : 

Checked By : GU CHIN

Name : GU CHIN

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Page 1 of 1

Report No. : GCC090300092 Date of Issue : 16-03-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 13-03-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 14-03-2009

GCE Serial No. : WQM032009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	496	489	1.4	22.6
Acceptance Criteria			< 2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	13 Mar 2009 / 13:50		13 Mar 2009 / 14:05		13 Mar 2009 / 14:20			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	1.5	1.5	1.1	1.3	13.2	12.8	

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	13 Mar 2009 / 13:30		13 Mar 2009 / 13:35		13 Mar 2009 / 13:45		13 Mar 2009 / 13:20	
	LOD	Units							
Suspended Solids (SS)	1	mg/L	10.5	10.5	2.9	3.0	8.1	7.9	8.3

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : _____

----- End -----

Tested By : K.L. FONG

Approved Signatory : 

Checked By : GU CHIN

Name : GU CHIN

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Page 1 of 1

Report No. : GCC090300123 Date of Issue : 21-03-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 17-03-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 18-03-2009

GCE Serial No. : WQM032009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	508	504	0.8	25.8
Acceptance Criteria			< 2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	16 Mar 2009 / 15:15		16 Mar 2009 / 15:25		16 Mar 2009 / 15:45			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	< 1.0	1.0	214.4	216.4	11.2	10.9	


TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	16 Mar 2009 / 16:20		16 Mar 2009 / 16:15		16 Mar 2009 / 16:10		16 Mar 2009 / 16:30	
	LOD	Units							
Suspended Solids (SS)	1	mg/L	3.9	4.2	3.0	2.9	4.7	5.1	11.9

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : _____

----- End -----

Tested By : K.L. FONG Approved Signatory : 
 Name : GU CHIN
 Checked By : GU CHIN Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Page 1 of 1

Report No. : GCC090300131 Date of Issue : 21-03-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 18-03-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 19-03-2009

GCE Serial No. : WQM032009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	495	495	0.0	23.6
Acceptance Criteria			<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	17 Mar 2009 / 15:10		17 Mar 2009 / 15:21		17 Mar 2009 / 15:40			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	1.1	1.0	6.2	6.6	10.7	10.9	

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	17 Mar 2009 / 16:18		17 Mar 2009 / 16:10		17 Mar 2009 / 16:16		17 Mar 2009 / 16:25	
	LOD	Units							
Suspended Solids (SS)	1	mg/L	10.8	10.9	9.5	9.1	6.6	6.9	8.9

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks :

----- End -----

Tested By : K.L. FONG

Approved Signatory : 

Name : GU CHIN

Checked By : GU CHIN

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC090300149 Date of Issue : 21-03-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 19-03-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 20-03-2009

GCE Serial No. : WQM032009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	487	498	-2.2	27.5
Acceptance Criteria			<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID		C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time		18 Mar 2009 / 15:15		18 Mar 2009 / 15:25		18 Mar 2009 / 15:45			
	LOD	Units								
Suspended Solids (SS)	1	mg/L	< 1.0	< 1.0	6.1	5.7	11.9	12.4		

TEST RESULTS	Sample ID		M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time		18 Mar 2009 / 16:20		18 Mar 2009 / 16:15		18 Mar 2009 / 16:10		18 Mar 2009 / 16:30	
	LOD	Units								
Suspended Solids (SS)	1	mg/L	11.9	12.1	< 1.0	< 1.0	10.2	9.8	8.4	8.5

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : _____

----- End -----

Tested By : K.L. FONG

Approved Signatory : 

Name : GU CHIN

Checked By : GU CHIN

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Page 1 of 1

Report No. : GCC090300270 Date of Issue : 31-03-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 24-03-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 25-03-2009

GCE Serial No. : WQM032009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	486	504	-3.6	21.9
Acceptance Criteria			<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	23 Mar 2009 / 10:15		23 Mar 2009 / 10:25		23 Mar 2009 / 10:40			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	1.9	2.0	2.3	2.0	12.6	12.8	

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	23 Mar 2009 / 09:40		23 Mar 2009 / 09:45		23 Mar 2009 / 09:50		23 Mar 2009 / 10:00	
	LOD	Units							
Suspended Solids (SS)	1	mg/L	4.1	4.1	3.0	2.9	7.6	7.9	9.3

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : _____

----- End -----

Tested By : K.L. FONG

Approved Signatory : 

Checked By : GU CHIN

Name : GU CHIN
 Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Page 1 of 1

Report No. : GCC090300288 Date of Issue : 31-03-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 25-03-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 26-03-2009

GCE Serial No. : WQM032009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	497	485	2.4	25.4
Acceptance Criteria			< 2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ± 5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	25 Mar 2009 / 11:20		25 Mar 2009 / 11:30		25 Mar 2009 / 11:45			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	2.9	2.8	7.0	7.2	11.8	12.4	

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	25 Mar 2009 / 10:45		25 Mar 2009 / 10:55		25 Mar 2009 / 11:05		25 Mar 2009 / 10:30	
	LOD	Units							
Suspended Solids (SS)	1	mg/L	5.3	5.6	1.8	2.4	7.0	6.8	5.6

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks :

----- End -----

Tested By : K.L. FONG

Approved Signatory : 

Name : GU CHIN

Checked By : GU CHIN

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC090300296 Date of Issue : 31-03-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 28-03-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 30-03-2009

GCE Serial No. : WQM032009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	500	491	1.8	22.9
Acceptance Criteria			<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	27 Mar 2009 / 13:30		27 Mar 2009 / 13:40		27 Mar 2009 / 13:50			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	< 1.0	< 1.0	1.4	1.8	7.6	7.2	

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	27 Mar 2009 / 13:05		27 Mar 2009 / 13:15		27 Mar 2009 / 13:20		27 Mar 2009 / 12:50	
	LOD	Units							
Suspended Solids (SS)	1	mg/L	7.6	8.0	3.0	3.0	5.4	5.3	5.2

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : _____

----- End -----

Tested By : K.L. FONG

Approved Signatory : 

Name : GU CHIN

Checked By : GU CHIN

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Page 1 of 1

Report No. : GCC090300301 Date of Issue : 31-03-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 28-03-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 30-03-2009

GCE Serial No. : WQM032009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	500	491	1.8	22.9
Acceptance Criteria			< 2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate
	Sampling Date/Time	28 Mar 2009 / 14:30					
	LOD	Units					
Suspended Solids (SS)	1	mg/L		1.5	1.7		

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	28 Mar 2009 / 14:45							
	LOD	Units							
Suspended Solids (SS)	1	mg/L		3.0	2.7				

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks :

----- End -----

Tested By : K.L. FONG

Approved Signatory : 

Name : GU CHIN

Checked By : GU CHIN

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC090300319 Date of Issue : 01-04-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 31-03-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 01-04-2009

GCE Serial No. : WQM032009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	506	506	0.0	23.1
Acceptance Criteria			<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	30 Mar 2009 / 14:20		30 Mar 2009 / 14:35		30 Mar 2009 / 14:45			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	1.5	1.3	3.2	3.1	7.9	8.2	

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	30 Mar 2009 / 15:10		30 Mar 2009 / 14:55		30 Mar 2009 / 15:02		30 Mar 2009 / 15:30	
	LOD	Units							
Suspended Solids (SS)	1	mg/L	6.7	7.0	2.3	2.3	8.4	8.1	8.6

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : _____

----- End -----

Tested By : K.L. FONG

Approved Signatory : 

Name : GU CHIN

Checked By : GU CHIN

Post : Chemist

Appendix G
Monitoring Schedule
for March 2009

Environmental Pioneers and Solutions Limited

DC/2006/11 - DRAINAGE IMPROVEMENT IN SOUTHERN LANTAU

Master Schedule of EM&A works in March 2009

Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
3/1	3/2	3/3	3/4	3/5	3/6	3/7
	WQM at: 15:30 Noise Monitoring	WQM at: 16:14	WQM at: 16:55		Site Inspection	
3/8	3/9	3/10	3/11	3/12	3/13	3/14
	WQM, EWQM at: 10:18 Noise Monitoring		WQM at: 12:42 Eco Survey		WQM at: 13:44 Site Inspection	
3/15	3/16	3/17	3/18	3/19	3/20	3/21
	WQM at: 15:35 Noise Monitoring	WQM at: 16:07	WQM at: 16:53		Eco Survey Site Inspection	
3/22	3/23	3/24	3/25	3/26	3/27	3/28
	WQM at: 08:55 Noise Monitoring		WQM at: 10:11	Eco Survey	WQM at: 12:59 Site Inspection	
3/29	3/30	3/31				
	WQM at: 14:41 Noise Monitoring					

Noise Monitoring Locations: Total 4 Locations as N1, N2, N3 and N4

Water Quality Monitoring (WQM) Locations: Total 7 Locations as M1, M2, M3, M4, C1, C2 and C3

Ecological Water Quality Monitoring (EWQM) Locations: Total 6 Locations as WE1, WE2, WE3, WE4, WE5 and WE6

Appendix H Implementation Status of environmental protection / mitigation measures


Environmental Aspect	Protection / Mitigation Measures	Implementation status	Follow-up action
Air Quality	Use of regular watering to reduce dust emissions from exposed site surfaces and unpaved road, with complete coverage.	Implemented	-
	Use of frequent watering for particular dusty static construction areas and areas close to ASRs.	Implemented	-
	Tarpaulin covering of all dusty vehicle loads transported to and from and between site location;	Implemented	-
	Establishment and use of vehicle wheel and body washing facilities at the exit points of the site.	Implemented	-
	Routing of vehicles and positioning of construction plant should be at the maximum possible distance from ASRs.	Implemented	-
Noise	Use of quiet powered mechanical equipment (PME)	Implemented	-
	Adoption of movable noise barriers and temporary noise barriers	Not applicable at this stage	-
	Application of good site practices mentioned in EM&A manual Clause 3.8.1	Implemented	-
Water Quality	Before commencing any site formation works, all sewer and drainage connections should be sealed to prevent debris, soil, sand etc. from entering public sewers/drains.	Implemented	-
	Temporary ditches should be provided to facilitate run-off discharge into appropriate watercourses, via a silt retention pond. No site run-off should enter the freshwater marshes at Luk Tei Tong.	Not applicable	-
	Sand/ silt removal facilities such as sand traps, silt traps and sediment basins should be provided to remove sand/ silt particles from runoff to meet the requirements of the Technical Memorandum standard under the Water Pollution Control Ordinance.	Implemented by natural soak-away at site ground	-
	Water pumped out from foundation excavations should be discharged into silt removal facilities.	Implemented by natural soak-away at site ground	-
	During rainstorms, exposed slope surface should be covered by a tarpaulin or the means.	Deficiencies were found on 7 th March	Geo-textile materials were then provided to the exposed slope surface and earth bunds
	Exposed soil areas should be minimized to reduce potential for increased siltation and contamination of runoff.	Implemented	-
	Exposed soil surfaces should be protected by paving or fill material as soon as possible to reduce potential of soil erosion.	Implemented	-
	Open stockpiles of construction materials or construction wastes on-site of more than 50m ³ should be covered with tarpaulin or similar fabric during rainstorms.	Implemented	-
	Oils and fuels should only be used and stored on designated areas which have pollution prevention facilities.	Implemented	-
	Temporary sanitary facilities, such as portable chemical toilets, should be employed on-site.	Not applicable	-

Environmental Aspect	Protection / Mitigation Measures	Implementation status	Follow-up action
	The excavation and widening works for the drainage improvements to the Pak Ngan Heung River, Tai Tei Tong River, Luk Tei Tong River and Luk Tei Tong By-pass Channel should be carried out in sections (approximately 300 –400 m in length) and in dry condition.	Deficiencies were found on 7 th March	Earth bunds were then formed to be an enclosed section for site works
	Maintenance desilting of the re-profiled river channels of the Pak Ngan Heung River, Tai Tei Tong River, Luk Tei tong River and Luk Tei Tong By-pass Channel, temporary barrier walls should be used to provide a dry zone for desilting work.	Not applicable at this stage	-
Ecology	Existing natural habitats should be retained as far as practicable	Implemented	-
	Boundary of working areas should be identified to prevent loss of vegetation	Implemented	-
	All existing trees / plant should be well protected within the site or transplanted properly	Implemented	-
	Turf removal from the Luk Tei Tong marsh due to the construction of Luk Tei Tong Bypass Channel shall be minimized	Implemented	-
	Turf from the Luk Tei Tong marsh shall be properly removed, stored, maintained and reused for lining the riverbed of the Luk Tei Tong Bypass Channel	Implemented	-
Chemical and Solid Waste	Chemical wastes should be properly stored in a proper store as per statutory requirements (i.e. on a hard standing, within an enclosed and locked area)	Implemented	-
	Chemical waste stores should be provided with fire precaution facilities (i.e. fire extinguisher, no smoking warning etc).	Implemented	-
	Chemical wastes should be properly stored in corrosion resistant containers placed inside the store and labelled with warning signs in English and Chinese.	Implemented	-
	Chemical wastes should be disposed of by licensed chemical waste collector with supporting delivery records.	Implemented	-
	All containers for fuel, diesel and fluid chemical (in use) and oil filled stationery plants located with proper drip pans.	Implemented	-
	Construction wastes should be managed and disposed to the designated public fill and landfill areas in acceptable manner.	Implemented	-
	All waste disposals managed in a proper manner i.e. trip ticket system implementation.	Implemented	-


Appendix I

Graphical plot of water
quality monitoring
results (SS, DO,
turbidity)

Graphical Plot of Turbidity Trend M1&C1 (Dec 08-Mar 09)




Graphical Plot of Turbidity Trend M2&C2 (Dec 08-Mar 09)




Remarks: The reading of C2 on Mar 16th 2009 is 329.6, which was over the range of the plot.


Graphical Plot of Turbidity Trend M3&C3 (Dec 08-Mar 09)




Graphical Plot of Turbidity Trend M4 (Dec 08-Mar 09)




Graphical Plot of Dissolved Oxygen Trend M1&C1 (Dec 08-Mar 09)




Graphical Plot of Dissolved Oxygen Trend M2&C2 (Dec 08-Mar 09)




Graphical Plot of Dissolved Oxygen Trend M3&C3 (Dec 08-Mar 09)




Graphical Plot of Dissolved Oxygen Trend M4 (Dec 08-Mar 09)



Graphical Plot of Suspended Soild M1&C1 (Dec 08 - Mar 09)




Graphical Plot of Suspended Soild M2&C2 (Dec 08 - Mar 09)




Remarks: The reading of C2 on Mar 16th 2009 is 215.4, which was over the range of the plot.

Graphical Plot of Suspended Soild M3&C3 (Dec 08 - Mar 09)



Graphical Plot of Suspended Soild M4 (Dec 08 - Mar 09)



Appendix J

Graphical plot of noise
monitoring results

