

Drainage Service Department

Monthly Environmental Monitoring & Auditing report for

Contract No.DC/2006/11

Drainage Improvement in Southern Lantau

April 2009

Revision 1

Environmental Pioneers & Solutions Limited

8/F, Chaiwan Industrial Centre Building

20 Lee Chung Street, Chaiwan, Hong Kong

Tel: 2889 0568

Fax: 2856 2010

APPROVAL SHEET

Prepared and Certified by: ET Leader (Environmental Pioneers & Solutions Limited)

Signature: _____
Miss Patricia Chung
(ET* Leader)

Date: _____

Signature: _____
Mr. Vincent Lai
(Ecologist)

Date: _____

* ET – Environmental Team

TABLE of CONTENT

TABLE of CONTENT	ii
EXECUTIVE SUMMARY	iv
1. Introduction	1
2. Project Information	1
2.1 Construction program	1
2.2 Project Organization	1
2.3 Key Personal Contact information chart	2
3. Construction Stage	3
3.1 Construction Activities in the reporting month	3
3.2 Construction Activities for the coming month	3
3.3 Environmental Status	3
4. Noise Monitoring	4
4.1 Monitoring Parameters and Methodology	4
4.2 Monitoring Equipment	4
4.3 Monitoring Locations	4
4.4 Monitoring Results and Interpretation	7
4.5 Action and Limit level for Construction noise	7
4.6 Noise Mitigation Measures	9
5. Water Monitoring	10
5.1 Water Quality Monitoring Parameters and methodology	10
5.2 Monitoring Equipment	10
5.3 Monitoring Locations	11
5.4 Monitoring Frequency	13
5.5 Monitoring Results and Interpretation	13
5.6 Action and limit level for Water Quality	15
5.7 Water Quality Mitigation Measures	17
5.8 Water Monitoring Schedule for the Next reporting period	17
6. Ecology Monitoring	18
6.1 Ecological Monitoring Parameters	18
6.2 Monitoring Equipment and Methodology	19
6.3 Monitoring Locations	20
6.4 Monitoring Frequency	23
6.5 Monitoring results	23
6.6 Action and Limit level for Monitoring of White-shouldered Starlings	34

6.7	Ecological monitoring Schedule	34
7.	Action taken in Event of Exceedence	35
8.	Construction waste disposal.....	37
9.	Status of Permits and Licenses obtained.....	38
10.	Complaint Log	38
11.	Site Environmental Audits	39
11.1	Site Inspection.....	39
11.2	Compliance with legal and Contractual requirement.....	41
11.3	Environmental Complaint and follow up actions.....	41
12.	Future key issues.....	42
13.	Conclusions.....	43

APPENDIXES

Appendix A	Construction Programme and location plan
Appendix B	Key Personal Contact information chart
Appendix C	Calibration Certificates for measuring instruments
Appendix D1	Plant species recorded at Pak Ngan Heung River (N)
Appendix D2	Plant species recorded at Pak Ngan Heung River (S)
Appendix D3	Plant species recorded at Luk Tei Tong River
Appendix D4	Ecological Water Monitoring results (on-site measurement)
Appendix D5	Ecological Water Monitoring results (lab-report)
Appendix E	Construction Noise Monitoring Data Sheet
Appendix F1	Water Quality Monitoring Data Sheet
Appendix F2	Water Quality Monitoring Lab report
Appendix G	Monitoring Schedule for April 2009
Appendix H	Implementation status of environmental protection / mitigation measures
Appendix I	Graphical plot of water quality monitoring results (SS, DO, turbidity)
Appendix J	Graphical plot of noise monitoring results

EXECUTIVE SUMMARY

This is the ninth monthly environmental Monitoring and audit (EM&A) report for “Drainage Improvement in Southern Lantau Investigation”. The environmental permit number is “EP-237/2005/A”. The report concludes the impact monitoring for the activities undertaken during the period of 1st April 2009 to 30th April 2009. The major activities in this reporting month include construction works of box culvert at Pak Ngan Heung (PNH) River, box culvert at Luk Tei Tong (LTT), gabion walls Tai Tei Tong (TTT) River as well as U-channel at Ling Tsui Tau.

Noise, water quality and ecological monitoring were performed. Results obtained were checked against the previously established Action / Limit (A/L) levels. Additionally, the implementation status of environmental mitigation measures, event/ action plan and environmental complaint handling procedures were inspected during weekly site environmental audit.

In general, waste management was satisfactory during the reporting month.

Impact monitoring for construction noise was conducted in the reporting period. No exceedance of A/L level was reported.

Furthermore, impact monitoring for water quality was conducted. Non-compliance events of water quality criteria were recorded on 1, 2, 6, 17, 22, 24, 27, 28 and 29 April. Exceedances were caused by several reasons including inadequate runoffs control, site water discharge by the other project, influx of marine water from silver bay and influence of rainstorm. Among the 24 events of exceedance recorded in this reporting month, 9 of them were believed to be caused by improper site practice carried out by the contractor.

During ecological monitoring survey, no White-shouldered Starling was recorded breeding in the watch tower. And there was no sign of disturbance from the Project to the watch tower, though the breeding season of White-shouldered Starling in this year has begun. The watch tower may not be suitable for birds as nesting habitat. In addition, no disturbance on the flora and fauna in the river channels were observed during the ecological monitoring.

Furthermore, there was no complaint, notification of any summons and successful prosecutions against the project received during the reporting period.

Key construction activity in the coming month will be construction of box culvert at PNH and retaining walls at TTT River. It is expected that noise, air and water quality impacts will be resulted from the works. With reference to the EM&A manual and mitigation measure report, mitigation measures are proposed to be taken, if necessary.

The ET will continue to implement the environmental monitoring & audit programme in accordance with the EM&A Manual and Environmental Permit requirement.

1. Introduction

This is the ninth monthly Environmental Monitoring and Audit (EM&A) Report for “Drainage Improvement in Southern Lantau Investigation” project (Environmental Permit No. EP-237/2005/A)

2. Project Information

2.1 Construction program

The “Drainage Improvement in Southern Lantau Investigation” project will be completed by June 2009. The project comprises the following:

- Construction of approximately 80m long gabion with natural bed in Pak Ngan Heung River, approximately 180m of three cells 3m x 2m box culvert and approximately 100m of rectangular channel at Pak Ngan Heung River;
- Construction of approximately 250m of 0.75m wide U-Channel at Ling Tsui Tau Village in Mui Wo;
- Construction of bypass channel of about 350m and 240m long of gabion channels at Luk Tei Tong River respectively; and Widening three existing bottlenecks with gabion lined at Tai Tei Tong River

Appendix A shows the construction program and location plan of the project.

2.2 Project Organization

The Main Contractor, Yick Hing Construction Company Limited, has commissioned Environmental Pioneers & Solutions Limited and Ecosystems Limited as the Environmental Team, which comprises the environmental team leader, the ecologists and the environmental technicians to undertake the environmental monitoring and audit work for this project.

The environmental management structure and is shown in Fig 2.2.1.




Figure. 2.2.1 Environmental Management structure for the project

2.3 Key Personal Contact information chart

Detailed contact of key persons involved in environmental aspect of the project is shown in appendix B.

3. Construction Stage

3.1 Construction Activities in the reporting month

Major activities in the reporting month included the followings:

1. Shuttering formwork, Steel fixing and concreting works for box culvert (coded BC12) at PNH;
2. Excavation works for box culvert (coded BC5 & 7) at PNH River.
3. Rock filling and shuttering to gabion blocks at LTT;
4. Excavation works of gabion trench, trimming of formation and rock filling at LTT River;
5. Trimming of formation as well as rock filling to gabion box at bottleneck A;
6. Demolition and excavation works of retaining wall H at TTT River; and
7. Shuttering formwork of catch pit, excavation works of pipe trench, concreting and pipe laying of pipe at Ling Tsui Tau.

3.2 Construction Activities for the coming month

Key Construction works in the coming month will include:

1. Construction of retaining wall H at TTT River;
2. Construction works of box culvert at PNH River;
3. Construction of retaining wall J, Gabion blocks & box culvert A at LTT River; and
4. Sewerage works at Ling Tsui Tau.

3.3 Environmental Status

Appendix A shows the drawing of the project area.

Locations of the monitoring and control stations with environmental sensitive receivers are presented in Section 4.3, 5.3 and 6.3 for noise, water and ecological monitoring respectively.

4. Noise Monitoring

4.1 Monitoring Parameters and Methodology

The construction noise level was measured in terms of the A-weighted equivalent continuous sound pressure level (L_{eq}). $L_{eq(30minutes)}$ was used as the monitoring parameter for the impact monitoring in the time period between 0700 to 1900 hours on normal weekdays. For all other time period, $L_{eq(5minutes)}$ was employed for comparison with the Noise Control Ordinance (NCO) criteria.

Noise measurement results obtained from each monitoring location were recorded in the Construction Noise Monitoring Data Sheet (Appendix E) immediately after the measurement. As supplementary information for data auditing, statistical results L_{10} and L_{90} were also be recorded for reference.

In case of non-compliance with the construction noise criteria, more frequent monitoring, as specified in the Action plan in table 4.5.2, shall be carried out. This additional monitoring shall be carried out until the recorded noise levels are rectified or proved to be irrelevant to the construction activities.

4.2 Monitoring Equipment

The sound level meters and calibrators comply with the International Electrotechnical Commission Publications 651:1979 (Type 1) and 804:1985 (Type 1) specifications as referred to in the Technical Memorandum (TM) to the Noise Control Ordinance was deployed as monitoring equipment for noise measurement.

Noise measurement was not be made in the presence of fog, rain, wind with a steady speed exceeding $5ms^{-1}$ or wind with gust exceeding $10ms^{-1}$. Thus wind speed was checked by the portable wind speed indicator capable of measuring the wind speed in m/s. Table 4.2.1 summarizes the equipment list for noise monitoring

Table 4.2.1 Equipment List for Noise Monitoring

Equipment	Manufacturer & Model No.	Precision Grade	Qty
Integrated sound level meter	ACO Japan, model 6224	IEC 651 Type 1 IEC 804 Type 1	1
Windscreen	Microtech gefell model W2	N/A	1
Acoustical calibrator	Castle GA 607	IEC 942 Type 1	1
Wind speed indicator	Kestrel K1000	N/A	1
Remarks: Calibration details for the sound level meter is given in Appendix C for reference			

4.3 Monitoring Locations

According to the Baseline Monitoring Report issued in May 2008 for the captioned project, four locations where are alternative from the locations proposed in EM&A manual, were designated for baseline noise monitoring. For the data validation, impact noise monitoring was undertaken in the same locations during the construction phase of the project. The proposed monitoring locations are summarized in Table 4.3.1. Figure 4.3.1 shows the Noise Monitoring Locations

Noise measurement in each monitoring locations were taken at a point 1m from the exterior of the selected premises and at a height with no disturbance to the dweller and least obstructed view.

Table 4.3.1 Noise Monitoring Locations during Construction Phase

Identification No.	Noise Monitoring Locations
N1	No. 73, Village House, Ling Tsui Tau Tsuen (ground level)
N2	No. 31, Village House, Ling Tsui Tau Tsuen (ground level)
N3	Fence wall outside No. 5 village house adjacent to Luk Tei Tong River Outlet (ground level)
N4	No. 23, Village House, Tai Tei Tong River (ground level)

In accordance with the requirements in the EM&A manual, weekly impact monitoring was conducted. For the time period between 0700 and 1900 hours on normal weekdays, and noise parameter of $L_{eq(30minutes)}$ was measured. As if the construction works were carried out during restricted period (ie. 1900-2300, 2300-0700 of next day and Sundays / general holiday), impact monitoring that comprises 3 consecutive $L_{eq(5minutes)}$ would be carried out.




Figure 4.3.1 Impact noise monitoring locations

4.4 Monitoring Results and Interpretation

Relevant details of the noise monitoring results are presented in table 4.4.1. The results, ranged between 46.3 dB (A) and 64.1 dB (A), were within the limit levels and therefore, no exceedance was found.

Table 4.4.1 Noise monitoring results

Table 4.4.1 Noise Monitoring Results for the reporting month							
Location	Parameter	Date	Time	L _{Aeq} dB(A)	Limit dB(A)	Exceedance	Weather
N1	L _{eq} 30mins	6/04/09	14:50	47.2	75	N	Cloudy
N1	L _{eq} 30mins	15/04/09	13:35	53.0	75	N	Sunny
N1	L _{eq} 30mins	20/04/09	13:40	55.7	75	N	Sunny
N1	L _{eq} 30mins	27/04/09	11:24	54.7	75	N	Sunny
N2	L _{eq} 30mins	6/04/09	14:15	52.0	75	N	Cloudy
N2	L _{eq} 30mins	15/04/09	14:08	61.2	75	N	Sunny
N2	L _{eq} 30mins	20/04/09	14:15	54.7	75	N	Sunny
N2	L _{eq} 30mins	27/04/09	13:00	52.6	75	N	Sunny
N3*	L _{eq} 30mins	6/04/09	13:40	51.1	75	N	Cloudy
N3*	L _{eq} 30mins	15/04/09	13:00	64.1	75	N	Sunny
N3*	L _{eq} 30mins	20/04/09	13:00	62.2	75	N	Sunny
N3*	L _{eq} 30mins	27/04/09	10:50	56.7	75	N	Sunny
N4	L _{eq} 30mins	6/04/09	13:00	46.3	75	N	Cloudy
N4	L _{eq} 30mins	15/04/09	14:42	59.0	75	N	Sunny
N4	L _{eq} 30mins	20/04/09	14:53	53.6	75	N	Sunny
N4	L _{eq} 30mins	27/04/09	13:35	58.6	75	N	Sunny

Remarks: Raw datasheet for noise monitoring are attached in appendix E for reference.

Remark*: The equivalent noise level of N3 is corrected by +3 dB from the raw data result due to the fact that free field measurement was carried out in the location.

4.5 Action and Limit level for Construction noise

The Action and Limit (A/L) levels for construction noise are defined in Table 4.5.1. Should non-compliance of the criteria occur, action in accordance with the Action Plan in Table 4.5.2 should be carried out.

There was no recorded exceedance in the reporting month.

Table 4.5.1 Action and Limit Levels for Construction noise		
Time Period	Action Level	Limit Level
0700 – 1900 hours on normal weekdays	When one documented complaint is received	75dB(A)
Remarks: If works are to be carried out during restricted hours, the conditions stipulated in the construction noise permit issued by the Noise Control Authority have to be followed.		

Table 4.5.2 Event / Action Plan for Construction Noise

EVENT	ACTION			
	ET	IC(E)	ER	Contractor
Action Level	<ol style="list-style-type: none"> 1. Notify IC(E) and Contractor; 2. Carry out investigation; 3. Report the results of investigation to the IC(E), ER and Contractor; 4. Discuss with the Contractor and formulate remedial measures; 5. Increase monitoring frequency to check mitigation effectiveness. 	<ol style="list-style-type: none"> 1. Review the analysed results submitted by the ET; 2. Review the proposed remedial measures by the Contractor and advise ER accordingly; 3. Supervise the implementation of remedial measures. 	<ol style="list-style-type: none"> 1. Confirm receipt of notification of failure in writing; 2. Notify Contractor; 3. Require Contractor to propose remedial measures for the analysed noise problem; 4. Ensure remedial measures are properly implemented. 	<ol style="list-style-type: none"> 1. Submit noise mitigation proposals to IC(E); 2. Implement Noise mitigation proposals.
Limit Level	<ol style="list-style-type: none"> 1. Identify source; 2. Inform IC(E), ER, EPD and Contractor; 3. Repeat measurements to confirm findings; 4. Increase monitoring frequency; 5. Carry out analysis of Contractor's working procedures to determine possible mitigation to be implemented; 6. Inform IC(E), ER and EPD the causes and actions taken for the exceedances; 7. Assess effectiveness of Contractor's remedial actions and keep IC(E), EPD and ER informed of the results 8. If exceedance stops, cease additional monitoring 	<ol style="list-style-type: none"> 1. Discuss amongst ER, ET, and Contractor on the potential remedial actions; 2. Review Contractors remedial actions whenever necessary to assure their effectiveness and advise the ER accordingly; 3. Supervise the implementation of remedial measures. 	<ol style="list-style-type: none"> 1. Confirm receipt of notification of failure in writing; 2. Notify Contractor; 3. Require Contractor to propose remedial measures for the analysed noise problem; 4. Ensure remedial measures properly implemented; 5. If exceedance continues, consider what portion of the work is responsible and instruct the Contractor to stop that portion of work until the exceedance is abated 	<ol style="list-style-type: none"> 1. Take immediate action to avoid further exceedance; 2. Submit proposals for remedial actions to IC(E) within 3 working days of notification; 3. Implement the agreed proposals; 4. Resubmit proposals if problem still not under control; 5. Stop the relevant portion of works as determined by the ER until the exceedance is abated

4.6 Noise Mitigation Measures

The following mitigation measures were observed from the weekly site inspection in the reporting month:

- Use of quiet powered mechanical equipment (PME)
- Implementation of the following good site practices:
 - Only well-maintained and regularly serviced plant should be operated on site;
 - Silencers or mufflers on construction equipment;
 - Mobile plant, if any, should be sited as far from noise sensitive receivers as possible; and
 - Machines and plant (such as trucks) that may be in intermittent use should be shut down between work periods or should be throttled down to a minimum.

5. Water Monitoring

5.1 Water Quality Monitoring Parameters and methodology

Turbidity in Nephelometric Turbidity Unit (NTU), Dissolved Oxygen (DO) in mg/L and Suspended Solids (SS) in mg/L are required to measure in this project. Turbidity, DO was measured in-situ while water samples were delivered to Accredited HOKLAS Laboratory for analysis of SS.

Other relevant data such as monitoring location, time, water depth, temperature, salinity, weather conditions and any other special phenomena and work underway at the construction site were recorded during sampling.

According to the requirement of the EM&A manual, two consecutive measurements for parameters of DO concentration, DO saturation and Turbidity are required to be taken at each monitoring location. When the difference in value between the first and second reading of DO or Turbidity is more than 25%, the reading would be discarded and further reading would be taken.

5.2 Monitoring Equipment

Turbidity, DO, Salinity, pH and temperature was measured by an instrument complied with the following requirements:

The instrument is a portable as well as weatherproof multimeter complete with cable and uses a DC power source. It is capable of measuring:

- A turbidity between 0-800NTU;
- A dissolved Oxygen level in the range of 0-20mg/L and 0-200% saturation;
- A temperature of 0-50°C;
- Salinity in the range of 0-40ppt;
- pH in the range of 0-14.

Suspended solid was determined by the water samples collected from the monitoring locations for further analysis in accredited HOKLAS laboratory. Water samples were contained by polythene bottles, packed in ice (cooled in 4°C without frozen) and delivered to the laboratory for analysis as soon as possible after collection. Duplicate samples from each independent sampling event were undertaken during impact monitoring.

Detailed calibration records of the multimeter were shown in Appendix C for reference.

5.3 Monitoring Locations

Seven locations included a control station in upstream of each stream/ river, a monitoring station at the end of each stream/ river of the works area and a monitoring station at Silver River were proposed for the impact water quality monitoring. Water samples were collected at mid-depth of each proposed monitoring stations for measurements and sample collection. The Location Plan is shown in Figure 5.3.1 for reference.




Figure 5.3.1 Water Quality Monitoring Locations

5.4 Monitoring Frequency

Impact water quality monitoring was undertaken three days per week and at ebb tides during the course of the construction river works. Upon the completion of the construction works, the monitoring exercises at the designated monitoring stations will be continued for four weeks in the same manner as the impact monitoring.

5.5 Monitoring Results and Interpretation

Water quality monitoring was carried out fourteen times during April. Detailed on-site measurements and laboratory analysis reports including QA/QC results are shown in appendix F1 and F2 respectively, while Table 5.5.1 presents consolidated results throughout the reporting month.

Exceedance events on parameters of dissolved oxygen, turbidity and suspended solids were recorded on 1, 2, 6, 17, 22, 24, 27, 28 and 29 April according to the established level. Findings from the investigations showed that exceedances were mainly caused by:

- 1.) Surface runoff of site water entered the branch and stream course of LTT River.
- 2.) Construction activities belonged to the other projects carried out at the upper stream area at LTT and TTT River.
- 3.) Influx of marine water.
- 4.) Water quality changes due to heavy rainstorm.

Detailed information of the exceedance events and action taken were presented in Section 7.

Among the 24 events of exceedance recorded in this reporting month, 9 of them were believed to be caused by improper site practice carried out by the contractor. As such, contractor was advised to conduct remedial works and provide necessary mitigation measures to prevent further deterioration of water quality.

Table 5.5.1 Water quality monitoring results in April 2009

	M1			M2			M3			M4		
	MIN	MAX	Ave	MIN	MAX	Ave	MIN	MAX	Ave	MIN	MAX	Ave
Turbidity (NTU)	2.8	25.9	9.2	2.5	63.8	16.6	5.5	38.8	14.0	4.8	42.7	12.1
DO (mg/l)	6.5	10.6	8.6	7.9	10.4	9.0	5.7	9.8	7.9	6.6	10.0	8.2
Suspended Solid (mg/l)	5.6	13.0	8.8	2.7	30.6	9.6	7.4	28.5	12.7	6.3	24.3	11.0

	C1			C2			C3		
	MIN	MAX	Ave	MIN	MAX	Ave	MIN	MAX	Ave
Turbidity (NTU)	0.0	5.6	1.9	1.4	732.1	159.8	4.1	12.2	7.2
DO (mg/l)	6.4	9.3	7.7	7.9	8.5	8.1	3.9	8.4	5.9
Suspended Solid (mg/l)	0.8	10.1	2.4	1.0	490.5	101.4	6.4	13.5	8.9

* Remarks: Detection limit for Turbidity, DO and SS are 1 NTU, 0.1 mg/L and 1 mg/L respectively.

5.6 Action and limit level for Water Quality

Based on the baseline water quality monitoring data obtained, the A/L levels are shown in Table 5.6.1. If the water quality monitoring results at any impact stations exceeded the criteria, the actions in accordance with the Event and Action Plan in Table 5.6.2 should be taken.

Table 5.6.1 Action and Limit Levels for water quality monitoring

Parameters	Monitoring locations							
	M1		M2		M3		M4	
	Action Level	Limit Level	Action Level	Limit Level	Action Level	Limit Level	Action Level	Limit Level
Turbidity (NTU)	15.2	16.9	5.3	6.5	16.8	26.0	16.2	18.0
DO (mg/L)	5.7	4.0	6.2	4.0	5.9	4.0	5.9	4.0
SS (mg/L)	12.2	12.8	3.1	4.2	12.4	17.7	13.9	15.2

Remarks:

For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits

For SS and turbidity, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.

Table 5.6.2 Event and action Plan for Water Quality

EVENT	ACTION			
	ET	IC(E)	ER	Contractor
Action Level being exceed by one sampling day	<ol style="list-style-type: none"> 1. Repeat in <i>situ</i> measurement to confirm findings; 2. Identify reasons for non-compliance and source(s) of impact; 3. Inform IC(E) and Contractor; 4. Check monitoring data, all plant, equipment and Contractor's working methods; 5. Discuss mitigation measures with IC(E) and Contractor; 6. Repeat measurement on next day of exceedance. 	<ol style="list-style-type: none"> 1. Discuss with ET and Contractor on the mitigation measures; 2. Review proposals in mitigation measures submitted by Contractor and advise the ER accordingly; 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Discuss with IC(E) on the proposed mitigation measures; 2. make agreement on the mitigation measures to be implemented; 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Inform the ER and confirm notification of the non-compliance in writing; 2. Rectify unacceptable practice; 3. Check all plant and equipment; 4. Consider changes of working methods; 5. Discuss with ET and IC(E) and propose mitigation measures to IC(E) and ER; 6. Implement the agreed mitigation measures.
Action level being exceed by more than two consecutive sampling days	<ol style="list-style-type: none"> 1. Repeat in <i>situ</i> measurement to confirm findings; 2. Identify reasons for non-compliance and source(s) of impact; 3. Inform IC(E) and Contractor; 4. Check monitoring data, all plant, equipment and Contractor's working methods; 5. Discuss mitigation measures with IC(E) and Contractor; 6. Ensure mitigation measures are implemented; prepare to increase the monitoring frequency to daily 7. Repeat measurement on next day of exceedance 	<ol style="list-style-type: none"> 1. Discuss with ET and Contractor on the mitigation measures; 2. Review proposals in mitigation measures submitted by Contractor and advise the ER accordingly; 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Discuss with IC(E) on the proposed mitigation measures; 2. make agreement on the mitigation measures to be implemented; 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Inform the ER and confirm notification of the non-compliance in writing; 2. Rectify unacceptable practice; 3. Check all plant and equipment; 4. Consider changes of working methods; 5. Discuss with ET and IC(E) and propose mitigation measures to IC(E) and ER within three working days; 6. Implement the agreed mitigation measures.
Limit level being exceeded by one sampling day	<ol style="list-style-type: none"> 1. Repeat in <i>situ</i> measurement to confirm findings; 2. Identify reasons for non-compliance and source(s) of impact; 3. Inform IC(E) and Contractor; 4. Check monitoring data, all plant, equipment and Contractor's working methods; 5. Discuss mitigation measures with IC(E) and Contractor; 6. Ensure mitigation measures are implemented; 7. Increase the monitoring frequency to daily until no exceedance of Limit Level 	<ol style="list-style-type: none"> 1. Discuss with ET and Contractor on the mitigation measures; 2. Review proposals in mitigation measures submitted by Contractor and advise the ER accordingly; 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Discuss with IC(E) on the proposed mitigation measures; 2. make agreement on the mitigation measures to be implemented; 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Inform the ER and confirm notification of the non-compliance in writing; 2. Rectify unacceptable practice; 3. Check all plant and equipment; 4. Consider changes of working methods; 5. Discuss with ET and IC(E) and propose mitigation measures to IC(E) and ER; 6. Implement the agreed mitigation measures.

5.7 Water Quality Mitigation Measures

Construction Run-off and Drainage

The site practices outlined in ProPECC PN 1/94 ‘Construction Site Drainage’ should be followed as far as practicable during both construction and operation phase of the drainage improvement works in order to minimize surface runoff and the chance of erosion, and also to retain and reduce any suspended solids prior to discharge.

As recommended in the final EM&A manual, attention would be paid specially construction run-off and drainage, general construction activities, sewage discharged from construction workforce and river channel excavation works.

As for the forthcoming wet season, contractor was recommended to provide sufficient water treatment facilities for accumulated site water.

5.8 Water Monitoring Schedule for the Next reporting period

Water monitoring in the next reporting period is scheduled for 4, 6, 8, 11, 13, 15, 20, 21, 22, 25, 27 and 29 May.

6. Ecology Monitoring

6.1 Ecological Monitoring Parameters

According to the Final EM&A Manual, a specific ecological monitoring programme of the improved section of PNH and LTT Rivers is recommended. The monitoring parameters required to measure in this project and survey methodology are described below:

- (1) Avifauna species and abundance: Birds will be surveyed quantitatively using transect count method. Birds within the river channel and on the riverbank will be identified and their abundance will be recorded.
- (2) Aquatic macroinvertebrate community species composition and abundance: Survey on aquatic fauna will focus on determination of the diversity and abundance of stream aquatic communities. Sampling methods, such as active searching, direct observation, netting, and kick sampling, will be determined according to the site conditions during field survey.
- (3) Fish community species composition and abundance: Sampling methods, such as active searching, direct observation, and hand netting, will be determined according to the site conditions during field survey.
- (4) Adult odonate community species composition and abundance: Adult dragonfly will be surveyed quantitatively using transect count method. Adult dragonflies within the river channel and on the riverbank will be identified and their abundance will be recorded. Species requiring close examination will be netted.
- (5) Aquatic, emergent and riparian vegetation community species composition and abundance: The area will be walked through. Plant species composition and their relative abundance will be recorded.
- (6) Surveys of White-shouldered Starling *Sturnus sinensis* will be conducted at the disused watchtowers next to LTT river. Breeding of the White-shouldered Starlings will be determined by checking signs of attempt to breed or sign of breeding which include carrying nesting materials, to-and-fro movement of adults carrying food, presence of recently fledged juveniles, etc. The number of breeding pairs and the site observation will be recorded whenever possible.

Water Quality Monitoring along LTT and PNH River as well as LTT bypass channel was carried out. Water quality monitoring will include Turbidity in Nephelometric Turbidity Unit (NTU), Dissolved Oxygen (DO) in mg/L and Suspended Solids (SS) in mg/L are required to measure in this project. Moreover, additional water monitoring parameters will be taken for the purposes of ecological monitoring of water quality in this project. The added information will include: BOD, Ammonia, Nitrate and Phosphate concentrations. Turbidity, DO, pH and water flow will be measured in-situ while water samples will be delivered to Accredited HOKLAS Laboratory accredited laboratory and the analyses followed the standard methods according to APHA Standard Methods for the Examination of Water and Wastewater, 20th Edition, or equivalent for analysis of SS, BOD, Ammonia, Nitrate and Phosphate concentrations.

Other relevant data such as monitoring location, time, water depth, temperature, salinity, weather conditions and any other special phenomena and work underway at the construction site will be recorded during sampling.

According to the requirement of the EM&A manual, two consecutive measurements for parameters of DO concentration, DO saturation and Turbidity are required to be taken at each monitoring. When the difference in value between the first and second reading of DO or Turbidity is more than 25%, the reading will be discarded and further reading will be taken.

6.2 Monitoring Equipment and Methodology

Turbidity, DO, Salinity, pH and Temperature will be measured by a instrument complied with the following requirements:

The instrument is a portable as well as weatherproof multimeter complete with cable and uses a DC power source. It is capable of measuring:

- A turbidity between 0-800NTU;
- A dissolved Oxygen level in the range of 0-20mg/L and 0-200% saturation;
- A temperature of 0-50°C;
- Salinity in the range of 0-40ppt;
- pH in the range of 0-14.

Suspended solid was determined by the water samples collected from the

monitoring locations for further analysis in accredited HOKLAS laboratory. Water samples were contained by polythene bottles, packed in ice (cooled in 4°C without frozen) and delivered to the laboratory for analysis as soon as possible after collection. Duplicate samples from each independent sampling event were undertaken during impact monitoring.

6.3 Monitoring Locations

According to the Final EM&A Manual, the improved section of the river channels will be divided into 50m long sections, and ecological survey will be carried out in each of the 50m sections. A total of nine sections will be divided for the two rivers which include:

- Two sections for existing upstream of PNH river (i.e. the proposed 80m long trapezoidal channel)
- Two sections for existing downstream of PNH river (i.e. the proposed 100m long rectangular channel)
- Five sections for existing Luk Tei Tong River (i.e. the proposed 240m long trapezoidal channel)

The disused watchtowers are located at the confluence of the three rivers and next to LTT river.

The Location Plan for ecological is shown in Figure 6.1 for reference.

The improved sections of the river channels require to carrying out water quality monitoring for the ecological purpose. The sampling points for impact monitoring was undertaken in the same place as the baseline monitoring proposed, where include:

- Three points for existing of PNH river
- Three points for existing of Luk Tei Tong River

The Location Plan for ecological water monitoring is shown in Figure 6.2 for reference.




Figure 6.1 Ecological Monitoring Locations




Figure 6.2 Ecological Water Quality monitoring locations

6.4 Monitoring Frequency

As proposed, ecological impact monitoring was carried out once for each monitoring location in the reporting month.

6.5 Monitoring results

Pak Ngan Heung Stream N and S sections

Vegetation

Surveys were conducted on 23 April 2009. The north section of Pak Ngan Heung Stream was fairly modified. Part of the west bank was lined with rock gabion bank and occupied by village houses and abandoned agricultural field. The stream channel was wider than the downstream section, but the stream bank was still fairly narrow and steep in gradient. Compared to the south section, the north section was relatively shaded due to presence of more trees with larger canopy.

The walk through survey recorded a total of 71 species, including 22 trees, 8 shrub, 27 herb and 4 grass species (Appendix D1). 53 of the species recorded are natives, while 18 were exotics. The quantitative sampling recorded 27 species at the north section. Large native (e.g. *Celtis sinensis*, *Cleistocalyx operculata*, *Ficus hispida*) and exotic trees (*Acacia confusa*) dominated the transects. Other species recorded include common and typical native pioneer forest and streamside tree species and ruderal species. No species of conservation interest was recorded.

Table 6.5.1 Relative percentage cover of vegetation recorded at Pak Ngan Heung (N) Section

Species	Relative % cover	
	PNH3	PNH4
<i>Acacia confusa</i>		16.69
<i>Acorus graminifolius</i>		1.05
<i>Alocasia macrorrhiza</i>		0.52
<i>Aporosa dioica</i>		2.94
Bamboo	12.55	
<i>Celtis sinensis</i>	21.98	26.19
<i>Christella parasitica</i>	1.47	1.8
<i>Cleistocalyx operculata</i>	33.71	
<i>Embelia ribes</i>		1.05
<i>Ficus hispida</i>		7.53
<i>Lemna minor</i>		0.92
<i>Liriope spicata</i>		0.49
<i>Litsea glutinosa</i>		14.4
<i>Litsea rotundifolia</i>	1.47	
<i>Macaranga tanarius</i>		15.71
<i>Mallotus paniculatus</i>	19.54	
<i>Microcos paniculata</i>		0.49
<i>Microstegium ciliatum</i>		3.34
<i>Mikania micrantha</i>	2.93	1.14
<i>Neyraudia reynaudiana</i>		0.33
<i>Plantago major</i>		0.33
<i>Psychotria asiatica</i>	0.49	
<i>Pueraria phaseoloides</i>	0.98	
<i>Sageretia thea</i>		1.64
<i>Sporobolus fertilis</i>		3.44
<i>Sterculia lanceolata</i>	3.42	
<i>Syzygium jambos</i>	1.46	
Total Relative % Cover	100.00	100.00
Total Transect Length (m)	13	34

*Total Cover rounded up to one decimal place to avoid round-off error.

The south section of Pak Ngan Heung Stream was highly modified. Both

banks were lined with rock gabions and were occupied by village houses immediately beyond the channel. The stream channel was lack of riparian zone and vegetation. A total of 18 species recorded, 13 of which were native and 5 were exotic. It was composed of isolated individuals of mangrove (*Kandelia obovata*), backshore species (*Clerodendrum inerme*), native (*Celtis sinensis*) and planted trees (*Acacia confusa*) (Appendix D2). No species of conservation interest was recorded.

Surveys were conducted on 17 April 2009.

A total of nine species of birds were recorded in the proposed work area of the Pak Ngan Heung River (Table 6.5.2). All are common in Hong Kong.

Table 6.5.2 Avifauna in Pak Ngan Heung

Common names	Latin names	PNH 1	PNH 2	PNH 3	PNH 4	Commonness & distribution
Little Egret	<i>Egretta garzetta</i>	1				CW
Black-crowned Night Heron	<i>Nycticorax nycticorax</i>	1				CL
Common Koel	<i>Eudynamis scolopacea</i>			1		CW
Spotted Dove	<i>Streptopelia chinensis</i>	2	2	2		CW
Crested Bulbul	<i>Pycnonotus jocosus</i>				2	CW
Magpie Robin	<i>Copsychus saularis</i>			1	1	CW
Yellow-browed Warbler	<i>Phylloscopus inornatus</i>			1	2	CW
Japanese White-eye	<i>Zosterops japonica</i>				2	CW
Great Tit	<i>Parus major</i>	1				CW

CW = common and widespread, CL = common/uncommon and localized

Seven species of dragonfly was recorded in the proposed work area of the Pak Ngan Heung River (Table 6.5.3). All are common and widespread in Hong Kong.

Table 6.5.3 Dragonfly in Pak Ngan Heung River

Common names	Latin names	PNH 1	PNH 2	PNH 3	PNH 4	Commonness & distribution
Orange-tailed Sprite	<i>Ceriagrion auranticum</i>				2	A
Yellow Featherlegs	<i>Copera marginpes</i>				1	A
Asian Amberwing	<i>Brachythemis contaminata</i>		1			A
Black Threadtail	<i>Prodasineura autumnalis</i>				3	A
Red Skimmer	<i>Orthetrum chrysis</i>	1				C
Green Skimmer	<i>Orthetrum sabina</i>			1		C
Crimson Dropwing	<i>Trithemis aurora</i>				4	A

A = abundant, UC = uncommon

Aquatic fauna and fish

9 species of fish and 3 crustacean were recorded in the 4 sections at PNH. All are common and widespread in Hong Kong. Both the species number of aquatic fauna and their abundance recorded in the present monitoring survey were lower than those recorded in previous wet season months (Aug to Oct 2008). As observed on site, the stream flow and the water level were still relatively low, in the early wet season in April. Though Predaceous Chub was observed, the another one fish species of conservation concern reported in the EIA report, i.e. Flagtail *Kuhlia marginata*, was not recorded in PNH during the present monthly monitoring survey.

Table 6.5.4 Aquatic Invertebrates and fish in Pak Ngan Heung

Common names	Scientific names	PNH 1	PNH 2	PNH3	PNH4
Invertebrates					
Atyid shrimp	<i>Caridina elongata</i>				+
Palaemonid shrimp	<i>Macrobrachium hainanensis</i>			+	+
Crab	<i>Varuna litterata</i>		+		
Mitten Crab	<i>Eriocheir japonica</i>				
Fish					
Mosquito fish	<i>Gamusia affinis</i>				+
Barcheek Goby	<i>Rhinogobius giurinus</i>				+
Goby	<i>Rhinogobius duospilus</i>		+		
Swordtail	<i>Xiphophorus hellerii</i>				+
Six-banded Barb	<i>Puntius semifasciolatus</i>				
Unidentified Cichlid fish					
Tilapia		+	++	+	
Predaceous Chub	<i>Parazacco spilurus</i>			++	
Jarboa Terapon	<i>Terapon jarbua</i>	++			
Common Silver-biddy	<i>Gerres oyena</i>	++			
Mullet	<i>Mugil cephalus</i>	+++	+++		
Broken-band Hillstream Loach	<i>Liniparhomaloptera disparis</i>				

+ = Occasional, less than 5 individuals were found; ++ = Common, 5 – 20 individuals were found; +++ = Abundant, more than 20 individuals were found.

Luk Tei Tong Stream Section

Vegetation

Surveys were conducted on 23 Apr 2009. The Luk Tei Tong Stream Section was highly modified. Vegetation only established on isolated muddy patches at the estuary and remaining semi-natural banks of Section 1 and Section 2. Vegetation on the eastern stream bank from the second half of Section 3 to Section 5 were largely cleared while the western bank was still lined with rock gabions or concrete. The whole section appeared to be subject to tidal influence, as mangrove associated or backshore species were recorded along the whole channel.

The walk through survey recorded a total of 26 species, including 11 tree, 6 shrub, 4 grass species (Appendix D3). 21 of the species recorded are natives, while 5 were exotics. The quantitative sampling recorded 10 species at Sections 2. Section 2 was dominated by *Terminalia catappa* and *Wollastonia biflora*, while Section 3 was dominated by *Hibiscus tiliaceus*. No quantitative survey was carried out on Section 3 and 4 due to vegetation clearance on stream banks as part of the site clearance works under the project. Remnants of mangrove stand were still observed along Section 3, which will be cleared in due course.

Due to the patchiness of streamside vegetation, the quantitative data should be interpreted with cautions and used as a reference only.

Table 6.5.5 Relative percentage cover of vegetation recorded at Luk Tei Tong Stream Section

	Relative % cover
Species	LLT2
<i>Acanthus ilicifolius</i>	7.97
<i>Celtis sinensis</i>	9.85
<i>Execoecaria agallocha</i>	3.68
<i>Fimbristylis</i> sp.	15.85
<i>Kandelia obovata</i>	2.57
<i>Papalum paspaloides</i>	11.40
<i>Premna serratifolia</i>	1.63
<i>Terminalia catappa</i>	35.13
<i>Toxocarpus wightianum</i>	0.69
<i>Wollastonia biflora</i>	11.23
Total Relative % Cover	100.00
Total Transect Length (m)	11

*Total Cover rounded up to one decimal place to avoid round-off error.

Terrestrial Fauna

The proposed work area of Luk Tei Tong River was divided into 5 sections. All recorded avifauna and dragonfly species are common in Hong Kong

Surveys were conducted on 17 April 2009.

A total of seven species of birds were recorded in these sections (Table 6.5.6). Most of these species are common and widely distributed in Hong Kong. Crested Goshawk is uncommon in Hong Kong.

Table 6.5.6 Avifauna in Luk Tei Tong River

Common names	Latin names	LTT 1	LTT 2	LTT 3	LTT 4	LTT 5	Commonness & distribution
Little Egret	<i>Egretta garzetta</i>	1					CW
Black-crowned Night Heron	<i>Nycticorax nycticorax</i>	1					CL
Chinese Pond Heron	<i>Ardeola bacchus</i>					1	CW
Crested Goshawk	<i>Accipiter trivirgatus</i>					1	R
Indian Cuckoo	<i>Cuculus micropterus</i>			1			CL
Plaintive Cuckoo	<i>Cacomantis merulinus</i>		1				CL
Crested Bulbul	<i>Pycnonotus jocosus</i>		5	2			CW

CW = common and widespread, CL = common/uncommon and localized, R = uncommon/rare and localised

Two species of dragonfly were recorded in the Luk Tei Tong River (Table 6.5.7). Both are common and widespread in Hong Kong.

Table 6.5.7 Dragonfly in Luk Tei Tong River

Common names	Latin names	LTT 1	LTT 2	LTT 3	LTT 4	LTT 5	Commonness & distribution
Green Skimmer	<i>Orthetrum sabina</i>			1		1	A
Wandering Glider	<i>Pantala flavescens</i>				1		A

A = abundant

Aquatic invertebrates and fish

5 species of fish, 4 species of crustacean and 5 species of mollusks were recorded in the 5 sections at LTT. All are common and widespread in Hong Kong. The species number of the aquatic fauna, in particular crustacean, and their abundance recorded in the present monitoring survey were lower than those recorded in previous wet season months (Aug to Oct 2008). As observed on site, the stream flow and the water level were still relatively low in upstream section. The two fish species of conservation concern reported in the EIA report, i.e. Flagtail *Kuhlia marginata* and Predaceous Chub *Parazacco spilurus* were not recorded in LTT during the present monitoring as well as the

baseline monitoring survey.

Table 6.5.8 Aquatic invertebrates and fish in Luk Tei Tong River

Common names	Scientific names	LTT1	LTT2	LTT3	LTT4	LTT5
Invertebrates						
Mangrove clam	<i>Geloina erosa</i>					
Rock oyster	<i>Saccostrea cuculata</i>		+++	+		
Snail	<i>Melanoides tuberculata</i>			+		
Snail	<i>Terebralia</i> sp.			+		
Snail	<i>Nerita</i> sp.		++	+		
Snail	<i>Littoraria articulata</i>		+	++		
Crab	<i>Varuna litterata</i>			+		
Fiddler crab	<i>Uca lactea</i>		+			
Fiddler crab	<i>Uca arcuata</i>					
Fiddler crab	<i>Uca crassipes</i>					
Crab	<i>Perisesarma bidens</i>		+			
Mangrove mud crab	<i>Scylla paramamosain</i>		+			
Mitten crab	<i>Eriocheir japonica</i>					
Fish						
Common mudskipper	<i>Periophthalmus cantonensis</i>	+				
Tilapia		++				
Jarbug terapon	<i>Terapon jarbug</i>		++	+		
Mullet	<i>Mugil cephalus</i>	+++	++	++		
Common Silver-biddy	<i>Gerres oyena</i>		+	+		
Barcheek Goby	<i>Rhinogobius giurinus</i>					

+ = Occasional, less than 5 individuals were found; ++ = Common, 5 – 20 individuals were found; +++ = Abundant, more than 20 individuals were found.

Disused Watchtowers

Surveys were conducted on 17 April 2009.

There was no sign (e.g., adults carrying food or nesting materials) of use of the watchtower as nesting habitat by White-shouldered Starling. This species was not observed during the April 2009 monitoring. No bird of other species was observed entering the watchtower.

Since the monitoring surveys commenced in August 2008, no bird was observed entering the watchtower. It seems the birds do not prefer the watchtower as roosting or nesting habitat.

Ecological Water Quality Monitoring (EWQM)

EWQM was conducted on 9 April 2009. Monitoring results are summarized in table 6.9. Detailed on-site measurements and laboratory report are presented in appendix D4 and D5.

Table 6.10 shows the baseline results of Ecological Water Quality Monitoring, from the information given in Baseline Monitoring Report.

To review the results in table 6.9 in general, the measured results were found similar with past months. As a section of gabion wall will be carried out at the riverside of LTT River, contractor was reminded to be cautious on the change of water quality due to site works, and provide proper mitigation measures if necessary.

Table 6.9 Summarized Ecological water quality monitoring results (9 April 2009)

Parameters	Limit of detection	WE1	WE2	WE3	WE4	WE5	WE6
Suspended Solid (mg/l)	1	2.00	6.50	9.70	7.55	9.05	1.00
Nitrogen (Ammonia) (mg/l)	0.01	0.18	0.18	0.15	0.14	0.13	0.02
Nitrogen (Nitrate) (mg/l)	0.01	0.19	0.18	0.27	0.39	0.41	0.05
Phosphorous (mg/l)	0.01	0.08	0.08	0.09	0.06	0.06	0.03
BOD ₅ (mg/l)	1	2.50	2.50	3.00	2.00	2.00	1.00
DO (mg/l)	0.01	7.33	8.64	9.46	8.80	8.12	7.45
Turbidity (NTU)	0.01	2.35	4.10	10.40	8.75	7.40	0.00
Temperature (oC)	0.1	20.8	22.0	22.5	22.7	22.1	20.9
pH	0.01	6.63	7.33	7.68	7.35	7.26	5.87
Salinity (ppt)	0.1	0	7.1	14.4	14.8	15.1	0
Conductivity (ms/m)	0.1	8.0	1240.0	2380.0	2460.0	2460.0	6.0
Water Flow (m/s)	N/A	0	0.05	0.045	0.06	0.1	0

Table 6.10 Baseline Results of Ecological water quality monitoring

Parameters	WE1	WE2	WE3	WE4	WE5	WE6
Suspended Solid (mg/l)	1.0	2.0	3.0	3.0	<1	<1
Nitrogen (Ammonia) (mg/l)	0.07	0.12	0.11	0.23	0.03	0.02
Nitrogen (Nitrate) (mg/l)	0.12	0.13	0.13	0.31	0.04	0.05
Phosphorous (mg/l)	0.04	0.06	0.06	0.09	0.06	0.05
BOD ₅ (mg/l)	<2	<2	<2	<2	<2	<2
DO (mg/l)	6.58	6.82	6.37	7.61	6.87	5.70
Turbidity (NTU)	4.44	5.12	5.93	6.96	4.65	2.73
PH	6.4	7.1	7.0	6.8	6.6	6.1
Salinity (ppt)	<0.1	0.1	0.3	7.6	0.1	<0.1

6.6 Action and Limit level for Monitoring of White-shouldered Starlings

A simple Event and Action Plan is shown in Table 6.6.1. Should the Event occur, action in accordance with the Action Plan should be carried out.

There was no recorded event in the reporting month.

Table 6.6.1 Event / Action Plan for Monitoring of White-shouldered Starlings

EVENT	ACTION	
	ET Leader	Contractor
Identification of disturbance to breeding White-shouldered Starlings	1. Increase frequency of monitoring to twice weekly	1. Check all construction actions and working methods
	2. Notify Site Engineer	2. Submit proposals for remedial action to prevent abandonment of the breeding site.
	3. Review construction activities of previous week.	3. Implement remedial action.
	4. Identify any changes in construction activities in previous week	4. Liaise with ET regarding effectiveness of remedial actions.
	5. Discuss remedial actions with Site Engineer	

6.7 Ecological monitoring Schedule

The next ecological surveys are scheduled on 7th, 8th and 15th May, while ecological water quality monitoring is scheduled on 6th May.

7. Action taken in Event of Exceedence

If the measurements (Noise, Water, Ecology) exceed the action / limit level, exceedance details will be reported and follow-up actions will be taken by relevant parties involved.

During the reporting period there was no exceedance for noise, ecological measurements recorded; therefore no actions were taken.

Non-compliance of water quality limits (dissolved oxygen, turbidity and suspended solids) were recorded on 1, 2, 6, 17, 22, 24, 27, 28 and 29 April according to the established level. ET has arranged site investigations for the exceedance events and causes were substantially attributable to:

- Surface runoff of site water entered the branch and then the main stream of LTT River;
- Channel improvement works of the branch at LTT, where is nearby the EVA carried out by the other projects. Silt water was found generated from the mentioned site and entered the river channel;
- Clearance works to the river channel carried out at the upper stream area of TTT River by the other project;
- Influx of marine water; and
- Water quality changes due to rainstorm.

The summary of non-compliance is listed in Table 7.1 for reference.

Among the 24 events of non-compliance recorded in this reporting month, 9 of them were believed to be caused by improper site practice carried out by the contractor.

For the exceedance events, ET has notified the relevant parties and conducted site investigation to find out the causes of results. ET also increased the monitoring frequency to daily basis until no exceedance of Limit level; at the mean time contractor was also urged to conduct necessary mitigation measures so as to keep the disturbance on water quality to minimal levels.

Further to the exceedance events in location M3 due to defective site practices of the project. Contractor provided de-silting tank for site water treatment, site water from

de-silting tank was then diverted to soak-away pond and enclosed site area for soak-away purpose.

Table 7.1 Summary of Non-compliance for Water Quality

Date	Location	Parameter	Level of exceedance	Main cause of exceedance
01/04/2009	M2	Turbidity	Limit Level	Silty water discharged from project site
02/04/2009	M2	Turbidity	Limit Level	Disturbance of marine water
06/04/2009	M1	Turbidity	Limit Level	Heavy rainstorm
06/04/2009	M2	Turbidity	Limit Level	Heavy rainstorm
17/04/2009	M2	Turbidity, S.S.	Limit Level	Channel clearance works at upper stream area
22/04/2009	M2	Turbidity, S.S.	Limit Level	Channel clearance works at upper stream area
24/04/2009	M2	Turbidity, S.S.	Limit Level	Channel clearance works at upper stream area
24/04/2009	M3	DO	Action Level	Surface runoff from the site and silty water generated from the construction activities of other project nearby EVA
	M3	Turbidity, S.S.	Limit Level	
27/04/2009	M2	Turbidity, S.S.	Limit Level	Channel clearance works at upper stream area
27/04/2009	M3	Turbidity, S.S.	Limit Level	Surface runoff from the site and silty water generated from the construction activities of other project nearby EVA
27/04/2009	M4	Turbidity, S.S.	Limit Level	Water quality affected by M2 and M3 at the upper stream
28/04/2009	M2	Turbidity, S.S.	Limit Level	Channel clearance works at upper stream area
	M3	S.S.	Action Level	Surface runoff from the site and silty water generated from the construction activities of other project nearby EVA
29/04/2009	M2	Turbidity, S.S.	Limit Level	Channel clearance works at upper stream area

8. Construction waste disposal

It is the contractor's responsibility to ensure that all wastes produced during the construction phase for the drainage improvement works are handled, stored and disposed of in accordance with good waste management practices and EPD's regulation and requirement. Waste materials generated during construction activities, such as construction and demolition (C&D) material, chemical wastes and general refuse, are recommended to be audited at regular intervals to ensure that proper storage, transportation and disposal practices are being implemented.

Contractor has completed the registration of Waste Producer under the Waste Disposal (Chemical Waste)(General) Regulation. The Waste Producer Number, WPN 5213-950-Y2443-03 was assigned by EPD on 12 Aug 2008. The Contractor would be responsible for the implementation of any mitigation measure to minimize waste or redress problems arising from the waste materials.

Table 8.1 is a summary of updated figures of the construction wastes disposal provided by the Contractor.

Table 8.1 Summary of Construction Waste Disposal

Month	Amount of Construction Waste disposed		
	Inert Waste (to Public Fill)	Non-inert Waste (to Landfill)	Chemical Waste (to treatment plant)
1 st April, 09 to 30 th April 09	144.10 (ton)	0.47 (ton)	Nil
Total (from June 08 to April 09)	9022.89 (ton)	65.23 (ton)	0

9. Status of Permits and Licenses obtained

Table 9.1 is the updated status of environmental related permits/ license obtained for the construction activities

Table 9 .1 Status of Permits and Licenses Obtained

Description	License / Permit No.#	Date of Issue	Date of Expiry	Remarks
Environmental Permit	EP-237/2005/A	05 Mar 2008	--	Issued
Registration of C&D Waste Producer	7006521	--	--	Issued
Chemical Waste Producer	5213-950-Y2443-03	12 Aug 2008	--	Issued
Construction Noise Permit	N/A	N/A	N/A	N/A
Effluent Discharge License	EP890/W2/XG032 EP890/W2/XG033 EP890/W2/XG034 EP890/W2/XG035 EP890/W2/XG036 EP890/W2/XG037 EP890/W2/XG038 EP890/W2/XG039 EP890/W2/XG040 EP890/W2/XG041	23 Oct 2008	31 Oct 2013	Issued

The contractor implemented various environmental mitigation measures as recommended in the Environmental Permit and Final Mitigation Measures Report. The implemented schedule is presented in appendix H.

10. Complaint Log

There was no formal complaint received during the reporting month.

	Noise	Water	Ecology	Cultural	Others
April 2009	0	0	0	0	0
Total	0	0	0	0	0

11. Site Environmental Audits

11.1 Site Inspection

With an intention to ensure that appropriate environmental protection and pollution control mitigation measures are properly implemented, regular environmental site inspections have been scheduled.

Within the reporting month, site inspections were conducted on 2, 9, 17, 24 and 30 of April.

A detailed checklist of each site inspection together with comments, relevant photos and maps have been filed and kept. A summary of observation and follow-up action is shown in table 11.1

Date	Observations	Advice from ET	Action taken	Closing Date
5 Mar 09	Falling leaves and stagnant water were found accumulated in the wheel washing bay, located at the site entrance of PNH BC9	Contractor was advised to clean up the wheel washing bay regularly (daily cleaning is preferable)	Regular cleaning to the wheel washing bay was observed during inspection	17 Apr 09
26 Mar 09	Open stockpile and exposed earth surfaces were observed at the bottleneck A of TTT River	Contractor was advised to removed the open stockpile and provided proper coverings to the earth surfaces exposed to river stream	Open stockpile have been removed as advised	2 Apr 09
2 Apr 09	Underground water was found accumulated in the excavated pits of box culvert bay 3 and bay 12 at PNH	Accumulated water on site should be removed for mosquito control and hygiene issues.	Regular removal of accumulated water was conducted claimed by contractor	Ongoing
2 Apr & 23 Apr 09	Chemical container was found placed at the site of LTT bypass channel during inspection	Contractor was advised provide proper drip pans to the chemicals temporarily stored on site; unused chemicals should be returned to designated chemical storage area for further storage.	To be follow up	Ongoing

Table 11.1 Summary of site inspection

Date	Observations	Advice from ET	Action taken	Closing Date
17 Apr, 23 Apr & 30 Apr 09	Stagnant water was observed at the site ground located at the end of LTT bypass channel	Contractor was advised to trace the source of the water, stagnant water should be removed for mosquito control	To be follow up	Ongoing
23 Apr 09	Site water from the excavated pit at ch.2B 150~200 was found pumped to the brushwood area where is out of site boundary and caused flooding	Contractor was warned improper discharge of site water is not allowed. Site water should be diverted to proper de-silting facilities for treatment and discharge to designated discharge point in accordance with discharge licenses applied	Site water was found diverted to a steel tank and then discharged to the pond behind of the Yuen's Compound.	Ongoing
30 Apr 09	River water was found entered the enclosed site retaining wall H during flood tide.	Contractor was advised to be cautious on the conditions of all sites nearby river channels. No site water or chemicals can be entered into the river course.	To be follow up	Ongoing

11.2 Compliance with legal and Contractual requirement

ET leader has reviewed the progress and programme of the works to check any relevant environmental laws has not violated.

A non-compliance of working method LTT was recorded during the joint site inspection carried out on 23rd April. Site water was found generated from the excavated pit for gabion walls at the riverside, those water was pumped to the brushwood area where is out of site boundary.

Contractor was requested to stop such practice immediately. ET, IEC and EPD representatives also advised contractor to provide proper de-silting facilities for site water treatment, treated effluent should be discharged to designated discharged point in accordance with the requirement of effluent discharge licenses applied. Contractor was also reminded to clearly identify their site boundary to prevent loss and damage of vegetation due to the site activities.

ET then carried out a spot check inspection on 28th April to check the conditions of the site. Silty water from the concerned site area was found pumped to a steel tank and then further discharged to the pond behind of the Yuen's compound, which claimed was already hired for site water treatment purpose.

ET seriously reminded the Contractor again to be cautious on the requirements stated in relevant environmental law and documents and manage good site practices so as to minimize impacts to the environment as well as sensitive receivers.

11.3 Environmental Complaint and follow up actions

During this reporting period, there was no documented complaint received. Therefore, follow up actions for the Environmental Complaint is not required

12. Future key issues

Key construction activity in the coming month will include construction of box culverts, retaining walls and gabion walls at PNH, TTT and LTT River. It is expected that several impacts on environmental aspects will be generated on-site. With reference to the EM&A manual, mitigation measure report as well as the environmental permit, proper mitigation measures are proposed to be taken, if necessary.

Contractor was reminded to provide proper measures to mitigate water quality impacts to the river channels due to construction works. River based construction activities should be carried out in enclosed as well as dry condition to prevent discharge of site water to the stream; containment measures such as bunds and barriers should be provided as to restrict the carrying out of construction works within enclosed dry area of the river.

Underground water and site water may be accumulated on site. Contractor is recommended to treat the accumulated site water by proper silt removal facilities before discharging to the designated discharge point; also reuse of site water should be considered.

Contractor was reminded to be cautious on erosion and surface run-off from the stockpiles of earth materials and exposed earth surfaces. Coverings with tarpaulin and/or geo-textile materials should be provided to minimize the concerned impacts.

Dust impact may be resulted by boulder movement, breaking and installation works of gabion blocks, contractor is reminded to provide regular watering to the dusty static site area and stockpile. Meanwhile, size and height of stockpiles should be controlled as such erosion issue could be minimized.

13. Conclusions

In this reporting month, Construction work of box culvert at PNH, excavation and installation works for gabion blocks for LTT bypass channel were carried out.

Regular site meetings and inspection audits led by the seniors for discussing site environmental matters were held among Project Proponent, Contractor and the ET on weekly basis. Also monthly site meeting and inspection audits with the above parties and IEC were carried out at the mid of the reporting month.

For noise level monitoring, all results were within the established A/L limits.

For water quality monitoring, non-compliance events of water quality criteria were recorded on 1, 2, 6, 17, 22, 24, 27, 28 and 29 April. As exceedances were found caused by several factors include defective site practice of the project. Contractor was reminded to improve their site practice and provide necessary mitigation measures for water quality. According to the monthly ecological water monitoring results performed on 09 April 2009, measurements recorded in the monitoring locations were found similar with past months.

During ecological monitoring survey, no White-shouldered Starling was recorded breeding in the watch tower. There was no sign of disturbance from the Project to the watch tower. The breeding season of White-shouldered Starling in this year has begun. However, the absence of nesting of White-shouldered Starling in the watch tower did not seem to be related to construction works in Luk Tei Tong River. A bird species nests in village house should be to certain extent disturbance tolerant.

No bird was observed entering the watchtower since the monitoring surveys commenced in August 2008. Also, no breeding was recorded in the baseline survey in September 2007. It appears that the birds do not prefer to roost or nest in the watch tower.

Also, there were not any notifications of summons recorded during the reporting period. Furthermore, there were not any formal prosecution and complaints recorded.

Site water control was the major concern in this reporting month. Contractor was recommended to provide proper de-silting facilities for site water treatment, and provide necessary mitigation measures to minimize impacts to the river streams.

ET has reminded the contractor to provide environmental pollution control measures wherever necessary; and to keep a good environmental management at site practice.

The ET will continue to implement the environmental monitoring & audit programme in accordance with the EM&A Manual and Environmental Permit requirement.

Appendix A

Construction

Programmer and

Location plan

Location	2006				2007				2008				2009						
	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	
Site Clearance																			
Bank Erosion Control (BEC) - 240																			
Excavation																			
Retaining Wall																			
Backfilling																			
Jack-Up Box Outlet (CHI25 - CHI75)																			
Excavation																			
Retaining Wall																			
Basematt																			
Tie-In Box Outlet																			
Excavation																			
Retaining Wall																			
Backfilling																			
Pipe/Manure/Box - Box (CHI50 - CHI75)																			
Basematt/Manure/Box																			
Excavation (CHI75 - CHI9)																			
Low Flow Diversion Pipes and Box																			
Backfilling/Channel Lining																			
Backfilling/Channel Lining																			
Low Flow Diversion Pipes (CHI175 - CHI80)																			
Excavation (CHI175 - CHI80)																			
Backfilling																			
Backfilling/Channel Lining																			
Low Flow Diversion Channel																			
Construction of Gabion Channel (8ft to 10ft)																			
Box Culvert LIT2																			
Box Culvert LIT3																			
Tai Tai Tong River																			
Wearing of Roadway - O/S																			
Wearing of Roadway - Mid Section																			
Low Flow Diversion Channel																			
U-channel																			
Retaining Wall																			

40 4000' 1/2" 1/4" 1/8" 1/16" 1/32" 1/64" 1/128"

DEPARTMENT OF WATER RESOURCES AND ENVIRONMENT
 SOUTH AFRICA
 NATIONAL WATER RESEARCH INSTITUTE
 WATER MANAGEMENT AND RESEARCH
 WATER MANAGEMENT DIVISION

PRELIMINARY CONSTRUCTION PROGRAMME
 PRELIMINARY CONSTRUCTION PROGRAMME
Mercant & Eddy Ltd
 PROJECT NUMBER: P/03/2009

1-2
 PRELIMINARY
 PRELIMINARY CONSTRUCTION PROGRAMME

NOTES :
1. ALL LEVELS ARE IN METRES ABOVE P.D.H.K.,
2. ALL GRIDS REFER TO HONG KONG 1980 GRID.

LEGENDS :

- SITE BOUNDARIES
- ▨ PORTION D1 - PAK NGAM BEIANG
- ▧ PORTION D2 - LUNG TSUI TAI LAI
- ▦ PORTION D3 - LUNG TSUI TAI (B)
- ▤ PORTION D4 - TAI TEI TONG RIVER
- ▣ PORTION D5 - LUK TEI TONG
- ▢ PORTION D6 - FUI O
- ▣ PORTION D7 - LO UK TSEN
- ▣ PORTION D8 - CHEUNG SHIA SHEUNG YEHSEN
- ▣ PORTION D9 - EMERGENCY VEHICULAR ACCESS (EVA) AT HUI 'N'

NO.	DATE	BY	FOR
1	10 OCT 2006	H. T. CHAN	PRELIMINARY DESIGN
2	12 FEB 2006	H. T. CHAN	FINAL DESIGN
3	13 MAR 2006	B. D. CHAN	REVISED DESIGN
4	10 MAY 2007	W. H. CHAN	REVISED DESIGN
5	17 MAY 2007	T. Y. CHAN	REVISED DESIGN
6	17 MAY 2007	T. Y. CHAN	REVISED DESIGN

DESIGNER: H. T. CHAN 17 MAY 2007
DRAWN: B. D. CHAN 13 MAR 2006
CHECKED: W. H. CHAN 10 MAY 2007
APPROVED: T. Y. CHAN 17 MAY 2007

CONTRACT NO: DC/2006/11

FILE NO: DP/08/4128CD

PROJECT NO: 128CD

CONTRACT: DRAINAGE IMPROVEMENT IN SOUTHERN LANTAU

DRAINAGE IMPROVEMENT IN SOUTHERN LANTAU


DRAWING NO: 1114

SCALE: 1:2000

SHEET 1 OF 23

COPYRIGHT RESERVED

DRAINAGE PROJECTS DIVISION
DRAINAGE SERVICES DEPARTMENT
GOVERNMENT OF THE HONG KONG SPECIAL ADMINISTRATIVE REGION



Vertical text on the right margin: 81700, 81500, 81300, 81100, 61100, 61300, 61500. Horizontal text at the bottom: 81400 N, 81500 N, 81600 N, 81700 N, 61100 E, 61300 E, 61500 E. Vertical text on the far right: comments\user\workspaces\DC_2006_11\Drawn (C:\Program Files\Autodesk\MapInfo 10.0\MapInfo Software\MapInfo\MapInfo.exe) 17-05-2007 14:00:00

Appendix B Key Personal Contact information chart

Organization Name	Role	Title	Name	Telephone	Fax Number
Drainage Service Department	Project Proponent	Engineering Representative	Mr. Chan Wai Hong	2594 7464	2827 8700
Allied Environmental Consultants Limited	Independent Environmental Checker (IEC)	Principal Consultant	Ms. Claudine Lee	2815 7028	2815 5399
Yick-Hing Construction Company Limited	Main Contractor	Senior Project Manager	Mr. Liu Kai Choi	2394 4988	2787 4890
Environmental Pioneers & Solutions Limited	Environmental Team (ET)	Environmental Team Leader	Ms. Patricia Chung	2185 0123	2856 2010

Appendix C

Calibration Certificates for Measuring Equipments



Report for Calibration of Hand-held Water Quality Meter WQC-24

Calibration Reference No. : GCE/CAL/2009/MW/WQM/C1

Client : ENVIRONMENTAL PIONEER AND SOLUTION LIMITED

Equipment No. : WQC-24 Location : Mui Wo Site

Manufacturer : DKK-TOA Serial No.: 617892

Calibration Date : 26 to 28-02-2009 Due Date : 26-05-2009

Criterion: (Repeatabilty, Linearity)

- pH : Both within ± 0.05 pH
- Dissolved oxygen : Both within ± 0.1 mg/L
- Electric conductivity : Both within $\pm 1\%$ FS
- Turbidity : Repeatability : within $\pm 3\%$ FS
- Temperature : Repeatability $\pm 0.25^\circ\text{C}$; Linearity $\pm 0.5^\circ\text{C}$; (Ambient 5~45 $^\circ\text{C}$)

Electric Conductivity (Salinity converted from EC):

(Reference : APHA 20ed 2510 B, ISO 7888 - 1985 (E) and DKK-TOA Hand-held Water Quality Meter WQC-24 Instruction Manual)

Concentration of KCl Standard Solution (M)	Reference conductivity value at 25.0 $^\circ\text{C}$	Indicated value by meter	Linearity (R^2)
0	0.0 mS/m*	0.0 mS/m	0.9996
0.001	14.7 mS/m	14.5 mS/m	
0.005	71.8 mS/m	71.2 mS/m	
0.01	0.141 S/m	0.139 S/m	
0.05	0.667 S/m	0.664 S/m	
0.1	1.29 S/m	1.28 S/m	Acceptance Criterion
0.5	5.87 S/m	5.85 S/m	$R^2 > 0.995$
Repeatability	1 st time	0.00 , 5.85 S/m	-
	2 nd time	0.00 , 5.85 S/m	
	3 rd time	0.00 , 5.85 S/m	
	0.00 , 5.85 S/m	0.00 , 0.00	

* 1 S/m = 10^4 $\mu\text{mhos/cm}$ = 10^3 mS/m

Remark: For repeatability, the maximum difference from the average value of 3 measurements was taken.



Dissolved Oxygen:

(Reference : APHA 20ed 4500-O B&C, ISO 5814:1990(E) and DKK-TOA Hand-held Water Quality Meter WQC-24 Instruction Manual)

DO value evaluated by Iodometric Method (mg/L)	Indicated value by meter (mg/L)	Linearity (R^2)	
0.00	0.00	0.9997	
4.21	4.27		
6.42	6.56		
8.77	8.90		
10.52	10.64	Acceptance Criterion	
13.73	13.68	$R^2 > 0.995$	
Repeatability	1 st time	0.00 , 8.90	-
	2 nd time	0.00 , 8.91	
	3 rd time	0.00 , 8.88	
	0.00 , 8.77	0.00 , 0.03	

Remark: For repeatability, the maximum difference from the average value of 3 measurements was taken.

pH Value:

(Reference : APHA 20ed 4500-H⁺ B, ISO 10523:1994(E) and DKK-TOA Hand-held Water Quality Meter WQC-24 Instruction Manual)

Calibration pH buffer (25°C)	Input value (pH buffer) (25°C)	Indicated pH value by meter (25°C)	Linearity (R^2)
pH = 1.67	1.67	1.69	1.0000
pH = 6.86	4.00	4.02	
pH = 7.42	7.00	7.02	
pH = 9.18	10.00	10.05	Acceptance Criterion
pH = 12.45	12.45	12.50	$R^2 > 0.995$
Repeatability	1 st time	4.01 , 10.05	-
	2 nd time	4.01 , 10.05	
	3 rd time	4.01 , 10.04	
	pH 4.00 , 10.00	0.00 , 0.01	

Remark: For repeatability, the maximum difference from the average value of 3 measurements was taken.



Temperature:

(Reference : APHA 20ed 2550 B, In-house method and DKK-TOA Hand-held Water Quality Meter WQC-24 Instruction Manual)

Setting Temperature (°C)	Indicated value by meter (°C)		Linearity
5.0	5.2		R ² = 0.9998 And SD = ± 0.16°C
15.0	15.4		
25.0	25.5		
35.0	35.3		
45.0	45.2		Acceptance Criterion R ² > 0.995 and within ± 5°C
55.0	55.6		
Repeatability	1 st time	5.2 , 55.7	
	2 nd time	5.2 , 55.6	
	3 rd time	5.1 , 55.5	
	5.0 , 55.0	0.1 , 0.2	

Remark: For repeatability, the maximum difference from the average value of 3 measurements was taken.


Turbidity:

(Reference : APHA 20ed 2130 B and DKK-TOA Hand-held Water Quality Meter WQC-24 Instruction Manual)

Formazin Standards (NTU)	Indicated value by meter (NTU)		Linearity (R ²)
0.0	0.2		1.0000
20.0	19.4		
100.0	102.3		
400.0	403.6		Acceptance Criterion R ² > 0.995
800.0	804.7		
Repeatability	1 st time	0.3 , 805.0	
	2 nd time	0.3 , 804.7	
	3 rd time	0.3 , 804.6	
	0.0 , 800.0	0.0 , 0.4	

Remark: For repeatability, the maximum difference from the average value of 3 measurements was taken.

Comments : Pass, comply with the criteria.

Tested by : Ho Tin Kau Certified by : 
 Gu Chin
 Chemist

Checked by : Gu Chin Date : 28-2-2009



綜合試驗有限公司
SOILS & MATERIALS ENGINEERING CO., LTD.

G/F, 9/F, 12/F, 13/F. & 20/F, Leader Centre, 37 Wong Chuk Hang Road, Aberdeen, Hong Kong.
香港黃竹坑道37號利達中心地下, 9樓, 12樓, 13樓及20樓
E-mail: smec@cigismec.com Website: www.cigismec.com

Tel : (852) 2873 6860
Fax : (852) 2555 7533



CERTIFICATE OF CALIBRATION

D094

Certificate No.: 09CA0102 01-01 Page 1 of 2

Item tested

Description:	Sound Level Meter (Type I)	,	Microphone
Manufacturer:	ACO, Japan	,	ACO, Japan
Type/Model No.:	6224	,	7146
Serial/Equipment No.:	060166	,	34733
Adaptors used:	-	,	-

Item submitted by

Customer Name: Geotechnics & Concrete Engineering (H.K.) Ltd.
Address of Customer: G/F., 6 Ko Shan Road, Hung Hom, Kowloon, Hong Kong
Request No.: -
Date of request: 30-12-2008

Date of test: 02-01-2009

Reference equipment used in the calibration

Description:	Model:	Serial No.	Expiry Date:	Traceable to:
Multi function sound calibrator	B&K 4226	2288444	11-01-2009	CIGISMEC
Signal generator	DS 360	33873	12-06-2009	CEPREI
Signal generator	DS 360	61227	18-07-2009	CEPREI

Ambient conditions

Temperature: 23 ± 2 °C
Relative humidity: 55 ± 15 %
Air pressure: 1010 ± 15 hPa

Test specifications

- 1, The Sound Level Meter has been calibrated in accordance with the requirements as specified in BS 7580: Part 1: 1997 and the lab calibration procedure SMTP004-CA-152.
- 2, The electrical tests were performed using an electrical signal substituted for the microphone which was removed and replaced by an equivalent capacitance within a tolerance of ±20%.
- 3, The acoustic calibration was performed using an B&K 4226 sound calibrator and corrections was applied for the difference between the free-field and pressure responses of the Sound Level Meter.

Test results

This is to certify that the Sound Level Meter conforms to BS 7580: Part 1: 1997 for the conditions under which the test was performed.

Details of the performed measurements are presented on page 2 of this certificate.


Actual Measurement data are documented on worksheets.

Approved Signatory:

Huang Jian Min/Feng Jun Qi

Date: 02-01-2009

Company Chop:



Comments: The results reported in this certificate refer to the condition of the instrument on the date of calibration and carry no implication regarding the long-term stability of the instrument.



CERTIFICATE OF CALIBRATION

(Continuation Page)

D094

Certificate No.: 09CA0102 01-01

Page 2 of 2

1, Electrical Tests

The electrical tests were performed using an equivalent capacitance substituted for the microphone. The results are given in below with test status and the estimated uncertainties. The "Pass" means the result of the test is inside the tolerances stated in the test specifications. The "-" means the result of test is outside these tolerances.

Test:	Subtest:	Status:	Uncertainty (dB) / Coverage Factor	
Self-generated noise	A	Pass	0.3	
	C	Pass	1.0	2.1
	Lin	Pass	1.5	2.2
Linearity range for Leq	At reference range, Step 5 dB at 4 kHz	Pass	0.3	
	Reference SPL on all other ranges	Pass	0.3	
	2 dB below upper limit of each range	Pass	0.3	
	2 dB above lower limit of each range	Pass	0.3	
		Pass	0.3	
Linearity range for SPL	At reference range, Step 5 dB at 4 kHz	Pass	0.3	
	A	Pass	0.3	
	C	Pass	0.3	
Frequency weightings	Lin	Pass	0.3	
	Single Burst Fast	Pass	0.3	
	Single Burst Slow	Pass	0.3	
Time weightings	Single 100µs rectangular pulse	N/A	N/A	
Peak response	Crest factor of 3	Pass	0.3	
R.M.S. accuracy	Single burst 5 ms at 2000 Hz	Pass	0.3	
Time weighting I	Repeated at frequency of 100 Hz	Pass	0.3	
	1 ms burst duty factor 1/10 ³ at 4kHz	Pass	0.3	
Time averaging	1 ms burst duty factor 1/10 ⁴ at 4kHz	Pass	0.3	
	Single burst 10 ms at 4 kHz	Pass	0.4	
Pulse range	Single burst 10 ms at 4 kHz	Pass	0.4	
Sound exposure level	SPL	Pass	0.3	
Overload Indication	Leq	Pass	0.4	

2, Acoustic tests

The complete sound level meter was calibrated on the reference range using a B&K 4226 acoustic calibrator with 1000Hz and SPL 94 dB. The sensitivity of the sound level meter was adjusted. The test result at 125 Hz and 8000 Hz are given in below with test status and the estimated uncertainties.

Test:	Subtest	Status	Uncertainty (dB) / Coverage Factor	
Acoustic response	Weighting A at 125 Hz	Pass	0.3	
	Weighting A at 8000 Hz	Pass	0.5	

3, Response to associated sound calibrator

N/A

The uncertainties have been calculated in accordance with the ISO Publication "Guide to the expression of uncertainty in measurement", and gives an interval estimated to have a level of confidence of 95 %. A coverage factor of 2 is assumed unless explicitly stated.

- End -

Calibrated by: G.Y. Fung
Date: 02-01-2009

Checked by: 
Date: 02-01-2009

The standard(s) and equipment used in the calibration are traceable to national or international recognised standards and are calibrated on a schedule to maintain the required accuracy level.



綜合試驗有限公司
SOILS & MATERIALS ENGINEERING CO., LTD.

G/F, 9/F, 12/F, 13/F. & 20/F, Leader Centre, 37 Wong Chuk Hang Road, Aberdeen, Hong Kong.
香港黃竹坑道37號利達中心地下, 9樓, 12樓, 13樓及20樓
E-mail: smec@cigismec.com Website: www.cigismec.com

Tel : (852) 2873 6860
Fax : (852) 2555 7533



CERTIFICATE OF CALIBRATION

2095

Certificate No.: 09CA0102 01-02 Page: 1 of 2

Item tested

Description: Acoustical Calibrator (Class 1)
Manufacturer: Castle Group Ltd.
Type/Model No.: GA607
Serial/Equipment No.: 039543
Adaptors used: -

Item submitted by

Customer: Geotechnics & Concrete Engineering (H.K.) Ltd.
Address of Customer: G/F., 6 Ko Shan Road, Hung Hom, Kowloon, Hong Kong
Request No.: -
Date of request: 30-12-2008

Date of test: 02-01-2009

Reference equipment used in the calibration

Description:	Model:	Serial No.	Expiry Date:	Traceable to:
Lab standard microphone	B&K 4180	2412857	29-06-2009	SCL
Preamplifier	B&K 2673	2239857	02-12-2009	CEPREI
Measuring amplifier	B&K 2610	2346941	03-12-2009	CEPREI
Signal generator	DS 360	61227	18-07-2009	CEPREI
Digital multi-meter	34401A	US36087050	03-12-2009	CIGISMEC
Audio analyzer	8903B	GB41300350	27-11-2009	CEPREI
Universal counter	53132A	MY40003662	11-07-2009	CEPREI

Ambient conditions



Temperature: 22 ± 1 °C
Relative humidity: 55 ± 10 %
Air pressure: 1010 ± 15 hPa

Test specifications

- The Sound Calibrator has been calibrated in accordance with the requirements as specified in IEC 60942 1997 Annex B and the lab calibration procedure SMTP004-CA-156.
- The calibrator was tested with its axis vertical facing downwards at the specific frequency using insert voltage technique.
- The results are rounded to the nearest 0.01 dB and 0.1 Hz and have not been corrected for variations from a reference pressure of 1013.25 hectoPascals as the maker's information indicates that the instrument is insensitive to pressure changes.

Test results

Details of the performed measurements are presented on page 2 of this certificate.

Approved Signatory:  Date: 02-01-2009 Company Chop: 

Comments: The results reported in this certificate refer to the condition of the instrument on the date of calibration and carry no implication regarding the long-term stability of the instrument.

Appendix D1 Plant species recorded at Pak Ngan Heung River (N)

Species	Habit	Native	Relative	Occurrence	
			Abundance	PNH3	PNH4
<i>Acacia confusa</i>	tree	no	occasional		+
<i>Acorus gramineus</i>	herb	yes	scarce		+
<i>Acronychia pedunculata</i>	tree	yes	scarce		
<i>Ageratum conyzoides</i>	herb	yes	scarce	+	
<i>Alangium chinensis</i>	tree	yes	scarce		+
<i>Alocasia macrorrhiza</i>	herb	yes	occasional	+	+
<i>Aporosa dioica</i>	tree	yes	occasional	+	+
<i>Ardisia crenata</i>	shrub	yes	occasional	+	+
<i>Atalantia buxifolia</i>	tree	yes	scarce		+
<i>Bamboo</i>	herb	-	scarce	+	
<i>Bidens pilosa</i>	herb	no	scarce	+	
<i>Bischofia javanica</i>	herb	yes	scarce	+	
<i>Caryota mitis</i>	herb	yes	scarce		+
<i>Celtis sinensis</i>	tree	yes	occasional	+	+
<i>Celtis timorensis</i>	tree	yes	scarce		+
<i>Christella parasitica</i>	fern	yes	occasional	+	+
<i>Cleistocalyx operculata</i>	tree	yes	occasional	+	+
<i>Conyza canadensis</i>	herb	no	scarce	+	+
<i>Cyperus sp.</i>	herb	-	scarce	+	
<i>Desmos chinensis</i>	shrub	yes	occasional	+	
<i>Dimocarpus longan</i>	tree	no	occasional		+
<i>Elephantopus tomentosa</i>	herb	yes	scarce		+
<i>Embelia ribes</i>	climber	yes	scarce		+
<i>Eupatorium catarium</i>	herb	no	scarce	+	
<i>Ficus hispida</i>	tree	yes	common		+
<i>Ficus superba</i>	tree	yes	occasional		+
<i>Garcinia oblongifolia</i>	tree	yes	occasional		+
<i>Glochidion puberum</i>	shrub	yes	scarce	+	
<i>Hedychium coronarium</i>	herb	no	scarce		+
<i>Hedyotis auricularia</i>	herb	yes	scarce		+
<i>Hedyotis hedyotideia</i>	herb	yes	scarce		+
<i>Lemna minor</i>	herb	yes	common	+	+
<i>Leucaena leucocephala</i>	tree	no	scarce		+

Species	Habit	Native	Relative	Occurrence	
			Abundance	PNH3	PNH4
<i>Liriope spicata</i>	herb	yes	scarce		+
<i>Litsea glutinosa</i>	tree	yes	occasional		+
<i>Litsea rotundifolia</i>	shrub	yes	scarce	+	
<i>Lygodium japonicum</i>	fern	yes	scarce	+	+
<i>Macaranga tanarius</i>	tree	yes	occasional	+	+
<i>Mallotus paniculatus</i>	tree	yes	scarce	+	
<i>Microcos paniculata</i>	tree	yes	scarce		+
<i>Microstegium ciliatum</i>	grass	yes	common	+	+
<i>Mikania micrantha</i>	climber	no	common	+	+
<i>Millettia nitida</i>	climber	yes	scarce	+	
<i>Mimosa pudica</i>	herb	yes	scarce	+	
<i>Murraya paniculata</i>	shrub	no	scarce	+	
<i>Musa paradisiaca</i>	tree	no	scarce	+	
<i>Mussaenda erosa</i>	shrub	yes	scarce	+	
<i>Oxalis corymbosa</i>	herb	yes	scarce		+
<i>Panicum maximum</i>	grass	no	common		+
<i>Phyllanthus urinaria</i>	herb	yes	scarce	+	+
<i>Pilea microphylla</i>	herb	no	occasional	+	+
<i>Plantago major</i>	herb	yes	scarce		+
<i>Pogonatherum crinitum</i>	grass	yes	scarce		+
<i>Polygonum barbatum</i>	herb	yes	scarce	+	
<i>Polygonum chinense</i>	herb	yes	occasional	+	
<i>Polygonum sp.</i>	herb	yes	scarce	+	
<i>Psychotria asiatica</i>	shrub	yes	common	+	+
<i>Pueraria phaseoloides</i>	climber	yes	occasional	+	+
<i>Sageretia thea</i>	climber	yes	occasional		+
<i>Sida rhombifolia</i>	herb	yes	scarce		+
<i>Solanum nigrum</i>	herb	no	scarce		+
<i>Sporobolus fertilis</i>	grass	yes	scarce		+
<i>Stephania longa</i>	climber	yes	scarce		+
<i>Sterculia lanceolata</i>	tree	yes	common	+	+
<i>Syngonium podophyllum</i>	climber	no	occasional	+	
<i>Syzygium jambos</i>	tree	no	common	+	+
<i>Syzygium levinei</i>	tree	yes	scarce	+	
<i>Urena lobata</i>	herb	yes	scarce		+

			Relative	Occurrence	
Species	Habit	Native	Abundance	PNH3	PNH4
<i>Uvaria microcarpa</i>	shrub	yes	occasional		+
<i>Wedelia trilobata</i>	climber	no	scarce	+	+
<i>Zanthoxylum avicennae</i>	tree	yes	scarce		+

Appendix D2 Plant species recorded at Pak Ngan Heung River (S)

Species	Habit	Native	Relative	Occurrence	
			Abundance	PNH1	PNH2
<i>Acacia confusa</i>	tree	no	occasional	+	
<i>Acanthus ilicifolius</i>	shrub	yes	scarce	+	
<i>Acrostichum aureum</i>	fern	yes	scarce	+	
<i>Celtis sinensis</i>	tree	yes	occasional	+	
<i>Clerodendrum inerme</i>	shrub	yes	occasional	+	
<i>Dendrotrophe frutescens</i>	climber	yes	scarce	+	
<i>Ficus microcarpa</i>	tree	yes	scarce		+
<i>Ficus superba</i>	tree	yes	occasional		+
<i>Ipomoea cairica</i>	climber	yes	occasional		+
<i>Kandelia obovata</i>	shrub	yes	scarce	+	
<i>Melaleuca quinquenervia</i>	tree	no	common	+	
<i>Morus alba</i>	tree	no	scarce		+
<i>Neyraudia reynaudiana</i>	grass	yes	occasional	+	
<i>Panicum maximum</i>	grass	no	common	+	+
<i>Phyllanthus urinaria</i>	shrub	yes	common		+
<i>Sapium sebiferum</i>	tree	yes	occasional		+
<i>Wedelia triloba</i>	climber	no	occasional	+	+
<i>Wollastonia biflora</i>	climber	yes	occasional	+	

Appendix D3 Plant species recorded at Luk Tei Tong River

Species	Habit	Native	Relative	Occurrence				
			Abundance	LLT1	LLT2	LLT3	LLT4	LLT5
<i>Acanthus ilicifolius</i>	shrub	yes	common	+	+			
<i>Acrostichum aureum</i>	fern	yes	scarce					+
<i>Aegiceras corniculatum</i>	shrub	yes	scarce	+	+			
<i>Bougainvillea spectabilis</i>	climber	no	scarce	+				
<i>Bridelia tomentosa</i>	tree	yes	occasional	+				
<i>Celtis sinensis</i>	tree	yes	scarce	+	+	+		
<i>Clerodendrum inerme</i>	shrub	yes	abundant	+	+		+	
<i>Cyperus malaccensis</i>	sedge	yes	occasional		+			
<i>Excoecaria agallocha</i>	shrub	yes	common	+	+			
<i>Ficus microcarpa</i>	tree	yes	scarce			+		
<i>Ficus superba</i>	tree	yes	occasional	+				
<i>Fimbristylis ferruginea</i>	sedge	yes	occasional		+		+	
<i>Hibiscus tiliaceus</i>	tree	yes	abundant	+	+		+	
<i>Kandelia obovata</i>	tree	yes	common	+	+			
<i>Leucaena leucocephala</i>	tree	no	occasional	+				
<i>Litsea glutinosa</i>	tree	yes	scarce		+	+		
<i>Neyraudia reynaudiana</i>	grass	yes	occasional	+		+	+	+
<i>Panicum maximum</i>	grass	no	common	+		+		
<i>Paspalum paspaloides</i>	grass	no	occasional		+			
<i>Premna serratifolia</i>	tree	yes	scarce		+			
<i>Saccharum arundinaceum</i>	grass	yes	scarce	+				
<i>Scolopia chinensis</i>	tree	yes	scarce				+	
<i>Terminalia catappa</i>	tree	no	scarce		+			
<i>Toxocarpus wightianus</i>	climber	yes	scarce		+			
<i>Wikstroemia indica</i>	shrub	yes	scarce				+	
<i>Wollastonia biflora</i>	climber	yes	occasional	+	+			

Appendix D4

Ecological Water Monitoring Results (on-site measurements)

Environmental Pioneers & Solutions Limited
Ecological Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 2009/4/9

Weather Condition: Sunny

Monitoring Location	WE1			WE2			WE3			WE4			WE5			WE6		
Time (hhmm)	1120			1206			1215			1235			1150			1135		
Tide Mode	ebb			ebb			ebb			ebb			ebb			ebb		
River Condition	Normal			Normal			Normal			Normal			Normal			Normal		
Water Depth (m)	< 1.0			< 1.0			< 1.0			< 1.0			< 1.0			< 1.0		
pH value	6.63			7.33			7.68			7.35			7.26			5.87		
Temperature (oC)	20.8			22.0			22.5			22.7			22.1			20.9		
Salinity (ppt)	0.0			7.1			14.4			14.8			15.1			0.0		
Conductivity (ms/m)	8.0			1240.0			2380.0			2460.0			2460.0			6.0		
Water flow (m/s)	0.000			0.050			0.045			0.060			0.100			0.000		
Turbidity (NTU)	2.3	2.4	Average	4.1	4.2	Average	10.3	10.5	Average	8.7	8.8	Average	7.5	7.3	Average	0.0	0.0	Average
			2.35						4.15						10.40			
DO (mg/l)	7.33	7.32	Average	8.65	8.62	Average	9.46	9.46	Average	8.80	8.80	Average	8.13	8.11	Average	7.44	7.46	Average
			7.33						8.64						9.46			
DO Saturation (%)	82	82	Average	103	103	Average	119	119	Average	112	112	Average	102	102	Average	84	84	Average
			82						103						119			

Name
Prepared By: Jimmy Cheng

Signature


Date
2009/4/9

remark or observation: _____

Appendix D5

Ecological Water Monitoring Results (lab report)



TEST SUMMARY ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC090400062 Date of Issue : 15-03-2009

Client* : Environmental Pioneers & Solutions Limited Date Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 09-04-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 14-04-2009

GCE Serial No. : WQM042009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	485	482	0.6	27.7
Acceptance Criteria			< 2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ± 5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	WE1	WE1 Duplicate	WE2	WE2 Duplicate	WE3	WE3 Duplicate		
	Sampling Date/Time	09 Apr. 2009 / 11:20		09 Apr. 2009 / 12:06		09 Apr. 2009 / 12:15			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	2.1	1.9	6.5	6.5	9.5	9.9	


TEST RESULTS	Sample ID	WE4	WE4 Duplicate	WE5	WE5 Duplicate	WE6	WE6 Duplicate		
	Sampling Date/Time	09 Apr. 2009 / 12:35		09 Apr. 2009 / 11:50		09 Apr. 2009 / 11:35			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	7.6	7.5	8.9	9.2	< 1.0	< 1.0	

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : Location M1 & WE3 and Location M3 & WE4 are the same location.

----- End -----

Tested By : LI YUKE Approved Signatory : 
 Name : GU CHIN
 Checked By : GU CHIN Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Report No. : GCC090400151 Date of Issue : 27-04-2009

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 09-04-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 24-04-2009

GCE Serial No. : WQM042009 Sampling Date* : 09-04-2009 / 11:20 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE1

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour	TCU	APHA 20ed 2120 B
Turbidity	NTU	APHA 20ed 2130 B
Conductivity at 25°C	µS/cm	APHA 20ed 2510 B
Salinity	g/L	APHA 20ed 2520 B
Nitrogen (Ammonia)	mg/L	APHA 20ed 4500-NH ₃ D
		APHA 20ed 4500-NH ₃ E
		APHA 18ed 4500-NH ₃ C
Nitrogen (Nitrate)	mg/L	APHA 20ed 4500-NO ₃ ⁻ E
Phosphorus	mg/L	APHA 20ed 4500-P D
Biochemical Oxygen Demand (BOD ₅)	mg/L	APHA 20ed 5210 B
Chemical Oxygen Demand (COD)	mg/L	APHA 20ed 5220 D
Total Suspended Solid	mg/L	APHA 20ed 2540 D


* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 April 2009.

REMARKS : Sample Location WE1.

----- End -----

Tested By : T.W. Lam, K.L. Fong Certified By : 
 Name : Gu Chin
 Checked By : Gu Chin Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Report No. : GCC090400177 Date of Issue : 27-04-2009

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 09-04-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 24-04-2009

GCE Serial No. : WQM042009 Sampling Date* : 09-04-2009 / 12:06 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE2

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	0.31
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.29
Phosphorus mg/L	APHA 20ed 4500-P D	0.12
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	3
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--


* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 April 2009.

REMARKS : Sample Location WE2.

----- End -----

Tested By : T.W. Lam, K.L. Fong Certified By : 
 Name : Gu Chin
 Checked By : Gu Chin Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Page 1 of 1

Report No. : GCC090400169 Date of Issue : 27-04-2009

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 09-04-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 24-04-2009

GCE Serial No. : WQM042009 Sampling Date* : 09-04-2009 / 11:20 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE1 Duplicate

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	0.04
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.07
Phosphorus mg/L	APHA 20ed 4500-P D	0.04
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	2
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--


* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 April 2009.

REMARKS : Sample Location WE1.

----- End -----

Tested By : T.W. Lam, K.L. Fong Certified By : 
 Name : Gu Chin
 Checked By : Gu Chin Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Page 1 of 1

Report No. : GCC090400185

Date of Issue : 27-04-2009

Client* : Environmental Pioneers & Solutions Limited

Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon.

Date Started : 09-04-2009

W.O. No.* : --

Contract No.* : --

Date Completed : 24-04-2009

GCE Serial No. : WQM042009

Sampling Date* : 09-04-2009 / 12:06

Sample Type* : River Water

GCE Reg. No. : GCE 081096

Test Unit No. : CH 08258

Sample I.D.* : WE2 Duplicate

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	0.31
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.29
Phosphorus mg/L	APHA 20ed 4500-P D	0.12
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	3
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 April 2009.

REMARKS : Sample Location WE2.

----- End -----

Tested By : T.W. Lam, K.L. Fong

Certified By

Name

Post

Gu Chin

Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Report No. : GCC090400193 Date of Issue : 27-04-2009

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 09-04-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 24-04-2009

GCE Serial No. : WOM042009 Sampling Date* : 09-04-2009 / 12:15 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE3

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	0.14
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.27
Phosphorus mg/L	APHA 20ed 4500-P D	0.09
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	3
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--


* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 April 2009.

REMARKS : Sample Location WE3.

----- End -----

Tested By : T.W. Lam, K.L. Fong Certified By : 
 Name : Gu Chin
 Checked By : Gu Chin Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Report No. : GCC090400208 Date of Issue : 27-04-2009

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 09-04-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 24-04-2009

GCE Serial No. : WQM042009 Sampling Date* : 09-04-2009 / 12:15 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE3 Duplicate

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	0.15
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.27
Phosphorus mg/L	APHA 20ed 4500-P D	0.09
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	3
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--


* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 April 2009.

REMARKS : Sample Location WE3.

---- End ----

Tested By : T.W. Lam, K.L. Fong Certified By : 
 Name : Gu Chin
 Checked By : Gu Chin Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Report No. : GCC090400216

Date of Issue : 27-04-2009

Client* : Environmental Pioneers & Solutions Limited

Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon.

Date Started : 09-04-2009

W.O. No.* : --

Contract No.* : --

Date Completed : 24-04-2009

GCE Serial No. : WQM042009

Sampling Date* : 09-04-2009 / 12:35

Sample Type* : River Water

GCE Reg. No. : GCE 081096

Test Unit No. : CH 08258

Sample I.D.* : WE4

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour	TCU	APHA 20ed 2120 B
Turbidity	NTU	APHA 20ed 2130 B
Conductivity at 25°C	µS/cm	APHA 20ed 2510 B
Salinity	g/L	APHA 20ed 2520 B
Nitrogen (Ammonia)	mg/L	APHA 20ed 4500-NH ₃ D
		APHA 20ed 4500-NH ₃ E
		APHA 18ed 4500-NH ₃ C
Nitrogen (Nitrate)	mg/L	APHA 20ed 4500-NO ₃ E
Phosphorus	mg/L	APHA 20ed 4500-P D
Biochemical Oxygen Demand (BOD ₅)	mg/L	APHA 20ed 5210 B
Chemical Oxygen Demand (COD)	mg/L	APHA 20ed 5220 D
Total Suspended Solid	mg/L	APHA 20ed 2540 D

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 April 2009.

REMARKS : Sample Location WE4.

----- End -----

Tested By : T.W. Lam, K.L. Fong

Certified By :

Name

Gu Chin

Checked By : Gu Chin

Post

Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Page 1 of 1

Report No. : GCC090400224

Date of Issue : 27-04-2009

Client* : Environmental Pioneers & Solutions Limited

Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon.

Date Started : 09-04-2009

W.O. No.* : --

Contract No.* : --

Date Completed : 24-04-2009

GCE Serial No. : WOM042009

Sampling Date* : 09-04-2009 / 12:35

Sample Type* : River Water

GCE Reg. No. : GCE 081096

Test Unit No. : CH 08258

Sample I.D.* : WE4 Duplicate

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	0.13
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.39
Phosphorus mg/L	APHA 20ed 4500-P D	0.06
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	2
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 April 2009.

REMARKS : Sample Location WE4.

----- End -----

Tested By : T.W. Lam, K.L. Fong

Certified By

Name

Gu Chin

Checked By : Gu Chin

Post

Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Report No. : GCC090400232 Date of Issue : 27-04-2009

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 09-04-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 24-04-2009

GCE Serial No. : WQM042009 Sampling Date* : 09-04-2009 / 11:50 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE5

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	0.13
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.40
Phosphorus mg/L	APHA 20ed 4500-P D	0.06
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	2
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--


* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 April 2009.

REMARKS : Sample Location WE5.

----- End -----

Tested By : T.W. Lam, K.L. Fong Certified By : 
 Name : Gu Chin
 Checked By : Gu Chin Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Page 1 of 1

Report No. : GCC090400240

Date of Issue : 27-04-2009

Client* : Environmental Pioneers & Solutions Limited

Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon.

Date Started : 09-04-2009

W.O. No.* : --

Contract No.* : --

Date Completed : 24-04-2009

GCE Serial No. : WQM042009

Sampling Date* : 09-04-2009 / 11:50

Sample Type* : River Water

GCE Reg. No. : GCE 081096

Test Unit No. : CH 08258

Sample I.D.* : WE5 Duplicate

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	0.13
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.41
Phosphorus mg/L	APHA 20ed 4500-P D	0.06
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	2
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 April 2009.

REMARKS : Sample Location WE5.

----- End -----

Tested By : T.W. Lam, K.L. Fong

Certified By

Name

Gu Chin

Checked By : Gu Chin

Post

Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Page 1 of 1

Report No. : GCC09000258

Date of Issue : 27-04-2009

Client* : Environmental Pioneers & Solutions Limited

Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon.

Date Started : 09-04-2009

W.O. No.* : --

Contract No.* : --

Date Completed : 24-04-2009

GCE Serial No. : WQM042009

Sampling Date* : 09-04-2009 / 11:35

Sample Type* : River Water

GCE Reg. No. : GCE 081096

Test Unit No. : CH 08258

Sample I.D.* : WE6

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	0.02
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.05
Phosphorus mg/L	APHA 20ed 4500-P D	0.03
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	1
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 April 2009.

REMARKS : Sample Location WE6.

----- End -----

Tested By : T.W. Lam, K.L. Fong

Certified By

Name

Gu Chin

Checked By : Gu Chin

Post

Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Page 1 of 1

Report No. : GCC090400266 Date of Issue : 27-04-2009

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 09-04-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 24-04-2009

GCE Serial No. : WQM042009 Sampling Date* : 09-04-2009 / 11:35 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE6 Duplicate

Description : River Water

DESCRIPTION	TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance	APHA 20ed 2110	--
Odour	APHA 20ed 2150 B	Odour Characteristics : --
		Threshold Odour Number (TON) : --
pH Value at temperature [] °C	APHA 20ed 4500-H ⁺ B	--
Colour TCU	APHA 20ed 2120 B	--
Turbidity NTU	APHA 20ed 2130 B	--
Conductivity at 25°C μS/cm	APHA 20ed 2510 B	--
Salinity g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia) mg/L	APHA 20ed 4500-NH ₃ D	0.02
	APHA 20ed 4500-NH ₃ E	--
	APHA 18ed 4500-NH ₃ C	--
Nitrogen (Nitrate) mg/L	APHA 20ed 4500-NO ₃ ⁻ E	0.05
Phosphorus mg/L	APHA 20ed 4500-P D	0.03
Biochemical Oxygen Demand (BOD ₅) mg/L	APHA 20ed 5210 B	1
Chemical Oxygen Demand (COD) mg/L	APHA 20ed 5220 D	--
Total Suspended Solid mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 09 April 2009.

REMARKS : Sample Location WE6.

----- End -----

Tested By : T.W. Lam, K.L. Fong

Certified By : 

Name : Gu Chin

Checked By : Gu Chin

Post : Chemist

Appendix E

Construction Noise Monitoring Data Sheet



大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N1	N2
Description of Location		Façade	Façade
Date of Monitoring		2009/4/6	
Measurement Start Time (hhmm)		1450	1415
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		SVAN 949	
Calibrator Model/ Identification		SVAN SV 30A	
Wind Speed (m/s)		0.3	0.8
Measurement Results	L90 (dB(A))	43.7	42.2
	L10 (dB(A))	48.8	55.0
	Leq (dB(A))	47.2	52.0
Weather condition:		Cloudy	
Major Construction Noise Source(s) During Monitoring		no construction works are being carried out during measurement.	1. Hammer noise 2. House Keeping noise
Other Noise Source(s) During Monitoring			1. Public noise
Remarks			

Name & Designation

Signature

Date:

Prepared by:

Jimmy Cheng

2009/4/6



大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N3	N4
Description of Location		Freefield	Facade
Date of Monitoring		2009/4/6	
Measurement Start Time (hhmm)		1340	1300
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		SVAN 949	
Calibrator Model/ Identification		SVAN SV 30A	
Wind Speed (m/s)		0.9	0.6
Measurement Results	L90 (dB(A))	43.6	41.7
	L10 (dB(A))	49.5	48.2
	Leq (dB(A))	48.1	46.3
Weather condition:		Cloudy	
Major Construction Noise Source(s) During Monitoring		no construction works are being carried out during measurement.	no construction works are being carried out during measurement.
Other Noise Source(s) During Monitoring		1. Public noise 2. Traffic noise (Bicycles)	1. Public noise
Remarks			

Name & Designation

Signature

Date:

Prepared by:

Jimmy Cheng

2009/4/6



大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N1	N2
Description of Location		Façade	Façade
Date of Monitoring		2009/4/15	
Measurement Start Time (hhmm)		13:35	14:08
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		SVAN 949	
Calibrator Model/ Identification		SVAN SV 30A	
Wind Speed (m/s)		0.7	1.5
Measurement Results	L90 (dB(A))	47.8	50.6
	L10 (dB(A))	55.9	64.0
	Leq (dB(A))	53.0	61.2
Weather condition:		Sunny	
Major Construction Noise Source(s) During Monitoring		1. Excavator noise	1. Excavator noise 2. Hand breaking noise
Other Noise Source(s) During Monitoring			1. Public noise
Remarks			

Name & Designation

Signature

Date:

Prepared by:

Jimmy Cheng

2009/4/15



大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N3	N4
Description of Location		Freefield	Facade
Date of Monitoring		2009/4/15	
Measurement Start Time (hhmm)		13:00	14:42
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		SVAN 949	
Calibrator Model/ Identification		SVAN SV 30A	
Wind Speed (m/s)		1.3	0.9
Measurement Results	L90 (dB(A))	57.3	47.2
	L10 (dB(A))	62.4	61.7
	Leq (dB(A))	61.1	59.0
Weather condition:		Sunny	
Major Construction Noise Source(s) During Monitoring		1. Excavator noise	1. Excavator noise
Other Noise Source(s) During Monitoring		1. Public noise 2. Traffic noise (Bicycle)	1. Public noise
Remarks			

Name & Designation

Signature

Date:

Prepared by:

Jimmy Cheng

2009/4/15



大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N1	N2
Description of Location		Façade	Façade
Date of Monitoring		2009/4/20	
Measurement Start Time (hhmm)		13:40	14:15
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		SVAN 949	
Calibrator Model/ Identification		SVAN SV 30A	
Wind Speed (m/s)		1.0	1.8
Measurement Results	L90 (dB(A))	49.8	47.7
	L10 (dB(A))	59.1	58.3
	Leq (dB(A))	55.7	54.7
Weather condition:		Sunny	
Major Construction Noise Source(s) During Monitoring		1. Excavator noise 2. Concrete Cutting Noise 3. Truck noise	1. Excavator noise
Other Noise Source(s) During Monitoring			1. Public noise
Remarks			

Name & Designation

Signature

Date:

Prepared by:

Jimmy Cheng

2009/4/20



大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N3	N4
Description of Location		Freefield	Facede
Date of Monitoring		2009/4/20	
Measurement Start Time (hhmm)		13:00	14:53
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		SVAN 949	
Calibrator Model/ Identification		SVAN SV 30A	
Wind Speed (m/s)		1.4	1.5
Measurement Results	L90 (dB(A))	54.5	47.3
	L10 (dB(A))	60.6	56.6
	Leq (dB(A))	59.2	53.6
Weather condition:		Sunny	
Major Construction Noise Source(s) During Monitoring		1. Power Generator noise 2. Excavator noise	1. Excavator noise
Other Noise Source(s) During Monitoring		1. Public noise 2. Traffic noise (Bicycle)	1. Public noise
Remarks			

Name & Designation

Signature

Date:

Prepared by:

Jimmy Cheng

2009/4/20



大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N1	N2
Description of Location		Façade	Façade
Date of Monitoring		2009/4/27	
Measurement Start Time (hhmm)		11:24	13:00
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		SVAN 949	
Calibrator Model/ Identification		SVAN SV 30A	
Wind Speed (m/s)		0.5	0.9
Measurement Results	L90 (dB(A))	47.0	42.4
	L10 (dB(A))	58.3	54.0
	Leq (dB(A))	54.7	52.6
Weather condition:		Sunny	
Major Construction Noise Source(s) During Monitoring		1. Excavator noise 2. Power generator noise 3. Hand-held breaking noise	No construction works are being carried out during measurement.
Other Noise Source(s) During Monitoring			1. Public noise
Remarks			

Name & Designation

Signature

Date:

Prepared by:

Jimmy Cheng

2009/4/27



大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N3	N4
Description of Location		Freefield	Facade
Date of Monitoring		2009/4/27	
Measurement Start Time (hhmm)		10:50	13:35
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		SVAN 949	
Calibrator Model/ Identification		SVAN SV 30A	
Wind Speed (m/s)		1.2	0.7
Measurement Results	L90 (dB(A))	47.3	48.7
	L10 (dB(A))	55.1	62.5
	Leq (dB(A))	53.7	58.6
Weather condition:		Sunny	
Major Construction Noise Source(s) During Monitoring		1. Excavator noise 2. Power generator noise	1. Excavator noise
Other Noise Source(s) During Monitoring		1. Public noise 2. Traffic noise (Bicycle)	1. Public noise
Remarks			

Name & Designation

Signature

Date:

Prepared by:

Jimmy Cheng

2009/4/27

Appendix F1

Water Quality

Monitoring Data Sheet

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 1/4/2009

Cloudy

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1700			1650			1642			1710			1600			1610			1622		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			<1			<1			1.1			<1			<1			<1		
pH value	7.80			7.61			7.79			7.96			6.22			5.85			6.99		
Temperature (oC)	22.1			22.1			21.7			22.5			22.1			22.5			21.9		
Salinity (ppt)	19.7			8.3			22.0			22.9			0.0			0.0			14.1		
Turbidity (NTU)	8.9	8.8	Average	7.1	7.1	Average	6.5	6.4	Average	6.6	6.5	Average	0.0	0.0	Average	18.2	18.0	Average	7.0	6.9	Average
			8.9			7.1			6.5			6.6			0.0			18.1			7.0
DO (mg/l)	8.73	8.71	Average	8.61	8.61	Average	8.01	8.01	Average	8.60	8.59	Average	8.05	8.03	Average	8.13	8.10	Average	7.62	7.60	Average
			8.72			8.61			8.01			8.60			8.04			8.12			7.61
DO Saturation (%)	111	111	Average	107	107	Average	105	105	Average	110	110	Average	103	102	Average	105	105	Average	96	96	Average
			111			107			105			110			103			105			96

Name
Prepared By: Jimmy Cheng

Signature


Date
1/4/2009

remark or observation: works are being carried out in the upper river the location C2

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 2/4/2009 Sunny

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1705			1655			1700			1720			1620			1630			1645		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			1.3			< 1			2			< 1			< 1			< 1		
pH value	7.95			7.73			7.89			8.01			5.75			5.87			6.61		
Temperature (oC)	20.0			20.4			20.5			20.1			19.8			21.3			19.8		
Salinity (ppt)	21.1			16.8			23.1			24.3			0.0			0.0			10.5		
Turbidity (NTU)	7.5	7.5	Average	12.8	12.8	Average	13.8	13.8	Average	9.1	9.1	Average	3.3	3.3	Average	7.5	7.5	Average	5.2	5.2	Average
			7.5			12.8			13.8			9.1			3.3			7.5			5.2
DO (mg/l)	8.56	8.56	Average	9.25	9.25	Average	8.36	8.36	Average	8.28	8.28	Average	7.87	7.87	Average	8.22	8.22	Average	3.89	3.89	Average
			8.56			9.25			8.36			8.28			7.87			8.22			3.89
DO Saturation (%)	109	109	Average	115	115	Average	109	109	Average	108	108	Average	90	90	Average	95	95	Average	46	46	Average
			109			115			109			108			90			95			46

Name
Prepared By: Jimmy Cheng

Signature


Date
2/4/2009

remark or observation: Water level is high
works are being carried out in the upper river the location C2

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 6/4/2009

Cloudy

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1105			1110			1115			1045			1125			1135			1145		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	< 1			< 1			< 1			< 1			< 1			< 1			< 1		
pH value	7.04			6.95			6.75			7.51			6.25			5.81			6.77		
Temperature (oC)	21.3			21.0			21.3			21.3			21.9			21.4			20.8		
Salinity (ppt)	2.6			0.5			11.7			20.3			0.0			0.0			2.7		
Turbidity (NTU)	25.9	25.9	Average	10.4	10.4	Average	13.1	13.1	Average	9.2	9.2	Average	4.1	4.1	Average	2.8	2.8	Average	6.9	6.9	Average
			25.9			10.4			13.1			9.2			4.1			2.8			6.9
DO (mg/l)	7.48	7.48	Average	9.14	9.14	Average	6.75	6.75	Average	6.55	6.55	Average	6.79	6.79	Average	8.08	8.08	Average	4.13	4.13	Average
			7.48			9.14			6.75			6.55			6.79			8.08			4.13
DO Saturation (%)	85	85	Average	103	103	Average	84	84	Average	84	84	Average	79	79	Average	91	91	Average	40	40	Average
			85			103			84			84			79			91			40

Name
Prepared By: Jimmy Cheng

Signature


Date
6/4/2009

remark or observation: M2: A high school field trip event was carried out at the point
works are being carried out in the upper river the location C2
sediments & contaminants accumulated in riverbed were brought to the downstream area by steep flow.

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 8/4/2009 Sunny

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1140			1135			1130			1150			1055			1110			1120		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			<1			<1			1.2			<1			<1			<1		
pH value	7.36			7.27			7.07			7.76			5.91			5.68			6.73		
Temperature (oC)	22.6			22.2			22.7			22.5			19.6			22.0			21.7		
Salinity (ppt)	9.6			4.5			20.3			21.5			0.0			0.0			1.3		
Turbidity (NTU)	10.7	10.7	Average	2.5	2.5	Average	5.5	5.5	Average	4.8	4.8	Average	2.3	2.3	Average	2.9	2.9	Average	6.7	6.7	Average
			10.7			2.5			5.5			4.8			2.3			2.9			6.7
DO (mg/l)	9.74	9.74	Average	10.42	10.42	Average	8.23	8.23	Average	8.59	8.59	Average	6.74	6.74	Average	7.86	7.86	Average	4.21	4.21	Average
			9.74			10.42			8.23			8.59			6.74			7.86			4.21
DO Saturation (%)	119	119	Average	123	123	Average	107	107	Average	112	112	Average	74	74	Average	90	90	Average	41	41	Average
			119			123			107			112			74			90			41

Name
Prepared By: Jimmy Cheng

Signature


Date
8/4/2009

remark or observation: works are being carried out in the upper river the location C2

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 9/4/2009 Sunny

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1215			1225			1235			1245			1120			1130			1145		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			<1			<1			1.4			<1			<1			<1		
pH value	7.68			7.54			7.35			7.85			6.63			6.01			6.73		
Temperature (oC)	22.5			2.2			22.7			22.8			20.8			21.6			21.6		
Salinity (ppt)	14.4			7.7			14.8			21.8			0.0			0.0			7.3		
Turbidity (NTU)	10.3	10.5	Average	4.6	4.8	Average	8.7	8.8	Average	11.5	11.4	Average	2.3	2.4	Average	2.8	2.8	Average	7.3	7.3	Average
			10.4			4.7			8.8			11.5			2.4			2.8			7.3
DO (mg/l)	9.46	9.46	Average	10.03	10.03	Average	8.80	8.80	Average	8.26	8.26	Average	7.33	7.32	Average	8.15	8.15	Average	7.01	7.01	Average
			9.46			10.03			8.80			8.26			7.33			8.15			7.01
DO Saturation (%)	119	119	Average	120	120	Average	112	112	Average	109	109	Average	82	82	Average	93	93	Average	83	83	Average
			119			120			112			109			82			93			83

Name
Prepared By: Jimmy Cheng

Signature


Date
9/4/2009

remark or observation: works are being carried out in the upper river the location C2

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 14/4/2009 Sunny

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1540			1510			1530			1550			1440			1450			1500		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	< 1			< 1			< 1			< 1			< 1			< 1			< 1		
pH value	7.87			7.41			7.53			7.95			5.56			5.79			6.33		
Temperature (oC)	27.4			26.2			27.8			27.4			26.5			25.8			27.1		
Salinity (ppt)	13.3			8.5			18.5			23.0			0.0			0.0			4.4		
Turbidity (NTU)	8.8	8.7	Average	5.1	5.2	Average	9.7	9.5	Average	12.7	12.5	Average	2.3	2.3	Average	1.4	1.4	Average	10.0	9.9	Average
			8.8			5.2			9.6			12.6			2.3			1.4			10.0
DO (mg/l)	10.62	10.61	Average	10.41	10.43	Average	9.81	9.80	Average	9.94	9.96	Average	9.27	9.27	Average	8.38	8.40	Average	8.44	8.43	Average
			10.62			10.42			9.81			9.95			9.27			8.39			8.44
DO Saturation (%)	146	146	Average	138	138	Average	140	140	Average	144	144	Average	118	118	Average	105	105	Average	110	110	Average
			146			138			140			144			118			105			110

Name
Prepared By: Jimmy Cheng

Signature


Date
14/4/2009

remark or observation: works are being carried out in the upper river the location C2

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 15/4/2009 Sunny

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1610			1550			1600			1615			1520			1530			1545		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			<1			<1			1.3			<1			<1			<1		
pH value	7.53			7.16			7.33			7.90			5.96			5.84			6.55		
Temperature (oC)	24.8			24.2			25.5			25.3			24.3			24.4			24.8		
Salinity (ppt)	12.0			5.9			19.3			22.0			0.0			0.0			7.7		
Turbidity (NTU)	9.7	9.7	Average	3.5	3.5	Average	10.7	10.7	Average	8.5	8.5	Average	5.6	5.6	Average	1.7	1.6	Average	8.3	8.3	Average
			9.7			3.5			10.7			8.5			5.6			1.7			8.3
DO (mg/l)	8.13	8.13	Average	9.10	9.10	Average	8.03	8.03	Average	8.76	8.76	Average	8.49	8.49	Average	8.47	8.47	Average	7.72	7.72	Average
			8.13			9.10			8.03			8.76			8.49			8.47			7.72
DO Saturation (%)	105	105	Average	112	112	Average	109	109	Average	121	121	Average	102	102	Average	102	102	Average	96	96	Average
			105			112			109			121			102			102			96

Name
Prepared By: Jimmy Cheng

Signature


Date
15/4/2009

remark or observation: works are being carried out in the upper river the location C2

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 17/4/2009 Sunny

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1715			1710			1705			1725			1635			1645			1655		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			<1			<1			1.4			<1			<1			<1		
pH value	7.99			7.18			7.64			8.07			6.46			6.02			6.87		
Temperature (oC)	26.3			25.0			26.5			26.6			25.5			24.6			25.3		
Salinity (ppt)	11.0			2.4			16.6			19.5			0.0			0.0			7.3		
Turbidity (NTU)	10.2	10.2	Average	13.1	13.1	Average	8.9	8.9	Average	8.3	8.3	Average	1.8	1.8	Average	18.8	18.8	Average	6.9	6.9	Average
			10.2			13.1			8.9			8.3			1.8			18.8			6.9
DO (mg/l)	9.83	9.83	Average	8.44	8.44	Average	9.48	9.48	Average	9.58	9.58	Average	7.98	7.98	Average	8.25	8.25	Average	5.77	5.77	Average
			9.83			8.44			9.48			9.58			7.98			8.25			5.77
DO Saturation (%)	130	130	Average	104	104	Average	129	129	Average	133	133	Average	98	98	Average	99	99	Average	71	71	Average
			130			104			129			133			98			99			71

Name
Prepared By: Jimmy Cheng

Signature


Date
17/4/2009

remark or observation: River constrution (demolition to the old bank) near M2 is in works are being carried out in the upper river the location C2

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 20/4/2009 Sunny

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	955			1000			1010			950			1020			1030			1040		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	< 1			< 1			< 1			1.1			< 1			< 1			< 1		
pH value	6.99			6.63			6.66			7.57			6.32			6.03			6.78		
Temperature (oC)	26.9			25.3			27.3			26.9			25.6			25.7			26.1		
Salinity (ppt)	0.6			0.0			6.2			11.1			0.0			0.0			1.3		
Turbidity (NTU)	8.1	8.1	Average	5.0	4.9	Average	13.3	13.3	Average	8.6	8.6	Average	0.0	0.0	Average	135.1	135.1	Average	9.3	9.3	Average
			8.1			5.0			13.3			8.6			0.0			135.1			9.3
DO (mg/l)	8.44	8.44	Average	8.41	8.41	Average	8.21	8.21	Average	7.86	7.86	Average	7.08	7.08	Average	8.27	8.27	Average	6.18	6.18	Average
			8.44			8.41			8.21			7.86			7.08			8.27			6.18
DO Saturation (%)	106	106	Average	103	103	Average	108	108	Average	106	106	Average	87	87	Average	102	102	Average	71	71	Average
			106			103			108			106			87			102			71

Name
Prepared By: Jimmy Cheng

Signature


Date
20/4/2009

remark or observation: works are being carried out in the upper river the location C2

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 22/4/2009

Cloudy

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1050			1055			1100			1040			1110			1120			1130		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	< 1			< 1			< 1			< 1			< 1			< 1			< 1		
pH value	6.85			7.34			6.95			7.58			6.21			6.03			6.48		
Temperature (oC)	22.8			22.6			22.7			23.0			22.8			22.5			22.7		
Salinity (ppt)	2.6			0.4			8.6			16.0			0.1			0.0			0.6		
Turbidity (NTU)	5.9	5.9	Average	8.8	8.8	Average	6.3	6.3	Average	12.8	12.8	Average	0.0	0.0	Average	528.6	528.6	Average	4.1	4.1	Average
			5.9			8.8			6.3			12.8			0.0			528.6			4.1
DO (mg/l)	7.61	7.61	Average	8.54	8.54	Average	6.71	6.71	Average	6.81	6.81	Average	6.37	6.37	Average	7.85	7.85	Average	5.77	5.77	Average
			7.61			8.54			6.71			6.81			6.37			7.85			5.77
DO Saturation (%)	89	89	Average	99	99	Average	82	82	Average	87	87	Average	74	74	Average	89	89	Average	69	69	Average
			89			99			82			87			74			89			69

Name
Prepared By: Jimmy Cheng

Signature


Date
22/4/2009

remark or observation: works are being carried out in the upper river the location C2

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 24/4/2009

Cloudy

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1220			1225			1235			1250			1145			1155			1205		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	< 1			< 1			< 1			< 1			< 1			< 1			< 1		
pH value	6.97			7.22			6.75			7.15			6.38			6.48			6.62		
Temperature (oC)	23.0			22.9			23.3			23.3			21.0			21.8			22.5		
Salinity (ppt)	9.9			2.3			10.9			16.5			0.3			0.3			4.8		
Turbidity (NTU)	2.8	2.8	Average	16.5	16.5	Average	35.1	35.1	Average	12.9	12.9	Average	2.9	2.9	Average	238.2	238.2	Average	7.2	7.2	Average
			2.8			16.5			35.1			12.9			2.9			238.2			7.2
DO (mg/l)	6.48	6.48	Average	7.85	7.85	Average	5.74	5.74	Average	6.68	6.68	Average	7.95	7.95	Average	8.22	8.22	Average	7.22	7.22	Average
			6.48			7.85			5.74			6.68			7.95			8.22			7.22
DO Saturation (%)	80	80	Average	93	93	Average	72	72	Average	85	85	Average	90	90	Average	94	94	Average	86	86	Average
			80			93			72			85			90			94			86

Name
Prepared By: Jimmy Cheng

Signature


Date
24/4/2009

Other construction activities are being carried out in the river upper
 remark or observation: works are being carried out in the upper river the location C2

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 27/4/2009

Sunny

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1430			1435			1440			1420			1448			1455			1505		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	< 1			< 1			< 1			< 1			< 1			< 1			< 1		
pH value	7.14			7.17			7.05			7.48			7.23			6.46			6.65		
Temperature (oC)	23.7			23.5			24.7			24.6			22.9			23.1			23.8		
Salinity (ppt)	8.9			1.6			15.4			8.7			0.0			0.0			2.9		
Turbidity (NTU)	5.6	5.6	Average	63.8	63.8	Average	38.8	38.8	Average	42.7	42.7	Average	0.0	0.0	Average	732.1	732.1	Average	4.3	4.3	Average
			5.6			63.8			38.8			42.7			0.0			732.1			4.3
DO (mg/l)	8.04	8.04	Average	8.39	8.39	Average	7.33	7.33	Average	7.98	7.98	Average	8.41	8.41	Average	8.31	8.31	Average	5.31	5.31	Average
			8.04			8.39			7.33			7.98			8.41			8.31			5.31
DO Saturation (%)	99	99	Average	100	100	Average	96	96	Average	101	101	Average	98	98	Average	97	97	Average	64	64	Average
			99			100			96			101			98			97			64

Name
Prepared By: Jimmy Cheng

Signature


Date
27/4/2009

remark or observation: _____
works are being carried out in the upper river the location C2

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 28/4/2009

Sunny

Monitoring Location	M1		M2		M3		M4		C1		C2		C3						
Time (hhmm)			1540		1550		1603				1515		1525						
Tide Mode	mid-ebb		mid-ebb		mid-ebb		mid-ebb		mid-ebb		mid-ebb		mid-ebb						
River Condition	normal		normal		normal		normal		normal		normal		normal						
Water Depth (m)	<1		<1		<1		1		<1		<1		<1						
pH value			6.85		7.01		7.51				6.71		6.63						
Temperature (oC)			23.7		24.2		24.3				24.3		23.2						
Salinity (ppt)			1.6		13.3		12.1				0.1		3.3						
Turbidity (NTU)			Average	23.5	23.5	Average	13.2	13.2	Average	13.6	13.6	Average	360.5	360.5	Average	5.8	5.8	Average	
			#DIV/0!			23.5		13.2		13.6		360.5		360.5		5.8		5.8	
DO (mg/l)			Average	8.48	8.48	Average	7.14	7.14	Average	8.42	8.42	Average	7.87	7.87	Average	4.11	4.11	Average	
			#DIV/0!			8.48		7.14		8.42		7.87		7.87		4.11		4.11	
DO Saturation (%)			Average	101	101	Average	92	92	Average	108	108	Average	94	94	Average	49	49	Average	
			#DIV/0!			101		92		108		94		94		49		49	

Name
Prepared By: Jimmy Cheng

Signature


Date
28/4/2009

remark or observation: The results are the ad hoc monitoring due to exceedance
works are being carried out in the upper river the location C2

Environmental Pioneers & Solutions Limited
Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 29/4/2009 Sunny

Monitoring Location	M1			M2			M3			M4			C1			C2			C3		
Time (hhmm)	1550			1535			1540			1600			1500			1514			1530		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	< 1			< 1			< 1			1.2			< 1			< 1			< 1		
pH value	7.34			7.05			7.09			7.58			6.55			6.30			6.62		
Temperature (oC)	22.9			23.8			23.6			23.5			23.6			24.5			23.4		
Salinity (ppt)	10.6			4.4			14.4			13.0			0.0			0.0			3.8		
Turbidity (NTU)	5.7	5.7	Average	56.1	56.1	Average	11.8	11.8	Average	8.3	8.3	Average	0.3	0.3	Average	186.7	186.7	Average	12.2	12.2	Average
			5.7			56.1			11.8			8.3			0.3			186.7			12.2
DO (mg/l)	8.72	8.72	Average	8.37	8.37	Average	7.69	7.69	Average	8.35	8.35	Average	7.71	7.71	Average	7.95	7.95	Average	5.18	5.18	Average
			8.72			8.37			7.69			8.35			7.71			7.95			5.18
DO Saturation (%)	108	108	Average	102	102	Average	99	99	Average	106	106	Average	91	91	Average	96	96	Average	62	62	Average
			108			102			99			106			91			96			62

Name
Prepared By: Jimmy Cheng

Signature


Date
29/4/2009

remark or observation: Muddy water is observed at location C2 and M2 due to the construction works are being carried out in the upper river the location C2

Appendix F2

Water Quality

Monitoring Lab report



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Page 1 of 1

Report No. : GCC090400012 Date of Issue : 06-04-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 02-04-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 03-04-2009

GCE Serial No. : WQM042009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	497	489	1.6	26.4
Acceptance Criteria			< 2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	01 Apr 2009 / 16:00		01 Apr 2009 / 16:10		01 Apr 2009 / 16:22			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	1.6	1.8	12.5	12.0	12.1	11.6	

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	01 Apr 2009 / 17:00		01 Apr 2009 / 16:50		01 Apr 2009 / 16:42		01 Apr 2009 / 17:10	
	LOD	Units							
Suspended Solids (SS)	1	mg/L	8.1	8.9	5.5	5.1	11.0	11.1	11.1

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : _____

----- End -----

Tested By : Li Yuke

Approved Signatory : 

Name : GU CHIN

Checked By : GU CHIN

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Page 1 of 1

Report No. : GCC090400020 Date of Issue : 03-04-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 02-04-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 03-04-2009

GCE Serial No. : WQM042009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	495	497	-0.4	21.8
Acceptance Criteria			< 2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	02 Apr 2009 / 16:20		02 Apr 2009 / 16:30		02 Apr 2009 / 16:45			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	1.1	1.0	3.7	3.9	8.1	7.9	

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	02 Apr 2009 / 17:05		02 Apr 2009 / 16:55		02 Apr 2009 / 17:00		02 Apr 2009 / 17:20	
	LOD	Units							
Suspended Solids (SS)	1	mg/L	6.4	6.2	9.1	9.0	12.2	12.1	11.3

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : _____

----- End -----

Tested By : Li Yuke

Approved Signatory : 

Name : GU CHIN

Checked By : GU CHIN

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC090400038 Date of Issue : 15-04-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 06-04-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 07-04-2009

GCE Serial No. : WQM042009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	506	511	-1.0	27.3
Acceptance Criteria			< 2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	06 Apr 2009 / 11:25		06 Apr 2009 / 11:35		06 Apr 2009 / 11:45			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	1.5	2.0	2.3	2.2	8.8	8.6	

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	06 Apr 2009 / 11:05		06 Apr 2009 / 11:10		06 Apr 2009 / 11:15		06 Apr 2009 / 10:45	
	LOD	Units							
Suspended Solids (SS)	1	mg/L	13.2	12.8	5.0	4.8	9.2	9.2	7.4

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : _____

----- End -----

Tested By : LI YUKE

Approved Signatory : 

Checked By : GU CHIN

Name : GU CHIN

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Page 1 of 1

Report No. : GCC090400046 Date of Issue : 15-04-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 08-04-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 09-04-2009

GCE Serial No. : WQM042009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	509	502	1.4	21.9
Acceptance Criteria			< 2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ± 5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	08 Apr 2009 / 10:55		08 Apr 2009 / 11:10		08 Apr 2009 / 11:20			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	3.5	3.1	1.1	1.3	6.5	6.3	

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	08 Apr 2009 / 11:40		08 Apr 2009 / 11:35		08 Apr 2009 / 11:30		08 Apr 2009 / 11:50	
	LOD	Units							
Suspended Solids (SS)	1	mg/L	11.5	11.6	2.7	2.7	7.2	7.6	6.4 6.1

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : _____

----- End -----

Tested By : LI YUKE

Approved Signatory : 

Name : GU CHIN

Checked By : GU CHIN

Post : Chemist



TEST SUMMARY ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC090400054 Date of Issue : 15-03-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 09-04-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 14-04-2009

GCE Serial No. : WQM042009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	485	482	0.6	27.7
Acceptance Criteria			<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	09 Apr. 2009 / 11:20		09 Apr. 2009 / 11:30		09 Apr. 2009 / 11:45			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	2.6	2.8	< 1.0	< 1.0	7.6	7.9	

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	09 Apr. 2009 / 12:15		09 Apr. 2009 / 12:25		09 Apr. 2009 / 12:35		09 Apr. 2009 / 12:45	
	LOD	Units							
Suspended Solids (SS)	1	mg/L	9.5	9.9	2.6	2.8	7.6	7.5	10.1

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : Location M1 & WE3 and Location M3 & WE4 are the same location.

----- End -----

Tested By : LI YUKE

Approved Signatory : 

Checked By : GU CHIN

Name : GU CHIN
 Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Page 1 of 1

Report No. : GCC090400070 Date of Issue : 20-04-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 15-04-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 16-04-2009

GCE Serial No. : WQM042009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	483	486	-0.6	25.4
Acceptance Criteria			<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	14 Apr 2009 / 14:40		14 Apr 2009 / 14:50		14 Apr 2009 / 15:00			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	2.1	1.9	1.1	1.3	8.7	8.4	

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	14 Apr 2009 / 15:40		14 Apr 2009 / 15:10		14 Apr 2009 / 15:30		14 Apr 2009 / 15:50	
	LOD	Units							
Suspended Solids (SS)	1	mg/L	8.5	8.7	2.8	3.0	9.8	9.6	11.5 11.1

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks :

----- End -----

Tested By : LI YUKE

Approved Signatory : 

Checked By : GU CHIN

Name : GU CHIN

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Page 1 of 1

Report No. : GCC090400088 Date of Issue : 20-04-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 16-04-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 16-04-2009

GCE Serial No. : WQM042009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	503	492	2.2	27.0
Acceptance Criteria			<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	15 Apr 2009 / 15:20		15 Apr 2009 / 15:30		15 Apr 2009 / 15:45			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	9.8	10.4	1.6	1.6	6.7	6.3	

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	15 Apr 2009 / 16:10		15 Apr 2009 / 15:50		15 Apr 2009 / 16:00		15 Apr 2009 / 16:15	
	LOD	Units							
Suspended Solids (SS)	1	mg/L	9.3	9.1	2.9	2.9	11.3	11.3	9.8

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks :

----- End -----

Tested By : LI YUKE

Approved Signatory : 

Name : GU CHIN

Checked By : GU CHIN

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Page 1 of 1

Report No. : GCC090400096 Date of Issue : 20-04-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 17-04-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 18-04-2009

GCE Serial No. : WQM042009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	498	492	1.2	24.2
Acceptance Criteria			<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID		C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time		17 Apr 2009 / 16:35		17 Apr 2009 / 16:45		17 Apr 2009 / 16:55			
	LOD	Units								
Suspended Solids (SS)	1	mg/L	1.4	1.6	7.0	7.0	11.7	11.3		

TEST RESULTS	Sample ID		M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time		17 Apr 2009 / 17:15		17 Apr 2009 / 17:10		17 Apr 2009 / 17:05		17 Apr 2009 / 17:25	
	LOD	Units								
Suspended Solids (SS)	1	mg/L	10.1	10.0	7.7	7.8	7.9	8.2	7.6	7.5

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks :

----- End -----

Tested By : LI YUKE

Approved Signatory : 

Checked By : GU CHIN

Name : GU CHIN

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC090400127 Date of Issue : 27-04-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 22-04-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 23-04-2009

GCE Serial No. : WQM042009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	490	486	0.8	25.5
Acceptance Criteria			<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	20 Apr 2009 / 10:20		20 Apr 2009 / 10:30		20 Apr 2009 / 10:40			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	1.1	< 1.0	73.2	73.6	7.9	7.5	

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	20 Apr 2009 / 9:55		20 Apr 2009 / 10:00		20 Apr 2009 / 10:10		20 Apr 2009 / 9:50	
	LOD	Units							
Suspended Solids (SS)	1	mg/L	8.3	8.3	2.8	2.9	12.1	12.3	9.3

* : Information provided by client


Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : _____

----- End -----

Tested By : LI YUKE

Checked By : GU CHIN

Approved Signatory : 
 Name : GU CHIN
 Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Page 1 of 1

Report No. : GCC090400135 Date of Issue : 27-04-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 23-04-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 25-04-2009

GCE Serial No. : WQM042009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results						
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L		
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	484	486	-0.4	24.2		
Acceptance Criteria			<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29		
TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	22 Apr 2009 / 11:10		22 Apr 2009 / 11:20		22 Apr 2009 / 11:30			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	1.6	1.6	326.0	320.0	9.2	9.2	
TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	22 Apr 2009 / 10:50		22 Apr 2009 / 10:55		22 Apr 2009 / 11:00		22 Apr 2009 / 10:40	
	LOD	Units							
Suspended Solids (SS)	1	mg/L	8.4	8.8	6.9	6.6	7.4	7.8	10.8

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : _____

----- End -----

Tested By : LI YUKE

Approved Signatory : 

Name : GU CHIN

Checked By : GU CHIN

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Page 1 of 1

Report No. : GCC090400143 Date of Issue : 27-04-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 25-04-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 25-04-2009

GCE Serial No. : WQM042009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	490	498	-1.6	23.8
Acceptance Criteria			< 2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	24 Apr 2009 / 11:45		24 Apr 2009 / 11:55		24 Apr 2009 / 12:05			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	2.7	2.3	146.8	147.2	7.6	7.6	

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time	24 Apr 2009 / 12:20		24 Apr 2009 / 12:25		24 Apr 2009 / 12:35		24 Apr 2009 / 12:50	
	LOD	Units							
Suspended Solids (SS)	1	mg/L	5.9	5.3	13.7	13.3	26.0	26.0	11.1 11.3

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks :

----- End -----

Tested By : LI YUKE

Approved Signatory : 

Name : GU CHIN

Checked By : GU CHIN

Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC090400347 Date of Issue : 30-04-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : Mui Wo Village Sewerage Phase 1 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 27-04-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 28-04-2009

GCE Serial No. : WQM042009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	483	485	-0.4	25.1
Acceptance Criteria			< 2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ± 5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID		C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time		27 Apr 2009 / 14:48		27 Apr 2009 / 14:55		27 Apr 2009 / 15:05			
	LOD	Units								
Suspended Solids (SS)	1	mg/L	< 1.0	< 1.0	485.0	496.0	9.2	9.2		

TEST RESULTS	Sample ID		M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time		27 Apr 2009 / 14:30		27 Apr 2009 / 14:35		27 Apr 2009 / 14:40		27 Apr 2009 / 14:20	
	LOD	Units								
Suspended Solids (SS)	1	mg/L	5.9	6.4	29.0	29.6	28.4	28.6	24.4	24.2


* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : ----- End -----

Tested By : K.L. Fong

Checked By : GU CHIN

Approved Signatory : 
 Name : GU CHIN
 Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Page 1 of 1

Report No. : GCC090400355 Date of Issue : 30-04-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 28-04-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 29-04-2009

GCE Serial No. : WQM042009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	506	498	1.6	22.5
Acceptance Criteria			<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate			
	Sampling Date/Time				28 Apr 2009 / 15:15		28 Apr 2009 / 15:25			
	LOD	Units								
Suspended Solids (SS)	1	mg/L		237.6	240.0	8.4	9.0			


TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate	
	Sampling Date/Time				28 Apr 2009 / 15:40		28 Apr 2009 / 15:50		28 Apr 2009 / 16:03	
	LOD	Units								
Suspended Solids (SS)	1	mg/L		13.0	13.4	15.6	15.3	15.1	14.7	

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : _____
 ----- End -----

Tested By : K.L. Fong
 Checked By : GU CHIN

Approved Signatory : 
 Name : GU CHIN
 Post : Chemist



TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Page 1 of 1

Report No. : GCC090400363 Date of Issue : 30-04-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.
 DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of

Project* : Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 30-04-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 30-04-2009

GCE Serial No. : WQM042009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	488	482	1.2	22.5
Acceptance Criteria			<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID	C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time	29 Apr 2009 / 15:00		29 Apr 2009 / 15:14		29 Apr 2009 / 15:30			
	LOD	Units							
Suspended Solids (SS)	1	mg/L	< 1.0	< 1.0	118.8	115.2	13.7	13.3	

TEST RESULTS	Sample ID	M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate	
	Sampling Date/Time	29 Apr 2009 / 15:50		29 Apr 2009 / 15:35		29 Apr 2009 / 15:40		29 Apr 2009 / 16:00		
	LOD	Units								
Suspended Solids (SS)	1	mg/L	8.4	8.3	30.8	30.4	11.9	12.3	8.7	9.1

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : _____

----- End -----

Tested By : K.L. Fong

Approved Signatory : 

Name : GU CHIN

Checked By : GU CHIN

Post : Chemist

Appendix G
Monitoring Schedule
for Apr 2009

Environmental Pioneers and Solutions Limited

DC/2006/11 - DRAINAGE IMPROVEMENT IN SOUTHERN LANTAU

Master Schedule of EM&A works in April 2009

Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
			4/1	4/2	4/3	4/4
			WQM at: 16:18	WQM at: 16:58 Site Inspection		
4/5	4/6	4/7	4/8	4/9	4/10	4/11
	WQM at: 10:18 Noise monitoring		WQM at: 11:49	WQM & EWQM at: 12:18 Ecological Survey Site Inspection		
4/12	4/13	4/14	4/15	4/16	4/17	4/18
		WQM at: 15:09	WQM at: 15:46 Noise monitoring		WQM at: 17:12 Ecological Survey Site Inspection	
4/19	4/20	4/21	4/22	4/23	4/24	4/25
	WQM at: 08:55 Noise monitoring		WQM at: 10:11		WQM at: 11:59 Site Inspection	
4/26	4/27	4/28	4/29	4/30		
	WQM at: 13:51 Noise monitoring	WQM repeat measurement	WQM at: 15:33			

Noise Monitoring Locations: Total 4 Locations as N1, N2, N3 and N4

Water Quality Monitoring (WQM) Locations: Total 7 Locations as M1, M2, M3, M4, C1, C2 and C3

Ecological Water Quality Monitoring (EWQM) Locations: Total 6 Locations as WE1, WE2, WE3, WE4, WE5 and WE6

Appendix H Implementation Status of environmental protection / mitigation measures


Environmental Aspect	Protection / Mitigation Measures	Implementation status	Follow-up action
Air Quality	Use of regular watering to reduce dust emissions from exposed site surfaces and unpaved road, with complete coverage.	Implemented	-
	Use of frequent watering for particular dusty static construction areas and areas close to ASRs.	Implemented	-
	Tarpaulin covering of all dusty vehicle loads transported to and from and between site location;	Implemented	-
	Establishment and use of vehicle wheel and body washing facilities at the exit points of the site.	Implemented	-
	Routing of vehicles and positioning of construction plant should be at the maximum possible distance from ASRs.	Implemented	-
Noise	Use of quiet powered mechanical equipment (PME)	Implemented	-
	Adoption of movable noise barriers and temporary noise barriers	Not applicable at this stage	-
	Application of good site practices mentioned in EM&A manual Clause 3.8.1	Implemented	-
Water Quality	Before commencing any site formation works, all sewer and drainage connections should be sealed to prevent debris, soil, sand etc. from entering public sewers/drains.	Implemented	-
	Temporary ditches should be provided to facilitate run-off discharge into appropriate watercourses, via a silt retention pond. No site run-off should enter the freshwater marshes at Luk Tei Tong.	Not applicable	-
	Sand/ silt removal facilities such as sand traps, silt traps and sediment basins should be provided to remove sand/ silt particles from runoff to meet the requirements of the Technical Memorandum standard under the Water Pollution Control Ordinance.	Deficiencies found on 23 Apr 09	To be follow up
	Water pumped out from foundation excavations should be discharged into silt removal facilities.	Deficiencies found on 23 Apr 09	To be follow up
	During rainstorms, exposed slope surface should be covered by a tarpaulin or the means.	Implemented	-
	Exposed soil areas should be minimized to reduce potential for increased siltation and contamination of runoff.	Implemented	-
	Exposed soil surfaces should be protected by paving or fill material as soon as possible to reduce potential of soil erosion.	Implemented	-
	Open stockpiles of construction materials or construction wastes on-site of more than 50m ³ should be covered with tarpaulin or similar fabric during rainstorms.	Implemented	-
	Oils and fuels should only be used and stored on designated areas which have pollution prevention facilities.	Implemented	-
	Temporary sanitary facilities, such as portable chemical toilets, should be employed on-site.	Not applicable	-
	The excavation and widening works for the drainage improvements to the Pak Ngan Heung River, Tai Tei Tong River, Luk Tei Tong River and Luk Tei Tong By-pass Channel should be carried out in sections (approximately 300 –400 m in length) and in dry condition.	Implemented	-

Environmental Aspect	Protection / Mitigation Measures	Implementation status	Follow-up action
	Maintenance desilting of the re-profiled river channels of the Pak Ngan Heung River, Tai Tei Tong River, Luk Tei tong River and Luk Tei Tong By-pass Channel, temporary barrier walls should be used to provide a dry zone for desilting work.	Not applicable at this stage	-
Ecology	Existing natural habitats should be retained as far as practicable	Implemented	-
	Boundary of working areas should be identified to prevent loss of vegetation	Implemented	
	All existing trees / plant should be well protected within the site or transplanted properly	Implemented	-
	Turf removal from the Luk Tei Tong marsh due to the construction of Luk Tei Tong Bypass Channel shall be minimized	Implemented	
	Turf from the Luk Tei Tong marsh shall be properly removed, stored, maintained and reused for lining the riverbed of the Luk Tei Tong Bypass Channel	Implemented	
Chemical and Solid Waste	Chemical wastes should be properly stored in a proper store as per statutory requirements (i.e. on a hard standing, within an enclosed and locked area)	Implemented	-
	Chemical waste stores should be provided with fire precaution facilities (i.e. fire extinguisher, no smoking warning etc).	Implemented	-
	Chemical wastes should be properly stored in corrosion resistant containers placed inside the store and labelled with warning signs in English and Chinese.	Implemented	-
	Chemical wastes should be disposed of by licensed chemical waste collector with supporting delivery records.	Implemented	-
	All containers for fuel, diesel and fluid chemical (in use) and oil filled stationery plants located with proper drip pans.	Implemented	-
	Construction wastes should be managed and disposed to the designated public fill and landfill areas in acceptable manner.	Implemented	-
	All waste disposals managed in a proper manner i.e. trip ticket system implementation.	Implemented	-


Appendix I

Graphical plot of water
quality monitoring
results (SS, DO,
turbidity)

Graphical Plot of Turbidity Trend M1&C1 (Jan- Apr 09)




Graphical Plot of Turbidity Trend M2&C2 (Jan- Apr 09)




Remarks: The reading of C2 on 27th, 28th and 29th April 2009 is 732.1, 360.5, and 186.7, which was over the range of the plot.


Graphical Plot of Turbidity Trend M3&C3 (Jan- Apr 09)




Graphical Plot of Turbidity Trend M4 (Jan- Apr 09)




Graphical Plot of Dissolved Oxygen Trend M1&C1 (Jan-Apr 09)




Graphical Plot of Dissolved Oxygen Trend M2&C2 (Jan-Apr 09)




Graphical Plot of Dissolved Oxygen Trend M3&C3 (Jan-Apr 09)




Graphical Plot of Dissolved Oxygen Trend M4 (Jan-Apr 09)



Graphical Plot of Suspended Soild M1&C1 (Jan-Apr 08)




Graphical Plot of Suspended Soild M2&C2 (Jan-Apr 08)




Remarks: The reading of M2 on 30th April 2009 is 30.6 and C2 on 27th April 2009 is 490.5, which was over the range of the plot.

Graphical Plot of Suspended Soild M3&C3 (Jan-Apr 08)



Graphical Plot of Suspended Soild M4 (Jan-Apr 08)



Appendix J

Graphical plot of noise
monitoring results

