Drainage Service Department

Monthly Environmental Monitoring & Auditing report for

Contract No.DC/2006/11
Drainage Improvement in Southern Lantau

December 2009

Environmental Pioneers & Solutions Limited
8/F, Chaiwan Industrial Centre Building
20 Lee Chung Street, Chaiwan, Hong Kong
Tel: 2965 0828 Fax: 2856 2010

APPROVAL SHEET

Prepared and Certified by: ET Leader (Environmental Pioneers & Solutions Limited)

Signature: _____ Date: 1/3/2010

Miss Patricia Chung
(ET* Leader)

Signature: _____ Date: 1/3/2010

Mr. Vincent Lai
(Ecologist)

* ET – Environmental Team

TABLE of CONTENT

APPENDIXES

EXECUTIVE SUMMARY

This is the seventeenth monthly environmental Monitoring and audit (EM&A) report for "Drainage Improvement in Southern Lantau Investigation". The environmental permit number is "EP-237/2005/A". The report concludes the impact monitoring for the activities undertaken during the period of 1 December 2009 to 31 December 2009. The major activities in this reporting month include site formation, construction of box culverts, retaining wall and gabion wall at Pak Ngan Heung (PNH) and Luk Tei Tong (LTT) River.

Noise, water quality and ecological monitoring were performed. Results obtained were checked against the previously established Action / Limit (A/L) levels. Additionally, the implementation status of environmental mitigation measures, event/ action plan and environmental complaint handling procedures were inspected during weekly site environmental audit.

In general, waste management was satisfactory during the reporting month.

Impact monitoring for construction noise was conducted in the reporting period. No exceedance of A/L level was reported.

Furthermore, impact monitoring for water quality was conducted. Total 66 non-compliance events of water quality criteria were recorded in this reporting period while 6 of them were believed to be mainly attributed to improper site practice and insufficient of water quality mitigation measures on site. As such, contractor was advised to implement necessary corrective actions and mitigation measures as to minimize further deterioration of water quality.

During ecological monitoring survey, no White-shouldered Starling was recorded breeding in the watch tower. There was no sign of disturbance from the Project to the watch tower. The watch tower may not be suitable for birds as nesting habitat. In addition, no disturbance on the flora and fauna in the river channels were observed during the ecological monitoring.

There was no complaint, notification of any summons and successful prosecutions against the project received during the reporting period.

Key construction activity in the coming month will include construction of box culvert, gabion wall, retaining wall and sloping seawall. It is expected that noise, air and water quality impacts will be resulted from the works. With reference to the EM&A manual and mitigation measure report, mitigation measures are proposed to be taken, if necessary.

The ET will continue to implement the environmental monitoring & audit programme in accordance with the EM&A Manual and Environmental Permit requirement.

1. Introduction

This is the seventeenth monthly Environmental Monitoring and Audit (EM&A) Report for "Drainage Improvement in Southern Lantau Investigation" project (Environmental Permit No. EP-237/2005/A)

2. Project Information

2.1 Construction program

The "Drainage Improvement in Southern Lantau Investigation" project will be completed by January 2011. The project comprises the following:

- Construction of approximately 80m long gabion with natural bed in Pak Ngan Heung River, approximately 180m of three cells 3m x 2m box culvert and approximately 100m of rectangular channel at Pak Ngan Heung River;
- Construction of approximately 250m of 0.75m wide U-Channel at Ling Tsui Tau Village in Mui Wo;
- Construction of bypass channel of about 350m and 240m long of gabion channels at Luk Tei Tong River respectively; and
- Widening three existing bottlenecks with gabion lined at Tai Tei Tong (TTT) River

Appendix A shows the construction program and location plan of the project.

2.2 Project organization

The Main Contractor, Yick Hing Construction Company Limited, has commissioned Environmental Pioneers & Solutions Limited and Ecosystems Limited as the Environmental Team, which comprises the environmental team leader, the ecologists and the environmental technicians to undertake the environmental monitoring and audit work for this project.

The environmental management structure and is shown in Fig 2.2.1.



Figure. 2.2.1 Environmental Management structure for the project

2.3 Key personal contact information chart

Detailed contact of key persons involved in environmental aspect of the project is shown in Appendix B.

3. Construction Stage

3.1 Construction activities in the reporting month

Major activities in the reporting month included the followings:

1. Construction of box culverts at PNH.
2. Construction of retaining wall C, E and F at PNH.
3. Construction of gabion wall at LTT River.
4. Construction of retaining wall J near Yuen's Compound.
5. Formation of haul access for sloping sea wall at Yuen's Compound.

3.2 Construction activities for the coming month

Proposed key construction works in the coming month will include:

1. Construction of box culverts at PNH.
2. Construction of retaining wall C, E and F at PNH.
3. Site formation and construction for fish ladder at PNH.
4. Construction of pipe trench along Ling Tsui Tau.
5. Construction of sloping seawall (near Yuen's Compound) at LTT River.
6. Construction of retaining wall J (near Yuen's Compound) at LTT River.

3.3 Environmental Status

Appendix A shows the drawing of the project area.

Locations of the monitoring and control stations with environmental sensitive receivers are presented in Section 4.3, 5.3 and 6.3 for noise, water and ecological monitoring respectively.

4. Noise Monitoring

4.1 Monitoring Parameters and Methodology

The construction noise level was measured in terms of the A-weighted equivalent continuous sound pressure level (L_{eq}). $L_{eq\ (30minutes)}$ was used as the monitoring parameter for the impact monitoring in the time period between 0700 to 1900 hours on normal weekdays. For all other time period, $L_{eq\ (5minutes)}$ was employed for comparison with the Noise Control Ordinance (NCO) criteria.

Noise measurement results obtained from each monitoring location were recorded in the Construction Noise Monitoring Data Sheet (Appendix E) immediately after the measurement. As supplementary information for data auditing, statistical results L_{10} and L_{90} were also be recorded for reference.

In case of non-compliance with the construction noise criteria, more frequent monitoring, as specified in the Action plan in Table 4.5.2, shall be carried out. This additional monitoring shall be carried out until the recorded noise levels are rectified or proved to be irrelevant to the construction activities.

4.2 Monitoring Equipment

The sound level meters and calibrators comply with the International Electrotechnical Commission Publications 651:1979 (Type 1) and 804:1985 (Type 1) specifications as referred to in the Technical Memorandum (TM) to the Noise Control Ordinance was deployed as monitoring equipment for noise measurement.

Noise measurement was not be made in the presence of fog, rain, wind with a steady speed exceeding $5ms^{-1}$ or wind with gust exceeding $10ms^{-1}$. Thus wind speed was checked by the portable wind speed indicator capable of measuring the wind speed in m/s. Table 4.2.1 summarizes the equipment list for noise monitoring

Table 4.2.1 Equipment List for Noise Monitoring

Equipment	Manufacturer & Model No.	Precision Grade	Qty
Integrated sound level meter	ACO Japan, model 6224	IEC 651 Type 1 IEC 804 Type 1	1
Windscreen	Microtech gefell model W2	N/A	1
Acoustical calibrator	Castle GA 607	IEC 942 Type 1	1
Wind speed indicator	Kestrel K1000	N/A	1
Remarks: Calibration details for the sound level meter is given in Appendix C for reference			

4.3 Monitoring Locations

According to the Baseline Monitoring Report issued in May 2008 for the captioned project, four locations where are alternative from the locations proposed in EM&A manual, were designated for baseline noise monitoring. For the data validation, impact noise monitoring was undertaken in the same locations during the construction phase of the project. The proposed monitoring locations are summarized in Table 4.3.1. Figure 4.3.1 shows the Noise Monitoring Locations

Noise measurement in each monitoring locations were taken at a point 1m from the exterior of the selected premises and at a height with no disturbance to the dweller and least obstructed view.

Table 4.3.1 Noise Monitoring Locations during Construction Phase

Identification No.	Noise Monitoring Locations
N1	No. 73, Village House, Ling Tsui Tau Tsuen (ground level)
N2	No. 31, Village House, Ling Tsui Tau Tsuen (ground level)
N3	Fence wall outside No. 5 village house adjacent to Luk Tei Tong River Outlet (ground level)
N4	No. 23, Village House, Tai Tei Tong River (ground level)

In accordance with the requirements in the EM&A manual, weekly impact monitoring was conducted. For the time period between 0700 and 1900 hours on normal weekdays, and noise parameter of $L_{eq\ (30minutes)}$ was measured. As if the construction works were carried out during restricted period (ie. 1900-2300, 2300-0700 of next day and Sundays / general holiday), impact monitoring that comprises 3 consecutive $L_{eq\ (5minutes)}$ would be carried out.



Figure 4.3.1 Impact noise monitoring locations

4.4 Monitoring Results and Interpretation

Relevant details of the noise monitoring results are presented in Table 4.4.1. The results, ranged between 44.9 dB(A) and 65.4 dB(A), were within the limit levels and therefore, no exceedance was found.

Table 4.4.1 Noise monitoring results

Table 4.4.1 Noise Monitoring Results for the reporting month

Location	Parameter	Date	Time	L_{Aeq} dB(A)	Limit dB(A)	Exceedance	Weather
N1	$L_{eq\ 30mins}$	2-Dec-09	11:55	44.9	75	N	Sunny
N1	$L_{eq\ 30mins}$	9-Dec-09	15:10	50.6	75	N	Cloudy
N1	$L_{eq\ 30mins}$	16-Dec-09	15:00	56.8	75	N	Cloudy
N1	$L_{eq\ 30mins}$	23-Dec-09	14:10	52.4	75	N	Sunny
N1	$L_{eq\ 30mins}$	30-Dec-09	14:45	57.3	75	N	Cloudy
N2	$L_{eq\ 30mins}$	2-Dec-09	13:30	62.3	75	N	Sunny
N2	$L_{eq\ 30mins}$	9-Dec-09	15:45	61.7	75	N	Cloudy
N2	$L_{eq\ 30mins}$	16-Dec-09	14:25	59.7	75	N	Cloudy
N2	$L_{eq\ 30mins}$	23-Dec-09	13:35	62.3	75	N	Sunny
N2	$L_{eq\ 30mins}$	30-Dec-09	14:10	60.3	75	N	Cloudy
N3*	$L_{eq\ 30mins}$	2-Dec-09	11:20	57.7	75	N	Sunny
N3*	$L_{eq\ 30mins}$	9-Dec-09	14:35	65.4	75	N	Cloudy
N3*	$L_{eq\ 30mins}$	16-Dec-09	13:40	64	75	N	Cloudy
N3*	$L_{eq\ 30mins}$	23-Dec-09	13:00	55.5	75	N	Sunny
N3*	$L_{eq\ 30mins}$	30-Dec-09	13:35	53.4	75	N	Cloudy
N4	$L_{eq\ 30mins}$	2-Dec-09	10:45	54.0	75	N	Sunny
N4	$L_{eq\ 30mins}$	9-Dec-09	14:00	52.0	75	N	Cloudy
N4	$L_{eq\ 30mins}$	16-Dec-09	13:05	50.4	75	N	Cloudy
N4	$L_{eq\ 30mins}$	23-Dec-09	11:30	48.9	75	N	Sunny
N4	$L_{eq\ 30mins}$	30-Dec-09	13:00	46.6	75	N	Cloudy

Remarks: Raw datasheet for noise monitoring are attached in Appendix E for reference.
Remark*: The equivalent noise level of N3 is corrected by +3 dB from the raw data result due to the fact that free field measurement was carried out in the location.

4.5 Action and Limit level for Construction noise

The Action and Limit (A/L) levels for construction noise are defined in Table 4.5.1. Should non-compliance of the criteria occur, action in accordance with the Action Plan in Table 4.5.2 should be carried out.

There was no recorded exceedance in the reporting month.

Table 4.5.1 Action and Limit Levels for Construction noise		
Time Period	**Action Level**	**Limit Level**
0700 – 1900 hours on normal weekdays	When one documented complaint is received	75dB(A)
Remarks: If works are to be carried out during restricted hours, the conditions stipulated in the construction noise permit issued by the Noise Control Authority have to be followed.		

Table 4.5.2 Event / Action Plan for Construction Noise

EVENT	**ACTION**			
	ET	**IC(E)**	**ER**	**Contractor**
Action Level	1. Notify IC(E) and Contractor; 2. Carry out investigation; 3. Report the results of investigation to the IC(E), ER and Contractor; 4. Discuss with the Contractor and formulate remedial measures; 5. Increase monitoring frequency to check mitigation effectiveness.	1. Review the analysed results submitted by the ET; 2. Review the proposed remedial measures by the Contractor and advise ER accordingly; 3. Supervise the implementation of remedial measures.	1. Confirm receipt of notification of failure in writing; 2. Notify Contractor; 3. Require Contractor to propose remedial measures for the analysed noise problem; 4. Ensure remedial measures are properly implemented.	1. Submit noise mitigation proposals to IC(E); 2. Implement Noise mitigation proposals.
Limit Level	1. Identify source; 2. Inform IC(E), ER, EPD and Contractor; 3. Repeat measurements to confirm findings; 4. Increase monitoring frequency; 5. Carry out analysis of Contractor's working procedures to determine possible mitigation to be implemented; 6. Inform IC(E), ER and EPD the causes and actions taken for the exceedances; 7. Assess effectiveness of Contractor's remedial actions and keep IC(E), EPD and ER informed of the results 8. If exceedance stops, cease additional monitoring	1. Discuss amongst ER, ET, and Contractor on the potential remedial actions; 2. Review Contractors remedial actions whenever necessary to assure their effectiveness and advise the ER accordingly; 3. Supervise the implementation of remedial measures.	1. Confirm receipt of notification of failure in writing; 2. Notify Contractor; 3. Require Contractor to propose remedial measures for the analysed noise problem; 4. Ensure remedial measures properly implemented; 5. If exceedance continues, consider what portion of the work is responsible and instruct the Contractor to stop that portion of work until the exceedance is abated	1. Take immediate action to avoid further exceedance; 2. Submit proposals for remedial actions to IC(E) within 3 working days of notification; 3. Implement the agreed proposals; 4. Resubmit proposals if problem still not under control; 5. Stop the relevant portion of works as determined by the ER until the exceedance is abated

4.6 Noise Mitigation Measures

The following mitigation measures were observed from the weekly site inspection in the reporting month:

- Use of quiet powered mechanical equipment (PME)
- Implementation of the following good site practices:
  - Only well-maintained and regularly serviced plant should be operated on site;
  - Silencers or mufflers on construction equipment;
  - Mobile plant, if any, should be sited as far from noise sensitive receivers as possible; and
  - Machines and plant (such as trucks) that may be in intermittent use should be shut down between work periods or should be throttled down to a minimum.

5. Water Monitoring

5.1 Water Quality Monitoring Parameters and methodology

Turbidity in Nephelometric Turbidity Unit (NTU), Dissolved Oxygen (DO) in mg/L and Suspended Solids (SS) in mg/L are required to measure in this project. Turbidity, DO was measured in-situ while water samples were delivered to Accredited HOKLAS Laboratory for analysis of SS.

Other relevant data such as monitoring location, time, water depth, temperature, salinity, weather conditions and any other special phenomena and work underway at the construction site were recorded during sampling.

According to the requirement of the EM&A manual, two consecutive measurements for parameters of DO concentration, DO saturation and Turbidity are required to be taken at each monitoring location. When the difference in value between the first and second reading of DO or Turbidity is more than 25%, the reading would be discarded and further reading would be taken.

5.2 Monitoring Equipment

Turbidity, DO, Salinity, pH and temperature was measured by an instrument complied with the following requirements:

The instrument is a portable as well as weatherproof multimeter complete with cable and uses a DC power source. It is capable of measuring:

- A turbidity between 0-800NTU;
- A dissolved Oxygen level in the range of 0-20mg/L and 0-200% saturation;
- A temperature of 0-50^{o}C;
- Salinity in the range of 0-40ppt;
- pH in the range of 0-14.

Suspended solid was determined by the water samples collected from the monitoring locations for further analysis in accredited HOKLAS laboratory. Water samples were contained by polythene bottles, packed in ice (cooled in 4^{o}C without frozen) and delivered to the laboratory for analysis as soon as possible after collection. Duplicate samples from each independent sampling event were undertaken during impact monitoring.

Detailed calibration records of the multimeter were shown in Appendix C for reference.

5.3 Monitoring Locations

Seven locations included a control station in upstream of each stream/ river, a monitoring station at the end of each stream/ river of the works area and a monitoring station at Silver River were proposed for the impact water quality monitoring. Water samples were collected at mid-depth of each proposed monitoring stations for measurements and sample collection. The Location Plan is shown in Figure 5.3.1 for reference.



Figure 5.3.1 Water Quality Monitoring Locations

5.4 Monitoring Frequency

Impact water quality monitoring was undertaken three days per week and at ebb tides during the course of the construction river works. Upon the completion of the construction works, the monitoring exercises at the designated monitoring stations will be continued for four weeks in the same manner as the impact monitoring.

5.5 Monitoring Results and Interpretation

Water quality monitoring was carried out fifteen times during December. Detailed on-site measurements and laboratory analysis reports including QA/QC results are shown in Appendix F1 and F2 respectively, while Table 5.5.1 presents consolidated results throughout the reporting month.

Total 66 exceedance events on parameters of turbidity and suspended solids were recorded in this reporting month according to the established level. Findings from the investigations showed most of the exceedance events were mainly caused by natural fluctuation and deficiencies of site practice.

As 6 events were suspected to be related to improper site practices, contractor was seriously reminded to review the site conditions and implement corrective actions as well as mitigation measures as soon as possible to minimize further deterioration of water quality.

Detailed information of the exceedance events and action taken were presented in Section 7.

Table 5.5.1 Water quality monitoring results in December 2009

	M1			M2			M3			M4		
	MIN	MAX	Ave	MIN	MAX	Ave	MIN	MAX	Ave	MIN	MAX	Ave
Turbidity (NTU)	2.6	19.4	8.3	0.0	4.0	0.6	1.6	38.6	8.3	2.3	10.9	5.8
DO (mg/l)	7.6	10.4	9.3	7.7	10.4	9.1	6.1	10.0	8.0	7.1	10.9	8.8
Suspended Solid (mg/l)	3.6	19.5	9.5	1.3	3.1	1.8	3.6	34.9	9.4	3.0	11.3	8.1

	C1			C2			C3		
	MIN	MAX	Ave	MIN	MAX	Ave	MIN	MAX	Ave
Turbidity (NTU)	0.0	0.3	0.0	0.0	0.0	0.0	1.8	6.2	4.0
DO (mg/l)	6.9	9.7	8.4	7.4	9.4	8.2	6.6	8.8	7.4
Suspended Solid (mg/l)	1.0	1.3	1.0	1.0	1.0	1.0	3.4	7.8	5.7

* Remarks: Detection limit for Turbidity, DO and SS are 1 NTU, 0.1 mg/L and 1 mg/L respectively.

5.6 Action and limit level for Water Quality

Based on the criteria stipulated in EM&A manual Section 4.8 and baseline water quality monitoring data obtained, the A/L levels are shown in Table 5.6.1 and Table 5.6.2. If the water quality monitoring results at any impact stations exceeded the criteria, the actions in accordance with the Event and Action Plan in Table 5.6.3 should be taken.

Table 5.6.1 Water quality criteria for monitoring

Parameters	Action	Limit
DO in mg/L (mid-depth)	- 5%-ile of baseline data	- 4mg/L
SS in mg/L (mid-depth)	- 95%-ile of baseline data; or - 120% of control station's SS on the same day of measurement	- 99%-ile of baseline; or - 130% of control station's SS on the same day of measurement
Turbidity in NTU (mid-depth)	- 95%-ile of baseline data; or - 120% of control station's turbidity on the same day of measurement	- 99%-ile of baseline; or - 130% of control station's turbidity on the same day of measurement

Table 5.6.2 Action and Limit Levels established according to baseline data

Parameters	Monitoring locations							
	M1		M2		M3		M4	
	Action Level	Limit Level	Action Level	Limit Level	Action Level	Limit Level	Action Level	Limit Level
Turbidity (NTU)	15.2	16.9	5.3	6.5	16.8	26.0	16.2	18.0
DO (mg/L)	5.7	4.0	6.2	4.0	5.9	4.0	5.9	4.0
SS (mg/L)	12.2	12.8	3.1	4.2	12.4	17.7	13.9	15.2

Remarks:
For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits
For SS and turbidity, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.

Table 5.6.3 Event and action Plan for Water Quality

EVENT	ACTION			
	ET	**IC(E)**	**ER**	**Contractor**
Action Level being exceed by one sampling day	1. Repeat in *situ* measurement to confirm findings; 2. Identify reasons for non-compliance and source(s) of impact; 3. Inform IC(E) and Contractor; 4. Check monitoring data, all plant, equipment and Contractor's working methods; 5. Discuss mitigation measures with IC(E) and Contractor; 6. Repeat measurement on next day of exceedance.	1. Discuss with ET and Contractor on the mitigation measures; 2. Review proposals in mitigation measures submitted by Contractor and advise the ER accordingly; 3. Assess the effectiveness of the implemented mitigation measures.	1. Discuss with IC(E) on the proposed mitigation measures; 2. make agreement on the mitigation measures to be implemented; 3. Assess the effectiveness of the implemented mitigation measures.	1. Inform the ER and confirm notification of the non-compliance in writing; 2. Rectify unacceptable practice; 3. Check all plant and equipment; 4. Consider changes of working methods; 5. Discuss with ET and IC(E) and propose mitigation measures to IC(E) and ER; 6. Implement the agreed mitigation measures.
Action level being exceed by more than two consecutive sampling days	1. Repeat in *situ* measurement to confirm findings; 2. Identify reasons for non-compliance and source(s) of impact; 3. Inform IC(E) and Contractor; 4. Check monitoring data, all plant, equipment and Contractor's working methods; 5. Discuss mitigation measures with IC(E) and Contractor; 6. Ensure mitigation measures are implemented; prepare to increase the monitoring frequency to daily 7. Repeat measurement on next day of exceedance	1. Discuss with ET and Contractor on the mitigation measures; 2. Review proposals in mitigation measures submitted by Contractor and advise the ER accordingly; 3. Assess the effectiveness of the implemented mitigation measures.	1. Discuss with IC(E) on the proposed mitigation measures; 2. make agreement on the mitigation measures to be implemented; 3. Assess the effectiveness of the implemented mitigation measures.	1. Inform the ER and confirm notification of the non-compliance in writing; 2. Rectify unacceptable practice; 3. Check all plant and equipment; 4. Consider changes of working methods; 5. Discuss with ET and IC(E) and propose mitigation measures to IC(E) and ER within three working days; 6. Implement the agreed mitigation measures.
Limit level being exceeded by one sampling day	1. Repeat in *situ* measurement to confirm findings; 2. Identify reasons for non-compliance and source(s) of impact; 3. Inform IC(E) and Contractor; 4. Check monitoring data, all plant, equipment and Contractor's working methods; 5. Discuss mitigation measures with IC(E) and Contractor; 6. Ensure mitigation measures are implemented; 7. Increase the monitoring frequency to daily until no exceedance of Limit Level	1. Discuss with ET and Contractor on the mitigation measures; 2. Review proposals in mitigation measures submitted by Contractor and advise the ER accordingly; 3. Assess the effectiveness of the implemented mitigation measures.	1. Discuss with IC(E) on the proposed mitigation measures; 2. make agreement on the mitigation measures to be implemented; 3. Assess the effectiveness of the implemented mitigation measures.	1. Inform the ER and confirm notification of the non-compliance in writing; 2. Rectify unacceptable practice; 3. Check all plant and equipment; 4. Consider changes of working methods; 5. Discuss with ET and IC(E) and propose mitigation measures to IC(E) and ER; 6. Implement the agreed mitigation measures.

5.7 Water Quality Mitigation Measures

Construction Run-off and Drainage

The site practices outlined in ProPECC PN 1/94 'Construction Site Drainage" should be followed as far as practicable during both construction and operation phase of the drainage improvement works in order to minimize surface runoff and the chance of erosion, and also to retain and reduce any suspended solids prior to discharge.

As recommended in the final EM&A manual, attention would be paid especially construction run-off and drainage, general construction activities, sewage discharged from construction workforce and river channel excavation works.

Contractor was recommended to provide sufficient water treatment facilities for accumulated site water and excavation activities carried out nearby river channel. Earth bunds should be provided to the construction site in / next to the river channel to form an enclosed, dry environment to minimize water quality impact.

5.8 Water Monitoring Schedule for the Next reporting period

Water monitoring scheduled for the next reporting period is 4, 5, 6, 13, 14, 15, 18, 20, 22, 28, 29 and 30 January 2010.

6. Ecology Monitoring

6.1 Ecological Monitoring Parameters

According to the Final EM&A Manual, a specific ecological monitoring programme of the improved section of PNH and LTT Rivers is recommended. The monitoring parameters required to measure in this project and survey methodology are described below:

(1) Avifauna species and abundance: Birds will be surveyed quantitatively using transect count method. Birds within the river channel and on the riverbank will be identified and their abundance will be recorded.

(2) Aquatic macroinvertebrate community species composition and abundance: Survey on aquatic fauna will focus on determination of the diversity and abundance of stream aquatic communities. Sampling methods, such as active searching, direct observation, netting, and kick sampling, will be determined according to the site conditions during field survey.

(3) Fish community species composition and abundance: Sampling methods, such as active searching, direct observation, and hand netting, will be determined according to the site conditions during field survey.

(4) Adult odonate community species composition and abundance: Adult dragonfly will be surveyed quantitatively using transect count method. Adult dragonflies within the river channel and on the riverbank will be identified and their abundance will be recorded. Species requiring close examination will be netted.

(5) Aquatic, emergent and riparian vegetation community species composition and abundance: The area will be walked through. Plant species composition and their relative abundance will be recorded.

(6) Surveys of White-shouldered Starling Sturnus sinensis will be conducted at the disused watchtowers next to LTT river. Breeding of the White-shouldered Starlings will be determined by checking signs of attempt to breed or sign of breeding which include carrying nesting materials, to-and-fro movement of adults carrying food, presence of recently fledged juveniles, etc. The number of breeding pairs and the site observation will be recorded whenever possible.

Water Quality Monitoring along LTT and PNH River as well as LTT bypass channel was carried out. Water quality monitoring will include Turbidity in Nephelometric Turbidity Unit (NTU), Dissolved Oxygen (DO) in mg/L and Suspended Solids (SS) in mg/L are required to measure in this project. Moreover, additional water monitoring parameters will be taken for the purposes of ecological monitoring of water quality in this project. The added information will include: BOD, Ammonia, Nitrate and Phosphate concentrations. Turbidity, DO, pH and water flow will be measured in-situ while water samples will be delivered to Accredited HOKLAS Laboratory accredited laboratory and the analyses followed the standard methods according to APHA Standard Methods for the Examination of Water and Wastewater, 20th Edition, or equivalent for analysis of SS, BOD, Ammonia, Nitrate and Phosphate concentrations.

Other relevant data such as monitoring location, time, water depth, temperature, salinity, weather conditions and any other special phenomena and work underway at the construction site will be recorded during sampling.

According to the requirement of the EM&A manual, two consecutive measurements for parameters of DO concentration, DO saturation and Turbidity are required to be taken at each monitoring. When the difference in value between the first and second reading of DO or Turbidity is more than 25%, the reading will be discarded and further reading will be taken.

6.2 Monitoring Equipment and Methodology

Turbidity, DO, Salinity, pH and Temperature will be measured by a instrument complied with the following requirements:

The instrument is a portable as well as weatherproof multimeter complete with cable and uses a DC power source. It is capable of measuring:

- A turbidity between 0-800NTU;
- A dissolved Oxygen level in the range of 0-20mg/L and 0-200% saturation;
- A temperature of 0-50^{o}C;
- Salinity in the range of 0-40ppt;
- pH in the range of 0-14.

Suspended solid was determined by the water samples collected from the

monitoring locations for further analysis in accredited HOKLAS laboratory. Water samples were contained by polythene bottles, packed in ice (cooled in 4^{o}C without frozen) and delivered to the laboratory for analysis as soon as possible after collection. Duplicate samples from each independent sampling event were undertaken during impact monitoring.

6.3 Monitoring Locations

According to the Final EM&A Manual, the improved section of the river channels will be divided into 50m long sections, and ecological survey will be carried out in each of the 50m sections. A total of nine sections will be divided for the two rivers which include:

- Two sections for existing upstream of PNH river (i.e. the proposed 80m long trapezoidal channel)
- Two sections for existing downstream of PNH river (i.e. the proposed 100m long rectangular channel)
- Five sections for existing Luk Tei Tong River (i.e. the proposed 240m long trapezoidal channel)

The disused watchtowers are located at the confluence of the three rivers and next to LTT river.

The Location Plan for ecological is shown in Figure 6.1 for reference.

The improved sections of the river channels require to carrying out water quality monitoring for the ecological purpose. The sampling points for impact monitoring was undertaken in the same place as the baseline monitoring proposed, where include:

- Three points for existing of PNH river
- Three points for existing of Luk Tei Tong River

The Location Plan for ecological water monitoring is shown in Figure 6.2 for reference.



Figure 6.1 Ecological Monitoring Locations



Figure 6.2 Ecological Water Quality monitoring locations

6.4 Monitoring Frequency

As proposed, ecological impact monitoring was carried out once for each monitoring location in the reporting month.

6.5 Monitoring results

Pak Ngan Heung Stream N and S sections

Vegetation

Surveys were conducted on 8 December 2009. The north section of Pak Ngan Heung Stream was fairly modified. Part of the west bank was lined with rock gabion bank and occupied by village houses and abandoned agricultural field. The stream channel was wider than the downstream section, but the stream bank was still fairly narrow and steep in gradient. Compared to the south section, the north section was relatively shaded due to presence of more trees with larger canopy. During the current monitoring session, new rock gabion wall on the east bank was under construction. Stream bank of PNH4 was still intact, while stream bank of PNH3 was almost cleared.

The walk through survey recorded a total of 67 species, including 22 trees, 9 shrub, 21 herb and 6 grass species (Appendix D1). 54 of the species recorded are natives, while 13 were exotics. The quantitative sampling on PNH4 recorded 19 species at the north section. Large native (e.g. *Ficus hispida, Macaranga tanarius, Litsea glutinosa*) dominated the transects. Other species recorded include common and typical native pioneer forest and streamside tree species and ruderal species. No species of conservation interest was recorded. No quantitative survey was carried out along PNH3 due to on-going vegetation clearance on stream banks as part of the site clearance works under the project.

Table 6.5.1 Relative percentage cover of vegetation recorded at Pak Ngan Heung (N) Section

	Relative % cover
Species	**PNH4**
Alocasia macrorrhiza	5.53
Aporosa dioica	2.35
Celtis sinensis	1.34
Christella parasitca	1.68
Dimocarpus longan	0.50
Ficus hispida	36.57
Floscopa scandens	0.34
Hedyotis auricularia	0.17
Hibiscus rosa-sinensis	1.51
Litsea glutinosa	15.42
Macaranga tanarius	13.41
Microstegium ciliatum	10.90
Mikania micrantha	4.02
Neyraudia reynaudiana	1.84
Paedaria scandens	0.07
Pueraria phaseoloides	0.67
Sageretia thea	0.67
Sporobolus fertilis	2.01
Wedelia triloba	1.01
Total Percetage Cover	100.0
Total Transect Length (m)	34

*Total Cover rounded up to one decimal place to avoid round-off error.

The south section of Pak Ngan Heung Stream was highly modified. Both banks were lined with rock gabions and were occupied by village houses immediately beyond the channel. The stream channel was lack of riparian zone and vegetation. A total of 8 species recorded, 6 of which were native and 2 were exotic. It was composed of isolated individuals of mangrove (*Kandelia obovata*), backshore species (*Clerodendrum inerme*) and native trees (*Celtis sinensis*, *Ficus microcarpa*) (Appendix D2). No species of conservation interest was recorded. During the current monitoring session, construction work at both Sections PNH1 and PNH2 were underway. Vegetation was only found on remnants of the old rocky bank.

Terrestrial Fauna

Surveys were conducted on 4 December 2009.

One species of birds were recorded in the proposed work area of the Pak Ngan Heung River (Table 6.5.2). Yellow-browed Warbler *Phylloscopus inornatus* is common in Hong Kong.

Table 6.5.2 Avifauna in Pak Ngan Heung

Common names	**Latin names**	**PNH 1**	**PNH 2**	**PNH 3**	**PNH 4**	**Commonness & distribution**
Yellow-browed Warbler	*Phylloscopus inornatus*				1	CW

CW = common and widespread

No dragonfly was recorded in the proposed work area of the Pak Ngan Heung River in December 2009.

Aquatic fauna and fish

8 species of fish and 2rustacean were recorded in the 4 sections at PNH. All are common and widespread in Hong Kong. Though Predaceous Chub was observed, the another one fish species of conservation concern reported in the EIA report, i.e. Flagtail *Kuhlia marginata*, was not recorded in PNH during the present monthly monitoring survey.

Table 6.5.4 Aquatic Invertebrates and fish in Pak Ngan Heung

Common names	Scientific names	PNH 1	PNH 2	PNH3	PNH4
Invertebrates					
Atyid shrimp	*Caridina elongata*				++
Palaemonid shrimp	*Macrobrachium hainanensis*			+	+
Crab	*Varuna litterata*				
Mitten Crab	*Eriocheir japonica*				
Fish					
Mosquito fish	*Gamusia affinis*				+
Goby	*Rhinogobius duospilus*				+
Barcheek Goby	*Rhinogobius giurinus*				
Swordtail	*Xiphophorus hellerii*				+
Six-banded Barb	*Puntius semifasciolatus*				+
Unidentified Cichlid fish					
Tilapia		+	++	++	
Predaceous Chub	*Parazacco spilurus*			++	+
Jarbua Terapon	*Terapon jarbua*	++			
Common Silver-biddy	*Gerres oyena*				
Mullet	*Mugil cephalus*	+	+++		
Broken-band Hillstream Loach	*Liniparhomaloptera disparis*				

+ = Occasional, less than 5 individuals were found; ++ = Common, 5 – 20 individuals were found; +++ = Abundant, more than 20 individuals were found.

Luk Tei Tong Stream Section

Vegetation

Surveys were conducted on 8 December 2009. The Luk Tei Tong Stream Section was highly modified. Vegetation only established on isolated muddy patches at the estuary and remaining semi-natural banks of LLT1, LLT2, and LLT5. Vegetation clearance was underway along LLT2 and was completed , along LLT3 and LLT 4 while LLT5 was still lined with old rock gabions. The whole section appeared to be subject to tidal influence, as mangrove associated or backshore species were recorded along the whole channel.

The walk through survey recorded a total of 14 species, including 7 tree, 3 shrub, 3 grass species (Appendix D3). 10 of the species recorded are natives, while 4 were exotics. No quantitative survey was carried out due to vegetation clearance on stream banks as part of the site clearance works under the project.

Terrestrial Fauna

The proposed work area of Luk Tei Tong River was divided into 5 sections. All recorded avifauna and dragonfly species are common in Hong Kong

Surveys were conducted on 4 December 2009.

A total of five species of birds were recorded in these sections (Table 6.5.6). All these species are common and widely distributed in Hong Kong.

Table 6.5.6 Avifauna in Luk Tei Tong River

Common names	Latin names	LTT 1	LTT 2	LTT 3	LTT 4	LTT 5	Commonness & distribution
Little Egret	*Egretta garzetta*	2					CW
Great Egret	*Casmerodius albus*	1					CW
Grey Heron	*Ardea cinerea*	1					CL
Common Sandpiper	*Actitis hypoleucos*	2					CW
White Wagtail	*Motacilla alba*	1					CW

CW = common and widespread, CL = common/uncommon and localised

Two species of dragonfly were recorded in the Luk Tei Tong River (Table 6.5.7). Both are common and widespread in Hong Kong.

Table 6.5.7 Dragonfly in Luk Tei Tong River

Common names	Latin names	LTT 1	LTT 2	LTT 3	LTT 4	LTT 5	Commonness & distribution
Green Skimmer	*Orthetrum sabina*	1				1	C
Wandering Glider	*Pantala flaviventris*	2				1	A

A = abundant, C = common

Aquatic invertebrates and fish

5 species of fish, 1 species of crustacean and 5species of mollusks were recorded in the 5 sections at LTT. All are common and widespread in Hong Kong. The two fish species of conservation concern reported in the EIA report, i.e. Flagtail *Kuhlia marginata* and Predaceous Chub *Parazacco spilurus* were not recorded in LTT during the present monitoring as well as the baseline monitoring survey.

Table 6.5.8 Aquatic invertebrates and fish in Luk Tei Tong River

Common names	Scientific names	LTT1	LTT2	LTT3	LTT4	LTT5
Invertebrates						
Mangrove clam	*Geloina erosa*					
Rock oyster	*Saccostrea cuculata*		++			
Snail	*Melanoides tuberculata*				+	
Snail	*Terebralia* sp.			+		
Snail	*Nerita* sp.		+		+	
Snail	*Littoraria articulata*		++			
Crab	*Varuna litterata*					
Fiddler crab	*Uca lactea*					
Fiddler crab	*Uca arcuata*					
Fiddler crab	*Uca crassipes*					
Sesarmid crab	*Perisesarma bidens*		++	+		
Mangrove mud crab	*Scylla paramamosain*					
Mitten crab	*Eriocheir japonica*					
Fish						
Common mudskipper	*Periophthalmus cantonensis*		+	+		
Tilapia		++	+	+		
Jarbua terapon	*Terapon jarbua*		++			
Mullet	*Mugil cephalus*	++	++	+++		
Common Silver-biddy	*Gerres oyena*					
Barcheek Goby	*Rhinogobius giurinus*				+	

+ = Occasional, less than 5 individuals were found; ++ = Common, 5 – 20 individuals were found; +++ = Abundant, more than 20 individuals were found.

Disused Watchtowers

Surveys were conducted on 4 December 2009.

There was no sign (e.g., adults carrying food or nesting materials) of use of the watchtower as nesting habitat by White-shouldered Starling.

White-shouldered Starling was not observed during the December2009 monitoring. No bird of other species was observed entering the watchtower. The breeding season of 2009 was already over.

Since the monitoring surveys commenced in August 2008, no bird was observed entering the watchtower. It seems the birds do not prefer the watchtower as roosting or nesting habitat.

Ecological Water Quality Monitoring (EWQM)

EWQM was conducted on 14 December 2009. Monitoring results are summarized in Table 6.9. Detailed on-site measurements and laboratory report are presented in Appendix D4 and D5.

Table 6.10 shows the baseline results of Ecological Water Quality Monitoring, from the information given in Baseline Monitoring Report.

To review the results in Table 6.9 in general, the measured results of Suspended Solids and Turbidity measured in WE3 (PNH River) and WE4 (LTT River) was found higher than the previous months. Such facts were believed to be caused by disturbance of sediments, and site effluent discharge due to construction activities.

Table 6.9 Summarized Ecological water quality monitoring results (14 Dec 2009)

Parameters	Limit of detection	WE1	WE2	WE3	WE4	WE5	WE6
Suspended Solid (mg/l)	1	1.40	1.85	10.70	5.70	8.35	1.00
Nitrogen (Ammonia) (mg/l)	0.01	0.05	0.14	0.13	0.23	2.89	0.04
Nitrogen (Nitrate) (mg/l)	0.01	0.09	0.16	0.38	0.42	0.15	0.05
Phosphorous (mg/l)	0.01	0.03	0.04	0.05	0.05	0.44	0.02
BOD_5 (mg/l)	1	1.00	1.00	1.00	1.00	2.00	1.00
DO (mg/l)	0.01	6.86	8.42	8.58	8.00	9.15	7.43
Turbidity (NTU)	0.1	0.00	0.00	8.40	2.40	3.10	0.00
Temperature (oC)	0.1	19.8	20.1	20.6	21.4	21.0	19.5
pH	0.01	7.28	7.72	7.88	7.11	7.12	6.87
Salinity (ppt)	0.1	0	0.2	2.3	13.7	2.1	0
Conductivity (ms/m)	0.1	10.6	56.5	79.4	207.0	407.0	5.9
Water Flow (m/s)	N/A	0.05	0.02	0.08	0.01	0.04	0

Table 6.10 Baseline Results of Ecological water quality monitoring

Parameters	WE1	WE2	WE3	WE4	WE5	WE6
Suspended Solid (mg/l)	1.0	2.0	3.0	3.0	<1	<1
Nitrogen (Ammonia) (mg/l)	0.07	0.12	0.11	0.23	0.03	0.02
Nitrogen (Nitrate) (mg/l)	0.12	0.13	0.13	0.31	0.04	0.05
Phosphorous (mg/l)	0.04	0.06	0.06	0.09	0.06	0.05
BOD_5 (mg/l)	<2	<2	<2	<2	<2	<2
DO (mg/l)	6.58	6.82	6.37	7.61	6.87	5.70
Turbidity (NTU)	4.44	5.12	5.93	6.96	4.65	2.73
PH	6.4	7.1	7.0	6.8	6.6	6.1
Salinity (ppt)	<0.1	0.1	0.3	7.6	0.1	<0.1

6.6 Action and Limit level for Monitoring of White-shouldered Starlings

A simple Event and Action Plan is shown in Table 6.6.1. Should the Event occur, action in accordance with the Action Plan should be carried out.

There was no recorded event in the reporting month.

Table 6.6.1 Event / Action Plan for Monitoring of White-shouldered Starlings

EVENT	ACTION	
	ET Leader	**Contractor**
Identification of disturbance to breeding White-shouldered Starlings	1. Increase frequency of monitoring to twice weekly	1. Check all construction actions and working methods
	2. Notify Site Engineer	2. Submit proposals for remedial action to prevent abandonment of the breeding site.
	3. Review construction activities of previous week.	3. Implement remedial action.
	4. Identify any changes in construction activities in previous week	4. Liaise with ET regarding effectiveness of remedial actions.
	5. Discuss remedial actions with Site Engineer	

6.7 Ecological monitoring Schedule

The next ecological surveys are scheduled on 15 and 22 January 2010, while ecological water quality monitoring is scheduled on 14 January 2010.

7. Action taken in Event of Exceedence

If the measurements (Noise, Water, Ecology) exceed the action / limit level, exceedance details will be reported and follow-up actions will be taken by relevant parties involved.

During the reporting period there was no exceedance for noise, ecological measurements recorded; therefore no actions were taken.

Total 66 non-compliance events of water quality limits (Turbidity and Suspended Solids) were recorded in this reporting month according to the established level. ET has arranged site investigations for the exceedance events. Although most of the water quality exceedance was believed to be caused by natural fluctuation, 6 events were identified to be substantially attributable to improper site practices. As such, the contractor was strongly recommended to review their sites condition and working method. Necessary as well as effective mitigation measures have to be implemented to minimize water quality impact from project site activities.

The summary of non-compliance events for water quality exceedance is listed in Table 7.1 for reference.

Table 7.1 Summary of Non-compliance for Water Quality

Date	Location	Parameter	Level of exceedance	Main cause of exceedance
7/12/09	M3	Turbidity, S.S.	Limit Level	Surface run-off and disturbance of sediment occurred due to excavation activities at riverside and influence of adverse weather.
16/12/09	M1	Turbidity, S.S.	Limit Level	Muddy effluent was directly discharged from site BC15 and retaining wall D to the river course
17/12/09	M1	Turbidity, S.S.	Limit Level	Muddy effluent was directly discharged from site BC15 and retaining wall D to the river course

8. Construction waste disposal

It is the contractor's responsibility to ensure that all wastes produced during the construction phase for the drainage improvement works are handled, stored and disposed of in accordance with good waste management practices and EPD's regulation and requirement. Waste materials generated during construction activities, such as construction and demolition (C&D) material, chemical wastes and general refuse, are recommended to be audited at regular intervals to ensure that proper storage, transportation and disposal practices are being implemented.

Contractor has completed the registration of Waste Producer under the Waste Disposal (Chemical Waste)(General) Regulation. The Waste Producer Number, WPN 5213-950-Y2443-03 was assigned by EPD on 12 Aug 2008. The Contractor would be responsible for the implementation of any mitigation measure to minimize waste or redress problems arising from the waste materials.

Table 8.1 is a summary of figures of the construction wastes disposal provided by Contractor.

Table 8.1 Summary of Construction Waste Disposal

	Amount of Construction Waste disposed		
Month	**Inert Waste (to Public Fill)**	**Non-inert Waste (to Landfill)**	**Chemical Waste (to treatment plant)**
1st to 31st Dec 09	955.90 (ton)	25.40 (ton)	Nil
Total	22798.16 (ton)	137.63 (ton)	0

9. Status of Permits and Licenses obtained

Table 9.1 is the updated status of environmental related permits/ license obtained for the construction activities

Table 9 .1 Status of Permits and Licenses Obtained

Description	License / Permit No.#	Date of Issue	Date of Expiry	Remarks
Environmental Permit	EP-237/2005/A	05 Mar 2007	--	Issued
Varied Environmental Permit	EP-237/2005/B	23 April 2009	--	Issued
Registration of C&D Waste Producer	7006521	--	--	Issued
Chemical Waste Producer	5213-950-Y2443-03	12 Aug 2008	--	Issued
Construction Noise Permit	N/A	N/A	N/A	N/A
Effluent Discharge License	EP890/W2/XG032 EP890/W2/XG033 EP890/W2/XG034 EP890/W2/XG035 EP890/W2/XG036 EP890/W2/XG037 EP890/W2/XG038 EP890/W2/XG039 EP890/W2/XG040 EP890/W2/XG041	23 Oct 2008	31 Oct 2013	Issued

The contractor implemented various environmental mitigation measures as recommended in the Environmental Permit and Final Mitigation Measures Report. The implemented schedule is presented in Appendix H.

10. Complaint Log

There was no formal complaint received during the reporting month.

Table 10.1 Summary of Formal Complaints received

	Noise	Water	Ecology	Cultural	Others
December 2009	0	0	0	0	0
Total	0	1	0	0	0

11. Site Environmental Audits

11.1 Site Inspection

With an intention to ensure that appropriate environmental protection and pollution control mitigation measures are properly implemented, regular environmental site inspections have been scheduled.

Within the reporting month, site inspections were conducted on 10, 17, 24 and 29 December 2009.

A detailed checklist of each site inspection together with comments, relevant photos and maps have been filed and kept. A summary of observation and follow-up action is shown in Table 11.1

Table 11.1 Summary of site inspection

Date	Observations	Advice from ET	Action taken	Closing Date
23 Oct 09	Influent was overflowing from the de-silting tank installed at site retaining wall D of PNH, and seeping to the nearby bushes	Contractor was recommended to review if the capacity of the de-silting tank is capable for site water treatment in the concerned area; additional de-silting tank should be provided and/or flow rate of influent should be controlled.	Site water seepage was ceased as the de-silting tank has been removed prior to the inspection on 17 Dec.	17 Dec 09
5 Nov 09	River water of PNHR at section outside retaining wall D and BC13 was observed to be muddy during inspection	Contractor was urged to trace the cause of contamination and implement necessary corrective actions and mitigation measures as soon as possible to stop further deterioration of water quality.	As retaining wall D was mostly finished, the concerned earth bund has been removed and no further muddy water discharge was observed from the site	10 Dec 09
19 and 24 Nov 09	Site water leakage was observed from soak-away pond to the marshland area next to Yuen's compound	Contractor was advised to implement corrective actions to stop further site water leakage as soon as possible.	No further site water diversion to the concerned soak-awp-0pond was observed during follow up inspections	10 Dec 09
24 Nov 09	River water in downstream of TTT River was observed to be muddy during inspection. Such condition was believed to be caused by construction activities	Contractor was urged to trace the cause of contamination and implement necessary corrective actions and mitigation measures as soon as possible to stop further deterioration of water quality.	Deterioration of water quality was ceased during follow up inspections as construction in concerned river was completed	10 Dec 09
30 Nov 09	No wheel washing facility was observed in construction site exit at bottleneck A and site connected to Ngan Shu Street	Contractor was requested to clean up mud deposited on public areas and provide adequate properly maintained wheel washing facilities at all site exit as soon as possible.	Follow up action for site bottleneck A was not conducted as the site was closed that reported by contractor. Provision of wheel washing bay at site entrance of retaining wall D was also not conducted but high jet water sprayer was provided on site	10 Dec 09

Table 11.1 Summary of site inspection

Date	Observations	Advice from ET	Action taken	Closing Date
30 Nov 09	Site water was overflowed to PNH River from construction site near retaining wall D	Contractor was required to provide and properly utilize site water treatment facilities such as properly maintained earth bunds and sedimentation tank on site	As retaining wall D was completed, the concerned earth bund and de-silting facilities causing site water seepage was removed. No further improper site water discharge was observed from site retaining wall D	17 Dec 09
30 Nov 09	Poorly maintained Soak-away pond was found at PNH box culvert site BC15 that accumulation of silt clay, algae, solid wastes were observed. Insufficient geo-textile covering and/or protection measures were provided to the soak-away pond also	Contractor was advised to provide regular cleaning and maintenance to maintain effectiveness of the soak-away pond. Proper bund wall and geo-textile materials should be provided also, to prevent erosion of the pond and site water run-off to the surrounding area	Deficiencies were still observed during inspections on 10 and 24 Dec. Further improvement works were required and to be followed with the outcome	Ongoing
30 Nov 09 & 29 Dec 09	Gaps were observed between sheet piles crossing located at LTT River site	Contractor was advised to provide improvement works to prevent grit, soil and site run-off entering the river course	Deficiencies were still observed during inspections on 29 Dec. Improvement works were required and to be followed with the outcome	Ongoing
10 Dec 09	Open stockpiles of earth materials were observed at site area of TTT bottleneck A	Contractor was advised to cover the stockpiles with tarpaulin coverings to prevent wind erosion and soil run-off	Follow up action has been taken as advised prior to the inspection on 17 Dec	17 Dec 09
10 Dec 09	Turbid water was found seeped into the river channel from the newly formed soak-away pond at LTT gabion wall site	Contractor was requested to provide improvement works to ensure site water was properly treated by sufficient as well as effective de-silting facility before discharge.	Usage of the concerned soak-away pond was ceased as reported by Contractor.	24 Dec 09
10 Dec 09	Site materials were found stockpiled on top of the earth bunds at BC1 of PNH	Contractor was advised to remove the concerned materials away from the bund to prevent site materials from dropping into the river channel causing pollution and clogging.	Follow up action has been taken as advised prior to the inspection on 24 Dec	24 Dec 09

Table 11.1 Summary of site inspection

Date	Observations	Advice from ET	Action taken	Closing Date
10 & 24 Dec 09	Drip pan for the power generator at gabion wall site was accumulated with stagnant water	Contractor was reminded to clean up the drip pan for mosquito control.	Stagnant water has been drained prior to the site inspection on 29 Dec	29 Dec 09
17, 24 & 29 Dec 09	Earth bunds and banks at LTT retaining wall site (outside Yuen's Compound) were not completely covered with geo-textile coverings	Contractor was advised to rectify such discrepancy to prevent soil run-off from entering the river channel.	Still outstanding. Improvement works were required and to be followed with the outcome	Ongoing
17 Dec 09	Wheel washing bay at site entrance to fish ladder site was filled with earth material and therefore it is not functional.	Contractor was recommended to rectify such discrepancy as to provide proper washing area for vehicles before leaving site.	Follow up action has been taken by contractor as advised prior to the inspection on 29 Dec	29 Dec 09
29 Dec 09	No protective measure was implemented to the surface channel that connected with the site at PNH and Ling Tsui Tau respectively	Contractor was recommended to provide proper coverings to the surface channel to avoid grit, soil and run-off from entering the public drainage	To be followed in the next reporting period	Ongoing

11.2 Compliance with legal and Contractual requirement

ET leader has reviewed the progress and programme of the works to check any relevant environmental laws has not violated.

11.3 Environmental Complaint and follow up actions

During this reporting period, there was no documented complaint received. Therefore, follow up actions for the environmental complaint is not required.

Further to the environmental concerns raised by green group during May 2009, Ecologist of ET has conducted a monthly survey to mangrove area at the east of Luk Tei Tong River. Details of findings refer to Appendix K.

12. Future key issues

As informed by contractor major site activities in the upcoming will include construction of box culverts, retaining walls, gabion walls, sloping sea wall and fish ladder on project sites. It is expected that several impacts on environmental aspects will be generated on-site. With reference to the EM&A manual, mitigation measure report as well as the environmental permit, proper mitigation measures are proposed to be taken, if necessary.

Contractor was seriously recommended to provide proper measures to mitigate water quality impacts to the river channels due to construction works. River based construction sites should be well enclosed by bunds in dry condition, as to prevent surface run-off and site water seepage to the stream. Bare soil surface, which is directly exposed to the river channel in the site area, should be completely covered with geo-textile to prevent soil erosion. For river-based and any construction activities carried at riverside, contractor should implement proper protection measures such as barriers and/or silt curtains to prevent surface run-off from entering water bodies.

Underground water and site water may be accumulated on site. Contractor is recommended to treat the accumulated site water by proper silt removal facilities before discharging to the designated discharge point; reuse of site water should be considered also. Channel, trench and manholes connected with project sites should be sealed to prevent site water and any construction materials entering public drainage and causing water quality impact.

Construction activities such as backfilling, earth movement may generate dust impact to the vicinity of sensitive receivers. Contractor is advised to provide regular water spraying for the dusty static area. Stockpiling may be found on site and those should be covered by tarpaulin to prevent erosion and run-off.

Heavy plants and vehicles may be deployed for the construction and those would generate certain noise impacts to the sensitive receivers. Noisy activities should be well planned and scheduled to avoid parallel operation of multiple plants, so as to minimize noise impacts to the nearby sensitive receivers.

13. Conclusions

In this reporting month, major site activities included haul access formation, construction of retaining walls, gabion wall and box culvert at PNH River and LTT River respectively.

Regular site meetings and inspection audits led by the seniors for discussing site environmental matters were held among Project Proponent, Contractor and the ET on weekly basis. Also monthly site meeting and inspection audits with the above parties and IEC were carried out on 29 December 2009.

For noise level monitoring, all results were within the established A/L limits.

For water quality monitoring, total 66 non-compliance events of water quality criteria were recorded in this reporting month. Except the natural fluctuation, 6 events were believed to be caused by improper site practices. Hence, the contractor was urged to review the site condition and implement necessary mitigation measures and corrective actions as soon as possible to minimize water quality impact due to site works.

During ecological monitoring survey, no White-shouldered Starling was recorded breeding in the watch tower. There was no sign of disturbance from the Project to the watch tower. The absence of nesting of White-shouldered Starling in the watch tower did not seem to be related to construction works in Luk Tei Tong River. A bird species nests in village house should be to certain extent disturbance tolerant.

No bird was observed entering the watchtower since the monitoring surveys commenced in August 2008. Also, no breeding was recorded in the baseline survey in September 2007. It appears that the birds do not prefer to roost or nest in the watch tower.

Also, there were not any notifications of summons recorded during the reporting period. Furthermore, there were not any formal prosecution and complaints recorded.

Site water control was the major concern in this reporting month. Therefore, ET recommended the contractor to implement sufficient and effective mitigation measures to minimize water quality impact from site works. Proper

de-silting facilities should be provided for site water treatment. To prevent surface run-off and soil erosion from site activities, earth bunds with complete coverage of geo-textile materials should be formed at river-based and/or riverside project sites. Contractor should be cautious on change of river water quality, immediate corrective action was required once muddy effluent discharge, or disturbance of sediment was found from site works.

ET has reminded the contractor to provide environmental pollution control measures wherever necessary; and to keep a good environmental management at site practice.

The ET will continue to implement the environmental monitoring & audit programme in accordance with the EM&A Manual and Environmental Permit requirement.

Appendix A

Construction Programmer and Location plan

Act ID	Description	Orig Dur	Rem Dur	Early Start	Early Finish	%	Predecessors
0000	DRAINAGE IMPROVEMENT WORK IN S LANTAU	534 *	534 *	06AUG2009	21JAN2011	0	
0001	Section Commencement	11	0	07JAN2008 A	17JAN2008 A	100	
0010	Preliminaries	534 *	534 *	06AUG2009	21JAN2011	0	
0020	Engineer's Accommodation	80	0	07JAN2008 A	26MAR2008 A	100	
0030	Contactor's Accommodation	55	0	07JAN2008 A	01MAR2008 A	100	
0040	Engineer's Accommodation (Secondary)	40	0	07JAN2008 A	15FEB2008 A	100	
0050	Record Survey & Site Investigation	180	0	07JAN2008 A	04JUL2008 A	100	
0060	Recruitment of Environment Team	80	0	07JAN2008 A	26MAR2008 A	100	
0070	Establish Base line monitoring for EP	30	0	27MAR2008 A	25APR2008 A	100	**0060**
0080	Monitoring for Environmental Permit	1001	534	26APR2008 A	21JAN2011	47	**0070**
0100	Temporary Traffic Management Schemes	180	0	07JAN2008 A	04JUL2008 A	100	
0110	Construction Proposals and Submissions	80	0	07JAN2008 A	26MAR2008 A	100	
0120	Permits Application & Approval	180	0	07JAN2008 A	04JUL2008 A	100	
0130	Liaison Works with Others (Initial)	220	0	07JAN2008 A	13AUG2008 A	100	
0140	Temporary Noise Barrier (Fabrication)	60	0	14AUG2008 A	12OCT2008 A	100	**0130**
1000	Works at Ling Tsui Tau &TTT River (D2&D3, D4)	510	0	18JAN2008 A	10JUN2009 A	100	**0001**
1010	Drainage Channel at Ling Tsui Tau (D2&D3)	510	0	18JAN2008 A	10JUN2009 A	100	**0001**
1020	Sub. & app. from AMO by Archaeologist	268	0	07JAN2008 A	30SEP2008 A	100	
1030	Covered U-Channel	0	0	01OCT2008 A		100	**1020**
1031	600 & Covered 750 U-Channel (D3)	120	0	01OCT2008 A	28JAN2009 A	100	**1030**
1032	Covered 300 U-Channel (D2)	30	0	25FEB2009 A	26MAR2009 A	100	**1030**
1040	Concrete Pipe Drainage at Ling Tsui Tau (D3)	0	0	22APR2009 A		100	
1041	CP1.3 to MH1.4 (2 x DN600)	14	0	22APR2009 A	05MAY2009 A	100	**1040**
1042	MH1.4 to MH1 (2 x DN 600)	14	0	06MAY2009 A	19MAY2009 A	100	**1041**
1043	MH1 to MH2 (2 x DN 600)	21	0	20MAY2009 A	09JUN2009 A	100	**1042**
1044	MH2 to MH3 (2 x DN 600)	75	18	10JUN2009 A	23AUG2009	76	**1043**
1045	MH3 to MH4 (2 x DN 600)	21	21	21AUG2009 *	10SEP2009	0	**1044**
1046	MH4 to MH5 (2 x DN 600)	14	14	11SEP2009	24SEP2009	0	**1045**
1047	MH5 to MH6 (2 x DN 600)	14	14	25SEP2009	08OCT2009	0	**1046**
1048	MH6 to MH7 (2 x DN 600)	14	14	09OCT2009	22OCT2009	0	**1047**
1049	MH7 to MH8 (2 x DN 750)	80	42	29JUN2009 A	16SEP2009	48	
1050	MH8 to Outlet Structure	21	21	23OCT2009	12NOV2009	0	**1048, 1049**
1100	Gabion Channel at Tai Tei Tong River (D4)	510	0	18JAN2008 A	10JUN2009 A	100	**0001**
1110	Preparation Work for Gabion Channel	409	0	18JAN2008 A	01MAR2009 A	100	**0001**
1120	Bottleneck A widening excavation (LHS)	10	0	02MAR2009 A	11MAR2009 A	100	**1110**
1121	Bottleneck A type 6 gabion (LHS)	20	0	12MAR2009 A	31MAR2009 A	100	**1120**
1122	Bottleneck A widening excavation (RHS)	10	0	01APR2009 A	10APR2009 A	100	**1121**
1123	Bottleneck A type 6 gabion (RHS) & river bed	20	0	11APR2009 A	30APR2009 A	100	**1122**
1130	Approval of temp access from bottleneck A to B	60	0	31MAR2009 A	29MAY2009 A	100	
1131	Forming of access form bottleneck A to B	12	0	30MAY2009 A	10JUN2009 A	100	**1130**
1132	Bottleneck B widening excavation (North Side)	85	29	11JUN2009 A	03SEP2009	66	**1131**
1133	Bottleneck B type 6 gabion (South Side)	25	25	04SEP2009	28SEP2009	0	**1132**
1134	Bottleneck B widening excavation (RHS)	14	14	29SEP2009	12OCT2009	0	**1133**
1135	Bottleneck B type 6 gabion (RHS) & river bed	14	14	13OCT2009	26OCT2009	0	**1134**
1140	Reinforced Concrete Retaining Wall [H]	0	0	01APR2009 A		100	
1141	R C Retaining Wall H	180	53	01APR2009 A	27SEP2009	71	**1140**
1150	Drainage Works for Channels & Retaining Wall	0	0	07JAN2008 A		100	
1151	U-Channel and Catchpit for Widened Bottle Neck A	15	15	27OCT2009	10NOV2009	0	**1123, 1135**
1152	U-Channel and Catchpit for Widened Bottle Neck B	15	15	27OCT2009	10NOV2009	0	**1135**
1153	U-Channel and Catchpit for Retaining Wall H	20	20	28SEP2009	17OCT2009	0	**1141**
1160	Soft & Hard Landscaping Works	0	0	18OCT2009		0	**1123, 1153**
1170	Hard Landscaping & Paving Works	50	50	18OCT2009	06DEC2009	0	**1153**
1180	Soft Landscaping (Planting) Works	50	50	18OCT2009	06DEC2009	0	**1153**
1200	Phase 2 sewerage works at TTT river	60	60	01SEP2009 *	30OCT2009	0	
1210	Submission and approval MS by DSD & EPD	90	0	01MAY2009 A	29JUL2009 A	100	
1220	Excavation 1st half trench at TTT river	20	20	01SEP2009 *	20SEP2009	0	**1210**
1230	Pipe laying and backfilling 1st half trench	5	5	21SEP2009	25SEP2009	0	**1220**
1240	Excavation 2nd half trench at TTT river	20	20	26SEP2009	15OCT2009	0	**1230**



Start date	07JAN2008
Finish date	21JAN2011
Data date	06AUG2009
Run date	15AUG2009
Page number	1A
c Primavera Systems, Inc.	

Yick Hing Construction Co. Ltd.

Drainage Improvement Work in South Lantau
and Construction of Mui Wo Village Sewerage Phase 1

Master Programme (Rev.9b)

Early bar
Progress bar
Critical bar
Summary bar
Start milestone point
Finish milestone point

Act ID	Description	Orig Dur	Rem Dur	Early Start	Early Finish	%	Predecessors
1250	Pipe laying and backfilling 2nd half trench	5	5	16OCT2009	20OCT2009	0	**1240**
1260	Connection to existing manholes	4	4	21OCT2009	24OCT2009	0	**1250**
1270	Site clearance and reinstatement of river	5	5	25OCT2009	29OCT2009	0	**1260**
2000	Works at D6, D7 & D8 (HTST, LUT & CShST)	614	48	18JAN2008 A	22SEP2009	92	**0001**
2100	Drainage Works at Pui O - Ham Tin San Tsuen (D6)	614	48	18JAN2008 A	22SEP2009	92	**0001**
2110	Preparation works	430	0	18JAN2008 A	22MAR2009 A	100	**0001**
2111	Sheet piling for flood protection wall	120	0	23MAR2009 A	20JUL2009 A	100	**2110**
2112	Set up cover dam for excavation of FPW	90	0	23MAR2009 A	20JUN2009 A	100	**2110**
2113	excavation and shoring for bay 1 FPW	50	4	21JUN2009 A	09AUG2009	92	**2112**
2114	Concreting mass concrete wall bay 1 FPW	30	30	10AUG2009	08SEP2009	0	**2113**
2115	excavation and shoring for bay 2 FPW	20	20	09SEP2009	28SEP2009	0	**2114**
2116	Concreting mass concrete wall bay 2 FPW	15	15	29SEP2009	13OCT2009	0	**2115**
2117	excavation and shoring for bay 3 FPW	20	20	14OCT2009	02NOV2009	0	**2116**
2118	Concreting mass concrete wall bay 3 FPW	15	15	03NOV2009	17NOV2009	0	**2117**
2120	Associated Railing & Paving Works	60	60	29SEP2009 *	27NOV2009	0	**2113, 2118**
2130	Associated Granite Paving (vertical)	60	60	29SEP2009	27NOV2009	0	**2113, 2118**
2200	Drainage Works at Pui O - Lo Uk Tsuen (D7)	614	48	18JAN2008 A	22SEP2009	92	**0001**
2210	Permit Application and Approval	400	0	18JAN2008 A	20FEB2009 A	100	**0001**
2211	Mobilization of plant and equipment	5	0	21FEB2009 A	25FEB2009 A	100	**2210**
2212	Trial holes excavation	15	0	26FEB2009 A	12MAR2009 A	100	**2211**
2213	Reinstatement of trial hole	5	0	13MAR2009 A	17MAR2009 A	100	**2212**
2220	Issuing VO no.8 (Twin DI pipe crossing CP A & B)	1	0	06APR2009 A	06APR2009 A	100	
2223	Mobilization of plant and equipment	10	0	07APR2009 A	16APR2009 A	100	**2220**
2224	Pipe layer at crossing CP A to MH6	65	0	17APR2009 A	20JUN2009 A	100	**2223**
2225	Reinstatement of carriageway at CP A	7	0	21JUN2009 A	27JUN2009 A	100	**2224**
2226	Excavation of crossing at CP B to MH7	70	0	17APR2009 A	25JUN2009 A	100	**2223**
2227	Reinstatement of carriageway at CP B	7	0	26JUN2009 A	02JUL2009 A	100	**2226**
2230	Pre-cast Concrete Pipeline and Manhole	0	0	03JUL2009 A		100	**2225, 2227**
2231	MH6 to MH7	105	71	03JUL2009 A	15OCT2009	32	**2230**
2232	MH7 to MH8	60	60	16OCT2009	14DEC2009	0	**2231**
2233	MH8 to MH9	45	45	15DEC2009	28JAN2010	0	**2232**
2234	MH9 to MH10	31	31	29JAN2010	28FEB2010	0	**2233**
2235	MH10 to Outlet B	21	21	01MAR2010	21MAR2010	0	**2234**
2236	Connection to existing catchpit A & B	7	7	17MAR2010	23MAR2010	0	**2235**
2240	Reinstatement of South Lantau Road	170	170	16OCT2009	03APR2010	0	**2231, 2236**
2300	Drainage Works at Cheung Sha Sheung Tsuen (D8)	614	48	18JAN2008 A	22SEP2009	92	**0001**
2310	Permit Application and Approval	353	0	18JAN2008 A	04JAN2009 A	100	**0001**
2311	Mobilization of plant and equipment	5	0	05JAN2009 A	09JAN2009 A	100	**2310**
2312	DSD request a quotation for re-lining	35	0	18APR2009 A	22MAY2009 A	100	**2311**
2313	Approval of re-lining	60	0	23MAY2009 A	21JUL2009 A	100	**2312**
2314	Material ordering	75	60	22JUL2009 A	04OCT2009	20	**2313**
2315	MHS2 - MHS1	3	3	05OCT2009	07OCT2009	0	**2314**
2316	MHS1 - MHS0	3	3	08OCT2009	10OCT2009	0	**2315**
2317	MHS0 - Outlet	3	3	11OCT2009	13OCT2009	0	**2316**
2340	Site clearance	5	5	14OCT2009	18OCT2009	0	**2317**
3000	Box Culvert & Gabion Wall at PNH River (D1)	926	360	18JAN2008 A	31JUL2010	61	**0001**
3010	Preparation of Works & Frogs Capture	288	0	18JAN2008 A	31OCT2008 A	100	**0001**
3020	EVA application	224	0	18JAN2008 A	28AUG2008 A	100	**0001**
3030	Erection of Control Gate of EVA	25	0	29AUG2008 A	22SEP2008 A	100	**3020**
3040	Maintenance of EVA	876	534	29AUG2008 A	21JAN2011	39	**3020**
3100	Pak Ngan Heung River Box Culvert	0	0	29AUG2008 A		100	**3020**
3110	Construction of Wheel Washing Bays	30	0	29AUG2008 A	27SEP2008 A	100	**3100**
3111	RC Box Culvert (3mx3mx2,25m) Bay 10	35	0	28SEP2008 A	01NOV2008 A	100	**3110**
3112	RC Box Culvert (3mx3mx2,25m) Bay 9	35	0	21OCT2008 A	24NOV2008 A	100	**3111**
3113	RC Box Culvert (3mx3mx2,25m) Bay 2	35	0	13NOV2008 A	17DEC2008 A	100	**3112**
3114	RC Box Culvert (3mx3mx2,25m) Bay 3	35	0	06DEC2008 A	09JAN2009 A	100	**3113**
3115	RC Box Culvert (3mx3mx2,25m) Bay 11	45	0	29DEC2008 A	11FEB2009 A	100	**3114**
3116	RC Box Culvert (3mx3mx2,25m) Bay 12	45	0	31JAN2009 A	16MAR2009 A	100	**3115**
3117	Approval of tree felling at Mui Wo	1	0	30APR2009 A	30APR2009 A	100	



Start date	07JAN2008
Finish date	21JAN2011
Data date	06AUG2009
Run date	15AUG2009
Page number	2A

Yick Hing Construction Co. Ltd.

Drainage Improvement Work in South Lantau
and Construction of Mui Wo Village Sewerage Phase 1

Master Programme (Rev.9b)

Early bar
Progress bar
Critical bar
Summary bar
Start milestone point
Finish milestone point

Act ID	Description	Orig Dur	Rem Dur	Early Start	Early Finish	%	Predecessors
3118	RC Box Culvert (3mx3mx2,25m) Bay 13	55	0	01MAY2009 A	24JUN2009 A	100	3117
3119	Approval of tree tranplant at bay 7 & 8	41	0	01MAY2009 A	10JUN2009 A	100	
3120	RC Box Culvert (3mx3mx2,25m) Bay 8	40	0	11JUN2009 A	20JUL2009 A	100	3119
3121	RC Box Culvert (3mx3mx2,25m) Bay 7	40	19	16JUL2009 A	24AUG2009	53	3120
3122	Awaiting divertion of UU at bay 4, 5 & 6	70	0	01MAY2009 A	09JUL2009 A	100	
3123	RC Box Culvert (3mx3mx2,25m) Bay 4	40	13	10JUL2009 A	18AUG2009	68	3122
3124	RC Box Culvert (3mx3mx2,25m) Bay 5	40	40	14AUG2009	22SEP2009	0	3123
3125	RC Box Culvert (3mx3mx2,25m) Bay 6	35	35	18SEP2009	22OCT2009	0	3124
3130	Backfill and Reinstatement EVA	20	20	23OCT2009	11NOV2009	0	3125
3140	Backfilling for RC Box Culvert	385	108	02NOV2008 A	21NOV2009	72	3111, 3125
3150	PNHR Box Culvert Inlet & Outlet Structure	0	0	01NOV2009 *		0	
3160	RC Box Culvert Outlet Structure (Bay 14)	50	50	01NOV2009	20DEC2009	0	3150
3170	RC Box Culvert Inlet Structure (Bay 1-Partly)	50	50	11NOV2009	30DEC2009	0	3150
3300	RC Retaining Walls at PNH River (D1)	0	0	01OCT2009 *		0	
3310	RC Retaining Wall A	0	0	15NOV2009		0	3510
3311	Retaining Wall A - Bay 1	20	20	15NOV2009	04DEC2009	0	3310
3312	Retaining Wall A - Bay 3	15	15	25NOV2009	09DEC2009	0	3311
3313	Retaining Wall A - Bay 2	15	15	30NOV2009	14DEC2009	0	3312
3314	Retaining Wall A - Bay 4	15	15	05DEC2009	19DEC2009	0	3313
3315	Gabion block at retaining wall A	5	5	20DEC2009	24DEC2009	0	3314
3320	RC Retaining Wall B	0	0	31DEC2009		0	3170, 3315
3321	Retaining Wall B - Bay 1	20	20	31DEC2009	19JAN2010	0	3320
3322	Retaining Wall B - Bay 2	15	15	10JAN2010	24JAN2010	0	3321
3323	Retaining Wall B - Bay 3	15	15	15JAN2010	29JAN2010	0	3322
3324	Retaining Wall B - Bay 4	15	15	20JAN2010	03FEB2010	0	3323
3325	Retaining Wall B - Bay 5	15	15	25JAN2010	08FEB2010	0	3324
3326	Retaining Wall B - Bay 6	15	15	30JAN2010	13FEB2010	0	3325
3327	Gabion block at retaining wall B	5	5	14FEB2010	18FEB2010	0	3326
3330	RC Retaining Wall C	0	0	01NOV2009 *		0	
3331	Retaining Wall C - Bay 1	30	30	01NOV2009	30NOV2009	0	3330
3332	Retaining Wall C - Bay 2	30	30	01DEC2009	30DEC2009	0	3331
3333	Retaining Wall C - Bay 3	30	30	31DEC2009	29JAN2010	0	3332
3334	Gabion block at retaining wall C	7	7	30JAN2010	05FEB2010	0	3333
3340	RC Retaining Wall D	0	0	01AUG2009 A		100	
3341	Retaining Wall D - Bay 1	30	30	01NOV2009 *	30NOV2009	0	3344
3342	Retaining Wall D - Bay 2	21	21	01DEC2009	21DEC2009	0	3341
3343	Retaining Wall D - Bay 3	21	16	01AUG2009 A	21AUG2009	24	3340
3344	Retaining Wall D - Bay 4	15	15	22AUG2009	05SEP2009	0	3343
3345	Gabion block at retaining wall D	7	7	22DEC2009	28DEC2009	0	3342
3350	RC Retaining Wall E	0	0	01NOV2009 *		0	
3351	Retaining Wall E - Bay 1	30	30	01NOV2009	30NOV2009	0	3350
3352	Retaining Wall E - Bay 2	30	30	01DEC2009	30DEC2009	0	3351
3360	RC Maintanence Ramp	0	0	06SEP2009		0	3344
3361	Ramp bay 1	20	20	06SEP2009	25SEP2009	0	3360
3362	Ramp bay 2	20	20	26SEP2009	15OCT2009	0	3361
3363	Ramp bay 3	30	30	16OCT2009	14NOV2009	0	3362
3368	Gabion block at maint. ramp	10	10	15NOV2009	24NOV2009	0	3363
3369	Turning Bay & Maintenance Access	70	70	26SEP2009	04DEC2009	0	3361
3370	Retaining Wall F	0	0	05DEC2009		0	3369
3371	Retaining Wall F - Bay 1	30	30	05DEC2009	03JAN2010	0	3370
3372	Retaining Wall F - Bay 2	30	30	30DEC2009	28JAN2010	0	3371
3373	Retaining Wall F - Bay 3	25	25	24JAN2010	17FEB2010	0	3372
3374	Gabion block at retaining wall F	7	7	18FEB2010	24FEB2010	0	3373
3380	RC Retaining Wall G	0	0	27MAR2010		0	3421
3381	Retaining Wall G - Bay 1	30	30	27MAR2010	25APR2010	0	3380
3382	Retaining Wall G - Bay 2	30	30	11APR2010	10MAY2010	0	3381
3383	Retaining Wall G - Bay 3	30	30	26APR2010	25MAY2010	0	3382
3384	Retaining Wall G - Bay 4	30	30	11MAY2010	09JUN2010	0	3383



Start date	07JAN2008
Finish date	21JAN2011
Data date	06AUG2009
Run date	15AUG2009
Page number	3A

Yick Hing Construction Co. Ltd.

Drainage Improvement Work in South Lantau
and Construction of Mui Wo Village Sewerage Phase 1

Master Programme (Rev.9b)

Early bar
Progress bar
Critical bar
Summary bar
Start milestone point
Finish milestone point

Act ID	Description	Orig Dur	Rem Dur	Early Start	Early Finish	%	Predecessors
3385	Retaining Wall G - Bay 5	30	30	26MAY2010	24JUN2010	0	**3384**
3386	Gabion block at retaining wall G	10	10	25JUN2010	04JUL2010	0	**3385**
3400	Alternative Mass Retaining Walls 1& 2	0	0	22DEC2009		0	**3342**
3410	RW1	45	45	22DEC2009	04FEB2010	0	**3400**
3411	Skin Wall for RW1	15	15	05FEB2010	19FEB2010	0	**3410**
3412	Gabion block at RW1	7	7	20FEB2010	26FEB2010	0	**3411**
3420	RW2	35	35	05FEB2010	11MAR2010	0	**3352, 3410**
3421	Skin Wall for RW2	15	15	12MAR2010	26MAR2010	0	**3420**
3422	Gabion block at RW2	7	7	27MAR2010	02APR2010	0	**3421**
3500	Gabion Wall (Type 2, 3, 4 & 5) at PNH River	0	0	01OCT2009 *		0	
3510	Gabion Wall (opposite to RW-A & B)	45	45	01OCT2009	14NOV2009	0	**3500**
3530	Fish Ladder and Diversion Dam	50	50	14FEB2010	04APR2010	0	**3326**
3600	Drainage Works Provision to New PNHR Channel	0	0	10JUN2010		0	**3385**
3610	Pre-cast Pipe Drains	50	50	10JUN2010	29JUL2010	0	**3600**
3620	Concrete U-Channels	50	50	10JUN2010	29JUL2010	0	**3600**
3630	Catchpits	50	50	10JUN2010	29JUL2010	0	**3600**
4000	Luk Tei Tong Bypass Channel and River (D5)	926	360	18JAN2008 A	31JUL2010	61	**0001**
4010	Preparation Work	288	0	18JAN2008 A	31OCT2008 A	100	**0001**
4020	No Excavation Period (1)	214	0 *	01APR2008 A	31OCT2008 A	100	
4100	Luk Tei Tong By-pass Channel	0	0	01NOV2008 A		100	**4020**
4101	General Site Clearance	20	0	01NOV2008 A	20NOV2008 A	100	**4100**
4102	Mobilization of Plant and Equipment	15	0	21NOV2008 A	05DEC2008 A	100	**4101**
4103	Preparation Work of Gabion Block Mesh	61	0	01NOV2008 A	31DEC2008 A	100	**4100**
4110	LTT By-pass Channel (CH0+50 to Ch2+60)	0	0	01JAN2009 A		100	**4103**
4111	LTT BPC CH2A 2+60 to CH2A 2+00	30	0	01JAN2009 A	30JAN2009 A	100	**4110**
4112	LTT BPC CH2A 2+00 to CH2A 1+50	30	0	21JAN2009 A	19FEB2009 A	100	**4111**
4113	LTT BPC CH2A 1+50 to CH2A 1+00	30	0	10FEB2009 A	11MAR2009 A	100	**4112**
4114	LTT BPC CH2A 1+00 to CH2A 0+50	30	0	02MAR2009 A	31MAR2009 A	100	**4113**
4200	No Excavation Period (2)	214	87 *	01APR2009 A	31OCT2009	59	**4110**
4210	LTT By-pass Channel (CH2A 2+60 to Ch2A 3+30)	0	0	01NOV2009		0	**4200**
4211	LTT BPC CH2A 2+60 to CH2A 3+00	30	30	01NOV2009	30NOV2009	0	**4210**
4212	LTT BPC CH2A 3+00 to CH2A 3+30	50	50	21NOV2009	09JAN2010	0	**4211**
4220	LTT By-pass Channel (CH2A 0+50 to Ch2A 0+00)	0	0	01NOV2009		0	**4200**
4221	LTT BPC CH2A 0+50 to CH2A 0+00	50	50	01NOV2009	20DEC2009	0	**4220**
4230	LTT Rectangular Channel A	90	90	21DEC2009	20MAR2010	0	**4221**
4240	Box Culvert - A	75	46	08JUL2009 A	20SEP2009	39	
4241	Reprovision of EVA & Footpath at BC-A	10	10	21SEP2009	30SEP2009	0	**4240**
4250	Box Culvert - B	60	0	31JAN2009 A	31MAR2009 A	100	**4111**
4260	Reprovision of EVA & Footpath at BC-B	180	53	01APR2009 A	27SEP2009	71	**4250**
4300	LTT River Channel & Sea Wall	0	0	01NOV2009		0	**4200**
4310	LTT RC (CH2B 0+00 to CH2B 1+50) East Side	0	0	01NOV2009		0	**4300**
4311	LTT RC (CH2B 0+00 to CH2B 0+50) ES	31	31	01NOV2009	01DEC2009	0	**4310**
4312	LTT RC (CH2B 0+50 to CH2B 1+00) ES	25	25	22NOV2009	16DEC2009	0	**4311**
4313	LTT RC (CH2B 1+00 to CH2B 1+50) ES	25	25	07DEC2009	31DEC2009	0	**4312**
4314	LTT RC (CH2B 2+00 to CH2B 0+00) West Side	0	0	20JAN2010		0	**4313, 4428**
4315	LTT RC (CH2B 2+00 to CH2B 1+50) WS	30	30	20JAN2010	18FEB2010	0	**4314**
4316	LTT RC (CH2B 1+50 to CH2B 1+00) WS	25	25	19FEB2010	15MAR2010	0	**4315**
4317	No works between Apr & Oct 2010	214	214	01APR2010 *	31OCT2010	0	
4318	LTT RC (CH2B 1+00 to CH2B 0+50) WS	30	30	01NOV2010	30NOV2010	0	**4317**
4319	LTT RC (CH2B 0+50 to CH2B 0+00) WS	16	16	01DEC2010	16DEC2010	0	**4318**
4320	LTT Sea Wall (CH2B 2+00 to CH2B3+00)	0	0	01NOV2009		0	**4300**
4321	LTT SW (CH2B 3+00 to CH2B2+50)	75	75	01NOV2009	14JAN2010	0	**4320**
4322	LTT SW (CH2B 2+00 to CH2B2+50)	75	75	15JAN2010	30MAR2010	0	**4321**
4323	Coping Concret Wall	50	50	31MAR2010	19MAY2010	0	**4322**
4324	Drainage & Railing	88	88	24APR2010	20JUL2010	0	**4323**
4340	RC Retaining Wall J at LTT River (D5)	0	0	01JUN2009 A		100	
4341	Retaining Wall J - Bay 1	30	0	01JUN2009 A	30JUN2009 A	100	**4340**
4342	Retaining Wall J - Bay 2	21	0	01JUL2009 A	21JUL2009 A	100	**4341**



Start date	07JAN2008
Finish date	21JAN2011
Data date	06AUG2009
Run date	15AUG2009
Page number	4A

Yick Hing Construction Co. Ltd.

Drainage Improvement Work in South Lantau
and Construction of Mui Wo Village Sewerage Phase 1

Master Programme (Rev.9b)

Early bar
Progress bar
Critical bar
Summary bar
Start milestone point
Finish milestone point

Act ID	Description	Orig Dur	Rem Dur	Early Start	Early Finish	%	Predecessors
4343	Retaining Wall J - Bay 3	21	6	22JUL2009 A	11AUG2009	71	4342
4344	Retaining Wall J - Bay 4	21	21	12AUG2009	01SEP2009	0	4343
4345	Retaining Wall J - Bay 5	21	21	02SEP2009	22SEP2009	0	4344
4346	Retaining Wall J - Bay 6	25	25	23SEP2009	17OCT2009	0	4345
4347	Retaining Wall J - Bay 7	25	25	18OCT2009	11NOV2009	0	4346
4400	Phase 2 sewer at LTT River (Section A)	149	149	01NOV2009 *	29MAR2010	0	
4420	Section A Sewers (J139a.1 - J146a.1)	80	80	01NOV2009 *	19JAN2010	0	
4421	Sewers J139a.1	12	12	01NOV2009 *	12NOV2009	0	
4422	Sewers J140a.1	12	12	13NOV2009	24NOV2009	0	4421
4423	Sewers J141a.1	12	12	25NOV2009	06DEC2009	0	4422
4424	Sewers J142a.1	12	12	07DEC2009	18DEC2009	0	4423
4425	Sewers J143a.1	12	12	19DEC2009	30DEC2009	0	4424
4427	Sewers J144a.1	12	12	31DEC2009	11JAN2010	0	4425
4428	Sewers J146a.1	8	8	12JAN2010	19JAN2010	0	4427
4430	Section A Sewers (144.1, B135.1 & B136.1)	69	69	20JAN2010	29MAR2010	0	4428
4431	Sewers 144.1	10	10	20JAN2010	29JAN2010	0	4428
4433	Sewers B135.1	10	10	20JAN2010	29JAN2010	0	4428
4434	Sewers B136.1	10	10	30JAN2010	08FEB2010	0	4433
4435	Reinstatement of gabion block	20	20	09FEB2010	28FEB2010	0	4434
4500	Mini-bored Pile Wall C at LTT River	60	60	01NOV2009 *	30DEC2009	0	
4510	Mini-bored Pile Wall C (RC Retaining Wall)	0	0	01NOV2009 *		0	
4511	MP-C bay 1	14	14	01NOV2009	14NOV2009	0	4510
4512	MP-C bay 2	14	14	12NOV2009	25NOV2009	0	4511
4513	MP-C bay 3	14	14	23NOV2009	06DEC2009	0	4512
4514	MP-C bay 4	14	14	04DEC2009	17DEC2009	0	4513
4515	MP-C bay 5	14	14	15DEC2009	28DEC2009	0	4514
4520	Skin Wall for PPW - C	24	24	07DEC2009	30DEC2009	0	4513
4800	Remain Works within PNH & LTT River (D1&D5)	1010	444	18JAN2008 A	23OCT2010	56	0001
4810	Approval of use of EVA	0	0	29AUG2008 A		100	3020
4820	No exca period (1) at Confluence of PNH,TTT&LTT	214	0	01APR2008 A	31OCT2008 A	100	
4830	Works within Section 3 (A) at PNH River	151	0	01NOV2008 A	31MAR2009 A	100	4820
4840	Works within Section 3 (B) at LTT River	151	0	01NOV2008 A	31MAR2009 A	100	4820
4850	No exca period (2) at Confluence of PNH,TTT&LTT	214	87	01APR2009 A	31OCT2009	59	
4860	Works within Section 3 (B) at LTT River	151	151	01NOV2009	31MAR2010	0	4850
4900	No exca period (3) at Confluence of PNH,TTT&LTT	214	214	01APR2010	31OCT2010	0	4860
4910	Remaining Drainage Works for (3A) Embankment	50	50	01JUN2010	20JUL2010	0	3385
4920	Remaining Drainage Works for (4) Embankment	50	50	01JUN2010	20JUL2010	0	3385
4930	Remain Road & Paving Works for (3A) Embankment	50	50	21JUN2010	09AUG2010	0	4910
4940	Remain Road & Paving Works for (4) Embankment	50	50	21JUL2010	08SEP2010	0	4920
4950	Remain Soft Landscaping Planting(3A) Works	50	50	10AUG2010	28SEP2010	0	4930
4960	Remain Soft Landscaping Planting (4) Works	110	110	09SEP2010	27DEC2010	0	4940
5000	Works within Portions S1 of the Site (Chung Hau)	748	182	18JAN2008 A	03FEB2010	76	0001
5010	Construction Proposals and Submissions	203	0	18JAN2008 A	07AUG2008 A	100	0001
5020	uPVC Sewer (DN160-400) (New works)	0	0	08AUG2008 A	07AUG2008 A	100	5010
5030	Applocation and Approval of XP	290	0	18JAN2008 A	02NOV2008 A	100	0001
5040	uPVC Sewer (DN225-->400) (On-line Replace)	0	0	03NOV2008 A		100	5030
5041	Preparation works for sewers	10	0	03NOV2008 A	12NOV2008 A	100	5040
5042	MH EB13 - MH EB18	350	84	13NOV2008 A	28OCT2009	76	5041
5043	MH EB18 - MH EB25	145	145	29OCT2009	22MAR2010	0	5042
5044	MH EB11 - MH EB13	90	90	29OCT2009	26JAN2010	0	5042
5045	MH EB25 - MH EB26	50	50	27JAN2010	17MAR2010	0	5044
5046	MH EB26 - MH EB31 - EB8	145	145	29OCT2009	22MAR2010	0	5042
6000	Sewerage Works at TTT (S2A & 2B)	863	297	18JAN2008 A	29MAY2010	66	0001
6010	Prepartion for works (Minor Portion)	131	0	18JAN2008 A	27MAY2008 A	100	0001
6020	uPVC Sewer (DN160-400) M/H C48 - M/H C84	230	0	28MAY2008 A	12JAN2009 A	100	6010
6030	uPVC Sewer (DN160-400) M/H C85 - M/H C131	230	25	13JAN2009 A	30AUG2009	89	6020
6040	uPVC Sewer (DN160-400) M/H C1 - M/H C47	249	249	31AUG2009	06MAY2010	0	6030
7000	Sewerage at TWT (S3A & 3B)	638	72	18JAN2008 A	16OCT2009	89	0001



Start date	07JAN2008
Finish date	21JAN2011
Data date	06AUG2009
Run date	15AUG2009
Page number	5A

Yick Hing Construction Co. Ltd.

Drainage Improvement Work in South Lantau
and Construction of Mui Wo Village Sewerage Phase 1

Master Programme (Rev.9b)

Early bar
Progress bar
Critical bar
Summary bar
Start milestone point
Finish milestone point

Act ID	Description	Orig Dur	Rem Dur	Early Start	Early Finish	%	Predecessors
7010	Preparation for works (Minor Portion)	131	0	18JAN2008 A	27MAY2008 A	100	**0001**
7020	Non-working Period at TWT Beach (1)	196	0 *	01APR2008 A	13OCT2008 A	100	
7030	uPVC Sewer (DN160-400) M/H A16 - M/H A34	465	30	28MAY2008 A	04SEP2009	94	**7010**
7040	uPVC Sewer (DN160-400) M/H A15 - M/H A13	50	0	14OCT2008 A	02DEC2008 A	100	**7020**
7050	uPVC Sewer (DN160-400) M/H A11 - M/H A7	50	0	03DEC2008 A	21JAN2009 A	100	**7040**
7060	uPVC Sewer (DN160-400) M/H A1 - M/H A3	65	0	22JAN2009 A	27MAR2009 A	100	**7050**
8000	Sewerage works at PNH (S4)	772	206	18JAN2008 A	27FEB2010	73	**0001**
8010	Preparation of works	168	0	07JAN2008 A	22JUN2008 A	100	
8020	uPVC Sewer (DN160-400) M/H ED2 -D28 - D118	320	0	23JUN2008 A	08MAY2009 A	100	**8010**
8030	uPVC Sewer (DN160-400) M/H D1 - D27	280	191	09MAY2009 A	12FEB2010	32	**8020**
9000	Preservation & Protection of Exist Trees	534 *	534 *	06AUG2009	21JAN2011	0	**0001**
9010	Preparton for works	100	0	07JAN2008 A	15APR2008 A	100	
9020	Protection & Transplanting Works	1011	534	16APR2008 A	21JAN2011	47	**9010**



Start date	07JAN2008
Finish date	21JAN2011
Data date	06AUG2009
Run date	15AUG2009
Page number	6A

Yick Hing Construction Co. Ltd.

Drainage Improvement Work in South Lantau
and Construction of Mui Wo Village Sewerage Phase 1

Master Programme (Rev.9b)

- Early bar
- Progress bar
- Critical bar
- Summary bar
- Start milestone point
- Finish milestone point

Act ID	Description	Orig Dur	Rem Dur	Early Start	Early Finish	%	Predecessors
0000	DRAINAGE IMPROVEMENT WORK IN S LANTAU	534 *	534 *	06AUG2009	21JAN2011	0	
0010	Preliminaries	534 *	534 *	06AUG2009	21JAN2011	0	
0080	Monitoring for Environmental Permit	1001	534	26APR2008 A	21JAN2011	47	0070
1044	MH2 to MH3 (2 x DN 600)	75	18	10JUN2009 A	23AUG2009	76	1043
1045	MH3 to MH4 (2 x DN 600)	21	21	21AUG2009 *	10SEP2009	0	1044
1046	MH4 to MH5 (2 x DN 600)	14	14	11SEP2009	24SEP2009	0	1045
1047	MH5 to MH6 (2 x DN 600)	14	14	25SEP2009	08OCT2009	0	1046
1048	MH6 to MH7 (2 x DN 600)	14	14	09OCT2009	22OCT2009	0	1047
1049	MH7 to MH8 (2 x DN 750)	80	42	29JUN2009 A	16SEP2009	48	
1050	MH8 to Outlet Structure	21	21	23OCT2009	12NOV2009	0	1048, 1049
1132	Bottleneck B widening excavation (North Side)	85	29	11JUN2009 A	03SEP2009	66	1131
1133	Bottleneck B type 6 gabion (South Side)	25	25	04SEP2009	28SEP2009	0	1132
1134	Bottleneck B widening excavation (RHS)	14	14	29SEP2009	12OCT2009	0	1133
1135	Bottleneck B type 6 gabion (RHS) & river bed	14	14	13OCT2009	26OCT2009	0	1134
1141	R C Retaining Wall H	180	53	01APR2009 A	27SEP2009	71	1140
1151	U-Channel and Catchpit for Widened Bottle Neck A	15	15	27OCT2009	10NOV2009	0	1123, 1135
1152	U-Channel and Catchpit for Widened Bottle Neck B	15	15	27OCT2009	10NOV2009	0	1135
1153	U-Channel and Catchpit for Retaining Wall H	20	20	28SEP2009	17OCT2009	0	1141
1160	Soft & Hard Landscaping Works	0	0	18OCT2009		0	1123, 1153
1170	Hard Landscaping & Paving Works	50	50	18OCT2009	06DEC2009	0	1153
1180	Soft Landscaping (Planting) Works	50	50	18OCT2009	06DEC2009	0	1153
1200	Phase 2 sewerage works at TTT river	60	60	01SEP2009 *	30OCT2009	0	
1220	Excavation 1st half trench at TTT river	20	20	01SEP2009 *	20SEP2009	0	1210
1230	Pipe laying and backfilling 1st half trench	5	5	21SEP2009	25SEP2009	0	1220
1240	Excavation 2nd half trench at TTT river	20	20	26SEP2009	15OCT2009	0	1230
1250	Pipe laying and backfilling 2nd half trench	5	5	16OCT2009	20OCT2009	0	1240
1260	Connection to existing manholes	4	4	21OCT2009	24OCT2009	0	1250
1270	Site clearance and reinstatement of river	5	5	25OCT2009	29OCT2009	0	1260
2000	Works at D6, D7 & D8 (HTST, LUT & CShST)	614	48	18JAN2008 A	22SEP2009	92	0001
2100	Drainage Works at Pui O - Ham Tin San Tsuen (D6)	614	48	18JAN2008 A	22SEP2009	92	0001
2113	excavation and shoring for bay 1 FPW	50	4	21JUN2009 A	09AUG2009	92	2112
2114	Concreting mass concrete wall bay 1 FPW	30	30	10AUG2009	08SEP2009	0	2113
2115	excavation and shoring for bay 2 FPW	20	20	09SEP2009	28SEP2009	0	2114
2116	Concreting mass concrete wall bay 2 FPW	15	15	29SEP2009	13OCT2009	0	2115
2117	excavation and shoring for bay 3 FPW	20	20	14OCT2009	02NOV2009	0	2116
2120	Associated Railing & Paving Works	60	60	29SEP2009 *	27NOV2009	0	2113, 2118
2130	Associated Granite Paving (vertical)	60	60	29SEP2009	27NOV2009	0	2113, 2118
2200	Drainage Works at Pui O - Lo Uk Tsuen (D7)	614	48	18JAN2008 A	22SEP2009	92	0001
2231	MH6 to MH7	105	71	03JUL2009 A	15OCT2009	32	2230
2232	MH7 to MH8	60	60	16OCT2009	14DEC2009	0	2231
2240	Reinstatement of South Lantau Road	170	170	16OCT2009	03APR2010	0	2231, 2236
2300	Drainage Works at Cheung Sha Sheung Tsuen (D8)	614	48	18JAN2008 A	22SEP2009	92	0001
2314	Material ordering	75	60	22JUL2009 A	04OCT2009	20	2313
2315	MHS2 - MHS1	3	3	05OCT2009	07OCT2009	0	2314
2316	MHS1 - MHS0	3	3	08OCT2009	10OCT2009	0	2315
2317	MHS0 - Outlet	3	3	11OCT2009	13OCT2009	0	2316
2340	Site clearance	5	5	14OCT2009	18OCT2009	0	2317
3000	Box Culvert & Gabion Wall at PNH River (D1)	926	360	18JAN2008 A	31JUL2010	61	0001
3040	Maintenance of EVA	876	534	29AUG2008 A	21JAN2011	39	3020
3121	RC Box Culvert (3mx3mx2,25m) Bay 7	40	19	16JUL2009 A	24AUG2009	53	3120
3123	RC Box Culvert (3mx3mx2,25m) Bay 4	40	13	10JUL2009 A	18AUG2009	68	3122
3124	RC Box Culvert (3mx3mx2,25m) Bay 5	40	40	14AUG2009	22SEP2009	0	3123
3125	RC Box Culvert (3mx3mx2,25m) Bay 6	35	35	18SEP2009	22OCT2009	0	3124
3130	Backfill and Reinstatement EVA	20	20	23OCT2009	11NOV2009	0	3125
3140	Backfilling for RC Box Culvert	385	108	02NOV2008 A	21NOV2009	72	3111, 3125
3300	RC Retaining Walls at PNH River (D1)	0	0	01OCT2009 *		0	
3343	Retaining Wall D - Bay 3	21	16	01AUG2009 A	21AUG2009	24	3340
3344	Retaining Wall D - Bay 4	15	15	22AUG2009	05SEP2009	0	3343



Start date	07JAN2008
Finish date	21JAN2011
Data date	06AUG2009
Run date	15AUG2009
Page number	1A
c Primavera Systems, Inc.	

Yick Hing Construction Co. Ltd.

Drainage Improvement Work in South Lantau
and Construction of Mui Wo Village Sewerage Phase 1

3-Month Rolling Programme (Rev.9b)

- Early bar
- Progress bar
- Critical bar
- Summary bar
- Start milestone point
- Finish milestone point

Act ID	Description	Orig Dur	Rem Dur	Early Start	Early Finish	%	Predecessors
3360	RC Maintanence Ramp	0	0	06SEP2009		0	**3344**
3361	Ramp bay 1	20	20	06SEP2009	25SEP2009	0	**3360**
3362	Ramp bay 2	20	20	26SEP2009	15OCT2009	0	**3361**
3363	Ramp bay 3	30	30	16OCT2009	14NOV2009	0	**3362**
3369	Turning Bay & Maintenance Access	70	70	26SEP2009	04DEC2009	0	**3361**
3500	Gabion Wall (Type 2, 3, 4 & 5) at PNH River	0	0	01OCT2009 *		0	
3510	Gabion Wall (opposite to RW-A & B)	45	45	01OCT2009	14NOV2009	0	**3500**
4000	Luk Tei Tong Bypass Channel and River (D5)	926	360	18JAN2008 A	31JUL2010	61	**0001**
4200	No Excavation Period (2)	214	87 *	01APR2009 A	31OCT2009	59	**4110**
4240	Box Culvert - A	75	46	08JUL2009 A	20SEP2009	39	
4241	Reprovision of EVA & Footpath at BC-A	10	10	21SEP2009	30SEP2009	0	**4240**
4260	Reprovision of EVA & Footpath at BC-B	180	53	01APR2009 A	27SEP2009	71	**4250**
4343	Retaining Wall J - Bay 3	21	6	22JUL2009 A	11AUG2009	71	**4342**
4344	Retaining Wall J - Bay 4	21	21	12AUG2009	01SEP2009	0	**4343**
4345	Retaining Wall J - Bay 5	21	21	02SEP2009	22SEP2009	0	**4344**
4346	Retaining Wall J - Bay 6	25	25	23SEP2009	17OCT2009	0	**4345**
4347	Retaining Wall J - Bay 7	25	25	18OCT2009	11NOV2009	0	**4346**
4800	Remain Works within PNH & LTT River (D1&D5)	1010	444	18JAN2008 A	23OCT2010	56	**0001**
4850	No exca period (2) at Confluence of PNH,TTT&LTT	214	87	01APR2009 A	31OCT2009	59	
5000	Works within Portions S1 of the Site (Chung Hau)	748	182	18JAN2008 A	03FEB2010	76	**0001**
5042	MH EB13 - MH EB18	350	84	13NOV2008 A	28OCT2009	76	**5041**
5043	MH EB18 - MH EB25	145	145	29OCT2009	22MAR2010	0	**5042**
5044	MH EB11 - MH EB13	90	90	29OCT2009	26JAN2010	0	**5042**
5046	MH EB26 - MH EB31 - EB8	145	145	29OCT2009	22MAR2010	0	**5042**
6000	Sewerage Works at TTT (S2A & 2B)	863	297	18JAN2008 A	29MAY2010	66	**0001**
6030	uPVC Sewer (DN160-400) M/H C85 - M/H C131	230	25	13JAN2009 A	30AUG2009	89	**6020**
6040	uPVC Sewer (DN160-400) M/H C1 - M/H C47	249	249	31AUG2009	06MAY2010	0	**6030**
7000	Sewerage at TWT (S3A & 3B)	638	72	18JAN2008 A	16OCT2009	89	**0001**
7030	uPVC Sewer (DN160-400) M/H A16 - M/H A34	465	30	28MAY2008 A	04SEP2009	94	**7010**
8000	Sewerage works at PNH (S4)	772	206	18JAN2008 A	27FEB2010	73	**0001**
8030	uPVC Sewer (DN160-400) M/H D1 - D27	280	191	09MAY2009 A	12FEB2010	32	**8020**
9000	Preservation & Protection of Exist Trees	534 *	534 *	06AUG2009	21JAN2011	0	**0001**
9020	Protection & Transplanting Works	1011	534	16APR2008 A	21JAN2011	47	**9010**



Start date	07JAN2008
Finish date	21JAN2011
Data date	06AUG2009
Run date	15AUG2009
Page number	2A

Yick Hing Construction Co. Ltd.

Drainage Improvement Work in South Lantau
and Construction of Mui Wo Village Sewerage Phase 1

3-Month Rolling Programme (Rev.9b)

Early bar
Progress bar
Critical bar
Summary bar
Start milestone point
Finish milestone point



NOTES:

1. GRID LINES ARE HONG KONG GRID 1980
2. ALL LEVELS ARE IN METERS AND REFERRED TO H.K.P.D.

DRAINAGE SERVICES DEPARTMENT, THE GOVERNMENT OF THE HONG KONG SPECIAL ADMINISTRATIVE REGION

STORMWATER IMPROVEMENT IN SOUTHERN KOWLOON INVESTIGATION

LOCATION PLAN OF THE PROJECT

Metcalf & Eddy Ltd 美地工程顧問有限公司

ORIGINAL SIZE: A3

1.1

SEP 2004

PREPARED BY: JLFL

SCALE: 1:50000

PRELIMINARY

DRAWING NO. IN METRES

K:/A02703/DRAWING/REPORT/EM&A/MAPS/LOCAT_PLAN.DGN



NOTES :

1. ALL LEVELS ARE IN METRES ABOVE P.D.H.K..
2. ALL GRIDS REFER TO HONG KONG 1980 GRID.

LEGENDS :

- SITE BOUNDARIES
- PORTION D1 - PAK NGAN HEUNG
- PORTION D2 - LING TSUI TAU (A)
- PORTION D3 - LING TSUI TAU (B)
- PORTION D4 - TAI TEI TONG RIVER
- PORTION D5 - LUK TEI TONG
- PORTION D6 - PUI O
- PORTION D7 - LO UK TSUEN
- PORTION D8 - CHEUNG SHA SHEUNG TSUEN
- PORTION D9 - EMERGENCY VEHICULAR ACCESS (EVA) AT HUI WO

FOR TENDER PURPOSES ONLY

No.	date	description	initial
A	16 MAY 2007	GENERAL REVISION	SIGNED H. Y. CHOW for

REVISION

	name		date
designed	SIGNED	H. Y. CHOW	12 FEB 2006
drawn	SIGNED	B. D. CHAN	23 MAR 2007
checked	SIGNED	W. H. CHAN	10 MAY 2007
vetted	SIGNED	T. Y. CHAN	11 MAY 2007

approved

SIGNED K. K. CHAN, Chief Engineer, 14 MAY 2007 Date

contract no. DC/2006/11

file no. DP/6/4128CD

project no. 128CD

contract

DRAINAGE IMPROVEMENT IN SOUTHERN LANTAU

drawing title

PORTIONS OF SITE - SOUTHERN LANTAU

(SHEET 1 OF 2)

drawing no.	scale
DDN/128CD2/1002A	1 : 2000

office

DRAINAGE PROJECTS DIVISION

DRAINAGE SERVICES DEPARTMENT
GOVERNMENT OF THE
HONG KONG
SPECIAL ADMINISTRATIVE REGION

A1 841x594

Appendix B Key Personal Contact information chart

Organization Name	Role	Title	Name	Telephone	Fax Number
Drainage Service Department	Project Proponent	Engineering Representative	Mr. Chan Wai Hong	2594 7464	2827 8700
Ellied Environmental Consultants Limited	Independent Environmental Checker (IEC)	Principal Consultant	Ms. Grace Kwok	2815 7028	2815 5399
Yick-Hing Construction Company Limited	Main Contractor	Senior Project Manager	Mr. Liu Kai Choi	2394 4988	2787 4890
Environmental Pioneers & Solutions Limited	Environmental Team (ET)	Environmental Team Leader	Ms. Patricia Chung	2965 0888	2856 2010

Appendix C

Calibration Certificates for Measuring Equipments

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

Report for Calibration of Hand-held Water Quality Meter WQC-24

Calibration Reference No. : GCE/CAL/2009/MW/WQM/C4

Client : ENVIRONMENTAL PIONEER AND SOLUTION LIMITED

Equipment No. : WQC-24 Location : Mui Wo Site

Manufacturer : DKK-TOA Serial No.: 640274

Calibration Date : 24 to 28-12-2009 Due Date : 23-03-2010

Criterion: (Repeatabilty, Linearity)

pH	:	Both within ±0.05pH
Dissolved oxygen	:	Both within ±0.1mg/L
Electric conductivity	:	Both within ±1%FS
Turbidity	:	Repeatability : within ±3%FS
Temperature	:	Repeatability ±0.25°C; Linearity ±0.5°C; (Ambient 5~45°C)

Electric Conductivity (Salinity converted from EC):

(Reference : APHA 20ed 2510 B, ISO 7888 - 1985 (E) and DKK-TOA Hand-held Water Quality Meter WQC-24 Instruction Manual)

Concentration of KCl Standard Solution (M)	Reference conductivity value at 25.0 °C	Indicated value by meter	Linearity (R^2)
0	0.0 mS/m*	0.0 mS/m	1.0000
0.001	14.7 mS/m	15.2 mS/m	
0.005	71.8 mS/m	72.3 mS/m	Acceptance Criterion
0.01	0.141 S/m	0.147 S/m	$R^2 > 0.995$ Within ± 1% F.S. against calibration standard value 71.8 mS/m, 0.667 S/m and 5.87 S/m.
0.05	0.667 S/m	0.674 S/m	
0.1	1.29 S/m	1.29 S/m	
0.5	5.87 S/m	5.87 S/m	
Repeatability	1st time	0.00 , 5.87 S/m	Within ± 1% F.S. against average value
	2nd time	0.00 , 5.87 S/m	
	3rd time	0.00 , 5.87 S/m	
	0.00 , 5.87 S/m	Ave.: 0.00 , 5.87	

* 1 S/m = 10^4 μmhos/cm = 10^3 mS/m

Remark: For repeatability, the maximum difference from the average value of 3 measurements was taken.

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

Dissolved Oxygen:

(Reference : APHA 20ed 4500-O B&C, ISO 5814:1990(E) and DKK-TOA Hand-held Water Quality Meter WQC-24 Instruction Manual)

DO value evaluated by Iodometric Method (mg/L)		Indicated value by meter (mg/L)	Linearity (R^2)
0.00		0.00	0.9987
3.27		3.36	
5.73		5.80	Acceptance Criterion
8.46		8.50	$R^2 > 0.995$ Within ± 0.1 mg/L against standard value
10.38		10.33	
13.13		13.07	
Repeatability	1st time	0.00 , 8.52	Within ± 0.1 mg/L against average value
	2nd time	0.00 , 8.50	
	3rd time	0.00 , 8.47	
	0.00 , 8.46	Ave.: 0.00 , 0.04	

Remark: For repeatability, the maximum difference from the average value of 3 measurements was taken.

pH Value:

(Reference : APHA 20ed 4500-H^+ B, ISO 10523:1994(E) and DKK-TOA Hand-held Water Quality Meter WQC-24 Instruction Manual)

Calibration pH buffer (25°C)	Input value (pH buffer) (25°C)	Indicated pH value by meter (25°C)	Linearity (R^2)
pH = 1.67	1.67	1.70	1.0000
pH = 6.86	4.00	4.02	Acceptance Criterion
pH = 7.42	7.00	7.02	$R^2 > 0.995$ Within ± 0.05 pH against standard value
pH = 9.18	10.00	10.04	
pH = 12.45	12.45	12.47	
Repeatability	1st time	4.02 , 10.03	Within ± 0.05 pH against average value
	2nd time	4.02 , 10.04	
	3rd time	4.01 , 10.04	
	pH 4.00 , 10.00	Ave.: 4.02 , 10.04	

Remark: For repeatability, the maximum difference from the average value of 3 measurements was taken.

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

Temperature:

(Reference : APHA 20ed 2550 B, In-house method and DKK-TOA Hand-held Water Quality Meter WQC-24 Instruction Manual)

Setting Temperature (°C)	Indicated value by meter (°C)		Linearity (R^2)
5.0	5.3		1.0000
15.0	15.3		
25.0	25.1		Acceptance Criterion
35.0	35.2		$R^2 > 0.995$ Within ± 0.5°C against standard value
45.0	45.3		
55.0	55.2		
Repeatability	1st time	15.2 , 45.4	Within ± 0.25°C against average value
	2nd time	15.1 , 45.2	
	3rd time	15.2 , 45.3	
	15.0 , 45.0	Ave.: 25.2 , 45.3	

Remark: For repeatability, the maximum difference from the average value of 3 measurements was taken.

Turbidity:

(Reference : APHA 20ed 2130 B and DKK-TOA Hand-held Water Quality Meter WQC-24 Instruction Manual)

Formazin Standards (NTU)	Indicated value by meter (NTU)		Linearity (R^2)
0.0	0.0		1.0000
20.0	20.5		Acceptance Criterion
100.0	102.1		$R^2 > 0.995$ Within ± 3% F.S. against span calibration value 100.0 and 400.0 NTU
400.0	403.5		
800.0	804.8		
Repeatability	1st time	0.0 , 804.9	
	2nd time	0.0 , 804.8	Within ± 3% F.S. against average value
	3rd time	0.0 , 804.7	
	0.0 , 800.0	Ave.: 0.0 , 804.8	

Remark: For repeatability, the maximum difference from the average value of 3 measurements was taken.

Comments : Pass, (comply with the criteria)

Tested by : Ho Tin Kau Certified by : Gu Chin
Chemist

Checked by : Gu Chin Date : 28-12-2009

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

Report for Calibration of Hand-held Water Quality Meter WQC-24

Calibration Reference No. : GCE/CAL/2009/MW/WQM/C3

Client : ENVIRONMENTAL PIONEER AND SOLUTION LIMITED

Equipment No. : WQC-24 Location : Mui Wo Site

Manufacturer : DKK-TOA Serial No.: 640274

Calibration Date : 24-09-2009 Due Date : 23-12-2009

Criterion: (Repeatabilty, Linearity)

pH	:	Both within ±0.05pH
Dissolved oxygen	:	Both within ±0.1mg/L
Electric conductivity	:	Both within ±1%FS
Turbidity	:	Repeatability : within ±3%FS
Temperature	:	Repeatability ±0.25°C; Linearity ±0.5°C; (Ambient 5~45°C)

Electric Conductivity (Salinity converted from EC):

(Reference : APHA 20ed 2510 B, ISO 7888 - 1985 (E) and DKK-TOA Hand-held Water Quality Meter WQC-24 Instruction Manual)

Concentration of KCl Standard Solution (M)	Reference conductivity value at 25.0 °C	Indicated value by meter	Linearity (R^2)
0	0.0 mS/m*	0.0 mS/m	1.0000
0.001	14.7 mS/m	14.9 mS/m	
0.005	71.8 mS/m	72.0 mS/m	Acceptance Criterion
0.01	0.141 S/m	0.142 S/m	$R^2 > 0.995$ Within ± 1% F.S. against calibration standard value 71.8 mS/m, 0.667 S/m and 5.87 S/m.
0.05	0.667 S/m	0.678 S/m	
0.1	1.29 S/m	1.29 S/m	
0.5	5.87 S/m	5.87 S/m	
Repeatability	1st time	0.00 , 5.87 S/m	Within ± 1% F.S. against average value
	2nd time	0.00 , 5.87 S/m	
	3rd time	0.00 , 5.87 S/m	
	0.00 , 5.87 S/m	Ave.: 0.00 , 5.87	

* 1 S/m = 10^4 μmhos/cm = 10^3 mS/m

Remark: For repeatability, the maximum difference from the average value of 3 measurements was taken.

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

Dissolved Oxygen:

(Reference : APHA 20ed 4500-O B&C, ISO 5814:1990(E) and DKK-TOA Hand-held Water Quality Meter WQC-24 Instruction Manual)

DO value evaluated by Iodometric Method (mg/L)		Indicated value by meter (mg/L)	Linearity (R^2)
0.00		0.00	1.0000
3.95		3.89	
6.50		6.45	Acceptance Criterion
8.70		8.65	$R^2 > 0.995$ Within ± 0.1 mg/L against standard value
10.80		10.76	
13.90		13.84	
Repeatability	1st time	0.00 , 8.63	Within ± 0.1 mg/L against average value
	2nd time	0.00 , 8.69	
	3rd time	0.00 , 8.64	
	0.00 , 8.70	Ave.: 0.00 , 8.65	

Remark: For repeatability, the maximum difference from the average value of 3 measurements was taken.

pH Value:

(Reference : APHA 20ed 4500-H^+ B, ISO 10523:1994(E) and DKK-TOA Hand-held Water Quality Meter WQC-24 Instruction Manual)

Calibration pH buffer (25°C)	Input value (pH buffer) (25°C)	Indicated pH value by meter (25°C)	Linearity (R^2)
pH = 1.67	1.67	1.69	
pH = 6.86	4.00	4.01	Acceptance Criterion
pH = 7.42	7.00	7.01	$R^2 > 0.995$ Within ± 0.05 pH against standard value
pH = 9.18	10.00	10.03	
pH = 12.45	12.45	12.48	
Repeatability	1st time	4.01 , 10.04	Within ± 0.05 pH against average value
	2nd time	4.01 , 10.03	
	3rd time	4.01 , 10.03	
	pH 4.00 , 10.00	Ave.: 4.01 , 10.03	

Remark: For repeatability, the maximum difference from the average value of 3 measurements was taken.

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

Temperature:

(Reference : APHA 20ed 2550 B, In-house method and DKK-TOA Hand-held Water Quality Meter WQC-24 Instruction Manual)

Setting Temperature (°C)	Indicated value by meter (°C)		Linearity (R^2)
5.0	5.2		1.0000
15.0	15.1		
25.0	25.1		Acceptance Criterion
35.0	35.1		$R^2 > 0.995$ Within ± 0.5°C against standard value
45.0	45.2		
55.0	55.3		
Repeatability	1st time	15.1 , 45.2	Within ± 0.25°C against average value
	2nd time	15.2 , 45.3	
	3rd time	15.1 , 45.2	
	15.0 , 45.0	Ave.: 15.1 , 45.2	

Remark: For repeatability, the maximum difference from the average value of 3 measurements was taken.

Turbidity:

(Reference : APHA 20ed 2130 B and DKK-TOA Hand-held Water Quality Meter WQC-24 Instruction Manual)

Formazin Standards (NTU)	Indicated value by meter (NTU)		Linearity (R^2)
0.0	0.0		1.0000
20.0	20.8		Acceptance Criterion
100.0	102.0		$R^2 > 0.995$ Within ± 3% F.S. against span calibration value 100.0 and 400.0 NTU
400.0	403.3		
800.0	804.5		
Repeatability	1st time	0.0 , 804.4	
	2nd time	0.0 , 804.5	Within ± 3% F.S. against average value
	3rd time	0.0 , 804.5	
	0.0 , 800.0	Ave.: 0.0 , 804.5	

Remark: For repeatability, the maximum difference from the average value of 3 measurements was taken.

Comments : Pass, (comply with the criteria)

Tested by : Ho Tin Kau Certified by : Gu Chin
Chemist

Checked by : Gu Chin Date : 24-9-2009

綜合試驗有限公司
SOILS & MATERIALS ENGINEERING CO., LTD.
G/F., 9/F., 12/F., 13/F. & 20/F., Leader Centre, 37 Wong Chuk Hang Road, Aberdeen, Hong Kong. Tel : (852) 2873 6860
香港黃竹坑道37號利達中心地下，9樓，12樓，13樓及20樓 Fax : (852) 2555 7533
E-mail: smec@cigismec.com Website: www.cigismec.com
HOKLAS 028

CERTIFICATE OF CALIBRATION

D094

Certificate No.: 09CA0102 01-01

Item tested

Description:	Sound Level Meter (Type I)	,	Microphone
Manufacturer:	ACO, Japan	,	ACO, Japan
Type/Model No.:	6224	,	7146
Serial/Equipment No.:	060166	,	34733
Adaptors used:	-	,	-

Item submitted by

Customer Name:	Geotechnics & Concrete Engineering (H.K.) Ltd.
Address of Customer:	G/F., 6 Ko Shan Road, Hung Hom, Kowloon, Hong Kong
Request No.:	-
Date of request:	30-12-2008

Date of test: 02-01-2009

Reference equipment used in the calibration

Description:	Model:	Serial No.	Expiry Date:	Traceable to:
Multi function sound calibrator	B&K 4226	2288444	11-01-2009	CIGISMEC
Signal generator	DS 360	33873	12-06-2009	CEPREI
Signal generator	DS 360	61227	18-07-2009	CEPREI

Ambient conditions

Temperature:	23 ± 2 °C
Relative humidity:	55 ± 15 %
Air pressure:	1010 ± 15 hPa

Test specifications

1, The Sound Level Meter has been calibrated in accordance with the requirements as specified in BS 7580: Part 1: 1997 and the lab calibration procedure SMTP004-CA-152.
2, The electrical tests were performed using an electrical signal substituted for the microphone which was removed and replaced by an equivalent capacitance within a tolerance of ±20%.
3, The acoustic calibration was performed using an B&K 4226 sound calibrator and corrections was applied for the difference between the free-field and pressure responsess of the Sound Level Meter.

Test results

This is to certify that the Sound Level Meter conforms to BS 7580: Part 1: 1997 for the conditions under which the test was performed.

Details of the performed measurements are presented on page 2 of this certificate.

Actual Measurement data are documented on worksheets.

Approved Signatory: Huang Jian Min/Feng Jun Qi **Date:** 02-01-2009 **Company Chop:** 綜合試驗有限公司 SOILS & MATERIALS ENGINEERING COMPANY LTD.

Comments: The results reported in this certificate refer to the condition of the instrument on the date of calibration and carry no implication regarding the long-term stability of the instrument.

綜合試驗有限公司
SOILS & MATERIALS ENGINEERING CO., LTD.
G/F., 9/F., 12/F., 13/F. & 20/F., Leader Centre, 37 Wong Chuk Hang Road, Aberdeen, Hong Kong. Tel : (852) 2873 6860
香港黃竹坑道37號利達中心地下，9樓，12樓，13樓及20樓 Fax : (852) 2555 7533
E-mail: smec@cigismec.com Website: www.cigismec.com
HOKLAS 028

CERTIFICATE OF CALIBRATION

0094

(Continuation Page)

1, Electrical Tests

The electrical tests were perfomed using an equivalent capacitance substituted for the microphone. The results are given in below with test status and the estimated uncertainties. The "Pass" means the result of the test is inside the tolerances stated in the test specifications. The "-" means the result of test is outside these tolerances.

Test:	Subtest:	Status:	Uncertainty (dB) / Coverage Factor	
Self-generated noise	A	Pass	0.3	
	C	Pass	1.0	2.1
	Lin	Pass	1.5	2.2
Linearity range for Leq	At reference range , Step 5 dB at 4 kHz	Pass	0.3	
	Reference SPL on all other ranges	Pass	0.3	
	2 dB below upper limit of each range	Pass	0.3	
	2 dB above lower limit of each range	Pass	0.3	
Linearity range for SPL	At reference range , Step 5 dB at 4 kHz	Pass	0.3	
Frequency weightings	A	Pass	0.3	
	C	Pass	0.3	
	Lin	Pass	0.3	
Time weightings	Single Burst Fast	Pass	0.3	
	Single Burst Slow	Pass	0.3	
Peak response	Single 100μs rectangular pulse	N/A	N/A	
R.M.S. accuracy	Crest factor of 3	Pass	0.3	
Time weighting I	Single burst 5 ms at 2000 Hz	Pass	0.3	
	Repeated at frequency of 100 Hz	Pass	0.3	
Time averaging	1 ms burst duty factor $1/10^3$ at 4kHz	Pass	0.3	
	1 ms burst duty factor $1/10^4$ at 4kHz	Pass	0.3	
Pulse range	Single burst 10 ms at 4 kHz	Pass	0.4	
Sound exposure level	Single burst 10 ms at 4 kHz	Pass	0.4	
Overload indication	SPL	Pass	0.3	
	Leq	Pass	0.4	

2, Acoustic tests

The complete sound level meter was calibrated on the reference range using a B&K 4226 acoustic calibrator with 1000Hz and SPL 94 dB. The sensitivity of the sound level meter was adjusted. The test result at 125 Hz and 8000 Hz are given in below with test status and the estimated uncertainties.

Test:	Subtest	Status	Uncertainty (dB) / Coverage Factor
Acoustic response	Weighting A at 125 Hz	Pass	0.3
	Weighting A at 8000 Hz	Pass	0.5

3, Response to associated sound calibrator

N/A

The uncertainties have been calculated in accordance with the ISO Publication "Guide to the expression of uncertainty in measurement", and gives an interval estimated to have a level of confidence of 95 %. A coverage factor of 2 is assumed unless explicitly stated.

- End -

Calibrated by: C.Y. Fung Checked by:
Date: 02-01-2009 Date: 02-01-2009

The standard(s) and equipment used in the calibration are traceable to national or international recognised standards and are calibrated on a schedule to maintain the required accuracy level.

綜合試驗有限公司
SOILS & MATERIALS ENGINEERING CO., LTD.
G/F., 9/F., 12/F., 13/F. & 20/F., Leader Centre, 37 Wong Chuk Hang Road, Aberdeen, Hong Kong.
香港黃竹坑道37號利達中心地下，9樓，12樓，13樓及20樓
E-mail: smec@cigismec.com Website: www.cigismec.com
Tel : (852) 2873 6860
Fax : (852) 2555 7533
HOKLAS 028

CERTIFICATE OF CALIBRATION

D095

Certificate No.: 09CA0102 01-02 **Page:** 1 of 2

Item tested

Description:	Acoustical Calibrator (Class 1)
Manufacturer:	Castle Group Ltd.
Type/Model No.:	GA607
Serial/Equipment No.:	039543
Adaptors used:	-

Item submitted by

Curstomer:	Geotechnics & Concrete Engineering (H.K.) Ltd.
Address of Customer:	G/F., 6 Ko Shan Road, Hung Hom, Kowloon, Hong Kong
Request No.:	-
Date of request:	30-12-2008

Date of test: 02-01-2009

Reference equipment used in the calibration

Description:	Model:	Serial No.	Expiry Date:	Traceable to:
Lab standard microphone	B&K 4180	2412857	29-06-2009	SCL
Preamplifier	B&K 2673	2239857	02-12-2009	CEPREI
Measuring amplifier	B&K 2610	2346941	03-12-2009	CEPREI
Signal generator	DS 360	61227	18-07-2009	CEPREI
Digital multi-meter	34401A	US36087050	03-12-2009	CIGISMEC
Audio analyzer	8903B	GB41300350	27-11-2009	CEPREI
Universal counter	53132A	MY40003662	11-07-2009	CEPREI

Ambient conditions

Temperature:	22 ± 1 °C
Relative humidity:	55 ± 10 %
Air pressure:	1010 ± 15 hPa

Test specifications

1, The Sound Calibrator has been calibrated in accordance with the requirements as specified in IEC 60942 1997 Annex B and the lab calibration procedure SMTP004-CA-156.

2, The calibrator was tested with its axis vertical facing downwards at the specific frequency using insert voltage technique.

3, The results are rounded to the nearest 0.01 dB and 0.1 Hz and have not been corrected for variations from a reference pressure of 1013.25 hectoPascals as the maker's information indicates that the instrument is insensitive to pressure changes.

Test results

Details of the performed measurements are presented on page 2 of this certificate.

Approved Signatory: Huang Jian Min/Feng Jun Qi **Date:** 02-01-2009 **Company Chop:**

SOILS & MATERIALS ENGINEERING COMPANY LTD. 綜合試驗有限公司

Comments: The results reported in this certificate refer to the conditon of the instrument on the date of calibration and carry no implication regarding the long-term stability of the instrument.

綜合試驗有限公司
SOILS & MATERIALS ENGINEERING CO., LTD.
G/F., 9/F., 12/F., 13/F. & 20/F., Leader Centre, 37 Wong Chuk Hang Road, Aberdeen, Hong Kong. Tel : (852) 2873 6860
香港黃竹坑道37號利達中心地下，9樓，12樓，13樓及20樓 Fax : (852) 2555 7533
E-mail: smec@cigismec.com Website: www.cigismec.com

HOKLAS 028

CERTIFICATE OF CALIBRATION

D095

(Continuation Page)

Certificate No.: 09CA0102 01-02 **Page:** 2 of 2

1, Measured Sound Pressure Level

The output Sound Pressure Level in the calibrator head was measured at the setting and frequency shown using a calibrated laboratory standard microphone and insert voltage technique. The results are given in below with the estimated uncertainties.

(Output level in dB re 20 μPa)

Frequency Shown Hz	Output Sound Pressure Level Setting dB	Measured Output Sound Pressure Level dB	Estimated Uncertainty dB
1000	94.00	94.30	0.1

2, Sound Pressure Level Stability - Short Term Fluctuations

The Short Term Fluctuations was determined by measuring the maximum and minimum of the fast weighted DC output of the B&K 2610 measuring amplifier over a 20 second time interval as required in the standard. The Short Term Fluctuation was found to be:

At 1000 Hz **STF = 0.002 dB**

Estimated uncertainty 0.005 dB

3, Actual Output Frequency

The determination of actual output frequency was made using a B&K 4180 microphone together with a B&K 2673 preamplifier connected to a B&K 2610 measuring amplifier. The AC output of the B&K 2610 was taken to an universal counter which was used to determine the frequency averaged over 20 second of operation as required by the standard. The actual output frequency at 1 KHz was:

At 1000 Hz **Actual Frequency = 1000.0 Hz**

Estimated uncertainty 0.1 Hz Coverage factor k = 2.2

4, Total Noise and Distortion

For the Total Noise and Distortion measurement, the unfiltered AC output of the B&K 2610 measuring amplifier was connected to an Agilent Type 8903 B distortion analyser. The TND result at 1 KHz was:

At 1000 Hz **TND = 2.1%**

Estimated uncertainty 0.7%

The uncertainties have been calculated in accordance with the ISO Publication "Guide to the expression of uncertainty in measurement", and gives an interval estimated to have a level of confidence of 95 %. A coverage factor of 2 is assumed unless explicitly stated.

- End -

Calibrated by: C.Y. Fung **Checked by:**
Date: 02-01-2009 **Date:** 02-01-2009

The standard(s) and equipment used in the calibration are traceable to national or international recognised standards and are calibrated on a schedule to maintain the required accuracy level.

Appendix D1 Plant species recorded at Pak Ngan Heung River (N)

			Relative	Occurrence	
Species	**Habit**	**Native**	**Abundance**	**PNH3**	**PNH4**
Acacia confusa	tree	no	occasional		+
Achyranthes aspera	herb	yes	scarce		+
Acorus gramineus	herb	yes	scarce	+	+
Ageratum conyzoides	herb	yes	scarce		+
Alangium chinensis	tree	yes	scarce		+
Alocasia macrorrhiza	herb	yes	occasional		+
Aporosa dioica	tree	yes	occasional		+
Ardisia crenata	shrub	yes	occasional	+	+
Bamboo	herb	-	scarce	+	
Bidens pilosa	herb	yes	scarce		+
Bischofia javanica	tree	yes	scarce	+	
Celtis sinensis	tree	yes	occasional		+
Centotheca lappacea	grass	yes	scarce		+
Christella parasitica	fern	yes	occasional	+	+
Cleistocalyx operculata	tree	yes	occasional	+	
Commelina sp.	herb	yes	scarce		+
Conyza canadensis	herb	no	scarce		+
Desmos chinensis	shrub	yes	scarce		+
Dimocarpus longan	tree	no	occasional		+
Ficus hispida	tree	yes	common	+	+
Ficus superba	tree	yes	occasional		+
Floscopa scandens	herb	yes	occasional		+
Garcinia oblongifolia	tree	yes	occasional	+	+
Hedychium coronarium	herb	no	scarce		+
Hedyotis auricularia	herb	yes	scarce		+
Hibiscus rosa-sinensis	shrub	no	occasional		+
Homalium cochinchinensis	tree	yes	scarce		+
Liriope spicata	herb	yes	scarce		+
Litsea glutinosa	tree	yes	occasional		+
Litsea rotundifolia	shrub	yes	scarce	+	
Lophatherum gracile	grass	yes	scarce	+	+
Ludwigia perennis	herb	yes	scarce		+
Lygodium japonicum	fern	yes	scarce		+

			Relative	Occurrence	
Species	**Habit**	**Native**	**Abundance**	**PNH3**	**PNH4**
Macaranga tanarius	tree	yes	occasional	+	+
Mallotus paniculatus	tree	yes	scarce	+	
Melastoma sanguineum	shrub	yes	scarce		+
Microcos paniculata	tree	yes	scarce		+
Microstegium ciliatum	grass	yes	common		+
Mikania micrantha	climber	no	common	+	+
Musa paradisiaca	tree	no	scarce	+	
Mussaenda erosa	shrub	yes	scarce	+	
Neyraudia reynaudiana	grass	yes	occasional		+
Panicum maximum	grass	no	common		+
Phyllanthus urinaria	herb	yes	scarce		+
Pilea microphylla	herb	no	occasional		+
Pistia stratiotes	herb	yes	scarce		+
Plantago major	herb	yes	scarce		+
Pogonatherum crinitum	grass	yes	scarce		+
Polygonum chinense	herb	yes	occasional	+	
Psychotria asiatica	shrub	yes	common	+	+
Pueraria phaseoloides	climber	yes	occasional	+	+
Sageretia thea	climber	yes	occasional		+
Scherfflera heptaphylla	tree	yes	scarce	+	
Scoparia dulcis	herb	yes	herb		+
Severinia buxifolia	shrub	yes	scarce		+
Sporobolus fertilis	grass	yes	scarce		+
Stephania longa	climber	yes	scarce		+
Sterculia lanceolata	tree	yes	common	+	+
Synedrella nodiflora	herb	yes	scarce		+
Syngonium podophyllum	climber	no	occasional	+	
Syzygium jambos	tree	no	common	+	+
Syzygium levenei	tree	yes	scarce	+	
Urena lobata	tree	yes	scarce		+
Uvaria microcarpa	shrub	yes	scarce	+	
Vernonia cinera	herb	yes	scarce		+
Wedelia triloba	climber	no	scarce	+	
Zanthoxylum avicennae	tree	yes	scarce		+

Appendix D2 Plant species recorded at Pak Ngan Heung River (S)

			Relative	Occurrence	
Species	**Habit**	**Native**	**Abundance**	**PNH1**	**PNH2**
Celtis sinensis	tree	yes	occasional		+
Clerodendrum inerme	tree	yes	occasional	+	+
Ficus microcarpa	tree	yes	scarce		+
Ficus superba	tree	yes	occasional		+
Ipomoea cairica	climber	yes	occasional		+
Kandelia obovata	tree	yes	scarce	+	
Lantana camara	shrub	no	scarce		+
Panicum maximum	grass	no	common	+	+

Appendix D3 Plant species recorded at Luk Tei Tong River

			Relative	Occurrence				
Species	**Habit**	**Native**	**Abundance**	**LLT1**	**LLT2**	**LLT3**	**LLT4**	**LLT5**
Acanthus ilicifolius	shrub	yes	common	+				
Aegiceras corniculatum	shrub	yes	scarce	+				
Bougainvillea spectabilis	climber	no	scarce	+				
Bridelia tomentosa	tree	yes	occasional	+				
Celtis sinensis	tree	yes	scarce	+				
Clerodendrum inerme	shrub	yes	abundant	+				
Ficus superba	tree	yes	occasional	+				
Hibiscus tiliaceus	tree	yes	abundant	+				
Kandelia obovata	tree	yes	common	+	+			
Leucaena leucocephala	tree	no	occasional	+				
Neyraudia reynaudiana	grass	yes	occasional	+				+
Panicum maximum	grass	no	common	+				
Saccharum arundinaceum	grass	yes	scarce	+				
Terminalia catappa	tree	no	scarce		+			

Appendix D4

Ecological Water Monitoring Results (on-site measurements)

Environmental Pioneers & Solutions Limited

Ecological Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 14/12/2009 **Weather Condition: Sunny**

Monitoring Location	**WE1**			**WE2**			**WE3**			**WE4**			**WE5**			**WE6**		
Time (hhmm)	1120			1110			1050			1100			1205			1140		
Tide Mode	ebb			ebb			ebb			ebb			ebb			ebb		
River Condition	Normal			Normal			Muddy			Muddy			Normal			Normal		
Water Depth (m)	< 1.0			< 1.0			< 1.0			< 1.0			< 1.0			< 1.0		
pH value	7.28			7.72			7.88			7.11			7.12			6.87		
Temperature (oC)	19.8			20.1			20.6			21.4			21.0			19.5		
Salinity (ppt)	0.0			0.2			2.3			13.7			2.1			0.0		
Conductivity (ms/m)	10.6			56.5			79.4			207.0			407.0			5.9		
Water flow (m/s)	0.050			0.020			0.080			0.000			0.040			0.000		
Turbidity (NTU)	0.0	0.0	Average 0.00	0.0	0.0	Average 0.00	8.4	8.4	Average 8.40	2.4	2.4	Average 2.4	3.1	3.1	Average 3.10	0.0	0.0	Average 0.0
DO (mg/l)	6.86	6.86	Average 6.86	8.42	8.42	Average 8.42	8.58	8.58	Average 8.58	8.00	8.00	Average 8.00	9.15	9.15	Average 9.15	7.43	7.43	Average 7.43
DO Saturation (%)	76	76	Average 76	93	93	Average 93	96	96	Average 96	91	91	Average 91	103	103	Average 103	81	81	Average 81

Name **Signature** **Date**

Prepared By: Jimmy Cheng 14/12/2009

remark or observation:

Appendix D5

Ecological Water Monitoring Results (lab report)

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST SUMMARY ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC091200075 Date of Issue : 21-12-2009

Client* : Environmental Pioneers & Solutions Limited Date Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 14-12-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 15-12-2009

GCE Serial No. : WQM122009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	501	496	1.0	24.7
		Acceptance Criteria	<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID		WE1	WE1 Duplicate	WE2	WE2 Duplicate	WE3	WE3 Duplicate		
	Sampling Date/Time		14 Dec 2009 / 11:20		14 Dec 2009 / 11:10		14 Dec 2009 / 10:50			
	LOD	Units								
Suspended Solids (SS)	1	mg/L	1.5	1.3	1.9	1.8	10.5	10.9		
TEST RESULTS	Sample ID		WE4	WE4 Duplicate	WE5	WE5 Duplicate	WE6	WE6 Duplicate		
	Sampling Date/Time		14 Dec 2009 / 11:00		14 Dec 2009 / 12:05		14 Dec 2009 / 11:40			
	LOD	Units								
Suspended Solids (SS)	1	mg/L	5.7	5.7	8.3	8.4	< 1.0	< 1.0		

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : Location M1 & WE3 and Location M3 & WE4 are the same location.

----- End -----

Tested By : K.L FONG

Checked By : GU CHIN

Approved Signatory :

Name : GU CHIN

Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Report No. : GCC091200287 Date of Issue : 04-01-2010

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 14-12-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 30-12-2009

GCE Serial No. : WQM122009 Sampling Date* : 14-12-2009 / 11:20 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE1

Descripption : River Water

DESCRIPTION		TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance		APHA 20ed 2110	--
Odour		APHA 20ed 2150 B	Odour Characteristics : --
			Threshold Odour Number (TON) : --
pH Value at temperature [ ] °C		APHA 20ed 4500-H^+ B	--
Colour	TCU	APHA 20ed 2120 B	--
Turbidity	NTU	APHA 20ed 2130 B	--
Conductivity at 25°C	µS/cm	APHA 20ed 2510 B	--
Salinity	g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia)	mg/L	APHA 20ed 4500-NH_3 D	0.05
		APHA 20ed 4500-NH_3 E	--
		APHA 18ed 4500-NH_3 C	--
Nitrogen (Nitrate)	mg/L	APHA 20ed 4500-NO_3^- E	0.09
Phosphorus	mg/L	APHA 20ed 4500-P D	0.03
Biochemical Oxygen Demand (BOD_5)	mg/L	APHA 20ed 5210 B	1
Chemical Oxygen Demand (COD)	mg/L	APHA 20ed 5220 D	--
Total Suspended Solid	mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 14 December 2009.

REMARKS : Sample Location WE1.

----- End -----

Tested By : T.W. Lam, K.L. Fong Certified By :

Name : Gu Chin

Checked By : Gu Chin Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Report No. : GCC091200295 Date of Issue : 04-01-2010

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 14-12-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 30-12-2009

GCE Serial No. : WQM122009 Sampling Date* : 14-12-2009 / 11:20 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE1 Duplicate

Descripption : River Water

DESCRIPTION		TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance		APHA 20ed 2110	--
Odour		APHA 20ed 2150 B	Odour Characteristics : --
			Threshold Odour Number (TON) : --
pH Value at temperature [	] °C	APHA 20ed 4500-H^+ B	--
Colour	TCU	APHA 20ed 2120 B	--
Turbidity	NTU	APHA 20ed 2130 B	--
Conductivity at 25°C	µS/cm	APHA 20ed 2510 B	--
Salinity	g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia)	mg/L	APHA 20ed 4500-NH_3 D	0.04
		APHA 20ed 4500-NH_3 E	--
		APHA 18ed 4500-NH_3 C	--
Nitrogen (Nitrate)	mg/L	APHA 20ed 4500-NO_3^- E	0.08
Phosphorus	mg/L	APHA 20ed 4500-P D	0.02
Biochemical Oxygen Demand (BOD_5)	mg/L	APHA 20ed 5210 B	1
Chemical Oxygen Demand (COD)	mg/L	APHA 20ed 5220 D	--
Total Suspended Solid	mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 14 December 2009.

REMARKS : Sample Location WE1.

----- End -----

Tested By : T.W. Lam, K.L. Fong Certified By :

Name : Gu Chin

Checked By : Gu Chin Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Report No. : GCC091200300 Date of Issue : 04-01-2010

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 14-12-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 30-12-2009

GCE Serial No. : WQM122009 Sampling Date* : 14-12-2009 / 11:10 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE2

Descripption : River Water

DESCRIPTION		TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance		APHA 20ed 2110	--
Odour		APHA 20ed 2150 B	Odour Characteristics : --
			Threshold Odour Number (TON) : --
pH Value at temperature [ ] °C		APHA 20ed 4500-H^+ B	--
Colour	TCU	APHA 20ed 2120 B	--
Turbidity	NTU	APHA 20ed 2130 B	--
Conductivity at 25°C	µS/cm	APHA 20ed 2510 B	--
Salinity	g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia)	mg/L	APHA 20ed 4500-NH_3 D	0.14
		APHA 20ed 4500-NH_3 E	--
		APHA 18ed 4500-NH_3 C	--
Nitrogen (Nitrate)	mg/L	APHA 20ed 4500-NO_3^- E	0.15
Phosphorus	mg/L	APHA 20ed 4500-P D	0.04
Biochemical Oxygen Demand (BOD_5)	mg/L	APHA 20ed 5210 B	1
Chemical Oxygen Demand (COD)	mg/L	APHA 20ed 5220 D	--
Total Suspended Solid	mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 14 December 2009.

REMARKS : Sample Location WE2.

----- End -----

Tested By : T.W. Lam, K.L. Fong

Checked By : Gu Chin

Certified By :

Name : Gu Chin

Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Report No. : GCC091200318 Date of Issue : 04-01-2010

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 14-12-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 30-12-2009

GCE Serial No. : WQM122009 Sampling Date* : 14-12-2009 / 11:10 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE2 Duplicate

Descripption : River Water

DESCRIPTION		TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance		APHA 20ed 2110	--
Odour		APHA 20ed 2150 B	Odour Characteristics : --
			Threshold Odour Number (TON) : --
pH Value at temperature [	] °C	APHA 20ed 4500-H^+ B	--
Colour	TCU	APHA 20ed 2120 B	--
Turbidity	NTU	APHA 20ed 2130 B	--
Conductivity at 25°C	µS/cm	APHA 20ed 2510 B	--
Salinity	g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia)	mg/L	APHA 20ed 4500-NH_3 D	0.14
		APHA 20ed 4500-NH_3 E	--
		APHA 18ed 4500-NH_3 C	--
Nitrogen (Nitrate)	mg/L	APHA 20ed 4500-NO_3^- E	0.16
Phosphorus	mg/L	APHA 20ed 4500-P D	0.04
Biochemical Oxygen Demand (BOD_5)	mg/L	APHA 20ed 5210 B	1
Chemical Oxygen Demand (COD)	mg/L	APHA 20ed 5220 D	--
Total Suspended Solid	mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 14 December 2009.

REMARKS : Sample Location WE2.

----- End -----

Tested By : T.W. Lam, K.L. Fong

Checked By : Gu Chin

Certified By : 

Name : Gu Chin

Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Report No. : GCC091200326 Date of Issue : 04-01-2010

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 14-12-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 30-12-2009

GCE Serial No. : WQM122009 Sampling Date* : 14-12-2009 / 10:50 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE3

Descripption : River Water

DESCRIPTION		TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance		APHA 20ed 2110	--
Odour		APHA 20ed 2150 B	Odour Characteristics : --
			Threshold Odour Number (TON) : --
pH Value at temperature [ ]	°C	APHA 20ed 4500-H^+ B	--
Colour	TCU	APHA 20ed 2120 B	--
Turbidity	NTU	APHA 20ed 2130 B	--
Conductivity at 25°C	µS/cm	APHA 20ed 2510 B	--
Salinity	g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia)	mg/L	APHA 20ed 4500-NH_3 D	0.13
		APHA 20ed 4500-NH_3 E	--
		APHA 18ed 4500-NH_3 C	--
Nitrogen (Nitrate)	mg/L	APHA 20ed 4500-NO_3^- E	0.37
Phosphorus	mg/L	APHA 20ed 4500-P D	0.05
Biochemical Oxygen Demand (BOD_5)	mg/L	APHA 20ed 5210 B	1
Chemical Oxygen Demand (COD)	mg/L	APHA 20ed 5220 D	--
Total Suspended Solid	mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 14 December 2009.

REMARKS : Sample Location WE3.

----- End -----

Tested By : T.W. Lam, K.L. Fong

Checked By : Gu Chin

Certified By : 

Name : Gu Chin

Post : Chemist

Form No. : EWA-D2/R (19-1-2009)

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Report No. : GCC091200334 Date of Issue : 04-01-2010

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 14-12-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 30-12-2009

GCE Serial No. : WQM122009 Sampling Date* : 14-12-2009 / 10:50 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE3 Duplicate

Descripption : River Water

DESCRIPTION		TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance		APHA 20ed 2110	--
Odour		APHA 20ed 2150 B	Odour Characteristics : --
			Threshold Odour Number (TON) : --
pH Value at temperature [	] °C	APHA 20ed 4500-H^+ B	--
Colour	TCU	APHA 20ed 2120 B	--
Turbidity	NTU	APHA 20ed 2130 B	--
Conductivity at 25°C	µS/cm	APHA 20ed 2510 B	--
Salinity	g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia)	mg/L	APHA 20ed 4500-NH_3 D	0.12
		APHA 20ed 4500-NH_3 E	--
		APHA 18ed 4500-NH_3 C	--
Nitrogen (Nitrate)	mg/L	APHA 20ed 4500-NO_3^- E	0.38
Phosphorus	mg/L	APHA 20ed 4500-P D	0.05
Biochemical Oxygen Demand (BOD_5)	mg/L	APHA 20ed 5210 B	1
Chemical Oxygen Demand (COD)	mg/L	APHA 20ed 5220 D	--
Total Suspended Solid	mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 14 December 2009.

REMARKS : Sample Location WE3.

----- End -----

Tested By : T.W. Lam, K.L. Fong

Checked By : Gu Chin

Certified By : 

Name : Gu Chin

Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Report No. : GCC091200342 Date of Issue : 04-01-2010

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 14-12-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 30-12-2009

GCE Serial No. : WQM122009 Sampling Date* : 14-12-2009 / 11:00 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE4

Descripption : River Water

DESCRIPTION		TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance		APHA 20ed 2110	--
Odour		APHA 20ed 2150 B	Odour Characteristics : --
			Threshold Odour Number (TON) : --
pH Value at temperature [ ] °C		APHA 20ed 4500-H^+ B	--
Colour	TCU	APHA 20ed 2120 B	--
Turbidity	NTU	APHA 20ed 2130 B	--
Conductivity at 25°C	µS/cm	APHA 20ed 2510 B	--
Salinity	g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia)	mg/L	APHA 20ed 4500-NH_3 D	0.23
		APHA 20ed 4500-NH_3 E	--
		APHA 18ed 4500-NH_3 C	--
Nitrogen (Nitrate)	mg/L	APHA 20ed 4500-NO_3^- E	0.41
Phosphorus	mg/L	APHA 20ed 4500-P D	0.04
Biochemical Oxygen Demand (BOD_5)	mg/L	APHA 20ed 5210 B	1
Chemical Oxygen Demand (COD)	mg/L	APHA 20ed 5220 D	--
Total Suspended Solid	mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 14 December 2009.

REMARKS : Sample Location WE4.

----- End -----

Tested By : T.W. Lam, K.L. Fong

Checked By : Gu Chin

Certified By : 

Name : Gu Chin

Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Report No. : GCC091200350 Date of Issue : 04-01-2010

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 14-12-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 30-12-2009

GCE Serial No. : WQM122009 Sampling Date* : 14-12-2009 / 11:00 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE4 Duplicate

Descripption : River Water

DESCRIPTION		TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance		APHA 20ed 2110	--
Odour		APHA 20ed 2150 B	Odour Characteristics : --
			Threshold Odour Number (TON) : --
pH Value at temperature [ ]	°C	APHA 20ed 4500-H^+ B	--
Colour	TCU	APHA 20ed 2120 B	--
Turbidity	NTU	APHA 20ed 2130 B	--
Conductivity at 25°C	µS/cm	APHA 20ed 2510 B	--
Salinity	g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia)	mg/L	APHA 20ed 4500-NH_3 D	0.22
		APHA 20ed 4500-NH_3 E	--
		APHA 18ed 4500-NH_3 C	--
Nitrogen (Nitrate)	mg/L	APHA 20ed 4500-NO_3^- E	0.42
Phosphorus	mg/L	APHA 20ed 4500-P D	0.05
Biochemical Oxygen Demand (BOD_5)	mg/L	APHA 20ed 5210 B	1
Chemical Oxygen Demand (COD)	mg/L	APHA 20ed 5220 D	--
Total Suspended Solid	mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 14 December 2009.

REMARKS : Sample Location WE4.

----- End -----

Tested By : T.W. Lam, K.L. Fong Certified By :

Name : Gu Chin

Checked By : Gu Chin Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Report No. : GCC091200368 Date of Issue : 04-01-2010

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 14-12-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 30-12-2009

GCE Serial No. : WQM122009 Sampling Date* : 14-12-2009 / 12:05 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE5

Descripption : River Water

DESCRIPTION		TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance		APHA 20ed 2110	--
Odour		APHA 20ed 2150 B	Odour Characteristics : --
			Threshold Odour Number (TON) : --
pH Value at temperature [	] °C	APHA 20ed 4500-H^+ B	--
Colour	TCU	APHA 20ed 2120 B	--
Turbidity	NTU	APHA 20ed 2130 B	--
Conductivity at 25°C	µS/cm	APHA 20ed 2510 B	--
Salinity	g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia)	mg/L	APHA 20ed 4500-NH_3 D	2.86
		APHA 20ed 4500-NH_3 E	--
		APHA 18ed 4500-NH_3 C	--
Nitrogen (Nitrate)	mg/L	APHA 20ed 4500-NO_3^- E	0.14
Phosphorus	mg/L	APHA 20ed 4500-P D	0.43
Biochemical Oxygen Demand (BOD_5)	mg/L	APHA 20ed 5210 B	2
Chemical Oxygen Demand (COD)	mg/L	APHA 20ed 5220 D	--
Total Suspended Solid	mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 14 December 2009.

REMARKS : Sample Location WE5.

----- End -----

Tested By : T.W. Lam, K.L. Fong Certified By :

Name : Gu Chin

Checked By : Gu Chin Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Report No. : GCC091200376 Date of Issue : 04-01-2010

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 14-12-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 30-12-2009

GCE Serial No. : WQM122009 Sampling Date* : 14-12-2009 / 12:05 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE5 Duplicate

Descripption : River Water

DESCRIPTION		TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance		APHA 20ed 2110	--
Odour		APHA 20ed 2150 B	Odour Characteristics : --
			Threshold Odour Number (TON) : --
pH Value at temperature [ ]	°C	APHA 20ed 4500-H^+ B	--
Colour	TCU	APHA 20ed 2120 B	--
Turbidity	NTU	APHA 20ed 2130 B	--
Conductivity at 25°C	µS/cm	APHA 20ed 2510 B	--
Salinity	g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia)	mg/L	APHA 20ed 4500-NH_3 D	2.92
		APHA 20ed 4500-NH_3 E	--
		APHA 18ed 4500-NH_3 C	--
Nitrogen (Nitrate)	mg/L	APHA 20ed 4500-NO_3^- E	0.15
Phosphorus	mg/L	APHA 20ed 4500-P D	0.44
Biochemical Oxygen Demand (BOD_5)	mg/L	APHA 20ed 5210 B	2
Chemical Oxygen Demand (COD)	mg/L	APHA 20ed 5220 D	--
Total Suspended Solid	mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 14 December 2009.

REMARKS : Sample Location WE5.

----- End -----

Tested By : T.W. Lam, K.L. Fong Certified By :

Name : Gu Chin

Checked By : Gu Chin Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Report No. : GCC091200384 Date of Issue : 04-01-2010

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 14-12-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 30-12-2009

GCE Serial No. : WQM122009 Sampling Date* : 14-12-2009 / 11:40 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE6

Descripption : River Water

DESCRIPTION		TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance		APHA 20ed 2110	--
Odour		APHA 20ed 2150 B	Odour Characteristics : --
			Threshold Odour Number (TON) : --
pH Value at temperature [ ] °C		APHA 20ed 4500-H^+ B	--
Colour	TCU	APHA 20ed 2120 B	--
Turbidity	NTU	APHA 20ed 2130 B	--
Conductivity at 25°C	µS/cm	APHA 20ed 2510 B	--
Salinity	g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia)	mg/L	APHA 20ed 4500-NH_3 D	0.04
		APHA 20ed 4500-NH_3 E	--
		APHA 18ed 4500-NH_3 C	--
Nitrogen (Nitrate)	mg/L	APHA 20ed 4500-NO_3^- E	0.04
Phosphorus	mg/L	APHA 20ed 4500-P D	0.02
Biochemical Oxygen Demand (BOD_5)	mg/L	APHA 20ed 5210 B	< 1
Chemical Oxygen Demand (COD)	mg/L	APHA 20ed 5220 D	--
Total Suspended Solid	mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 14 December 2009.

REMARKS : Sample Location WE6.

----- End -----

Tested By : T.W. Lam, K.L. Fong Certified By :

Name : Gu Chin

Checked By : Gu Chin Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER

Report No. : GCC091200392 Date of Issue : 04-01-2010

Client* : Environmental Pioneers & Solutions Limited Order Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 14-12-2009

W.O. No.* : -- Contract No.* : -- Date Completed : 30-12-2009

GCE Serial No. : WQM122009 Sampling Date* : 14-12-2009 / 11:40 Sample Type* : River Water

GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258 Sample I.D.* : WE6 Duplicate

Descripption : River Water

DESCRIPTION		TEST REFERENCE (In-House Method based on)	TEST RESULT
Appearance		APHA 20ed 2110	--
Odour		APHA 20ed 2150 B	Odour Characteristics : --
			Threshold Odour Number (TON) : --
pH Value at temperature [ ] °C		APHA 20ed 4500-H^+ B	--
Colour	TCU	APHA 20ed 2120 B	--
Turbidity	NTU	APHA 20ed 2130 B	--
Conductivity at 25°C	µS/cm	APHA 20ed 2510 B	--
Salinity	g/L	APHA 20ed 2520 B	--
Nitrogen (Ammonia)	mg/L	APHA 20ed 4500-NH_3 D	0.04
		APHA 20ed 4500-NH_3 E	--
		APHA 18ed 4500-NH_3 C	--
Nitrogen (Nitrate)	mg/L	APHA 20ed 4500-NO_3^- E	0.05
Phosphorus	mg/L	APHA 20ed 4500-P D	0.02
Biochemical Oxygen Demand (BOD_5)	mg/L	APHA 20ed 5210 B	< 1
Chemical Oxygen Demand (COD)	mg/L	APHA 20ed 5220 D	--
Total Suspended Solid	mg/L	APHA 20ed 2540 D	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Sample received on 14 December 2009.

REMARKS : Sample Location WE6.

----- End -----

Tested By : T.W. Lam, K.L. Fong Certified By :

Name : Gu Chin

Checked By : Gu Chin Post : Chemist

Appendix E

Construction Noise Monitoring Data Sheet

大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N1	N2
Description of Location		Façade	Façade
Date of Monitoring		2/12/2009	
Measurement Start Time (hhmm)		11:55	13:30
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		ACO Japan, model 6224	
Calibrator Model/ Identification		Castle Group, GA607	
Wind Speed (m/s)		0.1	0.2
Measurement Results	L_{90} (dB(A))	39.7	55.0
	L_{10} (dB(A))	45.3	63.3
	Leq (dB(A))	44.9	62.3
Weather condition:		Sunny	
Major Construction Noise Sourse(s) During Monitoring		No construction works are being carried out during measurement.	1. Excavator noise
Other Noise Source(s) During Monitoring		1. Traffic noise	1. Traffic noise
Remarks			

	Name & Designation	Signature	Date:
Prepared by:	Jimmy Cheng		2/12/2009

大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N3	N4
Description of Location		Freefield	Facede
Date of Monitoring		2/12/2009	
Measurement Start Time (hhmm)		11:20	10:45
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		ACO Japan, model 6224	
Calibrator Model/ Identification		Castle Group, GA607	
Wind Speed (m/s)		0.3	0.1
Measurement Results	L_{90} (dB(A))	47.6	44.6
	L_{10} (dB(A))	54.1	57
	Leq (dB(A))	54.7	54
Weather condition:		Sunny	
Major Construction Noise Sourse(s) During Monitoring		1. Excavator noise	1. Excavator noise
Other Noise Source(s) During Monitoring		1. Public noise	
Remarks			

	Name & Designation	Signature	Date:
Prepared by:	Jimmy Cheng		2/12/2009

大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N1	N2
Description of Location		Façade	Façade
Date of Monitoring		9/12/2009	
Measurement Start Time (hhmm)		15:10	15:45
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		ACO Japan, model 6224	
Calibrator Model/ Identification		Castle Group, GA607	
Wind Speed (m/s)		0.4	0.6
Measurement Results	L_{90} (dB(A))	42.1	54.1
	L_{10} (dB(A))	52.9	64.4
	Leq (dB(A))	50.6	61.7
Weather condition:		Cloudy	
Major Construction Noise Sourse(s) During Monitoring		No construction works are being carried out during measurement.	1. Excavator noise 2. Power generator noise
Other Noise Source(s) During Monitoring		1. Excavator noise 2. Power generator noise	1. Public noise
Remarks			

	Name & Designation	Signature	Date:
Prepared by:	Jimmy Cheng		9/12/2009

大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N3	N4
Description of Location		Freefield	Facede
Date of Monitoring		9/12/2009	
Measurement Start Time (hhmm)		14:35	14:00
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		ACO Japan, model 6224	
Calibrator Model/ Identification		Castle Group, GA607	
Wind Speed (m/s)		0.8	0.4
Measurement Results	L_{90} (dB(A))	58.3	44.7
	L_{10} (dB(A))	64.8	54.2
	Leq (dB(A))	62.4	52.0
Weather condition:		Cloudy	
Major Construction Noise Sourse(s) During Monitoring		1. Power generator noise 2. Piling noise	1. Excavator noise 2. Construction trucks noise
Other Noise Source(s) During Monitoring		1. Public noise 2. Traffic noise (bicycle)	1. Public noise
Remarks			

	Name & Designation	Signature	Date:
Prepared by:	Jimmy Cheng		9/12/2009

大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N1	N2
Description of Location		Façade	Façade
Date of Monitoring		16/12/2009	
Measurement Start Time (hhmm)		15:00	14:25
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		ACO Japan, model 6224	
Calibrator Model/ Identification		Castle Group, GA607	
Wind Speed (m/s)		1.3	1.7
Measurement Results	L_{90} (dB(A))	49.7	52.1
	L_{10} (dB(A))	59.1	62.8
	Leq (dB(A))	56.8	59.7
Weather condition:		Cloudy	
Major Construction Noise Sourse(s) During Monitoring		1. Excavator noise	1. Excavator noise 2. Construction trucks unloading noise
Other Noise Source(s) During Monitoring		1. Power generator noise	1. Traffic noise
Remarks			

	Name & Designation	Signature	Date:
Prepared by:	Jimmy Cheng		16/12/2009

大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N3	N4
Description of Location		Freefield	Facede
Date of Monitoring		16/12/2009	
Measurement Start Time (hhmm)		13:40	13:05
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		ACO Japan, model 6224	
Calibrator Model/ Identification		Castle Group, GA607	
Wind Speed (m/s)		1.4	1.5
Measurement Results	L_{90} (dB(A))	55.1	46.2
	L_{10} (dB(A))	62.9	52.7
	Leq (dB(A))	61.0	50.4
Weather condition:		Cloudy	
Major Construction Noise Sourse(s) During Monitoring		1. Excavator noise 2. Piling noise	1. Excavator noise
Other Noise Source(s) During Monitoring		1. Public noise 2. Traffic noise (bicycle)	1. Public noise
Remarks			

	Name & Designation	Signature	Date:
Prepared by:	Jimmy Cheng		16/12/2009

大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N1	N2
Description of Location		Façade	Façade
Date of Monitoring		23/12/2009	
Measurement Start Time (hhmm)		14:10	13:35
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		ACO Japan, model 6224	
Calibrator Model/ Identification		Castle Group, GA607	
Wind Speed (m/s)		0.4	1.1
Measurement Results	L_{90} (dB(A))	44.3	50.8
	L_{10} (dB(A))	53.8	64.4
	Leq (dB(A))	52.4	62.3
Weather condition:		Sunny	
Major Construction Noise Sourse(s) During Monitoring		1. Excavator noise	1. Excavator noise 2. Concrete curing noise 3. Hammer noise 4. Cutting machine noise
Other Noise Source(s) During Monitoring		1. Public noise	1. Public noise
Remarks			

	Name & Designation	Signature	Date:
Prepared by:	Jimmy Cheng		23/12/2009

大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N3	N4
Description of Location		Freefield	Facede
Date of Monitoring		23/12/2009	
Measurement Start Time (hhmm)		13:00	11:30
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		ACO Japan, model 6224	
Calibrator Model/ Identification		Castle Group, GA607	
Wind Speed (m/s)		0.9	0.5
Measurement Results	L_{90} (dB(A))	43.7	41.1
	L_{10} (dB(A))	54.2	51.4
	Leq (dB(A))	52.5	48.9
Weather condition:		Sunny	
Major Construction Noise Sourse(s) During Monitoring		No construction works are being carried out during measurement.	1. Excavator noise
Other Noise Source(s) During Monitoring		1. Public noise 2. Traffic noise (bicycle)	1. Public noise
Remarks			

	Name & Designation	Signature	Date:
Prepared by:	Jimmy Cheng		23/12/2009

大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N1	N2
Description of Location		Façade	Façade
Date of Monitoring		30/12/2009	
Measurement Start Time (hhmm)		14:45	14:10
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		ACO Japan, model 6224	
Calibrator Model/ Identification		Castle Group, GA607	
Wind Speed (m/s)		0.7	0.8
Measurement Results	L_{90} (dB(A))	47.3	51.6
	L_{10} (dB(A))	58.3	61.4
	Leq (dB(A))	57.3	60.3
Weather condition:		Cloudy	
Major Construction Noise Sourse(s) During Monitoring		No construction works are being carried out during measurement.	1. Excavator noise
Other Noise Source(s) During Monitoring		1. Public noise	1. Public noise
Remarks			

	Name & Designation	Signature	Date:
Prepared by:	Jimmy Cheng		30/12/2009

大成環境科技拓展有限公司
Environmental Pioneers and Solutions Limited

Construction Noise Monitoring Data Sheet

Monitoring Location		N3	N4
Description of Location		Freefield	Facede
Date of Monitoring		30/12/2009	
Measurement Start Time (hhmm)		13:35	13:00
Measurement Time Length (mins.)		30 mins	
Noise Meter Model/ Identification		ACO Japan, model 6224	
Calibrator Model/ Identification		Castle Group, GA607	
Wind Speed (m/s)		0.7	0.5
Measurement Results	L_{90} (dB(A))	39.7	37.5
	L_{10} (dB(A))	51.7	48.8
	Leq (dB(A))	50.4	46.6
Weather condition:		Cloudy	
Major Construction Noise Sourse(s) During Monitoring		1. Excavator noise	No construction works are being carried out during measurement.
Other Noise Source(s) During Monitoring		1. Public noise 2. Traffic noise (bicycle)	1. Public noise
Remarks			

	Name & Designation	Signature	Date:
Prepared by:	Jimmy Cheng		30/12/2009

Appendix F1

Water Quality
Monitoring Data Sheet

Environmental Pioneers & Solutions Limited

Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 2/12/2009 Sunny

Monitoring Location	**M1**			**M2**			**M3**			**M4**			**C1**			**C2**			**C3**		
Time (hhmm)	1220			1230			1240			1210			1310			1300			1250		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			< 1			< 1			1.2			< 1			< 1			< 1		
pH value	7.81			7.67			7.08			7.77			7.27			7.46			7.47		
Temperature (oC)	22.0			21.4			23.0			22.9			20.5			22.4			23.0		
Salinity (ppt)	6.5			0.8			15.3			19.6			0.0			0.1			2.1		
Turbidity (NTU)	**4.9**	**4.9**	Average **4.9**	**4.3**	**3.7**	Average **4.0**	**15.3**	**14.7**	Average **15.0**	5.7	5.7	Average 5.7	0.0	0.0	Average 0.0	0.0	0.0	Average 0.0	5.0	5.0	Average 5.0
DO (mg/l)	9.25	9.20	Average 9.23	9.16	9.10	Average 9.13	8.73	8.71	Average 8.72	9.13	9.08	Average 9.11	7.62	7.63	Average 7.63	7.38	7.38	Average 7.38	7.86	7.86	Average 7.86
DO Saturation (%)	109	109	Average 109	106	106	Average 106	104	104	Average 104	106	106	Average 106	86	86	Average 86	88	88	Average 88	91	91	Average 91

	Name	**Signature**	**Date**
Prepared By:	**Jimmy Cheng**		2/12/2009

remark or observation: _____

Environmental Pioneers & Solutions Limited

Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 4/12/2009 Sunny

Monitoring Location	**M1**			**M2**			**M3**			**M4**			**C1**			**C2**			**C3**		
Time (hhmm)	1415			1420			1425			1405			1435			1445			1455		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			< 1			< 1			1.2			< 1			< 1			< 1		
pH value	7.88			7.14			7.01			7.84			7.53			7.12			6.82		
Temperature (oC)	20.8			20.7			21.9			21.9			18.3			20.3			20.2		
Salinity (ppt)	5.4			1.2			13.6			19.0			0.0			0.0			2.6		
Turbidity (NTU)	**7.6**	**7.6**	Average **7.6**	**0.9**	**0.9**	Average **0.9**	**11.9**	**11.9**	Average **11.9**	8.1	8.1	Average 8.1	0.0	0.0	Average 0.0	0.0	0.0	Average 0.0	3.9	3.9	Average 3.9
DO (mg/l)	10.35	10.35	Average 10.35	9.22	9.22	Average 9.22	9.07	9.07	Average 9.07	10.32	10.32	Average 10.32	8.34	8.34	Average 8.34	8.31	8.31	Average 8.31	8.07	8.07	Average 8.07
DO Saturation (%)	116	116	Average 116	103	103	Average 103	103	103	Average 103	118	118	Average 118	88	88	Average 88	92	92	Average 92	89	89	Average 89

	Name	**Signature**	**Date**
Prepared By:	**Jimmy Cheng**		4/12/2009

remark or observation: _____

Environmental Pioneers & Solutions Limited

Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 7/12/2009 Rainy

Monitoring Location	**M1**			**M2**			**M3**			**M4**			**C1**			**C2**			**C3**		
Time (hhmm)	1610			1605			1600			1620			1530			1540			1550		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			< 1			< 1			1.4			< 1			< 1			< 1		
pH value	7.09			7.45			6.71			7.71			7.11			6.75			6.77		
Temperature (oC)	19.1			19.3			19.9			19.8			18.0			18.9			18.3		
Salinity (ppt)	4.6			0.9			17.2			17.8			0.0			0.0			2.1		
Turbidity (NTU)	**9.5**	**9.5**	Average 9.5	**1.8**	**1.8**	Average 1.8	**38.6**	**38.6**	Average 38.6	6.2	6.2	Average 6.2	0.0	0.0	Average 0.0	0.0	0.0	Average 0.0	5.6	5.6	Average 5.6
DO (mg/l)	7.60	7.60	Average 7.60	7.66	7.66	Average 7.66	6.83	6.83	Average 6.83	7.12	7.12	Average 7.12	7.33	7.33	Average 7.33	7.67	7.67	Average 7.67	6.87	6.87	Average 6.87
DO Saturation (%)	83	83	Average 83	83	83	Average 83	77	77	Average 77	78	78	Average 78	78	78	Average 78	83	83	Average 83	71	71	Average 71

	Name	**Signature**	**Date**
Prepared By:	**Jimmy Cheng**		7/12/2009

remark or observation: M3 - rainy condition and the construction work of excavation is carried out beside the river.

Environmental Pioneers & Solutions Limited

Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 8/12/2009 Cloudy

Monitoring Location	**M1**			**M2**			**M3**			**M4**			**C1**			**C2**			**C3**		
Time (hhmm)	1645			1640			1630			1655			1600			1610			1620		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			< 1			< 1			1.3			< 1			< 1			< 1		
pH value	7.26			7.73			7.07			7.59			7.17			6.93			6.88		
Temperature (oC)	19.7			20.4			20.7			20.3			19.2			20.1			20.0		
Salinity (ppt)	2.8			0.9			13.6			15.9			0.0			0.0			1.3		
Turbidity (NTU)	**12.3**	**12.3**	Average **12.3**	**0.0**	**0.0**	Average **0.0**	**7.1**	**7.1**	Average **7.1**	6.8	6.8	Average 6.8	0.0	0.0	Average 0.0	0.0	0.0	Average 0.0	4.8	4.8	Average 4.8
DO (mg/l)	8.64	8.64	Average 8.64	8.38	8.38	Average 8.38	7.95	7.95	Average 7.95	8.32	8.32	Average 8.32	8.09	8.09	Average 8.09	8.30	8.30	Average 8.30	6.57	6.57	Average 6.57
DO Saturation (%)	95	95	Average 95	93	93	Average 93	88	88	Average 88	92	92	Average 92	88	88	Average 88	92	92	Average 92	64	64	Average 64

	Name	**Signature**	**Date**
Prepared By:	**Jimmy Cheng**		8/12/2009

remark or observation: _____

Environmental Pioneers & Solutions Limited

Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 9/12/2009 Sunny

Monitoring Location	**M1**			**M2**			**M3**			**M4**			**C1**			**C2**			**C3**		
Time (hhmm)	1705			1700			1655			1710			1625			1635			1645		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			< 1			< 1			1.3			< 1			< 1			< 1		
pH value	7.43			7.68			7.73			7.70			7.37			7.06			6.81		
Temperature (oC)	19.9			20.2			20.4			20.2			19.1			19.9			20.2		
Salinity (ppt)	7.7			4.1			18.4			17.8			0.0			0.0			3.2		
Turbidity (NTU)	**6.7**	**6.7**	Average **6.7**	**0.0**	**0.0**	Average **0.0**	**13.1**	**13.1**	Average **13.1**	9.1	9.1	Average 9.1	0.0	0.0	Average 0.0	0.0	0.0	Average 0.0	6.2	6.2	Average 6.2
DO (mg/l)	8.17	8.17	Average 8.17	7.94	7.94	Average 7.94	7.57	7.57	Average 7.57	7.99	7.99	Average 7.99	7.86	7.86	Average 7.86	8.07	8.07	Average 8.07	6.88	6.88	Average 6.88
DO Saturation (%)	90	90	Average 90	88	88	Average 88	84	84	Average 84	89	89	Average 89	85	85	Average 85	89	89	Average 89	78	78	Average 78

	Name	**Signature**	**Date**
Prepared By:	**Jimmy Cheng**		9/12/2009

remark or observation: _____

Environmental Pioneers & Solutions Limited

Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 14/12/2009 Sunny

Monitoring Location	**M1**			**M2**			**M3**			**M4**			**C1**			**C2**			**C3**		
Time (hhmm)	1050			1055			1100			1040			1120			1130			1150		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			< 1			< 1			1.2			< 1			< 1			< 1		
pH value	7.88			7.84			7.11			7.85			7.28			6.87			6.83		
Temperature (oC)	20.6			20.4			21.4			21.4			19.8			20.8			20.5		
Salinity (ppt)	2.3			0.8			13.7			20.0			0.0			0.0			0.8		
Turbidity (NTU)	**8.4**	**8.4**	Average **8.4**	**0.0**	**0.0**	Average **0.0**	2.4	2.4	Average 2.4	3.6	3.6	Average 3.6	0.0	0.0	Average 0.0	0.0	0.0	Average 0.0	3.7	3.7	Average 3.7
DO (mg/l)	8.58	8.58	Average 8.58	9.04	9.04	Average 9.04	8.00	8.00	Average 8.00	7.49	7.49	Average 7.49	6.85	6.85	Average 6.85	7.47	7.47	Average 7.47	7.33	7.33	Average 7.33
DO Saturation (%)	96	96	Average 96	101	101	Average 101	91	91	Average 91	84	84	Average 84	76	76	Average 76	83	83	Average 83	80	80	Average 80

	Name	**Signature**	**Date**
Prepared By:	**Jimmy Cheng**		14/12/2009

remark or observation: _____

Environmental Pioneers & Solutions Limited

Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: **16/12/2009** Cloudy

Monitoring Location	**M1**			**M2**			**M3**			**M4**			**C1**			**C2**			**C3**		
Time (hhmm)	1215			1220			1225			1205			1235			1245			1255		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			< 1			< 1			1.3			< 1			< 1			< 1		
pH value	7.74			7.88			6.99			7.87			7.88			7.52			6.97		
Temperature (oC)	17.2			16.4			17.1			17.1			16.1			16.5			16.2		
Salinity (ppt)	3.8			0.0			8.4			14.6			0.0			0.0			0.8		
Turbidity (NTU)	**19.4**	**19.4**	Average 19.4	**0.0**	**0.0**	Average **0.0**	1.6	1.6	Average 1.6	3.8	3.8	Average 3.8	0.0	0.0	Average 0.0	0.0	0.0	Average 0.0	1.8	1.8	Average 1.8
DO (mg/l)	9.22	9.22	Average 9.22	9.48	9.48	Average 9.48	7.13	7.13	Average 7.13	8.92	8.92	Average 8.92	8.73	8.73	Average 8.73	9.14	9.14	Average 9.14	7.56	7.56	Average 7.56
DO Saturation (%)	96	96	Average 96	97	97	Average 97	74	74	Average 74	93	93	Average 93	89	89	Average 89	94	94	Average 94	75	75	Average 75

	Name	**Signature**	**Date**
Prepared By:	**Jimmy Cheng**		16/12/2009

remark or observation: M1 - water pump from the site and from washing construction trucks wheels and the muddy ground which without desilting properly discharged to the river.

Environmental Pioneers & Solutions Limited

Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: **17/12/2009** Cloudy

Monitoring Location	**M1**			**M2**			**M3**			**M4**			**C1**			**C2**			**C3**		
Time (hhmm)	1245												1255								
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			< 1			< 1			< 1			< 1			< 1			< 1		
pH value	7.80												7.81								
Temperature (oC)	15.5												14.3								
Salinity (ppt)	2.1												0.0								
Turbidity (NTU)	**18.5**	**18.5**	Average 18.5			Average #DIV/0!			Average #DIV/0!			Average #DIV/0!	0.0	0.0	Average 0.0			Average #DIV/0!			Average #DIV/0!
DO (mg/l)	9.89	9.89	Average 9.89			Average #DIV/0!			Average #DIV/0!			Average #DIV/0!	9.14	9.14	Average 9.14			Average #DIV/0!			Average #DIV/0!
DO Saturation (%)	100	100	Average 100			Average #DIV/0!			Average #DIV/0!			Average #DIV/0!	91	91	Average 91			Average #DIV/0!			Average #DIV/0!

	Name	**Signature**	**Date**
Prepared By:	**Jimmy Cheng**		17/12/2009

remark or observation: M1 - water from the site without desilting properly which directly discharge to the river.

Environmental Pioneers & Solutions Limited

Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 18/12/2009 Sunny

Monitoring Location	**M1**			**M2**			**M3**			**M4**			**C1**			**C2**			**C3**		
Time (hhmm)	1335			1340			1345			1355			1405			1415			1425		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			< 1			< 1			1.2			< 1			< 1			< 1		
pH value	7.59			7.82			7.10			7.63			7.52			7.58			7.01		
Temperature (oC)	15.6			15.3			15.9			15.8			13.8			15.6			15.3		
Salinity (ppt)	5.3			0.8			15.4			18.3			0.0			0.0			1.9		
Turbidity (NTU)	**2.6**	**2.6**	Average **2.6**	**0.0**	**0.0**	Average **0.0**	3.7	3.7	Average 3.7	2.3	2.3	Average 2.3	0.0	0.0	Average 0.0	0.0	0.0	Average 0.0	4.1	4.1	Average 4.1
DO (mg/l)	10.23	10.23	Average 10.23	10.17	10.17	Average 10.17	9.96	9.96	Average 9.96	9.99	9.99	Average 9.99	9.71	9.71	Average 9.71	9.41	9.41	Average 9.41	8.78	8.78	Average 8.78
DO Saturation (%)	103	103	Average 103	102	102	Average 102	101	101	Average 101	101	101	Average 101	94	94	Average 94	95	95	Average 95	88	88	Average 88

	Name	**Signature**	**Date**
Prepared By:	**Jimmy Cheng**		18/12/2009

remark or observation: _____

Environmental Pioneers & Solutions Limited

Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 21/12/2009 Sunny

Monitoring Location	**M1**			**M2**			**M3**			**M4**			**C1**			**C2**			**C3**		
Time (hhmm)	1540			1535			1550			1600			1505			1515			1525		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			< 1			< 1			1.2			< 1			< 1			< 1		
pH value	6.97			7.04			7.03			7.90			7.53			6.89			6.77		
Temperature (oC)	17.3			18.1			18.5			18.2			15.5			18.5			18.1		
Salinity (ppt)	3.4			0.5			15.2			16.9			0.0			0.0			1.3		
Turbidity (NTU)	**7.4**	**7.4**	Average **7.4**	**0.2**	**0.2**	Average **0.2**	3.6	3.6	Average 3.6	5.8	5.8	Average 5.8	0.0	0.0	Average 0.0	0.0	0.0	Average 0.0	5.1	5.1	Average 5.1
DO (mg/l)	10.28	10.28	Average 10.28	10.43	10.43	Average 10.43	9.36	9.36	Average 9.36	10.86	10.86	Average 10.86	9.26	9.26	Average 9.26	7.91	7.91	Average 7.91	7.13	7.13	Average 7.13
DO Saturation (%)	109	109	Average 109	111	111	Average 111	103	103	Average 103	115	115	Average 115	92	92	Average 92	85	85	Average 85	69	69	Average 69

	Name	**Signature**	**Date**
Prepared By:	**Jimmy Cheng**		21/12/2009

remark or observation: _____

Environmental Pioneers & Solutions Limited

Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 22/12/2009 Sunny

Monitoring Location	**M1**			**M2**			**M3**			**M4**			**C1**			**C2**			**C3**		
Time (hhmm)	1605			1620			1615			1555			1630			1640			1650		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			< 1			< 1			1.2			< 1			< 1			< 1		
pH value	8.40			8.15			7.56			8.02			8.14			7.41			7.02		
Temperature (oC)	19.1			19.8			20.8			20.1			17.1			19.0			18.3		
Salinity (ppt)	4.1			0.9			14.1			19.9			0.1			0.0			1.0		
Turbidity (NTU)	**7.4**	**7.4**	Average **7.4**	**0.0**	**0.0**	Average **0.0**	**8.3**	**8.3**	Average **8.3**	10.9	10.9	Average 10.9	0.0	0.0	Average 0.0	0.0	0.0	Average 0.0	2.9	2.9	Average 2.9
DO (mg/l)	9.43	9.43	Average 9.43	9.94	9.94	Average 9.94	9.68	9.68	Average 9.68	9.77	9.77	Average 9.77	9.55	9.55	Average 9.55	8.51	8.51	Average 8.51	7.96	7.96	Average 7.96
DO Saturation (%)	104	104	Average 104	109	109	Average 109	110	110	Average 110	109	109	Average 109	99	99	Average 99	91	91	Average 91	83	83	Average 83

	Name	**Signature**	**Date**
Prepared By:	**Jimmy Cheng**		22/12/2009

remark or observation: _____

Environmental Pioneers & Solutions Limited

Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 23/12/2009 Sunny

Monitoring Location	**M1**			**M2**			**M3**			**M4**			**C1**			**C2**			**C3**		
Time (hhmm)	1655			1640			1650			1705			1610			1620			1630		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			< 1			< 1			1.2			< 1			< 1			< 1		
pH value	7.61			7.46			7.06			7.78			7.45			6.75			6.83		
Temperature (oC)	19.5			20.6			21.0			20.4			18.3			20.4			19.7		
Salinity (ppt)	3.3			0.6			10.6			19.7			0.0			0.0			0.8		
Turbidity (NTU)	**4.9**	**4.9**	Average **4.9**	**0.0**	**0.0**	Average **0.0**	3.1	3.1	Average 3.1	4.6	4.6	Average 4.6	0.0	0.0	Average 0.0	0.0	0.0	Average 0.0	4.1	4.1	Average 4.1
DO (mg/l)	10.28	10.28	Average 10.28	9.52	9.52	Average 9.52	8.75	8.75	Average 8.75	9.61	9.61	Average 9.61	9.68	9.68	Average 9.68	7.83	7.83	Average 7.83	7.35	7.35	Average 7.35
DO Saturation (%)	112	112	Average 112	106	106	Average 106	99	99	Average 99	106	106	Average 106	103	103	Average 103	87	87	Average 87	82	82	Average 82

Name	**Signature**	**Date**	
Prepared By: **Jimmy Cheng**		23/12/2009	remark or observation:

Environmental Pioneers & Solutions Limited

Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: **29/12/2009** Cloudy

Monitoring Location	**M1**			**M2**			**M3**			**M4**			**C1**			**C2**			**C3**		
Time (hhmm)	1045			1100			1055			1035			1110			1120			1130		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			< 1			< 1			1.3			< 1			< 1			< 1		
pH value	8.04			7.65			7.06			7.91			7.71			7.16			6.79		
Temperature (oC)	16.6			17.3			17.9			17.0			15.6			17.4			17.2		
Salinity (ppt)	2.2			0.7			9.1			21.5			0.0			0.0			0.9		
Turbidity (NTU)	**3.7**	**3.7**	Average **3.7**	**0.9**	**0.9**	Average **0.9**	2.7	2.7	Average 2.7	5.1	5.1	Average 5.1	0.0	0.0	Average 0.0	0.0	0.0	Average 0.0	4.4	4.4	Average 4.4
DO (mg/l)	9.13	9.13	Average 9.13	9.07	9.07	Average 9.07	6.06	6.06	Average 6.06	7.45	7.45	Average 7.45	8.57	8.57	Average 8.57	8.31	8.31	Average 8.31	7.43	7.43	Average 7.43
DO Saturation (%)	94	94	Average 94	95	95	Average 95	63	63	Average 63	76	76	Average 76	85	85	Average 85	87	87	Average 87	74	74	Average 74

	Name	**Signature**	**Date**
Prepared By:	**Jimmy Cheng**		29/12/2009

remark or observation: _____

Environmental Pioneers & Solutions Limited

Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: **30/12/2009** Cloudy

Monitoring Location	**M1**			**M2**			**M3**			**M4**			**C1**			**C2**			**C3**		
Time (hhmm)	1050			1105			1100			1040			1115			1125			1135		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			< 1			< 1			1.2			< 1			< 1			< 1		
pH value	7.83			7.70			7.05			7.75			7.71			7.12			7.11		
Temperature (oC)	17.6			18.2			19.0			18.4			17.0			16.9			18.5		
Salinity (ppt)	2.8			1.0			10.6			17.3			0.1			0.0			0.7		
Turbidity (NTU)	**2.7**	**2.7**	Average **2.7**	**0.5**	**0.5**	Average **0.5**	**2.6**	**2.6**	Average 2.6	3.7	3.7	Average 3.7	0.3	0.3	Average 0.3	0.0	0.0	Average 0.0	2.1	2.1	Average 2.1
DO (mg/l)	9.33	9.33	Average 9.33	9.14	9.14	Average 9.14	6.71	6.71	Average 6.71	8.03	8.03	Average 8.03	8.27	8.27	Average 8.27	8.11	8.11	Average 8.11	6.57	6.57	Average 6.57
DO Saturation (%)	98	98	Average 98	97	97	Average 97	74	74	Average 74	86	86	Average 86	86	86	Average 86	84	84	Average 84	75	75	Average 75

	Name	**Signature**	**Date**
Prepared By:	**Jimmy Cheng**		30/12/2009

remark or observation: _____

Environmental Pioneers & Solutions Limited

Water Quality Monitoring - Summary of On-site measurement results

Date of Sampling: 31/12/2009 Cloudy

Monitoring Location	**M1**			**M2**			**M3**			**M4**			**C1**			**C2**			**C3**		
Time (hhmm)	1150			1205			1200			1140			1215			1225			1235		
Tide Mode	mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb			mid-ebb		
River Condition	normal			normal			normal			normal			normal			normal			normal		
Water Depth (m)	<1			< 1			< 1			1.3			< 1			< 1			< 1		
pH value	7.72			7.59			7.05			7.51			7.41			7.01			6.81		
Temperature (oC)	17.4			17.5			17.8			17.4			16.9			17.7			17.5		
Salinity (ppt)	3.2			0.8			11.5			15.5			0.1			0.0			0.9		
Turbidity (NTU)	**8.9**	**8.9**	Average **8.9**	**0.0**	**0.0**	Average **0.0**	**3.1**	**3.1**	Average **3.1**	5.1	5.1	Average 5.1	0.0	0.0	Average 0.0	0.0	0.0	Average 0.0	2.3	2.3	Average 2.3
DO (mg/l)	8.95	8.95	Average 8.95	8.78	8.78	Average 8.78	6.66	6.66	Average 6.66	7.71	7.71	Average 7.71	7.67	7.67	Average 7.67	8.46	8.46	Average 8.46	7.71	7.71	Average 7.71
DO Saturation (%)	94	94	Average 94	92	92	Average 92	69	69	Average 69	82	82	Average 82	79	79	Average 79	89	89	Average 89	81	81	Average 81

	Name	**Signature**	**Date**
Prepared By:	**Jimmy Cheng**		31/12/2009

remark or observation: _____

Appendix F2

Water Quality
Monitoring Lab report

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC091200017 Date of Issue : 11-12-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 02-12-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 03-12-2009

GCE Serial No. : WQM122009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	497	504	-1.4	24.5
		Acceptance Criteria	<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID		C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time		02 Dec 2009 / 13:10		02 Dec 2009 / 13:00		02 Dec 2009 / 12:50			
	LOD	Units								
Suspended Solids (SS)	1	mg/L	< 1.0	< 1.0	< 1.0	< 1.0	5.6	5.3		

TEST RESULTS	Sample ID		M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time		02 Dec 2009 / 12:20		02 Dec 2009 / 12:30		02 Dec 2009 / 12:40		02 Dec 2009 / 12:10	
	LOD	Units								
Suspended Solids (SS)	1	mg/L	9.5	9.8	2.5	2.7	11.9	11.8	7.2	7.3

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks :

----- End -----

Tested By : K.L. FONG

Checked By : GU CHIN

Approved Signatory :

Name : GU CHIN

Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC091200025 Date of Issue : 11-12-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 04-12-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 05-12-2009

GCE Serial No. : WQM122009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	498	504	-1.2	24.9
		Acceptance Criteria	<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID		C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time		04 Dec 2009 / 14:35		04 Dec 2009 / 14:45		04 Dec 2009 / 14:55			
	LOD	Units								
Suspended Solids (SS)	1	mg/L	< 1.0	< 1.0	< 1.0	< 1.0	5.4	5.1		

TEST RESULTS	Sample ID		M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time		04 Dec 2009 / 14:15		04 Dec 2009 / 14:20		04 Dec 2009 / 14:25		04 Dec 2009 / 14:05	
	LOD	Units								
Suspended Solids (SS)	1	mg/L	10.2	10.5	3.0	3.1	10.5	10.9	7.9	7.8

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks :

----- End -----

Tested By : K.L. FONG

Checked By : GU CHIN

Approved Signatory :

Name : GU CHIN

Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC091200033 Date of Issue : 11-12-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 07-12-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 08-12-2009

GCE Serial No. : WQM122009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	497	502	-1.0	25.3
		Acceptance Criteria	<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID		C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time		07 Dec 2009 / 15:30		07 Dec 2009 / 15:40		07 Dec 2009 / 15:50			
	LOD	Units								
Suspended Solids (SS)	1	mg/L	< 1.0	< 1.0	< 1.0	< 1.0	7.5	7.3		

TEST RESULTS	Sample ID		M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time		07 Dec 2009 / 16:10		07 Dec 2009 / 16:05		07 Dec 2009 / 16:00		07 Dec 2009 / 16:20	
	LOD	Units								
Suspended Solids (SS)	1	mg/L	7.4	7.4	1.4	1.2	35.2	34.6	9.2	9.6

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks :

----- End -----

Tested By : K.L. FONG

Checked By : GU CHIN

Approved Signatory :

Name : GU CHIN

Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC091200041 Date of Issue : 11-12-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 08-12-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 09-12-2009

GCE Serial No. : WQM122009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	505	497	1.6	25.5
		Acceptance Criteria	<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID		C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time		08 Dec 2009 / 16:00		08 Dec 2009 / 16:10		08 Dec 2009 / 16:20			
	LOD	Units								
Suspended Solids (SS)	1	mg/L	< 1.0	< 1.0	< 1.0	< 1.0	3.3	3.5		

TEST RESULTS	Sample ID		M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time		08 Dec 2009 / 16:45		08 Dec 2009 / 16:40		08 Dec 2009 / 16:30		08 Dec 2009 / 16:55	
	LOD	Units								
Suspended Solids (SS)	1	mg/L	11.4	11.3	1.9	1.7	10.3	10.2	10.1	9.7

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks :

----- End -----

Tested By : K.L. FONG

Checked By : GU CHIN

Approved Signatory :

Name : GU CHIN

Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC091200059 Date of Issue : 11-12-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 09-12-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 10-12-2009

GCE Serial No. : WQM122009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	497	501	-0.8	24.3
		Acceptance Criteria	<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID		C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time		09 Dec 2009 / 16:25		09 Dec 2009 / 16:35		09 Dec 2009 / 16:45			
	LOD	Units								
Suspended Solids (SS)	1	mg/L	< 1.0	< 1.0	< 1.0	< 1.0	7.7	7.9		

TEST RESULTS	Sample ID		M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time		09 Dec 2009 / 17:05		09 Dec 2009 / 17:00		09 Dec 2009 / 16:55		09 Dec 2009 / 17:10	
	LOD	Units								
Suspended Solids (SS)	1	mg/L	11.6	11.6	2.4	2.7	12.0	12.2	9.2	9.4

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks :

----- End -----

Tested By : K.L. FONG

Checked By : GU CHIN

Approved Signatory :

Name : GU CHIN

Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST SUMMARY ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC091200067 Date of Issue : 21-12-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 14-12-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 15-12-2009

GCE Serial No. : WQM122009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	501	496	1.0	24.7
		Acceptance Criteria	<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID		C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time		14 Dec 2009 / 11:20		14 Dec 2009 / 11:30		14 Dec 2009 / 11:50			
	LOD	Units								
Suspended Solids (SS)	1	mg/L	1.2	1.4	< 1.0	< 1.0	5.5	5.7		

TEST RESULTS	Sample ID		M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time		14 Dec 2009 / 10:50		14 Dec 2009 / 10:55		14 Dec 2009 / 11:00		14 Dec 2009 / 10:40	
	LOD	Units								
Suspended Solids (SS)	1	mg/L	10.5	10.9	2.4	2.1	5.7	5.7	7.4	7.8

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks : Location M1 & WE3 and Location M3 & WE4 are the same location.

----- End -----

Tested By : K.L. FONG Approved Signatory :

Name : GU CHIN

Checked By : GU CHIN Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC091200083 Date of Issue : 21-12-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 16-12-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 17-12-2009

GCE Serial No. : WQM122009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	499	503	-0.8	25.1
		Acceptance Criteria	<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID		C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time		16 Dec 2009 / 12:35		16 Dec 2009 / 12:45		16 Dec 2009 / 12:55			
	LOD	Units								
Suspended Solids (SS)	1	mg/L	< 1.0	< 1.0	< 1.0	< 1.0	4.6	4.7		

TEST RESULTS	Sample ID		M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time		16 Dec 2009 / 12:15		16 Dec 2009 / 12:20		16 Dec 2009 / 12:25		16 Dec 2009 / 12:05	
	LOD	Units								
Suspended Solids (SS)	1	mg/L	19.6	19.3	1.3	1.2	3.7	3.9	2.8	3.1

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks :

----- End -----

Tested By : K.L. FONG

Checked By : GU CHIN

Approved Signatory :

Name : GU CHIN

Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC091200091 Date of Issue : 21-12-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 17-12-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 18-12-2009

GCE Serial No. : WQM122009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	497	503	-1.2	24.9
		Acceptance Criteria	<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID		C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time		17 Dec 2009 / 12:55		--		--			
	LOD	Units								
Suspended Solids (SS)	1	mg/L	< 1.0	< 1.0	--	--	--	--		

TEST RESULTS	Sample ID		M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time		17 Dec 2009 / 12:45		--		--		--	
	LOD	Units								
Suspended Solids (SS)	1	mg/L	16.8	16.9	--	--	--	--	--	--

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks :

----- End -----

Tested By : K.L. FONG

Checked By : GU CHIN

Approved Signatory :

Name : GU CHIN

Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC091200106 Date of Issue : 21-12-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 18-12-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 19-12-2009

GCE Serial No. : WQM122009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	500	506	-1.2	24.7
		Acceptance Criteria	<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID		C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time		18 Dec 2009 / 14:05		18 Dec 2009 / 14:15		18 Dec 2009 / 14:25			
	LOD	Units								
Suspended Solids (SS)	1	mg/L	< 1.0	< 1.0	< 1.0	< 1.0	4.0	3.9		

TEST RESULTS	Sample ID		M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time		18 Dec 2009 / 13:35		18 Dec 2009 / 13:40		18 Dec 2009 / 13:45		18 Dec 2009 / 13:55	
	LOD	Units								
Suspended Solids (SS)	1	mg/L	5.1	5.4	1.6	1.5	6.2	6.0	5.0	4.9

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks :

----- End -----

Tested By : K.L. FONG

Checked By : GU CHIN

Approved Signatory :

Name : GU CHIN

Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC091200198 Date of Issue : 29-12-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 21-12-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 22-12-2009

GCE Serial No. : WQM122009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	498	503	-1.0	26.1
		Acceptance Criteria	<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID		C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time		21 Dec 2009 / 15:05		21 Dec 2009 / 15:15		21 Dec 2009 / 15:25			
	LOD	Units								
Suspended Solids (SS)	1	mg/L	1.1	1.2	< 1.0	< 1.0	6.3	6.6		

TEST RESULTS	Sample ID		M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time		21 Dec 2009 / 15:40		21 Dec 2009 / 15:35		21 Dec 2009 / 15:50		21 Dec 2009 / 16:00	
	LOD	Units								
Suspended Solids (SS)	1	mg/L	7.3	7.1	1.6	1.5	3.9	3.7	6.6	6.5

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks :

----- End -----

Tested By : K.L. FONG

Checked By : GU CHIN

Approved Signatory :

Name : GU CHIN

Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC091200203 Date of Issue : 29-12-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 22-12-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 23-12-2009

GCE Serial No. : WQM122009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	495	501	-1.2	25.7
		Acceptance Criteria	<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID		C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time		22 Dec 2009 / 16:30		22 Dec 2009 / 16:40		22 Dec 2009 / 16:50			
	LOD	Units								
Suspended Solids (SS)	1	mg/L	< 1.0	< 1.0	< 1.0	< 1.0	5.6	5.7		

TEST RESULTS	Sample ID		M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time		22 Dec 2009 / 16:05		22 Dec 2009 / 16:20		22 Dec 2009 / 16:15		22 Dec 2009 / 15:55	
	LOD	Units								
Suspended Solids (SS)	1	mg/L	7.4	7.4	1.5	1.3	9.7	9.4	11.1	11.4

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks :

----- End -----

Tested By : K.L. FONG

Checked By : GU CHIN

Approved Signatory :

Name : GU CHIN

Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC091200211 Date of Issue : 29-12-2009

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 23-12-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 24-12-2009

GCE Serial No. : WQM122009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	495	491	0.8	24.3
		Acceptance Criteria	<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID		C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time		23 Dec 2009 / 16:10		23 Dec 2009 / 16:20		23 Dec 2009 / 16:30			
	LOD	Units								
Suspended Solids (SS)	1	mg/L	1.2	1.3	< 1.0	< 1.0	6.7	6.8		

TEST RESULTS	Sample ID		M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time		23 Dec 2009 / 16:55		23 Dec 2009 / 16:40		23 Dec 2009 / 16:50		23 Dec 2009 / 17:05	
	LOD	Units								
Suspended Solids (SS)	1	mg/L	8.8	8.5	2.0	2.1	10.5	10.3	9.7	9.6

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks :

----- End -----

Tested By : K.L. FONG

Checked By : GU CHIN

Approved Signatory :

Name : GU CHIN

Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC091200407 Date of Issue : 05-01-2010

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 29-12-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 30-12-2009

GCE Serial No. : WQM122009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	504	499	1.0	24.5
		Acceptance Criteria	<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID		C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time		29 Dec 2009 / 11:10		29 Dec 2009 / 11:20		29 Dec 2009 / 11:30			
	LOD	Units								
Suspended Solids (SS)	1	mg/L	< 1.0	< 1.0	< 1.0	< 1.0	5.9	5.6		

TEST RESULTS	Sample ID		M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time		29 Dec 2009 / 10:45		29 Dec 2009 / 11:00		29 Dec 2009 / 10:55		29 Dec 2009 / 10:35	
	LOD	Units								
Suspended Solids (SS)	1	mg/L	3.4	3.7	1.2	1.4	3.5	3.6	10.0	10.1

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks :

----- End -----

Tested By : K.L. FONG

Checked By : GU CHIN

Approved Signatory :

Name : GU CHIN

Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC091200415 Date of Issue : 05-01-2010

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 30-12-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 31-12-2009

GCE Serial No. : WQM122009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	502	505	-0.6	25.1
		Acceptance Criteria	<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID		C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time		30 Dec 2009 / 11:15		30 Dec 2009 / 11:25		30 Dec 2009 / 11:35			
	LOD	Units								
Suspended Solids (SS)	1	mg/L	< 1.0	< 1.0	< 1.0	< 1.0	6.0	5.7		

TEST RESULTS	Sample ID		M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time		30 Dec 2009 / 10:50		30 Dec 2009 / 11:05		30 Dec 2009 / 11:00		30 Dec 2009 / 10:40	
	LOD	Units								
Suspended Solids (SS)	1	mg/L	4.3	4.6	1.5	1.2	5.2	5.0	6.1	5.8

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks :

----- End -----

Tested By : K.L. FONG

Checked By : GU CHIN

Approved Signatory :

Name : GU CHIN

Post : Chemist

GEOTECHNICS & CONCRETE ENGINEERING (H. K.) LTD.
6 KO SHAN RD., GROUND FL., HUNG HOM, KOWLOON, HONG KONG.
TEL.: 852-2365 9123 FAX NO.: 852-2765 8034

TEST REPORT ON ENVIRONMENTAL ANALYSIS OF WATER AND WASTEWATER

Report No. : GCC091200423 Date of Issue : 05-01-2010

Client* : Environmental Pioneers & Solutions Limited P.O. Received : 08-09-2008

Client Address* : 8/F, Chaiwan Industrial Centre Building, 20 Lee Chung Street, Chaiwan, HK.

Project* : DSD Contract No. DC/2006/11 - Drainage Improvement in Southern Lantau & Construction of Mui Wo Village Sewerage Phase 1

Test Location : G/F, 20 Pak Kung Street, Hung Hom, Kowloon. Date Started : 31-12-2009

W.O. No.* : -- Sample Type* : River Water Date Completed : 02-01-2010

GCE Serial No. : WQM122009 GCE Reg. No. : GCE 081096 Test Unit No. : CH 08258

Analysis Description	Test Method	Units	Quality Control Results				
			Method Blank	QC 500 mg/L	QC Duplicate	RPD%	Spike 25 mg/L
Suspended Solids (SS)	APHA 20ed 2540 D	mg/L	< 1.0	497	501	-0.8	25.5
		Acceptance Criteria	<2.5 mg/L	475 ≤ Control Limit ≤ 514		≤ ±5%	21 ≤ R ≤ 29

TEST RESULTS	Sample ID		C1	C1 Duplicate	C2	C2 Duplicate	C3	C3 Duplicate		
	Sampling Date/Time		31 Dec 2009 / 12:15		31 Dec 2009 / 12:25		31 Dec 2009 / 12:35			
	LOD	Units								
Suspended Solids (SS)	1	mg/L	< 1.0	< 1.0	< 1.0	< 1.0	5.6	5.3		

TEST RESULTS	Sample ID		M1	M1 Duplicate	M2	M2 Duplicate	M3	M3 Duplicate	M4	M4 Duplicate
	Sampling Date/Time		31 Dec 2009 / 11:50		31 Dec 2009 / 12:05		31 Dec 2009 / 12:00		31 Dec 2009 / 11:40	
	LOD	Units								
Suspended Solids (SS)	1	mg/L	8.5	8.7	1.2	1.4	3.9	3.6	11.0	10.7

* : Information provided by client

Note : This laboratory has no responsibility on sampling and all the test results relate only to the sample tested as received.

Remarks :

----- End -----

Tested By : K.L. FONG Approved Signatory :

Name : GU CHIN

Checked By : GU CHIN Post : Chemist

Appendix G
Monitoring Schedule
for Dec 2009

Environmental Pioneers and Solutions Limited

DC/2006/11 - DRAINAGE IMPROVEMENT IN SOUTHERN LANTAU

Master Schedule of EM&A works in December 2009

Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
11/29	11/30	12/1	12/2	12/3	12/4	12/5
			WQM at: 12:59 Noise monitoring		WQM at: 14:21 Ecological Survey	
12/6	12/7	12/8	12/9	12/10	12/11	12/12
	WQM at: 16:00	WQM at: 16:30 Ecological Survey	WQM at: 17:00 Noise monitoring			
12/13	12/14	12/15	12/16	12/17	12/18	12/19
	WQM, EWQM at: 10:55		WQM at: 12:10 Noise monitoring	additional WQM at: 12:45	WQM at: 13:20	
12/20	12/21	12/22	12/23	12/24	12/25	12/26
	WQM at: 15:25	WQM at: 16:00	WQM at: 17:00 Noise monitoring			
12/27	12/28	12/29	12/30	12/31	1/1	1/2
		WQM at: 10:30	WQM at: 10:50 Noise monitoring	WQM at: 11:39		

Noise Monitoring Locations: Total 4 Locations as N1, N2, N3 and N4

Water Quality Monitoring (WQM) Locations: Total 7 Locations as M1, M2, M3, M4, C1, C2 and C3

Ecological Water Quality Monitoring (EWQM) Locations: Total 6 Locations as WE1, WE2, WE3, WE4, WE5 and WE6

Appendix H Implementation Status of environmental protection / mitigation measures

Environmental Aspect	Protection / Mitigation Measures	Implementation status	Follow-up action
Air Quality	Use of regular watering to reduce dust emissions from exposed site surfaces and unpaved road, with complete coverage.	Implemented	-
	Use of frequent watering for particular dusty static construction areas and areas close to ASRs.	Implemented	-
	Tarpaulin covering of all dusty vehicle loads transported to and from and between site location;	Implemented	-
	Establishment and use of vehicle wheel and body washing facilities at the exit points of the site.	Implemented	-
	Routing of vehicles and positioning of construction plant should be at the maximum possible distance from ASRs.	Implemented	-
Noise	Use of quiet powered mechanical equipment (PME)	Implemented	-
	Adoption of movable noise barriers and temporary noise barriers	Implemented	
	Application of good site practices mentioned in EM&A manual Clause 3.8.1	Implemented	-
Water Quality	Before commencing any site formation works, all sewer and drainage connections should be sealed to prevent debris, soil, sand etc. from entering public sewers/drains.	Deficiencies found	Outstanding. Improvements are required
	Temporary ditches should be provided to facilitate run-off discharge into appropriate watercourses, via a silt retention pond. No site run-off should enter the freshwater marshes at Luk Tei Tong.	Implemented	-
	Sand/ silt removal facilities such as sand traps, silt traps and sediment basins should be provided to remove sand/ silt particles from runoff to meet the requirements of the Technical Memorandum standard under the Water Pollution Control Ordinance.	Deficiencies found	Outstanding. Improvements are required
	Water pumped out from foundation excavations should be discharged into silt removal facilities.	Implemented	-
	During rainstorms, exposed slope surface should be covered by a tarpaulin or the means.	Implemented	-
	Exposed soil areas should be minimized to reduce potential for increased siltation and contamination of runoff.	Implemented	-
	Exposed soil surfaces should be protected by paving or fill material as soon as possible to reduce potential of soil erosion.	Implemented	-
	Open stockpiles of construction materials or construction wastes on-site of more than $50m^3$ should be covered with tarpaulin or similar fabric during rainstorms.	Implemented	-
	Oils and fuels should only be used and stored on designated areas which have pollution prevention facilities.	Implemented	-
	Temporary sanitary facilities, such as portable chemical toilets, should be employed on-site.	Not available	-
	The excavation and widening works for the drainage improvements to the Pak Ngan Heung River, Tai Tei Tong River, Luk Tei Tong River and Luk Tei Tong By-pass Channel should be carried out in sections (approximately 300 –400 m in length) and in dry condition.	Implemented	-

Environmental Aspect	Protection / Mitigation Measures	Implementation status	Follow-up action
	Maintenance desiltng of the re-profiled river channels of the Pak Ngan Heung River, Tai Tei Tong River, Luk Tei tong River and Luk Tei Tong By-pass Channel, temporary barrier walls should be used to provide a dry zone for desiltng work.	Not applicable at this stage	-
Ecology	Existing natural habitats should be retained as far as practicable	Implemented	-
	Boundary of working areas should be identified to prevent loss of vegetation	Implemented	-
	All existing trees / plant should be well protected within the site or transplanted properly	Implemented	-
	Turf removal from the Luk Tei Tong marsh due to the construction of Luk Tei Tong Bypass Channel shall be minimized	Implemented	-
	Turf from the Luk Tei Tong marsh shall be properly removed, stored, maintained and reused for lining the riverbed of the Luk Tei Tong Bypass Channel	Implemented	-
Chemical and Solid Waste	Chemical wastes should be properly stored in a proper store as per statutory requirements (i.e. on a hard standing, within an enclosed and locked area)	Implemented	-
	Chemical waste stores should be provided with fire precaution facilities (i.e. fire extinguisher, no smoking warning etc).	Implemented	-
	Chemical wastes should be properly stored in corrosion resistant containers placed inside the store and labelled with warning signs in English and Chinese.	Implemented	-
	Chemical wastes should be disposed of by licensed chemical waste collector with supporting delivery records.	Implemented	-
	All containers for fuel, diesel and fluid chemical (in use) and oil filled stationery plants located with proper drip pans.	Implemented	
	Construction wastes should be managed and disposed to the designated public fill and landfill areas in acceptable manner.	Implemented	-
	All waste disposals managed in a proper manner i.e. trip ticket system implementation.	Implemented	-

Appendix I

Graphical plot of water quality monitoring results (SS, DO, turbidity)

Graphical Plot of Turbidity Trend M1&C1 (Sep - Dec 09)



Graphical Plot of Turbidity Trend M2&C2 (Sep - Dec 09)



Graphical Plot of Turbidity Trend M3&C3 (Sep - Dec 09)



Graphical Plot of Turbidity Trend M4 (Sep - Dec 09)



Graphical Plot of Dissolved Oxygen Trend M1&C1 (Sep - Dec 09)



Graphical Plot of Dissolved Oxygen Trend M2&C2 (Sep - Dec 09)



Graphical Plot of Dissolved Oxygen Trend M3&C3 (Sep - Dec 09)



Graphical Plot of Dissolved Oxygen Trend M4 (Sep - Dec 09)



Graphical Plot of Suspended Soild M1&C1 (Sep - Dec 09)



Graphical Plot of Suspended Soild M2&C2 (Sep - Dec 09)



Graphical Plot of Suspended Soild M3&C3 (Sep - Dec 09)



Graphical Plot of Suspended Soild M4 (Sep - Dec 09)



Appendix J

Graphical plot of noise monitoring results


Nl (Sep - Dec09)
dB (A)
80
70
60
50
40
30
20
10
0
7-Sep-09
16-Sep-09
21-Sep-09
2-Oct-09
7-Oct-09
14-Oct-09
21-Oct-09
28-Oct-09
4-Nov-09
11-Nov-09
18-Nov-09
26-Nov-09
2-Dec-09
9-Dec-09
16-Dec-09
23-Dec-09
30-Dec-09
Day Time Level
Day Time Limit


N2 (Sep - Dec09)
dB (A)
80
70
60
50
40
30
20
10
0
7-Sep-09
16-Sep-09
21-Sep-09
2-Oct-09
7-Oct-09
14-Oct-09
21-Oct-09
28-Oct-09
4-Nov-09
11-Nov-09
18-Nov-09
26-Nov-09
2-Dec-09
9-Dec-09
16-Dec-09
23-Dec-09
30-Dec-09
Day Time Level
Day Time Limit


N3 (Sep - Dec09)
dB (A)
80
70
60
50
40
30
20
10
0
7-Sep-09
16-Sep-09
21-Sep-09
2-Oct-09
7-Oct-09
14-Oct-09
21-Oct-09
28-Oct-09
4-Nov-09
11-Nov-09
18-Nov-09
26-Nov-09
2-Dec-09
9-Dec-09
16-Dec-09
23-Dec-09
30-Dec-09
Day Time Level
Day Time Limit


N4 (Sep - Dec09)
dB (A)
80.0
70.0
60.0
50.0
40.0
30.0
20.0
10.0
0.0
7-Sep-09
16-Sep-09
21-Sep-09
28-Sep-09
7-Oct-09
14-Oct-09
21-Oct-09
28-Oct-09
4-Nov-09
11-Nov-09
18-Nov-09
26-Nov-09
2-Dec-09
9-Dec-09
16-Dec-09
23-Dec-09
30-Dec-09
Day Time Level
Day Time Limit

Appendix K

Ecological Survey Report

for the mangrove area at Luk Tei Tong

Background

In response to the concerns from green groups on the mangrove area to the east of Luk Tei Tong River, contractor took action to install pipes between Luk Tei Tong River and the mangrove area on 25 May 2009 as agreed on a meeting in mid May.

The inlet pipes from Luk Tei Tong River to the mangrove area consisted of two sections. The first section was between the mangrove area wetland and the excavation area. The second section was between the excavation area and Luk Tei Tong River. The inlet pipes was constructed at a level of 1.7mPD so as to allow water to flow naturally from Luk Tei Tong River during high tide into the wetland. The tidal effects on the mangroves were maintained at all times throughout the remaining part of the river works.

A monitoring for the mangrove area was conducted, weekly for one month starting form 27 May 2009 after installation of the twin pipes. Thereafter, the monitoring would be monthly till the completion of gabion wall construction and the original water inlet is reinstated (the end of September 2009), and three months after the completion.

The objectives of the ecological monitoring are to:

- to document the completion installation and proper operation of the temporary twin 400mm pipes
- to document the general health condition of the mangrove community at Luk Tei Tong
- to evaluate reinstatement of the natural tidal flow

Method

Field survey was conducted on 8 December 2009. This was the last session of mangrove community monitoring.

The survey was conducted during low tide period (around 9 am). Photos of the construction site and the mangrove communities were taken for documentation. The installed inlet pipes were removed and the inlet at the rock gabions was constructed in September 2009 to allow natural tidal exchange. The condition of tidal exchange was checked, and the health condition of the mangroves were observed and recorded.

Results

The tidal inlet was of its original level before construction. During the survey stream water was flowing out from the mangrove area to the stream channel (**Photo 1**).

The mangrove communities were exposed during the current survey. The dominant mangrove or mangrove associated species in Area 1 (i.e. the western pond adjacent to the inlet at the rock gabion) were in good conditions. Blooming of *Phragmites australis* (**Photos 2**) was completed, while *Aegiceras corniculatum* (**Photos 3**) was in good health condition with little yellowing leaves compared with before. Other plant species were also in good condition. An individual of *Excoecaria agallocha* was observed flowering.

Recovery of mangrove community in Area 2 (i.e. the eastern pond separated from the western pond by a pond bund) varied by species. P*hragmites australis* and *Hibiscus tiliaceus* were in good condition. *Aegiceras corniculatum* on the periphery and *Acanthus ilicifolius* in the middle section was in fair condition (**Photo 4)**. The population of *Acanthus ilicifolius* on the periphery withered, and regeneration was slow**.** Mortality of many individuals of Mangrove Fern *Acrostichum aureum* (**Photo 5**) continued since November 2009. ,.

Mortality of Mangrove Fern at Area 2 was not observed in previous months. Impedance in tidal water exchange could be the reason of poor conditions of the mangroves in this area as standing water, although shallow, was always observed in this area even in low tide condition.

No fishes or mangrove crabs were observed in the standing water of both mangrove areas probably due to the adverse weather condition during survey.

The works between the new gabion and the mangrove areas have been reinstated to form a gentle slope covered with sediments (Photo 6). Weeds started to colonise and establish on the bare slope.

Conclusions and Recommendations

The reinstatement of inlet has been completed at the end of September. Removal of pipes and rock gabions to the original level of the tidal inlet has significant improved

the tidal exchange. Recovery of mangrove communities is satisfactory in Area 1, while more mangrove and mangrove associates were in poor condition in Area 2. It is recommended that water samples be taken at both areas for water quality checking. Should water quality and exchange be identified as the factor, measures should be proposed to restore the hydrological conditions. For example, connection between Area 1 and Area 2 by breaking the in-between old bund could be considered, to improve the tidal water circulation.

It is also recommended that a planting programme be implemented at the reinstated area between the mangrove area and the gabion to avoid growth of weeds. Potential species can include mangrove backshore species such as *Hibiscus tiliaceus* and *Pandanus tectorius*. An alternative is to remove the surplus sediment to about high tide level in order to allow natural colonisation of the mangrove community.

 Photo 1	 Photo 2
 Photo 3	 Photo 4
 Photo 5	 Photo 6