



**DRAINAGE SERVICES DEPARTMENT
CONTRACT NO. DC/2011/06**

**REPROVISIONING OF BOUNDARY PATROL ROAD
AND ASSOCIATED SECURITY FACILITIES
BETWEEN PING YUEN RIVER AND PAK FU SHAN
AND DRAINAGE WORKS IN NORTH DISTRICT**

**EM&A REPORT FOR DRAINAGE WORKS UNDER
EP-277/2007/A (MAY 2013)**

**PREPARED FOR
SANG HING CIVIL CONSTRUCTORS CO., LTD.**

Quality Index

Date	Reference No.	Prepared By	Approval By
10 June 2013	TCS00599/12/600/R0115	 F. N. Wong Senior Environmental Consultant	 T. W. Tam Environmental Team Leader

Version	Date	Description
0	10 June 2013	First Submission
1	13 June 2013	Amended against IEC's comments

This report has been prepared by Action-United Environmental Services & Consulting with all reasonable skill, care and diligence within the terms of the Agreement with the client, incorporating our General Terms and Conditions of Business and taking account of the resources devoted to it by agreement with the client. We disclaim any responsibility to the client and others in respect of any matters outside the scope of the above. This report is confidential to the client and we accept no responsibility of whatsoever nature to third parties to whom this report, or any part thereof, is made known. Any such party relies upon the report at their own risk.

Ref.: DSDBPRNDEM00_0_0147L.13

14 June 2013

By Post and Fax (2959 6079)

Action-United Environmental Services & Consulting
Unit A, 20/F,
Gold King Industrial Building,
New Territories, Hong Kong

Attention: Mr. T.W. Tam

Dear Sir,

**Re: Contract No. DC/2011/06
Reprovisioning of Boundary Patrol Road and Associated Security Facilities
between Ping Yuen River and Pak Fu Shan and Drainage Works in North
District
EM&A report for Drainage Works under EP-277/2007/A (May 2013)**

Reference is made to the Environmental Team's submission of the captioned report (Version 1) dated 13 June 2013 received through E-mail on 14 June 2013 for our review and comment.

Please be informed that we have no adverse comment on the captioned submission. We write to verify the captioned submission in accordance with Condition 3.4 in the captioned Environmental Permit.

Thank you for your kind attention and please do not hesitate to contact the undersigned should you have any queries.

Yours sincerely,



Roger Leung
Independent Environmental Checker

c.c.	DSD	Mr. Eric Y.M. Cheng	by fax: 2827 8700
	SHCCCL	Mr. Raymond W.M. Yau	by fax: 2403 1162

Q:\Projects\DSDBPRNDEM00\02 Project Management\02 Corr\DSDBPRNDEM00_0_0147L.13.doc

EXECUTIVE SUMMARY

BREACHES OF ENVIRONMENTAL QUALITY CRITERIA (A/L LEVELS)

- ES01 Monitoring results indicated no exceedances of A/L Levels for air quality and construction noise during the Reporting Period. Neither NOE nor remedial actions were required.
- ES02 Power supply at MUP-A1 (MUP05) and the associated 24-Hour TSP monitoring has been reinstated during Reporting Period.

COMPLAINTS LOG

- ES03 No environmental complaint was registered in the Reporting Period. The complaint log is presented as follows:

Reporting Month	Environmental Complaint Statistics		
	Frequency	Cumulative	Complaint Nature
May 2012 to May 2013	0	0	NA

NOTIFICATIONS OF SUMMONS AND SUCCESSFUL PROSECUTIONS

- ES04 No notifications of summons and successful prosecutions were registered during the Reporting Period.

REPORTING CHANGES

- ES05 No reporting changes were made during the Reporting Period.

FUTURE KEY ISSUES

- ES06 Construction dust, noise and water quality continue to be the key environmental issues for construction of the Works during the coming Reporting Period.
- ES07 As predicted in the EIA Report (Register No. in the EP: AEIAR-108/2007), with full implementation of the recommended environmental protection measures, adverse environmental impacts generated from future construction activities under the Works can be eliminated to acceptable levels.
- ES08 Special attention is drawn to implementation of air quality mitigation measures, in particular construction dust suppression measures during dusty construction activities under dry and windy conditions.
- ES098 In addition, water quality mitigation measures is reminded during rainy days to eliminate adverse water quality impacts generated from surfaces runoff of haul roads, stock pile of excavated materials, etc.
- ES10 Construction noise mitigation measures should also be implemented during noisy construction activities.

RECOMMENDATIONS

- ES11 Special attention is drawn to high SS levels due to heavy rain detected during the Reporting Period in order to avoid potential adverse water quality impacts on the environment.

TABLE OF CONTENTS

1 ENVIRONMENTAL IMPLEMENTATION STATUS1
2 SUMMARY OF REQUIREMENTS FOR CONSTRUCTION IMPACT MONITORING3
3 ENVIRONMENTAL MONITORING RESULTS10
4 WASTE MANAGEMENT13
5 ENVIRONMENTAL SITE INSPECTION13
6 ENVIRONMENTAL COMPLAINT, SUMMONS AND PROSECUTION14
7 IMPACT FORECAST15
8 CONCLUSIONS AND RECOMMENDATIONS.....16

LIST OF TABLES

TABLE 1-1 STATUS OF ENVIRONMENTAL LICENSES AND PERMIT
TABLE 1-2 MAJOR CONSTRUCTION ACTIVITIES FOR THE WORKS DURING THE REPORTING PERIOD
TABLE 1-3 MAJOR CONSTRUCTION ACTIVITIES FOR THE WORKS FOR THE FORTHCOMING TWO MONTHS
TABLE 2-1 SUMMARY OF MONITORING PARAMETERS
TABLE 2-2 MONITORING LOCATIONS
TABLE 2-3 SUMMARY OF ADDITIONAL ENVIRONMENTAL MONITORING LOCATIONS
TABLE 2-4 AIR QUALITY MONITORING EQUIPMENT
TABLE 2-5 CONSTRUCTION NOISE MONITORING EQUIPMENT
TABLE 2-6 WATER QUALITY MONITORING EQUIPMENT
TABLE 2-7 ACTION AND LIMIT LEVELS FOR AIR QUALITY
TABLE 2-8 ACTION AND LIMIT LEVELS FOR CONSTRUCTION NOISE (dB(A))
TABLE 2-9 ACTION AND LIMIT LEVELS FOR ADDITIONAL WATER QUALITY MONITORING
TABLE 3-1 AIR QUALITY (1-HOUR TSP) MONITORING RESULTS AT MUP-A1 (MUP05)
TABLE 3-2 AIR QUALITY (24-HOUR TSP) MONITORING RESULTS AT MUP-A1 (MUP05)
TABLE 3-3 CONSTRUCTION NOISE MONITORING RESULTS AT MUP-N1 (MUP05)
TABLE 3-4 CONSTRUCTION NOISE MONITORING RESULTS AT MUP-Nx (MUP05)
TABLE 3-5 WATER QUALITY MONITORING RESULTS AT Wx1 AND Wx2 (MUP05)
TABLE 5-1 OBSERVATIONS OF SITE INSPECTION DURING THE REPORTING PERIOD
TABLE 6-1 SUMMARY OF ENVIRONMENTAL COMPLAINTS
TABLE 6-2 SUMMARY OF ENVIRONMENTAL SUMMONS
TABLE 6-3 SUMMARY OF ENVIRONMENTAL PROSECUTION
TABLE 7-1 KEY ENVIRONMENTAL ISSUES FOR THE UP-COMING MONTH
TABLE 7-2 ENVIRONMENTAL MITIGATION MEASURES FOR THE UP-COMING MONTH

LIST OF ANNEXES

ANNEX A LOCATION PLAN FOR THE WORKS UNDER EP-277/2007/A
ANNEX B ENVIRONMENTAL MANAGEMENT ORGANIZATION AND COMMUNICATION LINES
ANNEX C IMPLEMENTATION SCHEDULE FOR ENVIRONMENTAL MITIGATION MEASURES
ANNEX D 3-MONTH ROLLING CONSTRUCTION PROGRAM
ANNEX E IMPACT MONITORING SCHEDULE
ANNEX F MONITORING LOCATIONS
ANNEX G MONITORING EQUIPMENT CALIBRATION CERTIFICATES
ANNEX H EVENT/ ACTION PLAN
ANNEX I 24-Hr TSP DATA AND GRAPHICAL PLOT OF ENVIRONMENTAL MONITORING RESULTS
ANNEX J METEOROLOGICAL
ANNEX K WASTE FLOW TABLE AND SUMMARY OF WORKS PROCESSES OR ACTIVITIES REQUIRING TIMBER FOR TEMPORARY WORKS

1 ENVIRONMENTAL IMPLEMENTATION STATUS

- 1.01 This is the monthly EM&A report (herein after “this Report”) for Drainage Works under EP-277/2007/A for the period from 1 to 31 May 2013 (hereinafter “the Reporting Period”).
- 1.02 Location plan for the works under the Contract is shown in *Annex A*, whereas environmental management organization and communication lines, including contacts of key personnel under the Contract are shown in *Annex B*.
- 1.03 Status of environmental licenses and permit is summarized in the following *Table 1-1*.

Table 1-1 Status of Environmental Licenses and Permit

Permit Type	Licenses / Permit No.	Date of Issuance by EPD	Expiry Date	Concerned Location	Status
Environmental Permit	EP-277/2007	09 July 2007	N.A.	Lin Ma Hang and Man Uk Pin	EP-277/2007/A to supersede EP-277/2007
	EP-277/2007/A	01 December 2009			
Notification pursuant to Section 3(1) of the Air Pollution Control Ordinance (APCO) (Construction Dust) Regulation	N.A.	N.A.	N.A.	Contract Area (Lin Ma Hang, Man Uk Pin, Ma Wat Wai and Ping Yuen River)	Valid
Account for Disposal of Construction Waste	7015003	07 May 2012	N.A.	Contract Area (Lin Ma Hang, Man Uk Pin, Ma Wat Wai and Ping Yuen River)	Valid
Application for Wastewater Discharge License under Water Pollution Control Ordinance (WPCO)	W5/11363/1	29 August 2012	31 Aug 2017	Lin Ma Hang, Man Uk Pin and Ma Wat Wai	Valid
Register as a Chemical Waste Producer under Waste Disposal Ordinance	5123-642-S3565-03	3 October 2012	N.A.	Contract Area (Lin Ma Hang, Man Uk Pin, Ma Wat Wai and Ping Yuen River)	Valid

- 1.04 Construction program of the Works with fine tuning of construction activities showing the interrelationship with environmental protection/mitigation measures is presented in Implementation Schedule for the recommended mitigation measures attached in *Annex C* of this Report whereas updated 3-Month Construction Program of the Works is shown in *Annex D*.
- 1.05 Implementation Status for the recommended mitigation measures are presented in the monthly site inspection checklists which are endorsed by related parties including representatives of the ER, IEC, Contractor, EO and ET.

MAJOR CONSTRUCTION ACTIVITIES

THE REPORTING PERIOD

1.06 Major construction activities of the Works undertaken during the Reporting Period are listed in **Table 1-2** below:

Table 1-2 Major Construction Activities for the Works during the Reporting Period

Portion of the Works	Major Construction Activities
Portion E (Man Uk Pin)	1) Installation of sheet pile for excavation; 2) Construction of transition at CH321; 3) Construction of gabion wall at CH317; 4) Establishment of Transplanting of tree T1107; and 5) Installation of temporary noise barrier.

FORTHCOMING TWO MONTHS

1.07 Major construction activities of the Works for the forthcoming two months are listed in **Table 1-3** below:

Table 1-3 Major Construction Activities for the Works for the Forthcoming Two Months

Portion of the Works	Major Construction Activities
Portion E (Man Uk Pin)	1) Pruning, felling and transporting of existing trees; 2) Construction of box culvert transition; 3) Construction of gabion channel; and 4) Installation of temporary noise barrier.

EM&A ACTIVITIES

BASELINE MONITORING AND ENVIRONMENTAL QUALITY CRITERIA

1.08 The baseline monitoring for air quality, construction noise and water quality has been carried out since 17 September 2008, whereas that for ecology has been performed since 16 September 2008 in close accordance with the requirements of the EM&A Manual.

1.09 It is agreed amongst the Engineer, IEC, Contractor and ET that the established environmental quality criteria i.e. Action/Limit Levels (hereinafter “the A/L Levels”) for air quality, construction noise and water quality as shown in **Tables 2-7** and **Tables 2-8** respectively are to be used in the EM&A for air quality, construction noise and water quality under Drainage Works under EP-277/2007/A.

ENVIRONMENTAL MONITORING

1.10 The environmental monitoring during the Reporting Period followed monitoring schedules submitted to relevant parties upon agreement with the IEC and ER prior to implementation. They are presented in **Annex E**.

2 SUMMARY OF REQUIREMENTS FOR CONSTRUCTION IMPACT MONITORING

2.01 The requirements for EM&A for Drainage Works under EP-277/2007/A are detailed in *Methodology for Environmental Monitoring and Audit under the Contract* (hereinafter “the Methodology”, which has been verified by the IEC on 27 July 2012 and submitted to EPD for approval subsequently. They are summarized as follows.

MONITORING PARAMETERS

2.02 The monitoring parameters required for the Works are summarized in *Table 2-1*.

Table 2-1 Summary of Monitoring Parameters

Environmental Aspect	Parameters
Air Quality	(a) 1-Hour Total Suspended Particulate (hereinafter ‘1-Hr TSP’); and (b) 24-Hour Total Suspended Particulate (hereinafter ‘24-Hr TSP’).
Construction Noise	(c) A-weighted equivalent continuous sound pressure level (30min) (hereinafter ‘Leq(30min)’ during the normal working hours; and (d) A-weighted equivalent continuous sound pressure level (5min) (hereinafter ‘Leq(5min)’ for construction work during the restricted hours.
Water Quality	(e) In Situ temperature, Dissolved Oxygen, Dissolved Oxygen Saturation, pH value, Water Depth, Temperature & Turbidity Measurement:
	(f) Laboratory Analysis Suspended Solids (hereinafter ‘SS’),
Ecology (MUP05)	(g) The stream conditions monitoring (in-situ measurements of DO, pH and turbidity; laboratory testing of SS); (h) Riparian vegetation along the banks of channel monitoring; (i) General site audit to ensure the existing natural stream channel is protected; and (j) Reported the sediment condition during the construction phase

MONITORING LOCATIONS

DESIGNATED LOCATIONS IN THE EM&A MANUAL

2.03 Monitoring locations for EM&A under EP-277/2007/A have been identified in the EM&A Manual. They are shown in *Annex F*. According to the EM&A Manual and agreement among the Engineer, IEC, Contractor and ET, the environmental monitoring stations closest to the construction site are to be adopted for the EM&A under the Contract. As sensitive receiver MUP05-2 is the closest location to the Works site, it will most likely be impacted by the construction under the Works. The sensitive receiver MUP05-1 is therefore adopted as environmental monitoring locations for air quality namely MUP-A1 and construction noise namely MUP-N1.

2.04 On the other hand, as there was neither riparian vegetation along the banks of channel nor existing natural stream channel within the site of the Works, no ecology monitoring is required during the construction period of the Works.

2.05 *Table 2-2* summarizes all the monitoring locations under the Works.

Table 2-2 Monitoring Locations

Issue	Channel	Sensitive Receiver	Location ID	Detailed Address
Air	MUP05	MUP05-2	MUP-A1	Village house at Man Uk Pin
Noise	MUP05	MUP05-2	MUP-N1	Same village house at Man Uk Pin as MUP-A1 above

ADDITIONAL MONITORING LOCATIONS

2.06 In order to monitor the potential construction impacts more effectively, additional environmental monitoring for construction noise and water quality has been recommended by the Engineer and IEC. They are summarized in **Table 2-3** and shown in **Annex F**.

Table 2-3 Summary of Additional Environmental Monitoring Locations

Issue	Channel	Sensitive Receiver	Location ID	Monitoring Time
Construction Noise	MUP05	MUP05-2	MUP-Nx (Village house)	The whole construction period
Water Quality	MUP05	-	MUP-Wx1 (Up-Stream Control Station)	The whole construction period
		-	MUP-Wx2 (Impact Monitoring Station)	Before connection of stream diversion
		-	MUP-Wx3 (Impact Monitoring Station)	After connection of stream diversion

2.07 The additional monitoring has been commenced since August 2012 upon the IEC’s verification of the Methodology.

MONITORING FREQUENCY

2.08 The impact monitoring should be conducted during the construction period to ensure the environmental conditions comply with the environmental quality criteria i.e. A/L Levels. The impact monitoring frequency as stipulated in the EM&A Manual is summarized below.

AIR QUALITY

- Parameters:** 24-Hour TSP and 1-Hour TSP.
- Frequency:** Once every 6 days for 24-Hour TSP & three times every 6 days for 1-Hour TSP.
- Duration:** During the course of construction works

CONSTRUCTION NOISE

- Parameters:** Leq(30 min) in six consecutive Leq(5 min) measurements
- Frequency:** Once a week during 0700-1900 on normal weekdays
- Duration:** During the course of construction works

WATER QUALITY

- Parameters:** Duplicate in-situ measurements of water depth, temperature, DO, pH & turbidity; and laboratory testing of SS. Relevant data will also be measured time of sampling, DO Saturation, weather conditions and special phenomena.
- Depths:** All measurements will be carried out at three water depths, namely, 1 m below water surface, mid-water depth, and 1 m above river bed. If the water depth is less than 6 m, the mid-depth measurement will be omitted. If the depth is less than 3 m, only the mid-depth measurement will be taken.
- Frequency:** 3 times a week with an interval of at least 36 hours between two consecutive sampling days
- Duration:** During the construction period of the channel works

MONITORING EQUIPMENT

2.09 The monitoring equipment for air quality, construction noise, stream water quality and ecology are summarized below.

AIR QUALITY

2.10 Air quality monitoring equipment is listed in the following **Table 2-4**.

Table 2-4 Air Quality Monitoring Equipment

Equipment	Model
24-Hour TSP	
High Volume Air Sampler (herein after 'HVS')	Grasby Anderson GMWS 2310 HVS
Calibration Kit	TISCH Model TE-5025A
1-Hour TSP	
Portable Dust Meter	AM510; Dust Trak Model 8520

CONSTRUCTION NOISE

2.11 Construction noise monitoring equipment is listed in *Table 2-5*.

Table 2-5 Construction Noise Monitoring Equipment

Equipment	Model
Integrating Sound Level Meter	B&K Type 2238
Calibrator	B&K Type 4231
Portable Wind Speed Indicator	Testo Anemometer

WATER QUALITY

2.12 Monitoring equipment for water quality is listed in *Table 2-6*.

Table 2-6 Water Quality Monitoring Equipment

Equipment	Model / Description
<i>In-situ Measurement</i>	
Water Depth Detector	Eagle Sonar or steel ruler
Water Sampler	Teflon bailer / bucket
Thermometer & DO meter	YSI Multimeter
pH meter	Extech pH EC 500
Turbidimeter	Hach 2100p
Sample Container and Storage	High density polythene bottles (provided by laboratory) and 'Willow' 33-liter plastic cool box
<i>Laboratory Analysis</i>	
Suspended Solids	HOKLAS accredited Laboratory

EQUIPMENT CALIBRATION

2.13 The calibrations certificate of all monitoring equipment are used during the impact monitoring program are attached in *Annex G* and the calibration requirement are described in below:

AIR QUALITY

2.14 The calibration of the HVS is performed at a bimonthly interval in accordance with the manufacturer's instruction using the NIST-certified standard calibrator (Tisch Calibration Kit Model No.TE-5025A). The calibration data are properly documented and the associated records are maintained by the ET for future reference.

2.15 The 1-Hour TSP meter is calibrated at a year intervals in accordance with the in-house method. Zero response of the equipment is checked before and after each monitoring event.

NOISE

2.16 The sound level meters are calibrated using an acoustic calibrator prior to and after spot checking measurements. The meters are calibrated annually by HOKLAS accredited laboratory. Prior to and following each noise measurement, the accuracy of the sound level meter is checked using an acoustic calibrator generating a known sound pressure level at a known frequency. Measurements are considered valid only if the calibration levels before and after the noise measurement agree to within 1.0 dB.

WATER QUALITY

- 2.17 Once every three months, the in-situ monitoring instruments are calibrated and certified by a laboratory accredited under HOKLAS or any other international accreditation scheme.

MONITORING PROCEDURE

- 2.18 The monitoring methodology and procedure during the impact monitoring are presented as below:

AIR QUALITY

1-Hour TSP

- 2.19 Operation of the 1-Hour TSP meter is follow manufacturer's Operation and Service Manual. The 1-Hour TSP monitor, a TSI Dust Track Aerosol Monitor Model 8520, or Sibata LD-3 Laser Dust Meter is a portable, battery-operated laser photometer. The 1-Hour TSP meter provides a real time 1-Hour TSP measurement based on 90° light scattering. The 1-Hour TSP monitor consists of the following:
- 1) A pump to draw sample aerosol through the optic chamber where TSP is measured;
 - 2) A sheath air system to isolate the aerosol in the chamber to keep the optics clean for maximum reliability; and
 - 3) A built-in data logger compatible with Windows based program to facilitate data collection, analysis and reporting.
- 2.20 The 1-Hour TSP meter using was within the valid period, calibrated by the manufacturer prior to purchasing. Zero response of the instrument was checked before and after each monitoring event.

24-hour TSP

- 2.21 The equipment used for 24-Hour TSP measurement is the HVS brand named Thermo Andersen, Model GS2310 TSP high volume air sampling system, which complied with EPA Code of Federal Regulation, Annex B to Part 50. The HVS consists of the following:
- 1) An anodized aluminum shelter;
 - 2) A 8"x10" stainless steel filter holder;
 - 3) A blower motor assembly;
 - 4) A continuous flow/pressure recorder;
 - 5) A motor speed-voltage control/elapsed time indicator;
 - 6) A 6-day mechanical timer, and
 - 7) A power supply of 220v/50 Hz
- 2.22 The HVS is calibrated prior the impact monitoring to following the manufacturer's instruction using the NIST-certified standard calibrator brand named Tisch Calibration Kit Model TE-5028A. Regular HVS operation and maintenance as well as filter paper installation and collection was performed by the ET's competent technicians, whereas laboratory analyses were conducted in a local HOKLAS accredited laboratory, ALS Technichem (HK) Pty Ltd (hereinafter 'ALS'). The analyzed 24-Hour TSP filters were kept in ALS for six months prior to disposal.

METEOROLOGICAL INFORMATION

- 2.23 All relevant data including temperature, pressure, weather conditions, elapsed-time meter reading for the start and stop of the sampler, identification and weight of the filter paper is recorded in detail.
- 2.24 Meteorological information is sourced from the Hong Kong Observatory (Ta Kwu Ling Station). The data included wind direction, wind speed, humidity, rainfall, air pressure and temperature etc that in general is required for evaluating the air quality for air quality monitoring.

CONSTRUCTION NOISE

- 2.25 Sound level meters listed above comply with the International Electrotechnical Commission Publications 651: 1979 (Type 1) and 804: 1985 (Type 1) specifications, as recommended in Technical Memorandum BE issued under the Noise Control Ordinance (NCO).
- 2.26 All noise measurements are performed with the meter set to FAST response and on the A-weighted equivalent continuous sound pressure level (Leq). Leq(30min) measurements are used as the monitoring parameter for the time period throughout the construction phase.
- 2.27 The sound level meter is set higher than 1.2m above the existing ground. The microphone is pointed to the site with the microphone facing perpendicular to the line of sight. The windshield is fitted for all measurements. As the measurement point at impact locations is set close to the exterior of the building, i.e. no free field noise measurement is performed, free field correction will not be made for monitoring results.
- 2.28 Immediately prior to and following each noise measurement the accuracy of the sound level meter is checked using an acoustic calibrator generating a known sound pressure level at a known frequency (94 dBA). Measurements are accepted as valid due to the calibration levels from before and after the noise measurement agree to within 1.0 dB.

WATER QUALITY

- 2.29 Water quality monitoring is conducted at the middle of the water columns (Mid-Depth) due to water columns at all sampling locations are less than 3.0 meters during monitoring.

Water Depth

- 2.30 Water depths are determined prior to measurement and sampling. A steel ruler with a suitable weight was dropped to the bottom of the water column to measure the water depth which is actually well below 1 meter.

Dissolved Oxygen (DO)

- 2.31 A portable Extech Instrument, ExStikR DO600 DO Meter is used for in-situ DO measurement. The DO meter is capable of measuring DO in the range of 0 – 20 mg/L and 0 – 200 % saturation and checked against water saturated ambient air on each monitoring day prior to monitoring.
- 2.32 Although the DO Meter automatically compensates ambient water temperature to a standard temperature of 20⁰C for ease of comparison of the data under the changing reality, the temperature readings of the DO Meter is recorded.

pH

- 2.33 A portable Extech Instrument, ExStikTM Models pH EC 500 or a Hanna HI98107 pH Meter is used for in-situ pH measurement. The pH meter is capable of measuring pH in the range of 0 – 14 and readable to 0.1. Standard buffer solutions of pH 7 and pH 10 are used for calibration of the instrument before and after measurement.

Turbidity

- 2.34 A portable Hach 2100p turbidity Meter is used for in-situ turbidity measurement. The turbidity meter is capable of measuring turbidity in the range of 0 – 1000 NTU.

Suspended Solids (SS)

- 2.35 SS is determined by ALS using HOKLAS accredited analytical methods namely ALS Method EA-025. The Limit of Reporting (hereinafter “LOR”) is 2 mg/L.

Water Sampler

- 2.36 Water samples are collected by the ET using a plastic sampler to avoid metal contamination. Due to water depth for both sampling locations are lesser than 0.5 m, a cleaned plastic beaker is used for sample collection.

2.37 The sampler is rinsed with the sample before collection with the sample to be taken. 1,000mL water sample is collected from depth for laboratory analyses.

Sample Container

2.38 Water samples are contained in screw-cap PE (Poly-Ethylene) bottles as provided by ALS. The PE bottles are pretreated by laboratory in accordance with the corresponding analytical requirements of HOKLAS. Where appropriate, the sampling bottles are rinsed with the water to be contained. Water sample is transferred from the sampler to the sample bottles to 95% bottle capacity to allow possible volume expansion during delivery and storage.

Sample Storage and delivery

2.39 A ‘Willow’ 33-liter plastic cool box packed with ice is used to preserve the collected water samples prior to arrival at the laboratory. The temperature of the cool box is maintained as close to 4⁰C as possible without being frozen. Samples are delivered to the laboratory end of sampling day or following day within the maximum storage time requirement.

Chemical Analysis

2.40 ALS Technichem (HK) Pty Ltd (HOKLAS No. 66) is appointed by ET to provide analytical services for this project. The analysis of suspended solids is carried out to follow the APHA Standard Methods for the Examination of Water and Wastewater 19ed 2540D. The sample preparation and analysis under the QA/QC control is follow the HOKLAS QA/QC requirements and undertaken by the laboratory.

ENVIRONMENTAL QUALITY PERFORMANCE LIMITS

2.41 Baseline monitoring for air quality and construction noise was carried out during 17 September to 13 October 2008 in close accordance with the requirements stipulated in the EM&A Manual. The A/L Levels of MUP-A1 and MUP-N1 will be adopted for EM&A for air quality and construction noise respectively. They are summarized in **Table 2-7, Table 2-8 and Table 2-9** respectively.

Table 2-7 Action and Limit Levels for Air Quality

Monitoring Station	Action Level (µg /m ³)		Limit Level (µg/m ³)	
	1-Hour TSP	24-Hour TSP	1-Hour TSP	24-Hour TSP
MUP-A1	307	156	500	260

Table 2-8 Action and Limit Levels for Construction Noise (dB(A))

Time Period	Action Level	Limit Level
0700-1900 hours on normal weekdays	When one documented complaint is received	75* dB(A)

* Reduces to 70 dB(A) for schools and 65 dB(A) during the school examination periods.

2.42 Environmental quality criteria for additional water quality monitoring are proposed in **Table 2-9** as follows:

Table 2-9 Action and Limit Levels for Additional Water Quality Monitoring

Action Level	Limit Level
120% of the corresponding Levels of Up-Stream Control Station	130% of the corresponding Levels of Up-Stream Control Station

EVENT AND ACTION PLAN

2.43 Event Action Plan for air quality, construction noise and water quality as stipulated in **Annex H** will be triggered in cases of exceedances of A/L Levels.

ENVIRONMENTAL MITIGATION MEASURES

- 2.44 Environmental mitigation measures to minimize potential environmental impacts arising from the construction of the Contract have been recommended and summarized in **Annex C** of the previous *First Monthly EM&A Report for Drainage Works under EP-277/2007/A*. Those related to the construction activities for the up-coming construction period are summarized in **Table 7-2 Environmental Mitigation Measures for the Coming Month** in **Section 7** of this Report.

DATA MANAGEMENT AND DATA QUALITY CONTROL

- 2.45 The impact monitoring data is handled by the ET's systematic data recording and management, which complies with an in-house certified (ISO 9001:2000) Quality Management System. Standard Field Data Sheets (FDS) are used in the EM&A program.
- 2.46 The monitoring data recorded in the equipment e.g. 1-Hour TSP meters and noise meters are downloaded directly at the end of each monitoring day. The downloaded monitoring data are input into a computerized database properly maintained by the ET. The laboratory results are input directly into the computerized database and QA/QC checked by personnel other than those who input the data.
- 2.47 For monitoring activities which require laboratory analysis, the responsible laboratory, ALS, follows the QA/QC requirements as set out under their HOKLAS scheme for all laboratory testing.

3 ENVIRONMENTAL MONITORING RESULTS

AIR QUALITY

3.01 As agreed among the Engineer, IEC, Contractor and ET, the construction noise monitoring is performed at MUP-A1 of Channel MUP05.

MONITORING RESULTS

3.02 The air quality monitoring results of 24-Hour and 1-Hour TSP during the Reporting Period are summarized in **Tables 3-1** and **Table 3-2**. Detailed 24-Hour TSP monitoring data and the graphic plots of both 24-Hour and 1-Hour TSP are shown in **Annex I**.

Table 3-1 Air Quality (1-Hour TSP) Monitoring Results at MUP-A1 (MUP05)

Date	Start Time	1-Hour TSP Monitoring Results at MUP-A1 (MUP05), $\mu\text{g}/\text{m}^3$			
		1 st	2 nd	3 rd	Mean
2-May-13	11:37	21	28	24	24
8-May-13	10:31	93	102	94	96
14-May-13	13:40	46	39	42	42
20-May-13	13:00	28	30	31	30
25-May-13	10:00	49	57	51	52
31-May-13	12:07	20	23	25	23
Average (Range)	45 (20-102)				
A/L Levels	307 / 500				

Table 3-2 Air Quality (24-Hour TSP) Monitoring Results at MUP-A1 (MUP05)

Date	24-Hour TSP Monitoring Results, $\mu\text{g}/\text{m}^3$
1- 27 May 2013	Data not available due to power failure
28-May-13	95
Average (Range)	Not applicable
A/L Levels	156 / 260

DISCUSSION

3.03 Power supply for operation of the HVS at MUP-A1 (MUP05) and the associated 24-Hour TSP monitoring has been reinstated since 28 May 2013.

3.04 As shown in **Table 3-1** and **Table 3-2**, no exceedances of A/L Levels were recorded for 1-Hour TSP and 24-Hour TSP during the Reporting Period.

3.05 Neither Notice of Exceedance (hereinafter “NOE”) nor the associated remedial actions were required for air quality during the Reporting Period.

CONSTRUCTION NOISE

3.06 As agreed among the Engineer, IEC, Contractor and ET, the construction noise monitoring is performed at MUP-N1 of Channel MUP05 as recommended in the EM&A Manual.

3.07 Additional construction noise monitoring has also been commenced since August 2012 at MUP-Nx upon verification of the Methodology by the IEC prior to implementation.

3.08 As the measurement point is set close to the exterior of the building at **MUP-N1**, **no free field correction of +3 dB(A) will be made** for monitoring results of MUP-N1.

3.09 On the other hand, the measurement point is **NOT** set close to the exterior of the building at **MUP-Nx**, **free field correction of +3 dB(A) is made for monitoring results of MUP-Nx**.

MONITORING RESULTS

3.10 Construction noise monitoring results are summarized in *Table 3-3* and *Table 3-4* below and graphic plots of the monitoring results are shown in *Annex I*.

Table 3-3 Construction Noise Monitoring Results at MUP-N1 (MUP05)

Date	Start Time	1 st Leq5	2 nd Leq5	3 rd Leq5	4 th Leq5	5 th Leq5	6 th Leq5	Leq30 (dB(A))
2-May-13	13:57	62.2	63.3	63.0	68.1	64.7	61.6	64
8-May-13	11:02	66.6	70.2	69.0	66.9	67.8	68.5	68
14-May-13	14:37	57.2	58.3	56.7	58.3	59.9	61.2	59
20-May-13	15:05	65.7	61.6	62.1	64.0	65.4	62.3	64
31-May-13	13:42	69.1	69.0	67.9	69.9	69.5	66.4	69
Average (Range)		65 (59 - 69)						

Table 3-4 Construction Noise Monitoring Results at MUP-Nx (MUP05)

Date	Start Time	1 st Leq5	2 nd Leq5	3 rd Leq5	4 th Leq5	5 th Leq5	6 th Leq5	Leq30	Corrected Leq30 (dB(A))
2-May-13	13:01	60.8	59.6	58.1	61.7	62.3	65.4	62	65
8-May-13	10:11	60.1	59.3	59.7	59.9	59.5	57.3	59	62
14-May-13	14:45	57.6	58.0	56.0	58.2	58.7	61.5	59	62
20-May-13	15:08	56.5	61.8	59.3	60.8	61.7	58.1	60	63
31-May-13	13:07	61.9	58.5	63.1	62.7	61.3	61.7	62	65
Average (Range)		63 (62 - 65)							

DISCUSSION

3.11 No environmental complaints against construction noise were registered, indicating no Action Level exceedances were documented during the Reporting Period. In addition, no exceedances of construction noise Limit Level of 75 dB(A) were recorded.

3.12 Neither NOE nor the associated remedial actions were required for construction noise during the Reporting Period.

RECOMMENDATION

3.13 Attention is drawn to construction noise mitigation measures during noisy construction activities.

WATER QUALITY

3.14 No environmental monitoring is recommended in the EM&A Manual during construction of the Works.

3.15 However, additional water quality monitoring at MUP-Wx1 (Up-Stream Control Station) and MUP-Wx2 (Impact Monitoring Station) is recommended by the Engineer and IEC to commence from August 2012 upon verification of the Methodology prior to implementation.

MONITORING RESULTS

3.16 Water quality monitoring results are summarized in *Table 3-5* below and graphically presented in *Annex I*.

Table 3-5 Water Quality Monitoring Results at Wx1 and Wx2 (MUP05)*

Date	Monitoring Parameter							
	DO, mg/L		Turbidity, NTU		pH, pH Value		SS, mg/L	
	Wx1	Wx2	Wx1	Wx2	Wx1	Wx2	Wx1	Wx2
2-May-13	6.5	7.2	17	16	8.25	8.17	21	21
4-May-13	6.1	6.3	15	13	7.81	7.61	18	15
6-May-13	6.0	7.1	12	9	7.66	7.33	60	9
8-May-13	5.1	6.8	20	15	7.41	7.02	38	8
10-May-13	5.3	5.3	11	7	8.68	8.87	11	11
14-May-13	5.1	5.6	6	5	8.79	8.55	64	5
16-May-13	4.4	4.8	15	9	6.85	6.55	104	11
18-May-13	4.3	4.4	8	7	6.75	6.55	12	11
20-May-13	5.7	5.9	24	15	6.65	6.60	58	11
22-May-13	5.2	5.4	9	4	6.55	6.35	8	8
25-May-13	5.7	5.8	38	27	6.85	6.60	155	97
27-May-13	5.5	5.8	56	32	6.40	6.35	311	193
29-May-13	5.1	5.6	6	1	7.70	7.90	14	2
31-May-13	5.8	6.3	4	2	7.65	7.70	9	8

*Note: Wx1- up-stream control station ; Wx2 – Impact monitoring station

DISCUSSION

- 3.17 Neither exceedances of 120% (Action Level) nor 130% (Limit Level) of the corresponding Up-Stream Control levels were documented during the Reporting Period. Therefore, neither NOE nor the associated remedial actions were required for water quality during the Reporting Period.

RECOMMENDATION

- 3.18 Special attention is drawn to high SS levels detected sometimes due to heavy rain during the Reporting Period. Although sedimentation pond was established at the upstream of the channel within the site and part of the water were diverted to the downstream of WX2 after sedimentation during construction of the channel, full implementation of the required water quality mitigation measures, including proper maintenance of the sedimentation pond and regular clearance of the sediment as appropriate, is reminded to avoid adverse water quality impacts on the receiving water bodies.

METEOROLOGICAL DATA

- 3.19 Meteorological information downloaded from the Hong Kong Observatory Ta Kwu Ling Weather Station was summarized in *Annex J* and used in the EM&A of the Works as appropriate.

CONCLUSION

- 3.20 Monitoring results indicated no exceedances of environmental quality criteria during the Reporting Period. Neither NOE nor the associated remedial actions were therefore required for air quality, construction noise and water quality
- 3.21 Nevertheless, fully implementation of the required environmental protection measures are reminded, in particular construction dust suppression measures during dusty construction activities under dry and windy conditions and water quality protection measures during wet season.

4 WASTE MANAGEMENT

- 4.01 Waste management is routinely carried out by the on-site Environmental Officer or Environmental Supervisor.
- 4.02 The quantity of waste for disposal or reuse is summarized in *Monthly Summary of Waste Flow Table* in *Annex K*.
- 4.03 To ensure satisfactory performance of the waste management, the Contractor is reminded to comply with all relevant regulatory requirements, including those stipulated in the effluent discharge licenses and chemical waste producer registration, as well as the EM&A Manual, etc.
- 4.04 Where possible, construction materials should be reused on-site as far as practicable to reduce the construction waste, which should then be sorted or classified on site for proper recycling and disposal as recommended in the Environmental Management Plan and the associated Waste Management Plan.

5 ENVIRONMENTAL SITE INSPECTION

- 5.01 According to the EM&A Manual, the environmental site inspection should be formulated by the ET Leader and regularly conducted jointly by the representatives of the ET, Contractor and ER. During the Reporting Period, a total of five (5) occasions of the site inspection were conducted on 2, 9, 20, 24 and 30 May 2013.
- 5.02 No non-compliance with the relevant regulatory requirements was identified. Observations of the regular site inspection and environmental audit during the Reporting Period are summarized in *Table 5-1*.

Table 5-1 Observations of Site Inspection during the Reporting Period

Date	Findings / Deficiencies	Follow-Up Status
2 May 2013	Muddy haul road was observed within MUP5 site. Wheel washing of the construction vehicles prior to exit the site is reminded in order to avoid construction dust impacts on the air quality of the surrounding.	Muddy haul road was not observed on the haul road at MUP5 on 9 May 2013.
9 May 2013	No adverse environmental impacts were observed. However, full implementation of the required environmental mitigation measures is reminded.	No follow-up actions were required.
20 May 2013		
24 May 2013		
30 May 2013		

- 5.03 Site inspection checklists completed and endorsed by all related parties on the date of site inspection have been kept by the ET and are available for inspection upon request.

6 ENVIRONMENTAL COMPLAINT, SUMMONS AND PROSECUTION

6.01 No environmental complaint was received during the Reporting Period. Summary of environmental complaint is presented in **Table 6-1** below.

Table 6-1 Summary of Environmental Complaints

Reporting Month	Environmental Complaint Statistics		
	Frequency	Cumulative	Complaint Nature
May 2012 to May 2013	0	0	NA

6.02 No summons and prosecution was received during the Reporting Period. Summary of summon and prosecution is presented in **Table 6-2** and **Table 6-3** below.

Table 6-2 Summary of Environmental Summons

Reporting Month	Environmental Summons Statistics		
	Frequency	Cumulative	Nature
May 2012 to May 2013	0	0	NA

Table 6-3 Summary of Environmental Prosecution

Reporting Month	Environmental Prosecution Statistics		
	Frequency	Cumulative	Nature
May 2012 to May 2013	0	0	NA

7 IMPACT FORECAST

KEY ENVIRONMENTAL ISSUES

7.01 Key environmental issues to be considered in the up-coming month are summarized in **Table 7-1** below:

Table 7-1 Key Environmental Issues for the Up-Coming Month

Item	Environmental Issue	Description
(a)	Air Quality	Construction activities under the Contract may have the potential of generating adverse construction dust impacts during dusty construction activities under dry and windy conditions.
(b)	Water Quality	Surface runoff during heavy storm/rain may pollute the surrounding water bodies with suspended solids or turbidity, and concrete washing may change the alkalinity or acidity or pH value of the water bodies;
(c)	Chemical Waste	Potential adverse water quality impacts and soil contamination may be generated from chemicals used or chemical waste generated during construction of the Contract, e.g., organic solvents, cleaning solutions, waste batteries, oil & grease spillage or leakage from construction equipment and the associated oil containers within site areas;
(d)	Construction Noise	Construction noise impacts may be caused by noisy construction activities;

ENVIRONMENTAL MITIGATION MEASURES FOR THE COMING MONTH

7.02 Environmental mitigation measures for construction of the Contract have been compiled in **Annex C**. Attention is drawn to implementation of the environmental mitigation measures for construction activities in the up-coming month as summarized in **Table 7-2** below:

Table 7-2 Environmental Mitigation Measures for the Up-Coming Month

Item	Environmental Issue	Description
(a)	Air Quality	Dust suppression measures, in particular proper watering during dusty construction activities under dry and dusty conditions, should be fully implemented;
(b)	Water Quality	Sedimentation or silt removal facilities of adequate capacity should be used, for proper treatment of any site effluent generated from stockpiles of construction materials/waste or dusty haul roads or excavated surfaces within the site during storm rain, prior to discharge to nearby water bodies in order to remove suspended solids or turbidity;
(c)	Chemical Waste	Proper handling and storage of chemical wastes should be maintained;
(d)	Construction Noise	Implementation of the construction noise mitigation measures during noisy construction works
(e)	Other	Follow-up actions for any defects identified during regular site inspection should be promptly taken to rectify the situation.

8 CONCLUSIONS AND RECOMMENDATIONS

CONCLUSIONS

- 8.01 Monitoring results indicated that no exceedances of A/L Levels for air quality, construction noise and water quality during the Reporting Period. Neither NOE nor remedial actions were therefore required during the Reporting Period.
- 8.02 No environmental complaint, notification of summons or successful prosecution were registered during the Reporting Period.
- 8.03 No non-compliance with regulatory requirements was found during the site inspection and environmental audit of the Reporting Period, including the regular joint site inspection by the ER, IEC, ET and Contractor. Defects of minor environmental significance were sometimes observed during the site inspection, they were normally rectified in-situ or within the specified time prior to the next site inspection.
- 8.04 Power supply at MUP-A1 (MUP05) and the associated 24-Hour TSP monitoring has been reinstated during Reporting Period.

RECOMMENDATIONS

- 8.05 The Contractor is reminded to fully comply with all relevant regulatory environmental requirements, including environmental mitigation measures stipulated in the EM&A Manual.
- 8.06 Special attention is drawn to high SS levels due to heavy rain detected during the Reporting Period in order to avoid potential adverse water quality impacts on the environment.
- 8.07 Moreover, attention is drawn to implementation of the construction noise mitigation measures during noisy construction works.

ANNEX A

LOCATION PLAN FOR THE WORKS UNDER EP-277/2007/A

© Copyright by Black & Veatch Asia Hong Kong Limited

NOTES:

1. ALL LEVELS ARE IN METERS ABOVE MEAN SEA LEVEL UNLESS OTHERWISE SPECIFIED.
2. UNLESS OTHERWISE SPECIFIED, ALL CHANNELS ARE TO BE CONSTRUCTED WITH A 1:1 SLOPE.
3. EMBANKMENTS AND CHANNELS ARE TO BE CONSTRUCTED WITH A 1:1 SLOPE UNLESS OTHERWISE SPECIFIED.
4. THE CHANNELS FOR THE DRAINAGE OF THE SITE ARE TO BE CONSTRUCTED WITH A 1:1 SLOPE UNLESS OTHERWISE SPECIFIED.
5. THE EXACT LOCATION FOR THE SUBMISSION OF WALLS, BARRIERS AND GATES TO BE AGREED WITH THE ENGINEER IN CHARGE.
6. FLOOD MARKING SIGN NOTICES TO BE SUBMITTED WITHIN 30 DAYS OF THE DATE OF THE DRAWING.

LEGEND:

- HORIZONAL LIMIT
- SETTING OUT POINT (S.O.P.) FOR CHANNEL
- BEGINNING OF ALIGNMENT
- END OF ALIGNMENT
- CHANNEL WITH CONCRETE LINING
- CHANNEL WITH GRAVEL LINING
- PROPOSED BANKLINE
- PROPOSED FLOOD MARKING SIGN

FOR TENDER PURPOSES ONLY

Description	Quantity	Unit	Remarks
Channel	1.00	m	
Bank	1.00	m	
Structure	1.00	m	
Gate	1.00	m	
Wall	1.00	m	
Other	1.00	m	


Contract No. DC/2011/06

REPRODUCTION OF BOUNDARY, FACTORY, ROAD AND ASSOCIATED SECURITY FACILITIES BETWEEN PING YUEN RIVER AND PAK TU SHAN AND DRAINAGE WORKS IN NORTH DISTRICT

Drawing Title: GENERAL LAYOUT PLAN FOR DRAINAGE CHANNEL MIP05

Scale: 1:500 A1
1:1000 A3

Black & Veatch Asia Hong Kong Limited




SETTING OUT POINTS FOR DRAINAGE CHANNELS

S.O.P. CHANNEL NO.	EASTING	NORTHING
01	875002.15	42745.22
02	875002.15	42745.22
03	875002.15	42745.22
04	875002.15	42745.22
05	875002.15	42745.22
06	875002.15	42745.22
07	875002.15	42745.22
08	875002.15	42745.22
09	875002.15	42745.22
10	875002.15	42745.22
11	875002.15	42745.22
12	875002.15	42745.22
13	875002.15	42745.22
14	875002.15	42745.22
15	875002.15	42745.22
16	875002.15	42745.22
17	875002.15	42745.22
18	875002.15	42745.22
19	875002.15	42745.22
20	875002.15	42745.22
21	875002.15	42745.22
22	875002.15	42745.22
23	875002.15	42745.22
24	875002.15	42745.22
25	875002.15	42745.22
26	875002.15	42745.22
27	875002.15	42745.22
28	875002.15	42745.22
29	875002.15	42745.22
30	875002.15	42745.22
31	875002.15	42745.22
32	875002.15	42745.22
33	875002.15	42745.22
34	875002.15	42745.22
35	875002.15	42745.22
36	875002.15	42745.22
37	875002.15	42745.22
38	875002.15	42745.22
39	875002.15	42745.22
40	875002.15	42745.22
41	875002.15	42745.22
42	875002.15	42745.22
43	875002.15	42745.22
44	875002.15	42745.22
45	875002.15	42745.22
46	875002.15	42745.22
47	875002.15	42745.22
48	875002.15	42745.22
49	875002.15	42745.22
50	875002.15	42745.22

ANNEX B

***ENVIRONMENTAL MANAGEMENT ORGANIZATION
AND COMMUNICATION LINES***



Key
- - - - - Line of Communication

EM&A Organisation Chart

Contact Details of Key Personnel

Organization	Project Role	Name of Key Staff	Tel No.	Fax No.
DSD	Project Proponent / Employer	Mr. Eric Y. M. Cheng	2594-7341	2827-8700
Environ	Independent Environmental Checker	Mr. Roger W. K. Leung	3465-2888	3465-2899
CHCC	Project Manager	Mr. Raymond Yau	2403 1165	2403 1165
SHCC	Site Agent	Mr. Elvin Lam	2640 9286	2640 9286
AUES	Environmental Team Leader	Mr. T. W. Tam	2959-6059	2959-6079
AUES	Senior Environmental Consultant	Mr. Wong Fu Nam	2959-6059	2959-6079
AUES	Environmental Team Supervisor	Mr. Ben Tam	2959-6059	2959-6079

24-Hour Hotline Telephone Number for the Public to Make Enquiries

24-Hour Hotline: 6770 3827
Contact Person: Mr. Mocha Mok

Legends:

DSD (Project Proponent / Engineer) – Drainage Services Department

SHCC (Main Contractor) – Sang Hing Civil Constructors Co., Ltd

Environ (IEC) – Environ Hong Kong Limited

AUES (ET) – Action-United Environmental Services & Consulting

ANNEX C


IMPLEMENTATION SCHEDULE

FOR ENVIRONMENTAL MITIGATION MEASURES

**(REFER TO ANNEX C OF THE
First Monthly EM&A Report for Drainage Works under EP-277/2007/A)**

ANNEX D

3-MONTH ROLLING CONSTRUCTION PROGRAM



ANNEX E

IMPACT MONITORING SCHEDULE

IMPACT MONITORING SCHEDULE FOR THE REPORTING PERIOD

Date		Noise	Air Quality	24-Hr TSP**	Water Quality
Wed	1-May-13				
Thu	2-May-13			*	
Fri	3-May-13				
Sat	4-May-13				
Sun	5-May-13				
Mon	6-May-13				
Tue	7-May-13				
Wed	8-May-13			*	
Thu	9-May-13				
Fri	10-May-13				
Sat	11-May-13				
Sun	12-May-13				
Mon	13-May-13				
Tue	14-May-13			*	
Wed	15-May-13				
Thu	16-May-13				
Fri	17-May-13				
Sat	18-May-13				
Sun	19-May-13				
Mon	20-May-13			*	
Tue	21-May-13				
Wed	22-May-13				
Thu	23-May-13				
Fri	24-May-13				
Sat	25-May-13			*	
Sun	26-May-13				
Mon	27-May-13				
Tue	28-May-13				
Wed	29-May-13				
Thu	30-May-13				
Fri	31-May-13				

	Monitoring Day
	Sunday or Public Holiday

Note: *No 24-Hr TSP was scheduled due to failure of power supply.

**Supplementary monitoring for 24-Hr TSP as the power supply was reinstated on 25 May 2013.

IMPACT MONITORING SCHEDULE FOR THE NEXT MONITORING PERIOD

Date		Noise	Air Quality	24-Hr TSP	Water Quality
Sat	1-Jun-13				
Sun	2-Jun-13				
Mon	3-Jun-13				
Tue	4-Jun-13				
Wed	5-Jun-13				
Thu	6-Jun-13				
Fri	7-Jun-13				
Sat	8-Jun-13				
Sun	9-Jun-13				
Mon	10-Jun-13				
Tue	11-Jun-13				
Wed	12-Jun-13				
Thu	13-Jun-13				
Fri	14-Jun-13				
Sat	15-Jun-13				
Sun	16-Jun-13				
Mon	17-Jun-13				
Tue	18-Jun-13				
Wed	19-Jun-13				
Thu	20-Jun-13				
Fri	21-Jun-13				
Sat	22-Jun-13				
Sun	23-Jun-13				
Mon	24-Jun-13				
Tue	25-Jun-13				
Wed	26-Jun-13				
Thu	27-Jun-13				
Fri	28-Jun-13				
Sat	29-Jun-13				
Sun	30-Jun-13				

	Monitoring Day
	Sunday or Public Holiday

ANNEX F

MONITORING LOCATIONS

LOCATION PLAN FOR ENVIRONMENTAL MONITORING STATIONS

Legend:




MUP-A1 Air Quality Monitoring Location



MUP-N1 Construction Noise Monitoring Location



MUP-W Water Quality Monitoring Location



***ANNEX G
MONITORING EQUIPMENT CALIBRATION CERTIFICATES***

MONITORING EQUIPMENT CALIBRATION CERTIFICATES*

Items	Aspect	Description of Equipment	Date of Calibration	Date of Next Calibration
1	Air	TSP Sampler Calibration Spreadsheet for MUP-A1**	23 May 13	23 July 2013
2		Laser Dust Monitor, Model LD-3B Serial No. 2X6145	15 Nov 12	15 Nov 13
3		AM510 (Serial No. 11008018)	16 Aug 2012	16 Aug 2013
5	Noise	Bruel & Kjaer Integrating Sound Level Meter (Serial No. 2285690)	7 Jan 13	7 Jan 14
6		NL-31 Rion Sound Level Meter (Serial No. 00410221)	8 Mar 13	8 Mar 14
7		Bruel & Kjaer 4231 Acoustical Calibrator EQ081 (Serial number 2326408)	15 Apr 13	15 Apr 14

Note:

- * This Appendix G presents only calibration certificates of new monitoring equipment or those expired and re-calibrated during the Reporting Period (**Renewed Item No. and Calibration dates will be highlighted for ease of checking**). No valid calibration certificates presented in the previous report will be dittoed under environmental consideration.

TSP SAMPLER CALIBRATION CALCULATION SPREADSHEET

Location :	Man Uk Pin Near DD46 Lot 820	Date of Calibration: 23-May-13
Location ID :	MUP-A1	Next Calibration Date: 23-Jul-13
		Technician: Mr. Ben Tam

CONDITIONS

Sea Level Pressure (hPa)	1009	Corrected Pressure (mm Hg)	756.75
Temperature (°C)	26.5	Temperature (K)	300

CALIBRATION ORIFICE

Make->	TISCH	Qstd Slope ->	2.11662
Model->	5025A	Qstd Intercept ->	-0.01714
Calibration Date->	9-Apr-13		

CALIBRATION

Plate No.	H2O (L) (in)	H2O (R) (in)	H2O (in)	Qstd (m3/min)	I (chart)	IC corrected	LINEAR REGRESSION
18	5.4	5.4	10.8	1.554	53	52.62	Slope = 34.2169 Intercept = -0.6414 Corr. coeff. = 0.9987
13	4.7	4.7	9.4	1.450	49	48.65	
10	3.3	3.3	6.6	1.216	42	41.70	
7	2.1	2.1	4.2	0.972	32	31.77	
5	1.1	1.1	2.2	0.706	24	23.83	

Calculations :

$$Q_{std} = 1/m[\sqrt{H_2O(P_a/P_{std})(T_{std}/T_a)} - b]$$


$$IC = I[\sqrt{P_a/P_{std})(T_{std}/T_a)}]$$

Qstd = standard flow rate
 IC = corrected chart responses
 I = actual chart response
 m = calibrator Qstd slope
 b = calibrator Qstd intercept
 Ta = actual temperature during calibration (deg K)
 Pstd = actual pressure during calibration (mm Hg)

For subsequent calculation of sampler flow:

$$1/m((I) [\sqrt{298/T_{av}}(P_{av}/760)] - b)$$

m = sampler slope
 b = sampler intercept
 I = chart response
 Tav = daily average temperature
 Pav = daily average pressure



ANNEX H

EVENT/ ACTION PLAN

Table 2.4
Event/Action Plan for Air Quality

EVENT	ACTION			
	ET Leader	IEC	ER	Contractor
ACTION LEVEL				
1. Exceedance for one sample	<ol style="list-style-type: none"> Identify source Inform IEC, ER and Contractor Repeat measurement to confirm findings Increase monitoring frequency to daily 	<ol style="list-style-type: none"> Check monitoring data submitted by ET Leader Check Contractor's working method 	<ol style="list-style-type: none"> Notify Contractor 	<ol style="list-style-type: none"> Rectify any unacceptable practice Amend working methods if appropriate
2. Exceedance for two or more consecutive samples	<ol style="list-style-type: none"> Identify source Inform IEC, ER and Contractor Repeat measurement to confirm findings Increase monitoring frequency to daily Discuss with IEC, Contractor and ER on remedial actions required If exceedance continue, arrange meeting with IEC, ER and Contractor If exceedance stops, cease additional monitoring 	<ol style="list-style-type: none"> Checking monitoring data submitted by ET Leader. Check Contractor's working method Discuss with ET Leader and Contractor on possible remedial measures Advise the ER on the effectiveness of the proposed remedial measures Supervise implementation of remedial measures 	<ol style="list-style-type: none"> Confirm receipt of notification of failure in writing Notify Contractor Ensure remedial measures properly implemented 	<ol style="list-style-type: none"> Submit proposals for remedial actions to IEC and ER within 3 working days of notification Implement the agreed proposals Amend proposal if appropriate
LIMIT LEVEL				
1. Exceedance for one sample	<ol style="list-style-type: none"> Identify source Inform IEC, ER, EPD and Contractor Repeat measurement to confirm findings Increase monitoring frequency to daily Assess effectiveness of Contractor's remedial actions and kept IEC, EPD and ER informed of the results 	<ol style="list-style-type: none"> Check monitoring data submitted by ET Leader Check Contractor's working method Discuss with ET Leader and Contractor on possible remedial measures Advise the ER on the effectiveness of the proposed remedial measures Audit implementation of remedial measures 	<ol style="list-style-type: none"> Confirm receipt of notification of failure in writing Notify Contractor Ensure remedial measures properly implemented 	<ol style="list-style-type: none"> Take immediate action to avoid for the exceedance Submit proposals for remedial actions to IEC and ER within 3 working days of notification Implement the agreed proposals Amend proposal if appropriate
2. Exceedance for two or more consecutive samples	<ol style="list-style-type: none"> Notify IEC, ER, Contractor and EPD Identify source Repeat measurement to confirm findings Increase monitoring frequency to daily Carry out analysis of Contractor's working procedures to determine possible mitigation to be implemented Arrange meeting with IEC, Contractor and ER to discuss the remedial actions to be taken Assess effectiveness of Contractor's remedial actions and keep IEC, EPD and ER informed of the results If exceedance stops, cease additional monitoring 	<ol style="list-style-type: none"> Discuss amongst ER, ET leader and Contractor on the potential remedial actions Review Contractor's remedial actions whenever necessary to assure their effectiveness and advise the ER accordingly Audit the implementation of remedial measures 	<ol style="list-style-type: none"> Confirm receipt of notification of failure in writing Notify Contractor In consultation with IEC, agree with the Contractor on the remedial measures to be implemented Ensure remedial measures properly implemented If exceedance continues, consider what portion of the work is responsible and instruct the Contractor to stop that portion of work until the exceedance is abated. 	<ol style="list-style-type: none"> Take immediate action to avoid for the exceedance Submit proposals for remedial actions to IEC and ER within 3 working days of notification Implement the agreed proposals Resubmit proposals if problem still not under control Stop the relevant portion of works as determined by the ER until the exceedance is abate.

Table 3.3 Event/Action Plan for Construction Noise Monitoring

EVENT	ACTION			
	ET Leader	IEC	ER	Contractor
Action Level	<ol style="list-style-type: none"> 1. Notify IEC, Contractor and ER 2. Carry out investigation and identify source 3. Report the results of investigation to the IEC, Contractor and ER 4. Discuss with the Contractor and formulate remedial measures 5. Increase monitoring frequency 6. Check compliance to Action/Limit Levels after application of mitigation measures 	<ol style="list-style-type: none"> 1. Review the analysed results submitted by the ET Leader 2. Review the proposed remedial measures by the Contractor and advise the ER & ET accordingly 3. Review the implementation of remedial measures 	<ol style="list-style-type: none"> 1. Confirm receipt of notification of complaint in writing 2. Notify Contractor 3. Check monitoring data submitted by the ET 4. Require Contractor to propose remedial measures for the analysed noise problem 5. Ensure remedial measures are properly implemented 	<ol style="list-style-type: none"> 1. Submit noise mitigation proposals to ER and IEC within three working 2. Liaise with the ER to ensure the effectiveness of the agreed mitigation 3. Amend proposal if required 4. Implement noise mitigation proposals
Limit Level	<ol style="list-style-type: none"> 1. Notify IEC, ER, EPD and Contractor 2. Identify Source 3. Repeat measurement to confirm findings 4. Increase monitoring frequency 5. Carry out analysis of Contractor's working procedures to determine possible mitigation to be implemented 6. Inform IEC, ER and EPD the causes & actions taken for the exceedances 7. Assess effectiveness of Contractor's remedial actions and keep IEC, EPD and ER informed of the results 8. If exceedance stops, cease additional monitoring 	<ol style="list-style-type: none"> 1. Check monitoring data submitted by ET 2. Discuss amongst ER, ET Leader and Contractor on the potential remedial actions 3. Review Contractor's remedial actions whenever necessary to assure their effectiveness and advise the ER & ET accordingly 4. Audit the implementation of remedial measures 	<ol style="list-style-type: none"> 1. Confirm receipt of notification of exceedance 2. Notify Contractor 3. Check monitoring data submitted by the ET 4. Require Contractor to propose remedial measures for the analysed noise problem 5. Discuss with ET, IEC and Contractor on proposed remedial actions to be implemented 6. Ensure remedial measures are properly implemented 7. Assess the effectiveness of the remedial actions and keep the Contractor informed 8. If exceedance continues, consider what portion of the work is responsible and instruct the Contractor to stop that portion of work until the exceedance is abated 	<ol style="list-style-type: none"> 1. Take immediate action to avoid further exceedance 2. Submit proposals for remedial actions to ER within 3 working days of notification 3. Liaise with the ER to ensure the effectiveness of the agreed mitigation 4. Amend proposal if required 5. Implement the agreed proposals 6. Resubmit proposals if problem still not under control 7. Stop the relevant portion of works as determined by the ER until the exceedance is abated

Table 4.6 Event and Action Plan for Water Quality

Event	ET Leader	IEC	ER	Contractor
Action Level being exceeded by one sampling day	<ol style="list-style-type: none"> Repeat in-site measurement to confirm findings. Identify source(s) of impact. Inform IEC and Contractor. Check monitoring data, all plant, equipment and Contractor's working methods. Discuss mitigation measures with IEC and Contractor. Repeat measurement on next day of exceedance. 	<ol style="list-style-type: none"> Discuss with ET and Contractor on the mitigation measures. Review proposals on mitigation measures submitted by Contractor and advise the ER accordingly. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> Discuss with IEC on the proposed mitigation measures. Make agreement on the mitigation measures to be implemented. Assess effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> Inform the ER and confirm notification of the non-compliance in writing. Rectify unacceptable practice. Check all plant and equipment. Consider changes of working methods. Discuss with ET and IEC and propose mitigation measures to IEC and ER. Implement the agreed mitigation measures.
Action Level being exceeded by more than one consecutive sampling days	<ol style="list-style-type: none"> Repeat in-situ measurement to confirm findings; Identify source(s) of impact. Inform IEC and Contractor. Check monitoring data, all plant, equipment and Contractor's working methods. Discuss mitigation measures with IEC and Contractor. Ensure mitigation measures are implemented. Prepare to increase the monitoring frequency to daily. Repeat measurement on next day of exceedance. 	<ol style="list-style-type: none"> Discuss with ET and Contractor on the mitigation measures. Review proposals on mitigation measures submitted by Contractor and advise the ER accordingly. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> Discuss with IEC on the proposed mitigation measures. Make agreement on the mitigation measures to be implemented. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> Inform the ER and confirm notification of the non-compliance in writing. Rectify unacceptable practice. Check all plant and equipment. Consider changes of working methods. Discuss with ET and IEC and propose mitigation measures to IEC and ER within 3 working days. Implement the agreed mitigation measures.
Limit Level being exceeded by one sampling day	<ol style="list-style-type: none"> Repeat in-situ measurement to confirm findings. Identify source(s) of impact. Inform IEC, contractor and EPD. Check monitoring data, all plant, equipment and Contractor's working methods. Discuss mitigation measures with IEC, ER and Contractor. Ensure mitigation measures are implemented; Increase the monitoring frequency to daily until no exceedance of Limit Level. 	<ol style="list-style-type: none"> Discuss with ET and Contractor on the mitigation measures. Review proposals on mitigation measures submitted by Contractor and advise the ER accordingly. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> Discuss with IEC, ET and Contractor on the proposed mitigation measures. Request Contract to critically review the working methods. Make agreement on the mitigation measures to be implemented. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> Inform the ER and confirm notification of the non-compliance in writing. Rectify unacceptable practice. Check all plant and equipment. Consider changes of working methods. Discuss with ET, IEC and ER and propose mitigation measures to IEC and ER within 3 working days. Implement the agreed mitigation measures.

Event	ET Leader	IEC	ER	Contractor
Limit Level being exceeded by more than one consecutive sampling days	<ol style="list-style-type: none"> 1. Repeat in-situ measurement to confirm findings. 2. Identify source(s) of impact. 3. Inform IEC, contractor and EPD. 4. Check monitoring data, all plant, equipment and Contractor's working methods. 5. Discuss mitigation measures with IEC, ER and Contractor. 6. Ensure mitigation measures are implemented. 7. Increase the monitoring frequency to daily until no exceedance of Limit Level for two consecutive days. 	<ol style="list-style-type: none"> 1. Discuss with ET and Contractor on the mitigation measures. 2. Review proposals on mitigation measures submitted by Contractor and advise the ER accordingly. 3. Assess the effectiveness of the implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Discuss with IEC, ET and Contractor on the proposed mitigation measures. 2. Request Contractor to critically review the working methods. 3. Make agreement on the mitigation measures to be implemented. 4. Assess the effectiveness of the implemented mitigation measures. 5. Consider and instruct, if necessary, the Contractor to slow down or to stop all or part of the work until no exceedance of Limit Level. 	<ol style="list-style-type: none"> 1. Inform the ER and confirm notification of the non-compliance in writing. 2. Rectify unacceptable practice. 3. Check all plant and equipment. 4. Consider changes of working methods. 5. Discuss with ET, IEC and ER and propose mitigation measures to IEC and ER within 3 working days. 6. Implement the agreed mitigation measures. 7. As directed by the ER, to slow down or to stop all or part of the work or construction activities.

ANNEX I

24-HR TSP DATA AND

GRAPHICAL PLOTS OF ENVIRONMENTAL MONITORING RESULTS

A) AIR QUALITY

B) CONSTRUCTION NOISE


C) WATER QUALITY


24-Hr TSP DATA

DATE	SAMPLE NUMBER	ELAPSED TIME			CHART READING			AVG TEMP (°C)	STANDARD			FILTER WEIGHT (g)		WEIGHT DUST COLLECTED (g)	24-hr TSP in air (µg/m³)
		INITIAL	FINAL	(min)	MIN	MAX	AVG		AVG PRESS (hPa)	FLOW RATE (m3/min)	AIR VOLUME (std m3)	INITIAL	FINAL		
1-May-13 to 27-May-13	No data during 1 – 27 May 2013 due to power failure														
28-May-13	25102	4606.88	4630.88	1440.00	34	38	36	29.2	1008.9	1.0612	1528.17	2.8268	2.9729	0.1461	95



A) AIR QUALITY

24-Hr TSP






B) CONSTRUCTION NOISE



C) WATER QUALITY MONITORING RESULTS AT MUP-Wx1 AND Wx2



ANNEX J

METEOROLOGICAL DATA

Meteorological Data from HKO for the Reporting Period

Date		Weather	*Total Rainfall (mm)	Ta Kwu Ling			
				Mean Air Temp. (°C)	Wind Speed (km/h)	Mean Relative Humidity (%)	Wind Direction
1-May-13	Wed	Cloudy, rain, fresh easterly winds, strong offshore.	1.2	22.6	16.3	73	E/SE
2-May-13	Thu	Cloudy, rain, fresh easterly winds, strong offshore.	0.9	18.8	16.1	63	E/SE
3-May-13	Fri	Cloudy, rain, Moderate to fresh east to northeasterly winds.	33.8	20.1	9.5	79.7	E/SE
4-May-13	Sat	Cloudy, rain, Moderate to fresh east to northeasterly winds.	Trace	20.7	6.6	83	E/SE
5-May-13	Sun	Cloudy, mist, sunny intervals, moderate easterly winds.	Trace	22.1	11	82.5	E
6-May-13	Mon	Cloudy, mist, sunny intervals, moderate easterly winds.	Trace	23.2	11.2	88	E
7-May-13	Tue	Cloudy, mist, sunny intervals, moderate easterly winds.	Trace	25.1	13.5	81.5	E
8-May-13	Wed	Cloudy, rain, fog, moderate to fresh easterly winds.	29.7	23.3	16.3	88.5	E
9-May-13	Thu	Cloudy, a few showers, mist, showers, moderate southerly winds.	31.3	26.1	12.9	84.7	E
10-May-13	Fri	Cloudy, rain, fog, moderate to fresh easterly winds.	23.4	26.1	9.9	85	E/SE
11-May-13	Sat	Cloudy, a few showers, mist, showers, moderate southerly winds.	0.1	Maintenance	7.5	84	W/SW
12-May-13	Sun	Cloudy, sunny intervals, moderate east to southeasterly winds.	1.4	24.7	12	89.7	E
13-May-13	Mon	Cloudy, sunny intervals, isolated showers, mist, moderate east to southeasterly winds.	0.2	26.7	12	83.5	E
14-May-13	Tue	Cloudy, rain, squally thunderstorms, moderate south to southwesterly winds, fresh offshore.	Trace	26.3	14.8	87.5	E
15-May-13	Wed	Cloudy, sunny intervals, isolated showers, mist, moderate east to southeasterly winds.	Trace	28.8	14	80.5	S/SW
16-May-13	Thu	Cloudy, rain, squally thunderstorms, moderate south to southwesterly winds, fresh offshore.	5.4	27.2	12.7	84.7	S/SW
17-May-13	Fri	Cloudy, rain, fog, moderate to fresh easterly winds.	13.9	26.2	8.2	94	S/SW
18-May-13	Sat	Cloudy, rain, squally thunderstorms, moderate south to southwesterly winds, fresh offshore.	21	29	16.7	88	S/SW
19-May-13	Sun	Cloudy, rain, fog, moderate to fresh easterly winds.	0.1	29.1	13.2	77.5	S/SW
20-May-13	Mon	Cloudy, rain, fog, moderate to fresh easterly winds.	26	28	15.4	79.5	S/SW
21-May-13	Tue	Cloudy, rain, squally thunderstorms, moderate south to southwesterly winds, fresh offshore.	26.3	26.2	15	89	E
22-May-13	Wed	Cloudy, rain, squally thunderstorms, moderate south to southwesterly winds, fresh offshore.	230.8	24.8	11.7	93.5	E/SE
23-May-13	Thu	Cloudy, rain, squally thunderstorms, moderate south to southwesterly winds, fresh offshore.	Trace	26.7	12.5	84.5	E
24-May-13	Fri	Cloudy, rain, squally thunderstorms, moderate south to southwesterly winds, fresh offshore.	Trace	27.8	12.5	79.5	E
25-May-13	Sat	Fine, very hot, light to moderate southerly winds.	52	26.1	4.7	96	E/SE
26-May-13	Sun	Hot, sunny intervals. moderate south to southeasterly winds.	11.3	27.6	12	84.5	S/SW
27-May-13	Mon	Fine, very hot, light to moderate southerly winds.	0.1	28.8	15.8	80	SE
28-May-13	Tue	Fine, very hot, light to moderate southerly winds.	Trace	28.9	10.6	80	S/SW
29-May-13	Wed	Fine, very hot, light to moderate southerly winds.	0.4	28.8	9	82.5	E/SE
30-May-13	Thu	Fine, very hot, light to moderate southerly winds.	0	28.6	11	78.2	E/SE
31-May-13	Fri	Fine, very hot, light to moderate southerly winds.	0	28.7	8.7	72.7	SW

***Note:**

- means no rainfall

***** unavailable

missing (less than 24 hourly observations a day)

Rainfall measured in increment of 0.5 mm. Amount of < 0.5 mm cannot be detected

ANNEX K

**WASTE FLOW TABLE AND
SUMMARY OF WORKS PROCESSES OR ACTIVITIES
REQUIRING TIMBER FOR TEMPORARY WORKS**

Summary Table for Work Processes or Activities Requiring Timber for Temporary Works

Contract No.: DC/2011/06

Contract Title: *Reprovisioning of Boundary Patrol Road and Associated Security Facilities between Ping Yuen River and Pak Fu Shan and Drainage Works in North District*

Report Period: May-13

Item No	Description of Works Process or Activity [see note (a) below]	Justifications for Using Timber in Temporary Construction Works	Est. Quantities of Timber Used (m ³)	Actual Quantities used (m ³)	Remarks
1	Transition formwork & falsework (Portion A,B,E)	Temporery formwork & falsework design	10	9	
2	Transition formwork & falsework (Portion A,B,C)	Temporery formwork & falsework design	25	18	
3	Transition formwork & falsework (Portion A,B,C,E)	Temporery formwork & falsework design	52	40	
4	Transition formwork & falsework (Portion A,B,C,E)	Temporery formwork & falsework design	77	72	
5	Transition formwork & falsework (Portion A,B,C,E)	Temporery formwork & falsework design	102	86	
6	Transition formwork & falsework (Portion A,B,C,E)	Temporery formwork & falsework design	115	103	
7	Transition formwork & falsework (Portion A,B,C,E)	Temporery formwork & falsework design	121	112	
8	Transition formwork & falsework (Portion A,B,C,E)	Temporery formwork & falsework design	145	139	

Notes

(a) The Contractor shall list out all the work items requiring timber for use in temporary construction works. Several minor work items may be grouped into one for ease of updating.

(b) The summary table shall be submitted to the Engineer's Representative monthly together with the Waste Flow Table for review and monitoring