

Civil Engineering and Development Department

**Agreement No. CE 59/2015 (EP)
Environmental Team for
Tseung Kwan O – Lam Tin Tunnel
Design and Construction**

**Monthly Environmental Monitoring and
Audit Report for April 2017**

(version 2.0)

Approved By



(Dr. Priscilla Choy,
Environmental Team Leader)

REMARKS:

The information supplied and contained within this report is, to the best of our knowledge, correct at the time of printing.

CINOTECH accepts no responsibility for changes made to this report by third parties.

CINOTECH CONSULTANTS LTD

Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong
Tel: (852) 2151 2083 Fax: (852) 3107 1388
Email: info@cinotech.com.hk

TABLE OF CONTENTS

EXECUTIVE SUMMARY	1
Introduction.....	1
Environmental Monitoring Works.....	1
Key Information in the Reporting Month.....	3
Future Key Issues.....	3
1. INTRODUCTION	4
Purpose of the Report.....	4
Structure of the Report.....	4
2. PROJECT INFORMATION	6
Background.....	6
Project Organizations.....	6
Construction Activities undertaken during the Reporting Month.....	7
Status of Environmental Licences, Notification and Permits.....	8
Summary of EM&A Requirements.....	9
3. AIR QUALITY	10
Monitoring Requirements.....	10
Monitoring Locations.....	10
Monitoring Equipment.....	10
Monitoring Parameters and Frequency.....	11
Monitoring Methodology.....	11
Results and Observations.....	14
4. NOISE	15
Monitoring Requirements.....	15
Monitoring Locations.....	15
Monitoring Equipments.....	15
Monitoring Methodology and QA/QC Procedure.....	16
Results and Observations.....	17
Updated Construction Noise Assessment.....	17
5. WATER QUALITY	18
Monitoring Requirements.....	18
Monitoring Locations.....	18
Monitoring Equipments.....	19
Monitoring Parameters and Frequency.....	21
Monitoring Methodology.....	21
Laboratory Analytical Methods.....	22
QA/QC Requirements.....	23
Decontamination Procedures.....	23
Sampling Management and Supervision.....	23
Results and Observations.....	23
6. ECOLOGY	25
Post-Translocation Coral Monitoring.....	25
Event and Action Plan.....	25
Results and Observations.....	25
7. MONITORING ON CULTURAL HERITAGE	26

Monitoring Requirement	26
Monitoring Locations	26
Monitoring Equipment	26
Monitoring Methodology	27
Alert, Alarm and Action Levels	27
Results	27
Mitigation Measures for Cultural Heritage	27
8. LANDSCAPE AND VISUAL IMPACT REQUIREMENTS	29
9. LANDFILL GAS MONITORING	30
Monitoring Requirement	30
Monitoring Parameters and Frequency	30
Monitoring Locations	30
Monitoring Equipment	30
Results	31
10. ENVIRONMENTAL AUDIT	32
Site Audits	32
Implementation Status of Environmental Mitigation Measures	32
11. WASTE MANAGEMENT	35
12. ENVIRONMENTAL NON-CONFORMANCE	36
Summary of Exceedances	36
Summary of Environmental Non-Compliance	36
Summary of Environmental Complaint	36
Summary of Environmental Summon and Successful Prosecution	36
13. FUTURE KEY ISSUES	37
Key Issues for the Coming Month	37
Monitoring Schedule for the Next Month	38
14. CONCLUSIONS AND RECOMMENDATIONS	39
Conclusions	39
Recommendations	40

LIST OF TABLES

Table I	Non-compliance Recorded for the Project in the Reporting Month
Table II	Summary Table for Key Information in the Reporting Month
Table 2.1	Key Project Contacts
Table 2.2	Summary Table for Major Site Activities in the Reporting Month
Table 2.3	Construction Programme Showing the Inter-Relationship with Environmental Protection/Mitigation Measures
Table 2.4	Summary of the Status of Environmental Licences, Notification and Permits
Table 3.1	Locations for Air Quality Monitoring
Table 3.2	Air Quality Monitoring Equipment
Table 3.3	Impact Dust Monitoring Parameters, Frequency and Duration
Table 3.4	Major Dust Source during Air Quality Monitoring
Table 4.1	Noise Monitoring Stations
Table 4.2	Noise Monitoring Equipment
Table 4.3	Noise Monitoring Parameters, Frequency and Duration

Table 4.4	Major Noise Source during Noise Monitoring
Table 4.5	Baseline Noise Level and Noise Limit Level for Monitoring Stations
Table 5.1	Groundwater Quality Monitoring Stations
Table 5.2	Marine Water Quality Monitoring Stations
Table 5.3	Water Quality Monitoring Equipment
Table 5.4	Water Quality Monitoring Parameters and Frequency
Table 5.5	Methods for Laboratory Analysis for Water Samples
Table 5.6	Summary of Groundwater Quality Monitoring Results
Table 7.1	Vibration Monitoring Equipment
Table 7.2	AAA Levels for Monitoring for Cultural Heritage
Table 7.3	Vibration Monitoring Results
Table 9.1	Landfill Gas Monitoring Equipment
Table 10.1	Observations and Recommendations of Site Audit
Table 13.1	Summary Table for Site Activities in the next Reporting Period

LIST OF FIGURES

Figure 1	Site Layout Plan
Figure 2	Locations of Air Quality Monitoring Stations
Figure 3	Locations of Construction Noise Monitoring Stations
Figure 4	Locations of Groundwater Quality Monitoring Stations
Figure 5	Locations of Marine Water Quality Monitoring Stations
Figure 6	Locations of Landfill Gas Monitoring
Figure 7	Location of Post-translocation Coral Monitoring
Figure 8	Location of Monitoring for Cultural Heritage

LIST OF APPENDICES

Appendix A	Action and Limit Levels
Appendix B	Copies of Calibration Certificates
Appendix C	Weather Information
Appendix D	Environmental Monitoring Schedules
Appendix E	1-hour TSP Monitoring Results and Graphical Presentations
Appendix F	24-hour TSP Monitoring Results and Graphical Presentations
Appendix G	Noise Monitoring Results and Graphical Presentations
Appendix H	Groundwater Quality Monitoring Results and Graphical Presentations
Appendix I	Marine Water Quality Monitoring Results and Graphical Presentations
Appendix J	Quality Control Reports for Laboratory Analysis
Appendix K	Summary of Exceedance
Appendix L	Site Audit Summary
Appendix M	Event and Action Plans
Appendix N	Implementation Schedule And Recommended Mitigation Measures
Appendix O	Summaries of Environmental Complaint, Warning, Summon and Notification of Successful Prosecution
Appendix P	Waste Generation in the Reporting Month
Appendix Q	Tentative Construction Programme
Appendix R	Record of Landfill Gas Monitoring by Contractor
Appendix S	Updated Construction Noise Assessment
Appendix T	Photo record of the Post-Translocation Coral Monitoring Survey

EXECUTIVE SUMMARY

Introduction

1. This is the 6th Environmental Monitoring and Audit (EM&A) Report prepared by Cinotech Consultants Limited for the “Agreement No. CE 59/2015 (EP) Environmental Team for Tseung Kwan O – Lam Tin Tunnel – Design and Construction” (hereinafter called “the Project”). This report documents the findings of EM&A Works conducted in April 2017.
2. During the reporting month, the following works contracts were undertaken:
 - Contract No. NE/2015/01 – Tseung Kwan O – Lam Tin Tunnel – Main Tunnel and Associated Works; and
 - Contract No. NE/2015/02 – Tseung Kwan O – Lam Tin Tunnel – Road P2 and Associated Works.

Environmental Monitoring Works

3. Environmental monitoring for the Project was performed in accordance with the EM&A Manual and the monitoring results were checked and reviewed. Site Inspections/Audits were conducted once per week. The implementation of the environmental mitigation measures, Event Action Plans and environmental complaint handling procedures were also checked.
4. Summary of the non-compliance in the reporting month for the Project is tabulated in **Table I**.

Table I Non-compliance Record for the Project in the Reporting Month

Environmental Monitoring	No. of Exceedance		No. of Exceedance due to Construction Activities of this Project		Action Taken
	Action Level	Limit Level	Action Level	Limit Level	
Air Quality	0	0	0	0	N/A
Noise	0	0	0	0	N/A
Groundwater Quality	1	7	0	0	N/A (Refer to Part 8, Executive Summary)
Marine Water Quality	0	0	0	0	N/A
Groundwater Level Monitoring (Piezometer Monitoring)	N/A	N/A	N/A	N/A	N/A
Ecological	N/A	N/A	N/A	N/A	N/A
Cultural Heritage	0	0	0	0	N/A
Landfill Gas	0	0	0	0	N/A

Air Quality Monitoring

5. All 1-hour TSP monitoring was conducted as scheduled in the reporting month. No Action/Limit Level exceedance was recorded.
6. All 24-hour TSP monitoring was conducted as scheduled in the reporting month. No

Action/Limit Level exceedance was recorded.

Construction Noise Monitoring

7. All noise monitoring was conducted as scheduled in the reporting month. No Action/Limit Level exceedance was recorded.

Water Quality Monitoring

8. Groundwater monitoring was conducted as scheduled in the reporting month. One Action Level Exceedance and Seven Limit Level exceedance were recorded. The exceedances are considered to be non-Project related.
9. All marine water monitoring was conducted as scheduled in the reporting month. No Action/Limit Level exceedance was recorded.
10. Construction phase daily piezometer monitoring was not carried out in this reporting period as there is no tunnel construction activities are carried out within +/- 50m of the piezometer gate in plan.

Ecological Monitoring

11. Post-translocation coral monitoring survey shall be conducted once every 3 months for a period of 12 months after completion of coral translocation. The 2nd post-translocation coral monitoring survey is scheduled in May 2017.

Monitoring on Cultural Heritage

12. Monitoring of vibration impacts at Cha Kwo Ling Tin Hau Temple commenced on 8 April 2017. No Alert Alarm and Action (AAA) Level exceedance was recorded in the reporting month.

Landscape and Visual Monitoring and Audit

13. The implementation of landscape and visual mitigation measures was checked during the environmental site inspections. Recommended follow-up actions have been discharged by the Contractor. Details of the audit findings and implementation status are presented in Section 10.

Landfill Gas Monitoring

14. Monitoring of landfill gases commenced in December 2016 and were carried out by the Contractor at excavation location, Portion III. No Limit Level exceedance was recorded.

Environmental Site Inspection

15. Joint weekly site inspections were conducted by representatives of the Contractor, Engineer and Environmental Team. The representative of the IEC joined the site inspection on 26 April 2017. Details of the audit findings and implementation status are presented in Section 10.

Waste Management

16. Wastes generated from this Project include inert construction and demolition (C&D) materials, non-inert C&D materials and marine sediments. Details of waste management data is presented in Section 11 and **Appendix P**.

Key Information in the Reporting Month

17. Summary of key information in the reporting month is tabulated in **Table II**.

Table II Summary Table for Key Information in the Reporting Month

Event	Event Details		Action Taken	Status	Remark
	Number	Nature			
Complaint received / Complaint referred by EPD (March 2017)	2	Construction dust nuisance / waste water due to wheel washing	Under investigation	On-going	Details refer to App O
Complaint received / Complaint referred by EPD (April 2017)	1	Construction dust nuisance	Under investigation	On-going	Details refer to App O
Reporting Changes	0	---	N/A	N/A	---
Notifications of any summons & prosecutions received	0	---	N/A	N/A	---

Future Key Issues

18. The future key environmental issues in the coming month include:

- Watering for dust generation from haul road, stockpiles of dusty materials, exposed site area, excavation works and rock breaking activities;
- Noisy construction activity such as rock-breaking activities and piling works;
- Runoff from exposed slope or site area;
- Wastewater and runoff discharge from site;
- Accumulation of silt, mud and sand along U-channels and sedimentation tanks;
- Set up and implementation of temporary drainage system for the surface runoff;
- Storage of chemicals/fuel and chemical waste/waste oil on site;
- Accumulation and storage of general and construction waste on site; and
- Marine water quality impact and indirect impact to coral communities due to marine construction for TKO-LTT reclamation.

1. INTRODUCTION

- 1.1 Cinotech Consultants Limited (Cinotech) was commissioned by Civil Engineering and Development Department (CEDD) as the Environmental Team (ET) to undertake environmental monitoring and auditing services for the Works Contracts involved in the implementation of Tseung Kwan O – Lam Tin Tunnel (TKO-LTT) project to ensure that the environmental performance of the Works Contracts comply with the requirements specified in the Environmental Permit (EP), Environmental Monitoring & Audit (EM&A) Manual, Environmental Impact Assessment (EIA) Report of the TKO-LTT project and other relevant statutory requirements. This is the 6th Monthly EM&A report summarizing the EM&A works for the Project in April 2017.

Purpose of the Report

- 1.2 This is the 6th Monthly EM&A Report which summarises the impact monitoring results and audit findings for the EM&A programme during the reporting period in April 2017. The commencement date of construction of this Project is 7 November 2016.

Structure of the Report

- 1.3 The structure of the report is as follows:

Section 1: **Introduction** – purpose and structure of the report.

Section 2: **Contract Information** – summarises background and scope of the Contract, site description, project organization and contact details, construction programme, the construction works undertaken and the status of Environmental Permits/Licenses during the reporting month.

Section 3: **Air Quality Monitoring** – summarises the monitoring parameters, monitoring programmes, monitoring methodologies, monitoring frequency, monitoring locations, Action and Limit Levels, monitoring results and Event / Action Plans.

Section 4: **Noise Monitoring** – summarises the monitoring parameters, monitoring programmes, monitoring methodologies, monitoring frequency, monitoring locations, Action and Limit Levels, monitoring results and Event / Action Plans.

Section 5: **Water Quality Monitoring** – summarises the monitoring parameters, monitoring programmes, monitoring methodologies, monitoring frequency, monitoring locations, Action and Limit Levels, monitoring results and Event / Action Plans.

Section 6: **Ecological Monitoring** – summarises the monitoring parameters, monitoring programmes, monitoring methodologies, monitoring frequency, monitoring locations and Action and Limit Levels, monitoring results and Event / Action Plans.

Section 7: **Monitoring on Cultural Heritage** – summarises the monitoring parameters, monitoring programmes, monitoring methodologies, monitoring frequency, monitoring locations and monitoring results.

Section 8: **Landscape and Visual Monitoring Requirements** – summarises the requirements of landscape and visual monitoring

Section 9: **Landfill Gas Monitoring** – summarises the monitoring parameters, monitoring programmes, monitoring methodologies, monitoring frequency, monitoring locations, monitoring results and Limit Levels and Action Plan

Section 10: **Environmental Site Inspection** – summarises the audit findings of the weekly site inspections undertaken within the reporting month.

Section 11: **Waste Management** – summarises the waste management data in the reporting month.

Section 12: **Environmental Non-conformance** – summarises any monitoring exceedance, environmental complaints, environmental summons and successful prosecutions within the reporting month.

Section 13: **Future Key Issues** – summarises the impact forecast and monitoring schedule for the next three months.

Section 14: **Conclusions and Recommendation**

2. PROJECT INFORMATION

Background

- 2.1 In 2002, Civil Engineering and Development Department (CEDD) commissioned an integrated planning and engineering study under Agreement No. CE 87/2001 (CE) “Further Development of Tseung Kwan O – Feasibility Study” (the “TKO Study”) to formulate a comprehensive plan for further development of TKO New Town. It recommended to further develop TKO to house a total population of 450,000 besides the district’s continuous commercial and industrial developments.
- 2.2 At present, the Tseung Kwan O Tunnel is the main connection between Tseung Kwan O (TKO) and other areas in the territory. To cope with the anticipated transport need, the TKO Study recommended the provision of Tseung Kwan O – Lam Tin Tunnel (TKO-LTT) (hereinafter referred to as “the Project”) and Cross Bay Link (CBL) to meet the long-term traffic demand between TKO and the external areas. The site layout plan for the Project is shown in **Figure 1**.
- 2.3 The Environmental Impact Assessment (EIA) Report for the TKO-LTT project was approved under the Environmental Impact Assessment Ordinance (EIAO) in July 2013. The corresponding Environmental Permit (EP) was issued in August 2013 (EP no.: EP-458/2013). Variations to the EP was applied and the latest EP (EP no.: EP-458/2013/C) was issued by the Director of Environmental Protection (DEP) in January 2017.

Project Organizations

- 2.4 Different parties with different levels of involvement in the project organization include:
- Project Proponent – Civil Engineering and Development Department (CEDD)
 - The Engineer and the Engineer’s Representative (ER) – AECOM
 - Environmental Team (ET) – Cinotech Consultants Limited (Cinotech)
 - Independent Environmental Checker (IEC) – ANewR Consulting Limited (ANewR)
- 2.5 The key contacts of the Project are shown in **Table 2.1**.

Table 2.1 Key Project Contacts

Party	Role	Contact Person	Phone No.	Fax No.
CEDD	Project Proponent	Mr. Chiang Nin Tat, Eric	2301 1384	2739 0076
AECOM	Engineer’s Representative	Mr. KY Chan	3922 9000	2759 1698
Cinotech	Environmental Team	Dr. Priscilla Choy	2151 2089	3107 1388
		Ms. Ivy Tam	2151 2090	
AnewR	Independent Environmental Checker	Mr. Adi Lee	2618 2836	3007 8648

Construction Activities undertaken during the Reporting Month

2.6 The major site activities undertaken in the reporting month included:

Table 2.2 Summary Table for Major Site Activities in the Reporting Month

Contract No.	Project Title	Site Activities (April 2017)	
NE/2015/01	Tseung Kwan O – Lam Tin Tunnel – Main Tunnel and Associated Works	Lam Tin Interchange	1) Excavation for Tunnel Adit 2) Slope Feature no. 11NE-D/C119 (along Lei Yue Mun Road) 3) EHC2 U-Trough 4) Site Formation – Area 1G1, Area 2, Area 3, Area 4 5) Temp Steel Bridge across Cha Kwo Ling Road & Barging Facility 6) Pipe Pile wall – Area 2A 7) Ground Investigation
		Main Tunnel	1) Tunnel Team Mobilisation Works
		TKO Interchange	1) Haul Road Construction, Site Formation and Slope Works 2) Temporary Barging Facilities & Temporary Works 3) Temporary Cut Slope For BMCP
NE/2015/02	Tseung Kwan O – Lam Tin Tunnel – Road P2 and Associated Works	1) Advance Works for Construction of Temporary Cofferdam 2) Installation of silt curtain 3) Construction of Retaining Wall 4) Construction of DSD transformation room 5) Piling and Sheet Piling Works 6) Site Clearance 7) Hoarding Erection	

2.7 The construction programme showing the inter-relationship with environmental protection/mitigation measures are presented in **Table 2.3**.

Table 2.3 Construction Programme Showing the Inter-Relationship with Environmental Protection/Mitigation Measures

Construction Works	Major Environmental Impact	Control Measures
As mentioned in Table 2.2	Noise, dust impact, water quality and waste generation	<ul style="list-style-type: none"> • Sufficient watering of the works site with active dust emitting activities • Properly cover the stockpiles • On-site waste sorting and implementation of trip ticket system • Appropriate desilting/sedimentation devices provided on site for treatment before discharge • Use of quiet plant and well-maintained construction plant • Provide movable noise barrier

Status of Environmental Licences, Notification and Permits

2.8 A summary of the relevant permits, licences, and/or notifications on environmental protection for this Project is presented in **Table 2.4**.

Table 2.4 Summary of the Status of Environmental Licences, Notification and Permits

Contract No.	Permit / License No.	Valid Period		Status
		From	To	
Environmental Permit (EP)				
N/A	EP-458/2013/C	20/1/2017	N/A	Valid
Notification pursuant to Air Pollution Control (Construction Dust) Regulation				
NE/2015/01	EPD Ref no.: 405305	21/07/2016	N/A	Valid
	EPD Ref no.: 405582	28/07/2016	N/A	Valid
NE/2015/02	EPD Ref no.: 406100	12/08/2016	N/A	Valid
Billing Account for Construction Waste Disposal				
NE/2015/01	Account No. 7025431	11/07/2016	N/A	Valid
NE/2015/02	Account No. 7025654	16/08/2016	N/A	Valid
Registration of Chemical Waste Producer				
NE/2015/01	Waste Producer No. 5218-290-L2881-02	22/08/2016	N/A	Valid
	Waste Producer No. 5213-833-L2532-03	22/08/2016	N/A	Valid
NE/2015/02	Waste Producer No. 5213-838-C4094-01	19/08/2016	N/A	Valid
Effluent Discharge License under Water Pollution Control Ordinance				
NE/2015/01	WT00025806-2016	22/11/2016	30/11/2021	Valid
	WT00026212-2016	25/11/2016	30/11/2021	Valid
	WT00027354-2017	22/03/2017	31/03/2022	Valid
	WT00027405-2017	22/03/2017	31/03/2022	Valid
NE/2015/02	WT00026386-2016	15/12/2016	31/12/2021	Valid
Construction Noise Permit (CNP)				
NE/2015/01	GW-RE1211-16	24/12/2016	22/06/2017	Valid
	GW-RE0154-17	08/03/2017	05/09/2017	Valid
	GW-RE0164-17	08/03/2017	07/04/2017	Expired on 7 Apr 2017
	GW-RE0191-17	20/03/2017	19/09/2017	Valid
	GW-RE0224-17	26/03/2017	25/06/2017	Valid

Contract No.	Permit / License No.	Valid Period		Status
		From	To	
	GW-RE0267-17	08/04/2017	07/05/2017	Valid
NE/2015/02	GW-RE1141-16	06/12/2016	17/05/2017	Valid
	GW-RE1208-16	23/12/2016	22/06/2017	Valid
	GW-RE0049-17	01/02/2017	31/07/2017	Valid
	GW-RE0097-17	15/02/2017	14/08/2017	Valid
	GW-RE0281-17	13/04/2017	02/10/2017	Valid
Marine Dumping Permit				
NE/2015/02	EP/MD/17-118	1/12/2016	31/05/2017	Valid

Summary of EM&A Requirements

- 2.9 The EM&A programme requires construction noise monitoring, air quality monitoring, water quality monitoring, environmental site audit, etc. The EM&A requirements for each parameter are described in the following sections, including:
- All monitoring parameters;
 - Action and Limit levels for all environmental parameters;
 - Event Action Plans;
 - Environmental mitigation measures, as recommended in the Project EIA Report.
- 2.10 The advice on the implementation status of environmental protection and pollution control/mitigation measures is summarized in Section 10 of this report.
- 2.11 This report presents the monitoring results, observations, locations, equipment, period, methodology and QA/QC procedures of the monitoring parameters of the required environmental monitoring works and audit works for the Project in April 2017.

3. AIR QUALITY

Monitoring Requirements

- 3.1 According to EM&A Manual of the Project, 1-hour and 24-hour TSP monitoring are required to monitor the air quality. For regular impact monitoring, a sampling frequency of at least once in every six days shall be undertaken at all of the monitoring stations for 24-hour TSP monitoring. For 1-hour TSP monitoring, the sampling frequency of at least three times in every six days shall be undertaken when the highest dust impact occurs. **Appendix A** shows the established Action/Limit Levels for the environmental monitoring works.

Monitoring Locations

- 3.2 Six designated monitoring stations were selected for air quality monitoring programme. **Table 3.1** describes the air quality monitoring locations, which are also depicted in **Figure 2**.

Table 3.1 Locations for Air Quality Monitoring

Monitoring Stations	Location	Location of Measurement
AM1	Tin Hau Temple	Ground Level
AM2	Sai Tso Wan Recreation Ground	Ground Level
AM3	Yau Lai Estate Bik Lai House	Rooftop (41/F)
AM4 ⁽¹⁾	Sitting-out Area at Cha Kwo Ling Village	Ground Level
AM4(A) ^{(2) (*)}	Cha Kwo Ling Public Cargo Working Area Administrative Office	Rooftop (3/F)
AM5(A) ^(*)	Tseung Kwan O DSD Desilting Compound	Ground Level
AM6(A) ^(*)	Park Central, L1/F Open Space Area	1/F

Remarks: (1) For 1-hour TSP monitoring; (2) For 24-hour TSP monitoring
(*) Air quality monitoring at designated station AM4(24-hr TSP), AM5 and AM6 was rejected by the premise owners. Therefore, baseline and impact air quality monitoring works were carried out at alternative air quality monitoring stations AM4(A) (24-hr TSP only), AM5(A) and AM6(A) respectively.

Monitoring Equipment

- 3.3 High Volume Samplers (HVS) were used to carry out 24-hour TSP monitoring. Direct reading dust meter were also used to measure 1-hour average TSP levels. The 1-hour sampling was determined periodically by HVS to check the validity and accuracy of the results measured by direct reading method.
- 3.4 Wind data monitoring equipment was set at rooftop (about 41/F) of Yau Lai Estate Bik Lai House for logging wind speed and wind direction such that the wind sensors are clear of obstructions or turbulence caused by building. The wind data monitoring equipment is re-calibrated at least once every six months and the wind directions are divided into 16 sectors of 22.5 degrees each. The location is shown in **Figure 2**.
- 3.5 **Table 3.2** summarizes the equipment to be used in the air quality monitoring. Copies of calibration certificates are attached in **Appendix B**.

Table 3.2 Air Quality Monitoring Equipment

Equipment	Model and Make	Quantity
Calibrator	TISCH Model: TE-5025A	1
1-hour TSP Dust Meter	Sibata Model No.: LD-3 / LD-3B	4
	Met One Instruments Model No.: AEROCET-531	0
	Handheld Particle Counter Hal-HPC300 / Hal-HPC301	7
HVS Sampler	TISCH Model: TE-5170	1
	GMW Model: GS2310	5
Wind Anemometer	Davis Weather Monitor II, Model no. 7440	1

Monitoring Parameters and Frequency

- 3.6 **Table 3.3** summarizes the monitoring parameters, monitoring period and frequencies of air quality monitoring.

Table 3.3 Frequency and Parameters of Air Quality Monitoring

Monitoring Stations	Parameter	Frequency
AM1, AM2, AM3, AM4, AM5(A) and AM6(A)	1-hour TSP	3 times per 6 day
AM1, AM2, AM3, AM4(A), AM5(A) and AM6(A)	24-hour TSP	Once per 6 days

Monitoring Methodology

1-hour TSP Monitoring

Measuring Procedures

- 3.7 The measuring procedures of the 1-hour dust meter are in accordance with the Manufacturer's Instruction Manual as follows:

(Model LD3 / LD3B)

- The 1-hour dust meter is placed at least 1.3 meters above ground.
- Set POWER to "ON" and make sure that the battery level was not flash or in low level.
- Allow the instrument to stand for about 3 minutes and then the cap of the air sampling inlet has been released.
- Push the knob at MEASURE position.
- Set time/mode setting to [BG] by pushing the time setting switch. Then, start the background measurement by pushing the start/stop switch once. It will take 6 sec. to complete the background measurement.
- Push the time setting switch to change the time setting display to [MANUAL] at the bottom left of the liquid crystal display. Finally, push the start/stop switch to stop the measuring after 1 hour sampling.
- Information such as sampling date, time, count value and site condition were recorded during the monitoring period.

(AEROCET-531)

- The 1-hour dust meter is placed at least 1.3 meters above ground.
- Remove the red rubber cap from the AEROCET-531 inlet nozzle.
- Turn on the power switch that is located on the right side of the AEROCET-531.
- On power up the product intro screen is displayed for 3 seconds. The intro screen displays the product name and firmware version.
- Then the main counter screen will be displayed.
- Press the START button. Internal vacuum pump start running. After 1 minute the pump will stop and the 0.5 μ m and 5 μ m channels will show the cumulative counts of particles larger than 0.5 μ m and 5 μ m per cubic foot.
- The AEROCET-531 is now checked out and ready for use.
- To switch off the AEROCET-531 power to stop the measuring after 1 hour sampling.
- Information such as sampling date, time, and display value and site condition were recorded during the monitoring period.

(Equipment: Hal Technology; Model no. Hal-HPC300)

- The 1-hour dust meter is placed at least 1.3 meters above ground.
- Set POWER to “ON” and make sure that the battery level was not flash or in low level.
- Allow the instrument to stand for about 3 minutes and then the cap of the air sampling inlet has been released.
- Push the knob at MEASURE position.
- Set time/mode setting to [BG] by pushing the time setting switch. Then, start the background measurement by pushing the start/stop switch once. It will take 6 sec. to complete the background measurement.
- Push the time setting switch to change the time setting display to [MANUAL] at the bottom left of the liquid crystal display. Finally, push the start/stop switch to stop the measuring after 1 hour sampling.
- Information such as sampling date, time, count value and site condition were recorded during the monitoring period.

Maintenance/Calibration

3.8 The following maintenance/calibration is required for the direct dust meters:

- Check and calibrate the meter by HVS to check the validity and accuracy of the results measured by direct reading method at 2-month intervals throughout all stages of the air quality monitoring.

24-hour TSP MonitoringInstrumentation

3.9 High volume samplers (HVS) (TISCH Model: TE-5170) complete with appropriate sampling inlets were employed for 24-hour TSP monitoring. The sampler is composed of a motor, a filter holder, a flow controller and a sampling inlet and its performance specification complied with that required by USEPA Standard Title 40, Code of Federation Regulations Chapter 1 (Part 50).

3.10 The positioning of the HVS samplers are as follows:

- a horizontal platform with appropriate support to secure the samplers against gusty wind shall be provided;
- no two samplers shall be placed less than 2 meter apart

- the distance between the sampler and an obstacle, such as buildings, must be at least twice the height that the obstacle protrudes above the sampler;
- a minimum of 2 metres of separation from walls, parapets and penthouses is required for rooftop samplers;
- a minimum of 2 metres of separation from any supporting structure, measured horizontally is required;
- no furnace or incinerator flue is nearby;
- airflow around the sampler is unrestricted;
- the sampler is more than 20 metres from the dripline;
- any wire fence and gate, to protect the sampler, shall not cause any obstruction during monitoring;
- permission must be obtained to set up the samplers and to obtain access to the monitoring stations; and
- a secured supply of electricity is needed to operate the samplers.

Operating/analytical procedures for the operation of HVS

- 3.11 Prior to the commencement of the dust sampling, the flow rate of the high volume sampler was properly set (between 1.1 m³/min. and 1.4 m³/min.) in accordance with the manufacturer's instruction to within the range recommended in USEPA Standard Title 40, CFR Part 50.
- 3.12 For TSP sampling, fiberglass filters with a collection efficiency of > 99% for particles of 0.3µm diameter were used.
- 3.13 The power supply was checked to ensure the sampler worked properly. On sampling, the sampler was operated for 5 minutes to establish thermal equilibrium before placing any filter media at the designated air monitoring station.
- 3.14 The filter holding frame was then removed by loosening the four nuts and a weighted and conditioned filter was carefully centered with the stamped number upwards, on a supporting screen.
- 3.15 The filter was aligned on the screen so that the gasket formed an airtight seal on the outer edges of the filter. Then the filter holding frame was tightened to the filter holder with swing bolts. The applied pressure should be sufficient to avoid air leakage at the edges.
- 3.16 The shelter lid was closed and secured with the aluminum strip.
- 3.17 The timer was then programmed. Information was recorded on the record sheet, which included the starting time, the weather condition and the filter number (the initial weight of the filter paper can be found out by using the filter number).
- 3.18 After sampling, the filter was removed and sent to the HOKLAS laboratory (Wellab Ltd.) for weighing. The elapsed time will be also recorded.
- 3.19 Before weighing, all filters was equilibrated in a conditioning environment for 24 hours. The conditioning environment temperature should be between 25°C and 30°C and not vary by more than ±3°C; the relative humidity (RH) should be < 50% and not vary by more than ±5%. A convenient working RH is 40%.

Maintenance/Calibration

- 3.20 The following maintenance/calibration is required for the HVS:
- The high volume motors and their accessories will be properly maintained. Appropriate maintenance such as routine motor brushes replacement and electrical wiring checking will be made to ensure that the equipment and necessary power supply are in good working condition.
 - High volume samplers will be calibrated at bi-monthly intervals using TE-5025A Calibration Kit throughout all stages of the air quality monitoring.

Results and Observations

- 3.21 All 1-hour TSP monitoring was conducted as scheduled in the reporting month. No Action/Limit Level exceedance was recorded.
- 3.22 All 24-hour TSP monitoring was conducted as scheduled in the reporting month. No Action/Limit Level exceedance was recorded.
- 3.23 The air temperature, precipitation and the relative humidity data was obtained from Hong Kong Observatory where the wind speed and wind direction were recorded by the installed Wind Anemometer at rooftop of Yau Lai Estate Bik Lai House (41/F). The location is shown in **Figure 2**. This weather information for the reporting month is summarized in **Appendix C**.
- 3.24 The monitoring data and graphical presentations of 1-hour and 24-hour TSP monitoring results are shown in **Appendix E** and **Appendix F** respectively.
- 3.25 The summary of exceedance record in reporting month is shown in **Appendix K**. No exceedance was recorded for the air quality monitoring.
- 3.26 According to our field observations, the major dust source identified at the designated air quality monitoring stations are as follows:

Table 3.4 Major Dust Source during Air Quality Monitoring

Station	Major Dust Source
AM1 – Tin Hau Temple	Road Traffic at Cha Kwo Ling Road
AM2 – Sai Tso Wan Recreation Ground	N/A
AM3 – Yau Lai Estate Bik Lai House	Road Traffic near Eastern Cross Harbour Tunnel Toll Plaza
AM4 - Sitting-out Area at Cha Kwo Ling Village	Road Traffic at Cha Kwo Ling Road
AM4(A) - Cha Kwo Ling Public Cargo Working Area Administrative Office	Road Traffic at Cha Kwo Ling Road
AM5(A) - Tseung Kwan O DSD Desilting Compound	Vehicle Movement within the Desilting Compound
AM6(A) - Park Central, L1/F Open Space Area	Road Traffic at Po Yap Road

4. NOISE

Monitoring Requirements

- 4.1 According to EM&A Manual of the Project, construction noise monitoring was conducted to monitor the construction noise arising from the construction activities. The regular monitoring frequency for each monitoring station shall be on a weekly basis and conduct one set of measurements between 0700 and 1900 hours on normal weekdays. **Appendix A** shows the established Action and Limit Levels for the environmental monitoring works.

Monitoring Locations

- 4.2 Noise monitoring was conducted at 8 designated monitoring stations (CM1, CM2, CM3, CM4, CM5, CM6(A), CM7(A), CM8(A)) in the reporting period. **Table 4.1** and **Figure 3** show the locations of these stations.

Table 4.1 Noise Monitoring Stations

Monitoring Stations	Locations	Location of Measurement
CM1	Nga Lai House, Yau Lai Estate Phase 1, Yau Tong	Rooftop (41/F)
CM2	Bik Lai House, Yau Lai Estate Phase 1, Yau Tong	Rooftop (41/F)
CM3	Block S, Yau Lai Estate Phase 5, Yau Tong	Rooftop (40/F)
CM4	Tin Hau Temple, Cha Kwo Ling	Ground Level
CM5	CCC Kei Faat Primary School, Yau Tong	Rooftop (6/F)
CM6(A)*	Site Boundary of Contract No. NE/2015/02 near Tower 1, Ocean Shores	Ground Level
CM7(A)*	Site Boundary of Contract No. NE/2015/02 near Tower 7, Ocean Shores	Ground Level
CM8(A)*	Park Central, L1/F Open Space Area	1/F

Remarks: * Noise monitoring at designated station CM6, CM7 & CM8 was rejected by the premise owners. Therefore, baseline and impact noise monitoring works were carried out at alternative noise monitoring stations CM6(A), CM7(A) and CM8(A) respectively.

Monitoring Equipments

- 4.3 Integrating Sound Level Meter was used for impact noise monitoring. The meters are Type 1 sound level meter capable of giving a continuous readout of the noise level readings including equivalent continuous sound pressure level (L_{eq}) and percentile sound pressure level (L_x) that also complied with International Electrotechnical Commission Publications 651:1979 (Type 1) and 804:1985 (Type 1) specifications. **Table 4.2** summarizes the noise monitoring equipment being used. Copies of calibration certificates are attached in **Appendix B**.

Table 4.2 Noise Monitoring Equipment

Equipment	Model and Make	Quantity
Integrating Sound Level Meter	SVAN 955 / 957 / 977	5
	BSWA 801	1
Calibrator	SV30A	3
	Brüel & Kjær 4231	2

4.4 **Table 4.3** summarizes the monitoring parameters, frequency and total duration of monitoring. The noise monitoring schedule is shown in **Appendix D**.

Table 4.3 Frequency and Parameters of Noise Monitoring

Monitoring Stations	Parameter	Period	Frequency	Measurement
CM1	L ₁₀ (30 min) dB(A)	0700-1900 hrs on normal weekdays	Once per week	Façade
CM2				Façade
CM3				Façade
CM4	L ₉₀ (30 min) dB(A)			Façade
CM5	Façade			
CM6(A)	L _{eq} (30 min) dB(A)			Free Field
CM7(A)	Façade			
CM8(A)	Façade			

Monitoring Methodology and QA/QC Procedure

4.5 The monitoring procedures are as follows:

- The monitoring station was normally be at a point 1m from the exterior of the sensitive receivers building façade and be at a position 1.2m above the ground.
- For free field measurement, the meter was positioned away from any nearby reflective surfaces. All records for free field noise levels was adjusted with a correction of +3 dB(A).
- The battery condition was checked to ensure the correct functioning of the meter.
- Parameters such as frequency weighting, the time weighting and the measurement time was set as follows:
 - frequency weighting : A
 - time weighting : Fast
 - measurement time : 30 minutes
- Prior to and after each noise measurement, the meter was calibrated using a Calibrator for 94.0 dB at 1000 Hz. If the difference in the calibration level before and after measurement will be more than 1.0 dB, the measurement would be considered invalid and repeat of noise measurement would be required after re-calibration or repair of the equipment.
- At the end of the monitoring period, the L_{eq}, L₉₀ and L₁₀ was recorded. In addition, noise sources was recorded on a standard record sheet.
- Noise monitoring will be cancelled in the presence of fog, rain, and wind with a steady speed exceeding 5 m/s, or wind with gusts exceeding 10 m/s. Supplementary monitoring was provided to ensure sufficient data would be obtained.

Maintenance and Calibration

- 4.6 The microphone head of the sound level meter and calibrator was cleaned with a soft cloth at quarterly intervals.
- 4.7 The sound level meter and calibrator was checked and calibrated at yearly intervals.
- 4.8 Immediately prior to and following each noise measurement the accuracy of the sound level meter was checked using an acoustic calibrator generating a known sound pressure level at a known frequency. Measurements may be accepted as valid only if the calibration levels from before and after the noise measurement agree to within 1.0 dB.

Results and Observations

- 4.9 All noise monitoring was conducted as scheduled in the reporting month. No Action/Limit Level exceedance was recorded.
- 4.10 Noise monitoring results and graphical presentations are shown in **Appendix G**.
- 4.11 The summary of exceedance record in the reporting month is shown in **Appendix K**.
- 4.12 The major noise source identified at the noise monitoring stations are shown in **Table 4.4**.

Table 4.4 Major Noise Source during Noise Monitoring

Monitoring Stations	Locations	Major Noise Source
CM1	Nga Lai House, Yau Lai Estate Phase 1, Yau Tong	Road Traffic near Eastern Cross Harbour Tunnel Toll Plaza
CM2	Bik Lai House, Yau Lai Estate Phase 1, Yau Tong	Road Traffic near Eastern Cross Harbour Tunnel Toll Plaza
CM3	Block S, Yau Lai Estate Phase 5, Yau Tong	Road Traffic near Eastern Cross Harbour Tunnel Toll Plaza
CM4	Tin Hau Temple, Cha Kwo Ling	Road Traffic at Cha Kwo Ling Road
CM5	CCC Kei Faat Primary School, Yau Tong	Road Traffic at Yau Tong Road
CM6(A)	Site Boundary of Contract No. NE/2015/02 near Tower 1, Ocean Shores	Road Traffic at O King Road near Ocean Shores
CM7(A)	Site Boundary of Contract No. NE/2015/02 near Tower 7, Ocean Shores	Road Traffic at Tong Yin Street
CM8(A)	Park Central, L1/F Open Space Area	Road Traffic at Po Yap Road

- 4.13 All the Construction Noise Levels (CNLs) reported in this report were adjusted with the corresponding baseline level (i.e. Measured L_{eq} – Baseline L_{eq} = CNL), in order to facilitate the interpretation of the noise exceedance. The baseline noise level and the Noise Limit Level at each designated noise monitoring station are presented in **Table 4.5**.

Table 4.5 Baseline Noise Level and Noise Limit Level for Monitoring Stations

Station	Baseline Noise Level, dB (A) (at 0700 – 1900 hrs on normal weekdays)	Noise Limit Level, dB (A) (at 0700 – 1900 hrs on normal weekdays)
CM1	65.5	75
CM2	63.6	
CM3	65.6	
CM4	62.0	
CM5	68.2	70*
CM6(A)	61.9	75
CM7(A)	58.3	
CM8(A)	69.1	

(*) Noise Limit Level is 65 dB(A) during school examination periods.

Updated Construction Noise Assessment

Contract No. NE/2015/01 & Contract No. NE/2015/02

- 4.14 No update of Construction Noise Assessment in the reporting period. Any updated Construction Noise Assessment will be shown in **Appendix S**.

5. WATER QUALITY

Monitoring Requirements

Groundwater Quality

- 5.1 Groundwater quality monitoring shall be conducted as identified in the EIA report (locations refer to Figure 4, Stream 1 to 3). According to the EM&A Manual, dissolved oxygen (DO), pH, temperature, turbidity, suspended solids (SS), 5-day biochemical oxygen demand (BOD₅), Total organic carbon (TOC), Total Nitrogen, Ammonia-N and Total Phosphate are the parameters for the monitoring. **Appendix A** shows the established Action and Limit Levels.
- 5.2 As stated in the Baseline Environmental Monitoring Plan submitted to EPD in September 2016, Groundwater quality monitoring could not be conducted at the other identified monitoring station in the EIA Report, Stream 4, as it was found to be not accessible due to safety reason. EPD has no further comment on the Plan in October 2016.

Marine Water Quality

- 5.3 Marine water quality monitoring was conducted three times per week at the designated monitoring stations. Monitoring took place two times per monitoring day during mid ebb and mid flood tides at three depths (1 meter from surface, mid depth and 1 meter from the bottom). For Tseung Kwan O Salt Water Intake (i.e. Station M6), water sampling and in situ measurements was taken at the vertical level where the water abstraction point of the intake is located (i.e. approximately mid-depth level). If the water depth is less than 6m, the mid-depth measurement may be omitted. If the depth is less than 3m, only the mid-depth measurements need to be taken.
- 5.4 Duplicate in-situ measurements (Dissolved oxygen (DO) concentration, DO saturation, turbidity, pH, temperature and salinity) and water samples (suspended solids (SS)) at each depth were monitored in accordance with the requirements in the EM&A Manual. For selection of tides for in-situ measurement and water sampling, tidal range of individual flood and ebb tides were not less than 0.5m.

Groundwater Level Monitoring (Piezometer Monitoring)

- 5.5 Daily piezometer monitoring at any time of the day shall be carried throughout the whole period when any tunnel construction activities are carried out within +/- 50m of the piezometer gate in plan. The monitoring has not commenced in this reporting period.

Monitoring Locations

Groundwater Quality

- 5.6 Stream 1 – Stream 3 is designated for the groundwater quality monitoring according to EM&A Manual. The locations are also summarized in **Table 5.1** and shown on **Figure 4**.

Table 5.1 Groundwater Quality Monitoring Stations

Monitoring Streams	Descriptions	Sampling Location
Stream 1	Stream running between the Kwong Tin Estate and Lei Yue Mun Road	1 sampling location for each stream
Stream 2	Stream on western coast of Chiu Keng Wan	
Stream 3	Stream on western coast of Chiu Keng Wan	

Marine Water Quality

- 5.7 A total of twelve monitoring stations are designated for the water quality monitoring program according to EM&A Manual. The locations are also summarized in **Table 5.2** and shown on **Figure 5**.

Table 5.2 Marine Water Quality Monitoring Stations

Monitoring Stations	Descriptions	Coordinates	
		Easting	Northing
M1	Junk Bay Coral Site – Junk Bay near Chiu Keng Wan	844255	817565
M2	Junk Bay Coral Site – Junk Bay	844076	817087
M3	Junk Bay Coral Site – Junk Island	844491	817890
M4	Junk Bay Coral Site – Chiu Keng Wan	843209	816416
M5	Junk Bay Coral Site – Fat Tong Chau	845463	815769
M6	Tseung Kwan O Salt Water Intake	845512	817442
C1	Control Station – Southeast	844696	814773
C2	Control Station – Northwest	842873	816014
G1	Gradient Station	844418	817560
G2	Gradient Station	844290	817384
G3	Gradient Station	844488	817735
G4	Gradient Station	844967	817551

Monitoring Equipments

- 5.8 For in-situ monitoring, a multi-parameter meter (Aquaread AP-2000-D) was used to measure Dissolved oxygen (DO) concentration, DO saturation (DO %), pH, temperature and turbidity. A sampler was used to collect water samples for laboratory analysis of SS, BOD₅, TOC, Total Nitrogen, Ammonia-N and Total Phosphate.

Dissolved Oxygen (DO) and Temperature Measuring Equipment

- 5.9 The instrument for measuring dissolved oxygen and temperature was portable and weatherproof complete with cable, sensor, comprehensive operation manuals and use DC power source. It was capable of measuring:
- a dissolved oxygen level in the range of 0-20 mg/L and 0-200% saturation; and
 - a temperature of 0-45 degree Celsius.
- 5.10 It has a membrane electrode with automatic temperature compensation complete with a cable.
- 5.11 Sufficient stocks of spare electrodes and cables were available for replacement where necessary.

5.12 Salinity compensation was built-in in the DO equipment.

Turbidity

5.13 Turbidity was measured in situ by the nephelometric method. The instrument was portable and weatherproof using a DC power source complete with cable, sensor and comprehensive operation manuals. The equipment was capable of measuring turbidity between 0-1000 NTU. The probe cable was not be less than 25m in length.

pH

5.14 The instrument was consisting of a potentiometer, a glass electrode, a reference electrode and a temperature-compensating device. It was readable to 0.1pH in a range of 0 to 14. Standard buffer solutions of at least pH 7 and pH 10 were used for calibration of the instrument before and after use.

Water Depth Detector

5.15 A portable, battery-operated echo sounder was used for the determination of water depth at each designated monitoring station.

Water Sampler

5.16 Water samples collected for laboratory analysis were stored in high density polythene bottles sample containers, with appropriate preservatives added. All sampling bottles were labeled (waterproof) with the sampling date and time, sample lot number and sampling location reference number to avoid mishandling.

Sample Container and Storage

5.17 Following collection, water samples for laboratory analysis were stored in high density polythene bottles, with preservative appropriately added where necessary. They will be packed in ice (cooled to 4°C without being frozen), delivered to the laboratory and analysed as soon as possible.

Calibration of In Situ Instruments

5.18 All in situ monitoring instruments were checked, calibrated and certified by a laboratory accredited under HOKLAS or other international accreditation scheme before use, and subsequently re-calibrated at 3 monthly intervals throughout all stages of the water quality monitoring.

5.19 For the on-site calibration of field equipment, the BS 1427:1993, "Guide to Field and on-site test methods for the analysis of waters" was observed.

5.20 Before each round of monitoring, a zero check in distilled water was performed with the turbidity probe of Aquaread AP-2000-D. The probe was then be calibrated with a solution of known NTU.

5.21 Sufficient stocks of spare parts were maintained for replacements when necessary. Backup monitoring equipment was also being made available so that monitoring can proceed uninterrupted even when some equipment is under maintenance, calibration, etc.

5.22 **Table 5.3** summarizes the equipment used in the water quality monitoring program. Copies of the calibration certificates of the equipment are shown in **Appendix B**.

Table 5.3 Water Quality Monitoring Equipment

Equipment	Model and Make	Qty.
Water Sampler	Kahlsico Water-Bottle Model 135DW 150	1
Multi-parameter Water Quality System	YSI 6820-C-M / YSI 6920-C-M	0
	Aquaread AP-2000-D	3
	YSI EXO1 Multiparameter Sondes	0
Monitoring Position Equipment	“Magellan” Handheld GPS Model GPS-320	1
Water Depth Detector	Fishfinder 140	1

Monitoring Parameters and Frequency

5.23 **Table 5.4** summarizes the monitoring parameters, monitoring period and frequencies of the water quality monitoring in the reporting period.

Table 5.4 Water Quality Monitoring Parameters and Frequency

Monitoring Stations	Parameters, unit	Depth	Frequency
Groundwater Quality			
Stream 1- Stream 3	<ul style="list-style-type: none"> • DO, mg/L • DO Saturation, % • pH • Water Temperature (°C) • Turbidity, NTU • SS, mg/L • BOD₅, mg O₂/L • TOC, mg-TOC/L • Total Nitrogen, mg/L • Ammonia-N, mg NH₃-N/L • Total Phosphate, mg-P/L 	Mid-depth	Biweekly (When the tunnel construction works are found within 50m of the location, weekly.)
Marine Water Quality			
M1 M2 M3 M4 M5 M6 C1 C2 G1 G2 G3 G4	<p><i>In-situ:</i> Dissolved oxygen (DO) concentration, DO saturation, turbidity, pH, temperature and salinity</p> <p><u>Laboratory Testing:</u> Suspended Solids (SS)</p>	<p><u>M1-M5, C1-C2, G1-G4</u></p> <ul style="list-style-type: none"> • 3 water depths: 1m below water surface, mid-depth and 1m above sea bed. • If the water depth is less than 3m, mid-depth sampling only. • If the water depth is less than 6m, omit mid-depth sampling. <p><u>M6</u></p> <ul style="list-style-type: none"> • at the vertical level where the water abstraction point of the intake is located(i.e. approximately mid-depth level) 	<p>3 days per week / 2 per monitoring day (1 for mid-ebb and 1 for mid-flood)</p>

Monitoring Methodology**Groundwater Quality**

5.24 At each monitoring location, two consecutive in-situ measurements for DO concentration,

DO saturation, pH, temperature and turbidity were taken for water samples on site. The probes were retrieved out of the water after the first measurement and then re-deployed for the second measurement. Where the difference in the value between the first and second readings of each set was more than 25% of the value of the first reading, the reading was discarded and further readings were taken.

- 5.25 For SS, BOD₅, TOC, Total Nitrogen, Ammonia-N and Total Phosphate, measurement and grab samples of surface water was collected. Water samples of about adequate volume was collected and stored in high density polythene bottles. Following collection, water samples was stored in high density polythene bottles. Preservation H₂SO₄ was appropriately added for water samples for TOC, Total Nitrogen, Ammonia-N and Total Phosphate testing. Water samples was packed in ice and cooled to 4°C (without being frozen), delivered to the HOKLAS accredited laboratory, Wellab Limited and analyzed.

Marine Water Quality

- 5.26 The monitoring stations were accessed using survey boat by the guide of a hand-held Global Positioning System (GPS). The depth of the monitoring location was measured using depth meter in order to determine the sampling depths. Afterwards, the probes of the in-situ measurement equipment was lowered to the predetermined depths (1 m below water surface, mid-depth and 1 m above seabed) and the measurements was carried out accordingly. The in-situ measurements at predetermined depths was carried out in duplicate. In case the difference in the duplicate in-situ measurement results was larger than 25%, the third set of in-situ measurement would be carried out for result confirmation purpose.
- 5.27 Water sampler was lowered into the water to the required depths of sampling. Upon reaching the pre-determined depth, a messenger to activate the sampler was then released to travel down the wire. The water sample was sealed within the sampler before retrieving. At each station, water samples for SS at three depths (1 m below water surface, mid-depth and 1 m above seabed) were collected accordingly. Water samples were stored in a cool box and kept at less than 4°C but without frozen and sent to the laboratory as soon as possible.

Laboratory Analytical Methods

- 5.28 The testing of all parameters were conducted by Wellab Ltd. (HOKLAS Registration No.083) and comprehensive quality assurance and control procedures in place in order to ensure quality and consistency in results. The testing method and limit of reporting are provided in **Table 5.5**.

Table 5.5 Methods for Laboratory Analysis for Water Samples

Parameters (Unit)	Proposed Method	Reporting Limit	Detection Limit
SS (mg/L)	APHA 2540 D	0.5 mg/L ⁽¹⁾	0.5 mg/L
BOD ₅ (mg O ₂ /L)	APHA 19ed 5210B	2 mg O ₂ /L	--
TOC (mg-TOC/L)	In-house method SOP020 (Wet Oxidation)	1 mg-TOC/L	--
Total Nitrogen (mg/L)	In-house method SOP063 (FIA)	0.6 mg/L	--
Ammonia-N (mg NH ₃ -N/L)	In-house method SOP057 (FIA)	0.05 mg NH ₃ - N/L	--
Total Phosphorus (mg-P/L) ⁽²⁾	In-house method SOP055 (FIA)	0.05 mg-P/L	--

Note:

1) Limit of Reporting is reported as Detection Limit for non-HOKLAS report.

2) Parameter Total Phosphorus represents the laboratory testing for total phosphate content in water which is the sum of all three forms of phosphates in water.

QA/QC Requirements

Decontamination Procedures

- 5.29 Water sampling equipment used during the course of the monitoring programme was decontaminated by manual washing and rinsed clean seawater/distilled water after each sampling event. All disposal equipment was discarded after sampling.

Sampling Management and Supervision

- 5.30 Water samples were dispatched to the testing laboratory for analysis as soon as possible after the sampling. All samples were stored in a cool box and kept at less than 4°C but without frozen. All water samples were handled under chain of custody protocols and relinquished to the laboratory representatives at locations specified by the laboratory.
- 5.31 QA/QC procedures as attached in **Appendix J** are available for the parameters analyzed in the HOKLAS-accredited laboratory, WELLAB Ltd.

Results and Observations

Groundwater Quality Monitoring

- 5.32 All groundwater quality monitoring was conducted as scheduled in the reporting month. Summary of groundwater quality monitoring results and Action/Limit Level exceedance are shown in **Table 5.6**. Groundwater monitoring result and graphical presentations are shown in **Appendix H**.

Table 5.6 Summary of Groundwater Quality Monitoring Results

Location	Date	Parameters (unit)								
		pH	Dissolved Oxygen (mg/L)	Turbidity (NTU)	SS (mg/L)	BOD ₅ (mg O ₂ /L)	TOC (mg-TOC/L)	Total Nitrogen (mg/L)	NH ₃ -N (mg NH ₃ -N/L)	Total Phosphorus (mg-P/L)
Stream 1	11 Apr 2017	7.2	7.8	1.7	<0.5	<2	<u>6</u>	1.0	0.05	<0.05
	27 Apr 2017	6.9	8.2	1.8	1.6	<2	<u>5</u>	1.2	<0.05	<0.05
Stream 2	11 Apr 2017	7.2	7.8	0.4	3.8	<2	<u>17</u>	1.1	<u>0.13</u>	<0.05
	27 Apr 2017	6.9	8.3	2.0	4.2	<2	<u>9</u>	1.3	<u>0.08</u>	<0.05
Stream 3	11 Apr 2017	7.2	7.7	1.7	1.0	<2	4	0.9	<0.05	<0.05
	27 Apr 2017	6.7	8.1	1.8	3.3	<2	<u>5</u>	1.2	<u>0.06</u>	<0.05
No. of Exceedance	Action Level	0	0	0	0	0	0	0	1	0
	Limit Level	0	0	0	0	0	5	0	2	0

Note: ***Bold Italic*** means Action Level exceedance
Bold Italic with underline means Limit Level exceedance

5.33 According to the information provided by the Contractor, no tunnel boring or tunnel construction works were carried out in both Lam Tin side and Tseung Kwan O side in April 2017. Therefore, it is considered that the exceedance is not project-related. The summary of exceedance record in the reporting month is shown in **Appendix K**.

5.34 Other relevant data was also recorded, such as monitoring location / position, time, sampling depth, weather conditions and any special phenomena or work underway nearby.

Marine Water Quality Monitoring

5.35 All marine water quality monitoring was conducted as scheduled in the reporting month. Marine water monitoring results and graphical presentations are shown in **Appendix I**. Other relevant data was also recorded, such as monitoring location / position, time, sampling depth, weather conditions and any special phenomena or work underway nearby.

5.36 Calculated Action and Limit Levels for Marine Water Quality is presented in **Appendix I**. No exceedance of Action and Limit Levels of marine water quality was recorded during the reporting period.

Groundwater Level Monitoring (Piezometer Monitoring)

5.37 Daily piezometer monitoring at any time of the day shall be carried throughout the whole period when any tunnel construction activities are carried out within +/- 50m of the piezometer gate in plan.

5.38 Construction Phase Piezometer Monitoring has not commenced in this reporting period.

6. ECOLOGY

Post-Translocation Coral Monitoring

- 6.1 Post-translocation monitoring survey is recommended in the EM&A Manual to audit the success of coral translocation. Information gathered during each post-translocation monitoring survey should include observations on the presence, survival, health condition and growth of the translocated coral colonies. These parameters should then be compared with the baseline results collected from the pre-translocation survey.
- 6.2 The post-translocation coral monitoring shall be conducted once every 3 months after completion for a period of 12 months. The first post-translocation coral monitoring was carried out on 6 March 2017.
- 6.3 The second post-translocation coral monitoring is scheduled to be carried out in May 2017 tentatively. Location of post-translocation coral monitoring is shown in **Figure 7**.

Event and Action Plan

- 6.4 The post-translocation monitoring result shall be evaluated against Action and Limit Levels presented in **Appendix A**. Evaluation shall be based on recorded changes in percentage of partial mortality of the corals.
- 6.5 If the defined Action Level or Limit Level for coral monitoring is exceeded, the actions as set out in **Appendix M** will be implemented.
- 6.6 If observations of any die-off / abnormal conditions of the translocated corals are made during the post-translocation monitoring, the ET shall inform the Contractor, IEC and AFCD, and liaise with AFCD to investigate any mitigation measures needed.

Results and Observations

- 6.7 No post-translocation coral monitoring was conducted in the reporting month.
- 6.8 Photographs of the coral colonies of coming post-translocation coral monitoring will be shown in **Appendix T**.

7. MONITORING ON CULTURAL HERITAGE

Monitoring Requirement

- 7.1 According to the EP Conditions and EM&A Manual, monitoring of vibration impacts should be conducted when the construction works are less than 100m from the Built Heritage in close proximity of the worksite, namely the Cha Kwo Ling Tin Hau temple. Tilting and settlement monitoring should be applied on the Cha Kwo Ling Tin Hau Temple. Construction works less than 100m from the Cha Kwo Ling Tin Hau temple commenced on 8 April 2017.
- 7.2 As stated in the approved “*Built Heritage Mitigation Plan*” for this Project, during the period of the construction works conducted within 100m from the Cha Kwo Ling Tin Hau Temple, monitoring on settlement and tilting will be conducted once a day for the Cha Kwo Ling. Monitoring of vibration will be conducted during blasting at Cha Kwo Ling area once a day. When there is no blasting to be conducted at the area, vibration monitoring at the Cha Kwo Ling Tin Hau Temple will be conducted once per day when there are piling works or rock breaking works within the 100m from the Cha Kwo Ling Tin Hau Temple.

Monitoring Locations

- 7.3 One (1) vibration monitoring point, one (1) building settlement monitoring point and one (1) building tilting monitoring point are proposed for the vibration impacts monitoring of the construction works. The building settlement marker and the tiltmeter will be placed on the wall of the Cha Kwo Ling Tin Hau Temple and the vibration monitoring point is located within the Cha Kwo Ling Tin Hau Temple.
- 7.4 Confirmation from the Cha Kwo Ling Tin Hau Temple on the installation of these monitoring equipment is yet to be obtained by the Contractor. Vibration monitoring was carried out at a temporary location outside the Cha Kwo Ling Tin Hau Temple in the reporting period. Monitoring Location is shown in **Figure 8**.

Monitoring Equipment

- 7.5 Building settlement should be measured by surveyors via settlement marker and tiltmeter attached to the wall of the Cha Kwo Ling Tin Hau Temple.
- 7.6 Vibration monitoring was conducted by using vibrographs: Minimate Plus manufactured by Instatel. These vibrographs will be calibrated annually and its performance follows the requirements given in the “*Guidance Note on Vibration Monitoring*” (GN-VM) issued by the Civil Engineering and Development Department, which is based on the Performance Specification for Blasting Seismographs by International Society of Explosive Engineers (ISEE (2000)).
- 7.7 **Table 7.1** summarizes the equipment employed by the Contractor for vibration monitoring. Copies of calibration certificates are attached in **Appendix B**.

Table 7.1 Vibration Monitoring Equipment

Equipment	Model and Make	Quantity
Vibrographs for vibration monitoring	BE17906 V 10.30-8.17 MiniMate Plus manufactured by Instatel	1

Monitoring Methodology

- 7.8 Vibrograph (velocity seismograph) was deployed at each monitoring station to measure and record the PPV and amplitude of ground motion in three mutually perpendicular directions. Vibration monitoring equipment fulfils the requirements stated in the Government guidelines and is calibrated to HOKLAS standards. Each monitoring would not be more than 10 minutes. Settlement and tilting monitoring should be conducted by surveyors manually.

Alert, Alarm and Action Levels

- 7.9 The Alert, Alarm and Action (AAA) Levels are given in **Table 7.2**.

Table 7.2 AAA Levels for Monitoring for Cultural Heritage

Parameter	Alert Level	Alarm Level	Action Level
Vibration	ppv: 4.5 mm/s	ppv: 4.8 mm/s	ppv: 5mm/s Maximum Allowable Vibration Amplitude: 0.1mm
Building Settlement Markers	6mm	8mm	10mm
Building Tilting	1:2000	1:1500	1:1000

Results

- 7.10 In the reporting month, vibration monitoring was carried out by the Contractor at the aforesaid location on 12 occasions. No AAA Level exceedance for vibration monitoring was recorded in the reporting month. The monitoring results are provided in **Table 7.3**.

Table 7.3 Vibration Monitoring Results

Date	Time	Measurement Direction		
		Tran	Vertical	Longitudinal
10 Apr 2017	14:54	0.254	0.254	0.127
11 Apr 2017	14:05	0.254	1.524	0.254
12 Apr 2017	13:29	0.254	0.508	0.254
13 Apr 2017	11:10	0.381	0.381	0.508
18 Apr 2017	13:11	0.254	0.508	0.127
20 Apr 2017	13:56	0.381	0.381	0.254
21 Apr 2017	13:41	0.254	0.508	0.254
22 Apr 2017	14:24	0.381	0.381	0.254
24 Apr 2017	13:29	0.254	0.254	0.254
25 Apr 2017	14:51	0.254	0.381	0.254
27 Apr 2017	16:46	0.381	0.254	0.254
29 Apr 2017	15:30	0.254	0.254	0.127

- 7.11 Settlement and tilting monitoring will be conducted when confirmation from the Cha Kwo Ling Tin Hau Temple on the installation of these monitoring equipment is obtained by the Contractor.

Mitigation Measures for Cultural Heritage

- 7.12 According to Condition 3.6 of the EP (EP No.: EP-458/2013/C), to prevent damage to Cha Kwo Ling Tin Hau Temple and its fung Shui rocks (Child-given rocks) during the construction phase, a temporarily fenced-off buffer zone (Rocks buffer zone is 5 m from the edge of Rocks and 15m from the edge of Rocks alter) with allowance for public access (minimum 1 m) around the temple and the fung shui rocks shall be provided. The open yard in front of the temple should be kept as usual for annual Tin Hau festival.
- 7.13 As there is a large buffer distance from the current works to Cha Kwo Ling Tin Hau Temple and the fung Shui rocks (Child-given rocks), the temporarily fenced-off rocks buffer zone and from the edge of Rocks alter is not required. The fenced-off rocks buffer zone would be implemented when there is construction activities in vicinity of the cultural heritage.

8. LANDSCAPE AND VISUAL IMPACT REQUIREMENTS

- 8.1 Landscape and visual mitigation measures during the construction phase shall be checked to ensure that they are fully realized and implemented on site.
- 8.2 Site audits were carried out on a weekly basis to monitor and audit the timely implementation of landscape and visual mitigation measures. The summaries of site audits are attached in **Appendix L**.
- 8.3 No non-compliance of the landscape and visual impact was recorded in the reporting month.

9. LANDFILL GAS MONITORING

Monitoring Requirement

- 9.1 In accordance with the EM&A Manual, monitoring of landfill gas is required for construction works within the Sai Tso Wan Landfill Consultation Zone during the construction phase. This section presents the results of landfill gas measurements performed by the Contractor. **Appendix A** shows the Limit Levels for the monitoring works.
- 9.2 The “Landfill Gas Monitoring Proposal”, including the monitoring programme and detailed actions, is submitted to the EPD for approval. Details of monitoring in this Proposal is in line with the monitoring requirements stipulated in the EM&A Manual.

Monitoring Parameters and Frequency

- 9.3 Monitoring parameters for Landfill gas monitoring include Methane, Carbon dioxide and Oxygen.
- 9.4 According to the implementation schedule and recommended mitigation measures of the EM&A Manual, measurements of the following frequencies should be carried out:

Excavations deeper than 1m

- at the ground surface before excavation commences;-
- immediately before any worker enters the excavation;
- at the beginning of each working day for the entire period the excavation remains open; and
- periodically throughout the working day whilst workers are in the excavation.

Excavations between 300mm and 1m deep

- directly after the excavation has been completed; and
- periodically whilst the excavation remains open.

For excavations less than 300mm deep

- monitoring may be omitted, at the discretion of the Safety Officer or other appropriately qualified person

Monitoring Locations

- 9.5 Monitoring of oxygen, methane and carbon dioxide was performed for excavations at 1m depth or more within the Consultation Zone. In this reporting month, the area required to be monitored for landfill gas are shown below and **Figure 6** shows the landfill gas monitoring locations.
- | | |
|-----------------------------------|-------------|
| ➤ Excavation Locations: | Portion III |
| ➤ Manholes and Chambers: | N/A |
| ➤ Relocation of monitoring wells: | N/A |
| ➤ Any other Confined Spaces: | N/A |

Monitoring Equipment

- 9.6 **Table 9.1** summarizes the equipment employed by the Contractor for the landfill gas monitoring.

Table 9.1 Landfill Gas Monitoring Equipment

Equipment	Model and Make	Quantity
Intrinsically safe, portable gas detector	Crowcon Tetra Portable Gas Detector (Serial No. 100486262/01-020)	1

Results

- 9.7 In the reporting month, landfill gas monitoring was carried out by the Contractor at the aforesaid locations on 52 occasions. No Limit Level exceedance for landfill gas monitoring was recorded in the reporting month. The monitoring results are provided in **Appendix R**. Copies of calibration certificates are attached in **Appendix B**.

10. ENVIRONMENTAL AUDIT**Site Audits**

- 10.1 Site audits were carried out on a weekly basis to monitor the timely implementation of proper environmental management practices and mitigation measures in the Project site. The summaries of site audits are attached in **Appendix L**.
- 10.2 Joint weekly site audits by the representatives of the Engineer, Contractor and the ET were conducted in the reporting month as shown in below:
- Contract No. NE/2015/01: 5, 12, 19, 26 April 2017
 - Contract No. NE/2015/02: 6, 13, 18, 26 April 2017
- Monthly joint site inspection with the representative of IEC was conducted on 26 April 2017 (Contract No. NE/2015/01 and NE/2015/02).

Implementation Status of Environmental Mitigation Measures

- 10.3 According to the EIA Study Report, Environmental Permit and the EM&A Manual of the Project, the mitigation measures detailed in the documents are recommended to be implemented during the construction phase. An updated summary of the Implementation Schedule and Recommended Mitigation Measures is provided in **Appendix N**.
- 10.4 During site inspections in the reporting month, no non-conformance was identified. The observations and recommendations made during the audit sessions are summarized in **Table 10.1**.

Table 10.1 Observations and Recommendations of Site Audit

Parameters	Date	Observations and Recommendations	Follow-up
Contract No. NE/2015/01			
<i>Water Quality</i>	15, 22 Mar, 12, 19 Apr 2017	<u>Observation:</u> To set up proper drainage system in CKL site Portion 3.	Follow up action will be reported in next reporting month.
	22, 29 Mar 2017	<u>Observation:</u> Silty water on the sea observed near the marine works area. The contractor is reminded to check the silt curtain deployed and ensure the effectiveness.	The deficiency was observed to be improved/rectified by the Contractor during the audit session on 5 April 2017.
	12 Apr 2017	<u>Reminder:</u> To cover or seal the gaps of covers of catchpit in Portion 1 to prevent silt water or oil stain flow out of site.	The deficiency was observed to be improved/rectified by the Contractor during the audit session on 19 April 2017.
	19 Apr 2017	<u>Observation:</u> To remove the construction waste in U-channel in Portion 3.	The deficiency was observed to be improved/rectified by the Contractor during the audit session on 26 April 2017.
	26 Apr 2017	<u>Observation:</u> Muddy water observed without proper containment in TKO. The Contractor is reminded to provide bunds or containment pit to prevent muddy water flow out of site.	The deficiency was observed to be improved/rectified by the Contractor during the audit session on 2 May 2017.
<i>Noise</i>	18, 25 Jan, 1, 8, 15, 22 Feb, 1, 8, 15, 22, 29 Mar 2017	<u>Reminder:</u> The contractor is reminded to provide noise mitigation measures (e.g. Temporary noise barrier or Full enclosure) to PME as proposed in the approved NMP in Cha Kwo Ling.	The deficiency was observed to be improved/rectified by the Contractor during the audit session on 5 April 2017.
<i>Landscape and Visual</i>	5 Apr 2017	<u>Reminder:</u> To set-up tree protection zone for retained tree in TKO slope.	The deficiency was observed to be improved/rectified by the Contractor during the audit

Parameters	Date	Observations and Recommendations	Follow-up
			session on 12 April 2017.
	12, 19 Apr 2017	<u>Reminder:</u> To properly set-up tree protection area in Portion 3.	Follow up action will be reported in next reporting month.
<i>Air Quality</i>	29 Mar 2017	<u>Observation:</u> Dust emission observed at the top of slope of TKO. The contractor is reminded to provide frequent water spray to unpaved works area.	The deficiency was observed to be improved/rectified by the Contractor during the audit session on 5 April 2017.
	29 Mar 2017	<u>Reminder:</u> Clear the used cement bags in TKO slope.	The deficiency was observed to be improved/rectified by the Contractor during the audit session on 5 April 2017.
	5 Apr 2017	<u>Reminder:</u> To provide frequent water spray for TKO slope to prevent dust generation.	The deficiency was observed to be improved/rectified by the Contractor during the audit session on 12 April 2017.
	26 Apr 2017	<u>Observation:</u> Grouting equipment in TKO observed without proper enclosure. The Contractor is reminded to provide top and 3-side enclosure.	The deficiency was observed to be improved/rectified by the Contractor during the audit session on 2 May 2017.
<i>Waste / Chemical Management</i>	29 Mar 2017	<u>Reminder:</u> Provide drip tray to chemical containers at the top of slope of TKO.	The deficiency was observed to be improved/rectified by the Contractor during the audit session on 5 April 2017.
	12 Apr 2017	<u>Observation:</u> Oil stain observed in unpaved excavation area of Portion 3 and paved ground of Portion 1. The Contractor is reminded to properly remove the oil stain as “chemical waste”.	The deficiency was observed to be improved/rectified by the Contractor during the audit session on 19 April 2017.
	12 Apr 2017	<u>Reminder:</u> To provide drip tray to chemical containers in Portion 3.	The deficiency was observed to be improved/rectified by the Contractor during the audit session on 19 April 2017.
	26 Apr 2017	<u>Reminder:</u> To remove oil stain mixed with muddy water in CKL site.	The deficiency was observed to be improved/rectified by the Contractor during the audit session on 2 May 2017.
<i>Impact on Cultural Heritage</i>	12, 19 Apr 2017	<u>Reminder:</u> To properly set up fenced-off buffer zone around Tin Hau Temple.	The deficiency was observed to be improved/rectified by the Contractor during the audit session on 26 April 2017.
<i>Permits / Licenses</i>	--	--	--
Contract No. NE/2015/02			
<i>Water Quality</i>	6 Apr 2017	<u>Reminder:</u> To remove the accumulated sediments in the U-channels in Area A.	The deficiency was observed to be improved/rectified by the Contractor during the audit session on 13 April 2017.
	26 Apr 2017	<u>Reminder:</u> To repair the holes near the discharge point in Area A to prevent surface runoff flow into the discharge point.	Follow up action will be reported in next reporting month.
<i>Noise</i>	18 Apr 2017	<u>Reminder:</u> To provide proper acoustic material for enclosing the breaker head at Portion SR2B.	The deficiency was observed to be improved/rectified by the Contractor during the audit session on 26 April 2017.
<i>Landscape</i>	--	--	--

Parameters	Date	Observations and Recommendations	Follow-up
<i>and Visual</i>			
<i>Air Quality</i>	29 Mar, 6 April 2017	<u>Reminder:</u> To cover the stockpile of dusty material by tarpaulin sheet properly in Area A.	The deficiency was observed to be improved/rectified by the Contractor during the audit session on 13 April 2017.
	18 Apr 2017	<u>Reminder:</u> To remove the dusty used cement bags at Portion 1.	The deficiency was observed to be improved/rectified by the Contractor during the audit session on 26 April 2017.
<i>Waste / Chemical Management</i>	29 Mar 2017	<u>Reminder:</u> To clear the oil stain near the drip tray as “chemical waste” in Portion 8.	The deficiency was observed to be improved/rectified by the Contractor during the audit session on 6 April 2017.
	6 Apr 2017	<u>Reminder:</u> To remove the accumulation of C&D waste and general refuse regularly in Portion 8. Empty chemical containers should be separated with other C&D waste and be treated as “chemical waste”.	The deficiency was observed to be improved/rectified by the Contractor during the audit session on 13 April 2017.
	6 Apr 2017	<u>Reminder:</u> To provide drip tray to chemical containers in Portion 8	The deficiency was observed to be improved/rectified by the Contractor during the audit session on 13 April 2017.
<i>Permits / Licenses</i>	--	--	--

11. WASTE MANAGEMENT

- 11.1 Waste generated from this Project includes inert construction and demolition (C&D) materials, non-inert C&D materials and marine sediments. Inert C&D waste includes soil, broken rock, broken concrete and building debris, while non-inert C&D materials are made up of C&D waste which cannot be reused or recycled and has to be disposed of at the designated landfill sites. Marine sediment shall be expected from excavation and dredging works of this Project.
- 11.2 With reference to relevant handling records of this Project, the quantities of different types of waste generated in the reporting month are summarised and presented in **Appendix P**.
- 11.3 The Contractors are advised to minimize the wastes generated through the recycling or reusing. All mitigation measures stipulated in the approved EM&A Manual and waste management plans shall be fully implemented. The status of implementation of waste management and reduction measures are summited in **Appendix N**.

12. ENVIRONMENTAL NON-CONFORMANCE

Summary of Exceedances

- 12.1 No exceedance of Action and Limit Levels of air quality monitoring in the reporting period.
- 12.2 No exceedance of Action and Limit Levels of noise monitoring in the reporting period.
- 12.3 One Action Level exceedance and Seven Limit Level exceedances in ground water quality monitoring was recorded during the reporting period. The exceedance is considered to be non-Project related. The summary of exceedance is provided in **Appendix K**.
- 12.4 No exceedance of Action and Limit Levels of marine water quality monitoring in the reporting period.
- 12.5 No Alert Alarm and Action (AAA) Level exceedance of vibration monitoring on cultural heritage was recorded in the reporting month.
- 12.6 No Limit Level exceedance for landfill gas monitoring was recorded.
- 12.7 Should the monitoring results of the environmental monitoring parameters at any designated monitoring stations indicate that the Action / Limit Levels are exceeded, the actions in accordance with the Event and Action Plans in **Appendix M** be carried out.

Summary of Environmental Non-Compliance

- 12.8 No environmental non-compliance was recorded in the reporting month.

Summary of Environmental Complaint

- 12.9 One environmental complaint was received in the reporting month. The Cumulative Complaint Log since the commencement of the Project is presented in **Appendix O**. The investigation status and result is also reported in **Appendix O**.

Summary of Environmental Summon and Successful Prosecution

- 12.10 There was no successful environmental prosecution or notification of summons received since the Project commencement. The Cumulative Log for environmental summon and successful prosecution since the commencement of the Project is presented in **Appendix O**.

13. FUTURE KEY ISSUES

13.1 Tentative construction programmes for the next three months are provided in **Appendix Q**.

13.2 Major site activities to be undertaken for the next reporting period are summarized in **Table 13.1**.

Table 13.1 Summary Table for Site Activities in the next Reporting Period

Contract No.	Project Title	Site Activities (May 2017)	
NE/2015/01	Tseung Kwan O - Lam Tin Tunnel - Main Tunnel and Associated Works	Lam Tin Interchange	1) Excavation for Tunnel Adit 2) EHC2 U-Trough 3) Haul Road Construction 4) Site Formation – Area 1G1, Area 2, Area 3, Area 4 5) Temp Steel Bridge across CKL Road & Barging Facility 6) Pipe Pile Wall – Area 2A 7) Ground Investigation
		Mined Tunnel	1) Tunnel Team Mobilisation Works
		TKO Interchange	1) Haul Road Construction and Site Formation 2) Temporary Barging Facilities & Temporary Works 3) Temporary Cut Slope For BMCP
NE/2015/02	Tseung Kwan O – Lam Tin Tunnel – Road P2 and Associated Works	1) Construction and Backfilling of Retaining wall 2) Installation of silt curtain 3) Installation of Temporary Cofferdam 4) Installation of Double Water Gate 5) Dredging Works 6) Construction of sloping seawall 7) Ground investigation at Portion VI 8) Preparation of Treatment work for Marine Sediment 9) Construction of Temporary Transformer Room 10) Construction of outfall for diversion of existing drainpipe 11) Installation of 2100mm dia. Drainage at Portion IV 12) Construction of preboring socket H-piles	

Key Issues for the Coming Month

13.3 Key environmental issues in the coming month include:

- Watering for dust generation from haul road, stockpiles of dusty materials, exposed site area, excavation works and rock breaking activities;
- Noisy construction activity such as rock-breaking activities and piling works;

- Runoff from exposed slope or site area;
- Wastewater and runoff discharge from site;
- Accumulation of silt, mud and sand along U-channels and sedimentation tanks;
- Set up and implementation of temporary drainage system for the surface runoff;
- Storage of chemicals/fuel and chemical waste/waste oil on site;
- Accumulation and storage of general and construction waste on site; and
- Marine water quality impact and indirect impact to coral communities due to marine construction for TKO-LTT reclamation.

Monitoring Schedule for the Next Month

13.4 The tentative environmental monitoring schedules for the next month are shown in **Appendix D**.

14. CONCLUSIONS AND RECOMMENDATIONS

Conclusions

- 14.1 This is the 6th Environmental Monitoring and Audit (EM&A) Report which presents the EM&A works undertaken during the period in April 2017 in accordance with EM&A Manual and the requirement under EP.

Air Quality Monitoring

- 14.2 All 1-hour TSP monitoring was conducted as scheduled in the reporting month. No Action/Limit Level exceedance was recorded.
- 14.3 All 24-hour TSP monitoring was conducted as scheduled in the reporting month. No Action/Limit Level exceedance was recorded.

Construction Noise Monitoring

- 14.4 All noise monitoring was conducted as scheduled in the reporting month. No Action/Limit Level exceedance was recorded.

Water Quality Monitoring

- 14.5 All groundwater Quality monitoring was conducted as scheduled in the reporting month. One Action Level Exceedance and Seven Limit Level exceedance were recorded. The exceedance is considered to be non-Project related.
- 14.6 All marine water quality monitoring was conducted as scheduled in the reporting month. No Action/Limit Level exceedance was recorded.

Ecological Monitoring

- 14.7 Second post-translocation coral monitoring survey is scheduled in May 2017 tentatively.

Monitoring on Cultural Heritage

- 14.8 No Alert Alarm and Action (AAA) Level exceedance of vibration monitoring on cultural heritage was recorded in the reporting month.

Landscape and Visual Monitoring and Audit

- 14.9 No non-compliance of the landscape and visual impact was recorded in the reporting month.

Landfill Gas Monitoring

- 14.10 Monitoring of landfill gases commenced in the reporting month and were carried out by the Contractor at excavation location, Portion III. No Limit Level exceedance was recorded.

Environmental Site Inspection

- 14.11 Joint weekly site inspections were conducted by representatives of the Contractor, Engineer and Environmental Team. During site inspections in the reporting month, no non-conformance was identified

Complaint, Prosecution and Notification of Summons

- 14.12 1 environmental complaint, no successful prosecution or notification of summons were received during the reporting period.

Recommendations

- 14.13 According to environmental audits performed in the reporting month, the following recommendations were made:

Air Quality Impact

- To implement dust suppression measures such as water spray on all haul roads, stockpiles, dry surfaces and open slopes.
- To cover stockpile of dusty material by impervious material.
- To remove the dusty cement bags after use.
- To provide top and 3-side enclosure to grouting equipment.

Construction Noise

- To provide proper acoustic material for enclosing the breaker head.

Water Quality Impact

- To review and implement temporary drainage system.
- To clear the litter, debris, silt and sediment in drainage or catchpits.
- To repair the holes near the discharge point to prevent surface runoff flow into the discharge point.
- To provide bund or covers to gullies and stockpile storage area on site to avoid leakage of surface runoff.
- To divert all the water generated from construction site to de-silting facilities with enough handling capacity before discharge.

Waste/Chemical Management

- To provide drip tray to chemical containers and provide plug to drip tray.
- To check for any accumulation of waste materials or rubbish on site or in drainage.
- To remove oil stain near any powered mechanical equipment on paved ground
- To remove the accumulation of C&D waste and general refuse regularly


Landscape and Visual

- To set up proper tree protection area.

Permits/Licenses

- N/A

FIGURES




LEGEND:

 PROJECT BOUNDARY

CINOTECH
Cinotech Consultants Limited

Agreement No. CE/59/2015 (EP)
Environmental Team for Tseung Kwan O - Lam Tin Tunnel
- Design and Construction
Site Layout Plan

SCALE	1:15000 @ A4	DATE	APR 2017	
CHECK	JF	DRAWN	JW	
JOB No.	MA16034	FIGURE NO.	1	REV
				-




LEGEND:

- PROJECT BOUNDARY
- AIR QUALITY MONITORING STATION



Agreement No. CE/59/2015 (EP)
 Environmental Team for Tseung Kwan O - Lam Tin Tunnel -
 Design and Construction
 Air Quality Monitoring Stations

SCALE	1:15000 @ A4	DATE	APR 2017	
CHECK	JF	DRAWN	JW	
JOB No.	MA16034	FIGURE NO.	2	REV
				-




LEGEND:

- PROJECT BOUNDARY
- NOISE MONITORING STATION



Agreement No. CE/59/2015 (EP)
 Environmental Team for Tseung Kwan O - Lam Tin Tunnel -
 Design and Construction
 Noise Monitoring Stations

SCALE	1:15000 @ A4	DATE	APR 2017	
CHECK	JF	DRAWN	JW	
JOB No.	MA16034	FIGURE NO.	3	REV
			-	



LEGEND:

	SITE BOUNDARY
	STREAM
	SAMPLING LOCATIONS FOR GROUNDWATER QUALITY
	SAMPLING LOCATIONS FOR GROUNDWATER LEVEL



Agreement No. CE/59/2015 (EP)
 Environmental Team for Tseung Kwan O - Lam Tin Tunnel -
 Design and Construction
 Location of Streams for Groundwater Quality and Groundwater Level Monitoring

SCALE	1:10000 @ A4	DATE	APR 2017	
CHECK	JF	DRAWN	JW	
JOB No.	MA16034	FIGURE NO.	4	REV
				-



CINOTECH

Cinotech Consultants Limited

Agreement No. CE/59/2015 (EP)
 Environmental Team for Tseung Kwan O – Lam Tin Tunnel –
 Design and Construction

Locations of Water Quality Monitoring Stations

SCALE	N.T.S	DATE	AUG 2016	
CHECK	JF	DRAWN	JW	
PROJECT NO.	MA16034	FIGURE NO.	5	REV —




Title Agreement No. CE/59/2015 (EP)
 Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction
 Locations of Landfill Gas Monitoring

Scale N.T.S
 Date Dec-16

Project No. MA16034
 Figure 6





Title Agreement No. CE/59/2015 (EP)
 Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction
 Location of Post-translocation Coral Monitoring

Scale N.T.S
 Date Mar-17

Project No. MA16034
 Figure 7





Cha Kwo Ling Tin Hau Temple




Child Giving Rock

No works in this area (in blue color) in the reporting peiod.

Temporary Location of Vibration Monitoring

LEGEND

- - - SITE BOUNDARY
- - - 100M FROM THE CHA KWO LING TIN HAU TEMPLE
- CHA KWO LING TIN HAU TEMPLE
- ⊕ VIBRATION MONITORING POINT
- ⊗ BUILDING SETTLEMENT POINT
- ⊘ TILTMETER



Title Agreement No. CE/59/2015 (EP)
Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction

Scale N.T.S

Project No. MA16034

Locations of Monitoring for Cultural Heritage

Date Apr-17

Figure 8



**APPENDIX A
ACTION AND LIMIT LEVELS**

APPENDIX A – Action and Limit Levels**Air Quality*****1-hr TSP***

Monitoring Stations	Location	Action Level, $\mu\text{g}/\text{m}^3$	Limit Level, $\mu\text{g}/\text{m}^3$
AM1	Tin Hau Temple	275	500
AM2	Sai Tso Wan Recreation Ground	273	
AM3	Yau Lai Estate Bik Lai House	271	
AM4	Sitting-out Area at Cha Kwo Ling Village	278	
AM5(A)	Tseung Kwan O DSD Desilting Compound	273	
AM6(A)	Park Central, L1/F Open Space Area	285	

24-hr TSP

Monitoring Stations	Location	Action Level, $\mu\text{g}/\text{m}^3$	Limit Level, $\mu\text{g}/\text{m}^3$
AM1	Tin Hau Temple	173	500
AM2	Sai Tso Wan Recreation Ground	192	
AM3	Yau Lai Estate Bik Lai House	167	
AM4(A)	Cha Kwo Ling Public Cargo Working Area Administrative Office	210	
AM5(A)	Tseung Kwan O DSD Desilting Compound	175	
AM6(A)	Park Central, L1/F Open Space Area	165	

Noise

Time Period	Action Level	Limit Level
0700-1900 hrs on normal weekdays	When one documented complaint is received	75 dB(A) ⁽¹⁾
1900-2300 on all days and 0700-2300 on general holidays (including Sundays)		60/65/70 dB(A) ⁽²⁾⁽³⁾
2300-0700 on all days		45/50/55 dB(A) ⁽²⁾⁽³⁾

¹ 70 dB(A) for schools and 65 dB(A) for schools during examination period.² Acceptable Noise Levels for Area Sensitivity Rating of A/B/C³ If works are to be carried out during restricted hours, the conditions stipulated in the construction noise permit issued by the Noise Control Authority have to be followed.

Water Quality***Groundwater***

Parameters	Action	Limit
DO in mg L ⁻¹	7.6	7.5
pH	6.0 – 8.9	6.0 – 9.0
BOD ₅ in mg L ⁻¹	2.0	2.0
TOC in mg L ⁻¹	4.3	4.9
Total Nitrogen in mg L ⁻¹	1.7	1.7
Ammonia-N in mg L ⁻¹	0.05	0.06
Total Phosphate in mg L ⁻¹	0.05	0.05
SS in mg L ⁻¹	5.5	6.2
Turbidity in NTU	2.2	2.4

Notes:

1. For pH, non-compliance of the water quality limits occurs when monitoring result is out of the range of the limits.
2. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
3. For turbidity, SS, 5-day biochemical oxygen demand (BOD₅), Total organic carbon (TOC), Total Nitrogen, Ammonia-N and Total Phosphate, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
4. All the figures given in the table are used for reference only and the EPD may amend the figures whenever it is considered as necessary.

Groundwater Level Monitoring

Drill Hole No.	38568-LDH1	TKO-LBH907
Action Level (mPD)	+74.65	+17.59

Marine Water Quality

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2, 4 and 5)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
SS in mg/L (See Note 2, 4 and 5)	<u>Stations G1-G4</u>		
	Surface	<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day	<u>6.9mg/L</u> or 130% of upstream control station's SS at the same tide of the same day
	<u>Stations M1-M5</u>		
	Surface	<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day
	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day
	<u>Station M6</u>		
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.
5. Refer to Appendix I – Marine Water Quality Monitoring Results and Graphical Presentations for results of upstream control stations at each tide on each day.

Ecology***Post-translocation Coral Monitoring***

Parameter	Action Level Definition	Limit Level Definition
Mortality	If during Impact Monitoring a 15% increase in the percentage of partial mortality on hard corals occurs at more than 20% of the tagged coral at any one Impact Monitoring Site that is not recorded at the Control Site, then the Action Level is exceeded.	If during the Impact Monitoring a 25% increase in the percentage of partial mortality occurs at more than 20% of the tagged coral at any one Impact Monitoring Site that is not recorded at the Control Site, then the Limit Level is exceeded.

Landfill Gas Monitoring

Parameter	Limit Level
Oxygen	<19%
	<18%
Methane	>10% LEL (i.e. > 0.5% by volume)
	>20% LEL (i.e. > 1% by volume)
Carbon Dioxide	>0.5%
	>1.5%

**APPENDIX B
COPIES OF CALIBRATION
CERTIFICATES**

High-Volume TSP Sampler

5-POINT CALIBRATION DATA SHEET

CINOTECH

File No. MA16034/08/0004

Station: AM1 - Tin Hau Temple Operator: HL
 Date: 17-Mar-17 Next Due Date: 16-May-17
 Equipment No.: A-01-05 Serial No. 10599

Ambient Condition			
Temperature, Ta (K)	290.6	Pressure, Pa (mmHg)	766.4

Orifice Transfer Standard Information					
Serial No.:	0993	Slope, mc (CFM)	0.0578	Intercept, bc	-0.04890
Last Calibration Date:	28-Feb-17	$mc \times Qstd + bc = [\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$			
Next Calibration Date:	27-Feb-18	$Qstd = \{[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2} - bc\} / mc$			

Calibration of TSP Sampler					
Calibration Point	Orifice			HVS	
	ΔH (orifice), in. of water	[ΔH x (Pa/760) x (298/Ta)] ^{1/2}	Qstd (CFM) X - axis	ΔW (HVS), in. of water	[ΔW x (Pa/760) x (298/Ta)] ^{1/2} Y-axis
1	13.4	3.72	65.28	7.4	2.77
2	10.2	3.25	57.06	5.6	2.41
3	8.6	2.98	52.46	4.8	2.23
4	5.5	2.38	42.13	3.3	1.85
5	3.2	1.82	32.33	2.1	1.47

By Linear Regression of Y on X

Slope, mw = 0.0388 Intercept, bw : 0.2094
 Correlation coefficient* = 0.9994

*If Correlation Coefficient < 0.990, check and recalibrate.

Set Point Calculation	
From the TSP Field Calibration Curve, take Qstd = 43 CFM	
From the Regression Equation, the "Y" value according to	
$mw \times Qstd + bw = [\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$	
Therefore, Set Point; W = (mw x Qstd + bw) ² x (760 / Pa) x (Ta / 298) =	<u>3.41</u>

Remarks: _____

Conducted by: he Signature: he Date: 17/3/2017
 Checked by: Wk Tang Signature: Wk Tang Date: 17/3/17

High-Volume TSP Sampler

5-POINT CALIBRATION DATA SHEET

CINOTECH

File No. MA16034/08/0004

Station: AM2 - Sai Tso Wan Recreation Ground Operator: HL
 Date: 13-Mar-17 Next Due Date: 12-May-17
 Equipment No.: A-01-08 Serial No. 1287

Ambient Condition			
Temperature, Ta (K)	291.3	Pressure, Pa (mmHg)	764.1

Orifice Transfer Standard Information					
Serial No.:	0993	Slope, mc (CFM)	0.0578	Intercept, bc	-0.04890
Last Calibration Date:	28-Feb-17	$mc \times Qstd + bc = [\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$			
Next Calibration Date:	27-Feb-18	$Qstd = \{[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2} - bc\} / mc$			

Calibration of TSP Sampler					
Calibration Point	Orifice			HVS	
	ΔH (orifice), in. of water	$[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$	Qstd (CFM) X-axis	ΔW (HVS), in. of water	$[\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$ Y-axis
1	13.3	3.70	64.86	7.5	2.78
2	10.8	3.33	58.54	6.2	2.53
3	8.6	2.97	52.33	5.0	2.27
4	5.3	2.33	41.26	3.3	1.84
5	3.3	1.84	32.74	2.0	1.43

By Linear Regression of Y on X

Slope, $mw =$ 0.0413 Intercept, $bw =$ 0.1043
 Correlation coefficient* = 0.9993

*If Correlation Coefficient < 0.990, check and recalibrate.

Set Point Calculation

From the TSP Field Calibration Curve, take Qstd = 43 CFM

From the Regression Equation, the "Y" value according to

$$mw \times Qstd + bw = [\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$$

Therefore, Set Point; $W = (mw \times Qstd + bw)^2 \times (760 / Pa) \times (Ta / 298) =$ 3.44

Remarks: _____

Conducted by: LEE MAN MEI Signature: lee Date: 13-3-2017
 Checked by: W.K. TANG Signature: W.K. Tang Date: 13/3/17

High-Volume TSP Sampler

5-POINT CALIBRATION DATA SHEET

CINOTECH

File No. MA16034/03/0004

Station: AM3 - Yau Lai Estate, Bik Lai House Operator: HL
 Date: 7-Mar-17 Next Due Date: 6-May-17
 Equipment No.: A-01-03 Serial No. 10379

Ambient Condition			
Temperature, Ta (K)	290.2	Pressure, Pa (mmHg)	766.1

Orifice Transfer Standard Information					
Serial No.:	0993	Slope, mc (CFM)	0.0578	Intercept, bc	-0.04890
Last Calibration Date:	28-Feb-17	$mc \times Qstd + bc = [\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$			
Next Calibration Date:	27-Feb-18	$Qstd = \{[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2} - bc\} / mc$			

Calibration of TSP Sampler					
Calibration Point	Orifice			HVS	
	ΔH (orifice), in. of water	$[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$	Qstd (CFM) X - axis	ΔW (HVS), in. of water	$[\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$ Y-axis
1	12.7	3.63	63.60	7.0	2.69
2	10.5	3.30	57.91	5.9	2.47
3	7.6	2.80	49.39	4.4	2.13
4	5.4	2.36	41.77	3.3	1.85
5	3.4	1.88	33.32	2.0	1.44

By Linear Regression of Y on X

Slope, mw = 0.0409 Intercept, bw = 0.1070
 Correlation coefficient* = 0.9988

*If Correlation Coefficient < 0.990, check and recalibrate.

Set Point Calculation	
From the TSP Field Calibration Curve, take Qstd = 43 CFM	
From the Regression Equation, the "Y" value according to	
$mw \times Qstd + bw = [\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$	
Therefore, Set Point; W = $(mw \times Qstd + bw)^2 \times (760 / Pa) \times (Ta / 298) =$ <u>3.36</u>	

Remarks: _____

Conducted by: W.E. MAN Signature: W.E. Man Date: 7/3/2017
 Checked by: W.K. Tang Signature: W.K. Tang Date: 7/13/17

High-Volume TSP Sampler

5-POINT CALIBRATION DATA SHEET

CINOTECH

File No. MA16034/54/0004

Station: AM4(A) - Cha Kwo Ling Public Cargo Working Area Administrative Office Operator: HL

Date: 17-Mar-17 Next Due Date: 16-May-17

Equipment No.: A-01-54 Serial No. 1536

Ambient Condition			
Temperature, Ta (K)	291.3	Pressure, Pa (mmHg)	764.4

Orifice Transfer Standard Information					
Serial No.:	0993	Slope, mc (CFM)	0.0578	Intercept, bc	-0.04890
Last Calibration Date:	28-Feb-17	$mc \times Qstd + bc = [\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$			
Next Calibration Date:	27-Feb-18	$Qstd = \{[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2} - bc\} / mc$			

Calibration of TSP Sampler					
Calibration Point	Orifice			HVS	
	ΔH (orifice), in. of water	[ΔH x (Pa/760) x (298/Ta)] ^{1/2}	Qstd (CFM) X - axis	ΔW (HVS), in. of water	[ΔW x (Pa/760) x (298/Ta)] ^{1/2} Y-axis
1	17.7	4.27	74.71	10.4	3.27
2	13.0	3.66	64.15	7.9	2.85
3	10.7	3.32	58.28	6.4	2.57
4	6.8	2.65	46.63	4.2	2.08
5	4.2	2.08	36.83	2.8	1.70

By Linear Regression of Y on X

Slope, mw = 0.0419 Intercept, bw = 0.1393

Correlation coefficient* = 0.9996

*If Correlation Coefficient < 0.990, check and recalibrate.

Set Point Calculation

From the TSP Field Calibration Curve, take Qstd = 43 CFM

From the Regression Equation, the "Y" value according to

$$mw \times Qstd + bw = [\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$$

Therefore, Set Point; W = $(mw \times Qstd + bw)^2 \times (760 / Pa) \times (Ta / 298) =$ 3.67

Remarks: _____

Conducted by: LEE MAN WAI Signature: Lee Date: 17-3-2017

Checked by: W.K. TANG Signature: W.K. Tang Date: 17/3/17

High-Volume TSP Sampler

5-POINT CALIBRATION DATA SHEET

CINOTECH

File No. MA16034/37/0004

Station: AM5(A) - DSD Desilting Compound Operator: HL
 Date: 13-Mar-17 Next Due Date: 12-May-17
 Equipment No.: A-01-37 Serial No. 1704

Ambient Condition			
Temperature, Ta (K)	292	Pressure, Pa (mmHg)	764.5

Orifice Transfer Standard Information					
Serial No.:	0993	Slope, mc (CFM)	0.0578	Intercept, bc	-0.04890
Last Calibration Date:	28-Feb-17	$mc \times Qstd + bc = [\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$			
Next Calibration Date:	27-Feb-18	$Qstd = \{[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2} - bc\} / mc$			

Calibration of TSP Sampler					
Calibration Point	Orifice			HVS	
	ΔH (orifice), in. of water	$[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$	Qstd (CFM) X - axis	ΔW (HVS), in. of water	$[\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$ Y-axis
1	17.1	4.19	73.37	9.0	3.04
2	13.6	3.74	65.52	7.1	2.70
3	10.7	3.31	58.21	5.9	2.46
4	6.4	2.56	45.21	3.5	1.90
5	4.3	2.10	37.21	2.3	1.54

By Linear Regression of Y on X

Slope, mw = 0.0412 Intercept, bw = 0.0214
 Correlation coefficient* = 0.9991

*If Correlation Coefficient < 0.990, check and recalibrate.

Set Point Calculation	
From the TSP Field Calibration Curve, take Qstd = 43 CFM	
From the Regression Equation, the "Y" value according to	
$mw \times Qstd + bw = [\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$	
Therefore, Set Point; W = (mw x Qstd + bw) ² x (760 / Pa) x (Ta / 298) =	<u>3.14</u>

Remarks: _____

Conducted by: LEE MAN YEE Signature: he Date: 13-3-2017
 Checked by: W.K. TANG Signature: Kashi Date: 13/3/17

High-Volume TSP Sampler

5-POINT CALIBRATION DATA SHEET

CINOTECH

File No. MA16034/07/0004

Station AM6 - Park Central Operator: WK
 Date: 31-Mar-17 Next Due Date: 30-May-17
 Equipment No.: A-01-07 Serial No. 10592

Ambient Condition			
Temperature, Ta (K)	294.4	Pressure, Pa (mmHg)	763.2

Orifice Transfer Standard Information			
Serial No.:	0993	Slope, mc (CFM)	0.0578
		Intercept, bc	-0.04890
Last Calibration Date:	28-Feb-17	$mc \times Qstd + bc = [\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$	
Next Calibration Date:	27-Feb-18	$Qstd = \{[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2} - bc\} / mc$	

Calibration of TSP Sampler					
Calibration Point	Orifice			HVS	
	ΔH (orifice), in. of water	$[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$	Qstd (CFM) X - axis	ΔW (HVS), in. of water	$[\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$ Y-axis
1	11.8	3.46	60.79	7.5	2.76
2	9.7	3.14	55.20	5.9	2.45
3	7.4	2.74	48.32	4.7	2.19
4	5.2	2.30	40.64	3.3	1.83
5	3.3	1.83	32.55	2.1	1.46

By Linear Regression of Y on X

Slope, mw = 0.0452 Intercept, bw : -0.0105
 Correlation coefficient* = 0.9990

*If Correlation Coefficient < 0.990, check and recalibrate.

Set Point Calculation

From the TSP Field Calibration Curve, take Qstd = 43 CFM

From the Regression Equation, the "Y" value according to

$$mw \times Qstd + bw = [\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$$

Therefore, Set Point; W = $(mw \times Qstd + bw)^2 \times (760 / Pa) \times (Ta / 298) =$ 3.68

Remarks: _____

Conducted by: Wk Tang Signature: [Signature]
 Checked by: [Signature] Signature: _____

Date: 31/3/17
 Date: 31 March 2017



TISCH ENVIRONMENTAL, INC.
 145 SOUTH MIAMI AVE
 VILLAGE OF CLEVELS, OH
 45002
 513.467.9000
 877.263.7610 TOLL FREE
 513.467.9009 FAX

ORIFICE TRANSFER STANDARD CERTIFICATION WORKSHEET TE-5025A

Date - Feb 28, 2017 Rootsmeter S/N 0438320 Ta (K) - 294
 Operator Tisch Orifice I.D. - 0993 Pa (mm) - 750.57

PLATE OR Run #	VOLUME START (m3)	VOLUME STOP (m3)	DIFF VOLUME (m3)	DIFF TIME (min)	METER	ORFICE
					DIFF Hg (mm)	DIFF H2O (in.)
1	NA	NA	1.00	1.3860	3.2	2.00
2	NA	NA	1.00	0.9910	6.4	4.00
3	NA	NA	1.00	0.8840	7.9	5.00
4	NA	NA	1.00	0.8430	8.7	5.50
5	NA	NA	1.00	0.6970	12.6	8.00

DATA TABULATION

Vstd	(x axis) Qstd	(y axis)	Va	(x axis) Qa	(y axis)
0.9967	0.7191	1.4149	0.9957	0.7184	0.8851
0.9925	1.0015	2.0010	0.9915	1.0005	1.2517
0.9904	1.1204	2.2372	0.9894	1.1192	1.3995
0.9894	1.1737	2.3464	0.9884	1.1725	1.4678
0.9842	1.4120	2.8299	0.9832	1.4106	1.7702
Qstd slope (m) = 2.04055			Qa slope (m) = 1.27776		
intercept (b) = -0.04890			intercept (b) = -0.03059		
coefficient (r) = 0.99995			coefficient (r) = 0.99995		
y axis = SQRT [H2O (Pa/760) (298/Ta)]			y axis = SQRT [H2O (Ta/Pa)]		

CALCULATIONS

Vstd = Diff. Vol [(Pa-Diff. Hg)/760] (298/Ta)
 Qstd = Vstd/Time

Va = Diff Vol [(Pa-Diff Hg)/Pa]
 Qa = Va/Time

For subsequent flow rate calculations:

Qstd = 1/m{ [SQRT (H2O (Pa/760) (298/Ta))] - b}
 Qa = 1/m{ [SQRT H2O (Ta/Pa)] - b}

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/170217
Date of Issue:	2017-02-20
Date Received:	2017-02-17
Date Tested:	2017-02-17
Date Completed:	2017-02-20
Next Due Date:	2017-08-19

ATTN: Miss Mei Ling Tang

Page: 1 of 2

Certificate of Calibration

Item for calibration:

Description : Weather Monitor II
Manufacturer : Davis Instruments
Model No. : 7440
Serial No. : MC01010A44

Test conditions:

Room Temperature : 21 degree Celsius
Relative Humidity : 60 %

Test Specifications:


1. Performance check of anemometer
2. Performance check of wind direction sensor

Methodology:

In-house method with reference anemometer (RS232 Integral Vane Digital Anemometer)

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



PATRICK TSE
Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/A/170303A
Date of Issue:	2017-03-06
Date Received:	2017-03-03
Date Tested:	2017-03-03
Date Completed:	2017-03-06
Next Due Date:	2017-05-05

ATTN: Mr. W. K. Tang

Page: 1 of 1

Certificate of Calibration

Item for Calibration:

Description	: Laser Dust Monitor
Manufacturer	: Sibata
Model No.	: LD-3B
Serial No.	: 853944
Sensitivity (K) 1 CPM	: 0.001 mg/m ³
Sen. Adjustment Scale Setting	: 685 CPM
Equipment No.	: A-02-04

Test Conditions:

Room Temperature	: 23 degree Celsius
Relative Humidity	: 64 %

Test Specifications & Methodology:

1. Instruction and Operation Manual High Volume Sampler, Andersen Samplers, Inc.
2. In-house method in according to the instruction manual: The Laser Dust Monitor was compared with a calibrated High Volume Sampler and the result was used to generate the Correlation Factor (CF) between the Laser Dust Monitor and High Volume Sampler.

Results:

Correlation Factor (CF)	0.0034
-------------------------	--------

PREPARED AND CHECKED BY:
For and On Behalf of **WELLAB Ltd.**


PATRICK TSE
Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/A/170303B
Date of Issue:	2017-03-06
Date Received:	2017-03-03
Date Tested:	2017-03-03
Date Completed:	2017-03-06
Next Due Date:	2017-05-05

ATTN: Mr. W. K. Tang

Page: 1 of 1

Certificate of Calibration

Item for Calibration:

Description	: Laser Dust Monitor
Manufacturer	: Sibata
Model No.	: LD-3B
Serial No.	: 014750
Sensitivity (K) 1 CPM	: 0.001 mg/m ³
Sen. Adjustment Scale Setting	: 790 CPM
Equipment No.	: A-02-06

Test Conditions:

Room Temperature	: 23 degree Celsius
Relative Humidity	: 64 %

Test Specifications & Methodology:

1. Instruction and Operation Manual High Volume Sampler, Andersen Samplers, Inc.
2. In-house method in according to the instruction manual: The Laser Dust Monitor was compared with a calibrated High Volume Sampler and the result was used to generate the Correlation Factor (CF) between the Laser Dust Monitor and High Volume Sampler.

Results:

Correlation Factor (CF)	0.0034
-------------------------	--------

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**


PATRICK TSE
Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/A/170303C
Date of Issue:	2017-03-06
Date Received:	2017-03-03
Date Tested:	2017-03-03
Date Completed:	2017-03-06
Next Due Date:	2017-05-05

ATTN: Mr. W. K. Tang

Page: 1 of 1

Certificate of Calibration

Item for Calibration:

Description	: Laser Dust Monitor
Manufacturer	: Sibata
Model No.	: LD-3B
Serial No.	: 541146
Sensitivity (K) 1 CPM	: 0.001 mg/m ³
Sen. Adjustment Scale Setting	: 625 CPM
Equipment No.	: A-02-07

Test Conditions:

Room Temperature	: 23 degree Celsius
Relative Humidity	: 64 %

Test Specifications & Methodology:

1. Instruction and Operation Manual High Volume Sampler, Andersen Samplers, Inc.
2. In-house method in according to the instruction manual: The Laser Dust Monitor was compared with a calibrated High Volume Sampler and the result was used to generate the Correlation Factor (CF) between the Laser Dust Monitor and High Volume Sampler.

Results:

Correlation Factor (CF)	0.0034
-------------------------	--------

PREPARED AND CHECKED BY:
For and On Behalf of **WELLAB Ltd.**


PATRICK TSE
Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/170302C
Date of Issue:	2017-03-04
Date Received:	2017-03-02
Date Tested:	2017-03-02
Date Completed:	2017-03-04
Next Due Date:	2017-05-03

ATTN: Mr. W. K. Tang

Page: 1 of 1

Certificate of Calibration

Item for Calibration:

Description	: Laser Dust Monitor
Manufacturer	: Sibata
Model No.	: LD-3B
Serial No.	: 095029
Sensitivity (K) 1 CPM	: 0.001 mg/m ³
Sen. Adjustment Scale Setting	: 551 CPM
Equipment No.	: A-02-10

Test Conditions:

Room Temperature	: 22 degree Celsius
Relative Humidity	: 61 %

Test Specifications & Methodology:

1. Instruction and Operation Manual High Volume Sampler, Andersen Samplers, Inc.
2. In-house method in according to the instruction manual: The Laser Dust Monitor was compared with a calibrated High Volume Sampler and the result was used to generate the Correlation Factor (CF) between the Laser Dust Monitor and High Volume Sampler.

Results:

Correlation Factor (CF)	0.0037
-------------------------	--------

PREPARED AND CHECKED BY:
For and On Behalf of **WELLAB Ltd.**


PATRICK TSE
Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/170419A
Date of Issue:	2017-04-22
Date Received:	2017-04-19
Date Tested:	2017-04-19
Date Completed:	2017-04-22
Next Due Date:	2017-06-21

ATTN: Mr. W. K. Tang

Page: 1 of 1

Certificate of Calibration

Item for Calibration:

Description	: Handheld Particle Counter
Manufacturer	: Hal Technology
Model No.	: Hal-HPC300
Serial No.	: 3020408
Flow rate	: 0.1 cfm
Zero Count Test	: 0 count per 5 minutes
Equipment No.	: A-26-01

Test Conditions:

Room Temperature	: 22 degree Celsius
Relative Humidity	: 62 %

Test Specifications & Methodology:

1. Instruction and Operation Manual High Volume Sampler, Andersen Samplers, Inc.
2. In-house method in according to the instruction manual: The Dust Monitor was compared with a calibrated High Volume Sampler and the result was used to generate the Correlation Factor (CF) between the Dust Monitor and High Volume Sampler.

Results:

Correlation Factor (CF)	1.137
-------------------------	-------

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



PATRICK TSE

Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/170210
Date of Issue:	2017-02-13
Date Received:	2017-02-10
Date Tested:	2017-02-10
Date Completed:	2017-02-13
Next Due Date:	2017-04-12

ATTN: Mr. W. K. Tang

Page: 1 of 1

Certificate of Calibration

Item for Calibration:

Description	: Handheld Particle Counter
Manufacturer	: Hal Technology
Model No.	: Hal-HPC300
Serial No.	: 3020411
Flow rate	: 0.1 cfm
Zero Count Test	: 0 count per 5 minutes
Equipment No.	: A-26-04

Test Conditions:

Room Temperature	: 23 degree Celsius
Relative Humidity	: 65 %

Test Specifications & Methodology:

1. Instruction and Operation Manual High Volume Sampler, Andersen Samplers, Inc.
2. In-house method in according to the instruction manual: The Laser Dust Monitor was compared with a calibrated High Volume Sampler and the result was used to generate the Correlation Factor (CF) between the Laser Dust Monitor and High Volume Sampler.

Results:

Correlation Factor (CF)	1.159
-------------------------	-------

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



PATRICK TSE
Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/170407B
Date of Issue:	2017-04-10
Date Received:	2017-04-07
Date Tested:	2017-04-07
Date Completed:	2017-04-10
Next Due Date:	2017-06-09

ATTN: Mr. W. K. Tang

Page: 1 of 1

Certificate of Calibration

Item for Calibration:

Description	: Handheld Particle Counter
Manufacturer	: Hal Technology
Model No.	: Hal-HPC301
Serial No.	: 3011701016
Flow rate	: 0.1 cfm
Zero Count Test	: 0 count per 5 minutes
Equipment No.	: A-27-03

Test Conditions:

Room Temperature	: 22 degree Celsius
Relative Humidity	: 61 %

Test Specifications & Methodology:

1. Instruction and Operation Manual High Volume Sampler, Andersen Samplers, Inc.
2. In-house method in according to the instruction manual: The Dust Monitor was compared with a calibrated High Volume Sampler and the result was used to generate the Correlation Factor (CF) between the Dust Monitor and High Volume Sampler.

Results:

Correlation Factor (CF)	1.167
-------------------------	-------

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



PATRICK TSE
Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/170407C
Date of Issue:	2017-04-10
Date Received:	2017-04-07
Date Tested:	2017-04-07
Date Completed:	2017-04-10
Next Due Date:	2017-06-09

ATTN: Mr. W. K. Tang

Page: 1 of 1

Certificate of Calibration

Item for Calibration:

Description : Handheld Particle Counter
Manufacturer : Hal Technology
Model No. : Hal-HPC301
Serial No. : 3011701017
Flow rate : 0.1 cfm
Zero Count Test : 0 count per 5 minutes
Equipment No. : A-27-04

Test Conditions:

Room Temperature : 22 degree Celsius
Relative Humidity : 61 %

Test Specifications & Methodology:

1. Instruction and Operation Manual High Volume Sampler, Andersen Samplers, Inc.
2. In-house method in according to the instruction manual: The Dust Monitor was compared with a calibrated High Volume Sampler and the result was used to generate the Correlation Factor (CF) between the Dust Monitor and High Volume Sampler.

Results:

Correlation Factor (CF)	1.303
-------------------------	-------

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**


PATRICK TSE
Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/170407D
Date of Issue:	2017-04-10
Date Received:	2017-04-07
Date Tested:	2017-04-07
Date Completed:	2017-04-10
Next Due Date:	2017-06-09

ATTN: Mr. W. K. Tang

Page: 1 of 1

Certificate of Calibration

Item for Calibration:

Description : Handheld Particle Counter
Manufacturer : Hal Technology
Model No. : Hal-HPC301
Serial No. : 3011701018
Flow rate : 0.1 cfm
Zero Count Test : 0 count per 5 minutes
Equipment No. : A-27-05

Test Conditions:

Room Temperature : 22 degree Celsius
Relative Humidity : 61 %

Test Specifications & Methodology:

1. Instruction and Operation Manual High Volume Sampler, Andersen Samplers, Inc.
2. In-house method in according to the instruction manual: The Dust Monitor was compared with a calibrated High Volume Sampler and the result was used to generate the Correlation Factor (CF) between the Dust Monitor and High Volume Sampler.

Results:

Correlation Factor (CF)	1.133
-------------------------	-------

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**


PATRICK TSE
Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/170407E
Date of Issue:	2017-04-10
Date Received:	2017-04-07
Date Tested:	2017-04-07
Date Completed:	2017-04-10
Next Due Date:	2017-06-09

ATTN: Mr. W. K. Tang

Page: 1 of 1

Certificate of Calibration

Item for Calibration:

Description	: Handheld Particle Counter
Manufacturer	: Hal Technology
Model No.	: Hal-HPC301
Serial No.	: 3011701014
Flow rate	: 0.1 cfm
Zero Count Test	: 0 count per 5 minutes
Equipment No.	: A-27-06

Test Conditions:

Room Temperature	: 22 degree Celsius
Relative Humidity	: 61 %

Test Specifications & Methodology:

1. Instruction and Operation Manual High Volume Sampler, Andersen Samplers, Inc.
2. In-house method in according to the instruction manual: The Dust Monitor was compared with a calibrated High Volume Sampler and the result was used to generate the Correlation Factor (CF) between the Dust Monitor and High Volume Sampler.

Results:

Correlation Factor (CF)	1.143
-------------------------	-------

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



PATRICK TSE
Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/170407H
Date of Issue:	2017-04-10
Date Received:	2017-04-07
Date Tested:	2017-04-07
Date Completed:	2017-04-10
Next Due Date:	2017-06-09

ATTN: Mr. W. K. Tang

Page: 1 of 1

Certificate of Calibration

Item for Calibration:

Description : Handheld Particle Counter
 Manufacturer : Hal Technology
 Model No. : Hal-HPC301
 Serial No. : 3011701015
 Flow rate : 0.1 cfm
 Zero Count Test : 0 count per 5 minutes
 Equipment No. : A-27-09

Test Conditions:

Room Temperature : 22 degree Celsius
 Relative Humidity : 61 %

Test Specifications & Methodology:

1. Instruction and Operation Manual High Volume Sampler, Andersen Samplers, Inc.
2. In-house method in according to the instruction manual: The Dust Monitor was compared with a calibrated High Volume Sampler and the result was used to generate the Correlation Factor (CF) between the Dust Monitor and High Volume Sampler.

Results:

Correlation Factor (CF)	1.222
-------------------------	-------

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



PATRICK TSE
Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/N/160917B
Date of Issue:	2016-09-19
Date Received:	2016-09-17
Date Tested:	2016-09-17
Date Completed:	2016-09-19
Next Due Date:	2017-09-18

ATTN: Mr. W.K. Tang

Page: 1 of 1

Certificate of Calibration

Item for calibration:

Description	: 'SVANTEK' Integrating Sound Level Meter
Manufacturer	: SVANTEK
Model No.	: SVAN 955
Serial No.	: 12553
Microphone No.	: 35222
Equipment No.	: N-08-02

Test conditions:

Room Temperature	: 24 degree Celsius
Relative Humidity	: 57%

Test Specifications:

Performance checking at 94 and 114 dB

Methodology:

In-house method, according to manufacturer instruction manual

Results:

Reference Set Point, dB	Instrument Readings, dB
94	94.0
114	114.0

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**


PATRICK TSE
Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/N/160819B
Date of Issue:	2016-08-22
Date Received:	2016-08-19
Date Tested:	2016-08-19
Date Completed:	2016-08-22
Next Due Date:	2017-08-21

ATTN: Mr. W.K. Tang

Page: 1 of 1

Certificate of Calibration

Item for calibration:

Description	: 'SVANTEK' Integrating Sound Level Meter
Manufacturer	: SVANTEK
Model No.	: SVAN 957
Serial No.	: 21459
Microphone No.	: 43676
Equipment No.	: N-08-08

Test conditions:

Room Temperature	: 24 degree Celsius
Relative Humidity	: 58%

Test Specifications:

Performance checking at 94 and 114 dB

Methodology:

In-house method, according to manufacturer instruction manual

Results:

Reference Set Point, dB	Instrument Readings, dB
94	94.0
114	114.0

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**


PATRICK TSE
Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/N/160819C
Date of Issue:	2016-08-22
Date Received:	2016-08-19
Date Tested:	2016-08-19
Date Completed:	2016-08-22
Next Due Date:	2017-08-21

ATTN: Mr. W.K. Tang

Page: 1 of 1

Certificate of Calibration

Item for calibration:

Description	: 'SVANTEK' Integrating Sound Level Meter
Manufacturer	: SVANTEK
Model No.	: SVAN 957
Serial No.	: 21460
Microphone No.	: 43679
Equipment No.	: N-08-09

Test conditions:

Room Temperature	: 24 degree Celsius
Relative Humidity	: 58%

Test Specifications:

Performance checking at 94 and 114 dB

Methodology:

In-house method, according to manufacturer instruction manual

Results:

Reference Set Point, dB	Instrument Readings, dB
94	94.0
114	114.0

PREPARED AND CHECKED BY:
For and On Behalf of **WELLAB Ltd.**


PATRICK TSE
Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/N/161128
Date of Issue:	2016-11-30
Date Received:	2016-11-28
Date Tested:	2016-11-28
Date Completed:	2016-11-30
Next Due Date:	2017-11-29

ATTN: Mr. W.K. Tang

Page: 1 of 1

Certificate of Calibration

Item for calibration:

Description	: 'SVANTEK' Integrating Sound Level Meter
Manufacturer	: SVANTEK
Model No.	: SVAN 957
Serial No.	: 23853
Microphone No.	: 48530
Equipment No.	: N-08-10

Test conditions:

Room Temperature	: 21 degree Celsius
Relative Humidity	: 66%

Test Specifications:

Performance checking at 94 and 114 dB

Methodology:


In-house method, according to manufacturer instruction manual

Results:

Reference Set Point, dB	Instrument Readings, dB
94	94.0
114	114.0

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**


PATRICK TSE
Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	CN/160919
Date of Issue:	2016-09-21
Date Received:	2016-09-19
Date Tested:	2016-09-19
Date Completed:	2016-09-21
Next Due Date:	2017-09-20

ATTN: Mr. W.K. Tang

Page: 1 of 1

Certificate of Calibration

Item for calibration:

Description	: 'SVANTEK' Integrating Sound Level Meter
Manufacturer	: SVANTEK
Model No.	: SVAN 977
Serial No.	: 45482
Microphone No.	: 63626
Equipment No.	: N-08-14

Test conditions:

Room Temperature	: 22 degree Celsius
Relative Humidity	: 56%

Test Specifications:

Performance checking at 94 and 114 dB

Methodology:

In-house method, according to manufacturer instruction manual

Results:

Reference Set Point, dB	Instrument Readings, dB
94	94.0
114	114.0

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



PATRICK TSE
Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/N/161216
Date of Issue:	2016-12-19
Date Received:	2016-12-16
Date Tested:	2016-12-16
Date Completed:	2016-12-19
Next Due Date:	2017-12-15

ATTN: Mr. W. K. Tang

Page: 1 of 1

Certificate of Calibration

Item for calibration:

Description	: Sound & Vibration Analyser
Manufacturer	: BSWA
Model No.	: BSWA 801
Serial No.	: 35924
Equipment No.	: N-13-01

Test conditions:

Room Temperature	: 21 degree Celsius
Relative Humidity	: 60 %

Test Specifications:

Performance checking at 94 and 114 dB

Methodology:

In-house method, according to manufacturer instruction manual

Results:

Reference Set Point, dB	Instrument Readings, dB
94	94.0
114	114.0

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



PATRICK TSE

Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/N/160930A
Date of Issue:	2016-10-03
Date Received:	2016-09-30
Date Tested:	2016-09-30
Date Completed:	2016-10-03
Next Due Date:	2017-10-02

ATTN: Mr. W.K. Tang

Page: 1 of 1

Item for calibration:

Description	: Acoustical Calibrator
Manufacturer	: SVANTEK
Model No.	: SV30A
Serial No.	: 24803
Equipment No.	: N-09-03

Test conditions:

Room Temperature	: 25 degree Celsius
Relative Humidity	: 60%

Methodology:

The Sound Level Calibrator has been calibrated in accordance with the documented procedures and using standard(s) and instrument(s) which are recommended by the manufacturer, or equivalent.

Results:

Sound Pressure Level (1kHz)	Measured SPL	Tolerance
At 94 dB SPL	94.0	94.0 ± 0.1 dB
At 114 dB SPL	114.0	114.0 ± 0.1 dB

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



PATRICK TSE
Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/N/160930B
Date of Issue:	2016-10-03
Date Received:	2016-09-30
Date Tested:	2016-09-30
Date Completed:	2016-10-03
Next Due Date:	2017-10-02

ATTN: Mr. W.K. Tang

Page: 1 of 1

Item for calibration:

Description	: Acoustical Calibrator
Manufacturer	: SVANTEK
Model No.	: SV30A
Serial No.	: 24791
Equipment No.	: N-09-04

Test conditions:

Room Temperature	: 25 degree Celsius
Relative Humidity	: 60%

Methodology:

The Sound Level Calibrator has been calibrated in accordance with the documented procedures and using standard(s) and instrument(s) which are recommended by the manufacturer, or equivalent.

Results:

Sound Pressure Level (1kHz)	Measured SPL	Tolerance
At 94 dB SPL	94.0	94.0 ± 0.1 dB
At 114 dB SPL	114.0	114.0 ± 0.1 dB

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**


PATRICK TSE
Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/N/160930C
Date of Issue:	2016-10-03
Date Received:	2016-09-30
Date Tested:	2016-09-30
Date Completed:	2016-10-03
Next Due Date:	2017-10-02

ATTN: Mr. W.K. Tang

Page: 1 of 1

Item for calibration:

Description	: Acoustical Calibrator
Manufacturer	: SVANTEK
Model No.	: SV30A
Serial No.	: 24780
Equipment No.	: N-09-05

Test conditions:

Room Temperature	: 25 degree Celsius
Relative Humidity	: 60%

Methodology:

The Sound Level Calibrator has been calibrated in accordance with the documented procedures and using standard(s) and instrument(s) which are recommended by the manufacturer, or equivalent.

Results:

Sound Pressure Level (1kHz)	Measured SPL	Tolerance
At 94 dB SPL	94.0	94.0 ± 0.1 dB
At 114 dB SPL	114.0	114.0 ± 0.1 dB

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



PATRICK TSE

Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/N/161104/1
Date of Issue:	2016-11-07
Date Received:	2016-11-04
Date Tested:	2016-11-04
Date Completed:	2016-11-07
Next Due Date:	2017-11-06

ATTN: Mr. W.K. Tang

Page: 1 of 1

Item for calibration:

Description	: Acoustical Calibrator
Manufacturer	: Brüel & Kjær
Model No.	: 4231
Serial No.	: 2326353
Equipment No.	: N-02-01

Test conditions:

Room Temperature	: 21 degree Celsius
Relative Humidity	: 62 %

Methodology:

The sound calibrator has been calibrated in accordance with the documented procedures and using standard(s) and instrument(s) which are recommended by the manufacturer, or equivalent.

Results:

Sound Pressure Level (1kHz)	Measured SPL	Tolerance
At 94 dB SPL	94.0	94.0 ± 0.1 dB
At 114 dB SPL	114.0	114.0 ± 0.1 dB

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



PATRICK TSE

Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
Room 1710, Technology Park,
18 On Lai Street,
Shatin, NT, Hong Kong

Test Report No.:	C/N/160819D
Date of Issue:	2016-08-22
Date Received:	2016-08-19
Date Tested:	2016-08-19
Date Completed:	2016-08-22
Next Due Date:	2017-08-21

ATTN: Mr. W.K. Tang

Page: 1 of 1

Certificate of Calibration

Item for calibration:

Description	: Acoustical Calibrator
Manufacturer	: Brüel & Kjær
Model No.	: 4231
Serial No.	: 2412367
Equipment No.	: N-02-03

Test conditions:

Room Temperature	: 24 degree Celsius
Relative Humidity	: 58%

Methodology:


The Sound Level Calibrator has been calibrated in accordance with the documented procedures and using standard(s) and instrument(s) which are recommended by the manufacturer, or equivalent.

Results:

Sound Pressure Level (1kHz)	Measured SPL	Tolerance
At 94 dB SPL	94.0	94.0 ± 0.1 dB
At 114 dB SPL	114.0	114.0 ± 0.1 dB

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



PATRICK TSE

Laboratory Manager

TEST REPORT

APPLICANT: Cinotech Consultants Limited
RM 1710, Technology Park,
18 On Lai Street,
Shatin, N.T., Hong Kong

Test Report No.:	C/W/170214
Date of Issue:	2017-02-14
Date Received:	2017-02-14
Date Tested:	2017-02-14
Date Completed:	2017-02-14
Next Due Date:	2017-05-13

ATTN: Miss Mei Ling Tang

Page: 1 of 2

Certificate of Calibration

Item for calibration:

Description	: Multiparameter Water Quality Probe
Manufacturer	: Aquaread Ltd
Model No.	: AP-2000-D
Serial No.	: 122252120
Equipment No.	: W.18.02

Test conditions:

Room Temperature	: 22 degree Celsius
Relative Humidity	: 55%

Test Specifications:

Performance checking for pH, Oxidation Reduction Potential (ORP), Dissolved oxygen (D.O.), Turbidity, Salinity, Conductivity and Temperature

Methodology:

According to manufacturer instruction manual, APHA 20e 4500-O C

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**


PATRICK TSE
Laboratory Manager

TEST REPORT

Test Report No.:	C/W/170214
Date of Issue:	2017-02-14
Date Received:	2017-02-14
Date Tested:	2017-02-14
Date Completed:	2017-02-14
Next Due Date:	2017-05-13
Page:	2 of 2

Certificate of Calibration

Results:

pH performance checking

	Instrument Readings (pH unit)	Acceptance Criteria	Comment
pH QC buffer 4.01	4.06	4.01 ± 0.10	Pass
pH QC buffer 6.86	6.87	6.86 ± 0.10	Pass
pH QC buffer 9.18	9.18	9.18 ± 0.10	Pass

ORP performance checking

	Instrument Readings (mV)	Acceptance Criteria	Comment
Zobell Solution	228.8	229 ± 10	Pass

D.O. performance checking

Winkler Titration value (mg/L)	Instrument Readings (mg/L)	Acceptance Criteria	Comment
8.40	8.45	Difference between Titration value and instrument reading <0.2mg/L	Pass

Turbidity check

Turbidity solution (NTU)	Instrument Readings (NTU)	Acceptance Criteria	Comment
0.00	0.00	0.00 ± 0.05	Pass
100	100	100 ± 5	Pass
1000	1000	1000 ± 100	Pass

Salinity Performance check

Salinity, ppt		Acceptable range	Comment
Instrument Reading	Theoretical Value		
30.1	30.0	30.0 ± 3	Pass

Conductivity performance checking

	Instrument Readings (mV)	Acceptance Criteria	Comment
KCl stock solution (2570 μ s/cm)	2586	2442-2698	Pass

Temperature performance checking

Reference thermometer- E431 Readings (°C)	Instrument Readings (°C)	Correction (°C)	Comment
24.1	24.0	+0.1	N/A

*****END OF REPORT*****

TEST REPORT

APPLICANT: Cinotech Consultants Limited
RM 1710, Technology Park,
18 On Lai Street,
Shatin, N.T., Hong Kong

Test Report No.:	C/W/170410
Date of Issue:	2017-04-10
Date Received:	2017-04-10
Date Tested:	2017-04-10
Date Completed:	2017-04-10
Next Due Date:	2017-07-09

ATTN: Miss Mei Ling Tang

Page: 1 of 2

Certificate of Calibration

Item for calibration:

Description	: Multiparameter Water Quality Probe
Manufacturer	: Aquaread Ltd
Model No.	: AP-2000-D
Serial No.	: 122251620
Equipment No.	: W.18.09

Test conditions:

Room Temperature	: 21 degree Celsius
Relative Humidity	: 59 %

Test Specifications:

Performance checking for pH, Oxidation Reduction Potential (ORP), Dissolved oxygen (D.O.), Turbidity, Salinity, Conductivity and Temperature

Methodology:

According to manufacturer instruction manual, APHA 20e 4500-O C

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



PATRICK TSE

Laboratory Manager

TEST REPORT

Test Report No.:	C/W/170410
Date of Issue:	2017-04-10
Date Received:	2017-04-10
Date Tested:	2017-04-10
Date Completed:	2017-04-10
Next Due Date:	2017-07-09

Page: 2 of 2

Certificate of Calibration

Results:

pH performance checking

	Instrument Readings (pH unit)	Acceptance Criteria	Comment
pH QC buffer 4.01	4.05	4.01 ± 0.10	Pass
pH QC buffer 6.86	6.88	6.86 ± 0.10	Pass
pH QC buffer 9.18	9.19	9.18 ± 0.10	Pass

ORP performance checking

	Instrument Readings (mV)	Acceptance Criteria	Comment
Zobell Solution	228.7	229 ± 10	Pass

D.O. performance checking

Winkler Titration value (mg/L)	Instrument Readings (mg/L)	Acceptance Criteria	Comment
8.40	8.43	Difference between Titration value and instrument reading <0.2mg/L	Pass

Turbidity check

Turbidity solution (NTU)	Instrument Readings (NTU)	Acceptance Criteria	Comment
0.00	0.00	0.00 ± 0.05	Pass
100	100	100 ± 5	Pass
1000	1000	1000 ± 100	Pass

Salinity Performance check

Salinity, ppt		Acceptable range	Comment
Instrument Reading	Theoretical Value	30.0 ± 3	Pass
30.3	30.0		

Conductivity performance checking

	Instrument Readings (mV)	Acceptance Criteria	Comment
KCl stock solution (2570 µs/cm)	2668	2442-2698	Pass

Temperature performance checking

Reference thermometer- E431 Readings (°C)	Instrument Readings (°C)	Correction (°C)	Comment
24.1	24.2	-0.1	N/A

*****END OF REPORT*****

TEST REPORT

APPLICANT: Cinotech Consultants Limited
RM 1710, Technology Park,
18 On Lai Street,
Shatin, N.T., Hong Kong

Test Report No.:	C/W/170410A
Date of Issue:	2017-04-10
Date Received:	2017-04-10
Date Tested:	2017-04-10
Date Completed:	2017-04-10
Next Due Date:	2017-07-09

ATTN: Miss Mei Ling Tang

Page: 1 of 2

Certificate of Calibration

Item for calibration:

Description	: Multiparameter Water Quality Probe
Manufacturer	: Aquaread Ltd
Model No.	: AP-2000-D
Serial No.	: 122251520
Equipment No.	: W.18.12

Test conditions:

Room Temperature	: 21 degree Celsius
Relative Humidity	: 59 %

Test Specifications:

Performance checking for pH, Oxidation Reduction Potential (ORP), Dissolved oxygen (D.O.), Turbidity, Salinity, Conductivity and Temperature

Methodology:

According to manufacturer instruction manual, APHA 20e 4500-O C

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



PATRICK TSE

Laboratory Manager

TEST REPORT

Test Report No.:	C/W/170410A
Date of Issue:	2017-04-10
Date Received:	2017-04-10
Date Tested:	2017-04-10
Date Completed:	2017-04-10
Next Due Date:	2017-07-09

Page: 2 of 2

Certificate of Calibration

Results:

pH performance checking

	Instrument Readings (pH unit)	Acceptance Criteria	Comment
pH QC buffer 4.01	4.03	4.01 ± 0.10	Pass
pH QC buffer 6.86	6.89	6.86 ± 0.10	Pass
pH QC buffer 9.18	9.15	9.18 ± 0.10	Pass

ORP performance checking

	Instrument Readings (mV)	Acceptance Criteria	Comment
Zobell Solution	228.3	229 ± 10	Pass

D.O. performance checking

Winkler Titration value (mg/L)	Instrument Readings (mg/L)	Acceptance Criteria	Comment
8.40	8.42	Difference between Titration value and instrument reading <0.2mg/L	Pass

Turbidity check

Turbidity solution (NTU)	Instrument Readings (NTU)	Acceptance Criteria	Comment
0.00	0.00	0.00 ± 0.05	Pass
100	100	100 ± 5	Pass
1000	1000	1000 ± 100	Pass

Salinity Performance check

Salinity, ppt		Acceptable range	Comment
Instrument Reading	Theoretical Value	30.0 ± 3	Pass
30.9	30.0		

Conductivity performance checking

	Instrument Readings (mV)	Acceptance Criteria	Comment
KCl stock solution (2570 µs/cm)	2644	2442-2698	Pass

Temperature performance checking

Reference thermometer- E431 Readings (°C)	Instrument Readings (°C)	Correction (°C)	Comment
24.1	24.2	-0.1	N/A

*****END OF REPORT*****



Calibration Certificate

Number: CCP/66453

Customer Name: Far East Metal & Hardware Company
Contact Person: Ms. Cherry Yiu
Detector Model: Crowcon Tetra Portable Gas Detector
Serial Number: 100486262/01-020

Sensor Type	Measuring Range	Alarm Level Settings				Test Gas	Result
		Alarm 1	Alarm 2	STEL	LTEL		
CH4	0 to 100%LEL	20	40	NA	NA	50%LEL	Passed
H2S	0 to 100ppm	5	10	10	5	25ppm	Passed
O2	0 to 25%v/v	19.0	23.5	NA	NA	18.0%v/v	Passed
CO	0 to 500ppm	30	100	200	30	100ppm	Passed

Next Calibration Date: 5th January 2018

Remarks:

1. "Passed" refers to the detector has been successfully calibrated to meet with manufacturer tolerance of the instrument & sensor specification and repeatability $\pm 5\%$ FSD.
2. The above equipment has been tested and calibrated in accordance with procedures referred to in Crowcon's BSI validated ISO9001 quality manual. Test equipment used has been factory calibrated and is traceable to national standards. Canned calibration gas has been prepared in accordance with BS4559 and original gas mixture has been prepared using NPL (UK) certified Gravimetric Standard. Gas generator has been tested to meet with: Mil Std 45662A / ANSI/NCSL Z540-1

Mark Chan

Technical Service Manager

6th January 2017



FireMark Hong Kong Limited
Flat A, 11/F., Hop Hing Industrial Building, 704 Castle Peak Road, Lai Chi Kok,
Kowloon, Hong Kong.
Tel : (852) 2751 8871 Fax : (852) 2751 880

APPENDIX C
WEATHER INFORMATION

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

I. General Information

Date	Mean Air Temperature (°C)	Mean Relative Humidity (%)	Precipitation (mm)
1 April 2017	15.5 – 23.9	70	0.2
2 April 2017	17.0 – 24.2	64	0.0
3 April 2017	17.5 – 24.5	68	0.0
4 April 2017	19.3 – 26.0	77	0.0
5 April 2017	20.9 – 27.9	81	0.0
6 April 2017	22.5 – 25.0	87	0.3
7 April 2017	22.6 – 27.9	84	0.0
8 April 2017	23.0 – 27.5	85	0.0
9 April 2017	23.5 – 27.9	84	0.0
10 April 2017	23.3 – 28.1	83	Trace
11 April 2017	22.2 – 27.8	90	0.6
12 April 2017	18.2 – 22.8	89	21.5
13 April 2017	18.8 – 21.5	80	Trace
14 April 2017	19.9 – 24.7	78	0.0
15 April 2017	21.6 – 26.9	86	0.0
16 April 2017	23.0 – 30.2	82	Trace
17 April 2017	23.7 – 29.4	79	Trace
18 April 2017	23.9 – 30.7	79	0.0
19 April 2017	24.7 – 29.4	78	0.0

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

I. General Information

Date	Mean Air Temperature (°C)	Mean Relative Humidity (%)	Precipitation (mm)
20 April 2017	25.1 – 27.5	86	3.1
21 April 2017	22.8 – 29.4	88	7.8
22 April 2017	18.5 – 24.5	79	6.6
23 April 2017	19.9 – 21.8	83	1.4
24 April 2017	20.9 – 22.8	83	Trace
25 April 2017	20.7 – 22.9	92	10.9
26 April 2017	22.4 – 26.8	95	2.9
27 April 2017	20.6 – 24.0	88	3.5
28 April 2017	20.2 – 24.8	74	0.0
29 April 2017	19.9 – 27.3	75	0.0
30 April 2017	21.4 – 28.2	75	0.0

* The above information was extracted from the daily weather summary by Hong Kong Observatory.

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

II. Mean Wind Speed and Wind Direction

Date	Time	Wind Speed m/s	Direction
1-Apr-2017	0:00	0.4	ENE
1-Apr-2017	1:00	0.3	ENE
1-Apr-2017	2:00	0.3	ENE
1-Apr-2017	3:00	0.4	ENE
1-Apr-2017	4:00	0.4	ENE
1-Apr-2017	5:00	0.4	ENE
1-Apr-2017	6:00	0.3	NE
1-Apr-2017	7:00	0.4	ENE
1-Apr-2017	8:00	0.4	ENE
1-Apr-2017	9:00	0.5	NE
1-Apr-2017	10:00	1.6	NE
1-Apr-2017	11:00	2.1	NE
1-Apr-2017	12:00	2.4	NE
1-Apr-2017	13:00	3.2	NNE
1-Apr-2017	14:00	2.5	NE
1-Apr-2017	15:00	2.1	NE
1-Apr-2017	16:00	2	NE
1-Apr-2017	17:00	1.8	NE
1-Apr-2017	18:00	1	NE
1-Apr-2017	19:00	0.9	NE
1-Apr-2017	20:00	0.9	ENE
1-Apr-2017	21:00	0.8	ENE
1-Apr-2017	22:00	0.7	ENE
1-Apr-2017	23:00	1.1	NW
2-Apr-2017	0:00	1.4	NE
2-Apr-2017	1:00	1.7	NE
2-Apr-2017	2:00	1.4	NE
2-Apr-2017	3:00	1.3	N
2-Apr-2017	4:00	0.8	N
2-Apr-2017	5:00	0.7	NE
2-Apr-2017	6:00	0.3	N
2-Apr-2017	7:00	1	E
2-Apr-2017	8:00	0.3	ENE
2-Apr-2017	9:00	0.6	ENE

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

II. Mean Wind Speed and Wind Direction

2-Apr-2017	10:00	0.8	ENE
2-Apr-2017	11:00	3.1	ENE
2-Apr-2017	12:00	3.2	ENE
2-Apr-2017	13:00	3.7	ENE
2-Apr-2017	14:00	3.7	ENE
2-Apr-2017	15:00	2.6	NE
2-Apr-2017	16:00	2.8	NE
2-Apr-2017	17:00	3.1	NE
2-Apr-2017	18:00	3.2	NNE
2-Apr-2017	19:00	3.3	N
2-Apr-2017	20:00	3	ENE
2-Apr-2017	21:00	2.9	E
2-Apr-2017	22:00	2.2	ENE
2-Apr-2017	23:00	1.8	SE
3-Apr-2017	0:00	2.2	SE
3-Apr-2017	1:00	2.4	SSE
3-Apr-2017	2:00	2.7	SSE
3-Apr-2017	3:00	2.7	ESE
3-Apr-2017	4:00	2.7	SSE
3-Apr-2017	5:00	2.5	SE
3-Apr-2017	6:00	2.4	SSE
3-Apr-2017	7:00	3.3	SSE
3-Apr-2017	8:00	3	SSE
3-Apr-2017	9:00	2.5	SE
3-Apr-2017	10:00	2.1	ENE
3-Apr-2017	11:00	2.8	ENE
3-Apr-2017	12:00	2.8	ENE
3-Apr-2017	13:00	2	E
3-Apr-2017	14:00	2.1	ENE
3-Apr-2017	15:00	2.1	ENE
3-Apr-2017	16:00	2.1	N
3-Apr-2017	17:00	1.8	NE
3-Apr-2017	18:00	2.2	ENE
3-Apr-2017	19:00	2.4	SE
3-Apr-2017	20:00	1.5	ENE

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

II. Mean Wind Speed and Wind Direction

3-Apr-2017	21:00	1.5	ENE
3-Apr-2017	22:00	1.3	ENE
3-Apr-2017	23:00	1.6	ENE
4-Apr-2017	0:00	2	ENE
4-Apr-2017	1:00	1.7	ENE
4-Apr-2017	2:00	1.2	ENE
4-Apr-2017	3:00	1.3	ENE
4-Apr-2017	4:00	1.1	N
4-Apr-2017	5:00	1.4	N
4-Apr-2017	6:00	1.6	N
4-Apr-2017	7:00	2.1	NE
4-Apr-2017	8:00	2.4	N
4-Apr-2017	9:00	2.3	ENE
4-Apr-2017	10:00	2.8	ENE
4-Apr-2017	11:00	3.3	E
4-Apr-2017	12:00	3.2	ENE
4-Apr-2017	13:00	3.4	NE
4-Apr-2017	14:00	3.2	N
4-Apr-2017	15:00	3.3	NE
4-Apr-2017	16:00	2.7	E
4-Apr-2017	17:00	2.5	SE
4-Apr-2017	18:00	2.1	SE
4-Apr-2017	19:00	1.4	ENE
4-Apr-2017	20:00	1.3	N
4-Apr-2017	21:00	1.7	N
4-Apr-2017	22:00	2	ENE
4-Apr-2017	23:00	1.9	ENE
5-Apr-2017	0:00	2.1	ENE
5-Apr-2017	1:00	2.1	ENE
5-Apr-2017	2:00	2.4	ENE
5-Apr-2017	3:00	2.6	ENE
5-Apr-2017	4:00	2.6	NE
5-Apr-2017	5:00	2.4	N
5-Apr-2017	6:00	2.1	NNE
5-Apr-2017	7:00	2.2	NE

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

II. Mean Wind Speed and Wind Direction

5-Apr-2017	8:00	1.4	NE
5-Apr-2017	9:00	1.8	NE
5-Apr-2017	10:00	2.5	NE
5-Apr-2017	11:00	2.9	ENE
5-Apr-2017	12:00	3.3	ENE
5-Apr-2017	13:00	3.5	NE
5-Apr-2017	14:00	4.2	E
5-Apr-2017	15:00	4.1	E
5-Apr-2017	16:00	4	ENE
5-Apr-2017	17:00	3.3	ESE
5-Apr-2017	18:00	2.8	ENE
5-Apr-2017	19:00	2.3	SE
5-Apr-2017	20:00	2.1	E
5-Apr-2017	21:00	2.1	ESE
5-Apr-2017	22:00	2.4	SE
5-Apr-2017	23:00	2.7	ENE
6-Apr-2017	0:00	2.2	SE
6-Apr-2017	1:00	2.8	SE
6-Apr-2017	2:00	2.1	SSE
6-Apr-2017	3:00	2.2	SSE
6-Apr-2017	4:00	2.3	NE
6-Apr-2017	5:00	2.1	SE
6-Apr-2017	6:00	1.8	SSE
6-Apr-2017	7:00	1.5	SSE
6-Apr-2017	8:00	1.8	SSE
6-Apr-2017	9:00	1.9	SE
6-Apr-2017	10:00	1.6	E
6-Apr-2017	11:00	2.7	E
6-Apr-2017	12:00	2.7	E
6-Apr-2017	13:00	3	E
6-Apr-2017	14:00	2.9	ENE
6-Apr-2017	15:00	2.5	ENE
6-Apr-2017	16:00	2.8	E
6-Apr-2017	17:00	2.5	E
6-Apr-2017	18:00	2	E

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

II. Mean Wind Speed and Wind Direction

6-Apr-2017	19:00	1.8	E
6-Apr-2017	20:00	1.2	E
6-Apr-2017	21:00	1.2	E
6-Apr-2017	22:00	1.2	SSE
6-Apr-2017	23:00	1.2	SSE
7-Apr-2017	0:00	1.1	SE
7-Apr-2017	1:00	1.3	SE
7-Apr-2017	2:00	1.5	SE
7-Apr-2017	3:00	1.3	SE
7-Apr-2017	4:00	1	ENE
7-Apr-2017	5:00	0.8	ENE
7-Apr-2017	6:00	0.7	SSE
7-Apr-2017	7:00	0.8	SSE
7-Apr-2017	8:00	0.8	SE
7-Apr-2017	9:00	1	SE
7-Apr-2017	10:00	1.3	SSW
7-Apr-2017	11:00	1.8	SSW
7-Apr-2017	12:00	1.6	SSW
7-Apr-2017	13:00	1.7	SSE
7-Apr-2017	14:00	1.8	E
7-Apr-2017	15:00	2.1	E
7-Apr-2017	16:00	1.4	SE
7-Apr-2017	17:00	1.6	SE
7-Apr-2017	18:00	1	N
7-Apr-2017	19:00	0.7	NE
7-Apr-2017	20:00	0.4	ENE
7-Apr-2017	21:00	0.4	NE
7-Apr-2017	22:00	0.4	ENE
7-Apr-2017	23:00	0.6	NNE
8-Apr-2017	0:00	0.9	NNE
8-Apr-2017	1:00	1.4	NE
8-Apr-2017	2:00	1.3	NE
8-Apr-2017	3:00	1.2	NE
8-Apr-2017	4:00	1.5	SSW
8-Apr-2017	5:00	1.9	WSW

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

II. Mean Wind Speed and Wind Direction

8-Apr-2017	6:00	1.3	NNE
8-Apr-2017	7:00	1.4	ENE
8-Apr-2017	8:00	1.5	ENE
8-Apr-2017	9:00	1.3	E
8-Apr-2017	10:00	1.7	NNE
8-Apr-2017	11:00	1.4	ENE
8-Apr-2017	12:00	1.1	E
8-Apr-2017	13:00	1.2	ENE
8-Apr-2017	14:00	1.3	NE
8-Apr-2017	15:00	2.1	ENE
8-Apr-2017	16:00	1.7	ENE
8-Apr-2017	17:00	1.1	ENE
8-Apr-2017	18:00	0.6	NNE
8-Apr-2017	19:00	0.7	E
8-Apr-2017	20:00	0.6	ENE
8-Apr-2017	21:00	0.6	N
8-Apr-2017	22:00	0.4	NE
8-Apr-2017	23:00	0.3	ENE
9-Apr-2017	0:00	0.6	ENE
9-Apr-2017	1:00	1.3	E
9-Apr-2017	2:00	2	NW
9-Apr-2017	3:00	1.7	WNW
9-Apr-2017	4:00	1.5	W
9-Apr-2017	5:00	2	SE
9-Apr-2017	6:00	1.7	SE
9-Apr-2017	7:00	2.2	SE
9-Apr-2017	8:00	2.6	NNE
9-Apr-2017	9:00	3	NE
9-Apr-2017	10:00	3.7	SSE
9-Apr-2017	11:00	3.3	SSE
9-Apr-2017	12:00	4.1	NE
9-Apr-2017	13:00	3.7	NE
9-Apr-2017	14:00	3.5	ENE
9-Apr-2017	15:00	3	ENE
9-Apr-2017	16:00	2.8	ENE

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

II. Mean Wind Speed and Wind Direction

9-Apr-2017	17:00	2.5	ENE
9-Apr-2017	18:00	2	S
9-Apr-2017	19:00	1.3	SE
9-Apr-2017	20:00	1.1	NE
9-Apr-2017	21:00	1.2	NE
9-Apr-2017	22:00	1.3	ENE
9-Apr-2017	23:00	1.4	E
10-Apr-2017	0:00	1.4	E
10-Apr-2017	1:00	1.5	E
10-Apr-2017	2:00	1.5	ENE
10-Apr-2017	3:00	2.2	E
10-Apr-2017	4:00	2.4	E
10-Apr-2017	5:00	2.2	E
10-Apr-2017	6:00	2	E
10-Apr-2017	7:00	2	ENE
10-Apr-2017	8:00	2.3	ENE
10-Apr-2017	9:00	2.4	ENE
10-Apr-2017	10:00	2.9	ENE
10-Apr-2017	11:00	3	ENE
10-Apr-2017	12:00	3.4	ENE
10-Apr-2017	13:00	3	ENE
10-Apr-2017	14:00	2.8	ENE
10-Apr-2017	15:00	2.6	ENE
10-Apr-2017	16:00	2.5	ENE
10-Apr-2017	17:00	2.7	NE
10-Apr-2017	18:00	2	NE
10-Apr-2017	19:00	1.6	NE
10-Apr-2017	20:00	1.9	ENE
10-Apr-2017	21:00	1.4	E
10-Apr-2017	22:00	2.4	E
10-Apr-2017	23:00	1.6	E
11-Apr-2017	0:00	2.5	E
11-Apr-2017	1:00	1.4	NE
11-Apr-2017	2:00	1.6	NE
11-Apr-2017	3:00	1.5	NE

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

II. Mean Wind Speed and Wind Direction

11-Apr-2017	4:00	2	NE
11-Apr-2017	5:00	2	NE
11-Apr-2017	6:00	2.1	NE
11-Apr-2017	7:00	1.8	NE
11-Apr-2017	8:00	2	NNE
11-Apr-2017	9:00	2.3	NNE
11-Apr-2017	10:00	2.6	NNE
11-Apr-2017	11:00	2.8	NNE
11-Apr-2017	12:00	2.6	NNE
11-Apr-2017	13:00	2.3	NE
11-Apr-2017	14:00	2.3	NE
11-Apr-2017	15:00	2.8	ENE
11-Apr-2017	16:00	1.9	NE
11-Apr-2017	17:00	1.2	NNE
11-Apr-2017	18:00	2	SSE
11-Apr-2017	19:00	2	SSE
11-Apr-2017	20:00	2.3	NNE
11-Apr-2017	21:00	2.3	NE
11-Apr-2017	22:00	2.5	E
11-Apr-2017	23:00	2.3	E
12-Apr-2017	0:00	2.2	E
12-Apr-2017	1:00	2.2	E
12-Apr-2017	2:00	1.8	E
12-Apr-2017	3:00	2.1	E
12-Apr-2017	4:00	2.4	NNE
12-Apr-2017	5:00	2.4	NNE
12-Apr-2017	6:00	2.4	NE
12-Apr-2017	7:00	2.6	ENE
12-Apr-2017	8:00	2.3	ENE
12-Apr-2017	9:00	2.5	SE
12-Apr-2017	10:00	2.2	S
12-Apr-2017	11:00	2.1	NNE
12-Apr-2017	12:00	2.3	NNE
12-Apr-2017	13:00	2.9	ENE
12-Apr-2017	14:00	2.5	ENE

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

II. Mean Wind Speed and Wind Direction

12-Apr-2017	15:00	3	E
12-Apr-2017	16:00	2.3	NNE
12-Apr-2017	17:00	1.6	NNE
12-Apr-2017	18:00	1.9	NNE
12-Apr-2017	19:00	1.6	NE
12-Apr-2017	20:00	1.4	ENE
12-Apr-2017	21:00	1	ENE
12-Apr-2017	22:00	0.9	ENE
12-Apr-2017	23:00	1.3	ESE
13-Apr-2017	0:00	0.9	E
13-Apr-2017	1:00	1	ENE
13-Apr-2017	2:00	0.6	ENE
13-Apr-2017	3:00	0.6	NE
13-Apr-2017	4:00	1.3	ENE
13-Apr-2017	5:00	1.1	ENE
13-Apr-2017	6:00	1.9	N
13-Apr-2017	7:00	1.3	NNE
13-Apr-2017	8:00	1.5	N
13-Apr-2017	9:00	1.5	NNE
13-Apr-2017	10:00	1.7	NE
13-Apr-2017	11:00	2.6	NNE
13-Apr-2017	12:00	2.6	E
13-Apr-2017	13:00	2.8	ENE
13-Apr-2017	14:00	2.5	ENE
13-Apr-2017	15:00	2.3	N
13-Apr-2017	16:00	2.1	NE
13-Apr-2017	17:00	2	NE
13-Apr-2017	18:00	1.9	E
13-Apr-2017	19:00	1.4	E
13-Apr-2017	20:00	0.9	E
13-Apr-2017	21:00	0.7	ENE
13-Apr-2017	22:00	0.9	N
13-Apr-2017	23:00	1.8	ENE
14-Apr-2017	0:00	2	ESE
14-Apr-2017	1:00	1.9	ESE

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

II. Mean Wind Speed and Wind Direction

14-Apr-2017	2:00	2.1	SE
14-Apr-2017	3:00	1.9	ESE
14-Apr-2017	4:00	1.6	ENE
14-Apr-2017	5:00	1.3	ENE
14-Apr-2017	6:00	1.2	ESE
14-Apr-2017	7:00	1.1	NE
14-Apr-2017	8:00	1	NE
14-Apr-2017	9:00	1.6	NE
14-Apr-2017	10:00	2.1	SE
14-Apr-2017	11:00	1.7	SE
14-Apr-2017	12:00	1.8	N
14-Apr-2017	13:00	2	N
14-Apr-2017	14:00	1.9	NE
14-Apr-2017	15:00	1.8	ENE
14-Apr-2017	16:00	1.4	E
14-Apr-2017	17:00	2.1	ENE
14-Apr-2017	18:00	1.8	N
14-Apr-2017	19:00	1.3	NE
14-Apr-2017	20:00	1.2	ESE
14-Apr-2017	21:00	1.5	ESE
14-Apr-2017	22:00	2	ENE
14-Apr-2017	23:00	1.7	E
15-Apr-2017	0:00	1.2	NE
15-Apr-2017	1:00	1.1	N
15-Apr-2017	2:00	1.6	N
15-Apr-2017	3:00	1.6	SSE
15-Apr-2017	4:00	1.4	ENE
15-Apr-2017	5:00	1.3	ENE
15-Apr-2017	6:00	1.6	ENE
15-Apr-2017	7:00	1.2	ENE
15-Apr-2017	8:00	1.4	ENE
15-Apr-2017	9:00	1.4	ESE
15-Apr-2017	10:00	1.7	SSE
15-Apr-2017	11:00	2.2	ESE
15-Apr-2017	12:00	2.4	ESE

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

II. Mean Wind Speed and Wind Direction

15-Apr-2017	13:00	1.7	NE
15-Apr-2017	14:00	1.3	NE
15-Apr-2017	15:00	1.9	E
15-Apr-2017	16:00	1.7	ESE
15-Apr-2017	17:00	1.6	WNW
15-Apr-2017	18:00	1.3	WSW
15-Apr-2017	19:00	0.4	SSW
15-Apr-2017	20:00	0.3	WNW
15-Apr-2017	21:00	0.5	WNW
15-Apr-2017	22:00	0.7	WNW
15-Apr-2017	23:00	0.5	WNW
16-Apr-2017	0:00	0.7	WNW
16-Apr-2017	1:00	0.4	WNW
16-Apr-2017	2:00	0.5	WNW
16-Apr-2017	3:00	0.2	W
16-Apr-2017	4:00	0.5	W
16-Apr-2017	5:00	0.9	W
16-Apr-2017	6:00	1.4	W
16-Apr-2017	7:00	1.8	W
16-Apr-2017	8:00	1.7	WNW
16-Apr-2017	9:00	2.1	WNW
16-Apr-2017	10:00	2.8	SW
16-Apr-2017	11:00	3.2	W
16-Apr-2017	12:00	3.4	WNW
16-Apr-2017	13:00	2.7	WNW
16-Apr-2017	14:00	2.9	WNW
16-Apr-2017	15:00	2.1	WNW
16-Apr-2017	16:00	2.2	WNW
16-Apr-2017	17:00	2.6	SW
16-Apr-2017	18:00	2	WSW
16-Apr-2017	19:00	2.1	WSW
16-Apr-2017	20:00	1.4	WNW
16-Apr-2017	21:00	1.9	WNW
16-Apr-2017	22:00	1.3	WNW
16-Apr-2017	23:00	1.4	WNW

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

II. Mean Wind Speed and Wind Direction

17-Apr-2017	0:00	1.9	WNW
17-Apr-2017	1:00	1.6	NNE
17-Apr-2017	2:00	0.6	WNW
17-Apr-2017	3:00	0.9	WNW
17-Apr-2017	4:00	1.3	SSW
17-Apr-2017	5:00	1	W
17-Apr-2017	6:00	2.7	WSW
17-Apr-2017	7:00	1.9	SW
17-Apr-2017	8:00	1.3	SW
17-Apr-2017	9:00	2.5	SW
17-Apr-2017	10:00	2	WSW
17-Apr-2017	11:00	1.8	WSW
17-Apr-2017	12:00	3	SW
17-Apr-2017	13:00	2.6	WNW
17-Apr-2017	14:00	2.5	WNW
17-Apr-2017	15:00	2.2	WSW
17-Apr-2017	16:00	2.5	WSW
17-Apr-2017	17:00	1.2	WSW
17-Apr-2017	18:00	1	SW
17-Apr-2017	19:00	0.9	WSW
17-Apr-2017	20:00	0.5	WSW
17-Apr-2017	21:00	0.6	WSW
17-Apr-2017	22:00	0.6	WSW
17-Apr-2017	23:00	1	WSW
18-Apr-2017	0:00	1.3	SW
18-Apr-2017	1:00	1.5	WSW
18-Apr-2017	2:00	0.7	WSW
18-Apr-2017	3:00	0.8	WSW
18-Apr-2017	4:00	0.7	WNW
18-Apr-2017	5:00	1.1	W
18-Apr-2017	6:00	1.6	W
18-Apr-2017	7:00	1.4	SSW
18-Apr-2017	8:00	2.1	SW
18-Apr-2017	9:00	2.7	W
18-Apr-2017	10:00	2.7	WNW

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

II. Mean Wind Speed and Wind Direction

18-Apr-2017	11:00	2.8	WNW
18-Apr-2017	12:00	2.4	SSW
18-Apr-2017	13:00	2.2	SSW
18-Apr-2017	14:00	2.7	W
18-Apr-2017	15:00	3	ESE
18-Apr-2017	16:00	2.6	SW
18-Apr-2017	17:00	2	WNW
18-Apr-2017	18:00	2.3	SW
18-Apr-2017	19:00	1.9	W
18-Apr-2017	20:00	1.9	SSW
18-Apr-2017	21:00	1.8	ESE
18-Apr-2017	22:00	2	ESE
18-Apr-2017	23:00	1.6	ESE
19-Apr-2017	0:00	2.1	SW
19-Apr-2017	1:00	2	WNW
19-Apr-2017	2:00	2.6	WNW
19-Apr-2017	3:00	2.2	NW
19-Apr-2017	4:00	2.2	W
19-Apr-2017	5:00	2.5	W
19-Apr-2017	6:00	2.5	W
19-Apr-2017	7:00	2.2	WNW
19-Apr-2017	8:00	2.7	WNW
19-Apr-2017	9:00	2.9	NNE
19-Apr-2017	10:00	3.4	ESE
19-Apr-2017	11:00	3.8	NE
19-Apr-2017	12:00	3.4	NE
19-Apr-2017	13:00	3.4	NE
19-Apr-2017	14:00	2.7	NE
19-Apr-2017	15:00	2.7	ENE
19-Apr-2017	16:00	3	NE
19-Apr-2017	17:00	2.8	NE
19-Apr-2017	18:00	2.4	NE
19-Apr-2017	19:00	2.4	NE
19-Apr-2017	20:00	2.5	NE
19-Apr-2017	21:00	1.7	NE

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

II. Mean Wind Speed and Wind Direction

19-Apr-2017	22:00	2.7	NNE
19-Apr-2017	23:00	2.6	NE
20-Apr-2017	0:00	2.3	N
20-Apr-2017	1:00	2.6	NE
20-Apr-2017	2:00	2.5	ENE
20-Apr-2017	3:00	2.7	ENE
20-Apr-2017	4:00	2.7	E
20-Apr-2017	5:00	3.4	NE
20-Apr-2017	6:00	3.1	NNE
20-Apr-2017	7:00	2.5	NNE
20-Apr-2017	8:00	2.5	NE
20-Apr-2017	9:00	3.5	NNE
20-Apr-2017	10:00	3.7	NE
20-Apr-2017	11:00	4.2	NE
20-Apr-2017	12:00	4	NE
20-Apr-2017	13:00	4.1	NNE
20-Apr-2017	14:00	3.9	NE
20-Apr-2017	15:00	3.2	E
20-Apr-2017	16:00	3.5	E
20-Apr-2017	17:00	2.4	SSW
20-Apr-2017	18:00	1.8	WNW
20-Apr-2017	19:00	1.7	SSW
20-Apr-2017	20:00	1.7	W
20-Apr-2017	21:00	1.3	NNE
20-Apr-2017	22:00	2.1	ENE
20-Apr-2017	23:00	2.7	NE
21-Apr-2017	0:00	2.1	W
21-Apr-2017	1:00	2.2	W
21-Apr-2017	2:00	2.3	WNW
21-Apr-2017	3:00	2.1	WSW
21-Apr-2017	4:00	1.8	SW
21-Apr-2017	5:00	2.4	WSW
21-Apr-2017	6:00	2.1	WSW
21-Apr-2017	7:00	1.8	WNW
21-Apr-2017	8:00	1.7	WSW

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

II. Mean Wind Speed and Wind Direction

21-Apr-2017	9:00	1.7	WSW
21-Apr-2017	10:00	1.9	W
21-Apr-2017	11:00	2.6	WNW
21-Apr-2017	12:00	2.6	WNW
21-Apr-2017	13:00	2.8	WSW
21-Apr-2017	14:00	1.3	WSW
21-Apr-2017	15:00	1.1	WSW
21-Apr-2017	16:00	1.2	WSW
21-Apr-2017	17:00	0.7	WSW
21-Apr-2017	18:00	0.6	W
21-Apr-2017	19:00	1	SSW
21-Apr-2017	20:00	0.9	ENE
21-Apr-2017	21:00	1	NNE
21-Apr-2017	22:00	0.7	ESE
21-Apr-2017	23:00	0.8	ESE
22-Apr-2017	0:00	0.7	W
22-Apr-2017	1:00	0.7	WNW
22-Apr-2017	2:00	0.6	WSW
22-Apr-2017	3:00	1	W
22-Apr-2017	4:00	1.6	W
22-Apr-2017	5:00	0.8	SSW
22-Apr-2017	6:00	0.9	WNW
22-Apr-2017	7:00	1.1	W
22-Apr-2017	8:00	1.5	WNW
22-Apr-2017	9:00	2	E
22-Apr-2017	10:00	3	N
22-Apr-2017	11:00	3.2	N
22-Apr-2017	12:00	3.5	N
22-Apr-2017	13:00	3.3	SSW
22-Apr-2017	14:00	3.5	WSW
22-Apr-2017	15:00	3.4	WNW
22-Apr-2017	16:00	2.5	NNE
22-Apr-2017	17:00	1.7	NE
22-Apr-2017	18:00	1.9	SE
22-Apr-2017	19:00	1.6	NE

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

II. Mean Wind Speed and Wind Direction

22-Apr-2017	20:00	2.4	N
22-Apr-2017	21:00	1.5	NNE
22-Apr-2017	22:00	1.5	ENE
22-Apr-2017	23:00	2.8	ENE
23-Apr-2017	0:00	1.7	NNE
23-Apr-2017	1:00	1.7	NNE
23-Apr-2017	2:00	1.5	NE
23-Apr-2017	3:00	1.5	NE
23-Apr-2017	4:00	1.3	W
23-Apr-2017	5:00	1.3	W
23-Apr-2017	6:00	1.2	W
23-Apr-2017	7:00	1	W
23-Apr-2017	8:00	2	W
23-Apr-2017	9:00	2.4	W
23-Apr-2017	10:00	3.2	W
23-Apr-2017	11:00	3	SE
23-Apr-2017	12:00	2.5	N
23-Apr-2017	13:00	2.5	N
23-Apr-2017	14:00	2.7	N
23-Apr-2017	15:00	3.5	WSW
23-Apr-2017	16:00	2.9	WSW
23-Apr-2017	17:00	1.8	WSW
23-Apr-2017	18:00	1.3	W
23-Apr-2017	19:00	1.1	W
23-Apr-2017	20:00	0.6	SW
23-Apr-2017	21:00	0.4	W
23-Apr-2017	22:00	0.6	W
23-Apr-2017	23:00	0.5	W
24-Apr-2017	0:00	0.4	SW
24-Apr-2017	1:00	0.5	SW
24-Apr-2017	2:00	0.8	SW
24-Apr-2017	3:00	1.1	SW
24-Apr-2017	4:00	1.2	SW
24-Apr-2017	5:00	1.7	W
24-Apr-2017	6:00	1.6	W

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

II. Mean Wind Speed and Wind Direction

24-Apr-2017	7:00	1.4	W
24-Apr-2017	8:00	2.1	SW
24-Apr-2017	9:00	2.8	SW
24-Apr-2017	10:00	3.2	NNE
24-Apr-2017	11:00	3	NNE
24-Apr-2017	12:00	3.1	NE
24-Apr-2017	13:00	2.9	ENE
24-Apr-2017	14:00	2.8	ENE
24-Apr-2017	15:00	3.7	NNE
24-Apr-2017	16:00	2.9	N
24-Apr-2017	17:00	2.2	ENE
24-Apr-2017	18:00	1.1	ENE
24-Apr-2017	19:00	1	SW
24-Apr-2017	20:00	0.9	WNW
24-Apr-2017	21:00	0.8	WNW
24-Apr-2017	22:00	0.9	WNW
24-Apr-2017	23:00	0.8	WNW
25-Apr-2017	0:00	0.8	WNW
25-Apr-2017	1:00	1	WNW
25-Apr-2017	2:00	1	W
25-Apr-2017	3:00	1.7	W
25-Apr-2017	4:00	2.1	WSW
25-Apr-2017	5:00	1.8	SW
25-Apr-2017	6:00	1.4	WNW
25-Apr-2017	7:00	1.6	SW
25-Apr-2017	8:00	1.4	WNW
25-Apr-2017	9:00	1.9	WNW
25-Apr-2017	10:00	3	SW
25-Apr-2017	11:00	3.5	SW
25-Apr-2017	12:00	3.4	SSW
25-Apr-2017	13:00	2	SSW
25-Apr-2017	14:00	2.1	WSW
25-Apr-2017	15:00	2.5	WSW
25-Apr-2017	16:00	2.2	WSW
25-Apr-2017	17:00	1.6	WSW

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

II. Mean Wind Speed and Wind Direction

25-Apr-2017	18:00	1	WNW
25-Apr-2017	19:00	0.8	SSW
25-Apr-2017	20:00	0.7	WNW
25-Apr-2017	21:00	1	SW
25-Apr-2017	22:00	0.7	WSW
25-Apr-2017	23:00	0.9	W
26-Apr-2017	0:00	0.6	WSW
26-Apr-2017	1:00	0.8	WNW
26-Apr-2017	2:00	1.2	WNW
26-Apr-2017	3:00	2.5	SW
26-Apr-2017	4:00	1.9	SW
26-Apr-2017	5:00	2.4	SW
26-Apr-2017	6:00	2.5	WNW
26-Apr-2017	7:00	3	WNW
26-Apr-2017	8:00	2.8	WNW
26-Apr-2017	9:00	2.4	SE
26-Apr-2017	10:00	2.8	SE
26-Apr-2017	11:00	3.9	SE
26-Apr-2017	12:00	3.2	NE
26-Apr-2017	13:00	3.8	ESE
26-Apr-2017	14:00	3.2	ESE
26-Apr-2017	15:00	2.5	ESE
26-Apr-2017	16:00	3.1	NE
26-Apr-2017	17:00	2.6	NE
26-Apr-2017	18:00	2.5	NE
26-Apr-2017	19:00	2.7	ENE
26-Apr-2017	20:00	2.5	NE
26-Apr-2017	21:00	2.4	NNE
26-Apr-2017	22:00	2.4	NE
26-Apr-2017	23:00	2.6	NE
27-Apr-2017	0:00	3	E
27-Apr-2017	1:00	3	E
27-Apr-2017	2:00	2.7	E
27-Apr-2017	3:00	2.7	ENE
27-Apr-2017	4:00	2.8	ENE

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

II. Mean Wind Speed and Wind Direction

27-Apr-2017	5:00	2.9	ENE
27-Apr-2017	6:00	2.3	ENE
27-Apr-2017	7:00	2.9	ENE
27-Apr-2017	8:00	3.2	ENE
27-Apr-2017	9:00	3.4	NE
27-Apr-2017	10:00	3.8	ENE
27-Apr-2017	11:00	3.3	E
27-Apr-2017	12:00	2.8	NE
27-Apr-2017	13:00	3.4	NE
27-Apr-2017	14:00	3.3	NE
27-Apr-2017	15:00	3	NE
27-Apr-2017	16:00	2.6	ENE
27-Apr-2017	17:00	2.6	ENE
27-Apr-2017	18:00	1.6	E
27-Apr-2017	19:00	0.9	E
27-Apr-2017	20:00	0.6	NE
27-Apr-2017	21:00	0.6	SSE
27-Apr-2017	22:00	0.3	ENE
27-Apr-2017	23:00	0.8	E
28-Apr-2017	0:00	1	E
28-Apr-2017	1:00	0.9	E
28-Apr-2017	2:00	1.2	E
28-Apr-2017	3:00	0.7	SE
28-Apr-2017	4:00	1	ESE
28-Apr-2017	5:00	1	E
28-Apr-2017	6:00	0.8	E
28-Apr-2017	7:00	0.7	ENE
28-Apr-2017	8:00	0.5	NE
28-Apr-2017	9:00	0.7	E
28-Apr-2017	10:00	1.7	SE
28-Apr-2017	11:00	2.4	SE
28-Apr-2017	12:00	2.5	ESE
28-Apr-2017	13:00	2	ESE
28-Apr-2017	14:00	2	SE
28-Apr-2017	15:00	1.9	ENE

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

II. Mean Wind Speed and Wind Direction

28-Apr-2017	16:00	1.6	ENE
28-Apr-2017	17:00	1.4	ESE
28-Apr-2017	18:00	1	NE
28-Apr-2017	19:00	0.4	NE
28-Apr-2017	20:00	0.5	SE
28-Apr-2017	21:00	0.9	N
28-Apr-2017	22:00	0.7	ENE
28-Apr-2017	23:00	0.7	ENE
29-Apr-2017	0:00	0.7	ENE
29-Apr-2017	1:00	0.9	NE
29-Apr-2017	2:00	1.1	E
29-Apr-2017	3:00	0.7	NE
29-Apr-2017	4:00	0.5	N
29-Apr-2017	5:00	0.5	N
29-Apr-2017	6:00	0.6	ENE
29-Apr-2017	7:00	0.3	SSE
29-Apr-2017	8:00	0.6	NE
29-Apr-2017	9:00	0.6	E
29-Apr-2017	10:00	1.3	E
29-Apr-2017	11:00	1.9	ENE
29-Apr-2017	12:00	1.5	N
29-Apr-2017	13:00	2	ENE
29-Apr-2017	14:00	1.8	ENE
29-Apr-2017	15:00	2.3	ENE
29-Apr-2017	16:00	1.9	W
29-Apr-2017	17:00	1.8	WNW
29-Apr-2017	18:00	1.3	WNW
29-Apr-2017	19:00	1.3	WSW
29-Apr-2017	20:00	0.9	W
29-Apr-2017	21:00	1	SW
29-Apr-2017	22:00	1.6	SSW
29-Apr-2017	23:00	1.3	WNW
30-Apr-2017	0:00	1.7	WNW
30-Apr-2017	1:00	1.8	WNW
30-Apr-2017	2:00	1.4	NE

**APPENDIX C –
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

II. Mean Wind Speed and Wind Direction

30-Apr-2017	3:00	1.2	SSW
30-Apr-2017	4:00	1.8	WNW
30-Apr-2017	5:00	1.5	WNW
30-Apr-2017	6:00	1	WNW
30-Apr-2017	7:00	1	W
30-Apr-2017	8:00	0.9	W
30-Apr-2017	9:00	1.4	W
30-Apr-2017	10:00	1.5	WNW
30-Apr-2017	11:00	1.7	W
30-Apr-2017	12:00	2.7	W
30-Apr-2017	13:00	2.7	W
30-Apr-2017	14:00	2.1	WNW
30-Apr-2017	15:00	2.4	SW
30-Apr-2017	16:00	2.1	W
30-Apr-2017	17:00	1.4	W
30-Apr-2017	18:00	1	WNW
30-Apr-2017	19:00	1	W
30-Apr-2017	20:00	0.8	WNW
30-Apr-2017	21:00	0.8	WNW
30-Apr-2017	22:00	0.9	NW
30-Apr-2017	23:00	0.8	SW

**APPENDIX D
ENVIRONMENTAL MONITORING
SCHEDULES**

Agreement No. CE/59/2015 (EP)
Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction
Impact Air Quality and Noise Monitoring Schedule (April 2017)

Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
						1-Apr
2-Apr	3-Apr	4-Apr	5-Apr	6-Apr	7-Apr	8-Apr
	1 hr TSP X3 [AM1, AM2, AM3, AM4, AM5(A) & AM6(A)] Noise [CM2, CM4, CM6(A), CM7(A), CM8(A)] 24 hr TSP			Noise [CM1, CM3, CM5]	1 hr TSP X3 [AM1, AM2, AM3, AM4, AM5(A) & AM6(A)] 24 hr TSP	
9-Apr	10-Apr	11-Apr	12-Apr	13-Apr	14-Apr	15-Apr
		Noise [CM1, CM3, CM5]		1 hr TSP X3 [AM1, AM2, AM3, AM4, AM5(A) & AM6(A)] Noise [CM2, CM4, CM6(A), CM7(A), CM8(A)] 24 hr TSP		
16-Apr	17-Apr	18-Apr	19-Apr	20-Apr	21-Apr	22-Apr
			1 hr TSP X3 [AM1, AM2, AM3, AM4, AM5(A) & AM6(A)] Noise [CM2, CM4, CM6(A), CM7(A), CM8(A)] 24 hr TSP		Noise [CM1, CM3, CM5]	
23-Apr	24-Apr	25-Apr	26-Apr	27-Apr	28-Apr	29-Apr
		1 hr TSP X3 [AM1, AM2, AM3, AM4, AM5(A) & AM6(A)] Noise [CM2, CM4, CM6(A), CM7(A), CM8(A)] 24 hr TSP		Noise [CM1, CM3, CM5]	1 hr TSP X3 [AM1, AM2, AM3, AM4, AM5(A) & AM6(A)]	
30-Apr				24 hr TSP		

Air Quality Monitoring Station

AM1 - Tin Hau Temple
AM2 - Sai Tso Wan Recreation Ground
AM3 - Yau Lai Estate Bik Lai House
AM4⁽¹⁾ - Sitting-out Area at Cha Kwo Ling Village
AM4(A)⁽²⁾ - Cha Kwo Ling Public Cargo Working Area Administrative Office
AM5(A) - Tseung Kwan O DSD Desilting Compound
AM6(A) - Park Central, L1/F Open Space Area

Noise Monitoring Station

CM1 - Nga Lai House, Yau Lai Estate Phase 1, Yau Tong
CM2 - Bik Lai House, Yau Lai Estate Phase 1, Yau Tong
CM3 - Block S, Yau Lai Estate Phase 5, Yau Tong
CM4 - Tin Hau Temple, Cha Kwo Ling
CM5 - CCC Kei Faat Primary School, Yau Tong
CM6(A) - Site Boundary of Contract No. NE/2015/02 near Tower 1, Ocean Shores
CM7(A) - Site Boundary of Contract No. NE/2015/02 near Tower 7, Ocean Shores
CM8(A) - Park Central, L1/F Open Space Area

Note (1) For 1-hour TSP monitoring; (2) For 24-hour TSP monitoring

Agreement No. CE/59/2015 (EP)
Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction
Impact Groundwater Quality Monitoring Schedule (April 2017)

Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
						1-Apr
2-Apr	3-Apr	4-Apr	5-Apr	6-Apr	7-Apr	8-Apr
9-Apr	10-Apr	11-Apr	12-Apr	13-Apr	14-Apr	15-Apr
		Groundwater Quality Monitoring				
16-Apr	17-Apr	18-Apr	19-Apr	20-Apr	21-Apr	22-Apr
23-Apr	24-Apr	25-Apr	26-Apr	27-Apr	28-Apr	29-Apr
				Groundwater Quality Monitoring		
30-Apr						

The schedule may be changed due to unforeseen circumstances (adverse weather, etc)

Monitoring Location:
Stream 1, Stream 2, Stream 3

Agreement No. CE/59/2015 (EP)
Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction
Impact Water Quality Monitoring Schedule (April 2017)

Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
						1-Apr
2-Apr	3-Apr	4-Apr	5-Apr	6-Apr	7-Apr	8-Apr
	Mid-Flood 10:30 Mid-Ebb 17:47		Mid-Flood 12:55 Mid-Ebb 20:27			Mid-Ebb 10:57 Mid-Flood 16:40
9-Apr	10-Apr	11-Apr	12-Apr	13-Apr	14-Apr	15-Apr
	Mid-Ebb 12:02 Mid-Flood 18:10		Mid-Ebb 13:03 Mid-Flood 19:29		Mid-Flood 7:46 Mid-Ebb 14:08	
16-Apr	17-Apr	18-Apr	19-Apr	20-Apr	21-Apr	22-Apr
		Mid-Flood 9:18 Mid-Ebb 16:48		Mid-Flood 6:34 Mid-Ebb 19:18		Mid-Ebb 9:50 Mid-Flood 14:50
23-Apr	24-Apr	25-Apr	26-Apr	27-Apr	28-Apr	29-Apr
	Mid-Ebb 11:01 Mid-Flood 16:51		Mid-Ebb 12:17 Mid-Flood 18:35		Mid-Flood 7:13 Mid-Ebb 13:42	
30-Apr						

Agreement No. CE/59/2015 (EP)
Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction
Tentative Impact Air Quality and Noise Monitoring Schedule (May 2017)

Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
	1-May	2-May	3-May	4-May	5-May	6-May
		24 hr TSP		1 hr TSP X3 [AM1, AM2, AM3, AM4, AM5(A) & AM6(A)] Noise [CM2, CM4, CM6(A), CM7(A), CM8(A)]	Noise [CM1, CM3, CM5]	
7-May	8-May	9-May	10-May	11-May	12-May	13-May
	24 hr TSP	1 hr TSP X3 [AM5(A), AM6(A)] Noise [CM6(A), CM7(A), CM8(A)]	1 hr TSP X3 [AM1, AM2, AM3, AM4] Noise [CM2, CM4]	Noise [CM1, CM3, CM5]	24 hr TSP	
14-May	15-May	16-May	17-May	18-May	19-May	20-May
	1 hr TSP X3 [AM5(A), AM6(A)] Noise [CM6(A), CM7(A), CM8(A)]	1 hr TSP X3 [AM1, AM2, AM3, AM4] Noise [CM2, CM4]		Noise [CM1, CM3, CM5] 24 hr TSP	1 hr TSP X3 [AM5(A), AM6(A)]	
21-May	22-May	23-May	24-May	25-May	26-May	27-May
	1 hr TSP X3 [AM1, AM2, AM3, AM4] Noise [CM2, CM4]	Noise [CM1, CM3, CM5]	24 hr TSP	1 hr TSP X3 [AM5(A), AM6(A)] Noise [CM6(A), CM7(A), CM8(A)]	1 hr TSP X3 [AM1, AM2, AM3, AM4]	
28-May	29-May	30-May	31-May			
	24 hr TSP		1 hr TSP X3 [AM5(A), AM6(A)] Noise [CM6(A), CM7(A), CM8(A)]			

The schedule may be changed due to unforeseen circumstances (adverse weather, etc)

Air Quality Monitoring Station

AM1 - Tin Hau Temple
AM2 - Sai Tso Wan Recreation Ground
AM3 - Yau Lai Estate Bik Lai House
AM4⁽¹⁾ - Sitting-out Area at Cha Kwo Ling Village
AM4(A)⁽²⁾ - Cha Kwo Ling Public Cargo Working Area Administrative Office
AM5(A) - Tseung Kwan O DSD Desilting Compound
AM6(A) - Park Central, L1/F Open Space Area

Noise Monitoring Station

CM1 - Nga Lai House, Yau Lai Estate Phase 1, Yau Tong
CM2 - Bik Lai House, Yau Lai Estate Phase 1, Yau Tong
CM3 - Block S, Yau Lai Estate Phase 5, Yau Tong
CM4 - Tin Hau Temple, Cha Kwo Ling
CM5 - CCC Kei Faat Primary School, Yau Tong
CM6(A) - Site Boundary of Contract No. NE/2015/02 near Tower 1, Ocean Shores
CM7(A) - Site Boundary of Contract No. NE/2015/02 near Tower 7, Ocean Shores
CM8(A) - Park Central, L1/F Open Space Area

Note (1) For 1-hour TSP monitoring; (2) For 24-hour TSP monitoring

Agreement No. CE/59/2015 (EP)
Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction
Tentative Impact Groundwater Quality Monitoring Schedule (May 2017)

Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
	1-May	2-May	3-May	4-May	5-May	6-May
7-May	8-May	9-May	10-May	11-May	12-May	13-May
				Groundwater Quality Monitoring		
14-May	15-May	16-May	17-May	18-May	19-May	20-May
21-May	22-May	23-May	24-May	25-May	26-May	27-May
		Groundwater Quality Monitoring				
28-May	29-May	30-May				

The schedule may be changed due to unforeseen circumstances (adverse weather, etc)

Monitoring Location:
Stream 1, Stream 2, Stream 3

Agreement No. CE/59/2015 (EP)
Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction
Tentative Impact Water Quality Monitoring Schedule (May 2017)

Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
	1-May	2-May	3-May	4-May	5-May	6-May
		Mid-Flood 10:06 Mid-Ebb 17:27		Mid-Flood 12:43 Mid-Ebb 19:55		Mid-Ebb 9:52 Mid-Flood 15:35
7-May	8-May	9-May	10-May	11-May	12-May	13-May
	Mid-Ebb 11:07 Mid-Flood 17:18		Mid-Ebb 12:10 Mid-Flood 18:42		Mid-Ebb 13:11 Mid-Flood 19:58	
14-May	15-May	16-May	17-May	18-May	19-May	20-May
	Mid-Flood 7:44 Mid-Ebb 14:39		Mid-Flood 8:50 Mid-Ebb 16:15		Mid-Flood 11:12 Mid-Ebb 18:17	
21-May	22-May	23-May	24-May	25-May	26-May	27-May
	Mid-Ebb 9:50 Mid-Flood 15:35		Mid-Ebb 11:12 Mid-Flood 17:33		Mid-Ebb 12:40 Mid-Flood 19:20	
28-May	29-May	30-May	31-May			1-Jan
	Mid-Flood 8:11 Mid-Ebb 15:09		Mid-Flood 9:53 Mid-Ebb 17:05			

The schedule may be changed due to unforeseen circumstances (adverse weather, etc)

Agreement No. CE/59/2015 (EP)
Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction
Tentative Post-Translocation Coral Monitoring Schedule (May 2017)

Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
			1-Mar	2-Mar	3-Mar	4-Mar
5-Mar	6-Mar	7-Mar	8-Mar	9-Mar	10-Mar	11-Mar
12-Mar	13-Mar	14-Mar	15-Mar	16-Mar	17-Mar	18-Mar
	Any 1-2 day within this period (To be confirmed)					
19-Mar	20-Mar	21-Mar	22-Mar	23-Mar	24-Mar	25-Mar
26-Mar	27-Mar	28-Mar	29-Mar	30-Mar	31-Mar	

The schedule may be changed due to unforeseen circumstances (adverse weather, etc)

**APPENDIX E
1-HOUR TSP MONITORING RESULTS
AND GRAPHICAL PRESENTATIONS**

Appendix E - 1-hour TSP Monitoring Results

Location AM1 - Tin Hau Temple			
Date	Time	Weather	Particulate Concentration ($\mu\text{g}/\text{m}^3$)
3-Apr-17	9:00	Sunny	159.3
3-Apr-17	10:00	Sunny	161.2
3-Apr-17	11:00	Sunny	165.1
7-Apr-17	9:00	Cloudy	201.1
7-Apr-17	10:00	Cloudy	228.0
7-Apr-17	11:00	Cloudy	202.8
13-Apr-17	9:00	Sunny	171.4
13-Apr-17	10:00	Sunny	162.1
13-Apr-17	11:00	Sunny	156.1
19-Apr-17	13:00	Sunny	110.4
19-Apr-17	14:00	Sunny	111.5
19-Apr-17	15:00	Sunny	111.2
25-Apr-17	9:00	Rainy	115.9
25-Apr-17	10:00	Rainy	114.2
25-Apr-17	11:00	Rainy	114.3
28-Apr-17	9:00	Cloudy	58.4
28-Apr-17	10:00	Cloudy	65.4
28-Apr-17	11:00	Cloudy	68.9
Average			137.6
Maximum			228.0
Minimum			58.4

Location AM2 - Sai Tso Wan Recreation Ground			
Date	Time	Weather	Particulate Concentration ($\mu\text{g}/\text{m}^3$)
3-Apr-17	13:00	Sunny	140.6
3-Apr-17	14:00	Sunny	137.1
3-Apr-17	15:00	Sunny	142.7
7-Apr-17	13:00	Cloudy	107.3
7-Apr-17	14:00	Cloudy	109.3
7-Apr-17	15:00	Cloudy	115.8
13-Apr-17	8:45	Sunny	115.2
13-Apr-17	9:45	Sunny	119.7
13-Apr-17	10:45	Sunny	111.5
19-Apr-17	9:00	Sunny	59.0
19-Apr-17	10:00	Sunny	59.7
19-Apr-17	11:00	Sunny	59.6
25-Apr-17	9:00	Rainy	102.3
25-Apr-17	10:00	Rainy	100.3
25-Apr-17	11:00	Rainy	102.4
28-Apr-17	9:00	Cloudy	49.5
28-Apr-17	10:00	Cloudy	53.4
28-Apr-17	11:00	Cloudy	56.0
Average			96.7
Maximum			142.7
Minimum			49.5

Appendix E - 1-hour TSP Monitoring Results

Location AM3 - Yau Lai Estate Bik Lai House			
Date	Time	Weather	Particulate Concentration ($\mu\text{g}/\text{m}^3$)
3-Apr-17	13:00	Sunny	173.9
3-Apr-17	14:00	Sunny	185.7
3-Apr-17	15:00	Sunny	194.1
7-Apr-17	13:00	Cloudy	155.5
7-Apr-17	14:00	Cloudy	154.2
7-Apr-17	15:00	Cloudy	172.7
13-Apr-17	13:15	Sunny	176.7
13-Apr-17	14:15	Sunny	187.0
13-Apr-17	15:15	Sunny	181.7
19-Apr-17	9:00	Sunny	94.7
19-Apr-17	10:00	Sunny	93.8
19-Apr-17	11:00	Sunny	96.0
25-Apr-17	13:00	Rainy	111.6
25-Apr-17	14:00	Rainy	113.4
25-Apr-17	15:00	Rainy	113.9
28-Apr-17	13:00	Cloudy	51.4
28-Apr-17	14:00	Cloudy	57.1
28-Apr-17	15:00	Cloudy	60.6
Average			131.9
Maximum			194.1
Minimum			51.4




Location AM4 - Sitting-out Area at Cha Kwo Ling Village			
Date	Time	Weather	Particulate Concentration ($\mu\text{g}/\text{m}^3$)
3-Apr-17	9:00	Sunny	182.5
3-Apr-17	10:00	Sunny	159.4
3-Apr-17	11:00	Sunny	187.5
7-Apr-17	9:00	Cloudy	197.3
7-Apr-17	10:00	Cloudy	191.5
7-Apr-17	11:00	Cloudy	185.0
13-Apr-17	13:00	Sunny	215.6
13-Apr-17	14:00	Sunny	222.2
13-Apr-17	15:00	Sunny	212.4
19-Apr-17	13:00	Sunny	70.0
19-Apr-17	14:00	Sunny	70.2
19-Apr-17	15:00	Sunny	69.3
25-Apr-17	13:00	Rainy	115.8
25-Apr-17	14:00	Rainy	112.7
25-Apr-17	15:00	Rainy	113.5
28-Apr-17	13:00	Cloudy	69.1
28-Apr-17	14:00	Cloudy	77.0
28-Apr-17	15:00	Cloudy	83.8
Average			140.8
Maximum			222.2
Minimum			69.1

Appendix E - 1-hour TSP Monitoring Results

Location AM5(A) - Tseung Kwan O DSD Desilting Compound			
Date	Time	Weather	Particulate Concentration ($\mu\text{g}/\text{m}^3$)
3-Apr-17	9:00	Sunny	48.7
3-Apr-17	10:00	Sunny	64.9
3-Apr-17	11:00	Sunny	54.5
7-Apr-17	9:00	Sunny	44.0
7-Apr-17	10:00	Sunny	41.7
7-Apr-17	11:00	Sunny	45.2
13-Apr-17	9:00	Cloudy	116.9
13-Apr-17	10:00	Cloudy	131.6
13-Apr-17	11:00	Cloudy	111.6
19-Apr-17	9:00	Sunny	190.1
19-Apr-17	10:00	Sunny	121.9
19-Apr-17	11:00	Sunny	132.0
25-Apr-17	9:00	Cloudy	124.9
25-Apr-17	10:00	Cloudy	114.1
25-Apr-17	11:00	Cloudy	128.8
28-Apr-17	9:00	Cloudy	42.1
28-Apr-17	10:00	Cloudy	44.3
28-Apr-17	11:00	Cloudy	48.9
Average			89.2
Maximum			190.1
Minimum			41.7




Location AM6(A) - Park Central, L1/F Open Space Area			
Date	Time	Weather	Particulate Concentration ($\mu\text{g}/\text{m}^3$)
3-Apr-17	13:00	Sunny	27.8
3-Apr-17	14:00	Sunny	29.0
3-Apr-17	15:00	Sunny	31.3
7-Apr-17	13:00	Sunny	41.7
7-Apr-17	14:00	Sunny	51.0
7-Apr-17	15:00	Sunny	48.7
13-Apr-17	13:00	Cloudy	121.3
13-Apr-17	14:00	Cloudy	120.6
13-Apr-17	15:00	Cloudy	125.1
19-Apr-17	13:00	Sunny	171.4
19-Apr-17	14:00	Sunny	112.8
19-Apr-17	15:00	Sunny	131.0
25-Apr-17	13:00	Cloudy	124.1
25-Apr-17	14:00	Cloudy	116.4
25-Apr-17	15:00	Cloudy	111.2
28-Apr-17	13:00	Cloudy	38.7
28-Apr-17	14:00	Cloudy	43.2
28-Apr-17	15:00	Cloudy	45.5
Average			82.8
Maximum			171.4
Minimum			27.8

1-hr TSP Concentration Levels



Title	Agreement No. CE/59/2015 (EP)	Scale	Project	CINOTECH
	Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction	N.T.S	No. MA16034	
Graphical Presentation of 1-hour TSP Monitoring Results		Date	Appendix	
		Apr 17	E	

1-hr TSP Concentration Levels



Title Agreement No. CE/59/2015 (EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction Graphical Presentation of 1-hour TSP Monitoring Results	Scale N.T.S	Project No. MA16034	
	Date Apr 17	Appendix E	

**APPENDIX F
24-HOUR TSP MONITORING RESULTS
AND GRAPHICAL PRESENTATIONS**

Appendix F - 24-hour TSP Monitoring Results

Location AM1 - Tin Hau Temple

Start Date	Weather Condition	Air Temp. (K)	Atmospheric Pressure, Pa (mmHg)	Filter Weight (g)		Particulate Weight (g)	Elapse Time		Sampling Time(hrs.)	Flow Rate (m ³ /min.)		Av. flow (m ³ /min)	Total vol. (m ³)	Conc. (µg/m ³)
				Initial	Final		Initial	Final		Initial	Final			
3-Apr-17	Cloudy	294.2	759.1	2.8335	3.0157	0.1822	1715.0	1739.0	24.0	1.20	1.20	1.20	1728.1	105.4
7-Apr-17	Cloudy	300.4	760.9	2.8016	2.9727	0.1711	1739.0	1763.0	24.0	1.19	1.19	1.19	1710.1	100.1
13-Apr-17	Sunny	290.6	766.4	3.5764	3.7458	0.1694	1763.0	1787.0	24.0	1.22	1.21	1.21	1749.5	96.8
19-Apr-17	Sunny	302.7	759.1	3.5985	3.7659	0.1674	1787.0	1811.0	24.0	1.18	1.18	1.18	1700.5	98.4
25-Apr-17	Cloudy	294.8	760.9	3.5609	3.7466	0.1857	1811.0	1835.0	24.0	1.20	1.20	1.20	1728.4	107.4
27-Apr-17	Cloudy	293.3	761.7	3.6345	3.8062	0.1717	1835.0	1859.0	24.0	1.20	1.20	1.20	1734.4	99.0
													Min	96.8
													Max	107.4
													Average	101.2

Location AM2 - Sai Tso Wan Recreation Ground

Start Date	Weather Condition	Air Temp. (K)	Atmospheric Pressure, Pa (mmHg)	Filter Weight (g)		Particulate Weight (g)	Elapse Time		Sampling Time(hrs.)	Flow Rate (m ³ /min.)		Av. flow (m ³ /min)	Total vol. (m ³)	Conc. (µg/m ³)
				Initial	Final		Initial	Final		Initial	Final			
3-Apr-17	Cloudy	293.8	759.6	2.8385	2.9880	0.1495	22679.3	22703.3	24.0	1.20	1.20	1.20	1729.0	86.5
7-Apr-17	Cloudy	299.5	761.4	2.8915	2.9764	0.0849	22703.3	22727.3	24.0	1.19	1.19	1.19	1713.6	49.5
13-Apr-17	Sunny	290.2	766.8	2.8703	2.9687	0.0984	22727.3	22751.3	24.0	1.21	1.21	1.21	1749.2	56.3
19-Apr-17	Sunny	302.3	758.5	3.6496	3.7658	0.1162	22751.3	22775.3	24.0	1.18	1.18	1.18	1701.8	68.3
25-Apr-17	Cloudy	294.3	761.4	3.5976	3.7029	0.1053	22775.3	22799.3	24.0	1.20	1.20	1.20	1729.6	60.9
27-Apr-17	Cloudy	293.9	761.3	3.5791	3.6507	0.0716	22799.3	22823.3	24.0	1.20	1.20	1.20	1730.7	41.4
													Min	41.4
													Max	86.5
													Average	60.5

Location AM3 - Yau Lai Estate, Bik Lai House

Start Date	Weather Condition	Air Temp. (K)	Atmospheric Pressure, Pa (mmHg)	Filter Weight (g)		Particulate Weight (g)	Elapse Time		Sampling Time(hrs.)	Flow Rate (m ³ /min.)		Av. flow (m ³ /min)	Total vol. (m ³)	Conc. (µg/m ³)
				Initial	Final		Initial	Final		Initial	Final			
3-Apr-17	Cloudy	294.7	763.3	2.8869	3.0247	0.1378	11246.7	11270.7	24.0	1.22	1.21	1.21	1744.9	79.0
7-Apr-17	Cloudy	299.9	761.1	2.8682	2.9530	0.0848	11270.7	11294.7	24.0	1.20	1.20	1.20	1726.1	49.1
13-Apr-17	Sunny	292.4	765.6	3.5876	3.6734	0.0858	11294.7	11318.7	24.0	1.22	1.22	1.22	1755.0	48.9
19-Apr-17	Sunny	299.5	759.2	3.6341	3.7087	0.0746	11318.7	11342.7	24.0	1.20	1.20	1.20	1725.1	43.2
25-Apr-17	Cloudy	294.3	763.3	3.6076	3.6931	0.0855	11342.7	11366.7	24.0	1.21	1.21	1.21	1746.1	49.0
27-Apr-17	Cloudy	294.6	762.0	3.6640	3.7628	0.0988	11366.7	11390.7	24.0	1.21	1.21	1.21	1743.6	56.7
													Min	43.2
													Max	79.0
													Average	54.3

Appendix F - 24-hour TSP Monitoring Results

Location AM4(A) - Cha Kwo Ling Public Cargo Working Area Administrative Office

Start Date	Weather Condition	Air Temp. (K)	Atmospheric Pressure, Pa (mmHg)	Filter Weight (g)		Particulate Weight (g)	Elapse Time		Sampling Time(hrs.)	Flow Rate (m ³ /min.)		Av. flow (m ³ /min)	Total vol. (m ³)	Conc. (µg/m ³)
				Initial	Final		Initial	Final		Initial	Final			
3-Apr-17	Cloudy	294.6	758.2	2.8601	3.1560	0.2959	8233.2	8257.2	24.0	1.21	1.21	1.21	1743.9	169.7
7-Apr-17	Cloudy	299.5	762.0	2.8339	3.1358	0.3019	8257.2	8281.2	24.0	1.20	1.20	1.20	1733.1	174.2
13-Apr-17	Sunny	292.8	765.3	3.5712	3.8868	0.3156	8281.2	8305.2	24.0	1.22	1.22	1.22	1758.5	179.5
19-Apr-17	Sunny	303.1	758.7	3.6200	3.8313	0.2113	8305.2	8329.2	24.0	1.19	1.19	1.19	1718.0	123.0
25-Apr-17	Cloudy	295.3	761.5	3.5961	3.8522	0.2561	8329.2	8353.2	24.0	1.21	1.21	1.21	1745.7	146.7
27-Apr-17	Cloudy	293.7	762.1	3.6441	3.7958	0.1517	8353.2	8377.2	24.0	1.22	1.22	1.22	1751.6	86.6
													Min	86.6
													Max	179.5
													Average	146.6




Location AM5(A) - Tseung Kwan O DSD Desilting Compound

Start Date	Weather Condition	Air Temp. (K)	Atmospheric Pressure, Pa (mmHg)	Filter Weight (g)		Particulate Weight (g)	Elapse Time		Sampling Time(hrs.)	Flow Rate (m ³ /min.)		Av. flow (m ³ /min)	Total vol. (m ³)	Conc. (µg/m ³)
				Initial	Final		Initial	Final		Initial	Final			
3-Apr-17	Sunny	294.0	759.5	2.8273	2.8908	0.0635	21975.5	21999.5	24.0	1.20	1.20	1.20	1731.6	36.7
7-Apr-17	Cloudy	297.2	763.1	2.8666	2.9368	0.0702	21999.5	22023.5	24.0	1.20	1.20	1.20	1726.3	40.7
13-Apr-17	Sunny	290.4	766.7	2.8516	2.9492	0.0976	22023.5	22047.5	24.0	1.22	1.22	1.22	1750.8	55.7
19-Apr-17	Sunny	299.6	759.5	2.8242	3.0079	0.1837	22047.5	22071.5	24.0	1.19	1.19	1.19	1715.1	107.1
25-Apr-17	Cloudy	293.4	761.7	3.6068	3.7361	0.1293	22071.5	22095.5	24.0	1.21	1.21	1.21	1735.9	74.5
27-Apr-17	Cloudy	294.3	761.3	3.6140	3.6960	0.0820	22095.5	22119.5	24.0	1.20	1.20	1.20	1732.8	47.3
													Min	36.7
													Max	107.1
													Average	60.3

Location AM6(A) - Park Central, L1/F Open Space Area




Start Date	Weather Condition	Air Temp. (K)	Atmospheric Pressure, Pa (mmHg)	Filter Weight (g)		Particulate Weight (g)	Elapse Time		Sampling Time(hrs.)	Flow Rate (m ³ /min.)		Av. flow (m ³ /min)	Total vol. (m ³)	Conc. (µg/m ³)
				Initial	Final		Initial	Final		Initial	Final			
3-Apr-17	Sunny	294.4	758.5	2.8470	2.9054	0.0584	15035.8	15059.8	24.0	1.22	1.22	1.22	1752.6	33.3
7-Apr-17	Cloudy	297.3	763.7	2.8283	2.8779	0.0496	15059.8	15083.8	24.0	1.22	1.21	1.22	1750.0	28.3
13-Apr-17	Sunny	291.0	766.6	2.8496	2.9341	0.0845	15083.8	15107.8	24.0	1.23	1.23	1.23	1772.1	47.7
19-Apr-17	Sunny	303.4	758.3	3.6258	3.7291	0.1033	15107.8	15131.8	24.0	1.20	1.20	1.20	1726.3	59.8
25-Apr-17	Cloudy	294.4	761.5	3.6056	3.7421	0.1365	15131.8	15155.8	24.0	1.22	1.22	1.22	1756.0	77.7
27-Apr-17	Cloudy	293.5	762.2	3.6152	3.6944	0.0792	15155.8	15179.8	24.0	1.22	1.22	1.22	1759.5	45.0
													Min	28.3
													Max	77.7
													Average	48.7

24-hr TSP Concentration Levels



Title Agreement No. CE/59/2015 (EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction Graphical Presentation of 24-hour TSP Monitoring Results	Scale N.T.S	Project No. MA16034	CINOTECH
	Date Apr 17	Appendix F	

24-hr TSP Concentration Levels



Title Agreement No. CE/59/2015 (EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction Graphical Presentation of 24-hour TSP Monitoring Results	Scale N.T.S	Project No. MA16034	CINOTECH
	Date Apr 17	Appendix F	

**APPENDIX G
NOISE MONITORING RESULTS AND
GRAPHICAL PRESENTATIONS**

Appendix G - Noise Monitoring Results

(0700-1900 hrs on Normal Weekdays)

Location CM1 - Nga Lai House, Yau Lai Estate Phase 1, Yau Tong							
Date	Time	Weather	Unit: dB (A) (30-min)				
			Measured Noise Level			Baseline Level	Construction Noise Level
			L _{eq}	L ₁₀	L ₉₀	L _{eq}	L _{eq}
6-Apr-17	10:43	Cloudy	70.4	71.9	68.4	65.5	68.7
11-Apr-17	10:05	Sunny	65.7	66.8	64.3		52.2
21-Apr-17	15:30	Cloudy	69.5	72.1	66.4		67.3
27-Apr-17	14:45	Cloudy	65.4	66.5	64.2		65.4 Measured ≤ Baseline

Location CM2 - Bik Lai House, Yau Lai Estate Phase 1, Yau Tong							
Date	Time	Weather	Unit: dB (A) (30-min)				
			Measured Noise Level			Baseline Level	Construction Noise Level
			L _{eq}	L ₁₀	L ₉₀	L _{eq}	L _{eq}
3-Apr-17	13:05	Sunny	71.8	73.7	70.1	63.6	71.1
13-Apr-17	14:15	Sunny	73.8	75.2	70.7		73.4
19-Apr-17	9:30	Sunny	71.3	73.2	68.1		70.5
25-Apr-17	14:00	Cloudy	69.8	71.9	65.4		68.6

Location CM3 - Block S, Yau Lai Estate Phase 5, Yau Tong							
Date	Time	Weather	Unit: dB (A) (30-min)				
			Measured Noise Level			Baseline Level	Construction Noise Level
			L _{eq}	L ₁₀	L ₉₀	L _{eq}	L _{eq}
6-Apr-17	9:00	Cloudy	69.6	70.9	68.1	65.6	67.4
11-Apr-17	11:05	Cloudy	69.1	71.4	66.4		66.5
21-Apr-17	14:45	Cloudy	67.3	68.5	66.0		62.4
27-Apr-17	15:30	Cloudy	66.9	68.0	65.3		61.0

Location CM4 - Tin Hau Temple, Cha Kwo Ling							
Date	Time	Weather	Unit: dB (A) (30-min)				
			Measured Noise Level			Baseline Level	Construction Noise Level
			L _{eq}	L ₁₀	L ₉₀	L _{eq}	L _{eq}
3-Apr-17	9:15	Sunny	62.6	63.8	58.4	62.0	53.7
13-Apr-17	10:10	Sunny	74.3	76.2	71.5		74.0
19-Apr-17	13:30	Sunny	74.7	76.3	73.2		74.5
25-Apr-17	10:00	Cloudy	68.5	70.3	64.2		65.5

Location CM5 - CCC Kei Faat Primary School, Yau Tong							
Date	Time	Weather	Unit: dB (A) (30-min)				
			Measured Noise Level			Baseline Level	Construction Noise Level
			L _{eq}	L ₁₀	L ₉₀	L _{eq}	L _{eq}
6-Apr-17	9:00	Cloudy	66.9	69.4	62.5	68.2	66.9 Measured ≤ Baseline
11-Apr-17	9:10	Cloudy	68.5	70.9	65.0		56.7
21-Apr-17	14:00	Cloudy	68.5	70.9	64.9		56.7
27-Apr-17	14:00	Cloudy	66.2	68.5	63.0		66.2 Measured ≤ Baseline

Appendix G - Noise Monitoring Results




(0700-1900 hrs on Normal Weekdays)

Location CM6(A) - Site Boundary of Contract No. NE/2015/02 near Tower 1, Ocean Shores							
Date	Time	Weather	Unit: dB (A) (30-min)				
			Measured Noise Level			Baseline Level	Construction Noise Level
			L _{eq}	L ₁₀	L ₉₀	L _{eq}	L _{eq}
3-Apr-17	9:15	Sunny	63.3	70.9	65.7	61.9	57.7
13-Apr-17	9:00	Cloudy	67.6	71.6	59.5		66.2
19-Apr-17	10:00	Sunny	64.7	68.0	58.6		61.5
25-Apr-17	9:32	Cloudy	66.8	70.6	60.8		65.1

Location CM7(A) - Site Boundary of Contract No. NE/2015/02 near Tower 7, Ocean Shores							
Date	Time	Weather	Unit: dB (A) (30-min)				
			Measured Noise Level			Baseline Level	Construction Noise Level
			L _{eq}	L ₁₀	L ₉₀	L _{eq}	L _{eq}
3-Apr-17	10:10	Sunny	68.4	77.7	70.8	58.3	68.0
13-Apr-17	9:30	Cloudy	68.7	68.6	54.0		68.3
19-Apr-17	11:00	Sunny	64.7	68.0	58.6		63.6
25-Apr-17	10:30	Cloudy	66.2	69.0	59.2		65.4




Location CM8(A) - Park Central, L1/F Open Space Area							
Date	Time	Weather	Unit: dB (A) (30-min)				
			Measured Noise Level			Baseline Level	Construction Noise Level
			L _{eq}	L ₁₀	L ₉₀	L _{eq}	L _{eq}
3-Apr-17	13:10	Sunny	64.6	72.5	67.5	69.1	64.6 Measured ≤ Baseline
13-Apr-17	13:00	Cloudy	64.5	66.7	59.5		64.5 Measured ≤ Baseline
19-Apr-17	13:00	Sunny	65.0	68.1	60.4		65.0 Measured ≤ Baseline
25-Apr-17	13:00	Cloudy	63.3	65.9	59.5		63.3 Measured ≤ Baseline

Noise Levels





Title Agreement No. CE/59/2015 (EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction Graphical Presentation of Construction Noise Monitoring Results	Scale N.T.S	Project No. MA16034	
	Date Apr 17	Appendix G	

Noise Levels



Title Agreement No. CE/59/2015 (EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction Graphical Presentation of Construction Noise Monitoring Results	Scale N.T.S	Project No. MA16034	
	Date Apr 17	Appendix G	

Noise Levels



Title Agreement No. CE/59/2015 (EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction Graphical Presentation of Construction Noise Monitoring Results	Scale N.T.S	Project No. MA16034	
	Date Apr 17	Appendix G	

**APPENDIX H
GROUNDWATER QUALITY
MONITORING RESULTS AND
GRAPHICAL PRESENTATIONS**

Agreement No. CE/59/2015 (EP)**Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction****Groundwater Quality Monitoring Results at Stream 1**

Date	Weather Condition	Sampling Time	Depth (m)	Temperature (°C)		pH		Salinity ppt		DO Saturation (%)		Dissolved Oxygen (mg/L)		Turbidity(NTU)	
				Value	Average	Value	Average	Value	Average	Value	Average	Value	Average	Value	Average
11-Apr-17	Cloudy	12:27	Middle	26.5	26.5	7.2	7.2	0.1	0.1	97.2	97.0	7.8	7.8	1.6	1.7
				26.4		7.2		0.1		96.8		7.8		1.7	
27-Apr-17	Cloudy	09:55	Middle	22.3	22.3	6.8	6.9	0.3	0.3	93.9	93.9	8.1	8.2	1.8	1.8
				22.2		6.9		0.3		93.9		8.2		1.8	

Groundwater Quality Monitoring Results at Stream 2

Date	Weather Condition	Sampling Time	Depth (m)	Temperature (°C)		pH		Salinity ppt		DO Saturation (%)		Dissolved Oxygen (mg/L)		Turbidity(NTU)	
				Value	Average	Value	Average	Value	Average	Value	Average	Value	Average	Value	Average
11-Apr-17	Cloudy	13:08	Middle	25.4	25.4	7.2	7.2	0.7	0.7	95.0	94.9	7.8	7.8	0.4	0.4
				25.4		7.2		0.7		94.8		7.8		0.4	
27-Apr-17	Cloudy	09:29	Middle	22.3	22.3	6.9	6.9	0.1	0.1	95.2	95.0	8.3	8.3	1.9	2.0
				22.3		6.9		0.1		94.8		8.2		2.0	

Groundwater Quality Monitoring Results at Stream 3

Date	Weather Condition	Sampling Time	Depth (m)	Temperature (°C)		pH		Salinity ppt		DO Saturation (%)		Dissolved Oxygen (mg/L)		Turbidity(NTU)	
				Value	Average	Value	Average	Value	Average	Value	Average	Value	Average	Value	Average
11-Apr-17	Cloudy	12:59	Middle	25.7	25.7	7.2	7.2	0.1	0.1	94.2	94.0	7.7	7.7	1.6	1.7
				25.7		7.2		0.1		93.8		7.7		1.7	
27-Apr-17	Cloudy	09:20	Middle	22.2	22.2	6.7	6.7	0.1	0.1	93.2	93.1	8.1	8.1	1.8	1.8
				22.2		6.7		0.1		93.0		8.1		1.8	

Agreement No. CE/59/2015 (EP)


Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction

Summary of Groundwater Quality Monitoring Results

Location	Date	Parameters (unit)								
		pH	Dissolved Oxygen (mg/L)	Turbidity (NTU)	SS (mg/L)	BOD ₅ (mg O ₂ /L)	TOC (mg-TOC/L)	Total Nitrogen (mg/L)	NH ₃ -N (mg NH ₃ -N/L)	Total Phosphorus (mg-P/L)
Stream 1	11-Apr-17	7.2	7.8	1.7	<0.5	<2	<u>6</u>	1	0.05	<0.05
	27-Apr-17	6.9	8.2	1.8	1.6	<2	<u>5</u>	1.2	<0.05	<0.05
Stream 2	11-Apr-17	7.2	7.8	0.4	3.8	<2	<u>17</u>	1.1	<u>0.13</u>	<0.05
	27-Apr-17	6.9	8.3	2	4.2	<2	<u>9</u>	1.3	<u>0.08</u>	<0.05
Stream 3	11-Apr-17	7.2	7.7	1.7	1	<2	4	0.9	<0.05	<0.05
	27-Apr-17	6.7	8.1	1.8	3.3	<2	<u>5</u>	1.2	<u>0.06</u>	<0.05
No. of Exceedance	Action Level	0	0	0	0	0	0	0	1	0
	Limit Level	0	0	0	0	0	5	0	2	0

Note: ***Bold Italic*** means Action Level exceedance
Bold Italic with underline means Limit Level exceedance

pH




Title Agreement No. CE 59/2015(EP)
 Environmental Team for Tseung Kwan O - Lam Tin Tunnel
 Design and Construction
 Graphical Presentation of Groundwater Quality
 Monitoring Result

Scale N.T.S
 Date Apr 17

Project No. MA16034
 Appendix H



Dissolved Oxygen




Title
 Agreement No. CE 59/2015(EP)
 Environmental Team for Tseung Kwan O - Lam Tin Tunnel
 Design and Construction
 Graphical Presentation of Groundwater Quality
 Monitoring Result

Scale
 N.T.S
 Date
 Apr 17

Project
 No. MA16034
 Appendix
 H



Turbidity




Title
 Agreement No. CE 59/2015(EP)
 Environmental Team for Tseung Kwan O - Lam Tin Tunnel
 Design and Construction
 Graphical Presentation of Groundwater Quality
 Monitoring Result

Scale
 N.T.S
 Date
 Apr 17

Project
 No. MA16034
 Appendix
 H



Suspended Solids




Title Agreement No. CE 59/2015(EP)
 Environmental Team for Tseung Kwan O - Lam Tin Tunnel
 Design and Construction
 Graphical Presentation of Groundwater Quality
 Monitoring Result

Scale N.T.S
 Date Apr 17

Project No. MA16034
 Appendix H




5-day Biochemical Oxygen Demand (BOD₅)



Remarks: The graphical point at zero concentration is presented as <2 mg/L

Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction Graphical Presentation of Groundwater Quality Monitoring Result	Scale N.T.S	Project No. MA16034	
	Date Apr 17	Appendix H	

Total Organic Carbon (TOC)




Title Agreement No. CE 59/2015(EP)
 Environmental Team for Tseung Kwan O - Lam Tin Tunnel
 Design and Construction
 Graphical Presentation of Groundwater Quality
 Monitoring Result

Scale N.T.S
 Date Apr 17

Project No. MA16034
 Appendix H




Total Nitrogen



Remarks: The graphical point at zero concentration is presented as <0.6 mg/L

Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction Graphical Presentation of Groundwater Quality Monitoring Result	Scale N.T.S	Project No. MA16034	
	Date Apr 17	Appendix H	


Ammonia-Nitrogen



Remarks: The graphical point at zero concentration is presented as <0.05 mg/L

Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction Graphical Presentation of Groundwater Quality Monitoring Result	Scale	N.T.S	Project No. MA16034	
	Date	Apr 17	Appendix	

Total Phosphate



Remarks: The graphical point at zero concentration is presented as <0.05 mg/L

Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction Graphical Presentation of Groundwater Quality Monitoring Result	Scale	N.T.S	Project No. MA16034	
	Date	Apr 17	Appendix	

**APPENDIX I
MARINE WATER QUALITY
MONITORING RESULTS AND
GRAPHICAL PRESENTATIONS**

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction
Water Quality Monitoring Results on 03 April 2017**

(Mid-Ebb Tide)

Location	Weather Condition	Sea Condition**	Sampling Time	Depth (m)		Temperature (°C)		pH		Salinity ppt		DO Saturation (%)		Dissolved Oxygen (mg/L)			Turbidity(NTU)			Suspended Solids (mg/L)			
						Value	Average	Value	Average	Value	Average	Value	Average	Value	Average	DA*	Value	Average	DA*	Value	Average	DA*	
C1	Cloudy	Moderate	18:22	Surface	1	21.0	20.9	7.9	7.9	30.3	30.2	99.8	99.5	7.5	7.5	7.1	4.3	4.5	5.4	1.8	1.8	2.3	
					20.8	20.7	7.9	7.9	30.0	30.8	99.1	98.7	7.4	6.6	4.6		5.6	1.8		3.4			
				Middle	10	20.7	20.7	7.9	7.9	30.8	30.8	88.7	89.3	89.0	6.7	6.7	6.7	5.5	5.6	3.4	3.4		
C2	Cloudy	Moderate	16:34	Surface	1	20.8	20.7	7.9	7.9	30.1	30.1	95.5	96.1	7.2	7.3	7.1	4.1	4.1	4.9	2.3	2.3	3.3	
					20.6	20.7	7.9	7.9	30.1	30.8	96.7	89.3	7.3	6.7	4.0		4.6	2.3		3.2			
				Middle	17.5	20.7	20.6	7.9	7.9	30.8	30.8	89.3	90.4	89.9	6.7	6.8	6.8	4.5	4.6	3.1	3.2		
G1	Cloudy	Moderate	17:22	Surface	1	20.9	20.8	7.9	7.9	30.5	30.5	94.0	92.1	93.1	7.0	7.0	6.9	4.5	4.6	4.9	1.4	1.4	2.0
					20.7	20.7	7.9	7.9	30.5	30.8	92.1	89.8	6.9	6.8	4.7	5.0		1.4	2.5				
				Middle	4	20.6	20.5	7.9	7.9	30.7	30.8	87.7	89.8	88.8	6.6	6.7	6.7	4.9	5.0	2.5	2.5		
G2	Cloudy	Moderate	17:04	Surface	1	20.7	20.8	8.0	8.0	30.7	30.7	95.0	95.9	7.1	7.2	7.0	4.3	4.4	5.2	2.5	2.5	3.2	
					20.8	20.7	7.9	7.9	31.0	31.0	96.8	89.2	7.2	6.6	4.4		4.8	2.5		3.9			
				Middle	5	20.8	20.7	7.9	7.9	31.0	31.0	88.6	89.7	89.2	6.6	6.7	6.7	4.7	4.8	3.9	3.9		
G3	Cloudy	Moderate	17:33	Surface	1	20.7	20.7	7.9	7.9	30.7	30.7	93.9	93.9	7.0	7.1	7.1	4.2	4.2	5.1	1.3	1.3	1.3	
					20.6	20.7	7.9	7.9	30.7	30.7	93.9	93.9	7.1	7.1	4.1		4.2	1.3		1.3			
				Middle	4	20.5	20.5	7.9	8.0	30.9	30.9	93.1	92.9	93.0	7.0	7.0	7.0	5.0	5.0	1.4	1.4		
G4	Cloudy	Moderate	17:53	Surface	1	21.0	20.9	7.9	7.9	30.0	30.1	85.8	85.1	6.4	6.4	6.4	4.9	4.8	5.4	2.6	2.7	2.7	
					20.8	20.8	7.9	7.9	30.1	30.6	84.4	83.3	6.3	6.2	4.6		5.7	2.7		2.2			
				Middle	4	20.9	20.8	7.9	7.9	30.6	30.6	83.1	83.4	83.3	6.2	6.3	6.3	5.7	5.7	2.1	2.2		
M1	Cloudy	Moderate	17:13	Surface	1	20.7	20.7	7.9	8.0	30.7	30.7	91.4	91.6	91.5	6.9	6.9	6.9	4.6	4.7	5.1	2.5	2.5	3.2
					20.7	20.7	8.0	8.0	30.7	30.7	91.6	91.5	6.9	6.9	4.7	4.7		2.4	2.4				
				Middle	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	0.0	0.0	
M2	Cloudy	Moderate	16:55	Surface	1	20.7	20.7	7.9	7.9	30.2	30.2	90.1	90.1	6.8	6.8	6.8	4.4	4.3	5.1	1.9	2.0	2.1	
					20.6	20.7	7.9	7.9	30.1	30.6	90.1	88.9	6.8	6.7	4.2		5.2	2.0		2.6			
				Middle	5.5	20.7	20.6	7.9	7.9	30.6	30.6	88.9	88.6	88.8	6.7	6.7	6.7	5.3	5.3	2.6	2.6		
M3	Cloudy	Moderate	17:44	Surface	1	21.1	21.0	7.9	7.9	30.1	30.1	90.7	91.1	6.8	6.9	6.7	3.6	3.6	4.8	1.5	1.5	1.7	
					20.9	20.9	7.9	7.9	30.1	30.6	91.5	84.6	6.9	6.3	3.6		4.7	1.5		1.9			
				Middle	4	21.0	20.9	7.9	7.9	30.6	30.6	83.9	85.3	84.6	6.3	6.4	6.4	4.9	4.8	1.9	1.9		
M4	Cloudy	Moderate	16:46	Surface	1	20.5	20.6	7.9	7.9	30.7	30.8	96.7	96.6	7.3	7.3	7.1	4.1	4.2	5.3	2.0	2.0	1.9	
					20.6	20.4	7.9	7.9	30.8	30.9	96.6	91.8	7.2	6.9	4.2		5.1	1.9		2.0			
				Middle	4	20.5	20.4	7.9	7.9	30.9	30.9	91.8	91.2	91.5	6.9	6.9	6.9	5.1	5.1	2.0	2.0		
M5	Cloudy	Moderate	18:13	Surface	1	20.9	20.9	7.9	7.9	30.2	30.3	88.3	89.1	6.6	6.7	6.7	4.7	4.6	5.8	1.7	1.7	2.0	
					20.9	20.7	7.9	7.9	30.4	30.7	89.9	88.4	6.7	6.6	4.5		5.7	1.7		1.9			
				Middle	5.5	20.8	20.7	7.9	7.9	30.6	30.7	87.5	89.2	88.4	6.6	6.7	6.7	5.8	5.8	1.9	1.9		
M6	Cloudy	Moderate	18:02	Surface	-	-	-	-	-	-	-	-	-	-	7.1	-	-	5.2	-	-	2.1		
					20.9	20.9	8.0	8.0	29.8	30.0	94.6	94.6	7.1	7.1		5.1	5.2		2.1	2.1			
				Middle	2	20.8	20.9	8.0	8.0	30.1	30.0	94.6	94.6	7.1	7.1	7.1	5.2	5.2	-	-			

Remarks: *DA: Depth-Averaged
**Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

Appendix I - Action and Limit Levels for Marine Water Quality on 3 April 2017 (Mid-Ebb Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>C2: 7.3 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>C2: 7.9 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>		
	Surface	<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 2.8 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 3.0 mg/L</u>
	<u>Stations M1-M5</u>		
	Surface	<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 2.8 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 3.0 mg/L</u>
	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 5.2 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 5.6 mg/L</u>
	<u>Station M6</u>		
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction
Water Quality Monitoring Results on 03 April 2017

(Mid-Flood Tide)

Location	Weather Condition	Sea Condition**	Sampling Time	Depth (m)		Temperature (°C)		pH		Salinity ppt		DO Saturation (%)		Dissolved Oxygen (mg/L)			Turbidity(NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Value	Average	DA*	Value	Average	DA*	Value	Average	DA*
C1	Cloudy	Moderate	11:42	Surface	1	21.2	21.2	7.9	8.0	30.1	30.0	94.2	94.5	7.0	7.1	6.8	4.5	4.5	5.9	3.2	3.3	3.2
				Middle	10	21.1	21.0	7.9	7.9	30.2	30.2	86.0	85.7	6.4	6.4	6.4	6.0	6.1	3.1	3.2		
				Bottom	19	20.8	20.8	7.9	7.9	29.8	29.8	83.9	84.0	6.3	6.3	6.3	6.9	7.0	3.2	3.2		
C2	Cloudy	Moderate	09:31	Surface	1	20.8	20.9	7.9	7.9	29.7	29.6	91.0	91.0	6.8	6.8	6.7	4.1	4.1	5.3	2.3	2.4	2.0
				Middle	17.5	20.9	20.9	7.9	7.9	29.4	29.5	86.3	86.7	6.5	6.6	6.6	4.8	5.0	1.8	1.8		
				Bottom	34	20.7	20.7	7.9	7.9	29.6	29.6	85.3	85.3	6.4	6.4	6.4	6.8	6.8	1.9	1.9		
G1	Cloudy	Moderate	10:21	Surface	1	20.9	20.9	7.9	7.9	29.7	30.0	90.9	90.8	6.8	6.8	6.7	3.9	3.9	4.9	1.1	1.1	1.0
				Middle	4	20.8	20.8	8.0	8.0	30.3	30.3	85.9	86.7	6.4	6.5	6.5	4.5	4.6	1.0	1.0		
				Bottom	7	20.7	20.7	8.0	8.0	30.4	30.5	83.7	82.9	6.3	6.3	6.3	6.1	6.2	0.9	0.9		
G2	Cloudy	Moderate	10:03	Surface	1	20.9	20.9	7.9	7.9	30.2	30.3	91.5	91.4	6.9	6.9	6.6	3.9	3.9	4.8	3.6	3.7	2.8
				Middle	5	20.8	20.8	7.9	7.9	30.6	30.6	84.8	84.3	6.3	6.3	6.6	4.8	4.9	2.5	2.5		
				Bottom	9	20.8	20.8	8.0	8.0	30.9	30.9	82.9	82.4	6.2	6.2	6.2	5.7	5.7	2.1	2.1		
G3	Cloudy	Moderate	10:34	Surface	1	20.9	20.9	7.9	7.9	30.4	30.3	92.5	92.8	6.9	7.0	6.7	4.4	4.5	5.2	1.7	1.7	2.4
				Middle	4	20.8	20.8	7.9	7.9	30.3	30.3	85.9	85.1	6.4	6.4	6.4	5.2	5.3	1.6	1.6		
				Bottom	7	20.8	20.8	7.9	7.9	30.6	30.6	84.7	85.0	6.3	6.4	6.4	5.8	5.9	3.7	3.8		
G4	Cloudy	Moderate	11:08	Surface	1	21.0	21.0	7.9	7.9	29.6	29.7	91.8	91.8	6.9	6.9	6.7	4.0	3.9	4.5	1.1	1.1	1.7
				Middle	4	20.9	20.9	7.9	7.9	30.3	30.3	86.5	86.9	6.5	6.5	6.5	4.5	4.6	2.8	2.9		
				Bottom	7	20.8	20.9	7.9	7.9	30.5	30.5	88.7	85.5	6.6	6.5	6.5	6.7	6.8	1.0	1.0		
M1	Cloudy	Moderate	10:12	Surface	1	20.9	21.0	7.9	7.9	30.5	30.5	90.1	90.4	6.7	6.8	6.8	4.5	4.6	5.0	2.5	2.5	2.4
				Middle	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
				Bottom	4.4	21.0	20.9	7.9	7.9	30.3	30.4	86.5	86.4	6.5	6.5	6.5	5.4	5.2	2.2	2.2		
M2	Cloudy	Moderate	09:54	Surface	1	21.0	21.0	7.9	7.9	30.6	30.5	89.1	88.7	6.7	6.7	6.4	4.0	4.0	4.8	2.2	2.2	3.1
				Middle	5.5	20.9	20.9	7.9	7.9	30.5	30.5	82.1	82.1	6.1	6.1	6.1	4.9	4.9	5.3	5.3		
				Bottom	10	20.7	20.8	7.9	7.9	30.7	30.7	81.5	82.1	6.1	6.1	6.1	5.5	5.6	1.8	1.8		
M3	Cloudy	Moderate	10:55	Surface	1	21.0	21.0	7.9	7.9	30.3	30.3	98.2	97.8	7.3	7.3	6.9	4.1	4.2	5.0	3.1	3.1	3.3
				Middle	4	21.0	21.0	7.9	7.9	30.7	30.7	86.5	86.5	6.5	6.5	6.5	5.4	5.3	3.7	3.8		
				Bottom	7	20.9	20.9	7.9	7.9	30.9	30.9	80.5	80.5	6.0	6.0	6.0	5.4	5.5	3.1	3.1		
M4	Cloudy	Moderate	09:45	Surface	1	20.8	20.8	7.9	7.9	29.5	29.6	91.7	92.2	6.9	7.0	6.8	4.9	4.9	5.5	2.5	2.6	3.7
				Middle	4	20.9	20.8	7.9	7.9	30.0	30.0	86.5	85.7	6.5	6.5	6.5	4.8	5.4	5.5	5.5		
				Bottom	7	20.8	20.7	7.9	7.9	30.2	30.2	83.5	83.1	6.3	6.3	6.3	6.0	6.1	3.0	3.1		
M5	Cloudy	Moderate	11:34	Surface	1	21.0	21.0	7.9	7.9	30.2	30.2	90.6	90.5	6.8	6.8	6.6	4.8	4.9	5.7	1.7	1.7	1.9
				Middle	5.5	20.9	20.9	7.9	7.9	30.3	30.4	85.0	85.3	6.4	6.4	6.4	5.5	5.6	1.8	1.8		
				Bottom	10	20.8	20.8	8.0	8.0	30.4	30.4	83.2	83.0	6.2	6.2	6.2	6.6	6.6	2.1	2.1		
M6	Cloudy	Moderate	11:20	Surface	-	-	-	-	-	-	-	-	-	-	-	6.9	-	-	5.2	-	-	2.4
				Middle	2	21.0	21.0	7.9	7.9	30.5	30.5	92.0	92.6	6.9	6.9	6.9	5.1	5.3	2.4	2.4		
				Bottom	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		

Remarks: *DA: Depth-Averaged
 **Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

Appendix I - Action and Limit Levels for Marine Water Quality on 3 April 2017 (Mid-Flood Tide)

<u>Parameter</u> <u>(unit)</u>	<u>Depth</u>	<u>Action Level</u>	<u>Limit Level</u>
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>CI: 8.4 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>CI: 9.1 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
	SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>	
Surface		<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 4.0 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 4.3 mg/L</u>
<u>Stations M1-M5</u>			
Surface		<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 4.0 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 4.3 mg/L</u>
<u>Stations G1-G4, M1-M5</u>			
Bottom		<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 3.8 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 4.2 mg/L</u>
<u>Station M6</u>			
Intake Level		<u>8.3 mg/L</u>	<u>8.6 mg/L</u>

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

Appendix I - Action and Limit Levels for Marine Water Quality on 5 April 2017 (Mid-Ebb Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>C2: 6.7 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>C2: 7.3 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
	SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>	
Surface		<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 6.2 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 6.8 mg/L</u>
<u>Stations M1-M5</u>			
Surface		<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 6.2 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 6.8 mg/L</u>
<u>Stations G1-G4, M1-M5</u>			
Bottom		<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 5.3 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 5.7 mg/L</u>
<u>Station M6</u>			
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

Appendix I - Action and Limit Levels for Marine Water Quality on 5 April 2017 (Mid-Flood Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>CI: 10.3 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>CI: 10.8 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
	SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>	
Surface		<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 7.1 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 7.7 mg/L</u>
<u>Stations M1-M5</u>			
Surface		<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 7.1 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 7.7 mg/L</u>
<u>Stations G1-G4, M1-M5</u>			
Bottom		<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 4.2 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 4.6 mg/L</u>
<u>Station M6</u>			
Intake Level		<u>8.3 mg/L</u>	<u>8.6 mg/L</u>

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

Appendix I - Action and Limit Levels for Marine Water Quality on 8 April 2017 (Mid-Ebb Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>C2: 9.1 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>C2: 9.9 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
	SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>	
Surface		<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 3.2 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 3.5 mg/L</u>
<u>Stations M1-M5</u>			
Surface		<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 3.2 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 3.5 mg/L</u>
<u>Stations G1-G4, M1-M5</u>			
Bottom		<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 2.9 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 3.1 mg/L</u>
<u>Station M6</u>			
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction
Water Quality Monitoring Results on 08 April 2017

(Mid-Flood Tide)

Location	Weather Condition	Sea Condition**	Sampling Time	Depth (m)	Temperature (°C)		pH		Salinity ppt		DO Saturation (%)		Dissolved Oxygen (mg/L)			Turbidity (NTU)			Suspended Solids (mg/L)				
					Value	Average	Value	Average	Value	Average	Value	Average	Value	Average	DA*	Value	Average	DA*	Value	Average	DA*		
C1	Sunny	Moderate	16:57	Surface	1	24.5	24.4	8.2	8.2	31.1	31.1	98.8	100.0	6.9	7.1	7.0	6.6	4.0	3.8	4.9	2.4	2.4	2.5
				Middle	10	24.5	24.4	8.1	8.2	31.3	31.3	87.6	87.8	6.1	6.2	6.2	6.1	6.2	4.1	4.5	2.3	2.4	
				Bottom	19	24.3	24.3	8.1	8.2	31.4	31.4	86.6	86.6	6.1	6.1	6.1	6.1	6.1	6.0	6.4	2.6	2.6	
C2	Sunny	Moderate	15:19	Surface	1	24.2	24.2	8.2	8.2	31.4	31.4	95.0	95.6	6.7	6.8	6.8	6.5	2.2	2.2	2.7	2.8	2.3	
				Middle	18	24.2	24.2	8.1	8.1	31.4	31.4	88.2	88.2	6.2	6.2	6.2	6.1	6.2	2.4	2.6	2.1		2.1
				Bottom	35	24.1	24.2	8.1	8.2	31.5	31.5	87.8	87.9	6.2	6.2	6.2	6.2	6.2	4.9	4.8	2.1		2.1
G1	Sunny	Moderate	16:01	Surface	1	24.1	24.1	8.2	8.2	31.2	31.2	94.7	95.3	6.7	6.7	6.7	6.4	2.7	2.6	2.1	2.1	2.1	
				Middle	4	24.1	24.0	8.2	8.2	31.3	31.3	85.5	86.5	6.0	6.1	6.1	6.1	6.1	2.9	3.1	2.3		2.3
				Bottom	7	24.0	23.8	8.2	8.2	31.4	31.4	85.9	86.8	6.0	6.1	6.1	6.1	6.1	4.3	4.4	2.0		2.0
G2	Sunny	Moderate	15:43	Surface	1	24.1	24.1	8.1	8.1	31.7	31.7	93.6	94.3	6.6	6.6	6.6	6.4	2.9	2.9	1.3	1.4	1.8	
				Middle	5	24.1	24.0	8.1	8.2	31.8	31.8	87.5	86.4	6.1	6.1	6.1	6.1	6.1	3.4	3.4	1.8		1.8
				Bottom	9	24.1	24.0	8.1	8.1	32.2	32.2	83.7	82.4	5.9	5.8	5.9	5.9	5.9	3.9	3.9	2.1		2.1
G3	Sunny	Moderate	16:11	Surface	1	24.1	24.1	8.1	8.1	31.1	31.1	95.4	96.0	6.7	6.8	6.8	6.5	3.0	2.9	1.8	1.8	1.9	
				Middle	4	24.0	24.0	8.1	8.1	31.5	31.5	86.6	86.4	6.1	6.1	6.1	6.1	6.1	3.5	3.8	2.1		2.1
				Bottom	7	24.1	23.9	8.1	8.1	31.8	31.7	85.2	84.4	6.0	5.9	6.0	6.0	6.0	4.7	4.7	1.8		1.8
G4	Sunny	Moderate	16:30	Surface	1	24.5	24.4	8.1	8.1	31.2	31.2	95.0	95.1	6.6	6.7	6.7	6.4	2.7	2.7	2.1	2.1	2.0	
				Middle	4	24.5	24.4	8.1	8.1	31.5	31.5	87.0	87.1	6.1	6.1	6.1	6.1	6.1	3.0	3.1	1.8		1.8
				Bottom	7	24.3	24.3	8.1	8.1	31.9	32.0	90.7	90.8	6.3	6.3	6.3	6.3	6.3	5.9	6.1	2.1		2.1
M1	Sunny	Moderate	15:52	Surface	1	24.1	24.1	8.1	8.1	31.4	31.4	93.9	94.1	6.6	6.6	6.6	6.4	2.6	2.8	2.2	2.3	2.3	
				Middle	3	24.1	24.0	8.1	8.1	31.4	31.4	87.0	86.6	6.1	6.1	6.1	6.1	6.1	2.8	2.8	1.8		1.9
				Bottom	5	24.5	24.4	8.1	8.1	31.4	31.4	87.9	88.3	6.1	6.2	6.2	6.2	6.2	3.8	3.7	2.7		2.7
M2	Sunny	Moderate	15:36	Surface	1	24.1	24.1	8.2	8.2	31.6	31.6	89.4	89.6	6.3	6.3	6.3	6.1	2.7	2.8	2.8	2.8	2.6	
				Middle	5.5	24.1	24.1	8.1	8.1	31.6	31.7	83.0	82.8	5.8	5.8	5.8	5.7	5.7	3.6	3.5	2.4		2.4
				Bottom	10	24.1	24.1	8.1	8.1	31.9	31.9	81.4	81.4	5.7	5.7	5.7	5.7	5.7	3.7	3.7	2.5		2.5
M3	Sunny	Moderate	16:23	Surface	1	24.4	24.4	8.1	8.2	31.7	31.7	106.9	104.9	7.5	7.4	7.4	6.8	2.9	3.0	1.8	1.8	1.5	
				Middle	4.5	24.4	24.4	8.1	8.1	31.9	32.0	88.8	89.0	6.2	6.2	6.2	6.1	6.2	3.7	3.6	2.2		2.2
				Bottom	8	24.3	24.3	8.1	8.1	32.3	32.3	81.6	81.1	5.7	5.7	5.7	5.7	5.7	3.5	3.6	0.5		0.6
M4	Sunny	Moderate	15:27	Surface	1	24.1	24.1	8.1	8.1	31.5	31.5	95.2	95.2	6.7	6.7	6.7	6.5	4.0	3.9	1.4	1.4	2.0	
				Middle	4	24.1	23.8	8.1	8.1	31.5	31.5	87.8	86.3	6.2	6.2	6.2	6.1	6.2	4.2	4.1	2.2		2.2
				Bottom	7	24.1	23.4	8.1	8.2	31.5	31.6	84.4	82.0	5.9	5.8	5.9	5.9	5.9	4.3	4.4	2.2		2.4
M5	Sunny	Moderate	16:49	Surface	1	24.5	24.4	8.1	8.2	31.4	31.4	94.8	94.4	6.6	6.6	6.6	6.4	3.4	3.6	2.4	2.5	2.5	
				Middle	5.5	24.5	24.4	8.2	8.2	31.5	31.5	86.2	86.7	6.0	6.1	6.1	6.1	6.1	4.0	4.0	2.5		2.5
				Bottom	10	24.3	24.3	8.2	8.2	31.6	31.6	83.3	83.0	5.8	5.8	5.8	5.8	5.8	4.9	5.1	2.5		2.5
M6	Sunny	Moderate	16:37	Surface	-	-	-	-	-	-	-	-	-	-	-	-	6.9	-	-	-	-	2.4	
				Middle	2.1	24.5	24.4	8.2	8.2	31.1	31.1	97.4	98.8	6.8	6.9	6.9	6.1	6.1	3.2	3.4	2.3		2.4
				Bottom	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		-

Remarks: *DA: Depth-Averaged
**Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

Appendix I - Action and Limit Levels for Marine Water Quality on 8 April 2017 (Mid-Flood Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>CI: 7.7 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>CI: 8.3 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
	SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>	
Surface		<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 2.9 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 3.1 mg/L</u>
<u>Stations M1-M5</u>			
Surface		<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 2.9 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 3.1 mg/L</u>
<u>Stations G1-G4, M1-M5</u>			
Bottom		<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 3.1 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 3.4 mg/L</u>
<u>Station M6</u>			
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

Appendix I - Action and Limit Levels for Marine Water Quality on 10 April 2017 (Mid-Ebb Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>C2: 7.6 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>C2: 8.2 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
	SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>	
Surface		<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 4.2 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 4.6 mg/L</u>
<u>Stations M1-M5</u>			
Surface		<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 4.2 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 4.6 mg/L</u>
<u>Stations G1-G4, M1-M5</u>			
Bottom		<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 3.6 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 3.9 mg/L</u>
<u>Station M6</u>			
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

Appendix I - Action and Limit Levels for Marine Water Quality on 10 April 2017 (Mid-Flood Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>CI: 7.7 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>CI: 8.3 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
	SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>	
Surface		<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 3.6 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 3.9 mg/L</u>
<u>Stations M1-M5</u>			
Surface		<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 3.6 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 3.9 mg/L</u>
<u>Stations G1-G4, M1-M5</u>			
Bottom		<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 7.1 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 7.7 mg/L</u>
<u>Station M6</u>			
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

Appendix I - Action and Limit Levels for Marine Water Quality on 12 April 2017 (Mid-Ebb Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>C2: 7.1 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>C2: 7.7 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
	SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>	
Surface		<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 6.1 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 6.6 mg/L</u>
<u>Stations M1-M5</u>			
Surface		<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 6.1 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 6.6 mg/L</u>
<u>Stations G1-G4, M1-M5</u>			
Bottom		<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 7.7 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 8.3 mg/L</u>
<u>Station M6</u>			
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction
Water Quality Monitoring Results on 12 April 2017**

(Mid-Flood Tide)

Location	Weather Condition	Sea Condition**	Sampling Time	Depth (m)		Temperature (°C)		pH		Salinity ppt		DO Saturation (%)		Dissolved Oxygen (mg/L)			Turbidity(NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Value	Average	DA*	Value	Average	DA*	Value	Average	DA*
C1	Rainy	Moderate	20:01	Surface	1	22.6	22.5	8.0	8.0	31.0	31.0	100.3	100.4	7.3	7.3	7.1	4.3	4.3	5.7	4.8	4.8	3.5
				Middle	10	22.3	22.2	8.1	8.1	31.1	31.2	93.1	92.6	6.8	6.8	7.1	5.5	5.5		4.0	1.6	
				Bottom	19	21.7	21.6	8.2	8.2	31.3	31.3	89.8	90.0	6.6	6.6	6.6	7.1	7.2		4.0	3.9	
C2	Rainy	Moderate	18:02	Surface	1	22.4	22.6	8.0	8.0	31.8	31.8	98.2	98.4	7.1	7.1	7.0	2.7	2.8	3.9	1.7	1.8	2.3
				Middle	18	21.8	21.8	8.2	8.2	32.1	32.1	93.2	92.6	6.8	6.8	7.0	3.1	3.1		1.0	1.0	
				Bottom	35	21.6	21.7	8.2	8.3	32.1	32.1	91.5	92.2	6.7	6.7	6.7	5.8	5.9		4.0	3.9	
G1	Rainy	Moderate	18:52	Surface	1	22.3	22.2	8.1	8.1	31.0	31.0	96.7	96.1	7.0	7.0	6.9	3.0	3.0	3.9	3.7	3.7	3.6
				Middle	4	21.9	21.9	8.2	8.2	31.2	31.2	91.3	90.6	6.7	6.7	6.9	3.3	3.3		4.2	4.1	
				Bottom	7	21.5	21.6	8.2	8.2	31.3	31.4	89.6	89.5	6.6	6.6	6.6	5.4	5.4		2.8	2.8	
G2	Rainy	Moderate	18:32	Surface	1	22.0	22.1	8.0	8.0	31.7	31.7	94.9	94.8	6.9	6.9	6.8	3.3	3.4	4.2	3.8	3.9	2.5
				Middle	5	22.1	22.2	8.2	8.2	32.1	32.1	92.2	92.8	6.7	6.7	6.8	4.1	4.1		1.8	1.8	
				Bottom	9	21.4	21.4	8.2	8.2	32.8	32.8	86.5	86.9	6.3	6.4	6.4	5.1	5.2		1.8	1.8	
G3	Rainy	Moderate	19:03	Surface	1	22.1	22.0	7.9	7.9	31.5	31.5	98.3	97.5	7.1	7.1	6.9	3.4	3.3	4.4	2.2	2.2	2.3
				Middle	4	21.9	22.1	8.1	8.1	31.5	31.5	91.9	92.9	6.7	6.7	6.9	4.2	4.2		3.6	3.5	
				Bottom	7	21.3	21.6	8.2	8.2	32.0	32.0	88.0	88.6	6.5	6.5	6.5	5.8	5.7		1.1	1.2	
G4	Rainy	Moderate	19:29	Surface	1	22.6	22.6	8.0	8.0	31.4	31.4	97.0	96.3	7.0	7.0	6.8	3.5	3.5	4.7	1.2	1.2	1.8
				Middle	4	22.1	22.1	8.1	8.1	32.2	32.3	91.6	91.5	6.6	6.6	6.8	3.7	3.7		1.2	1.2	
				Bottom	7	21.6	21.6	8.2	8.3	32.1	32.1	93.2	92.5	6.8	6.8	6.8	7.0	6.8		2.9	2.8	
M1	Rainy	Moderate	18:42	Surface	1	22.2	22.3	8.0	8.0	31.7	31.7	96.0	95.9	7.0	6.9	6.9	2.9	2.8	3.7	1.7	1.8	2.0
				Middle	3	21.8	21.9	8.1	8.1	31.7	31.8	91.8	92.5	6.7	6.7	6.9	3.4	3.4		2.7	2.7	
				Bottom	5	21.6	21.6	8.2	8.2	32.0	32.0	90.2	89.9	6.6	6.6	6.6	4.9	4.7		1.5	1.4	
M2	Rainy	Moderate	18:23	Surface	1	22.1	22.2	8.0	8.0	32.2	32.2	92.8	93.2	6.7	6.8	6.6	3.4	3.4	4.0	2.6	2.6	1.3
				Middle	5.5	22.0	22.0	8.1	8.1	32.2	32.2	87.7	87.7	6.4	6.4	6.3	4.1	4.1		<0.5	<0.5	
				Bottom	10	21.1	21.1	8.3	8.3	32.4	32.5	84.5	84.7	6.2	6.3	6.3	4.6	4.6		0.9	0.9	
M3	Rainy	Moderate	19:16	Surface	1	22.4	22.5	8.0	8.0	31.8	31.9	107.9	108.0	7.8	7.8	7.3	3.2	3.3	4.2	2.9	2.9	2.2
				Middle	4.5	22.2	22.2	8.1	8.1	32.4	32.4	93.4	93.8	6.7	6.8	7.3	4.4	4.5		2.5	2.6	
				Bottom	8	21.4	21.5	8.1	8.2	32.4	32.4	83.7	84.4	6.1	6.2	6.2	4.7	4.6		1.2	1.2	
M4	Rainy	Moderate	18:14	Surface	1	22.4	22.4	8.1	8.1	30.8	30.8	97.9	97.4	7.1	7.1	6.9	4.4	4.5	4.9	4.8	4.8	3.3
				Middle	4	22.0	22.1	8.1	8.1	31.3	31.4	92.3	92.3	6.7	6.7	6.9	4.6	4.7		2.6	2.6	
				Bottom	7	21.2	21.3	8.1	8.1	31.4	31.4	87.3	87.2	6.5	6.5	6.5	5.5	5.6		2.5	2.6	
M5	Rainy	Moderate	19:51	Surface	1	22.4	22.4	8.0	8.0	32.1	32.2	96.6	96.6	7.0	7.0	6.9	4.1	4.1	4.8	1.6	1.7	2.1
				Middle	5.5	22.3	22.4	8.2	8.2	31.7	31.7	91.9	92.3	6.7	6.7	6.9	4.3	4.3		2.7	2.7	
				Bottom	10	21.4	21.5	8.3	8.3	32.0	32.0	86.8	87.2	6.4	6.4	6.4	6.0	6.1		1.9	1.9	
M6	Rainy	Moderate	19:42	Surface	-	-	-	-	-	-	-	-	-	-	-	7.2	-	-	4.0	-	-	4.2
				Middle	2.1	22.3	22.3	8.0	8.0	31.7	31.8	99.4	100.0	7.2	7.2	7.2	3.9	4.0		4.3	4.1	
				Bottom	-	-	-	-	-	-	-	-	-	-	-	-	-	-		-	-	

Remarks: *DA: Depth-Averaged
 **Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.
 The reporting limit for laboratory analysis of suspended solids is 2.5 mg/L. For the results below the reporting limit, the SS level will be taken as 2.5 mg/L.

Appendix I - Action and Limit Levels for Marine Water Quality on 12 April 2017 (Mid-Flood Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>CI: 8.6 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>CI: 9.4 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
	SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>	
Surface		<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 5.8 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 6.2 mg/L</u>
<u>Stations M1-M5</u>			
Surface		<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 5.8 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 6.2 mg/L</u>
<u>Stations G1-G4, M1-M5</u>			
Bottom		<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 4.8 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 5.2 mg/L</u>
<u>Station M6</u>			
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction
Water Quality Monitoring Results on 14 April 2017**

(Mid-Ebb Tide)

Location	Weather Condition	Sea Condition**	Sampling Time	Depth (m)		Temperature (°C)		pH		Salinity ppt		DO Saturation (%)		Dissolved Oxygen (mg/L)			Turbidity(NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Value	Average	DA*	Value	Average	DA*	Value	Average	DA*
C1	Fine	Moderate	14:57	Surface	1	20.7	20.5	7.9	7.9	30.0	30.0	95.5	95.4	7.2	7.2	7.2	3.5	3.6	4.6	3.2	3.2	1.9
					20.2	20.5	7.8	7.8	30.0	30.0	95.2	95.2	7.2	7.2	3.6		3.6	3.1		3.1		
					20.3	20.4	7.8	7.7	29.9	30.0	93.0	93.1	7.1	7.1	5.3		5.4	0.9		0.9		
C2	Fine	Moderate	13:05	Middle	10	20.5	20.4	7.6	7.6	30.0	30.0	93.2	93.1	7.0	7.1	6.6	4.8	4.9	3.7	2.6	2.7	3.1
					20.1	20.3	7.6	7.5	30.0	30.0	91.1	91.5	6.9	6.9	5.5		5.5	0.9		0.9		
					20.5	20.3	7.5	7.6	30.1	30.1	91.9	91.5	6.9	6.9	4.8		4.9	1.5		1.5		
G1	Fine	Moderate	13:58	Surface	1	20.8	20.6	7.6	7.6	29.4	29.5	87.9	87.2	6.6	6.6	6.6	3.1	3.3	4.1	3.8	3.8	2.0
					20.3	20.1	7.6	7.5	29.5	29.8	87.1	85.7	6.6	6.6	3.4		3.6	3.7		3.7		
					19.9	20.2	7.5	7.5	29.8	29.8	85.1	85.7	6.5	6.6	3.8		3.6	2.6		2.7		
G2	Fine	Moderate	13:37	Middle	4	20.2	20.4	7.4	7.5	29.7	29.8	87.2	86.4	6.6	6.6	6.6	3.9	4.3	3.7	2.8	2.8	3.4
					20.2	20.4	7.5	7.5	29.7	29.8	85.5	86.4	6.6	6.6	4.7		4.3	2.8		2.8		
					20.6	20.5	7.8	7.9	30.0	30.0	91.5	91.7	6.9	7.0	3.9		4.2	1.7		1.7		
G3	Fine	Moderate	14:08	Surface	1	20.7	20.5	8.0	8.0	29.7	29.8	90.7	90.0	6.8	6.8	6.9	3.0	3.0	4.4	1.2	1.2	3.0
					20.2	20.3	8.0	7.9	29.8	29.9	90.0	91.7	6.8	6.8	3.0		3.0	1.2		1.2		
					20.6	20.5	7.8	7.9	29.9	30.0	91.5	91.7	6.9	7.0	3.9		4.2	1.7		1.7		
G4	Fine	Moderate	14:30	Middle	4	20.3	20.3	7.9	7.9	30.3	30.3	90.0	89.7	6.8	6.8	6.9	2.6	2.7	3.7	3.4	3.4	2.0
					20.3	20.3	7.9	7.9	30.3	30.3	90.0	89.3	6.8	6.8	3.5		3.6	3.6		3.7		
					20.0	20.4	7.8	7.8	30.5	30.5	89.7	90.3	6.8	6.8	4.7		4.8	3.2		3.2		
M1	Fine	Moderate	13:48	Surface	1	21.0	21.0	8.0	8.0	30.1	30.0	89.2	89.3	6.7	6.7	6.8	3.2	3.3	4.2	1.2	1.2	1.1
					21.0	20.5	7.9	7.9	29.9	30.2	89.3	89.4	6.7	6.8	3.4		3.3	1.2		1.2		
					20.6	20.4	7.9	7.9	30.1	30.2	90.0	89.7	6.8	6.8	4.8		5.1	1.2		1.2		
M2	Fine	Moderate	13:26	Middle	3	20.4	20.5	7.9	7.9	30.2	30.2	89.4	89.4	6.8	6.8	6.7	4.0	4.3	3.0	2.9	2.9	2.8
					19.9	20.6	7.7	7.8	29.7	29.7	89.4	89.9	6.8	6.9	3.2		3.1	2.6		2.6		
					20.4	20.5	7.6	7.8	29.7	29.7	90.4	88.4	6.8	6.7	3.0		3.0	2.5		2.9		
M3	Fine	Moderate	14:19	Surface	1	20.4	20.6	7.7	7.7	29.6	29.7	91.6	91.8	6.9	6.9	6.9	2.8	3.1	3.6	2.9	2.9	2.3
					20.7	20.8	7.7	7.7	29.7	29.8	92.0	89.9	6.9	6.8	3.3		3.1	2.9		2.9		
					20.6	20.7	7.6	7.7	29.7	29.8	89.6	89.9	6.8	6.8	3.0		3.1	2.9		2.9		
M4	Fine	Moderate	13:17	Middle	4	20.4	20.4	7.7	7.7	30.0	30.1	85.7	86.1	6.5	6.5	6.5	4.4	4.6	3.4	1.1	1.1	3.3
					20.4	20.1	7.7	7.7	29.7	29.8	89.1	89.1	6.8	6.8	4.4		4.4	1.1		1.1		
					20.5	20.4	7.7	7.7	30.0	30.0	87.8	87.3	6.6	6.6	3.9		3.9	3.1		3.1		
M5	Fine	Moderate	14:48	Surface	1	19.9	20.1	7.7	7.7	30.6	30.4	92.3	92.4	7.0	7.0	7.0	4.5	4.5	4.7	4.0	4.0	3.1
					20.3	20.2	7.7	7.6	30.1	30.0	92.5	91.4	7.0	6.9	4.4		4.4	3.9		3.9		
					20.2	20.2	7.6	7.5	29.9	30.0	91.4	91.4	6.9	6.9	4.7		5.1	3.9		3.9		
M6	Fine	Moderate	14:40	Middle	3.7	19.9	20.1	7.9	7.8	30.2	30.1	91.0	90.3	6.9	6.9	6.9	5.1	4.9	4.9	1.4	1.4	1.4
					20.3	20.3	7.7	7.7	30.0	30.1	89.5	90.3	6.8	6.9	4.6		4.6	1.4		1.4		
					-	-	-	-	-	-	-	-	-	-	-		-	-		-	-	

Remarks: *DA: Depth-Averaged
**Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

Appendix I - Action and Limit Levels for Marine Water Quality on 14 April 2017 (Mid-Ebb Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>C2: 5.2 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>C2: 5.6 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>		
	Surface	<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 4.6 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 4.9 mg/L</u>
	<u>Stations M1-M5</u>		
	Surface	<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 4.6 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 6.9 mg/L</u>
	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 3.4 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 3.6 mg/L</u>
	<u>Station M6</u>		
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction
Water Quality Monitoring Results on 14 April 2017**

(Mid-Flood Tide)

Location	Weather Condition	Sea Condition**	Sampling Time	Depth (m)		Temperature (°C)		pH		Salinity ppt		DO Saturation (%)		Dissolved Oxygen (mg/L)			Turbidity(NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Value	Average	DA*	Value	Average	DA*	Value	Average	DA*
C1	Fine	Moderate	08:51	Surface	1	19.9	19.9	7.9	7.9	29.7	29.7	88.4	89.2	6.8	6.9	6.9	4.9	4.9	4.4	4.5	4.5	3.5
				Middle	10	20.5	20.3	7.7	7.7	29.9	29.9	90.0	88.3	6.8	6.7	6.8	3.8	3.7		0.9	0.9	
				Bottom	19	20.7	20.6	7.7	7.7	30.2	30.2	89.3	89.6	6.7	6.8	6.8	4.6	4.6		5.2	5.2	
C2	Fine	Moderate	07:03	Surface	1	19.7	19.8	7.8	7.8	29.8	29.8	85.9	85.8	6.6	6.6	6.6	2.9	3.1	3.2	1.7	1.7	1.7
				Middle	18	20.1	20.4	7.5	7.5	29.8	29.9	85.1	86.3	6.5	6.5	6.5	3.3	3.3		0.5	0.5	
				Bottom	35	20.4	20.6	7.7	7.7	30.0	30.0	87.4	86.9	6.6	6.6	6.6	3.1	3.2		2.9	2.9	
G1	Fine	Moderate	07:53	Surface	1	19.9	20.1	7.8	7.9	30.2	30.1	87.7	87.9	6.7	6.7	6.7	3.5	3.7	4.2	4.3	4.3	3.7
				Middle	4	20.5	20.6	7.8	7.8	30.1	30.1	89.6	87.9	6.8	6.6	6.7	4.1	4.2		1.0	1.0	
				Bottom	7	20.6	20.4	7.8	7.9	30.2	30.2	89.3	87.8	6.7	6.7	6.7	4.4	4.6		5.7	5.7	
G2	Fine	Moderate	07:34	Surface	1	19.9	20.1	7.8	7.8	29.9	29.9	89.8	90.2	6.9	6.9	6.9	3.5	3.4	4.1	3.8	3.9	2.9
				Middle	5	20.2	20.3	7.6	7.7	29.8	29.9	88.8	90.1	6.8	6.8	6.8	3.6	3.9		1.8	1.8	
				Bottom	9	20.3	20.1	7.6	7.6	29.9	30.0	88.9	87.0	6.7	6.7	6.7	5.0	5.0		3.1	3.1	
G3	Fine	Moderate	08:03	Surface	1	20.7	20.5	7.8	7.9	29.8	29.8	90.3	89.5	6.8	6.8	6.8	3.1	3.3	3.8	3.1	3.2	3.0
				Middle	4	19.8	19.8	7.9	7.9	29.9	30.0	89.1	89.6	6.8	6.9	6.9	3.9	3.9		2.7	2.7	
				Bottom	7	19.6	20.0	7.9	7.9	30.1	30.1	88.4	88.0	6.8	6.8	6.8	4.1	4.1		3.1	3.1	
G4	Fine	Moderate	08:21	Surface	1	20.5	20.1	7.9	7.9	29.6	29.7	89.3	88.4	6.8	6.8	6.8	4.1	3.7	3.7	2.7	2.7	2.7
				Middle	4	20.4	20.2	8.0	8.0	30.1	30.2	87.6	86.3	6.6	6.6	6.6	3.6	3.5		1.2	1.2	
				Bottom	7	20.7	20.5	7.9	8.0	30.2	30.2	87.4	86.8	6.6	6.6	6.6	3.9	3.9		4.3	4.3	
M1	Fine	Moderate	07:43	Surface	1	20.1	20.1	7.8	7.8	30.2	30.1	89.6	89.5	6.8	6.8	6.8	3.5	3.6	3.9	2.2	2.3	2.6
				Middle	3	19.7	19.6	7.8	7.8	30.0	30.0	88.2	87.7	6.8	6.8	6.8	3.7	3.8		1.1	1.1	
				Bottom	5	20.3	20.3	7.7	7.8	30.0	30.1	88.3	87.8	6.7	6.7	6.7	4.3	4.2		4.4	4.5	
M2	Fine	Moderate	07:25	Surface	1	20.3	20.2	7.8	7.8	29.7	29.7	89.0	87.9	6.8	6.7	6.7	3.3	3.3	4.1	3.5	3.6	4.1
				Middle	5	20.0	20.3	7.7	7.8	29.8	29.8	87.0	88.0	6.6	6.6	6.6	3.7	3.9		3.7	3.7	
				Bottom	9	20.6	20.5	7.7	7.7	29.8	29.8	89.1	89.5	6.7	6.8	6.8	5.2	5.1		5.0	4.9	
M3	Fine	Moderate	08:12	Surface	1	20.4	20.5	7.8	7.9	30.1	30.1	89.3	89.1	6.8	6.8	6.8	3.8	3.7	3.5	3.1	3.1	3.0
				Middle	4	19.9	20.1	7.7	7.7	30.3	30.3	87.0	87.5	6.6	6.6	6.6	3.7	3.8		3.7	3.8	
				Bottom	7	20.1	20.3	7.7	7.8	30.5	30.5	85.3	84.9	6.5	6.5	6.5	3.0	3.0		2.1	2.2	
M4	Fine	Moderate	07:15	Surface	1	20.3	20.1	7.7	7.7	29.9	29.9	88.5	87.8	6.7	6.7	6.7	2.7	2.8	3.4	2.2	1.3	2.3
				Middle	4	20.2	20.1	7.7	7.7	29.8	29.9	88.4	86.6	6.7	6.7	6.7	3.4	3.3		2.9	2.9	
				Bottom	7	20.6	20.6	7.7	7.7	29.8	29.9	87.9	86.1	6.6	6.6	6.6	4.1	4.2		2.8	2.8	
M5	Fine	Moderate	08:40	Surface	1	20.1	20.0	8.0	8.0	29.9	29.9	91.1	90.3	6.9	6.9	6.9	3.6	3.7	4.2	3.0	3.0	2.5
				Middle	5.5	20.4	20.2	7.8	7.9	29.8	29.8	90.1	88.8	6.8	6.8	6.8	3.7	4.0		3.0	3.1	
				Bottom	10	20.1	20.3	7.9	7.9	29.9	29.9	86.6	89.4	6.6	6.7	6.7	5.0	4.9		1.4	1.4	
M6	Fine	Moderate	08:31	Surface	-	-	-	-	-	-	-	-	-	-	-	-	-	-	5.3	-	-	5.1
				Middle	3.7	20.1	19.9	7.9	7.9	30.0	30.1	85.6	84.6	6.5	6.5	6.5	5.2	5.3		5.1	5.1	
				Bottom	-	-	-	-	-	-	-	-	-	-	-	-	-	-		-	-	

Remarks: *DA: Depth-Averaged
**Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

Appendix I - Action and Limit Levels for Marine Water Quality on 14 April 2017 (Mid-Flood Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>CI: 5.5 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>CI: 6.0 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>		
	Surface	<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 5.4 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 5.9 mg/L</u>
	<u>Stations M1-M5</u>		
	Surface	<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 5.4 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 5.9 mg/L</u>
	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 6.2 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 6.8 mg/L</u>
	<u>Station M6</u>		
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

Appendix I - Action and Limit Levels for Marine Water Quality on 18 April 2017 (Mid-Ebb Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>C2: 8.4 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>C2: 9.1 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
	SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>	
Surface		<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 4.9 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 5.3 mg/L</u>
<u>Stations M1-M5</u>			
Surface		<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 4.9 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 5.3 mg/L</u>
<u>Stations G1-G4, M1-M5</u>			
Bottom		<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 6.7 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 7.3 mg/L</u>
<u>Station M6</u>			
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

Appendix I - Action and Limit Levels for Marine Water Quality on 18 April 2017 (Mid-Flood Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>CI: 8.2 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>CI: 8.8 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
	SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>	
Surface		<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 5.0 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 5.5 mg/L</u>
<u>Stations M1-M5</u>			
Surface		<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 5.0 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 5.5 mg/L</u>
<u>Stations G1-G4, M1-M5</u>			
Bottom		<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 6.4 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 6.9 mg/L</u>
<u>Station M6</u>			
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

Appendix I - Action and Limit Levels for Marine Water Quality on 20 April 2017 (Mid-Ebb Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>C2: 5.4 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>C2: 5.9 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
	SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>	
Surface		<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 6.7 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 7.3 mg/L</u>
<u>Stations M1-M5</u>			
Surface		<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 6.7 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 7.3 mg/L</u>
<u>Stations G1-G4, M1-M5</u>			
Bottom		<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 6.2 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 6.8 mg/L</u>
<u>Station M6</u>			
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction
Water Quality Monitoring Results on 20 April 2017**

(Mid-Flood Tide)

Location	Weather Condition	Sea Condition**	Sampling Time	Depth (m)		Temperature (°C)		pH		Salinity ppt		DO Saturation (%)		Dissolved Oxygen (mg/L)			Turbidity(NTU)			Suspended Solids (mg/L)			
						Value	Average	Value	Average	Value	Average	Value	Average	Value	Average	DA*	Value	Average	DA*	Value	Average	DA*	
C1	Cloudy	Moderate	07:43	Surface	1	23.3	23.3	8.1	8.1	31.1	31.2	102.6	7.3	7.4	7.4	3.9	4.0	4.1	4.0	4.0	4.3	5.1	5.2
						23.3	23.2	8.1	8.1	31.1	31.3	103.1	7.4	7.4		3.9	4.0		4.0	4.0		2.5	2.6
						23.2	23.1	8.1	8.1	31.5	31.4	100.2	7.2	7.2		4.6	4.0		4.3	4.0		2.6	2.6
C2	Cloudy	Moderate	05:07	Surface	1	23.2	23.1	8.1	8.1	27.1	27.8	92.6	6.8	6.7	6.6	3.7	4.0	3.8	4.0	4.0	4.9	4.4	4.4
						22.9	22.7	8.0	8.3	28.4	28.8	91.0	6.6	6.5		4.3	3.7		3.8	4.4		4.4	
						23.0	22.6	8.4	8.2	27.3	29.3	92.8	6.8	6.4		4.0	3.3		3.8	4.6		4.6	
G1	Cloudy	Moderate	06:17	Surface	1	23.0	22.8	8.0	8.1	29.0	29.7	93.4	6.8	6.6	6.7	4.9	4.5	4.4	4.5	4.5	4.2	5.0	5.0
						22.5	23.2	8.2	8.5	30.3	28.7	87.1	6.3	6.8		4.0	4.6		4.0	4.9		3.6	
						23.0	23.0	8.4	8.4	29.2	29.2	92.7	6.7	6.7		4.3	4.0		4.0	3.5		3.6	
G2	Cloudy	Moderate	05:51	Surface	1	22.9	22.6	8.1	8.1	29.8	30.5	90.8	6.6	6.4	6.6	4.3	4.5	4.3	4.5	4.5	2.8	2.9	2.9
						22.3	23.0	8.1	8.1	31.2	29.2	85.3	6.2	6.7		4.6	4.4		4.0	2.7		2.7	
						22.9	23.1	8.0	8.2	30.0	28.4	90.7	6.6	6.8		4.2	4.4		4.0	2.6		2.7	
G3	Cloudy	Moderate	06:32	Surface	1	23.2	22.9	8.9	8.6	28.8	29.4	95.7	6.9	6.6	6.8	4.6	4.5	4.2	4.5	4.5	3.7	3.5	3.5
						22.6	23.3	8.3	8.3	30.0	28.8	87.0	6.3	7.0		4.4	4.4		4.0	4.4		4.7	
						23.4	23.4	8.2	8.2	28.9	28.6	95.5	6.9	6.7		4.3	3.7		3.7	4.6		2.9	
G4	Cloudy	Moderate	06:59	Surface	1	23.8	23.6	8.1	8.4	26.3	28.4	104.0	7.6	7.4	7.3	3.9	3.8	3.8	3.8	3.8	3.1	3.1	3.2
						23.4	23.2	8.6	8.3	30.5	31.0	101.2	7.2	7.2		3.7	3.7		4.0	3.2		3.2	
						23.1	23.3	8.0	8.6	31.1	30.8	97.5	7.0	7.2		4.0	3.3		3.7	3.5		3.6	
M1	Cloudy	Moderate	06:04	Surface	1	23.0	22.8	8.4	8.5	29.0	29.6	91.8	6.7	6.6	6.7	4.6	4.2	4.4	4.2	4.2	4.3	6.1	6.1
						22.6	23.0	8.6	8.5	30.1	28.9	87.7	6.4	6.7		3.8	4.6		4.0	6.0		3.3	
						22.9	23.1	8.5	8.5	29.3	28.4	90.8	6.6	6.8		4.5	4.5		4.5	3.2		3.3	
M2	Cloudy	Moderate	05:37	Surface	1	23.1	22.8	8.1	8.4	29.2	29.9	93.4	6.8	6.5	6.6	4.6	4.5	4.3	4.5	4.5	2.4	2.2	2.3
						22.5	23.0	8.6	8.2	30.6	29.4	85.5	6.2	6.7		4.4	4.4		4.0	2.3		3.0	
						22.9	23.0	8.2	8.2	29.6	29.2	90.8	6.6	6.8		4.2	4.5		4.0	3.0		3.0	
M3	Cloudy	Moderate	06:46	Surface	1	23.2	23.0	8.1	8.2	29.3	29.9	92.8	6.7	6.5	6.7	4.4	4.5	4.3	4.5	4.5	5.4	3.8	3.9
						22.7	23.2	8.3	8.2	30.4	28.8	86.6	6.3	6.8		4.6	3.8		4.0	3.9		6.6	
						23.0	23.4	8.2	8.2	29.6	29.8	90.5	6.6	6.7		4.4	3.8		4.2	6.5		6.6	
M4	Cloudy	Moderate	05:22	Surface	1	23.1	22.9	8.2	8.3	28.3	29.2	93.2	6.8	6.6	6.6	3.2	3.5	4.0	3.5	3.5	5.9	6.0	5.9
						22.6	22.7	8.3	8.5	30.1	29.8	88.0	6.4	6.5		3.7	4.9		4.0	5.8		5.9	
						22.7	22.7	8.7	8.2	29.6	29.3	88.0	6.4	6.6		4.5	4.5		4.0	5.9		6.0	
M5	Cloudy	Moderate	07:26	Surface	1	23.2	22.9	8.6	8.7	31.1	31.6	102.7	7.3	6.9	6.9	3.6	4.0	4.2	4.0	4.0	3.1	3.2	3.2
						22.5	22.9	8.7	8.7	32.1	31.6	89.0	6.4	6.9		4.3	4.2		4.4	3.5		3.5	
						23.2	22.5	8.6	8.7	31.1	32.1	102.6	7.3	6.4		4.1	4.2		4.4	3.5		2.6	
M6	Cloudy	Moderate	07:17	Surface	-	-	-	-	-	-	-	-	-	-	7.3	-	-	4.0	-	-	6.1	-	-
						23.2	23.2	8.6	8.6	31.0	31.1	102.7	7.3	7.3		4.4	4.0		6.1	6.1			
						23.2	-	-	-	31.1	-	102.7	7.3	-		3.6	-		-	-		-	

Remarks: *DA: Depth-Averaged
**Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

Appendix I - Action and Limit Levels for Marine Water Quality on 20 April 2017 (Mid-Flood Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>CI: 5.2 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>CI: 5.6 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
	SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>	
Surface		<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 6.2 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 6.8 mg/L</u>
<u>Stations M1-M5</u>			
Surface		<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 6.2 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 6.8 mg/L</u>
<u>Stations G1-G4, M1-M5</u>			
Bottom		<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 6.1 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 6.6 mg/L</u>
<u>Station M6</u>			
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

Appendix I - Action and Limit Levels for Marine Water Quality on 22 April 2017 (Mid-Ebb Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>C2: 10.1 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>C2: 10.9 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
	SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>	
Surface		<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 5.2 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 5.6 mg/L</u>
<u>Stations M1-M5</u>			
Surface		<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 5.2 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 5.6 mg/L</u>
<u>Stations G1-G4, M1-M5</u>			
Bottom		<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 5.3 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 5.7 mg/L</u>
<u>Station M6</u>			
Intake Level		<u>8.3 mg/L</u>	<u>8.6 mg/L</u>

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction
Water Quality Monitoring Results on 22 April 2017**

(Mid-Flood Tide)

Location	Weather Condition	Sea Condition**	Sampling Time	Depth (m)		Temperature (°C)		pH		Salinity ppt		DO Saturation (%)		Dissolved Oxygen (mg/L)			Turbidity(NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Value	Average	DA*	Value	Average	DA*	Value	Average	DA*
C1	Rainy	Rough	15:53	Surface	1	23.4	23.5	8.1	8.1	31.3	31.4	104.8	104.8	7.5	7.5	7.5	4.3	4.4	6.7	5.7	5.7	5.1
					23.2	23.2	8.1	8.1	31.3	31.3	103.8	103.9	7.4	7.4	7.4	4.5	4.4	7.6	5.7	5.7		
					23.2	23.2	8.1	8.1	31.3	31.3	104.0	103.9	7.4	7.4	7.4	7.2	7.4	7.2	7.4	3.1	3.2	
C2	Rainy	Rough	14:10	Surface	1	23.4	23.4	8.0	8.0	31.3	31.3	102.0	101.9	7.3	7.3	7.3	5.6	5.4	7.3	4.0	4.0	3.2
					23.4	23.4	8.0	8.0	31.3	31.3	101.7	102.5	7.2	7.3	7.2	5.2	5.4	7.7	4.0	4.0		
					23.2	23.2	8.1	8.1	31.4	31.4	102.5	102.6	7.3	7.3	7.3	7.5	7.6	7.5	7.6	2.6	2.6	
G1	Rainy	Rough	15:00	Surface	1	24.2	24.3	8.1	8.1	31.8	31.8	108.4	108.6	7.6	7.6	7.6	4.7	4.7	6.1	4.8	4.9	3.9
					24.3	24.3	8.1	8.1	31.7	31.7	108.7	105.1	7.6	7.5	7.5	4.6	5.1	5.4	4.9	4.9		
					23.3	23.3	8.2	8.2	31.3	31.4	105.3	105.3	7.5	7.5	7.5	4.8	5.1	4.8	3.5	3.5		
G2	Rainy	Rough	14:40	Surface	1	23.9	23.9	8.1	8.1	31.6	31.6	107.4	107.3	7.6	7.6	7.6	3.7	3.7	5.7	3.1	3.1	2.6
					23.8	23.9	8.1	8.1	31.6	31.6	107.1	106.3	7.6	7.5	7.5	3.6	6.0	5.9	2.4	2.5		
					23.5	23.6	8.1	8.1	31.5	31.5	106.2	106.4	7.5	7.5	7.5	6.1	6.0	6.1	2.5	2.5		
G3	Rainy	Rough	15:10	Surface	1	23.9	23.9	8.2	8.2	31.5	31.6	106.2	106.3	7.5	7.5	7.5	5.0	5.4	6.0	5.5	5.5	5.5
					23.9	23.9	8.1	8.1	31.6	31.6	106.3	106.3	7.5	7.5	7.5	5.8	5.4	5.9	5.5	5.5		
					23.4	23.4	8.1	8.2	31.3	31.4	103.9	104.1	7.4	7.4	7.4	6.2	6.1	6.2	6.4	6.5		
G4	Rainy	Rough	15:30	Surface	1	23.4	23.5	8.2	8.2	31.4	31.4	105.6	105.8	7.5	7.5	7.5	4.2	3.9	7.5	2.4	2.4	2.9
					23.5	23.5	8.1	8.2	31.4	31.4	105.9	105.7	7.5	7.5	7.5	3.5	6.1	5.7	2.4	2.4		
					23.2	23.2	8.1	8.2	31.3	31.3	105.6	105.7	7.5	7.5	7.5	6.4	6.1	6.4	2.9	3.4		
M1	Rainy	Rough	14:50	Surface	1	24.2	24.2	8.1	8.1	31.8	31.8	109.1	109.3	7.6	7.7	7.7	5.6	5.7	7.7	2.8	2.8	2.6
					24.2	24.2	8.1	8.1	31.8	31.8	109.5	107.5	7.7	7.6	7.6	5.8	6.7	6.7	2.8	2.5		
					23.7	23.8	8.1	8.2	31.6	31.6	107.4	107.6	7.6	7.6	7.6	6.7	6.7	6.7	2.5	2.5		
M2	Rainy	Rough	14:31	Surface	1	23.5	23.5	8.1	8.1	31.5	31.5	106.5	106.4	7.6	7.6	7.6	4.5	4.3	7.6	2.3	2.4	2.4
					23.5	23.5	8.1	8.1	31.5	31.5	106.3	105.8	7.5	7.5	7.5	4.0	5.4	5.3	2.4	2.4		
					23.4	23.4	8.2	8.2	31.3	31.4	105.8	106.0	7.5	7.6	7.6	5.5	7.6	5.5	2.4	2.4		
M3	Rainy	Rough	15:21	Surface	1	23.9	24.0	8.1	8.2	31.6	31.7	105.6	105.7	7.4	7.4	7.4	4.2	4.2	7.4	3.2	3.2	3.7
					24.0	24.0	8.2	8.2	31.7	31.7	105.7	103.0	7.4	7.3	7.3	4.2	7.0	4.2	3.2	3.2		
					23.3	23.4	8.1	8.2	31.4	31.5	102.9	103.0	7.3	7.3	7.3	7.2	7.0	7.2	4.0	4.1		
M4	Rainy	Rough	14:22	Surface	1	23.7	23.7	8.1	8.1	31.6	31.6	109.3	109.0	7.7	7.7	7.7	4.8	4.9	7.7	4.5	4.6	3.5
					23.7	23.7	8.1	8.1	31.5	31.5	108.6	105.4	7.7	7.5	7.5	5.0	6.3	4.8	4.6	4.6		
					23.1	23.1	8.2	8.2	31.5	31.5	105.4	105.3	7.5	7.5	7.5	6.5	6.0	6.5	2.7	2.7		
M5	Rainy	Rough	15:40	Surface	1	23.7	23.7	8.1	8.1	31.6	31.6	106.9	106.8	7.6	7.6	7.6	5.2	5.4	7.6	2.7	2.8	2.7
					23.7	23.7	8.1	8.1	31.6	31.6	106.6	104.7	7.5	7.5	7.5	5.5	7.0	5.5	2.8	2.6		
					23.2	23.2	8.1	8.1	31.2	31.3	104.6	104.8	7.5	7.5	7.5	7.0	7.0	6.9	7.0	6.9	2.6	
M6	Rainy	Rough	15:39	Surface	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	3.5	
					23.4	23.4	8.2	8.2	31.4	31.4	106.4	106.4	7.6	7.6	7.6	5.9	6.0	5.9	3.5	3.5		
					23.4	23.4	8.1	8.1	31.4	31.4	106.3	106.3	7.6	7.6	7.6	6.0	6.0	6.0	3.5	3.5		

Remarks: *DA: Depth-Averaged
**Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

Appendix I - Action and Limit Levels for Marine Water Quality on 22 April 2017 (Mid-Flood Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>CI: 10.1 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>CI: 10.9 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
	SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>	
Surface		<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 6.8 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 7.4 mg/L</u>
<u>Stations M1-M5</u>			
Surface		<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 6.8 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 7.4 mg/L</u>
<u>Stations G1-G4, M1-M5</u>			
Bottom		<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 7.8 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 8.5 mg/L</u>
<u>Station M6</u>			
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

Appendix I - Action and Limit Levels for Marine Water Quality on 24 April 2017 (Mid-Ebb Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>C2: 5.8 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>C2: 6.2 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
	SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>	
Surface		<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 4.1 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 4.4 mg/L</u>
<u>Stations M1-M5</u>			
Surface		<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 4.1 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 4.4 mg/L</u>
<u>Stations G1-G4, M1-M5</u>			
Bottom		<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 3.7 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 4.0 mg/L</u>
<u>Station M6</u>			
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

Appendix I - Action and Limit Levels for Marine Water Quality on 24 April 2017 (Mid-Flood Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>CI: 6.1 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>CI: 6.6 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>		
	Surface	<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 6.2 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 6.8 mg/L</u>
	<u>Stations M1-M5</u>		
	Surface	<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 6.2 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 6.8 mg/L</u>
	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 5.8 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 6.2 mg/L</u>
	<u>Station M6</u>		
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction
Water Quality Monitoring Results on 26 April 2017

(Mid-Ebb Tide)

Location	Weather Condition	Sea Condition**	Sampling Time	Depth (m)		Temperature (°C)		pH		Salinity ppt		DO Saturation (%)		Dissolved Oxygen (mg/L)			Turbidity(NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Value	Average	DA*	Value	Average	DA*	Value	Average	DA*
C1	Sunny	Moderate	12:51	Surface	1	26.5	26.3	8.1	8.1	30.3	30.3	101.1	99.8	6.9	6.8	6.4	3.1	3.2	4.7	4.4	4.4	4.0
				Middle	10.5	26.4	26.2	8.1	8.1	31.4	31.4	85.5	85.9	5.8	5.9		4.7	4.6		3.0	3.1	
				Bottom	20	26.1	26.1	8.1	8.1	32.4	32.0	82.7	83.7	5.6	5.7		6.3	6.4		3.5	4.5	
C2	Sunny	Moderate	10:52	Surface	1	26.2	25.9	8.1	8.1	30.5	30.5	94.7	96.7	6.5	6.7	6.4	2.6	2.9	4.4	5.9	5.9	5.4
				Middle	18	26.2	25.8	8.1	8.1	31.7	31.7	85.5	87.1	5.8	6.0		4.3	4.3		4.4	4.4	
				Bottom	35	25.4	25.5	8.1	8.1	31.9	32.0	79.0	79.5	5.4	5.4		5.8	6.0		5.9	6.0	
G1	Sunny	Moderate	11:34	Surface	1	26.0	26.0	8.1	8.1	31.9	31.9	91.5	89.9	6.2	6.1	6.1	4.3	4.0	3.6	4.6	4.6	4.7
				Middle	4	26.1	26.0	8.1	8.1	32.1	32.2	84.0	88.2	5.7	6.0		3.6	3.6		5.7	5.7	
				Bottom	7	25.9	25.9	8.1	8.1	32.4	32.4	83.9	85.2	5.7	5.8		3.2	3.1		3.8	3.8	
G2	Sunny	Moderate	11:18	Surface	1	25.9	25.9	8.1	8.1	31.9	31.9	95.0	97.5	6.5	6.7	6.4	3.5	3.6	3.2	3.4	3.5	5.1
				Middle	5	25.9	25.9	8.1	8.1	32.2	32.2	85.3	87.4	5.8	6.0		3.3	3.4		6.2	6.2	
				Bottom	9	25.9	25.9	8.2	8.2	33.0	32.9	79.8	80.5	5.4	5.4		2.6	2.7		5.5	5.5	
G3	Sunny	Moderate	11:48	Surface	1	25.6	25.6	8.1	8.1	32.3	32.3	91.9	91.9	6.3	6.3	6.3	2.9	2.8	2.9	4.5	4.5	4.3
				Middle	4	25.6	25.6	8.1	8.1	32.3	32.3	92.2	92.0	6.3	6.3		3.1	3.0		3.9	3.9	
				Bottom	7	25.5	25.6	8.1	8.1	32.3	32.3	93.2	94.6	6.4	6.5		3.1	2.9		4.4	4.4	
G4	Sunny	Moderate	12:20	Surface	1	26.5	26.2	8.0	8.0	30.3	30.3	79.1	76.6	5.4	5.3	5.3	3.3	3.1	3.7	4.1	4.2	4.4
				Middle	4	26.5	26.2	8.1	8.1	31.3	31.3	75.8	76.1	5.1	5.2		3.7	3.9		4.0	4.0	
				Bottom	7	25.9	25.9	8.1	8.1	31.9	31.8	76.5	71.4	5.2	5.1		4.0	4.1		5.1	5.0	
M1	Sunny	Moderate	11:26	Surface	1	25.6	25.6	8.1	8.1	32.2	32.2	88.7	88.9	6.0	6.1	6.1	2.8	2.9	3.4	4.6	4.6	4.8
				Middle	3	25.6	25.6	8.1	8.1	32.4	32.5	87.7	87.3	6.0	6.0		3.3	3.6		4.4	4.4	
				Bottom	5	25.5	25.6	8.1	8.1	32.4	32.5	87.7	87.3	6.0	6.0		3.6	3.8		5.4	5.4	
M2	Sunny	Moderate	11:12	Surface	1	26.2	25.9	8.1	8.1	30.5	30.5	88.0	87.8	6.0	6.0	6.0	2.6	2.9	4.4	5.0	5.0	4.2
				Middle	5.5	26.2	25.8	8.1	8.1	31.7	31.7	87.5	86.9	5.9	6.0		3.1	4.3		3.7	3.8	
				Bottom	10	25.4	25.5	8.1	8.1	31.7	32.0	86.9	78.2	6.0	5.4		4.3	5.9		3.8	3.8	
M3	Sunny	Moderate	12:08	Surface	1	26.5	26.3	8.1	8.1	30.1	30.1	85.4	86.4	5.8	5.9	5.6	2.5	2.6	3.0	3.6	3.6	3.9
				Middle	4.5	26.5	26.2	8.1	8.1	30.7	30.7	75.8	77.6	6.0	5.3		2.9	3.0		3.6	3.6	
				Bottom	8	26.1	26.0	8.1	8.1	31.1	31.1	79.3	75.7	5.2	5.2		3.3	3.3		4.5	4.5	
M4	Sunny	Moderate	11:04	Surface	1	25.6	25.6	8.1	8.1	32.3	32.3	96.8	96.1	6.6	6.6	6.4	2.8	2.9	3.5	3.8	3.8	3.9
				Middle	4	25.6	25.3	8.1	8.1	32.4	32.4	95.3	88.9	6.5	6.1		2.9	3.3		3.6	3.7	
				Bottom	7	25.0	25.3	8.1	8.1	32.4	33.3	88.5	86.8	6.1	5.9		3.2	4.3		3.7	4.3	
M5	Sunny	Moderate	12:44	Surface	1	26.4	26.3	8.1	8.1	30.3	30.3	82.2	85.1	5.6	5.8	5.9	3.3	3.1	4.8	5.9	5.9	5.7
				Middle	5.5	26.4	26.2	8.1	8.1	31.3	31.3	87.9	86.1	6.0	5.9		2.9	5.2		6.3	6.4	
				Bottom	10	26.1	26.0	8.1	8.1	31.3	32.0	88.5	80.3	6.0	5.7		4.8	6.0		6.4	4.8	
M6	Sunny	Moderate	12:30	Surface	-	-	-	-	-	-	-	-	-	-	-	6.4	-	-	3.9	-	-	4.6
				Middle	2	26.6	26.4	8.1	8.1	30.0	30.1	94.0	93.5	6.4	6.4		3.9	3.9		4.6	4.6	
				Bottom	-	-	-	-	-	-	-	-	-	-	-		-	-		-	-	

Remarks: *DA: Depth-Averaged
**Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

Appendix I - Action and Limit Levels for Marine Water Quality on 26 April 2017 (Mid-Ebb Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>C2: 7.1 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>C2: 7.7 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
	SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>	
Surface		<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 7.1 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 7.7 mg/L</u>
<u>Stations M1-M5</u>			
Surface		<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 7.1 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 7.7 mg/L</u>
<u>Stations G1-G4, M1-M5</u>			
Bottom		<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 7.2 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 7.8 mg/L</u>
<u>Station M6</u>			
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

Appendix I - Action and Limit Levels for Marine Water Quality on 26 April 2017 (Mid-Flood Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>CI: 5.5 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>CI: 6.0 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
	SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>	
Surface		<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 6.4 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 6.9 mg/L</u>
<u>Stations M1-M5</u>			
Surface		<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 6.4 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 6.9 mg/L</u>
<u>Stations G1-G4, M1-M5</u>			
Bottom		<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 5.9 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 6.4 mg/L</u>
<u>Station M6</u>			
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

Appendix I - Action and Limit Levels for Marine Water Quality on 28 April 2017 (Mid-Ebb Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>C2: 7.9 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>C2: 8.6 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
	SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>	
Surface		<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 6.7 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 7.3 mg/L</u>
<u>Stations M1-M5</u>			
Surface		<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 6.7 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 7.3 mg/L</u>
<u>Stations G1-G4, M1-M5</u>			
Bottom		<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>C2: 5.6 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>C2: 6.1 mg/L</u>
<u>Station M6</u>			
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction
Water Quality Monitoring Results on 28 April 2017**

(Mid-Flood Tide)

Location	Weather Condition	Sea Condition**	Sampling Time	Depth (m)		Temperature (°C)		pH		Salinity ppt		DO Saturation (%)		Dissolved Oxygen (mg/L)			Turbidity(NTU)			Suspended Solids (mg/L)		
						Value	Average	Value	Average	Value	Average	Value	Average	Value	Average	DA*	Value	Average	DA*	Value	Average	DA*
C1	Cloudy	Moderate	08:13	Surface	1	23.4	23.4	8.0	8.0	30.1	30.1	101.4	101.3	7.3	7.3	6.9	3.7	3.7	5.9	5.1	5.2	4.8
						23.7	23.7	8.0	8.0	30.6	30.6	89.4	89.2	6.4	6.4		5.1	5.1		4.3	4.4	
						23.3	23.4	8.0	8.0	31.2	31.2	91.6	91.8	6.5	6.5		8.8	8.9		4.5	4.8	
C2	Cloudy	Moderate	06:02	Surface	1	23.5	23.4	8.0	8.0	30.0	30.0	95.2	95.3	6.8	6.9	6.7	3.3	3.4	4.8	5.1	5.1	4.5
						23.2	23.4	8.0	8.0	30.0	31.8	95.4	90.2	6.9	6.5		4.6	4.6		4.3	4.3	
						23.4	23.4	8.0	8.0	31.8	31.8	91.0	90.6	6.5	6.5		6.3	6.4		3.9	4.0	
G1	Cloudy	Moderate	06:54	Surface	1	23.0	22.9	8.0	8.0	31.8	31.8	94.7	94.2	6.8	6.8	6.7	3.5	3.7	5.3	5.2	5.3	4.1
						22.8	23.1	8.0	8.1	31.7	31.7	93.6	91.3	6.7	6.5		4.3	4.3		3.3	3.3	
						23.4	23.4	8.0	8.0	31.7	31.7	91.8	91.3	6.5	6.5		7.7	7.8		3.6	3.7	
G2	Cloudy	Moderate	06:33	Surface	1	23.3	23.5	8.0	8.0	31.3	31.4	96.9	97.3	6.9	6.9	6.7	2.9	3.1	3.8	3.1	3.1	2.5
						23.6	23.2	8.0	8.0	31.6	31.6	97.7	89.1	6.9	6.4		3.6	3.6		3.1	3.1	
						23.1	22.8	8.1	8.1	31.6	32.8	89.2	88.6	6.4	6.3		4.7	4.7		1.3	1.4	
G3	Cloudy	Moderate	07:09	Surface	1	22.9	22.9	8.0	8.0	32.3	32.3	101.2	101.4	7.2	7.3	7.1	3.6	3.6	6.0	4.9	5.0	4.1
						22.8	23.1	8.0	8.0	32.3	31.6	101.5	97.1	7.3	6.9		5.7	5.8		3.8	3.8	
						23.1	22.9	8.0	8.0	31.6	31.6	96.0	96.6	6.9	6.9		8.6	8.6		3.5	3.6	
G4	Cloudy	Moderate	07:40	Surface	1	24.1	24.1	7.9	7.9	30.2	30.2	98.4	98.6	7.0	7.0	6.9	2.7	2.9	4.2	4.9	4.8	4.2
						24.1	23.9	8.0	8.0	30.1	30.9	98.7	95.6	7.0	6.7		4.1	4.0		4.7	4.8	
						23.9	23.4	8.0	8.0	30.9	31.3	95.9	92.5	6.8	6.6		3.9	5.6		3.0	3.1	
M1	Cloudy	Moderate	06:43	Surface	1	22.8	22.9	8.0	8.0	31.4	31.4	96.5	96.5	6.9	6.9	6.7	3.4	3.5	4.6	4.7	4.7	4.7
						22.9	23.1	8.0	8.0	31.4	31.7	96.5	90.9	6.9	6.5		3.6	3.8		4.6	5.3	
						22.8	22.9	8.0	8.0	31.7	31.9	91.0	89.9	6.5	6.4		3.8	6.4		4.2	4.2	
M2	Cloudy	Moderate	06:24	Surface	1	23.6	23.7	8.0	8.0	30.5	30.5	95.9	96.0	6.8	6.8	6.7	2.9	3.0	4.8	5.1	5.0	5.0
						23.8	23.2	8.0	8.0	30.5	31.5	96.0	91.9	6.8	6.6		3.1	4.8		4.9	6.6	
						23.6	23.0	8.0	8.0	31.5	31.9	92.2	87.3	6.6	6.6		5.0	6.4		6.5	3.3	
M3	Cloudy	Moderate	07:26	Surface	1	24.0	23.9	8.0	8.0	30.0	30.0	94.8	94.8	6.7	6.7	6.7	2.8	2.7	3.6	3.8	3.8	4.7
						23.8	23.6	8.0	8.0	30.0	30.0	94.7	93.0	6.7	6.7		2.6	3.6		5.8	6.0	
						23.6	23.5	8.0	8.0	30.0	30.6	92.7	90.9	6.6	6.5		3.5	4.5		6.1	4.3	
M4	Cloudy	Moderate	06:12	Surface	1	22.9	23.0	8.0	8.0	31.4	31.4	97.9	98.2	7.0	7.1	7.0	3.4	3.4	4.1	3.7	3.7	4.6
						23.0	22.7	8.0	8.0	31.4	32.2	98.5	95.7	7.1	6.8		3.3	4.0		5.7	5.8	
						22.7	22.5	8.0	8.0	32.2	32.7	95.5	95.9	6.8	6.9		4.0	4.0		5.8	4.1	
M5	Cloudy	Moderate	08:03	Surface	1	23.8	23.9	8.0	8.0	30.1	30.1	99.6	99.6	7.1	7.1	7.1	4.0	4.0	6.0	3.9	3.8	4.9
						23.9	23.6	8.0	8.0	30.1	30.8	99.5	97.8	7.1	7.0		3.9	6.2		5.7	5.6	
						23.6	23.8	8.0	8.1	30.8	31.6	97.9	96.1	7.0	6.9		6.3	7.7		5.5	5.3	
M6	Cloudy	Moderate	07:53	Surface	-	-	-	-	-	-	-	-	-	-	7.0	-	-	4.3	-	-	4.2	
						24.0	24.0	8.0	8.0	29.8	29.8	98.9	97.7	7.0		7.0	4.2		4.3	4.1		4.2
						24.0	-	8.0	-	29.8	-	96.5	-	6.9		-	4.3		-	4.2		-

Remarks: *DA: Depth-Averaged
**Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.


Appendix I - Action and Limit Levels for Marine Water Quality on 28 April 2017 (Mid-Flood Tide)

Parameter (unit)	Depth	Action Level	Limit Level
DO in mg/L (See Note 1 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Depth Average	<u>4.9 mg/L</u>	<u>4.6 mg/L</u>
	Bottom	<u>4.2 mg/L</u>	<u>3.6 mg/L</u>
	<u>Station M6</u>		
	Intake Level	<u>5.0 mg/L</u>	<u>4.7 mg/L</u>
Turbidity in NTU (See Note 2 and 4)	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>19.3 NTU</u> or 120% of upstream control station's Turbidity at the same tide of the same day <u>CI: 10.7 NTU</u>	<u>22.2 NTU</u> or 130% of upstream control station's Turbidity at the same tide of the same day <u>CI: 11.6 NTU</u>
	<u>Station M6</u>		
	Intake Level	<u>19.0 NTU</u>	<u>19.4 NTU</u>
SS in mg/L (See Note 2 and 4)	<u>Stations G1-G4</u>		
	Surface	<u>6.0 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 6.2 mg/L</u>	<u>6.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 6.8 mg/L</u>
	<u>Stations M1-M5</u>		
	Surface	<u>6.2 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 6.2 mg/L</u>	<u>7.4 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 6.8 mg/L</u>
	<u>Stations G1-G4, M1-M5</u>		
	Bottom	<u>6.9 mg/L</u> or 120% of upstream control station's SS at the same tide of the same day <u>CI: 5.8 mg/L</u>	<u>7.9 mg/L</u> or 130% of upstream control station's SS at the same tide of the same day <u>CI: 6.2 mg/L</u>
	<u>Station M6</u>		
Intake Level	<u>8.3 mg/L</u>	<u>8.6 mg/L</u>	

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

Dissolved Oxygen (Depth-averaged) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction


Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I



Dissolved Oxygen (Depth-averaged) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction


Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I



Dissolved Oxygen (Depth-averaged) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction


Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I




Dissolved Oxygen (Depth-averaged) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction Graphical Presentation of Water Quality Monitoring Results	Scale N.T.S	Project No. MA16034	
	Date Apr 17	Appendix I	

Dissolved Oxygen (Depth-averaged) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction


Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I



Dissolved Oxygen (Depth-averaged) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction


Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S




Date Apr 17

Project No. MA16034

Appendix I



Dissolved Oxygen (Depth-averaged) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction


Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I



Dissolved Oxygen (Depth-averaged) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction


Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S




Date Apr 17

Project No. MA16034

Appendix I




Dissolved Oxygen (Bottom) at Mid-Ebb Tide




Title
 Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction
 Graphical Presentation of Water Quality Monitoring Results

Scale
 N.T.S
Date
 Apr 17

Project No.
 MA16034
Appendix
 I



Dissolved Oxygen (Bottom) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction


Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I



Dissolved Oxygen (Bottom) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction


Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I



Dissolved Oxygen (Bottom) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction


Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I



Dissolved Oxygen (Bottom) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction


Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I



Dissolved Oxygen (Bottom) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction


Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S




Date Apr 17

Project No. MA16034

Appendix I



Dissolved Oxygen (Bottom) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction


Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I



Dissolved Oxygen (Bottom) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction


Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I




Dissolved Oxygen (Intake Level of WSD Salt Water Intake) at Mid-Ebb Tide




Title
 Agreement No. CE 59/2015(EP) Environmental Team for
 Tseung Kwan O - Lam Tin Tunnel Design and Construction
 Graphical Presentation of Water Quality Monitoring
 Results

Scale
 N.T.S
Date
 Apr 17

Project No.
 MA16034
Appendix
 I




Dissolved Oxygen (Intake Level of WSD Salt Water Intake) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction Graphical Presentation of Water Quality Monitoring Results	Scale N.T.S	Project No. MA16034	
	Date Apr 17	Appendix I	

Turbidity (Depth-averaged) at Mid-Ebb Tide




Title
 Agreement No. CE 59/2015(EP) Environmental Team for
 Tseung Kwan O - Lam Tin Tunnel Design and Construction
 Graphical Presentation of Water Quality Monitoring
 Results

Scale
 N.T.S
Date
 Apr 17

Project No.
 MA16034
Appendix
 I



Turbidity (Depth-averaged) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I



Turbidity (Depth-averaged) at Mid-Ebb Tide




Title
 Agreement No. CE 59/2015(EP) Environmental Team for
 Tseung Kwan O - Lam Tin Tunnel Design and Construction
 Graphical Presentation of Water Quality Monitoring
 Results

Scale
 N.T.S
Date
 Apr 17

Project No.
 MA16034
Appendix
 I




Turbidity (Depth-averaged) at Mid-Ebb Tide



Title	Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction	Scale	N.T.S	Project No.	MA16034	CINOTECH
	Graphical Presentation of Water Quality Monitoring Results	Date	Apr 17	Appendix	I	

Turbidity (Depth-averaged) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I



Turbidity (Depth-averaged) at Mid-Flood Tide




Title
 Agreement No. CE 59/2015(EP) Environmental Team for
 Tseung Kwan O - Lam Tin Tunnel Design and Construction
 Graphical Presentation of Water Quality Monitoring
 Results

Scale
 N.T.S
Date
 Apr 17

Project No.
 MA16034
Appendix
 I



Turbidity (Depth-averaged) at Mid-Flood Tide




Title
 Agreement No. CE 59/2015(EP) Environmental Team for
 Tseung Kwan O - Lam Tin Tunnel Design and Construction
 Graphical Presentation of Water Quality Monitoring
 Results

Scale
 N.T.S
Date
 Apr 17

Project No.
 MA16034
Appendix
 I






Turbidity (Depth-averaged) at Mid-Flood Tide



Title	Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction	Scale	N.T.S	Project No.	MA16034	CINOTECH
	Graphical Presentation of Water Quality Monitoring Results	Date	Apr 17	Appendix	I	

Turbidity (Bottom) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S




Date Apr 17

Project No. MA16034

Appendix I



Turbidity (Bottom) at Mid-Ebb Tide



Title

Agreement No. CE 59/2015(EP) Environmental Team for
Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring
Results

Scale

N.T.S

Date

Apr 17

Project No.


MA16034

Appendix

I



Turbidity (Bottom) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I



Turbidity (Bottom) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I



Turbidity (Bottom) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I



Turbidity (Bottom) at Mid-Flood Tide




Title
 Agreement No. CE 59/2015(EP) Environmental Team for
 Tseung Kwan O - Lam Tin Tunnel Design and Construction
 Graphical Presentation of Water Quality Monitoring
 Results

Scale
 N.T.S
 Date
 Apr 17

Project
 No. MA16034
 Appendix
 I



Turbidity (Bottom) at Mid-Flood Tide




Title
 Agreement No. CE 59/2015(EP) Environmental Team for
 Tseung Kwan O - Lam Tin Tunnel Design and Construction
 Graphical Presentation of Water Quality Monitoring
 Results

Scale
 N.T.S
 Date
 Apr 17

Project
 No. MA16034
 Appendix
 I



Turbidity (Bottom) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I




Turbidity (Intake Level of WSD Salt Water Intake) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction Graphical Presentation of Water Quality Monitoring Results	Scale N.T.S	Project No. MA16034	CINOTECH
	Date Apr 17	Appendix I	


Turbidity (Intake Level of WSD Salt Water Intake) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction Graphical Presentation of Water Quality Monitoring Results	Scale	N.T.S	Project No.	MA16034
	Date	Apr 17	Appendix	I



Suspended Solids (Depth-averaged) at Mid-Ebb Tide




Title
 Agreement No. CE 59/2015(EP) Environmental Team for
 Tseung Kwan O - Lam Tin Tunnel Design and Construction
 Graphical Presentation of Water Quality Monitoring
 Results

Scale
 N.T.S
Date
 Apr 17

Project No.
 MA16034
Appendix
 I



Suspended Solids (Depth-averaged) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I



Suspended Solids (Depth-averaged) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I




Suspended Solids (Depth-averaged) at Mid-Ebb Tide



Title	Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction	Scale	N.T.S	Project No.	MA16034	CINOTECH
	Graphical Presentation of Water Quality Monitoring Results	Date	Apr 17	Appendix	I	

Suspended Solids (Depth-averaged) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I



Suspended Solids (Depth-averaged) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I



Suspended Solids (Depth-averaged) at Mid-Flood Tide




Title
 Agreement No. CE 59/2015(EP) Environmental Team for
 Tseung Kwan O - Lam Tin Tunnel Design and Construction
 Graphical Presentation of Water Quality Monitoring
 Results

Scale
 N.T.S
Date
 Apr 17

Project No.
 MA16034
Appendix
 I



Suspended Solids (Depth-averaged) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S




Date Apr 17

Project No. MA16034

Appendix I



Suspended Solids (Surface) at Mid-Ebb Tide



Title

Agreement No. CE 59/2015(EP) Environmental Team for
Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring
Results

Scale

N.T.S

Date

Apr 17

Project No.


MA16034

Appendix

I




Suspended Solids (Surface) at Mid-Ebb Tide



ReAprks: The graphical point at zero concentration is presented as <2.5mg/L.

Title	Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction	Scale	N.T.S	Project No.	MA16034	CINOTECH
	Graphical Presentation of Water Quality Monitoring Results	Date	Apr 17	Appendix	I	

Suspended Solids (Surface) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I



Suspended Solids (Surface) at Mid-Ebb Tide



Title

Agreement No. CE 59/2015(EP) Environmental Team for
Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring
Results

Scale

N.T.S

Date

Apr 17

Project No.


MA16034

Appendix

I

CINOTECH


Suspended Solids (Surface) at Mid-Flood Tide



ReAprks: The graphical point at zero concentration is presented as <2.5mg/L.

Title	Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction	Scale	N.T.S	Project No.	MA16034	CINOTECH
	Graphical Presentation of Water Quality Monitoring Results	Date	Apr 17	Appendix	I	

Suspended Solids (Surface) at Mid-Flood Tide




ReAprks: The graphical point at zero concentration is presented as <math><2.5\text{mg/L}</math>.

Title	Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction	Scale	N.T.S	Project No.	MA16034
	Graphical Presentation of Water Quality Monitoring Results	Date	Apr 17	Appendix	I

CINOTECH

Suspended Solids (Surface) at Mid-Flood Tide




ReAprks: The graphical point at zero concentration is presented as <2.5mg/L.

Title	Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction	Scale	N.T.S	Project No.	MA16034
	Graphical Presentation of Water Quality Monitoring Results	Date	Apr 17	Appendix	I

CINOTECH


Suspended Solids (Surface) at Mid-Flood Tide



ReAprks: The graphical point at zero concentration is presented as <2.5mg/L.

Title	Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction	Scale	N.T.S	Project No.	MA16034	CINOTECH
	Graphical Presentation of Water Quality Monitoring Results	Date	Apr 17	Appendix	I	


Suspended Solids (Bottom) at Mid-Ebb Tide



ReAprks: The graphical point at zero concentration is presented as <2.5mg/L.

Title	Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction	Scale	N.T.S	Project No.	MA16034	CINOTECH
	Graphical Presentation of Water Quality Monitoring Results	Date	Apr 17	Appendix	I	


Suspended Solids (Bottom) at Mid-Ebb Tide



ReAprks: The graphical point at zero concentration is presented as <math><2.5\text{mg/L}</math>.

Title	Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction	Scale	N.T.S	Project No.	MA16034	CINOTECH
	Graphical Presentation of Water Quality Monitoring Results	Date	Apr 17	Appendix	I	


Suspended Solids (Bottom) at Mid-Ebb Tide



ReAprks: The graphical point at zero concentration is presented as <2.5mg/L.

Title	Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction	Scale	N.T.S	Project No.	MA16034	CINOTECH
	Graphical Presentation of Water Quality Monitoring Results	Date	Apr 17	Appendix	I	

Suspended Solids (Bottom) at Mid-Ebb Tide



Title

Agreement No. CE 59/2015(EP) Environmental Team for
Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring
Results

Scale

N.T.S

Date

Apr 17

Project No.




MA16034

Appendix

I

CINOTECH

Suspended Solids (Bottom) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Apr 17

Project No. MA16034

Appendix I



Suspended Solids (Bottom) at Mid-Flood Tide




ReAprks: The graphical point at zero concentration is presented as <2.5mg/L.

Title	Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction	Scale	N.T.S	Project No.	MA16034
	Graphical Presentation of Water Quality Monitoring Results	Date	Apr 17	Appendix	I

CINOTECH


Suspended Solids (Bottom) at Mid-Flood Tide



ReAprks: The graphical point at zero concentration is presented as <2.5mg/L.

Title	Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction	Scale	N.T.S	Project No.	MA16034	CINOTECH
	Graphical Presentation of Water Quality Monitoring Results	Date	Apr 17	Appendix	I	


Suspended Solids (Bottom) at Mid-Flood Tide



ReAprks: The graphical point at zero concentration is presented as <2.5mg/L.

Title	Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction	Scale	N.T.S	Project No.	MA16034	CINOTECH
	Graphical Presentation of Water Quality Monitoring Results	Date	Apr 17	Appendix	I	


Suspended Solids (Intake Level of WSD Salt Water Intake) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction Graphical Presentation of Water Quality Monitoring Results	Scale	N.T.S	Project No.	MA16034
	Date	Apr 17	Appendix	I



Suspended Solids (Intake Level of WSD Salt Water Intake) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction Graphical Presentation of Water Quality Monitoring Results	Scale N.T.S	Project No. MA16034	CINOTECH
	Date Apr 17	Appendix I	

**APPENDIX J
QUALITY CONTROL REPORTS FOR
LABORATORY ANALYSIS**

TEST REPORT

APPLICANT: Cinotech Consultants Limited
1710, Technology Park,
18 On Lai Street,
Shatin, N.T.

Report No.:	QC26801
Date of Issue:	2017-04-24
Date Received:	2017-04-11
Date Tested:	2017-04-11
Date Completed:	2017-04-24

ATTN: Ms. Mei Ling Tang
QC report:

Page: 1 of 2

Method Blank

Parameter	MB 1	Acceptance
Suspended Solids (SS) (mg/L)	<0.5	<0.5
Biochemical Oxygen Demand	N/A	N/A
Total Organic Carbon (mg-TOC/L)	<0.2	<0.2
Nitrogen (Total Kjeldahl + nitrate + nitrite)	N/A	N/A
Ammonia (mg NH ₃ -N/L)	<0.01	<0.01
Total Phosphorus (mg-P/L)	<0.01	<0.01

Method QC

Parameter	MQC1	Acceptance
Suspended Solids (SS) (%)	101	80-120
Biochemical Oxygen Demand (mg O ₂ /L)	176	170-220
Total Organic Carbon (%)	104	80-120
Nitrogen (Total Kjeldahl + nitrate + nitrite)	N/A	N/A
Ammonia (%)	97	80-120
Total Phosphorus (%)	92	80-120

Remarks: 1) < = less than

2) N/A = Not applicable

3) This report is the summary of quality control data for report number 26801.

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



PATRICK TSE
Laboratory Manager

TEST REPORT

Report No.:	QC26801
Date of Issue:	2017-04-24
Date Received:	2017-04-11
Date Tested:	2017-04-11
Date Completed:	2017-04-24

Page: 2 of 2

QC report:

Sample Duplicate

Parameter	26801-3 chk	Acceptance
Suspended Solids (SS) (%)	4	RPD \leq 20%
Biochemical Oxygen Demand (%)	N/A	RPD \leq 20%
Total Organic Carbon (%)	4	RPD \leq 20%
Nitrogen (Total Kjeldahl + nitrate + nitrite)	N/A	N/A
Ammonia (%)	N/A	RPD \leq 20%
Total Phosphorus (%)	N/A	RPD \leq 20%

Sample Spike

Parameter	26801-3 spk	Acceptance
Suspended Solids (SS) (%)	N/A	N/A
Biochemical Oxygen Demand (%)	N/A	N/A
Total Organic Carbon (%)	111	80-120
Nitrogen (Total Kjeldahl + nitrate + nitrite)	N/A	N/A
Ammonia (%)	107	80-120
Total Phosphorus (%)	104	80-120

Remarks: 1) \leq less than

2) N/A = Not applicable

3) This report is the summary of quality control data for report number 26801.

*****END OF REPORT*****

TEST REPORT

APPLICANT: Cinotech Consultants Limited
1710, Technology Park,
18 On Lai Street,
Shatin, N.T.

Report No.:	QC26866
Date of Issue:	2017-05-11
Date Received:	2017-04-27
Date Tested:	2017-04-27
Date Completed:	2017-05-11

ATTN: Ms. Mei Ling Tang
QC report:

Page: 1 of 2

Method Blank

Parameter	MB 1	Acceptance
Suspended Solids (SS) (mg/L)	<0.5	<0.5
Biochemical Oxygen Demand	N/A	N/A
Total Organic Carbon (mg-TOC/L)	<0.2	<0.2
Nitrogen (Total Kjeldahl + nitrate + nitrite)	N/A	N/A
Ammonia (mg NH ₃ -N/L)	<0.01	<0.01
Total Phosphorus (mg-P/L)	<0.01	<0.01

Method QC

Parameter	MQC1	Acceptance
Suspended Solids (SS) (%)	100	80-120
Biochemical Oxygen Demand (mg O ₂ /L)	178	170-220
Total Organic Carbon (%)	112	80-120
Nitrogen (Total Kjeldahl + nitrate + nitrite)	N/A	N/A
Ammonia (%)	105	80-120
Total Phosphorus (%)	93	80-120

Remarks: 1) < = less than

2) N/A = Not applicable

3) This report is the summary of quality control data for report number 26866.

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**


PATRICK TSE
Laboratory Manager

TEST REPORT

Report No.:	QC26866
Date of Issue:	2017-05-11
Date Received:	2017-04-27
Date Tested:	2017-04-27
Date Completed:	2017-05-11

Page: 2 of 2

QC report:

Sample Duplicate

Parameter	26866-3 chk	Acceptance
Suspended Solids (SS) (%)	1	RPD \leq 20%
Biochemical Oxygen Demand (%)	N/A	RPD \leq 20%
Total Organic Carbon (%)	12	RPD \leq 20%
Nitrogen (Total Kjeldahl + nitrate + nitrite)	N/A	N/A
Ammonia (%)	1	RPD \leq 20%
Total Phosphorus (%)	N/A	RPD \leq 20%

Sample Spike

Parameter	26866-3 spk	Acceptance
Suspended Solids (SS) (%)	N/A	N/A
Biochemical Oxygen Demand (%)	N/A	N/A
Total Organic Carbon (%)	104	80-120
Nitrogen (Total Kjeldahl + nitrate + nitrite)	N/A	N/A
Ammonia (%)	100	80-120
Total Phosphorus (%)	100	80-120

Remarks: 1) \leq less than

2) N/A = Not applicable

3) This report is the summary of quality control data for report number 26866.

*****END OF REPORT*****

TEST REPORT
QC REPORT

APPLICANT: Cinotech Consultants Limited
RM 1710, Technology Park,
18 On Lai Street,
Shatin, N.T., Hong Kong

Report No.:	26755
Date of Issue:	2017/04/05
Date Received:	2017/04/03
Date Tested:	2017/04/03
Date Completed:	2017/04/05

ATTN: Ms. Mei Ling Tang

Page: 1 of 1

Project Name: Enviromental Team for Tseung Kwan O - Lam Tin Tunnel -
Design and Construction Agreement No. CE/59/2015 (EP)
Project No.: MA16034
Sampling Date: 2017/04/03
Number of Sample: 132
Custody No.: MA16034-CE/59/2015(EP)/170403

Total Suspended Solids Sampling Point	Duplicate Analysis			QC Recovery, %
	Trial 1, mg/L	Trial 2, mg/L	Difference, %	
M4se	2.0	2.0	2	102

*******END OF REPORT*******

PREPARED AND CHECKED BY:
For and On Behalf of **WELLAB Ltd.**



PATRICK TSE
Laboratory Manager

TEST REPORT

QC REPORT

APPLICANT: Cinotech Consultants Limited
RM 1710, Technology Park,
18 On Lai Street,
Shatin, N.T., Hong Kong

Report No.:	26761
Date of Issue:	2017/04/06
Date Received:	2017/04/05
Date Tested:	2017/04/05
Date Completed:	2017/04/06

ATTN: Ms. Mei Ling Tang

Page: 1 of 1

Project Name: Enviromental Team for Tseung Kwan O - Lam Tin Tunnel -
Design and Construction Agreement No. CE/59/2015 (EP)

Project No.: MA16034

Sampling Date: 2017/04/05

Number of Sample: 136

Custody No.: MA16034-CE/59/2015(EP)/170405

Total Suspended Solids	Duplicate Analysis			QC Recovery, %
Sampling Point	Trial 1, mg/L	Trial 2, mg/L	Difference, %	
M4se	3.2	3.3	1	99

*****END OF REPORT*****

PREPARED AND CHECKED BY:

For and On Behalf of WELLAB Ltd.



PATRICK TSE

Laboratory Manager

TEST REPORT

QC REPORT

APPLICANT: Cinotech Consultants Limited
RM 1710, Technology Park,
18 On Lai Street,
Shatin, N.T., Hong Kong

Report No.:	26777
Date of Issue:	2017/04/10
Date Received:	2017/04/08
Date Tested:	2017/04/08
Date Completed:	2017/04/10

ATTN: Ms. Mei Ling Tang

Page: 1 of 1

Project Name: Enviromental Team for Tseung Kwan O - Lam Tin Tunnel -
Design and Construction Agreement No. CE/59/2015 (EP)

Project No.: MA16034

Sampling Date: 2017/04/08

Number of Sample: 136

Custody No.: MA16034-CE/59/2015(EP)/170408

Total Suspended Solids Sampling Point	Duplicate Analysis			QC Recovery, %
	Trial 1, mg/L	Trial 2, mg/L	Difference, %	
M4se	2.2	2.2	1	103

*****END OF REPORT*****

PREPARED AND CHECKED BY:
For and On Behalf of **WELLAB Ltd.**



PATRICK TSE
Laboratory Manager

TEST REPORT
QC REPORT

APPLICANT: Cinotech Consultants Limited
RM 1710, Technology Park,
18 On Lai Street,
Shatin, N.T., Hong Kong

Report No.:	26780
Date of Issue:	2017/04/11
Date Received:	2017/04/10
Date Tested:	2017/04/10
Date Completed:	2017/04/11

ATTN: Ms. Mei Ling Tang

Page: 1 of 1

Project Name: Enviromental Team for Tseung Kwan O - Lam Tin Tunnel -
Design and Construction Agreement No. CE/59/2015 (EP)
Project No.: MA16034
Sampling Date: 2017/04/10
Number of Sample: 136
Custody No.: MA16034-CE/59/2015(EP)/170410

Total Suspended Solids Sampling Point	Duplicate Analysis			QC Recovery, %
	Trial 1, mg/L	Trial 2, mg/L	Difference, %	
M4se	1.9	2.0	2	98

*****END OF REPORT*****

PREPARED AND CHECKED BY:
For and On Behalf of **WELLAB Ltd.**



PATRICK TSE
Laboratory Manager

TEST REPORT

QC REPORT

APPLICANT: Cinotech Consultants Limited
RM 1710, Technology Park,
18 On Lai Street,
Shatin, N.T., Hong Kong

Report No.:	26798
Date of Issue:	2017/04/13
Date Received:	2017/04/12
Date Tested:	2017/04/12
Date Completed:	2017/04/13

ATTN: Ms. Mei Ling Tang

Page: 1 of 1

Project Name: Enviromental Team for Tseung Kwan O - Lam Tin Tunnel -
Design and Construction Agreement No. CE/59/2015 (EP)
Project No.: MA16034
Sampling Date: 2017/04/12
Number of Sample: 136
Custody No.: MA16034-CE/59/2015(EP)/170412

Total Suspended Solids Sampling Point	Duplicate Analysis			QC Recovery, %
	Trial 1, mg/L	Trial 2, mg/L	Difference, %	
M4se	2.5	2.6	3	100

*****END OF REPORT*****

PREPARED AND CHECKED BY:
For and On Behalf of WELLAB Ltd.



PATRICK TSE
Laboratory Manager

TEST REPORT

QC REPORT

APPLICANT: Cinotech Consultants Limited
RM 1710, Technology Park,
18 On Lai Street,
Shatin, N.T., Hong Kong

Report No.:	26811
Date of Issue:	2017/04/18
Date Received:	2017/04/14
Date Tested:	2017/04/14
Date Completed:	2017/04/18

ATTN: Ms. Mei Ling Tang

Page: 1 of 1

Project Name: Enviromental Team for Tseung Kwan O - Lam Tin Tunnel -
Design and Construction Agreement No. CE/59/2015 (EP)

Project No.: MA16034

Sampling Date: 2017/04/14


Number of Sample: 136

Custody No.: MA16034-CE/59/2015(EP)/170414

Total Suspended Solids	Duplicate Analysis			QC Recovery, %
Sampling Point	Trial 1, mg/L	Trial 2, mg/L	Difference, %	
M4se	2.8	2.7	3	101

*****END OF REPORT*****

PREPARED AND CHECKED BY:
For and On Behalf of **WELLAB Ltd.**



PATRICK TSE
Laboratory Manager

TEST REPORT

QC REPORT

APPLICANT: Cinotech Consultants Limited
RM 1710, Technology Park,
18 On Lai Street,
Shatin, N.T., Hong Kong

Report No.:	26814
Date of Issue:	2017/04/19
Date Received:	2017/04/18
Date Tested:	2017/04/18
Date Completed:	2017/04/19

ATTN: Ms. Mei Ling Tang

Page: 1 of 1

Project Name: Enviromental Team for Tseung Kwan O - Lam Tin Tunnel -
Design and Construction Agreement No. CE/59/2015 (EP)

Project No.: MA16034

Sampling Date: 2017/04/18

Number of Sample: 136

Custody No.: MA16034-CE/59/2015(EP)/170418

Total Suspended Solids	Duplicate Analysis			QC Recovery, %
Sampling Point	Trial 1, mg/L	Trial 2, mg/L	Difference, %	
G3me	3.2	3.3	1	102

*****END OF REPORT*****

PREPARED AND CHECKED BY:
For and On Behalf of **WELLAB Ltd.**



PATRICK TSE
Laboratory Manager

TEST REPORT

QC REPORT

APPLICANT: Cinotech Consultants Limited
RM 1710, Technology Park,
18 On Lai Street,
Shatin, N.T., Hong Kong

Report No.:	26824
Date of Issue:	21/4/2017
Date Received:	20/4/2017
Date Tested:	20/4/2017
Date Completed:	21/4/2017

ATTN: Ms. Mei Ling Tang

Page: 1 of 1

Project Name: Enviromental Team for Tseung Kwan O - Lam Tin Tunnel -
Design and Construction Agreement No. CE/59/2015 (EP)
Project No.: MA16034
Sampling Date: 20/4/2017
Number of Sample: 136
Custody No.: MA16034-CE/59/2015(EP)/170420

Total Suspended Solids	Duplicate Analysis			QC Recovery, %
Sampling Point	Trial 1, mg/L	Trial 2, mg/L	Difference, %	
M4se	3.7	3.8	3	104

*****END OF REPORT*****

PREPARED AND CHECKED BY:
For and On Behalf of **WELLAB Ltd.**



PATRICK TSE
Laboratory Manager

TEST REPORT

QC REPORT

APPLICANT: Cinotech Consultants Limited
RM 1710, Technology Park,
18 On Lai Street,
Shatin, N.T., Hong Kong

Report No.:	26835
Date of Issue:	24/4/2017
Date Received:	22/4/2017
Date Tested:	22/4/2017
Date Completed:	24/4/2017

ATTN: Ms. Mei Ling Tang

Page: 1 of 1

Project Name: Enviromental Team for Tseung Kwan O - Lam Tin Tunnel -
Design and Construction Agreement No. CE/59/2015 (EP)

Project No.: MA16034

Sampling Date: 22/4/2017

Number of Sample: 136

Custody No.: MA16034-CE/59/2015(EP)/170422

Total Suspended Solids	Duplicate Analysis			QC Recovery, %
Sampling Point	Trial 1, mg/L	Trial 2, mg/L	Difference, %	
M4se	2.9	3.0	3	100

*****END OF REPORT*****

PREPARED AND CHECKED BY:
For and On Behalf of **WELLAB Ltd.**



PATRICK TSE
Laboratory Manager

TEST REPORT

QC REPORT

APPLICANT: Cinotech Consultants Limited
RM 1710, Technology Park,
18 On Lai Street,
Shatin, N.T., Hong Kong

Report No.:	26838
Date of Issue:	25/4/2017
Date Received:	24/4/2017
Date Tested:	24/4/2017
Date Completed:	25/4/2017

ATTN: Ms. Mei Ling Tang

Page: 1 of 1

Project Name: Enviromental Team for Tseung Kwan O - Lam Tin Tunnel -
Design and Construction Agreement No. CE/59/2015 (EP)
Project No.: MA16034
Sampling Date: 24/4/2017
Number of Sample: 136
Custody No.: MA16034-CE/59/2015(EP)/170424

Total Suspended Solids	Duplicate Analysis			QC Recovery, %
Sampling Point	Trial 1, mg/L	Trial 2, mg/L	Difference, %	
C2se	3.4	3.3	2	100

*****END OF REPORT*****

PREPARED AND CHECKED BY:
For and On Behalf of **WELLAB Ltd.**



PATRICK TSE
Laboratory Manager

TEST REPORT

QC REPORT

APPLICANT: Cinotech Consultants Limited
RM 1710, Technology Park,
18 On Lai Street,
Shatin, N.T., Hong Kong

Report No.:	26852
Date of Issue:	27/4/2017
Date Received:	26/4/2017
Date Tested:	26/4/2017
Date Completed:	27/4/2017

ATTN: Ms. Mei Ling Tang

Page: 1 of 1

Project Name: Enviromental Team for Tseung Kwan O - Lam Tin Tunnel -
Design and Construction Agreement No. CE/59/2015 (EP)

Project No.: MA16034

Sampling Date: 26/4/2017

Number of Sample: 136

Custody No.: MA16034-CE/59/2015(EP)/170426

Total Suspended Solids	Duplicate Analysis			QC Recovery, %
Sampling Point	Trial 1, mg/L	Trial 2, mg/L	Difference, %	
M4se	3.8	3.6	5	99

*****END OF REPORT*****

PREPARED AND CHECKED BY:
For and On Behalf of **WELLAB Ltd.**



PATRICK TSE
Laboratory Manager

TEST REPORT

QC REPORT

APPLICANT: Cinotech Consultants Limited
RM 1710, Technology Park,
18 On Lai Street,
Shatin, N.T., Hong Kong

Report No.:	26864
Date of Issue:	2/4/2017
Date Received:	28/4/2017
Date Tested:	28/4/2017
Date Completed:	2/5/2017

ATTN: Ms. Mei Ling Tang

Page: 1 of 1

Project Name: Enviromental Team for Tseung Kwan O - Lam Tin Tunnel -
Design and Construction Agreement No. CE/59/2015 (EP)

Project No.: MA16034

Sampling Date: 28/4/2017

Number of Sample: 136

Custody No.: MA16034-CE/59/2015(EP)/170428

Total Suspended Solids Sampling Point	Duplicate Analysis			QC Recovery, %
	Trial 1, mg/L	Trial 2, mg/L	Difference, %	
M4se	5.6	5.8	4	93

*****END OF REPORT*****

PREPARED AND CHECKED BY:
For and On Behalf of WELLAB Ltd.



PATRICK TSE
Laboratory Manager

**APPENDIX K
SUMMARY OF EXCEEDANCE**

**Agreement No. CE 59/2015 (EP)
Environmental Team for Tseung Kwan O - Lam Tin Tunnel –
Design and Construction**

Appendix K – Summary of Exceedance

Reporting Period: April 2017

**(A) Exceedance Report for Air Quality
(NIL in the reporting month)**

**(B) Exceedance Report for Construction Noise
(NIL in the reporting month)**

**(C) Exceedance Report for Water Quality
(One Action Level and Seven Limit Level exceedance in groundwater quality monitoring as followed:**

Date	Monitoring Location	Monitoring Parameter	Monitoring Results	Action Level	Limit Level
11 Apr 2017	Stream 1	Total Organic Carbon	6 mg-TOC/L	4.3	4.9
	Stream 2	Total Organic Carbon	17 mg-TOC/L	4.3	4.9
	Stream 2	Ammonia-N	0.13 mg NH ₃ -N/L	0.05	0.06
27 Apr 2017	Stream 1	Total Organic Carbon	5 mg-TOC/L	4.3	4.9
	Stream 2	Total Organic Carbon	9 mg-TOC/L	4.3	4.9
	Stream 2	Ammonia-N	0.08 mg NH ₃ -N/L	0.05	0.06
	Stream 3	Total Organic Carbon	5 mg-TOC/L	4.3	4.9
	Stream 3	Ammonia-N	0.06 mg NH ₃ -N/L	0.05	0.06

According to the information provided by the Contractor, no tunnel boring or tunnel construction works were carried out in both Lam Tin side and Tseung Kwan O side in April 2017. Therefore, it is considered that the exceedance is not project-related.)

**(D) Exceedance Report for Ecology
(NIL in the reporting month)**

**(E) Exceedance Report for Cultural Heritage
(NIL in the reporting month)**

**(F) Exceedance Report for Landfill Gas
(NIL in the reporting month)**

**APPENDIX L
SITE AUDIT SUMMARY**

Agreement No. CE 59/2015 (EP)

Environmental Team for Tseung Kwan O–Lam Tin Tunnel - Design and Construction

Contract NE/2015/01

Tseung Kwan O–Lam Tin Tunnel–Main Tunnel and Associated Works



Weekly Site Inspection Record Summary

Inspection Information

Checklist Reference Number	170405
Date	5 April 2017 (Wednesday)
Time	09:00 – 10:45

Ref. No.	Non-Compliance	Related Item No.
-	None identified	-

Ref. No.	Remarks/Observations	Related Item No.
170405-R01	B. Water Quality <ul style="list-style-type: none">No environmental deficiency was identified during site inspection. C. Ecology <ul style="list-style-type: none">No environmental deficiency was identified during site inspection. D. Landscape & Visual <ul style="list-style-type: none">To set-up tree protection zone for retained tree in TKO slope.	D2
170405-R02	E. Air Quality <ul style="list-style-type: none">To provide frequent water spray for TKO slope to prevent dust generation. F. Construction Noise Impact <ul style="list-style-type: none">No environmental deficiency was identified during site inspection. G. Waste / Chemical Management <ul style="list-style-type: none">No environmental deficiency was identified during site inspection. H. Permits/Licences <ul style="list-style-type: none">No environmental deficiency was identified during site inspection. I. Others <ul style="list-style-type: none">Follow-up on previous audit session (Ref. No.: 170329), all identified environmental deficiency was observed improved/rectified by the Contractor.	E5

	Name	Signature	Date
Recorded by	Johnny Fung		5 April 2017
Checked by	Dr. Priscilla Choy		5 April 2017

Agreement No. CE 59/2015 (EP)

Environmental Team for Tseung Kwan O–Lam Tin Tunnel - Design and Construction

Contract NE/2015/01

Tseung Kwan O–Lam Tin Tunnel–Main Tunnel and Associated Works



Weekly Site Inspection Record Summary

Inspection Information

Checklist Reference Number	170412
Date	12 April 2017 (Wednesday)
Time	09:00 – 11:00

Ref. No.	Non-Compliance	Related Item No.
-	None identified	-

Ref. No.	Remarks/Observations	Related Item No.
170412-R03	B. Water Quality <ul style="list-style-type: none">To set up proper drainage system in Portion 3 and U-channel should not diverted out of site.	B 1
170412-R05	<ul style="list-style-type: none">To cover or seal the gaps of covers of catchpit in Portion 1 to prevent silt water or oil stain flow out of site.	B 11
	C. Ecology <ul style="list-style-type: none">No environmental deficiency was identified during site inspection.	
170412-R04	D. Landscape & Visual <ul style="list-style-type: none">To properly set-up tree protection area in Portion 3.	D 3
	E. Air Quality <ul style="list-style-type: none">No environmental deficiency was identified during site inspection.	
	F. Construction Noise Impact <ul style="list-style-type: none">No environmental deficiency was identified during site inspection.	
170412-O01	G. Waste / Chemical Management <ul style="list-style-type: none">Oil stain observed in unpaved excavation area of Portion 3 and paved ground of Portion 1. The Contractor is reminded to properly remove the oil stain as “chemical waste”.	G 9
170412-R02	<ul style="list-style-type: none">To provide drip tray to chemical containers in Portion 3.	G10
	H. Permits/Licences <ul style="list-style-type: none">No environmental deficiency was identified during site inspection	
170412-R06	I. Impact on Cultural Heritage <ul style="list-style-type: none">To properly set up fenced-off buffer zone around Tin Hau Temple.	I 1
	J. Others <ul style="list-style-type: none">Follow-up on previous audit session (Ref. No.: 170405), all identified environmental deficiency was observed improved/rectified by the Contractor.	

	Name	Signature	Date
Recorded by	Johnny Fung		12 April 2017
Checked by	Dr. Priscilla Choy		12 April 2017

Agreement No. CE 59/2015 (EP)

Environmental Team for Tseung Kwan O–Lam Tin Tunnel - Design and Construction

Contract NE/2015/01

Tseung Kwan O–Lam Tin Tunnel–Main Tunnel and Associated Works



Weekly Site Inspection Record Summary

Inspection Information

Checklist Reference Number	170419
Date	19 April 2017 (Wednesday)
Time	09:00 – 11:00

Ref. No.	Non-Compliance	Related Item No.
-	None identified	-

Ref. No.	Remarks/Observations	Related Item No.
170419-R01	B. Water Quality <ul style="list-style-type: none">To remove the construction waste in U-channel in Portion 3.	B 7
170419-R02	<ul style="list-style-type: none">To set up proper drainage system in Portion 3 and U-channel should not be diverted out of site.	B 1
	C. Ecology <ul style="list-style-type: none">No environmental deficiency was identified during site inspection.	
170419-R03	D. Landscape & Visual <ul style="list-style-type: none">To properly set-up tree protection area in Portion 3.	D 3
	E. Air Quality <ul style="list-style-type: none">No environmental deficiency was identified during site inspection.	
	F. Construction Noise Impact <ul style="list-style-type: none">No environmental deficiency was identified during site inspection.	
	G. Waste / Chemical Management <ul style="list-style-type: none">No environmental deficiency was identified during site inspection.	
	H. Permits/Licences <ul style="list-style-type: none">No environmental deficiency was identified during site inspection	
170419-R04	I. Impact on Cultural Heritage <ul style="list-style-type: none">To properly set up fenced-off buffer zone around Tin Hau Temple.	I 1
	J. Others <ul style="list-style-type: none">Follow-up on previous audit session (Ref. No.: 170412), item ref no. 170412-R03, 170412-R04 and 170412-R06 are remarked as 170419-R02, 170419-R03, 170419-R04 respectively. Follow up action is needed to be reviewed during the next site inspection.	

	Name	Signature	Date
Recorded by	Johnny Fung		19 April 2017
Checked by	Dr. Priscilla Choy		19 April 2017

Agreement No. CE 59/2015 (EP)

Environmental Team for Tseung Kwan O-Lam Tin Tunnel - Design and Construction

Contract NE/2015/01

Tseung Kwan O-Lam Tin Tunnel-Main Tunnel and Associated Works



Weekly Site Inspection Record Summary

Inspection Information

Checklist Reference Number	170426
Date	26 April 2017 (Wednesday)
Time	09:00 – 11:00

Ref. No.	Non-Compliance	Related Item No.
-	None identified	-

Ref. No.	Remarks/Observations	Related Item No.
170426-002	B. Water Quality <ul style="list-style-type: none">Muddy water observed without proper containment in TKO. The Contractor is reminded to provide bunds or containment pit to prevent muddy water flow out of site.	B 3, 20, 21
	C. Ecology <ul style="list-style-type: none">No environmental deficiency was identified during site inspection.	
	D. Landscape & Visual <ul style="list-style-type: none">No environmental deficiency was identified during site inspection.	
170426-001	E. Air Quality <ul style="list-style-type: none">Grouting equipment in TKO observed without proper enclosure. The Contractor is reminded to provide top and 3-side enclosure.	E 11
	F. Construction Noise Impact <ul style="list-style-type: none">No environmental deficiency was identified during site inspection.	
170426-R03	G. Waste / Chemical Management <ul style="list-style-type: none">To remove oil stain mixed with muddy water in CKL site.	G 8
	H. Permits/Licences <ul style="list-style-type: none">No environmental deficiency was identified during site inspection	
	I. Impact on Cultural Heritage <ul style="list-style-type: none">No environmental deficiency was identified during site inspection	
170426-J04	J. Others <ul style="list-style-type: none">Follow-up on previous audit session (Ref. No.: 170419), follow up action is needed to be reviewed for item ref no.170419-R02 and 170419-R03 during the next site inspection.	J2, 3

	Name	Signature	Date
Recorded by	Johnny Fung		26 April 2017
Checked by	Dr. Priscilla Choy		26 April 2017

Agreement No. CE 59/2015 (EP)

Environmental Team for Tseung Kwan O–Lam Tin Tunnel - Design and Construction

Contract NE/2015/02

Tseung Kwan O–Lam Tin Tunnel–Road P2 and Associated Works



Weekly Site Inspection Record Summary

Inspection Information

Checklist Reference Number	170406
Date	6 April 2017 (Thursday)
Time	14:00-15:15

Ref. No.	Non-Compliance	Related Item No.
-	None identified	-

Ref. No.	Remarks/Observations	Related Item No.
170406-R04	B. Water Quality <ul style="list-style-type: none">To remove the accumulated sediments in the U-channels in Area A.	B 7
	C. Ecology <ul style="list-style-type: none">No environmental deficiency was identified during site inspection.	
	D. Landscape & Visual <ul style="list-style-type: none">No environmental deficiency was identified during site inspection.	
170406-R03	E. Air Quality <ul style="list-style-type: none">To cover the stockpile of dusty material properly in Area A by tarpaulin sheet.	E 6
	F. Construction Noise Impact <ul style="list-style-type: none">No environmental deficiency was identified during site inspection.	
170406-R01	G. Waste / Chemical Management <ul style="list-style-type: none">To remove the accumulation of C&D waste and general refuse regularly in Portion 8. Empty chemical containers should be separated with other C&D waste and be treated as “chemical waste”.	G 1i, 2ii, 4ii, 4iii
170406-R02	<ul style="list-style-type: none">To provide drip tray to chemical containers in Portion 8.	G10
	H. Permits/Licences <ul style="list-style-type: none">No environmental deficiency was identified during site inspection.	
	I. Others <p>Follow-up on previous audit section (Ref. No.: 170329), follow up action is needed to reviewed for item ref no. 170329-R01. Item remarked as 170406-R03.</p>	

	Name	Signature	Date
Recorded by	Johnny Fung		6 April 2017
Checked by	Dr. Priscilla Choy		6 April 2017

Agreement No. CE 59/2015 (EP)

Environmental Team for Tseung Kwan O-Lam Tin Tunnel - Design and Construction

Contract NE/2015/02

Tseung Kwan O-Lam Tin Tunnel-Road P2 and Associated Works



Weekly Site Inspection Record Summary

Inspection Information

Checklist Reference Number	170413
Date	13 April 2017 (Thursday)
Time	14:00-15:00

Ref. No.	Non-Compliance	Related Item No.
-	None identified	-

Ref. No.	Remarks/Observations	Related Item No.
	<p>B. Water Quality</p> <ul style="list-style-type: none">• No environmental deficiency was identified during site inspection. <p>C. Ecology</p> <ul style="list-style-type: none">• No environmental deficiency was identified during site inspection. <p>D. Landscape & Visual</p> <ul style="list-style-type: none">• No environmental deficiency was identified during site inspection. <p>E. Air Quality</p> <ul style="list-style-type: none">• No environmental deficiency was identified during site inspection. <p>F. Construction Noise Impact</p> <ul style="list-style-type: none">• No environmental deficiency was identified during site inspection. <p>G. Waste / Chemical Management</p> <ul style="list-style-type: none">• No environmental deficiency was identified during site inspection. <p>H. Permits/Licences</p> <ul style="list-style-type: none">• No environmental deficiency was identified during site inspection. <p>I. Others</p> <p>Follow-up on previous audit section (Ref. No.: 170406), all identified environmental deficiency was observed improved/rectified by the Contractor.</p>	

	Name	Signature	Date
Recorded by	Victor Wong		13 April 2017
Checked by	Dr. Priscilla Choy		13 April 2017

Agreement No. CE 59/2015 (EP)

Environmental Team for Tseung Kwan O-Lam Tin Tunnel - Design and Construction

Contract NE/2015/02

Tseung Kwan O-Lam Tin Tunnel-Road P2 and Associated Works



Weekly Site Inspection Record Summary

Inspection Information

Checklist Reference Number	170418
Date	18 April 2017 (Tuesday)
Time	9:00-10:00

Ref. No.	Non-Compliance	Related Item No.
-	None identified	-

Ref. No.	Remarks/Observations	Related Item No.
170418-R02	B. Water Quality <ul style="list-style-type: none">No environmental deficiency was identified during site inspection. C. Ecology <ul style="list-style-type: none">No environmental deficiency was identified during site inspection. D. Landscape & Visual <ul style="list-style-type: none">No environmental deficiency was identified during site inspection. E. Air Quality <ul style="list-style-type: none">To remove the dusty used cement bags at Portion 1.	E16
170418-R01	F. Construction Noise Impact <ul style="list-style-type: none">To provide proper acoustic material for enclosing the breaker head at Portion SR2B. G. Waste / Chemical Management <ul style="list-style-type: none">No environmental deficiency was identified during site inspection. H. Permits/Licences <ul style="list-style-type: none">No environmental deficiency was identified during site inspection. I. Others <p>Follow-up on previous audit section (Ref. No.: 170413), no environmental deficiency was identified during site inspection.</p>	P5

	Name	Signature	Date
Recorded by	Johnny Fung		18 April 2017
Checked by	Dr. Priscilla Choy		18 April 2017

Agreement No. CE 59/2015 (EP)

Environmental Team for Tseung Kwan O-Lam Tin Tunnel - Design and Construction

Contract NE/2015/02

Tseung Kwan O-Lam Tin Tunnel-Road P2 and Associated Works



Weekly Site Inspection Record Summary

Inspection Information

Checklist Reference Number	170426
Date	26 April 2017 (Wednesday)
Time	14:30-15:30

Ref. No.	Non-Compliance	Related Item No.
-	None identified	-

Ref. No.	Remarks/Observations	Related Item No.
170426-R01	<p>B. Water Quality</p> <ul style="list-style-type: none">To repair the holes near the discharge point in Area A to prevent surface runoff flow into the discharge point. <p>C. Ecology</p> <ul style="list-style-type: none">No environmental deficiency was identified during site inspection. <p>D. Landscape & Visual</p> <ul style="list-style-type: none">No environmental deficiency was identified during site inspection. <p>E. Air Quality</p> <ul style="list-style-type: none">No environmental deficiency was identified during site inspection. <p>F. Construction Noise Impact</p> <ul style="list-style-type: none">No environmental deficiency was identified during site inspection. <p>G. Waste / Chemical Management</p> <ul style="list-style-type: none">No environmental deficiency was identified during site inspection. <p>H. Permits/Licences</p> <ul style="list-style-type: none">No environmental deficiency was identified during site inspection. <p>I. Others</p> <ul style="list-style-type: none">Follow-up on previous audit section (Ref. No.: 170413), no environmental deficiency was identified during site inspection.	B 21

	Name	Signature	Date
Recorded by	Johnny Fung		26 April 2017
Checked by	Dr. Priscilla Choy		26 April 2017

APPENDIX M
EVENT AND ACTION PLANS

Event and Action Plan for Air Quality (Dust)

EVENT	ACTION			
	ET	IEC	ER	CONTRACTOR
Action level being exceeded by one sampling	<ol style="list-style-type: none"> 1. Identify source, investigate the causes of complaint and propose remedial measures; 2. Inform IEC and ER; 3. Repeat measurement to confirm finding; 4. Increase monitoring frequency to daily. 	<ol style="list-style-type: none"> 1. Check monitoring data submitted by ET; 2. Check Contractor's working method. 	<ol style="list-style-type: none"> 1. Notify Contractor. 	<ol style="list-style-type: none"> 1. Rectify any unacceptable practice; 2. Amend working methods if appropriate.
Action level being exceeded by two or more consecutive sampling	<ol style="list-style-type: none"> 1. Identify source; 2. Inform IEC and ER; 3. Advise the ER on the effectiveness of the proposed remedial measures; 4. Repeat measurements to confirm findings; 5. Increase monitoring frequency to daily; 6. Discuss with IEC and Contractor on remedial actions required; 7. If exceedance continues, arrange meeting with IEC and ER; 	<ol style="list-style-type: none"> 1. Check monitoring data submitted by ET; 2. Check Contractor's working method; 3. Discuss with ET and Contractor on possible remedial measures; 4. Advise the ET on the effectiveness of the proposed remedial measures; 5. Supervise Implementation of remedial measures. 	<ol style="list-style-type: none"> 1. Confirm receipt of notification of exceedance in writing; 2. Notify Contractor; 3. Ensure remedial measures properly implemented. 	<ol style="list-style-type: none"> 1. Submit proposals for remedial actions to IEC within three working days of notification; 2. Implement the agreed proposals; 3. Amend proposal if appropriate.

EVENT	ACTION			
	ET	IEC	ER	CONTRACTOR
	8. If exceedance stops, cease additional monitoring.			
Limit level being exceeded by one sampling	<ol style="list-style-type: none"> 1. Identify source, investigate the causes of exceedance and propose remedial measures; 2. Inform Contractor ,IEC, ER, and EPD; 3. Repeat measurement to confirm finding; 4. Increase monitoring frequency to daily; 5. Assess effectiveness of Contractor's remedial actions and keep IEC, EPD and ER informed of the results. 	<ol style="list-style-type: none"> 1. Check monitoring data submitted by ET; 2. Check Contractor's working method; 3. Discuss with ET and Contractor on possible remedial measures; 4. Advise the ER on the effectiveness of the proposed remedial measures; 5. Supervise implementation of remedial measures. 	<ol style="list-style-type: none"> 1. Confirm receipt of notification of exceedance in writing; 2. Notify Contractor; 3. Ensure remedial measures properly implemented. 	<ol style="list-style-type: none"> 1. Take immediate action to avoid further exceedance; 2. Submit proposals for remedial actions to IEC within three working days of notification; 3. Implement the agreed proposals; 4. Amend proposal if appropriate.
Limit level being exceeded by two or more consecutive sampling	<ol style="list-style-type: none"> 1. Notify IEC, ER, Contractor and EPD; 2. Identify source; 3. Repeat measurement to confirm findings; 4. Increase monitoring frequency to daily; 	<ol style="list-style-type: none"> 1. Discuss amongst ER, ET, and Contractor on the potential remedial actions; 2. Review Contractor's remedial actions whenever necessary to assure their effectiveness and advise the ER accordingly; 	<ol style="list-style-type: none"> 1. Confirm receipt of notification of exceedance in writing; 2. Notify Contractor; 3. In consolidation with the IEC, agree with the Contractor on the remedial measures to be implemented; 	<ol style="list-style-type: none"> 1. Take immediate action to avoid further exceedance; 2. Submit proposals for remedial actions to IEC within three working days of notification; 3. Implement the agreed proposals;

EVENT	ACTION			
	ET	IEC	ER	CONTRACTOR
	5. Carry out analysis of Contractor’s working procedures to determine possible mitigation to be implemented; 6. Arrange meeting with IEC and ER to discuss the remedial actions to be taken; 7. Assess effectiveness of Contractor’s remedial actions and keep IEC, EPD and ER informed of the results; 8. If exceedance stops, cease additional monitoring.	3. Supervise the implementation of remedial measures.	4. Ensure remedial measures properly implemented; 5. If exceedance continues, consider what portion of the work is responsible and instruct the Contractor to stop that portion of work until the exceedance is abated.	4. Resubmit proposals if problem still not under control; 5. Stop the relevant portion of works as determined by the ER until the exceedance is abated.

Event and Action Plan for Construction Noise

EVENT	ACTION			
	ET	IEC	ER	CONTRACTOR
Action Level	<ol style="list-style-type: none"> 1. Notify IEC and Contractor; 2. Carry out investigation; 3. Report the results of investigation to the IEC, ER and Contractor; 4. Discuss with the Contractor and formulate remedial measures; 5. Increase monitoring frequency to check mitigation effectiveness. 	<ol style="list-style-type: none"> 1. Review the analysed results submitted by the ET; 2. Review the proposed remedial measures by the Contractor and advise the ER accordingly; 3. Supervise the implementation of remedial measures. 	<ol style="list-style-type: none"> 1. Confirm receipt of notification of failure in writing; 2. Notify Contractor; 3. Require Contractor to propose remedial measures for the analysed noise problem; 4. Ensure remedial measures are properly implemented. 	<ol style="list-style-type: none"> 1. Submit noise mitigation proposals to IEC; 2. Implement noise mitigation proposals.
Limit Level	<ol style="list-style-type: none"> 1. Identify source; 2. Inform IEC, ER, EPD and Contractor; 3. Repeat measurements to confirm findings; 4. Increase monitoring frequency; 5. Carry out analysis of Contractor's working procedures to determine possible mitigation to be implemented; 6. Inform IEC, ER and EPD the causes and actions taken for the exceedances; 	<ol style="list-style-type: none"> 1. Discuss amongst ER, ET, and Contractor on the potential remedial actions; 2. Review Contractors remedial actions whenever necessary to assure their effectiveness and advise the ER accordingly; 3. Supervise the implementation of remedial measures. 	<ol style="list-style-type: none"> 1. Confirm receipt of notification of failure in writing; 2. Notify Contractor; 3. Require Contractor to propose remedial measures for the analysed noise problem; 4. Ensure remedial measures properly implemented; 5. If exceedance continues, consider what portion of the work is responsible and instruct the Contractor to stop that portion of work until the exceedance is abated. 	<ol style="list-style-type: none"> 1. Take immediate action to avoid further exceedance; 2. Submit proposals for remedial actions to IEC within 3 working days of notification; 3. Implement the agreed proposals; 4. Resubmit proposals if problem still not under control; 5. Stop the relevant portion of works as determined by the ER until the exceedance is abated.

EVENT	ACTION			
	ET	IEC	ER	CONTRACTOR
	7. Assess effectiveness of Contractor's remedial actions and keep IEC, EPD and ER informed of the results; 8. If exceedance stops, cease additional monitoring.			

Event and Action Plan for Marine Water Quality

Event	Action			
	ET	IEC	ER	CONTRACTOR
Action level being exceeded by one sampling day at water sensitive receiver(s)	<ul style="list-style-type: none"> Identify the source(s) of impact by comparing the results with those collected at the control stations as appropriate; If exceedance is found to be caused by the reclamation activities, repeat <i>in-situ</i> measurement to confirm findings; Inform IEC and contractor; Check monitoring data, all plant, equipment and Contractor's working methods; If exceedance occurs at WSD salt water intake, inform WSD; Discuss mitigation measures with IEC and Contractor; Repeat measurement on next day of exceedance. 	<ul style="list-style-type: none"> Discuss with ET and Contractor on the mitigation measures; Review proposal on mitigation measures submitted by Contractor and advise the ER accordingly; Assess the effectiveness of the implemented mitigation measures. 	<ul style="list-style-type: none"> Discuss with IEC on the proposed mitigation measures; Make agreement on the mitigation proposal. 	<ul style="list-style-type: none"> Inform the ER and confirm notification of the non-compliance in writing; Rectify unacceptable practice; Check all plant and equipment; Amend working methods if appropriate; Discuss with ET and IEC and propose mitigation measures to IEC and ER; Implement the agree mitigation measures.
Action level being exceeded by two or more consecutive	<ul style="list-style-type: none"> Identify the source(s) of impact by comparing the results with those collected at the control stations as appropriate; 	<ul style="list-style-type: none"> Discuss with ET and Contractor on the mitigation measures; 	<ul style="list-style-type: none"> Discuss with IEC on the proposed mitigation measures; Make agreement on the mitigation proposal; 	<ul style="list-style-type: none"> Inform the Engineer and confirm notification of the non-compliance in writing; Rectify unacceptable practice;

Event	Action			
	ET	IEC	ER	CONTRACTOR
<p>sampling days at water sensitive receiver(s)</p>	<ul style="list-style-type: none"> • If exceedance is found to be caused by the reclamation activities, repeat in-situ measurement to confirm findings; • Inform IEC and contractor; • Check monitoring data, all plant, equipment and Contractor's working methods; • Discuss mitigation measures with IEC and Contractor; • Ensure mitigation measures are implemented; • Prepare to increase the monitoring frequency to daily; • If exceedance occurs at WSD salt water intake, inform WSD; • Repeat measurement on next day of exceedance. 	<ul style="list-style-type: none"> • Review proposal on mitigation measures submitted by Contractor and advise the ER accordingly; • Assess the effectiveness of the implemented mitigation measures. 	<ul style="list-style-type: none"> • Assess the effectiveness of the implemented mitigation measures. 	<ul style="list-style-type: none"> • Check all plant and equipment and consider changes of working methods; • Discuss with ET, IEC and ER and propose mitigation measures to IEC and ER within 3 working days; • Implement the agreed mitigation measures.
<p>Limit level being exceeded by one sampling day at water sensitive receiver(s)</p>	<ul style="list-style-type: none"> • Identify the source(s) of impact by comparing the results with those collected at the control stations as appropriate; 	<ul style="list-style-type: none"> • Discuss with ET and Contractor on the mitigation measures; • Review proposal on mitigation measures submitted by Contractor and advise the ER accordingly; 	<ul style="list-style-type: none"> • Discuss with IEC, ET and Contractor on the proposed mitigation measures; • Request Contractor to critically review the working methods; 	<ul style="list-style-type: none"> • Inform the ER and confirm notification of the non-compliance in writing; • Rectify unacceptable practice;

Event	Action			
	ET	IEC	ER	CONTRACTOR
	<ul style="list-style-type: none"> • If exceedance is found to be caused by the reclamation activities, repeat <i>in-situ</i> measurement to confirm findings; • Inform IEC, contractor, AFCD and EPD • Check monitoring data, all plant, equipment and Contractor's working methods; • Discuss mitigation measures with IEC, ER and Contractor; • Ensure mitigation measures are implemented; • Increase the monitoring frequency to daily until no exceedance of Limit level; • If exceedance occurs at WSD salt water intake, inform WSD. 	<ul style="list-style-type: none"> • Assess the effectiveness of the implemented mitigation measures. 	<ul style="list-style-type: none"> • Make agreement on the mitigation measures to be implemented; • Assess the effectiveness of the implemented mitigation measures. 	<ul style="list-style-type: none"> • Check all plant and equipment and consider changes of working methods; • Discuss with ET, IEC and ER and submit proposal of mitigation measures to IEC and ER within 3 working days of notification; • Implement the agreed mitigation measures.
Limit level being exceeded by two or more consecutive sampling days at	<ul style="list-style-type: none"> • Identify the source(s) of impact by comparing the results with those collected at the control stations as appropriate; 	<ul style="list-style-type: none"> • Discuss with ET and Contractor on the mitigation measures; • Review proposal on mitigation measures submitted by Contractor and advise the ER accordingly; 	<ul style="list-style-type: none"> • Discuss with IC(E), ET and Contractor on the proposed mitigation measures; • Request Contractor to critically review the working methods; 	<ul style="list-style-type: none"> • Inform the ER and confirm notification of the non-compliance in writing; • Rectify unacceptable practice;

Event	Action			
	ET	IEC	ER	CONTRACTOR
water sensitive receiver(s)	<ul style="list-style-type: none"> • If exceedance is found to be caused by the reclamation activities, repeat in-situ measurement to confirm findings; • Inform IC(E), AFCD, contractor and EPD; • Check monitoring data, all plant, equipment and Contractor's working methods; • Discuss mitigation measures with IC(E), ER and Contractor; • Ensure mitigation measures are implemented; • Increase the monitoring frequency to daily until no exceedance of Limit level for two consecutive days; • If exceedance occurs at WSD salt water intake, inform WSD. 	<ul style="list-style-type: none"> • Assess the effectiveness of the implemented mitigation measures. 	<ul style="list-style-type: none"> • Make agreement on the mitigation measures to be implemented; • Assess the effectiveness of the implemented mitigation measures; • Consider and instruct, if necessary, the Contractor to slow down or to stop all or part of the marine work until no exceedance of Limit level. 	<ul style="list-style-type: none"> • Check all plant and equipment and consider changes of working methods; • Discuss with ET, IC(E) and ER and submit proposal of mitigation measures to IC(E) and ER within 3 working days of notification; • Implement the agreed mitigation measures; • As directed by the Engineer, to slow down or to stop all or part of the construction activities.

Limit Levels and Action Plan for Landfill Gas

Parameter	Limit Level	Action
Oxygen	<19%	<ul style="list-style-type: none"> • Ventilate to restore oxygen to >19%
	<18%	<ul style="list-style-type: none"> • Stop works • Evacuate personnel/prohibit entry • Increase ventilation to restore oxygen to >19%
Methane	>10% LEL (i.e. > 0.5% by volume)	<ul style="list-style-type: none"> • Prohibit hot works • Ventilate to restore methane to <10% LEL
	>20% LEL (i.e. > 1% by volume)	<ul style="list-style-type: none"> • Stop works • Evacuate personnel / prohibit entry • Increase ventilation to restore methane to <10% LEL
Carbon Dioxide	>0.5%	<ul style="list-style-type: none"> • Ventilate to restore carbon dioxide to < 0.5%
	>1.5%	<ul style="list-style-type: none"> • Stop works • Evacuate personnel / prohibit entry • Increase ventilation to restore carbon dioxide to < 0.5%

Event and Action Plan for Coral Post-Translocation Monitoring

Event	Action			
	ET Leader	IEC	ER	Contractor
Action Level Exceedance	1. Check monitoring data; 2. Inform the IEC, ER and Contractor of the findings; 3. Increase the monitoring to at least once a month to confirm findings; 4. Propose mitigation measures for consideration	1. Discuss monitoring with the ET and the Contractor; 2. Review proposals for additional Monitoring and any other measures submitted by the Contractor and advise the ER accordingly.	1. Discuss with the IEC additional monitoring requirements and any other measures proposed by the ET; 2. Make agreement on the measures to be implemented.	1. Inform the ER and confirm notification of the non-compliance in writing; 2. Discuss with the ET and the IEC and propose measures to the IEC and the ER; 3. Implement the agreed measures.
Limit Level Exceedance	Undertake Steps 1-4 as in the Action Level Exceedance. If further exceedance of Limit Level, suspend construction works until an effective solution is identified.	1. Discuss monitoring with the ET and the Contractor; 2. Review proposals for additional Monitoring and any other measures submitted by the Contractor and advise the ER accordingly.	1. Discuss with the IEC additional monitoring requirements and any other measures proposed by the ET; 2. Make agreement on the measures to be implemented.	1. Inform the ER and confirm notification of the non-compliance in writing; 2. Discuss with the ET and the IEC and propose measures to the IEC and the ER; 3. Implement the agreed measures.

Mitigation Measures for Vibration Monitoring

Level	Contingency Action
Alert Level	<ul style="list-style-type: none"> ● The Engineer shall be informed immediately. ● The Contractor shall submit an investigation report to describe works being undertaken. To review the instrument responses and to study the cause of undue response. ● The Contractor shall review and increase the instrumentation monitoring and reporting frequency, if applicable. ● The Contractor shall submit a detailed plan of action describing the measures to be taken should the concerned instrument reach the action level to the Engineer for approval.
Alarm Level	<ul style="list-style-type: none"> ● The Engineer shall be informed immediately. ● The active construction works may require to be suspended subject to the Engineer's review of monitoring data. ● The Contractor shall immediately implement the measures as defined in the detailed plan of action to prevent further ground movement and groundwater drawdown etc. ● The Contractor shall prepare a detailed investigation report to study the cause of the exceedance ● The Contractor shall propose a contingency plan for the Engineer's approval in the event that alarm value is reached or exceeded ● The Contractor shall develop an emergency plan for the Engineer's approval in the event the applied contingency measures cannot control the situation. ● The Contractor shall meet the Engineer to discuss the instrument response and review the effectiveness of the implemented measures. ● The Contractor shall carry out design review of the works

Action Level	<ul style="list-style-type: none">● Consideration shall be given to suspend all active construction works and the Engineer shall be informed immediately● The Contractor shall immediately implement the measures defined in the contingency plan● The Contractor shall implement the measures defined in the emergency plan in the event that the applied contingency measures are found inadequate● The Contractor shall provide a complete report to examine the construction method and review the response of the instruments with full history of the monitoring data and construction activities and necessary design update● To resume the suspended activities, the Contractor shall demonstrate to the Engineer's satisfaction that it is safe to do so with approval from the Engineer.
--------------	--

**APPENDIX N
ENVIRONMENTAL MITIGATION
IMPLEMENTATION SCHEDULE (EMIS)**

Table I – Recommended Mitigation Measures stipulated in EM&A Manual of the Project

(Further information on observations/reminders/non-compliance made during site audit should refer to Table II)

- Key:**
- ^ Mitigation measure was fully implemented.
 - * Observation/reminder was made during site audit but improved/rectified by the contractor.
 - # Observation/reminder was made during site audit but not yet improved/rectified by the contractor.
 - X Non-compliance of mitigation measure
 - Non-compliance but rectified by the contractor
 - N/A Not Applicable

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
Air Quality Impact							
S3.8.1	Watering eight times a day on active works areas, exposed areas and paved haul roads	To minimize the dust impact	Contractor	All Active Work Sites	Construction phase	APCO	* (1)
S3.8.1	Enclosing the unloading process at barging point by a 3-sided screen with top tipping hall, provision of water spraying and flexible dust curtains	To minimize the dust impact	Contractor	Barging Points	Construction phase	APCO	N/A
S3.8.7	Dust suppression measures stipulated in the Air Pollution Control (Construction Dust) Regulation and good site practices: <ul style="list-style-type: none"> - Use of regular watering to reduce dust emissions from exposed site surfaces and unpaved roads, particularly during dry weather. - Use of frequent watering for particularly dusty construction areas and areas close to ASRs. - Side enclosure and covering of any aggregate or dusty material storage piles to reduce emissions. Where this is not practicable owing to frequent usage, watering shall be 	To minimize the dust impact	Contractor	All Construction Work Sites	Construction phase	APCO and Air Pollution Control (Construction Dust) Regulation	* (1) * (1) * (2)

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
	<p>applied to aggregate fines.</p> <ul style="list-style-type: none"> - Open stockpiles shall be avoided or covered. Where possible, prevent placing dusty material storage piles near ASRs. - Tarpaulin covering of all dusty vehicle loads transported to, from and between site locations. - Establishment and use of vehicle wheel and body washing facilities at the exit points of the site. - Provision of wind shield and dust extraction units or similar dust mitigation measures at the loading area of barging point, and use of water sprinklers at the loading area where dust generation is likely during the loading process of loose material, particularly in dry seasons/ periods. - Provision of not less than 2.4m high hoarding from ground level along site boundary where adjoins a road, streets or other accessible to the public except for a site entrance or exit. - Imposition of speed controls for vehicles on site haul roads. - Where possible, routing of vehicles and positioning of construction plant should be at the maximum possible distance from ASRs - Every stock of more than 20 bags of cement or dry pulverised fuel ash (PFA) should be covered entirely by impervious sheeting or placed in an area sheltered on the top and the 3 sides. - Instigation of an environmental monitoring and auditing program to monitor the construction process in order to enforce controls and modify method of work if dusty conditions arise. 						<p>* (3)</p> <p>^</p> <p>^</p> <p>N/A</p> <p>^</p> <p>^</p> <p>^</p> <p>* (4)</p> <p>^</p>

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
/	Emission from Vehicles and Plants <ul style="list-style-type: none"> • All vehicles shall be shut down in intermittent use. • Only well-maintained plant should be operated on-site and plant should be serviced regularly to avoid emission of black smoke. • All diesel fuelled construction plant within the works areas shall be powered by ultra low sulphur diesel fuel (ULSD) 	Reduce air pollution emission from construction vehicles and plants	Contractor	All construction sites	Construction stage	• APCO	^ ^ ^
/	Valid No-road Mobile Machinery (NRMM) labels should be provided to regulated machines	Reduce air pollution emission from construction vehicles and plants	Contractor	All construction sites	Construction stage	• APCO	^
Noise Impact (Construction Phase)							
S4.8	- Use of quiet PME. Use of movable noise barriers for Excavator, Lorry, Dump Truck, Mobile Crane, Compactor, Concrete Mixer Truck, Concrete Lorry Mixer, Breaker, Mobile Crusher, Backhoe, Vibratory Poker, Saw, Asphalt Paver, Vibratory Roller, Vibrolance, Hydraulic Vibratory Lance and Piling (Vibration Hammer). Use of full enclosure for Air Compressor, Compressor, Bar Bender, Generator, Drilling Rig, Chisel, Large Diameter Bore Piling, Grout Mixer & Pump and Concrete Pump.	To minimize construction noise impact arising from the Project at the affected NSRs	Contractor	Work Sites	Construction phase	EIAO-TM, NCO	* (5)
S4.9	Good Site Practice <ul style="list-style-type: none"> - Only well-maintained plant should be operated on-site and plant should be serviced regularly during the construction program - Silencers or mufflers on construction equipment should be utilized and should be properly maintained during the construction program. - Mobile plant, if any, should be sited as far away from NSRs as possible. 	To minimize construction noise impact arising from the Project at the affected NSRs	Project Proponent	Work sites	Construction Period	EIAO-TM, NCO	^ ^ ^

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
	<ul style="list-style-type: none"> - Machines and plant (such as trucks) that may be in intermittent use should be shut down between works periods or should be throttled down to a minimum. - Plant known to emit noise strongly in one direction should, wherever possible, be orientated so that the noise is directed away from the nearby NSRs. - Material stockpiles and other structures should be effectively utilized, wherever practicable, in screening noise from on-site construction activities. 						<p style="text-align: center;">^</p> <p style="text-align: center;">^</p> <p style="text-align: center;">^</p>
S4.9	Scheduling of Construction Works during School Examination Period	To minimize construction noise impact arising from the Project at the affected NSRs	Contractor	Work site near school	Construction phase	EIAO-TM, NCO	N/A
Water Quality Impact (Construction Phase)							
S5.6.24	The dry density of filling material for the TKO-LT Tunnel reclamation should be 1,900kg/m ³ , with fine content of 25% or less	Control potential impacts from filling activities	CEDD's Contractors	Work site	Construction Phase	EIAO-TM, WPCO	N/A
S5.8.1	Non-dredged method by constructing steel cellular caisson structure with stone column shall be adopted for construction of seawall foundation. During the stone column installation (also including the installation of steel cellular caisson), silt curtain shall be employed around the active stone column installation points.	Control potential impacts from filling activities	CEDD's Contractors	Work site	Construction Phase	EIAO-TM, WPCO	N/A
S5.8.2	Formation of seawall enclosing the reclamation for Road P2 (notwithstanding an opening of about 50m for marine access) shall be completed prior to the filling activities. The seawall opening of about 50m wide for marine access shall be selected at a location as indicatively shown in Appendix 5.10. No more than 3 filling barge trips per day shall be made with a	Control potential impacts from filling activities	CEDD's Contractors	Work site	Construction Phase	EIAO-TM, WPCO	N/A

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
	<p>maximum daily rate of 3,000m³ (i.e. 1,000 m³ per trip) for the filling operation at the reclamation area for Road P2. All filling works shall be carried out behind the seawall with the use of single silt curtain at the marine access.</p>						
S5.8.3	<p>Other good site practices should be undertaken during filling operations include:</p> <ul style="list-style-type: none"> - all marine works should adopt the environmental friendly construction methods as far as practically possible including the use of cofferdams to cover the construction area to separate the construction works from the sea; - floating single silt curtain shall be employed for all marine works; - all vessels should be sized so that adequate clearance is maintained between vessels and the seabed in all tide conditions, to ensure that undue turbidity is not generated by turbulence from vessel movement or propeller wash; - all hopper barges should be fitted with tight fitting seals to their bottom openings to prevent leakage of material; - excess material shall be cleaned from the decks and exposed fittings of barges before the vessel is moved; - adequate freeboard shall be maintained on barges to reduce the likelihood of decks being washed by wave action; - loading of barges and hoppers should be controlled to prevent splashing of filling material into the surrounding water. Barges or hoppers should not be filled to a level that will cause the overflow of materials or polluted water during loading or transportation; - any pipe leakages shall be repaired quickly. Plant should not be operated with leaking pipes; - construction activities should not cause foam, oil, grease, scum, litter or other 	Control potential impacts from filling activities and marine-based construction	CEDD's Contractors	Work site	Construction Phase	EIAO-TM, WPCO, Waste Disposal Ordinance (WDO)	<p>^</p> <p>^</p> <p>^</p> <p>^</p> <p>^</p> <p>^</p> <p>^</p> <p>^</p> <p>^</p>

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
	<p>objectionable matter to be present on the water within the site or dumping grounds; and</p> <ul style="list-style-type: none"> - before commencement of the reclamation works, the holder of Environmental Permit has to submit plans showing the phased construction of the reclamation, design and operation of the silt curtain. 						^
S5.8.4	<p>Site specific mitigation plan for reclamation areas using public fill materials should be submitted for EPD agreement before commencement of construction phase with due consideration of good site practices.</p>	<p>Control potential impacts from filling activities and marine based construction</p>	<p>CEDD's Contractors</p>	<p>Work site</p>	<p>Construction Phase</p>	<p>ProPECC PN 1/94, EIAOTM, WPCO</p>	<p>N/A</p>
ERR S5.6.1	<p>To minimize water quality impact arising from the dredging and filling works for Reclamation for Road P2, the following mitigation measures shall be implemented:</p> <ul style="list-style-type: none"> - Before carrying out any dredging and underwater filling works, a temporary barrier shall first be constructed to a height above the high water mark to completely enclose the works site (without any opening at the barrier wall) - The temporary barrier fully enclosing the dredging and underwater filling works site shall not be removed before completion of all dredging and underwater filling works. - Water quality sampling and testing shall be carried out to demonstrate that the water quality inside the enclosed barrier is comparable to the ambient or baseline levels prior to the removal of the fully enclosed barrier. - Silt curtains shall be deployed for the installation and removal of the temporary barrier and at the double water gates marine access opening during its operation. The general of arrangement of silt curtain is shown in Figure 7 of the existing Environmental Permit (No. EP-458/2013/C). 	<p>Control potential impacts from dredging and filling works for Reclamation for Road P2</p>	<p>CEDD's Contractors</p>	<p>Work site</p>	<p>Construction Phase</p>	<p>ProPECC PN 1/94, EIAOTM, WPCO</p>	<p>^ N/A N/A ^</p>

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
S5.8.5	It is important that appropriate measures are implemented to control runoff and drainage and prevent high loading of SS from entering the marine environment. Proper site management is essential to minimise surface water runoff, soil erosion and sewage effluents.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	^
S5.8.6	Any practical options for the diversion and realignment of drainage should comply with both engineering and environmental requirements in order to ensure adequate hydraulic capacity of all drains.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Design Stage and Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO, TM-DSS	# (6)
S5.8.7	Construction site runoff and drainage should be prevented or minimised in accordance with the guidelines stipulated in the EPD's Practice Note for Professional Persons, Construction Site Drainage (ProPECC PN 1/94). Good housekeeping and stormwater best management practices, as detailed in below, should be implemented to ensure that all construction runoff complies with WPCO standards and no unacceptable impact on the WSRs arises due to construction of the TKO-LT Tunnel. All discharges from the construction site should be controlled to comply with the standards for effluents discharged into the corresponding WCZ under the TM-DSS.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO, TM-DSS	*(7)
S5.8.8	Exposed soil areas should be minimised to reduce the potential for increased siltation, contamination of runoff, and erosion. Construction runoff related impacts associated with the above ground construction activities can be readily controlled through the use of appropriate mitigation measures which include: - use of sediment traps; and	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	N/A

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
	- adequate maintenance of drainage systems to prevent flooding and overflow.						*(7)
S5.8.9	Construction site should be provided with adequately designed perimeter channel and pretreatment facilities and proper maintenance. The boundaries of critical areas of earthworks should be marked and surrounded by dykes or embankments for flood protection. Temporary ditches should be provided to facilitate runoff discharge into the appropriate watercourses, via a silt retention pond. Permanent drainage channels should incorporate sediment basins or traps and baffles to enhance deposition rates. The design of efficient silt removal facilities should be based on the guidelines in Appendix A1 of ProPECC PN 1/94.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	* (8)
S5.8.10	Ideally, construction works should be programmed to minimise surface excavation works during the rainy season (April to September). All exposed earth areas should be completed as soon as possible after earthworks have been completed, or alternatively, within 14 days of the cessation of earthworks where practicable. If excavation of soil cannot be avoided during the rainy season, or at any time of year when rainstorms are likely, exposed slope surfaces should be covered by tarpaulin or other means.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	^
S5.8.11	Sedimentation tanks of sufficient capacity, constructed from pre-formed individual cells of approximately 6 to 8m ³ capacity, are recommended as a general mitigation measure which can be used for settling surface runoff prior to disposal. The system capacity is flexible and able to handle multiple inputs from a variety of sources and particularly suited to applications where the influent is pumped.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO S5	^
S5.8.12	Earthworks final surfaces should be well compacted and the subsequent permanent work or surface protection should be carried out immediately after the final surfaces are formed to prevent erosion caused by rainstorms. Appropriate drainage like intercepting channels should be provided where necessary.	Control potential impacts from construction site runoff and land-	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO S5	^

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
		based construction					
S5.8.13	Measures should be taken to minimize the ingress of rainwater into trenches. If excavation of trenches in wet seasons is necessary, they should be dug and backfilled in short sections. Rainwater pumped out from trenches or foundation excavations should be discharged into storm drains via silt removal facilities.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO S5	^
S5.8.14	Open stockpiles of construction materials (for examples, aggregates, sand and fill material) of more than 50m ³ should be covered with tarpaulin or similar fabric during rainstorms. Measures should be taken to prevent the washing away of construction materials, soil, silt or debris into any drainage system.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	^
S5.8.15	Manholes (including newly constructed ones) should always be adequately covered and temporarily sealed so as to prevent silt, construction materials or debris being washed into the drainage system and storm runoff being directed into foul sewers. Discharge of surface runoff into foul sewers must always be prevented in order not to unduly overload the foul sewerage system.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	* (9)
S5.8.16	Precautions to be taken at any time of year when rainstorms are likely, actions to be taken when a rainstorm is imminent or forecast, and actions to be taken during or after rainstorms are summarised in Appendix A2 of ProPECC PN 1/94. Particular attention should be paid to the control of silty surface runoff during storm events, especially for areas located near steep slopes.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	^

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
S5.8.17	Oil interceptors should be provided in the drainage system and regularly cleaned to prevent the release of oils and grease into the storm water drainage system after accidental spillages. The interceptor should have a bypass to prevent flushing during periods of heavy rain.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	N/A
S5.8.18	All vehicles and plant should be cleaned before leaving a construction site to ensure no earth, mud, debris and the like is deposited by them on roads. An adequately designed and located wheel washing bay should be provided at every site exit, and washwater should have sand and silt settled out and removed at least on a weekly basis to ensure the continued efficiency of the process. The section of access road leading to, and exiting from, the wheelwash bay to the public road should be paved with sufficient backfall toward the wheel-wash bay to prevent vehicle tracking of soil and silty water to public roads and drains.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	^
S5.8.19	Silt removal facilities, channels and manholes should be maintained and the deposited silt and grit should be removed regularly, at the onset of and after each rainstorm to ensure that these facilities are functioning properly at all times.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	^
S5.8.20	It is recommended that on-site drainage system should be installed prior to the commencement of other construction activities. Sediment traps should be installed in order to minimise the sediment loading of the effluent prior to discharge into foul sewers. There shall be no direct discharge of effluent from the site into the sea.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	^

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
S5.8.21	All temporary and permanent drainage pipes and culverts provided to facilitate runoff discharge should be adequately designed for the controlled release of storm flows. All sediment control measures should be regularly inspected and maintained to ensure proper and efficient operation at all times and particularly following rain storms. The temporarily diverted drainage should be reinstated to its original condition when the construction work has finished or the temporary diversion is no longer required.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	^
S5.8.22	All fuel tanks and storage areas should be provided with locks and be located on sealed areas, within bunds of a capacity equal to 110% of the storage capacity of the largest tank, to prevent spilled fuel oils from reaching the coastal waters.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	* (10)
S5.8.23	Minimum distances of 100m shall be maintained between the existing or planned stormwater discharges and the existing or planned seawater intakes during construction and operational phases	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	EIAO-TM, WPCO, TMDSS	^
S5.8.24	Under normal circumstances, groundwater pumped out of wells, etc. for the lowering of ground water level in basement or foundation construction, and groundwater seepage pumped out of tunnels or caverns under construction should be discharged into storm drains after the removal of silt in silt removal facilities.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	^
S5.8.25 - S5.8.27	Grouting would be adopted as measure to reduce the groundwater inflow into the tunnel. During the tunnel excavation, the inflow rate of groundwater into the tunnel will be measured	Control potential impacts from	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM,	N/A

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
<p>& Table 5.18</p>	<p>during the excavation. The groundwater levels above the tunnel will also be monitored by piezometers. If the inflow rate exceeds the pre-determined groundwater control criteria or the groundwater drawdown exceeds the required limit, pre-excavation grouting will be required to reduce the groundwater inflow. No significant change of groundwater levels would therefore be expected. Any chemicals/ foaming agents which would be entrained to the groundwater should be biodegradable and non-toxic throughout the tunnel construction. Potential groundwater quality impact would be minimal as the used material is non-toxic and biodegradable. No adverse groundwater quality would therefore be expected. Prescriptive measures in the form of an Action Plan with pre-emptive and re-active to preserve the groundwater levels at all times during the tunnel construction are set out in Table 5.18.</p>	<p>construction site runoff and land-based construction</p>				<p>WPCO, Buildings Ordinance</p>	
<p>S5.8.28</p>	<p>Water used in ground boring and drilling for site investigation or rock / soil anchoring should as far as practicable be recirculated after sedimentation. When there is a need for final disposal, the wastewater should be discharged into storm drains via silt removal facilities.</p>	<p>Control potential impacts from construction site runoff and land-based construction</p>	<p>CEDD's Contractors</p>	<p>Work site</p>	<p>Design Stage and Construction Phas</p>	<p>ProPECC PN 1/94, EIAOTM, WPCO</p>	<p>N/A</p>
<p>S5.8.29 - S5.8.31</p>	<p>Wastewater generated from the washing down of mixing trucks and drum mixers and similar equipment should whenever practicable be recycled. The discharge of wastewater should be kept to a minimum. To prevent pollution from wastewater overflow, the pump sump of any water recycling system should be provided with an online standby pump of adequate capacity and with automatic alternating devices. Under normal circumstances, surplus wastewater may be discharged into foul sewers after treatment in silt removal and pH adjustment facilities (to within the pH range of 6 to 10). Disposal of wastewater into storm drains will require more elaborate treatment.</p>	<p>Control potential impacts from construction site runoff and land-based construction</p>	<p>CEDD's Contractors</p>	<p>Work site</p>	<p>Construction Phase</p>	<p>ProPECC PN 1/94, EIAOTM, WPCO</p>	<p>^</p>

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
S5.8.32	All vehicles and plant should be cleaned before they leave a construction site to ensure no earth, mud, debris and the like is deposited by them on roads. A wheel washing bay should be provided at every site exit if practicable and wash-water should have sand and silt settled out or removed before discharging into storm drains. The section of construction road between the wheel washing bay and the public road should be paved with backfall to reduce vehicle tracking of soil and to prevent site run-off from entering public road drains.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	^
S5.8.33	Bentonite slurries used in diaphragm wall and borepile construction should be reconditioned and reused wherever practicable. If the disposal of a certain residual quantity cannot be avoided, the used slurry may be disposed of at the marine spoil grounds subject to obtaining a marine dumping licence from EPD on a case-by-case basis.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	N/A
S5.8.34	If the used bentonite slurry is intended to be disposed of through the public drainage system, it should be treated to the respective effluent standards applicable to foul sewer, storm drains or the receiving waters as set out in the WPCO Technical Memorandum on Effluent Standards.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	N/A
S5.8.35	Water used in water testing to check leakage of structures and pipes should be reused for other purposes as far as practicable. Surplus unpolluted water could be discharged into storm drains.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	N/A

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
S5.8.36	Sterilization is commonly accomplished by chlorination. Specific advice from EPD should be sought during the design stage of the works with regard to the disposal of the sterilizing water. The sterilizing water should be reused wherever practicable.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Design Stage and Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	N/A
S5.8.37	Before commencing any demolition works, all sewer and drainage connections should be sealed to prevent building debris, soil, sand etc. from entering public sewers/drains.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	N/A
S5.8.38	Wastewater generated from building construction activities including concreting, plastering, internal decoration, cleaning of works and similar activities should not be discharged into the stormwater drainage system. If the wastewater is to be discharged into foul sewers, it should undergo the removal of settleable solids in a silt removal facility, and pH adjustment as necessary	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	^
S5.8.39	Acidic wastewater generated from acid cleaning, etching, pickling and similar activities should be neutralized to within the pH range of 6 to 10 before discharging into foul sewers. If there is no public foul sewer in the vicinity, the neutralized wastewater should be tinkered off site for disposal into foul sewers or treated to a standard acceptable to storm drains and the receiving waters	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	^
S5.8.40	Wastewater collected from canteen kitchens, including that from basins, sinks and floor drains, should be discharged into foul sewer via grease traps capable of providing at least 20 minutes retention during peak flow.	Control potential impacts from construction site	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	N/A

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
		runoff and land-based construction					
S5.8.41	Drainage serving an open oil filling point should be connected to storm drains via a petrol interceptor with peak storm bypass.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	^
S5.8.42	Vehicle and plant servicing areas, vehicle wash bays and lubrication bays should as far as possible be located within roofed areas. The drainage in these covered areas should be connected to foul sewers via a petrol interceptor. Oil leakage or spillage should be contained and cleaned up immediately. Waste oil should be collected and stored for recycling or disposal in accordance with the Waste Disposal Ordinance.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	^
S5.8.43	Construction work force sewage discharges on site are expected to be connected to the existing trunk sewer or sewage treatment facilities. The construction sewage may need to be handled by portable chemical toilets prior to the commission of the on-site sewer system. Appropriate numbers of portable toilets shall be provided by a licensed contractor to serve the large number of construction workers over the construction site. The Contractor shall also be responsible for waste disposal and maintenance practices.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO	^
S5.8.44	Contractor must register as a chemical waste producer if chemical wastes would be produced from the construction activities. The Waste Disposal Ordinance (Cap 354) and its subsidiary regulations in particular the Waste Disposal (Chemical Waste) (General) Regulation should be observed and complied with for control of chemical wastes.	Control potential impacts from accidental spillage of chemicals	CEDD's Contractors	Work site	Construction Phase	EIAO-TM, WPCO, WDO	^

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
S5.8.45	Any service shop and maintenance facilities should be located on hard standings within a bunded area, and sumps and oil interceptors should be provided. Maintenance of vehicles and equipment involving activities with potential for leakage and spillage should only be undertaken within the areas appropriately equipped to control these discharges.	Control potential impacts from accidental spillage of chemicals	CEDD's Contractors	Work site	Construction Phase	EIAO-TM, WPCO	* (10)
S5.8.46	<p>Disposal of chemical wastes should be carried out in compliance with the Waste Disposal Ordinance. The "Code of Practice on the Packaging, Labelling and Storage of Chemical Wastes" published under the Waste Disposal Ordinance details the requirements to deal with chemical wastes. General requirements are given as follows:</p> <ul style="list-style-type: none"> - suitable containers should be used to hold the chemical wastes to avoid leakage or spillage during storage, handling and transport; - chemical waste containers should be suitably labelled, to notify and warn the personnel who are handling the wastes, to avoid accidents; and - storage area should be selected at a safe location on site and adequate space should be allocated to the storage area. 	Control potential impacts from accidental spillage of chemicals	CEDD's Contractors	Work site	Construction Phase	EIAO-TM, WPCO, WDO	* (11) ^ ^
S5.8.47	Collection and removal of floating refuse should be performed at regular intervals on a daily basis. The contractor should be responsible for keeping the water within the site boundary and the neighbouring water free from rubbish.	Control potential impacts from floating refuse and debris	CEDD's Contractors	Work site	Construction Phase	EIAO-TM, WPCO,	^
Ecological Impact							
S6.8.4	<p>Measures to Minimize Disturbance</p> <ul style="list-style-type: none"> - Use of Quiet Mechanical Plant during the construction phase should be adopted wherever possible. - Hoarding or fencing should be erected around the works area boundaries during the 	Minimize noise, human and traffic disturbance to terrestrial habitat	Design Team / Contractor	Land-based works are	Construction Phase	N/A	^ ^

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
	<p>construction phase. The hoarding would screen adjacent habitats from construction phase activities, reduce noise disturbance to these habitats and also to restrict access to habitats adjacent to works areas by site workers;</p> <ul style="list-style-type: none"> - Regular spraying of haul roads to minimize impacts of dust deposition on adjacent vegetation and habitats during the construction activities 	<p>and wildlife; and reduce dust generation</p>					^
S6.8.5	<p>Standard Good Site Practice</p> <ul style="list-style-type: none"> - Placement of equipment or stockpile in designated works areas and access routes selected on existing disturbed land to minimise disturbance to natural habitats. - Construction activities should be restricted to works areas that should be clearly demarcated. The works areas should be reinstated after completion of the works. - Waste skips should be provided to collect general refuse and construction wastes. The wastes should be properly disposed off-site in a timely manner. - General drainage arrangements should include sediment and oil traps to collect and control construction site run-off. - Open burning on works sites is illegal, and should be strictly prohibited. - Measures should also be put into place so that litter, fuel and solvents do not enter the nearby watercourses. 	<p>Reduce disturbance to surrounding habitats</p>	Contractor	Land-based works are	Construction Phase	N/A	^ ^ ^ ^ ^ ^
S6.8.6	<p>Measure to Minimize Groundwater Inflow</p> <ul style="list-style-type: none"> - The drained tunnel construction method with groundwater inflow control measures would generally be adopted. - During the tunnel excavation, pre-excavation grouting could be adopted to reduce the groundwater inflow and ensure that the tunnel would meet the long term water tightness requirements. 	<p>Minimize groundwater inflow</p>	Contractor	Tunnel	Construction Phase	N/A	N/A N/A

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
S6.8.8	<p><i>Measure to Minimize Impact on Corals</i></p> <p><u>Coral translocation</u></p> <ul style="list-style-type: none"> - It is recommended to translocate the affected coral colonies, except the locally common <i>Oulastrea crispata</i>, within the reclamation area and bridge footprint to the other suitable locations as far as practicable. - The coral translocation should be conducted during the winter months (November-March) in order to avoid disturbance during their spawning period (i.e. July to October). - A detailed coral translocation plan with a description on the methodology for pretranslocation coral survey, translocation methodology, identification/proposal of coral recipient site, monitoring methodology for posttranslocation should be prepared during the detailed design stage. - The coral translocation plan should be subject to approval by relevant authorities (e.g. EPD and AFCD) before commencement of the coral translocation. All the translocation exercises should be conducted by experienced marine ecologist(s) who is/are approved by AFCD prior to commencement of coral translocation. <p><u>Post translocation Monitoring</u></p> <ul style="list-style-type: none"> - A coral monitoring programme is recommended to assess any adverse and unacceptable impacts to the translocated coral communities - Information gathered during each posttranslocation monitoring survey should include observations on the presence, survival, health condition and growth of the translocated coral colonies. These parameters should then be compared with the baseline results collected from the pre-translocation survey. 	Minimize loss of coral	Design team, contractor, project operator	Within reclamation areas and pier footprint	Prior construction	N/A	<p>^</p> <p>^</p> <p>^</p> <p>^</p> <p>^</p> <p>^</p>

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
S6.8.9 S6.8.10	<p>Measure to Control Water Quality Impact</p> <ul style="list-style-type: none"> - Deployment of silt curtains around the active stone column installation points, opening of newly installed seawall and marine works area. - Diverting of the site runoff to silt trap facilities before discharging into storm drain; - Proper waste and dumping management; and - Standard good-site practice for land-based construction. 	Control water quality impact, especially on suspended solid level; minimize the contamination of wastewater discharge, accidental chemical spillage and construction site runoff to the receiving water bodies	Design Team, contractor	Marine and landbased works area	Construction phase	WQO	N/A ^ ^ ^
S6.8.11	<p>Compensation for Vegetation Loss</p> <ul style="list-style-type: none"> - Felling of mature trees should be compensated by planting of standard or heavy standard trees within or in vicinity of the affected area as far as practicable. Such compensatory planting for trees should be provided with at least a 1:1 ratio. In addition, vegetation at the temporarily affected area should be reinstated with species similar to the existing condition. 	Compensate for the vegetation loss	Design Team, contractor	Land-based works area	Construction phase	N/A	^
Fisheries Impact							
S7.7.3	<p>Measure to Control Water Quality Impact</p> <ul style="list-style-type: none"> - Deployment of silt curtains around the active stone column installation points, opening of 	Control water quality impact,	Design Team / Contractor	Marine work area	Construction phase	WQO	^

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
	newly installed seawall and marine works area.	especially on suspended solid level					
Waste Management (Construction Phase)							
S8.6.3	<p>Good Site Practices and Waste Reduction Measures</p> <ul style="list-style-type: none"> - Nomination of an approved person, such as a site manager, to be responsible for good site practices, arrangements for collection and effective disposal to an appropriate facility, of all wastes generated at the site; - Training of site personnel in site cleanliness, proper waste management and chemical handling procedures; - Provision of sufficient waste disposal points and regular collection of waste; - Appropriate measures to minimize windblown litter and dust during transportation of waste by either covering trucks or by transporting wastes in enclosed containers; and - Regular cleaning and maintenance programme for drainage systems, sumps and oil interceptors. 	To reduce waste management impacts	Contractor	All work sites	Construction Phase	Waste Disposal Ordinance (Cap. 354) Land (Miscellaneous Provisions) Ordinance (Cap. 28)	^ ^ ^ ^ * (7)
S8.6.4	<p>Good Site Practices and Waste Reduction Measures (con't)</p> <ul style="list-style-type: none"> - Segregation and storage of different types of waste in different containers, skips or stockpiles to enhance reuse or recycling of materials and their proper disposal; - Encourage collection of aluminium cans by providing separate labelled bins to enable this waste to be segregated from other general refuse generated by the workforce; - Proper storage and site practices to minimize the potential for damage or contamination of construction materials; and - Plan and stock construction materials carefully to minimize amount of waste generated 	To achieve waste reduction	Contractor	All work sites	Construction Phase	Waste Disposal Ordinance (Cap. 354) Land (Miscellaneous Provisions) Ordinance (Cap.	^ ^ ^ ^

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
	and avoid unnecessary generation of waste.					28)	
S8.6.5	<p>Good Site Practices and Waste Reduction Measures (con't)</p> <p>The Contractor shall prepare and implement a WMP as part of the EMP in accordance with ETWB TCW No. 19/2005 which describes the arrangements for avoidance, reuse, recovery, recycling, storage, collection, treatment and disposal of different categories of waste to be generated from the construction activities. Such a management plan should incorporate site specific factors, such as the designation of areas for segregation and temporary storage of reusable and recyclable materials. The EMP should be submitted to the Engineer for approval. The Contractor should implement the waste management practices in the EMP throughout the construction stage of the Project. The EMP should be reviewed regularly and updated by the Contractor.</p>	To achieve waste reduction	Contractor	All work sites	Construction Phase	ETWB TCW No. 19/2005	^
S8.6.6	<p>Good Site Practices and Waste Reduction Measures (con't)</p> <ul style="list-style-type: none"> - C&D materials would be reused in the project and other local concurrent projects as far as possible. 	To achieve waste reduction	Contractor	All work sites	Construction Phase	ETWB TCW No. 19/2005	^
S8.6.7	<p>Storage, Collection and Transportation of Waste</p> <p>Should any temporary storage or stockpiling of waste is required, recommendations to minimize the impacts include:</p> <ul style="list-style-type: none"> - Waste, such as soil, should be handled and stored well to ensure secure containment, thus minimizing the potential of pollution; - Maintain and clean storage areas routinely; - Stockpiling area should be provided with covers and water spraying system to prevent materials from wind-blown or being washed away; and - Different locations should be designated to stockpile each material to enhance reuse. 	To minimize potential adverse environmental impacts arising from waste storage	Contractor	All work sites	Construction Phase	-	^ * (12) ^ ^

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
S8.6.8	<p><i>Storage, Collection and Transportation of Waste (con't)</i></p> <ul style="list-style-type: none"> - Remove waste in timely manner; - Waste collectors should only collect wastes prescribed by their permits; - Impacts during transportation, such as dust and odour, should be mitigated by the use of covered trucks or in enclosed containers; - Obtain relevant waste disposal permits from the appropriate authorities, in accordance with the Waste Disposal Ordinance (Cap. 354), Waste Disposal (Charges for Disposal of Construction Waste) Regulation (Cap. 345) and the Land (Miscellaneous Provisions) Ordinance (Cap. 28); - Waste should be disposed of at licensed waste disposal facilities; and - Maintain records of quantities of waste generated, recycled and disposed. 	To minimize potential adverse environmental impacts arising from waste collection and disposal	Contractor	All work sites	Construction Phase		* (12) ^ ^ ^ ^ ^
S8.6.9	<p><i>Storage, Collection and Transportation of Waste (con't)</i></p> <ul style="list-style-type: none"> - Implementation of trip ticket system with reference to DEVB TC(W) No. 6/2010, Trip Ticket System for Disposal of Construction & Demolition Materials, to monitor disposal of waste and to control fly-tipping at PFRFs or landfills. A recording system for the amount of waste generated, recycled and disposed (including disposal sites) should be proposed. 	To minimize potential adverse environmental impacts arising from waste collection and disposal	Contractor	All work sites	Construction Phase	DEVB TCW No. 6/2010	^
S8.6.11 - S8.6.13	<p><i>Sorting of C&D Materials</i></p> <ul style="list-style-type: none"> - Sorting to be performed to recover the inert materials, reusable and recyclable materials before disposal off-site. - Specific areas shall be provided by the Contractors for sorting and to provide temporary storage areas for the sorted materials. 	To minimize potential adverse environmental	Contractor	All work sites	Construction Phase	DEVB TCW No. 6/2010 ETWB TCW No. 33/2002	^ ^

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
	<ul style="list-style-type: none"> - The C&D materials should at least be segregated into inert and non-inert materials, in which the inert portion could be reused and recycled in the reclamation as far as practicable before delivery to PFRFs. While opportunities for reusing the non-inert portion should be investigated before disposal of at designated landfills 					ETWB TCW No. 19/2005	^
<p>S8.6.15</p> <p>–</p> <p>S8.6.16</p>	<p>Sediments</p> <ul style="list-style-type: none"> - Sediment encountered may be reused as filling material on-site after cement stabilization. Cement-stabilization process is undertaken by mixing sediment and cement and will convert sediment to earth filling material. The treated sediment has to comply with Risk-Based Remediation Goals (RBRGs) before being reused in order not to raise any land contamination issue. The adoption of RBRGs to assess stabilized sediment has been proposed in the current C&DMMP. MFC has no adverse comment on the current C&DMMP. The sediment quality indicates that all sediments comply with most stringent RBRGs except for one sediment sample (TKO-EBH501 3-3.95m) with lead exceeding the RBRG. Except for the sediment sample (TKO-EBH501 3-3.95m), the chemical screening results do not indicate sediment as contaminated soil. It is anticipated that reuse of sediment except sediment sample (TKO-EBH501 3-3.95m) will not lead to land contamination. - Despite exceedance of RBRG, onsite reuse of sediment under sample (TKO-EBH501 33.95m) as filling material after cement stabilization is also a suitable treatment. Sediment quality indicates the sediment sample (TKO-EBH501 3-3.95m) exceed RBRG for lead. While cement stabilization will immobilize metal contaminants, it is capable to treat the exceedance on lead. The stabilized material should comply with UTS of Lead and UCS. If the treated material do not comply with UTS or UCS, re-stabilization have to 	To ensure the sediment to be disposed of in an authorized and least impacted way	contractor	All works areas with sediments concern	Construction Phase	RBRG	<p>N/A</p> <p>N/A</p>

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
	<p>be undertaken to meet compliance of UTS and UCS before reusing the treated sediment as filling material. However, further agreement on final disposal/treatment on sediment under sample (TKO-EBH501 3-3.95m) has to be sought from DEP</p>						
<p>S8.6.17 – S8.6.20</p>	<p>Sediments (con't)</p> <ul style="list-style-type: none"> - Requirements of the Air Pollution Control (Construction Dust) Regulation, where relevant, shall be adhered to during boring, excavation, transportation and disposal of sediments or cement stabilization of sediment. - A treatment area should be confined for carrying out the cement stabilization mixing and temporary stockpile. The area should be designed to prevent leachate from entering the ground. Leachate, if any, should be collected and discharged according to the Water Pollution Control Ordinance (WPCO). - In order to minimise the potential odour / dust emissions during boring, excavation and transportation of the sediment, the excavated sediments should be kept wet during excavation/boring and should be properly covered when placed on barges/trucks. Loading of the excavated sediment to the barge should be controlled to avoid splashing and overflowing of the sediment slurry to the surrounding water. - In order to minimise the exposure to contaminated materials, workers should, when necessary, wear appropriate personal protective equipments (PPE) when handling contaminated sediments. Adequate washing and cleaning facilities should also be provided on site. 	<p>To determine the best handling and treatment of sediment</p>	<p>Contractor</p>	<p>All works areas with sediments concern</p>	<p>Construction Phase</p>		<p>N/A N/A N/A N/A</p>
<p>S8.6.21</p>	<p>Sediments (con't)</p> <ul style="list-style-type: none"> - Alternatively, excavated sediment can be treated with marine disposal. The basic requirements and procedures for excavated sediment disposal specified under ETWB 	<p>To ensure the sediment to be disposed of in an</p>	<p>contractor</p>	<p>All works areas with sediments</p>	<p>Construction Phase</p>	<p>ETWB TC(W) No. 34/2002 & Dumping at Sea</p>	<p>N/A</p>

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
	TC(W) No. 34/2002 shall be followed. MFC is responsible for the provision and management of disposal capacity and facilities for the excavated sediment, while the permit of marine dumping is required under the Dumping at Sea Ordinance and is the responsibility of the DEP.	authorized and least impacted way		concern		Ordinance	
S8.6.23	<p>Sediments (con't)</p> <ul style="list-style-type: none"> - For allocation of sediment disposal sites and application of marine dumping permit, separate SSTP has to be submitted to EPD for agreement under DASO. Additional site investigation, based on the SSTP, maybe carried out in order to confirm the disposal arrangements for the proposed sediments removal. A Sediment Quality Report (SQR) shall then be required for EPD agreement under DASO prior to the tendering of the construction contract, discussing in details the site investigation, testing results as well as the delineation of each of the categories of excavated materials and the corresponding types of disposal. 	To determine the best handling and disposal option of sediment	Contractor	All works areas with sediments concern	Construction Phase	ETWB TC(W) No. 34/2002 & Dumping at Sea Ordinance	N/A
S8.6.24 - S8.6.28	<p>Sediments (con't)</p> <ul style="list-style-type: none"> - The excavated sediments is expected to be loaded onto the barge and transported to the designated disposal sites allocated by the MFC. The excavated sediment would be disposed of according to its determined disposal options and ETWB TC(W) No. 34/2002. - Stockpiling of contaminated sediments should be avoided as far as possible. If temporary stockpiling of contaminated sediments is necessary, the excavated sediment should be covered by tarpaulin and the area should be placed within earth bunds or sand bags to prevent leachate from entering the ground, nearby drains and surrounding water bodies. The stockpiling areas should be completely paved or covered by linings in order to avoid contamination to underlying soil or groundwater. Separate and clearly defined 	To ensure handling of sediments are in accordance to statutory requirements	Contractor	All works areas with sediments concern	Construction Phase	ETWB TC(W) No. 34/2002 & Dumping at Sea Ordinance	N/A N/A

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
	<p>areas should be provided for stockpiling of contaminated and uncontaminated materials. Leachate, if any, should be collected and discharged according to the Water Pollution Control Ordinance (WPCO).</p> <ul style="list-style-type: none"> - In order to minimise the potential odour / dust emissions during boring and transportation of the sediment, the excavated sediments should be kept wet during excavation/boring and should be properly covered when placed on barges. Loading of the excavated sediment to the barge should be controlled to avoid splashing and overflowing of the sediment slurry to the surrounding water. - The barge transporting the sediments to the designated disposal sites should be equipped with tight fitting seals to prevent leakage and should not be filled to a level that would cause overflow of materials or laden water during loading or transportation. In addition, monitoring of the barge loading shall be conducted to ensure that loss of material does not take place during transportation. Transport barges or vessels shall be equipped with automatic self-monitoring devices as specified by the DEP. - In order to minimise the exposure to contaminated materials, workers should, when necessary, wear appropriate personal protective equipments (PPE) when handling contaminated sediments. Adequate washing and cleaning facilities should also be provided on site. - Another possible arrangement for Type 3 disposal is by geosynthetic containment. A geosynthetic containment method is a method whereby the sediments are sealed in geosynthetic containers and, at the disposal site, the containers would be dropped into the designated contaminated mud pit where they would be covered by further mud disposal and later by the mud pit capping, thereby meeting the requirements for fully 						<p>N/A</p> <p>N/A</p> <p>N/A</p> <p>N/A</p>

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
	confined mud disposal.						
S8.6.26	<p>Chemical Wastes.</p> <ul style="list-style-type: none"> - If chemical wastes are produced at the construction site, the Contractor would be required to register with the EPD as a Chemical Waste Producer and to follow the guidelines stated in the Code of Practice on the Packaging, Labelling and Storage of Chemical Wastes. Good quality containers compatible with the chemical wastes should be used, and incompatible chemicals should be stored separately. Appropriate labels should be securely attached on each chemical waste container indicating the corresponding chemical characteristics of the chemical waste, such as explosive, flammable, oxidizing, irritant, toxic, harmful, corrosive, etc. The Contractor shall use a licensed collector to transport and dispose of the chemical wastes, to either the Chemical Waste Treatment Centre at Tsing Yi, or other licensed facility, in accordance with the Waste Disposal (Chemical Waste) (General) Regulation. 	To ensure proper management of chemical waste	Contractor	All works sites	Construction Phase	Code of Practice on the Packaging, Labelling and Storage of Chemical Wastes Waste Disposal (Chemical Waste) (General) Regulation	^
S8.6.27	<p>General Refuse</p> <ul style="list-style-type: none"> - General refuse should be stored in enclosed bins or compaction units separate from C&D material. A reputable waste collector should be employed by the contractor to remove general refuse from the site, separately from C&D material. Preferably an enclosed and covered area should be provided to reduce the occurrence of 'wind blown' light material. 	To ensure proper management of general refuse	Contractor	All works sites	Construction Phase	Public Health and Municipal Services Ordinance (Cap. 132)	^
Impact on Cultural Heritage (Construction Phase)							
S9.6.4	<p>Dust and visual impacts</p> <ul style="list-style-type: none"> - Temporarily fenced off buffer zone with allowance for public access (minimum 1 m) should be provided; - The open yard in front of the temple should be kept as usual for annual Tin Hau festival; 	To prevent dust and visual impacts	Contractors	Work areas	Construction Phase	EIAO; GCHIA; AMO	* (13) ^

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
	<ul style="list-style-type: none"> - Monitoring of vibration impacts should be conducted when the construction works are less than 100m from the temple. 						^
S9.6.4	Indirect vibration impact <ul style="list-style-type: none"> - Vibration level is suggest to be controlled within a peak particle velocity (ppv) limit of 5mm/s measured inside the historical buildings; - Monitoring of vibration should be carried out during construction phase. - Tilting and settlement monitoring should will be applied on the Cha Kwo Ling Tin Hau Temple as well. - A proposal with details for the mitigation measures and monitoring of impacts on built heritage shall be submitted to AMO for comments before commencement of work. 	To prevent indirect vibration impact	Contractors	Work areas	Construction Phase	Vibration Limits on Heritage Buildings by CEDD; GCHIA; AMO.	^ ^ ^ ^
<i>Landscape and Visual Impact (Construction Phase)</i>							
Table 10.8.1	CM1 - Construction area and contractor's temporary works areas to be minimised to avoid impacts on adjacent landscape.	Avoid impact on adjacent landscape areas	CEDD (via Contractor)	General	Construction planning and during construction period	N/A	^
Table 10.8.1	CM2 - Reduction of construction period to practical minimum.	Minimise duration of impact	CEDD (via Contractor)	N/A	Construction planning	N/A	^
Table 10.8.1	CM3 - Topsoil, where the soil material meets acceptable criteria and where practical, to be stripped and stored for re-use in the construction of the soft landscape works. The Contract Specification shall include storage and reuse of topsoil as appropriate.	To allow re-use of topsoil	CEDD (via Contractor)	General	Site clearance	As per the Particular Specification	^
Table 10.8.1	CM4 - Existing trees at boundary of site and retained trees within site boundary to be carefully protected during construction. Detailed Tree Protection Specification shall be provided in the	To minimize tree loss	CEDD (via Contractor)	As per approved	Site clearance and	ETWB TC 3/2006 and as per tree	# (14)

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
	Contract Specification, under which the Contractor shall be required to submit, for approval, a detailed working method statement for the protection of trees prior to undertaking any works adjacent to all retained trees, including trees in contractor's works areas. (Tree protection measures will be detailed at Tree Removal Application stage).			Tree Removal Application(s)	throughout construction period	protection measures in Particular Specification	
Table 10.8.1	CM5 - Trees unavoidably affected by the works shall be transplanted where practicable. Where possible, trees should be transplanted direct to permanent locations rather than temporary holding nurseries. A detailed tree transplanting specification shall be provided in the Contract Specification and sufficient time for preparation shall be allowed in the construction programme.	To maximize preservation of existing trees	CEDD (via Contractor)	As per approved Tree Removal Application(s)	Site clearance	ETWB TC 3/2006 and as per tree protection measures in Particular Specification	^
Table 10.8.1	CM6 - Advance screen planting of fast growing tree and shrub species to noise barriers and hoardings. Trees shall be capable of reaching a height >10m within 10 years.	To maximize screening of the works	CEDD (via Contractor)	At Lam Tin Interchange and edge of Road P2 landscape deck, TKO	Beginning of construction period	N/A	^
Table 10.8.1	CM7 - Hydroseeding or sheeting of soil stockpiles with visually unobtrusive material	To reduce visual intrusion	CEDD (via Contractor)	General	Throughout construction period	As per Particular Specification	N/A
Table 10.8.1	CM8 - Control of night-time lighting by hooding all lights and through minimisation of night working periods.	To reduce visual intrusion	CEDD (via Contractor)	General	Throughout construction period	N/A	^
Table	CM9 - Screening of works areas with hoardings with appropriate colours compatible with the	Reduction of visual	CEDD (via	Project site	Excretion of	N/A	^

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
10.8.1	surrounding area	intrusion	Contractor)	Boundary	site hoarding		
Table 10.8.1	CM10 - Avoidance of excessive height and bulk of site buildings and structure	Reduction of visual intrusion and integration with environment	CEDD (via Contractor)	Built structures	Design and construction stage	N/A	^
Table 10.8.1	CM11 - Limitation of run-off into freshwater streams, ponds and sea areas	Avoidance of contamination of water courses and water bodie	CEDD (via Contractor)	TKO reclamation, TKO tunnel portal, Cha Kwo Ling roadworks	Throughout construction period	N/A	^
Table 10.8.1	CM12 - Minimise area of reclamation and design the edges sensitively to tie in with adjacent coastline characte	Minimise loss of Junk Bay and integration with existing coastlin	CEDD (via Contractor)	Temporary reclamation for barging points at TKO and Lam Tin and permanent reclamation for TKO Interchange slip roads and Road P2	Construction planning and reclamation stages	N/A	N/A

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
Landfill Gas Hazard (Design and Construction Phase)							
S11.5.9	<p>A Safety Officer, trained in the use of gas detection equipment and landfill gas-related hazards, should be present on site throughout the groundworks phase. The Safety Officer should be provided with an intrinsically safe portable instrument, which is appropriately calibrated and able to measure the following gases in the ranges indicated below:</p> <p>Methane 0-100% LEL and 0100% v/v</p> <p>Carbon dioxide 0-100%</p> <p>Oxygen 0-21%</p>	Protect the workers from landfill gas hazards	Contractor	Project sites within the Sai Tso Wan Landfill Consultation Zone	Construction phase	EPD's Landfill Gas Hazard Assessment Guidance Note	^
S11.5.10 S11.5.25	<p>Safety Measures</p> <ul style="list-style-type: none"> - For staff who work in, or have responsibility for “at risk” area, such as all excavation workers, supervisors and engineers working within the Consultation Zone, should receive appropriate training on working in areas susceptible to landfill gas, fire and explosion hazards. - An excavation procedure or code of practice to minimize landfill gas related risk should be devised and carried out. - No worker should be allowed to work alone at any time in or near to any excavation. At least one other worker should be available to assist with a rescue if needed. - Smoking, naked flames and all other sources of ignition should be prohibited within 15m of any excavation or ground-level confined space. “No smoking” and “No naked flame” notices should be posted prominently on the construction site and, if necessary, special areas should be designed for smoking. - Welding, flame-cutting or other hot works should be confined to open areas at least 15m 	Protect the workers from landfill gas hazards	Contractor	Project sites within the Sai Tso Wan Landfill Consultation Zone	Construction phase	EPD's Landfill Gas Hazard Assessment Guidance Note Labour Department's Code of Practice for Safety and Health at Work in Confined Space	N/A N/A

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
	<p>from any trench or excavation.</p> <ul style="list-style-type: none"> - Welding, flame-cutting or other hot works may only be carried out in trenches or confined spaces when controlled by a “permit to work” procedure, properly authorized by the Safety Officer (or, in the case of small developments, other appropriately qualified person). - The permit to work procedure should set down clearly the requirements for continuous monitoring for methane, carbon dioxide and oxygen throughout the period during which the hot works are in progress. The procedure should also require the presence of an appropriately qualified person, in attendance outside the 'confined area', who should be responsible for reviewing the gas measurements as they are made, and who should have executive responsibility for suspending the work in the event of unacceptable or hazardous conditions. Only those workers who are appropriately trained and fully aware of the potentially hazardous conditions which may arise should be permitted to carry out hot works in confined areas. - Where there are any temporary site offices, or any other buildings located within the Sai Tso Wan Landfill Consultation Zone which have enclosed spaces with the capacity to accumulate landfill gas, then they should either be located in an area which has been proven to be free of landfill gas (by survey using portable gas detectors); or be raised clear of the ground by a minimum of 500mm. This aims to create a clear void under the structure which is ventilated by natural air movement such that emission of gas from the ground are mixed and diluted by air. - Any electrical equipment, such as motors and extension cords, should be intrinsically safe. During piping assembly or conduiting construction, all valves/seals should be closed 						<p>N/A</p> <p>N/A</p> <p>N/A</p> <p>N/A</p>

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
	<p>immediately after installation. As construction progresses, all valves/seals should be closed to prevent the migration of gases through the pipeline/conduit. All piping /conducting should be capped at the end of each working day.</p> <ul style="list-style-type: none"> - During construction, adequate fire extinguishing equipment, fire-resistant clothing and breathing apparatus (BA) sets should be made available on site. - Fire drills should be organized at not less than six monthly intervals. - The contractor should formulate a health and safety policy, standards and instructions for site personnel to follow. - All personnel who work on the site and all visitors to the site should be made aware of the possibility of ignition of gas in the vicinity of excavations. Safety notices (in Chinese and English) should be posted at prominent position around the site warning danger of the potential hazards. - Service runs within the Consultation Zone should be designated as “special routes”; utilities companies should be informed of this and precautionary measures should be implemented. Precautionary measures should include ensuring that staff members are aware of the potential hazards of working in confined spaces such as manholes and service chambers, and that appropriate monitoring procedures are in place to prevent hazards due to asphyxiating atmospheres in confined spaces. Detailed guidance on entry into confined spaces is given in Code of Practice on Safety and Health at Work in Confined Spaces (Labour Department, Hong Kong). - Periodically during ground-works construction within the 250m Consultation Zone, the works area should be monitored for methane, carbon dioxide and oxygen using appropriately calibrated portable gas detection equipment. The monitoring frequency 						<p>N/A</p> <p>N/A</p> <p>N/A</p> <p>N/A</p> <p>N/A</p> <p>N/A</p>

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
	and areas to be monitored should be set down prior to commencement of ground-works either by the Safety Officer or an approved and appropriately qualified person.						
<p>S11.5.26</p> <p>-</p> <p>S11.5.31</p>	<p>Monitoring</p> <ul style="list-style-type: none"> ● Routine monitoring should be carried out in all excavations, manholes, chambers, relocation of monitoring wells and any other confined spaces that may have been created. All measurements in excavations should be made with the extended monitoring tube located not more than 10 mm from the exposed ground surface. Monitoring should be performed properly to make sure that the area is free of landfill gas before any man enters into the area. ● For excavations deeper than 1m, measurements should be carried out: <ul style="list-style-type: none"> - at the ground surface before excavation commences;- - immediately before any worker enters the excavation; - at the beginning of each working day for the entire period the excavation remains open; and - periodically throughout the working day whilst workers are in the excavation. ● For excavations between 300mm and 1m deep, measurements should be carried out: <ul style="list-style-type: none"> - directly after the excavation has been completed; and - periodically whilst the excavation remains open. ● For excavations less than 300mm deep, monitoring may be omitted, at the discretion of the Safety Officer or other appropriately qualified person. ● Depending on the results of the measurements, actions required will vary and should be set down by the Safety Officer or other appropriately qualified person. ● The exact frequency of monitoring should be determined prior to the commencement of 	<p>Protect the workers from landfill gas hazards</p>	<p>Contractor</p>	<p>Project sites within the Sai Tso Wan Landfill Consultation Zone</p>	<p>Construction phase</p>	<p>EPD's Landfill Gas Hazard Assessment Guidance Note</p>	<p>^</p> <p>^</p> <p>^</p> <p>^</p> <p>^</p>

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

EIA Ref.	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	Status
	works, but should be at least once per day, and be carried out by a suitably qualified or qualified person before starting the work of the day. Measurements shall be recorded and kept as a record of safe working conditions with copies of the site diary and submitted to the Engineer for approval. The Contractor may elect to carry out monitoring via an automated monitoring system.						
S11.5.32	The hazards from landfill gas during the construction stage within the Sai Tso Wan Landfill Consultation Zone should be minimized by suitable precautionary measures recommended in Chapter 8 of the Landfill Gas Hazard Assessment Guidance Note.	construction stage within the Sai Tso Wan Protect the workers from landfill gas hazards	Contractor	Project sites within the Sai Tso Wan Landfill Consultation Zone	Construction phase	EPD's Landfill Gas Hazard Assessment Guidance Note	N/A

Table II - Observations/reminders/non-compliance made during Site Audit

- Key:**
- * Observation/reminder was made during site audit but improved/rectified by the contractor.
 - # Observation/reminder was made during site audit but not yet improved/rectified by the contractor.
 - X Non-compliance of mitigation measure
 - Non-compliance but rectified by the contractor

Status / Remark	EIA Ref.	Recommended Mitigation Measures	Contract No.	Contractor	Work Sites	Details of Observation/Reminder
Air Quality Impact						
* (1)	S3.8.1 S3.8.7	Watering eight times a day on active works areas, exposed areas and paved haul roads Dust suppression measures stipulated in the Air Pollution Control (Construction Dust) Regulation and good site practices: - Use of regular watering to reduce dust emissions from exposed site surfaces and unpaved roads, particularly during dry weather. - Use of frequent watering for particularly dusty construction areas and areas close to ASRs.	NE/2015/01	Leighton – China State JV	Site Formation of TKO Portal	To provide frequent water spray for TKO slope to prevent dust generation.
* (2)	S3.8.7	Dust suppression measures stipulated in the Air Pollution Control (Construction Dust) Regulation and good site practices: - Side enclosure and covering of any aggregate or dusty material storage piles to reduce emissions. Where this is not practicable owing to frequent usage, watering shall be applied to aggregate fines.	NE/2015/01	Leighton – China State JV	Site Formation of TKO Portal	Grouting equipment in TKO observed without proper enclosure. The Contractor is reminded to provide top and 3-side enclosure.
* (3)	S3.8.7	Dust suppression measures stipulated in the Air Pollution Control (Construction Dust) Regulation and good site practices: - Open stockpiles shall be avoided or covered. Where possible, prevent placing dusty material storage piles near ASRs.	NE/2015/02	CRBC – Build King JV	Construction of Road P2	To cover the stockpile of dusty material by tarpaulin sheet properly.
* (4)	S3.8.7	Dust suppression measures stipulated in the Air Pollution Control (Construction Dust) Regulation and good site practices:	NE/2015/02	CRBC – Build King JV	Construction of Road P2	To remove the dusty used cement bags.

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

Status / Remark	EIA Ref.	Recommended Mitigation Measures	Contract No.	Contractor	Work Sites	Details of Observation/Reminder
		- Every stock of more than 20 bags of cement or dry pulverised fuel ash (PFA) should be covered entirely by impervious sheeting or placed in an area sheltered on the top and the 3 sides.				
Noise Impact (Construction Phase)						
* (5)	S4.8	Use of quiet PME. Use of movable noise barriers for Excavator, Lorry, Dump Truck, Mobile Crane, Compactor, Concrete Mixer Truck, Concrete Lorry Mixer, Breaker, Mobile Crusher, Backhoe, Vibratory Poker, Saw, Asphalt Paver, Vibratory Roller, Vibrolance, Hydraulic Vibratory Lance and Piling (Vibration Hammer). Use of full enclosure for Air Compressor, Compressor, Bar Bender, Generator, Drilling Rig, Chisel, Large Diameter Bore Piling, Grout Mixer & Pump and Concrete Pump.	NE/2015/02	CRBC – Build King JV	Construction of Road P2	To provide proper acoustic material for enclosing the breaker head.
Water Quality Impact (Construction Phase) / Waste Management (Construction Phase)						
# (6)	S5.8.6	Any practical options for the diversion and realignment of drainage should comply with both engineering and environmental requirements in order to ensure adequate hydraulic capacity of all drains.	NE/2015/01	Leighton – China State JV	Construction of Lam Tin Interchange	To set up proper drainage system in CKL site Portion 3.
* (7)	S5.8.7 / S5.8.8 / S8.6.3	Construction site runoff and drainage should be prevented or minimised in accordance with the guidelines stipulated in the EPD's Practice Note for Professional Persons, Construction Site Drainage (ProPECC PN 1/94). Good housekeeping and stormwater best management practices, as detailed in below, should be implemented to ensure that all construction runoff complies with WPCO standards and no unacceptable impact on the WSRs arises due to construction of the TKO-LT Tunnel. All discharges from the construction site should be controlled to comply with the standards for effluents discharged into the corresponding WCZ under the TM-DSS. Exposed soil areas should be minimised to reduce the potential for increased	NE/2015/01	Leighton – China State JV	Construction of Lam Tin Interchange	To remove the construction waste in U-channel
			NE/2015/02	CRBC – Build King JV	Construction of Road P2	To remove the accumulated sediments in the U-channels

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

Status / Remark	EIA Ref.	Recommended Mitigation Measures	Contract No.	Contractor	Work Sites	Details of Observation/Reminder
		<p>siltation, contamination of runoff, and erosion. Construction runoff related impacts associated with the above ground construction activities can be readily controlled through the use of appropriate mitigation measures which include:</p> <ul style="list-style-type: none"> - adequate maintenance of drainage systems to prevent flooding and overflow. <p>Good Site Practices and Waste Reduction Measures</p> <ul style="list-style-type: none"> - Regular cleaning and maintenance programme for drainage systems, sumps and oil interceptors. 				
* (8)	S5.8.9	<p>Construction site should be provided with adequately designed perimeter channel and pretreatment facilities and proper maintenance. The boundaries of critical areas of earthworks should be marked and surrounded by dykes or embankments for flood protection. Temporary ditches should be provided to facilitate runoff discharge into the appropriate watercourses, via a silt retention pond. Permanent drainage channels should incorporate sediment basins or traps and baffles to enhance deposition rates. The design of efficient silt removal facilities should be based on the guidelines in Appendix A1 of ProPECC PN 1/94.</p>	NE/2015/01	Leighton – China State JV	Construction of Lam Tin Interchange	Muddy water observed without proper containment in TKO. The Contractor is reminded to provide bunds or containment pit to prevent muddy water flow out of site.
* (9)	S5.8.15	<p>Manholes (including newly constructed ones) should always be adequately covered and temporarily sealed so as to prevent silt, construction materials or debris being washed into the drainage system and storm runoff being directed into foul sewers. Discharge of surface run-off into foul sewers must always be prevented in order not to unduly overload the foul sewerage system.</p>	NE/2015/01	Leighton – China State JV	Construction of Lam Tin Interchange	To cover or seal the gaps of covers of catchpit in Portion 1 to prevent silt water or oil stain flow out of site.
			NE/2015/02	CRBC – Build King JV	Construction of Road P2	To repair the holes near the discharge point in Area A to prevent surface runoff flow into the discharge point.
* (10)	S5.8.22/	All fuel tanks and storage areas should be provided with locks and be located	NE/2015/01	Leighton –	Construction of	To provide drip tray to chemical containers

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

Status / Remark	EIA Ref.	Recommended Mitigation Measures	Contract No.	Contractor	Work Sites	Details of Observation/Reminder
	S5.8.45	<p>on sealed areas, within bunds of a capacity equal to 110% of the storage capacity of the largest tank, to prevent spilled fuel oils from reaching the coastal waters.</p> <p>Any service shop and maintenance facilities should be located on hard standings within a bunded area, and sumps and oil interceptors should be provided. Maintenance of vehicles and equipment involving activities with potential for leakage and spillage should only be undertaken within the areas appropriately equipped to control these discharges.</p>	NE/2015/02	China State JV CRBC – Build King JV	Lam Tin Interchange Construction of Road P2	To provide drip tray to chemical containers
* (11)	S5.8.46	<p>Disposal of chemical wastes should be carried out in compliance with the Waste Disposal Ordinance. The “Code of Practice on the Packaging, Labelling and Storage of Chemical Wastes” published under the Waste Disposal Ordinance details the requirements to deal with chemical wastes. General requirements are given as follows:</p> <ul style="list-style-type: none"> - suitable containers should be used to hold the chemical wastes to avoid leakage or spillage during storage, handling and transport; 	NE/2015/01	Leighton – China State JV	Construction of Lam Tin Interchange	Oil stain observed in unpaved excavation area of Portion 3 and paved ground of Portion 1. The Contractor is reminded to properly remove the oil stain as “chemical waste”.
* (12)	S8.6.7 / S8.6.8	<p>Storage, Collection and Transportation of Waste</p> <p>Should any temporary storage or stockpiling of waste is required, recommendations to minimize the impacts include:</p> <ul style="list-style-type: none"> - Maintain and clean storage areas routinely; <p>Storage, Collection and Transportation of Waste (con’t)</p> <ul style="list-style-type: none"> - Remove waste in timely manner; 	NE/2015/02	CRBC – Build King JV	Construction of Road P2	To remove the accumulation of C&D waste and general refuse regularly in Portion 8. Empty chemical containers should be separated with other C&D waste and be treated as “chemical waste”.
Impact on Cultural Heritage (Construction Phase)						
* (13)	S9.6.4	<p>Dust and visual impacts</p> <ul style="list-style-type: none"> - Temporarily fenced off buffer zone with allowance for public access 	NE/2015/01	Leighton – China State JV	Construction of Lam Tin	To properly set up fenced-off buffer zone around Tin Hau Temple.

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

April 2017

Status / Remark	EIA Ref.	Recommended Mitigation Measures	Contract No.	Contractor	Work Sites	Details of Observation/Reminder
		(minimum 1 m) should be provided;			Interchange	
<i>Landscape and Visual Impact (Construction Phase)</i>						
# (14)	Table 10.8.1	CM4 - Existing trees at boundary of site and retained trees within site boundary to be carefully protected during construction. Detailed Tree Protection Specification shall be provided in the Contract Specification, under which the Contractor shall be required to submit, for approval, a detailed working method statement for the protection of trees prior to undertaking any works adjacent to all retained trees, including trees in contractor's works areas. (Tree protection measures will be detailed at Tree Removal Application stage).	NE/2015/01	Leighton – China State JV	Site Formation of TKO Portal and Construction of Lam Tin Interchange	To set-up tree protection zone for retained tree in TKO slope and in Cha Kwo Ling Site.

**APPENDIX O
SUMMARIES OF ENVIRONMENTAL
COMPLAINT, WARNING, SUMMON
AND NOTIFICATION OF SUCCESSFUL
PROSECUTION**

Appendix O - Cumulative Log for Complaints, Notifications of Summons and Successful Prosecutions

Cumulative Complaint Log for Tseung Kwan O - Lam Tin Tunnel

Complaint No.	Received Date	Date/Location of Complaint	Complainant	Details of Complaint	Investigation/ Mitigation Action	File Closed
1	7 th December 2016	Not Specified / construction of Lam Tin Interchange	Resident of Yau Lai Estate Bik Lai House	The complainant complained about the construction noise and dust near Yau Lai Estate. (EPD Reference No.: K15/RE/00032001-16)	<p>According to information provided by the Contractor, powered Mechanical Equipment being operated for construction of Lam Tin Interchange on 7 and 9 December 2016 include breaker, dump truck, backhoes, drilling rig and small bulldozer. They were operated on and off with some idling time. It is considered that noise nuisance during the time of complaint was mainly due to high noise level emission during the use of breaker for rock breaking.</p> <p>The Contractors had implemented environmental mitigation measures in accordance with the “Implementation Schedule of Proposed Mitigation Measures” of EM&A Manual to reduce construction dust and noise nuisance to the vicinity.</p>	Closed
2	9 th December 2016	Not Specified / construction of Lam Tin Interchange	Resident of Yau Lai Estate Block A Nga Lai House	The complainant complained about the construction noise near Yau Lai Estate. (EPD Reference No.: K15/RE/00032317-16)	<p>According to the regular air quality monitoring conducted at Air Quality Monitoring Stations AM3, no Action or Limit Level Exceedance was recorded from 6 – 14 December 2016. Similarly, no Limit Level Exceedance was recorded at Noise Monitoring Station CM1, Station CM2 and Station CM3 from 6 – 16 December 2016. With the implementation of environmental mitigation measures by Contractor on site, it is considered that no adverse air quality and noise impact was brought to the nearby sensitive receivers by the works of this Project.</p>	Closed
3	9 th December 2016	Not Specified / Construction of Road P2	Sai Kung District Committee Member Mr. Chan Kai Wai	The complainant complained about the noise nuisance during transportation of construction materials on haul road and dust generation during construction activities.	<p>No construction activities were carried out for both construction of Road P2 and TKO portal during night time or at about 7am. Therefore, no construction noise nuisance were generated during night-time or at about 7am under this Project and it is considered that these noise nuisance is not project-related.</p> <p>The Contractors of this Project had implemented environmental mitigation measures for air quality, noise and visual impact (night-time lighting) in accordance with the “Implementation Schedule of Proposed Mitigation Measures” of EM&A Manual.</p>	Closed
4	20 th December 2016	Not Specified / Construction of Road P2	Resident of Ocean Shore	The complainant complained about the lighting and noise nuisance on construction vessels moored near Ocean Shores during night time.	<p>The Contractors had taken the initiative to provide additional noise</p>	Closed

Complaint No.	Received Date	Date/Location of Complaint	Complainant	Details of Complaint	Investigation/ Mitigation Action	File Closed
5	22 nd December 2016	21 Dec 2016 at night / Construction of TKO portal	Resident of Block 3, Ocean Shores	The complainant concerned the noise generated by the construction works at hillside near Block 3 of Ocean Shores in daytime.	<p>mitigation measures to works since the complaints were received including:</p> <ul style="list-style-type: none"> - Temporary noise barrier had been installed to reduce noise nuisance from piling works in construction of Road P2 Provision of noise enclosure to cover generators for reducing its noise nuisance in TKO portal; and - Provision of portable noise enclosures at breakers and generators to reduce noise emission from works in TKO portal <p>According to the regular air quality and noise monitoring for this Project, no Action or Limit Level Exceedance was recorded in December 2016. With the implementation of environmental mitigation measures by Contractors on site, it is considered that no adverse air quality and noise impact was brought to the nearby sensitive receivers by the works of this Project.</p> <p>According to the ET's ad-hoc site inspection during night-time, no unacceptable noise nuisance from this Project was heard. No strong light emission from all the construction vessels near Ocean Shores was observed yet minimum lighting for marine safety purpose was observed from the construction vessel and anchors.</p> <p>According to the findings of investigation, minimum lighting on the construction vessel was required for guard watching the works site. Adverse night-time light and noise nuisance from the marine works area near Ocean Shores as alleged by the complainant are considered not caused by this Project.</p> <p>The Contractor had continuously implemented environmental mitigation measures in accordance with the "Implementation Schedule of Proposed Mitigation Measures" of EM&A Manual. To avoid strong light emission towards the sensitive receivers, night-time lighting is properly controlled by hooding all lights (except necessary lighting for safety purpose and guard watching);</p> <p>According to the ET's ad-hoc site inspection during night-time, no unacceptable noise nuisance from this Project was heard. No strong light emission from all the construction vessels near Ocean Shores was observed yet minimum lighting for marine safety and guard watching</p>	Closed
6	22 nd December 2016	Not specified / Construction of TKO portal	Public	The complainant complained about the noise generated by the construction works at hillside in daytime.		Closed
7	22 nd December 2016	Not specified / Construction of Road P2	Resident from Ocean Shore	The complainant complained about the noise nuisance of broadcast on construction vessel near Ocean Shores at 7am and the noise generated by the construction works outside Tseung Kwan O Chinese Permanent Cemetery.		Closed
8	22 nd December 2016	Not specified / Construction of Road P2 and TKO portal	Resident from Ocean Shore	The complainant complained about the noise nuisance generated by construction works of Tseung Kwan O portal in daytime and noise nuisance of "loud speaker" on construction vessel near Ocean Shores.		Closed
9	16 th December 2016	Not Specified / near Ocean Shores	DC member	The complainant complained that they noticed about 2 work vessels were being used at 00:00-01:00 and also moored there overnight which caused light pollution and affecting the residents.		
10	17 th January 2017	5 January 2017 / near Ocean Shores	DC member	The complainant complained that marine vessels were used at about 22:00 and around 01:00 on 5 Jan 2017, again causing noise and light nuisance to the residents.		

Complaint No.	Received Date	Date/Location of Complaint	Complainant	Details of Complaint	Investigation/ Mitigation Action	File Closed
					purpose was observed from the construction vessel and anchors. The Contractor was recommended to continuously implement the following visual impact mitigation measures: <ul style="list-style-type: none"> necessary lighting on construction vessels should be oriented as much as possible such that direct strong lighting towards the sensitive receivers is avoided. Strong lighting that may be in intermittent use should be shut down between works periods 	
11	23 rd December 2016	Not Specified / near Cha Kwo Ling Tsuen	Cha Kwo Ling Tsuen	The complainant complaint about the Soil/muddy water from construction site near Cha Kwo Ling Tsuen. (EPD Reference No.: K15/RE/00033951-16)	No construction works were being carried out on 23 rd December 2016 at Portion WA1, which is the site portion near Cha Kwo Ling Tsuen. Despite, it was recorded that some muddy water was flowing from the Contractor's wheel washing facility to the gullies within the site boundary.	Closed
12	29 th December 2016	23 rd December 2016 / near Cha Kwo Ling Tsuen	Cha Kwo Ling Tsuen	The complainant complaint that some muddy water flowing from the wheel washing facility to the gullies within the site boundary.	For complaint of muddy water on 23 rd December 2016, the Contractor has fixed the clear water hose for wheel washing on 24 th December 2016 early morning. During the recent weekly site inspections to Site Portion WA1, no muddy water was observed leaked out of the Site Boundary.	Closed
13	6 th January 2017	Not Specified / construction of Lam Tin Interchange	Resident of Yau Lai Estate Block A Nga Lai House	The complainant complained about the noise nuisance during rock breaking at the Eastern Harbour Crossing (EHC) portal and lack of noise mitigation measures during the construction works.	After investigation, it was found out that necessary rock breaking works by hydraulic or pneumatic breakers was conducted during excavation for tunnel adit at Lam Tin Interchange. Noise nuisance from the works area is considered due to the high noise level emission during use of hydraulic or pneumatic breakers. The Contractor had implemented environmental mitigation measures in accordance with the "Implementation Schedule of Proposed Mitigation Measures" of EM&A Manual as below:	Closed
14	6 th January 2017	Not Specified / Cha Kwo Ling Road	Resident of Yau Lai Estate	The complainant complained about the noise nuisance generated by the excavation works at Cha Kwo Ling Road on 6 January 2017 just after 7 a.m.	<u>Air Quality</u> Use of frequent watering during construction of Lam Tin Interchange, including watering of eight times a day on active work area, exposed area and paved haul roads to mitigate air quality impacts to the nearby Air Sensitive Receivers (ASRs)	Closed
15	6 th January 2017	Not Specified / Construction site near Yau Lai Estate	Resident of Yau Lai Estate Bik Lai House	The complainant complained about the noise nuisance during the construction works near Yau Lai Estate at 7:15am. He requested to erect noise barriers and set up water spraying	<u>Noise</u> <ul style="list-style-type: none"> Provision of portable noise enclosures to head of breakers to reduce noise emission during rock breaking works in Lam Tin Interchange; 	Closed

Complaint No.	Received Date	Date/Location of Complaint	Complainant	Details of Complaint	Investigation/ Mitigation Action	File Closed
				system to minimize the noise and air nuisances to the nearby residents.	<ul style="list-style-type: none"> ● Provision of portable noise enclosures to reduce noise nuisance from drilling works and generator in Lam Tin Interchange; and ● Use of Quiet PME on-site including generator and hydraulic excavator. 	
16	6 th January 2017	Not Specified / Construction of Lam Tin Interchange	Resident of Yau Lai Estate Cheuk Lai House	The complainant complained the construction noise generated from this Project (EPD Reference No.: K15/RE/0000564-17)	<p>The Contractor has taken the initiative to implement additional noise mitigation measures in order to further minimize noise nuisance to the nearby sensitive receivers, including the followings:</p> <ul style="list-style-type: none"> ● Provision and installation of additional temporary noise barrier during rock breaking works for construction of Lam Tin Interchange; ● Commencement time of daily construction works for construction of Lam Tin Interchange has been postponed from 7am to 8am each day. <p>According to the regular air quality and noise monitoring for this Project, no Action or Limit Level Exceedance was recorded from 16 December 2016 to 19 January 2017. With the implementation of environmental mitigation measures by Contractors on site, it is considered that no adverse air quality and noise impact was brought to the nearby sensitive receivers by the works of this Project.</p> <p>Nevertheless, the Contractor was recommended to continue to properly implement and strictly follow the air quality and noise mitigation measures as recommended in the Environmental Monitoring & Audit Manual and approved Noise Mitigation Plan to minimize environmental impact on the construction site.</p>	Closed
17	6 th January 2017	Not Specified / Construction site near Yau Lai Estate	Resident of Yau Lai Estate Bik Lai House	The Yau Lai Estate Property Services Management Office mentioned that one of the resident of Yau Lai Estate had complained to Hong Kong Housing Authority (HKHA) about the noise generated by the construction works.		Closed
18	10 th January 2017	Not Specified	Unknown	The complainant complained the construction noise generated from this Project (EPD Reference No.: K15/RE/0000967-17)		Closed
19	12 th January 2017	Not Specified / Construction of Lam Tin Interchange	Resident of Yau Lai Estate	The complainant complained the noise generated from rock breaking at Lam Tin Interchange. He requested concrete actions to improve the situation.		Closed
20	12 th January 2017	Not Specified / Construction of Lam Tin Interchange	Resident of Yau Lai Estate Bik Lai House	The complainant complained the noise generated from rock breaking at Lam Tin Interchange.		Closed
21	13 th January 2017	Not Specified / Construction of Lam Tin Interchange	Resident of Yau Lai Estate Bik Lai House	The complainant complained the construction noise generated at Lam Tin Interchange at 7am in the morning.		Closed

Complaint No.	Received Date	Date/Location of Complaint	Complainant	Details of Complaint	Investigation/ Mitigation Action	File Closed
22	13 th January 2017	Not Specified / Construction Works near Eastern Harbour Crossing tunnel portal	Anonymous	The complainant complained about the noise generated by the construction works near the toll plaza of the Eastern Harbour Crossing (EHC). The complainant complained again on 24 Jan 2017 and mentioned the noise problem still affected the daily life of residents		Closed
23	16 th January 2017	Not Specified / Construction of Lam Tin Interchange	Resident of Yau Lai Estate	The complainant complained the construction noise generated at Lam Tin Interchange at 7am in the morning.		Closed
24	17 th January 2017	Not Specified / construction of Lam Tin Interchange	Resident of Yau Lai Estate Bik Lai House	The complainant complained the construction noise generated at Lam Tin Interchange.		Closed
25	26 th January 2017	Not Specified / Construction Works near Eastern Harbour Crossing tunnel portal	黃國健議員及何啟明議員	LC members referred complaints about the noise generated by the construction works near the EHC tunnel portal. They mentioned that the noise generated by the construction works had greatly affected the daily life of nearby residents, especially occupants of Block 5 of Yau Lai Estate and those who lived at the upper floors.	<p>After investigation, it was found out that necessary rock breaking works by hydraulic or pneumatic breakers was conducted during excavation for tunnel adit at Lam Tin Interchange. Noise nuisance from the works area is considered due to the high noise level emission during use of hydraulic or pneumatic breakers.</p> <p>The Contractor had implemented environmental mitigation measures in accordance with the “Implementation Schedule of Proposed Mitigation Measures” of EM&A Manual.</p> <p>The Contractor has taken the initiative to implement additional noise mitigation measures in order to further minimize noise nuisance to the nearby sensitive receivers, including the followings:</p> <ul style="list-style-type: none"> ➤ Provision and installation of additional temporary noise barrier during rock breaking works for construction of Lam Tin Interchange; ➤ Commencement time of daily construction works for construction of Lam Tin Interchange has been postponed from 7am to 8am each day. 	Closed

Complaint No.	Received Date	Date/Location of Complaint	Complainant	Details of Complaint	Investigation/ Mitigation Action	File Closed
26	27 th January 2017	Not Specified / Construction of Lam Tin Interchange	Resident of Yau Lai Estate Bik Lai House	The complainant complained the construction noise generated at Lam Tin Interchange at 7am in the morning. (EPD Ref No. K15/RE/00002945-17)	According to information provided by the Contractor, powered Mechanical Equipment being operated on site during the time of complaint include breaker, dump truck, backhoes, drilling rig, mobile crane and small bulldozer. They were operated on and off with some idling time. It is considered that noise nuisance during the time of complaint was mainly due to high noise level emission during the use of breaker for rock breaking.	Closed
27	9 th February 2017	Not Specified / construction of Lam Tin Interchange	Resident of Yat Lai House, Yau Lai Estate	The complainant complained about the noise nuisance during the construction works of Lam Tin Interchange at 8:10am. (EPD Reference No.: K15/RE/00003855-17)	In addition to the the “Implementation Schedule of Proposed Mitigation Measures” of EM&A Manual, the Contractor has implemented the following additional noise mitigation measures since late including: <ul style="list-style-type: none"> ● Provision and installation of additional temporary noise barrier during rock breaking works for construction of Lam Tin Interchange; ● Sound absorptive materials with 50mm thickness were hanged on rock mountain wall as well as temporary noise barrier containers; and ● Adoption of alternative rock breaking method such as partial rock breaking by rock splitter. 	Closed
28	13 th February 2017	Not Specified / construction of Lam Tin Interchange	Resident of Yat Lai House, Yau Lai Estate	The complainant complained about the noise nuisance during the construction works of Lam tin Interchange.	In addition, the Contractor has taken the initiative to explore measures to further reduce construction noise nuisance such as: <ul style="list-style-type: none"> ● Installation of cantilever barrier on top of the containers; ● Installation of tuned mass dampers on breaker head; and ● Use of acoustic mat cover and a retractable noise barrier where feasible. <p>According to the regular noise monitoring no Limit Level Exceedance was recorded at Noise Monitoring Station CM1, Station CM2 and Station CM3 from 2 – 15 February 2017. With the implementation of environmental mitigation measures by Contractors on site, it is considered that no adverse air quality and noise impact was brought to the nearby sensitive receivers by the works of this Project.</p>	Closed
29	23 rd February 2017	18 Feb 2017 / Slope Works at Lei Yue Mun Road	Anonymous	The complainant complained about the dust generated by the slope works opposite to Lam Tin Ambulance Deport on 18 February 2017 afternoon. He mentioned that the dust greatly affected the pedestrian.	The major source of construction dust nuisance was construction of a temporary storage area. <p>As per investigation, the Contractor has provided environmental mitigation measures to prevent dust generation for the slope works. Water spray was prepared and provided next to the works for dust suppression during the use of handheld breaker.</p>	Closed

Complaint No.	Received Date	Date/Location of Complaint	Complainant	Details of Complaint	Investigation/ Mitigation Action	File Closed
30	23 rd February 2017	Not Specified / BMCPC Footpath	陳繼偉議員	Mr. Chan complained that some of the excavated materials fell from the dump trucks on the BMCPC footpath affecting the safety of pedestrian and hikers.	The major source of construction dust nuisance was formation of temporary site haul road. As per investigation, the following environmental mitigation measures are implemented by the Contractor:	Closed
31	2 nd March 2017	Not Specified / Construction Works near BMCPC Footpath	A resident of Ocean Shores	The complainant complained about the dust generated by the construction works near the existing BMCPC footpath	<ul style="list-style-type: none"> ➤ Water truck was provided for dust suppression at least 8 times per day along the footpath within our site boundary; ➤ Wheel washing were provided for all dump trucks once loaded; ➤ All the dump trucks were covered properly with a mechanical cover once loaded. ➤ The dump trucks were loaded in a specific area (off the footpath) near the formation works area. 	Closed
32	8 th March 2017	7 Mar 2017 / Slope works near Sin Fat Road Tennis Court	Public	The complainant complained the dust and noise generated by the slope works near Sin Fat Road Tennis Court	The major source of construction dust and noise nuisance was shotcreting of slope surface. As per investigation, the following environmental mitigation measures are implemented by the Contractor: <ul style="list-style-type: none"> ➤ Tarpaulin sheets were provided along the slope adjacent to the tennis court during shotcreting; ➤ After the complaint was received, the dust screen for tennis court has been enhanced immediately with additional tarpaulin along the fencing of tennis court; ➤ Additional acoustic sheets were also provided to minimize construction noise nuisance to users of the tennis courts. 	Closed
33 ^(*)	10 th March 2017	4 Mar 2017 / Slope works near Sin Fat Road Tennis Court	Anonymous	The complainant complained the dust generated by the slope works near Sin Fat Road Tennis Court.	Under investigation	On-going
34	13 th March 2017	27 Feb – 12 Mar 2017 / Barging point in front of Ocean Shore	Public	The complainant complained about noise from the loading / unloading activities at the barging point in front of Ocean Shore for material delivery to the LT-TKO Tunnel work site during 3:00 am and 4:00am over the past 2 weeks.	According to information provided by the Contractors, no works, including any loading / unloading works, was carried out during the restricted hours at site area near Ocean Shores in early March 2017. The complaint is concluded to be non-Project related. The Engineer and the Environmental Team have reminded the contractor(s) not to carry out any works, especially loading/unloading activities near the Ocean Shores during restricted hours to minimize	Closed

Complaint No.	Received Date	Date/Location of Complaint	Complainant	Details of Complaint	Investigation/ Mitigation Action	File Closed
					noise nuisance to the nearby residents.	
35 ^(*)	21 st March 2017	Not Specified / Construction Works near Cha Kwo Ling Village	茶果嶺鄉民聯誼會書記鍾先生	The complainant stated that villagers concerned about the waste water produced by car washing in construction site will flow into the sea/ existing drainage system directly and requested the contractors to improve the situation.	Under investigation	On-going
36	25 th March 2017	Not Specified / Construction Works of TKO Portal	Public	The complainant complaint about the construction dust impact due to marine works and construction of tunnel of this Project.	<p>The major source of construction dust and noise nuisance was site formation works for TKO Portal and marine works for construction of temporary barging facilities</p> <p>As per investigation, the following environmental mitigation measures are implemented by the Contractor:</p> <ul style="list-style-type: none"> ➤ Provision of frequent watering including watering of eight times a day on active work area, exposed area and paved haul roads; ➤ Installation of automatic sprinklers for water spray to minimize dust generation; ➤ Shotcreting or hydroseeding to surface of TKO Portal site formation; ➤ Provision of wheel washing to vehicles out of site; ➤ Covering of dusty slope surface by impervious material such tarpaulin sheets. <p>During the weekly site inspections by the Environmental Team (ET), no deficiencies about exhaust gas or black smoke generation was observed from the Powered Mechanical Equipment (PME) on site of construction of TKO Portal. Air quality impact due to exhaust gas or black smoke emission from PME is considered insignificant from the Project.</p>	Closed
37	6 th April 2017	1 Apr 2017 / Slope works near Sin Fat Road Tennis Court	Public	The complainant complained the smell and dust generated by the slope works near Sin Fat Road Tennis Court on 1 April 2017. He suspected that the shotcrete may contain toxic substances and may affect the health.	Under investigation	On-going

Note (*): The complaints were received in this reporting period and yet to be included in the previous Monthly EM&A Reports.

Cumulative Complaint Log since commencement of Project

Reporting Month	Number of Complaints in Reporting Month	Number of Summons in Reporting Month	Number of Prosecutions in Reporting Month
November 2016	0	0	0
December 2016	11	0	0
January 2017	15	0	0
February 2017	4	0	0
March 2017	6	0	0
April 2017	1	0	0
Total	37	0	0

Cumulative Log for Notifications of Summons*Contract No. NE/2015/01*

Log Ref.	Date/Location	Subject	Status	Total no. Received in this reporting month	Total no. Received since project commencement
--	--	--	--	--	--

Contract No. NE/2015/02

Log Ref.	Date/Location	Subject	Status	Total no. Received in this reporting month	Total no. Received since project commencement
--	--	--	--	--	--

Cumulative Log for Successful Prosecutions*Contract No. NE/2015/01*

Log Ref.	Date/Location	Subject	Status	Total no. Received in this reporting month	Total no. Received since the commencement of the project
--	--	--	--	--	--

Contract No. NE/2015/02

Log Ref.	Date/Location	Subject	Status	Total no. Received in this reporting month	Total no. Received since the commencement of the project
--	--	--	--	--	--

**APPENDIX P
WASTE GENERATION IN THE
REPORTING MONTH**

Monthly Summary Waste Flow Table for 2017



Month	Actual Quantities of Inert C&D Materials Generated Monthly						Actual Quantities of C&D Wastes Generated Monthly				
	a.Total Quantity Generated (see Note 8)	b. Hard Rock and Large Broken Concrete (see Note 9)	c. Reused in the Contract	d. Reused in Other Projects	e. Disposed as Public Fill (see Note 10)	f. Imported Fill	g. Metals (see Note 5)	h. Paper / Cardboard Packaging (see Note 5)	i. Plastics (see Note 3) (see Note 5)	j. Chemical Waste	k. Others, e.g. general refuse
	(in '000m ³)	(in '000m ³)	(in '000m ³)	(in '000m ³)	(in '000m ³)	(in '000m ³)	(in '000kg)	(in '000kg)	(in '000kg)	(in '000kg)	(in '000m ³)
January	40.484	0.000	22.688	5.063	12.733	0.000	0.000	0.257	0.000	0.000	0.292
February	23.357	0.000	12.911	3.874	6.572	0.000	0.000	0.000	0.000	1.000	0.488
March	20.078	0.000	6.359	11.713	2.006	0.000	0.000	0.000	0.000	0.000	0.284
April	13.516	0.000	4.862	7.751	0.903	0.000	0.000	0.120	0.000	0.000	0.396
May											
June											
Sub-total	97.435	0.000	46.820	28.401	22.214	0.000	0.000	0.377	0.000	1.000	1.460
July											
August											
September											
October											
November											
December											
Total	97.435	0.000	46.820	28.401	22.214	0.000	0.000	0.377	0.000	1.000	1.460

Total C&D waste generated = a+b+f+g+h+i+j+k

Total C&D waste generated (excluded excavated material) = g+h+i+j+k

Total C&D waste recycled = c+d+g+h+i

% of recycled C&D waste = (Total C&D waste generated - Total C&D waste recycled) / Total C&D waste generated

Monthly Summary Waste Flow Table for 2017 Year

Contract No.: NE/2015/02

Month	Actual Quantities of Inert C&D Materials Generated Monthly						Actual Quantities of C&D Wastes Generated Monthly				
	Total Quantity Generated	Hard Rock and Large Borken Concrete	Reused in the Contract	Reused in other Projects	Disposal as Public Fill	Imported Fill	Metals	Paper / Cardboard Packaging	Plastics (See note 3)	Chemical Waste	Other, e.g. general refuse
	[in '000m ³]	[in '000m ³]	[in '000m ³]	[in '000m ³]	[in '000m ³]	[in '000m ³]	[in '000kg]	[in '000kg]	[in '000kg]	[in '000kg]	[in '000m ³]
Jan	1.02115	0.00000	0.00000	0.00000	1.02115	0.00000	0.00000	0.00000	0.00000	0.00000	0.02306
Feb	1.04554	0.00000	0.00000	0.00000	1.04554	0.00000	0.00000	0.00000	0.00000	0.00000	0.01994
Mar	0.03860	0.00000	0.00000	0.00000	0.03860	0.00000	0.00000	0.00000	0.00000	0.00000	0.03012
Apr	0.02184	0.00000	0.00000	0.00000	0.02184	0.00000	0.00000	0.00000	0.00000	0.00000	0.18326
May											
June											
SUB-TOTAL											
Jul											
Aug											
Sep											
Oct											
Nov											
Dec											
TOTAL	2.12712	0.00000	0.00000	0.00000	2.12712	0.00000	0.00000	0.00000	0.00000	0.00000	0.25638

Note: Conversion to 1000m³ for general refuse is weight in 1000kg multiply by 0.002

Conversion to 1000m³ for Inert C&D is weight in 1000kg multiply by 0.0005

Plastics refer to plastic bottles / containers, plastic sheets / foam from packaging material

**APPENDIX Q
TENTATIVE CONSTRUCTION
PROGRAMME**

High Level 3 Months Look Ahead Programme

Activities	May-17	Jun-17	Jul-17
Lam Tin Interchange			
Excavation for Tunnel Adit			
Haul Road Construction			
EHC2 U-Trough			
Site Formation - Area 1G1			
Site Formation - Area 2			
Site Formation - Area 3			
Site Formation - Area 4			
Temp Steel Bridge across CKL Road & Barging Facility			
Pipe Pile Wall - Area 2A			
Ground Investigation			
Main Tunnel			
Tunnel Team Mobilisation Works			
Construction Adit			
TKO Interchange			
Haul Road Construction, Site Formation & Slope Works			
Temporary Cut Slope For BMCPC			
Temporary Barging Facilities & Temporary Works			

Activity ID	Activity Name	Calendar	Original Duration	Remaining Duration	Start	Finish	Total Float	Activity % Complete	Variance - BL1 Finish Date	2017					
										Apr	May	Jun	Jul	Aug	
NE/2015/02 Tseung Kwan O - Lam Tin Tunnel-Road P2 and Associated Works															
Preliminaries, Submission, Contractor's Design Submission and Approval															
Contractor's Design Submission and Approval															
Foundation Design															
AIP Submission for Foundation of Road P2 Structure (Reclaimed Section)															
S11240	Resubmit AIP Submission for Foundation of Road P2 Structure (Reclaimed Section)	P2-Cal.A	14	2	27-Jan-17 A	21-Apr-17	271	85.71%	-71						
S11250	Review and comment by GEO	P2-Cal.A	14	14	22-Apr-17	05-May-17	271	0%	0						
S11260	Accept AIP Submission for Foundation of Road P2 Structure (Reclaimed Section)	P2-Cal.A	21	21	06-May-17	26-May-17	271	0%	0						
DDA Submission for Foundation of Road P2 Structure (Reclaimed Section)															
S11360	Prepare and Submit DDA Submission for Foundation of Road P2 Structure (Reclaimed Section)	P2-Cal.A	21	21	27-May-17	16-Jun-17	271	0%	0						
S11380	Review and Discuss DDA Submission for Foundation of Road P2 Structure (Reclaimed Section)	P2-Cal.A	21	21	17-Jun-17	07-Jul-17	271	0%	0						
S11400	Resubmit DDA Submission for Foundation of Road P2 Structure (Reclaimed Section)	P2-Cal.A	14	14	08-Jul-17	21-Jul-17	271	0%	0						
E&M Design															
Detail Design for E&M Works (Tunnel and associated)															
S11600	Review and Discuss Detail Design for E&M Works (Tunnel and associated)	P2-Cal.A	21	9	08-Apr-17 A	28-Apr-17	616	57.14%	0						
S11620	Resubmit Detail Design for E&M Works (Tunnel and associated)	P2-Cal.A	21	21	29-Apr-17	19-May-17	616	0%	0						
S11640	Accept Detail Design for E&M Works (Tunnel and associated)	P2-Cal.A	21	21	20-May-17	09-Jun-17	616	0%	0						
Design of Architectural Finishes for Internal Walls of U-Trough Structures															
S11660	Prepare and Submit Design of Architectural Finishes for Internal Walls of U-Trough Structures	P2-Cal.A	21	21	20-Apr-17	10-May-17	932	0%	0						
S11680	Review and Discuss Design of Architectural Finishes for Internal Walls of U-Trough Structures	P2-Cal.A	21	21	11-May-17	31-May-17	932	0%	0						
S11700	Resubmit Design of Architectural Finishes for Internal Walls of U-Trough Structures	P2-Cal.A	14	14	01-Jun-17	14-Jun-17	932	0%	0						
S11720	Accept Design of Architectural Finishes for Internal Walls of U-Trough Structures	P2-Cal.A	21	21	15-Jun-17	05-Jul-17	932	0%	0						
Contractor Cost Saving Design															
AIP Submission for CSD of Existing Land Section (P2 CH423 - CH500)															
S11880	Accept AIP Submission for CSD of Existing Land Section (P2 CH423 - CH500)	P2-Cal.A	21	13	23-Mar-17 A	02-May-17	586	38.1%	-20						
DDA Submission for CSD of Existing Land Section (P2 CH423 - CH500)															
S11882	Prepare and Submit DDA Submission for CSD of Existing Land Section (P2 CH423 - CH500)	P2-Cal.A	21	21	03-May-17	23-May-17	586	0%	0						
S11884	Review and Discuss DDA Submission for CSD of Existing Land Section (P2 CH423 - CH500)	P2-Cal.A	21	21	24-May-17	13-Jun-17	586	0%	0						
S11886	Resubmit DDA Submission for CSD of Existing Land Section (P2 CH423 - CH500)	P2-Cal.A	14	14	14-Jun-17	27-Jun-17	586	0%	0						
S11888	Accept DDA Submission for CSD of Existing Land Section (P2 CH423 - CH500)	P2-Cal.A	21	21	28-Jun-17	18-Jul-17	586	0%	0						
AIP Submission for CSD of Reclaimed Section (S200 CH674 - CH755, S300 CH326-CH355)															
S11940	Resubmit AIP Submission for CSD of Reclaimed Section (S200 CH674 - CH755, S300 CH326-CH355)	P2-Cal.A	14	30	20-Feb-17 A	19-May-17	726	0%	-75						
S11960	Accept AIP Submission for CSD of Reclaimed Section (S200 CH674 - CH755, S300 CH326-CH355)	P2-Cal.A	21	21	20-May-17	09-Jun-17	726	0%	0						
DDA Submission for CSD of Reclaimed Section (S200 CH674 - CH755, S300 CH326-CH355)															
S11962	Prepare and Submit DDA Submission for CSD of Reclaimed Section (S200 CH674 - CH755, S300 CH326-CH355)	P2-Cal.A	21	21	10-Jun-17	30-Jun-17	726	0%	0						
S11964	Review and Discuss DDA Submission for CSD of Reclaimed Section (S200 CH674 - CH755, S300 CH326-CH355)	P2-Cal.A	21	21	01-Jul-17	21-Jul-17	726	0%	0						
Major Temporary Works Design															
ELS Design for U-Trough A & B (SR2 CH170 - CH250)															
S12440	Accept ELS Design for U-Trough A & B (SR2 CH170 - CH250)	P2-Cal.A	21	20	19-Apr-17 A	09-May-17	185	4.76%	0						
ELS Design for U-Trough A & B (P2 CH318 - CH363)															
S12460	Prepare and Submit ELS Design for U-Trough A & B (P2 CH318 - CH363)	P2-Cal.A	18	0	20-Mar-17 A	20-Apr-17	149	100%	-13						
S12480	Review and Discuss ELS Design for U-Trough A & B (P2 CH318 - CH363)	P2-Cal.A	21	21	20-Apr-17	10-May-17	149	0%	0						
S12500	Resubmit ELS Design for U-Trough A & B (P2 CH318 - CH363)	P2-Cal.A	14	14	11-May-17	24-May-17	149	0%	0						
S12520	Accept ELS Design for U-Trough A & B (P2 CH318 - CH363)	P2-Cal.A	21	21	25-May-17	14-Jun-17	149	0%	0						
ELS Design for U-Trough A & B (P2 CH411 - CH500)															
S12580	Resubmit ELS Design for U-Trough A & B (P2 CH411 - CH500)	P2-Cal.A	14	2	05-Apr-17 A	21-Apr-17	129	85.71%	-3						
S12600	Accept ELS Design for U-Trough A & B (P2 CH411 - CH500)	P2-Cal.A	21	21	22-Apr-17	12-May-17	129	0%	0						

█ Pr █ Critical Remaining Work
█ Actual Work ◆ Milestone
█ Remaining Work █ Summary

NE/2015/02 Tseung Kwan O - Lam Tin Tunnel-Road P2 and Associated Works

3 Months Rolling Programme
 (20 Apr 2017)
 Page: 1 of 7

Date	Revision	Checked	Approved
20-Apr-17			

Activity ID	Activity Name	Calendar	Original Duration	Remaining Duration	Start	Finish	Total Float	Activity % Complete	Variance - BL1	Finish Date	2017					
											Apr	May	Jun	Jul	Aug	
Design of sediment/ marine treatment area																
S12900	Resubmit Design of sediment/ marine treatment area	P2-Cal.A	14	0	07-Feb-17 A	20-Apr-17	69	100%	22							
S12920	Accept Design of sediment/ marine treatment area	P2-Cal.A	21	21	20-Apr-17	10-May-17	69	0%	0							
ELS Design for U-Trough A & B (P2 CH363 - CH411)																
S12940	Prepare and Submit ELS Design for U-Trough A & B (P2 CH363 - CH411)	P2-Cal.A	18	18	13-May-17	30-May-17	129	0%	0							
S12960	Review and Discuss ELS Design for U-Trough A & B (P2 CH363 - CH411)	P2-Cal.A	21	21	31-May-17	20-Jun-17	129	0%	0							
S12980	Resubmit ELS Design for U-Trough A & B (P2 CH363 - CH411)	P2-Cal.A	14	14	21-Jun-17	04-Jul-17	129	0%	0							
S13000	Accept ELS Design for U-Trough A & B (P2 CH363 - CH411)	P2-Cal.A	21	21	05-Jul-17	25-Jul-17	129	0%	0							
Temporary Jetty Design																
S13020	Prepare and Submit Temporary Jetty Design	P2-Cal.A	18	16	01-Apr-17 A	05-May-17	18	11.11%	-17							
S13040	Review and Discuss Temporary Jetty Design	P2-Cal.A	21	21	06-May-17	26-May-17	18	0%	0							
S13060	Resubmit Temporary Jetty Design	P2-Cal.A	14	14	27-May-17	09-Jun-17	18	0%	0							
S13080	Accept Temporary Jetty Design	P2-Cal.A	21	21	10-Jun-17	30-Jun-17	18	0%	0							
Design of Marine Survey Tower																
S13100	Prepare and Submit Marine Survey Tower	P2-Cal.A	18	18	01-Jul-17	18-Jul-17	205	0%	0							
S13120	Review and Discuss Marine Survey Tower	P2-Cal.A	21	21	19-Jul-17	08-Aug-17	205	0%	0							
Major Construction Works Method Statement																
Construction of Seawall Foundation for Road P2																
S13260	Prepare and Submit Method Statement for Construction of Seawall Foundation for Road P2	P2-Cal.A	18	18	20-Apr-17	07-May-17	26	0%	0							
S13280	Review and Discuss Method Statement for Construction of Seawall Foundation for Road P2	P2-Cal.A	21	21	08-May-17	28-May-17	26	0%	0							
S13300	Resubmit Method Statement for Construction of Seawall Foundation for Road P2	P2-Cal.A	7	7	29-May-17	04-Jun-17	26	0%	0							
S13320	Accept Method Statement for Construction of Seawall Foundation for Road P2	P2-Cal.A	21	21	05-Jun-17	25-Jun-17	26	0%	0							
Reclamation Filing																
S13360	Review and Discuss Method Statement for Reclamation Filing	P2-Cal.A	21	21	20-Apr-17	10-May-17	117	0%	0							
S13380	Resubmit Method Statement for Reclamation Filing	P2-Cal.A	7	7	11-May-17	17-May-17	117	0%	0							
S13400	Accept Method Statement for Reclamation Filing	P2-Cal.A	21	21	18-May-17	07-Jun-17	117	0%	0							
Demolishing/ Removing Existing Seawall																
S13580	Prepare and Submit Method Statement for Demolishing/ Removing Existing Seawall	P2-Cal.A	18	18	20-Apr-17	07-May-17	23	0%	0							
S13600	Review and Discuss Method Statement for Demolishing/ Removing Existing Seawall	P2-Cal.A	21	21	08-May-17	28-May-17	23	0%	0							
S13620	Resubmit Method Statement for Demolishing/ Removing Existing Seawall	P2-Cal.A	7	7	29-May-17	04-Jun-17	23	0%	0							
S13640	Accept Method Statement for Demolishing/ Removing Existing Seawall	P2-Cal.A	21	21	05-Jun-17	25-Jun-17	23	0%	0							
Installation, Operation and Removal of Water Gate																
S13820	Prepare and Submit Method Statement for Installation, Operation and Removal of Water Gate	P2-Cal.A	18	3	20-Jan-17 A	22-Apr-17	-61	83.33%	-75							
S13840	Review and Discuss Method Statement for Installation, Operation and Removal of Water Gate	P2-Cal.A	21	21	23-Apr-17	13-May-17	-61	0%	0							
S13860	Resubmit Method Statement for Installation, Operation and Removal of Water Gate	P2-Cal.A	7	7	14-May-17	20-May-17	-61	0%	0							
S13880	Accept Method Statement for Installation, Operation and Removal of Water Gate	P2-Cal.A	21	21	21-May-17	10-Jun-17	-61	0%	0							
Construction of Retaining Wall Structure RW P2-A																
S14044	Accept Method Statement for Construction of Retaining Wall Structure	P2-Cal.A	21	21	20-Apr-17	10-May-17	614	0%	0							
Excavation and ELS of U-Troughs																
S14060	Prepare and Submit Method Statement for Excavation and ELS of U-Troughs	P2-Cal.A	18	18	05-Jul-17	22-Jul-17	129	0%	0							
Construction of U-Troughs Structure																
S14140	Prepare and Submit Method Statement for Construction of U-Troughs Structure	P2-Cal.A	18	18	05-Jul-17	22-Jul-17	294	0%	0							
S14160	Review and Discuss Method Statement for Construction of U-Troughs Structure	P2-Cal.A	21	21	05-Jul-17	25-Jul-17	294	0%	0							
Treatment of Dredged Marine Sediment of Type 1																
S17900	2nd Resubmit Method Statement for Treatment of Dredging Marine Sediment of Type 1	P2-Cal.A	14	14	30-Mar-17 A	03-May-17	265	0%	-6							
S17920	Accept Method Statement for Treatment of Dredging Marine Sediment of Type 1	P2-Cal.A	21	21	04-May-17	24-May-17	265	0%	0							
Temporary Support for Excavation of Existing Seawall																

█ Primary Baseline █ Critical Remaining Work
█ Actual Work ◆ Milestone
█ Remaining Work ▬ Summary

NE/2015/02 Tseung Kwan O - Lam Tin Tunnel-Road P2 and Associated Works

3 Months Rolling Programme
(20 Apr 2017)
Page: 2 of 7

Date	Revision	Checked	Approved
20-Apr-17			

Activity ID	Activity Name	Calendar	Original Duration	Remaining Duration	Start	Finish	Total Float	Activity % Complete	Variance - BL1	Finish Date	2017				
											Apr	May	Jun	Jul	Aug
S14940	Prepare and Submit Method Statement for Temporary Support for Excavation of Existing Seawall	P2-Cal.A	18	18	20-Apr-17	07-May-17	16	0%	0						
S14960	Review and Discuss Method Statement for Temporary Support for Excavation of Existing Seawall	P2-Cal.A	21	21	08-May-17	28-May-17	16	0%	0						
S14980	Resubmit Method Statement for Temporary Support for Excavation of Existing Seawall	P2-Cal.A	14	14	29-May-17	11-Jun-17	16	0%	0						
S15000	Accept Method Statement for Temporary Support for Excavation of Existing Seawall	P2-Cal.A	21	21	12-Jun-17	02-Jul-17	16	0%	0						
Procurement of Major Material		P2-Cal.A	1015	925	20-Jan-17 A	31-Oct-19	272		0						
S15020	Procurement and Delivery of Steel H-Pile	P2-Cal.A	800	721	31-Jan-17 A	10-Apr-19	142	9.88%	0						
S15040	Procurement and Delivery of ELS Waling & Struts Members	P2-Cal.A	1015	925	20-Jan-17 A	31-Oct-19	272	8.87%	0						
S15060	Offsite Fabrication of Double Water Gate System	P2-Cal.A	100	9	01-Feb-17 A	28-Apr-17	-18	91%	13						
S15080	Offsite Fabrication of Pre-cast Seawall blocks	P2-Cal.A	90	90	26-Jun-17	23-Sep-17	26	0%	0						
S15100	Cast-in gantry for Road Works	P2-Cal.A	120	89	20-Mar-17 A	17-Jul-17	730	25.83%	0						
Subletting Package		P2-Cal.A	210	110	10-Jan-17 A	07-Aug-17	1004		0						
Marine Works		P2-Cal.A	100	0	10-Jan-17 A	20-Apr-17	90		0						
S16920	Tender Interview and Recommendation to PM for Marine Works	P2-Cal.A	21	0	10-Jan-17 A	20-Apr-17	90	100%	-79						
S16940	Marine Works Award	P2-Cal.A	0	0		20-Apr-17	90	0%	0						
Cement Stabilization and Solidification		P2-Cal.A	21	11	10-Apr-17 A	30-Apr-17	289		0						
S17000	Tender Interview and Recommendation to PM for Cement Stabilization and Solidification	P2-Cal.A	21	11	10-Apr-17 A	30-Apr-17	289	47.62%	0						
S17020	Cement Stabilization and Solidification Award	P2-Cal.A	0	0		30-Apr-17	289	0%	0						
Water Works		P2-Cal.A	35	26	11-Apr-17 A	15-May-17	640		0						
S17140	Submission and Opening of Tender for Water Works	P2-Cal.A	14	5	11-Apr-17 A	24-Apr-17	640	64.29%	0						
S17160	Tender Interview and Recommendation to PM for Water Works	P2-Cal.A	21	21	25-Apr-17	15-May-17	640	0%	0						
S17180	Water Works Award	P2-Cal.A	0	0		15-May-17	640	0%	0						
Road Works		P2-Cal.A	42	42	16-May-17	26-Jun-17	839		0						
S17200	Prepare Road Works Tender Document for PM Acceptance	P2-Cal.A	7	7	16-May-17	22-May-17	839	0%	0						
S17220	Submission and Opening of Tender for Road Works	P2-Cal.A	14	14	23-May-17	05-Jun-17	839	0%	0						
S17240	Tender Interview and Recommendation to PM for Road Works	P2-Cal.A	21	21	06-Jun-17	26-Jun-17	839	0%	0						
S17260	Road Works Award	P2-Cal.A	0	0		26-Jun-17	839	0%	0						
Irrigation Works		P2-Cal.A	42	42	27-Jun-17	07-Aug-17	1004		0						
S17280	Prepare Irrigation Works Tender Document for PM Acceptance	P2-Cal.A	7	7	27-Jun-17	03-Jul-17	1004	0%	0						
S17300	Submission and Opening of Tender for Irrigation Works	P2-Cal.A	14	14	04-Jul-17	17-Jul-17	1004	0%	0						
S17320	Tender Interview and Recommendation to PM for Irrigation Works	P2-Cal.A	21	21	18-Jul-17	07-Aug-17	1004	0%	0						
Section 1 of the Works		P2-Cal.B	95	74	22-Mar-17 A	19-Jul-17	136		0						
Reprovisioning of DSD Transformer Room		P2-Cal.B	95	74	22-Mar-17 A	19-Jul-17	136		0						
Structure Construction		P2-Cal.B	36	15	22-Mar-17 A	09-May-17	195		0						
LC10900	Construction of wall and ceiling finishing works for DSD Transformer Room	P2-Cal.B	5	0	22-Mar-17 A	20-Apr-17	-6	100%	-16						
LC10955	Construction of Draw Pits (PMI No.4)	P2-Cal.B	21	5	28-Mar-17 A	25-Apr-17	195	76.19%	0						
LC10980	Connection of Equipment and Cable Laying by CLP	P2-Cal.B	10	1	06-Apr-17 A	20-Apr-17	200	90%	0						
LC10985	Road Pavement Works	P2-Cal.B	10	10	26-Apr-17	09-May-17	195	0%	0						
P2 DSD Tx Room BS Installation Programme		P2-Cal.B	74	74	20-Apr-17	19-Jul-17	121		0						
Electrical		P2-Cal.B	52	52	20-Apr-17	23-Jun-17	143		0						
A1000	Installation of conduit at Tx Room	P2-Cal.B	4	4	20-Apr-17	24-Apr-17	-6	0%	0						
A1010	Cable wiring at Tx room	P2-Cal.B	4	4	22-Apr-17	27-Apr-17	-6	0%	0						
A1020	Installation of light fitting at Tx Room	P2-Cal.B	5	5	27-Apr-17	05-May-17	-6	0%	0						
A1030	Delivery of cable tray	P2-Cal.B	0	0		05-May-17*	-6	0%	0						
A1040	Installation of cable tray at trench	P2-Cal.B	5	5	05-May-17	10-May-17	160	0%	0						
A1060	Installation of conduit at LV switch Room	P2-Cal.B	4	4	20-Apr-17	24-Apr-17	121	0%	0						
A1070	Cable wiring at LV switch room	P2-Cal.B	4	4	24-Apr-17	28-Apr-17	121	0%	0						
A1080	Installation of light fitting at LV switch Room	P2-Cal.B	3	3	27-Apr-17	29-Apr-17	121	0%	0						

█ Primary Baseline █ Critical Remaining Work
█ Actual Work ◆ Milestone
█ Remaining Work ▬ Summary

NE/2015/02 Tseung Kwan O - Lam Tin Tunnel-Road P2 and Associated Works

3 Months Rolling Programme
 (20 Apr 2017)
 Page: 3 of 7

Date	Revision	Checked	Approved
20-Apr-17			

Activity ID	Activity Name	Calendar	Original Duration	Remaining Duration	Start	Finish	Total Float	Activity % Complete	Variance - BL1 Finish Date	2017				
										Apr	May	Jun	Jul	Aug
A1090	FAT LV switchboard	P2-Cal.B	2	2	29-Apr-17	04-May-17	121	0%	0					
A1100	Delivery and assembly of LV switchboard at LV switch room	P2-Cal.B	4	4	04-May-17	09-May-17	121	0%	0					
A1110	SAT LV Switchboard	P2-Cal.B	3	3	09-May-17	11-May-17	121	0%	0					
A1120	Installation of MCB Board	P2-Cal.B	6	6	12-May-17	19-May-17	121	0%	0					
A1130	System T&C	P2-Cal.B	4	4	19-May-17	24-May-17	121	0%	0					
A1140	Installation of Lighting down conductors	P2-Cal.B	4	4	11-May-17	15-May-17	160	0%	0					
A1150	Installation of Lightning pits	P2-Cal.B	4	4	16-May-17	19-May-17	160	0%	0					
A1160	Installation of Earthing Conductor	P2-Cal.B	4	4	20-May-17	24-May-17	160	0%	0					
A1170	Installation of Earthing Pit	P2-Cal.B	4	4	25-May-17	29-May-17	160	0%	0					
A1180	Earthing and Lightning T&C	P2-Cal.B	2	2	31-May-17	01-Jun-17	160	0%	0					
A1190	Cable Laying from LV Switch Board to pillar box	P2-Cal.B	1	1	02-Jun-17	03-Jun-17	160	0%	0					
A1200	1st Handover Inspection of CLP Tx Room	P2-Cal.B	0	0		08-May-17	129	0%	0					
A1203	1st Defect Rectification	P2-Cal.B	6	6	08-May-17	15-May-17	129	0%	0					
A1205	2nd Handover Inspection of CLP Tx Room	P2-Cal.B	0	0		15-May-17	129	0%	0					
A1210	Handover of CLP Tx Room	P2-Cal.B	0	0	15-May-17		129	0%	0					
A1220	Submit WR1	P2-Cal.B	4	4	24-May-17	27-May-17	121	0%	0					
A1225	CLP Working Period	P2-Cal.B	20	20	29-May-17	21-Jun-17	143	0%	0					
A1230	Energization of LV Switch Room	P2-Cal.B	1	1	22-Jun-17	23-Jun-17	143	0%	0					
MVAC		P2-Cal.B	31	31	20-Apr-17	27-May-17	121		0					
A1260	Installation of conduit at Tx Room	P2-Cal.B	4	4	20-Apr-17	24-Apr-17	95	0%	0					
A1270	Cable wiring at Tx room	P2-Cal.B	3	3	22-Apr-17	26-Apr-17	130	0%	0					
A1280	Installation of fan and air duct at Tx Room	P2-Cal.B	5	5	26-Apr-17	04-May-17	130	0%	0					
A1290	Installation of fan controller at Tx Room	P2-Cal.B	3	3	04-May-17	06-May-17	130	0%	0					
A1300	Installation of fan and air duct at switch Room	P2-Cal.B	5	5	04-May-17	10-May-17	130	0%	0					
A1310	Installation of LMCP at LV switch Room	P2-Cal.B	5	5	06-May-17	12-May-17	130	0%	0					
A1320	System T&C	P2-Cal.B	3	3	11-May-17	13-May-17	130	0%	0					
A1330	Submit WR1A	P2-Cal.B	4	4	24-May-17	27-May-17	121	0%	0					
FS		P2-Cal.B	74	74	20-Apr-17	19-Jul-17	95		0					
A1510	Installation of conduit at Tx Room	P2-Cal.B	4	4	20-Apr-17	24-Apr-17	95	0%	0					
A1520	Cable wiring at Tx room	P2-Cal.B	3	3	22-Apr-17	26-Apr-17	95	0%	0					
A1530	Installation of heat detector at Tx Room	P2-Cal.B	4	4	26-Apr-17	02-May-17	95	0%	0					
A1560	Installation of conduit at LV switch Room	P2-Cal.B	4	4	02-May-17	08-May-17	95	0%	0					
A1570	Cable wiring at LV switch room	P2-Cal.B	13	13	08-May-17	22-May-17	95	0%	0					
A1580	Installation of heat detector at LV switch Room	P2-Cal.B	6	6	22-May-17	29-May-17	95	0%	0					
A1590	Installation of AFA panel and visual/audio alarm equipment	P2-Cal.B	19	19	31-May-17	21-Jun-17	95	0%	0					
A1620	System T&C	P2-Cal.B	3	3	21-Jun-17	24-Jun-17	95	0%	0					
A1640	Submit WR1A	P2-Cal.B	1	1	24-Jun-17	26-Jun-17	95	0%	0					
A1650	Submit Form 314/501	P2-Cal.B	0	0		26-Jun-17	95	0%	0					
A1660	FSD Inspection	P2-Cal.B	1	1	18-Jul-17	19-Jul-17	95	0%	0					
Road Works		P2-Cal.B	10	10	19-Apr-17 A	09-May-17	195		-6					
LC11020	Road Marking	P2-Cal.B	10	9	19-Apr-17 A	08-May-17	196	10%	-5					
LC11040	Installation of Vehicle Gate - 2 gates	P2-Cal.B	10	9	19-Apr-17 A	09-May-17	195	10%	-6					
Section 3 of the Works		P2-Cal.B	141	118	20-Mar-17 A	08-Sep-17	674		0					
Existing Land Section		P2-Cal.B	141	118	20-Mar-17 A	08-Sep-17	674		0					
Retaining Wall P2-A CH 500- 650		P2-Cal.B	65	65	11-May-17	27-Jul-17	531		0					
LC11940	Excavation to formation level (Bay 4 - 15) (Total: 2054m3 - 200m3/day)	P2-Cal.B	11	11	11-May-17	23-May-17	501	0%	0					
LC11980	Laying Blinding (Bay 4 - 7)	P2-Cal.B	10	10	17-May-17	27-May-17	501	0%	0					

— Primary Baseline ■ Critical Remaining Work
— Actual Work ◆ Milestone
— Remaining Work — Summary

NE/2015/02 Tseung Kwan O - Lam Tin Tunnel-Road P2 and Associated Works

3 Months Rolling Programme
 (20 Apr 2017)
 Page: 4 of 7

Date	Revision	Checked	Approved
20-Apr-17			

Activity ID	Activity Name	Calendar	Original Duration	Remaining Duration	Start	Finish	Total Float	Activity % Complete	Variance - BL1 Finish Date	2017				
										Apr	May	Jun	Jul	Aug
LC11985	Laying Blinding (Bay 8 - 11)	P2-Cal.B	10	10	29-May-17	09-Jun-17	531	0%	0					
LC11990	Laying Blinding (Bay 12 - 15)	P2-Cal.B	10	10	10-Jun-17	21-Jun-17	561	0%	0					
LC12000	Construction of RW P2-A Base Slab - Bay 4 (Team C)	P2-Cal.B	10	10	29-May-17	09-Jun-17	501	0%	0					
LC12020	Construction of RW P2-A Wall Stem - Bay 4 (Team C)	P2-Cal.B	10	10	10-Jun-17	21-Jun-17	501	0%	0					
LC12040	Construction of RW P2-A Base Slab - Bay 5 (Team C)	P2-Cal.B	10	10	22-Jun-17	04-Jul-17	501	0%	0					
LC12060	Construction of RW P2-A Wall Stem - Bay 5 (Team C)	P2-Cal.B	10	10	05-Jul-17	15-Jul-17	501	0%	0					
LC12080	Construction of RW P2-A Base Slab - Bay 6 (Team D)	P2-Cal.B	10	10	29-May-17	09-Jun-17	501	0%	0					
LC12100	Construction of RW P2-A Wall Stem - Bay 6 (Team D)	P2-Cal.B	10	10	10-Jun-17	21-Jun-17	501	0%	0					
LC12120	Construction of RW P2-A Base Slab - Bay 7 (Team D)	P2-Cal.B	10	10	22-Jun-17	04-Jul-17	501	0%	0					
LC12140	Construction of RW P2-A Wall Stem - Bay 7 (Team D)	P2-Cal.B	10	10	05-Jul-17	15-Jul-17	501	0%	0					
LC12160	Construction of RW P2-A Base Slab - Bay 8 (Team C)	P2-Cal.B	10	10	17-Jul-17	27-Jul-17	501	0%	0					
LC12240	Construction of RW P2-A Base Slab - Bay 10 (Team D)	P2-Cal.B	10	10	17-Jul-17	27-Jul-17	501	0%	0					
P2 Road			P2-Cal.B	132	118	30-Mar-17 A	08-Sep-17	431	0%	0				
P2 CH 318 - 375			P2-Cal.B	75	75	20-Apr-17	20-Jul-17	113	0%	0				
TTA Stage 2 - TTA for Temp Road Construction at P2 CH375 - 399			P2-Cal.B	10	10	20-Apr-17	02-May-17	88	0%	0				
LC12760	Remove road lighting and street furnitures	P2-Cal.B	5	5	20-Apr-17	25-Apr-17	88	0%	0					
LC12780	Road Pavement Demolition at Tong Yin Street	P2-Cal.B	5	5	26-Apr-17	02-May-17	88	0%	0					
Ground Investigation			P2-Cal.B	20	20	04-May-17	26-May-17	88	0%	0				
LC12849	UU Detection (After Road Diversion at TTA - Stage 2)	P2-Cal.B	4	4	04-May-17	08-May-17	88	0%	0					
LC12850	Trial Pit	P2-Cal.B	4	4	09-May-17	12-May-17	88	0%	0					
LC12851	Predrilling (LPDH-017) (Rig A)	P2-Cal.B	4	4	13-May-17	17-May-17	92	0%	0					
LC12852	Predrilling (LPDH-021) (Rig B)	P2-Cal.B	4	4	13-May-17	17-May-17	92	0%	0					
LC12853	Predrilling (LPDH-022) (Rig C)	P2-Cal.B	4	4	13-May-17	17-May-17	92	0%	0					
LC12854	Predrilling (LPDH-023) (Rig D)	P2-Cal.B	4	4	13-May-17	17-May-17	88	0%	0					
LC12855	Predrilling (LPDH-024) (Rig A)	P2-Cal.B	4	4	18-May-17	22-May-17	92	0%	0					
LC12856	Predrilling (LPDH-025) (Rig B)	P2-Cal.B	4	4	18-May-17	22-May-17	92	0%	0					
LC12857	Predrilling (LPDH-026) (Rig C)	P2-Cal.B	4	4	18-May-17	22-May-17	92	0%	0					
LC12858	Predrilling (LPDH-036) (Rig D)	P2-Cal.B	4	4	18-May-17	22-May-17	88	0%	0					
LC12859	Predrilling (LPDH-039) (Rig D)	P2-Cal.B	4	4	23-May-17	26-May-17	88	0%	0					
Foundation			P2-Cal.B	45	45	27-May-17	20-Jul-17	113	0%	0				
LC12871	Plant mobilization and set up for piling works	P2-Cal.B	10	10	27-May-17	08-Jun-17	88	0%	0					
LC12872	Installation of socketed H-Pile (A17) (Rig A)	P2-Cal.B	5	5	09-Jun-17	14-Jun-17	88	0%	0					
LC12873	Installation of socketed H-Pile (A16) (Rig A)	P2-Cal.B	5	5	15-Jun-17	20-Jun-17	88	0%	0					
LC12874	Installation of socketed H-Pile (A15) (Rig A)	P2-Cal.B	5	5	21-Jun-17	26-Jun-17	88	0%	0					
LC12875	Installation of socketed H-Pile (A14) (Rig A)	P2-Cal.B	5	5	27-Jun-17	03-Jul-17	88	0%	0					
LC12876	Installation of socketed H-Pile (A13) (Rig A)	P2-Cal.B	5	5	04-Jul-17	08-Jul-17	88	0%	0					
LC12877	Installation of socketed H-Pile (A12) (Rig A)	P2-Cal.B	5	5	10-Jul-17	14-Jul-17	88	0%	0					
LC12878	Installation of socketed H-Pile (A11) (Rig A)	P2-Cal.B	5	5	15-Jul-17	20-Jul-17	88	0%	0					
LC12884	Installation of socketed H-Pile (B10) (Rig B)	P2-Cal.B	5	5	09-Jun-17	14-Jun-17	113	0%	0					
LC12885	Installation of socketed H-Pile (B11) (Rig B)	P2-Cal.B	5	5	15-Jun-17	20-Jun-17	113	0%	0					
LC12886	Installation of socketed H-Pile (B12) (Rig B)	P2-Cal.B	5	5	21-Jun-17	26-Jun-17	113	0%	0					
LC12887	Installation of socketed H-Pile (B13) (Rig B)	P2-Cal.B	5	5	27-Jun-17	03-Jul-17	113	0%	0					
LC12888	Installation of socketed H-Pile (B14) (Rig B)	P2-Cal.B	5	5	04-Jul-17	08-Jul-17	113	0%	0					
LC12889	Installation of socketed H-Pile (B15) (Rig B)	P2-Cal.B	5	5	10-Jul-17	14-Jul-17	113	0%	0					
LC12890	Installation of socketed H-Pile (B16) (Rig B)	P2-Cal.B	5	5	15-Jul-17	20-Jul-17	113	0%	0					
LC12891	Installation of socketed H-Pile (C10) (Rig C)	P2-Cal.B	5	5	09-Jun-17	14-Jun-17	103	0%	0					
LC12892	Installation of socketed H-Pile (C9) (Rig C)	P2-Cal.B	5	5	15-Jun-17	20-Jun-17	103	0%	0					

█ Primary Baseline █ Critical Remaining Work
█ Actual Work ◆ Milestone
█ Remaining Work ▬ Summary

NE/2015/02 Tseung Kwan O - Lam Tin Tunnel-Road P2 and Associated Works

3 Months Rolling Programme
 (20 Apr 2017)
 Page: 5 of 7

Date	Revision	Checked	Approved
20-Apr-17			

Activity ID	Activity Name	Calendar	Original Duration	Remaining Duration	Start	Finish	Total Float	Activity % Complete	Variance - BL1	2017					
										Finish Date	Apr	May	Jun	Jul	Aug
LC12893	Installation of socketed H-Pile (C8) (Rig C)	P2-Cal.B	5	5	21-Jun-17	26-Jun-17	103	0%	0				█		
LC12894	Installation of socketed H-Pile (C7) (Rig C)	P2-Cal.B	5	5	27-Jun-17	03-Jul-17	103	0%	0					█	
LC12895	Installation of socketed H-Pile (C6) (Rig C)	P2-Cal.B	5	5	04-Jul-17	08-Jul-17	103	0%	0					█	
LC12896	Installation of socketed H-Pile (C5) (Rig C)	P2-Cal.B	5	5	10-Jul-17	14-Jul-17	103	0%	0					█	
LC12897	Installation of socketed H-Pile (C4) (Rig C)	P2-Cal.B	5	5	15-Jul-17	20-Jul-17	103	0%	0					█	
LC12900	Installation of socketed H-Pile (D20) (Rig D)	P2-Cal.B	5	5	09-Jun-17	14-Jun-17	108	0%	0				█		
LC12901	Installation of socketed H-Pile (D19) (Rig D)	P2-Cal.B	5	5	15-Jun-17	20-Jun-17	108	0%	0				█		
LC12902	Installation of socketed H-Pile (D18) (Rig D)	P2-Cal.B	5	5	21-Jun-17	26-Jun-17	108	0%	0				█		
LC12903	Installation of socketed H-Pile (D17) (Rig D)	P2-Cal.B	5	5	27-Jun-17	03-Jul-17	108	0%	0				█		
LC12904	Installation of socketed H-Pile (D16) (Rig D)	P2-Cal.B	5	5	04-Jul-17	08-Jul-17	108	0%	0				█		
LC12905	Installation of socketed H-Pile (D15) (Rig D)	P2-Cal.B	5	5	10-Jul-17	14-Jul-17	108	0%	0				█		
LC12906	Installation of socketed H-Pile (D14) (Rig D)	P2-Cal.B	5	5	15-Jul-17	20-Jul-17	108	0%	0				█		
P2 CH 399 - 500		P2-Cal.B	132	118	30-Mar-17 A	08-Sep-17	431		0						
ELS		P2-Cal.B	132	118	30-Mar-17 A	08-Sep-17	431		0						
LC14651	Construction of Prebored ~ Rig 1 Stage 2 at CH 432.5 to 467 (54 hole for 3 hole/days)	P2-Cal.B	18	4	30-Mar-17 A	24-Apr-17	455	77.78%	0			█			
LC14652	Construction of Prebored ~ Rig 1 Stage 3 at CH 501.5 end wall (44 hole for 3 hole/days)	P2-Cal.B	15	2	31-Mar-17 A	26-Apr-17	455	86.67%	-4			█			
LC14658	Construction of Prebored ~ Rig 2 Stage 3 at CH 467 to 501.5 (54 hole for 3 hole/days)	P2-Cal.B	18	12	10-Apr-17 A	05-May-17	434	33.33%	0			█			
LC14664	Installation of sheetpile wall (48m) ~ Stage 3 at CH 409.5 to 453.5	P2-Cal.B	15	15	20-Apr-17	09-May-17	431	0%	0				█		
LC14666	Installation of sheetpile wall (48m) ~ Stage 4 at CH 453.5 to 501.5	P2-Cal.B	15	15	10-May-17	26-May-17	431	0%	0				█		
LC14668	Installation of sheetpile wall (48m) ~ Stage 5 at CH 409.5 and 501.5 end wall	P2-Cal.B	25	25	27-May-17	26-Jun-17	431	0%	0				█		
LC14680	Excavation and shoring installation (Total: 25436m3 - 200m3/day)	P2-Cal.B	63	63	27-Jun-17	08-Sep-17	431	0%	0				█		
SR2		P2-Cal.B	80	77	13-Apr-17 A	22-Jul-17	715		0						
Retaining Wall SR2-A & B CH250 - 310		P2-Cal.B	80	77	13-Apr-17 A	22-Jul-17	715		0						
LC16680	Construction of Base Slab (SR2-A Bay 2) (Team E)	P2-Cal.B	10	7	13-Apr-17 A	27-Apr-17	715	30%	0			█			
LC16700	Construction of Wall Stem (SR2-A Bay 2) (Team E)	P2-Cal.B	10	10	28-Apr-17	11-May-17	715	0%	0				█		
LC16720	Construction of Base Slab (SR2-A Bay 3) (Team E)	P2-Cal.B	10	10	12-May-17	23-May-17	715	0%	0				█		
LC16740	Construction of Wall Stem (SR2-A Bay 3) (Team E)	P2-Cal.B	10	10	24-May-17	05-Jun-17	715	0%	0				█		
LC16760	Construction of Base Slab (SR2-A Bay 4) (Team E)	P2-Cal.B	10	10	06-Jun-17	16-Jun-17	715	0%	0				█		
LC16780	Construction of Wall Stem (SR2-A Bay 4) (Team E)	P2-Cal.B	10	10	17-Jun-17	28-Jun-17	715	0%	0				█		
LC16820	Construction of Wall Stem (SR2-A Bay 5) (Team E)	P2-Cal.B	10	10	29-Jun-17	11-Jul-17	715	0%	0				█		
LC16860	Construction of Wall Stem (SR2-A Bay 6) (Team E)	P2-Cal.B	10	10	12-Jul-17	22-Jul-17	715	0%	0				█		
SR2 CH 170 - 250		P2-Cal.B	60	60	06-May-17	17-Jul-17	555		0						
ELS		P2-Cal.B	60	60	06-May-17	17-Jul-17	555		0						
LC17145	Plant mobilization and set up for prebored works	P2-Cal.B	7	7	06-May-17	13-May-17	555	0%	0			█			
LC17146	Construction of prebored ~ P1 Stage 1 at CH236 to CH251.5 and end wall (34 hole for 3 hole/days)	P2-Cal.B	12	12	15-May-17	27-May-17	555	0%	0			█			
LC17147	Construction of prebored ~ P1 Stage 2 at CH208 to CH236 (42 hole for 3 hole/days)	P2-Cal.B	15	15	29-May-17	15-Jun-17	555	0%	0			█			
LC17148	Construction of prebored ~ P1 Stage 3 at CH181 to CH208 (42 hole for 3 hole/days)	P2-Cal.B	15	15	16-Jun-17	04-Jul-17	555	0%	0			█			
LC17149	Construction of prebored ~ P1 Stage 4 at CH168.5 to CH181 and end wall (31 hole for 3 hole/days)	P2-Cal.B	11	11	05-Jul-17	17-Jul-17	555	0%	0			█			
LC17150	Construction of prebored ~ P2 Stage 1 at CH236 to CH251.5 and end wall (34 hole for 3 hole/days)	P2-Cal.B	12	12	15-May-17	27-May-17	555	0%	0			█			
LC17151	Construction of prebored ~ P2 Stage 2 at CH208 to CH236 (42 hole for 3 hole/days)	P2-Cal.B	15	15	29-May-17	15-Jun-17	555	0%	0			█			
LC17152	Construction of prebored ~ P2 Stage 3 at CH181 to CH208 (42 hole for 3 hole/days)	P2-Cal.B	15	15	16-Jun-17	04-Jul-17	555	0%	0			█			
LC17153	Construction of prebored ~ P2 Stage 4 at CH168.5 to CH181 and end wall (31 hole for 3 hole/days)	P2-Cal.B	11	11	05-Jul-17	17-Jul-17	555	0%	0			█			
Portion IV & VII		P2-Cal.B	97	74	20-Mar-17 A	19-Jul-17	-55		0						
LC17656	Breaking of existing concrete (190m for 7m/day)	P2-Cal.B	28	38	20-Mar-17 A	06-Jun-17	-55	0%	-33			█			
LC17660	ELS along Existing EVA to BMCPC for Dia. 2100 Drain Pipe ~ Phase 1 (SMH9108 to SMH9104)	P2-Cal.B	12	12	07-Jun-17	20-Jun-17	-55	0%	0			█			
LC17665	ELS along Existing EVA to BMCPC for Dia. 2100 Drain Pipe ~ Phase 2 (SMH9104 to SMH9103)	P2-Cal.B	12	12	21-Jun-17	05-Jul-17	-55	0%	0			█			
LC17666	ELS along Existing EVA to BMCPC for Dia. 2100 Drain Pipe ~ Stage 3 (SMH9108 to SMH9109)	P2-Cal.B	12	12	06-Jul-17	19-Jul-17	-55	0%	0			█			


█	Primary Baseline	█	Critical Remaining Work
█	Actual Work	◆	Milestone
█	Remaining Work	▶	Summary

NE/2015/02 Tseung Kwan O - Lam Tin Tunnel-Road P2 and Associated Works

3 Months Rolling Programme (20 Apr 2017)
Page: 6 of 7

Date	Revision	Checked	Approved
20-Apr-17			

Activity ID	Activity Name	Calendar	Original Duration	Remaining Duration	Start	Finish	Total Float	Activity % Complete	Variance - BL1	BL1 Finish Date	2017					
											Apr	May	Jun	Jul	Aug	
New Reclaimed Section																
Marine Works																
Initial Works																
Steel Cofferdam and Water Gate																
MC10320	Installation of Temporary Steel Cofferdam (Phase 4 - 20 nos type 2B, 2C and 2D Steel Box)	P2-Cal.B	12	9	13-Apr-17 A	29-Apr-17	-14	25%	0							
MC10340	Foundation Preparation of Water Gate System	P2-Cal.B	14	7	08-Apr-17 A	27-Apr-17	-12	50%	0							
MC10360	Installation of Water Gate System	P2-Cal.B	7	7	12-Jun-17	19-Jun-17	-47	0%	0							
MC10380	Installation of Pumping System (incl. pipeline)	P2-Cal.B	7	7	16-Jun-17	23-Jun-17	-47	0%	0							
MC10400	Testing of Water Gate System	P2-Cal.B	7	7	24-Jun-17	03-Jul-17	-47	0%	0							
Dredging Work																
MC10540	Dredge CH300-350 (31520m3)	P2-Cal.B	16	16	04-Jul-17	21-Jul-17	-47	0%	0							
Full-scale Treatment of Cement S/S of Marine Sediment																
MC14100	Set up Cement S/S Treatment Facility	P2-Cal.B	21	21	25-May-17	19-Jun-17	219	0%	0							
MC14120	Loading and unloading Point	P2-Cal.B	60	60	20-Jun-17	29-Aug-17	219	0%	0							
Section 4 of the Works - Preservation and Protection of Existing Trees																
LC25260	Preservation and Protection of Existing Trees	P2-Cal.A	1424	1326	12-Jan-17 A	05-Dec-20	-69	6.88%	0							
Section 5 of the Works - Landscaping Works																
LC25320	Tree Transplanting Preparation Works	P2-Cal.B	180	103	12-Jan-17 A	22-Aug-17	-21	42.78%	0							



Primary Baseline
 Critical Remaining Work
 Actual Work
◆ Milestone
 Remaining Work
 Summary

NE/2015/02 Tseung Kwan O - Lam Tin Tunnel-Road P2 and Associated Works

3 Months Rolling Programme
(20 Apr 2017)
Page: 7 of 7


Date	Revision	Checked	Approved
20-Apr-17			

**APPENDIX R
RECORD OF LANDFILL GAS
MONITORING BY CONTRACTOR**


APPENDIX R - RECORD OF LANDFILL GAS MONITORING BY THE CONTRACTOR

Location	Date of Measurement	Sampling time	Weather Condition	Temperature (°C)	Methane (%)	Carbon dioxide (%)	Oxygen (%)
Portion III	1-Apr-17	7:30 AM	Cloudy	20	0	0	20.9
	1-Apr-17	1:01 PM	Cloudy	25	0	0	20.9
	3-Apr-17	7:29 AM	Sunny	18	0	0	20.9
	3-Apr-17	1:00 PM	Sunny	24	0	0	20.9
	5-Apr-17	7:30 AM	Cloudy	20	0	0	20.9
	5-Apr-17	1:01 PM	Cloudy	25	0	0	20.9
	6-Apr-17	7:30 AM	Sunny	20	0	0	20.9
	6-Apr-17	1:00 PM	Sunny	25	0	0	20.9
	7-Apr-17	8:30 AM	Sunny	21	0	0	20.9
	7-Apr-17	1:03 PM	Sunny	26	0	0	20.9
	8-Apr-17	8:30 AM	Sunny	20	0	0	20.9
	8-Apr-17	1:03 PM	Sunny	26	0	0	20.9
	10-Apr-17	8:30 AM	Sunny	23	0	0	20.9
	10-Apr-17	1:00 PM	Sunny	28	0	0	20.9
	11-Apr-17	8:30 AM	Sunny	23	0	0	20.9
	11-Apr-17	1:01 PM	Sunny	26	0	0	20.9
	12-Apr-17	8:27 AM	Sunny	23	0	0	20.9
	12-Apr-17	1:00 PM	Cloudy	27	0	0	20.9
	13-Apr-17	8:30 AM	Cloudy	21	0	0	20.9
	13-Apr-17	1:01 PM	Cloudy	27	0	0	20.9
	18-Apr-17	8:27 AM	Sunny	23	0	0	20.9
	18-Apr-17	1:03 PM	Sunny	29	0	0	20.9
	19-Apr-17	8:30 AM	Sunny	22	0	0	20.9
	19-Apr-17	1:00 PM	Sunny	28	0	0	20.9
	20-Apr-17	8:30 AM	Sunny	21	0	0	20.9
	20-Apr-17	1:02 PM	Sunny	27	0	0	20.9
	21-Apr-17	8:30 AM	Sunny	20	0	0	20.9
	21-Apr-17	1:05 PM	Sunny	28	0	0	20.9
	22-Apr-17	8:30 AM	Cloudy	23	0	0	20.9
	22-Apr-17	1:02 PM	Cloudy	25	0	0	20.9
24-Apr-17	8:28 AM	Sunny	21	0	0	20.9	
24-Apr-17	1:01 PM	Sunny	25	0	0	20.9	
25-Apr-17	8:30 AM	Sunny	22	0	0	20.9	
25-Apr-17	1:00 PM	Sunny	26	0	0	20.9	
26-Apr-17	8:30 AM	Cloudy	21	0	0	20.9	
26-Apr-17	1:01 PM	Cloudy	26	0	0	20.9	
27-Apr-17	8:30 AM	Cloudy	23	0	0	20.9	
27-Apr-17	1:02 PM	Cloudy	28	0	0	20.9	
28-Apr-17	8:30 AM	Sunny	24	0	0	20.9	
28-Apr-17	1:01 PM	Sunny	28	0	0	20.9	
29-Apr-17	8:28 AM	Sunny	23	0	0	20.9	
29-Apr-17	1:05 PM	Cloudy	27	0	0	20.9	


Methane



Carbon Dioxide



Oxygen



Title	Agreement No. CE 59/2015 (EP)	Scale	Project	CINOTECH
	Environmental Team for Tseung Kwan O - Lam Tin Tunnel – Design and Construction	N.T.S	No. MA16034	
Graphical Presentation of Landfill Gas Measurement	Date	Apr 17	Appendix R	

**APPENDIX S
UPDATED CONSTRUCTION NOISE
ASSESSMENT**

No update on Construction Noise Assessment in the reporting month

**APPENDIX T
PHOTO RECORD OF THE 1ST POST-
TRANSLOCATION CORAL
MONITORING SURVEY**

No post-translocation coral monitoring was conducted in the reporting month