


# Civil Engineering and Development Department

**Agreement No. CE 59/2015 (EP)  
Environmental Team for  
Tseung Kwan O – Lam Tin Tunnel  
Design and Construction**

**Monthly Environmental Monitoring and  
Audit Report for June 2018  
(version 2.0)**

Approved By

---

(Dr Priscilla Choy,  
Environmental Team Leader)

REMARKS:

The information supplied and contained within this report is, to the best of our knowledge, correct at the time of printing.

CINOTECH accepts no responsibility for changes made to this report by third parties.

**CINOTECH CONSULTANTS LTD**  
Room 1710, Technology Park,  
18 On Lai Street,  
Shatin, NT, Hong Kong  
Tel: (852) 2151 2083 Fax: (852) 3107 1388  
Email: [info@cinotech.com.hk](mailto:info@cinotech.com.hk)

## TABLE OF CONTENTS

|  |           |
|--|-----------|
| <b>EXECUTIVE SUMMARY</b> .....   | <b>1</b>  |
| Introduction .....   | 1         |
| Environmental Monitoring Works .....   | 1         |
| Key Information in the Reporting Month .....                                 | 3         |
| Key Construction Work in the reporting month & the next reporting month..... | 4         |
| Future Key Issues .....  | 5         |
| <b>1. INTRODUCTION</b> .....   | <b>7</b>  |
| Purpose of the Report.....   | 7         |
| Structure of the Report.....   | 7         |
| <b>2. PROJECT INFORMATION</b> .....  | <b>9</b>  |
| Background .....   | 9         |
| Project Organizations .....  | 9         |
| Construction Activities undertaken during the Reporting Month.....           | 10        |
| Status of Environmental Licences, Notification and Permits .....             | 11        |
| Summary of EM&A Requirements.....  | 13        |
| <b>3. AIR QUALITY</b> .....  | <b>14</b> |
| Monitoring Requirements .....  | 14        |
| Monitoring Locations.....  | 14        |
| Monitoring Equipment .....   | 14        |
| Monitoring Parameters and Frequency .....                                    | 15        |
| Monitoring Methodology .....   | 15        |
| Results and Observations .....   | 18        |
| <b>4. NOISE</b> .....  | <b>19</b> |
| Monitoring Requirements .....  | 19        |
| Monitoring Locations.....  | 19        |
| Monitoring Equipments .....  | 19        |
| Monitoring Methodology and QA/QC Procedure .....                             | 20        |
| Results and Observations .....   | 21        |
| Updated Construction Noise Assessment .....                                  | 22        |
| <b>5. WATER QUALITY</b> .....  | <b>23</b> |
| Monitoring Requirements .....  | 23        |
| Monitoring Locations.....  | 24        |
| Monitoring Equipments .....  | 24        |
| Monitoring Parameters and Frequency .....                                    | 26        |
| Monitoring Methodology .....   | 27        |
| Laboratory Analytical Methods .....  | 28        |
| QA/QC Requirements .....   | 28        |
| Decontamination Procedures .....   | 28        |
| Sampling Management and Supervision.....                                     | 28        |
| Results and Observations .....   | 29        |
| <b>6. ECOLOGY</b> .....  | <b>31</b> |
| Post-Translocation Coral Monitoring .....                                    | 31        |
| Event and Action Plan.....   | 31        |

|  |             |
|--|-------------|
| Results and Observations .....                                   | 錯誤! 尚未定義書籤。 |
| <b>7. CULTURAL HERITAGE .....</b>                                | <b>32</b>   |
| Monitoring Requirement .....                                     | 32          |
| Monitoring Locations .....                                       | 32          |
| Monitoring Equipment .....                                       | 32          |
| Monitoring Methodology .....                                     | 33          |
| Alert, Alarm and Action Levels .....                             | 33          |
| Results .....  | 33          |
| Mitigation Measures for Cultural Heritage .....                  | 33          |
| <b>8. LANDSCAPE AND VISUAL IMPACT REQUIREMENTS .....</b>         | <b>34</b>   |
| <b>9. LANDFILL GAS MONITORING .....</b>                          | <b>35</b>   |
| Monitoring Requirement .....                                     | 35          |
| Monitoring Parameters and Frequency .....                        | 35          |
| Monitoring Locations .....                                       | 35          |
| Monitoring Equipment .....                                       | 36          |
| Results and Observations .....                                   | 36          |
| <b>10. ENVIRONMENTAL AUDIT .....</b>                             | <b>37</b>   |
| Site Audits .....  | 37          |
| Implementation Status of Environmental Mitigation Measures ..... | 37          |
| <b>11. WASTE MANAGEMENT .....</b>                                | <b>38</b>   |
| <b>12. ENVIRONMENTAL NON-CONFORMANCE .....</b>                   | <b>39</b>   |
| Summary of Exceedances .....                                     | 39          |
| Summary of Environmental Non-Compliance .....                    | 39          |
| Summary of Environmental Complaint .....                         | 39          |
| Summary of Environmental Summon and Successful Prosecution ..... | 39          |
| <b>13. FUTURE KEY ISSUES .....</b>                               | <b>40</b>   |
| Key Issues for the Coming Month .....                            | 41          |
| Monitoring Schedule for the Next Month .....                     | 41          |
| <b>14. CONCLUSIONS AND RECOMMENDATIONS .....</b>                 | <b>42</b>   |
| Conclusions .....  | 42          |
| Recommendations .....  | 43          |

## LIST OF TABLES

|            |   |
|------------|---|
| Table I    | Non-compliance (exceedance) Recorded for the Project in the Reporting Month                             |
| Table II   | Summary Table for Key Information in the Reporting Month  |
| Table III  | Summary Table for Key Construction Work in the Reporting Month  |
| Table IV   | Summary Table for Site Activities in the next Reporting Period  |
| Table 2.1  | Key Project Contacts  |
| Table 2.2  | Summary Table for Major Site Activities in the Reporting Month  |
| Table 2.3  | Construction Programme Showing the Inter-Relationship with Environmental Protection/Mitigation Measures |
| Table 2.4  | Summary of the Status of Environmental Licences, Notification and Permits                               |
| Table 3.1  | Locations for Air Quality Monitoring  |
| Table 3.2  | Air Quality Monitoring Equipment  |
| Table 3.3  | Impact Dust Monitoring Parameters, Frequency and Duration   |
| Table 3.4  | Major Dust Source during Air Quality Monitoring   |
| Table 4.1  | Noise Monitoring Stations   |
| Table 4.2  | Noise Monitoring Equipment  |
| Table 4.3  | Noise Monitoring Parameters, Frequency and Duration   |
| Table 4.4  | Major Noise Source during Noise Monitoring  |
| Table 4.5  | Baseline Noise Level and Noise Limit Level for Monitoring Stations                                      |
| Table 5.1  | Groundwater Quality Monitoring Stations   |
| Table 5.2  | Marine Water Quality Monitoring Stations  |
| Table 5.3  | Water Quality Monitoring Equipment  |
| Table 5.4  | Water Quality Monitoring Parameters and Frequency   |
| Table 5.5  | Methods for Laboratory Analysis for Water Samples   |
| Table 5.6  | Summary of Groundwater Quality Monitoring Results   |
| Table 6.1  | Location and Physical attributes of the Coral Recipient Site  |
| Table 7.1  | Cultural Heritage Monitoring Equipment  |
| Table 7.2  | AAA Levels for Monitoring for Cultural Heritage   |
| Table 9.1  | Landfill Gas Monitoring Equipment   |
| Table 13.1 | Summary Table for Site Activities in the next Reporting Period  |

## LIST OF FIGURES

|           |  |
|-----------|--|
| Figure 1  | Site Layout Plan   |
| Figure 1a | Site Portions under Works Contract No. NE/2015/01 (Lam Tin Side)       |
| Figure 1b | Site Portions under Works Contract No. NE/2015/01 (Tseung Kwan O Side) |
| Figure 1c | Site Portions under Works Contract No. NE/2015/02                      |
| Figure 1d | Site Portions under Works Contract No. NE/2015/03                      |
| Figure 1e | Site Portions under Works Contract No. NE/2017/01                      |
| Figure 1f | Site Portions under Works Contract No. NE/2017/01                      |
| Figure 1g | Site Portions under Works Contract No. NE/2017/02                      |
| Figure 1h | Site Portions under Works Contract No. NE/2017/02                      |
| Figure 2  | Locations of Air Quality Monitoring Stations                           |
| Figure 3  | Locations of Construction Noise Monitoring Stations                    |
| Figure 4  | Locations of Groundwater Quality Monitoring Stations                   |
| Figure 5  | Locations of Marine Water Quality Monitoring Stations                  |
| Figure 6  | Locations of Landfill Gas Monitoring                                   |
| Figure 7  | Location of Post-translocation Coral Monitoring                        |
| Figure 8  | Location of Monitoring for Cultural Heritage                           |
| Figure 9  | Location of Water Quality Monitoring in Temporary Embayment            |

## **LIST OF APPENDICES**

- Appendix A Action and Limit Levels
- Appendix B Copies of Calibration Certificates
- Appendix C Weather Information
- Appendix D Environmental Monitoring Schedules
- Appendix E 1-hour TSP Monitoring Results and Graphical Presentations
- Appendix F 24-hour TSP Monitoring Results and Graphical Presentations
- Appendix G Noise Monitoring Results and Graphical Presentations
- Appendix H Groundwater Quality Monitoring Results, Graphical Presentations and Laboratory Testing Reports
- Appendix I Marine Water Quality Monitoring Results and Graphical Presentations
- Appendix J Quality Control Reports for Laboratory Analysis
- Appendix K Summary of Exceedance
- Appendix L Site Audit Summary
- Appendix M Event and Action Plans
- Appendix N Implementation Schedule And Recommended Mitigation Measures
- Appendix O Summaries of Environmental Complaint, Warning, Summon and Notification of Successful Prosecution
- Appendix P Waste Generation in the Reporting Month
- Appendix Q Tentative Construction Programme
- Appendix R Record of Landfill Gas Monitoring by Contractor
- Appendix S Updated Construction Noise Assessment
- Appendix T Cultural Heritage Monitoring Results
- Appendix U Piezometer Monitoring Results

## EXECUTIVE SUMMARY

### Introduction

1. This is the 20<sup>th</sup> Environmental Monitoring and Audit (EM&A) Report prepared by Cinotech Consultants Limited for the “Agreement No. CE 59/2015 (EP) Environmental Team for Tseung Kwan O – Lam Tin Tunnel – Design and Construction” (hereinafter called “the Project”). This report documents the findings of EM&A Works conducted in June 2018.
2. During the reporting month, the following works contracts were undertaken:
  - Contract No. NE/2015/01 – Tseung Kwan O – Lam Tin Tunnel – Main Tunnel and Associated Works;
  - Contract No. NE/2015/02 – Tseung Kwan O – Lam Tin Tunnel – Road P2 and Associated Works;
  - Contract No. NE/2015/03 – Tseung Kwan O – Lam Tin Tunnel – Northern Footbridge;
  - Contract No. NE/2017/01 – Tseung Kwan O – Lam Tin Tunnel – Tseung Kwan O Interchange and Associated Works
  - Contract No. NE/2017/02 – Tseung Kwan O – Lam Tin Tunnel – Road P2/D4 and Associated Works.

### Environmental Monitoring Works

3. Environmental monitoring for the Project was performed in accordance with the EM&A Manual and the monitoring results were checked and reviewed. Site Inspections/Audits were conducted once per week. The implementation of the environmental mitigation measures, Event Action Plans and environmental complaint handling procedures were also checked.
4. Summary of the non-compliance (exceedance) in the reporting month for the Project is tabulated in **Table I**.

**Table I Non-compliance (exceedance) Record for the Project in the Reporting Month**

| Environment<br>al Monitoring                                     | No. of Non-compliance<br>(Exceedance) |                    | No. of Non-compliance (Exceedance)<br>due to Construction Activities of this<br>Project |             | Action<br>Taken               |
|--|---------------------------------------|--------------------|---|-------------|-------------------------------|
|  | Action Level                          | Limit Level        | Action Level  | Limit Level |                               |
| Air Quality  | 0                                     | 0                  | 0   | 0           | N/A                           |
| Noise  | 4                                     | 12                 | 0 <sup>(1)</sup>  | 12          | Refer to<br>Appendix K &<br>O |
| Groundwater<br>Quality   | 0                                     | 12                 | 0   | 0           | N/A                           |
| Marine Water<br>Quality  | 0                                     | 0                  | 0   | 0           | N/A                           |
| Groundwater<br>Level<br>Monitoring<br>(Piezometer<br>Monitoring) | 0                                     | N/A <sup>(2)</sup> | 0   | 0           | N/A                           |
| Ecological   | N/A                                   | N/A                | N/A   | N/A         | N/A                           |
| Cultural<br>Heritage   | 0                                     | 0                  | 0   | 0           | N/A                           |
| Landfill Gas   | 0                                     | 0                  | 0   | 0           | N/A                           |

Note: (1) Environmental complaints received in June 2018 are still under investigation.  
(2) No Limit Level for Groundwater Level Monitoring (Piezometer Monitoring).

*Action Taken by the Contractor after received the complaint (Details of the complaints are shown in **Appendix O**)*

- Additional water filter tank was adopted to reduce emission of dark smoke and exhaust;
- Preinstalled speaker was used on derrick barge to minimize the noise disturbance from on-site communication.
- Street washing truck would be provided once a week to clean the dust on the public street.
- Additional notice would be set up to remind the truck driver to perform wheel-washing properly before leaving site;
- Deployed staff at the access to check the dump trucks to ensure the dump truck are properly covered and wheel-washed before leaving site;
- Ensured blasting doors were closed while blasting associated works was undertaken in the tunnel;
- Installed steel-type blasting door mounted with sound absorptive lining to absorb construction noise in the tunnel;
- Erected movable cantilever noise barriers and the breaker head was wrapped with Silent Mat and TMD;
- Powered mechanical equipment (PME) for rock breaking were equipped with TMD and SilentMat;
- Drill rig was covered with Silent Mat and TMR.

#### *Air Quality Monitoring*

5. All 1-hour TSP monitoring was conducted as scheduled in the reporting month. No Action/Limit Level exceedance was recorded.
6. All 24-hour TSP monitoring was conducted as scheduled in the reporting month. No Action/Limit Level exceedance was recorded.

#### *Construction Noise Monitoring*

7. All noise monitoring was conducted as scheduled in the reporting month. Four (4) Action Level exceedance was recorded due to the documented complaints received in this reporting month. Twelve (12) Limit Level exceedance was recorded in the reporting month.

#### *Water Quality Monitoring*

8. Groundwater quality monitoring was conducted as scheduled in the reporting month. No Action Level and Fourteen (14) Limit Level exceedances were recorded in the reporting month.
9. All marine water monitoring was conducted as scheduled in the reporting month. No Action/Limit Level exceedance was recorded.
10. Construction phase daily piezometer monitoring by the Contractor commenced in June 2018. No Action Level exceedance was recorded in the reporting month.

*Ecological Monitoring*

11. Post-translation coral monitoring survey shall be conducted once every 3 months for a period of 12 months after completion of coral translocation. The post-translocation coral monitoring surveys were completed in November 2017.

*Monitoring on Cultural Heritage*

12. Monitoring of impacts on Cultural Heritage at Cha Kwo Ling Tin Hau Temple commenced in April 2017. No Alert Alarm and Action (AAA) Level exceedance was recorded in the reporting month.

*Landscape and Visual Monitoring and Audit*

13. The implementation of landscape and visual mitigation measures was checked during the environmental site inspections. Recommended follow-up actions have been discharged by the Contractor. Details of the audit findings and implementation status are presented in Section 10.

*Landfill Gas Monitoring*

14. Monitoring of landfill gases commenced in December 2016 and were carried out by the Contractor at excavation location, Portion III. No Limit Level exceedance was recorded.

*Environmental Site Inspection*

15. Joint weekly site inspections were conducted by representatives of the Contractor, Engineer and Environmental Team. The representative of the IEC joined the site inspection for NE/2015/01, NE/2015/02, NE/2015/03, NE/2017/01 and NE/2017/02 on 27, 13, 13, 27, 13 June 2018 respectively. Details of the audit findings and implementation status are presented in Section 10.

*Waste Management*

16. Wastes generated from this Project include inert construction and demolition (C&D) materials, non-inert C&D materials and marine sediments. Details of waste management data is presented in Section 11 and **Appendix P**.

**Key Information in the Reporting Month**

17. Summary of key information in the reporting month is tabulated in **Table II**.

**Table II Summary Table for Key Information in the Reporting Month**

| Event  | Event Details |   | Action Taken        | Status   | Remark                 |
|--|---------------|---|---------------------|----------|------------------------|
|  | Number        | Nature  |                     |          |                        |
| Complaint received by Project Team / Complaint referred by EPD (June 2018) | 10            | Construction dust/ Noise nuisance/ Odour/ Dark Smoke/ Waste management/ Landscape | Under investigation | On-going | Details refer to App O |
| Complaint received by Project Team /                                       | 22            | Construction dust / Noise nuisance/ Odour   | Under investigation | On-going |                        |



| Event  | Event Details |   | Action Taken  | Status   | Remark |
|--|---------------|---|---|----------|--------|
|  | Number        | Nature                                  |   |          |        |
| Complaint referred by EPD (May 2018)   |               |   |   |          |        |
| Complaint received by Project Team / Complaint referred by EPD (April 2018)* | 15            | Noise nuisance / Light pollution/ Odour | Erection of acoustics barriers/ Regular site checking/ Installation of water filter tanks/ Adjust illumination angle of spotlight | On-going |        |
| Notifications of any summons & prosecutions received                         | 0             | ---                                     | N/A   | N/A      | ---    |

Note (\*): Non-compliances were recorded on 16<sup>th</sup>, 18<sup>th</sup> and 23<sup>rd</sup> April 2018 for Contract No. NE/2015/02 due to non-conformance with the proposed quantity of powered mechanical equipment stated in the CNMP. Details of investigation are presented in **Appendix O**.

### Key Construction Work in the reporting month & the next reporting month

18. Summary of key construction work in the reporting month is tabulated in **Table III**.

**Table III Summary Table for Key Construction Work in the Reporting Month**

| Contract No. | Project Title   | Site Activities (June 2018)  |  |
|--------------|---|--|--|
| NE/2015/01   | Tseung Kwan O – Lam Tin Tunnel – Main Tunnel and Associated Works | Lam Tin Interchange  | 1) EHC2 U-Trough<br>2) Site Formation – Area 1G1, Area 1G2, Area 2, Area 3, Area 4 & Area 5            |
|              |   | Main Tunnel  | 1) Main tunnel Excavation  |
|              |   | TKO Interchange  | 1) Haul Road Construction, Site Formation and Slope Works<br>2) Steel Platform for Bridge Construction |
| NE/2015/02   | Tseung Kwan O – Lam Tin Tunnel – Road P2 and Associated Works     | 1) Lower ground works at Portion V<br>2) Cable diversion works at Portion IV and V<br>3) Pre-bore and interlocking pipe pile works for 2100 pipe at Portion IV and Portion VII<br>4) Sheet pile works for decked U-trough at Portion V<br>5) ELS works for 2100 pipe and P2A RW at Portion IV<br>6) Installation of DN 1500 Temporary Steel Corrugated Pipe at Portion V<br>7) Retaining wall works at Portion VIII<br>8) Dredging Works and Armour Rock Removal at Portion IX<br>9) Treatment of Marine Sediment at Area A<br>10) Rock filling works at Portion IX<br>11) Construction of U-trough structure at Portion VIII<br>12) General Site Clearance and Hoarding |  |

|            |   | Erection   |
|------------|---|--|
| NE/2015/03 | Tseung Kwan O –<br>Lam Tin Tunnel –<br>Northern Footbridge                                  | 1) Falsework erection of main bridge deck<br>2) Construction of Pile Cap PC4 and Sump Pit<br>3) Install steel mould and rebar fixing of main deck  |
| NE/2017/01 | Tseung Kwan O –<br>Lam Tin Tunnel –<br>Tseung Kwan O<br>Interchange and<br>Associated Works | 1) Site Accommodation<br>2) Erection of Temporary Platform<br>3) Pre-drilling  |
| NE/2017/02 | Tseung Kwan O –<br>Lam Tin Tunnel –<br>Road P2/D4 and<br>Associated Works                   | 4) Trial pit<br>5) Underground utilities detection<br>6) Temporary traffic arrangement Setup<br>7) Site office erection<br>8) Communication Liaison Center erection<br>9) Modification of traffic island<br>10) Fencing erection<br>11) Predrilling<br>12) Construction of Temporary cycle track |

### Future Key Issues

19. The future key environmental issues in the coming month include:

**Table IV Summary Table for Site Activities in the next Reporting Period**

| Contract No. and Project Title  | Site Activities (July 2018)   | Key environmental issues *  |                                   |
|---|---|---|-----------------------------------|
| NE/2015/01 -<br>Tseung Kwan O – Lam Tin Tunnel – Main Tunnel and Associated Works | Lam Tin Interchange   | 1) EHC2 U-Trough<br>2) Site Formation – Area 1G1, Area 1G2, Area 2, Area 3, Area 4 & Area 5             | (A) / (B) / (C) / (D) / (E) / (G) |
|   | Main Tunnel   | 1) Main Tunnel Excavation   | (B)                               |
|   | TKO Interchange   | 1) Haul Road Construction and Site Formation & Slope Works<br>2) Steel Platform for Bridge Construction | (A) / (C) / (D) / (E) / (F) / (I) |
| NE/2015/02 -<br>Tseung Kwan O – Lam Tin Tunnel – Road P2 and Associated Works     | 1) Operation of Double Watertgate<br>2) Treatment works of S/S Treatment Facility at Area A<br>3) Dredging works and reclamation works at Portion IX<br>4) Rock filling works at Portion IX<br>5) Installation of DN 1500 Temporary Steel Corrugated Pipe at Portion V<br>6) Installation of band drain in Portion IX | (A) / (B) / (C) / (D) / (E) / (G) / (I)   |                                   |

|   |  |                             |
|---|--|-----------------------------|
|   | 7) Laying of geotextile in Portion IX<br>8) Removal of existing seawall blocks at Portion IV & VII<br>9) Reconstruction of existing outfall and installation of DN2100 drainage system at Portion IV & VII<br>10) Laying of geotextile in Portion IX   |                             |
| NE/2015/03 - Tseung Kwan O – Lam Tin Tunnel – Northern Footbridge             | 1) Pier Construction at East Pier<br>2) Pier Construction at West Pier   | (A) / (B) / (C) / (D) / (E) |
| NE/2017/01 – Tseung Kwan O Interchange and Associated Works                   | 1) Site Accommodation<br>2) Erection of Temporary Platform<br>3) Pre-drilling  | (A) / (B) / (E) / (F) / (G) |
| NE/2017/02 – Tseung Kwan O - Lam Tin Tunnel - Road P2/D4 and Associated Works | 1) Trial pit<br>2) Underground utilities detection<br>3) Temporary traffic arrangement Setup<br>4) Site office erection<br>5) Communication Liaison Center erection<br>6) Modification of traffic island<br>7) Fencing erection<br>8) Pre-drilling<br>9) Construction of Temporary cycle track<br>10) Construction of drainage and watermain | (A) / (B) / (E) / (F) / (G) |

Note:

- (A) Watering for dust generation from haul road, stockpiles of dusty materials, exposed site area, excavation works and rock breaking activities;
- (B) Noisy construction activity such as rock-breaking activities and piling works;
- (C) Runoff from exposed slope or site area;
- (D) Wastewater and runoff discharge from site;
- (E) Accumulation of silt, mud and sand along U-channels and sedimentation tanks;
- (F) Set up and implementation of temporary drainage system for the surface runoff;
- (G) Storage of chemicals/fuel and chemical waste/waste oil on site;
- (H) Accumulation and storage of general and construction waste on site; and
- (I) Marine water quality impact and indirect impact to coral communities due to marine construction for TKO-LTT reclamation.

## 1. INTRODUCTION

- 1.1 Cinotech Consultants Limited (Cinotech) was commissioned by Civil Engineering and Development Department (CEDD) as the Environmental Team (ET) to undertake environmental monitoring and auditing services for the Works Contracts involved in the implementation of Tseung Kwan O – Lam Tin Tunnel (TKO-LTT) project to ensure that the environmental performance of the Works Contracts comply with the requirements specified in the Environmental Permit (EP), Environmental Monitoring & Audit (EM&A) Manual, Environmental Impact Assessment (EIA) Report of the TKO-LTT project and other relevant statutory requirements. This is the 20<sup>th</sup> Monthly EM&A report summarizing the EM&A works for the Project in June 2018.

### **Purpose of the Report**

- 1.2 This is the 20<sup>th</sup> Monthly EM&A Report which summarises the impact monitoring results and audit findings for the EM&A programme during the reporting period in June 2018.

### **Structure of the Report**

- 1.3 The structure of the report is as follows:

Section 1: **Introduction** – purpose and structure of the report.

Section 2: **Contract Information** – summarises background and scope of the Contract, site description, project organization and contact details, construction programme, the construction works undertaken and the status of Environmental Permits/Licenses during the reporting month.

Section 3: **Air Quality Monitoring** – summarises the monitoring parameters, monitoring programmes, monitoring methodologies, monitoring frequency, monitoring locations, Action and Limit Levels, monitoring results and Event / Action Plans.

Section 4: **Noise Monitoring** – summarises the monitoring parameters, monitoring programmes, monitoring methodologies, monitoring frequency, monitoring locations, Action and Limit Levels, monitoring results and Event / Action Plans.

Section 5: **Water Quality Monitoring** – summarises the monitoring parameters, monitoring programmes, monitoring methodologies, monitoring frequency, monitoring locations, Action and Limit Levels, monitoring results and Event / Action Plans.

Section 6: **Ecological Monitoring** – summarises the monitoring parameters, monitoring programmes, monitoring methodologies, monitoring frequency, monitoring locations and Action and Limit Levels, monitoring results and Event / Action Plans.

Section 7: **Cultural Heritage** – summarises the monitoring parameters, monitoring programmes, monitoring methodologies, monitoring frequency, monitoring locations and monitoring results.

Section 8: **Landscape and Visual Monitoring Requirements** – summarises the

requirements of landscape and visual monitoring

Section 9: **Landfill Gas Monitoring** – summarises the monitoring parameters, monitoring programmes, monitoring methodologies, monitoring frequency, monitoring locations, monitoring results and Limit Levels and Action Plan

Section 10: **Environmental Site Inspection** – summarises the audit findings of the weekly site inspections undertaken within the reporting month.

Section 11: **Waste Management** – summarises the waste management data in the reporting month.

Section 12: **Environmental Non-conformance** – summarises any monitoring exceedance, environmental complaints, environmental summons and successful prosecutions within the reporting month.

Section 13: **Future Key Issues** – summarises the impact forecast and monitoring schedule for the next three months.

Section 14: **Conclusions and Recommendation**

## 2. PROJECT INFORMATION

### Background

- 2.1 In 2002, Civil Engineering and Development Department (CEDD) commissioned an integrated planning and engineering study under Agreement No. CE 87/2001 (CE) “Further Development of Tseung Kwan O – Feasibility Study” (the “TKO Study”) to formulate a comprehensive plan for further development of TKO New Town. It recommended to further develop TKO to house a total population of 450,000 besides the district’s continuous commercial and industrial developments.
- 2.2 At present, the Tseung Kwan O Tunnel is the main connection between Tseung Kwan O (TKO) and other areas in the territory. To cope with the anticipated transport need, the TKO Study recommended the provision of Tseung Kwan O – Lam Tin Tunnel (TKO-LTT) (hereinafter referred to as “the Project”) and Cross Bay Link (CBL) to meet the long-term traffic demand between TKO and the external areas. The site layout plan for the Project is shown in **Figure 1**.
- 2.3 The Environmental Impact Assessment (EIA) Report for the TKO-LTT project was approved under the Environmental Impact Assessment Ordinance (EIAO) in July 2013. The corresponding Environmental Permit (EP) was issued in August 2013 (EP no.: EP-458/2013). Variations to the EP was applied and the latest EP (EP no.: EP-458/2013/C) was issued by the Director of Environmental Protection (DEP) in January 2017.
- 2.4 The commencement dates of construction of this Project is:
- Contract No. NE/2015/01 and Contract No. NE/2015/02: 7 November 2016.
  - Contract No. NE/2015/03: 29 May 2017.
  - Contract No. NE/2017/02: 15 March 2018.
  - Contract No. NE/2017/01: 23 April 2018.

### Project Organizations

- 2.5 Different parties with different levels of involvement in the project organization include:
- Project Proponent – Civil Engineering and Development Department (CEDD)
  - The Engineer and the Engineer’s Representative (ER) – AECOM
  - Environmental Team (ET) – Cinotech Consultants Limited (Cinotech)
  - Independent Environmental Checker (IEC) – AnewR Consulting Limited (AnewR)
- 2.6 The key contacts of the Project are shown in **Table 2.1**.

**Table 2.1 Key Project Contacts**

| Party    | Role                              | Contact Person           | Phone No. | Fax No.   |
|----------|-----------------------------------|--------------------------|-----------|-----------|
| CEDD     | Project Proponent                 | Mr. Chiang Nin Tat, Eric | 2301 1384 | 2739 0076 |
| AECOM    | Engineer’s Representative         | Mr. KY Chan              | 3922 9000 | 2759 1698 |
| Cinotech | Environmental Team                | Dr. Priscilla Choy       | 2151 2089 | 3107 1388 |
|          |                                   | Ms. Ivy Tam              | 2151 2090 |           |
| AnewR    | Independent Environmental Checker | Mr. Adi Lee              | 2618 2836 | 3007 8648 |

**Construction Activities undertaken during the Reporting Month**

2.7 The major site activities undertaken in the reporting month included:

**Table 2.2 Summary Table for Major Site Activities in the Reporting Month**

| <b>Contract No.</b> | <b>Project Title</b>  | <b>Site Activities (June 2018)</b>  |  |
|---------------------|---|---|--|
| NE/2015/01          | Tseung Kwan O – Lam Tin Tunnel – Main Tunnel and Associated Works               | Lam Tin Interchange   | 1) EHC2 U-Trough<br>2) Site Formation – Area 1G1, Area 1G2, Area 2 , Area 3, Area 4 & Area 5           |
|                     |   | Main Tunnel   | 1) Main tunnel Excavation  |
|                     |   | TKO Interchange   | 1) Haul Road Construction, Site Formation and Slope Works<br>2) Steel Platform for Bridge Construction |
| NE/2015/02          | Tseung Kwan O – Lam Tin Tunnel – Road P2 and Associated Works                   | 1) Installation of DN2100 Concrete Pipe at Portion IV & VII<br>2) ELS Installation for U-Trough B at Portion V & VI<br>3) Construction of Retaining Wall and U-Trough A at Portion VIII<br>4) Enhancement of Temporary Steel Cofferdam at Portion IX<br>5) Dredging Works and Armour Rock Removal at Portion IX<br>6) Treatment of Marine Sediment at Area A<br>7) General Site Clearance and Hoarding Erection |  |
| NE/2015/03          | Tseung Kwan O – Lam Tin Tunnel – Northern Footbridge                            | 1) Construction of lift shaft and sum pit<br>2) Construction of main deck   |  |
| NE/2017/01          | Tseung Kwan O – Lam Tin Tunnel – Tseung Kwan O Interchange and Associated Works | 1) Site Accommodation<br>2) Erection of Temporary Platform<br>3) Pre-drilling   |  |
| NE/2017/02          | Tseung Kwan O – Lam Tin Tunnel – Road P2/D4 and Associated Works                | 1) Trial pit<br>2) Underground utilities detection<br>3) Temporary traffic arrangement Setup<br>4) Site office erection<br>5) Communication Liaison Center erection<br>6) Modification of traffic island<br>7) Fencing erection<br>8) Modification of traffic island<br>9) Pre-drilling<br>10) Construction of Temporary cycle track  |  |

2.8 The construction programme showing the inter-relationship with environmental protection/mitigation measures are presented in **Table 2.3**.

**Table 2.3 Construction Programme Showing the Inter-Relationship with Environmental Protection/Mitigation Measures**

| Construction Works        | Major Environmental Impact                             | Control Measures   |
|---------------------------|--|--|
| As mentioned in Table 2.2 | Noise, dust impact, water quality and waste generation | <ul style="list-style-type: none"> <li>• Sufficient watering of the works site with active dust emitting activities</li> <li>• Properly cover the stockpiles</li> <li>• On-site waste sorting and implementation of trip ticket system</li> <li>• Appropriate desilting/sedimentation devices provided on site for treatment before discharge</li> <li>• Use of quiet plant and well-maintained construction plant</li> <li>• Provide movable noise barrier</li> </ul> |

**Status of Environmental Licences, Notification and Permits**

2.9 A summary of the relevant permits, licences, and/or notifications on environmental protection for this Project is presented in Table 2.4.

**Table 2.4 Summary of the Status of Environmental Licences, Notification and Permits**

| Contract No.   | Permit / License No.                 | Valid Period |            | Status |
|--|--------------------------------------|--------------|------------|--------|
|  |                                      | From         | To         |        |
| <b>Environmental Permit (EP)</b>   |                                      |              |            |        |
| N/A  | EP-458/2013/C                        | 20/1/2017    | N/A        | Valid  |
| <b>Notification pursuant to Air Pollution Control (Construction Dust) Regulation</b> |                                      |              |            |        |
| NE/2015/01   | EPD Ref no.: 405305                  | 21/07/2016   | N/A        | Valid  |
|  | EPD Ref no.: 405582                  | 28/07/2016   | N/A        | Valid  |
| NE/2015/02   | EPD Ref no.: 406100                  | 12/08/2016   | N/A        | Valid  |
| NE/2015/03   | EPD Ref no.: 416072                  | 26/04/2017   | N/A        | Valid  |
| NE/2017/02   | EPD Ref no.: 429867                  | 19/01/2018   | N/A        | Valid  |
| NE/2017/01   | EPD Ref no.: 430070                  | 25/01/2018   | N/A        | Valid  |
| <b>Billing Account for Construction Waste Disposal</b>                               |                                      |              |            |        |
| NE/2015/01   | Account No. 7025431                  | 11/07/2016   | N/A        | Valid  |
| NE/2015/02   | Account No. 7025654                  | 16/08/2016   | N/A        | Valid  |
| NE/2015/03   | Account No. 7026805                  | 30/12/2016   | N/A        | Valid  |
| NE/2017/02   | Account No. 7029651                  | 22/12/2017   | N/A        | Valid  |
| NE/2017/01   | Account No. 7029994                  | 01/02/2018   | N/A        | Valid  |
| <b>Vessel Billing Account under construction waste disposal charging scheme</b>      |                                      |              |            |        |
| NE/2015/01   | Account No. 7027764                  | 29/01/2018   | 10/05/2018 | Valid  |
| <b>Registration of Chemical Waste Producer</b>                                       |                                      |              |            |        |
| NE/2015/01   | Waste Producer No. 5218-290-L2881-02 | 22/08/2016   | N/A        | Valid  |
|  | Waste Producer No. 5213-833-L2532-03 | 22/08/2016   | N/A        | Valid  |



| Contract No.  | Permit / License No.                 | Valid Period |            | Status                |
|---|--------------------------------------|--------------|------------|-----------------------|
|   |                                      | From         | To         |                       |
| NE/2015/02  | Waste Producer No. 5213-838-C4094-01 | 23/08/2016   | N/A        | Valid                 |
| NE/2015/03  | Waste Producer No. 5213-265-W3435-04 | 19/07/2017   | N/A        | Valid                 |
| NE/2017/02  | Waste Producer No. 5213-833-Z4004-04 | 01/02/2018   | N/A        | Valid                 |
| NE/2017/01  | Waste Producer No. 5213-833-C4262-01 | 12/02/2018   | N/A        | Valid                 |
| <b>Effluent Discharge License under Water Pollution Control Ordinance</b> |                                      |              |            |                       |
| NE/2015/01  | WT00025806-2016                      | 22/11/2016   | 30/11/2021 | Valid                 |
|   | WT00026212-2016                      | 16/05/2017   | 30/11/2021 | Valid                 |
|   | WT00027354-2017                      | 22/03/2017   | 31/03/2022 | Valid                 |
|   | WT00027405-2017                      | 22/03/2017   | 31/03/2022 | Valid                 |
|   | WT-00028495-2017                     | 11/08/2017   | 31/08/2022 | Valid                 |
| NE/2015/02  | WT00026386-2016                      | 15/12/2016   | 31/12/2021 | Valid                 |
|   | WT00027226-2017                      | 23/02/2017   | 28/02/2022 | Valid                 |
| NE/2015/03  | WT00027295-2017                      | 20/03/2017   | 18/04/2019 | Valid                 |
|   | WT00027266-2017                      | 08/03/2017   | 18/04/2019 | Valid                 |
| NE/2017/01  | WT00030711-2018                      | 11/04/2018   | 30/04/2023 | Valid                 |
|   | WT00030716-2018                      | 23/05/2018   | 31/05/2023 | Valid                 |
| NE/2017/02  | WT00030654-2018                      | 16/04/2018   | 30/04/2023 | Valid                 |
| <b>Construction Noise Permit (CNP)</b>                                    |                                      |              |            |                       |
| NE/2015/01  | GW-RE1024-17                         | 23/12/2017   | 22/06/2018 | Expired on 22/06/2018 |
|   | GW-RE0140-18                         | 06/03/2018   | 05/09/2018 | Valid                 |
|   | GW-RE0278-18                         | 26/04/2018   | 24/06/2018 | Expired on 24/06/2018 |
|   | GW-RE0309-18                         | 04/05/2018   | 02/08/2018 | Valid                 |
|   | GW-RE0371-18                         | 05/06/2018   | 04/09/2018 | Valid                 |
|   | GW-RE0373-18                         | 01/06/2018   | 30/09/2018 | Valid                 |
|   | GW-RE0418-18                         | 23/06/2018   | 22/12/2018 | Valid                 |
|   | GW-RE0421-18                         | 25/06/2018   | 24/08/2018 | Valid                 |
| NE/2015/02  | GW-RE0916-17                         | 02/12/2017   | 01/06/2018 | Expired on 01/06/2018 |
|   | GW-RE0353-18                         | 16/05/2018   | 15/11/2018 | Valid                 |
|   | GW-RE0231-18                         | 30/04/2018   | 29/07/2018 | Valid                 |
|   | GW-RE0243-18                         | 01/05/2018   | 31/10/2018 | Valid                 |
|   | GW-RE0241-18                         | 11/04/2018   | 10/10/2018 | Valid                 |
|   | GW-RE0384-18                         | 02/06/2018   | 01/12/2018 | Valid                 |

| Contract No.                          | Permit / License No. | Valid Period |            | Status |
|---------------------------------------|----------------------|--------------|------------|--------|
|                                       |                      | From         | To         |        |
|                                       | GW-RE0434-18         | 16/06/2018   | 15/01/2019 | Valid  |
| NE/2017/01                            | GW-RE0442-18         | 21/06/2018   | 02/11/2018 | Valid  |
| <b>Marine Dumping Permit</b>          |                      |              |            |        |
|                                       | EP/MD/18-129         | 16/03/2018   | 15/09/2018 | Valid  |
| NE/2015/02                            | EP/MD/18-139         | 15/05/2018   | 14/11/2018 | Valid  |
|                                       | EP/MD/19-011         | 01/07/2018   | 31/07/2018 | Valid  |
| <b>Specified Process (SP) License</b> |                      |              |            |        |
| NE/2015/01                            | L-11-053             | 09/03/2018   | 08/03/2021 | Valid  |

### Summary of EM&A Requirements

- 2.10 The EM&A programme requires construction noise monitoring, air quality monitoring, water quality monitoring, environmental site audit, etc. The EM&A requirements for each parameter are described in the following sections, including:
- All monitoring parameters;
  - Action and Limit levels for all environmental parameters;
  - Event Action Plans;
  - Environmental mitigation measures, as recommended in the Project EIA Report.
- 2.11 The advice on the implementation status of environmental protection and pollution control/mitigation measures is summarized in Section 10 of this report.
- 2.12 This report presents the monitoring results, observations, locations, equipment, period, methodology and QA/QC procedures of the monitoring parameters of the required environmental monitoring works and audit works for the Project in June 2018.

### 3. AIR QUALITY

#### Monitoring Requirements

- 3.1 According to EM&A Manual of the Project, 1-hour and 24-hour TSP monitoring are required to monitor the air quality. For regular impact monitoring, a sampling frequency of at least once in every six days shall be undertaken at all of the monitoring stations for 24-hour TSP monitoring. For 1-hour TSP monitoring, the sampling frequency of at least three times in every six days shall be undertaken when the highest dust impact occurs. **Appendix A** shows the established Action/Limit Levels for the environmental monitoring works.

#### Monitoring Locations

- 3.2 Six designated monitoring stations were selected for air quality monitoring programme. **Table 3.1** describes the air quality monitoring locations, which are also depicted in **Figure 2**.

**Table 3.1 Locations for Air Quality Monitoring**

| Monitoring Stations       | Location  | Location of Measurement |
|---------------------------|---|-------------------------|
| AM1                       | Tin Hau Temple  | Ground Level            |
| AM2                       | Sai Tso Wan Recreation Ground                                   | Ground Level            |
| AM3                       | Yau Lai Estate Bik Lai House                                    | Rooftop (41/F)          |
| AM4 <sup>(1)</sup>        | Sitting-out Area at Cha Kwo Ling Village                        | Ground Level            |
| AM4(A) <sup>(2) (*)</sup> | Cha Kwo Ling Public Cargo Working Area<br>Administrative Office | Rooftop (3/F)           |
| AM5(A) <sup>(*)</sup>     | Tseung Kwan O DSD Desilting Compound                            | Ground Level            |
| AM6(A) <sup>(*)</sup>     | Park Central, L1/F Open Space Area                              | 1/F                     |

Remarks: (1) For 1-hour TSP monitoring; (2) For 24-hour TSP monitoring

(\*) Air quality monitoring at designated station AM4(24-hr TSP), AM5 and AM6 was rejected by the premise owners. Therefore, baseline and impact air quality monitoring works were carried out at alternative air quality monitoring stations AM4(A) (24-hr TSP only), AM5(A) and AM6(A) respectively.

#### Monitoring Equipment

- 3.3 High Volume Samplers (HVS) were used to carry out 24-hour TSP monitoring. Direct reading dust meter were also used to measure 1-hour average TSP levels. The 1-hour sampling was determined periodically by HVS to check the validity and accuracy of the results measured by direct reading method.
- 3.4 Wind data monitoring equipment was set at rooftop (about 41/F) of Yau Lai Estate Bik Lai House for logging wind speed and wind direction such that the wind sensors are clear of obstructions or turbulence caused by building. The wind data monitoring equipment is re-calibrated at least once every six months and the wind directions are divided into 16 sectors of 22.5 degrees each. The location is shown in **Figure 2**.
- 3.5 **Table 3.2** summarizes the equipment to be used in the air quality monitoring. Copies of calibration certificates are attached in **Appendix B**.

**Table 3.2 Air Quality Monitoring Equipment**

| Equipment             | Model and Make   | Quantity |
|-----------------------|--|----------|
| Calibrator            | TISCH Model: TE-5025A                                    | 1        |
| 1-hour TSP Dust Meter | Sibata Model No.: LD-3 / LD-3B                           | 0        |
|                       | Met One Instruments Model No.: AEROCET-531               | 0        |
|                       | Handheld Particle Counter Hal-HPC300 / Hal-HPC301        | 7        |
| HVS Sampler           | TISCH Model: TE-5170                                     | 1        |
|                       | GMW Model: GS2310  | 5        |
| Wind Anemometer       | Davis Weather Monitor II, Model no. 7440                 | 0        |
|                       | Davis Weather Stations, Vantage Pro 2, Model No. 6152CUK | 1        |

**Monitoring Parameters and Frequency**

3.6 **Table 3.3** summarizes the monitoring parameters, monitoring period and frequencies of air quality monitoring.

**Table 3.3 Frequency and Parameters of Air Quality Monitoring**

| Monitoring Stations                      | Parameter   | Frequency         |
|--|-------------|-------------------|
| AM1, AM2, AM3, AM4, AM5(A) and AM6(A)    | 1-hour TSP  | 3 times per 6 day |
| AM1, AM2, AM3, AM4(A), AM5(A) and AM6(A) | 24-hour TSP | Once per 6 days   |

**Monitoring Methodology*****1-hour TSP Monitoring******Measuring Procedures***

3.7 The measuring procedures of the 1-hour dust meter are in accordance with the Manufacturer's Instruction Manual as follows:

**(Model LD3 / LD3B)**

- The 1-hour dust meter is placed at least 1.3 meters above ground.
- Set POWER to "ON" and make sure that the battery level was not flash or in low level.
- Allow the instrument to stand for about 3 minutes and then the cap of the air sampling inlet has been released.
- Push the knob at MEASURE position.
- Set time/mode setting to [BG] by pushing the time setting switch. Then, start the background measurement by pushing the start/stop switch once. It will take 6 sec. to complete the background measurement.
- Push the time setting switch to change the time setting display to [MANUAL] at the bottom left of the liquid crystal display. Finally, push the start/stop switch to stop the measuring after 1 hour sampling.
- Information such as sampling date, time, count value and site condition were recorded during the monitoring period.

**(AEROCET-531)**

- The 1-hour dust meter is placed at least 1.3 meters above ground.
- Remove the red rubber cap from the AEROCET-531 inlet nozzle.

- Turn on the power switch that is located on the right side of the AEROCET-531.
- On power up the product intro screen is displayed for 3 seconds. The intro screen displays the product name and firmware version.
- Then the main counter screen will be displayed.
- Press the START button. Internal vacuum pump start running. After 1 minute the pump will stop and the 0.5 $\mu$ m and 5 $\mu$ m channels will show the cumulative counts of particles larger than 0.5 $\mu$ m and 5 $\mu$ m per cubic foot.
- The AEROCET-531 is now checked out and ready for use.
- To switch off the AEROCET-531 power to stop the measuring after 1 hour sampling.
- Information such as sampling date, time, and display value and site condition were recorded during the monitoring period.

(Equipment: Hal Technology; Model no. Hal-HPC300 / Hal-HPC301)

- The 1-hour dust meter is placed at least 1.3 meters above ground.
- Set POWER to “ON” and make sure that the battery level was not flash or in low level.
- Allow the instrument to stand for about 3 minutes and then the cap of the air sampling inlet has been released.
- Push the knob at MEASURE position.
- Set time/mode setting to [BG] by pushing the time setting switch. Then, start the background measurement by pushing the start/stop switch once. It will take 6 sec. to complete the background measurement.
- Push the time setting switch to change the time setting display to [MANUAL] at the bottom left of the liquid crystal display. Finally, push the start/stop switch to stop the measuring after 1 hour sampling.
- Information such as sampling date, time, count value and site condition were recorded during the monitoring period.

#### Maintenance/Calibration

3.8 The following maintenance/calibration is required for the direct dust meters:

- Check and calibrate the meter by HVS to check the validity and accuracy of the results measured by direct reading method at 2-month intervals throughout all stages of the air quality monitoring.

#### ***24-hour TSP Monitoring***

##### Instrumentation

3.9 High volume samplers (HVS) (TISCH Model: TE-5170 and GMW Model: GS2310) completed with appropriate sampling inlets were employed for 24-hour TSP monitoring. The sampler is composed of a motor, a filter holder, a flow controller and a sampling inlet and its performance specification complied with that required by USEPA Standard Title 40, Code of Federation Regulations Chapter 1 (Part 50).

3.10 The positioning of the HVS samplers are as follows:

- a horizontal platform with appropriate support to secure the samplers against gusty wind shall be provided;
- no two samplers shall be placed less than 2 meter apart
- the distance between the sampler and an obstacle, such as buildings, must be at least twice the height that the obstacle protrudes above the sampler;
- a minimum of 2 metres of separation from walls, parapets and penthouses is required for rooftop samplers;

- a minimum of 2 metres of separation from any supporting structure, measured horizontally is required;
- no furnace or incinerator flue is nearby;
- airflow around the sampler is unrestricted;
- the sampler is more than 20 metres from the dripline;
- any wire fence and gate, to protect the sampler, shall not cause any obstruction during monitoring;
- permission must be obtained to set up the samplers and to obtain access to the monitoring stations; and
- a secured supply of electricity is needed to operate the samplers.

#### Operating/analytical procedures for the operation of HVS

- 3.11 Prior to the commencement of the dust sampling, the flow rate of the high volume sampler was properly set (between 1.1 m<sup>3</sup>/min. and 1.4 m<sup>3</sup>/min.) in accordance with the manufacturer's instruction to within the range recommended in USEPA Standard Title 40, CFR Part 50.
- 3.12 For TSP sampling, fiberglass filters with a collection efficiency of > 99% for particles of 0.3µm diameter were used.
- 3.13 The power supply was checked to ensure the sampler worked properly. On sampling, the sampler was operated for 5 minutes to establish thermal equilibrium before placing any filter media at the designated air monitoring station.
- 3.14 The filter holding frame was then removed by loosening the four nuts and a weighted and conditioned filter was carefully centered with the stamped number upwards, on a supporting screen.
- 3.15 The filter was aligned on the screen so that the gasket formed an airtight seal on the outer edges of the filter. Then the filter holding frame was tightened to the filter holder with swing bolts. The applied pressure should be sufficient to avoid air leakage at the edges.
- 3.16 The shelter lid was closed and secured with the aluminum strip.
- 3.17 The timer was then programmed. Information was recorded on the record sheet, which included the starting time, the weather condition and the filter number (the initial weight of the filter paper can be found out by using the filter number).
- 3.18 After sampling, the filter was removed and sent to the HOKLAS laboratory (Wellab Ltd.) for weighing. The elapsed time will be also recorded.
- 3.19 Before weighing, all filters was equilibrated in a conditioning environment for 24 hours. The conditioning environment temperature should be between 25°C and 30°C and not vary by more than ±3°C; the relative humidity (RH) should be < 50% and not vary by more than ±5%. A convenient working RH is 40%.

#### Maintenance/Calibration

- 3.20 The following maintenance/calibration is required for the HVS:
- The high volume motors and their accessories will be properly maintained. Appropriate maintenance such as routine motor brushes replacement and electrical wiring checking will be made to ensure that the equipment and necessary power supply are in good working condition.

- High volume samplers will be calibrated at bi-monthly intervals using TE-5025A Calibration Kit throughout all stages of the air quality monitoring.

### Results and Observations

- 3.21 All 1-hour TSP monitoring was conducted as scheduled in the reporting month. No Action/Limit Level exceedance was recorded.
- 3.22 All 24-hour TSP monitoring was conducted as scheduled in the reporting month. No Action/Limit Level exceedance was recorded.
- 3.23 The air temperature, precipitation and the relative humidity data was obtained from Hong Kong Observatory where the wind speed and wind direction were recorded by the installed Wind Anemometer at rooftop of Yau Lai Estate Bik Lai House (41/F). The location is shown in **Figure 2**. This weather information for the reporting month is summarized in **Appendix C**.
- 3.24 The monitoring data and graphical presentations of 1-hour and 24-hour TSP monitoring results are shown in **Appendix E** and **Appendix F** respectively.
- 3.25 The summary of exceedance record in reporting month is shown in **Appendix K**. No exceedance was recorded for the air quality monitoring.
- 3.26 According to our field observations, the major dust source identified at the designated air quality monitoring stations are as follows:

**Table 3.4 Major Dust Source during Air Quality Monitoring**

| Station   | Major Dust Source   |
|---|---|
| AM1 – Tin Hau Temple  | Road Traffic at Cha Kwo Ling Road                         |
| AM2 – Sai Tso Wan Recreation Ground                                   | N/A   |
| AM3 – Yau Lai Estate Bik Lai House                                    | Road Traffic near Eastern Cross Harbour Tunnel Toll Plaza |
| AM4 - Sitting-out Area at Cha Kwo Ling Village                        | Road Traffic at Cha Kwo Ling Road                         |
| AM4(A) - Cha Kwo Ling Public Cargo Working Area Administrative Office | Road Traffic at Cha Kwo Ling Road                         |
| AM5(A) - Tseung Kwan O DSD Desilting Compound                         | Vehicle Movement within the Desilting Compound            |
| AM6(A) - Park Central, L1/F Open Space Area                           | Road Traffic at Po Yap Road                               |

## 4. NOISE

### Monitoring Requirements

- 4.1 According to EM&A Manual of the Project, construction noise monitoring was conducted to monitor the construction noise arising from the construction activities. The regular monitoring frequency for each monitoring station shall be on a weekly basis and conduct one set of measurements between 0700 and 1900 hours on normal weekdays. **Appendix A** shows the established Action and Limit Levels for the environmental monitoring works.

### Monitoring Locations

- 4.2 Noise monitoring was conducted at 8 designated monitoring stations (CM1, CM2, CM3, CM4, CM5, CM6(A), CM7(A), CM8(A)) in the reporting period. **Table 4.1** and **Figure 3** show the locations of these stations.

**Table 4.1 Noise Monitoring Stations**

| Monitoring Stations | Locations   | Location of Measurement |
|---------------------|---|-------------------------|
| CM1                 | Nga Lai House, Yau Lai Estate Phase 1, Yau Tong                     | Rooftop (41/F)          |
| CM2                 | Bik Lai House, Yau Lai Estate Phase 1, Yau Tong                     | Rooftop (41/F)          |
| CM3                 | Block S, Yau Lai Estate Phase 5, Yau Tong                           | Rooftop (40/F)          |
| CM4                 | Tin Hau Temple, Cha Kwo Ling  | Ground Level            |
| CM5                 | CCC Kei Faat Primary School, Yau Tong                               | Rooftop (6/F)           |
| CM6(A)*             | Site Boundary of Contract No. NE/2015/02 near Tower 1, Ocean Shores | Ground Level            |
| CM7(A)*             | Site Boundary of Contract No. NE/2015/02 near Tower 7, Ocean Shores | Ground Level            |
| CM8(A)*             | Park Central, L1/F Open Space Area                                  | 1/F                     |

Remarks: \* Noise monitoring at designated station CM6, CM7 & CM8 was rejected by the premise owners. Therefore, baseline and impact noise monitoring works were carried out at alternative noise monitoring stations CM6(A), CM7(A) and CM8(A) respectively.

### Monitoring Equipments

- 4.3 Integrating Sound Level Meter was used for impact noise monitoring. The meters are Type 1 sound level meter capable of giving a continuous readout of the noise level readings including equivalent continuous sound pressure level ( $L_{eq}$ ) and percentile sound pressure level ( $L_x$ ) that also complied with International Electrotechnical Commission Publications 651:1979 (Type 1) and 804:1985 (Type 1) specifications. **Table 4.2** summarizes the noise monitoring equipment being used. Copies of calibration certificates are attached in **Appendix B**.

**Table 4.2 Noise Monitoring Equipment**

| Equipment                     | Model and Make    | Quantity |
|-------------------------------|-------------------|----------|
| Integrating Sound Level Meter | SVAN 957 / 977    | 4        |
|                               | BSWA 801          | 2        |
| Calibrator                    | SV30A             | 2        |
|                               | Brüel & Kjær 4231 | 0        |



- 4.4 **Table 4.3** summarizes the monitoring parameters, frequency and total duration of monitoring. The noise monitoring schedule is shown in **Appendix D**.

**Table 4.3 Frequency and Parameters of Noise Monitoring**

| Monitoring Stations | Parameter                         | Period                              | Frequency        | Measurement |
|---------------------|-----------------------------------|-------------------------------------|------------------|-------------|
| CM1                 | L <sub>10</sub> (30 min)<br>dB(A) | 0700-1900 hrs on<br>normal weekdays | Once per<br>week | Façade      |
| CM2                 |                                   |                                     |                  | Façade      |
| CM3                 | Façade                            |                                     |                  |             |
| CM4                 | L <sub>90</sub> (30 min)<br>dB(A) |                                     |                  | Façade      |
| CM5                 | Façade                            |                                     |                  |             |
| CM6(A)              | L <sub>eq</sub> (30 min)<br>dB(A) |                                     |                  | Free Field  |
| CM7(A)              | Façade                            |                                     |                  |             |
| CM8(A)              | Façade                            |                                     |                  |             |

### Monitoring Methodology and QA/QC Procedure

- 4.5 The monitoring procedures are as follows:
- The monitoring station was normally be at a point 1m from the exterior of the sensitive receivers building façade and be at a position 1.2m above the ground.
  - For free field measurement, the meter was positioned away from any nearby reflective surfaces. All records for free field noise levels was adjusted with a correction of +3 dB(A).
  - The battery condition was checked to ensure the correct functioning of the meter.
  - Parameters such as frequency weighting, the time weighting and the measurement time was set as follows:
    - frequency weighting : A
    - time weighting : Fast
    - measurement time : 30 minutes
  - Prior to and after each noise measurement, the meter was calibrated using a Calibrator for 94.0 dB at 1000 Hz. If the difference in the calibration level before and after measurement will be more than 1.0 dB, the measurement would be considered invalid and repeat of noise measurement would be required after re-calibration or repair of the equipment.
  - At the end of the monitoring period, the L<sub>eq</sub>, L<sub>90</sub> and L<sub>10</sub> was recorded. In addition, noise sources was recorded on a standard record sheet.
  - Noise monitoring will be cancelled in the presence of fog, rain, and wind with a steady speed exceeding 5 m/s, or wind with gusts exceeding 10 m/s. Supplementary monitoring was provided to ensure sufficient data would be obtained.

### Maintenance and Calibration

- 4.6 The microphone head of the sound level meter and calibrator was cleaned with a soft cloth at quarterly intervals.
- 4.7 The sound level meter and calibrator was checked and calibrated at yearly intervals.
- 4.8 Immediately prior to and following each noise measurement the accuracy of the sound level meter was checked using an acoustic calibrator generating a known sound pressure level at a known frequency. Measurements may be accepted as valid only if the calibration levels from before and after the noise measurement agree to within 1.0

dB.

### Results and Observations

- 4.9 All noise monitoring was conducted as scheduled in the reporting month. Four (4) Action Level exceedance was recorded due to the documented complaints received in this reporting month. Twelve (12) Limit Level exceedance was recorded in the reporting month.
- 4.10 Noise monitoring results and graphical presentations are shown in **Appendix G**.
- 4.11 The major noise source identified at the noise monitoring stations are shown in **Table 4.4**.

**Table 4.4 Major Noise Source during Noise Monitoring**

| Monitoring Stations | Locations   | Major Noise Source  |
|---------------------|---|---|
| CM1                 | Nga Lai House, Yau Lai Estate Phase 1, Yau Tong                     | Road Traffic near Eastern Cross Harbour Tunnel Toll Plaza |
| CM2                 | Bik Lai House, Yau Lai Estate Phase 1, Yau Tong                     | Road Traffic near Eastern Cross Harbour Tunnel Toll Plaza |
| CM3                 | Block S, Yau Lai Estate Phase 5, Yau Tong                           | Road Traffic near Eastern Cross Harbour Tunnel Toll Plaza |
| CM4                 | Tin Hau Temple, Cha Kwo Ling  | Road Traffic at Cha Kwo Ling Road                         |
| CM5                 | CCC Kei Faat Primary School, Yau Tong                               | Road Traffic at Yau Tong Road                             |
| CM6(A)              | Site Boundary of Contract No. NE/2015/02 near Tower 1, Ocean Shores | Road Traffic at O King Road near Ocean Shores             |
| CM7(A)              | Site Boundary of Contract No. NE/2015/02 near Tower 7, Ocean Shores | Road Traffic at Tong Yin Street                           |
| CM8(A)              | Park Central, L1/F Open Space Area                                  | Road Traffic at Po Yap Road                               |

- 4.12 All the Construction Noise Levels (CNLs) reported in this report were adjusted with the corresponding baseline level (i.e. Measured  $L_{eq}$  – Baseline  $L_{eq}$  = CNL), in order to facilitate the interpretation of the noise exceedance. The baseline noise level and the Noise Limit Level at each designated noise monitoring station are presented in **Table 4.5**.

**Table 4.5 Baseline Noise Level and Noise Limit Level for Monitoring Stations**

| Station | Baseline Noise Level, dB (A)<br>(at 0700 – 1900 hrs on normal weekdays) | Noise Limit Level, dB (A)<br>(at 0700 – 1900 hrs on normal weekdays) |
|---------|---|--|
| CM1     | 65.5  | 75   |
| CM2     | 63.6  |  |
| CM3     | 65.6  |  |
| CM4     | 62.0  |  |
| CM5     | 68.2  | 70*  |
| CM6(A)  | 61.9  | 75   |
| CM7(A)  | 58.3  |  |
| CM8(A)  | 69.1  |  |

---

(\*) Noise Limit Level is 65 dB(A) during school examination periods.

### **Updated Construction Noise Assessment**

Contract No. NE/2015/01, Contract No. NE/2015/02, Contract No. NE/2015/03,  
Contract No. NE/2017/01 and Contract No. NE/2017/02

- 4.13 Construction Noise Assessment for Contract No. NE/2015/02 has been updated due to the change of construction work sequence. Updated Construction Noise Assessment for Contract No. NE/2015/02 and their corresponding proposed mitigation measures are shown in **Appendix S** and can be downloaded at the following address:

[http://files.cinotech.com.hk/download/MA16034/website/NE201502-NMP8.pdf#page=38%20 blank](http://files.cinotech.com.hk/download/MA16034/website/NE201502-NMP8.pdf#page=38%20blank)

- 4.14 No update of Construction Noise Assessment for other contracts in the reporting period.

## 5. WATER QUALITY

### Monitoring Requirements

#### Groundwater Quality

- 5.1 Groundwater quality monitoring shall be conducted as identified in the EIA report (locations refer to **Figure 4**, Stream 1 to 3). According to the EM&A Manual, dissolved oxygen (DO), pH, temperature, turbidity, suspended solids (SS), 5-day biochemical oxygen demand (BOD<sub>5</sub>), Total organic carbon (TOC), Total Nitrogen, Ammonia-N and Total Phosphate are the parameters for the monitoring. **Appendix A** shows the established Action and Limit Levels.
- 5.2 As stated in the Baseline Environmental Monitoring Plan submitted to EPD in September 2016, Groundwater quality monitoring could not be conducted at the other identified monitoring station in the EIA Report, Stream 4, as it was found to be not accessible due to safety reason. EPD has no further comment on the Plan in October 2016.

#### Marine Water Quality

- 5.3 Marine water quality monitoring was conducted three times per week at the designated monitoring stations. Monitoring took place two times per monitoring day during mid ebb and mid flood tides at three depths (1 meter from surface, mid depth and 1 meter from the bottom). For Tseung Kwan O Salt Water Intake (i.e. Station M6), water sampling and in-situ measurements was taken at the vertical level where the water abstraction point of the intake is located (i.e. approximately mid-depth level). If the water depth is less than 6m, the mid-depth measurement may be omitted. If the depth is less than 3m, only the mid-depth measurements need to be taken.
- 5.4 Duplicate in-situ measurements (Dissolved oxygen (DO) concentration, DO saturation, turbidity, pH, temperature and salinity) and water samples (suspended solids (SS)) at each depth were monitored in accordance with the requirements in the EM&A Manual. For selection of tides for in-situ measurement and water sampling, tidal range of individual flood and ebb tides were not less than 0.5m.
- 5.5 According to the Environmental Review Report (ERR) for Variations of Environmental Permit (Ref: C45-03), water quality monitoring and audit programme was implemented for monitoring of oxygen depletion (e.g. Dissolved Oxygen (DO) level) in this embayed waters during the period when the fully enclosed barrier is installed. A “Proposal for Water Quality Monitoring in Temporary Marine Embayment” has been submitted to EPD in July 2017 to propose the monitoring frequency, parameter, location, etc. EPD has no further comment on the Proposal.

#### Groundwater Level Monitoring (Piezometer Monitoring)

- 5.6 Daily piezometer monitoring at any time of the day shall be carried throughout the whole period when any tunnel construction activities are carried out within +/- 50m of the piezometer gate in plan. The monitoring is commenced in this reporting period.

## Monitoring Locations

### Groundwater Quality

- 5.7 Stream 1 – Stream 3 is designated for the groundwater quality monitoring according to EM&A Manual. The locations are summarized in **Table 5.1** and shown on **Figure 4**.

**Table 5.1 Groundwater Quality Monitoring Stations**

| Monitoring Streams | Descriptions   | Sampling Location                   |
|--------------------|--|-------------------------------------|
| Stream 1           | Stream running between the Kwong Tin Estate and Lei Yue Mun Road | 1 sampling location for each stream |
| Stream 2           | Stream on western coast of Chiu Keng Wan                         |                                     |
| Stream 3           | Stream on western coast of Chiu Keng Wan                         |                                     |

### Marine Water Quality

- 5.8 A total of twelve monitoring stations are designated for the water quality monitoring program according to EM&A Manual. One additional monitoring station (W1) is designated for monitoring of oxygen depletion in the embayed waters during the period when the fully enclosed barrier is installed. The locations are also summarized in **Table 5.2** and shown on **Figure 5** and **Figure 9**.

**Table 5.2 Marine Quality Monitoring Stations**

| Monitoring Stations | Descriptions   | Coordinates |          |
|---------------------|--|-------------|----------|
|                     |  | Easting     | Northing |
| M1                  | Junk Bay Coral Site – Junk Bay near Chiu Keng Wan    | 844255      | 817565   |
| M2                  | Junk Bay Coral Site – Junk Bay                       | 844076      | 817087   |
| M3                  | Junk Bay Coral Site – Junk Island                    | 844491      | 817890   |
| M4                  | Junk Bay Coral Site – Chiu Keng Wan                  | 843209      | 816416   |
| M5                  | Junk Bay Coral Site – Fat Tong Chau                  | 845463      | 815769   |
| M6                  | Tseung Kwan O Salt Water Intake                      | 845512      | 817442   |
| C1                  | Control Station – Southeast                          | 844696      | 814773   |
| C2                  | Control Station – Northwest                          | 842873      | 816014   |
| G1                  | Gradient Station                                     | 844418      | 817560   |
| G2                  | Gradient Station                                     | 844290      | 817384   |
| G3                  | Gradient Station                                     | 844488      | 817735   |
| G4                  | Gradient Station                                     | 844967      | 817551   |
| W1                  | Ocean Shores (for WQM in temporary marine embayment) | 844324      | 817791   |

## Monitoring Equipments

- 5.9 For in-situ monitoring, a multi-parameter meter (Aquaread AP-2000-D) was used to measure Dissolved oxygen (DO) concentration, DO saturation (DO %), pH, temperature and turbidity. A sampler was used to collect water samples for laboratory analysis of SS, BOD<sub>5</sub>, TOC, Total Nitrogen, Ammonia-N and Total Phosphate.

### Dissolved Oxygen (DO) and Temperature Measuring Equipment

- 5.10 The instrument for measuring dissolved oxygen and temperature was portable and weatherproof complete with cable, sensor, comprehensive operation manuals and use DC power source. It was capable of measuring:
- a dissolved oxygen level in the range of 0-20 mg/L and 0-200% saturation; and

- a temperature of 0-45 degree Celsius.
- 5.11 It has a membrane electrode with automatic temperature compensation complete with a cable.
- 5.12 Sufficient stocks of spare electrodes and cables were available for replacement where necessary.
- 5.13 Salinity compensation was built-in in the DO equipment.

#### Turbidity

- 5.14 Turbidity was measured in-situ by the nephelometric method. The instrument was portable and weatherproof using a DC power source complete with cable, sensor and comprehensive operation manuals. The equipment was capable of measuring turbidity between 0-1000 NTU. The probe cable was not be less than 25m in length.

#### pH

- 5.15 The instrument was consisting of a potentiometer, a glass electrode, a reference electrode and a temperature-compensating device. It was readable to 0.1pH in a range of 0 to 14. Standard buffer solutions of at least pH 7 and pH 10 were used for calibration of the instrument before and after use.

#### Water Depth Detector

- 5.16 A portable, battery-operated echo sounder was used for the determination of water depth at each designated monitoring station.

#### Water Sampler

- 5.17 Water samples collected for laboratory analysis were stored in high density polythene bottles sample containers, with appropriate preservatives added. All sampling bottles were labeled (waterproof) with the sampling date and time, sample lot number and sampling location reference number to avoid mishandling.

#### Sample Container and Storage

- 5.18 Following collection, water samples for laboratory analysis were stored in high density polythene bottles, with preservative appropriately added where necessary. They will be packed in ice (cooled to 4°C without being frozen), delivered to the laboratory and analysed as soon as possible.

#### Calibration of In-Situ Instruments

- 5.19 All in-situ monitoring instruments were checked, calibrated and certified by a laboratory accredited under HOKLAS or other international accreditation scheme before use, and subsequently re-calibrated at 3 monthly intervals throughout all stages of the water quality monitoring.
- 5.20 For the on-site calibration of field equipment, the BS 1427:1993, "Guide to Field and on-site test methods for the analysis of waters" was observed.
- 5.21 Before each round of monitoring, a zero check in distilled water was performed with the turbidity probe of Aquaread AP-2000-D. The probe was then be calibrated with a solution of known NTU.
- 5.22 Sufficient stocks of spare parts were maintained for replacements when necessary. Backup monitoring equipment was also made available so that monitoring can proceed

uninterrupted even when some equipment is under maintenance, calibration, etc.

- 5.23 **Table 5.3** summarizes the equipment used in the water quality monitoring program. Copies of the calibration certificates of the equipment are shown in **Appendix B**.

**Table 5.3 Water Quality Monitoring Equipment**

| Equipment                            | Model and Make                        | Qty. |
|--------------------------------------|---------------------------------------|------|
| Water Sampler                        | Kahlsico Water-Bottle Model 135DW 150 | 1    |
| Multi-parameter Water Quality System | YSI 6820-C-M                          | 0    |
|                                      | Aquaread AP-2000-D                    | 0    |
|                                      | YSI EXO1 Multiparameter Sondes        | 5    |
| Monitoring Position                  | “Magellan” Handheld GPS Model GPS-320 | 1    |
| Water Depth Detector                 | Fishfinder 140                        | 1    |

### Monitoring Parameters and Frequency

- 5.24 **Table 5.4** summarizes the monitoring parameters, monitoring period and frequencies of the water quality monitoring in the reporting period.

**Table 5.4 Water Quality Monitoring Parameters and Frequency**

| Monitoring Stations  | Parameters, unit  | Depth   | Frequency  |
|--|---|---|--|
| <b>Groundwater Quality</b>   |   |   |  |
| Stream 1-<br>Stream 3  | <ul style="list-style-type: none"> <li>• DO, mg/L</li> <li>• DO Saturation, %</li> <li>• pH</li> <li>• Water Temperature (°C)</li> <li>• Turbidity, NTU</li> <li>• SS, mg/L</li> <li>• BOD<sub>5</sub>, mg O<sub>2</sub>/L</li> <li>• TOC, mg-TOC/L</li> <li>• Total Nitrogen, mg/L</li> <li>• Ammonia-N, mg NH<sub>3</sub>-N/L</li> <li>• Total Phosphate, mg-P/L</li> </ul> | Mid-depth   | Biweekly<br><br>(When the tunnel construction works are found within 50m of the location, weekly.) |
| <b>Marine Water Quality</b>  |   |   |  |
| M1<br>M2<br>M3<br>M4<br>M5<br>M6<br>C1<br>C2<br>G1<br>G2<br>G3<br>G4 | <p><i>In-situ:</i><br/>Dissolved oxygen (DO) concentration, DO saturation, turbidity, pH, temperature and salinity</p> <p><u>Laboratory Testing:</u><br/>Suspended Solids (SS)</p>  | <p><u>M1-M5, C1-C2, G1-G4</u></p> <ul style="list-style-type: none"> <li>• 3 water depths: 1m below water surface, mid-depth and 1m above sea bed.</li> <li>• If the water depth is less than 3m, mid-depth sampling only.</li> <li>• If the water depth is less than 6m, omit mid-depth sampling.</li> </ul> <p><u>M6</u></p> <ul style="list-style-type: none"> <li>• at the vertical level where the water abstraction point of</li> </ul> | 3 days per week<br>/<br>2 per monitoring day<br>(1 for mid-ebb and 1 for mid-flood)                |

| Monitoring Stations   | Parameters, unit  | Depth  | Frequency   |
|---|---|--|---|
|   |   | the intake is located(i.e. approximately mid-depth level)  |   |
| <b>Water Quality Monitoring in Temporary Marine Embayment</b> |   |  |   |
| W1  | <ul style="list-style-type: none"> <li>• DO, mg/L</li> <li>• DO Saturation, %</li> <li>• pH</li> <li>• Water Temperature (°C)</li> <li>• Salinity, ppt</li> </ul> | <ul style="list-style-type: none"> <li>• 3 water depths: 1m below water surface, mid-depth and 1m above sea bed.</li> <li>• If the water depth is less than 3m, mid-depth monitoring only.</li> <li>• If the water depth is less than 6m, omit mid-depth monitoring</li> </ul> | Weekly during the period when the fully enclosed barrier is installed |

### Monitoring Methodology

#### Groundwater Quality

- 5.25 At each monitoring location, two consecutive in-situ measurements for DO concentration, DO saturation, pH, temperature and turbidity were taken for water samples on site. The probes were retrieved out of the water after the first measurement and then re-deployed for the second measurement. Where the difference in the value between the first and second readings of each set was more than 25% of the value of the first reading, the reading was discarded and further readings were taken.
- 5.26 For SS, BOD<sub>5</sub>, TOC, Total Nitrogen, Ammonia-N and Total Phosphate, measurement and grab samples of surface water was collected. Water samples of about adequate volume was collected and stored in high density polythene bottles. Following collection, water samples was stored in high density polythene bottles. Preservation H<sub>2</sub>SO<sub>4</sub> was appropriately added for water samples for TOC, Total Nitrogen, Ammonia-N and Total Phosphate testing. Water samples was packed in ice and cooled to 4°C (without being frozen), delivered to the HOKLAS accredited laboratory, Wellab Limited and analyzed.

#### Marine Water Quality

- 5.27 The monitoring stations were accessed using survey boat by the guide of a hand-held Global Positioning System (GPS). The depth of the monitoring location was measured using depth meter in order to determine the sampling depths. Afterwards, the probes of the in-situ measurement equipment was lowered to the predetermined depths (1 m below water surface, mid-depth and 1 m above seabed) and the measurements was carried out accordingly. The in-situ measurements at predetermined depths was carried out in duplicate. In case the difference in the duplicate in-situ measurement results was larger than 25%, the third set of in-situ measurement would be carried out for result confirmation purpose.



- 5.28 Water sampler was lowered into the water to the required depths of sampling. Upon reaching the pre-determined depth, a messenger to activate the sampler was then released to travel down the wire. The water sample was sealed within the sampler before retrieving. At each station, water samples for SS at three depths (1 m below water surface, mid-depth and 1 m above seabed) were collected accordingly. Water samples were stored in a cool box and kept at less than 4°C but without frozen and sent to the laboratory as soon as possible.

### Laboratory Analytical Methods

- 5.29 The testing of all parameters were conducted by Wellab Ltd. (HOKLAS Registration No.083) and comprehensive quality assurance and control procedures in place in order to ensure quality and consistency in results. The testing method and limit of reporting are provided in **Table 5.5**.

**Table 5.5 Methods for Laboratory Analysis for Water Samples**

| Parameters (Unit)                        | Proposed Method                           | Reporting Limit              | Detection Limit |
|--|---|------------------------------|-----------------|
| SS (mg/L)                                | APHA 2540 D                               | 0.5 mg/L <sup>(1)</sup>      | 0.5 mg/L        |
| BOD <sub>5</sub> (mg O <sub>2</sub> /L)  | APHA 19ed 5210B                           | 2 mg O <sub>2</sub> /L       | --              |
| TOC (mg-TOC/L)                           | In-house method<br>SOP020 (Wet Oxidation) | 1 mg-TOC/L                   | --              |
| Total Nitrogen (mg/L)                    | In-house method<br>SOP063 (FIA)           | 0.6 mg/L                     | --              |
| Ammonia-N (mg NH <sub>3</sub> -N/L)      | In-house method<br>SOP057 (FIA)           | 0.05 mg NH <sub>3</sub> -N/L | --              |
| Total Phosphorus (mg-P/L) <sup>(2)</sup> | In-house method<br>SOP055 (FIA)           | 0.05 mg-P/L                  | --              |

Note:

1) Limit of Reporting is reported as Detection Limit for non-HOKLAS report.

2) Parameter Total Phosphorus represents the laboratory testing for total phosphate content in water which is the sum of all three forms of phosphates in water.

### QA/QC Requirements

#### Decontamination Procedures

- 5.30 Water sampling equipment used during the course of the monitoring programme was decontaminated by manual washing and rinsed clean seawater/distilled water after each sampling event. All disposal equipment was discarded after sampling.

#### Sampling Management and Supervision

- 5.31 Water samples were dispatched to the testing laboratory for analysis as soon as possible after the sampling. All samples were stored in a cool box and kept at less than 4°C but without frozen. All water samples were handled under chain of custody protocols and relinquished to the laboratory representatives at locations specified by the laboratory.
- 5.32 QA/QC procedures as attached in **Appendix J** are available for the parameters analyzed in the HOKLAS-accredited laboratory, WELLAB Ltd.

## Results and Observations

### Groundwater Quality Monitoring

- 5.33 All groundwater quality monitoring was conducted as scheduled in the reporting month. Summary of groundwater quality monitoring results is shown in **Table 5.6**. Groundwater quality monitoring results, graphical presentations and laboratory testing reports are shown in **Appendix H**.
- 5.34 Other relevant data was also recorded, such as monitoring location / position, time, sampling depth, weather conditions and any special phenomena or work underway nearby.
- 5.35 Action and Limit Level for groundwater quality monitoring has been reviewed with consideration of monitoring results obtained from November 2016 to June 2017, as there was no tunnel boring or tunnel construction works from November 2016 to June 2017. A “Review Report for Action and Limit Levels of Groundwater Quality Monitoring” was submitted to EPD in August 2017. EPD has no further comment on the report and the updated Action and Limit Level is shown in **Appendix A**.

**Table 5.6 Summary of Groundwater Quality Monitoring Results**

| Date              | Location     | Parameters (unit) |                         |                 |            |   |                |                       |  |                           |
|-------------------|--------------|-------------------|-------------------------|-----------------|------------|---|----------------|-----------------------|--|---------------------------|
|                   |              | pH                | Dissolved Oxygen (mg/L) | Turbidity (NTU) | SS (mg/L)  | BOD <sub>5</sub> (mg O <sub>2</sub> /L) | TOC (mg-TOC/L) | Total Nitrogen (mg/L) | NH <sub>3</sub> -N (mg NH <sub>3</sub> -N/L) | Total Phosphorus (mg-P/L) |
| 5 June 2018       | Stream 1     | 8.2               | 7.7                     | <u>7.6</u>      | <u>39</u>  | <2                                      | 7              | <u>2.2</u>            | 0.1  | <u>0.11</u>               |
|                   | Stream 2     | 8.9               | 7.8                     | <u>72.2</u>     | <u>100</u> | <2                                      | 5              | 1.5                   | <0.05  | <0.05                     |
|                   | Stream 3     | 8.7               | 7.9                     | <u>86.9</u>     | <u>92</u>  | <2                                      | 5              | 1.5                   | <0.05  | <u>0.06</u>               |
| 20 June 2018      | Stream 1     | 8.5               | <u>7.4</u>              | <u>3.7</u>      | <2.5       | <2                                      | 3              | 0.8                   | 0.11   | <0.05                     |
|                   | Stream 2     | 8.5               | <u>7.5</u>              | <u>3.3</u>      | <2.5       | <2                                      | 4              | 1.5                   | <0.05  | <0.05                     |
|                   | Stream 3     | 8.5               | 7.6                     | <u>4.2</u>      | <2.5       | <2                                      | 4              | 1.5                   | <0.05  | <0.05                     |
| No. of Exceedance | Action Level | 0                 | 0                       | 0               | 0          | 0                                       | 0              | 0                     | 0  | 0                         |
|                   | Limit Level  | 0                 | 2                       | 6               | 3          | 0                                       | 0              | 1                     | 0  | 2                         |

Note: **Bold Italic** means Action Level exceedance

**Bold Italic with underline** means Limit Level exceedance

- 5.36 Further to Monthly EM&A Report (May 2018), the exceedance events on 24 May 2018 are considered due to human activities, therefore non-Project related. Details of the investigation are presented in **Appendix K**.
- 5.37 All groundwater quality monitoring was conducted as scheduled in the reporting month. Fourteen (14) Limit Level exceedances and no Action Level exceedance were recorded in the reporting month. The exceedances are considered due to rainfall and human activities, therefore non-Project related. Details of the investigation are presented in **Appendix K**.
- Marine Water Quality Monitoring**
- 5.38 All marine water quality monitoring was conducted as scheduled in the reporting month. Marine water monitoring results and graphical presentations are shown in **Appendix I**. Other relevant data was also recorded, such as monitoring location / position, time, sampling depth, weather conditions and any special phenomena or work underway nearby.
- 5.39 Calculated Action and Limit Levels for Marine Water Quality is presented in **Appendix I**. No Action/Limit Level exceedance was recorded in the reporting period.

Groundwater Level Monitoring (Piezometer Monitoring)

- 5.40 Daily piezometer monitoring at any time of the day shall be carried throughout the whole period when any tunnel construction activities are carried out within +/- 50m of the piezometer gate in plan.
- 5.41 Tunnel construction activities are within +/- 50m of the piezometer gate in plan. Construction phase daily piezometer monitoring by the Contractor commenced in June 2018. No Action Level exceedance was recorded in the reporting month. Details of the result are presented in **Appendix U**.

## 6. ECOLOGY

### Post-Translocation Coral Monitoring

- 6.1 Post-translocation monitoring survey is recommended in the EM&A Manual to audit the success of coral translocation. Information gathered during each post-translocation monitoring survey should include observations on the presence, survival, health condition and growth of the translocated coral colonies. These parameters should then be compared with the baseline results collected from the pre-translocation survey.
- 6.2 Under Contract No. NE/2015/01 and NE/2015/02, a total of 14 and 29 coral colonies were tagged and translocated respectively from the Donor Site to the Recipient Site in November 2016. Ten (10) corals at the Recipient Site were also tagged by each Contract as reference for post-translocation monitoring.
- 6.3 The post-translocation coral monitoring shall be conducted once every 3 months after completion for a period of 12 months. The fourth post-translocation coral monitoring was carried out on 07 November 2017.
- 6.4 Location of post-translocation coral monitoring is shown in **Figure 7**.

### Event and Action Plan

- 6.5 The post-translocation monitoring result was evaluated against Action and Limit Levels presented in **Appendix A**. Evaluation was based on recorded changes in percentage of partial mortality of the corals.
- 6.6 If the defined Action Level or Limit Level for coral monitoring is exceeded, the actions as set out in **Appendix M** will be implemented.
- 6.7 If observations of any die-off / abnormal conditions of the translocated corals are made during the post-translocation monitoring, the ET shall inform the Contractor, IEC and AFCD, and liaise with AFCD to investigate any mitigation measures needed.
- 6.8 The post-translocation coral monitoring surveys were completed in November 2017.

## 7. CULTURAL HERITAGE

### Monitoring Requirement

- 7.1 According to the EP Conditions and EM&A Manual, monitoring of vibration impacts was conducted when the construction works are less than 100m from the Built Heritage in close proximity of the worksite, namely the Cha Kwo Ling Tin Hau temple. Tilting and settlement monitoring should be applied on the Cha Kwo Ling Tin Hau Temple. Construction works less than 100m from the Cha Kwo Ling Tin Hau temple commenced on 8 April 2017.
- 7.2 As stated in the “*Built Heritage Mitigation Plan*” for this Project, during the period of the construction works conducted within 100m from the Cha Kwo Ling Tin Hau Temple, monitoring on settlement and tilting will be conducted once a day for the Cha Kwo Ling. Monitoring of vibration will be conducted during blasting at Cha Kwo Ling area once a day. When there is no blasting to be conducted at the area, vibration monitoring at the Cha Kwo Ling Tin Hau Temple will be conducted once per day when there are piling works or rock breaking works within the 100m from the Cha Kwo Ling Tin Hau Temple.

### Monitoring Locations

- 7.3 One vibration monitoring point and three building settlement monitoring points are proposed for monitoring of the cultural heritage. The building settlement markers are placed on the wall on three sides of the Temple, except the front, of the Cha Kwo Ling Tin Hau Temple and the vibration monitoring point is located within the Cha Kwo Ling Tin Hau Temple. Monitoring Location is shown in **Figure 8**.

### Monitoring Equipment

- 7.4 Building settlement is measured via a settlement marker attached to the wall of Cha Kwo Ling Tin Hau Temple by adhesive tape.
- 7.5 Vibration monitoring was conducted by using vibrographs: Minimate Plus manufactured by InstanTel. These vibrographs will be calibrated annually and its performance follows the requirements given in the “*Guidance Note on Vibration Monitoring*” (GN-VM) issued by the Civil Engineering and Development Department, which is based on the Performance Specification for Blasting Seismographs by International Society of Explosive Engineers (ISEE (2000)).
- 7.6 **Table 7.1** summarizes the equipment employed by the Contractor for cultural heritage monitoring. Copies of calibration certificates are attached in **Appendix B**.

**Table 7.1 Cultural Heritage Monitoring Equipment**

| Equipment  | Manufacturer and Model  | Quantity |
|--|---|----------|
| Digital Level for tilting                        | Leica<br>Serial No.: 701133   | 1        |
| iCivil-1011 Inclinometer for building settlement | iCivil-1011 Inclinometer<br>Serial No.: HK110118 / HK110120               | 2        |
| Vibrographs for vibration monitoring             | MiniMate Plus manufactured by InstanTel<br>Model No.: 716A0403 / 721A2501 | 10       |

### Monitoring Methodology

- 7.7 Vibrograph (velocity seismograph) was deployed at each monitoring station to measure and record the PPV and amplitude of ground motion in three mutually perpendicular directions. Vibration monitoring equipment fulfils the requirements stated in the Government guidelines and is calibrated to HOKLAS standards. Each monitoring would not be more than 10 minutes. Settlement monitoring should be conducted by surveyors manually.

### Alert, Alarm and Action Levels

- 7.8 The Alert, Alarm and Action (AAA) Levels are given in **Table 7.2**.

**Table 7.2 AAA Levels for Monitoring for Cultural Heritage**

| Parameter                       | Alert Level   | Alarm Level   | Action Level  |
|---------------------------------|---------------|---------------|---|
| Vibration                       | ppv: 4.5 mm/s | ppv: 4.8 mm/s | ppv: 5mm/s Maximum Allowable Vibration Amplitude: 0.1mm |
| Building Settlement Markers     | 6mm           | 8mm           | 10mm  |
| Building Tilting <sup>(1)</sup> | 1:2000        | 1:1500        | 1:1000  |

Remarks: (1) Building tilting measurement was replaced by building settlement point measurement. The tilting can be calculated by the ratio of the maximum settlement difference between 2 points and the distance between the 2 points.

### Results

- 7.9 In the reporting month, cultural heritage monitoring was carried out by the Contractor at the aforesaid location on 25 occasions. No AAA Level exceedance was recorded in the reporting month. The monitoring results are presented in **Appendix T**.

### Mitigation Measures for Cultural Heritage

- 7.10 According to Condition 3.6 of the EP (EP No.: EP-458/2013/C), to prevent damage to Cha Kwo Ling Tin Hau Temple and its Fung Shui rocks (Child-given rocks) during the construction phase, a temporarily fenced-off buffer zone (Rocks buffer zone is 5 m from the edge of Rocks and 15m from the edge of Rocks alter) with allowance for public access (minimum 1 m) around the temple and the Fung Shui rocks shall be provided. The open yard in front of the temple should be kept as usual for annual Tin Hau festival.
- 7.11 As there is a large buffer distance from the current works to Cha Kwo Ling Tin Hau Temple and the Fung Shui rocks (Child-given rocks), the temporarily fenced-off rocks buffer zone and from the edge of Rocks alter is not required. The fenced-off rocks buffer zone would be implemented when there is construction activities in vicinity of the cultural heritage.

## **8. LANDSCAPE AND VISUAL IMPACT REQUIREMENTS**

- 8.1 Landscape and visual mitigation measures during the construction phase shall be checked to ensure that they are fully realized and implemented on site.
- 8.2 Site audits were carried out on a weekly basis to monitor and audit the timely implementation of landscape and visual mitigation measures listed in “Implementation Schedule and Recommended Mitigation Measures” (shown in **Appendix N**). The summaries of observations and recommendations related to landscape and visual impacts, if any, are shown in **Appendix L**.
- 8.3 No non-compliance of the landscape and visual impact was recorded in the reporting month.

## 9. LANDFILL GAS MONITORING

### Monitoring Requirement

- 9.1 In accordance with the EM&A Manual, monitoring of landfill gas is required for construction works within the Sai Tso Wan Landfill Consultation Zone during the construction phase. This section presents the results of landfill gas measurements performed by the Contractor. **Appendix A** shows the Limit Levels for the monitoring works.
- 9.2 The “Landfill Gas Monitoring Proposal”, including the monitoring programme and detailed actions, is submitted to the EPD for approval. Details of monitoring in this Proposal is in line with the monitoring requirements stipulated in the EM&A Manual.

### Monitoring Parameters and Frequency

- 9.3 Monitoring parameters for Landfill gas monitoring include Methane, Carbon dioxide and Oxygen.
- 9.4 According to the implementation schedule and recommended mitigation measures of the EM&A Manual, measurements of the following frequencies should be carried out:

#### Excavations deeper than 1m

- at the ground surface before excavation commences:-
- immediately before any worker enters the excavation;
- at the beginning of each working day for the entire period the excavation remains open; and
- periodically throughout the working day whilst workers are in the excavation.

#### Excavations between 300mm and 1m deep

- directly after the excavation has been completed; and
- periodically whilst the excavation remains open.

#### For excavations less than 300mm deep

- monitoring may be omitted, at the discretion of the Safety Officer or other appropriately qualified person

### Monitoring Locations

- 9.5 Monitoring of oxygen, methane and carbon dioxide was performed for excavations at 1m depth or more within the Consultation Zone. In this reporting month, the area required to be monitored for landfill gas are shown below and **Figure 6** shows the landfill gas monitoring locations.

- |                                   |             |
|-----------------------------------|-------------|
| ➤ Excavation Locations:           | Portion III |
| ➤ Manholes and Chambers:          | N/A         |
| ➤ Relocation of monitoring wells: | N/A         |
| ➤ Any other Confined Spaces:      | N/A         |



**Monitoring Equipment**

- 9.6 **Table 9.1** summarizes the equipment employed by the Contractor for the landfill gas monitoring.

**Table 9.1 Landfill Gas Monitoring Equipment**

| <b>Equipment</b>      | <b>Model and Make</b>  | <b>Quantity</b> |
|-----------------------|--|-----------------|
| Portable gas detector | ALTAIR 5X<br>Multigas Detector<br>(Serial No. 120848 / 120847) | 2               |

**Results and Observations**

- 9.7 In the reporting month, landfill gas monitoring was carried out by the Contractor at the aforesaid locations on 50 occasions. No Limit Level exceedance for landfill gas monitoring was recorded in the reporting month. The monitoring results are provided in **Appendix R**. Copies of calibration certificates are attached in **Appendix B**.

## 10. ENVIRONMENTAL AUDIT

### Site Audits

- 10.1 Site audits were carried out on a weekly basis to monitor the timely implementation of proper environmental management practices and mitigation measures in the Project site. The summaries of site audits are attached in **Appendix L**.
- 10.2 Joint weekly site audits by the representatives of the Engineer, Contractor and the ET were conducted in the reporting month as shown in below:
- Contract No. NE/2015/01: 6, 13, 20 and 27 June 2018
  - Contract No. NE/2015/02: 6, 13, 20 and 27 June 2018
  - Contract No. NE/2015/03: 6, 13, 20 and 27 June 2018
  - Contract No. NE/2017/01: 6, 13, 20 and 27 June 2018
  - Contract No. NE/2017/02: 6, 13, 20 and 27 June 2018
- Monthly joint site inspection with the representative of IEC was conducted for NE/2015/01, NE/2015/02, NE/2015/03, NE/2017/01 and NE/2017/02 on 27, 13, 13, 27, 13 June 2018 respectively.

### Implementation Status of Environmental Mitigation Measures

- 10.3 According to the EIA Study Report, Environmental Permit and the EM&A Manual of the Project, the mitigation measures detailed in the documents are recommended to be implemented during the construction phase. An updated summary of the Implementation Schedule and Recommended Mitigation Measures is provided in **Appendix N**.
- 10.4 During site inspections in the reporting month, no non-compliance was identified. The observations and recommendations made during the audit sessions are summarized in **Appendix L**.

---

## 11. WASTE MANAGEMENT

- 11.1 Waste generated from this Project includes inert construction and demolition (C&D) materials, non-inert C&D materials and marine sediments. Inert C&D waste includes soil, broken rock, broken concrete and building debris, while non-inert C&D materials are made up of C&D waste which cannot be reused or recycled and has to be disposed of at the designated landfill sites. Marine sediment shall be expected from excavation and dredging works of this Project.
- 11.2 With reference to relevant handling records of this Project, the quantities of different types of waste generated in the reporting month are summarised and presented in **Appendix P**.
- 11.3 The Contractors are advised to minimize the wastes generated through the recycling or reusing. All mitigation measures stipulated in the approved EM&A Manual and waste management plans shall be fully implemented. The status of implementation of waste management and reduction measures are summited in **Appendix N**.

---

## 12. ENVIRONMENTAL NON-CONFORMANCE

### Summary of Exceedances

- 12.1 Four (4) Action Level exceedances were recorded due to the documented complaints received in the reporting month and Twelve (12) Limit Level exceedances for noise monitoring were recorded in the reporting month.
- 12.2 No Action Level and Fourteen (14) Limit Level exceedances for groundwater quality monitoring were recorded in the reporting month.
- 12.3 Actions carried out in accordance with the Event and Action Plans in **Appendix M** are presented in **Appendix K** – Summary of Exceedance.

### Summary of Environmental Non-Compliance

- 12.4 No environmental non-compliance was recorded in the reporting month.
- 12.5 After complaint investigation, non-compliances were recorded on 16<sup>th</sup>, 18<sup>th</sup> and 23<sup>rd</sup> April 2018 for Contract No. NE/2015/02 due to non-conformance with the proposed quantity of powered mechanical equipment stated in the CNMP. Details of investigation are presented in **Appendix O**.

### Summary of Environmental Complaint

- 12.6 Ten (10) environmental complaints were received in the reporting month. The Cumulative Complaint Log is presented in **Appendix O**. The investigation status and result is also reported in **Appendix O**.

### Summary of Environmental Summon and Successful Prosecution

- 12.7 No notification of summon was received in this reporting period. One successful environmental prosecution to the subcontractor under Contract No. NE/2015/02 was received in this reporting period. The Cumulative Log for environmental summon and successful prosecution since the commencement of the Project is presented in **Appendix O**.

**13. FUTURE KEY ISSUES**

13.1 Tentative construction programmes for the next three months are provided in **Appendix Q**.

13.2 Major site activities to be undertaken for the next reporting period are summarized in **Table 13.1**.

**Table 13.1 Summary Table for Site Activities in the next Reporting Period**

| <b>Contract No.</b> | <b>Project Title</b>  | <b>Site Activities (July 2018)</b>   |   |
|---------------------|---|--|---|
| NE/2015/01          | Tseung Kwan O – Lam Tin Tunnel – Main Tunnel and Associated Works | Lam Tin Interchange  | 1) EHC2 U-Trough<br>2) Site Formation – Area 1G1, Area 1G2, Area 2, Area 3, Area 4 & Area 5             |
|                     |   | Main Tunnel  | 1) Main Tunnel Excavation   |
|                     |   | TKO Interchange  | 1) Haul Road Construction and Site Formation & Slope Works<br>2) Steel Platform for Bridge Construction |
| NE/2015/02          | Tseung Kwan O – Lam Tin Tunnel – Road P2 and Associated Works     | 1) Pre-bored works, sheet piling and interlocking pipe piles installation works at Portion IV & VII<br>2) Removal of existing seawall blocks at Portion IV & VII<br>3) Reconstruction of existing outfall and installation of DN2100 drainage system at Portion IV & VII<br>4) Pre-bored works at Portion V & VI<br>5) Waterproofing, backfilling works and wall construction at Portion VIII<br>6) Dredging at Portion IX<br>7) Seawall Construction at Portion IX<br>8) Placing sand blanket at non-dredged area at Portion IX |   |
| NE/2015/03          | Tseung Kwan O – Lam Tin Tunnel – Northern Footbridge              | 1) Construction of main deck<br>2) Construction of lift shaft and sum pit  |   |
| NE/2017/01          | Tseung Kwan O Interchange and Associated Works                    | 1) Construction of Site Office<br>2) Temporary Platform and Ground Investigation   |   |
| NE/2017/02          | Tseung Kwan O - Lam Tin Tunnel - Road P2/D4 and Associated Works  | 1) Trial pit<br>2) Underground utilities detection<br>3) Temporary traffic arrangement Setup<br>4) Site office erection<br>5) Communication Liaison Center erection<br>6) Modification of traffic island<br>7) Fencing erection<br>8) Predrilling<br>9) Construction of Temporary cycle track<br>10) Construction of drainage and watermain  |   |

### **Key Issues for the Coming Month**

13.3 Key environmental issues in the coming month include:

- Watering for dust generation from haul road, stockpiles of dusty materials, exposed site area, excavation works and rock breaking activities;
- Noisy construction activity such as rock-breaking activities and piling works;
- Runoff from exposed slope or site area;
- Wastewater and runoff discharge from site;
- Accumulation of silt, mud and sand along U-channels and sedimentation tanks;
- Set up and implementation of temporary drainage system for the surface runoff;
- Storage of chemicals/fuel and chemical waste/waste oil on site;
- Accumulation and storage of general and construction waste on site; and
- Marine water quality impact and indirect impact to coral communities due to marine construction for TKO-LTT reclamation.

### **Monitoring Schedule for the Next Month**

13.4 The tentative environmental monitoring schedules for the next month are shown in **Appendix D**.

## 14. CONCLUSIONS AND RECOMMENDATIONS

### Conclusions

- 14.1 This is the 20<sup>th</sup> Environmental Monitoring and Audit (EM&A) Report which presents the EM&A works undertaken during the period in June 2018 in accordance with EM&A Manual and the requirement under EP.

#### Air Quality Monitoring

- 14.2 All 1-hour TSP monitoring was conducted as scheduled in the reporting month. No Action/Limit Level exceedance was recorded.
- 14.3 All 24-hour TSP monitoring was conducted as scheduled in the reporting month. No Action/Limit Level exceedance was recorded.

#### Construction Noise Monitoring

- 14.4 All noise monitoring was conducted as scheduled in the reporting month. Four (4) Action Level exceedances were recorded due to the documented complaints received in this reporting month and Twelve (12) Limit Level exceedances were recorded in the reporting month.

#### Water Quality Monitoring

- 14.5 Groundwater quality monitoring was conducted as scheduled in the reporting month. No Action Level and Fourteen (14) Limit Level exceedances were recorded in the reporting month. The exceedances are considered due to rainfall and human activities, therefore non-Project related.
- 14.6 Tunnel construction activities are within +/- 50m of the piezometer gate in plan. Construction phase daily piezometer monitoring by the Contractor commenced in June 2018. No Action Level exceedance was recorded in the reporting month.
- 14.7 All marine water monitoring was conducted as scheduled in the reporting month. No Action/Limit Level exceedance was recorded.

#### Ecological Monitoring

- 14.8 The post-translocation coral monitoring surveys were completed in November 2017.

#### Monitoring on Cultural Heritage

- 14.9 No Alert Alarm and Action (AAA) Level exceedance of cultural heritage monitoring on cultural heritage was recorded in the reporting month.

#### Landscape and Visual Monitoring and Audit

- 14.10 No non-compliance of the landscape and visual impact was recorded in the reporting month.

#### Landfill Gas Monitoring

- 14.11 Monitoring of landfill gases in the reporting month was carried out by the Contractor at excavation location, Portion III. No Limit Level exceedance was recorded.

#### Environmental Site Inspection

- 14.12 Joint weekly site inspections were conducted by representatives of the Contractor, Engineer and Environmental Team. During site inspections in the reporting month, no non-compliance was identified. The environmental deficiency observed during the reporting month are shown in **Appendix L**.

#### Complaint, Prosecution and Notification of Summons

- 14.13 Ten (10) environmental complaints, no successful prosecution and notification of summon were received during the reporting period.

#### **Recommendations**

- 14.14 The following recommendations were made to the Contractor for the reporting month:

##### *Air Quality Impact*

- To implement dust suppression measures such as water spray on all haul roads, stockpiles, dry surfaces and open slopes.
- To cover stockpile of dusty material by impervious material.
- To avoid dark smoke emitted from the generator.

##### *Construction Noise*

- To provide noise mitigation measures (e.g. Temporary noise barrier or Full enclosure) to PME as proposed in the approved Noise Mitigation Plan.
- To repair the gaps between the noise barriers.

##### *Water Quality Impact*

- To provide and repair the silt curtain to fully enclose the site and prevent any gap between the silt curtains.
- To review and implement temporary drainage system.
- To clear the litter, debris, silt and sediment in drainage or catchpits.
- To remove the sand or dusty material deposited near the seafront.
- To provide bund or covers to gullies and stockpile storage area on site to avoid leakage of surface runoff.
- To divert all the water generated from construction site to de-silting facilities with enough handling capacity before discharge.
- To maintain the sedimentation tank more frequently to ensure proper wastewater treatment before discharge.

##### *Waste/Chemical Management*

- To remove construction waste regularly.
- To avoid any discharge or accidental spillage of chemical waste or oil directly from the equipment.
- To provide drip tray to chemical containers to avoid any chemical leakage.
- To remove the oil stain and disposed of as chemical waste.
- To remove the stagnant water regularly found inside the drip tray.

##### *Landscape and Visual*

- To set up proper tree protection area.
- To avoid placing any construction materials in the tree protection zone.




---

---





## FIGURES

---

---




LEGEND:


|  |                         |
|--|-------------------------|
|  | Contract No. NE/2015/01 |
|  | Contract No. NE/2015/02 |
|  | Contract No. NE/2015/03 |
|  | Contract No. NE/2017/02 |
|  | Contract No. NE/2017/01 |

**CINOTECH**  
Cinotech Consultants Limited


Agreement No. CE/59/2015 (EP)  
Environmental Team for Tseung Kwan O - Lam Tin Tunnel  
- Design and Construction  
Site Layout Plan

|         |              |            |          |
|---------|--------------|------------|----------|
| SCALE   | 1:15000 @ A4 | DATE       | APR 2018 |
| CHECK   | JF           | DRAWN      | AC       |
| JOB No. | MA16034      | FIGURE NO. | 1        |
|         |              | REV        | -        |







|         |              |            |          |          |
|---------|--------------|------------|----------|----------|
| SCALE   | 1:15000 @ A4 | DATE       | AUG 2018 |          |
| CHECK   | VC           | DRAWN      | JW       |          |
| JOB No. | MA16034      | FIGURE NO. | 1b       | REV<br>- |



|         |         |            |          |          |
|---------|---------|------------|----------|----------|
| SCALE   | N.T.S.  | DATE       | AUG 2017 |          |
| CHECK   | JF      | DRAWN      | JW       |          |
| JOB No. | MA16034 | FIGURE NO. | 1c       | REV<br>- |



|         |             |            |          |
|---------|-------------|------------|----------|
| SCALE   | 1:2500 @ A4 | DATE       | AUG 2018 |
| CHECK   | VC          | DRAWN      | AC       |
| JOB No. | MA16034     | FIGURE NO. | 1d       |
|         |             | REV        | -        |




???

JUNK BAY  
(TSEUNG KWAN O)




Agreement No. CE/59/2015 (EP)  
 Environmental Team for Tseung Kwan O - Lam Tin Tunnel  
 - Design and Construction  
 Site Portions under Work Contract No. NE/2017/01


|         |             |            |          |
|---------|-------------|------------|----------|
| SCALE   | 1:2500 @ A4 | DATE       | AUG 2018 |
| CHECK   | VC          | DRAWN      | AC       |
| JOB No. | MA16034     | FIGURE NO. | 1e       |
|         |             | REV        | -        |




|         |             |            |          |     |
|---------|-------------|------------|----------|-----|
| SCALE   | 1:1500 @ A4 | DATE       | AUG 2018 |     |
| CHECK   | VC          | DRAWN      | AC       |     |
| JOB No. | MA16034     | FIGURE NO. | 1f       | REV |
|         |             |            |          | -   |







|         |             |            |          |     |
|---------|-------------|------------|----------|-----|
| SCALE   | 1:1500 @ A4 | DATE       | AUG 2018 |     |
| CHECK   | VC          | DRAWN      | AC       |     |
| JOB No. | MA16034     | FIGURE NO. | 1h       | REV |
|         |             |            |          | -   |




LEGEND:

-  PROJECT BOUNDARY
-  AIR QUALITY MONITORING STATION



**CINOTECH**  
Cinotech Consultants Limited

Agreement No. CE/59/2015 (EP)  
Environmental Team for Tseung Kwan O - Lam Tin Tunnel -  
Design and Construction  
Air Quality Monitoring Stations


|         |              |            |          |          |
|---------|--------------|------------|----------|----------|
| SCALE   | 1:15000 @ A4 | DATE       | JAN 2018 |          |
| CHECK   | JF           | DRAWN      | JW       |          |
| JOB No. | MA16034      | FIGURE NO. | 2        | REV<br>- |







LEGEND:

-  PROJECT BOUNDARY
-  NOISE MONITORING STATION

|         |              |            |          |          |
|---------|--------------|------------|----------|----------|
| SCALE   | 1:15000 @ A4 | DATE       | JAN 2018 |          |
| CHECK   | JF           | DRAWN      | JW       |          |
| JOB No. | MA16034      | FIGURE NO. | 3        | REV<br>- |




**LEGEND:**

-  SITE BOUNDARY
-  STREAM
-  SAMPLING LOCATIONS FOR GROUNDWATER QUALITY
-  SAMPLING LOCATIONS FOR GROUNDWATER LEVEL

**CINOTECH**  
Cinotech Consultants Limited

Agreement No. CE/59/2015 (EP)  
 Environmental Team for Tseung Kwan O - Lam Tin Tunnel -  
 Design and Construction  
 Location of Streams for Groundwater Quality and Groundwater Level Monitoring

|         |              |            |          |     |
|---------|--------------|------------|----------|-----|
| SCALE   | 1:10000 @ A4 | DATE       | APR 2017 |     |
| CHECK   | JF           | DRAWN      | JW       |     |
| JOB No. | MA16034      | FIGURE NO. | 4        | REV |
|         |              |            |          | -   |



**CINOTECH**

Cinotech Consultants Limited

Agreement No. CE/59/2015 (EP)  
 Environmental Team for Tseung Kwan O – Lam Tin Tunnel –  
 Design and Construction

**Locations of Water Quality Monitoring Stations**

|             |         |            |          |          |
|-------------|---------|------------|----------|----------|
| SCALE       | N.T.S   | DATE       | AUG 2016 |          |
| CHECK       | JF      | DRAWN      | JW       |          |
| PROJECT NO. | MA16034 | FIGURE NO. | 5        | REV<br>— |




Title Agreement No. CE/59/2015 (EP)  
 Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction  
 Locations of Landfill Gas Monitoring

Scale N.T.S  
 Date Dec-16

Project No. MA16034  
 Figure 6







Title Agreement No. CE/59/2015 (EP)  
 Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction  
 Location of Post-translocation Coral Monitoring

Scale N.T.S  
 Date Mar-17

Project No. MA16034  
 Figure 7









**LEGEND**

- SITE BOUNDARY
- 100M FORM THE CHA KWO LING TIN HAU TEMPLE
- CHA KWO LING TIN HAU TEMPLE
- X VIBRATION MONITORING POINT
- ⊗ BUILDING SETTLEMENT POINTS


|         |         |            |          |          |
|---------|---------|------------|----------|----------|
| SCALE   | N.T.S.  | DATE       | FEB 2018 |          |
| CHECK   | JF      | DRAWN      | AC       |          |
| JOB No. | MA16034 | FIGURE NO. | 8        | REV<br>- |



# LEGEND



IMPACT STATIONS



LOCATION OF TEMPORARY MARINE EMBAYMENT BY STEEL COFFERDAM



RECLAMATION FOOTPRINT

CURRENT SHORELINE

|             |         |            |          |
|-------------|---------|------------|----------|
| SCALE       | N.T.S   | DATE       | MAY 2017 |
| CHECK       | JF      | DRAWN      | JW       |
| PROJECT NO. | MA16034 | FIGURE NO. | 9        |
|             |         | REV        | —        |

---

---

**APPENDIX A  
ACTION AND LIMIT LEVELS**

---

---

## APPENDIX A – Action and Limit Levels

### Air Quality

#### *1-hr TSP*

| Monitoring Stations | Location                                 | Action Level, $\mu\text{g}/\text{m}^3$ | Limit Level, $\mu\text{g}/\text{m}^3$ |
|---------------------|--|--|---------------------------------------|
| AM1                 | Tin Hau Temple                           | 275                                    | 500                                   |
| AM2                 | Sai Tso Wan Recreation Ground            | 273                                    |                                       |
| AM3                 | Yau Lai Estate Bik Lai House             | 271                                    |                                       |
| AM4                 | Sitting-out Area at Cha Kwo Ling Village | 278                                    |                                       |
| AM5(A)              | Tseung Kwan O DSD Desilting Compound     | 273                                    |                                       |
| AM6(A)              | Park Central, L1/F Open Space Area       | 285                                    |                                       |

#### *24-hr TSP*

| Monitoring Stations | Location  | Action Level, $\mu\text{g}/\text{m}^3$ | Limit Level, $\mu\text{g}/\text{m}^3$ |
|---------------------|---|--|---------------------------------------|
| AM1                 | Tin Hau Temple  | 173                                    | 260                                   |
| AM2                 | Sai Tso Wan Recreation Ground                                   | 192                                    |                                       |
| AM3                 | Yau Lai Estate Bik Lai House                                    | 167                                    |                                       |
| AM4(A)              | Cha Kwo Ling Public Cargo Working Area<br>Administrative Office | 210                                    |                                       |
| AM5(A)              | Tseung Kwan O DSD Desilting Compound                            | 175                                    |                                       |
| AM6(A)              | Park Central, L1/F Open Space Area                              | 165                                    |                                       |

### Noise

| Time Period   | Action Level                              | Limit Level                      |
|---|---|----------------------------------|
| 0700-1900 hrs on normal weekdays  | When one documented complaint is received | 75 dB(A) <sup>(1)</sup>          |
| 1900-2300 on all days and 0700-2300 on general holidays (including Sundays) |   | 60/65/70 dB(A) <sup>(2)(3)</sup> |
| 2300-0700 on all days   |   | 45/50/55 dB(A) <sup>(2)(3)</sup> |

<sup>1</sup> 70 dB(A) for schools and 65 dB(A) for schools during examination period.

<sup>2</sup> Acceptable Noise Levels for Area Sensitivity Rating of A/B/C

<sup>3</sup> If works are to be carried out during restricted hours, the conditions stipulated in the construction noise permit issued by the Noise Control Authority have to be followed.

## Water Quality

### *Groundwater*

| <b>Parameters</b>                      | <b>Action</b>            | <b>Limit</b>             |
|--|--------------------------|--------------------------|
| DO in mg L <sup>-1</sup>               | 7.6                      | 7.6                      |
| pH                                     | 6.0 – 8.9                | 6.0 – 9.0                |
| BOD <sub>5</sub> in mg L <sup>-1</sup> | 2.0                      | 2.0                      |
| TOC in mg L <sup>-1</sup>              | Stream 1 and Stream 2: 9 | Stream 1 and Stream 2: 9 |
|  | Stream 3: 6              | Stream 3: 6              |
| Total Nitrogen in mg L <sup>-1</sup>   | 2.0                      | 2.1                      |
| Ammonia-N in mg L <sup>-1</sup>        | 0.15                     | 0.20                     |
| Total Phosphate in mg L <sup>-1</sup>  | 0.05                     | 0.05                     |
| SS in mg L <sup>-1</sup>               | 7.6                      | 12.1                     |
| Turbidity in NTU                       | 2.1                      | 2.3                      |

Notes:

1. For pH, non-compliance of the water quality limits occurs when monitoring result is out of the range of the limits.
2. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
3. For turbidity, SS, 5-day biochemical oxygen demand (BOD<sub>5</sub>), Total organic carbon (TOC), Total Nitrogen, Ammonia-N and Total Phosphate, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
4. All the figures given in the table are used for reference only and the EPD may amend the figures whenever it is considered as necessary.

### *Groundwater Level Monitoring*

| <b>Drill Hole No.</b> | <b>38568-LDH1</b> | <b>TKO-LBH907</b> |
|-----------------------|-------------------|-------------------|
| Action Level (mPD)    | +74.65            | +17.59            |

*Marine Water Quality*

| <u>Parameter<br/>(unit)</u>               | <u>Depth</u>                        | <u>Action Level</u>   | <u>Limit Level</u>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in NTU<br>(See Note 2, 4 and 5) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
| SS in mg/L<br>(See Note 2, 4 and 5)       | <b><u>Stations G1-G4</u></b>        |   |   |
|   | Surface                             | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day        | <u>6.9mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day         |
|   | <b><u>Stations M1-M5</u></b>        |   |   |
|   | Surface                             | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day        | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day        |
|   | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day        | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day        |
| <b><u>Station M6</u></b>                  |                                     |   |   |
|   | Intake Level                        | <u>8.3 mg/L</u>   | <u>8.6 mg/L</u>   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.
5. Refer to Appendix I – Marine Water Quality Monitoring Results and Graphical Presentations for results of upstream control stations at each tide on each day.

### *Water Quality Monitoring in Temporary Marine Embayment*

| Parameter (unit)                 | Depth         | Action Level                   | Limit Level                  |
|----------------------------------|---------------|--------------------------------|------------------------------|
| DO in mg/L<br>(See Note 1 and 2) | Depth Average | <u>4.8 mg/L</u> <sup>(4)</sup> | <u>4 mg/L</u> <sup>(3)</sup> |
|                                  | Bottom        | <u>2.4 mg/L</u> <sup>(4)</sup> | <u>2 mg/L</u> <sup>(3)</sup> |

Notes:

1. "depth-averaged" is calculated by taking the arithmetic means of reading of all sampling depths.
2. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
3. Current Water Quality Objectives (WQOs) for marine waters of Hong Kong
4. As an alert for adverse water quality impact, the Action Level is set as 120% of the Current WQOs for marine waters of Hong Kong.

### Ecology

#### *Post-translocation Coral Monitoring*

| Parameter        | Action Level Definition   | Limit Level Definition  |
|------------------|---|---|
| <b>Mortality</b> | If during Impact Monitoring a 15% increase in the percentage of partial mortality on hard corals occurs at more than 20% of the tagged coral at any one Impact Monitoring Site that is not recorded at the Control Site, then the Action Level is exceeded. | If during the Impact Monitoring a 25% increase in the percentage of partial mortality occurs at more than 20% of the tagged coral at any one Impact Monitoring Site that is not recorded at the Control Site, then the Limit Level is exceeded. |

### Landfill Gas Monitoring

| Parameter      | Limit Level                      |
|----------------|----------------------------------|
| Oxygen         | <19%                             |
|                | <18%                             |
| Methane        | >10% LEL (i.e. > 0.5% by volume) |
|                | >20% LEL (i.e. > 1% by volume)   |
| Carbon Dioxide | >0.5%                            |
|                | >1.5%                            |

### Alert, Alarm, Action Levels for Built Heritage Monitoring

| Parameter                 | Alert Level | Alarm Level  | Action Level  |
|---------------------------|-------------|--------------|---|
| Vibration                 | ppv:4.5mm/s | ppv: 4.8mm/s | ppv: 5mm/s<br>Maximum Allowable Vibration Amplitude:<br>0.1mm |
| Building Settlement Point | 6mm         | 8mm          | 10mm  |
| Building Tilting          | 1:2000      | 1:1500       | 1:1000  |

---

---

**APPENDIX B  
COPIES OF CALIBRATION  
CERTIFICATES**

---

---



# High-Volume TSP Sampler 5-POINT CALIBRATION DATA SHEET

**CINOTECH**

File No. MA16034/05/0011

Project No. AMI - Tin Hau Temple

Date: 27-Apr-18

Next Due Date: 26-Jun-18

Operator: MH

Equipment No.: A-01-05

Model No.: GS2310

Serial No.: 10599

| Ambient Condition   |       |                     |       |
|---------------------|-------|---------------------|-------|
| Temperature, Ta (K) | 297.3 | Pressure, Pa (mmHg) | 764.7 |

| Orifice Transfer Standard Information |           |  |        |               |          |
|---------------------------------------|-----------|--|--------|---------------|----------|
| Serial No.                            | 2896      | Slope, mc  | 0.0585 | Intercept, bc | -0.00045 |
| Last Calibration Date:                | 13-Feb-18 | $mc \times Qstd + bc = [\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ |        |               |          |
| Next Calibration Date:                | 13-Feb-19 | $Qstd = \{[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2} - bc\} / mc$  |        |               |          |

| Calibration of TSP Sampler |                                    |  |                        |                                |   |
|----------------------------|------------------------------------|--|------------------------|--------------------------------|---|
| Calibration Point          | Orifice                            |  |                        | HVS                            |   |
|                            | $\Delta H$ (orifice), in. of water | $[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ | Qstd (CFM)<br>X - axis | $\Delta W$ (HVS), in. of water | $[\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$ Y-axis |
| 1                          | 13.0                               | 3.62   | 61.87                  | 7.2                            | 2.69  |
| 2                          | 9.7                                | 3.13   | 53.45                  | 5.6                            | 2.38  |
| 3                          | 8.6                                | 2.95   | 50.33                  | 4.8                            | 2.20  |
| 4                          | 5.4                                | 2.33   | 39.88                  | 3.3                            | 1.82  |
| 5                          | 3.0                                | 1.74   | 29.73                  | 2.0                            | 1.42  |

By Linear Regression of Y on X

Slope, mw = 0.0396

Intercept, bw = 0.2401

Correlation coefficient\* = 0.9992

\*If Correlation Coefficient < 0.990, check and recalibrate.

### Set Point Calculation

From the TSP Field Calibration Curve, take Qstd = 43 CFM

From the Regression Equation, the "Y" value according to

$$mw \times Qstd + bw = [\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$$

Therefore, Set Point;  $W = (mw \times Qstd + bw)^2 \times (760 / Pa) \times (Ta / 298) =$  3.74

Remarks: \_\_\_\_\_

Conducted by: Hei Man Ho

Signature: \_\_\_\_\_

Date: 27/4/2018

Checked by: Wk Tang

Signature: \_\_\_\_\_

Date: 27/4/2018

# High-Volume TSP Sampler

## 5-POINT CALIBRATION DATA SHEET

**CINOTECH**

File No. MA16034/05/0012

Project No. AM1 - Tin Hau Temple

Date: 26-Jun-18

Next Due Date: 25-Aug-18

Operator: MH

Equipment No.: A-01-05

Model No.: GS2310

Serial No.: 10599

| Ambient Condition   |       |                     |       |
|---------------------|-------|---------------------|-------|
| Temperature, Ta (K) | 302.5 | Pressure, Pa (mmHg) | 758.6 |

| Orifice Transfer Standard Information |           |  |        |               |          |
|---------------------------------------|-----------|--|--------|---------------|----------|
| Serial No.                            | 2896      | Slope, mc  | 0.0585 | Intercept, bc | -0.00045 |
| Last Calibration Date:                | 13-Feb-18 | $mc \times Qstd + bc = [\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ |        |               |          |
| Next Calibration Date:                | 13-Feb-19 | $Qstd = \{[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2} - bc\} / mc$  |        |               |          |

| Calibration of TSP Sampler |                                    |  |                        |                                |   |
|----------------------------|------------------------------------|--|------------------------|--------------------------------|---|
| Calibration Point          | Orifice                            |  |                        | HVS                            |   |
|                            | $\Delta H$ (orifice), in. of water | $[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ | Qstd (CFM)<br>X - axis | $\Delta W$ (HVS), in. of water | $[\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$ Y-axis |
| 1                          | 13.2                               | 3.60   | 61.56                  | 7.6                            | 2.73  |
| 2                          | 9.4                                | 3.04   | 51.95                  | 5.4                            | 2.30  |
| 3                          | 8.2                                | 2.84   | 48.52                  | 4.6                            | 2.13  |
| 4                          | 5.3                                | 2.28   | 39.01                  | 3.3                            | 1.80  |
| 5                          | 3.1                                | 1.75   | 29.84                  | 2.0                            | 1.40  |

**By Linear Regression of Y on X**

Slope, mw = 0.0413

Intercept, bw = 0.1662

Correlation coefficient\* = 0.9984

\*If Correlation Coefficient < 0.990, check and recalibrate.

### Set Point Calculation

From the TSP Field Calibration Curve, take Qstd = 43 CFM

From the Regression Equation, the "Y" value according to

$$mw \times Qstd + bw = [\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$$

Therefore, Set Point;  $W = (mw \times Qstd + bw)^2 \times (760 / Pa) \times (Ta / 298) =$  3.84

Remarks: \_\_\_\_\_

Conducted by: [Signature]

Signature: \_\_\_\_\_

Date: 26/6/2018

Checked by: [Signature]

Signature: \_\_\_\_\_

Date: 26/6/2018

# High-Volume TSP Sampler

## 5-POINT CALIBRATION DATA SHEET

**CINOTECH**

File No. MA16034/08/0011

Project No. AM2 - Sai Tso Wan Recreation Ground

Date: 27-Apr-18

Next Due Date: 26-Jun-18

Operator: MH

Equipment No.: A-01-08

Model No.: GS2310

Serial No.: 1287

| Ambient Condition   |       |                     |       |
|---------------------|-------|---------------------|-------|
| Temperature, Ta (K) | 297.6 | Pressure, Pa (mmHg) | 764.2 |

| Orifice Transfer Standard Information |           |  |        |               |          |
|---------------------------------------|-----------|--|--------|---------------|----------|
| Serial No.                            | 2896      | Slope, mc  | 0.0585 | Intercept, bc | -0.00045 |
| Last Calibration Date:                | 13-Feb-18 | $mc \times Qstd + bc = [\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ |        |               |          |
| Next Calibration Date:                | 13-Feb-19 | $Qstd = \{[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2} - bc\} / mc$  |        |               |          |

| Calibration of TSP Sampler |                                    |  |                        |                                |   |
|----------------------------|------------------------------------|--|------------------------|--------------------------------|---|
| Calibration Point          | Orifice                            |  |                        | HVS                            |   |
|                            | $\Delta H$ (orifice), in. of water | $[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ | Qstd (CFM)<br>X - axis | $\Delta W$ (HVS), in. of water | $[\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$ Y-axis |
| 1                          | 13.4                               | 3.67   | 62.77                  | 8.1                            | 2.86  |
| 2                          | 10.6                               | 3.27   | 55.82                  | 6.4                            | 2.54  |
| 3                          | 8.9                                | 2.99   | 51.15                  | 5.3                            | 2.31  |
| 4                          | 5.4                                | 2.33   | 39.85                  | 3.2                            | 1.79  |
| 5                          | 3.2                                | 1.79   | 30.68                  | 2.0                            | 1.42  |

**By Linear Regression of Y on X**

Slope,  $mw =$  0.0450

Intercept,  $bw =$  0.0209

Correlation coefficient\* = 0.9996

\*If Correlation Coefficient < 0.990, check and recalibrate.

### Set Point Calculation

From the TSP Field Calibration Curve, take Qstd = 43 CFM

From the Regression Equation, the "Y" value according to

$$mw \times Qstd + bw = [\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$$

Therefore, Set Point;  $W = (mw \times Qstd + bw)^2 \times (760 / Pa) \times (Ta / 298) =$  3.80

Remarks: \_\_\_\_\_

Conducted by: Leo Man Ng Signature: \_\_\_\_\_

Date: 27/4/2018

Checked by: Wk Tang Signature: \_\_\_\_\_

Date: 27/4/2018

# High-Volume TSP Sampler 5-POINT CALIBRATION DATA SHEET

**CINOTECH**

File No. MA16034/08/0012

Project No. AM2 - Sai Tso Wan Recreation Ground

Date: 26-Jun-18

Next Due Date: 25-Aug-18

Operator: MH

Equipment No.: A-01-08

Model No.: GS2310

Serial No.: 1287

| Ambient Condition   |       |                     |       |
|---------------------|-------|---------------------|-------|
| Temperature, Ta (K) | 301.5 | Pressure, Pa (mmHg) | 758.6 |

| Orifice Transfer Standard Information |           |  |        |               |          |
|---------------------------------------|-----------|--|--------|---------------|----------|
| Serial No.                            | 2896      | Slope, mc  | 0.0585 | Intercept, bc | -0.00045 |
| Last Calibration Date:                | 13-Feb-18 | $mc \times Qstd + bc = [\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ |        |               |          |
| Next Calibration Date:                | 13-Feb-19 | $Qstd = \{[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2} - bc\} / mc$  |        |               |          |

| Calibration of TSP Sampler |                                    |  |                        |                                |   |
|----------------------------|------------------------------------|--|------------------------|--------------------------------|---|
| Calibration Point          | Orifice                            |  |                        | HVS                            |   |
|                            | $\Delta H$ (orifice), in. of water | $[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ | Qstd (CFM)<br>X - axis | $\Delta W$ (HVS), in. of water | $[\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$ Y-axis |
| 1                          | 13.4                               | 3.64   | 62.13                  | 8.0                            | 2.81  |
| 2                          | 10.8                               | 3.26   | 55.78                  | 6.5                            | 2.53  |
| 3                          | 8.7                                | 2.93   | 50.06                  | 5.1                            | 2.24  |
| 4                          | 5.5                                | 2.33   | 39.81                  | 3.4                            | 1.83  |
| 5                          | 3.3                                | 1.80   | 30.84                  | 2.0                            | 1.40  |

**By Linear Regression of Y on X**

Slope, mw = 0.0446

Intercept, bw = 0.0361

Correlation coefficient\* = 0.9995

\*If Correlation Coefficient < 0.990, check and recalibrate.

**Set Point Calculation**

From the TSP Field Calibration Curve, take Qstd = 43 CFM

From the Regression Equation, the "Y" value according to

$$mw \times Qstd + bw = [\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$$

Therefore, Set Point;  $W = (mw \times Qstd + bw)^2 \times (760 / Pa) \times (Ta / 298) =$  3.87

Remarks: \_\_\_\_\_

Conducted by: Liz Man Ho Signature: *Liz Man Ho*  
 Checked by: Wah Tang Signature: *Wah Tang*

Date: 26/6/2018  
 Date: 26/6/2018

# High-Volume TSP Sampler 5-POINT CALIBRATION DATA SHEET

**CINOTECH**

File No. MA16034/03/0009

Project No. AM3 - Yau Lai Estate, Bik Lai House

Date: 27-Apr-18

Next Due Date: 26-Jun-18

Operator: MH

Equipment No.: A-01-03

Model No.: GS2310

Serial No.: 10379

| Ambient Condition   |       |                     |       |
|---------------------|-------|---------------------|-------|
| Temperature, Ta (K) | 297.7 | Pressure, Pa (mmHg) | 764.9 |

| Orifice Transfer Standard Information |           |  |        |               |          |
|---------------------------------------|-----------|--|--------|---------------|----------|
| Serial No.                            | 2896      | Slope, mc  | 0.0585 | Intercept, bc | -0.00045 |
| Last Calibration Date:                | 13-Feb-18 | $mc \times Qstd + bc = [\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ |        |               |          |
| Next Calibration Date:                | 13-Feb-19 | $Qstd = \{[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2} - bc\} / mc$  |        |               |          |

| Calibration of TSP Sampler |                                    |  |                     |                                |   |
|----------------------------|------------------------------------|--|---------------------|--------------------------------|---|
| Calibration Point          | Orifice                            |  |                     | HVS                            |   |
|                            | $\Delta H$ (orifice), in. of water | $[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ | Qstd (CFM) X - axis | $\Delta W$ (HVS), in. of water | $[\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$ Y-axis |
| 1                          | 12.4                               | 3.53   | 60.40               | 7.5                            | 2.75  |
| 2                          | 10.6                               | 3.27   | 55.84               | 6.7                            | 2.60  |
| 3                          | 7.4                                | 2.73   | 46.66               | 4.6                            | 2.15  |
| 4                          | 5.4                                | 2.33   | 39.86               | 3.4                            | 1.85  |
| 5                          | 3.2                                | 1.80   | 30.68               | 2.1                            | 1.45  |

**By Linear Regression of Y on X**

Slope, mw = 0.0444 Intercept, bw = 0.0898

Correlation coefficient\* = 0.9993

\*If Correlation Coefficient < 0.990, check and recalibrate.

**Set Point Calculation**

From the TSP Field Calibration Curve, take Qstd = 43 CFM

From the Regression Equation, the "Y" value according to

$$mw \times Qstd + bw = [\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$$

Therefore, Set Point; W =  $(mw \times Qstd + bw)^2 \times (760 / Pa) \times (Ta / 298) =$  3.96

Remarks: \_\_\_\_\_

Conducted by: Lee Man Hei Signature: Lee Man Hei  
 Checked by: Wick Tang Signature: Wick Tang

Date: 27/4/2018  
 Date: 27/4/2018

# High-Volume TSP Sampler

## 5-POINT CALIBRATION DATA SHEET

**CINOTECH**

File No. MA16034/03/0010

Project No. AM3 - Yau Lai Estate, Bik Lai House

Date: 26-Jun-18

Next Due Date: 25-Aug-18

Operator: MH

Equipment No.: A-01-03

Model No.: GS2310

Serial No.: 10379

| Ambient Condition   |       |                     |     |
|---------------------|-------|---------------------|-----|
| Temperature, Ta (K) | 301.4 | Pressure, Pa (mmHg) | 758 |

| Orifice Transfer Standard Information |           |  |        |               |          |
|---------------------------------------|-----------|--|--------|---------------|----------|
| Serial No.                            | 2896      | Slope, mc  | 0.0585 | Intercept, bc | -0.00045 |
| Last Calibration Date:                | 13-Feb-18 | $mc \times Qstd + bc = [\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ |        |               |          |
| Next Calibration Date:                | 13-Feb-19 | $Qstd = \{[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2} - bc\} / mc$  |        |               |          |

| Calibration of TSP Sampler |                                    |  |                        |                                |   |
|----------------------------|------------------------------------|--|------------------------|--------------------------------|---|
| Calibration Point          | Orifice                            |  |                        | HVS                            |   |
|                            | $\Delta H$ (orifice), in. of water | $[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ | Qstd (CFM)<br>X - axis | $\Delta W$ (HVS), in. of water | $[\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$ Y-axis |
| 1                          | 12.5                               | 3.51   | 59.99                  | 7.4                            | 2.70  |
| 2                          | 10.7                               | 3.25   | 55.51                  | 6.7                            | 2.57  |
| 3                          | 7.8                                | 2.77   | 47.39                  | 4.8                            | 2.18  |
| 4                          | 5.6                                | 2.35   | 40.16                  | 3.4                            | 1.83  |
| 5                          | 3.2                                | 1.78   | 30.36                  | 2.0                            | 1.40  |

**By Linear Regression of Y on X**

Slope,  $mw =$  0.0448

Intercept,  $bw =$  0.0431

Correlation coefficient\* = 0.9988

\*If Correlation Coefficient < 0.990, check and recalibrate.

| Set Point Calculation   |  |
|---|--|
| From the TSP Field Calibration Curve, take Qstd = 43 CFM  |  |
| From the Regression Equation, the "Y" value according to  |  |
| $mw \times Qstd + bw = [\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$                              |  |
| Therefore, Set Point; $W = (mw \times Qstd + bw)^2 \times (760 / Pa) \times (Ta / 298) =$ <u>3.94</u> |  |

Remarks: \_\_\_\_\_

Conducted by: Lee Man Hee Signature: \_\_\_\_\_  
 Checked by: W.K. Tang Signature: \_\_\_\_\_

Date: 26/6/2018  
 Date: 26/6/2018

# High-Volume TSP Sampler

## 5-POINT CALIBRATION DATA SHEET

**CINOTECH**

File No. MA16034/54/0011

Project No. AM4(A) - Cha Kwo Ling Public Cargo Working Area Administrative Office

Date: 27-Apr-18

Next Due Date: 26-Jun-18

Operator: MH

Equipment No.: A-01-54

Model No.: TE-5170

Serial No.: 1536

| Ambient Condition   |       |                     |       |
|---------------------|-------|---------------------|-------|
| Temperature, Ta (K) | 298.4 | Pressure, Pa (mmHg) | 763.6 |

| Orifice Transfer Standard Information |           |  |        |               |          |
|---------------------------------------|-----------|--|--------|---------------|----------|
| Serial No.                            | 2896      | Slope, mc  | 0.0585 | Intercept, bc | -0.00045 |
| Last Calibration Date:                | 13-Feb-18 | $mc \times Qstd + bc = [\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ |        |               |          |
| Next Calibration Date:                | 13-Feb-19 | $Qstd = \{[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2} - bc\} / mc$  |        |               |          |

| Calibration of TSP Sampler |                                    |  |                     |                                |   |
|----------------------------|------------------------------------|--|---------------------|--------------------------------|---|
| Calibration Point          | Orifice                            |  |                     | HVS                            |   |
|                            | $\Delta H$ (orifice), in. of water | $[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ | Qstd (CFM) X - axis | $\Delta W$ (HVS), in. of water | $[\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$ Y-axis |
| 1                          | 17.1                               | 4.14   | 70.78               | 10.6                           | 3.26  |
| 2                          | 13.4                               | 3.67   | 62.66               | 8.7                            | 2.95  |
| 3                          | 10.0                               | 3.17   | 54.13               | 6.2                            | 2.49  |
| 4                          | 6.7                                | 2.59   | 44.31               | 4.3                            | 2.08  |
| 5                          | 4.3                                | 2.08   | 35.50               | 2.7                            | 1.65  |

**By Linear Regression of Y on X**

Slope, mw = 0.0462

Intercept, bw = 0.0155

Correlation coefficient\* = 0.9990

\*If Correlation Coefficient < 0.990, check and recalibrate.

**Set Point Calculation**

From the TSP Field Calibration Curve, take Qstd = 43 CFM

From the Regression Equation, the "Y" value according to

$$mw \times Qstd + bw = [\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$$

Therefore, Set Point;  $W = (mw \times Qstd + bw)^2 \times (760 / Pa) \times (Ta / 298) =$  4.00

Remarks: \_\_\_\_\_

Conducted by: LFE Kwok Hoi Signature: \_\_\_\_\_  
 Checked by: Wk Tang Signature: \_\_\_\_\_

Date: 27/4/2018  
 Date: 27/4/2018

# High-Volume TSP Sampler

## 5-POINT CALIBRATION DATA SHEET

**CINOTECH**

File No. MA16034/54/0012

Project No. AM4(A) - Cha Kwo Ling Public Cargo Working Area Administrative Office

Date: 26-Jun-18

Next Due Date: 25-Aug-18

Operator: MH

Equipment No.: A-01-54

Model No.: TE-5170

Serial No.: 1536

| Ambient Condition   |       |                     |       |
|---------------------|-------|---------------------|-------|
| Temperature, Ta (K) | 301.1 | Pressure, Pa (mmHg) | 759.3 |

| Orifice Transfer Standard Information |           |  |        |               |          |
|---------------------------------------|-----------|--|--------|---------------|----------|
| Serial No.                            | 2896      | Slope, mc  | 0.0585 | Intercept, bc | -0.00045 |
| Last Calibration Date:                | 13-Feb-18 | $mc \times Qstd + bc = [\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ |        |               |          |
| Next Calibration Date:                | 13-Feb-19 | $Qstd = \{[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2} - bc\} / mc$  |        |               |          |

| Calibration of TSP Sampler |                                    |  |                     |                                |   |
|----------------------------|------------------------------------|--|---------------------|--------------------------------|---|
| Calibration Point          | Orifice                            |  |                     | HVS                            |   |
|                            | $\Delta H$ (orifice), in. of water | $[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ | Qstd (CFM) X - axis | $\Delta W$ (HVS), in. of water | $[\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$ Y-axis |
| 1                          | 16.4                               | 4.03   | 68.81               | 9.7                            | 3.10  |
| 2                          | 12.8                               | 3.56   | 60.79               | 7.8                            | 2.78  |
| 3                          | 10.3                               | 3.19   | 54.53               | 6.5                            | 2.54  |
| 4                          | 6.9                                | 2.61   | 44.64               | 4.2                            | 2.04  |
| 5                          | 4.2                                | 2.04   | 34.83               | 2.7                            | 1.63  |

By Linear Regression of Y on X

Slope, mw = 0.0437

Intercept, bw = 0.1134

Correlation coefficient\* = 0.9990

\*If Correlation Coefficient < 0.990, check and recalibrate.

| Set Point Calculation   |
|---|
| From the TSP Field Calibration Curve, take Qstd = 43 CFM  |
| From the Regression Equation, the "Y" value according to  |
| $mw \times Qstd + bw = [\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$                              |
| Therefore, Set Point; $W = (mw \times Qstd + bw)^2 \times (760 / Pa) \times (Ta / 298) =$ <u>4.01</u> |

Remarks: \_\_\_\_\_

Conducted by: LEE WAN HOV Signature: Lee

Checked by: WIK TANG Signature: KINDI

Date: 26/6/2018

Date: 26/6/2018



# High-Volume TSP Sampler 5-POINT CALIBRATION DATA SHEET

**CINOTECH**

File No. MA16034/37/0011

Project No. AM5(A) - Tseung Kwan O DSD Desilting Compound

Date: 27-Apr-18

Next Due Date: 26-Jun-18

Operator: MH

Equipment No.: A-01-37

Model No.: GS2310

Serial No.: 1704

| Ambient Condition   |       |                     |     |
|---------------------|-------|---------------------|-----|
| Temperature, Ta (K) | 297.9 | Pressure, Pa (mmHg) | 764 |

| Orifice Transfer Standard Information |           |  |        |               |          |
|---------------------------------------|-----------|--|--------|---------------|----------|
| Serial No.                            | 2896      | Slope, mc  | 0.0585 | Intercept, bc | -0.00045 |
| Last Calibration Date:                | 13-Feb-18 | $mc \times Qstd + bc = [\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ |        |               |          |
| Next Calibration Date:                | 13-Feb-19 | $Qstd = \{[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2} - bc\} / mc$  |        |               |          |

| Calibration of TSP Sampler |                                    |  |                     |                                |   |
|----------------------------|------------------------------------|--|---------------------|--------------------------------|---|
| Calibration Point          | Orifice                            |  |                     | HVS                            |   |
|                            | $\Delta H$ (orifice), in. of water | $[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ | Qstd (CFM) X - axis | $\Delta W$ (HVS), in. of water | $[\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$ Y-axis |
| 1                          | 17.2                               | 4.16   | 71.06               | 9.2                            | 3.04  |
| 2                          | 14.0                               | 3.75   | 64.11               | 7.7                            | 2.78  |
| 3                          | 10.8                               | 3.30   | 56.31               | 5.9                            | 2.44  |
| 4                          | 6.7                                | 2.60   | 44.36               | 3.8                            | 1.95  |
| 5                          | 4.2                                | 2.06   | 35.12               | 2.7                            | 1.65  |

**By Linear Regression of Y on X**

Slope, mw = 0.0394

Intercept, bw = 0.2367

Correlation coefficient\* = 0.9991

\*If Correlation Coefficient < 0.990, check and recalibrate.

**Set Point Calculation**

From the TSP Field Calibration Curve, take Qstd = 43 CFM

From the Regression Equation, the "Y" value according to

$$mw \times Qstd + bw = [\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$$

Therefore, Set Point;  $W = (mw \times Qstd + bw)^2 \times (760 / Pa) \times (Ta / 298) =$  3.71

Remarks: \_\_\_\_\_

Conducted by: Lee Kwai Yee Signature: \_\_\_\_\_  
 Checked by: Wk. Tang Signature: \_\_\_\_\_

Date: 27/4/2018  
 Date: 27/4/2018

# High-Volume TSP Sampler

## 5-POINT CALIBRATION DATA SHEET

**CINOTECH**

File No. MA16034/37/0012

Project No. AM5(A) - Tseung Kwan O DSD Desilting Compound

Date: 26-Jun-18

Next Due Date: 25-Aug-18

Operator: MH

Equipment No.: A-01-37

Model No.: GS2310

Serial No.: 1704

| Ambient Condition   |       |                     |     |
|---------------------|-------|---------------------|-----|
| Temperature, Ta (K) | 301.7 | Pressure, Pa (mmHg) | 759 |

| Orifice Transfer Standard Information |           |  |        |               |          |
|---------------------------------------|-----------|--|--------|---------------|----------|
| Serial No.                            | 2896      | Slope, mc  | 0.0585 | Intercept, bc | -0.00045 |
| Last Calibration Date:                | 13-Feb-18 | $mc \times Qstd + bc = [\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ |        |               |          |
| Next Calibration Date:                | 13-Feb-19 | $Qstd = \{[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2} - bc\} / mc$  |        |               |          |

| Calibration of TSP Sampler |                                    |  |                     |                                |   |
|----------------------------|------------------------------------|--|---------------------|--------------------------------|---|
| Calibration Point          | Orifice                            |  |                     | HVS                            |   |
|                            | $\Delta H$ (orifice), in. of water | $[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ | Qstd (CFM) X - axis | $\Delta W$ (HVS), in. of water | $[\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$ Y-axis |
| 1                          | 16.6                               | 4.05   | 69.15               | 9.6                            | 3.08  |
| 2                          | 13.0                               | 3.58   | 61.19               | 7.8                            | 2.77  |
| 3                          | 9.8                                | 3.11   | 53.13               | 5.7                            | 2.37  |
| 4                          | 6.7                                | 2.57   | 43.93               | 4.0                            | 1.99  |
| 5                          | 4.6                                | 2.13   | 36.40               | 2.8                            | 1.66  |

**By Linear Regression of Y on X**

Slope, mw = 0.0437 Intercept, bw = 0.0670

Correlation coefficient\* = 0.9994

\*If Correlation Coefficient < 0.990, check and recalibrate.

**Set Point Calculation**

From the TSP Field Calibration Curve, take Qstd = 43 CFM

From the Regression Equation, the "Y" value according to

$$mw \times Qstd + bw = [\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$$

Therefore, Set Point; W =  $(mw \times Qstd + bw)^2 \times (760 / Pa) \times (Ta / 298) =$  3.84

Remarks: \_\_\_\_\_

Conducted by: Mr Man MBZ Signature: *Man MBZ*  
 Checked by: WKK Tang Signature: *WKK Tang*

Date: 26/6/2018  
 Date: 26/6/2018

# High-Volume TSP Sampler

## 5-POINT CALIBRATION DATA SHEET

**CINOTECH**

File No. MA16034/07/0011

Station AM6 - Park Central

Date: 25-May-18

Next Due Date: 24-Jul-18

Operator: MH

Equipment No.: A-01-07

Model No.: GS2310

Serial No.: 10592

| Ambient Condition   |       |                     |       |
|---------------------|-------|---------------------|-------|
| Temperature, Ta (K) | 305.2 | Pressure, Pa (mmHg) | 757.9 |

| Orifice Transfer Standard Information |           |  |        |               |          |
|---------------------------------------|-----------|--|--------|---------------|----------|
| Serial No.                            | 2896      | Slope, mc  | 0.0585 | Intercept, bc | -0.00045 |
| Last Calibration Date:                | 13-Feb-18 | $mc \times Qstd + bc = [\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ |        |               |          |
| Next Calibration Date:                | 13-Feb-19 | $Qstd = \{[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2} - bc\} / mc$  |        |               |          |

| Calibration of TSP Sampler |                                    |  |                     |                                |   |
|----------------------------|------------------------------------|--|---------------------|--------------------------------|---|
| Calibration Point          | Orifice                            |  |                     | HVS                            |   |
|                            | $\Delta H$ (orifice), in. of water | $[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ | Qstd (CFM) X - axis | $\Delta W$ (HVS), in. of water | $[\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$ Y-axis |
| 1                          | 11.4                               | 3.33   | 56.93               | 7.3                            | 2.67  |
| 2                          | 9.6                                | 3.06   | 52.24               | 6.2                            | 2.46  |
| 3                          | 7.4                                | 2.68   | 45.75               | 4.9                            | 2.18  |
| 4                          | 5.4                                | 2.29   | 39.19               | 3.4                            | 1.82  |
| 5                          | 3.3                                | 1.79   | 30.63               | 2.2                            | 1.46  |

**By Linear Regression of Y on X**

Slope, mw = 0.0463

Intercept, bw = 0.0355

Correlation coefficient\* = 0.9989

\*If Correlation Coefficient < 0.990, check and recalibrate.

### Set Point Calculation

From the TSP Field Calibration Curve, take Qstd = 43 CFM

From the Regression Equation, the "Y" value according to

$$mw \times Qstd + bw = [\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$$

Therefore, Set Point;  $W = (mw \times Qstd + bw)^2 \times (760 / Pa) \times (Ta / 298) =$  4.22

Remarks: \_\_\_\_\_

Conducted by: Leo Wan Hui Signature: \_\_\_\_\_

Date: 25/5/2018

Checked by: Wk Tang Signature: \_\_\_\_\_

Date: 25/5/2018

# Certificate of Calibration

| Calibration Certification Information |                        |           |       |
|---------------------------------------|------------------------|-----------|-------|
| Cal. Date: February 13, 2018          | Rootsmeter S/N: 438320 | Ta: 293   | °K    |
| Operator: Jim Tisch                   |                        | Pa: 763.3 | mm Hg |
| Calibration Model #: TE-5025A         | Calibrator S/N: 2896   |           |       |

| Run | Vol. Init (m3) | Vol. Final (m3) | ΔVol. (m3) | ΔTime (min) | ΔP (mm Hg) | ΔH (in H2O) |
|-----|----------------|-----------------|------------|-------------|------------|-------------|
| 1   | 1              | 2               | 1          | 1.4670      | 3.2        | 2.00        |
| 2   | 3              | 4               | 1          | 1.0380      | 6.4        | 4.00        |
| 3   | 5              | 6               | 1          | 0.9220      | 8.0        | 5.00        |
| 4   | 7              | 8               | 1          | 0.8840      | 8.8        | 5.50        |
| 5   | 9              | 10              | 1          | 0.7250      | 12.8       | 8.00        |

| Data Tabulation |               |  |           |             |                                    |  |
|-----------------|---------------|--|-----------|-------------|------------------------------------|--|
| Vstd (m3)       | Qstd (x-axis) | $\sqrt{\Delta H \left( \frac{Pa}{Pstd} \right) \left( \frac{Tstd}{Ta} \right)}$ (y-axis) | Va        | Qa (x-axis) | $\sqrt{\Delta H (Ta/Pa)}$ (y-axis) |  |
| 1.0172          | 0.6934        | 1.4293   | 0.9958    | 0.6788      | 0.8762                             |  |
| 1.0129          | 0.9758        | 2.0213   | 0.9916    | 0.9553      | 1.2392                             |  |
| 1.0107          | 1.0962        | 2.2599   | 0.9895    | 1.0732      | 1.3854                             |  |
| 1.0097          | 1.1422        | 2.3702   | 0.9885    | 1.1182      | 1.4530                             |  |
| 1.0043          | 1.3853        | 2.8586   | 0.9832    | 1.3562      | 1.7524                             |  |
| <b>QSTD</b>     | m=            | <b>2.06726</b>   | <b>QA</b> | m=          | <b>1.29448</b>                     |  |
|                 | b=            | <b>-0.00045</b>  |           | b=          | <b>-0.00028</b>                    |  |
|                 | r=            | <b>0.99992</b>   |           | r=          | <b>0.99992</b>                     |  |

| Calculations                           |   |     |   |
|--|---|-----|---|
| Vstd=                                  | $\Delta Vol \left( \frac{Pa - \Delta P}{Pstd} \right) \left( \frac{Tstd}{Ta} \right)$                                 | Va= | $\Delta Vol \left( \frac{Pa - \Delta P}{Pa} \right)$            |
| Qstd=                                  | Vstd/ΔTime  | Qa= | Va/ΔTime  |
| For subsequent flow rate calculations: |   |     |   |
| Qstd=                                  | $1/m \left( \left( \sqrt{\Delta H \left( \frac{Pa}{Pstd} \right) \left( \frac{Tstd}{Ta} \right)} \right) - b \right)$ | Qa= | $1/m \left( \left( \sqrt{\Delta H (Ta/Pa)} \right) - b \right)$ |

| Standard Conditions |                                       |
|---------------------|---------------------------------------|
| Tstd:               | 298.15 °K                             |
| Pstd:               | 760 mm Hg                             |
| Key                 |                                       |
| ΔH:                 | calibrator manometer reading (in H2O) |
| ΔP:                 | rootsmeter manometer reading (mm Hg)  |
| Ta:                 | actual absolute temperature (°K)      |
| Pa:                 | actual barometric pressure (mm Hg)    |
| b:                  | intercept                             |
| m:                  | slope                                 |

| RECALIBRATION  |
|--|
| US EPA recommends annual recalibration per 1998 40 Code of Federal Regulations Part 50 to 51, Appendix B to Part 50, Reference Method for the Determination of Suspended Particulate Matter in the Atmosphere, 9.2.17, page 30 |

## TEST REPORT

**APPLICANT:** Cinotech Consultants Limited  
Room 1710, Technology Park,  
18 On Lai Street,  
Shatin, NT, Hong Kong

|                  |            |
|------------------|------------|
| Test Report No.: | C/W/180127 |
| Date of Issue:   | 2018-01-28 |
| Date Received:   | 2018-01-27 |
| Date Tested:     | 2018-01-27 |
| Date Completed:  | 2018-01-28 |
| Next Due Date:   | 2018-07-27 |

**ATTN:** Mr. W.K. Tang

Page: 1 of 2

### Certificate of Calibration

**Item for calibration:**

|              |                                  |
|--------------|----------------------------------|
| Description  | : Weather Stations, Vantage Pro2 |
| Manufacturer | : Davis Instruments              |
| Model No.    | : 6152CUK                        |
| Serial No.   | : AK130520007                    |

**Test conditions:**

|                   |                     |
|-------------------|---------------------|
| Room Temperature  | : 21 degree Celsius |
| Relative Humidity | : 56 %              |

**Test Specifications:**

1. Performance check of anemometer
2. Performance check of wind direction sensor

**Methodology:**

In-house method with reference anemometer (RS232 Integral Vane Digital Anemometer)

*PREPARED AND CHECKED BY:*  
For and On Behalf of **WELLAB Ltd.**



**PATRICK TSE**  
Laboratory Manager

**TEST REPORT**

|                  |            |
|------------------|------------|
| Test Report No.: | C/W/180127 |
| Date of Issue:   | 2018-01-28 |
| Date Received:   | 2018-01-27 |
| Date Tested:     | 2018-01-27 |
| Date Completed:  | 2018-01-28 |
| Next Due Date:   | 2018-07-27 |

Page: 2 of 2

**Results:**

1. Performance check of anemometer

| Air Velocity, m/s       |                      | Difference D (m/s) |
|-------------------------|----------------------|--------------------|
| Instrument Reading (V1) | Reference Value (V1) | D = V1 - V2        |
| 2.00                    | 2.00                 | 0.00               |

2. Performance check of wind direction sensor

| Wind Direction (°)      |                      | Difference D (°) |
|-------------------------|----------------------|------------------|
| Instrument Reading (W1) | Reference Value (W2) | D = W1 - W2      |
| 0                       | 0                    | 0                |
| 45.3                    | 45                   | 0.3              |
| 90.1                    | 90                   | 0.1              |
| 135                     | 135                  | 0                |
| 180.1                   | 180                  | 0.1              |
| 225.2                   | 225                  | 0.2              |
| 270.2                   | 270                  | 0.2              |
| 315                     | 315                  | 0                |
| 360                     | 360                  | 0                |

\*\*\*\*\*END OF REPORT\*\*\*\*\*

**TEST REPORT**

**APPLICANT:** Cinotech Consultants Limited  
Room 1710, Technology Park,  
18 On Lai Street,  
Shatin, NT, Hong Kong

|                  |            |
|------------------|------------|
| Test Report No.: | 28791      |
| Date of Issue:   | 2018-04-23 |
| Date Received:   | 2018-04-20 |
| Date Tested:     | 2018-04-20 |
| Date Completed:  | 2018-04-23 |
| Next Due Date:   | 2018-06-22 |

**ATTN:** Mr. W. K. Tang

Page: 1 of 1

**Certificate of Calibration**

**Item for Calibration:**

|                 |                             |
|-----------------|-----------------------------|
| Description     | : Handheld Particle Counter |
| Manufacturer    | : Hal Technology            |
| Model No.       | : Hal-HPC300                |
| Serial No.      | : 3020408                   |
| Flow rate       | : 0.1 cfm                   |
| Zero Count Test | : 0 count per 5 minutes     |
| Equipment No.   | : A-26-01                   |

**Test Conditions:**

|                   |                        |
|-------------------|------------------------|
| Room Temperature  | : 17-22 degree Celsius |
| Relative Humidity | : 40-70%               |

**Test Specifications & Methodology:**

1. Instruction and Operation Manual High Volume Sampler, Andersen Samplers, Inc.
2. In-house method in according to the instruction manual: The Dust Monitor was compared with a calibrated High Volume Sampler and the result was used to generate the Correlation Factor (CF) between the Dust Monitor and High Volume Sampler.

**Results:**

|                         |       |
|-------------------------|-------|
| Correlation Factor (CF) | 1.199 |
|-------------------------|-------|

\*\*\*\*\*

*PREPARED AND CHECKED BY:*

For and On Behalf of **WELLAB Ltd.**

  
**PATRICK TSE**  
Laboratory Manager

**TEST REPORT**

**APPLICANT:** Cinotech Consultants Limited  
Room 1710, Technology Park,  
18 On Lai Street,  
Shatin, NT, Hong Kong

|                  |            |
|------------------|------------|
| Test Report No.: | 28792      |
| Date of Issue:   | 2018-04-23 |
| Date Received:   | 2018-04-20 |
| Date Tested:     | 2018-04-20 |
| Date Completed:  | 2018-04-23 |
| Next Due Date:   | 2018-06-22 |

**ATTN:** Mr. W. K. Tang

Page: 1 of 1

**Certificate of Calibration**

**Item for Calibration:**

Description : Handheld Particle Counter  
 Manufacturer : Hal Technology  
 Model No. : Hal-HPC300  
 Serial No. : 3020409  
 Flow rate : 0.1 cfm  
 Zero Count Test : 0 count per 5 minutes  
 Equipment No. : A-26-02

**Test Conditions:**

Room Temperature : 17-22 degree Celsius  
 Relative Humidity : 40-70%

**Test Specifications & Methodology:**

1. Instruction and Operation Manual High Volume Sampler, Andersen Samplers, Inc.
2. In-house method in according to the instruction manual: The Dust Monitor was compared with a calibrated High Volume Sampler and the result was used to generate the Correlation Factor (CF) between the Dust Monitor and High Volume Sampler.

**Results:**

|                         |       |
|-------------------------|-------|
| Correlation Factor (CF) | 1.183 |
|-------------------------|-------|

\*\*\*\*\*

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**

  
**PATRICK TSE**  
 Laboratory Manager



**TEST REPORT**

**APPLICANT:** Cinotech Consultants Limited  
Room 1710, Technology Park,  
18 On Lai Street,  
Shatin, NT, Hong Kong

|                  |            |
|------------------|------------|
| Test Report No.: | 28787      |
| Date of Issue:   | 2018-04-16 |
| Date Received:   | 2018-04-13 |
| Date Tested:     | 2018-04-13 |
| Date Completed:  | 2018-04-16 |
| Next Due Date:   | 2018-06-15 |

**ATTN:** Mr. W. K. Tang

Page: 1 of 1

**Certificate of Calibration**

**Item for Calibration:**

Description : Handheld Particle Counter  
 Manufacturer : Hal Technology  
 Model No. : Hal-HPC301  
 Serial No. : 3011701019  
 Flow rate : 0.1 cfm  
 Zero Count Test : 0 count per 5 minutes  
 Equipment No. : A-27-01

**Test Conditions:**

Room Temperature : 17-22 degree Celsius  
 Relative Humidity : 40-70%

**Test Specifications & Methodology:**

1. Instruction and Operation Manual High Volume Sampler, Andersen Samplers, Inc.
2. In-house method in according to the instruction manual: The Dust Monitor was compared with a calibrated High Volume Sampler and the result was used to generate the Correlation Factor (CF) between the Dust Monitor and High Volume Sampler.

**Results:**

|                         |       |
|-------------------------|-------|
| Correlation Factor (CF) | 1.168 |
|-------------------------|-------|

\*\*\*\*\*

*PREPARED AND CHECKED BY:*

For and On Behalf of **WELLAB Ltd.**

  
**PATRICK TSE**  
 Laboratory Manager

**TEST REPORT**

**APPLICANT:** Cinotech Consultants Limited  
Room 1710, Technology Park,  
18 On Lai Street,  
Shatin, NT, Hong Kong

|                  |            |
|------------------|------------|
| Test Report No.: | 29026      |
| Date of Issue:   | 2018-06-11 |
| Date Received:   | 2018-06-08 |
| Date Tested:     | 2018-06-08 |
| Date Completed:  | 2018-06-11 |
| Next Due Date:   | 2018-08-10 |

**ATTN:** Mr. W. K. Tang

Page: 1 of 1

**Certificate of Calibration**

**Item for Calibration:**

|                 |                             |
|-----------------|-----------------------------|
| Description     | : Handheld Particle Counter |
| Manufacturer    | : Hal Technology            |
| Model No.       | : Hal-HPC301                |
| Serial No.      | : 3011701019                |
| Flow rate       | : 0.1 cfm                   |
| Zero Count Test | : 0 count per 5 minutes     |
| Equipment No.   | : A-27-01                   |

**Test Conditions:**

|                   |                        |
|-------------------|------------------------|
| Room Temperature  | : 17-22 degree Celsius |
| Relative Humidity | : 40-70%               |

**Test Specifications & Methodology:**

1. Instruction and Operation Manual High Volume Sampler, Andersen Samplers, Inc.
2. In-house method in according to the instruction manual: The Dust Monitor was compared with a calibrated High Volume Sampler and the result was used to generate the Correlation Factor (CF) between the Dust Monitor and High Volume Sampler.

**Results:**

|                         |       |
|-------------------------|-------|
| Correlation Factor (CF) | 1.226 |
|-------------------------|-------|

\*\*\*\*\*

*PREPARED AND CHECKED BY:*

For and On Behalf of **WELLAB Ltd.**

  
**PATRICK TSE**  
 Laboratory Manager

**TEST REPORT**

**APPLICANT:** Cinotech Consultants Limited  
Room 1710, Technology Park,  
18 On Lai Street,  
Shatin, NT, Hong Kong

|                  |            |
|------------------|------------|
| Test Report No.: | 28787A     |
| Date of Issue:   | 2018-04-16 |
| Date Received:   | 2018-04-13 |
| Date Tested:     | 2018-04-13 |
| Date Completed:  | 2018-04-16 |
| Next Due Date:   | 2018-06-15 |

**ATTN:** Mr. W. K. Tang

Page: 1 of 1

**Certificate of Calibration**

**Item for Calibration:**

Description : Handheld Particle Counter  
Manufacturer : Hal Technology  
Model No. : Hal-HPC301  
Serial No. : 3011701016  
Flow rate : 0.1 cfm  
Zero Count Test : 0 count per 5 minutes  
Equipment No. : A-27-03

**Test Conditions:**

Room Temperature : 17-22 degree Celsius  
Relative Humidity : 40-70%

**Test Specifications & Methodology:**

1. Instruction and Operation Manual High Volume Sampler, Andersen Samplers, Inc.
2. In-house method in according to the instruction manual: The Dust Monitor was compared with a calibrated High Volume Sampler and the result was used to generate the Correlation Factor (CF) between the Dust Monitor and High Volume Sampler.

**Results:**

|                         |       |
|-------------------------|-------|
| Correlation Factor (CF) | 1.203 |
|-------------------------|-------|

\*\*\*\*\*

*PREPARED AND CHECKED BY:*

For and On Behalf of **WELLAB Ltd.**

  
**PATRICK TSE**  
Laboratory Manager

**TEST REPORT**

**APPLICANT:** Cinotech Consultants Limited  
Room 1710, Technology Park,  
18 On Lai Street,  
Shatin, NT, Hong Kong

|                  |            |
|------------------|------------|
| Test Report No.: | 28788      |
| Date of Issue:   | 2018-04-16 |
| Date Received:   | 2018-04-13 |
| Date Tested:     | 2018-04-13 |
| Date Completed:  | 2018-04-16 |
| Next Due Date:   | 2018-06-15 |

**ATTN:** Mr. W. K. Tang

Page: 1 of 1

**Certificate of Calibration**

**Item for Calibration:**

Description : Handheld Particle Counter  
 Manufacturer : Hal Technology  
 Model No. : Hal-HPC301  
 Serial No. : 3011701017  
 Flow rate : 0.1 cfm  
 Zero Count Test : 0 count per 5 minutes  
 Equipment No. : A-27-04

**Test Conditions:**

Room Temperature : 17-22 degree Celsius  
 Relative Humidity : 40-70%

**Test Specifications & Methodology:**

1. Instruction and Operation Manual High Volume Sampler, Andersen Samplers, Inc.
2. In-house method in according to the instruction manual: The Dust Monitor was compared with a calibrated High Volume Sampler and the result was used to generate the Correlation Factor (CF) between the Dust Monitor and High Volume Sampler.

**Results:**

|                         |       |
|-------------------------|-------|
| Correlation Factor (CF) | 1.158 |
|-------------------------|-------|

\*\*\*\*\*

*PREPARED AND CHECKED BY:*

For and On Behalf of **WELLAB Ltd.**

  
**PATRICK TSE**  
 Laboratory Manager

**TEST REPORT**

**APPLICANT:** Cinotech Consultants Limited  
Room 1710, Technology Park,  
18 On Lai Street,  
Shatin, NT, Hong Kong

|                  |            |
|------------------|------------|
| Test Report No.: | 29026B     |
| Date of Issue:   | 2018-06-11 |
| Date Received:   | 2018-06-08 |
| Date Tested:     | 2018-06-08 |
| Date Completed:  | 2018-06-11 |
| Next Due Date:   | 2018-08-10 |

**ATTN:** Mr. W. K. Tang

Page: 1 of 1

**Certificate of Calibration**

**Item for Calibration:**

Description : Handheld Particle Counter  
 Manufacturer : Hal Technology  
 Model No. : Hal-HPC301  
 Serial No. : 3011701017  
 Flow rate : 0.1 cfm  
 Zero Count Test : 0 count per 5 minutes  
 Equipment No. : A-27-04

**Test Conditions:**

Room Temperature : 17-22 degree Celsius  
 Relative Humidity : 40-70%

**Test Specifications & Methodology:**

1. Instruction and Operation Manual High Volume Sampler, Andersen Samplers, Inc.
2. In-house method in according to the instruction manual: The Dust Monitor was compared with a calibrated High Volume Sampler and the result was used to generate the Correlation Factor (CF) between the Dust Monitor and High Volume Sampler.


**Results:**

|                         |       |
|-------------------------|-------|
| Correlation Factor (CF) | 1.204 |
|-------------------------|-------|

\*\*\*\*\*

*PREPARED AND CHECKED BY:*

For and On Behalf of **WELLAB Ltd.**



**PATRICK TSE**  
Laboratory Manager

**TEST REPORT**

**APPLICANT:** Cinotech Consultants Limited  
Room 1710, Technology Park,  
18 On Lai Street,  
Shatin, NT, Hong Kong

|                  |            |
|------------------|------------|
| Test Report No.: | 29026C     |
| Date of Issue:   | 2018-06-11 |
| Date Received:   | 2018-06-08 |
| Date Tested:     | 2018-06-08 |
| Date Completed:  | 2018-06-11 |
| Next Due Date:   | 2018-08-10 |

**ATTN:** Mr. W. K. Tang

Page: 1 of 1

**Certificate of Calibration**

**Item for Calibration:**

|                 |                             |
|-----------------|-----------------------------|
| Description     | : Handheld Particle Counter |
| Manufacturer    | : Hal Technology            |
| Model No.       | : Hal-HPC301                |
| Serial No.      | : 3011701012                |
| Flow rate       | : 0.1 cfm                   |
| Zero Count Test | : 0 count per 5 minutes     |
| Equipment No.   | : A-27-07                   |

**Test Conditions:**

|                   |                        |
|-------------------|------------------------|
| Room Temperature  | : 17-22 degree Celsius |
| Relative Humidity | : 40-70%               |

**Test Specifications & Methodology:**

1. Instruction and Operation Manual High Volume Sampler, Andersen Samplers, Inc.
2. In-house method in according to the instruction manual: The Dust Monitor was compared with a calibrated High Volume Sampler and the result was used to generate the Correlation Factor (CF) between the Dust Monitor and High Volume Sampler.

**Results:**

|                         |       |
|-------------------------|-------|
| Correlation Factor (CF) | 1.239 |
|-------------------------|-------|

\*\*\*\*\*

*PREPARED AND CHECKED BY:*

For and On Behalf of **WELLAB Ltd.**

  
\_\_\_\_\_  
**PATRICK TSE**  
Laboratory Manager

**TEST REPORT**

**APPLICANT:** Cinotech Consultants Limited  
Room 1710, Technology Park,  
18 On Lai Street,  
Shatin, NT, Hong Kong

|                  |            |
|------------------|------------|
| Test Report No.: | 29026E     |
| Date of Issue:   | 2018-06-11 |
| Date Received:   | 2018-06-08 |
| Date Tested:     | 2018-06-08 |
| Date Completed:  | 2018-06-11 |
| Next Due Date:   | 2018-08-10 |

**ATTN:** Mr. W. K. Tang

Page: 1 of 1

**Certificate of Calibration**

**Item for Calibration:**

Description : Handheld Particle Counter  
Manufacturer : Hal Technology  
Model No. : Hal-HPC301  
Serial No. : 3011701010  
Flow rate : 0.1 cfm  
Zero Count Test : 0 count per 5 minutes  
Equipment No. : A-27-10

**Test Conditions:**

Room Temperature : 17-22 degree Celsius  
Relative Humidity : 40-70%

**Test Specifications & Methodology:**

1. Instruction and Operation Manual High Volume Sampler, Andersen Samplers, Inc.
2. In-house method in according to the instruction manual: The Dust Monitor was compared with a calibrated High Volume Sampler and the result was used to generate the Correlation Factor (CF) between the Dust Monitor and High Volume Sampler.

**Results:**

|                         |       |
|-------------------------|-------|
| Correlation Factor (CF) | 1.213 |
|-------------------------|-------|

\*\*\*\*\*

*PREPARED AND CHECKED BY:*

For and On Behalf of **WELLAB Ltd.**

  
**PATRICK TSEP**  
Laboratory Manager

## TEST REPORT

**APPLICANT:** Cinotech Consultants Limited  
Room 1710, Technology Park,  
18 On Lai Street,  
Shatin, NT, Hong Kong

|                  |            |
|------------------|------------|
| Test Report No.: | C/N/170825 |
| Date of Issue:   | 2017-08-28 |
| Date Received:   | 2017-08-25 |
| Date Tested:     | 2017-08-25 |
| Date Completed:  | 2017-08-28 |
| Next Due Date:   | 2018-08-27 |

**ATTN:** Mr. W.K. Tang

Page: 1 of 1

### Certificate of Calibration

**Item for calibration:**

|                |   |
|----------------|---|
| Description    | : 'SVANTEK' Integrating Sound Level Meter |
| Manufacturer   | : SVANTEK                                 |
| Model No.      | : SVAN 957                                |
| Serial No.     | : 21455                                   |
| Microphone No. | : 43730                                   |
| Equipment No.  | : N-08-07                                 |

**Test conditions:**

|                   |                     |
|-------------------|---------------------|
| Room Temperature  | : 23 degree Celsius |
| Relative Humidity | : 60 %              |

**Test Specifications:**

Performance checking at 94 and 114 dB

**Methodology:**


In-house method, according to manufacturer instruction manual

**Results:**

| Reference Set Point, dB | Instrument Readings, dB |
|-------------------------|-------------------------|
| 94                      | 94.0                    |
| 114                     | 114.0                   |

*PREPARED AND CHECKED BY:*

For and On Behalf of **WELLAB Ltd.**

  
**PATRICK TSE**  
Laboratory Manager



## TEST REPORT

**APPLICANT:** Cinotech Consultants Limited  
Room 1710, Technology Park,  
18 On Lai Street,  
Shatin, NT, Hong Kong

|                  |             |
|------------------|-------------|
| Test Report No.: | C/N/170818A |
| Date of Issue:   | 2017-08-21  |
| Date Received:   | 2017-08-18  |
| Date Tested:     | 2017-08-18  |
| Date Completed:  | 2017-08-21  |
| Next Due Date:   | 2018-08-20  |

**ATTN:** Mr. W.K. Tang

Page: 1 of 1

### Certificate of Calibration

**Item for calibration:**

|                |   |
|----------------|---|
| Description    | : 'SVANTEK' Integrating Sound Level Meter |
| Manufacturer   | : SVANTEK                                 |
| Model No.      | : SVAN 957                                |
| Serial No.     | : 21460                                   |
| Microphone No. | : 43679                                   |
| Equipment No.  | : N-08-09                                 |

**Test conditions:**

|                   |                     |
|-------------------|---------------------|
| Room Temperature  | : 22 degree Celsius |
| Relative Humidity | : 61 %              |

**Test Specifications:**

Performance checking at 94 and 114 dB

**Methodology:**

In-house method, according to manufacturer instruction manual

**Results:**

| Reference Set Point, dB | Instrument Readings, dB |
|-------------------------|-------------------------|
| 94                      | 94.0                    |
| 114                     | 114.0                   |

*PREPARED AND CHECKED BY:*  
For and On Behalf of **WELLAB Ltd.**

  
**PATRICK TSE**  
Laboratory Manager

## TEST REPORT

**APPLICANT:** Cinotech Consultants Limited  
Room 1710, Technology Park,  
18 On Lai Street,  
Shatin, NT, Hong Kong

|                  |             |
|------------------|-------------|
| Test Report No.: | C/N/170915B |
| Date of Issue:   | 2017-09-18  |
| Date Received:   | 2017-09-15  |
| Date Tested:     | 2017-09-15  |
| Date Completed:  | 2017-09-18  |
| Next Due Date:   | 2018-09-17  |

**ATTN:** Mr. W.K. Tang

Page: 1 of 1

### Certificate of Calibration

**Item for calibration:**

|                |   |
|----------------|---|
| Description    | : 'SVANTEK' Integrating Sound Level Meter |
| Manufacturer   | : SVANTEK                                 |
| Model No.      | : SVAN 977                                |
| Serial No.     | : 45467                                   |
| Microphone No. | : 62838                                   |
| Equipment No.  | : N-08-13                                 |

**Test conditions:**

|                   |                     |
|-------------------|---------------------|
| Room Temperature  | : 22 degree Celsius |
| Relative Humidity | : 60%               |

**Test Specifications:**

Performance checking at 94 and 114 dB

**Methodology:**

In-house method, according to manufacturer instruction manual

**Results:**

| Reference Set Point, dB | Instrument Readings, dB |
|-------------------------|-------------------------|
| 94                      | 94.0                    |
| 114                     | 114.0                   |

*PREPARED AND CHECKED BY:*

For and On Behalf of **WELLAB Ltd.**



**PATRICK TSE**  
Laboratory Manager

## TEST REPORT

**APPLICANT:** Cinotech Consultants Limited  
Room 1710, Technology Park,  
18 On Lai Street,  
Shatin, NT, Hong Kong

|                  |             |
|------------------|-------------|
| Test Report No.: | C/N/170915C |
| Date of Issue:   | 2017-09-18  |
| Date Received:   | 2017-09-15  |
| Date Tested:     | 2017-09-15  |
| Date Completed:  | 2017-09-18  |
| Next Due Date:   | 2018-09-17  |

**ATTN:** Mr. W.K. Tang

Page: 1 of 1

### Certificate of Calibration

**Item for calibration:**

|                |   |
|----------------|---|
| Description    | : 'SVANTEK' Integrating Sound Level Meter |
| Manufacturer   | : SVANTEK                                 |
| Model No.      | : SVAN 977                                |
| Serial No.     | : 45482                                   |
| Microphone No. | : 63626                                   |
| Equipment No.  | : N-08-14                                 |

**Test conditions:**

|                   |                     |
|-------------------|---------------------|
| Room Temperature  | : 22 degree Celsius |
| Relative Humidity | : 60%               |

**Test Specifications:**

Performance checking at 94 and 114 dB

**Methodology:**

In-house method, according to manufacturer instruction manual

**Results:**

| Reference Set Point, dB | Instrument Readings, dB |
|-------------------------|-------------------------|
| 94                      | 94.0                    |
| 114                     | 114.0                   |

*PREPARED AND CHECKED BY:*

For and On Behalf of **WELLAB Ltd.**

  
**PATRICK TSE**  
Laboratory Manager

## TEST REPORT

**APPLICANT:** Cinotech Consultants Limited  
Room 1710, Technology Park,  
18 On Lai Street,  
Shatin, NT, Hong Kong

|                  |            |
|------------------|------------|
| Test Report No.: | C/N/171215 |
| Date of Issue:   | 2017-12-18 |
| Date Received:   | 2017-12-15 |
| Date Tested:     | 2017-12-15 |
| Date Completed:  | 2017-12-18 |
| Next Due Date:   | 2018-12-17 |

**ATTN:** Mr. W.K. Tang

Page: 1 of 1

### Certificate of Calibration

**Item for calibration:**

|               |                              |
|---------------|------------------------------|
| Description   | : Sound & Vibration Analyser |
| Manufacturer  | : BSWA                       |
| Model No.     | : BSWA 801                   |
| Serial No.    | : 35924                      |
| Equipment No. | : N-13-01                    |

**Test conditions:**

|                   |                     |
|-------------------|---------------------|
| Room Temperature  | : 20 degree Celsius |
| Relative Humidity | : 64%               |

**Test Specifications:**

Performance checking at 94 and 114 dB

**Methodology:**


In-house method, according to manufacturer instruction manual

**Results:**

| Reference Set Point, dB | Instrument Readings, dB |
|-------------------------|-------------------------|
| 94                      | 94.0                    |
| 114                     | 114.0                   |

*PREPARED AND CHECKED BY:*

For and On Behalf of **WELLAB Ltd.**



**PATRICK TSE**

Laboratory Manager

## TEST REPORT

**APPLICANT:** Cinotech Consultants Limited  
Room 1710, Technology Park,  
18 On Lai Street,  
Shatin, NT, Hong Kong

|                  |             |
|------------------|-------------|
| Test Report No.: | C/N/171215B |
| Date of Issue:   | 2017-12-18  |
| Date Received:   | 2017-12-15  |
| Date Tested:     | 2017-12-15  |
| Date Completed:  | 2017-12-18  |
| Next Due Date:   | 2018-12-17  |

**ATTN:** Mr. W.K. Tang

Page: 1 of 1

### Certificate of Calibration

**Item for calibration:**

|               |                              |
|---------------|------------------------------|
| Description   | : Sound & Vibration Analyser |
| Manufacturer  | : BSWA                       |
| Model No.     | : BSWA 801                   |
| Serial No.    | : 35927                      |
| Equipment No. | : N-13-03                    |

**Test conditions:**

|                   |                     |
|-------------------|---------------------|
| Room Temperature  | : 20 degree Celsius |
| Relative Humidity | : 64%               |

**Test Specifications:**

Performance checking at 94 and 114 dB

**Methodology:**

In-house method, according to manufacturer instruction manual

**Results:**

| Reference Set Point, dB | Instrument Readings, dB |
|-------------------------|-------------------------|
| 94                      | 94.0                    |
| 114                     | 114.0                   |

*PREPARED AND CHECKED BY:*

For and On Behalf of **WELLAB Ltd.**

  
**PATRICK TSE**  
Laboratory Manager

**TEST REPORT****APPLICANT: Cinotech Consultants Limited**  
**Room 1710, Technology Park,**  
**18 On Lai Street,**  
**Shatin, NT, Hong Kong**

|                  |            |
|------------------|------------|
| Test Report No.: | C/N/170929 |
| Date of Issue:   | 2017-09-30 |
| Date Received:   | 2017-09-29 |
| Date Tested:     | 2017-09-29 |
| Date Completed:  | 2017-09-30 |
| Next Due Date:   | 2018-09-29 |

**ATTN: Mr. W.K. Tang**

Page: 1 of 1

**Item for calibration:**

|               |                         |
|---------------|-------------------------|
| Description   | : Acoustical Calibrator |
| Manufacturer  | : SVANTEK               |
| Model No.     | : SV30A                 |
| Serial No.    | : 24803                 |
| Equipment No. | : N-09-03               |

**Test conditions:**

|                   |                     |
|-------------------|---------------------|
| Room Temperature  | : 21 degree Celsius |
| Relative Humidity | : 60 %              |

**Methodology:**

The Sound Level Calibrator has been calibrated in accordance with the documented procedures and using standard(s) and instrument(s) which are recommended by the manufacturer, or equivalent.

**Results:**

| Sound Pressure Level (1kHz) | Measured SPL | Tolerance      |
|-----------------------------|--------------|----------------|
| At 94 dB SPL                | 94.0         | 94.0 ± 0.1 dB  |
| At 114 dB SPL               | 114.0        | 114.0 ± 0.1 dB |

*PREPARED AND CHECKED BY:*For and On Behalf of **WELLAB Ltd.**  
**PATRICK TSE**  
Laboratory Manager

**TEST REPORT****APPLICANT:** Cinotech Consultants Limited  
Room 1710, Technology Park,  
18 On Lai Street,  
Shatin, NT, Hong Kong

|                  |             |
|------------------|-------------|
| Test Report No.: | C/N/170929B |
| Date of Issue:   | 2017-09-30  |
| Date Received:   | 2017-09-29  |
| Date Tested:     | 2017-09-29  |
| Date Completed:  | 2017-09-30  |
| Next Due Date:   | 2018-09-29  |

**ATTN:** Mr. W.K. Tang

Page: 1 of 1

**Item for calibration:**

|               |                         |
|---------------|-------------------------|
| Description   | : Acoustical Calibrator |
| Manufacturer  | : SVANTEK               |
| Model No.     | : SV30A                 |
| Serial No.    | : 24780                 |
| Equipment No. | : N-09-05               |

**Test conditions:**

|                   |                     |
|-------------------|---------------------|
| Room Temperature  | : 21 degree Celsius |
| Relative Humidity | : 60 %              |

**Methodology:**

The Sound Level Calibrator has been calibrated in accordance with the documented procedures and using standard(s) and instrument(s) which are recommended by the manufacturer, or equivalent.

**Results:**

| Sound Pressure Level (1kHz) | Measured SPL | Tolerance      |
|-----------------------------|--------------|----------------|
| At 94 dB SPL                | 94.0         | 94.0 ± 0.1 dB  |
| At 114 dB SPL               | 114.0        | 114.0 ± 0.1 dB |

*PREPARED AND CHECKED BY:*For and On Behalf of **WELLAB Ltd.**  
**PATRICK TSE**  
Laboratory Manager

**TEST REPORT**

**APPLICANT:** Cinotech Consultants Limited  
RM 1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T., Hong Kong

|                  |            |
|------------------|------------|
| Test Report No.: | 29025B     |
| Date of Issue:   | 2018-05-25 |
| Date Received:   | 2018-05-25 |
| Date Tested:     | 2018-05-25 |
| Date Completed:  | 2018-05-25 |
| Next Due Date:   | 2018-08-24 |

**ATTN:** Miss Mei Ling Tang

Page: 1 of 2

**Certificate of Calibration**

**Item for calibration:**

|   |                                 |            |
|---|---------------------------------|------------|
| YSI EXO1 Multiparameter Sondes            | Equipment No.:                  | SW-08-09   |
| Manufacturer:                             | YSI Incorporated, a Xylem brand |            |
| Description:                              | Model No.                       | Serial No. |
| - EXO Optical DO Sensor, Ti               | 599100-01                       | 16H102988  |
| - EXO conductivity/Temperature Sensor, Ti | 599870                          | 16G102310  |
| - EXO Turbidity Sensor, Ti                | 599101-01                       | 16H102467  |
| - EXO pH Sensor Assembly, Guarded, Ti     | 599701                          | 16J100419  |

**Test conditions:**

Room Temperature : 17-22 degree Celsius  
Relative Humidity : 40-70%

**Test Specifications:**

Performance checking for Conductivity, Temperature, pH, Dissolved oxygen (D.O.) and Turbidity

**Methodology:**

According to manufacturer instruction manual, APHA 20e 4500-O C

\*\*\*\*\*

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**

  
**PATRICK TSE**  
Laboratory Manager



**TEST REPORT**

|                  |            |
|------------------|------------|
| Test Report No.: | 29025B     |
| Date of Issue:   | 2018-05-25 |
| Date Received:   | 2018-05-25 |
| Date Tested:     | 2018-05-25 |
| Date Completed:  | 2018-05-25 |
| Next Due Date:   | 2018-08-24 |

Page: 2 of 2

**Certificate of Calibration**

**Results:**

**Conductivity performance checking**

|  | Instrument Readings ( $\mu\text{S}/\text{cm}$ ) | Acceptance Criteria | Comment |
|--|---|---------------------|---------|
| KCl stock solution<br>(12890 $\mu\text{S}/\text{cm}$ ) | 13000   | 12246-13534         | Pass    |

**Temperature performance checking**

| Reference thermometer-<br>E431 Readings ( $^{\circ}\text{C}$ ) | Instrument Readings ( $^{\circ}\text{C}$ ) | Correction ( $^{\circ}\text{C}$ ) | Comment |
|--|--|-----------------------------------|---------|
| 20.7   | 20.703                                     | -0.003                            | N/A     |

**pH performance checking**

|                   | Instrument Readings<br>(pH unit) | Acceptance Criteria | Comment |
|-------------------|----------------------------------|---------------------|---------|
| pH QC buffer 4.00 | 4.05                             | $4.00 \pm 0.10$     | Pass    |
| pH QC buffer 6.86 | 6.87                             | $6.86 \pm 0.10$     | Pass    |
| pH QC buffer 9.18 | 9.20                             | $9.18 \pm 0.10$     | Pass    |

**D.O. performance checking**

|                  | Instrument Readings (mg/L) | Acceptance Criteria      | Comment |
|------------------|----------------------------|--------------------------|---------|
| Zero DO solution | 0.05                       | $<0.1\text{mg}/\text{L}$ | Pass    |

| Winkler Titration value<br>(mg/L) | Instrument Readings (mg/L) | Acceptance Criteria   | Comment |
|-----------------------------------|----------------------------|---|---------|
| 8.00                              | 8.02                       | Difference between<br>Titration value and<br>instrument reading<br>$<0.2\text{mg}/\text{L}$ | Pass    |

**Turbidity performance checking**

| Turbidity stock solution | Instrument Readings (NTU) | Acceptance Criteria | Comment |
|--------------------------|---------------------------|---------------------|---------|
| 10 NTU                   | 10.20                     | 9.0-11.0            | Pass    |
| 50 NTU                   | 50.16                     | 45.0-55.0           | Pass    |
| 100 NTU                  | 100.4                     | 90.0-110.0          | Pass    |

**Depth performance checking**

| Water Depth | Instrument Readings (NTU) | Acceptance Criteria | Comment |
|-------------|---------------------------|---------------------|---------|
| 0.5 meter   | 0.50                      | 0.45-0.55           | Pass    |

\*\*\*\*\*END OF REPORT\*\*\*\*\*

**TEST REPORT**

**APPLICANT:** Cinotech Consultants Limited  
RM 1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T., Hong Kong

|                  |            |
|------------------|------------|
| Test Report No.: | 29025D     |
| Date of Issue:   | 2018-05-25 |
| Date Received:   | 2018-05-25 |
| Date Tested:     | 2018-05-25 |
| Date Completed:  | 2018-05-25 |
| Next Due Date:   | 2018-08-24 |

**ATTN:** Miss Mei Ling Tang

Page: 1 of 2

**Certificate of Calibration**

**Item for calibration:**

|   |                                 |            |
|---|---------------------------------|------------|
| YSI EXO1 Multiparameter Sondes            | Equipment No.:                  | SW-08-20   |
| Manufacturer:                             | YSI Incorporated, a Xylem brand |            |
| Description:                              | Model No.                       | Serial No. |
| - EXO Optical DO Sensor, Ti               | 599100-01                       | 16J100944  |
| - EXO conductivity/Temperature Sensor, Ti | 599870                          | 16H100178  |
| - EXO Turbidity Sensor, Ti                | 599101-01                       | 16J101097  |
| - EXO pH Sensor Assembly, Guarded, Ti     | 599701                          | 17K103109  |

**Test conditions:**

Room Temperature : 17-22 degree Celsius  
Relative Humidity : 40-70%

**Test Specifications:**

Performance checking for Conductivity, Temperature, pH, Dissolved oxygen (D.O.) and Turbidity

**Methodology:**

According to manufacturer instruction manual, APHA 20e 4500-O C

\*\*\*\*\*

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**

  
\_\_\_\_\_  
**PATRICK TSE**  
Laboratory Manager

**TEST REPORT**

|                  |            |
|------------------|------------|
| Test Report No.: | 29025D     |
| Date of Issue:   | 2018-05-25 |
| Date Received:   | 2018-05-25 |
| Date Tested:     | 2018-05-25 |
| Date Completed:  | 2018-05-25 |
| Next Due Date:   | 2018-08-24 |

Page: 2 of 2

**Certificate of Calibration**

**Results:**

**Conductivity performance checking**

|  | Instrument Readings ( $\mu\text{S}/\text{cm}$ ) | Acceptance Criteria | Comment |
|--|---|---------------------|---------|
| KCl stock solution<br>(12890 $\mu\text{S}/\text{cm}$ ) | 13000   | 12246-13534         | Pass    |

**Temperature performance checking**

| Reference thermometer-<br>E431 Readings ( $^{\circ}\text{C}$ ) | Instrument Readings ( $^{\circ}\text{C}$ ) | Correction ( $^{\circ}\text{C}$ ) | Comment |
|--|--|-----------------------------------|---------|
| 20.0   | 20.004                                     | -0.004                            | N/A     |

**pH performance checking**

|                   | Instrument Readings<br>(pH unit) | Acceptance Criteria | Comment |
|-------------------|----------------------------------|---------------------|---------|
| pH QC buffer 4.00 | 4.03                             | 4.00 $\pm$ 0.10     | Pass    |
| pH QC buffer 6.86 | 6.87                             | 6.86 $\pm$ 0.10     | Pass    |
| pH QC buffer 9.18 | 9.20                             | 9.18 $\pm$ 0.10     | Pass    |

**D.O. performance checking**

|                  | Instrument Readings (mg/L) | Acceptance Criteria | Comment |
|------------------|----------------------------|---------------------|---------|
| Zero DO solution | 0.05                       | <0.1mg/L            | Pass    |

| Winkler Titration value<br>(mg/L) | Instrument Readings (mg/L) | Acceptance Criteria   | Comment |
|-----------------------------------|----------------------------|---|---------|
| 8.00                              | 8.03                       | Difference between<br>Titration value and<br>instrument reading<br><0.2mg/L | Pass    |

**Turbidity performance checking**

| Turbidity stock solution | Instrument Readings (NTU) | Acceptance Criteria | Comment |
|--------------------------|---------------------------|---------------------|---------|
| 10 NTU                   | 10.16                     | 9.0-11.0            | Pass    |
| 50 NTU                   | 50.43                     | 45.0-55.0           | Pass    |
| 100 NTU                  | 100.2                     | 90.0-110.0          | Pass    |

**Depth performance checking**

| Water Depth | Instrument Readings (NTU) | Acceptance Criteria | Comment |
|-------------|---------------------------|---------------------|---------|
| 0.5 meter   | 0.50                      | 0.45-0.55           | Pass    |

\*\*\*\*\*END OF REPORT\*\*\*\*\*

**TEST REPORT**

**APPLICANT:** Cinotech Consultants Limited  
RM 1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T., Hong Kong

|                  |            |
|------------------|------------|
| Test Report No.: | 29025E     |
| Date of Issue:   | 2018-05-25 |
| Date Received:   | 2018-05-25 |
| Date Tested:     | 2018-05-25 |
| Date Completed:  | 2018-05-25 |
| Next Due Date:   | 2018-08-24 |

**ATTN:** Miss Mei Ling Tang

Page: 1 of 2

**Certificate of Calibration**

**Item for calibration:**

|   |                                 |            |
|---|---------------------------------|------------|
| YSI EXO1 Multiparameter Sondes            | Equipment No.:                  | SW-08-26   |
| Manufacturer:                             | YSI Incorporated, a Xylem brand |            |
| Description:                              | Model No.                       | Serial No. |
| - EXO Optical DO Sensor, Ti               | 599100-01                       | 17B101535  |
| - EXO conductivity/Temperature Sensor, Ti | 599870                          | 16H100227  |
| - EXO Turbidity Sensor, Ti                | 599101-01                       | 17K100336  |
| - EXO pH Sensor Assembly, Guarded, Ti     | 599701                          | 17K103107  |

**Test conditions:**

Room Temperature : 17-22 degree Celsius  
Relative Humidity : 40-70%

**Test Specifications:**

Performance checking for Conductivity, Temperature, pH, Dissolved oxygen (D.O.) and Turbidity

**Methodology:**

According to manufacturer instruction manual, APHA 20e 4500-O C

\*\*\*\*\*

*PREPARED AND CHECKED BY:*

For and On Behalf of **WELLAB Ltd.**



**PATRICK TSE**  
Laboratory Manager

**TEST REPORT**

|                  |            |
|------------------|------------|
| Test Report No.: | 29025E     |
| Date of Issue:   | 2018-05-25 |
| Date Received:   | 2018-05-25 |
| Date Tested:     | 2018-05-25 |
| Date Completed:  | 2018-05-25 |
| Next Due Date:   | 2018-08-24 |

Page: 2 of 2

**Certificate of Calibration**

**Results:**

**Conductivity performance checking**

|  | Instrument Readings ( $\mu\text{S}/\text{cm}$ ) | Acceptance Criteria | Comment |
|--|---|---------------------|---------|
| KCl stock solution<br>(12890 $\mu\text{S}/\text{cm}$ ) | 13000   | 12246-13534         | Pass    |

**Temperature performance checking**

| Reference thermometer-<br>E431 Readings ( $^{\circ}\text{C}$ ) | Instrument Readings ( $^{\circ}\text{C}$ ) | Correction ( $^{\circ}\text{C}$ ) | Comment |
|--|--|-----------------------------------|---------|
| 20.0   | 20.001                                     | -0.001                            | N/A     |

**pH performance checking**

|                   | Instrument Readings<br>(pH unit) | Acceptance Criteria | Comment |
|-------------------|----------------------------------|---------------------|---------|
| pH QC buffer 4.00 | 4.05                             | 4.00 $\pm$ 0.10     | Pass    |
| pH QC buffer 6.86 | 6.88                             | 6.86 $\pm$ 0.10     | Pass    |
| pH QC buffer 9.18 | 9.21                             | 9.18 $\pm$ 0.10     | Pass    |

**D.O. performance checking**

|                  | Instrument Readings (mg/L) | Acceptance Criteria | Comment |
|------------------|----------------------------|---------------------|---------|
| Zero DO solution | 0.05                       | <0.1mg/L            | Pass    |

| Winkler Titration value<br>(mg/L) | Instrument Readings (mg/L) | Acceptance Criteria   | Comment |
|-----------------------------------|----------------------------|---|---------|
| 8.00                              | 8.01                       | Difference between<br>Titration value and<br>instrument reading<br><0.2mg/L | Pass    |

**Turbidity performance checking**

| Turbidity stock solution | Instrument Readings (NTU) | Acceptance Criteria | Comment |
|--------------------------|---------------------------|---------------------|---------|
| 10 NTU                   | 10.24                     | 9.0-11.0            | Pass    |
| 50 NTU                   | 50.46                     | 45.0-55.0           | Pass    |
| 100 NTU                  | 100.3                     | 90.0-110.0          | Pass    |

**Depth performance checking**

| Water Depth | Instrument Readings (NTU) | Acceptance Criteria | Comment |
|-------------|---------------------------|---------------------|---------|
| 0.5 meter   | 0.50                      | 0.45-0.55           | Pass    |

\*\*\*\*\*END OF REPORT\*\*\*\*\*

**TEST REPORT**

**APPLICANT:** Cinotech Consultants Limited  
RM 1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T., Hong Kong

|                  |            |
|------------------|------------|
| Test Report No.: | 29025F     |
| Date of Issue:   | 2018-05-25 |
| Date Received:   | 2018-05-25 |
| Date Tested:     | 2018-05-25 |
| Date Completed:  | 2018-05-25 |
| Next Due Date:   | 2018-08-24 |

**ATTN:** Miss Mei Ling Tang

Page: 1 of 2

**Certificate of Calibration**

**Item for calibration:**

|   |                                 |            |
|---|---------------------------------|------------|
| YSI EXO1 Multiparameter Sondes            | Equipment No.:                  | SW-08-85   |
| Manufacturer:                             | YSI Incorporated, a Xylem brand |            |
| Description:                              | Model No.                       | Serial No. |
| - EXO Optical DO Sensor, Ti               | 599100-01                       | 17A105009  |
| - EXO conductivity/Temperature Sensor, Ti | 599870                          | 17A105103  |
| - EXO Turbidity Sensor, Ti                | 599101-01                       | 17A104092  |
| - EXO pH Sensor Assembly, Guarded, Ti     | 599795-01                       | 17A105263  |

**Test conditions:**

Room Temperature : 17-22 degree Celsius  
Relative Humidity : 40-70%

**Test Specifications:**

Performance checking for Conductivity, Temperature, pH, Dissolved oxygen (D.O.) and Turbidity

**Methodology:**

According to manufacturer instruction manual, APHA 20e 4500-O C

\*\*\*\*\*

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



**PATRICK TSE**

Laboratory Manager

**TEST REPORT**

|                  |            |
|------------------|------------|
| Test Report No.: | 29025F     |
| Date of Issue:   | 2018-05-25 |
| Date Received:   | 2018-05-25 |
| Date Tested:     | 2018-05-25 |
| Date Completed:  | 2018-05-25 |
| Next Due Date:   | 2018-08-24 |

Page: 2 of 2

**Certificate of Calibration**

**Results:**

**Conductivity performance checking**

|  | Instrument Readings ( $\mu\text{S}/\text{cm}$ ) | Acceptance Criteria | Comment |
|--|---|---------------------|---------|
| KCl stock solution<br>(12890 $\mu\text{S}/\text{cm}$ ) | 13000   | 12246-13534         | Pass    |

**Temperature performance checking**

| Reference thermometer-<br>E431 Readings ( $^{\circ}\text{C}$ ) | Instrument Readings ( $^{\circ}\text{C}$ ) | Correction ( $^{\circ}\text{C}$ ) | Comment |
|--|--|-----------------------------------|---------|
| 20.7   | 20.701                                     | -0.001                            | N/A     |

**pH performance checking**

|                   | Instrument Readings<br>(pH unit) | Acceptance Criteria | Comment |
|-------------------|----------------------------------|---------------------|---------|
| pH QC buffer 4.00 | 4.02                             | 4.00 $\pm$ 0.10     | Pass    |
| pH QC buffer 6.86 | 6.86                             | 6.86 $\pm$ 0.10     | Pass    |
| pH QC buffer 9.18 | 9.21                             | 9.18 $\pm$ 0.10     | Pass    |

**D.O. performance checking**

|                  | Instrument Readings (mg/L) | Acceptance Criteria | Comment |
|------------------|----------------------------|---------------------|---------|
| Zero DO solution | 0.05                       | <0.1mg/L            | Pass    |

| Winkler Titration value<br>(mg/L) | Instrument Readings (mg/L) | Acceptance Criteria   | Comment |
|-----------------------------------|----------------------------|---|---------|
| 8.00                              | 8.01                       | Difference between<br>Titration value and<br>instrument reading<br><0.2mg/L | Pass    |

**Turbidity performance checking**

| Turbidity stock solution | Instrument Readings (NTU) | Acceptance Criteria | Comment |
|--------------------------|---------------------------|---------------------|---------|
| 10 NTU                   | 10.17                     | 9.0-11.0            | Pass    |
| 50 NTU                   | 50.60                     | 45.0-55.0           | Pass    |
| 100 NTU                  | 100.3                     | 90.0-110.0          | Pass    |

**Depth performance checking**

| Water Depth | Instrument Readings (NTU) | Acceptance Criteria | Comment |
|-------------|---------------------------|---------------------|---------|
| 0.5 meter   | 0.50                      | 0.45-0.55           | Pass    |

\*\*\*\*\*END OF REPORT\*\*\*\*\*

**TEST REPORT**

**APPLICANT:** Cinotech Consultants Limited  
RM 1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T., Hong Kong

|                  |            |
|------------------|------------|
| Test Report No.: | 29025H     |
| Date of Issue:   | 2018-05-25 |
| Date Received:   | 2018-05-25 |
| Date Tested:     | 2018-05-25 |
| Date Completed:  | 2018-05-25 |
| Next Due Date:   | 2018-08-24 |

**ATTN:** Miss Mei Ling Tang

Page: 1 of 2

**Certificate of Calibration**

**Item for calibration:**

|   |                                 |            |
|---|---------------------------------|------------|
| YSI EXO1 Multiparameter Sondes            | Equipment No.:                  | SW-08-164  |
| Manufacturer:                             | YSI Incorporated, a Xylem brand |            |
| Description:                              | Model No.                       | Serial No. |
| - EXO Optical DO Sensor, Ti               | 599100-01                       | 17K101623  |
| - EXO conductivity/Temperature Sensor, Ti | 599870                          | 17H103446  |
| - EXO Turbidity Sensor, Ti                | 599101-01                       | 17K100331  |
| - EXO pH Sensor Assembly, Guarded, Ti     | 599795-01                       | 17K103099  |

**Test conditions:**

Room Temperature : 17-22 degree Celsius  
Relative Humidity : 40-70%

**Test Specifications:**

Performance checking for Conductivity, Temperature, pH, Dissolved oxygen (D.O.) and Turbidity

**Methodology:**

According to manufacturer instruction manual, APHA 20e 4500-O C

\*\*\*\*\*

*PREPARED AND CHECKED BY:*

For and On Behalf of **WELLAB Ltd.**

  
\_\_\_\_\_  
**PATRICK TSE**  
Laboratory Manager



### TEST REPORT

|                  |            |
|------------------|------------|
| Test Report No.: | 29025H     |
| Date of Issue:   | 2018-05-25 |
| Date Received:   | 2018-05-25 |
| Date Tested:     | 2018-05-25 |
| Date Completed:  | 2018-05-25 |
| Next Due Date:   | 2018-08-24 |
| Page:            | 2 of 2     |

#### Certificate of Calibration

**Results:**

**Conductivity performance checking**

|  | Instrument Readings ( $\mu\text{S}/\text{cm}$ ) | Acceptance Criteria | Comment |
|--|---|---------------------|---------|
| KCl stock solution<br>(12890 $\mu\text{S}/\text{cm}$ ) | 13000   | 12246-13534         | Pass    |

**Temperature performance checking**

| Reference thermometer-<br>E431 Readings ( $^{\circ}\text{C}$ ) | Instrument Readings ( $^{\circ}\text{C}$ ) | Correction ( $^{\circ}\text{C}$ ) | Comment |
|--|--|-----------------------------------|---------|
| 20.7   | 20.703                                     | -0.003                            | N/A     |

**pH performance checking**

|                   | Instrument Readings<br>(pH unit) | Acceptance Criteria | Comment |
|-------------------|----------------------------------|---------------------|---------|
| pH QC buffer 4.00 | 4.02                             | 4.00 $\pm$ 0.10     | Pass    |
| pH QC buffer 6.86 | 6.86                             | 6.86 $\pm$ 0.10     | Pass    |
| pH QC buffer 9.18 | 9.20                             | 9.18 $\pm$ 0.10     | Pass    |

**D.O. performance checking**

|                  | Instrument Readings (mg/L) | Acceptance Criteria | Comment |
|------------------|----------------------------|---------------------|---------|
| Zero DO solution | 0.05                       | <0.1mg/L            | Pass    |

| Winkler Titration value<br>(mg/L) | Instrument Readings (mg/L) | Acceptance Criteria   | Comment |
|-----------------------------------|----------------------------|---|---------|
| 8.00                              | 8.01                       | Difference between<br>Titration value and<br>instrument reading<br><0.2mg/L | Pass    |

**Turbidity performance checking**

| Turbidity stock solution | Instrument Readings (NTU) | Acceptance Criteria | Comment |
|--------------------------|---------------------------|---------------------|---------|
| 10 NTU                   | 10.33                     | 9.0-11.0            | Pass    |
| 50 NTU                   | 50.36                     | 45.0-55.0           | Pass    |
| 100 NTU                  | 100.2                     | 90.0-110.0          | Pass    |

**Depth performance checking**

| Water Depth | Instrument Readings (NTU) | Acceptance Criteria | Comment |
|-------------|---------------------------|---------------------|---------|
| 0.5 meter   | 0.50                      | 0.45-0.55           | Pass    |

\*\*\*\*\*END OF REPORT\*\*\*\*\*

## CALIBRATION CERTIFICATE

Calibration Item: Micromate Unit (Calibration with Geophone  
UM12902)  
Model No.: 721A2501  
Serial No.: UM12902  
Calibration Date: 14 May 2018  
Next Calibration Date: 14 May 2019  
Method Used: In-house Method MM-001  
In-house Testing Procedure No.: MM-001

| <u>Test References</u>               | <u>Model</u> | <u>Serial No.</u> |
|--------------------------------------|--------------|-------------------|
| Blastmate III                        | 714A0801     | BA15521           |
| ISEE Triaxial Geophone               | 714A9701     | BG14463           |
| GLOBAL SPECIALISTS 3MHz*             | 2030         | 256812            |
| Stanford Spectrum Analyzer           | SR760        | 41550             |
| Aglient Multimeter*                  | 34410A       | MY47011119        |
| HP Distortion Meter*                 | 339A         | 810699            |
| Bruel & Kjaer Accelerometer*         | 4370         | 30323             |
| Bruel & Kjaer Charge Amplifier*      | 2647         | 2518810           |
| Bruel & Kjaer Conditional Amplifier* | 269          | 2152173           |
| LDS Air Cooled Vibrator              | V556         | 92794/1           |
| LDS Field Power Supply               | FPS10L       | ARA 04/05         |
| LDS Power Amplifier                  | PA1000L      | ARA 07/06         |

\*References are traceable to NIST or equivalent.

INSTANTEL INC. hereby certifies that this unit has been calibrated and that the results are consistent with the specifications published regarding this instrument. The SENSORCHECK feature of the unit is sufficiently reliable to indicate proper operation, although it is recommended that this unit be sent to INSTANTEL or an authorized service center for regular calibration.

Authorized by: \_\_\_\_\_

  
(Wong, Keefe Solomon)

Date: 14 May 2018

## CALIBRATION CERTIFICATE

Calibration Item: Minimate Plus Unit (Calibration with Geophone  
BG20673)  
Model No.: 716A0403  
Serial No.: BE13849  
Calibration Date: 10 April 2018  
Next Calibration Date: 10 April 2019  
Method Used: In-house Method B3-001  
In-house Testing Procedure No.: B3-001

| <u>Test References</u>               | <u>Model</u> | <u>Serial No.</u> |
|--------------------------------------|--------------|-------------------|
| Blastmate III                        | 714A0801     | BA15521           |
| ISEE Triaxial Geophone               | 714A9701     | BG14463           |
| GLOBAL SPECIALISTS 3MHz*             | 2030         | 256812            |
| Stanford Spectrum Analyzer           | SR760        | 41550             |
| Aglient Multimeter*                  | 34410A       | MY47011119        |
| HP Distortion Meter*                 | 339A         | 810699            |
| Bruel & Kjaer Accelerometer*         | 4370         | 30323             |
| Bruel & Kjaer Charge Amplifier*      | 2647         | 2518810           |
| Bruel & Kjaer Conditional Amplifier* | 269          | 2152173           |
| LDS Air Cooled Vibrator              | V556         | 92794/1           |
| LDS Field Power Supply               | FPS10L       | ARA 04/05         |
| LDS Power Amplifier                  | PA1000L      | ARA 07/06         |

\*References are traceable to NIST or equivalent.

INSTANTEL INC. hereby certifies that this unit has been calibrated and that the results are consistent with the specifications published regarding this instrument. The SENSORCHECK feature of the unit is sufficiently reliable to indicate proper operation, although it is recommended that this unit be sent to INSTANTEL or an authorized service center for regular calibration.

Authorized by: \_\_\_\_\_

  
( Wong, Keefe Solomon )

Date: 10 April 2018

## CALIBRATION CERTIFICATE

Calibration Item: Minimate Plus Unit (Calibration with Geophone  
BG14849)  
Model No.: 716A0403  
Serial No.: BE15892  
Calibration Date: 9 April 2018  
Next Calibration Date: 9 April 2019  
Method Used: In-house Method B3-001  
In-house Testing Procedure No.: B3-001

| <u>Test References</u>               | <u>Model</u> | <u>Serial No.</u> |
|--------------------------------------|--------------|-------------------|
| Blastmate III                        | 714A0801     | BA15521           |
| ISEE Triaxial Geophone               | 714A9701     | BG14463           |
| GLOBAL SPECIALISTS 3MHz*             | 2030         | 256812            |
| Stanford Spectrum Analyzer           | SR760        | 41550             |
| Aglient Multimeter*                  | 34410A       | MY47011119        |
| HP Distortion Meter*                 | 339A         | 810699            |
| Bruel & Kjaer Accelerometer*         | 4370         | 30323             |
| Bruel & Kjaer Charge Amplifier*      | 2647         | 2518810           |
| Bruel & Kjaer Conditional Amplifier* | 269          | 2152173           |
| LDS Air Cooled Vibrator              | V556         | 92794/1           |
| LDS Field Power Supply               | FPS10L       | ARA 04/05         |
| LDS Power Amplifier                  | PA1000L      | ARA 07/06         |

\*References are traceable to NIST or equivalent.

INSTANTEL INC. hereby certifies that this unit has been calibrated and that the results are consistent with the specifications published regarding this instrument. The SENSORCHECK feature of the unit is sufficiently reliable to indicate proper operation, although it is recommended that this unit be sent to INSTANTEL or an authorized service center for regular calibration.

Authorized by: \_\_\_\_\_



( Wong, Keefe Solomon )

Date: 9 April 2018

## CALIBRATION CERTIFICATE

Calibration Item: Minimate Plus Unit (Calibration with Geophone  
BG20674)  
Model No.: 716A0403  
Serial No.: BE17902  
Calibration Date: 10 April 2018  
Next Calibration Date: 10 April 2019  
Method Used: In-house Method B3-001  
In-house Testing Procedure No.: B3-001

| <u>Test References</u>               | <u>Model</u> | <u>Serial No.</u> |
|--------------------------------------|--------------|-------------------|
| Blastmate III                        | 714A0801     | BA15521           |
| ISEE Triaxial Geophone               | 714A9701     | BG14463           |
| GLOBAL SPECIALISTS 3MHz*             | 2030         | 256812            |
| Stanford Spectrum Analyzer           | SR760        | 41550             |
| Aglient Multimeter*                  | 34410A       | MY47011119        |
| HP Distortion Meter*                 | 339A         | 810699            |
| Bruel & Kjaer Accelerometer*         | 4370         | 30323             |
| Bruel & Kjaer Charge Amplifier*      | 2647         | 2518810           |
| Bruel & Kjaer Conditional Amplifier* | 269          | 2152173           |
| LDS Air Cooled Vibrator              | V556         | 92794/1           |
| LDS Field Power Supply               | FPS10L       | ARA 04/05         |
| LDS Power Amplifier                  | PA1000L      | ARA 07/06         |

\*References are traceable to NIST or equivalent.

INSTANTEL INC. hereby certifies that this unit has been calibrated and that the results are consistent with the specifications published regarding this instrument. The SENSORCHECK feature of the unit is sufficiently reliable to indicate proper operation, although it is recommended that this unit be sent to INSTANTEL or an authorized service center for regular calibration.

Authorized by: \_\_\_\_\_



( Wong, Keefe Solomon )

Date: 10 April 2018

## CALIBRATION CERTIFICATE

Calibration Item: Minimate Plus Unit (Calibration with Geophone  
BG14847)  
Model No.: 716A0403  
Serial No.: BE17904  
Calibration Date: 9 April 2018  
Next Calibration Date: 9 April 2019  
Method Used: In-house Method B3-001  
In-house Testing Procedure No.: B3-001

| <u>Test References</u>               | <u>Model</u> | <u>Serial No.</u> |
|--------------------------------------|--------------|-------------------|
| Blastmate III                        | 714A0801     | BA15521           |
| ISEE Triaxial Geophone               | 714A9701     | BG14463           |
| GLOBAL SPECIALISTS 3MHz*             | 2030         | 256812            |
| Stanford Spectrum Analyzer           | SR760        | 41550             |
| Aglient Multimeter*                  | 34410A       | MY47011119        |
| HP Distortion Meter*                 | 339A         | 810699            |
| Bruel & Kjaer Accelerometer*         | 4370         | 30323             |
| Bruel & Kjaer Charge Amplifier*      | 2647         | 2518810           |
| Bruel & Kjaer Conditional Amplifier* | 269          | 2152173           |
| LDS Air Cooled Vibrator              | V556         | 92794/1           |
| LDS Field Power Supply               | FPS10L       | ARA 04/05         |
| LDS Power Amplifier                  | PA1000L      | ARA 07/06         |

\*References are traceable to NIST or equivalent.

INSTANTEL INC. hereby certifies that this unit has been calibrated and that the results are consistent with the specifications published regarding this instrument. The SENSORCHECK feature of the unit is sufficiently reliable to indicate proper operation, although it is recommended that this unit be sent to INSTANTEL or an authorized service center for regular calibration.

Authorized by: \_\_\_\_\_

( Wong, Keefe Solomon )

Date: 9 April 2018

## CALIBRATION CERTIFICATE

Calibration Item: Minimate Plus Unit (Calibration with Geophone  
BG16959)  
Model No.: 716A0403  
Serial No.: BE17506  
Calibration Date: 9 April 2018  
Next Calibration Date: 9 April 2019  
Method Used: In-house Method B3-001  
In-house Testing Procedure No.: B3-001

| <u>Test References</u>               | <u>Model</u> | <u>Serial No.</u> |
|--------------------------------------|--------------|-------------------|
| Blastmate III                        | 714A0801     | BA15521           |
| ISEE Triaxial Geophone               | 714A9701     | BG14463           |
| GLOBAL SPECIALISTS 3MHz*             | 2030         | 256812            |
| Stanford Spectrum Analyzer           | SR760        | 41550             |
| Aglient Multimeter*                  | 34410A       | MY47011119        |
| HP Distortion Meter*                 | 339A         | 810699            |
| Bruel & Kjaer Accelerometer*         | 4370         | 30323             |
| Bruel & Kjaer Charge Amplifier*      | 2647         | 2518810           |
| Bruel & Kjaer Conditional Amplifier* | 269          | 2152173           |
| LDS Air Cooled Vibrator              | V556         | 92794/1           |
| LDS Field Power Supply               | FPS10L       | ARA 04/05         |
| LDS Power Amplifier                  | PA1000L      | ARA 07/06         |

\*References are traceable to NIST or equivalent.

INSTANTEL INC. hereby certifies that this unit has been calibrated and that the results are consistent with the specifications published regarding this instrument. The SENSORCHECK feature of the unit is sufficiently reliable to indicate proper operation, although it is recommended that this unit be sent to INSTANTEL or an authorized service center for regular calibration.

Authorized by: \_\_\_\_\_

( Wong, Keeffe Solomon )

Date: 9 April 2018

## CALIBRATION CERTIFICATE

Calibration Item: Minimate Plus Unit (Calibration with Geophone  
BG14849)  
Model No.: 716A0403  
Serial No.: BE15892  
Calibration Date: 9 April 2018  
Next Calibration Date: 9 April 2019  
Method Used: In-house Method B3-001  
In-house Testing Procedure No.: B3-001

| <u>Test References</u>               | <u>Model</u> | <u>Serial No.</u> |
|--------------------------------------|--------------|-------------------|
| Blastmate III                        | 714A0801     | BA15521           |
| ISEE Triaxial Geophone               | 714A9701     | BG14463           |
| GLOBAL SPECIALISTS 3MHz*             | 2030         | 256812            |
| Stanford Spectrum Analyzer           | SR760        | 41550             |
| Aglient Multimeter*                  | 34410A       | MY47011119        |
| HP Distortion Meter*                 | 339A         | 810699            |
| Bruel & Kjaer Accelerometer*         | 4370         | 30323             |
| Bruel & Kjaer Charge Amplifier*      | 2647         | 2518810           |
| Bruel & Kjaer Conditional Amplifier* | 269          | 2152173           |
| LDS Air Cooled Vibrator              | V556         | 92794/1           |
| LDS Field Power Supply               | FPS10L       | ARA 04/05         |
| LDS Power Amplifier                  | PA1000L      | ARA 07/06         |

\*References are traceable to NIST or equivalent.

INSTANTEL INC. hereby certifies that this unit has been calibrated and that the results are consistent with the specifications published regarding this instrument. The SENSORCHECK feature of the unit is sufficiently reliable to indicate proper operation, although it is recommended that this unit be sent to INSTANTEL or an authorized service center for regular calibration.

Authorized by: \_\_\_\_\_



( Wong, Keefe Solomon )

Date: 9 April 2018



## CALIBRATION CERTIFICATE

Calibration Item: Minimate Plus Unit (Calibration with Geophone  
BG16957)  
Model No.: 716A0403  
Serial No.: BE17505  
Calibration Date: 22 March 2018  
Next Calibration Date: 22 March 2019  
Method Used: In-house Method B3-001  
In-house Testing Procedure No.: B3-001

| <u>Test References</u>               | <u>Model</u> | <u>Serial No.</u> |
|--------------------------------------|--------------|-------------------|
| Blastmate III                        | 714A0801     | BA15521           |
| ISEE Triaxial Geophone               | 714A9701     | BG14463           |
| GLOBAL SPECIALISTS 3MHz*             | 2030         | 256812            |
| Stanford Spectrum Analyzer           | SR760        | 41550             |
| Aglient Multimeter*                  | 34410A       | MY47011119        |
| HP Distortion Meter*                 | 339A         | 810699            |
| Bruel & Kjaer Accelerometer*         | 4370         | 30323             |
| Bruel & Kjaer Charge Amplifier*      | 2647         | 2518810           |
| Bruel & Kjaer Conditional Amplifier* | 269          | 2152173           |
| LDS Air Cooled Vibrator              | V556         | 92794/1           |
| LDS Field Power Supply               | FPS10L       | ARA 04/05         |
| LDS Power Amplifier                  | PA1000L      | ARA 07/06         |

\*References are traceable to NIST or equivalent.

INSTANTEL INC. hereby certifies that this unit has been calibrated and that the results are consistent with the specifications published regarding this instrument. The SENSORCHECK feature of the unit is sufficiently reliable to indicate proper operation, although it is recommended that this unit be sent to INSTANTEL or an authorized service center for regular calibration.

Authorized by: \_\_\_\_\_

( Leung Man Hin, Eric )

Date: 22 March 2018

## CALIBRATION CERTIFICATE

Calibration Item: Minimate Plus Unit (Calibration with Geophone  
BG15353)  
Model No.: 716A0403  
Serial No.: BE15891  
Calibration Date: 22 March 2018  
Next Calibration Date: 22 March 2019  
Method Used: In-house Method B3-001  
In-house Testing Procedure No.: B3-001

| <b>Test References</b>               | <b>Model</b> | <b>Serial No.</b> |
|--------------------------------------|--------------|-------------------|
| Blastmate III                        | 714A0801     | BA15521           |
| ISEE Triaxial Geophone               | 714A9701     | BG14463           |
| GLOBAL SPECIALISTS 3MHz*             | 2030         | 256812            |
| Stanford Spectrum Analyzer           | SR760        | 41550             |
| Aglient Multimeter*                  | 34410A       | MY47011119        |
| HP Distortion Meter*                 | 339A         | 810699            |
| Bruel & Kjaer Accelerometer*         | 4370         | 30323             |
| Bruel & Kjaer Charge Amplifier*      | 2647         | 2518810           |
| Bruel & Kjaer Conditional Amplifier* | 269          | 2152173           |
| LDS Air Cooled Vibrator              | V556         | 92794/1           |
| LDS Field Power Supply               | FPS10L       | ARA 04/05         |
| LDS Power Amplifier                  | PA1000L      | ARA 07/06         |

\*References are traceable to NIST or equivalent.

INSTANTEL INC. hereby certifies that this unit has been calibrated and that the results are consistent with the specifications published regarding this instrument. The SENSORCHECK feature of the unit is sufficiently reliable to indicate proper operation, although it is recommended that this unit be sent to INSTANTEL or an authorized service center for regular calibration.

Authorized by: \_\_\_\_\_

( Leung Man Hin, Eric )

Date: 22 March 2018

## CALIBRATION CERTIFICATE

Calibration Item: Minimate Plus Unit (Calibration with Geophone  
BG16955)  
Model No.: 716A0403  
Serial No.: BE16223  
Calibration Date: 9 April 2018  
Next Calibration Date: 9 April 2019  
Method Used: In-house Method B3-001  
In-house Testing Procedure No.: B3-001

| <u>Test References</u>               | <u>Model</u> | <u>Serial No.</u> |
|--------------------------------------|--------------|-------------------|
| Blastmate III                        | 714A0801     | BA15521           |
| ISEE Triaxial Geophone               | 714A9701     | BG14463           |
| GLOBAL SPECIALISTS 3MHz*             | 2030         | 256812            |
| Stanford Spectrum Analyzer           | SR760        | 41550             |
| Aglient Multimeter*                  | 34410A       | MY47011119        |
| HP Distortion Meter*                 | 339A         | 810699            |
| Bruel & Kjaer Accelerometer*         | 4370         | 30323             |
| Bruel & Kjaer Charge Amplifier*      | 2647         | 2518810           |
| Bruel & Kjaer Conditional Amplifier* | 269          | 2152173           |
| LDS Air Cooled Vibrator              | V556         | 92794/1           |
| LDS Field Power Supply               | FPS10L       | ARA 04/05         |
| LDS Power Amplifier                  | PA1000L      | ARA 07/06         |

\*References are traceable to NIST or equivalent.

INSTANTEL INC. hereby certifies that this unit has been calibrated and that the results are consistent with the specifications published regarding this instrument. The SENSORCHECK feature of the unit is sufficiently reliable to indicate proper operation, although it is recommended that this unit be sent to INSTANTEL or an authorized service center for regular calibration.

Authorized by: \_\_\_\_\_

  
( Wong, Keefe Solomon )

Date: 9 April 2018



## CERTIFICATE OF CALIBRATION

Calibration Date: 1<sup>st</sup> September 2017

Model: iCivil-1011 Inclinometer

Serial No. : HK110118

Method Used: By direct measurement

### Laboratory Conditions:

Ambient Temperature: (23±2)°C

Relative Humidity: (50 ±20)%

Test Reference

Dual-Axis Digital Angle Protractor

Model

TLL-90S

Equipment ID

EPC001

### Calibration Result

X-Axis Measurement

| Applied Angle (degree) | UUT Reading (degree) | Error (degree) |
|------------------------|----------------------|----------------|
| 10.011                 | 9.943                | -0.068         |
| 5.005                  | 4.976                | -0.029         |
| 1.003                  | 0.995                | -0.008         |
| 0.001                  | -0.002               | -0.003         |
| -1.005                 | -0.996               | 0.009          |
| -5.015                 | -4.976               | 0.039          |
| -10.009                | -9.940               | 0.069          |

Remarks:

1. The above calibration data applies only to the instrument described above.

Checked By:

Date: 1<sup>st</sup> September 2017

\*\*\* End of Report\*\*\*



## CERTIFICATE OF CALIBRATION

Calibration Date: 1<sup>st</sup> September 2017

Model: iCivil-1011 Inclinometer

Serial No. : HK110120

Method Used: By direct measurement

### Laboratory Conditions:

Ambient Temperature: (23±2)°C

Relative Humidity: (50 ±20)%

Test Reference

Dual-Axis Digital Angle Protractor

Model

TLL-90S

Equipment ID

EPC001

### Calibration Result

X-Axis Measurement

| Applied Angle (degree) | UUT Reading (degree) | Error (degree) |
|------------------------|----------------------|----------------|
| 10.005                 | 9.945                | -0.06          |
| 5.007                  | 4.978                | -0.029         |
| 1.003                  | 0.998                | -0.005         |
| 0.001                  | -0.001               | -0.002         |
| -1.008                 | -0.998               | 0.01           |
| -5.010                 | -4.974               | 0.036          |
| -10.001                | -9.943               | 0.058          |

Remarks:

1. The above calibration data applies only to the instrument described above.

Checked By:

Date: 1<sup>st</sup> September 2017

\*\*\* End of Report\*\*\*



# YSF Corporation Limited

5/A., Blk 1 Kin Ho Ind Bldg 20-24, Au Pui Wan St,  
Fo Tan, Shatin, N.T. Hong Kong

Phone: 852-8109 8368 Fax: 852-3007 4857

## CERTIFICATE OF CALIBRATION

|                  |                        |                      |  |
|------------------|------------------------|----------------------|--|
| Certificate No.  | : CS-CC- 170820        | Customer             | : Leighton-China State Joint Venture                           |
| Manufacturer     | : Leica                | Address              | : 39/F., Sun Hung Kai Centre,<br>30 Harbour Road,<br>Hong Kong |
| Equipment        | : Digital Level        | Calibration Interval | : 12 months  |
| Model            | : LS15 0.3mm           | Reference Document   | : CS/ME/ 3(HKST)   |
| Serial No.       | : 701133               | Report No.           | : CS-CR- 170820  |
| Calibration Date | : 14th September, 2017 |                      |  |
| Expire Date      | : 13th September, 2018 |                      |  |

The instrument has been checked and calibrated according to document procedures and using standards and instruments which are traceable to international accepted standards. The standards and instruments used in the calibration are calibrated on a schedule which is adjusted to maintain traceability at the required accuracy level, or have been derived from the ratio type of self-calibration techniques. This is established by our Quality Management System, audited to ISO9001 :2008 by an independent national accredited body.

The specified calibration interval is a recommendation. Depending on the type of use ambient conditions or accuracy requirements, other calibration intervals may be applicable. The user shall be responsible that calibration is carried out at adequate intervals.

YSF Corporation Ltd. hereby certifies this instrument meets or exceeds all published specifications of the manufacturer at present inforce. This calibration certificate may only be distributed in a complete and unchanged form. Unsigned calibration certificates are invalid.

Calibrated by

Wayne

Wayne Ng, Service Engineer  
14th September, 2017

CKL/CSL/170820

Checked by



Wallace Yu, Service Manager  
14th September, 2017



# YSF Corporation Ltd.

## Calibration Report

Certificate No. : CS-CC-170820 Certificate Report No. : CS-CR-170820

Client : Leighton-China State Joint Venture

Address : 39/F., Sun Hung Kai Centre, 30 Harbour Road, Hong Kong

Item Calibrated : **Name/Description:** Digital Level

**Manufacturer:** Leica

**Model:** LS15 0.3mm **Eqt. No:** 701133

Reference Standard : 5198266  
Calibration check according to customer's requirement.

Calibration Method : Procedure CS02

### Calibration Conditions

Temperature : (  $31 \pm 3^{\circ}\text{C}$  )

Relative Humidity : 84% RH

Date of Test : 14th September, 2017

Test Results : **PASS** (All calibration points were within the tolerances as shown in the attached calibration results.)

Calibrated by : Wayne  
Wayne Ng, Service Engineer  
Date: 14th September, 2017

HKCS Approved Signatory: [Signature]  
Wallace Yu, Service Manager  
Date: 14th September, 2017

- Notes:
- 1, The test equipment used for calibration are traceable to national standards/international system of units(SI)
  - 2, The values given in this calibration certificate only to the values measured at the time of test & any uncertainties quoted will not include allowance for the equipment long term drift, variations with environmental changes, vibration and shock during transportation, overloading, mis-handling, or the capability of any other laboratory to repeat the measurement. YSF Corporation Ltd. shall not be liable for any loss/damage resulting from the use of the equipment.
  - 3, The test results apply to the above Unit-Under-Test only.
  - 4, This certificate shall not be reproduced, except on full, without approval of YSF Corporation Ltd.



# YSF Corporation Ltd.

## Calibration Report

Certificate Report No.:CS-CR-170820

Certificate No. :CS-CC-170820

Client : Leighton-China State Joint Venture

Address : 39/F., Sun Hung Kai Centre, 30 Harbour Road, Hong Kong

Item Calibrated :Name/Description: Digital Level

Manufacturer: Leica

Model: LS15 0.3mm

Eqt. No: 701133

| Inspection Item                | Result |
|--------------------------------|--------|
| Line of sight leveling         | Pass   |
| Compensation accuracy          | Pass   |
| Stadia spacing                 | Pass   |
| Circular bubble level accuracy | Pass   |
| Focusing                       | Pass   |
| Hori. Motion                   | Pass   |

**Overall Inspection Result : PASS**

Served by :

*Wayne*

Wayne Ng, Service Engineer

Date: 14th September, 2017

We hereby confirm the inspection has been completed and complied with the specifications required.

**YSF Corporation Ltd.**

*Wallace Yu*  
Wallace Yu, Service Manager

Date: 14th September, 2017





The Safety Company

MSA Corporate Center • 1000 Cranberry Woods Drive • Cranberry Township, PA 16066

www.msasafety.com

Telephone: (800) MSA-2222

ALTAIR5X  
CERTIFICATE OF CALIBRATION

Serial Number: 120848

Part Number: A-ALT5X-A-N-K-D-1-0-0-T-0-0-0

Sales Order Number:



Factory Calibration Date: 08/18/17

Set Points

|                  | METHANE<br>0-100.00<br>%LEL | O2<br>0-30.00 %VOL | CO<br>0-2000.00<br>PPM | H2S<br>0-200.00 PPM | NH3<br>0-100.00 PPM |  |
|------------------|-----------------------------|--------------------|------------------------|---------------------|---------------------|--|
| ↓ (Low)          | 10.00 %LEL                  | 19.50 %VOL         | 25.00 PPM              | 10.00 PPM           | 25.00 PPM           |  |
| ↑ (High)         | 20.00 %LEL                  | 23.00 %VOL         | 100.00 PPM             | 15.00 PPM           | 50.00 PPM           |  |
| STEL             |                             |                    | 100.00 PPM             | 15.00 PPM           | 35.00 PPM           |  |
| TWA              |                             |                    | 25.00 PPM              | 10.00 PPM           | 25.00 PPM           |  |
| Calibrated Value | Methane 1.45 %VOL           | O2 15.00 %VOL      | CO 60.4 PPM            | H2S 21.0 PPM        | NH3 25 PPM          |  |
| Cylinder Lot #   | 1027601826B                 | 1027601826B        | 1027601826B            | 1027601826B         | 201397              |  |

All applicable inspections, testing, and calibrations were performed using NIST traceable equipment, where available, in accordance with MSA's ISO 9001 Certified Quality System. Each material, component, and/or instrument must be installed, operated and maintained in strict accordance with its labels, cautions, warnings, instructions, and within the limitations stated in the supplied instruction manual. Routine calibration checks, equipment inspections, and applicable preventative maintenance measures must be performed to verify that the materials, components, and/or instruments are operating properly. Failure to perform these tasks on a routine basis, or suggested intervals, with specified equipment or methods, may result in inaccurate readings.

Process Certified By:

Calibrated By: E. Weber

JIM HOFFMAN  
QUALITY ENGINEER



The Safety Company

MSA Corporate Center • 1000 Cranberry Woods Drive • Cranberry Township, PA 16066

www.msasafety.com

Telephone: (800) MSA-2222

### ALTAIR5X CERTIFICATE OF CALIBRATION

Serial Number: 120847

Part Number: A-ALT5X-A-N-K-D-1-0-0-T-0-0-0

Sales Order Number:



Factory Calibration Date: 08/18/17

#### Set Points

|                  |                   |               |             |              |            |  |
|------------------|-------------------|---------------|-------------|--------------|------------|--|
|                  |                   |               |             |              |            |  |
| ↓ (Low)          |                   |               |             |              |            |  |
| ↑ (High)         |                   |               |             |              |            |  |
| STEL             |                   |               |             |              |            |  |
| TWA              |                   |               |             |              |            |  |
| Calibrated Value | Methane 1.45 %VOL | O2 15.00 %VOL | CO 60.4 PPM | H2S 21.0 PPM | NH3 25 PPM |  |
| Cylinder Lot #   | 1027601826B       | 1027601826B   | 1027601826B | 1027601826B  | 201397     |  |

All applicable inspections, testing, and calibrations were performed using NIST traceable equipment, where available, in accordance with MSA's ISO 9001 Certified Quality System. Each material, component, and/or instrument must be installed, operated and maintained in strict accordance with its labels, cautions, warnings, instructions, and within the limitations stated in the supplied instruction manual. Routine calibration checks, equipment inspections, and applicable preventative maintenance measures must be performed to verify that the materials, components, and/or instruments are operating properly. Failure to perform these tasks on a routine basis, or suggested intervals, with specified equipment or methods, may result in inaccurate readings.

Process Certified By:

Calibrated By: E. Weber

JIM HOFFMAN  
QUALITY ENGINEER

LOCATION: 1000 Cranberry Woods Drive • Cranberry Township, PA 16066-5296

---

---

**APPENDIX C**  
**WEATHER INFORMATION**

---

---

**APPENDIX C –  
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

**I. General Information**

| <b>Date</b>  | <b>Mean Air Temperature (°C)</b> | <b>Mean Relative Humidity (%)</b> | <b>Precipitation (mm)</b> |
|--------------|----------------------------------|-----------------------------------|---------------------------|
| 1 June 2018  | 27.8 – 35.1                      | 75                                | -                         |
| 2 June 2018  | 27.2 – 32.8                      | 74                                | Trace                     |
| 3 June 2018  | 27.3 – 32.6                      | 74                                | Trace                     |
| 4 June 2018  | 26.5 – 31.2                      | 85                                | 12.4                      |
| 5 June 2018  | 25.9 – 29.5                      | 92                                | 28.2                      |
| 6 June 2018  | 26.0 – 28.4                      | 93                                | 58.3                      |
| 7 June 2018  | 26.0 – 28.6                      | 92                                | 47.4                      |
| 8 June 2018  | 25.3 – 30.2                      | 88                                | 70.2                      |
| 9 June 2018  | 26.5 – 30.4                      | 79                                | 4.8                       |
| 10 June 2018 | 27.4 – 33.4                      | 69                                | -                         |
| 11 June 2018 | 28.0 – 34.3                      | 59                                | -                         |
| 12 June 2018 | 25.2 – 30.1                      | 88                                | 39.6                      |
| 13 June 2018 | 25.6 – 28.5                      | 94                                | 109.3                     |
| 14 June 2018 | 25.4 – 28.6                      | 82                                | 1.3                       |
| 15 June 2018 | 25.7 – 29.1                      | 76                                | 0.2                       |
| 16 June 2018 | 26.9 -31.5                       | 70                                | -                         |
| 17 June 2018 | 26.2 – 30.8                      | 72                                | Trace                     |
| 18 June 2018 | 27.4 – 31.9                      | 77                                | Trace                     |
| 19 June 2018 | 28.6 – 31.5                      | 79                                | Trace                     |

**APPENDIX C –  
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

**I. General Information**

| <b>Date</b>  | <b>Mean Air Temperature (°C)</b> | <b>Mean Relative Humidity (%)</b> | <b>Precipitation (mm)</b> |
|--------------|----------------------------------|-----------------------------------|---------------------------|
| 20 June 2018 | 28.8 – 32.4                      | 78                                | Trace                     |
| 21 June 2018 | 28.7 – 31.6                      | 81                                | 2.6                       |
| 22 June 2018 | 25.4 – 30.4                      | 87                                | 32.9                      |
| 23 June 2018 | 24.4 – 29.7                      | 90                                | 25.6                      |
| 24 June 2018 | 26.4 – 32.5                      | 84                                | 18.1                      |
| 25 June 2018 | 26.0 – 31.3                      | 85                                | 6.2                       |
| 26 June 2018 | 25.9 – 33.4                      | 80                                | 1.7                       |
| 27 June 2018 | 27.4 – 31.9                      | 78                                | Trace                     |
| 28 June 2018 | 27.7 – 32.6                      | 75                                | -                         |
| 29 June 2018 | 28.4 – 32.5                      | 76                                | Trace                     |
| 30 June 2018 | 28.9 – 32.8                      | 80                                | Trace                     |

\* The above information was extracted from the daily weather summary by Hong Kong Observatory.

\*\* Trace means rainfall less than 0.05 mm

**APPENDIX C –  
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

**II. Mean Wind Speed and Wind Direction**

| <b>Date</b> | <b>Time</b> | <b>Wind Speed m/s</b> | <b>Direction</b> |
|-------------|-------------|-----------------------|------------------|
| 1-Jun-2018  | 00:00       | 1.9                   | SW               |
| 1-Jun-2018  | 01:00       | 1.8                   | SW               |
| 1-Jun-2018  | 02:00       | 1.5                   | WNW              |
| 1-Jun-2018  | 03:00       | 1.7                   | SSW              |
| 1-Jun-2018  | 04:00       | 1.9                   | SSE              |
| 1-Jun-2018  | 05:00       | 1.8                   | ESE              |
| 1-Jun-2018  | 06:00       | 1.6                   | ESE              |
| 1-Jun-2018  | 07:00       | 1.8                   | SSE              |
| 1-Jun-2018  | 08:00       | 1.6                   | SSE              |
| 1-Jun-2018  | 09:00       | 2.4                   | SSE              |
| 1-Jun-2018  | 10:00       | 2                     | SSE              |
| 1-Jun-2018  | 11:00       | 2.7                   | SE               |
| 1-Jun-2018  | 12:00       | 3                     | SE               |
| 1-Jun-2018  | 13:00       | 2.6                   | SSE              |
| 1-Jun-2018  | 14:00       | 3                     | SSE              |
| 1-Jun-2018  | 15:00       | 2.5                   | SSE              |
| 1-Jun-2018  | 16:00       | 2.7                   | SSE              |
| 1-Jun-2018  | 17:00       | 2.7                   | ENE              |
| 1-Jun-2018  | 18:00       | 2.3                   | NE               |
| 1-Jun-2018  | 19:00       | 1.8                   | ENE              |
| 1-Jun-2018  | 20:00       | 1.6                   | NE               |
| 1-Jun-2018  | 21:00       | 1.6                   | ENE              |
| 1-Jun-2018  | 22:00       | 1.4                   | ENE              |
| 1-Jun-2018  | 23:00       | 1.5                   | ENE              |
| 2-Jun-2018  | 00:00       | 1.6                   | ENE              |
| 2-Jun-2018  | 01:00       | 1.7                   | ENE              |
| 2-Jun-2018  | 02:00       | 1.9                   | E                |
| 2-Jun-2018  | 03:00       | 1.6                   | ENE              |
| 2-Jun-2018  | 04:00       | 2                     | E                |
| 2-Jun-2018  | 05:00       | 1.8                   | ENE              |
| 2-Jun-2018  | 06:00       | 1.8                   | SSE              |
| 2-Jun-2018  | 07:00       | 1.8                   | ESE              |
| 2-Jun-2018  | 08:00       | 1.6                   | ENE              |
| 2-Jun-2018  | 09:00       | 1.9                   | ENE              |
| 2-Jun-2018  | 10:00       | 2.1                   | ENE              |
| 2-Jun-2018  | 11:00       | 2.6                   | ESE              |
| 2-Jun-2018  | 12:00       | 2.8                   | ENE              |

**APPENDIX C –  
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

**II. Mean Wind Speed and Wind Direction**

|            |       |     |     |
|------------|-------|-----|-----|
| 2-Jun-2018 | 13:00 | 2.6 | ESE |
| 2-Jun-2018 | 14:00 | 2.7 | ESE |
| 2-Jun-2018 | 15:00 | 2.9 | ESE |
| 2-Jun-2018 | 16:00 | 2.4 | ESE |
| 2-Jun-2018 | 17:00 | 1.7 | ESE |
| 2-Jun-2018 | 18:00 | 1.9 | ESE |
| 2-Jun-2018 | 19:00 | 2   | ESE |
| 2-Jun-2018 | 20:00 | 1.8 | ESE |
| 2-Jun-2018 | 21:00 | 1.7 | SSW |
| 2-Jun-2018 | 22:00 | 1.7 | SSW |
| 2-Jun-2018 | 23:00 | 1.7 | ESE |
| 3-Jun-2018 | 00:00 | 1.8 | ESE |
| 3-Jun-2018 | 01:00 | 1.7 | E   |
| 3-Jun-2018 | 02:00 | 1.7 | NNW |
| 3-Jun-2018 | 03:00 | 1.8 | ENE |
| 3-Jun-2018 | 04:00 | 1.9 | N   |
| 3-Jun-2018 | 05:00 | 1.7 | ENE |
| 3-Jun-2018 | 06:00 | 1.4 | N   |
| 3-Jun-2018 | 07:00 | 2   | ENE |
| 3-Jun-2018 | 08:00 | 1.6 | ENE |
| 3-Jun-2018 | 09:00 | 1.8 | ENE |
| 3-Jun-2018 | 10:00 | 2.3 | ENE |
| 3-Jun-2018 | 11:00 | 2.1 | SE  |
| 3-Jun-2018 | 12:00 | 2.4 | ENE |
| 3-Jun-2018 | 13:00 | 2.9 | ENE |
| 3-Jun-2018 | 14:00 | 2.6 | ENE |
| 3-Jun-2018 | 15:00 | 2.6 | SSE |
| 3-Jun-2018 | 16:00 | 2.9 | S   |
| 3-Jun-2018 | 17:00 | 2.7 | SSE |
| 3-Jun-2018 | 18:00 | 2.7 | ESE |
| 3-Jun-2018 | 19:00 | 2.8 | SE  |
| 3-Jun-2018 | 20:00 | 2   | SW  |
| 3-Jun-2018 | 21:00 | 1.8 | E   |
| 3-Jun-2018 | 22:00 | 2   | WSW |
| 3-Jun-2018 | 23:00 | 1.7 | SW  |
| 4-Jun-2018 | 00:00 | 2.1 | S   |
| 4-Jun-2018 | 01:00 | 2.1 | SSW |
| 4-Jun-2018 | 02:00 | 1.5 | SE  |

**APPENDIX C –  
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

**II. Mean Wind Speed and Wind Direction**

|            |       |     |     |
|------------|-------|-----|-----|
| 4-Jun-2018 | 03:00 | 1.7 | SSE |
| 4-Jun-2018 | 04:00 | 1.5 | SE  |
| 4-Jun-2018 | 05:00 | 1.4 | SSE |
| 4-Jun-2018 | 06:00 | 1.5 | ENE |
| 4-Jun-2018 | 07:00 | 1.3 | N   |
| 4-Jun-2018 | 08:00 | 1.9 | SSW |
| 4-Jun-2018 | 09:00 | 2.1 | SSW |
| 4-Jun-2018 | 10:00 | 2.5 | ENE |
| 4-Jun-2018 | 11:00 | 3.2 | ENE |
| 4-Jun-2018 | 12:00 | 2.8 | ENE |
| 4-Jun-2018 | 13:00 | 2.7 | SE  |
| 4-Jun-2018 | 14:00 | 2.8 | SE  |
| 4-Jun-2018 | 15:00 | 2.6 | SE  |
| 4-Jun-2018 | 16:00 | 2.7 | SE  |
| 4-Jun-2018 | 17:00 | 2   | ESE |
| 4-Jun-2018 | 18:00 | 1.8 | SSE |
| 4-Jun-2018 | 19:00 | 1.2 | S   |
| 4-Jun-2018 | 20:00 | 1   | SE  |
| 4-Jun-2018 | 21:00 | 1   | W   |
| 4-Jun-2018 | 22:00 | 1.2 | W   |
| 4-Jun-2018 | 23:00 | 1.2 | N   |
| 5-Jun-2018 | 00:00 | 1.3 | NE  |
| 5-Jun-2018 | 01:00 | 1.5 | N   |
| 5-Jun-2018 | 02:00 | 1.4 | ENE |
| 5-Jun-2018 | 03:00 | 1.4 | S   |
| 5-Jun-2018 | 04:00 | 1.7 | NNE |
| 5-Jun-2018 | 05:00 | 1.7 | ENE |
| 5-Jun-2018 | 06:00 | 1.2 | SSW |
| 5-Jun-2018 | 07:00 | 1.6 | SSE |
| 5-Jun-2018 | 08:00 | 1.6 | SSE |
| 5-Jun-2018 | 09:00 | 2.7 | NNE |
| 5-Jun-2018 | 10:00 | 2   | S   |
| 5-Jun-2018 | 11:00 | 2.5 | SSW |
| 5-Jun-2018 | 12:00 | 2.3 | S   |
| 5-Jun-2018 | 13:00 | 2.1 | S   |
| 5-Jun-2018 | 14:00 | 1.6 | SSE |
| 5-Jun-2018 | 15:00 | 2.6 | ENE |
| 5-Jun-2018 | 16:00 | 3   | NE  |



**APPENDIX C –  
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

**II. Mean Wind Speed and Wind Direction**

|            |       |     |     |
|------------|-------|-----|-----|
| 5-Jun-2018 | 17:00 | 2.2 | N   |
| 5-Jun-2018 | 18:00 | 2.2 | WSW |
| 5-Jun-2018 | 19:00 | 2.6 | SW  |
| 5-Jun-2018 | 20:00 | 2.7 | N   |
| 5-Jun-2018 | 21:00 | 2.1 | S   |
| 5-Jun-2018 | 22:00 | 1.9 | SSW |
| 5-Jun-2018 | 23:00 | 1.9 | SSW |
| 6-Jun-2018 | 00:00 | 1.9 | SW  |
| 6-Jun-2018 | 01:00 | 2   | SSW |
| 6-Jun-2018 | 02:00 | 2.7 | SSW |
| 6-Jun-2018 | 03:00 | 2.6 | SW  |
| 6-Jun-2018 | 04:00 | 2.4 | ESE |
| 6-Jun-2018 | 05:00 | 2.3 | WSW |
| 6-Jun-2018 | 06:00 | 2.3 | SW  |
| 6-Jun-2018 | 07:00 | 2.3 | WNW |
| 6-Jun-2018 | 08:00 | 2.3 | SW  |
| 6-Jun-2018 | 09:00 | 2.5 | SSW |
| 6-Jun-2018 | 10:00 | 2.8 | SSW |
| 6-Jun-2018 | 11:00 | 3   | SSW |
| 6-Jun-2018 | 12:00 | 3.1 | N   |
| 6-Jun-2018 | 13:00 | 3.1 | ENE |
| 6-Jun-2018 | 14:00 | 2.9 | NE  |
| 6-Jun-2018 | 15:00 | 3.4 | SW  |
| 6-Jun-2018 | 16:00 | 3.6 | N   |
| 6-Jun-2018 | 17:00 | 3.2 | ENE |
| 6-Jun-2018 | 18:00 | 2.6 | S   |
| 6-Jun-2018 | 19:00 | 2.6 | WNW |
| 6-Jun-2018 | 20:00 | 2.5 | E   |
| 6-Jun-2018 | 21:00 | 2.1 | NW  |
| 6-Jun-2018 | 22:00 | 2.5 | WNW |
| 6-Jun-2018 | 23:00 | 2.3 | NNE |
| 7-Jun-2018 | 00:00 | 2.3 | N   |
| 7-Jun-2018 | 01:00 | 2.6 | SSE |
| 7-Jun-2018 | 02:00 | 2.2 | SSE |
| 7-Jun-2018 | 03:00 | 2.3 | SSW |
| 7-Jun-2018 | 04:00 | 2.2 | WSW |
| 7-Jun-2018 | 05:00 | 1.9 | WSW |
| 7-Jun-2018 | 06:00 | 1.8 | ENE |

**APPENDIX C –  
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

**II. Mean Wind Speed and Wind Direction**

|            |       |     |     |
|------------|-------|-----|-----|
| 7-Jun-2018 | 07:00 | 1.7 | SW  |
| 7-Jun-2018 | 08:00 | 2   | SSE |
| 7-Jun-2018 | 09:00 | 2   | WNW |
| 7-Jun-2018 | 10:00 | 2   | WNW |
| 7-Jun-2018 | 11:00 | 1.8 | N   |
| 7-Jun-2018 | 12:00 | 1.8 | N   |
| 7-Jun-2018 | 13:00 | 1.7 | ENE |
| 7-Jun-2018 | 14:00 | 1.7 | ENE |
| 7-Jun-2018 | 15:00 | 1.8 | WNW |
| 7-Jun-2018 | 16:00 | 1.9 | W   |
| 7-Jun-2018 | 17:00 | 2.2 | W   |
| 7-Jun-2018 | 18:00 | 2.2 | SSW |
| 7-Jun-2018 | 19:00 | 2.3 | SSW |
| 7-Jun-2018 | 20:00 | 1.9 | NE  |
| 7-Jun-2018 | 21:00 | 1.7 | SW  |
| 7-Jun-2018 | 22:00 | 1.6 | SW  |
| 7-Jun-2018 | 23:00 | 1.6 | WNW |
| 8-Jun-2018 | 00:00 | 1.6 | WNW |
| 8-Jun-2018 | 01:00 | 1.5 | ENE |
| 8-Jun-2018 | 02:00 | 1.5 | SSW |
| 8-Jun-2018 | 03:00 | 1.4 | ENE |
| 8-Jun-2018 | 04:00 | 1.7 | NNW |
| 8-Jun-2018 | 05:00 | 1.7 | ENE |
| 8-Jun-2018 | 06:00 | 1.6 | ENE |
| 8-Jun-2018 | 07:00 | 1.7 | W   |
| 8-Jun-2018 | 08:00 | 2.2 | W   |
| 8-Jun-2018 | 09:00 | 2.3 | WSW |
| 8-Jun-2018 | 10:00 | 2.8 | SSW |
| 8-Jun-2018 | 11:00 | 2.8 | W   |
| 8-Jun-2018 | 12:00 | 2.7 | W   |
| 8-Jun-2018 | 13:00 | 2.3 | W   |
| 8-Jun-2018 | 14:00 | 2.8 | SSW |
| 8-Jun-2018 | 15:00 | 2.7 | SSW |
| 8-Jun-2018 | 16:00 | 2.4 | SSW |
| 8-Jun-2018 | 17:00 | 2   | SSW |
| 8-Jun-2018 | 18:00 | 1.7 | W   |
| 8-Jun-2018 | 19:00 | 1.6 | W   |
| 8-Jun-2018 | 20:00 | 1.9 | SW  |

**APPENDIX C –  
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

**II. Mean Wind Speed and Wind Direction**

|             |       |     |     |
|-------------|-------|-----|-----|
| 8-Jun-2018  | 21:00 | 2.1 | W   |
| 8-Jun-2018  | 22:00 | 2.2 | WSW |
| 8-Jun-2018  | 23:00 | 1.8 | SSW |
| 9-Jun-2018  | 00:00 | 2   | SSW |
| 9-Jun-2018  | 01:00 | 2   | WSW |
| 9-Jun-2018  | 02:00 | 1.9 | SSW |
| 9-Jun-2018  | 03:00 | 1.9 | SSW |
| 9-Jun-2018  | 04:00 | 2.1 | WSW |
| 9-Jun-2018  | 05:00 | 1.6 | WSW |
| 9-Jun-2018  | 06:00 | 1.3 | W   |
| 9-Jun-2018  | 07:00 | 1.3 | WSW |
| 9-Jun-2018  | 08:00 | 1.4 | WSW |
| 9-Jun-2018  | 09:00 | 1.8 | SSW |
| 9-Jun-2018  | 10:00 | 2.1 | SW  |
| 9-Jun-2018  | 11:00 | 2.3 | W   |
| 9-Jun-2018  | 12:00 | 2.3 | W   |
| 9-Jun-2018  | 13:00 | 2.2 | WNW |
| 9-Jun-2018  | 14:00 | 1.8 | SSW |
| 9-Jun-2018  | 15:00 | 1.9 | NNW |
| 9-Jun-2018  | 16:00 | 1.8 | NW  |
| 9-Jun-2018  | 17:00 | 1.8 | N   |
| 9-Jun-2018  | 18:00 | 1.3 | NNW |
| 9-Jun-2018  | 19:00 | 1   | NW  |
| 9-Jun-2018  | 20:00 | 1.1 | WNW |
| 9-Jun-2018  | 21:00 | 1.6 | WNW |
| 9-Jun-2018  | 22:00 | 1.3 | W   |
| 9-Jun-2018  | 23:00 | 1.2 | WNW |
| 10-Jun-2018 | 00:00 | 1   | WNW |
| 10-Jun-2018 | 01:00 | 1.2 | WNW |
| 10-Jun-2018 | 02:00 | 1   | WNW |
| 10-Jun-2018 | 03:00 | 1.1 | WNW |
| 10-Jun-2018 | 04:00 | 0.8 | NW  |
| 10-Jun-2018 | 05:00 | 0.9 | WNW |
| 10-Jun-2018 | 06:00 | 1   | WNW |
| 10-Jun-2018 | 07:00 | 0.7 | WNW |
| 10-Jun-2018 | 08:00 | 0.8 | NW  |
| 10-Jun-2018 | 09:00 | 1.3 | WNW |
| 10-Jun-2018 | 10:00 | 1.4 | NNW |

**APPENDIX C –  
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

**II. Mean Wind Speed and Wind Direction**

|             |       |     |     |
|-------------|-------|-----|-----|
| 10-Jun-2018 | 11:00 | 2.5 | WNW |
| 10-Jun-2018 | 12:00 | 2.7 | NNW |
| 10-Jun-2018 | 13:00 | 2.7 | N   |
| 10-Jun-2018 | 14:00 | 2.6 | NNW |
| 10-Jun-2018 | 15:00 | 2.5 | WNW |
| 10-Jun-2018 | 16:00 | 2.7 | WNW |
| 10-Jun-2018 | 17:00 | 2.5 | WNW |
| 10-Jun-2018 | 18:00 | 1.3 | WNW |
| 10-Jun-2018 | 19:00 | 1.3 | WNW |
| 10-Jun-2018 | 20:00 | 2.4 | WNW |
| 10-Jun-2018 | 21:00 | 1.2 | W   |
| 10-Jun-2018 | 22:00 | 2.1 | SSW |
| 10-Jun-2018 | 23:00 | 1.6 | SW  |
| 11-Jun-2018 | 00:00 | 1.4 | SW  |
| 11-Jun-2018 | 01:00 | 1.5 | WNW |
| 11-Jun-2018 | 02:00 | 2   | WNW |
| 11-Jun-2018 | 03:00 | 1.7 | W   |
| 11-Jun-2018 | 04:00 | 1.5 | SSW |
| 11-Jun-2018 | 05:00 | 1.3 | WSW |
| 11-Jun-2018 | 06:00 | 1.6 | WSW |
| 11-Jun-2018 | 07:00 | 1.6 | WSW |
| 11-Jun-2018 | 08:00 | 1.5 | WSW |
| 11-Jun-2018 | 09:00 | 2.1 | WSW |
| 11-Jun-2018 | 10:00 | 2.1 | WSW |
| 11-Jun-2018 | 11:00 | 2.3 | WNW |
| 11-Jun-2018 | 12:00 | 2.9 | W   |
| 11-Jun-2018 | 13:00 | 2.8 | WSW |
| 11-Jun-2018 | 14:00 | 2.8 | S   |
| 11-Jun-2018 | 15:00 | 2.8 | S   |
| 11-Jun-2018 | 16:00 | 2.7 | S   |
| 11-Jun-2018 | 17:00 | 1.7 | S   |
| 11-Jun-2018 | 18:00 | 1.6 | SW  |
| 11-Jun-2018 | 19:00 | 1.7 | WSW |
| 11-Jun-2018 | 20:00 | 1.6 | SW  |
| 11-Jun-2018 | 21:00 | 1.5 | WNW |
| 11-Jun-2018 | 22:00 | 1.6 | NNE |
| 11-Jun-2018 | 23:00 | 1.5 | N   |
| 12-Jun-2018 | 00:00 | 3.1 | E   |

**APPENDIX C –  
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

**II. Mean Wind Speed and Wind Direction**

|             |       |     |     |
|-------------|-------|-----|-----|
| 12-Jun-2018 | 01:00 | 2.6 | ENE |
| 12-Jun-2018 | 02:00 | 2.1 | ENE |
| 12-Jun-2018 | 03:00 | 2.6 | N   |
| 12-Jun-2018 | 04:00 | 2.3 | WNW |
| 12-Jun-2018 | 05:00 | 2.1 | W   |
| 12-Jun-2018 | 06:00 | 2   | WSW |
| 12-Jun-2018 | 07:00 | 1.9 | WSW |
| 12-Jun-2018 | 08:00 | 1.7 | WSW |
| 12-Jun-2018 | 09:00 | 2.5 | WNW |
| 12-Jun-2018 | 10:00 | 2.9 | WSW |
| 12-Jun-2018 | 11:00 | 3.2 | W   |
| 12-Jun-2018 | 12:00 | 2.1 | WSW |
| 12-Jun-2018 | 13:00 | 3   | SW  |
| 12-Jun-2018 | 14:00 | 2.3 | WNW |
| 12-Jun-2018 | 15:00 | 2.6 | SW  |
| 12-Jun-2018 | 16:00 | 2.6 | SW  |
| 12-Jun-2018 | 17:00 | 2.5 | WNW |
| 12-Jun-2018 | 18:00 | 2.3 | WNW |
| 12-Jun-2018 | 19:00 | 1.8 | SSW |
| 12-Jun-2018 | 20:00 | 1.9 | SW  |
| 12-Jun-2018 | 21:00 | 1.3 | SSW |
| 12-Jun-2018 | 22:00 | 1.2 | WSW |
| 12-Jun-2018 | 23:00 | 1.6 | S   |
| 13-Jun-2018 | 00:00 | 2.4 | SSW |
| 13-Jun-2018 | 01:00 | 1.8 | SSW |
| 13-Jun-2018 | 02:00 | 1.5 | WNW |
| 13-Jun-2018 | 03:00 | 1.2 | WNW |
| 13-Jun-2018 | 04:00 | 1.4 | WNW |
| 13-Jun-2018 | 05:00 | 1.3 | SW  |
| 13-Jun-2018 | 06:00 | 0.9 | WSW |
| 13-Jun-2018 | 07:00 | 1.2 | WSW |
| 13-Jun-2018 | 08:00 | 1.5 | W   |
| 13-Jun-2018 | 09:00 | 2.8 | W   |
| 13-Jun-2018 | 10:00 | 3.9 | S   |
| 13-Jun-2018 | 11:00 | 4.1 | NNE |
| 13-Jun-2018 | 12:00 | 4.7 | SW  |
| 13-Jun-2018 | 13:00 | 4.1 | WSW |
| 13-Jun-2018 | 14:00 | 4.7 | WSW |

**APPENDIX C –  
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

**II. Mean Wind Speed and Wind Direction**

|             |       |     |     |
|-------------|-------|-----|-----|
| 13-Jun-2018 | 15:00 | 4.3 | SW  |
| 13-Jun-2018 | 16:00 | 4.3 | W   |
| 13-Jun-2018 | 17:00 | 3.9 | W   |
| 13-Jun-2018 | 18:00 | 2.8 | SW  |
| 13-Jun-2018 | 19:00 | 1.8 | SSE |
| 13-Jun-2018 | 20:00 | 1.6 | NNE |
| 13-Jun-2018 | 21:00 | 2.4 | WNW |
| 13-Jun-2018 | 22:00 | 2.6 | WSW |
| 13-Jun-2018 | 23:00 | 2   | WSW |
| 14-Jun-2018 | 00:00 | 1.3 | WSW |
| 14-Jun-2018 | 01:00 | 1.2 | WNW |
| 14-Jun-2018 | 02:00 | 1.3 | WNW |
| 14-Jun-2018 | 03:00 | 1.5 | SW  |
| 14-Jun-2018 | 04:00 | 1.5 | WSW |
| 14-Jun-2018 | 05:00 | 1.4 | WSW |
| 14-Jun-2018 | 06:00 | 1.3 | WNW |
| 14-Jun-2018 | 07:00 | 1.3 | WNW |
| 14-Jun-2018 | 08:00 | 1.3 | WSW |
| 14-Jun-2018 | 09:00 | 1.6 | SW  |
| 14-Jun-2018 | 10:00 | 2   | WSW |
| 14-Jun-2018 | 11:00 | 2.1 | WSW |
| 14-Jun-2018 | 12:00 | 2.3 | W   |
| 14-Jun-2018 | 13:00 | 2.7 | WNW |
| 14-Jun-2018 | 14:00 | 2.5 | SW  |
| 14-Jun-2018 | 15:00 | 2.2 | ENE |
| 14-Jun-2018 | 16:00 | 2.3 | ENE |
| 14-Jun-2018 | 17:00 | 2.2 | SSW |
| 14-Jun-2018 | 18:00 | 1.7 | SW  |
| 14-Jun-2018 | 19:00 | 1.3 | SW  |
| 14-Jun-2018 | 20:00 | 1.1 | SW  |
| 14-Jun-2018 | 21:00 | 1.1 | W   |
| 14-Jun-2018 | 22:00 | 1.2 | W   |
| 14-Jun-2018 | 23:00 | 1   | W   |
| 15-Jun-2018 | 00:00 | 1.3 | ENE |
| 15-Jun-2018 | 01:00 | 1   | SSW |
| 15-Jun-2018 | 02:00 | 0.9 | W   |
| 15-Jun-2018 | 03:00 | 1.1 | W   |
| 15-Jun-2018 | 04:00 | 1.3 | SSW |

**APPENDIX C –  
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

**II. Mean Wind Speed and Wind Direction**

|             |       |     |     |
|-------------|-------|-----|-----|
| 15-Jun-2018 | 05:00 | 1.3 | WNW |
| 15-Jun-2018 | 06:00 | 1.3 | WSW |
| 15-Jun-2018 | 07:00 | 1.7 | S   |
| 15-Jun-2018 | 08:00 | 1.6 | S   |
| 15-Jun-2018 | 09:00 | 1.7 | S   |
| 15-Jun-2018 | 10:00 | 2.2 | ENE |
| 15-Jun-2018 | 11:00 | 1.9 | NE  |
| 15-Jun-2018 | 12:00 | 2   | NE  |
| 15-Jun-2018 | 13:00 | 2.7 | ENE |
| 15-Jun-2018 | 14:00 | 2.4 | SW  |
| 15-Jun-2018 | 15:00 | 3.8 | SW  |
| 15-Jun-2018 | 16:00 | 2.9 | WSW |
| 15-Jun-2018 | 17:00 | 2.1 | SW  |
| 15-Jun-2018 | 18:00 | 2.5 | NE  |
| 15-Jun-2018 | 19:00 | 1.8 | NE  |
| 15-Jun-2018 | 20:00 | 1.7 | SSW |
| 15-Jun-2018 | 21:00 | 1.8 | SSW |
| 15-Jun-2018 | 22:00 | 1.9 | SSW |
| 15-Jun-2018 | 23:00 | 1.6 | SW  |
| 16-Jun-2018 | 00:00 | 1.7 | SW  |
| 16-Jun-2018 | 01:00 | 1.8 | WSW |
| 16-Jun-2018 | 02:00 | 1.6 | NW  |
| 16-Jun-2018 | 03:00 | 1.3 | NW  |
| 16-Jun-2018 | 04:00 | 2.1 | SW  |
| 16-Jun-2018 | 05:00 | 1.8 | SW  |
| 16-Jun-2018 | 06:00 | 2   | SSE |
| 16-Jun-2018 | 07:00 | 2.2 | SE  |
| 16-Jun-2018 | 08:00 | 1.8 | SE  |
| 16-Jun-2018 | 09:00 | 2.3 | SE  |
| 16-Jun-2018 | 10:00 | 2.1 | SSE |
| 16-Jun-2018 | 11:00 | 2.5 | ESE |
| 16-Jun-2018 | 12:00 | 3   | E   |
| 16-Jun-2018 | 13:00 | 3   | SSE |
| 16-Jun-2018 | 14:00 | 3   | SSE |
| 16-Jun-2018 | 15:00 | 3   | WNW |
| 16-Jun-2018 | 16:00 | 3.2 | SW  |
| 16-Jun-2018 | 17:00 | 3.2 | SW  |
| 16-Jun-2018 | 18:00 | 3.2 | WSW |

**APPENDIX C –  
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

**II. Mean Wind Speed and Wind Direction**

|             |       |     |     |
|-------------|-------|-----|-----|
| 16-Jun-2018 | 19:00 | 2.8 | WNW |
| 16-Jun-2018 | 20:00 | 2.2 | SW  |
| 16-Jun-2018 | 21:00 | 1.7 | W   |
| 16-Jun-2018 | 22:00 | 1.6 | SSW |
| 16-Jun-2018 | 23:00 | 1.6 | SW  |
| 17-Jun-2018 | 00:00 | 1.7 | W   |
| 17-Jun-2018 | 01:00 | 1.7 | SW  |
| 17-Jun-2018 | 02:00 | 1.3 | WNW |
| 17-Jun-2018 | 03:00 | 1.3 | NW  |
| 17-Jun-2018 | 04:00 | 0.8 | W   |
| 17-Jun-2018 | 05:00 | 1.3 | NW  |
| 17-Jun-2018 | 06:00 | 1.8 | SSW |
| 17-Jun-2018 | 07:00 | 1   | SW  |
| 17-Jun-2018 | 08:00 | 1.1 | WSW |
| 17-Jun-2018 | 09:00 | 2.2 | SW  |
| 17-Jun-2018 | 10:00 | 2.4 | SW  |
| 17-Jun-2018 | 11:00 | 3   | WSW |
| 17-Jun-2018 | 12:00 | 2.7 | SW  |
| 17-Jun-2018 | 13:00 | 3.1 | SW  |
| 17-Jun-2018 | 14:00 | 3.3 | SW  |
| 17-Jun-2018 | 15:00 | 2.9 | WSW |
| 17-Jun-2018 | 16:00 | 3.1 | SW  |
| 17-Jun-2018 | 17:00 | 2.5 | SW  |
| 17-Jun-2018 | 18:00 | 2.2 | W   |
| 17-Jun-2018 | 19:00 | 1.6 | WNW |
| 17-Jun-2018 | 20:00 | 1.2 | W   |
| 17-Jun-2018 | 21:00 | 1.1 | WSW |
| 17-Jun-2018 | 22:00 | 1.1 | SSW |
| 17-Jun-2018 | 23:00 | 0.9 | SW  |
| 18-Jun-2018 | 00:00 | 1   | SSW |
| 18-Jun-2018 | 01:00 | 1.1 | W   |
| 18-Jun-2018 | 02:00 | 1   | WNW |
| 18-Jun-2018 | 03:00 | 0.7 | W   |
| 18-Jun-2018 | 04:00 | 0.7 | W   |
| 18-Jun-2018 | 05:00 | 0.8 | W   |
| 18-Jun-2018 | 06:00 | 0.6 | W   |
| 18-Jun-2018 | 07:00 | 0.8 | WNW |
| 18-Jun-2018 | 08:00 | 1   | WNW |



**APPENDIX C –  
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

**II. Mean Wind Speed and Wind Direction**

|             |       |     |     |
|-------------|-------|-----|-----|
| 18-Jun-2018 | 09:00 | 1.8 | SW  |
| 18-Jun-2018 | 10:00 | 2.5 | WSW |
| 18-Jun-2018 | 11:00 | 2.8 | SW  |
| 18-Jun-2018 | 12:00 | 3.2 | W   |
| 18-Jun-2018 | 13:00 | 3.2 | W   |
| 18-Jun-2018 | 14:00 | 2.9 | N   |
| 18-Jun-2018 | 15:00 | 2.8 | WSW |
| 18-Jun-2018 | 16:00 | 2.6 | SSW |
| 18-Jun-2018 | 17:00 | 2   | WSW |
| 18-Jun-2018 | 18:00 | 2.1 | WSW |
| 18-Jun-2018 | 19:00 | 1.7 | WSW |
| 18-Jun-2018 | 20:00 | 1.5 | WSW |
| 18-Jun-2018 | 21:00 | 1.3 | SW  |
| 18-Jun-2018 | 22:00 | 1.4 | SW  |
| 18-Jun-2018 | 23:00 | 1.1 | WSW |
| 19-Jun-2018 | 00:00 | 1.3 | WSW |
| 19-Jun-2018 | 01:00 | 1.1 | SW  |
| 19-Jun-2018 | 02:00 | 1.3 | WSW |
| 19-Jun-2018 | 03:00 | 1.2 | W   |
| 19-Jun-2018 | 04:00 | 1.3 | SW  |
| 19-Jun-2018 | 05:00 | 1.2 | SW  |
| 19-Jun-2018 | 06:00 | 1.4 | SW  |
| 19-Jun-2018 | 07:00 | 1.2 | SW  |
| 19-Jun-2018 | 08:00 | 1.6 | SW  |
| 19-Jun-2018 | 09:00 | 2.1 | SW  |
| 19-Jun-2018 | 10:00 | 2.4 | SW  |
| 19-Jun-2018 | 11:00 | 2.8 | SW  |
| 19-Jun-2018 | 12:00 | 3.1 | WSW |
| 19-Jun-2018 | 13:00 | 2   | SW  |
| 19-Jun-2018 | 14:00 | 2.1 | SW  |
| 19-Jun-2018 | 15:00 | 2.4 | SSW |
| 19-Jun-2018 | 16:00 | 2.1 | SSW |
| 19-Jun-2018 | 17:00 | 2   | S   |
| 19-Jun-2018 | 18:00 | 1.4 | S   |
| 19-Jun-2018 | 19:00 | 1.6 | SSW |
| 19-Jun-2018 | 20:00 | 1.7 | S   |
| 19-Jun-2018 | 21:00 | 1.1 | SSE |
| 19-Jun-2018 | 22:00 | 1.3 | S   |

**APPENDIX C –  
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

**II. Mean Wind Speed and Wind Direction**

|             |       |     |     |
|-------------|-------|-----|-----|
| 19-Jun-2018 | 23:00 | 1.4 | SE  |
| 20-Jun-2018 | 00:00 | 1.4 | SSE |
| 20-Jun-2018 | 01:00 | 1.6 | SSE |
| 20-Jun-2018 | 02:00 | 1.7 | SSE |
| 20-Jun-2018 | 03:00 | 1.5 | SSW |
| 20-Jun-2018 | 04:00 | 1.6 | SE  |
| 20-Jun-2018 | 05:00 | 2   | SE  |
| 20-Jun-2018 | 06:00 | 1.9 | SE  |
| 20-Jun-2018 | 07:00 | 1.6 | SE  |
| 20-Jun-2018 | 08:00 | 1.3 | SSW |
| 20-Jun-2018 | 09:00 | 2.2 | SSW |
| 20-Jun-2018 | 10:00 | 2.3 | SSE |
| 20-Jun-2018 | 11:00 | 2.6 | SSE |
| 20-Jun-2018 | 12:00 | 2.7 | ESE |
| 20-Jun-2018 | 13:00 | 2.8 | NE  |
| 20-Jun-2018 | 14:00 | 2.6 | NE  |
| 20-Jun-2018 | 15:00 | 2.9 | E   |
| 20-Jun-2018 | 16:00 | 2.8 | ESE |
| 20-Jun-2018 | 17:00 | 2.7 | NE  |
| 20-Jun-2018 | 18:00 | 1.7 | ESE |
| 20-Jun-2018 | 19:00 | 1.5 | ESE |
| 20-Jun-2018 | 20:00 | 1.2 | E   |
| 20-Jun-2018 | 21:00 | 1.6 | SW  |
| 20-Jun-2018 | 22:00 | 2.2 | NW  |
| 20-Jun-2018 | 23:00 | 2.1 | NE  |
| 21-Jun-2018 | 00:00 | 1.2 | N   |
| 21-Jun-2018 | 01:00 | 1.8 | NE  |
| 21-Jun-2018 | 02:00 | 1.7 | SE  |
| 21-Jun-2018 | 03:00 | 2.1 | SE  |
| 21-Jun-2018 | 04:00 | 1.8 | SE  |
| 21-Jun-2018 | 05:00 | 2.5 | SE  |
| 21-Jun-2018 | 06:00 | 2   | ENE |
| 21-Jun-2018 | 07:00 | 1.7 | E   |
| 21-Jun-2018 | 08:00 | 1.8 | ESE |
| 21-Jun-2018 | 09:00 | 2.3 | E   |
| 21-Jun-2018 | 10:00 | 3.1 | E   |
| 21-Jun-2018 | 11:00 | 3   | NNE |
| 21-Jun-2018 | 12:00 | 3.6 | N   |

**APPENDIX C –  
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

**II. Mean Wind Speed and Wind Direction**

|             |       |     |     |
|-------------|-------|-----|-----|
| 21-Jun-2018 | 13:00 | 3.6 | SE  |
| 21-Jun-2018 | 14:00 | 3   | SE  |
| 21-Jun-2018 | 15:00 | 2.7 | SE  |
| 21-Jun-2018 | 16:00 | 2.7 | SE  |
| 21-Jun-2018 | 17:00 | 2.8 | SE  |
| 21-Jun-2018 | 18:00 | 2.7 | SE  |
| 21-Jun-2018 | 19:00 | 2.3 | SE  |
| 21-Jun-2018 | 20:00 | 2   | SE  |
| 21-Jun-2018 | 21:00 | 2.2 | ESE |
| 21-Jun-2018 | 22:00 | 2.2 | SSE |
| 21-Jun-2018 | 23:00 | 2.3 | SSE |
| 22-Jun-2018 | 00:00 | 2.2 | SE  |
| 22-Jun-2018 | 01:00 | 2.1 | SSE |
| 22-Jun-2018 | 02:00 | 1.6 | SE  |
| 22-Jun-2018 | 03:00 | 1.9 | SE  |
| 22-Jun-2018 | 04:00 | 1.8 | SSW |
| 22-Jun-2018 | 05:00 | 1.3 | WSW |
| 22-Jun-2018 | 06:00 | 1.7 | WSW |
| 22-Jun-2018 | 07:00 | 1.7 | W   |
| 22-Jun-2018 | 08:00 | 2.1 | SW  |
| 22-Jun-2018 | 09:00 | 2.2 | SW  |
| 22-Jun-2018 | 10:00 | 2.8 | SW  |
| 22-Jun-2018 | 11:00 | 3.1 | WNW |
| 22-Jun-2018 | 12:00 | 3.2 | SW  |
| 22-Jun-2018 | 13:00 | 2.9 | SW  |
| 22-Jun-2018 | 14:00 | 2.8 | SW  |
| 22-Jun-2018 | 15:00 | 2.5 | SSE |
| 22-Jun-2018 | 16:00 | 2.6 | SSE |
| 22-Jun-2018 | 17:00 | 2.3 | SSW |
| 22-Jun-2018 | 18:00 | 2.5 | SW  |
| 22-Jun-2018 | 19:00 | 2.2 | SSW |
| 22-Jun-2018 | 20:00 | 1.9 | W   |
| 22-Jun-2018 | 21:00 | 1.8 | WSW |
| 22-Jun-2018 | 22:00 | 1.3 | WSW |
| 22-Jun-2018 | 23:00 | 1.3 | SSW |
| 23-Jun-2018 | 00:00 | 1.3 | NNW |
| 23-Jun-2018 | 01:00 | 1.2 | WNW |
| 23-Jun-2018 | 02:00 | 1.3 | WNW |

**APPENDIX C –  
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

**II. Mean Wind Speed and Wind Direction**

|             |       |     |     |
|-------------|-------|-----|-----|
| 23-Jun-2018 | 03:00 | 1.3 | WNW |
| 23-Jun-2018 | 04:00 | 1   | W   |
| 23-Jun-2018 | 05:00 | 0.9 | SW  |
| 23-Jun-2018 | 06:00 | 1   | W   |
| 23-Jun-2018 | 07:00 | 1   | WSW |
| 23-Jun-2018 | 08:00 | 1.2 | NNE |
| 23-Jun-2018 | 09:00 | 1.5 | NE  |
| 23-Jun-2018 | 10:00 | 2.5 | W   |
| 23-Jun-2018 | 11:00 | 2.8 | WSW |
| 23-Jun-2018 | 12:00 | 2.8 | WSW |
| 23-Jun-2018 | 13:00 | 2.5 | W   |
| 23-Jun-2018 | 14:00 | 2.6 | W   |
| 23-Jun-2018 | 15:00 | 2.8 | NE  |
| 23-Jun-2018 | 16:00 | 2.5 | NNE |
| 23-Jun-2018 | 17:00 | 1.8 | W   |
| 23-Jun-2018 | 18:00 | 1.3 | W   |
| 23-Jun-2018 | 19:00 | 1.5 | WSW |
| 23-Jun-2018 | 20:00 | 1.1 | W   |
| 23-Jun-2018 | 21:00 | 1.1 | W   |
| 23-Jun-2018 | 22:00 | 0.9 | WNW |
| 23-Jun-2018 | 23:00 | 0.9 | W   |
| 24-Jun-2018 | 00:00 | 0.7 | WSW |
| 24-Jun-2018 | 01:00 | 0.7 | WNW |
| 24-Jun-2018 | 02:00 | 0.7 | WNW |
| 24-Jun-2018 | 03:00 | 0.8 | W   |
| 24-Jun-2018 | 04:00 | 0.9 | W   |
| 24-Jun-2018 | 05:00 | 1.2 | WNW |
| 24-Jun-2018 | 06:00 | 1   | WNW |
| 24-Jun-2018 | 07:00 | 1   | SSW |
| 24-Jun-2018 | 08:00 | 1.3 | SSE |
| 24-Jun-2018 | 09:00 | 2   | SSE |
| 24-Jun-2018 | 10:00 | 2.6 | E   |
| 24-Jun-2018 | 11:00 | 2.7 | ENE |
| 24-Jun-2018 | 12:00 | 2.7 | ESE |
| 24-Jun-2018 | 13:00 | 3   | ESE |
| 24-Jun-2018 | 14:00 | 3.2 | SE  |
| 24-Jun-2018 | 15:00 | 3.3 | SSE |
| 24-Jun-2018 | 16:00 | 3.2 | ESE |

**APPENDIX C –  
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

**II. Mean Wind Speed and Wind Direction**

|             |       |     |     |
|-------------|-------|-----|-----|
| 24-Jun-2018 | 17:00 | 3.2 | SSE |
| 24-Jun-2018 | 18:00 | 2.6 | ESE |
| 24-Jun-2018 | 19:00 | 2.4 | SSE |
| 24-Jun-2018 | 20:00 | 2.1 | SSE |
| 24-Jun-2018 | 21:00 | 2.5 | SSE |
| 24-Jun-2018 | 22:00 | 2.9 | SSE |
| 24-Jun-2018 | 23:00 | 2.7 | ESE |
| 25-Jun-2018 | 00:00 | 2.1 | ESE |
| 25-Jun-2018 | 01:00 | 2.3 | ESE |
| 25-Jun-2018 | 02:00 | 2.2 | ESE |
| 25-Jun-2018 | 03:00 | 1.8 | S   |
| 25-Jun-2018 | 04:00 | 1.8 | SSE |
| 25-Jun-2018 | 05:00 | 1.8 | SSE |
| 25-Jun-2018 | 06:00 | 1.7 | ENE |
| 25-Jun-2018 | 07:00 | 1.5 | ENE |
| 25-Jun-2018 | 08:00 | 1.6 | ENE |
| 25-Jun-2018 | 09:00 | 2.2 | NE  |
| 25-Jun-2018 | 10:00 | 2.5 | NNE |
| 25-Jun-2018 | 11:00 | 2.8 | N   |
| 25-Jun-2018 | 12:00 | 3.3 | N   |
| 25-Jun-2018 | 13:00 | 3.4 | SE  |
| 25-Jun-2018 | 14:00 | 4   | SE  |
| 25-Jun-2018 | 15:00 | 3.7 | ESE |
| 25-Jun-2018 | 16:00 | 3.7 | SSW |
| 25-Jun-2018 | 17:00 | 2.9 | N   |
| 25-Jun-2018 | 18:00 | 2.9 | NE  |
| 25-Jun-2018 | 19:00 | 2.7 | ENE |
| 25-Jun-2018 | 20:00 | 2.7 | ENE |
| 25-Jun-2018 | 21:00 | 2.6 | ENE |
| 25-Jun-2018 | 22:00 | 2.2 | NE  |
| 25-Jun-2018 | 23:00 | 2.5 | SSW |
| 26-Jun-2018 | 00:00 | 1.7 | SW  |
| 26-Jun-2018 | 01:00 | 1.5 | SSW |
| 26-Jun-2018 | 02:00 | 1.8 | SSW |
| 26-Jun-2018 | 03:00 | 1.3 | SSW |
| 26-Jun-2018 | 04:00 | 0.7 | WSW |
| 26-Jun-2018 | 05:00 | 1   | SSW |
| 26-Jun-2018 | 06:00 | 1.1 | SW  |

**APPENDIX C –  
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

**II. Mean Wind Speed and Wind Direction**

|             |       |     |     |
|-------------|-------|-----|-----|
| 26-Jun-2018 | 07:00 | 1.5 | SSW |
| 26-Jun-2018 | 08:00 | 2.1 | SW  |
| 26-Jun-2018 | 09:00 | 2.7 | SW  |
| 26-Jun-2018 | 10:00 | 2.9 | WSW |
| 26-Jun-2018 | 11:00 | 3.1 | WNW |
| 26-Jun-2018 | 12:00 | 3.5 | SSW |
| 26-Jun-2018 | 13:00 | 4.2 | WNW |
| 26-Jun-2018 | 14:00 | 4   | W   |
| 26-Jun-2018 | 15:00 | 3.9 | W   |
| 26-Jun-2018 | 16:00 | 3.7 | NNW |
| 26-Jun-2018 | 17:00 | 3.3 | N   |
| 26-Jun-2018 | 18:00 | 3   | W   |
| 26-Jun-2018 | 19:00 | 2.8 | W   |
| 26-Jun-2018 | 20:00 | 2.4 | SSW |
| 26-Jun-2018 | 21:00 | 2.7 | SW  |
| 26-Jun-2018 | 22:00 | 2.4 | SW  |
| 26-Jun-2018 | 23:00 | 2.7 | SW  |
| 27-Jun-2018 | 00:00 | 2.9 | SW  |
| 27-Jun-2018 | 01:00 | 2.3 | W   |
| 27-Jun-2018 | 02:00 | 2.7 | W   |
| 27-Jun-2018 | 03:00 | 2.3 | W   |
| 27-Jun-2018 | 04:00 | 2.1 | WNW |
| 27-Jun-2018 | 05:00 | 2.1 | WNW |
| 27-Jun-2018 | 06:00 | 2   | W   |
| 27-Jun-2018 | 07:00 | 2.1 | NW  |
| 27-Jun-2018 | 08:00 | 2   | WNW |
| 27-Jun-2018 | 09:00 | 2.6 | NW  |
| 27-Jun-2018 | 10:00 | 2.8 | WNW |
| 27-Jun-2018 | 11:00 | 2.9 | WNW |
| 27-Jun-2018 | 12:00 | 3.5 | WNW |
| 27-Jun-2018 | 13:00 | 3.2 | NW  |
| 27-Jun-2018 | 14:00 | 3   | WNW |
| 27-Jun-2018 | 15:00 | 2.6 | W   |
| 27-Jun-2018 | 16:00 | 2.3 | WNW |
| 27-Jun-2018 | 17:00 | 2.3 | W   |
| 27-Jun-2018 | 18:00 | 1.5 | NW  |
| 27-Jun-2018 | 19:00 | 1.3 | W   |
| 27-Jun-2018 | 20:00 | 1.1 | WSW |

**APPENDIX C –  
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

**II. Mean Wind Speed and Wind Direction**

|             |       |     |     |
|-------------|-------|-----|-----|
| 27-Jun-2018 | 21:00 | 1.3 | NW  |
| 27-Jun-2018 | 22:00 | 1.3 | NW  |
| 27-Jun-2018 | 23:00 | 2.3 | NW  |
| 28-Jun-2018 | 00:00 | 2.3 | W   |
| 28-Jun-2018 | 01:00 | 2   | W   |
| 28-Jun-2018 | 02:00 | 2.2 | WSW |
| 28-Jun-2018 | 03:00 | 2.5 | SW  |
| 28-Jun-2018 | 04:00 | 2.3 | SSW |
| 28-Jun-2018 | 05:00 | 2.6 | W   |
| 28-Jun-2018 | 06:00 | 2.2 | W   |
| 28-Jun-2018 | 07:00 | 2.6 | W   |
| 28-Jun-2018 | 08:00 | 2.3 | WNW |
| 28-Jun-2018 | 09:00 | 3.1 | W   |
| 28-Jun-2018 | 10:00 | 3.3 | W   |
| 28-Jun-2018 | 11:00 | 3.3 | W   |
| 28-Jun-2018 | 12:00 | 3.3 | W   |
| 28-Jun-2018 | 13:00 | 3.4 | WSW |
| 28-Jun-2018 | 14:00 | 2.7 | WSW |
| 28-Jun-2018 | 15:00 | 2.8 | NW  |
| 28-Jun-2018 | 16:00 | 2.8 | WNW |
| 28-Jun-2018 | 17:00 | 3   | WNW |
| 28-Jun-2018 | 18:00 | 2.7 | W   |
| 28-Jun-2018 | 19:00 | 2   | SW  |
| 28-Jun-2018 | 20:00 | 2.5 | SSW |
| 28-Jun-2018 | 21:00 | 2.6 | SSW |
| 28-Jun-2018 | 22:00 | 2.2 | SSW |
| 28-Jun-2018 | 23:00 | 2   | WSW |
| 29-Jun-2018 | 00:00 | 2   | SSW |
| 29-Jun-2018 | 01:00 | 2.7 | W   |
| 29-Jun-2018 | 02:00 | 3   | WNW |
| 29-Jun-2018 | 03:00 | 3.5 | NW  |
| 29-Jun-2018 | 04:00 | 2.6 | WSW |
| 29-Jun-2018 | 05:00 | 2.5 | W   |
| 29-Jun-2018 | 06:00 | 2.5 | SW  |
| 29-Jun-2018 | 07:00 | 2.5 | SW  |
| 29-Jun-2018 | 08:00 | 2.5 | SSE |
| 29-Jun-2018 | 09:00 | 3.2 | SSE |
| 29-Jun-2018 | 10:00 | 4.3 | SSE |

**APPENDIX C –  
WEATHER CONDITIONS DURING THE MONITORING PERIOD**

**II. Mean Wind Speed and Wind Direction**

|             |       |     |     |
|-------------|-------|-----|-----|
| 29-Jun-2018 | 11:00 | 4.4 | ESE |
| 29-Jun-2018 | 12:00 | 4.5 | SE  |
| 29-Jun-2018 | 13:00 | 4.4 | SE  |
| 29-Jun-2018 | 14:00 | 4   | SSE |
| 29-Jun-2018 | 15:00 | 3.7 | ESE |
| 29-Jun-2018 | 16:00 | 4   | SSE |
| 29-Jun-2018 | 17:00 | 3.5 | ENE |
| 29-Jun-2018 | 18:00 | 2.9 | ENE |
| 29-Jun-2018 | 19:00 | 3.1 | ESE |
| 29-Jun-2018 | 20:00 | 3   | E   |
| 29-Jun-2018 | 21:00 | 2.8 | E   |
| 29-Jun-2018 | 22:00 | 3.6 | SE  |
| 29-Jun-2018 | 23:00 | 2.9 | ESE |
| 30-Jun-2018 | 00:00 | 2.6 | ESE |
| 30-Jun-2018 | 01:00 | 3.1 | SSE |
| 30-Jun-2018 | 02:00 | 2.5 | SSE |
| 30-Jun-2018 | 03:00 | 2.8 | SE  |
| 30-Jun-2018 | 04:00 | 3.5 | ESE |
| 30-Jun-2018 | 05:00 | 3.7 | ESE |
| 30-Jun-2018 | 06:00 | 3.3 | ESE |
| 30-Jun-2018 | 07:00 | 3   | SE  |
| 30-Jun-2018 | 08:00 | 3.5 | ESE |
| 30-Jun-2018 | 09:00 | 3.6 | ESE |
| 30-Jun-2018 | 10:00 | 4   | ESE |
| 30-Jun-2018 | 11:00 | 4.3 | SSE |
| 30-Jun-2018 | 12:00 | 4   | SSE |
| 30-Jun-2018 | 13:00 | 4.1 | SE  |
| 30-Jun-2018 | 14:00 | 2.3 | SE  |
| 30-Jun-2018 | 15:00 | 2.4 | SE  |
| 30-Jun-2018 | 16:00 | 2   | SE  |
| 30-Jun-2018 | 17:00 | 2.5 | SE  |
| 30-Jun-2018 | 18:00 | 2.7 | ESE |
| 30-Jun-2018 | 19:00 | 2.6 | SE  |
| 30-Jun-2018 | 20:00 | 2.4 | ESE |
| 30-Jun-2018 | 21:00 | 2.4 | SE  |
| 30-Jun-2018 | 22:00 | 2.1 | SE  |
| 30-Jun-2018 | 23:00 | 2.5 | ESE |



---

**APPENDIX D  
ENVIRONMENTAL MONITORING  
SCHEDULES**

---

**Agreement No. CE/59/2015 (EP)**  
**Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction**  
**Impact Air Quality and Noise Monitoring Schedule (June 2018)**

| Sunday  | Monday  | Tuesday   | Wednesday   | Thursday  | Friday  | Saturday |
|---|---|---|---|---|---|----------|
|   |   |   |   |   | 1-Jun<br>Noise [Evening time (19:00-23:00)]<br>[CM1, CM2, CM3, CM4]   | 2-Jun    |
| 3-Jun   | 4-Jun   | 5-Jun   | 6-Jun   | 7-Jun   | 8-Jun   | 9-Jun    |
|   | 24 hr TSP   | 1 hr TSP X3<br>[AM1, AM2, AM3, AM4]<br>Noise [Daytime (07:00-19:00)]<br>[CM1, CM2, CM3, CM4, CM5]   | 1 hr TSP X3<br>[AM5(A), AM6(A)]<br>Noise [Daytime (07:00-19:00)]<br>[CM6(A), CM7(A), CM8(A)]  |   | 24 hr TSP<br>Noise [Evening time (19:00-23:00)]<br>[CM1, CM2, CM3, CM4]<br>Noise [Night-time (23:00-07:00)]<br>[CM1, CM2, CM3, CM4] |          |
| 10-Jun  | 11-Jun  | 12-Jun  | 13-Jun  | 14-Jun  | 15-Jun  | 16-Jun   |
| Noise [Daytime (07:00-19:00)]<br>[CM1, CM2, CM3, CM4] | 1 hr TSP X3<br>[AM1, AM2, AM3, AM4]<br>Noise [Daytime (07:00-19:00)]<br>[CM1, CM2, CM4] | 1 hr TSP X3<br>[AM5(A), AM6(A)]<br>Noise [Daytime (07:00-19:00)]<br>[CM6(A), CM7(A), CM8(A)]<br>[CM3, CM5]  | 24 hr TSP   | 1 hr TSP X3<br>[AM1, AM2, AM3, AM4]<br>Noise [Evening time (19:00-23:00)]<br>[CM1, CM2, CM3, CM4]<br>Noise [Night-time (23:00-07:00)]<br>[CM1, CM2, CM3, CM4] | 1 hr TSP X3<br>[AM5(A), AM6(A)]   |          |
| 17-Jun  | 18-Jun  | 19-Jun  | 20-Jun  | 21-Jun  | 22-Jun  | 23-Jun   |
| Noise [Daytime (07:00-19:00)]<br>[CM1, CM2, CM3, CM4] |   | 24 hr TSP   | 1 hr TSP X3<br>[AM1, AM2, AM3, AM4]<br>Noise [Daytime (07:00-19:00)]<br>[CM1, CM2, CM3, CM4, CM5]<br>Noise [Evening time (19:00-23:00)]<br>[CM1, CM2, CM3, CM4]<br>Noise [Night-time (23:00-07:00)]<br>[CM1, CM2, CM3, CM4] | 1 hr TSP X3<br>[AM5(A), AM6(A)]<br>Noise [Daytime (07:00-19:00)]<br>[CM6(A), CM7(A), CM8(A)]  |   |          |
| 24-Jun  | 25-Jun  | 26-Jun  | 27-Jun  | 28-Jun  | 29-Jun  | 30-Jun   |
| Noise [Daytime (07:00-19:00)]<br>[CM1, CM2, CM3, CM4] | 24 hr TSP   | 1 hr TSP X3<br>[AM1, AM2, AM3, AM4]<br>Noise [Daytime (07:00-19:00)]<br>[CM1, CM2, CM3, CM4, CM5]<br>Noise [Evening time (19:00-23:00)]<br>[CM1, CM2, CM3, CM4]<br>Noise [Night-time (23:00-07:00)]<br>[CM1, CM2, CM3, CM4] | 1 hr TSP X3<br>[AM5(A), AM6(A)]<br>Noise [Daytime (07:00-19:00)]<br>[CM6(A), CM7(A), CM8(A)]  | 24 hr TSP   | 1 hr TSP X3<br>[AM1, AM2, AM3, AM4]   |          |

**Air Quality Monitoring Station**

AM1 - Tin Hau Temple  
 AM2 - Sai Tso Wan Recreation Ground  
 AM3 - Yau Lai Estate Bik Lai House  
 AM4<sup>(1)</sup> - Sitting-out Area at Cha Kwo Ling Village  
 AM4(A)<sup>(2)</sup> - Cha Kwo Ling Public Cargo Working Area Administrative Office  
 AM5(A) - Tseung Kwan O DSD Desilting Compound  
 AM6(A) - Park Central, L1/F Open Space Area

**Noise Monitoring Station**

CM1 - Nga Lai House, Yau Lai Estate Phase 1, Yau Tong  
 CM2 - Bik Lai House, Yau Lai Estate Phase 1, Yau Tong  
 CM3 - Block S, Yau Lai Estate Phase 5, Yau Tong  
 CM4 - Tin Hau Temple, Cha Kwo Ling  
 CM5 - CCC Kei Faat Primary School, Yau Tong  
 CM6(A) - Site Boundary of Contract No. NE/2015/02 near Tower 1, Ocean Shores  
 CM7(A) - Site Boundary of Contract No. NE/2015/02 near Tower 7, Ocean Shores  
 CM8(A) - Park Central, L1/F Open Space Area

Note (1) For 1-hour TSP monitoring; (2) For 24-hour TSP monitoring

**Agreement No. CE/59/2015 (EP)**  
**Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction**  
**Impact Water Quality Monitoring Schedule (June 2018)**

| Sunday        | Monday                           | Tuesday                          | Wednesday                        | Thursday                         | Friday                           | Saturday                         |
|---------------|----------------------------------|----------------------------------|----------------------------------|----------------------------------|----------------------------------|----------------------------------|
|               |                                  |                                  |                                  |                                  | 1-Jun                            | 2-Jun                            |
|               |                                  |                                  |                                  |                                  | Mid-Flood 07:08<br>Mid-Ebb 13:59 |                                  |
| <b>3-Jun</b>  | 4-Jun                            | 5-Jun                            | 6-Jun                            | 7-Jun                            | 8-Jun                            | 9-Jun                            |
|               | Mid-Flood 08:22<br>Mid-Ebb 15:45 |                                  | Mid-Flood 10:16<br>Mid-Ebb 17:24 |                                  |                                  | Mid-Ebb 09:14<br>Mid-Flood 14:42 |
| <b>10-Jun</b> | 11-Jun                           | 12-Jun                           | 13-Jun                           | 14-Jun                           | 15-Jun                           | 16-Jun                           |
|               | Mid-Ebb 10:33<br>Mid-Flood 16:52 |                                  | Mid-Ebb 11:55<br>Mid-Flood 18:38 |                                  | Mid-Ebb 13:29<br>Mid-Flood 20:26 |                                  |
| <b>17-Jun</b> | <b>18-Jun</b>                    | 19-Jun                           | 20-Jun                           | 21-Jun                           | 22-Jun                           | 23-Jun                           |
|               |                                  | Mid-Flood 10:02<br>Mid-Ebb 17:06 |                                  | Mid-Flood 12:39<br>Mid-Ebb 19:15 |                                  | Mid-Ebb 09:21<br>Mid-Flood 15:31 |
| <b>24-Jun</b> | 25-Jun                           | 26-Jun                           | 27-Jun                           | 28-Jun                           | 29-Jun                           | 30-Jun                           |
|               | Mid-Ebb 10:50<br>Mid-Flood 17:31 |                                  | Mid-Ebb 12:00<br>Mid-Flood 19:04 |                                  | Mid-Ebb 13:08<br>Mid-Flood 20:21 |                                  |

Monitoring Station:

C1, C2, G1, G2, G3, G4, M1, M2, M3, M4, M5, M6

**Agreement No. CE/59/2015 (EP)**  
**Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction**  
**Impact Water Quality Monitoring Schedule in Temporary Marine Embayment (June 2018)**

| Sunday        | Monday        | Tuesday                          | Wednesday                        | Thursday | Friday | Saturday |
|---------------|---------------|----------------------------------|----------------------------------|----------|--------|----------|
|               |               |                                  |                                  |          | 1-Jun  | 2-Jun    |
|               |               |                                  |                                  |          |        |          |
| <b>3-Jun</b>  | 4-Jun         | 5-Jun                            | 6-Jun                            | 7-Jun    | 8-Jun  | 9-Jun    |
|               |               | Mid-Flood 09:08<br>Mid-Ebb 16:33 |                                  |          |        |          |
| <b>10-Jun</b> | 11-Jun        | 12-Jun                           | 13-Jun                           | 14-Jun   | 15-Jun | 16-Jun   |
|               |               | Mid-Ebb 11:13<br>Mid-Flood 17:46 |                                  |          |        |          |
| <b>17-Jun</b> | <b>18-Jun</b> | 19-Jun                           | 20-Jun                           | 21-Jun   | 22-Jun | 23-Jun   |
|               |               |                                  | Mid-Flood 10:02<br>Mid-Ebb 17:06 |          |        |          |
| <b>24-Jun</b> | 25-Jun        | 26-Jun                           | 27-Jun                           | 28-Jun   | 29-Jun | 30-Jun   |
|               |               | Mid-Ebb 11:26<br>Mid-Flood 18:20 |                                  |          |        |          |

Monitoring Station:

W1

**Agreement No. CE/59/2015 (EP)**  
**Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction**  
**Impact Groundwater Quality Monitoring Schedule (June 2018)**

| Sunday        | Monday        | Tuesday                           | Wednesday                         | Thursday | Friday | Saturday |
|---------------|---------------|-----------------------------------|-----------------------------------|----------|--------|----------|
|               |               |                                   |                                   |          | 1-Jun  | 2-Jun    |
|               |               |                                   |                                   |          |        |          |
| <b>3-Jun</b>  | 4-Jun         | 5-Jun                             | 6-Jun                             | 7-Jun    | 8-Jun  | 9-Jun    |
|               |               | Groundwater Quality<br>Monitoring |                                   |          |        |          |
| <b>10-Jun</b> | 11-Jun        | 12-Jun                            | 13-Jun                            | 14-Jun   | 15-Jun | 16-Jun   |
|               |               |                                   |                                   |          |        |          |
| <b>17-Jun</b> | <b>18-Jun</b> | 19-Jun                            | 20-Jun                            | 21-Jun   | 22-Jun | 23-Jun   |
|               |               |                                   | Groundwater Quality<br>Monitoring |          |        |          |
| <b>24-Jun</b> | 25-Jun        | 26-Jun                            | 27-Jun                            | 28-Jun   | 29-Jun | 30-Jun   |
|               |               |                                   |                                   |          |        |          |

Monitoring Location:

Stream 1, Stream 2, Stream 3

**Agreement No. CE/59/2015 (EP)**  
**Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction**  
**Tentative Impact Air Quality and Noise Monitoring Schedule (July 2018)**

| Sunday  | Monday  | Tuesday  | Wednesday  | Thursday   | Friday   | Saturday |
|---|---|--|--|--|--|----------|
| 1-Jul   | 2-Jul   | 3-Jul  | 4-Jul  | 5-Jul  | 6-Jul  | 7-Jul    |
| <p>Noise [Daytime (07:00-19:00)]<br/>[CM1, CM2, CM3, CM4]</p> |   | <p>1 hr TSP X3<br/>[AM5(A), AM6(A)]</p> <p>Noise [Daytime (07:00-19:00)]<br/>[CM6(A), CM7(A), CM8(A)]</p>  | <p>24 hr TSP</p> <p>Noise [Daytime (07:00-19:00)]<br/>[CM3, CM5]</p>                                 | <p>1 hr TSP X3<br/>[AM1, AM2, AM3, AM4]</p> <p>Noise [Daytime (07:00-19:00)]<br/>[CM1, CM2, CM4]</p> <p>Noise [Evening time (19:00-23:00)]<br/>[CM1, CM2, CM3, CM4]</p> <p>Noise [Night-time (23:00-07:00)]<br/>[CM1, CM2, CM3, CM4]</p> | <p>1 hr TSP X3<br/>[AM5(A), AM6(A)]</p>  |          |
| 8-Jul   | 9-Jul   | 10-Jul   | 11-Jul   | 12-Jul   | 13-Jul   | 14-Jul   |
| <p>Noise [Daytime (07:00-19:00)]<br/>[CM1, CM2, CM3, CM4]</p> |   | <p>24 hr TSP</p> <p>Noise [Daytime (07:00-19:00)]<br/>[CM3, CM5]</p>   | <p>1 hr TSP X3<br/>[AM1, AM2, AM3, AM4]</p> <p>Noise [Daytime (07:00-19:00)]<br/>[CM1, CM2, CM4]</p> | <p>1 hr TSP X3<br/>[AM5(A), AM6(A)]</p> <p>Noise [Daytime (07:00-19:00)]<br/>[CM6(A), CM7(A), CM8(A)]</p>  | <p>Noise [Evening time (19:00-23:00)]<br/>[CM1, CM2, CM3, CM4]</p> <p>Noise [Night-time (23:00-07:00)]<br/>[CM1, CM2, CM3, CM4]</p>  |          |
| 15-Jul  | 16-Jul  | 17-Jul   | 18-Jul   | 19-Jul   | 20-Jul   | 21-Jul   |
| <p>Noise [Daytime (07:00-19:00)]<br/>[CM1, CM2, CM3, CM4]</p> | <p>24 hr TSP</p>  | <p>1 hr TSP X3<br/>[AM1, AM2, AM3, AM4]<br/>[AM5(A), AM6(A)]</p> <p>Noise [Daytime (07:00-19:00)]<br/>[CM1, CM2, CM4]<br/>[CM6(A), CM7(A), CM8(A)]</p> |  | <p>Noise [Daytime (07:00-19:00)]<br/>[CM3, CM5]</p>  | <p>24 hr TSP</p> <p>Noise [Evening time (19:00-23:00)]<br/>[CM1, CM2, CM3, CM4]</p> <p>Noise [Night-time (23:00-07:00)]<br/>[CM1, CM2, CM3, CM4]</p>   |          |
| 22-Jul  | 23-Jul  | 24-Jul   | 25-Jul   | 26-Jul   | 27-Jul   | 28-Jul   |
| <p>Noise [Daytime (07:00-19:00)]<br/>[CM1, CM2, CM3, CM4]</p> | <p>1 hr TSP X3<br/>[AM1, AM2, AM3, AM4]<br/>[AM5(A), AM6(A)]</p> <p>Noise [Daytime (07:00-19:00)]<br/>[CM1, CM2, CM4]</p> | <p>Noise [Daytime (07:00-19:00)]<br/>[CM3, CM5]</p>  |  | <p>24 hr TSP</p>   | <p>1 hr TSP X3<br/>[AM1, AM2, AM3, AM4]<br/>[AM5(A), AM6(A)]</p> <p>Noise [Daytime (07:00-19:00)]<br/>[CM6(A), CM7(A), CM8(A)]</p> <p>Noise [Evening time (19:00-23:00)]<br/>[CM1, CM2, CM3, CM4]</p> <p>Noise [Night-time (23:00-07:00)]<br/>[CM1, CM2, CM3, CM4]</p> |          |
| 29-Jul  | 30-Jul  | 31-Jul   |  |  |  |          |
| <p>Noise [Daytime (07:00-19:00)]<br/>[CM1, CM2, CM3, CM4]</p> |   | <p>Noise [Daytime (07:00-19:00)]<br/>[CM3, CM5]</p>  |  |  |  |          |

The schedule may be changed due to unforeseen circumstances (adverse weather, etc)

**Air Quality Monitoring Station**

AM1 - Tin Hau Temple  
AM2 - Sai Tso Wan Recreation Ground  
AM3 - Yau Lai Estate Bik Lai House  
AM4<sup>(1)</sup> - Sitting-out Area at Cha Kwo Ling Village  
AM4(A)<sup>(2)</sup> - Cha Kwo Ling Public Cargo Working Area Administrative Office  
AM5(A) - Tseung Kwan O DSD Desilting Compound  
AM6(A) - Park Central, L1/F Open Space Area

**Noise Monitoring Station**

CM1 - Nga Lai House, Yau Lai Estate Phase 1, Yau Tong  
CM2 - Bik Lai House, Yau Lai Estate Phase 1, Yau Tong  
CM3 - Block S, Yau Lai Estate Phase 5, Yau Tong  
CM4 - Tin Hau Temple, Cha Kwo Ling  
CM5 - CCC Kei Faat Primary School, Yau Tong  
CM6(A) - Site Boundary of Contract No. NE/2015/02 near Tower 1, Ocean Shores  
CM7(A) - Site Boundary of Contract No. NE/2015/02 near Tower 7, Ocean Shores  
CM8(A) - Park Central, L1/F Open Space Area

Note (1) For 1-hour TSP monitoring; (2) For 24-hour TSP monitoring

**Agreement No. CE/59/2015 (EP)**  
**Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction**  
**Tentative Impact Water Quality Monitoring Schedule (July 2018)**

| Sunday        | Monday                          | Tuesday                         | Wednesday                        | Thursday                         | Friday                           | Saturday                        |
|---------------|---------------------------------|---------------------------------|----------------------------------|----------------------------------|----------------------------------|---------------------------------|
| <b>1-Jul</b>  | <b>2-Jul</b>                    | 3-Jul                           | 4-Jul                            | 5-Jul                            | 6-Jul                            | 7-Jul                           |
|               |                                 | Mid-Flood 8:27<br>Mid-Ebb 15:21 |                                  | Mid-Flood 10:04<br>Mid-Ebb 16:43 |                                  | Mid-Ebb 7:27<br>Mid-Flood 12:57 |
| <b>8-Jul</b>  | 9-Jul                           | 10-Jul                          | 11-Jul                           | 12-Jul                           | 13-Jul                           | 14-Jul                          |
|               | Mid-Ebb 9:17<br>Mid-Flood 15:36 |                                 | Mid-Ebb 10:51<br>Mid-Flood 17:42 |                                  | Mid-Ebb 12:28<br>Mid-Flood 19:29 |                                 |
| <b>15-Jul</b> | 16-Jul                          | 17-Jul                          | 18-Jul                           | 19-Jul                           | 20-Jul                           | 21-Jul                          |
|               | Mid-Flood 8:04<br>Mid-Ebb 14:56 |                                 | Mid-Flood 9:54<br>Mid-Ebb 16:36  |                                  | Mid-Flood 12:18<br>Mid-Ebb 18:33 |                                 |
| <b>22-Jul</b> | 23-Jul                          | 24-Jul                          | 25-Jul                           | 26-Jul                           | 27-Jul                           | 28-Jul                          |
|               | Mid-Ebb 9:55<br>Mid-Flood 16:46 |                                 | Mid-Ebb 11:10<br>Mid-Flood 18:21 |                                  | Mid-Ebb 12:16<br>Mid-Flood 19:30 |                                 |
| <b>29-Jul</b> | 30-Jul                          | 31-Jul                          |                                  |                                  |                                  |                                 |
|               | Mid-Flood 7:06<br>Mid-Ebb 13:52 |                                 |                                  |                                  |                                  |                                 |

The schedule may be changed due to unforeseen circumstances (adverse weather, etc)

Monitoring Station:

C1, C2, G1, G2, G3, G4, M1, M2, M3, M4, M5, M6

**Agreement No. CE/59/2015 (EP)**  
**Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction**  
**Tentative Impact Water Quality Monitoring Schedule in Temporary Marine Embayment (July 2018)**

| Sunday        | Monday       | Tuesday                          | Wednesday                       | Thursday                         | Friday | Saturday |
|---------------|--------------|----------------------------------|---------------------------------|----------------------------------|--------|----------|
| <b>1-Jul</b>  | <b>2-Jul</b> | 3-Jul                            | 4-Jul                           | 5-Jul                            | 6-Jul  | 7-Jul    |
|               |              |                                  | Mid-Flood 9:12<br>Mid-Ebb 16:00 |                                  |        |          |
| <b>8-Jul</b>  | 9-Jul        | 10-Jul                           | 11-Jul                          | 12-Jul                           | 13-Jul | 14-Jul   |
|               |              | Mid-Ebb 10:05<br>Mid-Flood 16:43 |                                 |                                  |        |          |
| <b>15-Jul</b> | 16-Jul       | 17-Jul                           | 18-Jul                          | 19-Jul                           | 20-Jul | 21-Jul   |
|               |              |                                  |                                 | Mid-Flood 11:00<br>Mid-Ebb 17:33 |        |          |
| <b>22-Jul</b> | 23-Jul       | 24-Jul                           | 25-Jul                          | 26-Jul                           | 27-Jul | 28-Jul   |
|               |              | Mid-Flood 10:36<br>Mid-Ebb 17:40 |                                 |                                  |        |          |
| <b>29-Jul</b> | 30-Jul       | 31-Jul                           |                                 |                                  |        |          |
|               |              | Mid-Flood 7:45<br>Mid-Ebb 14:25  |                                 |                                  |        |          |

The schedule may be changed due to unforeseen circumstances (adverse weather, etc)

Monitoring Station:

W1



**Agreement No. CE/59/2015 (EP)**  
**Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction**  
**Tentative Impact Groundwater Quality Monitoring Schedule (July 2018)**

| Sunday | Monday | Tuesday                        | Wednesday                      | Thursday                       | Friday | Saturday |
|--------|--------|--------------------------------|--------------------------------|--------------------------------|--------|----------|
| 1-Jul  | 2-Jul  | 3-Jul                          | 4-Jul                          | 5-Jul                          | 6-Jul  | 7-Jul    |
|        |        |                                | Groundwater Quality Monitoring |                                |        |          |
| 8-Jul  | 9-Jul  | 10-Jul                         | 11-Jul                         | 12-Jul                         | 13-Jul | 14-Jul   |
|        |        |                                |                                |                                |        |          |
| 15-Jul | 16-Jul | 17-Jul                         | 18-Jul                         | 19-Jul                         | 20-Jul | 21-Jul   |
|        |        |                                |                                | Groundwater Quality Monitoring |        |          |
| 22-Jul | 23-Jul | 24-Jul                         | 25-Jul                         | 26-Jul                         | 27-Jul | 28-Jul   |
|        |        |                                |                                |                                |        |          |
| 29-Jul | 30-Jul | 31-Jul                         |                                |                                |        |          |
|        |        | Groundwater Quality Monitoring |                                |                                |        |          |

The schedule may be changed due to unforeseen circumstances (adverse weather, etc)

Monitoring Location:

Stream 1, Stream 2, Stream 3

---

**APPENDIX E  
1-HOUR TSP MONITORING RESULTS  
AND GRAPHICAL PRESENTATIONS**

---

## Appendix E - 1-hour TSP Monitoring Results

| Location AM1 - Tin Hau Temple |       |         |  |
|-------------------------------|-------|---------|--|
| Date                          | Time  | Weather | Particulate Concentration ( $\mu\text{g}/\text{m}^3$ ) |
| 5-Jun-18                      | 9:00  | Rainy   | 121.9  |
| 5-Jun-18                      | 10:00 | Rainy   | 126.8  |
| 5-Jun-18                      | 11:00 | Rainy   | 123.8  |
| 11-Jun-18                     | 9:00  | Sunny   | 25.2   |
| 11-Jun-18                     | 10:00 | Sunny   | 28.8   |
| 11-Jun-18                     | 11:00 | Sunny   | 18.0   |
| 14-Jun-18                     | 9:00  | Cloudy  | 244.6  |
| 14-Jun-18                     | 10:00 | Cloudy  | 254.5  |
| 14-Jun-18                     | 11:00 | Cloudy  | 250.8  |
| 20-Jun-18                     | 9:00  | Sunny   | 252.2  |
| 20-Jun-18                     | 10:00 | Sunny   | 231.7  |
| 20-Jun-18                     | 11:00 | Sunny   | 227.6  |
| 26-Jun-18                     | 9:00  | Sunny   | 128.1  |
| 26-Jun-18                     | 10:00 | Sunny   | 146.4  |
| 26-Jun-18                     | 11:00 | Sunny   | 129.1  |
| 29-Jun-18                     | 9:00  | Cloudy  | 111.0  |
| 29-Jun-18                     | 10:00 | Cloudy  | 118.4  |
| 29-Jun-18                     | 11:00 | Cloudy  | 103.3  |
| Average                       |       |         | 146.8  |
| Maximum                       |       |         | 254.5  |
| Minimum                       |       |         | 18.0   |

| Location AM2 - Sai Tso Wan Recreation Ground |       |         |  |
|--|-------|---------|--|
| Date   | Time  | Weather | Particulate Concentration ( $\mu\text{g}/\text{m}^3$ ) |
| 5-Jun-18                                     | 13:00 | Rainy   | 116.0  |
| 5-Jun-18                                     | 14:00 | Rainy   | 114.6  |
| 5-Jun-18                                     | 15:00 | Rainy   | 117.3  |
| 11-Jun-18                                    | 13:00 | Cloudy  | 26.0   |
| 11-Jun-18                                    | 14:00 | Cloudy  | 26.0   |
| 11-Jun-18                                    | 15:00 | Cloudy  | 23.7   |
| 14-Jun-18                                    | 13:00 | Cloudy  | 208.1  |
| 14-Jun-18                                    | 14:00 | Cloudy  | 209.7  |
| 14-Jun-18                                    | 15:00 | Cloudy  | 188.5  |
| 20-Jun-18                                    | 13:00 | Sunny   | 201.9  |
| 20-Jun-18                                    | 14:00 | Sunny   | 185.8  |
| 20-Jun-18                                    | 15:00 | Sunny   | 191.0  |
| 26-Jun-18                                    | 13:00 | Sunny   | 113.6  |
| 26-Jun-18                                    | 14:00 | Sunny   | 120.8  |
| 26-Jun-18                                    | 15:00 | Sunny   | 119.4  |
| 29-Jun-18                                    | 14:30 | Sunny   | 100.0  |
| 29-Jun-18                                    | 15:30 | Sunny   | 98.3   |
| 29-Jun-18                                    | 16:30 | Sunny   | 76.4   |
| Average                                      |       |         | 124.3  |
| Maximum                                      |       |         | 209.7  |
| Minimum                                      |       |         | 23.7   |

## Appendix E - 1-hour TSP Monitoring Results

| Location AM3 - Yau Lai Estate Bik Lai House |       |         |  |
|---|-------|---------|--|
| Date  | Time  | Weather | Particulate Concentration ( $\mu\text{g}/\text{m}^3$ ) |
| 5-Jun-18                                    | 9:00  | Rainy   | 180.1  |
| 5-Jun-18                                    | 10:00 | Rainy   | 179.6  |
| 5-Jun-18                                    | 11:00 | Rainy   | 182.1  |
| 11-Jun-18                                   | 9:00  | Sunny   | 26.0   |
| 11-Jun-18                                   | 10:00 | Sunny   | 24.8   |
| 11-Jun-18                                   | 11:00 | Sunny   | 23.7   |
| 14-Jun-18                                   | 13:00 | Cloudy  | 241.1  |
| 14-Jun-18                                   | 14:00 | Cloudy  | 260.4  |
| 14-Jun-18                                   | 15:00 | Cloudy  | 267.9  |
| 20-Jun-18                                   | 13:00 | Sunny   | 253.4  |
| 20-Jun-18                                   | 14:00 | Sunny   | 245.7  |
| 20-Jun-18                                   | 15:00 | Sunny   | 249.2  |
| 26-Jun-18                                   | 9:00  | Sunny   | 153.9  |
| 26-Jun-18                                   | 10:00 | Sunny   | 161.7  |
| 26-Jun-18                                   | 11:00 | Sunny   | 148.3  |
| 29-Jun-18                                   | 10:00 | Sunny   | 135.6  |
| 29-Jun-18                                   | 11:00 | Sunny   | 173.4  |
| 29-Jun-18                                   | 12:00 | Sunny   | 132.2  |
|   |       | Average | 168.8  |
|   |       | Maximum | 267.9  |
|   |       | Minimum | 23.7   |




| Location AM4 - Sitting-out Area at Cha Kwo Ling Village |       |         |  |
|---|-------|---------|--|
| Date  | Time  | Weather | Particulate Concentration ( $\mu\text{g}/\text{m}^3$ ) |
| 5-Jun-18  | 13:00 | Rainy   | 207.2  |
| 5-Jun-18  | 14:00 | Rainy   | 214.3  |
| 5-Jun-18  | 15:00 | Rainy   | 209.2  |
| 11-Jun-18   | 14:10 | Sunny   | 28.8   |
| 11-Jun-18   | 15:10 | Sunny   | 31.2   |
| 11-Jun-18   | 16:10 | Sunny   | 32.4   |
| 14-Jun-18   | 9:00  | Cloudy  | 244.0  |
| 14-Jun-18   | 10:00 | Cloudy  | 253.3  |
| 14-Jun-18   | 11:00 | Cloudy  | 273.5  |
| 20-Jun-18   | 9:00  | Sunny   | 229.9  |
| 20-Jun-18   | 10:00 | Sunny   | 208.7  |
| 20-Jun-18   | 11:00 | Sunny   | 225.5  |
| 26-Jun-18   | 9:00  | Sunny   | 164.3  |
| 26-Jun-18   | 10:00 | Sunny   | 161.7  |
| 26-Jun-18   | 11:00 | Sunny   | 157.9  |
| 29-Jun-18   | 13:00 | Cloudy  | 113.6  |
| 29-Jun-18   | 14:00 | Cloudy  | 118.1  |
| 29-Jun-18   | 15:00 | Cloudy  | 110.7  |
|   |       | Average | 165.8  |
|   |       | Maximum | 273.5  |
|   |       | Minimum | 28.8   |

## Appendix E - 1-hour TSP Monitoring Results

| Location AM5(A) - Tseung Kwan O DSD Desilting Compound |       |         |  |
|--|-------|---------|--|
| Date   | Time  | Weather | Particulate Concentration ( $\mu\text{g}/\text{m}^3$ ) |
| 6-Jun-18   | 13:00 | Rainy   | 207.6  |
| 6-Jun-18   | 14:00 | Rainy   | 146.2  |
| 6-Jun-18   | 15:00 | Rainy   | 166.8  |
| 12-Jun-18  | 13:00 | Rainy   | 31.2   |
| 12-Jun-18  | 14:00 | Rainy   | 37.2   |
| 12-Jun-18  | 15:00 | Rainy   | 27.6   |
| 15-Jun-18  | 13:00 | Sunny   | 240.5  |
| 15-Jun-18  | 14:00 | Sunny   | 224.9  |
| 15-Jun-18  | 15:00 | Sunny   | 116.7  |
| 21-Jun-18  | 13:00 | Rainy   | 221.9  |
| 21-Jun-18  | 14:00 | Rainy   | 153.4  |
| 21-Jun-18  | 15:00 | Rainy   | 173.2  |
| 27-Jun-18  | 9:00  | Cloudy  | 111.2  |
| 27-Jun-18  | 10:00 | Cloudy  | 114.1  |
| 27-Jun-18  | 11:00 | Cloudy  | 118.1  |
| Average  |       |         | 139.4  |
| Maximum  |       |         | 240.5  |
| Minimum  |       |         | 27.6   |




| Location AM6(A) - Park Central, L1/F Open Space Area |       |         |  |
|--|-------|---------|--|
| Date   | Time  | Weather | Particulate Concentration ( $\mu\text{g}/\text{m}^3$ ) |
| 6-Jun-18   | 9:00  | Rainy   | 225.2  |
| 6-Jun-18   | 10:00 | Rainy   | 194.6  |
| 6-Jun-18   | 11:00 | Rainy   | 200.1  |
| 12-Jun-18  | 9:00  | Rainy   | 21.6   |
| 12-Jun-18  | 10:00 | Rainy   | 22.8   |
| 12-Jun-18  | 11:00 | Rainy   | 22.8   |
| 15-Jun-18  | 9:00  | Sunny   | 116.1  |
| 15-Jun-18  | 10:00 | Sunny   | 153.5  |
| 15-Jun-18  | 11:00 | Sunny   | 112.3  |
| 21-Jun-18  | 9:00  | Rainy   | 153.2  |
| 21-Jun-18  | 10:00 | Rainy   | 167.6  |
| 21-Jun-18  | 11:00 | Rainy   | 184.4  |
| 27-Jun-18  | 14:00 | Cloudy  | 88.1   |
| 27-Jun-18  | 15:00 | Cloudy  | 97.1   |
| 27-Jun-18  | 16:00 | Cloudy  | 103.2  |
| Average  |       |         | 124.2  |
| Maximum  |       |         | 225.2  |
| Minimum  |       |         | 21.6   |

### 1-hr TSP Concentration Levels



|   |   |        |             |          |
|---|---|--------|-------------|----------|
| Title   | Agreement No. CE/59/2015 (EP)   | Scale  | Project     | CINOTECH |
|   | Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction | N.T.S  | No. MA16034 |          |
| Graphical Presentation of 1-hour TSP Monitoring Results |   | Date   | Appendix    |          |
|   |   | Jun-18 | E           |          |

### 1-hr TSP Concentration Levels



|   |   |        |             |          |
|---|---|--------|-------------|----------|
| Title   | Agreement No. CE/59/2015 (EP)   | Scale  | Project     | CINOTECH |
|   | Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction | N.T.S  | No. MA16034 |          |
| Graphical Presentation of 1-hour TSP Monitoring Results |   | Date   | Appendix    |          |
|   |   | Jun-18 | E           |          |

---

---

**APPENDIX F  
24-HOUR TSP MONITORING RESULTS  
AND GRAPHICAL PRESENTATIONS**

---

---



## Appendix F - 24-hour TSP Monitoring Results

### Location AM1 - Tin Hau Temple

| Start Date | Weather Condition | Air Temp. (K) | Atmospheric Pressure, Pa (mmHg) | Filter Weight (g) |        | Particulate Weight (g) | Elapse Time |        | Sampling Time(hrs.) | Flow Rate (m <sup>3</sup> /min.) |       | Av. flow (m <sup>3</sup> /min) | Total vol. (m <sup>3</sup> ) | Conc. (µg/m <sup>3</sup> ) |
|------------|-------------------|---------------|---------------------------------|-------------------|--------|------------------------|-------------|--------|---------------------|----------------------------------|-------|--------------------------------|------------------------------|----------------------------|
|            |                   |               |                                 | Initial           | Final  |                        | Initial     | Final  |                     | Initial                          | Final |                                |                              |                            |
| 4-Jun-18   | Rainy             | 302.0         | 758.5                           | 3.2974            | 3.4368 | 0.1394                 | 3587.0      | 3611.0 | 24.0                | 1.19                             | 1.19  | 1.19                           | 1717.3                       | 81.2                       |
| 8-Jun-18   | Rainy             | 299.1         | 753.7                           | 2.8193            | 2.8537 | 0.0344                 | 3611.0      | 3635.0 | 24.0                | 1.20                             | 1.19  | 1.19                           | 1720.6                       | 20.0                       |
| 13-Jun-18  | Cloudy            | 299.7         | 751.5                           | 2.8743            | 2.9680 | 0.0937                 | 3635.0      | 3659.0 | 24.0                | 1.19                             | 1.19  | 1.19                           | 1715.7                       | 54.6                       |
| 19-Jun-18  | Sunny             | 302.5         | 755.5                           | 2.9744            | 3.1294 | 0.1550                 | 3659.0      | 3683.0 | 24.0                | 1.19                             | 1.19  | 1.19                           | 1711.8                       | 90.5                       |
| 25-Jun-18  | Cloudy            | 300.9         | 759.1                           | 2.9833            | 3.0829 | 0.0996                 | 3683.0      | 3707.0 | 24.0                | 1.20                             | 1.20  | 1.20                           | 1721.7                       | 57.9                       |
| 28-Jun-18  | Cloudy            | 302.3         | 758.8                           | 3.2362            | 3.3640 | 0.1278                 | 3707.0      | 3731.0 | 24.0                | 1.21                             | 1.21  | 1.21                           | 1744.3                       | 73.3                       |
|            |                   |               |                                 |                   |        |                        |             |        |                     |                                  |       |                                | Min                          | 20.0                       |
|            |                   |               |                                 |                   |        |                        |             |        |                     |                                  |       |                                | Max                          | 90.5                       |
|            |                   |               |                                 |                   |        |                        |             |        |                     |                                  |       |                                | Average                      | 62.9                       |

### Location AM2 - Sai Tso Wan Recreation Ground

| Start Date | Weather Condition | Air Temp. (K) | Atmospheric Pressure, Pa (mmHg) | Filter Weight (g) |        | Particulate Weight (g) | Elapse Time |         | Sampling Time(hrs.) | Flow Rate (m <sup>3</sup> /min.) |       | Av. flow (m <sup>3</sup> /min) | Total vol. (m <sup>3</sup> ) | Conc. (µg/m <sup>3</sup> ) |
|------------|-------------------|---------------|---------------------------------|-------------------|--------|------------------------|-------------|---------|---------------------|----------------------------------|-------|--------------------------------|------------------------------|----------------------------|
|            |                   |               |                                 | Initial           | Final  |                        | Initial     | Final   |                     | Initial                          | Final |                                |                              |                            |
| 4-Jun-18   | Rainy             | 301.5         | 759.2                           | 3.6284            | 3.6982 | 0.0698                 | 24551.3     | 24575.3 | 24.0                | 1.21                             | 1.20  | 1.21                           | 1735.2                       | 40.2                       |
| 8-Jun-18   | Rainy             | 299.6         | 753.1                           | 2.8507            | 2.9182 | 0.0675                 | 24575.3     | 24599.3 | 24.0                | 1.20                             | 1.20  | 1.20                           | 1733.7                       | 38.9                       |
| 13-Jun-18  | Cloudy            | 300.4         | 751.5                           | 3.6151            | 3.6784 | 0.0633                 | 24599.3     | 24623.3 | 24.0                | 1.20                             | 1.20  | 1.20                           | 1729.5                       | 36.6                       |
| 19-Jun-18  | Sunny             | 303.0         | 755.6                           | 2.9981            | 3.0637 | 0.0656                 | 24623.3     | 24647.3 | 24.0                | 1.20                             | 1.20  | 1.20                           | 1726.7                       | 38.0                       |
| 25-Jun-18  | Cloudy            | 301.2         | 758.8                           | 2.9668            | 3.0203 | 0.0535                 | 24647.3     | 24671.3 | 24.0                | 1.21                             | 1.21  | 1.21                           | 1735.6                       | 30.8                       |
| 28-Jun-18  | Cloudy            | 302.7         | 758.1                           | 3.2174            | 3.3161 | 0.0987                 | 24671.3     | 24695.3 | 24.0                | 1.22                             | 1.22  | 1.22                           | 1755.2                       | 56.2                       |
|            |                   |               |                                 |                   |        |                        |             |         |                     |                                  |       |                                | Min                          | 30.8                       |
|            |                   |               |                                 |                   |        |                        |             |         |                     |                                  |       |                                | Max                          | 56.2                       |
|            |                   |               |                                 |                   |        |                        |             |         |                     |                                  |       |                                | Average                      | 40.1                       |

### Location AM3 - Yau Lai Estate, Bik Lai House

| Start Date | Weather Condition | Air Temp. (K) | Atmospheric Pressure, Pa (mmHg) | Filter Weight (g) |        | Particulate Weight (g) | Elapse Time |         | Sampling Time(hrs.) | Flow Rate (m <sup>3</sup> /min.) |       | Av. flow (m <sup>3</sup> /min) | Total vol. (m <sup>3</sup> ) | Conc. (µg/m <sup>3</sup> ) |
|------------|-------------------|---------------|---------------------------------|-------------------|--------|------------------------|-------------|---------|---------------------|----------------------------------|-------|--------------------------------|------------------------------|----------------------------|
|            |                   |               |                                 | Initial           | Final  |                        | Initial     | Final   |                     | Initial                          | Final |                                |                              |                            |
| 4-Jun-18   | Rainy             | 302.4         | 758.3                           | 3.2569            | 3.3038 | 0.0469                 | 13118.7     | 13142.7 | 24.0                | 1.21                             | 1.21  | 1.21                           | 1737.8                       | 27.0                       |
| 8-Jun-18   | Rainy             | 299.1         | 753.6                           | 3.2956            | 3.3454 | 0.0498                 | 13142.7     | 13166.7 | 24.0                | 1.21                             | 1.21  | 1.21                           | 1742.1                       | 28.6                       |
| 13-Jun-18  | Cloudy            | 300.5         | 751.9                           | 3.6424            | 3.6989 | 0.0565                 | 13166.7     | 13190.7 | 24.0                | 1.21                             | 1.21  | 1.21                           | 1735.8                       | 32.6                       |
| 19-Jun-18  | Sunny             | 302.6         | 755.3                           | 2.9822            | 3.0275 | 0.0453                 | 13190.7     | 13214.7 | 24.0                | 1.20                             | 1.20  | 1.20                           | 1733.6                       | 26.1                       |
| 25-Jun-18  | Cloudy            | 300.9         | 758.5                           | 3.2171            | 3.2605 | 0.0434                 | 13214.7     | 13238.7 | 24.0                | 1.21                             | 1.21  | 1.21                           | 1742.6                       | 24.9                       |
| 28-Jun-18  | Cloudy            | 302.2         | 757.8                           | 3.6291            | 3.6684 | 0.0393                 | 13238.7     | 13262.7 | 24.0                | 1.21                             | 1.21  | 1.21                           | 1742.1                       | 22.6                       |
|            |                   |               |                                 |                   |        |                        |             |         |                     |                                  |       |                                | Min                          | 22.6                       |
|            |                   |               |                                 |                   |        |                        |             |         |                     |                                  |       |                                | Max                          | 32.6                       |
|            |                   |               |                                 |                   |        |                        |             |         |                     |                                  |       |                                | Average                      | 27.0                       |

## Appendix F - 24-hour TSP Monitoring Results

### Location AM4(A) - Cha Kwo Ling Public Cargo Working Area Administrative Office

| Start Date | Weather Condition | Air Temp. (K) | Atmospheric Pressure, Pa (mmHg) | Filter Weight (g) |        | Particulate Weight (g) | Elapse Time |         | Sampling Time(hrs.) | Flow Rate (m <sup>3</sup> /min.) |       | Av. flow (m <sup>3</sup> /min) | Total vol. (m <sup>3</sup> ) | Conc. (µg/m <sup>3</sup> ) |
|------------|-------------------|---------------|---------------------------------|-------------------|--------|------------------------|-------------|---------|---------------------|----------------------------------|-------|--------------------------------|------------------------------|----------------------------|
|            |                   |               |                                 | Initial           | Final  |                        | Initial     | Final   |                     | Initial                          | Final |                                |                              |                            |
| 4-Jun-18   | Rainy             | 301.6         | 758.9                           | 3.2980            | 3.5222 | 0.2242                 | 10105.2     | 10129.2 | 24.0                | 1.21                             | 1.21  | 1.21                           | 1738.7                       | 129.0                      |
| 8-Jun-18   | Rainy             | 300.5         | 752.4                           | 2.8398            | 2.9678 | 0.1280                 | 10129.2     | 10153.2 | 24.0                | 1.20                             | 1.20  | 1.20                           | 1734.3                       | 73.8                       |
| 13-Jun-18  | Cloudy            | 299.9         | 751.5                           | 2.8431            | 3.0091 | 0.1660                 | 10153.2     | 10177.2 | 24.0                | 1.21                             | 1.20  | 1.20                           | 1735.0                       | 95.7                       |
| 19-Jun-18  | Sunny             | 302.5         | 754.6                           | 3.0004            | 3.1884 | 0.1880                 | 10177.2     | 10201.2 | 24.0                | 1.20                             | 1.20  | 1.20                           | 1731.1                       | 108.6                      |
| 25-Jun-18  | Cloudy            | 300.8         | 759.3                           | 2.9823            | 3.1904 | 0.2081                 | 10201.2     | 10225.2 | 24.0                | 1.21                             | 1.21  | 1.21                           | 1741.4                       | 119.5                      |
| 28-Jun-18  | Cloudy            | 302.6         | 758.5                           | 2.9897            | 3.0218 | 0.0321                 | 10225.2     | 10249.2 | 24.0                | 1.21                             | 1.21  | 1.21                           | 1743.3                       | 18.4                       |
|            |                   |               |                                 |                   |        |                        |             |         |                     |                                  |       |                                | Min                          | 18.4                       |
|            |                   |               |                                 |                   |        |                        |             |         |                     |                                  |       |                                | Max                          | 129.0                      |
|            |                   |               |                                 |                   |        |                        |             |         |                     |                                  |       |                                | Average                      | 90.8                       |




### Location AM5(A) - Tseung Kwan O DSD Desilting Compound

| Start Date | Weather Condition | Air Temp. (K) | Atmospheric Pressure, Pa (mmHg) | Filter Weight (g) |        | Particulate Weight (g) | Elapse Time |         | Sampling Time(hrs.) | Flow Rate (m <sup>3</sup> /min.) |       | Av. flow (m <sup>3</sup> /min) | Total vol. (m <sup>3</sup> ) | Conc. (µg/m <sup>3</sup> ) |
|------------|-------------------|---------------|---------------------------------|-------------------|--------|------------------------|-------------|---------|---------------------|----------------------------------|-------|--------------------------------|------------------------------|----------------------------|
|            |                   |               |                                 | Initial           | Final  |                        | Initial     | Final   |                     | Initial                          | Final |                                |                              |                            |
| 4-Jun-18   | Cloudy            | 301.5         | 758.3                           | 3.6085            | 3.6723 | 0.0638                 | 26434.9     | 26458.9 | 24.0                | 1.20                             | 1.20  | 1.20                           | 1730.9                       | 36.9                       |
| 8-Jun-18   | Cloudy            | 299.8         | 753.7                           | 2.8123            | 2.8579 | 0.0456                 | 26458.9     | 26482.9 | 24.0                | 1.20                             | 1.20  | 1.20                           | 1730.5                       | 26.4                       |
| 13-Jun-18  | Sunny             | 300.2         | 750.8                           | 2.8510            | 2.8905 | 0.0395                 | 26482.9     | 26506.9 | 24.0                | 1.20                             | 1.20  | 1.20                           | 1725.4                       | 22.9                       |
| 19-Jun-18  | Cloudy            | 303.1         | 755.7                           | 3.0101            | 3.0775 | 0.0674                 | 26506.9     | 26530.9 | 24.0                | 1.20                             | 1.20  | 1.20                           | 1722.3                       | 39.1                       |
| 25-Jun-18  | Cloudy            | 301.7         | 759.4                           | 2.9897            | 3.0218 | 0.0321                 | 26530.9     | 26554.9 | 24.0                | 1.20                             | 1.20  | 1.20                           | 1731.7                       | 18.5                       |
| 28-Jun-18  | Cloudy            | 301.9         | 759.1                           | 2.8019            | 2.8234 | 0.0215                 | 26560.3     | 26584.3 | 24.0                | 1.21                             | 1.21  | 1.21                           | 1742.5                       | 12.3                       |
|            |                   |               |                                 |                   |        |                        |             |         |                     |                                  |       |                                | Min                          | 12.3                       |
|            |                   |               |                                 |                   |        |                        |             |         |                     |                                  |       |                                | Max                          | 39.1                       |
|            |                   |               |                                 |                   |        |                        |             |         |                     |                                  |       |                                | Average                      | 26.0                       |

### Location AM6(A) - Park Central, L1/F Open Space Area




| Start Date | Weather Condition | Air Temp. (K) | Atmospheric Pressure, Pa (mmHg) | Filter Weight (g) |        | Particulate Weight (g) | Elapse Time |         | Sampling Time(hrs.) | Flow Rate (m <sup>3</sup> /min.) |       | Av. flow (m <sup>3</sup> /min) | Total vol. (m <sup>3</sup> ) | Conc. (µg/m <sup>3</sup> ) |
|------------|-------------------|---------------|---------------------------------|-------------------|--------|------------------------|-------------|---------|---------------------|----------------------------------|-------|--------------------------------|------------------------------|----------------------------|
|            |                   |               |                                 | Initial           | Final  |                        | Initial     | Final   |                     | Initial                          | Final |                                |                              |                            |
| 4-Jun-18   | Cloudy            | 302.3         | 758.6                           | 3.6178            | 3.6965 | 0.0787                 | 16907.8     | 16931.8 | 24.0                | 1.22                             | 1.22  | 1.22                           | 1758.0                       | 44.8                       |
| 8-Jun-18   | Cloudy            | 299.6         | 753.5                           | 2.8639            | 2.9018 | 0.0379                 | 16931.8     | 16955.8 | 24.0                | 1.22                             | 1.22  | 1.22                           | 1760.0                       | 21.5                       |
| 13-Jun-18  | Sunny             | 300.0         | 751.3                           | 3.3643            | 3.3856 | 0.0213                 | 16955.8     | 16979.8 | 24.0                | 1.22                             | 1.22  | 1.22                           | 1756.2                       | 12.1                       |
| 19-Jun-18  | Cloudy            | 302.7         | 755.4                           | 2.9711            | 2.9977 | 0.0266                 | 16979.8     | 17003.8 | 24.0                | 1.22                             | 1.22  | 1.22                           | 1753.1                       | 15.2                       |
| 25-Jun-18  | Cloudy            | 301.4         | 759.3                           | 3.6106            | 3.7669 | 0.1563                 | 17003.8     | 17027.8 | 24.0                | 1.22                             | 1.22  | 1.22                           | 1761.5                       | 88.7                       |
| 28-Jun-18  | Cloudy            | 301.7         | 759.0                           | 2.9804            | 3.0932 | 0.1128                 | 17027.8     | 17051.8 | 24.0                | 1.22                             | 1.22  | 1.22                           | 1760.3                       | 64.1                       |
|            |                   |               |                                 |                   |        |                        |             |         |                     |                                  |       |                                | Min                          | 12.1                       |
|            |                   |               |                                 |                   |        |                        |             |         |                     |                                  |       |                                | Max                          | 88.7                       |
|            |                   |               |                                 |                   |        |                        |             |         |                     |                                  |       |                                | Average                      | 41.1                       |

### 24-hr TSP Concentration Levels



|  |   |        |             |          |
|--|---|--------|-------------|----------|
| Title  | Agreement No. CE/59/2015 (EP)   | Scale  | Project     | CINOTECH |
|  | Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction | N.T.S  | No. MA16034 |          |
| Graphical Presentation of 24-hour TSP Monitoring Results |   | Date   | Appendix    |          |
|  |   | Jun 18 | F           |          |

### 24-hr TSP Concentration Levels



|  |   |        |             |          |
|--|---|--------|-------------|----------|
| Title  | Agreement No. CE/59/2015 (EP)   | Scale  | Project     | CINOTECH |
|  | Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction | N.T.S  | No. MA16034 |          |
| Graphical Presentation of 24-hour TSP Monitoring Results |   | Date   | Appendix    |          |
|  |   | Jun 18 | F           |          |

---

---

**APPENDIX G  
NOISE MONITORING RESULTS AND  
GRAPHICAL PRESENTATIONS**

---

---

## Appendix G - Noise Monitoring Results

(0700-1900 hrs on Normal Weekdays)

| Location CM1 - Nga Lai House, Yau Lai Estate Phase 1, Yau Tong |       |         |                       |                 |                 |                 |                          |
|--|-------|---------|-----------------------|-----------------|-----------------|-----------------|--------------------------|
| Date   | Time  | Weather | Unit: dB (A) (30-min) |                 |                 |                 |                          |
|  |       |         | Measured Noise Level  |                 |                 | Baseline Level  | Construction Noise Level |
|  |       |         | L <sub>eq</sub>       | L <sub>10</sub> | L <sub>90</sub> | L <sub>eq</sub> | L <sub>eq</sub>          |
| 5-Jun-18   | 9:50  | Rainy   | 74.6                  | 77.9            | 69.3            | 65.5            | 74.0                     |
| 11-Jun-18  | 10:35 | Sunny   | 68.9                  | 69.7            | 62.7            |                 | 66.2                     |
| 20-Jun-18  | 14:00 | Sunny   | 74.2                  | 76.7            | 70.6            |                 | 73.6                     |
| 26-Jun-18  | 16:30 | Sunny   | 69.9                  | 71.6            | 67.9            |                 | 67.9                     |

| Location CM2 - Bik Lai House, Yau Lai Estate Phase 1, Yau Tong |       |         |                       |                 |                 |                 |                          |
|--|-------|---------|-----------------------|-----------------|-----------------|-----------------|--------------------------|
| Date   | Time  | Weather | Unit: dB (A) (30-min) |                 |                 |                 |                          |
|  |       |         | Measured Noise Level  |                 |                 | Baseline Level  | Construction Noise Level |
|  |       |         | L <sub>eq</sub>       | L <sub>10</sub> | L <sub>90</sub> | L <sub>eq</sub> | L <sub>eq</sub>          |
| 5-Jun-18   | 9:00  | Cloudy  | 74.6                  | 77.6            | 69.4            | 63.6            | 74.2                     |
| 11-Jun-18  | 10:00 | Sunny   | 69.6                  | 71.2            | 63.6            |                 | 68.3                     |
| 20-Jun-18  | 13:05 | Sunny   | 74.3                  | 76.2            | 71.0            |                 | 73.9                     |
| 26-Jun-18  | 9:10  | Sunny   | 69.8                  | 71.2            | 64.4            |                 | 68.6                     |

| Location CM3 - Block S, Yau Lai Estate Phase 5, Yau Tong |       |         |                       |                 |                 |                 |                          |
|--|-------|---------|-----------------------|-----------------|-----------------|-----------------|--------------------------|
| Date   | Time  | Weather | Unit: dB (A) (30-min) |                 |                 |                 |                          |
|  |       |         | Measured Noise Level  |                 |                 | Baseline Level  | Construction Noise Level |
|  |       |         | L <sub>eq</sub>       | L <sub>10</sub> | L <sub>90</sub> | L <sub>eq</sub> | L <sub>eq</sub>          |
| 5-Jun-18   | 10:20 | Rainy   | 66.0                  | 68.4            | 61.2            | 65.6            | 55.4                     |
| 12-Jun-18  | 10:30 | Cloudy  | 73.4                  | 75.0            | 71.1            |                 | 72.6                     |
| 20-Jun-18  | 13:50 | Cloudy  | 72.1                  | 73.9            | 69.4            |                 | 71.0                     |
| 26-Jun-18  | 11:30 | Sunny   | 72.2                  | 74.8            | 69.2            |                 | 71.1                     |

| Location CM4 - Tin Hau Temple, Cha Kwo Ling |       |         |                       |                 |                 |                 |                          |
|---|-------|---------|-----------------------|-----------------|-----------------|-----------------|--------------------------|
| Date  | Time  | Weather | Unit: dB (A) (30-min) |                 |                 |                 |                          |
|   |       |         | Measured Noise Level  |                 |                 | Baseline Level  | Construction Noise Level |
|   |       |         | L <sub>eq</sub>       | L <sub>10</sub> | L <sub>90</sub> | L <sub>eq</sub> | L <sub>eq</sub>          |
| 5-Jun-18                                    | 13:00 | Rainy   | 61.2                  | 64.3            | 57.2            | 62.0            | 61.2 Measured ≤ Baseline |
| 11-Jun-18                                   | 11:30 | Sunny   | 63.7                  | 64.9            | 57.6            |                 | 58.8                     |
| 20-Jun-18                                   | 9:05  | Sunny   | 69.8                  | 71.4            | 65.3            |                 | 69.0                     |
| 26-Jun-18                                   | 9:05  | Sunny   | 70.1                  | 72.4            | 66.3            |                 | 69.4                     |

| Location CM5 - CCC Kei Faat Primary School, Yau Tong |       |         |                       |                 |                 |                 |                          |
|--|-------|---------|-----------------------|-----------------|-----------------|-----------------|--------------------------|
| Date   | Time  | Weather | Unit: dB (A) (30-min) |                 |                 |                 |                          |
|  |       |         | Measured Noise Level  |                 |                 | Baseline Level  | Construction Noise Level |
|  |       |         | L <sub>eq</sub>       | L <sub>10</sub> | L <sub>90</sub> | L <sub>eq</sub> | L <sub>eq</sub>          |
| 5-Jun-18   | 11:00 | Rainy   | 69.2                  | 73.7            | 67.4            | 68.2            | 62.3                     |
| 12-Jun-18  | 11:25 | Cloudy  | 70.9                  | 72.7            | 66.3            |                 | 67.6                     |
| 20-Jun-18  | 13:05 | Cloudy  | 69.3                  | 71.2            | 65.1            |                 | 62.8                     |
| 26-Jun-18  | 10:00 | Sunny   | 69.7                  | 71.9            | 66.5            |                 | 64.4                     |

## Appendix G - Noise Monitoring Results




(0700-1900 hrs on Normal Weekdays)

| Location CM6(A) - Site Boundary of Contract No. NE/2015/02 near Tower 1, Ocean Shores |       |         |                       |                 |                 |                 |                          |
|---|-------|---------|-----------------------|-----------------|-----------------|-----------------|--------------------------|
| Date  | Time  | Weather | Unit: dB (A) (30-min) |                 |                 |                 |                          |
|   |       |         | Measured Noise Level  |                 |                 | Baseline Level  | Construction Noise Level |
|   |       |         | L <sub>eq</sub>       | L <sub>10</sub> | L <sub>90</sub> | L <sub>eq</sub> | L <sub>eq</sub>          |
| 6-Jun-18  | 15:00 | Cloudy  | 71.0                  | 75.6            | 56.9            | 61.9            | 70.4                     |
| 12-Jun-18   | 16:30 | Cloudy  | 66.7                  | 68.5            | 61.6            |                 | 65.0                     |
| 21-Jun-18   | 13:00 | Cloudy  | 72.3                  | 74.3            | 69.8            |                 | 71.9                     |
| 27-Jun-18   | 11:30 | Cloudy  | 69.1                  | 71.5            | 67.4            |                 | 68.2                     |

| Location CM7(A) - Site Boundary of Contract No. NE/2015/02 near Tower 7, Ocean Shores |       |         |                       |                 |                 |                 |                          |
|---|-------|---------|-----------------------|-----------------|-----------------|-----------------|--------------------------|
| Date  | Time  | Weather | Unit: dB (A) (30-min) |                 |                 |                 |                          |
|   |       |         | Measured Noise Level  |                 |                 | Baseline Level  | Construction Noise Level |
|   |       |         | L <sub>eq</sub>       | L <sub>10</sub> | L <sub>90</sub> | L <sub>eq</sub> | L <sub>eq</sub>          |
| 6-Jun-18  | 14:15 | Cloudy  | 63.7                  | 62.8            | 56.8            | 58.3            | 62.2                     |
| 12-Jun-18   | 15:05 | Cloudy  | 69.3                  | 71.5            | 63.5            |                 | 68.9                     |
| 21-Jun-18   | 13:30 | Cloudy  | 70.2                  | 71.3            | 69.1            |                 | 69.9                     |
| 27-Jun-18   | 10:30 | Cloudy  | 68.9                  | 71.2            | 66.3            |                 | 68.5                     |

| Location CM8(A) - Park Central, L1/F Open Space Area |       |         |                       |                 |                 |                 |                          |
|--|-------|---------|-----------------------|-----------------|-----------------|-----------------|--------------------------|
| Date   | Time  | Weather | Unit: dB (A) (30-min) |                 |                 |                 |                          |
|  |       |         | Measured Noise Level  |                 |                 | Baseline Level  | Construction Noise Level |
|  |       |         | L <sub>eq</sub>       | L <sub>10</sub> | L <sub>90</sub> | L <sub>eq</sub> | L <sub>eq</sub>          |
| 6-Jun-18   | 9:00  | Cloudy  | 62.6                  | 66.5            | 55.1            | 69.1            | 62.6 Measured ≤ Baseline |
| 12-Jun-18  | 11:00 | Cloudy  | 69.6                  | 72.1            | 61.6            |                 | 60.0                     |
| 21-Jun-18  | 9:00  | Cloudy  | 60.1                  | 63.0            | 56.7            |                 | 60.1 Measured ≤ Baseline |
| 27-Jun-18  | 16:00 | Cloudy  | 66.6                  | 70.7            | 58.7            |                 | 66.6 Measured ≤ Baseline |




## Noise Levels



|  |                    |                        |  |
|--|--------------------|------------------------|--|
| Title<br>Agreement No. CE/59/2015 (EP)<br>Environmental Team for Tseung Kwan O - Lam Tin Tunnel -<br>Design and Construction<br><br>Graphical Presentation of<br>Construction Noise Monitoring Results | Scale<br><br>N.T.S | Project<br>No. MA16034 |  |
|  | Date<br><br>Jun 18 | Appendix<br><br>G      |  |





## Noise Levels



Remark: Examination Period for CM5: 4/6, 5/6, 7/6 and 8/6. Noise Criteria during examination is 65 db(A).

|  |                |                        |                                      |
|--|----------------|------------------------|--------------------------------------|
| Title<br>Agreement No. CE/59/2015 (EP)<br>Environmental Team for Tseung Kwan O - Lam Tin Tunnel -<br>Design and Construction<br><br>Graphical Presentation of<br>Construction Noise Monitoring Results | Scale<br>N.T.S | Project<br>No. MA16034 | <h1 style="margin: 0;">CINOTECH</h1> |
|  | Date<br>Jun 18 | Appendix<br>G          |                                      |

## Noise Levels



|  |                |                        |                                      |
|--|----------------|------------------------|--------------------------------------|
| Title<br>Agreement No. CE/59/2015 (EP)<br>Environmental Team for Tseung Kwan O - Lam Tin Tunnel -<br>Design and Construction<br><br>Graphical Presentation of<br>Construction Noise Monitoring Results | Scale<br>N.T.S | Project<br>No. MA16034 | <h1 style="margin: 0;">CINOTECH</h1> |
|  | Date<br>Jun 18 | Appendix<br>G          |                                      |

**Appendix G - Noise Monitoring Results**

(Restricted Hours - 19:00 to 23:00 on all other days & 07:00 to 23:00 holidays)

| Location CM1 - Nga Lai House, Yau Lai Estate Phase 1, Yau Tong |       |         |                 |                 |                 |                         |                                   |   |      |      |
|--|-------|---------|-----------------|-----------------|-----------------|-------------------------|-----------------------------------|---|------|------|
| Date   | Time  | Weather | dB (A) (5-min)  |                 |                 |                         | Baseline Level<br>L <sub>eq</sub> | Construction Noise Level<br>L <sub>eq</sub> |      |      |
|  |       |         | L <sub>eq</sub> | L <sub>10</sub> | L <sub>90</sub> | Average L <sub>eq</sub> |                                   |   |      |      |
| 1-Jun-18   | 20:55 | Cloudy  | 64.5            | 66.7            | 62.6            | 64.3                    | 64.4                              | 64.3 Measured ≤ Baseline                    |      |      |
|  | 21:00 |         | 64.3            | 65.6            | 62.5            |                         |                                   |   |      |      |
|  | 21:05 |         | 64.0            | 65.3            | 62.4            |                         |                                   |   |      |      |
| 8-Jun-18   | 22:45 | Cloudy  | 65.9            | 66.9            | 64.4            | 66.0                    |                                   | 64.4  | 60.9 |      |
|  | 22:50 |         | 66.1            | 67.0            | 65.0            |                         |                                   |   |      |      |
|  | 22:55 |         | 66.0            | 67.0            | 64.7            |                         |                                   |   |      |      |
| 10-Jun-18  | 10:45 | Sunny   | 64.5            | 66.0            | 62.3            | 64.9                    |                                   |   | 64.4 | 55.3 |
|  | 10:50 |         | 64.9            | 66.1            | 63.4            |                         |                                   |   |      |      |
|  | 10:55 |         | 65.3            | 66.7            | 62.6            |                         |                                   |   |      |      |
| 14-Jun-18  | 22:45 | Cloudy  | 65.3            | 66.7            | 63.7            | 65.2                    |                                   |   |      | 64.4 |
|  | 22:50 |         | 65.1            | 66.5            | 63.6            |                         |                                   |   |      |      |
|  | 22:55 |         | 65.3            | 66.8            | 63.4            |                         |                                   |   |      |      |
| 17-Jun-18  | 14:20 | Sunny   | 64.0            | 65.5            | 63.2            | 64.5                    | 64.4                              |   |      |      |
|  | 14:25 |         | 64.6            | 66.4            | 63.5            |                         |                                   |   |      |      |
|  | 14:30 |         | 64.8            | 66.7            | 63.9            |                         |                                   |   |      |      |
| 20-Jun-18  | 22:05 | Cloudy  | 65.2            | 66.5            | 63.5            | 65.3                    |                                   | 64.4  |      |      |
|  | 22:10 |         | 65.1            | 66.7            | 63.5            |                         |                                   |   |      |      |
|  | 22:15 |         | 65.6            | 67.1            | 64.0            |                         |                                   |   |      |      |
| 24-Jun-18  | 11:15 | Sunny   | 66.1            | 67.5            | 64.6            | 66.0                    |                                   |   | 64.4 |      |
|  | 11:20 |         | 65.9            | 67.4            | 64.2            |                         |                                   |   |      |      |
|  | 11:25 |         | 66.1            | 67.6            | 64.2            |                         |                                   |   |      |      |
| 26-Jun-18  | 22:10 | Fine    | 66.6            | 67.9            | 64.6            | 66.3                    |                                   |   |      | 64.4 |
|  | 22:15 |         | 66.4            | 68.1            | 64.0            |                         |                                   |   |      |      |
|  | 22:20 |         | 65.9            | 67.3            | 64.2            |                         |                                   |   |      |      |

| Location CM2 - Bik Lai House, Yau Lai Estate Phase 1, Yau Tong |       |         |                 |                 |                 |                         |                                   |   |      |      |
|--|-------|---------|-----------------|-----------------|-----------------|-------------------------|-----------------------------------|---|------|------|
| Date   | Time  | Weather | dB (A) (5-min)  |                 |                 |                         | Baseline Level<br>L <sub>eq</sub> | Construction Noise Level<br>L <sub>eq</sub> |      |      |
|  |       |         | L <sub>eq</sub> | L <sub>10</sub> | L <sub>90</sub> | Average L <sub>eq</sub> |                                   |   |      |      |
| 1-Jun-18   | 20:20 | Cloudy  | 65.1            | 66.5            | 63.1            | 65.0                    | 64.2                              | 57.3  |      |      |
|  | 20:25 |         | 64.8            | 65.9            | 63.6            |                         |                                   |   |      |      |
|  | 20:30 |         | 65.1            | 66.4            | 63.7            |                         |                                   |   |      |      |
| 8-Jun-18   | 22:20 | Cloudy  | 65.9            | 67.1            | 64.4            | 65.6                    |                                   | 64.2  | 60.0 |      |
|  | 22:25 |         | 65.7            | 67.1            | 64.0            |                         |                                   |   |      |      |
|  | 22:30 |         | 65.1            | 66.8            | 63.6            |                         |                                   |   |      |      |
| 10-Jun-18  | 10:05 | Cloudy  | 65.3            | 66.8            | 63.4            | 65.6                    |                                   |   | 64.2 | 60.0 |
|  | 10:10 |         | 66.0            | 67.7            | 64.0            |                         |                                   |   |      |      |
|  | 10:15 |         | 65.4            | 66.8            | 64.1            |                         |                                   |   |      |      |
| 14-Jun-18  | 22:15 | Cloudy  | 65.3            | 66.5            | 64.1            | 64.9                    |                                   |   |      | 64.2 |
|  | 22:20 |         | 64.4            | 65.8            | 62.6            |                         |                                   |   |      |      |
|  | 22:25 |         | 64.9            | 65.9            | 63.4            |                         |                                   |   |      |      |
| 17-Jun-18  | 13:42 | Sunny   | 67.5            | 69.8            | 65.1            | 67.4                    | 64.2                              |   |      |      |
|  | 13:47 |         | 67.7            | 70.1            | 65.8            |                         |                                   |   |      |      |
|  | 13:52 |         | 66.8            | 68.7            | 64.3            |                         |                                   |   |      |      |
| 20-Jun-18  | 21:40 | Cloudy  | 64.0            | 65.4            | 62.2            | 64.1                    |                                   | 64.2  |      |      |
|  | 21:45 |         | 64.1            | 65.4            | 62.6            |                         |                                   |   |      |      |
|  | 21:50 |         | 64.1            | 65.5            | 62.4            |                         |                                   |   |      |      |
| 24-Jun-18  | 10:50 | Sunny   | 64.2            | 65.5            | 62.8            | 65.0                    |                                   |   | 64.2 |      |
|  | 10:55 |         | 65.5            | 66.9            | 63.4            |                         |                                   |   |      |      |
|  | 11:00 |         | 65.3            | 66.8            | 63.5            |                         |                                   |   |      |      |
| 26-Jun-18  | 21:45 | Fine    | 67.1            | 68.3            | 64.1            | 67.7                    |                                   |   |      | 64.2 |
|  | 21:50 |         | 68.3            | 69.6            | 65.5            |                         |                                   |   |      |      |
|  | 21:55 |         | 67.5            | 69.0            | 65.0            |                         |                                   |   |      |      |

| Location CM3 - Block S, Yau Lai Estate Phase 5, Yau Tong |       |         |                 |                 |                 |                         |                                   |   |      |                          |
|--|-------|---------|-----------------|-----------------|-----------------|-------------------------|-----------------------------------|---|------|--------------------------|
| Date   | Time  | Weather | dB (A) (5-min)  |                 |                 |                         | Baseline Level<br>L <sub>eq</sub> | Construction Noise Level<br>L <sub>eq</sub> |      |                          |
|  |       |         | L <sub>eq</sub> | L <sub>10</sub> | L <sub>90</sub> | Average L <sub>eq</sub> |                                   |   |      |                          |
| 1-Jun-18   | 21:35 | Cloudy  | 58.5            | 59.8            | 57.1            | 58.6                    | 64.7                              | 58.6 Measured ≤ Baseline                    |      |                          |
|  | 21:40 |         | 58.6            | 59.9            | 57.1            |                         |                                   |   |      |                          |
|  | 21:45 |         | 58.8            | 60.3            | 57.1            |                         |                                   |   |      |                          |
| 8-Jun-18   | 21:50 | Cloudy  | 66.2            | 67.8            | 64.4            | 66.1                    |                                   | 64.7  | 60.5 |                          |
|  | 21:55 |         | 66.7            | 67.9            | 64.5            |                         |                                   |   |      |                          |
|  | 22:00 |         | 65.4            | 66.7            | 64.1            |                         |                                   |   |      |                          |
| 10-Jun-18  | 9:35  | Sunny   | 63.4            | 64.8            | 61.7            | 63.9                    |                                   |   | 64.7 | 63.9 Measured ≤ Baseline |
|  | 9:40  |         | 64.0            | 65.2            | 62.4            |                         |                                   |   |      |                          |
|  | 9:45  |         | 64.3            | 65.5            | 62.9            |                         |                                   |   |      |                          |
| 14-Jun-18  | 21:45 | Cloudy  | 66.8            | 68.6            | 65.0            | 66.1                    |                                   |   |      | 64.7                     |
|  | 21:50 |         | 66.0            | 66.9            | 64.5            |                         |                                   |   |      |                          |
|  | 21:55 |         | 65.5            | 66.7            | 64.2            |                         |                                   |   |      |                          |
| 17-Jun-18  | 13:00 | Sunny   | 57.4            | 61.2            | 50.9            | 57.2                    | 64.7                              |   |      |                          |
|  | 13:05 |         | 57.3            | 60.3            | 50.5            |                         |                                   |   |      |                          |
|  | 13:10 |         | 57.0            | 60.2            | 50.1            |                         |                                   |   |      |                          |
| 20-Jun-18  | 21:05 | Cloudy  | 65.3            | 66.7            | 63.6            | 64.9                    |                                   | 64.7  |      |                          |
|  | 21:10 |         | 64.6            | 65.7            | 63.5            |                         |                                   |   |      |                          |
|  | 21:15 |         | 64.8            | 65.9            | 63.4            |                         |                                   |   |      |                          |
| 24-Jun-18  | 11:45 | Sunny   | 63.7            | 65.1            | 61.5            | 64.1                    |                                   |   | 64.7 |                          |
|  | 11:50 |         | 64.3            | 65.4            | 62.0            |                         |                                   |   |      |                          |
|  | 11:55 |         | 64.4            | 65.5            | 62.3            |                         |                                   |   |      |                          |
| 26-Jun-18  | 22:40 | Fine    | 65.6            | 66.8            | 64.0            | 65.4                    |                                   |   |      | 64.7                     |
|  | 22:45 |         | 65.4            | 66.8            | 64.1            |                         |                                   |   |      |                          |
|  | 22:50 |         | 65.1            | 66.0            | 63.9            |                         |                                   |   |      |                          |

**Appendix G - Noise Monitoring Results**

| Location CM4 - Tin Hau Temple, Cha Kwo Ling |       |         |                 |                 |                 |      |                         |                                   |   |      |
|---|-------|---------|-----------------|-----------------|-----------------|------|-------------------------|-----------------------------------|---|------|
| Date  | Time  | Weather | dB (A) (5-min)  |                 |                 |      | Average L <sub>eq</sub> | Baseline Level<br>L <sub>eq</sub> | Construction Noise Level<br>L <sub>eq</sub> |      |
|   |       |         | L <sub>eq</sub> | L <sub>10</sub> | L <sub>90</sub> |      |                         |                                   |   |      |
| 1-Jun-18                                    | 21:43 | Cloudy  | 51.7            | 54.8            | 44.1            | 51.5 | 57.0                    | 51.5 Measured ≤ Baseline          |   |      |
|   | 21:48 |         | 50.6            | 53.6            | 44.5            |      |                         |                                   |   |      |
|   | 21:53 |         | 52.1            | 54.7            | 45.5            |      |                         |                                   |   |      |
| 8-Jun-18                                    | 21:20 | Cloudy  | 53.5            | 56.2            | 47.8            | 53.6 |                         | 57.0                              | 53.6 Measured ≤ Baseline                    |      |
|   | 21:25 |         | 53.6            | 56.4            | 47.6            |      |                         |                                   |   |      |
|   | 21:30 |         | 53.7            | 56.8            | 46.3            |      |                         |                                   |   |      |
| 10-Jun-18                                   | 9:00  | Cloudy  | 57.2            | 58.6            | 55.2            | 58.7 |                         |                                   | 57.0  | 53.8 |
|   | 9:05  |         | 59.8            | 61.6            | 57.3            |      |                         |                                   |   |      |
|   | 9:10  |         | 58.8            | 60.6            | 56.7            |      |                         |                                   |   |      |
| 14-Jun-18                                   | 21:20 | Cloudy  | 56.0            | 59.0            | 49.5            | 53.9 |                         |                                   |   | 57.0 |
|   | 21:25 |         | 51.3            | 54.2            | 47.6            |      |                         |                                   |   |      |
|   | 21:30 |         | 52.9            | 55.6            | 47.6            |      |                         |                                   |   |      |
| 17-Jun-18                                   | 15:30 | Sunny   | 56.7            | 58.9            | 52.6            | 56.2 | 57.0                    |                                   |   |      |
|   | 15:35 |         | 56.2            | 58.6            | 52.1            |      |                         |                                   |   |      |
|   | 15:40 |         | 55.6            | 57.4            | 51.5            |      |                         |                                   |   |      |
| 20-Jun-18                                   | 22:35 | Cloudy  | 49.4            | 52.5            | 44.1            | 49.6 |                         | 57.0                              |   |      |
|   | 22:40 |         | 50.2            | 53.4            | 45.2            |      |                         |                                   |   |      |
|   | 22:45 |         | 49.1            | 52.2            | 44.0            |      |                         |                                   |   |      |
| 24-Jun-18                                   | 10:00 | Sunny   | 57.6            | 60.1            | 55.2            | 57.1 |                         |                                   | 57.0  |      |
|   | 10:05 |         | 56.4            | 59.5            | 52.7            |      |                         |                                   |   |      |
|   | 10:10 |         | 57.2            | 59.9            | 55.0            |      |                         |                                   |   |      |
| 26-Jun-18                                   | 21:15 | Fine    | 52.6            | 55.0            | 46.3            | 51.4 |                         |                                   |   | 57.0 |
|   | 21:20 |         | 50.2            | 52.8            | 45.6            |      |                         |                                   |   |      |
|   | 21:25 |         | 50.9            | 52.8            | 45.8            |      |                         |                                   |   |      |

## Appendix G - Noise Monitoring Results

(Restricted Hours - 2300-0700 on all days)




| Location CM1 - Nga Lai House, Yau Lai Estate Phase 1, Yau Tong |       |         |                 |                 |                 |                         |                                   |   |
|--|-------|---------|-----------------|-----------------|-----------------|-------------------------|-----------------------------------|---|
| Date   | Time  | Weather | dB (A) (5-min)  |                 |                 |                         | Baseline Level<br>L <sub>eq</sub> | Construction Noise Level<br>L <sub>eq</sub> |
|  |       |         | L <sub>eq</sub> | L <sub>10</sub> | L <sub>90</sub> | Average L <sub>eq</sub> |                                   |   |
| 8-Jun-18   | 23:00 | Cloudy  | 65.6            | 66.9            | 64.3            | 65.7                    | 60.5                              | 64.1  |
|  | 23:05 |         | 65.6            | 67.1            | 64.1            |                         |                                   |   |
|  | 23:10 |         | 65.9            | 67.1            | 64.5            |                         |                                   |   |
| 14-Jun-18  | 23:00 | Cloudy  | 64.2            | 65.7            | 62.4            | 64.2                    |                                   | 61.8  |
|  | 23:05 |         | 64.2            | 65.6            | 62.7            |                         |                                   |   |
|  | 23:10 |         | 64.2            | 65.7            | 62.3            |                         |                                   |   |
| 21-Jun-18  | 0:35  | Cloudy  | 62.1            | 64.1            | 59.6            | 62.3                    |                                   | 57.6  |
|  | 0:40  |         | 63.5            | 64.9            | 59.4            |                         |                                   |   |
|  | 0:45  |         | 61.1            | 63.1            | 58.7            |                         |                                   |   |
| 26-Jun-18  | 23:50 | Fine    | 64.2            | 65.8            | 61.4            | 63.9                    | 61.2                              |   |
|  | 23:55 |         | 63.4            | 64.7            | 62.0            |                         |                                   |   |
|  | 0:00  |         | 64.2            | 64.8            | 61.1            |                         |                                   |   |

| Location CM2 - Bik Lai House, Yau Lai Estate Phase 1, Yau Tong |       |         |                 |                 |                 |                         |                                   |   |
|--|-------|---------|-----------------|-----------------|-----------------|-------------------------|-----------------------------------|---|
| Date   | Time  | Weather | dB (A) (5-min)  |                 |                 |                         | Baseline Level<br>L <sub>eq</sub> | Construction Noise Level<br>L <sub>eq</sub> |
|  |       |         | L <sub>eq</sub> | L <sub>10</sub> | L <sub>90</sub> | Average L <sub>eq</sub> |                                   |   |
| 8-Jun-18   | 23:25 | Cloudy  | 64.8            | 66.0            | 63.4            | 64.9                    | 58.0                              | 63.9  |
|  | 23:30 |         | 64.8            | 65.9            | 63.0            |                         |                                   |   |
|  | 23:35 |         | 65.0            | 66.3            | 63.2            |                         |                                   |   |
| 14-Jun-18  | 23:20 | Cloudy  | 63.1            | 64.7            | 61.1            | 63.1                    |                                   | 61.5  |
|  | 23:25 |         | 63.0            | 64.8            | 60.7            |                         |                                   |   |
|  | 23:30 |         | 63.2            | 64.9            | 60.9            |                         |                                   |   |
| 21-Jun-18  | 0:05  | Cloudy  | 60.9            | 62.7            | 58.7            | 61.1                    |                                   | 58.2  |
|  | 0:10  |         | 61.0            | 62.5            | 59.0            |                         |                                   |   |
|  | 0:15  |         | 61.4            | 62.7            | 60.0            |                         |                                   |   |
| 26-Jun-18  | 23:28 | Fine    | 65.1            | 66.2            | 62.6            | 64.2                    | 63.0                              |   |
|  | 23:33 |         | 63.5            | 64.8            | 62.1            |                         |                                   |   |
|  | 23:38 |         | 63.8            | 65.4            | 62.1            |                         |                                   |   |

| Location CM3 - Block S, Yau Lai Estate Phase 5, Yau Tong |       |         |                 |                 |                 |                         |                                   |   |
|--|-------|---------|-----------------|-----------------|-----------------|-------------------------|-----------------------------------|---|
| Date   | Time  | Weather | dB (A) (5-min)  |                 |                 |                         | Baseline Level<br>L <sub>eq</sub> | Construction Noise Level<br>L <sub>eq</sub> |
|  |       |         | L <sub>eq</sub> | L <sub>10</sub> | L <sub>90</sub> | Average L <sub>eq</sub> |                                   |   |
| 8-Jun-18   | 0:00  | Cloudy  | 64.2            | 65.7            | 62.3            | 64.1                    | 60.2                              | 61.8  |
|  | 0:05  |         | 64.4            | 65.8            | 62.8            |                         |                                   |   |
|  | 0:10  |         | 63.5            | 64.9            | 62.0            |                         |                                   |   |
| 14-Jun-18  | 23:55 | Cloudy  | 65.1            | 66.7            | 63.2            | 64.6                    |                                   | 62.6  |
|  | 0:00  |         | 64.1            | 65.9            | 62.4            |                         |                                   |   |
|  | 0:05  |         | 64.6            | 66.2            | 62.7            |                         |                                   |   |
| 21-Jun-18  | 23:35 | Cloudy  | 63.2            | 64.6            | 61.6            | 62.9                    |                                   | 59.6  |
|  | 23:40 |         | 62.7            | 63.9            | 61.2            |                         |                                   |   |
|  | 23:45 |         | 62.7            | 64.1            | 61.1            |                         |                                   |   |
| 26-Jun-18  | 23:00 | Fine    | 64.7            | 65.8            | 63.3            | 64.7                    | 62.8                              |   |
|  | 23:05 |         | 65.3            | 67.1            | 63.3            |                         |                                   |   |
|  | 23:10 |         | 64.0            | 65.1            | 62.4            |                         |                                   |   |


| Location CM4 - Tin Hau Temple, Cha Kwo Ling |       |         |                 |                 |                 |                         |                                   |   |
|---|-------|---------|-----------------|-----------------|-----------------|-------------------------|-----------------------------------|---|
| Date  | Time  | Weather | dB (A) (5-min)  |                 |                 |                         | Baseline Level<br>L <sub>eq</sub> | Construction Noise Level<br>L <sub>eq</sub> |
|   |       |         | L <sub>eq</sub> | L <sub>10</sub> | L <sub>90</sub> | Average L <sub>eq</sub> |                                   |   |
| 8-Jun-18                                    | 0:05  | Fine    | 53.9            | 55.1            | 52.4            | 53.4                    | 55.8                              | 53.4 Measured ≤ Baseline                    |
|   | 0:10  |         | 55.6            | 54.4            | 55.7            |                         |                                   |   |
|   | 0:15  |         | 46.4            | 45.6            | 46.3            |                         |                                   |   |
| 15-Jun-18                                   | 0:25  | Cloudy  | 54.1            | 55.8            | 47.4            | 53.9                    |                                   | 53.9 Measured ≤ Baseline                    |
|   | 0:30  |         | 54.8            | 56.1            | 49.1            |                         |                                   |   |
|   | 0:35  |         | 52.4            | 54.8            | 46.9            |                         |                                   |   |
| 20-Jun-18                                   | 23:00 | Cloudy  | 48.5            | 51.6            | 44.4            | 48.7                    |                                   | 48.7 Measured ≤ Baseline                    |
|   | 23:05 |         | 48.7            | 51.5            | 45.2            |                         |                                   |   |
|   | 23:10 |         | 48.9            | 51.8            | 44.9            |                         |                                   |   |
| 26-Jun-18                                   | 0:20  | Fine    | 50.4            | 52.7            | 45.2            | 49.5                    | 49.5 Measured ≤ Baseline          |   |
|   | 0:25  |         | 48.9            | 50.9            | 45.4            |                         |                                   |   |
|   | 0:30  |         | 49.2            | 51.6            | 45.4            |                         |                                   |   |

**Noise Levels**  
**(Restricted Hours - 07:00 - 23:00 holidays & 19:00 - 23:00 on all other days )**






|   |                |                        |  |
|---|----------------|------------------------|--|
| Title<br>Agreement No. CE/59/2015 (EP)<br>Environmental Team for Tseung Kwan O - Lam Tin Tunnel -<br>Design and Construction<br><br>Graphical Presentation of Restricted Noise Monitoring Results | Scale<br>N.T.S | Project<br>No. MA16034 |  |
|   | Date<br>Jun 18 | Appendix<br>G          |  |

**Noise Levels**  
**(Restricted Hours - 07:00 - 23:00 holidays & 19:00 - 23:00 on all other days )**



|   |                |                        |                 |
|---|----------------|------------------------|-----------------|
| Title<br>Agreement No. CE/59/2015 (EP)<br>Environmental Team for Tseung Kwan O - Lam Tin Tunnel -<br>Design and Construction<br>Graphical Presentation of Restricted Noise Monitoring Results | Scale<br>N.T.S | Project No.<br>MA16034 | <b>CINOTECH</b> |
|   | Date<br>Jun 18 | Appendix<br>G          |                 |


## Noise Levels (Restricted Hours - 2300-0700 on all days )



|   |                |                        |  |
|---|----------------|------------------------|--|
| Title<br>Agreement No. CE/59/2015 (EP)<br>Environmental Team for Tseung Kwan O - Lam Tin Tunnel -<br>Design and Construction<br><br>Graphical Presentation of Restricted Noise Monitoring Results | Scale<br>N.T.S | Project<br>No. MA16034 |  |
|   | Date<br>Jun 18 | Appendix<br>G          |  |



## Noise Levels (Restricted Hours - 2300-0700 on all days )



|   |                |                        |          |
|---|----------------|------------------------|----------|
| Title<br>Agreement No. CE/59/2015 (EP)<br>Environmental Team for Tseung Kwan O - Lam Tin Tunnel -<br>Design and Construction<br><br>Graphical Presentation of Restricted Noise Monitoring Results | Scale<br>N.T.S | Project No.<br>MA16034 | CINOTECH |
|   | Date<br>Jun 18 | Appendix<br>G          |          |

---

**APPENDIX H  
GROUNDWATER QUALITY  
MONITORING RESULTS AND  
GRAPHICAL PRESENTATIONS**

---

**Agreement No. CE/59/2015 (EP)****Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction****Groundwater Quality Monitoring Results at Stream 1**

| Date      | Weather Condition | Sampling Time | Depth (m) | Temperature (°C) |         | pH    |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         | Turbidity(NTU) |         |
|-----------|-------------------|---------------|-----------|------------------|---------|-------|---------|--------------|---------|-------------------|---------|-------------------------|---------|----------------|---------|
|           |                   |               |           | Value            | Average | Value | Average | Value        | Average | Value             | Average | Value                   | Average | Value          | Average |
| 5-Jun-18  | Rainy             | 14:42         | Middle    | 27.6             | 27.6    | 8.2   | 8.2     | 0.3          | 0.3     | 99.3              | 98.1    | 7.8                     | 7.7     | 7.7            | 7.6     |
|           |                   |               |           | 27.5             |         | 8.2   |         | 0.3          |         | 96.9              |         | 7.6                     |         | 7.5            |         |
| 20-Jun-18 | Sunny             | 13:14         | Middle    | 26.4             | 26.5    | 8.5   | 8.5     | 1.4          | 1.4     | 102.5             | 102.5   | 7.4                     | 7.4     | 3.8            | 3.7     |
|           |                   |               |           | 26.5             |         | 8.5   |         | 1.4          |         | 102.5             |         | 7.4                     |         | 3.6            |         |

**Groundwater Quality Monitoring Results at Stream 2**

| Date      | Weather Condition | Sampling Time | Depth (m) | Temperature (°C) |         | pH    |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         | Turbidity(NTU) |         |
|-----------|-------------------|---------------|-----------|------------------|---------|-------|---------|--------------|---------|-------------------|---------|-------------------------|---------|----------------|---------|
|           |                   |               |           | Value            | Average | Value | Average | Value        | Average | Value             | Average | Value                   | Average | Value          | Average |
| 5-Jun-18  | Rainy             | 13:48         | Middle    | 27.6             | 27.6    | 8.8   | 8.9     | 0.2          | 0.2     | 99.4              | 99.2    | 7.8                     | 7.8     | 72.1           | 72.2    |
|           |                   |               |           | 27.6             |         | 8.9   |         | 0.2          |         | 99.0              |         | 7.8                     |         | 72.2           |         |
| 20-Jun-18 | Sunny             | 15:15         | Middle    | 26.3             | 26.4    | 8.6   | 8.5     | 0.1          | 0.1     | 101.5             | 101.5   | 7.5                     | 7.5     | 3.5            | 3.3     |
|           |                   |               |           | 26.5             |         | 8.4   |         | 0.1          |         | 101.5             |         | 7.5                     |         | 3.1            |         |

**Groundwater Quality Monitoring Results at Stream 3**

| Date      | Weather Condition | Sampling Time | Depth (m) | Temperature (°C) |         | pH    |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         | Turbidity(NTU) |         |
|-----------|-------------------|---------------|-----------|------------------|---------|-------|---------|--------------|---------|-------------------|---------|-------------------------|---------|----------------|---------|
|           |                   |               |           | Value            | Average | Value | Average | Value        | Average | Value             | Average | Value                   | Average | Value          | Average |
| 5-Jun-18  | Rainy             | 14:15         | Middle    | 27.3             | 27.2    | 8.6   | 8.7     | 0.1          | 0.1     | 98.9              | 98.9    | 7.8                     | 7.9     | 86.8           | 86.9    |
|           |                   |               |           | 27.1             |         | 8.8   |         | 0.1          |         | 98.8              |         | 7.9                     |         | 86.9           |         |
| 20-Jun-18 | Sunny             | 15:26         | Middle    | 26.4             | 26.2    | 8.5   | 8.5     | 0.1          | 0.1     | 102.7             | 102.5   | 7.6                     | 7.6     | 4.1            | 4.2     |
|           |                   |               |           | 26.0             |         | 8.5   |         | 0.1          |         | 102.2             |         | 7.5                     |         | 4.2            |         |

**Agreement No. CE/59/2015 (EP)****Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction****Summary of Groundwater Quality Monitoring Results**

| Location | Date      | Parameters (unit) |                         |                 |           |   |                |                       |  |                           |
|----------|-----------|-------------------|-------------------------|-----------------|-----------|---|----------------|-----------------------|--|---------------------------|
|          |           | pH                | Dissolved Oxygen (mg/L) | Turbidity (NTU) | SS (mg/L) | BOD <sub>5</sub> (mg O <sub>2</sub> /L) | TOC (mg-TOC/L) | Total Nitrogen (mg/L) | NH <sub>3</sub> -N (mg NH <sub>3</sub> -N/L) | Total Phosphorus (mg-P/L) |
| Stream 1 | 5-Jun-18  | 8.2               | 7.7                     | 7.6             | 39        | <2                                      | 7              | 2.2                   | 0.1  | 0.11                      |
|          | 20-Jun-18 | 8.5               | 7.4                     | 3.7             | <2.5      | <2                                      | 3              | 0.8                   | 0.11   | <0.05                     |
| Stream 2 | 5-Jun-18  | 8.9               | 7.8                     | 72.2            | 100       | <2                                      | 5              | 1.5                   | <0.05  | <0.05                     |
|          | 20-Jun-18 | 8.5               | 7.5                     | 3.3             | <2.5      | <2                                      | 4              | 1.5                   | <0.05  | <0.05                     |
| Stream 3 | 5-Jun-18  | 8.7               | 7.9                     | 86.9            | 92        | <2                                      | 5              | 1.5                   | <0.05  | 0.06                      |
|          | 20-Jun-18 | 8.5               | 7.6                     | 4.2             | <2.5      | <2                                      | 4              | 1.5                   | <0.05  | <0.05                     |

## TEST REPORT

**APPLICANT:** Cinotech Consultants Limited  
1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T.

|                 |            |
|-----------------|------------|
| Report No.:     | 29033      |
| Date of Issue:  | 2018-06-14 |
| Date Received:  | 2018-06-05 |
| Date Tested:    | 2018-06-05 |
| Date Completed: | 2018-06-14 |

**ATTN:** Ms. Mei Ling Tang

Page: 1 of 1

**Sample Description :** 3 liquid samples as received from client said to be groundwater  
**Laboratory No. :** 29033  
**Project No. :** MA16034 (Groundwater)  
**Project Name :** Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O –  
 Lam Tin Tunnel – Design and Construction  
**Custody No. :** MA16034(Groundwater)/20180605  
**Sampling Date :** 2018-06-05

**Tests Requested & Methodology:**

| Item | Parameters                                    | Ref. Method                               | Limit of reporting           |
|------|---|---|------------------------------|
| 1    | Total Suspended Solids                        | APHA 17ed 2540 D                          | *0.5 mg/L                    |
| 2    | Biochemical Oxygen Demand                     | APHA 19ed 5210B                           | 2 mg O <sub>2</sub> /L       |
| 3    | Total Organic Carbon                          | In-house method SOP020<br>(Wet Oxidation) | 1 mg-TOC/L                   |
| 4    | Nitrogen (Total Kjeldahl + nitrate + nitrite) | In-house method SOP063 (FIA)              | 0.6 mg N/L                   |
| 5    | Ammonia                                       | In-house method SOP057 (FIA)              | 0.05 mg NH <sub>3</sub> -N/L |
| 6    | Total Phosphorus                              | In-house method SOP055 (FIA)              | 0.05 mg-P/L                  |

**Results:**

| Sample ID  | Stream 1 | Stream 2 | Stream 3 |
|--|----------|----------|----------|
| Sampling Depth   | S        | S        | S        |
| Sample No.   | 29033-1  | 29033-2  | 29033-3  |
| Total Suspended Solids (mg/L)                          | 39       | 100      | 92       |
| Biochemical Oxygen Demand (mg O <sub>2</sub> /L)       | <2       | <2       | <2       |
| Total Organic Carbon (mg-TOC/L)                        | 7        | 5        | 5        |
| Nitrogen (Total Kjeldahl + nitrate + nitrite) (mg N/L) | 2.2      | 1.5      | 1.5      |
| Ammonia (mg NH <sub>3</sub> -N/L)                      | 0.10     | <0.05    | <0.05    |
| Total Phosphorus (mg-P/L)                              | 0.11     | <0.05    | 0.06     |

Remarks: 1) < = less than  
 2) S = Surface, M = Middle, B = Bottom  
 3) \* Limit of Reporting is reported as Detection Limit

\*\*\*\*\*END OF REPORT\*\*\*\*\*

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**

  
**PATRICK TSE**  
 Laboratory Manager

## TEST REPORT

**APPLICANT:** Cinotech Consultants Limited  
1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T.

|                 |            |
|-----------------|------------|
| Report No.:     | 29129      |
| Date of Issue:  | 2018-06-29 |
| Date Received:  | 2018-06-20 |
| Date Tested:    | 2018-06-20 |
| Date Completed: | 2018-06-29 |

**ATTN:** Ms. Mei Ling Tang

Page: 1 of 1

**Sample Description** : 3 liquid samples as received from client said to be groundwater  
**Laboratory No.** : 29129  
**Project No.** : MA16034 (Groundwater)  
**Project Name** : Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O –  
 Lam Tin Tunnel – Design and Construction  
**Custody No.** : MA16034(Groundwater)/20180620  
**Sampling Date** : 2018-06-20

### Tests Requested & Methodology:

| Item | Parameters                                    | Ref. Method                               | Limit of reporting           |
|------|---|---|------------------------------|
| 1    | Total Suspended Solids                        | APHA 17ed 2540 D                          | *0.5 mg/L                    |
| 2    | Biochemical Oxygen Demand                     | APHA 19ed 5210B                           | 2 mg O <sub>2</sub> /L       |
| 3    | Total Organic Carbon                          | In-house method SOP020<br>(Wet Oxidation) | 1 mg-TOC/L                   |
| 4    | Nitrogen (Total Kjeldahl + nitrate + nitrite) | In-house method SOP063 (FIA)              | 0.6 mg N/L                   |
| 5    | Ammonia                                       | In-house method SOP057 (FIA)              | 0.05 mg NH <sub>3</sub> -N/L |
| 6    | Total Phosphorus                              | In-house method SOP055 (FIA)              | 0.05 mg-P/L                  |

### Results:

| Sample ID  | Stream 1 | Stream 2 | Stream 3 |
|--|----------|----------|----------|
| Sampling Depth   | S        | S        | S        |
| Sample No.   | 29129-1  | 29129-2  | 29129-3  |
| Total Suspended Solids (mg/L)                          | <2.5     | <2.5     | <2.5     |
| Biochemical Oxygen Demand (mg O <sub>2</sub> /L)       | <2       | <2       | <2       |
| Total Organic Carbon (mg-TOC/L)                        | 3        | 4        | 4        |
| Nitrogen (Total Kjeldahl + nitrate + nitrite) (mg N/L) | 0.8      | 1.5      | 1.5      |
| Ammonia (mg NH <sub>3</sub> -N/L)                      | 0.11     | <0.05    | <0.05    |
| Total Phosphorus (mg-P/L)                              | <0.05    | <0.05    | <0.05    |

Remarks: 1) <= less than  
 2) S = Surface, M = Middle, B = Bottom  
 3) \* Limit of Reporting is reported as Detection Limit




\*\*\*\*\*END OF REPORT\*\*\*\*\*

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**


  
**PATRICK TSE**  
 Laboratory Manager

# pH



|   |                 |                        |  |
|---|-----------------|------------------------|--|
| Title<br>Agreement No. CE 59/2015(EP)<br>Environmental Team for Tseung Kwan O - Lam Tin Tunnel<br>Design and Construction<br><br>Graphical Presentation of Groundwater Quality<br>Monitoring Result | Scale<br>N.T.S  | Project<br>No. MA16034 |  |
|   | Date<br>June 18 | Appendix<br>H          |  |


## Dissolved Oxygen



|   |                 |                        |  |
|---|-----------------|------------------------|--|
| Title<br>Agreement No. CE 59/2015(EP)<br>Environmental Team for Tseung Kwan O - Lam Tin Tunnel<br>Design and Construction<br><br>Graphical Presentation of Groundwater Quality<br>Monitoring Result | Scale<br>N.T.S  | Project<br>No. MA16034 |  |
|   | Date<br>June 18 | Appendix<br>H          |  |






## Turbidity



|   |                 |                        |  |
|---|-----------------|------------------------|--|
| Title<br>Agreement No. CE 59/2015(EP)<br>Environmental Team for Tseung Kwan O - Lam Tin Tunnel<br>Design and Construction<br><br>Graphical Presentation of Groundwater Quality<br>Monitoring Result | Scale<br>N.T.S  | Project<br>No. MA16034 |  |
|   | Date<br>June 18 | Appendix<br>H          |  |


## Suspended Solids



Remarks: The graphical point at zero concentration is presented as <2.5 mg/L

|   |                 |                        |  |
|---|-----------------|------------------------|--|
| Title<br>Agreement No. CE 59/2015(EP)<br>Environmental Team for Tseung Kwan O - Lam Tin Tunnel<br>Design and Construction<br><br>Graphical Presentation of Groundwater Quality<br>Monitoring Result | Scale<br>N.T.S  | Project<br>No. MA16034 |  |
|   | Date<br>June 18 | Appendix<br>H          |  |




## 5-day Biochemical Oxygen Demand (BOD<sub>5</sub>)



Remarks: The graphical point at zero concentration is presented as <2 mg/L


|   |                 |                        |          |
|---|-----------------|------------------------|----------|
| Title<br>Agreement No. CE 59/2015(EP)<br>Environmental Team for Tseung Kwan O - Lam Tin Tunnel<br>Design and Construction<br><br>Graphical Presentation of Groundwater Quality<br>Monitoring Result | Scale<br>N.T.S  | Project<br>No. MA16034 | CINOTECH |
|   | Date<br>June 18 | Appendix<br>H          |          |

## Total Organic Carbon (TOC)



|   |                 |                        |  |
|---|-----------------|------------------------|--|
| Title<br>Agreement No. CE 59/2015(EP)<br>Environmental Team for Tseung Kwan O - Lam Tin Tunnel<br>Design and Construction<br><br>Graphical Presentation of Groundwater Quality<br>Monitoring Result | Scale<br>N.T.S  | Project<br>No. MA16034 |  |
|   | Date<br>June 18 | Appendix<br>H          |  |


## Total Nitrogen



Remarks: The graphical point at zero concentration is presented as <0.6 mg/L

|   |                 |                        |  |
|---|-----------------|------------------------|--|
| Title<br>Agreement No. CE 59/2015(EP)<br>Environmental Team for Tseung Kwan O - Lam Tin Tunnel<br>Design and Construction<br><br>Graphical Presentation of Groundwater Quality<br>Monitoring Result | Scale<br>N.T.S  | Project<br>No. MA16034 |  |
|   | Date<br>June 18 | Appendix<br>H          |  |


# Ammonia-Nitrogen



Remarks: The graphical point at zero concentration is presented as <0.05 mg/L

|   |                 |                        |  |
|---|-----------------|------------------------|--|
| Title<br>Agreement No. CE 59/2015(EP)<br>Environmental Team for Tseung Kwan O - Lam Tin Tunnel<br>Design and Construction<br><br>Graphical Presentation of Groundwater Quality<br>Monitoring Result | Scale<br>N.T.S  | Project<br>No. MA16034 |  |
|   | Date<br>June 18 | Appendix<br>H          |  |

## Total Phosphate



Remarks: The graphical point at zero concentration is presented as <0.05 mg/L

|   |                 |                        |  |
|---|-----------------|------------------------|--|
| Title<br>Agreement No. CE 59/2015(EP)<br>Environmental Team for Tseung Kwan O - Lam Tin Tunnel<br>Design and Construction<br><br>Graphical Presentation of Groundwater Quality<br>Monitoring Result | Scale<br>N.T.S  | Project<br>No. MA16034 |  |
|   | Date<br>June 18 | Appendix<br>H          |  |

---

**APPENDIX I  
MARINE WATER QUALITY  
MONITORING RESULTS AND  
GRAPHICAL PRESENTATIONS**

---



**Appendix I - Action and Limit Levels for Marine Water Quality on 1 June 2018 (Mid-Ebb Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 2.9 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 3.1 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.2 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.8 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.2 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.8 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.6 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.2 mg/L</u>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction**  
**Water Quality Monitoring Results on 01 June 2018**

**(Mid-Ebb Tide)**

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) | Temperature (°C) |              | pH    |            | Salinity ppt |              | DO Saturation (%) |                | Dissolved Oxygen (mg/L) |              |      | Turbidity(NTU) |            |     | Suspended Solids (mg/L) |            |     |     |
|----------|-------------------|-----------------|---------------|-----------|------------------|--------------|-------|------------|--------------|--------------|-------------------|----------------|-------------------------|--------------|------|----------------|------------|-----|-------------------------|------------|-----|-----|
|          |                   |                 |               |           | Value            | Average      | Value | Average    | Value        | Average      | Value             | Average        | Value                   | Average      | DA*  | Value          | Average    | DA* | Value                   | Average    | DA* |     |
| C1       | Cloudy            | Moderate        | 15:05         | Surface   | 1                | 25.6<br>25.9 | 25.8  | 8.2<br>8.1 | 8.2          | 33.3<br>33.2 | 33.2              | 86.6<br>88.2   | 87.4                    | 5.9<br>6.0   | 6.0  | 5.8            | 1.4<br>1.3 | 1.4 | 1.6                     | 5.6<br>5.5 | 5.6 | 5.3 |
|          |                   |                 |               | Middle    | 9                | 24.1<br>24.2 | 24.2  | 8.2<br>8.2 | 8.2          | 34.4<br>34.3 | 34.4              | 81.0<br>81.3   | 81.2                    | 5.6<br>5.6   | 5.6  |                | 1.6<br>1.7 | 1.7 |                         | 4.1<br>4.1 | 4.1 |     |
|          |                   |                 |               | Bottom    | 17               | 23.7<br>23.8 | 23.8  | 8.1<br>8.1 | 8.1          | 34.6<br>34.5 | 34.6              | 77.8<br>78.4   | 78.1                    | 5.4<br>5.4   | 5.4  |                | 1.7<br>1.6 | 1.7 |                         | 6.1<br>6.1 | 6.1 |     |
| C2       | Cloudy            | Moderate        | 13:57         | Surface   | 1                | 26.6<br>26.8 | 26.7  | 8.1<br>8.1 | 8.1          | 32.6<br>32.3 | 32.5              | 97.2<br>97.8   | 97.5                    | 6.5<br>6.5   | 6.5  | 6.1            | 0.6<br>0.7 | 0.7 | 1.5                     | 5.2<br>5.1 | 5.2 | 4.9 |
|          |                   |                 |               | Middle    | 16.5             | 24.9<br>24.5 | 24.7  | 8.1<br>8.1 | 8.1          | 33.9<br>34.1 | 34.0              | 84.2<br>81.9   | 83.1                    | 5.8<br>5.6   | 5.7  |                | 1.4<br>1.5 | 1.5 |                         | 4.0<br>3.9 | 4.0 |     |
|          |                   |                 |               | Bottom    | 32               | 23.8<br>24.0 | 23.9  | 8.1<br>8.1 | 8.1          | 34.5<br>34.4 | 34.5              | 78.7<br>78.5   | 78.6                    | 5.5<br>5.4   | 5.5  |                | 2.4<br>2.4 | 2.4 |                         | 5.4<br>5.5 | 5.5 |     |
| G1       | Cloudy            | Moderate        | 14:29         | Surface   | 1                | 27.3<br>27.1 | 27.2  | 8.4<br>8.4 | 8.4          | 33.2<br>33.3 | 33.3              | 152.4<br>148.0 | 150.2                   | 10.0<br>9.8  | 9.9  | 9.3            | 0.6<br>0.6 | 0.6 | 1.0                     | 4.8<br>4.7 | 4.8 | 4.2 |
|          |                   |                 |               | Middle    | 4                | 26.4<br>26.3 | 26.4  | 8.3<br>8.3 | 8.3          | 33.5<br>33.5 | 33.5              | 133.2<br>127.5 | 130.4                   | 8.9<br>8.5   | 8.7  |                | 0.8<br>0.8 | 0.8 |                         | 3.0<br>3.0 | 3.0 |     |
|          |                   |                 |               | Bottom    | 7                | 24.4<br>24.6 | 24.5  | 8.2<br>8.1 | 8.2          | 34.3<br>34.3 | 34.3              | 85.0<br>83.7   | 84.4                    | 5.8<br>5.7   | 5.8  |                | 1.4<br>1.5 | 1.5 |                         | 4.8<br>4.8 | 4.8 |     |
| G2       | Cloudy            | Moderate        | 14:17         | Surface   | 1                | 26.5<br>26.5 | 26.5  | 8.3<br>8.3 | 8.3          | 33.5<br>33.5 | 33.5              | 134.3<br>132.9 | 133.6                   | 9.0<br>8.9   | 9.0  | 8.2            | 0.7<br>0.7 | 0.7 | 0.9                     | 4.8<br>4.7 | 4.8 | 5.7 |
|          |                   |                 |               | Middle    | 5                | 25.3<br>25.4 | 25.4  | 8.2<br>8.2 | 8.2          | 33.9<br>33.9 | 33.9              | 106.2<br>108.1 | 107.2                   | 7.2<br>7.3   | 7.3  |                | 0.8<br>0.8 | 0.8 |                         | 6.0<br>6.2 | 6.1 |     |
|          |                   |                 |               | Bottom    | 9                | 24.3<br>24.3 | 24.3  | 8.1<br>8.1 | 8.1          | 34.4<br>34.4 | 34.4              | 80.2<br>81.0   | 80.6                    | 5.5<br>5.6   | 5.6  |                | 1.1<br>1.2 | 1.2 |                         | 6.2<br>6.3 | 6.3 |     |
| G3       | Cloudy            | Moderate        | 14:35         | Surface   | 1                | 27.6<br>27.5 | 27.6  | 8.4<br>8.4 | 8.4          | 33.2<br>33.2 | 33.2              | 157.3<br>156.0 | 156.7                   | 10.3<br>10.2 | 10.3 | 9.6            | 0.6<br>0.6 | 0.6 | 1.2                     | 5.9<br>5.8 | 5.9 | 5.8 |
|          |                   |                 |               | Middle    | 4                | 27.0<br>27.0 | 27.0  | 8.3<br>8.3 | 8.3          | 33.3<br>33.3 | 33.3              | 133.7<br>135.8 | 134.8                   | 8.8<br>9.0   | 8.9  |                | 1.4<br>1.5 | 1.5 |                         | 5.3<br>6.2 | 5.8 |     |
|          |                   |                 |               | Bottom    | 7                | 24.6<br>24.4 | 24.5  | 8.1<br>8.1 | 8.1          | 34.2<br>34.3 | 34.3              | 83.8<br>81.3   | 82.6                    | 5.7<br>5.6   | 5.7  |                | 1.5<br>1.5 | 1.5 |                         | 5.8<br>5.8 | 5.8 |     |
| G4       | Cloudy            | Moderate        | 14:47         | Surface   | 1                | 26.9<br>27.0 | 27.0  | 8.4<br>8.4 | 8.4          | 33.3<br>33.3 | 33.3              | 146.1<br>145.9 | 146.0                   | 9.7<br>9.7   | 9.7  | 9.5            | 0.6<br>0.7 | 0.7 | 0.8                     | 4.0<br>4.0 | 4.0 | 3.9 |
|          |                   |                 |               | Middle    | 4                | 26.7<br>26.7 | 26.7  | 8.3<br>8.3 | 8.3          | 33.3<br>33.3 | 33.3              | 139.6<br>137.8 | 138.7                   | 9.3<br>9.2   | 9.3  |                | 0.6<br>0.6 | 0.6 |                         | 3.2<br>3.1 | 3.2 |     |
|          |                   |                 |               | Bottom    | 7                | 24.6<br>24.6 | 24.6  | 8.2<br>8.2 | 8.2          | 34.2<br>34.2 | 34.2              | 89.1<br>87.1   | 88.1                    | 6.1<br>6.0   | 6.1  |                | 1.1<br>1.1 | 1.1 |                         | 4.4<br>4.7 | 4.6 |     |
| M1       | Cloudy            | Moderate        | 14:25         | Surface   | 1                | 27.2<br>27.1 | 27.2  | 8.4<br>8.4 | 8.4          | 33.3<br>33.3 | 33.3              | 150.5<br>148.6 | 149.6                   | 9.9<br>9.8   | 9.9  | 9.7            | 0.7<br>0.6 | 0.7 | 0.8                     | 3.6<br>3.6 | 3.6 | 3.8 |
|          |                   |                 |               | Middle    | 3                | 26.7<br>26.7 | 26.7  | 8.3<br>8.3 | 8.3          | 33.4<br>33.3 | 33.4              | 140.8<br>141.0 | 140.9                   | 9.4<br>9.4   | 9.4  |                | 0.6<br>0.6 | 0.6 |                         | 3.9<br>3.9 | 3.9 |     |
|          |                   |                 |               | Bottom    | 5                | 25.0<br>25.1 | 25.1  | 8.2<br>8.2 | 8.2          | 34.1<br>34.0 | 34.1              | 96.9<br>97.2   | 97.1                    | 6.6<br>6.6   | 6.6  |                | 0.9<br>1.0 | 1.0 |                         | 3.9<br>4.0 | 4.0 |     |
| M2       | Cloudy            | Moderate        | 14:11         | Surface   | 1                | 27.1<br>27.2 | 27.2  | 8.4<br>8.4 | 8.4          | 33.3<br>33.3 | 33.3              | 152.0<br>151.0 | 151.5                   | 10.0<br>10.0 | 10.0 | 8.5            | 0.6<br>0.6 | 0.6 | 1.2                     | 5.9<br>5.9 | 5.9 | 4.9 |
|          |                   |                 |               | Middle    | 6                | 24.9<br>24.9 | 24.9  | 8.2<br>8.2 | 8.2          | 34.1<br>34.1 | 34.1              | 101.6<br>99.7  | 100.7                   | 6.9<br>6.8   | 6.9  |                | 0.7<br>0.8 | 0.8 |                         | 4.3<br>4.3 | 4.3 |     |
|          |                   |                 |               | Bottom    | 11               | 23.7<br>23.7 | 23.7  | 8.1<br>8.1 | 8.1          | 34.7<br>34.7 | 34.7              | 75.9<br>76.1   | 76.0                    | 5.3<br>5.3   | 5.3  |                | 2.3<br>2.3 | 2.3 |                         | 4.6<br>4.5 | 4.6 |     |
| M3       | Cloudy            | Moderate        | 14:40         | Surface   | 1                | 27.4<br>27.4 | 27.4  | 8.4<br>8.4 | 8.4          | 33.2<br>33.2 | 33.2              | 146.6<br>149.1 | 147.9                   | 9.6<br>9.8   | 9.7  | 9.3            | 0.6<br>0.6 | 0.6 | 1.2                     | 3.1<br>3.3 | 3.2 | 4.6 |
|          |                   |                 |               | Middle    | 4                | 27.1<br>27.1 | 27.1  | 8.3<br>8.3 | 8.3          | 33.3<br>33.3 | 33.3              | 133.3<br>134.0 | 133.7                   | 8.8<br>8.9   | 8.9  |                | 1.4<br>1.3 | 1.4 |                         | 5.5<br>5.6 | 5.6 |     |
|          |                   |                 |               | Bottom    | 7                | 24.4<br>24.4 | 24.4  | 8.1<br>8.1 | 8.1          | 34.4<br>34.4 | 34.4              | 80.4<br>79.1   | 79.8                    | 5.5<br>5.4   | 5.5  |                | 1.6<br>1.6 | 1.6 |                         | 5.1<br>5.0 | 5.1 |     |
| M4       | Cloudy            | Moderate        | 14:05         | Surface   | 1                | 26.6<br>26.6 | 26.6  | 8.3<br>8.3 | 8.3          | 33.4<br>33.4 | 33.4              | 131.5<br>132.4 | 132.0                   | 8.8<br>8.8   | 8.8  | 8.4            | 0.8<br>0.7 | 0.8 | 0.7                     | 5.8<br>5.9 | 5.9 | 5.4 |
|          |                   |                 |               | Middle    | 5                | 25.7<br>25.6 | 25.7  | 8.3<br>8.3 | 8.3          | 33.7<br>33.7 | 33.7              | 118.6<br>117.9 | 118.3                   | 8.0<br>8.0   | 8.0  |                | 0.7<br>0.7 | 0.7 |                         | 4.6<br>4.7 | 4.7 |     |
|          |                   |                 |               | Bottom    | 9                | 24.9<br>24.7 | 24.8  | 8.2<br>8.2 | 8.2          | 34.0<br>34.1 | 34.1              | 98.3<br>95.6   | 97.0                    | 6.7<br>6.5   | 6.6  |                | 0.7<br>0.7 | 0.7 |                         | 5.5<br>5.7 | 5.6 |     |
| M5       | Cloudy            | Moderate        | 14:58         | Surface   | 1                | 25.8<br>25.7 | 25.8  | 8.2<br>8.2 | 8.2          | 33.4<br>33.4 | 33.4              | 101.7<br>100.8 | 101.3                   | 6.9<br>6.8   | 6.9  | 6.9            | 0.9<br>0.9 | 0.9 | 1.0                     | 3.4<br>3.5 | 3.5 | 3.5 |
|          |                   |                 |               | Middle    | 5.5              | 25.8<br>25.7 | 25.8  | 8.2<br>8.2 | 8.2          | 33.4<br>33.4 | 33.4              | 100.9<br>100.7 | 100.8                   | 6.8<br>6.8   | 6.8  |                | 0.9<br>0.9 | 0.9 |                         | 3.6<br>3.6 | 3.6 |     |
|          |                   |                 |               | Bottom    | 10               | 25.7<br>25.7 | 25.7  | 8.2<br>8.2 | 8.2          | 33.4<br>33.4 | 33.4              | 99.7<br>100.7  | 100.2                   | 6.7<br>6.8   | 6.8  |                | 1.2<br>1.1 | 1.2 |                         | 3.3<br>3.4 | 3.4 |     |
| M6       | Cloudy            | Moderate        | 14:53         | Surface   | -                | -            | -     | -          | -            | -            | -                 | -              | -                       | -            | 9.4  | -              | -          | 0.8 | -                       | -          | 4.8 |     |
|          |                   |                 |               | Middle    | 2                | 26.5<br>26.5 | 26.5  | 8.3<br>8.3 | 8.3          | 33.4<br>33.4 | 33.4              | 140.5<br>141.0 | 140.8                   | 9.4<br>9.4   |      | 9.4            | 0.8<br>0.8 |     | 0.8                     | 4.8<br>4.7 |     | 4.8 |
|          |                   |                 |               | Bottom    | -                | -            | -     | -          | -            | -            | -                 | -              | -                       | -            |      | -              | -          |     | -                       | -          |     | -   |

Remarks: \*DA: Depth-Averaged  
\*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

**Appendix I - Action and Limit Levels for Marine Water Quality on 1 June 2018 (Mid-Flood Tide)**

| <b><u>Parameter</u></b><br><b><u>(unit)</u></b> | <b><u>Depth</u></b>                 | <b><u>Action Level</u></b>  | <b><u>Limit Level</u></b>   |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)                | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <b><u>4.9 mg/L</u></b>  | <b><u>4.6 mg/L</u></b>  |
|   | Bottom                              | <b><u>4.2 mg/L</u></b>  | <b><u>3.6 mg/L</u></b>  |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <b><u>5.0 mg/L</u></b>  | <b><u>4.7 mg/L</u></b>  |
| Turbidity in<br>NTU<br>(See Note 2 and 4)       | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <b><u>19.3 NTU</u></b><br>or 120% of upstream control<br>station's Turbidity at the same<br>tide of the same day<br><b><u>CI: 2.8 NTU</u></b> | <b><u>22.2 NTU</u></b><br>or 130% of upstream control<br>station's Turbidity at the same tide<br>of the same day<br><b><u>CI: 3.0 NTU</u></b> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <b><u>19.0 NTU</u></b>  | <b><u>19.4 NTU</u></b>  |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface   |                                     | <b><u>6.0 mg/L</u></b><br>or 120% of upstream control<br>station's SS at the same tide of<br>the same day<br><b><u>CI: 7.0 mg/L</u></b>       | <b><u>6.9 mg/L</u></b><br>or 130% of upstream control<br>station's SS at the same tide of the<br>same day<br><b><u>CI: 7.5 mg/L</u></b>       |
| <b><u>Stations M1-M5</u></b>                    |                                     |   |   |
| Surface   |                                     | <b><u>6.2 mg/L</u></b><br>or 120% of upstream control<br>station's SS at the same tide of<br>the same day<br><b><u>CI: 7.0 mg/L</u></b>       | <b><u>7.4 mg/L</u></b><br>or 130% of upstream control<br>station's SS at the same tide of the<br>same day<br><b><u>CI: 7.5 mg/L</u></b>       |
| <b><u>Stations G1-G4, M1-M5</u></b>             |                                     |   |   |
| Bottom  |                                     | <b><u>6.9 mg/L</u></b><br>or 120% of upstream control<br>station's SS at the same tide of<br>the same day<br><b><u>CI: 7.7 mg/L</u></b>       | <b><u>7.9 mg/L</u></b><br>or 130% of upstream control<br>station's SS at the same tide of the<br>same day<br><b><u>CI: 8.3 mg/L</u></b>       |
| <b><u>Station M6</u></b>                        |                                     |   |   |
| Intake Level                                    | <b><u>8.3 mg/L</u></b>              | <b><u>8.6 mg/L</u></b>  |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction**  
**Water Quality Monitoring Results on 01 June 2018**

**(Mid-Flood Tide)**

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) | Temperature (°C) |              | pH    |            | Salinity ppt |              | DO Saturation (%) |                | Dissolved Oxygen (mg/L) |            |     | Turbidity(NTU) |            |     | Suspended Solids (mg/L) |            |     |     |
|----------|-------------------|-----------------|---------------|-----------|------------------|--------------|-------|------------|--------------|--------------|-------------------|----------------|-------------------------|------------|-----|----------------|------------|-----|-------------------------|------------|-----|-----|
|          |                   |                 |               |           | Value            | Average      | Value | Average    | Value        | Average      | Value             | Average        | Value                   | Average    | DA* | Value          | Average    | DA* | Value                   | Average    | DA* |     |
| C1       | Cloudy            | Moderate        | 08:15         | Surface   | 1                | 25.9<br>25.9 | 25.9  | 8.2<br>8.2 | 8.2          | 33.5<br>33.5 | 33.5              | 98.9<br>98.2   | 98.6                    | 6.7<br>6.6 | 6.7 | 6.5            | 1.0<br>1.0 | 1.0 | 1.5                     | 5.8<br>5.8 | 5.8 | 6.2 |
|          |                   |                 |               | Middle    | 9                | 25.0<br>25.1 | 25.1  | 8.2<br>8.2 | 8.2          | 33.9<br>33.8 | 33.9              | 91.1<br>91.8   | 91.5                    | 6.2<br>6.3 | 6.3 |                | 1.3<br>1.3 | 1.3 |                         | 6.2<br>6.3 | 6.3 |     |
|          |                   |                 |               | Bottom    | 17               | 23.4<br>23.4 | 23.4  | 8.2<br>8.2 | 8.2          | 34.8<br>34.8 | 34.8              | 79.0<br>78.9   | 79.0                    | 5.5<br>5.5 | 5.5 |                | 2.2<br>2.3 | 2.3 |                         | 6.5<br>6.3 | 6.4 |     |
| C2       | Cloudy            | Moderate        | 07:00         | Surface   | 1                | 25.1<br>25.6 | 25.4  | 8.1<br>8.2 | 8.2          | 33.8<br>33.5 | 33.7              | 89.9<br>95.5   | 92.7                    | 6.1<br>6.5 | 6.1 | 5.9            | 0.7<br>0.6 | 0.7 | 1.7                     | 5.4<br>5.5 | 5.5 | 4.5 |
|          |                   |                 |               | Middle    | 16.5             | 23.4<br>23.4 | 23.4  | 8.1<br>8.1 | 8.1          | 34.7<br>34.8 | 34.8              | 77.9<br>78.6   | 78.3                    | 5.4<br>5.5 | 5.5 |                | 1.8<br>1.9 | 1.9 |                         | 4.8<br>4.6 | 4.7 |     |
|          |                   |                 |               | Bottom    | 32               | 23.3<br>23.3 | 23.3  | 8.1<br>8.1 | 8.1          | 34.8<br>34.8 | 34.8              | 77.1<br>76.8   | 77.0                    | 5.4<br>5.4 | 5.4 |                | 2.4<br>2.3 | 2.4 |                         | 3.4<br>3.3 | 3.4 |     |
| G1       | Cloudy            | Moderate        | 07:41         | Surface   | 1                | 26.0<br>26.0 | 26.0  | 8.2<br>8.2 | 8.2          | 33.4<br>33.4 | 33.4              | 106.0<br>100.1 | 103.1                   | 7.1<br>6.7 | 7.1 | 6.3            | 0.9<br>0.9 | 0.9 | 1.6                     | 5.3<br>5.3 | 5.3 | 6.0 |
|          |                   |                 |               | Middle    | 4                | 24.6<br>24.6 | 24.6  | 8.2<br>8.1 | 8.2          | 34.2<br>34.2 | 34.2              | 81.6<br>81.4   | 81.5                    | 5.6<br>5.6 | 5.6 |                | 1.3<br>1.3 | 1.3 |                         | 6.6<br>6.3 | 6.5 |     |
|          |                   |                 |               | Bottom    | 7                | 24.0<br>24.0 | 24.0  | 8.1<br>8.1 | 8.1          | 34.6<br>34.6 | 34.6              | 77.7<br>77.2   | 77.5                    | 5.4<br>5.3 | 5.4 |                | 2.6<br>2.5 | 2.6 |                         | 6.1<br>6.1 | 6.1 |     |
| G2       | Cloudy            | Moderate        | 07:23         | Surface   | 1                | 26.1<br>26.4 | 26.3  | 8.2<br>8.2 | 8.2          | 33.4<br>33.2 | 33.3              | 107.4<br>111.3 | 109.4                   | 7.2<br>7.5 | 7.4 | 6.5            | 0.7<br>0.7 | 0.7 | 1.3                     | 4.3<br>4.6 | 4.5 | 5.4 |
|          |                   |                 |               | Middle    | 5                | 24.4<br>24.3 | 24.4  | 8.1<br>8.1 | 8.1          | 34.3<br>34.4 | 34.4              | 80.2<br>77.8   | 79.0                    | 5.5<br>5.4 | 5.5 |                | 1.5<br>1.5 | 1.5 |                         | 5.1<br>5.2 | 5.2 |     |
|          |                   |                 |               | Bottom    | 9                | 23.9<br>23.9 | 23.9  | 8.1<br>8.1 | 8.1          | 34.6<br>34.6 | 34.6              | 78.0<br>76.9   | 77.5                    | 5.4<br>5.3 | 5.4 |                | 1.8<br>1.7 | 1.8 |                         | 6.5<br>6.5 | 6.5 |     |
| G3       | Cloudy            | Moderate        | 07:46         | Surface   | 1                | 25.3<br>26.0 | 25.7  | 8.2<br>8.2 | 8.2          | 33.8<br>33.6 | 33.6              | 94.9<br>102.9  | 98.9                    | 6.4<br>6.9 | 6.4 | 6.1            | 1.0<br>0.8 | 0.9 | 1.6                     | 5.6<br>5.7 | 5.7 | 5.1 |
|          |                   |                 |               | Middle    | 4                | 24.4<br>24.5 | 24.5  | 8.1<br>8.2 | 8.2          | 34.3<br>34.3 | 34.3              | 79.2<br>81.3   | 80.3                    | 5.4<br>5.6 | 5.5 |                | 1.7<br>1.6 | 1.7 |                         | 5.5<br>5.3 | 5.4 |     |
|          |                   |                 |               | Bottom    | 7                | 24.0<br>24.1 | 24.1  | 8.1<br>8.1 | 8.1          | 34.6<br>34.5 | 34.6              | 76.1<br>77.0   | 76.6                    | 5.3<br>5.3 | 5.3 |                | 2.1<br>2.2 | 2.2 |                         | 4.3<br>4.3 | 4.3 |     |
| G4       | Cloudy            | Moderate        | 07:56         | Surface   | 1                | 25.7<br>25.8 | 25.8  | 8.2<br>8.2 | 8.2          | 33.6<br>33.5 | 33.6              | 96.2<br>97.1   | 96.7                    | 6.5<br>6.5 | 6.5 | 6.0            | 0.6<br>0.9 | 0.9 | 1.3                     | 4.7<br>4.9 | 4.8 | 4.7 |
|          |                   |                 |               | Middle    | 4                | 24.5<br>24.4 | 24.5  | 8.1<br>8.1 | 8.1          | 34.2<br>34.3 | 34.3              | 77.0<br>78.0   | 77.5                    | 5.3<br>5.4 | 5.4 |                | 2.0<br>2.0 | 2.0 |                         | 4.6<br>4.6 | 4.6 |     |
|          |                   |                 |               | Bottom    | 7                | 24.0<br>24.0 | 24.0  | 8.1<br>8.1 | 8.1          | 34.5<br>34.5 | 34.5              | 77.2<br>77.2   | 77.2                    | 5.3<br>5.3 | 5.3 |                | 1.1<br>1.1 | 1.1 |                         | 4.8<br>4.8 | 4.8 |     |
| M1       | Cloudy            | Moderate        | 07:29         | Surface   | 1                | 25.9<br>25.9 | 25.9  | 8.2<br>8.2 | 8.2          | 33.6<br>33.5 | 33.6              | 98.4<br>99.6   | 99.0                    | 6.6<br>6.7 | 6.7 | 6.5            | 0.9<br>0.9 | 0.9 | 1.3                     | 4.9<br>4.7 | 4.8 | 5.1 |
|          |                   |                 |               | Middle    | 3                | 25.2<br>25.3 | 25.3  | 8.2<br>8.2 | 8.2          | 33.9<br>33.8 | 33.9              | 90.2<br>91.7   | 90.7                    | 6.1<br>6.2 | 6.2 |                | 1.4<br>1.2 | 1.3 |                         | 5.1<br>5.1 | 5.1 |     |
|          |                   |                 |               | Bottom    | 5                | 24.4<br>24.4 | 24.4  | 8.2<br>8.2 | 8.2          | 34.3<br>34.4 | 34.4              | 81.7<br>82.5   | 82.1                    | 5.6<br>5.7 | 5.7 |                | 1.9<br>1.7 | 1.8 |                         | 5.3<br>5.5 | 5.4 |     |
| M2       | Cloudy            | Moderate        | 07:19         | Surface   | 1                | 26.2<br>26.2 | 26.2  | 8.2<br>8.2 | 8.2          | 33.3<br>33.3 | 33.3              | 109.9<br>109.4 | 109.7                   | 7.4<br>7.3 | 7.4 | 6.6            | 0.6<br>0.6 | 0.6 | 1.2                     | 4.8<br>4.7 | 4.8 | 5.2 |
|          |                   |                 |               | Middle    | 6                | 24.1<br>24.0 | 24.1  | 8.2<br>8.2 | 8.2          | 34.6<br>34.5 | 34.6              | 83.8<br>82.9   | 83.4                    | 5.8<br>5.7 | 5.8 |                | 1.1<br>1.0 | 1.1 |                         | 4.8<br>4.7 | 4.8 |     |
|          |                   |                 |               | Bottom    | 11               | 23.5<br>23.5 | 23.5  | 8.1<br>8.1 | 8.1          | 34.8<br>34.8 | 34.8              | 77.6<br>77.4   | 77.5                    | 5.4<br>5.4 | 5.4 |                | 2.1<br>1.9 | 2.0 |                         | 5.9<br>5.8 | 5.9 |     |
| M3       | Cloudy            | Moderate        | 07:51         | Surface   | 1                | 26.2<br>25.8 | 26.0  | 8.2<br>8.2 | 8.2          | 33.5<br>33.6 | 33.6              | 94.0<br>93.9   | 94.0                    | 6.3<br>6.3 | 6.3 | 5.8            | 1.3<br>1.4 | 1.4 | 2.1                     | 5.9<br>6.0 | 6.0 | 5.9 |
|          |                   |                 |               | Middle    | 4                | 24.3<br>24.3 | 24.3  | 8.1<br>8.1 | 8.1          | 34.4<br>34.4 | 34.4              | 74.6<br>76.1   | 75.4                    | 5.1<br>5.2 | 5.2 |                | 2.6<br>2.7 | 2.7 |                         | 5.5<br>5.7 | 5.6 |     |
|          |                   |                 |               | Bottom    | 7                | 24.1<br>24.1 | 24.1  | 8.1<br>8.1 | 8.1          | 34.5<br>34.5 | 34.5              | 75.1<br>75.6   | 75.4                    | 5.2<br>5.2 | 5.2 |                | 2.3<br>2.3 | 2.3 |                         | 6.3<br>6.1 | 6.2 |     |
| M4       | Cloudy            | Moderate        | 07:11         | Surface   | 1                | 26.2<br>26.4 | 26.3  | 8.2<br>8.2 | 8.2          | 33.1<br>33.1 | 33.1              | 104.6<br>106.4 | 105.5                   | 7.0<br>7.1 | 7.1 | 6.9            | 0.5<br>0.5 | 0.5 | 0.9                     | 3.9<br>3.9 | 3.9 | 4.1 |
|          |                   |                 |               | Middle    | 5                | 25.8<br>25.8 | 25.8  | 8.2<br>8.2 | 8.2          | 33.3<br>33.2 | 33.3              | 97.8<br>99.3   | 98.6                    | 6.6<br>6.7 | 6.7 |                | 0.6<br>0.6 | 0.6 |                         | 3.4<br>3.5 | 3.5 |     |
|          |                   |                 |               | Bottom    | 9                | 23.8<br>23.9 | 23.9  | 8.2<br>8.1 | 8.2          | 34.6<br>34.5 | 34.6              | 82.4<br>80.2   | 81.3                    | 5.7<br>5.6 | 5.7 |                | 1.7<br>1.5 | 1.6 |                         | 5.0<br>5.0 | 5.0 |     |
| M5       | Cloudy            | Moderate        | 08:08         | Surface   | 1                | 26.3<br>26.4 | 26.4  | 8.2<br>8.2 | 8.2          | 33.1<br>33.1 | 33.1              | 104.8<br>103.4 | 104.1                   | 7.0<br>6.9 | 7.0 | 6.6            | 0.5<br>0.5 | 0.5 | 0.6                     | 5.7<br>6.0 | 5.9 | 4.3 |
|          |                   |                 |               | Middle    | 5.5              | 25.1<br>25.4 | 25.3  | 8.2<br>8.2 | 8.2          | 33.7<br>33.6 | 33.7              | 88.1<br>91.2   | 89.7                    | 6.0<br>6.2 | 6.1 |                | 0.6<br>0.6 | 0.6 |                         | 3.9<br>4.0 | 4.0 |     |
|          |                   |                 |               | Bottom    | 10               | 24.3<br>24.2 | 24.3  | 8.2<br>8.2 | 8.2          | 34.3<br>34.3 | 34.3              | 82.3<br>82.2   | 82.3                    | 5.7<br>5.7 | 5.7 |                | 0.8<br>0.8 | 0.8 |                         | 3.0<br>3.1 | 3.1 |     |
| M6       | Cloudy            | Moderate        | 08:02         | Surface   | -                | -            | -     | -          | -            | -            | -                 | -              | -                       | -          | 6.2 | -              | -          | 0.6 | -                       | -          | 5.7 |     |
|          |                   |                 |               | Middle    | 2                | 25.6<br>25.6 | 25.6  | 8.2<br>8.2 | 8.2          | 33.6<br>33.6 | 33.6              | 91.3<br>91.5   | 91.4                    | 6.2<br>6.2 |     | 6.2            | 0.6<br>0.6 |     | 0.6                     | 5.7<br>5.6 |     | 5.7 |
|          |                   |                 |               | Bottom    | -                | -            | -     | -          | -            | -            | -                 | -              | -                       | -          |     | -              | -          |     | -                       | -          |     | -   |

Remarks: \*DA: Depth-Averaged  
\*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

**Appendix I - Action and Limit Levels for Marine Water Quality on 4 June 2018 (Mid-Ebb Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 4.8 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 5.2 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.1 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.6 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.1 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.6 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.8 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 8.5 mg/L</u>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction**  
**Water Quality Monitoring Results on 04 June 2018**

**(Mid-Ebb Tide)**

| Location | Weather Condition | Sea Condition* | Sampling Time | Depth (m) |      | Temperature (°C) |         | pH    |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         |     | Turbidity(NTU) |         |     | Suspended Solids (mg/L) |         |     |
|----------|-------------------|----------------|---------------|-----------|------|------------------|---------|-------|---------|--------------|---------|-------------------|---------|-------------------------|---------|-----|----------------|---------|-----|-------------------------|---------|-----|
|          |                   |                |               |           |      | Value            | Average | Value | Average | Value        | Average | Value             | Average | Value                   | Average | DA* | Value          | Average | DA* | Value                   | Average | DA* |
| C1       | Cloudy            | Moderate       | 16:28         | Surface   | 1    | 27.9             | 27.9    | 8.4   | 8.4     | 31.9         | 31.9    | 113.5             | 114.6   | 7.5                     | 7.6     | 7.4 | 1.1            | 1.1     | 1.7 | 4.8                     | 4.9     | 4.1 |
|          |                   |                |               | Middle    | 9    | 27.5             | 27.5    | 8.3   | 8.3     | 32.2         | 32.2    | 107.7             | 107.8   | 7.1                     | 7.1     |     | 1.4            | 1.5     |     | 4.1                     | 4.2     |     |
|          |                   |                |               | Bottom    | 17   | 26.1             | 26.1    | 8.2   | 8.2     | 33.1         | 33.2    | 85.3              | 84.2    | 5.7                     | 5.7     |     | 2.5            | 2.6     |     | 3.3                     | 3.3     |     |
| C2       | Cloudy            | Moderate       | 15:09         | Surface   | 1    | 27.4             | 27.4    | 8.3   | 8.3     | 32.2         | 32.2    | 104.5             | 105.0   | 6.9                     | 7.0     | 6.5 | 2.0            | 2.0     | 2.9 | 5.1                     | 5.1     | 6.0 |
|          |                   |                |               | Middle    | 16.5 | 26.7             | 26.6    | 8.2   | 8.2     | 32.7         | 32.8    | 92.9              | 86.8    | 6.2                     | 5.8     |     | 2.7            | 2.6     |     | 6.4                     | 6.4     |     |
|          |                   |                |               | Bottom    | 32   | 26.1             | 26.1    | 8.2   | 8.2     | 33.1         | 33.1    | 84.9              | 82.9    | 5.7                     | 5.7     |     | 4.0            | 3.9     |     | 6.6                     | 6.4     |     |
| G1       | Cloudy            | Moderate       | 15:52         | Surface   | 1    | 27.8             | 27.9    | 8.3   | 8.4     | 31.9         | 31.9    | 108.6             | 110.4   | 7.1                     | 7.3     | 6.9 | 1.4            | 1.3     | 3.0 | 5.5                     | 5.6     | 5.3 |
|          |                   |                |               | Middle    | 4    | 27.4             | 27.4    | 8.3   | 8.3     | 32.2         | 32.3    | 98.0              | 97.5    | 6.5                     | 6.4     |     | 3.4            | 3.7     |     | 5.3                     | 5.4     |     |
|          |                   |                |               | Bottom    | 7    | 27.1             | 27.2    | 8.3   | 8.3     | 32.4         | 32.4    | 92.9              | 93.6    | 6.2                     | 6.2     |     | 4.1            | 4.1     |     | 5.0                     | 4.9     |     |
| G2       | Cloudy            | Moderate       | 15:33         | Surface   | 1    | 28.0             | 28.0    | 8.4   | 8.4     | 31.8         | 31.8    | 114.2             | 114.1   | 7.5                     | 7.5     | 7.5 | 1.4            | 1.3     | 1.7 | 4.0                     | 4.1     | 7.1 |
|          |                   |                |               | Middle    | 5    | 27.9             | 27.9    | 8.4   | 8.4     | 31.9         | 31.9    | 110.7             | 112.0   | 7.3                     | 7.4     |     | 1.5            | 1.4     |     | 10.4                    | 10.6    |     |
|          |                   |                |               | Bottom    | 9    | 26.9             | 27.1    | 8.2   | 8.3     | 32.6         | 32.5    | 93.4              | 100.1   | 6.2                     | 6.4     |     | 2.4            | 2.4     |     | 6.5                     | 6.6     |     |
| G3       | Cloudy            | Moderate       | 15:58         | Surface   | 1    | 27.9             | 28.0    | 8.4   | 8.4     | 31.4         | 31.7    | 114.9             | 115.2   | 7.6                     | 7.6     | 7.7 | 1.4            | 1.4     | 2.3 | 4.1                     | 4.1     | 4.5 |
|          |                   |                |               | Middle    | 4    | 27.9             | 27.9    | 8.4   | 8.4     | 31.9         | 31.9    | 116.8             | 116.0   | 7.7                     | 7.7     |     | 1.2            | 1.2     |     | 3.8                     | 3.8     |     |
|          |                   |                |               | Bottom    | 7    | 27.5             | 27.5    | 8.3   | 8.3     | 32.3         | 32.3    | 97.7              | 94.5    | 6.4                     | 6.3     |     | 4.2            | 4.4     |     | 5.9                     | 5.5     |     |
| G4       | Cloudy            | Moderate       | 16:08         | Surface   | 1    | 28.0             | 28.1    | 8.4   | 8.4     | 31.9         | 31.9    | 120.7             | 122.4   | 7.9                     | 8.0     | 7.6 | 1.0            | 1.0     | 2.6 | 3.7                     | 3.7     | 5.0 |
|          |                   |                |               | Middle    | 4.5  | 27.6             | 27.6    | 8.3   | 8.3     | 32.1         | 32.1    | 107.0             | 110.1   | 7.1                     | 7.3     |     | 2.6            | 2.2     |     | 5.7                     | 5.8     |     |
|          |                   |                |               | Bottom    | 8    | 26.6             | 26.6    | 8.2   | 8.2     | 32.8         | 32.8    | 84.5              | 86.0    | 5.6                     | 5.7     |     | 4.4            | 4.5     |     | 5.6                     | 5.6     |     |
| M1       | Cloudy            | Moderate       | 15:42         | Surface   | 1    | 28.0             | 27.9    | 8.4   | 8.4     | 31.8         | 31.9    | 113.0             | 110.3   | 7.4                     | 7.3     | 7.2 | 1.2            | 1.3     | 1.5 | 3.3                     | 3.4     | 4.2 |
|          |                   |                |               | Middle    | 3    | 27.8             | 27.8    | 8.3   | 8.3     | 32.0         | 32.0    | 107.1             | 107.5   | 7.1                     | 7.1     |     | 1.5            | 1.5     |     | 4.0                     | 4.1     |     |
|          |                   |                |               | Bottom    | 5    | 27.7             | 27.7    | 8.3   | 8.3     | 32.1         | 32.1    | 104.4             | 105.9   | 6.9                     | 7.0     |     | 1.7            | 1.6     |     | 5.0                     | 5.1     |     |
| M2       | Cloudy            | Moderate       | 15:26         | Surface   | 1    | 28.0             | 28.0    | 8.4   | 8.4     | 31.8         | 31.8    | 116.8             | 117.6   | 7.7                     | 7.8     | 7.6 | 1.0            | 1.0     | 2.2 | 5.8                     | 5.8     | 4.7 |
|          |                   |                |               | Middle    | 6    | 27.8             | 27.9    | 8.4   | 8.4     | 31.9         | 31.9    | 108.3             | 114.6   | 7.1                     | 7.3     |     | 1.3            | 1.3     |     | 4.3                     | 4.3     |     |
|          |                   |                |               | Bottom    | 11   | 26.5             | 26.6    | 8.2   | 8.2     | 32.9         | 32.9    | 83.1              | 82.2    | 5.6                     | 5.5     |     | 4.4            | 4.4     |     | 4.0                     | 4.0     |     |
| M3       | Cloudy            | Moderate       | 16:02         | Surface   | 1    | 27.9             | 27.9    | 8.3   | 8.3     | 31.6         | 31.8    | 107.4             | 109.9   | 7.1                     | 7.3     | 7.4 | 1.3            | 1.4     | 2.2 | 3.4                     | 3.5     | 4.1 |
|          |                   |                |               | Middle    | 4    | 27.9             | 27.9    | 8.3   | 8.3     | 31.9         | 31.9    | 112.8             | 111.3   | 7.4                     | 7.3     |     | 1.6            | 1.6     |     | 3.5                     | 3.6     |     |
|          |                   |                |               | Bottom    | 7    | 27.6             | 27.6    | 8.3   | 8.3     | 32.0         | 32.1    | 96.9              | 97.6    | 6.4                     | 6.4     |     | 3.6            | 3.7     |     | 5.3                     | 5.2     |     |
| M4       | Cloudy            | Moderate       | 15:18         | Surface   | 1    | 28.1             | 28.1    | 8.4   | 8.4     | 31.8         | 31.8    | 118.2             | 118.4   | 7.7                     | 7.8     | 7.7 | 1.0            | 1.1     | 1.4 | 5.8                     | 5.9     | 4.8 |
|          |                   |                |               | Middle    | 5    | 28.0             | 28.0    | 8.4   | 8.4     | 31.9         | 31.9    | 115.3             | 116.0   | 7.6                     | 7.6     |     | 1.2            | 1.3     |     | 3.5                     | 3.5     |     |
|          |                   |                |               | Bottom    | 9    | 27.2             | 27.4    | 8.3   | 8.3     | 32.4         | 32.3    | 99.3              | 108.0   | 6.6                     | 6.9     |     | 1.9            | 1.9     |     | 4.8                     | 4.9     |     |
| M5       | Cloudy            | Moderate       | 16:22         | Surface   | 1    | 27.8             | 27.8    | 8.4   | 8.4     | 32.0         | 32.0    | 114.4             | 114.9   | 7.5                     | 7.6     | 7.1 | 1.2            | 1.2     | 1.7 | 3.5                     | 3.5     | 5.0 |
|          |                   |                |               | Middle    | 5.5  | 27.0             | 27.1    | 8.3   | 8.3     | 32.5         | 32.5    | 98.3              | 100.0   | 6.5                     | 6.6     |     | 1.8            | 1.7     |     | 6.1                     | 6.1     |     |
|          |                   |                |               | Bottom    | 10   | 26.6             | 26.5    | 8.2   | 8.2     | 32.8         | 32.9    | 91.7              | 88.1    | 6.1                     | 6.0     |     | 2.1            | 2.2     |     | 5.4                     | 5.4     |     |
| M6       | Cloudy            | Moderate       | 16:16         | Surface   | -    | -                | -       | -     | -       | -            | -       | -                 | -       | -                       | 6.1     | -   | -              | 3.5     | -   | -                       | 5.3     |     |
|          |                   |                |               | Middle    | 1.3  | 27.7             | 27.5    | 8.3   | 8.3     | 32.0         | 32.2    | 95.4              | 88.1    | 6.3                     |         | 6.1 | 3.5            |         | 3.5 | 5.2                     |         | 5.3 |
|          |                   |                |               | Bottom    | -    | -                | -       | -     | -       | -            | -       | -                 | -       | -                       |         | -   | -              |         | -   | -                       |         | -   |

Remarks: \*DA: Depth-Averaged  
\*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

**Appendix I - Action and Limit Levels for Marine Water Quality on 4 June 2018 (Mid-Flood Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 3.4 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 3.7 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.2 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.8 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.2 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.8 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.6 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 7.2 mg/L</u>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction  
Water Quality Monitoring Results on 04 June 2018**

**(Mid-Flood Tide)**

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) | Temperature (°C) |              | pH    |            | Salinity ppt |              | DO Saturation (%) |                | Dissolved Oxygen (mg/L) |            |     | Turbidity(NTU) |            |            | Suspended Solids (mg/L) |            |     |     |
|----------|-------------------|-----------------|---------------|-----------|------------------|--------------|-------|------------|--------------|--------------|-------------------|----------------|-------------------------|------------|-----|----------------|------------|------------|-------------------------|------------|-----|-----|
|          |                   |                 |               |           | Value            | Average      | Value | Average    | Value        | Average      | Value             | Average        | Value                   | Average    | DA* | Value          | Average    | DA*        | Value                   | Average    | DA* |     |
| C1       | Cloudy            | Moderate        | 09:18         | Surface   | 1                | 28.0<br>28.1 | 28.1  | 8.4<br>8.4 | 8.4          | 31.9<br>31.9 | 31.9              | 115.6<br>117.5 | 116.6                   | 7.6<br>7.7 | 7.7 | 7.3            | 1.1<br>1.1 | 1.1        | 1.7                     | 5.2<br>5.2 | 5.2 | 5.5 |
|          |                   |                 |               | Middle    | 8.5              | 27.3<br>27.3 | 27.3  | 8.3<br>8.3 | 8.3          | 32.4<br>32.4 | 32.4              | 104.9<br>104.4 | 104.7                   | 6.9<br>6.9 | 6.9 | 1.2<br>1.2     | 1.2        | 5.8<br>5.8 |                         | 5.8        |     |     |
|          |                   |                 |               | Bottom    | 16               | 26.3<br>25.9 | 26.1  | 8.3<br>8.2 | 8.3          | 33.2<br>33.5 | 33.4              | 89.6<br>83.6   | 86.6                    | 6.0<br>5.6 | 5.8 | 2.8<br>2.8     | 2.8        | 5.5<br>5.4 |                         | 5.5        |     |     |
| C2       | Cloudy            | Moderate        | 08:15         | Surface   | 1                | 28.1<br>28.1 | 28.1  | 8.3<br>8.4 | 8.4          | 31.7<br>31.7 | 31.7              | 112.6<br>112.1 | 112.4                   | 7.4<br>7.3 | 7.4 | 7.1            | 0.8<br>0.9 | 0.9        | 1.4                     | 4.9<br>5.0 | 5.0 | 4.6 |
|          |                   |                 |               | Middle    | 16.5             | 27.2<br>27.5 | 27.4  | 8.3<br>8.3 | 8.3          | 32.4<br>32.2 | 32.3              | 98.3<br>102.3  | 100.3                   | 6.5<br>6.8 | 6.7 | 1.6<br>1.6     | 1.6        | 5.2<br>5.1 |                         | 5.2        |     |     |
|          |                   |                 |               | Bottom    | 32               | 26.6<br>26.5 | 26.6  | 8.2<br>8.2 | 8.2          | 32.7<br>32.8 | 32.8              | 92.7<br>91.8   | 92.3                    | 6.2<br>6.1 | 6.2 | 1.5<br>1.7     | 1.6        | 3.5<br>3.5 |                         | 3.5        |     |     |
| G1       | Cloudy            | Moderate        | 08:47         | Surface   | 1                | 28.0<br>28.0 | 28.0  | 8.3<br>8.3 | 8.3          | 31.8<br>31.8 | 31.8              | 108.8<br>110.4 | 109.6                   | 7.1<br>7.2 | 7.2 | 7.3            | 1.0<br>1.0 | 1.0        | 1.1                     | 3.3<br>3.2 | 3.3 | 3.7 |
|          |                   |                 |               | Middle    | 4                | 27.9<br>27.9 | 27.9  | 8.4<br>8.4 | 8.4          | 31.9<br>31.9 | 31.9              | 111.3<br>111.6 | 111.5                   | 7.3<br>7.3 | 7.3 | 1.1<br>1.1     | 1.1        | 4.4<br>4.4 |                         | 4.4        |     |     |
|          |                   |                 |               | Bottom    | 7                | 27.5<br>27.4 | 27.5  | 8.3<br>8.3 | 8.3          | 32.2<br>32.3 | 32.3              | 105.5<br>104.6 | 105.1                   | 7.0<br>6.9 | 7.0 | 1.2<br>1.3     | 1.3        | 3.5<br>3.5 |                         | 3.5        |     |     |
| G2       | Cloudy            | Moderate        | 08:35         | Surface   | 1                | 27.9<br>28.0 | 28.0  | 8.4<br>8.4 | 8.4          | 31.8<br>31.8 | 31.8              | 112.7<br>112.9 | 112.8                   | 7.4<br>7.4 | 7.4 | 7.3            | 1.0<br>0.9 | 1.0        | 1.2                     | 4.6<br>4.5 | 4.6 | 3.5 |
|          |                   |                 |               | Middle    | 5                | 27.8<br>27.8 | 27.8  | 8.3<br>8.3 | 8.3          | 32.0<br>32.0 | 32.0              | 110.0<br>109.2 | 109.6                   | 7.2<br>7.2 | 7.2 | 1.1<br>1.1     | 1.2        | 2.6<br>2.6 |                         | 2.6        |     |     |
|          |                   |                 |               | Bottom    | 9                | 27.2<br>27.0 | 27.1  | 8.3<br>8.3 | 8.3          | 32.4<br>32.5 | 32.5              | 102.1<br>99.8  | 101.0                   | 6.8<br>6.6 | 6.7 | 1.3<br>1.4     | 1.4        | 3.1<br>3.2 |                         | 3.2        |     |     |
| G3       | Cloudy            | Moderate        | 08:52         | Surface   | 1                | 27.9<br>27.9 | 27.9  | 8.4<br>8.4 | 8.4          | 31.7<br>31.7 | 31.7              | 111.1<br>113.1 | 112.1                   | 7.3<br>7.4 | 7.4 | 7.3            | 1.3<br>1.3 | 1.3        | 2.0                     | 3.5<br>3.5 | 3.5 | 4.5 |
|          |                   |                 |               | Middle    | 4                | 27.6<br>27.5 | 27.6  | 8.3<br>8.3 | 8.3          | 32.0<br>32.1 | 32.1              | 107.6<br>105.6 | 106.6                   | 7.1<br>7.0 | 7.1 | 1.7<br>1.8     | 1.8        | 5.0<br>5.0 |                         | 5.0        |     |     |
|          |                   |                 |               | Bottom    | 7                | 27.2<br>27.3 | 27.3  | 8.3<br>8.3 | 8.3          | 32.3<br>32.2 | 32.3              | 97.9<br>98.2   | 98.1                    | 6.5<br>6.5 | 6.5 | 3.0<br>3.0     | 3.0        | 5.0<br>5.1 |                         | 5.1        |     |     |
| G4       | Cloudy            | Moderate        | 09:03         | Surface   | 1                | 27.8<br>27.8 | 27.8  | 8.3<br>8.4 | 8.4          | 32.0<br>31.9 | 32.0              | 112.9<br>113.2 | 113.1                   | 7.4<br>7.4 | 7.4 | 7.4            | 1.2<br>1.1 | 1.2        | 1.2                     | 5.8<br>5.8 | 5.7 | 5.4 |
|          |                   |                 |               | Middle    | 4.5              | 27.5<br>27.7 | 27.6  | 8.3<br>8.3 | 8.3          | 32.2<br>32.0 | 32.1              | 109.4<br>112.2 | 110.8                   | 7.2<br>7.4 | 7.3 | 1.1<br>1.0     | 1.1        | 5.5<br>5.6 |                         | 5.6        |     |     |
|          |                   |                 |               | Bottom    | 8                | 27.4<br>27.2 | 27.3  | 8.3<br>8.3 | 8.3          | 32.3<br>32.4 | 32.4              | 104.3<br>100.1 | 102.2                   | 6.9<br>6.6 | 6.8 | 1.4<br>1.3     | 1.4        | 4.8<br>4.7 |                         | 4.8        |     |     |
| M1       | Cloudy            | Moderate        | 08:42         | Surface   | 1                | 28.0<br>28.0 | 28.0  | 8.3<br>8.3 | 8.3          | 31.8<br>31.8 | 31.8              | 106.9<br>107.8 | 107.4                   | 7.0<br>7.1 | 7.1 | 7.1            | 1.3<br>1.3 | 1.3        | 1.6                     | 5.0<br>4.9 | 5.0 | 5.2 |
|          |                   |                 |               | Middle    | 3                | 28.0<br>27.9 | 28.0  | 8.3<br>8.3 | 8.3          | 31.8<br>31.9 | 31.9              | 107.3<br>107.4 | 107.4                   | 7.0<br>7.1 | 7.1 | 1.6<br>1.6     | 1.6        | 4.2<br>4.2 |                         | 4.2        |     |     |
|          |                   |                 |               | Bottom    | 5                | 27.7<br>27.8 | 27.8  | 8.3<br>8.3 | 8.3          | 32.0<br>32.0 | 32.0              | 105.1<br>105.6 | 105.4                   | 6.9<br>7.0 | 7.0 | 2.0<br>1.8     | 1.9        | 6.4<br>6.3 |                         | 6.4        |     |     |
| M2       | Cloudy            | Moderate        | 08:30         | Surface   | 1                | 28.0<br>28.1 | 28.1  | 8.4<br>8.4 | 8.4          | 31.8<br>31.8 | 31.8              | 111.7<br>111.7 | 111.7                   | 7.3<br>7.3 | 7.3 | 7.3            | 1.1<br>1.0 | 1.1        | 1.8                     | 4.7<br>4.7 | 4.7 | 5.2 |
|          |                   |                 |               | Middle    | 6                | 27.9<br>27.9 | 27.9  | 8.3<br>8.3 | 8.3          | 31.9<br>31.9 | 31.9              | 110.9<br>110.8 | 110.9                   | 7.3<br>7.3 | 7.3 | 1.0<br>1.0     | 1.0        | 4.6<br>4.8 |                         | 4.7        |     |     |
|          |                   |                 |               | Bottom    | 11               | 26.3<br>26.3 | 26.3  | 8.2<br>8.2 | 8.2          | 33.0<br>33.0 | 33.0              | 81.9<br>81.5   | 81.7                    | 5.5<br>5.5 | 5.5 | 3.2<br>3.4     | 3.3        | 6.4<br>6.2 |                         | 6.3        |     |     |
| M3       | Cloudy            | Moderate        | 08:58         | Surface   | 1                | 27.9<br>28.0 | 28.0  | 8.3<br>8.4 | 8.4          | 31.6<br>31.6 | 31.6              | 109.8<br>112.5 | 111.2                   | 7.2<br>7.4 | 7.3 | 7.1            | 1.4<br>1.2 | 1.3        | 2.1                     | 3.3<br>3.3 | 3.3 | 4.0 |
|          |                   |                 |               | Middle    | 4                | 27.5<br>27.5 | 27.5  | 8.3<br>8.3 | 8.3          | 32.1<br>32.1 | 32.1              | 101.6<br>103.9 | 102.8                   | 6.7<br>6.9 | 6.8 | 2.2<br>2.0     | 2.1        | 3.8<br>3.8 |                         | 3.8        |     |     |
|          |                   |                 |               | Bottom    | 7                | 27.2<br>27.2 | 27.2  | 8.3<br>8.3 | 8.3          | 32.3<br>32.3 | 32.3              | 96.0<br>97.3   | 96.7                    | 6.4<br>6.5 | 6.5 | 2.9<br>2.7     | 2.8        | 4.9<br>4.9 |                         | 4.9        |     |     |
| M4       | Cloudy            | Moderate        | 08:23         | Surface   | 1                | 28.1<br>28.1 | 28.1  | 8.3<br>8.4 | 8.4          | 31.8<br>31.8 | 31.8              | 112.7<br>113.5 | 113.1                   | 7.4<br>7.4 | 7.4 | 7.4            | 1.0<br>0.9 | 1.0        | 1.0                     | 5.3<br>5.4 | 5.4 | 4.6 |
|          |                   |                 |               | Middle    | 5                | 28.0<br>28.0 | 28.0  | 8.4<br>8.4 | 8.4          | 31.8<br>31.8 | 31.8              | 113.0<br>113.4 | 113.2                   | 7.4<br>7.4 | 7.4 | 0.9<br>0.9     | 0.9        | 2.9<br>3.1 |                         | 3.0        |     |     |
|          |                   |                 |               | Bottom    | 9                | 27.9<br>28.0 | 28.0  | 8.3<br>8.4 | 8.4          | 31.9<br>31.9 | 31.9              | 110.0<br>112.1 | 111.1                   | 7.2<br>7.4 | 7.3 | 1.1<br>1.1     | 1.1        | 5.3<br>5.3 |                         | 5.3        |     |     |
| M5       | Cloudy            | Moderate        | 09:12         | Surface   | 1                | 28.1<br>28.2 | 28.2  | 8.4<br>8.4 | 8.4          | 31.8<br>31.8 | 31.8              | 116.9<br>118.4 | 117.7                   | 7.7<br>7.7 | 7.7 | 7.6            | 0.9<br>0.9 | 0.9        | 1.1                     | 4.3<br>4.4 | 4.4 | 4.5 |
|          |                   |                 |               | Middle    | 5.5              | 27.7<br>27.7 | 27.7  | 8.4<br>8.4 | 8.4          | 32.1<br>32.0 | 32.1              | 112.1<br>113.6 | 112.9                   | 7.4<br>7.5 | 7.5 | 1.1<br>1.1     | 1.1        | 4.4<br>4.6 |                         | 4.5        |     |     |
|          |                   |                 |               | Bottom    | 10               | 27.2<br>27.2 | 27.2  | 8.3<br>8.3 | 8.3          | 32.4<br>32.4 | 32.4              | 101.3<br>102.6 | 102.0                   | 6.7<br>6.8 | 6.8 | 1.4<br>1.2     | 1.3        | 4.5<br>4.5 |                         | 4.5        |     |     |
| M6       | Cloudy            | Moderate        | 09:07         | Surface   | -                | -            | -     | -          | -            | -            | -                 | -              | -                       | -          | -   | 7.5            | -          | -          | 1.6                     | -          | -   | 5.8 |
|          |                   |                 |               | Middle    | 1.2              | 28.0<br>28.0 | 28.0  | 8.4<br>8.4 | 8.4          | 32.0<br>32.0 | 32.0              | 112.9<br>116.5 | 114.7                   | 7.4<br>7.6 | 7.5 | 1.5<br>1.6     | 1.6        | 5.8<br>5.8 |                         | 5.8        |     |     |
|          |                   |                 |               | Bottom    | -                | -            | -     | -          | -            | -            | -                 | -              | -                       | -          | -   | -              | -          | -          |                         | -          | -   |     |

Remarks: \*DA: Depth-Averaged  
\*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough: White capped or rougher.



**Appendix I - Action and Limit Levels for Marine Water Quality on 6 June 2018 (Mid-Ebb Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 3.6 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 3.9 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.0 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.5 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.0 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.5 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.1 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.7 mg/L</u>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction  
Water Quality Monitoring Results on 06 June 2018**

**(Mid-Ebb Tide)**

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) |     | Temperature (°C) |         | pH         |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         |     | Turbidity (NTU) |         |     | Suspended Solids (mg/L) |         |     |
|----------|-------------------|-----------------|---------------|-----------|-----|------------------|---------|------------|---------|--------------|---------|-------------------|---------|-------------------------|---------|-----|-----------------|---------|-----|-------------------------|---------|-----|
|          |                   |                 |               |           |     | Value            | Average | Value      | Average | Value        | Average | Value             | Average | Value                   | Average | DA* | Value           | Average | DA* | Value                   | Average | DA* |
| C1       | Rainy             | Moderate        | 17:12         | Surface   | 1   | 27.5<br>27.5     | 27.5    | 8.3<br>8.3 | 8.3     | 31.4<br>31.4 | 31.4    | 95.4<br>95.2      | 95.3    | 6.3<br>6.3              | 6.3     | 6.2 | 0.7<br>0.6      | 0.7     | 1.3 | 4.3<br>4.2              | 4.3     | 4.6 |
|          |                   |                 |               | Middle    | 9   | 27.6<br>27.5     | 27.6    | 8.3<br>8.3 | 8.3     | 31.6<br>31.6 | 31.6    | 90.9<br>91.2      | 91.1    | 6.0<br>6.0              | 6.0     |     | 0.5<br>0.4      | 0.5     |     | 5.3<br>5.4              | 5.4     |     |
|          |                   |                 |               | Bottom    | 17  | 27.3<br>27.3     | 27.3    | 8.2<br>8.2 | 8.2     | 31.8<br>31.8 | 31.8    | 82.1<br>81.0      | 81.6    | 5.5<br>5.4              | 5.5     |     | 2.6<br>2.5      | 2.6     |     | 4.0<br>3.9              | 4.0     |     |
| C2       | Rainy             | Moderate        | 16:09         | Surface   | 1   | 27.4<br>27.4     | 27.4    | 8.3<br>8.3 | 8.3     | 30.6<br>30.6 | 30.6    | 93.0<br>92.1      | 92.6    | 6.2<br>6.2              | 6.2     | 5.9 | 0.7<br>0.6      | 0.7     | 1.9 | 5.8<br>5.8              | 5.8     | 5.8 |
|          |                   |                 |               | Middle    | 16  | 27.2<br>27.2     | 27.2    | 8.2<br>8.2 | 8.2     | 31.8<br>31.8 | 31.8    | 82.2<br>82.6      | 82.4    | 5.5<br>5.5              | 5.5     |     | 2.0<br>1.9      | 2.0     |     | 5.7<br>5.5              | 5.6     |     |
|          |                   |                 |               | Bottom    | 31  | 27.1<br>27.1     | 27.1    | 8.2<br>8.2 | 8.2     | 32.0<br>32.0 | 32.0    | 78.3<br>78.6      | 78.5    | 5.2<br>5.2              | 5.2     |     | 2.9<br>3.0      | 3.0     |     | 5.8<br>5.9              | 5.9     |     |
| G1       | Rainy             | Moderate        | 16:39         | Surface   | 1   | 27.5<br>27.5     | 27.5    | 8.3<br>8.3 | 8.3     | 31.0<br>31.0 | 31.0    | 95.6<br>95.1      | 95.6    | 6.4<br>6.3              | 6.4     | 6.3 | 0.6<br>0.6      | 0.6     | 0.8 | 5.5<br>5.5              | 5.5     | 4.0 |
|          |                   |                 |               | Middle    | 4   | 27.5<br>27.5     | 27.5    | 8.3<br>8.3 | 8.3     | 31.2<br>31.2 | 31.2    | 92.4<br>92.7      | 92.6    | 6.1<br>6.2              | 6.2     |     | 0.7<br>0.7      | 0.7     |     | 3.7<br>3.6              | 3.7     |     |
|          |                   |                 |               | Bottom    | 7   | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.3<br>31.4 | 31.4    | 86.1<br>83.9      | 85.0    | 5.7<br>5.6              | 5.7     |     | 1.1<br>1.1      | 1.1     |     | 2.8<br>2.7              | 2.8     |     |
| G2       | Rainy             | Moderate        | 16:30         | Surface   | 1   | 27.7<br>27.5     | 27.6    | 8.3<br>8.3 | 8.3     | 31.2<br>30.8 | 31.0    | 98.8<br>97.2      | 97.8    | 6.5<br>6.5              | 6.5     | 6.5 | 0.6<br>0.6      | 0.6     | 0.7 | 4.4<br>4.3              | 4.4     | 4.0 |
|          |                   |                 |               | Middle    | 5   | 27.8<br>27.8     | 27.8    | 8.3<br>8.3 | 8.3     | 31.5<br>31.5 | 31.5    | 96.9<br>97.0      | 97.0    | 6.4<br>6.4              | 6.4     |     | 0.3<br>0.3      | 0.3     |     | 3.4<br>3.2              | 3.3     |     |
|          |                   |                 |               | Bottom    | 9   | 27.4<br>27.5     | 27.5    | 8.2<br>8.2 | 8.2     | 31.6<br>31.5 | 31.6    | 86.2<br>86.5      | 86.4    | 5.7<br>5.7              | 5.7     |     | 1.2<br>1.3      | 1.3     |     | 4.4<br>4.4              | 4.4     |     |
| G3       | Rainy             | Moderate        | 16:45         | Surface   | 1   | 27.3<br>27.3     | 27.3    | 8.2<br>8.2 | 8.2     | 29.5<br>30.1 | 29.8    | 87.8<br>87.2      | 87.5    | 5.9<br>5.8              | 5.9     | 5.8 | 1.9<br>1.6      | 1.8     | 2.5 | 5.8<br>5.8              | 5.8     | 5.0 |
|          |                   |                 |               | Middle    | 4   | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.4<br>31.4 | 31.4    | 87.7<br>81.4      | 84.6    | 5.8<br>5.4              | 5.6     |     | 2.4<br>2.4      | 2.4     |     | 5.1<br>5.1              | 5.1     |     |
|          |                   |                 |               | Bottom    | 7   | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.6<br>31.6 | 31.6    | 80.9<br>82.3      | 81.6    | 5.4<br>5.5              | 5.5     |     | 3.2<br>3.1      | 3.2     |     | 4.1<br>4.0              | 4.1     |     |
| G4       | Rainy             | Moderate        | 16:56         | Surface   | 1   | 27.3<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 30.8<br>30.7 | 30.8    | 92.3<br>91.6      | 92.0    | 6.2<br>6.1              | 6.2     | 6.1 | 1.5<br>1.8      | 1.7     | 1.8 | 3.2<br>3.1              | 3.2     | 4.2 |
|          |                   |                 |               | Middle    | 4.5 | 27.3<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.3<br>31.4 | 31.4    | 89.5<br>88.2      | 88.8    | 6.0<br>5.9              | 6.0     |     | 0.8<br>0.7      | 0.8     |     | 3.3<br>3.2              | 3.3     |     |
|          |                   |                 |               | Bottom    | 8   | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.6<br>31.6 | 31.6    | 78.2<br>82.3      | 80.3    | 5.2<br>5.5              | 5.4     |     | 3.2<br>2.8      | 3.0     |     | 5.8<br>6.1              | 6.0     |     |
| M1       | Rainy             | Moderate        | 16:35         | Surface   | 1   | 27.5<br>27.5     | 27.5    | 8.3<br>8.3 | 8.3     | 31.0<br>31.0 | 31.0    | 95.6<br>94.3      | 95.0    | 6.4<br>6.3              | 6.4     | 6.4 | 0.9<br>0.8      | 0.9     | 0.8 | 3.0<br>2.9              | 3.0     | 3.2 |
|          |                   |                 |               | Middle    | 3   | 27.6<br>27.6     | 27.6    | 8.3<br>8.3 | 8.3     | 31.3<br>31.2 | 31.3    | 95.7<br>95.9      | 95.8    | 6.3<br>6.4              | 6.4     |     | 0.6<br>0.7      | 0.7     |     | 2.7<br>2.7              | 2.7     |     |
|          |                   |                 |               | Bottom    | 5   | 27.5<br>27.5     | 27.5    | 8.3<br>8.3 | 8.3     | 31.3<br>31.3 | 31.3    | 91.9<br>91.5      | 91.7    | 6.1<br>6.1              | 6.1     |     | 0.8<br>0.9      | 0.9     |     | 4.0<br>4.0              | 4.0     |     |
| M2       | Rainy             | Moderate        | 16:23         | Surface   | 1   | 27.8<br>27.7     | 27.8    | 8.3<br>8.3 | 8.3     | 31.2<br>31.3 | 31.3    | 98.9<br>98.5      | 98.7    | 6.5<br>6.5              | 6.5     | 6.4 | 0.2<br>0.2      | 0.2     | 1.2 | 5.0<br>5.0              | 5.0     | 4.3 |
|          |                   |                 |               | Middle    | 6   | 27.7<br>27.6     | 27.7    | 8.3<br>8.3 | 8.3     | 31.5<br>31.5 | 31.5    | 93.1<br>94.6      | 93.9    | 6.2<br>6.3              | 6.3     |     | 0.5<br>0.5      | 0.5     |     | 3.6<br>3.5              | 3.6     |     |
|          |                   |                 |               | Bottom    | 11  | 27.4<br>27.3     | 27.4    | 8.2<br>8.2 | 8.2     | 31.7<br>31.7 | 31.7    | 80.2<br>73.8      | 77.0    | 5.3<br>4.9              | 5.1     |     | 3.0<br>2.9      | 3.0     |     | 4.3<br>4.3              | 4.3     |     |
| M3       | Rainy             | Moderate        | 16:51         | Surface   | 1   | 27.3<br>27.3     | 27.3    | 8.2<br>8.2 | 8.2     | 30.0<br>30.4 | 30.2    | 89.6<br>88.7      | 89.2    | 6.0<br>5.9              | 6.0     | 5.9 | 1.5<br>1.4      | 1.5     | 1.8 | 3.9<br>3.8              | 3.9     | 5.8 |
|          |                   |                 |               | Middle    | 4   | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.4<br>31.2 | 31.3    | 85.3<br>85.0      | 85.2    | 5.7<br>5.7              | 5.7     |     | 1.7<br>1.8      | 1.8     |     | 7.5<br>7.2              | 7.4     |     |
|          |                   |                 |               | Bottom    | 7   | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.6<br>31.6 | 31.6    | 84.9<br>83.3      | 84.1    | 5.6<br>5.5              | 5.6     |     | 1.9<br>2.2      | 2.1     |     | 6.1<br>6.0              | 6.1     |     |
| M4       | Rainy             | Moderate        | 16:17         | Surface   | 1   | 27.4<br>27.4     | 27.4    | 8.3<br>8.3 | 8.3     | 30.9<br>30.9 | 30.9    | 92.6<br>92.6      | 92.6    | 6.2<br>6.2              | 6.2     | 6.2 | 0.7<br>0.7      | 0.7     | 0.9 | 5.3<br>5.2              | 5.3     | 5.0 |
|          |                   |                 |               | Middle    | 5   | 27.5<br>27.4     | 27.5    | 8.3<br>8.2 | 8.3     | 31.4<br>31.4 | 31.4    | 91.8<br>90.3      | 91.1    | 6.1<br>6.0              | 6.1     |     | 0.8<br>0.8      | 0.8     |     | 3.9<br>3.9              | 3.9     |     |
|          |                   |                 |               | Bottom    | 9   | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.5<br>31.5 | 31.5    | 89.2<br>88.0      | 88.6    | 5.9<br>5.8              | 5.9     |     | 1.0<br>1.2      | 1.1     |     | 5.8<br>5.7              | 5.8     |     |
| M5       | Rainy             | Moderate        | 17:06         | Surface   | 1   | 27.5<br>27.5     | 27.5    | 8.3<br>8.3 | 8.3     | 31.3<br>31.3 | 31.3    | 95.0<br>94.7      | 94.9    | 6.3<br>6.3              | 6.3     | 6.3 | 0.6<br>0.5      | 0.6     | 0.6 | 5.7<br>5.4              | 5.6     | 4.4 |
|          |                   |                 |               | Middle    | 5.5 | 27.5<br>27.5     | 27.5    | 8.3<br>8.3 | 8.3     | 31.4<br>31.5 | 31.5    | 92.2<br>93.2      | 92.7    | 6.1<br>6.2              | 6.2     |     | 0.5<br>0.6      | 0.6     |     | 3.1<br>3.1              | 3.1     |     |
|          |                   |                 |               | Bottom    | 10  | 27.5<br>27.5     | 27.5    | 8.3<br>8.3 | 8.3     | 31.5<br>31.5 | 31.5    | 91.2<br>91.3      | 91.3    | 6.0<br>6.1              | 6.1     |     | 0.4<br>0.5      | 0.5     |     | 4.5<br>4.4              | 4.5     |     |
| M6       | Rainy             | Moderate        | 17:02         | Surface   | -   | -                | -       | -          | -       | -            | -       | -                 | -       | -                       | -       | 6.1 | -               | -       | 1.1 | -                       | -       | 4.4 |
|          |                   |                 |               | Middle    | 1.1 | 27.3<br>27.3     | 27.3    | 8.2<br>8.2 | 8.2     | 29.7<br>29.8 | 29.8    | 91.0<br>90.4      | 90.7    | 6.1<br>6.1              | 6.1     |     | 1.1<br>1.0      | 1.1     |     | 4.4<br>4.4              | 4.4     |     |
|          |                   |                 |               | Bottom    | -   | -                | -       | -          | -       | -            | -       | -                 | -       | -                       | -       |     | -               | -       |     | -                       | -       |     |

Remarks: \*DA: Depth-Averaged  
\*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

**Appendix I - Action and Limit Levels for Marine Water Quality on 6 June 2018 (Mid-Flood Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 3.0 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 3.3 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 5.5 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.0 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 5.5 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.0 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 7.1 g/L</u>        | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 7.7/L</u>          |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction  
 Water Quality Monitoring Results on 06 June 2018

(Mid-Flood Tide)

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) |     | Temperature (°C) |         | pH         |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         |     | Turbidity (NTU) |         |     | Suspended Solids (mg/L) |         |     |
|----------|-------------------|-----------------|---------------|-----------|-----|------------------|---------|------------|---------|--------------|---------|-------------------|---------|-------------------------|---------|-----|-----------------|---------|-----|-------------------------|---------|-----|
|          |                   |                 |               |           |     | Value            | Average | Value      | Average | Value        | Average | Value             | Average | Value                   | Average | DA* | Value           | Average | DA* | Value                   | Average | DA* |
| C1       | Rainy             | Moderate        | 11:18         | Surface   | 1   | 27.6<br>27.5     | 27.6    | 8.3<br>8.3 | 8.3     | 31.3<br>31.2 | 31.3    | 97.4<br>96.9      | 97.2    | 6.5<br>6.4              | 6.5     | 6.3 | 0.4<br>0.4      | 0.4     | 1.3 | 4.6<br>4.5              | 4.6     | 4.7 |
|          |                   |                 |               | Middle    | 9   | 27.5<br>27.5     | 27.5    | 8.3<br>8.3 | 8.3     | 31.7<br>31.7 | 31.7    | 89.5<br>90.8      | 90.2    | 5.9<br>6.0              | 6.0     |     | 0.9<br>0.8      | 0.9     |     | 3.7<br>3.7              | 3.7     |     |
|          |                   |                 |               | Bottom    | 17  | 27.2<br>27.1     | 27.2    | 8.2<br>8.2 | 8.2     | 31.9<br>31.9 | 31.9    | 81.8<br>80.3      | 81.1    | 5.4<br>5.4              | 5.4     |     | 2.4<br>2.5      | 2.5     |     | 6.0<br>5.8              | 5.9     |     |
| C2       | Rainy             | Moderate        | 10:06         | Surface   | 1   | 27.4<br>27.3     | 27.4    | 8.2<br>8.2 | 8.2     | 30.9<br>31.1 | 31.0    | 93.4<br>91.5      | 92.5    | 6.2<br>6.1              | 6.2     | 5.9 | 0.7<br>0.7      | 0.7     | 1.4 | 5.1<br>5.1              | 5.1     | 5.1 |
|          |                   |                 |               | Middle    | 16  | 27.2<br>27.3     | 27.3    | 8.2<br>8.2 | 8.2     | 31.9<br>31.7 | 31.8    | 83.4<br>85.1      | 84.3    | 5.5<br>5.7              | 5.6     |     | 1.9<br>1.8      | 1.9     |     | 4.6<br>4.6              | 4.6     |     |
|          |                   |                 |               | Bottom    | 31  | 27.2<br>27.2     | 27.2    | 8.2<br>8.2 | 8.2     | 31.9<br>31.9 | 31.9    | 82.4<br>82.6      | 82.5    | 5.5<br>5.5              | 5.5     |     | 1.6<br>1.7      | 1.7     |     | 5.7<br>5.7              | 5.7     |     |
| G1       | Rainy             | Moderate        | 10:40         | Surface   | 1   | 27.3<br>27.2     | 27.3    | 8.2<br>8.2 | 8.2     | 30.2<br>29.7 | 30.0    | 91.0<br>92.1      | 91.6    | 6.1<br>6.2              | 6.2     | 6.1 | 0.8<br>1.0      | 0.9     | 0.9 | 3.6<br>3.6              | 3.6     | 3.2 |
|          |                   |                 |               | Middle    | 4   | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.5<br>31.5 | 31.5    | 89.8<br>89.5      | 89.8    | 6.0<br>5.9              | 6.0     |     | 0.7<br>0.7      | 0.7     |     | 3.5<br>3.5              | 3.5     |     |
|          |                   |                 |               | Bottom    | 7   | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.5<br>31.5 | 31.5    | 88.4<br>88.6      | 88.5    | 5.9<br>5.9              | 5.9     |     | 1.1<br>1.1      | 1.1     |     | 2.6<br>2.5              | 2.6     |     |
| G2       | Rainy             | Moderate        | 10:29         | Surface   | 1   | 27.4<br>27.3     | 27.4    | 8.2<br>8.2 | 8.2     | 30.8<br>30.7 | 30.8    | 92.0<br>91.6      | 91.8    | 6.1<br>6.1              | 6.1     | 6.1 | 0.7<br>0.7      | 0.7     | 1.4 | 3.8<br>3.7              | 3.8     | 4.1 |
|          |                   |                 |               | Middle    | 5   | 27.5<br>27.5     | 27.5    | 8.2<br>8.2 | 8.2     | 31.6<br>31.5 | 31.6    | 89.8<br>90.0      | 89.9    | 6.0<br>6.0              | 6.0     |     | 0.8<br>0.7      | 0.8     |     | 4.3<br>4.2              | 4.3     |     |
|          |                   |                 |               | Bottom    | 9   | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.7<br>31.7 | 31.7    | 86.4<br>86.0      | 86.2    | 5.7<br>5.7              | 5.7     |     | 2.8<br>2.4      | 2.6     |     | 4.0<br>4.1              | 4.1     |     |
| G3       | Rainy             | Moderate        | 10:46         | Surface   | 1   | 27.3<br>27.3     | 27.3    | 8.2<br>8.2 | 8.2     | 31.0<br>31.2 | 31.1    | 88.2<br>88.2      | 88.2    | 5.9<br>5.9              | 5.9     | 5.9 | 1.7<br>1.8      | 1.8     | 1.6 | 3.0<br>3.0              | 3.0     | 4.1 |
|          |                   |                 |               | Middle    | 4   | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.4<br>31.4 | 31.4    | 87.5<br>86.5      | 87.0    | 5.8<br>5.8              | 5.8     |     | 1.8<br>1.9      | 1.9     |     | 4.5<br>4.4              | 4.5     |     |
|          |                   |                 |               | Bottom    | 7   | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.5<br>31.5 | 31.5    | 86.4<br>85.9      | 86.2    | 5.7<br>5.7              | 5.7     |     | 0.9<br>1.1      | 1.0     |     | 4.9<br>4.9              | 4.9     |     |
| G4       | Rainy             | Moderate        | 10:58         | Surface   | 1   | 27.3<br>27.3     | 27.3    | 8.2<br>8.2 | 8.2     | 31.1<br>31.2 | 31.2    | 90.9<br>90.7      | 90.8    | 6.1<br>6.0              | 6.1     | 6.1 | 0.9<br>0.6      | 0.9     | 1.2 | 4.3<br>4.2              | 4.3     | 3.9 |
|          |                   |                 |               | Middle    | 4.5 | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.5<br>31.5 | 31.5    | 90.3<br>90.3      | 90.3    | 6.0<br>6.0              | 6.0     |     | 0.7<br>0.6      | 0.7     |     | 3.2<br>3.2              | 3.2     |     |
|          |                   |                 |               | Bottom    | 8   | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.5<br>31.5 | 31.5    | 85.3<br>86.7      | 86.0    | 5.7<br>5.8              | 5.8     |     | 2.0<br>2.1      | 2.1     |     | 4.4<br>4.2              | 4.3     |     |
| M1       | Rainy             | Moderate        | 10:36         | Surface   | 1   | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.3<br>30.6 | 31.0    | 85.2<br>87.3      | 86.3    | 5.7<br>5.8              | 5.8     | 5.8 | 1.2<br>1.3      | 1.3     | 1.4 | 4.8<br>4.9              | 4.9     | 4.3 |
|          |                   |                 |               | Middle    | 3   | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.5<br>31.5 | 31.5    | 88.5<br>85.9      | 87.2    | 5.9<br>5.7              | 5.8     |     | 1.3<br>1.5      | 1.4     |     | 3.6<br>3.6              | 3.6     |     |
|          |                   |                 |               | Bottom    | 5   | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.5<br>31.5 | 31.5    | 88.8<br>86.0      | 87.4    | 5.9<br>5.7              | 5.8     |     | 1.5<br>1.7      | 1.6     |     | 4.5<br>4.4              | 4.5     |     |
| M2       | Rainy             | Moderate        | 10:22         | Surface   | 1   | 27.4<br>27.5     | 27.4    | 8.2<br>8.2 | 8.2     | 31.1<br>31.3 | 31.2    | 92.0<br>90.8      | 91.4    | 6.1<br>6.0              | 6.1     | 6.1 | 0.6<br>0.6      | 0.6     | 1.3 | 5.0<br>5.1              | 5.1     | 5.1 |
|          |                   |                 |               | Middle    | 6   | 27.5<br>27.5     | 27.5    | 8.2<br>8.2 | 8.2     | 31.6<br>31.6 | 31.6    | 91.1<br>90.5      | 90.8    | 6.0<br>6.0              | 6.0     |     | 0.8<br>0.7      | 0.8     |     | 3.5<br>3.4              | 3.5     |     |
|          |                   |                 |               | Bottom    | 11  | 27.3<br>27.3     | 27.3    | 8.2<br>8.2 | 8.2     | 31.7<br>31.7 | 31.7    | 79.5<br>77.1      | 78.3    | 5.3<br>5.1              | 5.2     |     | 2.6<br>2.5      | 2.6     |     | 6.8<br>6.6              | 6.7     |     |
| M3       | Rainy             | Moderate        | 10:51         | Surface   | 1   | 27.3<br>27.3     | 27.3    | 8.2<br>8.2 | 8.2     | 31.2<br>31.1 | 31.2    | 89.5<br>86.5      | 88.0    | 6.0<br>5.8              | 5.9     | 6.0 | 1.1<br>1.3      | 1.2     | 1.0 | 3.1<br>3.2              | 3.2     | 3.0 |
|          |                   |                 |               | Middle    | 4   | 27.3<br>27.3     | 27.3    | 8.2<br>8.2 | 8.2     | 31.4<br>31.4 | 31.4    | 89.6<br>89.5      | 89.6    | 6.0<br>6.0              | 6.0     |     | 0.8<br>0.9      | 0.9     |     | 2.8<br>2.9              | 2.9     |     |
|          |                   |                 |               | Bottom    | 7   | 27.5<br>27.5     | 27.5    | 8.2<br>8.2 | 8.2     | 31.6<br>31.6 | 31.6    | 87.2<br>87.9      | 87.6    | 5.8<br>5.8              | 5.8     |     | 1.0<br>0.9      | 1.0     |     | 2.9<br>3.0              | 3.0     |     |
| M4       | Rainy             | Moderate        | 10:16         | Surface   | 1   | 27.4<br>27.3     | 27.4    | 8.2<br>8.2 | 8.2     | 30.9<br>30.1 | 30.5    | 94.3<br>94.4      | 94.4    | 6.3<br>6.3              | 6.3     | 6.3 | 0.5<br>0.4      | 0.5     | 0.7 | 4.1<br>4.1              | 4.1     | 3.6 |
|          |                   |                 |               | Middle    | 5   | 27.5<br>27.4     | 27.5    | 8.2<br>8.2 | 8.2     | 31.4<br>31.5 | 31.5    | 92.8<br>92.3      | 92.6    | 6.2<br>6.1              | 6.2     |     | 0.6<br>0.6      | 0.6     |     | 3.4<br>3.4              | 3.4     |     |
|          |                   |                 |               | Bottom    | 9   | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.5<br>31.5 | 31.5    | 91.4<br>89.7      | 90.6    | 6.1<br>5.9              | 6.0     |     | 1.0<br>1.0      | 1.0     |     | 3.2<br>3.2              | 3.2     |     |
| M5       | Rainy             | Moderate        | 11:09         | Surface   | 1   | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.5<br>31.5 | 31.5    | 90.6<br>89.9      | 90.3    | 6.0<br>6.0              | 6.0     | 6.0 | 0.7<br>0.8      | 0.8     | 1.3 | 4.4<br>4.4              | 4.4     | 3.7 |
|          |                   |                 |               | Middle    | 5.5 | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.6<br>31.6 | 31.6    | 89.1<br>89.0      | 89.1    | 5.9<br>5.9              | 5.9     |     | 1.1<br>1.1      | 1.1     |     | 3.1<br>3.0              | 3.1     |     |
|          |                   |                 |               | Bottom    | 10  | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.7<br>31.7 | 31.7    | 86.8<br>86.2      | 86.5    | 5.8<br>5.7              | 5.8     |     | 1.8<br>1.9      | 1.9     |     | 3.5<br>3.5              | 3.5     |     |
| M6       | Rainy             | Moderate        | 11:05         | Surface   | -   | -                | -       | -          | -       | -            | -       | -                 | -       | -                       | -       | 5.9 | -               | -       | 1.0 | -                       | -       | 4.1 |
|          |                   |                 |               | Middle    | 1.1 | 27.3<br>27.3     | 27.3    | 8.2<br>8.2 | 8.2     | 31.3<br>31.2 | 31.3    | 89.1<br>89.1      | 89.1    | 5.9<br>5.9              | 5.9     |     | 0.9<br>1.0      | 1.0     |     | 4.2<br>4.0              | 4.1     |     |
|          |                   |                 |               | Bottom    | -   | -                | -       | -          | -       | -            | -       | -                 | -       | -                       | -       |     | -               | -       |     | -                       | -       |     |

Remarks: \*DA: Depth-Averaged  
 \*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

**Appendix I - Action and Limit Levels for Marine Water Quality on 9 June 2018 (Mid-Ebb Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 2.9 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 3.1 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 5.8 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.2 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 5.8 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.2 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.6 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.2 mg/L</u>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction**  
**Water Quality Monitoring Results on 09 June 2018**

**(Mid-Ebb Tide)**

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) |     | Temperature (°C) |         | pH    |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         |     | Turbidity (NTU) |         |     | Suspended Solids (mg/L) |         |     |     |
|----------|-------------------|-----------------|---------------|-----------|-----|------------------|---------|-------|---------|--------------|---------|-------------------|---------|-------------------------|---------|-----|-----------------|---------|-----|-------------------------|---------|-----|-----|
|          |                   |                 |               |           |     | Value            | Average | Value | Average | Value        | Average | Value             | Average | Value                   | Average | DA* | Value           | Average | DA* | Value                   | Average | DA* |     |
| C1       | Fine              | Calm            | 10:39         | Surface   | 1   | 27.6             | 27.6    | 8.2   | 8.2     | 29.8         | 29.7    | 80.8              | 79.9    | 5.4                     | 5.4     | 5.3 | 1.3             | 1.3     | 1.6 | 3.5                     | 3.5     | 3.6 |     |
|          |                   |                 |               | Middle    | 9   | 27.4             | 27.4    | 8.2   | 8.2     | 32.2         | 32.3    | 76.4              | 76.6    | 5.1                     | 5.1     |     | 1.7             | 1.6     |     | 2.7                     | 2.7     |     |     |
|          |                   |                 |               | Bottom    | 17  | 27.8             | 27.8    | 8.3   | 8.3     | 32.7         | 32.7    | 86.4              | 85.8    | 5.7                     | 5.7     |     | 1.9             | 1.9     |     | 4.5                     | 4.5     |     |     |
| C2       | Fine              | Calm            | 09:48         | Surface   | 1   | 27.4             | 27.4    | 8.1   | 8.1     | 28.7         | 28.6    | 77.3              | 77.3    | 5.2                     | 5.2     | 5.1 | 0.8             | 0.8     | 1.9 | 4.8                     | 4.8     | 5.2 |     |
|          |                   |                 |               | Middle    | 16  | 27.4             | 27.4    | 8.2   | 8.2     | 32.4         | 32.4    | 75.8              | 74.7    | 5.0                     | 4.9     |     | 5.0             | 2.4     |     | 2.5                     | 5.4     |     | 5.4 |
|          |                   |                 |               | Bottom    | 31  | 27.5             | 27.5    | 8.2   | 8.2     | 32.5         | 32.5    | 77.9              | 77.3    | 5.1                     | 5.1     |     | 5.1             | 2.3     |     | 2.4                     | 5.5     |     | 5.5 |
| G1       | Fine              | Calm            | 10:13         | Surface   | 1   | 27.5             | 27.5    | 8.1   | 8.2     | 28.6         | 28.8    | 82.6              | 81.3    | 5.6                     | 5.5     | 5.3 | 1.1             | 1.2     | 1.6 | 4.0                     | 4.0     | 5.1 |     |
|          |                   |                 |               | Middle    | 4   | 27.4             | 27.4    | 8.2   | 8.2     | 29.9         | 30.2    | 75.1              | 74.7    | 5.0                     | 5.0     |     | 5.0             | 1.3     |     | 1.3                     | 9.3     |     | 9.3 |
|          |                   |                 |               | Bottom    | 7   | 27.3             | 27.4    | 8.2   | 8.2     | 31.8         | 31.8    | 67.7              | 67.9    | 4.5                     | 4.5     |     | 4.5             | 2.4     |     | 2.4                     | 1.9     |     | 1.9 |
| G2       | Fine              | Calm            | 10:05         | Surface   | 1   | 27.5             | 27.5    | 8.2   | 8.2     | 28.9         | 29.1    | 86.6              | 85.0    | 5.8                     | 5.7     | 5.4 | 1.2             | 1.2     | 1.7 | 3.0                     | 3.1     | 4.2 |     |
|          |                   |                 |               | Middle    | 5   | 27.3             | 27.4    | 8.2   | 8.2     | 30.8         | 30.9    | 76.3              | 74.6    | 5.1                     | 5.0     |     | 5.1             | 1.7     |     | 1.7                     | 4.8     |     | 4.8 |
|          |                   |                 |               | Bottom    | 9   | 27.5             | 27.5    | 8.2   | 8.2     | 32.2         | 32.2    | 75.0              | 75.0    | 5.0                     | 5.0     |     | 5.0             | 2.1     |     | 2.2                     | 4.8     |     | 4.8 |
| G3       | Fine              | Calm            | 10:17         | Surface   | 1   | 27.4             | 27.4    | 8.2   | 8.2     | 28.5         | 28.6    | 85.5              | 83.3    | 5.8                     | 5.7     | 5.4 | 1.5             | 1.5     | 1.7 | 4.5                     | 4.4     | 4.1 |     |
|          |                   |                 |               | Middle    | 4   | 27.3             | 27.3    | 8.2   | 8.2     | 30.6         | 30.4    | 75.5              | 73.6    | 5.0                     | 4.9     |     | 5.0             | 1.3     |     | 1.3                     | 4.2     |     | 4.2 |
|          |                   |                 |               | Bottom    | 7   | 27.3             | 27.3    | 8.2   | 8.2     | 31.4         | 31.6    | 64.4              | 64.6    | 4.3                     | 4.3     |     | 4.3             | 2.2     |     | 2.2                     | 3.8     |     | 3.8 |
| G4       | Fine              | Calm            | 10:26         | Surface   | 1   | 27.4             | 27.4    | 8.2   | 8.2     | 28.6         | 28.7    | 87.6              | 86.2    | 5.9                     | 5.8     | 5.4 | 1.5             | 1.5     | 2.1 | 2.8                     | 2.8     | 3.5 |     |
|          |                   |                 |               | Middle    | 4   | 27.4             | 27.4    | 8.2   | 8.2     | 31.4         | 31.5    | 75.7              | 75.7    | 5.0                     | 5.0     |     | 5.0             | 2.2     |     | 2.3                     | 3.2     |     | 3.1 |
|          |                   |                 |               | Bottom    | 7   | 27.4             | 27.4    | 8.2   | 8.2     | 31.8         | 31.8    | 70.5              | 73.8    | 4.7                     | 4.9     |     | 4.8             | 2.6     |     | 2.6                     | 4.5     |     | 4.4 |
| M1       | Fine              | Calm            | 10:09         | Surface   | 1   | 27.5             | 27.6    | 8.2   | 8.2     | 28.8         | 28.8    | 84.8              | 83.6    | 5.7                     | 5.6     | 5.5 | 1.2             | 1.2     | 1.1 | 3.3                     | 3.3     | 3.0 |     |
|          |                   |                 |               | Middle    | 3   | 27.5             | 27.5    | 8.2   | 8.2     | 29.3         | 29.2    | 79.3              | 81.9    | 5.3                     | 5.4     |     | 5.4             | 1.2     |     | 1.2                     | 2.9     |     | 3.0 |
|          |                   |                 |               | Bottom    | 5   | 27.4             | 27.4    | 8.2   | 8.2     | 31.0         | 31.0    | 75.8              | 73.7    | 5.1                     | 5.0     |     | 5.0             | 1.0     |     | 1.0                     | 2.8     |     | 2.8 |
| M2       | Fine              | Calm            | 10:00         | Surface   | 1   | 27.4             | 27.4    | 8.2   | 8.2     | 29.3         | 29.4    | 89.4              | 86.0    | 6.0                     | 5.8     | 5.4 | 1.2             | 1.2     | 2.1 | 3.3                     | 3.3     | 3.7 |     |
|          |                   |                 |               | Middle    | 6   | 27.3             | 27.3    | 8.2   | 8.2     | 31.5         | 31.4    | 73.3              | 73.3    | 4.9                     | 4.9     |     | 4.9             | 2.5     |     | 2.5                     | 3.5     |     | 3.5 |
|          |                   |                 |               | Bottom    | 11  | 27.5             | 27.5    | 8.2   | 8.2     | 32.3         | 32.3    | 76.9              | 76.9    | 5.1                     | 5.1     |     | 5.1             | 2.7     |     | 2.7                     | 4.3     |     | 4.3 |
| M3       | Fine              | Calm            | 10:20         | Surface   | 1   | 27.4             | 27.4    | 8.2   | 8.2     | 28.8         | 29.1    | 76.5              | 76.5    | 5.2                     | 5.2     | 5.1 | 2.1             | 2.1     | 2.3 | 5.4                     | 5.4     | 6.0 |     |
|          |                   |                 |               | Middle    | 4   | 27.3             | 27.3    | 8.2   | 8.2     | 30.6         | 30.7    | 74.7              | 74.2    | 5.0                     | 5.0     |     | 5.0             | 2.2     |     | 2.2                     | 6.5     |     | 6.5 |
|          |                   |                 |               | Bottom    | 7   | 27.3             | 27.3    | 8.1   | 8.1     | 31.7         | 31.8    | 65.2              | 65.1    | 4.3                     | 4.3     |     | 4.3             | 2.5     |     | 2.5                     | 6.1     |     | 6.1 |
| M4       | Fine              | Calm            | 09:54         | Surface   | 1   | 27.5             | 27.6    | 8.2   | 8.2     | 28.9         | 28.8    | 87.7              | 86.2    | 5.9                     | 5.8     | 5.5 | 1.3             | 1.3     | 1.5 | 3.9                     | 4.0     | 3.2 |     |
|          |                   |                 |               | Middle    | 4   | 27.4             | 27.4    | 8.2   | 8.2     | 30.5         | 30.3    | 77.6              | 77.4    | 5.2                     | 5.2     |     | 5.2             | 1.0     |     | 1.0                     | 3.3     |     | 3.4 |
|          |                   |                 |               | Bottom    | 7   | 27.4             | 27.4    | 8.2   | 8.2     | 30.6         | 30.6    | 73.1              | 72.5    | 4.9                     | 4.9     |     | 4.9             | 2.2     |     | 2.2                     | 2.3     |     | 2.3 |
| M5       | Fine              | Calm            | 10:34         | Surface   | 1   | 27.7             | 27.7    | 8.2   | 8.2     | 26.1         | 26.3    | 93.6              | 91.8    | 6.4                     | 6.3     | 5.8 | 2.5             | 2.4     | 1.7 | 4.7                     | 4.8     | 3.2 |     |
|          |                   |                 |               | Middle    | 5.5 | 27.4             | 27.4    | 8.2   | 8.2     | 31.3         | 31.3    | 78.3              | 77.8    | 5.2                     | 5.2     |     | 5.2             | 0.7     |     | 0.7                     | 3.5     |     | 3.5 |
|          |                   |                 |               | Bottom    | 10  | 27.4             | 27.4    | 8.2   | 8.2     | 31.7         | 31.7    | 72.5              | 73.9    | 4.8                     | 4.9     |     | 4.9             | 2.0     |     | 1.9                     | 1.2     |     | 1.2 |
| M6       | Fine              | Calm            | 10:30         | Surface   | -   | -                | -       | -     | -       | -            | -       | -                 | -       | -                       | -       | 5.6 | -               | -       | 0.8 | -                       | -       | 4.1 |     |
|          |                   |                 |               | Middle    | 2.1 | 27.3             | 27.3    | 8.2   | 8.2     | 29.7         | 29.7    | 83.0              | 82.3    | 5.6                     | 5.6     |     | 5.6             | 0.8     |     | 0.8                     | 4.0     |     | 4.1 |
|          |                   |                 |               | Bottom    | -   | -                | -       | -     | -       | -            | -       | -                 | -       | -                       | -       |     | -               | -       |     | -                       | -       |     | -   |

Remarks: \*DA: Depth-Averaged  
 \*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

**Appendix I - Action and Limit Levels for Marine Water Quality on 9 June 2018 (Mid-Flood Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 4.8 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 5.2 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 5.5 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.0 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 5.5 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.0 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 5.4 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 5.9 mg/L</u>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction**  
**Water Quality Monitoring Results on 09 June 2018**

**(Mid-Flood Tide)**

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) |      | Temperature (°C) |         | pH         |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         |     | Turbidity(NTU) |         |     | Suspended Solids (mg/L) |         |     |
|----------|-------------------|-----------------|---------------|-----------|------|------------------|---------|------------|---------|--------------|---------|-------------------|---------|-------------------------|---------|-----|----------------|---------|-----|-------------------------|---------|-----|
|          |                   |                 |               |           |      | Value            | Average | Value      | Average | Value        | Average | Value             | Average | Value                   | Average | DA* | Value          | Average | DA* | Value                   | Average | DA* |
| C1       | Fine              | Calm            | 14:29         | Surface   | 1    | 27.8<br>28.2     | 28.0    | 8.2<br>8.2 | 8.2     | 29.3<br>29.3 | 29.3    | 86.4<br>87.0      | 86.7    | 5.8<br>5.8              | 5.8     | 5.6 | 1.0<br>1.0     | 1.0     | 1.9 | 4.5<br>4.7              | 4.6     | 4.6 |
|          |                   |                 |               | Middle    | 9    | 27.6<br>27.6     | 27.6    | 8.2<br>8.2 | 8.2     | 31.8<br>31.6 | 31.7    | 81.5<br>81.1      | 81.3    | 5.4<br>5.4              | 5.4     |     | 0.6<br>0.6     | 0.6     |     | 4.7<br>4.5              | 4.7     |     |
|          |                   |                 |               | Bottom    | 17   | 28.0<br>28.0     | 28.0    | 8.3<br>8.3 | 8.3     | 32.9<br>32.9 | 32.9    | 88.5<br>88.3      | 88.4    | 5.8<br>5.8              | 5.8     |     | 4.0<br>4.0     | 4.0     |     | 4.5<br>4.5              | 4.5     |     |
| C2       | Fine              | Calm            | 13:37         | Surface   | 1    | 27.7<br>27.7     | 27.7    | 8.0<br>8.1 | 8.1     | 29.6<br>29.7 | 29.7    | 82.0<br>81.9      | 82.0    | 5.5<br>5.5              | 5.5     | 5.3 | 0.5<br>0.5     | 0.5     | 1.5 | 5.2<br>5.2              | 5.2     | 5.0 |
|          |                   |                 |               | Middle    | 15.5 | 27.4<br>27.4     | 27.4    | 8.1<br>8.2 | 8.2     | 32.3<br>32.3 | 32.3    | 75.6<br>75.4      | 75.5    | 5.0<br>5.0              | 5.0     |     | 1.9<br>1.9     | 1.9     |     | 4.8<br>4.8              | 4.8     |     |
|          |                   |                 |               | Bottom    | 30   | 27.5<br>27.4     | 27.5    | 8.1<br>8.2 | 8.2     | 32.4<br>32.3 | 32.4    | 76.4<br>75.4      | 75.9    | 5.0<br>5.0              | 5.0     |     | 2.1<br>2.0     | 2.1     |     | 4.8<br>5.0              | 4.9     |     |
| G1       | Fine              | Calm            | 14:00         | Surface   | 1    | 28.1<br>27.8     | 28.0    | 8.1<br>8.2 | 8.2     | 29.1<br>29.8 | 29.5    | 87.8<br>78.9      | 83.4    | 5.7<br>5.3              | 5.6     | 5.4 | 0.9<br>0.9     | 0.9     | 2.2 | 4.1<br>4.3              | 4.2     | 5.1 |
|          |                   |                 |               | Middle    | 4    | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.1<br>31.1 | 31.1    | 77.3<br>76.7      | 77.0    | 5.1<br>5.1              | 5.1     |     | 1.0<br>1.0     | 1.0     |     | 6.9<br>7.0              | 7.0     |     |
|          |                   |                 |               | Bottom    | 7    | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 32.0<br>32.0 | 32.0    | 71.8<br>69.4      | 70.6    | 4.8<br>4.6              | 4.7     |     | 4.3<br>4.9     | 4.6     |     | 4.1<br>4.1              | 4.2     |     |
| G2       | Fine              | Calm            | 13:53         | Surface   | 1    | 27.9<br>27.7     | 27.8    | 8.1<br>8.2 | 8.2     | 29.7<br>30.3 | 30.0    | 84.2<br>78.5      | 81.4    | 5.6<br>5.2              | 5.4     | 5.2 | 1.1<br>1.1     | 1.1     | 1.6 | 2.7<br>2.8              | 2.8     | 3.6 |
|          |                   |                 |               | Middle    | 5    | 27.4<br>27.5     | 27.5    | 8.1<br>8.2 | 8.2     | 31.3<br>31.2 | 31.3    | 74.6<br>74.4      | 74.5    | 5.0<br>4.9              | 5.0     |     | 1.5<br>1.3     | 1.4     |     | 3.4<br>3.5              | 3.5     |     |
|          |                   |                 |               | Bottom    | 9    | 27.5<br>27.5     | 27.5    | 8.2<br>8.2 | 8.2     | 32.0<br>32.2 | 32.1    | 77.8<br>78.4      | 78.1    | 5.1<br>5.2              | 5.2     |     | 2.3<br>2.3     | 2.3     |     | 4.4<br>4.3              | 4.4     |     |
| G3       | Fine              | Calm            | 14:05         | Surface   | 1    | 28.0<br>27.7     | 27.9    | 8.2<br>8.2 | 8.2     | 28.9<br>29.3 | 29.1    | 85.9<br>82.7      | 84.3    | 5.7<br>5.5              | 5.6     | 5.4 | 1.0<br>1.0     | 1.0     | 1.2 | 2.6<br>2.7              | 2.7     | 3.3 |
|          |                   |                 |               | Middle    | 4    | 27.4<br>27.5     | 27.5    | 8.2<br>8.2 | 8.2     | 31.0<br>30.8 | 30.9    | 77.5<br>77.1      | 77.3    | 5.2<br>5.1              | 5.2     |     | 1.0<br>1.1     | 1.1     |     | 3.8<br>3.7              | 3.8     |     |
|          |                   |                 |               | Bottom    | 7    | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.6<br>31.7 | 31.7    | 71.0<br>70.1      | 70.6    | 4.7<br>4.7              | 4.7     |     | 1.5<br>1.6     | 1.6     |     | 3.4<br>3.4              | 3.4     |     |
| G4       | Fine              | Calm            | 14:14         | Surface   | 1    | 27.8<br>27.7     | 27.8    | 8.2<br>8.2 | 8.2     | 28.6<br>28.8 | 28.7    | 88.8<br>86.2      | 87.5    | 6.0<br>5.8              | 5.9     | 5.6 | 1.1<br>1.3     | 1.2     | 2.2 | 4.2<br>4.2              | 4.2     | 4.1 |
|          |                   |                 |               | Middle    | 4.5  | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.1<br>31.0 | 31.1    | 78.2<br>78.6      | 78.4    | 5.2<br>5.2              | 5.2     |     | 0.8<br>0.7     | 0.8     |     | 3.5<br>3.4              | 3.5     |     |
|          |                   |                 |               | Bottom    | 8    | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.9<br>31.8 | 31.9    | 67.5<br>72.3      | 69.9    | 4.5<br>4.8              | 4.7     |     | 4.9<br>4.1     | 4.5     |     | 4.6<br>4.6              | 4.6     |     |
| M1       | Fine              | Calm            | 13:57         | Surface   | 1    | 27.7<br>27.6     | 27.7    | 8.1<br>8.2 | 8.2     | 29.9<br>30.0 | 30.0    | 80.0<br>79.1      | 79.6    | 5.3<br>5.3              | 5.3     | 5.3 | 1.8<br>1.7     | 1.8     | 1.3 | 2.8<br>2.8              | 2.8     | 2.8 |
|          |                   |                 |               | Middle    | 3    | 27.5<br>27.5     | 27.5    | 8.1<br>8.2 | 8.2     | 30.6<br>30.7 | 30.7    | 78.7<br>78.6      | 78.7    | 5.2<br>5.2              | 5.2     |     | 1.0<br>1.1     | 1.1     |     | 3.1<br>3.2              | 3.2     |     |
|          |                   |                 |               | Bottom    | 5    | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.2<br>31.1 | 31.2    | 76.9<br>76.9      | 76.9    | 5.1<br>5.1              | 5.1     |     | 0.9<br>0.8     | 0.9     |     | 2.5<br>2.5              | 2.5     |     |
| M2       | Fine              | Calm            | 13:48         | Surface   | 1    | 27.7<br>27.8     | 27.8    | 8.2<br>8.2 | 8.2     | 29.9<br>29.8 | 29.9    | 83.4<br>82.2      | 82.8    | 5.6<br>5.5              | 5.6     | 5.4 | 1.3<br>1.3     | 1.3     | 1.7 | 3.6<br>3.6              | 3.6     | 3.4 |
|          |                   |                 |               | Middle    | 5.5  | 27.4<br>27.5     | 27.5    | 8.2<br>8.2 | 8.2     | 31.8<br>31.9 | 31.9    | 76.7<br>76.5      | 76.6    | 5.1<br>5.1              | 5.1     |     | 1.4<br>1.5     | 1.5     |     | 3.0<br>3.1              | 3.1     |     |
|          |                   |                 |               | Bottom    | 10   | 27.6<br>27.6     | 27.6    | 8.2<br>8.2 | 8.2     | 32.4<br>32.4 | 32.4    | 77.6<br>77.3      | 77.5    | 5.1<br>5.1              | 5.1     |     | 2.1<br>2.2     | 2.2     |     | 3.5<br>3.4              | 3.5     |     |
| M3       | Fine              | Calm            | 14:09         | Surface   | 1    | 27.7<br>27.6     | 27.7    | 8.2<br>8.2 | 8.2     | 29.3<br>29.7 | 29.5    | 84.1<br>80.9      | 82.5    | 5.6<br>5.4              | 5.5     | 5.3 | 1.4<br>1.4     | 1.4     | 1.5 | 3.8<br>4.0              | 3.9     | 3.2 |
|          |                   |                 |               | Middle    | 4    | 27.4<br>27.5     | 27.5    | 8.2<br>8.2 | 8.2     | 30.8<br>30.5 | 30.7    | 77.1<br>76.1      | 76.6    | 5.1<br>5.1              | 5.1     |     | 1.2<br>1.2     | 1.2     |     | 2.7<br>2.8              | 2.8     |     |
|          |                   |                 |               | Bottom    | 7    | 27.3<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 31.7<br>31.6 | 31.7    | 67.2<br>67.7      | 67.5    | 4.5<br>4.5              | 4.5     |     | 1.9<br>1.8     | 1.9     |     | 2.9<br>2.9              | 2.9     |     |
| M4       | Fine              | Calm            | 13:42         | Surface   | 1    | 27.7<br>27.8     | 27.8    | 8.1<br>8.1 | 8.1     | 29.7<br>29.5 | 29.6    | 89.0<br>86.1      | 87.6    | 5.9<br>5.7              | 5.8     | 5.6 | 0.8<br>0.9     | 0.9     | 1.0 | 3.6<br>3.7              | 3.7     | 2.5 |
|          |                   |                 |               | Middle    | 5    | 27.6<br>27.6     | 27.6    | 8.1<br>8.1 | 8.1     | 30.4<br>30.2 | 30.3    | 80.7<br>80.9      | 80.8    | 5.4<br>5.4              | 5.4     |     | 0.9<br>0.9     | 0.9     |     | 1.1<br>1.1              | 1.1     |     |
|          |                   |                 |               | Bottom    | 9    | 27.4<br>27.5     | 27.5    | 8.1<br>8.1 | 8.1     | 31.5<br>30.9 | 31.2    | 76.4<br>75.8      | 76.1    | 5.1<br>5.0              | 5.1     |     | 1.2<br>1.1     | 1.2     |     | 2.7<br>2.7              | 2.7     |     |
| M5       | Fine              | Calm            | 14:24         | Surface   | 1    | 28.0<br>28.0     | 28.0    | 8.2<br>8.2 | 8.2     | 28.4<br>28.3 | 28.4    | 91.9<br>88.6      | 90.3    | 6.2<br>5.9              | 6.1     | 5.7 | 1.3<br>1.2     | 1.3     | 1.7 | 5.3<br>5.3              | 5.3     | 4.8 |
|          |                   |                 |               | Middle    | 5.5  | 27.6<br>27.7     | 27.7    | 8.2<br>8.2 | 8.2     | 31.9<br>31.7 | 31.8    | 80.9<br>80.0      | 80.5    | 5.3<br>5.3              | 5.3     |     | 1.1<br>1.1     | 1.1     |     | 6.3<br>6.2              | 6.3     |     |
|          |                   |                 |               | Bottom    | 10   | 27.7<br>27.9     | 27.8    | 8.2<br>8.3 | 8.3     | 32.6<br>32.8 | 32.7    | 85.9<br>85.5      | 85.7    | 5.6<br>5.6              | 5.6     |     | 2.6<br>2.6     | 2.6     |     | 2.8<br>2.7              | 2.8     |     |
| M6       | Fine              | Calm            | 14:19         | Surface   | -    | -                | -       | -          | -       | -            | -       | -                 | -       | -                       | 5.2     | -   | -              | 0.7     | -   | -                       | 3.4     |     |
|          |                   |                 |               | Middle    | 2    | 27.4<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 30.9<br>30.9 | 30.9    | 78.0<br>76.9      | 77.5    | 5.2<br>5.1              |         | 5.2 | 0.7<br>0.7     |         | 0.7 | 3.4<br>3.4              |         | 3.4 |
|          |                   |                 |               | Bottom    | -    | -                | -       | -          | -       | -            | -       | -                 | -       | -                       |         | -   | -              |         | -   | -                       |         | -   |

Remarks: \*DA: Depth-Averaged  
 \*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.



**Appendix I - Action and Limit Levels for Marine Water Quality on 11 June 2018 (Mid-Ebb Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 3.8 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 4.2 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.5 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.0 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.5 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.0 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.3 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 8.0 mg/L</u>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction**  
**Water Quality Monitoring Results on 11 June 2018**

**(Mid-Ebb Tide)**

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) |     | Temperature (°C) |         | pH    |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         | Turbidity(NTU) |       |         | Suspended Solids (mg/L) |       |         |     |
|----------|-------------------|-----------------|---------------|-----------|-----|------------------|---------|-------|---------|--------------|---------|-------------------|---------|-------------------------|---------|----------------|-------|---------|-------------------------|-------|---------|-----|
|          |                   |                 |               |           |     | Value            | Average | Value | Average | Value        | Average | Value             | Average | Value                   | Average | DA*            | Value | Average | DA*                     | Value | Average | DA* |
| C1       | Sunny             | Calm            | 10:59         | Surface   | 1   | 28.1             | 28.1    | 8.2   | 8.2     | 30.9         | 30.9    | 94.1              | 93.7    | 6.2                     | 6.2     | 6.1            | 1.1   | 1.1     | 1.4                     | 5.2   | 5.2     | 4.7 |
|          |                   |                 |               | Middle    | 9   | 28.2             | 28.2    | 8.3   | 8.3     | 31.6         | 31.6    | 89.9              | 90.2    | 5.9                     | 5.9     |                | 1.1   | 1.1     |                         | 4.3   | 4.3     |     |
|          |                   |                 |               | Bottom    | 17  | 28.2             | 28.2    | 8.3   | 8.3     | 31.6         | 31.6    | 89.3              | 89.4    | 5.8                     | 5.9     |                | 2.1   | 2.0     |                         | 4.7   | 4.7     |     |
| C2       | Sunny             | Calm            | 10:00         | Surface   | 1   | 28.1             | 28.1    | 8.1   | 8.2     | 30.8         | 30.8    | 93.5              | 93.0    | 6.2                     | 6.2     | 6.0            | 0.6   | 0.7     | 2.1                     | 5.5   | 5.4     | 5.3 |
|          |                   |                 |               | Middle    | 17  | 28.1             | 28.1    | 8.2   | 8.2     | 31.6         | 31.6    | 86.5              | 86.5    | 5.7                     | 5.7     |                | 2.4   | 2.5     |                         | 4.3   | 4.3     |     |
|          |                   |                 |               | Bottom    | 33  | 28.2             | 28.2    | 8.2   | 8.2     | 31.8         | 31.8    | 86.7              | 86.3    | 5.7                     | 5.7     |                | 3.3   | 3.2     |                         | 6.1   | 6.1     |     |
| G1       | Sunny             | Calm            | 10:29         | Surface   | 1   | 28.2             | 28.2    | 8.3   | 8.3     | 30.9         | 31.0    | 100.1             | 99.5    | 6.6                     | 6.6     | 6.6            | 0.7   | 0.7     | 0.8                     | 4.6   | 4.7     | 4.6 |
|          |                   |                 |               | Middle    | 4   | 28.2             | 28.2    | 8.3   | 8.3     | 31.2         | 31.2    | 98.7              | 98.6    | 6.5                     | 6.5     |                | 0.6   | 0.7     |                         | 4.1   | 4.2     |     |
|          |                   |                 |               | Bottom    | 7   | 28.1             | 28.1    | 8.3   | 8.3     | 31.3         | 31.4    | 91.3              | 90.1    | 6.0                     | 6.0     |                | 1.0   | 1.0     |                         | 4.9   | 5.0     |     |
| G2       | Sunny             | Calm            | 10:18         | Surface   | 1   | 28.2             | 28.2    | 8.3   | 8.3     | 31.0         | 31.0    | 101.7             | 101.5   | 6.7                     | 6.7     | 6.5            | 0.7   | 0.7     | 1.7                     | 5.7   | 5.7     | 5.7 |
|          |                   |                 |               | Middle    | 5.5 | 28.1             | 28.1    | 8.3   | 8.3     | 31.3         | 31.3    | 93.9              | 94.2    | 6.2                     | 6.2     |                | 0.7   | 0.7     |                         | 6.4   | 6.5     |     |
|          |                   |                 |               | Bottom    | 10  | 28.1             | 28.1    | 8.2   | 8.2     | 31.7         | 31.7    | 85.6              | 85.4    | 5.6                     | 5.6     |                | 3.6   | 3.6     |                         | 4.8   | 4.8     |     |
| G3       | Sunny             | Calm            | 10:37         | Surface   | 1   | 28.1             | 28.1    | 8.2   | 8.2     | 31.0         | 31.0    | 90.4              | 88.3    | 6.0                     | 5.9     | 5.8            | 1.4   | 1.5     | 1.7                     | 4.8   | 4.9     | 5.7 |
|          |                   |                 |               | Middle    | 4   | 28.0             | 28.0    | 8.2   | 8.2     | 31.2         | 31.2    | 88.8              | 87.0    | 5.8                     | 5.7     |                | 1.4   | 1.5     |                         | 7.8   | 7.7     |     |
|          |                   |                 |               | Bottom    | 7   | 28.0             | 28.0    | 8.2   | 8.2     | 31.4         | 31.4    | 79.9              | 83.7    | 5.3                     | 5.4     |                | 2.0   | 2.0     |                         | 4.6   | 4.6     |     |
| G4       | Sunny             | Calm            | 10:45         | Surface   | 1   | 28.2             | 28.2    | 8.3   | 8.3     | 31.0         | 31.0    | 99.0              | 99.5    | 6.5                     | 6.6     | 6.5            | 0.8   | 0.8     | 0.8                     | 4.0   | 4.0     | 4.7 |
|          |                   |                 |               | Middle    | 4   | 28.2             | 28.2    | 8.3   | 8.3     | 31.2         | 31.3    | 98.1              | 97.3    | 6.4                     | 6.4     |                | 0.7   | 0.8     |                         | 4.9   | 4.9     |     |
|          |                   |                 |               | Bottom    | 7   | 28.2             | 28.2    | 8.3   | 8.3     | 31.4         | 31.4    | 93.9              | 95.1    | 6.2                     | 6.2     |                | 0.9   | 0.9     |                         | 5.2   | 5.1     |     |
| M1       | Sunny             | Calm            | 10:24         | Surface   | 1   | 28.1             | 28.1    | 8.2   | 8.2     | 31.0         | 31.0    | 94.4              | 94.2    | 6.2                     | 6.2     | 6.2            | 1.0   | 1.0     | 0.9                     | 5.7   | 5.7     | 4.9 |
|          |                   |                 |               | Middle    | 3   | 28.1             | 28.1    | 8.2   | 8.2     | 31.1         | 31.1    | 94.8              | 94.4    | 6.2                     | 6.2     |                | 0.9   | 0.9     |                         | 4.8   | 4.8     |     |
|          |                   |                 |               | Bottom    | 5   | 28.1             | 28.1    | 8.2   | 8.2     | 31.1         | 31.1    | 94.0              | 93.6    | 6.2                     | 6.2     |                | 0.8   | 0.8     |                         | 4.2   | 4.1     |     |
| M2       | Sunny             | Calm            | 10:13         | Surface   | 1   | 28.2             | 28.2    | 8.3   | 8.3     | 31.0         | 31.0    | 101.9             | 101.5   | 6.7                     | 6.7     | 6.5            | 0.6   | 0.6     | 1.6                     | 5.8   | 6.0     | 5.1 |
|          |                   |                 |               | Middle    | 6   | 28.1             | 28.1    | 8.2   | 8.2     | 31.3         | 31.3    | 93.2              | 93.6    | 6.1                     | 6.2     |                | 0.9   | 0.9     |                         | 5.5   | 5.6     |     |
|          |                   |                 |               | Bottom    | 11  | 28.1             | 28.1    | 8.2   | 8.2     | 31.7         | 31.7    | 82.3              | 84.9    | 5.4                     | 5.5     |                | 3.3   | 3.3     |                         | 3.8   | 3.8     |     |
| M3       | Sunny             | Calm            | 10:40         | Surface   | 1   | 28.1             | 28.1    | 8.2   | 8.2     | 30.9         | 30.9    | 90.6              | 91.4    | 6.0                     | 6.1     | 6.1            | 1.1   | 1.1     | 1.5                     | 4.8   | 4.8     | 4.5 |
|          |                   |                 |               | Middle    | 4   | 28.1             | 28.1    | 8.2   | 8.2     | 31.1         | 31.2    | 91.6              | 91.5    | 6.0                     | 6.0     |                | 1.1   | 1.2     |                         | 3.7   | 3.8     |     |
|          |                   |                 |               | Bottom    | 7   | 28.0             | 28.0    | 8.2   | 8.2     | 31.4         | 31.4    | 80.0              | 77.9    | 5.3                     | 5.2     |                | 2.1   | 2.1     |                         | 5.0   | 5.0     |     |
| M4       | Sunny             | Calm            | 10:07         | Surface   | 1   | 28.2             | 28.2    | 8.2   | 8.2     | 31.0         | 31.0    | 101.0             | 100.2   | 6.6                     | 6.6     | 6.5            | 0.6   | 0.6     | 1.6                     | 5.3   | 5.4     | 3.7 |
|          |                   |                 |               | Middle    | 5   | 28.1             | 28.1    | 8.2   | 8.2     | 31.2         | 31.2    | 96.1              | 95.5    | 6.3                     | 6.3     |                | 0.8   | 0.8     |                         | 2.9   | 2.9     |     |
|          |                   |                 |               | Bottom    | 9   | 28.1             | 28.1    | 8.2   | 8.2     | 31.4         | 31.5    | 89.1              | 89.1    | 5.9                     | 5.9     |                | 3.4   | 3.5     |                         | 2.9   | 2.9     |     |
| M5       | Sunny             | Calm            | 10:54         | Surface   | 1   | 28.2             | 28.2    | 8.3   | 8.3     | 31.0         | 31.0    | 108.3             | 107.8   | 7.1                     | 7.1     | 6.9            | 0.7   | 0.7     | 0.7                     | 4.8   | 4.8     | 5.2 |
|          |                   |                 |               | Middle    | 5.5 | 28.2             | 28.2    | 8.3   | 8.3     | 31.2         | 31.1    | 99.7              | 100.0   | 6.6                     | 6.6     |                | 0.7   | 0.7     |                         | 5.7   | 5.8     |     |
|          |                   |                 |               | Bottom    | 10  | 28.1             | 28.1    | 8.3   | 8.3     | 31.1         | 31.2    | 97.6              | 96.4    | 6.4                     | 6.4     |                | 0.7   | 0.8     |                         | 4.9   | 4.9     |     |
| M6       | Sunny             | Calm            | 10:49         | Surface   | -   | -                | -       | -     | -       | -            | -       | -                 | -       | -                       | -       | 6.1            | -     | -       | 1.0                     | -     | -       | 6.5 |
|          |                   |                 |               | Middle    | 2.1 | 28.1             | 28.1    | 8.2   | 8.2     | 31.2         | 31.2    | 93.4              | 93.1    | 6.1                     | 6.1     |                | 1.0   | 1.0     |                         | 6.5   | 6.5     |     |
|          |                   |                 |               | Bottom    | -   | -                | -       | -     | -       | -            | -       | -                 | -       | -                       | -       |                | -     | -       |                         | -     | -       |     |

Remarks: \*DA: Depth-Averaged  
 \*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

**Appendix I - Action and Limit Levels for Marine Water Quality on 11 June 2018 (Mid-Flood Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 5.4 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 5.9 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 7.0 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 7.5 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 7.0 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 7.5 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 7.8 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 8.5 mg/L</u>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction**  
**Water Quality Monitoring Results on 11 June 2018**

**(Mid-Flood Tide)**

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) |     | Temperature (°C) |         | pH    |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         |       | Turbidity(NTU) |     |       | Suspended Solids (mg/L) |     |       |
|----------|-------------------|-----------------|---------------|-----------|-----|------------------|---------|-------|---------|--------------|---------|-------------------|---------|-------------------------|---------|-------|----------------|-----|-------|-------------------------|-----|-------|
|          |                   |                 |               |           |     | Value            | Average | Value | Average | Value        | Average | Value             | Average | Value                   | Average | Value | Average        | DA* | Value | Average                 | DA* | Value |
| C1       | Sunny             | Calm            | 16:24         | Surface   | 1   | 28.4             | 28.4    | 8.3   | 8.3     | 30.6         | 30.6    | 102.4             | 102.8   | 6.7                     | 6.8     | 6.7   | 0.8            | 0.8 | 1.3   | 5.8                     | 5.8 | 6.2   |
|          |                   |                 |               | Middle    | 9   | 28.2             | 28.2    | 8.3   | 8.3     | 30.9         | 31.0    | 100.2             | 98.8    | 6.6                     | 6.5     | 6.7   | 0.7            | 0.7 |       | 5.8                     | 5.8 |       |
|          |                   |                 |               | Bottom    | 17  | 28.2             | 28.2    | 8.3   | 8.3     | 31.5         | 31.5    | 90.3              | 90.3    | 5.9                     | 5.9     | 5.9   | 2.5            | 2.5 |       | 6.3                     | 6.3 |       |
| C2       | Sunny             | Calm            | 15:27         | Surface   | 1   | 28.4             | 28.4    | 8.1   | 8.2     | 30.3         | 30.3    | 100.4             | 99.7    | 6.6                     | 6.6     | 6.2   | 0.6            | 0.6 | 1.4   | 5.4                     | 5.4 | 4.8   |
|          |                   |                 |               | Middle    | 17  | 28.1             | 28.1    | 8.2   | 8.2     | 31.5         | 31.4    | 88.3              | 88.1    | 5.8                     | 5.8     | 6.2   | 1.3            | 1.3 |       | 5.4                     | 5.4 |       |
|          |                   |                 |               | Bottom    | 33  | 28.2             | 28.2    | 8.2   | 8.2     | 31.7         | 31.7    | 90.2              | 89.9    | 5.9                     | 5.9     | 5.9   | 2.2            | 2.2 |       | 3.3                     | 3.3 |       |
| G1       | Sunny             | Calm            | 15:53         | Surface   | 1   | 29.4             | 29.3    | 8.3   | 8.3     | 30.9         | 30.9    | 128.7             | 128.9   | 8.3                     | 8.4     | 8.2   | 0.9            | 0.9 | 1.0   | 5.0                     | 5.1 | 4.9   |
|          |                   |                 |               | Middle    | 4   | 28.4             | 28.5    | 8.3   | 8.3     | 31.1         | 31.1    | 120.4             | 119.6   | 7.9                     | 7.9     | 8.2   | 0.9            | 1.0 |       | 4.8                     | 4.8 |       |
|          |                   |                 |               | Bottom    | 7   | 28.2             | 28.2    | 8.3   | 8.3     | 31.3         | 31.3    | 100.4             | 99.0    | 6.6                     | 6.5     | 6.5   | 1.1            | 1.2 |       | 4.8                     | 4.9 |       |
| G2       | Sunny             | Calm            | 15:44         | Surface   | 1   | 28.9             | 29.1    | 8.3   | 8.3     | 31.0         | 31.0    | 132.8             | 133.2   | 8.6                     | 8.6     | 8.3   | 0.8            | 0.8 | 1.0   | 4.4                     | 4.4 | 4.3   |
|          |                   |                 |               | Middle    | 5   | 28.6             | 28.6    | 8.3   | 8.3     | 31.1         | 31.1    | 124.7             | 122.0   | 8.1                     | 8.0     | 8.3   | 0.9            | 1.0 |       | 4.4                     | 4.4 |       |
|          |                   |                 |               | Bottom    | 9   | 28.2             | 28.3    | 8.3   | 8.3     | 31.3         | 31.3    | 101.9             | 102.2   | 6.7                     | 6.7     | 6.7   | 1.1            | 1.1 |       | 3.7                     | 3.7 |       |
| G3       | Sunny             | Calm            | 15:58         | Surface   | 1   | 29.0             | 29.0    | 8.3   | 8.3     | 30.7         | 30.7    | 130.5             | 129.7   | 8.5                     | 8.5     | 7.9   | 1.0            | 1.0 | 1.1   | 5.6                     | 5.8 | 5.5   |
|          |                   |                 |               | Middle    | 4   | 28.4             | 28.4    | 8.3   | 8.3     | 31.1         | 31.1    | 110.2             | 110.3   | 7.2                     | 7.2     | 7.9   | 1.2            | 1.2 |       | 5.7                     | 5.8 |       |
|          |                   |                 |               | Bottom    | 7   | 28.2             | 28.2    | 8.3   | 8.3     | 31.3         | 31.4    | 99.9              | 99.4    | 6.6                     | 6.6     | 6.6   | 1.1            | 1.2 |       | 4.7                     | 4.8 |       |
| G4       | Sunny             | Calm            | 16:07         | Surface   | 1   | 29.2             | 29.2    | 8.4   | 8.4     | 31.0         | 31.0    | 132.3             | 132.4   | 8.5                     | 8.6     | 8.4   | 0.9            | 0.9 | 0.9   | 4.1                     | 4.1 | 5.2   |
|          |                   |                 |               | Middle    | 4   | 28.4             | 28.4    | 8.4   | 8.4     | 31.2         | 31.2    | 124.2             | 124.5   | 8.1                     | 8.2     | 8.4   | 0.7            | 0.7 |       | 5.5                     | 5.6 |       |
|          |                   |                 |               | Bottom    | 7   | 28.2             | 28.3    | 8.3   | 8.3     | 31.3         | 31.3    | 101.3             | 103.2   | 6.6                     | 6.8     | 6.8   | 1.0            | 1.0 |       | 5.7                     | 6.0 |       |
| M1       | Sunny             | Calm            | 15:50         | Surface   | 1   | 28.9             | 29.0    | 8.3   | 8.3     | 30.9         | 30.9    | 120.9             | 126.3   | 7.9                     | 8.1     | 7.9   | 1.0            | 1.0 | 1.0   | 5.4                     | 5.5 | 5.3   |
|          |                   |                 |               | Middle    | 3   | 28.7             | 28.8    | 8.3   | 8.3     | 30.9         | 30.9    | 116.8             | 117.6   | 7.6                     | 7.7     | 7.9   | 1.0            | 1.0 |       | 5.2                     | 5.3 |       |
|          |                   |                 |               | Bottom    | 5   | 28.3             | 28.3    | 8.3   | 8.3     | 31.2         | 31.2    | 102.2             | 107.1   | 6.7                     | 7.0     | 7.0   | 1.1            | 1.1 |       | 5.4                     | 5.1 |       |
| M2       | Sunny             | Calm            | 15:39         | Surface   | 1   | 29.2             | 29.2    | 8.3   | 8.4     | 31.0         | 31.0    | 138.0             | 137.4   | 8.9                     | 8.9     | 8.7   | 0.8            | 0.8 | 1.4   | 5.3                     | 5.4 | 5.5   |
|          |                   |                 |               | Middle    | 6   | 28.4             | 28.5    | 8.3   | 8.3     | 31.1         | 31.1    | 126.9             | 128.5   | 8.3                     | 8.4     | 8.7   | 0.7            | 0.7 |       | 5.4                     | 5.4 |       |
|          |                   |                 |               | Bottom    | 11  | 28.1             | 28.1    | 8.3   | 8.3     | 31.6         | 31.6    | 87.8              | 87.6    | 5.8                     | 5.8     | 5.8   | 2.7            | 2.7 |       | 4.4                     | 4.4 |       |
| M3       | Sunny             | Calm            | 16:02         | Surface   | 1   | 28.6             | 28.7    | 8.4   | 8.4     | 30.9         | 30.8    | 130.9             | 129.1   | 8.6                     | 8.5     | 8.0   | 0.9            | 1.0 | 1.1   | 4.4                     | 4.4 | 4.4   |
|          |                   |                 |               | Middle    | 4   | 28.2             | 28.2    | 8.3   | 8.3     | 31.1         | 31.2    | 113.3             | 112.9   | 7.4                     | 7.4     | 8.0   | 1.1            | 1.1 |       | 4.1                     | 4.1 |       |
|          |                   |                 |               | Bottom    | 7   | 28.1             | 28.2    | 8.3   | 8.3     | 31.3         | 31.3    | 96.8              | 98.1    | 6.4                     | 6.5     | 6.5   | 1.2            | 1.2 |       | 4.5                     | 4.7 |       |
| M4       | Sunny             | Calm            | 15:33         | Surface   | 1   | 28.7             | 28.8    | 8.3   | 8.3     | 31.0         | 31.0    | 125.3             | 126.8   | 8.2                     | 8.3     | 8.3   | 0.8            | 0.8 | 0.8   | 4.9                     | 4.6 | 5.0   |
|          |                   |                 |               | Middle    | 5   | 28.6             | 28.7    | 8.3   | 8.3     | 31.0         | 31.0    | 125.6             | 126.6   | 8.2                     | 8.3     | 8.3   | 0.7            | 0.7 |       | 4.3                     | 4.6 |       |
|          |                   |                 |               | Bottom    | 9   | 28.6             | 28.6    | 8.3   | 8.3     | 31.0         | 31.1    | 127.5             | 128.2   | 8.4                     | 8.4     | 8.4   | 0.9            | 0.9 |       | 5.0                     | 5.0 |       |
| M5       | Sunny             | Calm            | 16:18         | Surface   | 1   | 28.3             | 28.3    | 8.3   | 8.3     | 30.9         | 30.9    | 103.4             | 103.5   | 6.8                     | 6.8     | 6.6   | 0.7            | 0.7 | 1.4   | 4.4                     | 4.5 | 5.6   |
|          |                   |                 |               | Middle    | 5.5 | 28.2             | 28.2    | 8.3   | 8.3     | 31.1         | 31.1    | 96.8              | 96.2    | 6.4                     | 6.4     | 6.6   | 0.8            | 0.8 |       | 4.5                     | 4.5 |       |
|          |                   |                 |               | Bottom    | 10  | 28.2             | 28.2    | 8.3   | 8.3     | 31.4         | 31.4    | 90.9              | 90.9    | 6.0                     | 6.0     | 6.0   | 2.7            | 2.6 |       | 8.5                     | 8.5 |       |
| M6       | Sunny             | Calm            | 16:11         | Surface   | -   | -                | -       | -     | -       | -            | -       | -                 | -       | -                       | -       | -     | -              | -   | 0.9   | -                       | -   | 5.8   |
|          |                   |                 |               | Middle    | 2   | 28.4             | 28.4    | 8.4   | 8.4     | 31.1         | 31.1    | 138.9             | 139.1   | 9.1                     | 9.1     | 9.1   | 0.9            | 0.9 |       | 5.8                     | 5.8 |       |
|          |                   |                 |               | Bottom    | -   | -                | -       | -     | -       | -            | -       | -                 | -       | -                       | -       | -     | -              | -   |       | -                       | -   |       |

Remarks: \*DA: Depth-Averaged  
 \*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

**Appendix I - Action and Limit Levels for Marine Water Quality on 13 June 2018 (Mid-Ebb Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 3.0 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 3.3 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.2 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.8 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.0 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.8 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 5.6 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.1 mg/L</u>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction**  
**Water Quality Monitoring Results on 13 June 2018**

**(Mid-Ebb Tide)**

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) |      | Temperature (°C) |         | pH    |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         | Turbidity(NTU) |       |         | Suspended Solids (mg/L) |       |         |     |
|----------|-------------------|-----------------|---------------|-----------|------|------------------|---------|-------|---------|--------------|---------|-------------------|---------|-------------------------|---------|----------------|-------|---------|-------------------------|-------|---------|-----|
|          |                   |                 |               |           |      | Value            | Average | Value | Average | Value        | Average | Value             | Average | Value                   | Average | DA*            | Value | Average | DA*                     | Value | Average | DA* |
| C1       | Rainy             | Moderate        | 12:06         | Surface   | 1    | 28.2             | 28.2    | 8.3   | 8.3     | 31.0         | 31.1    | 87.8              | 87.3    | 5.8                     | 5.8     | 5.7            | 1.3   | 1.4     | 1.6                     | 1.9   | 2.0     | 2.8 |
|          |                   |                 |               | Middle    | 9    | 28.0             | 28.0    | 8.3   | 8.3     | 32.1         | 32.1    | 83.0              | 83.2    | 5.4                     | 5.5     |                | 1.7   | 1.8     |                         | 3.4   | 3.5     |     |
|          |                   |                 |               | Bottom    | 17   | 28.0             | 28.0    | 8.3   | 8.3     | 32.2         | 32.2    | 81.9              | 83.0    | 5.4                     | 5.4     |                | 1.7   | 1.7     |                         | 3.0   | 3.0     |     |
| C2       | Rainy             | Moderate        | 11:03         | Surface   | 1    | 28.1             | 28.1    | 8.2   | 8.3     | 30.9         | 30.9    | 89.3              | 89.1    | 5.9                     | 5.9     | 5.7            | 1.3   | 1.3     | 2.0                     | 5.2   | 5.2     | 4.6 |
|          |                   |                 |               | Middle    | 16.5 | 28.1             | 28.1    | 8.2   | 8.2     | 32.0         | 32.1    | 83.9              | 83.4    | 5.5                     | 5.5     |                | 2.2   | 2.3     |                         | 4.0   | 4.0     |     |
|          |                   |                 |               | Bottom    | 32   | 27.9             | 27.9    | 8.2   | 8.2     | 32.3         | 32.4    | 81.5              | 80.7    | 5.3                     | 5.3     |                | 2.5   | 2.5     |                         | 4.7   | 4.7     |     |
| G1       | Rainy             | Moderate        | 11:32         | Surface   | 1    | 28.4             | 28.4    | 8.3   | 8.3     | 31.7         | 31.7    | 92.3              | 92.4    | 6.0                     | 6.0     | 6.0            | 1.5   | 1.4     | 1.7                     | 5.1   | 5.2     | 4.7 |
|          |                   |                 |               | Middle    | 4    | 28.4             | 28.4    | 8.3   | 8.3     | 31.8         | 31.8    | 91.4              | 90.9    | 6.0                     | 6.0     |                | 1.2   | 1.2     |                         | 6.8   | 6.8     |     |
|          |                   |                 |               | Bottom    | 7    | 28.4             | 28.4    | 8.3   | 8.3     | 32.0         | 31.9    | 87.6              | 89.0    | 5.7                     | 5.8     |                | 2.6   | 2.6     |                         | 2.0   | 2.0     |     |
| G2       | Rainy             | Moderate        | 11:20         | Surface   | 1    | 28.3             | 28.3    | 8.3   | 8.3     | 31.3         | 31.3    | 94.2              | 93.8    | 6.2                     | 6.2     | 6.1            | 1.7   | 1.7     | 1.5                     | 4.4   | 4.5     | 4.0 |
|          |                   |                 |               | Middle    | 5    | 28.4             | 28.4    | 8.3   | 8.3     | 31.7         | 31.7    | 92.6              | 92.4    | 6.0                     | 6.0     |                | 1.3   | 1.3     |                         | 4.5   | 4.5     |     |
|          |                   |                 |               | Bottom    | 9    | 28.3             | 28.4    | 8.3   | 8.3     | 31.8         | 31.9    | 89.5              | 88.4    | 5.8                     | 5.8     |                | 1.6   | 1.6     |                         | 3.1   | 3.1     |     |
| G3       | Rainy             | Moderate        | 11:37         | Surface   | 1    | 28.3             | 28.3    | 8.3   | 8.3     | 31.5         | 31.2    | 86.7              | 86.7    | 5.7                     | 5.7     | 5.9            | 2.1   | 2.3     | 1.7                     | 2.1   | 2.2     | 2.5 |
|          |                   |                 |               | Middle    | 4    | 28.4             | 28.4    | 8.3   | 8.3     | 31.8         | 31.8    | 91.6              | 91.5    | 6.0                     | 6.0     |                | 1.2   | 1.2     |                         | 3.3   | 3.3     |     |
|          |                   |                 |               | Bottom    | 7    | 28.4             | 28.4    | 8.3   | 8.3     | 31.8         | 31.8    | 87.7              | 87.4    | 5.7                     | 5.7     |                | 1.5   | 1.5     |                         | 2.0   | 2.0     |     |
| G4       | Rainy             | Moderate        | 11:49         | Surface   | 1    | 28.3             | 28.3    | 8.3   | 8.3     | 31.6         | 31.6    | 93.3              | 92.1    | 6.1                     | 6.1     | 6.0            | 1.5   | 1.4     | 1.6                     | 5.6   | 5.7     | 4.1 |
|          |                   |                 |               | Middle    | 4.5  | 28.3             | 28.3    | 8.3   | 8.3     | 31.8         | 31.8    | 89.6              | 90.2    | 5.9                     | 5.9     |                | 1.2   | 1.2     |                         | 4.1   | 4.2     |     |
|          |                   |                 |               | Bottom    | 8    | 28.3             | 28.3    | 8.2   | 8.2     | 31.9         | 31.9    | 75.0              | 83.0    | 4.9                     | 5.2     |                | 2.2   | 2.3     |                         | 2.2   | 2.3     |     |
| M1       | Rainy             | Moderate        | 11:27         | Surface   | 1    | 28.3             | 28.3    | 8.3   | 8.3     | 31.5         | 31.6    | 88.0              | 86.6    | 5.8                     | 5.7     | 5.7            | 1.5   | 1.7     | 1.7                     | 3.8   | 3.9     | 3.6 |
|          |                   |                 |               | Middle    | 3    | 28.4             | 28.4    | 8.3   | 8.3     | 31.7         | 31.8    | 86.4              | 86.7    | 5.6                     | 5.7     |                | 1.6   | 1.7     |                         | 4.0   | 4.0     |     |
|          |                   |                 |               | Bottom    | 5    | 28.4             | 28.4    | 8.3   | 8.3     | 31.8         | 31.8    | 87.0              | 87.2    | 5.7                     | 5.7     |                | 1.7   | 1.7     |                         | 2.9   | 2.9     |     |
| M2       | Rainy             | Moderate        | 11:15         | Surface   | 1    | 28.3             | 28.3    | 8.3   | 8.3     | 31.2         | 31.0    | 94.0              | 92.9    | 6.2                     | 6.1     | 6.0            | 1.4   | 1.4     | 1.8                     | 2.8   | 2.8     | 2.4 |
|          |                   |                 |               | Middle    | 6    | 28.3             | 28.3    | 8.3   | 8.3     | 31.8         | 31.8    | 90.0              | 90.1    | 5.9                     | 5.9     |                | 1.2   | 1.2     |                         | 2.4   | 2.4     |     |
|          |                   |                 |               | Bottom    | 11   | 28.3             | 28.3    | 8.2   | 8.3     | 32.0         | 32.0    | 82.0              | 82.7    | 5.4                     | 5.4     |                | 2.6   | 2.7     |                         | 2.1   | 2.1     |     |
| M3       | Rainy             | Moderate        | 11:43         | Surface   | 1    | 28.3             | 28.3    | 8.2   | 8.3     | 31.5         | 31.5    | 83.2              | 85.5    | 5.4                     | 5.6     | 5.8            | 1.6   | 1.6     | 1.6                     | 4.3   | 4.3     | 4.1 |
|          |                   |                 |               | Middle    | 4    | 28.4             | 28.4    | 8.3   | 8.3     | 31.8         | 31.8    | 90.9              | 89.9    | 5.9                     | 5.9     |                | 1.2   | 1.3     |                         | 3.7   | 3.8     |     |
|          |                   |                 |               | Bottom    | 7    | 28.4             | 28.4    | 8.3   | 8.3     | 31.9         | 31.9    | 86.9              | 84.5    | 5.7                     | 5.6     |                | 1.7   | 1.9     |                         | 4.2   | 4.3     |     |
| M4       | Rainy             | Moderate        | 11:10         | Surface   | 1    | 28.1             | 28.1    | 8.3   | 8.3     | 31.2         | 31.3    | 91.7              | 90.1    | 6.0                     | 5.9     | 5.9            | 1.5   | 1.4     | 1.3                     | 3.5   | 3.6     | 2.9 |
|          |                   |                 |               | Middle    | 5    | 28.3             | 28.3    | 8.3   | 8.3     | 31.7         | 31.7    | 90.3              | 89.8    | 5.9                     | 5.9     |                | 1.2   | 1.2     |                         | 1.7   | 1.7     |     |
|          |                   |                 |               | Bottom    | 9    | 28.1             | 28.2    | 8.3   | 8.3     | 31.8         | 31.8    | 86.5              | 86.3    | 5.7                     | 5.7     |                | 1.3   | 1.4     |                         | 3.5   | 3.5     |     |
| M5       | Rainy             | Moderate        | 11:58         | Surface   | 1    | 28.2             | 28.2    | 8.3   | 8.3     | 31.3         | 31.3    | 92.5              | 92.7    | 6.1                     | 6.1     | 6.1            | 1.3   | 1.3     | 1.2                     | 2.5   | 2.5     | 3.1 |
|          |                   |                 |               | Middle    | 5.5  | 28.3             | 28.3    | 8.3   | 8.3     | 31.4         | 31.4    | 93.7              | 91.9    | 6.1                     | 6.1     |                | 1.2   | 1.2     |                         | 3.9   | 4.0     |     |
|          |                   |                 |               | Bottom    | 10   | 28.4             | 28.4    | 8.3   | 8.3     | 31.6         | 31.6    | 92.2              | 92.0    | 6.0                     | 6.0     |                | 1.1   | 1.2     |                         | 2.8   | 2.8     |     |
| M6       | Rainy             | Moderate        | 11:53         | Surface   | -    | -                | -       | -     | -       | -            | -       | -                 | -       | -                       | -       | 6.1            | -     | -       | 1.3                     | -     | -       | 2.6 |
|          |                   |                 |               | Middle    | 1.3  | 28.3             | 28.3    | 8.3   | 8.3     | 31.7         | 31.7    | 93.1              | 91.6    | 6.1                     | 6.1     |                | 1.2   | 1.3     |                         | 2.6   | 2.6     |     |
|          |                   |                 |               | Bottom    | -    | -                | -       | -     | -       | -            | -       | -                 | -       | -                       | -       |                | -     | -       |                         | -     | -       |     |

Remarks: \*DA: Depth-Averaged  
 \*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

**Appendix I - Action and Limit Levels for Marine Water Quality on 13 June 2018 (Mid-Flood Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 6.0 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 6.5 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 5.9 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.4 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 5.9 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.4 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.7 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 7.3 mg/L</u>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction**  
**Water Quality Monitoring Results on 13 June 2018**

**(Mid-Flood Tide)**

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) |      | Temperature (°C) |         | pH    |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         | Turbidity(NTU) |       |         | Suspended Solids (mg/L) |       |         |     |
|----------|-------------------|-----------------|---------------|-----------|------|------------------|---------|-------|---------|--------------|---------|-------------------|---------|-------------------------|---------|----------------|-------|---------|-------------------------|-------|---------|-----|
|          |                   |                 |               |           |      | Value            | Average | Value | Average | Value        | Average | Value             | Average | Value                   | Average | DA*            | Value | Average | DA*                     | Value | Average | DA* |
| C1       | Rainy             | Moderate        | 18:08         | Surface   | 1    | 28.1             | 28.1    | 8.3   | 8.3     | 30.5         | 30.6    | 87.1              | 86.6    | 5.7                     | 5.7     | 5.6            | 4.0   | 4.0     | 3.5                     | 4.9   | 4.9     | 5.2 |
|          |                   |                 |               | Middle    | 9    | 28.1             | 28.1    | 8.3   | 8.3     | 31.6         | 31.6    | 84.6              | 84.5    | 5.5                     | 5.5     |                | 1.4   | 1.4     |                         | 4.9   | 5.0     |     |
|          |                   |                 |               | Bottom    | 17   | 28.1             | 28.1    | 8.3   | 8.3     | 32.1         | 32.1    | 83.9              | 83.9    | 5.5                     | 5.5     |                | 5.1   | 5.0     |                         | 5.8   | 5.6     |     |
| C2       | Rainy             | Moderate        | 17:07         | Surface   | 1    | 28.0             | 28.0    | 8.1   | 8.2     | 29.0         | 29.3    | 93.8              | 91.7    | 6.3                     | 6.1     | 5.8            | 1.7   | 1.6     | 2.5                     | 4.9   | 4.9     | 5.3 |
|          |                   |                 |               | Middle    | 16.5 | 28.1             | 28.1    | 8.2   | 8.2     | 31.8         | 31.8    | 82.4              | 83.5    | 5.4                     | 5.5     |                | 2.3   | 2.4     |                         | 4.7   | 4.6     |     |
|          |                   |                 |               | Bottom    | 32   | 28.0             | 28.0    | 8.2   | 8.2     | 32.1         | 32.1    | 80.9              | 81.2    | 5.3                     | 5.3     |                | 3.7   | 3.6     |                         | 6.6   | 6.5     |     |
| G1       | Rainy             | Moderate        | 17:35         | Surface   | 1    | 28.2             | 28.3    | 8.3   | 8.3     | 30.2         | 30.6    | 92.9              | 93.5    | 6.1                     | 6.2     | 6.2            | 2.8   | 2.8     | 1.7                     | 4.2   | 4.2     | 3.6 |
|          |                   |                 |               | Middle    | 4    | 28.4             | 28.4    | 8.3   | 8.3     | 31.3         | 31.4    | 94.3              | 94.2    | 6.2                     | 6.2     |                | 1.3   | 1.3     |                         | 4.2   | 4.2     |     |
|          |                   |                 |               | Bottom    | 7    | 28.4             | 28.4    | 8.3   | 8.3     | 31.6         | 31.6    | 94.1              | 94.0    | 6.1                     | 6.1     |                | 1.1   | 1.1     |                         | 2.2   | 2.3     |     |
| G2       | Rainy             | Moderate        | 17:25         | Surface   | 1    | 28.2             | 28.2    | 8.3   | 8.3     | 30.9         | 30.8    | 92.0              | 92.4    | 6.1                     | 6.1     | 6.0            | 1.7   | 1.6     | 1.4                     | 3.0   | 3.0     | 2.1 |
|          |                   |                 |               | Middle    | 5    | 28.2             | 28.2    | 8.3   | 8.3     | 31.5         | 31.5    | 89.4              | 89.4    | 5.9                     | 5.9     |                | 1.5   | 1.5     |                         | 1.5   | 1.5     |     |
|          |                   |                 |               | Bottom    | 9    | 28.4             | 28.4    | 8.3   | 8.3     | 31.7         | 31.7    | 93.3              | 93.2    | 6.1                     | 6.1     |                | 1.2   | 1.2     |                         | 1.7   | 1.7     |     |
| G3       | Rainy             | Moderate        | 17:40         | Surface   | 1    | 28.3             | 28.3    | 8.3   | 8.3     | 30.9         | 30.8    | 93.8              | 93.2    | 6.2                     | 6.2     | 6.2            | 2.2   | 2.4     | 1.6                     | 4.5   | 4.5     | 4.9 |
|          |                   |                 |               | Middle    | 4    | 28.3             | 28.4    | 8.3   | 8.3     | 31.5         | 31.5    | 93.7              | 93.7    | 6.1                     | 6.1     |                | 1.1   | 1.2     |                         | 5.0   | 5.0     |     |
|          |                   |                 |               | Bottom    | 7    | 28.3             | 28.3    | 8.3   | 8.3     | 31.7         | 31.7    | 89.1              | 89.8    | 5.8                     | 5.9     |                | 1.3   | 1.3     |                         | 5.2   | 5.2     |     |
| G4       | Rainy             | Moderate        | 17:52         | Surface   | 1    | 28.3             | 28.3    | 8.3   | 8.3     | 31.2         | 31.1    | 94.4              | 93.5    | 6.2                     | 6.2     | 6.1            | 1.4   | 1.5     | 2.0                     | 5.0   | 5.1     | 3.8 |
|          |                   |                 |               | Middle    | 4.5  | 28.3             | 28.3    | 8.3   | 8.3     | 31.4         | 31.5    | 92.1              | 91.3    | 6.0                     | 6.0     |                | 1.4   | 1.4     |                         | 3.2   | 3.2     |     |
|          |                   |                 |               | Bottom    | 8    | 28.3             | 28.3    | 8.2   | 8.2     | 31.8         | 31.8    | 72.3              | 72.9    | 4.7                     | 4.8     |                | 2.9   | 3.0     |                         | 3.0   | 3.0     |     |
| M1       | Rainy             | Moderate        | 17:30         | Surface   | 1    | 28.3             | 28.3    | 8.3   | 8.3     | 31.0         | 31.0    | 91.0              | 90.3    | 6.0                     | 6.0     | 6.1            | 1.4   | 1.4     | 1.4                     | 4.0   | 4.1     | 3.7 |
|          |                   |                 |               | Middle    | 3    | 28.3             | 28.4    | 8.3   | 8.3     | 31.4         | 31.4    | 93.3              | 93.3    | 6.1                     | 6.1     |                | 1.3   | 1.3     |                         | 3.2   | 3.2     |     |
|          |                   |                 |               | Bottom    | 5    | 28.3             | 28.3    | 8.3   | 8.3     | 31.6         | 31.6    | 87.8              | 88.0    | 5.7                     | 5.8     |                | 1.4   | 1.4     |                         | 3.7   | 3.7     |     |
| M2       | Rainy             | Moderate        | 17:20         | Surface   | 1    | 28.3             | 28.3    | 8.3   | 8.3     | 31.0         | 31.0    | 96.7              | 96.0    | 6.4                     | 6.4     | 6.3            | 1.3   | 1.3     | 1.8                     | 2.9   | 2.9     | 2.2 |
|          |                   |                 |               | Middle    | 6    | 28.4             | 28.4    | 8.3   | 8.3     | 31.7         | 31.7    | 93.3              | 93.2    | 6.1                     | 6.1     |                | 1.2   | 1.2     |                         | 1.4   | 1.4     |     |
|          |                   |                 |               | Bottom    | 11   | 28.4             | 28.4    | 8.3   | 8.3     | 31.9         | 31.9    | 89.6              | 89.9    | 5.8                     | 5.9     |                | 3.0   | 2.9     |                         | 2.3   | 2.3     |     |
| M3       | Rainy             | Moderate        | 17:45         | Surface   | 1    | 28.2             | 28.2    | 8.3   | 8.3     | 30.6         | 30.5    | 90.9              | 91.3    | 6.0                     | 6.0     | 6.0            | 4.4   | 4.3     | 2.3                     | 3.6   | 3.7     | 3.3 |
|          |                   |                 |               | Middle    | 4    | 28.4             | 28.4    | 8.3   | 8.3     | 31.7         | 31.7    | 92.5              | 92.1    | 6.0                     | 6.0     |                | 1.3   | 1.3     |                         | 3.2   | 3.3     |     |
|          |                   |                 |               | Bottom    | 7    | 28.3             | 28.3    | 8.3   | 8.3     | 31.8         | 31.8    | 87.6              | 88.6    | 5.7                     | 5.8     |                | 1.4   | 1.4     |                         | 2.8   | 2.8     |     |
| M4       | Rainy             | Moderate        | 17:15         | Surface   | 1    | 28.2             | 28.3    | 8.3   | 8.3     | 30.7         | 30.9    | 96.7              | 96.1    | 6.4                     | 6.4     | 6.3            | 1.4   | 1.4     | 1.4                     | 2.4   | 2.4     | 2.6 |
|          |                   |                 |               | Middle    | 5    | 28.3             | 28.4    | 8.3   | 8.3     | 31.3         | 31.5    | 94.7              | 94.1    | 6.2                     | 6.2     |                | 1.2   | 1.3     |                         | 2.4   | 2.4     |     |
|          |                   |                 |               | Bottom    | 9    | 28.4             | 28.4    | 8.3   | 8.3     | 31.7         | 31.7    | 93.0              | 91.7    | 6.1                     | 6.1     |                | 1.3   | 1.4     |                         | 3.1   | 3.1     |     |
| M5       | Rainy             | Moderate        | 18:02         | Surface   | 1    | 28.1             | 28.1    | 8.2   | 8.2     | 30.7         | 30.7    | 89.0              | 87.2    | 5.9                     | 5.8     | 5.7            | 1.8   | 1.7     | 2.9                     | 2.3   | 2.3     | 3.5 |
|          |                   |                 |               | Middle    | 5.5  | 28.2             | 28.2    | 8.2   | 8.3     | 31.2         | 31.2    | 85.3              | 85.2    | 5.6                     | 5.6     |                | 2.0   | 2.0     |                         | 3.9   | 4.0     |     |
|          |                   |                 |               | Bottom    | 10   | 28.0             | 28.0    | 8.2   | 8.3     | 32.1         | 32.1    | 81.3              | 81.4    | 5.3                     | 5.3     |                | 5.1   | 5.1     |                         | 4.1   | 4.1     |     |
| M6       | Rainy             | Moderate        | 17:57         | Surface   | -    | -                | -       | -     | -       | -            | -       | -                 | -       | -                       | 6.0     | -              | -     | 2.0     | -                       | -     | 6.0     |     |
|          |                   |                 |               | Middle    | 1.3  | 28.1             | 28.1    | 8.3   | 8.3     | 29.8         | 30.3    | 92.3              | 90.2    | 6.1                     |         | 6.0            | 2.0   |         | 2.0                     | 5.9   |         | 6.0 |
|          |                   |                 |               | Bottom    | -    | -                | -       | -     | -       | -            | -       | -                 | -       | -                       |         | -              | -     |         | -                       | -     |         | -   |

Remarks: \*DA: Depth-Averaged  
 \*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.



**Appendix I - Action and Limit Levels for Marine Water Quality on 15 June 2018 (Mid-Ebb Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 4.0 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 4.3 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 5.4 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 5.9 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 5.4 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 5.9 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.8 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.4 mg/L</u>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction**  
**Water Quality Monitoring Results on 15 June 2018**

**(Mid-Ebb Tide)**

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) |      | Temperature (°C) |         | pH         |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         |     | Turbidity(NTU) |         |     | Suspended Solids (mg/L) |         |     |
|----------|-------------------|-----------------|---------------|-----------|------|------------------|---------|------------|---------|--------------|---------|-------------------|---------|-------------------------|---------|-----|----------------|---------|-----|-------------------------|---------|-----|
|          |                   |                 |               |           |      | Value            | Average | Value      | Average | Value        | Average | Value             | Average | Value                   | Average | DA* | Value          | Average | DA* | Value                   | Average | DA* |
| C1       | Cloudy            | Moderate        | 13:46         | Surface   | 1    | 27.9<br>28.1     | 28.0    | 8.2<br>8.2 | 8.2     | 33.6<br>33.5 | 33.6    | 98.9<br>97.4      | 98.2    | 6.9<br>6.8              | 6.9     | 6.4 | 1.0<br>1.0     | 1.0     | 1.8 | 4.5<br>4.4              | 4.5     | 3.2 |
|          |                   |                 |               | Middle    | 9    | 26.9<br>26.7     | 26.8    | 8.2<br>8.2 | 8.2     | 34.6<br>33.9 | 34.3    | 84.4<br>84.6      | 84.5    | 5.9<br>5.9              | 5.9     |     | 0.9<br>1.0     | 1.0     |     | 2.3<br>2.3              | 2.3     |     |
|          |                   |                 |               | Bottom    | 17   | 23.9<br>23.9     | 23.9    | 8.1<br>8.1 | 8.1     | 37.6<br>34.6 | 36.1    | 75.6<br>76.3      | 76.0    | 5.3<br>5.3              | 5.3     |     | 3.1<br>3.4     | 3.3     |     | 2.8<br>2.8              | 2.8     |     |
| C2       | Cloudy            | Moderate        | 12:01         | Surface   | 1    | 27.5<br>27.4     | 27.5    | 8.2<br>8.2 | 8.2     | 33.5<br>33.5 | 33.5    | 90.3<br>89.2      | 89.8    | 6.3<br>6.2              | 6.3     | 6.0 | 1.1<br>1.1     | 1.1     | 2.2 | 4.5<br>4.4              | 4.5     | 5.0 |
|          |                   |                 |               | Middle    | 16.5 | 26.5<br>26.4     | 26.5    | 8.1<br>8.1 | 8.1     | 34.0<br>34.1 | 34.1    | 77.9<br>80.1      | 79.0    | 5.5<br>5.6              | 5.6     |     | 2.1<br>2.1     | 2.1     |     | 4.6<br>4.7              | 4.7     |     |
|          |                   |                 |               | Bottom    | 32   | 25.1<br>24.9     | 25.0    | 8.1<br>8.1 | 8.1     | 33.9<br>34.2 | 34.1    | 71.2<br>71.8      | 71.5    | 5.0<br>5.1              | 5.1     |     | 3.3<br>3.2     | 3.3     |     | 5.6<br>5.7              | 5.7     |     |
| G1       | Cloudy            | Moderate        | 12:55         | Surface   | 1    | 27.3<br>27.3     | 27.3    | 8.2<br>8.2 | 8.2     | 33.6<br>33.6 | 33.6    | 99.5<br>96.1      | 97.8    | 6.9<br>6.7              | 6.8     | 6.8 | 1.1<br>1.1     | 1.1     | 1.9 | 2.8<br>2.8              | 2.8     | 3.6 |
|          |                   |                 |               | Middle    | 4    | 26.9<br>26.9     | 26.9    | 8.2<br>8.2 | 8.2     | 34.1<br>34.2 | 34.2    | 97.7<br>96.5      | 97.1    | 6.8<br>6.7              | 6.8     |     | 1.3<br>1.5     | 1.4     |     | 5.6<br>5.8              | 5.7     |     |
|          |                   |                 |               | Bottom    | 7    | 26.1<br>26.2     | 26.2    | 8.1<br>8.1 | 8.1     | 34.5<br>34.4 | 34.5    | 87.1<br>86.2      | 86.7    | 6.1<br>6.0              | 6.1     |     | 3.2<br>3.3     | 3.3     |     | 2.1<br>2.2              | 2.2     |     |
| G2       | Cloudy            | Moderate        | 12:37         | Surface   | 1    | 27.2<br>27.2     | 27.2    | 8.2<br>8.2 | 8.2     | 33.7<br>33.7 | 33.7    | 101.2<br>100.5    | 100.9   | 7.0<br>7.0              | 7.0     | 6.7 | 1.1<br>1.0     | 1.1     | 1.6 | 4.7<br>4.5              | 4.6     | 4.5 |
|          |                   |                 |               | Middle    | 5    | 26.8<br>26.8     | 26.8    | 8.2<br>8.2 | 8.2     | 34.3<br>34.3 | 34.3    | 89.8<br>89.3      | 89.6    | 6.3<br>6.2              | 6.3     |     | 1.5<br>1.5     | 1.5     |     | 3.8<br>3.7              | 3.8     |     |
|          |                   |                 |               | Bottom    | 9    | 26.1<br>26.0     | 26.1    | 8.1<br>8.1 | 8.1     | 34.6<br>34.6 | 34.6    | 79.5<br>82.0      | 80.8    | 5.6<br>5.7              | 5.7     |     | 2.0<br>2.2     | 2.1     |     | 5.0<br>5.1              | 5.1     |     |
| G3       | Cloudy            | Moderate        | 13:04         | Surface   | 1    | 27.6<br>27.6     | 27.6    | 8.2<br>8.2 | 8.2     | 33.1<br>33.0 | 33.1    | 91.8<br>79.3      | 85.6    | 6.4<br>5.5              | 6.0     | 6.1 | 1.1<br>1.1     | 1.1     | 1.5 | 3.3<br>3.4              | 3.4     | 3.4 |
|          |                   |                 |               | Middle    | 4    | 26.9<br>26.9     | 26.9    | 8.2<br>8.2 | 8.2     | 34.0<br>33.9 | 34.0    | 87.8<br>87.9      | 87.9    | 6.1<br>6.1              | 6.1     |     | 1.6<br>1.5     | 1.6     |     | 4.5<br>4.5              | 4.5     |     |
|          |                   |                 |               | Bottom    | 7    | 26.6<br>26.6     | 26.6    | 8.1<br>8.1 | 8.1     | 34.5<br>34.5 | 34.5    | 80.2<br>81.7      | 81.0    | 5.6<br>5.7              | 5.7     |     | 2.0<br>1.8     | 1.9     |     | 2.2<br>2.2              | 2.2     |     |
| G4       | Cloudy            | Moderate        | 13:19         | Surface   | 1    | 27.9<br>27.3     | 27.6    | 8.3<br>8.2 | 8.3     | 33.2<br>33.7 | 33.5    | 98.6<br>97.3      | 98.0    | 6.8<br>6.8              | 6.8     | 6.8 | 1.1<br>1.0     | 1.1     | 1.9 | 3.1<br>3.2              | 3.2     | 3.3 |
|          |                   |                 |               | Middle    | 4.5  | 26.9<br>26.9     | 26.9    | 8.2<br>8.2 | 8.2     | 34.2<br>34.2 | 34.2    | 96.0<br>95.9      | 96.0    | 6.7<br>6.7              | 6.7     |     | 1.2<br>1.2     | 1.2     |     | 1.4<br>1.4              | 1.4     |     |
|          |                   |                 |               | Bottom    | 8    | 26.2<br>26.2     | 26.2    | 8.1<br>8.1 | 8.1     | 34.3<br>34.4 | 34.4    | 79.8<br>80.4      | 80.1    | 5.6<br>5.6              | 5.6     |     | 3.4<br>3.5     | 3.5     |     | 5.4<br>5.4              | 5.4     |     |
| M1       | Cloudy            | Moderate        | 12:47         | Surface   | 1    | 27.3<br>27.3     | 27.3    | 8.2<br>8.2 | 8.2     | 33.7<br>33.7 | 33.7    | 99.6<br>94.9      | 97.3    | 6.9<br>6.6              | 6.8     | 6.8 | 1.1<br>1.1     | 1.1     | 1.3 | 1.1<br>1.2              | 1.2     | 1.9 |
|          |                   |                 |               | Middle    | 3    | 27.0<br>27.0     | 27.0    | 8.2<br>8.2 | 8.2     | 34.0<br>33.9 | 34.0    | 95.6<br>95.8      | 95.7    | 6.6<br>6.7              | 6.7     |     | 1.4<br>1.3     | 1.4     |     | 1.0<br>1.0              | 1.0     |     |
|          |                   |                 |               | Bottom    | 5    | 26.7<br>26.8     | 26.8    | 8.2<br>8.2 | 8.2     | 34.4<br>34.2 | 34.3    | 86.6<br>86.2      | 86.4    | 6.0<br>6.0              | 6.0     |     | 1.4<br>1.5     | 1.5     |     | 3.4<br>3.4              | 3.4     |     |
| M2       | Cloudy            | Moderate        | 12:26         | Surface   | 1    | 27.2<br>27.3     | 27.3    | 8.2<br>8.2 | 8.2     | 33.7<br>33.7 | 33.7    | 100.9<br>99.1     | 100.0   | 7.0<br>6.9              | 7.0     | 6.7 | 1.2<br>1.1     | 1.2     | 2.4 | 1.8<br>1.8              | 1.8     | 2.0 |
|          |                   |                 |               | Middle    | 5.5  | 26.4<br>26.3     | 26.4    | 8.1<br>8.1 | 8.1     | 35.0<br>34.1 | 34.6    | 89.1<br>91.4      | 90.3    | 6.2<br>6.4              | 6.3     |     | 2.9<br>2.9     | 2.9     |     | 2.3<br>2.2              | 2.3     |     |
|          |                   |                 |               | Bottom    | 10   | 25.9<br>25.8     | 25.9    | 8.1<br>8.1 | 8.1     | 34.6<br>34.7 | 34.7    | 73.6<br>77.2      | 75.4    | 5.2<br>5.4              | 5.3     |     | 3.0<br>3.3     | 3.2     |     | 2.0<br>1.9              | 2.0     |     |
| M3       | Cloudy            | Moderate        | 13:11         | Surface   | 1    | 27.6<br>27.6     | 27.6    | 8.2<br>8.2 | 8.2     | 33.2<br>33.4 | 33.3    | 86.5<br>84.2      | 85.4    | 6.0<br>5.9              | 6.0     | 6.0 | 1.1<br>1.1     | 1.1     | 1.8 | 3.7<br>3.7              | 3.7     | 3.6 |
|          |                   |                 |               | Middle    | 4    | 26.8<br>26.9     | 26.9    | 8.2<br>8.2 | 8.2     | 34.1<br>34.1 | 34.1    | 83.6<br>88.9      | 86.3    | 5.8<br>6.2              | 6.0     |     | 1.7<br>1.7     | 1.7     |     | 3.1<br>3.2              | 3.2     |     |
|          |                   |                 |               | Bottom    | 7    | 26.5<br>26.6     | 26.6    | 8.1<br>8.2 | 8.2     | 34.6<br>34.6 | 34.6    | 81.9<br>81.1      | 81.5    | 5.7<br>5.7              | 5.7     |     | 2.4<br>2.5     | 2.5     |     | 3.7<br>3.8              | 3.8     |     |
| M4       | Cloudy            | Moderate        | 12:11         | Surface   | 1    | 27.3<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 33.6<br>33.6 | 33.6    | 96.8<br>95.5      | 96.2    | 6.8<br>6.7              | 6.8     | 6.3 | 1.1<br>1.1     | 1.1     | 1.2 | 3.3<br>3.4              | 3.4     | 4.1 |
|          |                   |                 |               | Middle    | 5    | 27.3<br>27.0     | 27.2    | 8.2<br>8.2 | 8.2     | 33.7<br>34.0 | 33.9    | 78.5<br>82.5      | 80.5    | 5.5<br>5.8              | 5.7     |     | 1.1<br>1.2     | 1.2     |     | 3.4<br>3.4              | 3.4     |     |
|          |                   |                 |               | Bottom    | 9    | 27.1<br>26.9     | 27.0    | 8.2<br>8.2 | 8.2     | 33.9<br>34.1 | 34.0    | 73.3<br>75.4      | 74.4    | 5.1<br>5.3              | 5.2     |     | 1.2<br>1.4     | 1.3     |     | 5.5<br>5.6              | 5.6     |     |
| M5       | Cloudy            | Moderate        | 13:36         | Surface   | 1    | 27.4<br>27.5     | 27.5    | 8.2<br>8.2 | 8.2     | 33.6<br>33.6 | 33.6    | 97.4<br>96.5      | 97.0    | 6.8<br>6.7              | 6.8     | 6.7 | 1.4<br>1.4     | 1.4     | 1.9 | 4.5<br>4.4              | 4.5     | 5.2 |
|          |                   |                 |               | Middle    | 5.5  | 27.1<br>27.1     | 27.1    | 8.2<br>8.2 | 8.2     | 33.9<br>33.9 | 33.9    | 94.7<br>93.1      | 93.9    | 6.6<br>6.5              | 6.6     |     | 1.2<br>1.1     | 1.2     |     | 7.0<br>7.2              | 7.1     |     |
|          |                   |                 |               | Bottom    | 10   | 26.4<br>26.3     | 26.4    | 8.1<br>8.1 | 8.1     | 34.0<br>34.1 | 34.1    | 95.0<br>93.9      | 94.5    | 6.6<br>6.5              | 6.6     |     | 3.2<br>3.2     | 3.2     |     | 4.1<br>4.1              | 4.1     |     |
| M6       | Cloudy            | Moderate        | 13:28         | Surface   | -    | -                | -       | -          | -       | -            | -       | -                 | -       | -                       | -       | 5.7 | -              | -       | 1.1 | -                       | -       | 3.2 |
|          |                   |                 |               | Middle    | 1.6  | 27.2<br>27.3     | 27.3    | 8.2<br>8.2 | 8.2     | 33.8<br>33.7 | 33.8    | 81.9<br>81.5      | 81.7    | 5.7<br>5.7              | 5.7     |     | 1.1<br>1.1     | 1.1     |     | 3.1<br>3.2              | 3.2     |     |
|          |                   |                 |               | Bottom    | -    | -                | -       | -          | -       | -            | -       | -                 | -       | -                       | -       |     | -              | -       |     | -                       | -       |     |

Remarks: \*DA: Depth-Averaged  
 \*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

**Appendix I - Action and Limit Levels for Marine Water Quality on 15 June 2018 (Mid-Flood Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 4.4 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 4.8 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 5.4 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 5.9 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 5.4 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 5.9 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 5.5 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.0 mg/L</u>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction**  
**Water Quality Monitoring Results on 15 June 2018**

**(Mid-Flood Tide)**

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) |      | Temperature (°C) |         | pH         |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         |     | Turbidity (NTU) |         |     | Suspended Solids (mg/L) |         |     |
|----------|-------------------|-----------------|---------------|-----------|------|------------------|---------|------------|---------|--------------|---------|-------------------|---------|-------------------------|---------|-----|-----------------|---------|-----|-------------------------|---------|-----|
|          |                   |                 |               |           |      | Value            | Average | Value      | Average | Value        | Average | Value             | Average | Value                   | Average | DA* | Value           | Average | DA* | Value                   | Average | DA* |
| C1       | Cloudy            | Moderate        | 21:18         | Surface   | 1    | 26.3<br>26.2     | 26.3    | 8.2<br>8.2 | 8.2     | 33.3<br>33.5 | 33.4    | 90.7<br>89.7      | 90.2    | 6.3<br>6.2              | 6.3     | 6.3 | 1.4<br>1.4      | 1.4     | 2.5 | 4.5<br>4.5              | 4.5     | 4.5 |
|          |                   |                 |               | Middle    | 9    | 25.0<br>25.3     | 25.2    | 8.1<br>8.1 | 8.1     | 34.3<br>34.2 | 34.3    | 92.2<br>89.4      | 90.8    | 6.4<br>6.2              | 6.3     |     | 2.6<br>2.2      | 2.4     |     | 4.4<br>4.3              | 4.4     |     |
|          |                   |                 |               | Bottom    | 17   | 24.0<br>23.4     | 23.7    | 8.1<br>8.1 | 8.1     | 34.0<br>34.5 | 34.3    | 88.5<br>86.9      | 87.7    | 6.1<br>6.0              | 6.1     |     | 3.6<br>3.7      | 3.7     |     | 4.6<br>4.6              | 4.6     |     |
| C2       | Cloudy            | Moderate        | 19:49         | Surface   | 1    | 26.3<br>26.3     | 26.3    | 8.2<br>8.2 | 8.2     | 33.6<br>33.7 | 33.7    | 97.1<br>96.8      | 97.0    | 6.7<br>6.7              | 6.7     | 6.5 | 1.2<br>1.2      | 1.2     | 2.6 | 5.0<br>5.0              | 5.0     | 2.9 |
|          |                   |                 |               | Middle    | 16.5 | 24.9<br>24.6     | 24.8    | 8.1<br>8.1 | 8.1     | 34.5<br>34.0 | 34.3    | 83.9<br>94.4      | 89.2    | 5.9<br>6.5              | 6.2     |     | 2.9<br>3.0      | 3.0     |     | 1.8<br>1.8              | 1.8     |     |
|          |                   |                 |               | Bottom    | 32   | 24.3<br>24.1     | 24.2    | 8.1<br>8.1 | 8.1     | 34.6<br>33.8 | 34.2    | 77.2<br>77.5      | 77.4    | 5.4<br>5.4              | 5.4     |     | 3.6<br>3.6      | 3.6     |     | 1.9<br>2.0              | 2.0     |     |
| G1       | Cloudy            | Moderate        | 20:31         | Surface   | 1    | 27.5<br>27.4     | 27.5    | 8.2<br>8.2 | 8.2     | 33.5<br>33.5 | 33.5    | 98.2<br>99.2      | 98.7    | 6.7<br>6.8              | 6.8     | 6.7 | 1.5<br>1.5      | 1.5     | 1.5 | 4.6<br>4.8              | 4.7     | 3.8 |
|          |                   |                 |               | Middle    | 3.5  | 26.7<br>27.0     | 26.9    | 8.2<br>8.2 | 8.2     | 33.6<br>33.6 | 33.6    | 94.4<br>92.4      | 93.4    | 6.5<br>6.4              | 6.5     |     | 1.2<br>1.1      | 1.2     |     | 4.4<br>4.5              | 4.5     |     |
|          |                   |                 |               | Bottom    | 6    | 26.0<br>26.0     | 26.0    | 8.2<br>8.2 | 8.2     | 34.1<br>34.0 | 34.1    | 89.7<br>90.7      | 90.2    | 6.2<br>6.3              | 6.3     |     | 1.7<br>1.8      | 1.8     |     | 2.1<br>2.1              | 2.1     |     |
| G2       | Cloudy            | Moderate        | 20:20         | Surface   | 1    | 26.9<br>27.4     | 27.2    | 8.2<br>8.2 | 8.2     | 33.5<br>33.4 | 33.5    | 99.1<br>98.8      | 99.0    | 6.8<br>6.8              | 6.8     | 6.7 | 1.1<br>1.1      | 1.1     | 1.3 | 4.4<br>4.4              | 4.4     | 3.3 |
|          |                   |                 |               | Middle    | 4.5  | 26.2<br>26.2     | 26.2    | 8.2<br>8.2 | 8.2     | 33.8<br>33.8 | 33.8    | 93.7<br>93.3      | 93.5    | 6.5<br>6.5              | 6.5     |     | 1.1<br>1.2      | 1.2     |     | 1.6<br>1.6              | 1.6     |     |
|          |                   |                 |               | Bottom    | 8    | 25.6<br>25.9     | 25.8    | 8.1<br>8.2 | 8.2     | 34.7<br>34.1 | 34.4    | 92.2<br>91.8      | 92.0    | 6.4<br>6.4              | 6.4     |     | 1.7<br>1.7      | 1.7     |     | 4.0<br>4.0              | 4.0     |     |
| G3       | Cloudy            | Moderate        | 20:39         | Surface   | 1    | 27.7<br>27.8     | 27.8    | 8.2<br>8.2 | 8.2     | 33.1<br>33.1 | 33.1    | 87.4<br>86.2      | 86.8    | 6.1<br>6.0              | 6.1     | 5.9 | 1.2<br>1.1      | 1.2     | 1.3 | 1.8<br>1.7              | 1.8     | 2.9 |
|          |                   |                 |               | Middle    | 3.5  | 26.6<br>26.6     | 26.6    | 8.2<br>8.2 | 8.2     | 33.6<br>33.6 | 33.6    | 80.2<br>80.7      | 80.5    | 5.6<br>5.6              | 5.6     |     | 1.1<br>1.2      | 1.2     |     | 2.8<br>2.8              | 2.8     |     |
|          |                   |                 |               | Bottom    | 6    | 26.1<br>26.0     | 26.1    | 8.2<br>8.2 | 8.2     | 33.9<br>34.0 | 34.0    | 82.7<br>82.3      | 82.5    | 5.8<br>5.7              | 5.8     |     | 1.5<br>1.5      | 1.5     |     | 3.9<br>4.0              | 4.0     |     |
| G4       | Cloudy            | Moderate        | 20:50         | Surface   | 1    | 27.0<br>27.1     | 27.1    | 8.2<br>8.2 | 8.2     | 33.6<br>33.5 | 33.6    | 97.0<br>95.4      | 96.2    | 6.7<br>6.6              | 6.7     | 6.5 | 1.1<br>1.1      | 1.1     | 1.9 | 3.0<br>3.1              | 3.1     | 2.8 |
|          |                   |                 |               | Middle    | 4    | 26.5<br>26.5     | 26.5    | 8.2<br>8.2 | 8.2     | 33.6<br>33.7 | 33.7    | 89.8<br>89.1      | 89.5    | 6.2<br>6.2              | 6.2     |     | 1.2<br>1.2      | 1.2     |     | 2.0<br>2.0              | 2.0     |     |
|          |                   |                 |               | Bottom    | 7    | 25.3<br>25.3     | 25.3    | 8.1<br>8.1 | 8.1     | 34.3<br>34.3 | 34.3    | 91.1<br>91.2      | 91.2    | 6.3<br>6.3              | 6.3     |     | 3.4<br>3.2      | 3.3     |     | 3.2<br>3.1              | 3.2     |     |
| M1       | Cloudy            | Moderate        | 20:27         | Surface   | 1    | 27.3<br>27.4     | 27.4    | 8.2<br>8.2 | 8.2     | 33.5<br>33.5 | 33.5    | 92.8<br>96.6      | 94.7    | 6.4<br>6.6              | 6.5     | 6.5 | 1.1<br>1.1      | 1.1     | 1.2 | 2.7<br>2.7              | 2.7     | 2.4 |
|          |                   |                 |               | Middle    | 3    | 26.6<br>26.9     | 26.8    | 8.2<br>8.2 | 8.2     | 33.6<br>33.5 | 33.6    | 92.4<br>91.0      | 91.7    | 6.4<br>6.3              | 6.4     |     | 1.2<br>1.1      | 1.2     |     | 2.1<br>2.1              | 2.1     |     |
|          |                   |                 |               | Bottom    | 5    | 26.1<br>26.1     | 26.1    | 8.2<br>8.2 | 8.2     | 33.9<br>33.9 | 33.9    | 83.7<br>85.1      | 84.4    | 5.8<br>5.9              | 5.9     |     | 1.2<br>1.4      | 1.3     |     | 2.5<br>2.5              | 2.5     |     |
| M2       | Cloudy            | Moderate        | 20:10         | Surface   | 1    | 26.9<br>27.8     | 27.4    | 8.2<br>8.2 | 8.2     | 33.6<br>33.3 | 33.5    | 95.0<br>97.3      | 96.2    | 6.5<br>6.7              | 6.6     | 6.5 | 1.2<br>1.1      | 1.2     | 1.4 | 4.3<br>4.5              | 4.4     | 3.9 |
|          |                   |                 |               | Middle    | 5.5  | 26.0<br>26.0     | 26.0    | 8.2<br>8.2 | 8.2     | 34.0<br>34.0 | 34.0    | 91.6<br>92.7      | 92.2    | 6.4<br>6.4              | 6.4     |     | 1.4<br>1.3      | 1.4     |     | 2.0<br>2.0              | 2.0     |     |
|          |                   |                 |               | Bottom    | 10   | 25.9<br>25.9     | 25.9    | 8.2<br>8.2 | 8.2     | 34.1<br>34.1 | 34.1    | 78.1<br>79.3      | 78.7    | 5.4<br>5.5              | 5.5     |     | 1.5<br>1.5      | 1.5     |     | 5.4<br>5.4              | 5.4     |     |
| M3       | Cloudy            | Moderate        | 20:43         | Surface   | 1    | 27.8<br>26.1     | 27.0    | 8.2<br>8.2 | 8.2     | 33.1<br>32.1 | 32.6    | 88.7<br>86.9      | 87.8    | 6.1<br>6.0              | 6.1     | 5.7 | 1.2<br>1.2      | 1.2     | 1.4 | 2.1<br>2.1              | 2.1     | 1.9 |
|          |                   |                 |               | Middle    | 3.5  | 26.6<br>25.3     | 26.0    | 8.2<br>8.2 | 8.2     | 33.5<br>32.2 | 32.9    | 75.7<br>74.6      | 75.2    | 5.3<br>5.2              | 5.3     |     | 1.3<br>1.3      | 1.3     |     | 2.0<br>2.0              | 2.0     |     |
|          |                   |                 |               | Bottom    | 6    | 26.0<br>24.6     | 25.3    | 8.2<br>8.2 | 8.2     | 33.9<br>32.7 | 33.3    | 83.5<br>83.3      | 83.4    | 5.8<br>5.8              | 5.8     |     | 1.8<br>1.7      | 1.8     |     | 1.5<br>1.6              | 1.6     |     |
| M4       | Cloudy            | Moderate        | 19:58         | Surface   | 1    | 27.9<br>26.1     | 27.0    | 8.2<br>8.2 | 8.2     | 33.3<br>33.0 | 33.2    | 95.7<br>95.0      | 95.4    | 6.6<br>6.5              | 6.6     | 6.5 | 1.1<br>1.1      | 1.1     | 1.9 | 4.5<br>4.5              | 4.5     | 5.2 |
|          |                   |                 |               | Middle    | 5    | 26.1<br>26.1     | 26.1    | 8.2<br>8.2 | 8.2     | 34.0<br>34.0 | 34.0    | 90.6<br>90.8      | 90.7    | 6.3<br>6.3              | 6.3     |     | 1.2<br>1.2      | 1.2     |     | 6.9<br>7.0              | 7.0     |     |
|          |                   |                 |               | Bottom    | 9    | 25.7<br>26.0     | 25.9    | 8.2<br>8.2 | 8.2     | 34.5<br>34.2 | 34.4    | 86.2<br>88.8      | 87.5    | 6.0<br>6.2              | 6.1     |     | 3.3<br>3.3      | 3.3     |     | 4.0<br>3.9              | 4.0     |     |
| M5       | Cloudy            | Moderate        | 21:07         | Surface   | 1    | 26.7<br>26.7     | 26.7    | 8.2<br>8.2 | 8.2     | 33.9<br>33.9 | 33.9    | 92.4<br>91.2      | 91.8    | 6.4<br>6.3              | 6.4     | 6.2 | 1.0<br>1.0      | 1.0     | 1.9 | 5.3<br>5.2              | 5.3     | 3.7 |
|          |                   |                 |               | Middle    | 5.5  | 26.3<br>26.3     | 26.3    | 8.2<br>8.2 | 8.2     | 34.4<br>34.4 | 34.4    | 86.7<br>86.1      | 86.4    | 6.0<br>6.0              | 6.0     |     | 1.1<br>1.2      | 1.2     |     | 4.6<br>4.7              | 4.7     |     |
|          |                   |                 |               | Bottom    | 10   | 24.6<br>24.6     | 24.6    | 8.1<br>8.1 | 8.1     | 34.3<br>34.3 | 34.3    | 77.3<br>77.6      | 77.5    | 5.4<br>5.4              | 5.4     |     | 3.3<br>3.6      | 3.5     |     | 1.2<br>1.2              | 1.2     |     |
| M6       | Cloudy            | Moderate        | 20:57         | Surface   | -    | -                | -       | -          | -       | -            | -       | -                 | -       | -                       | 6.4     | -   | -               | 0.8     | -   | -                       | 1.7     |     |
|          |                   |                 |               | Middle    | 2.1  | 26.1<br>26.1     | 26.1    | 8.2<br>8.2 | 8.2     | 34.0<br>34.0 | 34.0    | 92.3<br>92.8      | 92.6    | 6.4<br>6.4              |         | 6.4 | 0.8<br>0.8      |         | 0.8 | 1.7<br>1.6              |         | 1.7 |
|          |                   |                 |               | Bottom    | -    | -                | -       | -          | -       | -            | -       | -                 | -       | -                       |         | -   | -               |         | -   | -                       |         | -   |

Remarks: \*DA: Depth-Averaged  
 \*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

**Appendix I - Action and Limit Levels for Marine Water Quality on 19 June 2018 (Mid-Ebb Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 2.0 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 2.2 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 5.3 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 5.7 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 5.3 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 5.7 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.7 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 8.3 mg/L</u>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction**  
**Water Quality Monitoring Results on 19 June 2018**

**(Mid-Ebb Tide)**

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) | Temperature (°C) |              | pH    |            | Salinity ppt |              | DO Saturation (%) |              | Dissolved Oxygen (mg/L) |            |     | Turbidity (NTU) |            |            | Suspended Solids (mg/L) |            |            |     |     |
|----------|-------------------|-----------------|---------------|-----------|------------------|--------------|-------|------------|--------------|--------------|-------------------|--------------|-------------------------|------------|-----|-----------------|------------|------------|-------------------------|------------|------------|-----|-----|
|          |                   |                 |               |           | Value            | Average      | Value | Average    | Value        | Average      | Value             | Average      | Value                   | Average    | DA* | Value           | Average    | DA*        | Value                   | Average    | DA*        |     |     |
| C1       | Cloudy            | Moderate        | 17:17         | Surface   | 1                | 28.6<br>28.6 | 28.6  | 8.3<br>8.3 | 8.3          | 30.0<br>29.9 | 30.0              | 95.5<br>95.7 | 95.6                    | 6.3<br>6.3 | 6.3 | 6.3             | 6.3        | 0.7<br>0.7 | 0.7                     | 1.1        | 4.5<br>4.3 | 4.4 | 4.5 |
|          |                   |                 |               | Middle    | 9                | 28.4<br>28.4 | 28.4  | 8.3<br>8.3 | 8.3          | 30.9<br>30.9 | 30.9              | 96.9<br>96.9 | 96.9                    | 6.3<br>6.3 | 6.3 | 6.3             |            | 0.7<br>0.7 | 0.7                     |            | 4.4<br>4.4 | 4.3 |     |
|          |                   |                 |               | Bottom    | 17               | 28.1<br>28.1 | 28.1  | 8.3<br>8.3 | 8.3          | 32.0<br>31.9 | 32.0              | 84.6<br>84.3 | 84.5                    | 5.5<br>5.5 | 5.5 | 5.5             |            | 1.9<br>1.9 | 1.9                     |            | 4.8<br>4.7 | 4.8 |     |
| C2       | Cloudy            | Moderate        | 15:59         | Surface   | 1                | 28.7<br>28.7 | 28.7  | 8.3<br>8.3 | 8.3          | 29.5<br>29.4 | 29.5              | 97.3<br>97.4 | 97.4                    | 6.4<br>6.4 | 6.4 | 6.2             | 0.6<br>0.6 | 0.6        | 1.2                     | 4.4<br>4.3 | 4.4        | 5.2 |     |
|          |                   |                 |               | Middle    | 16.5             | 28.4<br>28.4 | 28.4  | 8.3<br>8.3 | 8.3          | 30.7<br>30.8 | 30.8              | 91.8<br>91.4 | 91.6                    | 6.0<br>6.0 | 6.0 |                 | 6.0        | 1.2<br>1.3 |                         | 1.3        | 4.8<br>4.8 |     | 4.8 |
|          |                   |                 |               | Bottom    | 32               | 28.3<br>28.3 | 28.3  | 8.3<br>8.3 | 8.3          | 31.1<br>31.1 | 31.1              | 91.5<br>91.5 | 91.5                    | 6.0<br>6.0 | 6.0 |                 | 6.0        | 1.7<br>1.7 |                         | 1.7        | 6.3<br>6.5 |     | 6.4 |
| G1       | Cloudy            | Moderate        | 16:30         | Surface   | 1                | 28.6<br>28.6 | 28.6  | 8.3<br>8.3 | 8.3          | 29.7<br>29.7 | 29.7              | 95.6<br>95.8 | 95.7                    | 6.3<br>6.3 | 6.3 | 6.3             | 0.7<br>0.7 | 0.7        | 0.8                     | 4.6<br>4.5 | 4.6        | 4.3 |     |
|          |                   |                 |               | Middle    | 4                | 28.5<br>28.5 | 28.5  | 8.3<br>8.3 | 8.3          | 30.5<br>30.6 | 30.6              | 94.6<br>94.6 | 94.6                    | 6.2<br>6.2 | 6.2 |                 | 6.2        | 0.9<br>0.8 |                         | 0.9        | 4.6<br>4.7 |     | 4.7 |
|          |                   |                 |               | Bottom    | 7                | 28.4<br>28.4 | 28.4  | 8.3<br>8.3 | 8.3          | 30.8<br>30.8 | 30.8              | 95.9<br>96.0 | 96.0                    | 6.3<br>6.3 | 6.3 |                 | 6.3        | 0.7<br>0.7 |                         | 0.7        | 3.7<br>3.7 |     | 3.7 |
| G2       | Cloudy            | Moderate        | 16:20         | Surface   | 1                | 28.6<br>28.6 | 28.6  | 8.3<br>8.3 | 8.3          | 29.8<br>29.8 | 29.8              | 94.7<br>94.5 | 94.6                    | 6.2<br>6.2 | 6.2 | 6.2             | 0.7<br>0.7 | 0.7        | 1.0                     | 4.7<br>4.9 | 4.8        | 4.9 |     |
|          |                   |                 |               | Middle    | 5                | 28.4<br>28.4 | 28.4  | 8.3<br>8.3 | 8.3          | 30.5<br>30.6 | 30.6              | 93.0<br>92.9 | 93.0                    | 6.1<br>6.1 | 6.1 |                 | 6.1        | 1.1<br>1.1 |                         | 1.1        | 4.8<br>4.8 |     | 4.8 |
|          |                   |                 |               | Bottom    | 9                | 28.4<br>28.4 | 28.4  | 8.3<br>8.3 | 8.3          | 30.8<br>30.8 | 30.8              | 93.6<br>93.6 | 93.6                    | 6.1<br>6.1 | 6.1 |                 | 6.1        | 1.1<br>1.1 |                         | 1.1        | 4.9<br>5.0 |     | 5.0 |
| G3       | Cloudy            | Moderate        | 16:38         | Surface   | 1                | 28.6<br>28.6 | 28.6  | 8.3<br>8.3 | 8.3          | 29.6<br>29.6 | 29.6              | 96.4<br>96.4 | 96.4                    | 6.3<br>6.3 | 6.3 | 6.3             | 0.7<br>0.7 | 0.7        | 0.7                     | 2.2<br>2.2 | 2.2        | 2.7 |     |
|          |                   |                 |               | Middle    | 4                | 28.5<br>28.5 | 28.5  | 8.3<br>8.3 | 8.3          | 30.5<br>30.6 | 30.6              | 95.5<br>95.4 | 95.5                    | 6.3<br>6.2 | 6.3 |                 | 6.3        | 0.8<br>0.8 |                         | 0.8        | 3.1<br>3.0 |     | 3.1 |
|          |                   |                 |               | Bottom    | 7                | 28.4<br>28.4 | 28.4  | 8.3<br>8.3 | 8.3          | 30.7<br>30.7 | 30.7              | 96.5<br>96.6 | 96.6                    | 6.3<br>6.3 | 6.3 |                 | 6.3        | 0.6<br>0.6 |                         | 0.6        | 2.7<br>2.6 |     | 2.7 |
| G4       | Cloudy            | Moderate        | 16:51         | Surface   | 1                | 28.6<br>28.6 | 28.6  | 8.3<br>8.3 | 8.3          | 29.7<br>29.8 | 29.8              | 96.2<br>96.1 | 96.2                    | 6.3<br>6.3 | 6.3 | 6.3             | 0.7<br>0.7 | 0.7        | 0.7                     | 2.2<br>2.2 | 2.2        | 3.9 |     |
|          |                   |                 |               | Middle    | 4.5              | 28.5<br>28.5 | 28.5  | 8.3<br>8.3 | 8.3          | 30.3<br>30.4 | 30.4              | 95.3<br>95.2 | 95.3                    | 6.3<br>6.2 | 6.3 |                 | 6.3        | 0.7<br>0.7 |                         | 0.7        | 4.2<br>4.2 |     | 4.2 |
|          |                   |                 |               | Bottom    | 8                | 28.5<br>28.5 | 28.5  | 8.3<br>8.3 | 8.3          | 30.6<br>30.7 | 30.7              | 96.3<br>96.8 | 96.6                    | 6.3<br>6.3 | 6.3 |                 | 6.3        | 0.7<br>0.7 |                         | 0.7        | 5.4<br>5.2 |     | 5.3 |
| M1       | Cloudy            | Moderate        | 16:26         | Surface   | 1                | 28.7<br>28.7 | 28.7  | 8.3<br>8.3 | 8.3          | 29.5<br>29.6 | 29.6              | 96.8<br>96.7 | 96.8                    | 6.4<br>6.4 | 6.4 | 6.3             | 0.6<br>0.6 | 0.6        | 0.8                     | 3.9<br>3.9 | 3.9        | 5.2 |     |
|          |                   |                 |               | Middle    | 3                | 28.5<br>28.5 | 28.5  | 8.3<br>8.3 | 8.3          | 30.3<br>30.3 | 30.3              | 93.8<br>93.8 | 93.8                    | 6.2<br>6.2 | 6.2 |                 | 6.2        | 0.9<br>0.9 |                         | 0.9        | 5.5<br>5.7 |     | 5.6 |
|          |                   |                 |               | Bottom    | 5                | 28.4<br>28.4 | 28.4  | 8.3<br>8.3 | 8.3          | 30.6<br>30.6 | 30.6              | 94.3<br>94.3 | 94.3                    | 6.2<br>6.2 | 6.2 |                 | 6.2        | 0.9<br>0.9 |                         | 0.9        | 6.0<br>6.1 |     | 6.1 |
| M2       | Cloudy            | Moderate        | 16:16         | Surface   | 1                | 28.7<br>28.7 | 28.7  | 8.3<br>8.3 | 8.3          | 29.3<br>29.2 | 29.3              | 96.9<br>97.3 | 97.1                    | 6.4<br>6.4 | 6.4 | 6.3             | 0.6<br>0.6 | 0.6        | 0.9                     | 4.3<br>4.4 | 4.4        | 5.8 |     |
|          |                   |                 |               | Middle    | 6                | 28.5<br>28.5 | 28.5  | 8.3<br>8.3 | 8.3          | 30.4<br>30.4 | 30.4              | 92.7<br>92.7 | 92.7                    | 6.1<br>6.1 | 6.1 |                 | 6.1        | 1.1<br>1.1 |                         | 1.1        | 6.3<br>6.3 |     | 6.3 |
|          |                   |                 |               | Bottom    | 11               | 28.4<br>28.4 | 28.4  | 8.3<br>8.3 | 8.3          | 30.8<br>30.9 | 30.9              | 92.5<br>92.6 | 92.6                    | 6.1<br>6.1 | 6.1 |                 | 6.1        | 1.1<br>1.0 |                         | 1.1        | 6.6<br>6.6 |     | 6.6 |
| M3       | Cloudy            | Moderate        | 16:44         | Surface   | 1                | 28.6<br>28.6 | 28.6  | 8.3<br>8.3 | 8.3          | 29.8<br>29.8 | 29.8              | 95.9<br>95.9 | 95.9                    | 6.3<br>6.3 | 6.3 | 6.3             | 0.7<br>0.7 | 0.7        | 0.7                     | 4.1<br>4.1 | 4.1        | 4.7 |     |
|          |                   |                 |               | Middle    | 4                | 28.5<br>28.5 | 28.5  | 8.3<br>8.3 | 8.3          | 30.5<br>30.5 | 30.5              | 95.2<br>95.2 | 95.2                    | 6.2<br>6.2 | 6.2 |                 | 6.2        | 0.8<br>0.8 |                         | 0.8        | 4.6<br>4.8 |     | 4.7 |
|          |                   |                 |               | Bottom    | 7                | 28.5<br>28.5 | 28.5  | 8.3<br>8.3 | 8.3          | 30.7<br>30.7 | 30.7              | 96.8<br>97.0 | 96.9                    | 6.3<br>6.4 | 6.4 |                 | 6.4        | 0.6<br>0.6 |                         | 0.6        | 5.1<br>5.4 |     | 5.3 |
| M4       | Cloudy            | Moderate        | 16:06         | Surface   | 1                | 28.7<br>28.7 | 28.7  | 8.3<br>8.3 | 8.3          | 29.6<br>29.6 | 29.6              | 96.5<br>96.8 | 96.7                    | 6.3<br>6.4 | 6.4 | 6.2             | 0.6<br>0.6 | 0.6        | 1.0                     | 2.7<br>2.8 | 2.8        | 5.7 |     |
|          |                   |                 |               | Middle    | 5                | 28.4<br>28.4 | 28.4  | 8.3<br>8.3 | 8.3          | 30.8<br>30.7 | 30.8              | 92.0<br>91.8 | 91.9                    | 6.0<br>6.0 | 6.0 |                 | 6.0        | 1.3<br>1.3 |                         | 1.3        | 8.7<br>8.8 |     | 8.8 |
|          |                   |                 |               | Bottom    | 9                | 28.4<br>28.3 | 28.4  | 8.3<br>8.3 | 8.3          | 31.0<br>31.1 | 31.1              | 92.2<br>92.8 | 92.5                    | 6.0<br>6.1 | 6.1 |                 | 6.1        | 1.0<br>1.0 |                         | 1.0        | 5.5<br>5.7 |     | 5.6 |
| M5       | Cloudy            | Moderate        | 17:07         | Surface   | 1                | 28.6<br>28.6 | 28.6  | 8.3<br>8.3 | 8.3          | 29.9<br>29.9 | 29.9              | 95.6<br>95.7 | 95.7                    | 6.3<br>6.3 | 6.3 | 6.4             | 0.7<br>0.7 | 0.7        | 0.8                     | 4.9<br>4.6 | 4.8        | 4.7 |     |
|          |                   |                 |               | Middle    | 5.5              | 28.5<br>28.5 | 28.5  | 8.3<br>8.3 | 8.3          | 30.6<br>30.6 | 30.6              | 97.1<br>96.9 | 97.0                    | 6.4<br>6.4 | 6.4 |                 | 6.4        | 0.7<br>0.7 |                         | 0.7        | 5.0<br>5.2 |     | 5.1 |
|          |                   |                 |               | Bottom    | 10               | 28.3<br>28.3 | 28.3  | 8.3<br>8.3 | 8.3          | 31.4<br>31.4 | 31.4              | 91.2<br>91.1 | 91.2                    | 6.0<br>6.0 | 6.0 |                 | 6.0        | 1.0<br>1.0 |                         | 1.0        | 4.3<br>4.3 |     | 4.3 |
| M6       | Cloudy            | Moderate        | 16:57         | Surface   | -                | -            | -     | -          | -            | -            | -                 | -            | -                       | -          | -   | 6.3             | -          | -          | 0.8                     | -          | -          | 3.8 |     |
|          |                   |                 |               | Middle    | 2.1              | 28.5<br>28.5 | 28.5  | 8.3<br>8.3 | 8.3          | 30.2<br>30.2 | 30.2              | 95.3<br>95.1 | 95.2                    | 6.3<br>6.2 | 6.3 |                 | 6.3        | 0.8<br>0.8 |                         | 0.8        | 3.8<br>3.7 |     | 3.8 |
|          |                   |                 |               | Bottom    | -                | -            | -     | -          | -            | -            | -                 | -            | -                       | -          | -   |                 | -          | -          |                         | -          | -          |     | -   |

Remarks: \*DA: Depth-Averaged  
 \*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

**Appendix I - Action and Limit Levels for Marine Water Quality on 19 June 2018 (Mid-Flood Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <b><u>4.9 mg/L</u></b>  | <b><u>4.6 mg/L</u></b>  |
|   | Bottom                              | <b><u>4.2 mg/L</u></b>  | <b><u>3.6 mg/L</u></b>  |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <b><u>5.0 mg/L</u></b>  | <b><u>4.7 mg/L</u></b>  |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <b><u>19.3 NTU</u></b><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><b><u>CI: 1.4 NTU</u></b> | <b><u>22.2 NTU</u></b><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><b><u>CI: 1.6 NTU</u></b> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <b><u>19.0 NTU</u></b>  | <b><u>19.4 NTU</u></b>  |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <b><u>6.0 mg/L</u></b><br>or 120% of upstream control station's SS at the same tide of the same day<br><b><u>CI: 6.4 mg/L</u></b>       | <b><u>6.9 mg/L</u></b><br>or 130% of upstream control station's SS at the same tide of the same day<br><b><u>CI: 6.9 mg/L</u></b>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <b><u>6.2 mg/L</u></b><br>or 120% of upstream control station's SS at the same tide of the same day<br><b><u>CI: 6.4 mg/L</u></b>       | <b><u>7.4 mg/L</u></b><br>or 130% of upstream control station's SS at the same tide of the same day<br><b><u>CI: 6.9 mg/L</u></b>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <b><u>6.9 mg/L</u></b><br>or 120% of upstream control station's SS at the same tide of the same day<br><b><u>CI: 7.0 mg/L</u></b>       | <b><u>7.9 mg/L</u></b><br>or 130% of upstream control station's SS at the same tide of the same day<br><b><u>CI: 7.5 mg/L</u></b>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <b><u>8.3 mg/L</u></b>              | <b><u>8.6 mg/L</u></b>  |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction  
Water Quality Monitoring Results on 19 June 2018**

**(Mid-Flood Tide)**

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) |      | Temperature (°C) |         | pH    |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         |     | Turbidity (NTU) |         |     | Suspended Solids (mg/L) |         |     |
|----------|-------------------|-----------------|---------------|-----------|------|------------------|---------|-------|---------|--------------|---------|-------------------|---------|-------------------------|---------|-----|-----------------|---------|-----|-------------------------|---------|-----|
|          |                   |                 |               |           |      | Value            | Average | Value | Average | Value        | Average | Value             | Average | Value                   | Average | DA* | Value           | Average | DA* | Value                   | Average | DA* |
| C1       | Cloudy            | Moderate        | 11:26         | Surface   | 1    | 28.5             | 28.5    | 8.3   | 8.3     | 30.7         | 30.7    | 103.7             | 103.8   | 6.8                     | 6.8     | 6.5 | 0.9             | 0.9     | 1.0 | 5.3                     | 5.3     | 5.6 |
|          |                   |                 |               |           |      | 28.5             | 28.5    | 8.3   | 8.3     | 30.7         | 30.7    | 103.9             | 103.8   | 6.8                     | 6.8     |     | 0.9             | 0.9     |     | 5.2                     | 5.2     |     |
|          |                   |                 |               | Middle    | 9    | 28.3             | 28.3    | 8.3   | 8.3     | 31.2         | 31.2    | 93.0              | 93.0    | 6.1                     | 6.1     |     | 0.9             | 0.9     |     | 5.6                     | 5.6     |     |
|          |                   |                 |               | 28.0      | 28.0 | 8.3              | 8.3     | 32.2  | 32.2    | 82.8         | 82.7    | 5.4               | 5.4     | 5.4                     | 1.1     | 1.2 | 1.2             | 5.8     | 5.8 |                         |         |     |
|          |                   |                 |               | 28.0      | 28.0 | 8.3              | 8.3     | 32.2  | 32.2    | 82.7         | 82.7    | 5.4               | 5.4     | 5.4                     | 1.2     | 1.2 | 1.2             | 5.7     | 5.7 |                         |         |     |
| C2       | Cloudy            | Moderate        | 10:08         | Surface   | 1    | 28.5             | 28.5    | 8.2   | 8.2     | 30.5         | 30.5    | 100.4             | 100.4   | 6.6                     | 6.6     | 6.4 | 0.8             | 0.8     | 0.8 | 2.6                     | 2.6     | 4.7 |
|          |                   |                 |               |           |      | 28.5             | 28.5    | 8.2   | 8.2     | 30.5         | 30.5    | 100.4             | 100.4   | 6.6                     | 6.6     |     | 0.8             | 0.8     |     | 2.6                     | 2.6     |     |
|          |                   |                 |               | Middle    | 16.5 | 28.4             | 28.4    | 8.2   | 8.2     | 31.0         | 31.0    | 94.5              | 94.5    | 6.2                     | 6.2     |     | 0.8             | 0.8     |     | 7.2                     | 7.4     |     |
|          |                   |                 |               | 28.3      | 28.3 | 8.3              | 8.3     | 31.1  | 31.1    | 93.0         | 92.7    | 6.1               | 6.1     | 6.1                     | 0.9     | 0.9 | 0.9             | 4.2     | 4.2 |                         |         |     |
|          |                   |                 |               | 28.3      | 28.3 | 8.3              | 8.3     | 31.1  | 31.1    | 92.7         | 92.7    | 6.1               | 6.1     | 6.1                     | 0.9     | 0.9 | 0.9             | 4.2     | 4.2 |                         |         |     |
| G1       | Cloudy            | Moderate        | 10:45         | Surface   | 1    | 28.5             | 28.5    | 8.3   | 8.3     | 30.6         | 30.6    | 101.8             | 101.9   | 6.7                     | 6.7     | 6.7 | 1.0             | 1.0     | 0.9 | 3.9                     | 4.0     | 3.3 |
|          |                   |                 |               |           |      | 28.5             | 28.5    | 8.3   | 8.3     | 30.6         | 30.6    | 102.0             | 102.0   | 6.7                     | 6.7     |     | 0.9             | 0.9     |     | 4.1                     | 4.1     |     |
|          |                   |                 |               | Middle    | 4    | 28.4             | 28.4    | 8.3   | 8.3     | 30.8         | 30.8    | 100.3             | 100.1   | 6.6                     | 6.6     |     | 0.9             | 0.9     |     | 3.8                     | 3.8     |     |
|          |                   |                 |               | 28.4      | 28.4 | 8.3              | 8.3     | 30.8  | 30.8    | 99.9         | 99.9    | 6.5               | 6.5     | 6.6                     | 0.8     | 0.8 | 0.9             | 3.8     | 3.8 |                         |         |     |
|          |                   |                 |               | 28.3      | 28.3 | 8.3              | 8.3     | 31.1  | 31.1    | 94.5         | 94.4    | 6.2               | 6.2     | 6.2                     | 0.8     | 0.8 | 0.9             | 2.2     | 2.2 |                         |         |     |
|          |                   |                 |               | 28.3      | 28.3 | 8.3              | 8.3     | 31.1  | 31.1    | 94.4         | 94.4    | 6.2               | 6.2     | 6.2                     | 0.9     | 0.9 | 0.9             | 2.2     | 2.2 |                         |         |     |
| G2       | Cloudy            | Moderate        | 10:32         | Surface   | 1    | 28.5             | 28.5    | 8.3   | 8.3     | 30.6         | 30.6    | 101.3             | 101.3   | 6.6                     | 6.6     | 6.6 | 0.9             | 0.9     | 0.8 | 2.3                     | 2.3     | 3.0 |
|          |                   |                 |               |           |      | 28.5             | 28.5    | 8.3   | 8.3     | 30.6         | 30.6    | 101.3             | 101.3   | 6.6                     | 6.6     |     | 0.9             | 0.9     |     | 2.2                     | 2.2     |     |
|          |                   |                 |               | Middle    | 5    | 28.4             | 28.4    | 8.3   | 8.3     | 30.8         | 30.8    | 99.2              | 99.1    | 6.5                     | 6.5     |     | 0.8             | 0.8     |     | 2.9                     | 2.9     |     |
|          |                   |                 |               | 28.4      | 28.4 | 8.3              | 8.3     | 30.8  | 30.8    | 98.9         | 98.9    | 6.5               | 6.5     | 6.6                     | 0.8     | 0.8 | 0.8             | 2.9     | 2.9 |                         |         |     |
|          |                   |                 |               | 28.3      | 28.3 | 8.3              | 8.3     | 31.1  | 31.1    | 94.8         | 94.7    | 6.2               | 6.2     | 6.2                     | 0.8     | 0.8 | 0.8             | 3.8     | 3.8 |                         |         |     |
|          |                   |                 |               | 28.3      | 28.3 | 8.3              | 8.3     | 31.1  | 31.1    | 94.5         | 94.5    | 6.2               | 6.2     | 6.2                     | 0.8     | 0.8 | 0.8             | 3.8     | 3.8 |                         |         |     |
| G3       | Cloudy            | Moderate        | 10:52         | Surface   | 1    | 28.5             | 28.5    | 8.3   | 8.3     | 30.6         | 30.6    | 102.0             | 102.1   | 6.7                     | 6.7     | 6.7 | 0.9             | 0.9     | 0.9 | 2.8                     | 2.9     | 3.1 |
|          |                   |                 |               |           |      | 28.5             | 28.5    | 8.3   | 8.3     | 30.6         | 30.6    | 102.1             | 102.1   | 6.7                     | 6.7     |     | 0.9             | 0.9     |     | 3.0                     | 3.0     |     |
|          |                   |                 |               | Middle    | 4    | 28.4             | 28.4    | 8.3   | 8.3     | 30.8         | 30.8    | 101.4             | 101.2   | 6.6                     | 6.6     |     | 0.9             | 0.9     |     | 3.0                     | 3.0     |     |
|          |                   |                 |               | 28.4      | 28.4 | 8.3              | 8.3     | 30.8  | 30.8    | 100.9        | 100.9   | 6.6               | 6.6     | 6.6                     | 0.8     | 0.8 | 0.9             | 2.9     | 2.9 |                         |         |     |
|          |                   |                 |               | 28.3      | 28.3 | 8.3              | 8.3     | 31.1  | 31.1    | 94.4         | 94.4    | 6.2               | 6.2     | 6.2                     | 0.9     | 0.9 | 0.9             | 3.3     | 3.3 |                         |         |     |
|          |                   |                 |               | 28.3      | 28.3 | 8.3              | 8.3     | 31.1  | 31.1    | 94.2         | 94.2    | 6.2               | 6.2     | 6.2                     | 0.9     | 0.9 | 0.9             | 3.4     | 3.4 |                         |         |     |
| G4       | Cloudy            | Moderate        | 11:04         | Surface   | 1    | 28.5             | 28.5    | 8.3   | 8.3     | 30.6         | 30.6    | 102.6             | 102.7   | 6.7                     | 6.7     | 6.6 | 0.9             | 0.9     | 0.8 | 0.5                     | 0.5     | 3.2 |
|          |                   |                 |               |           |      | 28.5             | 28.5    | 8.3   | 8.3     | 30.6         | 30.6    | 102.8             | 102.7   | 6.7                     | 6.7     |     | 0.9             | 0.9     |     | 0.5                     | 0.5     |     |
|          |                   |                 |               | Middle    | 4.5  | 28.4             | 28.4    | 8.3   | 8.3     | 30.9         | 30.9    | 99.9              | 99.8    | 6.5                     | 6.5     |     | 0.8             | 0.8     |     | 5.2                     | 5.2     |     |
|          |                   |                 |               | 28.4      | 28.4 | 8.3              | 8.3     | 30.9  | 30.9    | 99.6         | 99.6    | 6.5               | 6.5     | 6.6                     | 0.8     | 0.8 | 0.8             | 5.2     | 5.2 |                         |         |     |
|          |                   |                 |               | 28.3      | 28.3 | 8.3              | 8.3     | 31.1  | 31.1    | 93.7         | 93.7    | 6.1               | 6.1     | 6.1                     | 0.8     | 0.8 | 0.8             | 3.9     | 4.0 |                         |         |     |
|          |                   |                 |               | 28.3      | 28.3 | 8.3              | 8.3     | 31.1  | 31.1    | 93.7         | 93.7    | 6.1               | 6.1     | 6.1                     | 0.8     | 0.8 | 0.8             | 4.0     | 4.0 |                         |         |     |
| M1       | Cloudy            | Moderate        | 10:39         | Surface   | 1    | 28.5             | 28.5    | 8.3   | 8.3     | 30.6         | 30.6    | 101.1             | 101.2   | 6.6                     | 6.6     | 6.6 | 1.1             | 1.0     | 0.9 | 5.1                     | 5.2     | 4.7 |
|          |                   |                 |               |           |      | 28.5             | 28.5    | 8.3   | 8.3     | 30.6         | 30.6    | 101.2             | 101.2   | 6.6                     | 6.6     |     | 0.9             | 0.9     |     | 5.3                     | 5.3     |     |
|          |                   |                 |               | Middle    | 3    | 28.4             | 28.4    | 8.3   | 8.3     | 30.7         | 30.7    | 100.9             | 100.9   | 6.6                     | 6.6     |     | 0.9             | 0.9     |     | 4.2                     | 4.2     |     |
|          |                   |                 |               | 28.4      | 28.4 | 8.3              | 8.3     | 30.7  | 30.7    | 100.8        | 100.8   | 6.6               | 6.6     | 6.6                     | 0.8     | 0.8 | 0.8             | 4.1     | 4.1 |                         |         |     |
|          |                   |                 |               | 28.4      | 28.4 | 8.3              | 8.3     | 31.0  | 31.0    | 96.0         | 96.0    | 6.3               | 6.3     | 6.3                     | 0.8     | 0.8 | 0.8             | 4.9     | 4.8 |                         |         |     |
|          |                   |                 |               | 28.4      | 28.4 | 8.3              | 8.3     | 30.9  | 30.9    | 95.9         | 95.9    | 6.3               | 6.3     | 6.3                     | 0.8     | 0.8 | 0.8             | 4.7     | 4.7 |                         |         |     |
| M2       | Cloudy            | Moderate        | 10:24         | Surface   | 1    | 28.5             | 28.5    | 8.3   | 8.3     | 30.6         | 30.6    | 100.7             | 100.7   | 6.6                     | 6.6     | 6.6 | 0.8             | 0.8     | 0.8 | 4.9                     | 4.9     | 5.7 |
|          |                   |                 |               |           |      | 28.5             | 28.5    | 8.3   | 8.3     | 30.6         | 30.6    | 100.7             | 100.7   | 6.6                     | 6.6     |     | 0.8             | 0.8     |     | 4.9                     | 4.9     |     |
|          |                   |                 |               | Middle    | 6    | 28.4             | 28.4    | 8.3   | 8.3     | 30.8         | 30.8    | 99.8              | 99.8    | 6.5                     | 6.5     |     | 0.8             | 0.8     |     | 5.7                     | 5.6     |     |
|          |                   |                 |               | 28.4      | 28.4 | 8.3              | 8.3     | 30.8  | 30.8    | 99.7         | 99.7    | 6.5               | 6.5     | 6.6                     | 0.8     | 0.8 | 0.8             | 5.5     | 5.5 |                         |         |     |
|          |                   |                 |               | 28.3      | 28.3 | 8.3              | 8.3     | 31.1  | 31.1    | 93.4         | 93.4    | 6.1               | 6.1     | 6.1                     | 0.9     | 0.9 | 0.9             | 6.5     | 6.5 |                         |         |     |
|          |                   |                 |               | 28.3      | 28.3 | 8.3              | 8.3     | 31.1  | 31.1    | 93.3         | 93.3    | 6.1               | 6.1     | 6.1                     | 0.9     | 0.9 | 0.9             | 6.4     | 6.4 |                         |         |     |
| M3       | Cloudy            | Moderate        | 10:57         | Surface   | 1    | 28.5             | 28.5    | 8.3   | 8.3     | 30.6         | 30.6    | 102.3             | 102.4   | 6.7                     | 6.7     | 6.7 | 0.9             | 0.9     | 0.9 | 2.3                     | 2.3     | 2.8 |
|          |                   |                 |               |           |      | 28.5             | 28.5    | 8.3   | 8.3     | 30.6         | 30.6    | 102.4             | 102.4   | 6.7                     | 6.7     |     | 0.9             | 0.9     |     | 2.2                     | 2.2     |     |
|          |                   |                 |               | Middle    | 4    | 28.4             | 28.4    | 8.3   | 8.3     | 30.8         | 30.8    | 100.2             | 99.7    | 6.6                     | 6.6     |     | 0.8             | 0.9     |     | 1.3                     | 1.3     |     |
|          |                   |                 |               | 28.4      | 28.4 | 8.3              | 8.3     | 30.8  | 30.8    | 99.2         | 99.2    | 6.5               | 6.5     | 6.6                     | 0.9     | 0.9 | 0.9             | 1.3     | 1.3 |                         |         |     |
|          |                   |                 |               | 28.3      | 28.3 | 8.3              | 8.3     | 31.1  | 31.1    | 93.9         | 93.8    | 6.2               | 6.2     | 6.2                     | 0.8     | 0.8 | 0.8             | 4.7     | 4.7 |                         |         |     |
|          |                   |                 |               | 28.3      | 28.3 | 8.3              | 8.3     | 31.1  | 31.1    | 93.7         | 93.7    | 6.2               | 6.2     | 6.2                     | 0.8     | 0.8 | 0.8             | 4.6     | 4.6 |                         |         |     |
| M4       | Cloudy            | Moderate        | 10:15         | Surface   | 1    | 28.5             | 28.5    | 8.3   | 8.3     | 30.5         | 30.5    | 100.4             | 100.5   | 6.6                     | 6.6     | 6.4 | 0.9             | 0.9     | 0.9 | 5.5                     | 5.5     | 4.9 |
|          |                   |                 |               |           |      | 28.5             | 28.5    | 8.3   | 8.3     | 30.5         | 30.5    | 100.6             | 100.5   | 6.6                     | 6.6     |     | 0.9             | 0.9     |     | 5.5                     | 5.5     |     |
|          |                   |                 |               | Middle    | 5    | 28.3             | 28.3    | 8.3   | 8.3     | 31.0         | 31.0    | 95.0              | 95.0    | 6.2                     | 6.2     |     | 0.8             | 0.8     |     | 4.3                     | 4.4     |     |
|          |                   |                 |               | 28.3      | 28.3 | 8.3              | 8.3     | 31.0  | 31.0    | 95.0         | 95.0    | 6.2               | 6.2     | 6.2                     | 0.8     | 0.8 | 0.8             | 4.4     | 4.4 |                         |         |     |
|          |                   |                 |               | 28.3      | 28.3 | 8.3              | 8.3     | 31.1  | 31.1    | 93.9         | 93.8    | 6.2               | 6.2     | 6.2                     | 0.9     | 0.9 | 0.9             | 4.7     | 4.7 |                         |         |     |
|          |                   |                 |               | 28.3      | 28.3 | 8.3              | 8.3     | 31.1  | 31.1    | 93.6         | 93.6    | 6.1               | 6.1     | 6.2                     | 0.9     | 0.9 | 0.9             | 4.6     | 4.6 |                         |         |     |
| M5       | Cloudy            | Moderate        | 11:18         | Surface   | 1    | 28.5             | 28.5    | 8.3   | 8.3     | 30.6         | 30.6    | 104.0             | 104.0   | 6.8                     | 6.8     | 6.6 | 0.9             | 0.9     | 0.9 | 5.6                     | 5.5     | 5.8 |
|          |                   |                 |               |           |      | 28.5             | 28.5    | 8.3   | 8.3     | 30.6         | 30.6    | 104.0             | 104.0   | 6.8                     | 6.8     |     | 0.9             | 0.9     |     | 5.4                     | 5.4     |     |
|          |                   |                 |               | Middle    | 5.5  | 28.4             | 28.4    | 8.3   | 8.3     | 30.9         | 30.9    | 97.8              | 97.8    | 6.4                     | 6.4     |     | 0.8             | 0.8     |     | 5.7                     | 5.7     |     |
|          |                   |                 |               | 28.4      | 28.4 | 8.3              | 8.3     | 30.9  | 30.9    | 97.7         | 97.7    | 6.4               | 6.4     | 6.4                     | 0.8     | 0.8 | 0.8             | 5.6     | 5.6 |                         |         |     |
|          |                   |                 |               | 28.3      | 28.3 | 8.3              | 8.3     | 31.2  | 31.2    | 93.3         | 93.2    | 6.1               | 6.1     | 6.1                     | 0.8     | 0.8 | 0.9             | 6.1     | 6.1 |                         |         |     |
|          |                   |                 |               | 28.3      | 28.3 | 8.3              | 8.3     | 31.2  | 31.2    | 93.0         | 93.0    | 6.1               | 6.1     | 6.1                     | 0.9     | 0.9 | 0.9             | 6.0     | 6.0 |                         |         |     |
| M6       | Cloudy            | Moderate        | 11:10         | Surface   | -    | -                | -       | -     | -       | -            | -       | -                 | -       | -                       | 6.7     | -   | -               | 0.8     | -   | -                       | 2.0     |     |
|          |                   |                 |               |           |      | 28.5             | 28.5    | 8.3   | 8.3     | 30.8         | 30.8    | 102.4             | 102.5   | 6.7                     |         | 6.7 | 0.8             |         | 0.8 | 2.0                     |         | 2.0 |
|          |                   |                 |               | Middle    | 2    | 28.5             | 28.5    | 8.3   | 8.3</   |              |         |                   |         |                         |         |     |                 |         |     |                         |         |     |



**Appendix I - Action and Limit Levels for Marine Water Quality on 21 June 2018 (Mid-Ebb Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 6.5 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 7.0 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.7 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.3 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.7 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.3 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 5.0 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 5.5 mg/L</u>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction**  
**Water Quality Monitoring Results on 21 June 2018**

**(Mid-Ebb Tide)**

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) |      | Temperature (°C) |         | pH    |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         |     | Turbidity(NTU) |         |     | Suspended Solids (mg/L) |         |     |     |
|----------|-------------------|-----------------|---------------|-----------|------|------------------|---------|-------|---------|--------------|---------|-------------------|---------|-------------------------|---------|-----|----------------|---------|-----|-------------------------|---------|-----|-----|
|          |                   |                 |               |           |      | Value            | Average | Value | Average | Value        | Average | Value             | Average | Value                   | Average | DA* | Value          | Average | DA* | Value                   | Average | DA* |     |
| C1       | Rainy             | Calm            | 19:16         | Surface   | 1    | 28.8             | 28.8    | 8.2   | 8.2     | 28.9         | 29.0    | 90.0              | 89.6    | 5.9                     | 5.9     | 5.7 | 1.3            | 1.4     | 2.7 | 4.7                     | 4.6     | 4.2 |     |
|          |                   |                 |               | Middle    | 9    | 28.0             | 28.0    | 8.2   | 8.2     | 32.5         | 32.5    | 81.9              | 82.2    | 5.4                     | 5.4     | 1.7 | 1.7            | 4.5     |     | 4.5                     |         |     |     |
|          |                   |                 |               | Bottom    | 17   | 27.4             | 27.5    | 8.2   | 8.2     | 33.3         | 33.3    | 73.1              | 75.4    | 4.8                     | 4.9     | 5.0 | 5.0            | 3.1     |     | 3.1                     |         |     |     |
| C2       | Rainy             | Calm            | 18:03         | Surface   | 1    | 29.2             | 29.2    | 8.2   | 8.2     | 27.3         | 27.3    | 101.6             | 101.3   | 6.7                     | 6.7     | 5.9 | 1.0            | 1.1     | 3.7 | 5.5                     | 5.6     | 4.6 |     |
|          |                   |                 |               | Middle    | 17.5 | 27.7             | 27.7    | 8.2   | 8.2     | 33.0         | 33.0    | 75.8              | 75.1    | 5.0                     | 4.9     | 5.0 | 4.7            | 4.7     |     | 4.1                     | 4.1     |     |     |
|          |                   |                 |               | Bottom    | 34   | 27.7             | 27.7    | 8.2   | 8.2     | 33.1         | 33.1    | 75.4              | 75.1    | 4.9                     | 4.9     | 5.8 | 5.4            | 4.2     |     | 4.2                     |         |     |     |
| G1       | Rainy             | Calm            | 18:40         | Surface   | 1    | 29.2             | 29.2    | 8.4   | 8.4     | 29.5         | 29.5    | 135.1             | 135.3   | 8.8                     | 8.8     | 8.5 | 0.6            | 0.6     | 1.1 | 2.8                     | 2.8     | 2.9 |     |
|          |                   |                 |               | Middle    | 4    | 29.1             | 29.1    | 8.4   | 8.4     | 29.7         | 29.7    | 123.3             | 123.5   | 8.0                     | 8.1     | 0.6 | 0.6            | 0.6     |     | 0.6                     | 3.0     |     | 3.1 |
|          |                   |                 |               | Bottom    | 7    | 28.1             | 28.1    | 8.2   | 8.2     | 32.4         | 32.4    | 84.9              | 84.6    | 5.5                     | 5.5     | 2.1 | 2.1            | 2.7     |     | 2.7                     |         |     |     |
| G2       | Rainy             | Calm            | 18:26         | Surface   | 1    | 29.1             | 29.1    | 8.4   | 8.4     | 29.7         | 29.8    | 129.4             | 126.2   | 8.4                     | 8.2     | 7.0 | 0.6            | 0.6     | 1.2 | 3.7                     | 3.7     | 3.7 |     |
|          |                   |                 |               | Middle    | 5    | 28.4             | 28.4    | 8.2   | 8.3     | 31.3         | 31.3    | 86.3              | 91.2    | 5.6                     | 6.0     | 1.1 | 1.2            | 4.2     |     | 4.2                     |         |     |     |
|          |                   |                 |               | Bottom    | 9    | 28.1             | 28.1    | 8.2   | 8.2     | 32.4         | 32.4    | 85.6              | 84.8    | 5.6                     | 5.5     | 1.9 | 1.9            | 3.1     |     | 3.1                     |         |     |     |
| G3       | Rainy             | Calm            | 18:46         | Surface   | 1    | 29.2             | 29.2    | 8.4   | 8.4     | 29.3         | 29.3    | 143.7             | 142.7   | 9.4                     | 9.3     | 8.8 | 0.7            | 0.7     | 1.3 | 3.4                     | 3.4     | 3.4 |     |
|          |                   |                 |               | Middle    | 4    | 29.1             | 29.1    | 8.4   | 8.4     | 29.6         | 29.6    | 126.9             | 124.6   | 8.3                     | 8.1     | 0.6 | 0.6            | 0.6     |     | 0.6                     | 3.5     |     | 3.5 |
|          |                   |                 |               | Bottom    | 7    | 28.2             | 28.2    | 8.2   | 8.2     | 32.1         | 32.3    | 85.0              | 81.3    | 5.6                     | 5.5     | 2.2 | 2.5            | 3.3     |     | 3.3                     |         |     |     |
| G4       | Rainy             | Calm            | 18:57         | Surface   | 1    | 29.4             | 29.4    | 8.5   | 8.5     | 29.1         | 29.1    | 152.0             | 149.5   | 9.9                     | 9.8     | 8.5 | 0.8            | 0.8     | 2.7 | 4.8                     | 4.8     | 3.9 |     |
|          |                   |                 |               | Middle    | 4.5  | 28.9             | 28.9    | 8.3   | 8.3     | 30.1         | 30.1    | 106.8             | 110.7   | 7.0                     | 7.1     | 1.1 | 1.1            | 3.1     |     | 3.1                     |         |     |     |
|          |                   |                 |               | Bottom    | 8    | 28.1             | 28.2    | 8.2   | 8.3     | 32.3         | 32.0    | 74.0              | 78.8    | 4.8                     | 5.0     | 6.5 | 6.2            | 3.7     |     | 3.8                     |         |     |     |
| M1       | Rainy             | Calm            | 18:35         | Surface   | 1    | 29.1             | 29.1    | 8.4   | 8.4     | 29.6         | 29.7    | 128.8             | 126.3   | 8.4                     | 8.3     | 8.2 | 0.6            | 0.6     | 0.7 | 2.1                     | 2.2     | 3.1 |     |
|          |                   |                 |               | Middle    | 3    | 29.1             | 29.1    | 8.4   | 8.4     | 29.7         | 29.7    | 121.3             | 122.9   | 7.9                     | 8.0     | 0.7 | 0.7            | 2.8     |     | 2.8                     |         |     |     |
|          |                   |                 |               | Bottom    | 5    | 28.7             | 28.8    | 8.3   | 8.3     | 30.6         | 30.3    | 99.0              | 111.7   | 6.5                     | 6.9     | 0.8 | 0.8            | 4.4     |     | 4.4                     |         |     |     |
| M2       | Rainy             | Calm            | 18:20         | Surface   | 1    | 29.1             | 29.0    | 8.4   | 8.4     | 29.8         | 29.9    | 130.1             | 121.4   | 8.5                     | 8.0     | 7.0 | 0.7            | 0.7     | 2.0 | 3.1                     | 3.1     | 2.8 |     |
|          |                   |                 |               | Middle    | 6    | 28.2             | 28.3    | 8.2   | 8.3     | 32.0         | 31.7    | 90.7              | 90.3    | 5.9                     | 5.9     | 0.9 | 1.0            | 2.4     |     | 2.4                     |         |     |     |
|          |                   |                 |               | Bottom    | 11   | 28.0             | 28.0    | 8.2   | 8.2     | 32.8         | 32.9    | 77.7              | 76.7    | 5.1                     | 5.1     | 4.4 | 4.4            | 3.0     |     | 3.0                     |         |     |     |
| M3       | Rainy             | Calm            | 18:51         | Surface   | 1    | 29.2             | 29.1    | 8.4   | 8.4     | 29.3         | 29.5    | 142.2             | 136.5   | 9.3                     | 9.0     | 8.6 | 0.6            | 0.6     | 1.2 | 4.3                     | 4.3     | 3.7 |     |
|          |                   |                 |               | Middle    | 4    | 29.1             | 29.1    | 8.4   | 8.4     | 29.7         | 29.7    | 125.7             | 122.5   | 8.2                     | 8.1     | 0.6 | 0.6            | 3.5     |     | 3.5                     |         |     |     |
|          |                   |                 |               | Bottom    | 7    | 28.1             | 28.1    | 8.2   | 8.2     | 32.3         | 32.4    | 83.2              | 84.0    | 5.4                     | 5.5     | 2.4 | 2.5            | 3.4     |     | 3.4                     |         |     |     |
| M4       | Rainy             | Calm            | 18:12         | Surface   | 1    | 29.0             | 29.0    | 8.3   | 8.3     | 29.6         | 29.6    | 114.3             | 113.1   | 7.5                     | 7.4     | 7.0 | 0.8            | 0.8     | 1.5 | 4.1                     | 4.2     | 3.8 |     |
|          |                   |                 |               | Middle    | 4.5  | 28.5             | 28.6    | 8.3   | 8.3     | 31.2         | 30.9    | 98.9              | 99.9    | 6.5                     | 6.5     | 0.9 | 0.9            | 3.0     |     | 3.1                     |         |     |     |
|          |                   |                 |               | Bottom    | 8    | 27.9             | 27.9    | 8.2   | 8.2     | 32.7         | 32.8    | 79.3              | 78.6    | 5.2                     | 5.2     | 2.8 | 2.9            | 3.9     |     | 4.0                     |         |     |     |
| M5       | Rainy             | Calm            | 19:08         | Surface   | 1    | 28.9             | 28.9    | 8.3   | 8.3     | 29.3         | 29.3    | 104.5             | 103.4   | 6.9                     | 6.8     | 6.3 | 0.8            | 0.8     | 2.6 | 3.6                     | 3.6     | 4.0 |     |
|          |                   |                 |               | Middle    | 5.5  | 28.2             | 28.3    | 8.3   | 8.3     | 31.9         | 31.5    | 85.6              | 89.5    | 5.6                     | 5.8     | 1.6 | 1.6            | 5.3     |     | 5.4                     |         |     |     |
|          |                   |                 |               | Bottom    | 10   | 28.0             | 28.0    | 8.2   | 8.2     | 32.6         | 32.6    | 78.7              | 79.8    | 5.1                     | 5.2     | 5.5 | 5.5            | 3.0     |     | 3.0                     |         |     |     |
| M6       | Rainy             | Calm            | 19:02         | Surface   | -    | -                | -       | -     | -       | -            | -       | -                 | -       | -                       | -       | 8.2 | -              | -       | 0.7 | -                       | -       | 3.7 |     |
|          |                   |                 |               | Middle    | 2.2  | 29.2             | 29.2    | 8.4   | 8.4     | 29.4         | 29.5    | 125.6             | 123.9   | 8.2                     | 8.2     | 0.7 | 0.7            | 3.6     |     | 3.7                     |         |     |     |
|          |                   |                 |               | Bottom    | -    | -                | -       | -     | -       | -            | -       | -                 | -       | -                       | -       | -   | -              | -       |     | -                       | -       |     |     |

Remarks: \*DA: Depth-Averaged  
 \*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

**Appendix I - Action and Limit Levels for Marine Water Quality on 21 June 2018 (Mid-Flood Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 7.0 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 7.5 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.2 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.8 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.2 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.8 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 5.9 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.4 mg/L</u>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction  
Water Quality Monitoring Results on 21 June 2018**

**(Mid-Flood Tide)**

| Location | Weather Condition | Sea Condition* | Sampling Time | Depth (m) |     | Temperature (°C) |         | pH         |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         |     | Turbidity(NTU) |         |     | Suspended Solids (mg/L) |         |     |
|----------|-------------------|----------------|---------------|-----------|-----|------------------|---------|------------|---------|--------------|---------|-------------------|---------|-------------------------|---------|-----|----------------|---------|-----|-------------------------|---------|-----|
|          |                   |                |               |           |     | Value            | Average | Value      | Average | Value        | Average | Value             | Average | Value                   | Average | DA* | Value          | Average | DA* | Value                   | Average | DA* |
|          |                   |                |               |           |     |                  |         |            |         |              |         |                   |         |                         |         |     |                |         |     |                         |         |     |
| C1       | Rainy             | Calm           | 12:31         | Surface   | 1   | 28.8<br>28.8     | 28.8    | 8.3<br>8.3 | 8.3     | 29.3<br>29.4 | 29.4    | 98.6<br>96.9      | 97.8    | 6.5<br>6.4              | 6.5     | 6.1 | 0.6<br>0.6     | 0.6     | 2.5 | 5.1<br>5.2              | 5.2     | 4.9 |
|          |                   |                |               | Middle    | 9.5 | 28.0<br>28.1     | 28.1    | 8.3<br>8.3 | 8.3     | 32.5<br>32.4 | 32.5    | 84.9<br>84.9      | 84.9    | 5.6<br>5.5              | 5.6     |     | 0.9<br>1.0     | 1.0     |     | 4.7<br>4.7              | 4.7     |     |
|          |                   |                |               | Bottom    | 18  | 27.6<br>27.6     | 27.6    | 8.2<br>8.2 | 8.2     | 33.2<br>33.2 | 33.2    | 77.1<br>77.2      | 77.2    | 5.1<br>5.1              | 5.1     |     | 5.8<br>5.7     | 5.8     |     | 4.9<br>4.9              | 4.9     |     |
| C2       | Rainy             | Calm           | 10:59         | Surface   | 1   | 28.9<br>28.9     | 28.9    | 8.1<br>8.2 | 8.2     | 27.8<br>27.9 | 27.9    | 83.9<br>84.3      | 84.1    | 5.5<br>5.6              | 5.6     | 5.5 | 1.0<br>0.9     | 1.0     | 1.5 | 4.2<br>4.3              | 4.3     | 3.8 |
|          |                   |                |               | Middle    | 17  | 28.0<br>28.0     | 28.0    | 8.2<br>8.2 | 8.2     | 32.6<br>32.6 | 32.6    | 81.3<br>81.0      | 81.2    | 5.3<br>5.3              | 5.3     |     | 1.7<br>1.8     | 1.8     |     | 3.7<br>3.8              | 3.8     |     |
|          |                   |                |               | Bottom    | 33  | 28.0<br>28.0     | 28.0    | 8.2<br>8.2 | 8.2     | 32.6<br>32.7 | 32.7    | 81.1<br>81.0      | 81.1    | 5.3<br>5.3              | 5.3     |     | 1.8<br>1.7     | 1.8     |     | 3.4<br>3.4              | 3.4     |     |
| G1       | Rainy             | Calm           | 11:49         | Surface   | 1   | 28.8<br>28.6     | 28.7    | 8.3<br>8.3 | 8.3     | 29.5<br>30.3 | 29.9    | 115.3<br>106.1    | 110.7   | 7.6<br>7.0              | 7.3     | 6.8 | 0.5<br>0.5     | 0.5     | 0.8 | 3.4<br>3.4              | 3.4     | 4.7 |
|          |                   |                |               | Middle    | 4   | 28.7<br>28.7     | 28.7    | 8.3<br>8.3 | 8.3     | 30.2<br>30.2 | 30.2    | 98.3<br>95.4      | 96.9    | 6.4<br>6.2              | 6.3     |     | 0.5<br>0.5     | 0.5     |     | 6.1<br>6.2              | 6.2     |     |
|          |                   |                |               | Bottom    | 7   | 28.1<br>28.4     | 28.3    | 8.2<br>8.3 | 8.3     | 32.1<br>31.3 | 31.7    | 78.2<br>82.9      | 80.6    | 5.1<br>5.4              | 5.3     |     | 1.4<br>1.5     | 1.5     |     | 4.3<br>4.5              | 4.4     |     |
| G2       | Rainy             | Calm           | 11:31         | Surface   | 1   | 28.8<br>28.8     | 28.8    | 8.3<br>8.3 | 8.3     | 29.6<br>29.5 | 29.6    | 110.3<br>110.2    | 110.3   | 7.2<br>7.2              | 7.2     | 6.5 | 0.5<br>0.5     | 0.5     | 0.7 | 2.1<br>2.1              | 2.1     | 3.5 |
|          |                   |                |               | Middle    | 5   | 28.2<br>28.3     | 28.3    | 8.3<br>8.3 | 8.3     | 31.6<br>31.4 | 31.5    | 85.3<br>86.3      | 85.8    | 5.6<br>5.7              | 5.7     |     | 0.7<br>0.7     | 0.7     |     | 3.7<br>3.8              | 3.8     |     |
|          |                   |                |               | Bottom    | 9   | 28.0<br>28.1     | 28.1    | 8.3<br>8.3 | 8.3     | 32.5<br>32.4 | 32.5    | 84.1<br>83.9      | 84.0    | 5.5<br>5.5              | 5.5     |     | 1.0<br>1.0     | 1.0     |     | 4.5<br>4.6              | 4.6     |     |
| G3       | Rainy             | Calm           | 11:54         | Surface   | 1   | 28.9<br>28.9     | 28.9    | 8.3<br>8.3 | 8.3     | 29.2<br>29.2 | 29.2    | 116.0<br>114.6    | 115.3   | 7.6<br>7.5              | 7.6     | 7.2 | 0.5<br>0.5     | 0.5     | 0.7 | 5.1<br>5.1              | 5.1     | 4.3 |
|          |                   |                |               | Middle    | 4   | 28.7<br>28.7     | 28.7    | 8.3<br>8.3 | 8.3     | 30.0<br>30.1 | 30.1    | 103.5<br>100.7    | 102.1   | 6.8<br>6.6              | 6.7     |     | 0.7<br>0.7     | 0.7     |     | 5.2<br>5.3              | 5.3     |     |
|          |                   |                |               | Bottom    | 7   | 28.4<br>28.2     | 28.3    | 8.3<br>8.2 | 8.3     | 30.9<br>31.8 | 31.4    | 86.2<br>74.6      | 80.4    | 5.6<br>4.9              | 5.3     |     | 0.8<br>0.9     | 0.9     |     | 2.6<br>2.6              | 2.6     |     |
| G4       | Rainy             | Calm           | 12:09         | Surface   | 1   | 28.6<br>28.6     | 28.6    | 8.3<br>8.3 | 8.3     | 29.3<br>29.5 | 29.4    | 115.7<br>112.7    | 114.2   | 7.6<br>7.4              | 7.5     | 6.9 | 0.5<br>0.5     | 0.5     | 2.1 | 4.8<br>4.8              | 4.8     | 4.6 |
|          |                   |                |               | Middle    | 4.5 | 28.7<br>28.6     | 28.7    | 8.3<br>8.3 | 8.3     | 30.3<br>30.6 | 30.5    | 97.5<br>92.2      | 95.2    | 6.4<br>6.1              | 6.3     |     | 0.7<br>0.7     | 0.7     |     | 5.0<br>5.0              | 5.0     |     |
|          |                   |                |               | Bottom    | 8   | 28.1<br>28.2     | 28.2    | 8.2<br>8.2 | 8.2     | 32.0<br>31.7 | 31.9    | 69.2<br>69.0      | 69.1    | 4.5<br>4.5              | 4.5     |     | 5.2<br>5.2     | 5.2     |     | 3.8<br>3.9              | 3.9     |     |
| M1       | Rainy             | Calm           | 11:42         | Surface   | 1   | 28.8<br>28.8     | 28.8    | 8.3<br>8.3 | 8.3     | 29.6<br>29.7 | 29.7    | 109.3<br>106.3    | 107.8   | 7.2<br>7.0              | 7.1     | 6.7 | 0.5<br>0.5     | 0.5     | 0.5 | 2.0<br>2.0              | 2.0     | 4.1 |
|          |                   |                |               | Middle    | 3   | 28.7<br>28.7     | 28.7    | 8.3<br>8.3 | 8.3     | 30.2<br>30.2 | 30.2    | 92.9<br>96.6      | 94.8    | 6.1<br>6.3              | 6.2     |     | 0.5<br>0.5     | 0.5     |     | 5.1<br>5.1              | 5.1     |     |
|          |                   |                |               | Bottom    | 5   | 28.6<br>28.6     | 28.6    | 8.2<br>8.3 | 8.3     | 30.5<br>30.4 | 30.5    | 90.6<br>91.9      | 91.3    | 5.9<br>6.0              | 6.0     |     | 0.5<br>0.5     | 0.5     |     | 5.3<br>5.3              | 5.3     |     |
| M2       | Rainy             | Calm           | 11:21         | Surface   | 1   | 28.8<br>28.7     | 28.8    | 8.3<br>8.3 | 8.3     | 29.6<br>29.9 | 29.8    | 109.5<br>106.4    | 108.0   | 7.2<br>7.0              | 7.1     | 6.4 | 0.5<br>0.5     | 0.5     | 1.1 | 4.5<br>4.4              | 4.5     | 3.7 |
|          |                   |                |               | Middle    | 6   | 28.1<br>28.1     | 28.1    | 8.3<br>8.3 | 8.3     | 32.2<br>32.2 | 32.2    | 87.0<br>85.3      | 86.2    | 5.7<br>5.6              | 5.7     |     | 0.9<br>0.9     | 0.9     |     | 4.0<br>3.9              | 4.0     |     |
|          |                   |                |               | Bottom    | 11  | 28.0<br>27.9     | 28.0    | 8.3<br>8.2 | 8.3     | 32.7<br>32.8 | 32.8    | 83.8<br>81.6      | 82.7    | 5.5<br>5.3              | 5.4     |     | 1.9<br>2.0     | 2.0     |     | 2.6<br>2.5              | 2.6     |     |
| M3       | Rainy             | Calm           | 12:02         | Surface   | 1   | 28.8<br>28.8     | 28.8    | 8.3<br>8.3 | 8.3     | 29.2<br>29.2 | 29.2    | 119.5<br>116.3    | 117.9   | 7.8<br>7.6              | 7.7     | 7.2 | 0.5<br>0.5     | 0.5     | 0.6 | 5.7<br>5.7              | 5.7     | 5.3 |
|          |                   |                |               | Middle    | 4   | 28.6<br>28.7     | 28.7    | 8.3<br>8.3 | 8.3     | 30.2<br>29.8 | 30.0    | 98.2<br>103.0     | 100.6   | 6.4<br>6.8              | 6.6     |     | 0.5<br>0.5     | 0.5     |     | 4.9<br>4.9              | 4.9     |     |
|          |                   |                |               | Bottom    | 7   | 28.3<br>28.3     | 28.3    | 8.3<br>8.2 | 8.3     | 31.3<br>31.5 | 31.4    | 87.9<br>82.4      | 85.2    | 5.8<br>5.4              | 5.6     |     | 0.7<br>0.7     | 0.7     |     | 5.2<br>5.2              | 5.2     |     |
| M4       | Rainy             | Calm           | 11:14         | Surface   | 1   | 28.8<br>28.7     | 28.8    | 8.3<br>8.2 | 8.3     | 29.5<br>29.7 | 29.6    | 99.7<br>98.1      | 98.9    | 6.5<br>6.4              | 6.5     | 6.4 | 0.6<br>0.6     | 0.6     | 0.8 | 5.3<br>5.4              | 5.4     | 4.8 |
|          |                   |                |               | Middle    | 4   | 28.6<br>28.5     | 28.6    | 8.3<br>8.3 | 8.3     | 30.3<br>30.8 | 30.6    | 95.5<br>92.0      | 93.8    | 6.3<br>6.0              | 6.2     |     | 0.5<br>0.5     | 0.5     |     | 4.0<br>4.1              | 4.1     |     |
|          |                   |                |               | Bottom    | 7   | 28.2<br>28.4     | 28.3    | 8.2<br>8.3 | 8.3     | 31.8<br>31.3 | 31.6    | 82.0<br>85.2      | 83.6    | 5.4<br>5.6              | 5.5     |     | 1.3<br>1.3     | 1.3     |     | 4.9<br>4.7              | 4.8     |     |
| M5       | Rainy             | Calm           | 12:22         | Surface   | 1   | 28.7<br>28.7     | 28.7    | 8.3<br>8.3 | 8.3     | 29.6<br>29.6 | 29.6    | 97.5<br>97.2      | 97.4    | 6.4<br>6.4              | 6.4     | 6.0 | 0.6<br>0.6     | 0.6     | 1.7 | 4.0<br>3.9              | 4.0     | 3.9 |
|          |                   |                |               | Middle    | 5.5 | 28.1<br>28.4     | 28.3    | 8.3<br>8.3 | 8.3     | 32.4<br>32.2 | 32.3    | 85.3<br>86.4      | 85.9    | 5.6<br>5.6              | 5.6     |     | 1.0<br>1.0     | 1.0     |     | 4.1<br>4.2              | 4.2     |     |
|          |                   |                |               | Bottom    | 10  | 27.9<br>27.8     | 27.9    | 8.2<br>8.2 | 8.2     | 32.9<br>33.0 | 33.0    | 81.3<br>79.9      | 80.6    | 5.3<br>5.2              | 5.3     |     | 3.3<br>3.8     | 3.6     |     | 3.4<br>3.4              | 3.4     |     |
| M6       | Rainy             | Calm           | 12:14         | Surface   | -   | -                | -       | -          | -       | -            | -       | -                 | -       | -                       | -       | 6.4 | -              | -       | 1.0 | -                       | -       | 4.7 |
|          |                   |                |               | Middle    | 2   | 28.7<br>28.7     | 28.7    | 8.3<br>8.3 | 8.3     | 30.3<br>30.3 | 30.3    | 98.3<br>98.0      | 98.2    | 6.4<br>6.4              | 6.4     |     | 1.0<br>1.0     | 1.0     |     | 4.6<br>4.7              | 4.7     |     |
|          |                   |                |               | Bottom    | -   | -                | -       | -          | -       | -            | -       | -                 | -       | -                       | -       |     | -              | -       |     | -                       | -       |     |

Remarks: \*DA: Depth-Averaged  
\*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

**Appendix I - Action and Limit Levels for Marine Water Quality on 23 June 2018 (Mid-Ebb Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 5.2 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 5.6 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 5.9 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.4 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 5.9 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.4 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 5.2 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 5.6 mg/L</u>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction**  
**Water Quality Monitoring Results on 23 June 2018**

**(Mid-Ebb Tide)**

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) |     | Temperature (°C) |         | pH         |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         |     | Turbidity (NTU) |         |     | Suspended Solids (mg/L) |         |     |
|----------|-------------------|-----------------|---------------|-----------|-----|------------------|---------|------------|---------|--------------|---------|-------------------|---------|-------------------------|---------|-----|-----------------|---------|-----|-------------------------|---------|-----|
|          |                   |                 |               |           |     | Value            | Average | Value      | Average | Value        | Average | Value             | Average | Value                   | Average | DA* | Value           | Average | DA* | Value                   | Average | DA* |
| C1       | Rainy             | Moderate        | 09:28         | Surface   | 1   | 28.1<br>28.1     | 28.1    | 8.1<br>8.1 | 8.1     | 29.7<br>29.8 | 29.8    | 83.5<br>83.0      | 83.3    | 5.5<br>5.5              | 5.5     | 5.2 | 1.2<br>1.2      | 1.2     | 1.6 | 5.3<br>5.6              | 5.5     | 4.7 |
|          |                   |                 |               | Middle    | 9   | 26.7<br>26.9     | 26.8    | 8.1<br>8.2 | 8.2     | 33.2<br>32.8 | 33.0    | 72.6<br>73.2      | 72.9    | 4.8<br>4.9              | 4.9     | 5.2 | 1.8<br>1.5      | 1.7     |     | 5.5<br>5.3              | 5.4     |     |
|          |                   |                 |               | Bottom    | 17  | 26.4<br>26.5     | 26.5    | 8.1<br>8.1 | 8.1     | 33.5<br>33.4 | 33.5    | 70.0<br>71.3      | 70.7    | 4.7<br>4.8              | 4.8     | 4.8 | 2.0<br>1.8      | 1.9     |     | 3.1<br>3.2              | 3.2     |     |
| C2       | Rainy             | Moderate        | 08:05         | Surface   | 1   | 28.7<br>28.7     | 28.7    | 8.1<br>8.1 | 8.1     | 26.7<br>26.7 | 26.7    | 89.8<br>88.2      | 89.0    | 6.0<br>5.9              | 6.0     | 5.3 | 0.7<br>0.7      | 0.7     | 3.1 | 5.0<br>4.8              | 4.9     | 4.0 |
|          |                   |                 |               | Middle    | 17  | 26.3<br>26.2     | 26.3    | 8.1<br>8.1 | 8.1     | 33.5<br>33.5 | 33.5    | 67.5<br>66.9      | 67.2    | 4.5<br>4.5              | 4.5     | 5.3 | 4.1<br>4.2      | 4.2     |     | 2.8<br>2.8              | 2.8     |     |
|          |                   |                 |               | Bottom    | 33  | 26.3<br>26.2     | 26.3    | 8.1<br>8.1 | 8.1     | 33.5<br>33.6 | 33.6    | 67.5<br>66.5      | 67.0    | 4.5<br>4.5              | 4.5     | 4.5 | 4.2<br>4.4      | 4.3     |     | 4.2<br>4.2              | 4.3     |     |
| G1       | Rainy             | Moderate        | 08:48         | Surface   | 1   | 28.6<br>28.5     | 28.6    | 8.2<br>8.2 | 8.2     | 28.9<br>29.3 | 29.1    | 97.9<br>93.1      | 95.5    | 6.5<br>6.1              | 6.3     | 5.7 | 0.4<br>0.4      | 0.4     | 1.1 | 4.8<br>4.8              | 4.8     | 4.1 |
|          |                   |                 |               | Middle    | 4   | 28.3<br>28.2     | 28.3    | 8.2<br>8.2 | 8.2     | 30.3<br>30.9 | 30.6    | 79.4<br>73.3      | 76.4    | 5.2<br>4.8              | 5.0     | 5.7 | 0.9<br>0.9      | 0.9     |     | 3.3<br>3.3              | 3.3     |     |
|          |                   |                 |               | Bottom    | 7   | 28.0<br>28.0     | 28.0    | 8.2<br>8.2 | 8.2     | 32.0<br>31.7 | 31.9    | 64.7<br>66.1      | 65.4    | 4.2<br>4.3              | 4.3     | 4.3 | 2.1<br>1.9      | 2.0     |     | 4.1<br>4.2              | 4.2     |     |
| G2       | Rainy             | Moderate        | 08:28         | Surface   | 1   | 28.3<br>28.5     | 28.4    | 8.2<br>8.2 | 8.2     | 29.0<br>29.3 | 29.2    | 96.3<br>98.6      | 97.5    | 6.4<br>6.5              | 6.5     | 6.1 | 0.5<br>0.5      | 0.5     | 1.3 | 4.2<br>4.1              | 4.2     | 4.3 |
|          |                   |                 |               | Middle    | 5   | 28.1<br>28.5     | 28.3    | 8.2<br>8.2 | 8.2     | 30.8<br>29.6 | 30.2    | 77.2<br>91.8      | 84.5    | 5.1<br>6.1              | 5.6     | 6.1 | 1.0<br>0.9      | 1.0     |     | 4.2<br>4.2              | 4.2     |     |
|          |                   |                 |               | Bottom    | 9   | 27.2<br>28.0     | 27.6    | 8.2<br>8.2 | 8.2     | 33.1<br>31.8 | 32.5    | 66.5<br>71.3      | 68.9    | 4.4<br>4.7              | 4.6     | 4.6 | 2.1<br>2.4      | 2.3     |     | 4.5<br>4.5              | 4.5     |     |
| G3       | Rainy             | Moderate        | 08:52         | Surface   | 1   | 28.6<br>28.6     | 28.6    | 8.2<br>8.2 | 8.2     | 29.2<br>29.1 | 29.2    | 95.8<br>99.9      | 97.9    | 6.3<br>6.6              | 6.5     | 5.7 | 0.4<br>0.4      | 0.4     | 1.1 | 4.2<br>4.1              | 4.2     | 4.2 |
|          |                   |                 |               | Middle    | 4   | 28.1<br>28.2     | 28.2    | 8.2<br>8.2 | 8.2     | 30.9<br>30.8 | 30.9    | 74.1<br>73.8      | 74.0    | 4.9<br>4.9              | 4.9     | 5.7 | 0.9<br>0.8      | 0.9     |     | 4.2<br>4.3              | 4.3     |     |
|          |                   |                 |               | Bottom    | 7   | 27.8<br>27.9     | 27.9    | 8.1<br>8.1 | 8.1     | 32.1<br>32.0 | 32.1    | 65.6<br>65.8      | 65.7    | 4.3<br>4.3              | 4.3     | 4.3 | 2.0<br>2.0      | 2.0     |     | 4.2<br>4.2              | 4.2     |     |
| G4       | Rainy             | Moderate        | 09:05         | Surface   | 1   | 28.5<br>28.5     | 28.5    | 8.3<br>8.2 | 8.3     | 29.1<br>31.2 | 30.2    | 103.5<br>98.7     | 101.1   | 6.8<br>6.5              | 6.7     | 6.2 | 0.6<br>0.6      | 0.6     | 1.2 | 3.0<br>3.0              | 3.0     | 3.5 |
|          |                   |                 |               | Middle    | 4   | 27.9<br>28.4     | 28.2    | 8.2<br>8.2 | 8.2     | 31.1<br>29.7 | 30.4    | 77.5<br>92.7      | 85.1    | 5.1<br>6.1              | 5.6     | 6.2 | 0.8<br>0.8      | 0.8     |     | 3.7<br>3.7              | 3.7     |     |
|          |                   |                 |               | Bottom    | 7   | 27.6<br>28.1     | 27.9    | 8.2<br>8.2 | 8.2     | 32.3<br>31.6 | 32.0    | 66.3<br>72.1      | 69.2    | 4.4<br>4.7              | 4.6     | 4.6 | 2.1<br>2.2      | 2.2     |     | 4.0<br>3.8              | 3.9     |     |
| M1       | Rainy             | Moderate        | 08:39         | Surface   | 1   | 28.5<br>28.5     | 28.5    | 8.2<br>8.2 | 8.2     | 29.3<br>29.3 | 29.3    | 98.3<br>96.6      | 97.5    | 6.5<br>6.4              | 6.5     | 6.2 | 0.5<br>0.5      | 0.5     | 1.1 | 2.8<br>2.9              | 2.9     | 3.6 |
|          |                   |                 |               | Middle    | 3   | 28.3<br>28.4     | 28.4    | 8.2<br>8.2 | 8.2     | 30.4<br>29.6 | 30.0    | 79.8<br>93.4      | 86.6    | 5.3<br>6.2              | 5.8     | 6.2 | 0.8<br>0.8      | 0.8     |     | 3.3<br>3.3              | 3.3     |     |
|          |                   |                 |               | Bottom    | 5   | 27.9<br>28.0     | 28.0    | 8.2<br>8.2 | 8.2     | 32.1<br>32.3 | 32.2    | 68.6<br>70.4      | 69.5    | 4.5<br>4.6              | 4.6     | 4.6 | 1.7<br>2.0      | 1.9     |     | 4.7<br>4.7              | 4.7     |     |
| M2       | Rainy             | Moderate        | 08:21         | Surface   | 1   | 28.3<br>28.3     | 28.3    | 8.2<br>8.2 | 8.2     | 28.9<br>28.8 | 28.9    | 99.0<br>96.8      | 97.9    | 6.6<br>6.4              | 6.5     | 6.0 | 0.5<br>0.5      | 0.5     | 1.3 | 3.0<br>2.9              | 3.0     | 3.5 |
|          |                   |                 |               | Middle    | 6   | 27.9<br>27.8     | 27.9    | 8.2<br>8.2 | 8.2     | 32.4<br>32.4 | 32.4    | 84.5<br>82.5      | 83.5    | 5.5<br>5.4              | 5.5     | 6.0 | 1.4<br>1.6      | 1.5     |     | 3.9<br>4.0              | 4.0     |     |
|          |                   |                 |               | Bottom    | 11  | 27.1<br>26.8     | 27.0    | 8.1<br>8.1 | 8.1     | 33.2<br>33.4 | 33.3    | 69.9<br>64.1      | 67.0    | 4.6<br>4.3              | 4.5     | 4.5 | 1.8<br>1.8      | 1.8     |     | 3.5<br>3.6              | 3.6     |     |
| M3       | Rainy             | Moderate        | 08:59         | Surface   | 1   | 28.6<br>28.4     | 28.5    | 8.3<br>8.3 | 8.3     | 29.1<br>29.1 | 29.1    | 105.8<br>103.6    | 104.7   | 7.0<br>6.9              | 7.0     | 6.5 | 0.4<br>0.4      | 0.4     | 1.2 | 3.5<br>3.5              | 3.5     | 5.3 |
|          |                   |                 |               | Middle    | 4   | 27.9<br>27.4     | 27.7    | 8.2<br>8.2 | 8.2     | 31.2<br>31.2 | 31.2    | 88.0<br>89.4      | 88.7    | 5.8<br>5.9              | 5.9     | 6.5 | 1.0<br>0.9      | 1.0     |     | 7.3<br>7.5              | 7.4     |     |
|          |                   |                 |               | Bottom    | 7   | 27.7<br>27.5     | 27.6    | 8.1<br>8.2 | 8.2     | 32.5<br>32.4 | 32.5    | 67.6<br>70.0      | 68.8    | 4.4<br>4.6              | 4.5     | 4.5 | 2.1<br>2.3      | 2.2     |     | 5.1<br>5.0              | 5.1     |     |
| M4       | Rainy             | Moderate        | 08:14         | Surface   | 1   | 28.4<br>28.4     | 28.4    | 8.2<br>8.2 | 8.2     | 28.9<br>29.0 | 29.0    | 94.1<br>93.5      | 93.8    | 6.2<br>6.2              | 6.2     | 6.0 | 0.5<br>0.5      | 0.5     | 1.0 | 3.0<br>3.0              | 3.0     | 3.4 |
|          |                   |                 |               | Middle    | 5   | 28.3<br>28.3     | 28.3    | 8.2<br>8.2 | 8.2     | 30.5<br>30.1 | 30.3    | 84.2<br>89.3      | 86.8    | 5.5<br>5.9              | 5.7     | 6.0 | 0.7<br>0.7      | 0.7     |     | 2.6<br>2.5              | 2.6     |     |
|          |                   |                 |               | Bottom    | 9   | 27.1<br>27.2     | 27.2    | 8.2<br>8.2 | 8.2     | 32.9<br>33.0 | 33.0    | 67.2<br>68.1      | 67.7    | 4.4<br>4.5              | 4.5     | 4.5 | 1.8<br>1.9      | 1.9     |     | 4.6<br>4.5              | 4.6     |     |
| M5       | Rainy             | Moderate        | 09:18         | Surface   | 1   | 28.3<br>28.3     | 28.3    | 8.2<br>8.2 | 8.2     | 29.5<br>29.5 | 29.5    | 85.9<br>84.2      | 85.1    | 5.7<br>5.6              | 5.7     | 5.4 | 0.8<br>0.8      | 0.8     | 2.2 | 4.6<br>4.6              | 4.6     | 4.2 |
|          |                   |                 |               | Middle    | 6   | 27.7<br>27.9     | 27.8    | 8.2<br>8.2 | 8.2     | 31.4<br>30.9 | 31.2    | 76.1<br>79.2      | 77.7    | 5.0<br>5.2              | 5.1     | 5.4 | 1.3<br>1.2      | 1.3     |     | 4.7<br>4.7              | 4.7     |     |
|          |                   |                 |               | Bottom    | 11  | 26.6<br>26.8     | 26.7    | 8.1<br>8.2 | 8.2     | 33.5<br>33.3 | 33.4    | 66.5<br>67.6      | 67.1    | 4.4<br>4.5              | 4.5     | 4.5 | 4.6<br>4.4      | 4.5     |     | 3.2<br>3.2              | 3.2     |     |
| M6       | Rainy             | Moderate        | 09:10         | Surface   | -   | -                | -       | -          | -       | -            | -       | -                 | -       | -                       | -       | -   | -               | -       | 0.4 | -                       | -       | 3.3 |
|          |                   |                 |               | Middle    | 2.3 | 28.6<br>28.6     | 28.6    | 8.3<br>8.3 | 8.3     | 29.1<br>29.1 | 29.1    | 108.0<br>108.4    | 108.2   | 7.1<br>7.2              | 7.2     | 7.2 | 0.4<br>0.4      | 0.4     |     | 3.2<br>3.3              | 3.3     |     |
|          |                   |                 |               | Bottom    | -   | -                | -       | -          | -       | -            | -       | -                 | -       | -                       | -       | -   | -               | -       |     | -                       | -       |     |

Remarks: \*DA: Depth-Averaged  
 \*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough: White capped or rougher.

**Appendix I - Action and Limit Levels for Marine Water Quality on 23 June 2018 (Mid-Flood Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 8.2 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 8.8 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.2 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.8 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.2 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.8 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.0 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.5 mg/L</u>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction**  
**Water Quality Monitoring Results on 23 June 2018**

**(Mid-Flood Tide)**

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) |     | Temperature (°C) |         | pH         |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         |     | Turbidity (NTU) |         |     | Suspended Solids (mg/L) |         |     |
|----------|-------------------|-----------------|---------------|-----------|-----|------------------|---------|------------|---------|--------------|---------|-------------------|---------|-------------------------|---------|-----|-----------------|---------|-----|-------------------------|---------|-----|
|          |                   |                 |               |           |     | Value            | Average | Value      | Average | Value        | Average | Value             | Average | Value                   | Average | DA* | Value           | Average | DA* | Value                   | Average | DA* |
| C1       | Rainy             | Moderate        | 15:38         | Surface   | 1   | 28.3<br>28.3     | 28.3    | 8.2<br>8.2 | 8.2     | 28.7<br>28.7 | 28.7    | 97.9<br>96.4      | 97.2    | 6.5<br>6.4              | 6.5     | 5.8 | 1.0<br>1.0      | 1.0     | 3.2 | 5.3<br>5.4              | 5.4     | 7.2 |
|          |                   |                 |               | Middle    | 9   | 27.2<br>27.0     | 27.1    | 8.2<br>8.1 | 8.2     | 32.5<br>32.5 | 32.5    | 76.8<br>73.9      | 75.4    | 5.1<br>4.9              | 5.0     |     | 1.7<br>1.7      | 1.7     |     | 10.6<br>10.5            | 10.6    |     |
|          |                   |                 |               | Bottom    | 17  | 25.8<br>25.8     | 25.8    | 8.1<br>8.1 | 8.1     | 33.7<br>33.6 | 33.7    | 66.7<br>66.1      | 66.4    | 4.5<br>4.5              | 4.5     |     | 6.8<br>6.7      | 6.8     |     | 5.5<br>5.6              | 5.6     |     |
| C2       | Rainy             | Moderate        | 14:15         | Surface   | 1   | 28.6<br>28.6     | 28.6    | 8.1<br>8.1 | 8.1     | 27.1<br>27.1 | 27.1    | 80.5<br>80.7      | 80.6    | 5.4<br>5.4              | 5.4     | 5.1 | 1.4<br>1.3      | 1.4     | 2.9 | 4.6<br>4.6              | 4.6     | 5.2 |
|          |                   |                 |               | Middle    | 16  | 27.1<br>27.1     | 27.1    | 8.1<br>8.1 | 8.1     | 33.0<br>33.0 | 33.0    | 73.2<br>73.0      | 73.1    | 4.8<br>4.8              | 4.8     |     | 2.0<br>2.0      | 2.0     |     | 4.7<br>4.7              | 4.7     |     |
|          |                   |                 |               | Bottom    | 31  | 26.4<br>26.4     | 26.4    | 8.1<br>8.1 | 8.1     | 33.3<br>33.3 | 33.3    | 67.0<br>66.9      | 67.0    | 4.5<br>4.5              | 4.5     |     | 5.5<br>5.1      | 5.3     |     | 6.2<br>6.3              | 6.3     |     |
| G1       | Rainy             | Moderate        | 14:54         | Surface   | 1   | 28.3<br>28.3     | 28.3    | 8.2<br>8.2 | 8.2     | 29.6<br>29.6 | 29.6    | 92.8<br>90.3      | 91.6    | 6.1<br>6.0              | 6.1     | 5.9 | 0.8<br>0.8      | 0.8     | 2.0 | 4.7<br>4.6              | 4.7     | 5.9 |
|          |                   |                 |               | Middle    | 4   | 28.1<br>28.0     | 28.1    | 8.2<br>8.2 | 8.2     | 30.3<br>30.4 | 30.4    | 86.1<br>84.3      | 85.2    | 5.7<br>5.6              | 5.7     |     | 1.3<br>1.4      | 1.4     |     | 6.7<br>6.9              | 6.8     |     |
|          |                   |                 |               | Bottom    | 7   | 27.2<br>27.2     | 27.2    | 8.1<br>8.1 | 8.1     | 33.2<br>33.2 | 33.2    | 66.8<br>67.0      | 66.9    | 4.4<br>4.4              | 4.4     |     | 3.7<br>4.0      | 3.9     |     | 6.2<br>6.0              | 6.1     |     |
| G2       | Rainy             | Moderate        | 14:40         | Surface   | 1   | 28.2<br>28.2     | 28.2    | 8.2<br>8.2 | 8.2     | 29.2<br>29.2 | 29.2    | 93.8<br>90.7      | 92.3    | 6.2<br>6.0              | 6.1     | 5.6 | 1.2<br>1.2      | 1.2     | 2.3 | 5.1<br>5.1              | 5.1     | 3.8 |
|          |                   |                 |               | Middle    | 5   | 27.8<br>27.5     | 27.7    | 8.2<br>8.2 | 8.2     | 31.4<br>32.4 | 31.9    | 78.7<br>75.1      | 76.9    | 5.2<br>5.0              | 5.1     |     | 1.2<br>1.1      | 1.2     |     | 2.5<br>2.4              | 2.5     |     |
|          |                   |                 |               | Bottom    | 9   | 26.5<br>26.5     | 26.5    | 8.1<br>8.1 | 8.1     | 33.4<br>33.4 | 33.4    | 65.7<br>64.8      | 65.3    | 4.4<br>4.3              | 4.4     |     | 4.5<br>4.6      | 4.6     |     | 3.9<br>3.9              | 3.9     |     |
| G3       | Rainy             | Moderate        | 15:01         | Surface   | 1   | 28.3<br>28.3     | 28.3    | 8.2<br>8.2 | 8.2     | 29.4<br>29.5 | 29.5    | 91.9<br>89.0      | 90.5    | 6.1<br>5.9              | 6.0     | 5.9 | 0.7<br>0.8      | 0.8     | 1.3 | 3.1<br>3.1              | 3.1     | 3.7 |
|          |                   |                 |               | Middle    | 4   | 28.3<br>28.2     | 28.3    | 8.2<br>8.2 | 8.2     | 29.8<br>29.9 | 29.9    | 86.0<br>86.0      | 86.0    | 5.7<br>5.7              | 5.7     |     | 1.0<br>0.9      | 1.0     |     | 3.9<br>3.9              | 3.9     |     |
|          |                   |                 |               | Bottom    | 7   | 27.8<br>27.8     | 27.8    | 8.2<br>8.1 | 8.2     | 32.3<br>32.3 | 32.3    | 65.0<br>64.9      | 65.0    | 4.3<br>4.3              | 4.3     |     | 2.3<br>2.0      | 2.2     |     | 4.2<br>4.2              | 4.2     |     |
| G4       | Rainy             | Moderate        | 15:15         | Surface   | 1   | 28.4<br>28.3     | 28.4    | 8.3<br>8.2 | 8.3     | 29.2<br>29.2 | 29.2    | 100.4<br>97.2     | 98.8    | 6.6<br>6.4              | 6.5     | 6.0 | 1.2<br>1.2      | 1.2     | 3.4 | 5.8<br>5.7              | 5.8     | 6.4 |
|          |                   |                 |               | Middle    | 4.5 | 27.4<br>27.4     | 27.4    | 8.1<br>8.2 | 8.2     | 31.6<br>31.5 | 31.6    | 82.4<br>83.3      | 82.9    | 5.5<br>5.5              | 5.5     |     | 1.7<br>1.7      | 1.7     |     | 6.7<br>6.8              | 6.8     |     |
|          |                   |                 |               | Bottom    | 8   | 27.0<br>26.9     | 27.0    | 8.1<br>8.1 | 8.1     | 33.3<br>33.4 | 33.4    | 71.1<br>66.2      | 68.7    | 4.7<br>4.4              | 4.6     |     | 7.2<br>7.1      | 7.2     |     | 6.9<br>6.3              | 6.6     |     |
| M1       | Rainy             | Moderate        | 14:47         | Surface   | 1   | 28.3<br>28.3     | 28.3    | 8.2<br>8.2 | 8.2     | 29.6<br>29.6 | 29.6    | 91.5<br>91.3      | 91.4    | 6.0<br>6.0              | 6.0     | 5.9 | 0.7<br>0.7      | 0.7     | 1.4 | 4.6<br>4.6              | 4.6     | 4.7 |
|          |                   |                 |               | Middle    | 3   | 28.3<br>28.3     | 28.3    | 8.2<br>8.2 | 8.2     | 29.9<br>29.9 | 29.9    | 88.2<br>88.2      | 88.2    | 5.8<br>5.8              | 5.8     |     | 0.8<br>0.8      | 0.8     |     | 5.2<br>5.1              | 5.2     |     |
|          |                   |                 |               | Bottom    | 5   | 27.8<br>27.6     | 27.8    | 8.2<br>8.2 | 8.2     | 32.1<br>32.1 | 32.1    | 68.0<br>65.4      | 66.7    | 4.5<br>4.3              | 4.4     |     | 2.9<br>2.5      | 2.7     |     | 4.3<br>4.5              | 4.4     |     |
| M2       | Rainy             | Moderate        | 14:33         | Surface   | 1   | 28.3<br>28.3     | 28.3    | 8.2<br>8.2 | 8.2     | 29.4<br>29.4 | 29.4    | 96.9<br>94.8      | 95.9    | 6.4<br>6.3              | 6.4     | 5.7 | 0.8<br>0.7      | 0.8     | 2.5 | 3.9<br>3.7              | 3.8     | 4.4 |
|          |                   |                 |               | Middle    | 6   | 27.2<br>27.3     | 27.3    | 8.2<br>8.2 | 8.2     | 33.1<br>33.0 | 33.1    | 76.4<br>74.4      | 75.4    | 5.0<br>4.9              | 5.0     |     | 2.0<br>2.1      | 2.1     |     | 5.1<br>5.1              | 5.1     |     |
|          |                   |                 |               | Bottom    | 11  | 26.3<br>26.4     | 26.4    | 8.1<br>8.1 | 8.1     | 33.5<br>33.5 | 33.5    | 68.7<br>68.1      | 68.4    | 4.6<br>4.6              | 4.6     |     | 4.6<br>4.7      | 4.7     |     | 4.4<br>4.4              | 4.4     |     |
| M3       | Rainy             | Moderate        | 15:07         | Surface   | 1   | 28.4<br>28.4     | 28.4    | 8.2<br>8.2 | 8.2     | 29.5<br>29.5 | 29.5    | 96.6<br>95.7      | 96.2    | 6.4<br>6.3              | 6.4     | 6.3 | 0.8<br>0.8      | 0.8     | 3.4 | 2.4<br>2.5              | 2.5     | 3.2 |
|          |                   |                 |               | Middle    | 4   | 28.2<br>28.1     | 28.2    | 8.2<br>8.2 | 8.2     | 30.1<br>30.3 | 30.2    | 91.2<br>92.0      | 91.6    | 6.0<br>6.1              | 6.1     |     | 1.9<br>2.1      | 2.0     |     | 3.8<br>3.9              | 3.9     |     |
|          |                   |                 |               | Bottom    | 7   | 27.1<br>27.0     | 27.1    | 8.1<br>8.1 | 8.1     | 33.3<br>33.3 | 33.3    | 65.9<br>67.5      | 66.7    | 4.4<br>4.5              | 4.5     |     | 7.9<br>7.0      | 7.5     |     | 3.3<br>3.3              | 3.3     |     |
| M4       | Rainy             | Moderate        | 14:25         | Surface   | 1   | 28.3<br>28.4     | 28.4    | 8.3<br>8.2 | 8.3     | 28.8<br>29.3 | 29.1    | 108.2<br>103.5    | 105.9   | 7.2<br>6.8              | 7.0     | 6.8 | 0.6<br>0.6      | 0.6     | 0.9 | 5.0<br>4.9              | 5.0     | 4.3 |
|          |                   |                 |               | Middle    | 5   | 28.4<br>28.3     | 28.4    | 8.2<br>8.2 | 8.2     | 29.3<br>29.8 | 29.6    | 102.3<br>91.8     | 97.1    | 6.8<br>6.1              | 6.5     |     | 0.6<br>0.6      | 0.6     |     | 3.9<br>3.8              | 3.9     |     |
|          |                   |                 |               | Bottom    | 9   | 27.8<br>27.8     | 27.8    | 8.1<br>8.2 | 8.2     | 31.4<br>31.4 | 31.4    | 73.0<br>74.9      | 74.0    | 4.8<br>4.9              | 4.9     |     | 1.4<br>1.4      | 1.4     |     | 4.0<br>4.0              | 4.0     |     |
| M5       | Rainy             | Moderate        | 15:30         | Surface   | 1   | 28.0<br>28.0     | 28.0    | 8.2<br>8.1 | 8.2     | 29.6<br>29.6 | 29.6    | 75.5<br>75.5      | 75.5    | 5.0<br>5.0              | 5.0     | 5.0 | 1.8<br>1.7      | 1.8     | 2.9 | 4.0<br>3.9              | 4.0     | 3.8 |
|          |                   |                 |               | Middle    | 5.5 | 27.8<br>27.4     | 27.6    | 8.2<br>8.1 | 8.2     | 30.7<br>31.5 | 31.1    | 76.4<br>72.3      | 74.4    | 5.1<br>4.8              | 5.0     |     | 3.0<br>3.1      | 3.1     |     | 4.5<br>4.5              | 4.5     |     |
|          |                   |                 |               | Bottom    | 10  | 26.4<br>26.7     | 26.6    | 8.1<br>8.1 | 8.1     | 33.3<br>32.8 | 33.1    | 65.4<br>66.6      | 66.0    | 4.4<br>4.4              | 4.4     |     | 3.6<br>3.7      | 3.7     |     | 2.9<br>2.9              | 2.9     |     |
| M6       | Rainy             | Moderate        | 15:22         | Surface   | -   | -                | -       | -          | -       | -            | -       | -                 | -       | -                       | 5.3     | -   | -               | 2.5     | -   | -                       | 4.1     |     |
|          |                   |                 |               | Middle    | 2.1 | 28.0<br>27.9     | 28.0    | 8.2<br>8.2 | 8.2     | 30.6<br>31.0 | 30.8    | 79.9<br>78.4      | 79.2    | 5.3<br>5.2              |         | 5.3 | 2.5<br>2.4      |         | 2.5 | 4.0<br>4.1              |         | 4.1 |
|          |                   |                 |               | Bottom    | -   | -                | -       | -          | -       | -            | -       | -                 | -       | -                       |         | -   | -               |         | -   | -                       |         | -   |

Remarks: \*DA: Depth-Averaged  
\*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough: White capped or rougher.



**Appendix I - Action and Limit Levels for Marine Water Quality on 25 June 2018 (Mid-Ebb Tide)**

| <b>Parameter<br/>(unit)</b>            | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|--|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)       | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|  | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|  | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|  | <b><u>Station M6</u></b>            |   |   |
|  | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|  | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 8.2 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 8.8 NTU</u> |
|  | <b><u>Station M6</u></b>            |   |   |
|  | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|  | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.2 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.8 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>           |                                     |   |   |
| Surface                                |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.2 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.8 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>    |                                     |   |   |
| Bottom                                 |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 7.0 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 7.5 mg/L</u>       |
| <b><u>Station M6</u></b>               |                                     |   |   |
| Intake Level                           | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction**  
**Water Quality Monitoring Results on 25 June 2018**

**(Mid-Ebb Tide)**

| Location | Weather Condition | Sea Condition* | Sampling Time | Depth (m) |      | Temperature (°C) |         | pH         |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         |     | Turbidity (NTU) |         |     | Suspended Solids (mg/L) |         |     |
|----------|-------------------|----------------|---------------|-----------|------|------------------|---------|------------|---------|--------------|---------|-------------------|---------|-------------------------|---------|-----|-----------------|---------|-----|-------------------------|---------|-----|
|          |                   |                |               |           |      | Value            | Average | Value      | Average | Value        | Average | Value             | Average | Value                   | Average | DA* | Value           | Average | DA* | Value                   | Average | DA* |
| C1       | Cloudy            | Moderate       | 11:29         | Surface   | 1    | 27.8<br>27.8     | 27.8    | 8.7<br>8.7 | 8.7     | 34.1<br>34.1 | 34.1    | 92.4<br>92.5      | 92.5    | 6.2<br>6.2              | 6.2     | 6.2 | 3.5<br>3.4      | 3.5     | 3.4 | 4.4<br>4.4              | 4.4     | 5.7 |
|          |                   |                |               | Middle    | 9    | 27.9<br>27.8     | 27.9    | 8.6<br>8.7 | 8.7     | 34.1<br>34.1 | 34.1    | 91.8<br>91.5      | 91.7    | 6.1<br>6.1              | 6.1     |     | 3.2<br>3.4      | 3.3     |     | 6.5<br>6.1              | 6.3     |     |
|          |                   |                |               | Bottom    | 17   | 27.8<br>27.9     | 27.9    | 8.7<br>8.8 | 8.8     | 34.1<br>34.1 | 34.1    | 91.1<br>91.1      | 91.1    | 6.1<br>6.1              | 6.1     |     | 3.4<br>3.2      | 3.3     |     | 6.5<br>6.2              | 6.4     |     |
| C2       | Cloudy            | Moderate       | 10:15         | Surface   | 1    | 27.8<br>27.8     | 27.8    | 8.2<br>8.1 | 8.2     | 33.7<br>33.7 | 33.7    | 85.0<br>85.0      | 85.0    | 5.7<br>5.7              | 5.7     | 5.7 | 3.1<br>3.2      | 3.2     | 4.7 | 5.2<br>5.1              | 5.2     | 5.4 |
|          |                   |                |               | Middle    | 16.5 | 28.0<br>28.0     | 28.0    | 8.2<br>8.3 | 8.3     | 34.0<br>34.0 | 34.0    | 86.0<br>85.9      | 86.0    | 5.7<br>5.7              | 5.7     |     | 4.1<br>4.0      | 4.1     |     | 5.0<br>5.1              | 5.1     |     |
|          |                   |                |               | Bottom    | 32   | 28.0<br>28.0     | 28.0    | 8.3<br>8.3 | 8.3     | 34.0<br>34.0 | 34.0    | 84.9<br>84.9      | 84.9    | 5.7<br>5.7              | 5.7     |     | 6.9<br>6.7      | 6.8     |     | 5.7<br>5.8              | 5.8     |     |
| G1       | Cloudy            | Moderate       | 10:49         | Surface   | 1    | 27.7<br>27.7     | 27.7    | 8.5<br>8.6 | 8.6     | 34.0<br>34.0 | 34.0    | 85.4<br>86.8      | 86.1    | 5.7<br>5.8              | 5.8     | 5.8 | 4.1<br>3.5      | 3.8     | 3.7 | 5.4<br>5.2              | 5.3     | 5.2 |
|          |                   |                |               | Middle    | 4    | 27.7<br>27.7     | 27.7    | 8.5<br>8.6 | 8.6     | 34.0<br>34.0 | 34.0    | 85.2<br>86.1      | 85.7    | 5.7<br>5.8              | 5.8     |     | 3.9<br>3.4      | 3.7     |     | 5.6<br>5.6              | 5.6     |     |
|          |                   |                |               | Bottom    | 7    | 27.7<br>27.7     | 27.7    | 8.5<br>8.7 | 8.6     | 34.0<br>34.0 | 34.0    | 84.8<br>86.1      | 85.5    | 5.7<br>5.8              | 5.8     |     | 3.8<br>3.5      | 3.7     |     | 4.6<br>4.7              | 4.7     |     |
| G2       | Cloudy            | Moderate       | 10:37         | Surface   | 1    | 27.9<br>27.9     | 27.9    | 8.4<br>8.5 | 8.5     | 34.1<br>34.1 | 34.1    | 89.5<br>89.9      | 89.7    | 6.0<br>6.0              | 6.0     | 6.0 | 3.8<br>3.9      | 3.9     | 3.8 | 4.6<br>4.7              | 4.7     | 5.4 |
|          |                   |                |               | Middle    | 5    | 27.9<br>27.9     | 27.9    | 8.4<br>8.6 | 8.5     | 34.1<br>34.1 | 34.1    | 89.2<br>89.5      | 89.4    | 6.0<br>6.0              | 6.0     |     | 3.8<br>3.5      | 3.7     |     | 5.5<br>5.6              | 5.6     |     |
|          |                   |                |               | Bottom    | 9    | 27.9<br>27.9     | 27.9    | 8.5<br>8.6 | 8.6     | 34.1<br>34.1 | 34.1    | 88.4<br>88.8      | 88.6    | 5.9<br>5.9              | 5.9     |     | 4.0<br>3.8      | 3.9     |     | 5.9<br>6.0              | 6.0     |     |
| G3       | Cloudy            | Moderate       | 10:56         | Surface   | 1    | 27.9<br>27.9     | 27.9    | 8.4<br>8.5 | 8.5     | 33.9<br>34.0 | 34.0    | 85.5<br>84.8      | 85.2    | 5.7<br>5.7              | 5.7     | 5.7 | 5.4<br>5.5      | 5.5     | 6.5 | 4.5<br>4.5              | 4.5     | 5.2 |
|          |                   |                |               | Middle    | 4    | 27.9<br>27.9     | 27.9    | 8.2<br>8.6 | 8.4     | 34.0<br>34.0 | 34.0    | 83.9<br>83.5      | 83.7    | 5.6<br>5.6              | 5.6     |     | 6.1<br>6.8      | 6.5     |     | 6.4<br>6.4              | 6.4     |     |
|          |                   |                |               | Bottom    | 7    | 27.9<br>27.9     | 27.9    | 8.4<br>8.6 | 8.5     | 34.0<br>34.0 | 34.0    | 82.1<br>82.2      | 82.2    | 5.5<br>5.5              | 5.5     |     | 7.6<br>7.3      | 7.5     |     | 4.8<br>4.8              | 4.8     |     |
| G4       | Cloudy            | Moderate       | 11:08         | Surface   | 1    | 27.8<br>27.8     | 27.8    | 8.6<br>8.6 | 8.6     | 33.9<br>33.9 | 33.9    | 83.7<br>84.3      | 84.0    | 5.6<br>5.6              | 5.6     | 5.7 | 4.2<br>4.3      | 4.3     | 4.6 | 5.2<br>5.3              | 5.3     | 5.7 |
|          |                   |                |               | Middle    | 4.5  | 27.8<br>27.8     | 27.8    | 8.4<br>8.7 | 8.6     | 34.0<br>34.0 | 34.0    | 83.4<br>84.5      | 84.0    | 5.6<br>5.7              | 5.7     |     | 4.2<br>4.4      | 4.3     |     | 5.3<br>5.4              | 5.4     |     |
|          |                   |                |               | Bottom    | 8    | 27.8<br>27.8     | 27.8    | 8.5<br>8.7 | 8.6     | 34.0<br>34.0 | 34.0    | 83.6<br>83.6      | 83.6    | 5.6<br>5.6              | 5.6     |     | 5.2<br>5.3      | 5.3     |     | 6.4<br>6.3              | 6.4     |     |
| M1       | Cloudy            | Moderate       | 10:42         | Surface   | 1    | 27.7<br>27.7     | 27.7    | 8.6<br>8.5 | 8.6     | 34.0<br>34.0 | 34.0    | 84.4<br>83.9      | 84.2    | 5.6<br>5.6              | 5.6     | 5.6 | 5.0<br>5.1      | 5.1     | 5.1 | 4.4<br>4.4              | 4.4     | 5.1 |
|          |                   |                |               | Middle    | 3    | 27.7<br>27.7     | 27.7    | 8.4<br>8.5 | 8.5     | 34.0<br>34.0 | 34.0    | 83.8<br>83.8      | 83.8    | 5.6<br>5.6              | 5.6     |     | 5.1<br>5.0      | 5.1     |     | 5.0<br>5.0              | 5.0     |     |
|          |                   |                |               | Bottom    | 5    | 27.7<br>27.7     | 27.7    | 8.4<br>8.6 | 8.5     | 34.0<br>34.0 | 34.0    | 83.4<br>83.7      | 83.6    | 5.6<br>5.6              | 5.6     |     | 5.0<br>4.9      | 5.0     |     | 5.8<br>5.9              | 5.9     |     |
| M2       | Cloudy            | Moderate       | 10:31         | Surface   | 1    | 27.8<br>27.9     | 27.9    | 8.0<br>8.2 | 8.1     | 34.1<br>34.1 | 34.1    | 88.9<br>89.1      | 89.0    | 5.9<br>5.9              | 5.9     | 5.9 | 4.6<br>3.8      | 4.2     | 4.1 | 4.9<br>5.0              | 5.0     | 4.8 |
|          |                   |                |               | Middle    | 6    | 27.8<br>27.8     | 27.8    | 8.0<br>8.3 | 8.2     | 34.1<br>34.1 | 34.1    | 88.4<br>88.4      | 88.4    | 5.9<br>5.9              | 5.9     |     | 4.0<br>3.9      | 4.0     |     | 4.7<br>4.7              | 4.7     |     |
|          |                   |                |               | Bottom    | 11   | 27.8<br>27.8     | 27.8    | 8.1<br>8.4 | 8.3     | 34.1<br>34.1 | 34.1    | 88.0<br>88.0      | 88.0    | 5.9<br>5.9              | 5.9     |     | 4.1<br>3.9      | 4.0     |     | 4.8<br>4.7              | 4.8     |     |
| M3       | Cloudy            | Moderate       | 11:02         | Surface   | 1    | 28.0<br>28.0     | 28.0    | 8.6<br>8.7 | 8.7     | 33.8<br>34.0 | 33.9    | 85.9<br>85.8      | 85.9    | 5.7<br>5.7              | 5.7     | 5.7 | 5.0<br>5.0      | 5.0     | 5.6 | 5.2<br>5.3              | 5.3     | 5.6 |
|          |                   |                |               | Middle    | 4    | 28.0<br>27.9     | 28.0    | 8.6<br>8.7 | 8.7     | 34.0<br>34.0 | 34.0    | 85.4<br>84.7      | 85.1    | 5.7<br>5.7              | 5.7     |     | 4.8<br>5.0      | 4.9     |     | 5.9<br>5.9              | 5.9     |     |
|          |                   |                |               | Bottom    | 7    | 27.9<br>27.9     | 27.9    | 8.6<br>8.7 | 8.7     | 34.0<br>34.0 | 34.0    | 82.3<br>82.4      | 82.4    | 5.5<br>5.5              | 5.5     |     | 6.9<br>6.7      | 6.8     |     | 5.6<br>5.7              | 5.7     |     |
| M4       | Cloudy            | Moderate       | 10:23         | Surface   | 1    | 28.0<br>28.0     | 28.0    | 8.2<br>8.2 | 8.2     | 34.0<br>34.0 | 34.0    | 88.6<br>88.1      | 88.4    | 5.9<br>5.9              | 5.9     | 5.9 | 3.7<br>3.8      | 3.8     | 3.8 | 5.6<br>5.7              | 5.7     | 5.6 |
|          |                   |                |               | Middle    | 5    | 28.0<br>28.0     | 28.0    | 8.1<br>8.4 | 8.3     | 34.1<br>34.0 | 34.1    | 88.1<br>87.9      | 88.0    | 5.9<br>5.9              | 5.9     |     | 3.8<br>3.7      | 3.8     |     | 5.2<br>5.2              | 5.2     |     |
|          |                   |                |               | Bottom    | 9    | 28.0<br>28.0     | 28.0    | 8.1<br>8.4 | 8.3     | 34.1<br>34.1 | 34.1    | 87.5<br>87.5      | 87.5    | 5.8<br>5.8              | 5.8     |     | 4.0<br>3.7      | 3.9     |     | 5.9<br>5.9              | 5.9     |     |
| M5       | Cloudy            | Moderate       | 11:21         | Surface   | 1    | 27.8<br>27.8     | 27.8    | 8.2<br>8.6 | 8.4     | 34.0<br>34.0 | 34.0    | 87.3<br>86.5      | 86.9    | 5.8<br>5.8              | 5.8     | 5.8 | 5.0<br>4.8      | 4.9     | 5.0 | 4.9<br>5.0              | 5.0     | 4.9 |
|          |                   |                |               | Middle    | 5.5  | 27.8<br>27.8     | 27.8    | 8.2<br>8.6 | 8.4     | 34.0<br>34.0 | 34.0    | 85.5<br>85.8      | 85.7    | 5.7<br>5.7              | 5.7     |     | 4.8<br>4.7      | 4.8     |     | 5.6<br>5.7              | 5.7     |     |
|          |                   |                |               | Bottom    | 10   | 27.8<br>27.8     | 27.8    | 8.4<br>8.7 | 8.6     | 34.0<br>34.0 | 34.0    | 84.8<br>85.1      | 85.0    | 5.7<br>5.7              | 5.7     |     | 5.3<br>5.1      | 5.2     |     | 4.1<br>4.0              | 4.1     |     |
| M6       | Cloudy            | Moderate       | 11:17         | Surface   | -    | -                | -       | -          | -       | -            | -       | -                 | -       | -                       | 5.5     | -   | -               | 5.3     | -   | -                       | 5.2     |     |
|          |                   |                |               | Middle    | 1.2  | 27.8<br>27.8     | 27.8    | 8.4<br>8.3 | 8.4     | 34.0<br>34.0 | 34.0    | 82.1<br>81.7      | 81.9    | 5.5<br>5.5              |         | 5.5 | 4.9<br>5.6      |         | 5.3 | 5.1<br>5.3              |         | 5.2 |
|          |                   |                |               | Bottom    | -    | -                | -       | -          | -       | -            | -       | -                 | -       | -                       |         | -   | -               |         | -   | -                       |         | -   |

Remarks: \*DA: Depth-Averaged  
\*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

**Appendix I - Action and Limit Levels for Marine Water Quality on 25 June 2018 (Mid-Flood Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>  | <b>Limit Level</b>   |
|---|-------------------------------------|--|--|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |  |  |
|   | Depth Average                       | <u>4.9 mg/L</u>  | <u>4.6 mg/L</u>  |
|   | Bottom                              | <u>4.2 mg/L</u>  | <u>3.6 mg/L</u>  |
|   | <b><u>Station M6</u></b>            |  |  |
|   | Intake Level                        | <u>5.0 mg/L</u>  | <u>4.7 mg/L</u>  |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |  |  |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 10.4 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 11.3 NTU</u> |
|   | <b><u>Station M6</u></b>            |  |  |
|   | Intake Level                        | <u>19.0 NTU</u>  | <u>19.4 NTU</u>  |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>   |  |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.2 mg/L</u>        | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.8 mg/L</u>        |
| <b><u>Stations M1-M5</u></b>              |                                     |  |  |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.2 mg/L</u>        | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.8 mg/L</u>        |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |  |  |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.7 mg/L</u>        | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 7.3 mg/L</u>        |
| <b><u>Station M6</u></b>                  |                                     |  |  |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>  |  |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction**  
**Water Quality Monitoring Results on 25 June 2018**

**(Mid-Flood Tide)**

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) |      | Temperature (°C) |         | pH         |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         |            | Turbidity (NTU) |            |     | Suspended Solids (mg/L) |         |     |
|----------|-------------------|-----------------|---------------|-----------|------|------------------|---------|------------|---------|--------------|---------|-------------------|---------|-------------------------|---------|------------|-----------------|------------|-----|-------------------------|---------|-----|
|          |                   |                 |               |           |      | Value            | Average | Value      | Average | Value        | Average | Value             | Average | Value                   | Average | DA*        | Value           | Average    | DA* | Value                   | Average | DA* |
| C1       | Cloudy            | Moderate        | 18:02         | Surface   | 1    | 27.9<br>27.9     | 27.9    | 8.1<br>8.2 | 8.2     | 34.1<br>34.1 | 34.1    | 101.2<br>101.0    | 101.1   | 6.7<br>6.7              | 6.7     | 6.5        | 3.3<br>3.4      | 3.4        | 5.5 | 5.1<br>5.3              | 5.2     | 5.3 |
|          |                   |                 |               | Middle    | 9    | 27.9<br>27.9     | 27.9    | 8.1<br>8.2 | 8.2     | 34.1<br>34.1 | 34.1    | 93.8<br>94.5      | 94.2    | 6.3<br>6.3              | 6.3     | 4.1<br>4.4 | 4.3             | 5.0<br>5.0 |     | 5.0                     |         |     |
|          |                   |                 |               | Bottom    | 17   | 27.8<br>27.8     | 27.8    | 8.2<br>8.3 | 8.3     | 34.2<br>34.2 | 34.2    | 89.6<br>90.1      | 89.9    | 6.0<br>6.0              | 6.0     | 8.7<br>8.7 | 8.7             | 5.7<br>5.5 |     | 5.6                     |         |     |
| C2       | Cloudy            | Moderate        | 16:30         | Surface   | 1    | 28.1<br>28.2     | 28.2    | 8.5<br>8.5 | 8.5     | 33.9<br>33.9 | 33.9    | 96.6<br>97.3      | 97.0    | 6.4<br>6.5              | 6.5     | 6.2        | 3.4<br>3.1      | 3.3        | 4.9 | 5.5<br>5.5              | 5.5     | 5.8 |
|          |                   |                 |               | Middle    | 16.5 | 28.0<br>28.0     | 28.0    | 8.8<br>8.8 | 8.8     | 34.0<br>34.0 | 34.0    | 86.5<br>86.4      | 86.5    | 5.8<br>5.8              | 5.8     | 4.2<br>3.9 | 4.1             | 5.4<br>5.4 |     | 5.4                     |         |     |
|          |                   |                 |               | Bottom    | 32   | 28.0<br>28.0     | 28.0    | 8.9<br>8.9 | 8.9     | 34.0<br>34.0 | 34.0    | 83.9<br>84.3      | 84.1    | 5.6<br>5.6              | 5.6     | 7.3<br>7.2 | 7.3             | 6.2<br>6.5 |     | 6.4                     |         |     |
| G1       | Cloudy            | Moderate        | 17:18         | Surface   | 1    | 28.0<br>28.0     | 28.0    | 8.1<br>8.3 | 8.2     | 34.0<br>33.8 | 33.9    | 95.6<br>95.8      | 95.7    | 6.4<br>6.4              | 6.4     | 6.3        | 4.7<br>4.6      | 4.7        | 5.0 | 5.3<br>5.6              | 5.5     | 5.4 |
|          |                   |                 |               | Middle    | 4    | 27.8<br>27.9     | 27.9    | 8.1<br>8.3 | 8.2     | 34.0<br>34.0 | 34.0    | 90.7<br>91.7      | 91.2    | 6.1<br>6.1              | 6.1     | 5.0<br>5.8 | 5.4             | 5.4<br>5.5 |     | 5.5                     |         |     |
|          |                   |                 |               | Bottom    | 7    | 27.8<br>27.8     | 27.8    | 8.2<br>8.3 | 8.3     | 34.1<br>34.1 | 34.1    | 90.0<br>89.5      | 89.8    | 6.0<br>6.0              | 6.0     | 4.6<br>5.1 | 4.9             | 5.2<br>5.1 |     | 5.2                     |         |     |
| G2       | Cloudy            | Moderate        | 17:04         | Surface   | 1    | 28.0<br>28.0     | 28.0    | 8.3<br>8.4 | 8.4     | 33.9<br>33.9 | 33.9    | 100.5<br>100.4    | 100.5   | 6.7<br>6.7              | 6.7     | 6.7        | 3.8<br>3.8      | 3.8        | 3.7 | 5.4<br>5.8              | 5.6     | 5.4 |
|          |                   |                 |               | Middle    | 5    | 27.9<br>27.9     | 27.9    | 8.4<br>8.5 | 8.5     | 34.1<br>34.1 | 34.1    | 98.4<br>97.9      | 98.2    | 6.6<br>6.5              | 6.6     | 3.6<br>3.7 | 3.7             | 5.4<br>5.6 |     | 5.5                     |         |     |
|          |                   |                 |               | Bottom    | 9    | 27.9<br>27.9     | 27.9    | 8.4<br>8.5 | 8.5     | 34.1<br>34.1 | 34.1    | 94.5<br>95.1      | 94.8    | 6.3<br>6.3              | 6.3     | 3.6<br>3.5 | 3.6             | 5.3<br>5.1 |     | 5.2                     |         |     |
| G3       | Cloudy            | Moderate        | 17:27         | Surface   | 1    | 27.9<br>27.9     | 27.9    | 8.3<br>8.2 | 8.3     | 33.4<br>33.6 | 33.5    | 88.4<br>88.4      | 88.4    | 5.9<br>5.9              | 5.9     | 5.9        | 6.2<br>6.8      | 6.5        | 8.4 | 4.0<br>4.1              | 4.1     | 5.2 |
|          |                   |                 |               | Middle    | 4    | 27.9<br>27.9     | 27.9    | 8.3<br>8.3 | 8.3     | 33.7<br>33.9 | 33.8    | 88.0<br>86.7      | 87.4    | 5.9<br>5.8              | 5.9     | 9.5<br>8.6 | 9.1             | 5.2<br>5.2 |     | 5.2                     |         |     |
|          |                   |                 |               | Bottom    | 7    | 27.8<br>27.8     | 27.8    | 8.4<br>8.4 | 8.4     | 33.9<br>34.0 | 34.0    | 86.7<br>85.7      | 86.2    | 5.8<br>5.7              | 5.8     | 9.3<br>9.7 | 9.5             | 6.2<br>6.1 |     | 6.2                     |         |     |
| G4       | Cloudy            | Moderate        | 17:40         | Surface   | 1    | 28.1<br>28.1     | 28.1    | 8.1<br>8.1 | 8.1     | 33.9<br>34.0 | 34.0    | 93.1<br>93.5      | 93.3    | 6.2<br>6.2              | 6.2     | 6.2        | 4.5<br>4.6      | 4.6        | 5.4 | 5.3<br>5.3              | 5.3     | 6.0 |
|          |                   |                 |               | Middle    | 4.5  | 27.9<br>27.9     | 27.9    | 8.3<br>8.3 | 8.3     | 34.0<br>34.0 | 34.0    | 93.1<br>89.5      | 91.3    | 6.2<br>6.0              | 6.1     | 4.7<br>4.8 | 4.8             | 6.0<br>6.2 |     | 6.1                     |         |     |
|          |                   |                 |               | Bottom    | 8    | 27.9<br>27.8     | 27.9    | 8.3<br>8.3 | 8.3     | 34.1<br>34.1 | 34.1    | 89.0<br>87.5      | 88.3    | 5.9<br>5.8              | 5.9     | 6.1<br>7.2 | 6.7             | 6.6<br>6.3 |     | 6.5                     |         |     |
| M1       | Cloudy            | Moderate        | 17:11         | Surface   | 1    | 28.0<br>28.0     | 28.0    | 8.4<br>8.2 | 8.3     | 34.0<br>34.0 | 34.0    | 96.5<br>97.2      | 96.9    | 6.4<br>6.5              | 6.5     | 6.4        | 4.5<br>4.4      | 4.5        | 5.4 | 3.9<br>3.7              | 3.8     | 4.1 |
|          |                   |                 |               | Middle    | 3    | 27.9<br>27.9     | 27.9    | 8.2<br>8.4 | 8.3     | 34.1<br>34.0 | 34.1    | 92.5<br>90.8      | 91.7    | 6.2<br>6.1              | 6.2     | 5.0<br>5.2 | 5.1             | 3.4<br>3.5 |     | 3.5                     |         |     |
|          |                   |                 |               | Bottom    | 5    | 27.8<br>27.8     | 27.8    | 8.2<br>8.4 | 8.3     | 34.0<br>34.0 | 34.0    | 89.8<br>88.7      | 89.3    | 6.0<br>5.9              | 6.0     | 6.3<br>6.9 | 6.6             | 5.0<br>5.1 |     | 5.1                     |         |     |
| M2       | Cloudy            | Moderate        | 16:54         | Surface   | 1    | 28.0<br>28.0     | 28.0    | 8.3<br>8.4 | 8.4     | 34.0<br>34.0 | 34.0    | 101.3<br>102.1    | 101.7   | 6.7<br>6.8              | 6.8     | 6.7        | 3.6<br>3.6      | 3.6        | 3.7 | 4.9<br>4.8              | 4.9     | 5.2 |
|          |                   |                 |               | Middle    | 6    | 28.0<br>28.0     | 28.0    | 8.2<br>8.5 | 8.4     | 34.1<br>34.1 | 34.1    | 98.2<br>99.3      | 98.8    | 6.5<br>6.6              | 6.6     | 3.2<br>3.2 | 3.2             | 5.6<br>5.4 |     | 5.5                     |         |     |
|          |                   |                 |               | Bottom    | 11   | 27.9<br>27.9     | 27.9    | 8.3<br>8.5 | 8.4     | 34.1<br>34.1 | 34.1    | 92.9<br>92.4      | 92.7    | 6.2<br>6.2              | 6.2     | 3.9<br>4.4 | 4.2             | 5.2<br>5.3 |     | 5.3                     |         |     |
| M3       | Cloudy            | Moderate        | 17:33         | Surface   | 1    | 27.9<br>27.9     | 27.9    | 8.4<br>8.3 | 8.4     | 33.3<br>33.8 | 33.6    | 88.9<br>89.3      | 89.1    | 6.0<br>6.0              | 6.0     | 6.0        | 5.5<br>5.6      | 5.6        | 6.1 | 4.1<br>4.0              | 4.1     | 4.7 |
|          |                   |                 |               | Middle    | 4    | 27.9<br>27.9     | 27.9    | 8.3<br>8.4 | 8.4     | 33.9<br>34.0 | 34.0    | 87.7<br>86.8      | 87.3    | 5.9<br>5.8              | 5.9     | 6.0<br>6.4 | 6.2             | 4.1<br>4.0 |     | 4.1                     |         |     |
|          |                   |                 |               | Bottom    | 7    | 27.8<br>27.8     | 27.8    | 8.3<br>8.4 | 8.4     | 34.0<br>34.0 | 34.0    | 87.1<br>86.0      | 86.6    | 5.8<br>5.7              | 5.8     | 5.8<br>6.9 | 6.4             | 5.9<br>5.8 |     | 5.9                     |         |     |
| M4       | Cloudy            | Moderate        | 16:40         | Surface   | 1    | 28.1<br>28.1     | 28.1    | 8.4<br>8.6 | 8.5     | 34.0<br>34.0 | 34.0    | 102.9<br>103.6    | 103.3   | 6.8<br>6.9              | 6.9     | 6.9        | 3.7<br>3.4      | 3.6        | 3.7 | 4.1<br>4.0              | 4.1     | 4.2 |
|          |                   |                 |               | Middle    | 5    | 28.0<br>28.1     | 28.1    | 8.5<br>8.6 | 8.6     | 34.1<br>34.1 | 34.1    | 101.3<br>103.3    | 102.3   | 6.7<br>6.9              | 6.8     | 3.7<br>3.4 | 3.6             | 4.0<br>4.2 |     | 4.1                     |         |     |
|          |                   |                 |               | Bottom    | 9    | 28.0<br>28.0     | 28.0    | 8.6<br>8.6 | 8.6     | 34.1<br>34.1 | 34.1    | 100.2<br>99.2     | 99.7    | 6.7<br>6.6              | 6.7     | 3.9<br>3.7 | 3.8             | 4.4<br>4.4 |     | 4.4                     |         |     |
| M5       | Cloudy            | Moderate        | 17:54         | Surface   | 1    | 28.0<br>28.0     | 28.0    | 8.1<br>8.2 | 8.2     | 34.1<br>34.1 | 34.1    | 104.8<br>101.5    | 103.2   | 7.0<br>6.8              | 6.9     | 6.5        | 3.3<br>3.8      | 3.6        | 4.7 | 4.3<br>4.2              | 4.3     | 5.1 |
|          |                   |                 |               | Middle    | 5.5  | 27.8<br>27.8     | 27.8    | 8.3<br>8.2 | 8.3     | 34.1<br>34.1 | 34.1    | 90.3<br>90.3      | 90.3    | 6.0<br>6.0              | 6.0     | 5.4<br>5.5 | 5.5             | 4.9<br>4.7 |     | 4.8                     |         |     |
|          |                   |                 |               | Bottom    | 10   | 27.9<br>27.9     | 27.9    | 8.4<br>8.3 | 8.4     | 34.1<br>34.1 | 34.1    | 90.3<br>91.8      | 91.1    | 6.0<br>6.1              | 6.1     | 5.0<br>4.8 | 4.9             | 6.3<br>6.3 |     | 6.3                     |         |     |
| M6       | Cloudy            | Moderate        | 17:47         | Surface   | -    | -                | -       | -          | -       | -            | -       | -                 | -       | -                       | -       | -          | -               | -          | 5.0 | -                       | -       | 5.2 |
|          |                   |                 |               | Middle    | 1.3  | 27.8<br>27.8     | 27.8    | 8.2<br>8.2 | 8.2     | 34.0<br>34.0 | 34.0    | 89.3<br>89.0      | 89.2    | 6.0<br>5.9              | 6.0     | 4.9<br>5.0 | 5.0             | 5.4<br>5.0 |     | 5.2                     |         |     |
|          |                   |                 |               | Bottom    | -    | -                | -       | -          | -       | -            | -       | -                 | -       | -                       | -       | -          | -               | -          |     | -                       |         |     |

Remarks: \*DA: Depth-Averaged  
 \*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

**Appendix I - Action and Limit Levels for Marine Water Quality on 27 June 2018 (Mid-Ebb Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 5.4 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 5.9 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.0 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.5 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.0 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.5 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.1 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 7.7 mg/L</u>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction  
Water Quality Monitoring Results on 27 June 2018**

**(Mid-Ebb Tide)**

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) | Temperature (°C) |              | pH    |            | Salinity ppt |              | DO Saturation (%) |                | Dissolved Oxygen (mg/L) |              |      | Turbidity (NTU) |            |     | Suspended Solids (mg/L) |            |     |     |
|----------|-------------------|-----------------|---------------|-----------|------------------|--------------|-------|------------|--------------|--------------|-------------------|----------------|-------------------------|--------------|------|-----------------|------------|-----|-------------------------|------------|-----|-----|
|          |                   |                 |               |           | Value            | Average      | Value | Average    | Value        | Average      | Value             | Average        | Value                   | Average      | DA*  | Value           | Average    | DA* | Value                   | Average    | DA* |     |
| C1       | Sunny             | Moderate        | 11:56         | Surface   | 1                | 27.6<br>27.6 | 27.6  | 8.4<br>8.4 | 8.4          | 26.7<br>26.7 | 26.7              | 113.0<br>115.6 | 114.3                   | 7.7<br>7.9   | 7.8  | 6.7             | 1.7<br>1.6 | 1.7 | 3.0                     | 4.9<br>5.1 | 5.0 | 6.0 |
|          |                   |                 |               | Middle    | 9                | 26.3<br>26.3 | 26.3  | 8.3<br>8.3 | 8.3          | 28.5<br>28.5 | 28.5              | 79.6<br>78.9   | 79.3                    | 5.5<br>5.4   | 5.5  |                 | 2.1<br>2.0 | 2.1 |                         | 6.1<br>6.3 | 6.2 |     |
|          |                   |                 |               | Bottom    | 17               | 23.8<br>23.7 | 23.8  | 8.1<br>8.1 | 8.1          | 30.8<br>30.8 | 30.8              | 61.1<br>60.8   | 61.0                    | 4.3<br>4.3   | 4.3  |                 | 5.2<br>5.1 | 5.2 |                         | 6.7<br>6.7 | 6.7 |     |
| C2       | Sunny             | Moderate        | 10:33         | Surface   | 1                | 28.3<br>28.3 | 28.3  | 8.5<br>8.5 | 8.5          | 26.7<br>26.9 | 26.8              | 152.0<br>146.5 | 149.3                   | 10.2<br>9.8  | 10.0 | 7.4             | 1.9<br>2.0 | 2.0 | 3.4                     | 5.8<br>5.8 | 5.8 | 5.8 |
|          |                   |                 |               | Middle    | 16.5             | 25.0<br>25.2 | 25.1  | 8.2<br>8.2 | 8.2          | 29.8<br>29.7 | 29.8              | 67.2<br>67.0   | 67.1                    | 4.7<br>4.7   | 4.7  |                 | 3.5<br>3.6 | 3.6 |                         | 5.6<br>5.6 | 5.6 |     |
|          |                   |                 |               | Bottom    | 32               | 24.9<br>25.0 | 25.0  | 8.2<br>8.1 | 8.2          | 29.9<br>30.0 | 29.9              | 65.0<br>62.6   | 63.8                    | 4.5<br>4.4   | 4.5  |                 | 4.1<br>4.8 | 4.5 |                         | 5.9<br>5.8 | 5.9 |     |
| G1       | Sunny             | Moderate        | 11:12         | Surface   | 1                | 28.4<br>28.4 | 28.4  | 8.5<br>8.5 | 8.5          | 27.2<br>27.1 | 27.2              | 160.1<br>157.0 | 158.6                   | 10.7<br>10.5 | 10.6 | 8.9             | 1.2<br>1.3 | 1.3 | 1.7                     | 5.2<br>5.2 | 5.2 | 4.4 |
|          |                   |                 |               | Middle    | 4                | 27.1<br>27.1 | 27.1  | 8.3<br>8.3 | 8.3          | 27.8<br>27.8 | 27.8              | 102.4<br>108.9 | 105.7                   | 7.0<br>7.4   | 7.2  |                 | 1.9<br>1.7 | 1.8 |                         | 5.3<br>5.3 | 5.3 |     |
|          |                   |                 |               | Bottom    | 7                | 26.2<br>26.3 | 26.3  | 8.2<br>8.2 | 8.2          | 28.4<br>28.4 | 28.4              | 74.6<br>77.7   | 76.2                    | 5.1<br>5.4   | 5.3  |                 | 2.0<br>2.0 | 2.0 |                         | 2.6<br>2.5 | 2.6 |     |
| G2       | Sunny             | Moderate        | 10:58         | Surface   | 1                | 27.9<br>27.7 | 27.8  | 8.5<br>8.4 | 8.5          | 27.2<br>27.3 | 27.3              | 138.7<br>135.4 | 137.1                   | 9.4<br>9.2   | 9.3  | 7.5             | 1.6<br>1.8 | 1.7 | 2.8                     | 4.9<br>5.0 | 5.0 | 5.6 |
|          |                   |                 |               | Middle    | 5                | 26.3<br>26.5 | 26.4  | 8.3<br>8.3 | 8.3          | 28.3<br>28.2 | 28.3              | 81.1<br>85.1   | 83.1                    | 5.6<br>5.8   | 5.7  |                 | 2.3<br>2.2 | 2.3 |                         | 5.5<br>5.5 | 5.5 |     |
|          |                   |                 |               | Bottom    | 9                | 25.1<br>25.3 | 25.2  | 8.2<br>8.2 | 8.2          | 29.8<br>29.7 | 29.8              | 66.5<br>68.1   | 67.3                    | 4.6<br>4.7   | 4.7  |                 | 4.3<br>4.2 | 4.3 |                         | 6.2<br>6.5 | 6.4 |     |
| G3       | Sunny             | Moderate        | 11:19         | Surface   | 1                | 28.8<br>28.7 | 28.8  | 8.5<br>8.5 | 8.5          | 26.7<br>25.5 | 26.1              | 161.2<br>146.4 | 153.8                   | 10.7<br>9.8  | 10.3 | 8.8             | 1.2<br>1.2 | 1.2 | 1.8                     | 4.1<br>4.0 | 4.1 | 5.7 |
|          |                   |                 |               | Middle    | 4                | 27.3<br>27.1 | 27.2  | 8.4<br>8.3 | 8.4          | 27.7<br>27.9 | 27.8              | 109.5<br>102.0 | 105.8                   | 7.4<br>6.9   | 7.2  |                 | 1.9<br>1.9 | 1.9 |                         | 6.6<br>6.5 | 6.6 |     |
|          |                   |                 |               | Bottom    | 7                | 26.3<br>26.5 | 26.4  | 8.2<br>8.3 | 8.3          | 28.5<br>28.4 | 28.5              | 78.1<br>77.8   | 78.0                    | 5.4<br>5.3   | 5.4  |                 | 2.2<br>2.2 | 2.2 |                         | 6.5<br>6.3 | 6.4 |     |
| G4       | Sunny             | Moderate        | 11:30         | Surface   | 1                | 28.2<br>28.0 | 28.1  | 8.5<br>8.5 | 8.5          | 27.2<br>27.2 | 27.2              | 150.0<br>140.9 | 145.5                   | 10.1<br>9.5  | 9.8  | 8.3             | 1.5<br>1.6 | 1.6 | 2.5                     | 4.9<br>4.8 | 4.9 | 4.8 |
|          |                   |                 |               | Middle    | 4                | 27.0<br>26.7 | 26.9  | 8.3<br>8.3 | 8.3          | 27.9<br>28.0 | 28.0              | 100.9<br>94.7  | 97.8                    | 6.9<br>6.5   | 6.7  |                 | 1.8<br>2.0 | 1.9 |                         | 4.6<br>4.4 | 4.5 |     |
|          |                   |                 |               | Bottom    | 7                | 25.8<br>25.8 | 25.8  | 8.2<br>8.2 | 8.2          | 29.0<br>29.0 | 29.0              | 62.3<br>66.4   | 64.4                    | 4.3<br>4.6   | 4.5  |                 | 4.1<br>3.7 | 3.9 |                         | 4.9<br>4.9 | 4.9 |     |
| M1       | Sunny             | Moderate        | 11:06         | Surface   | 1                | 28.2<br>28.2 | 28.2  | 8.5<br>8.5 | 8.5          | 27.2<br>27.2 | 27.2              | 150.5<br>150.7 | 150.6                   | 10.1<br>10.1 | 10.1 | 9.5             | 1.5<br>1.4 | 1.5 | 1.8                     | 3.1<br>3.1 | 3.1 | 3.9 |
|          |                   |                 |               | Middle    | 3                | 27.7<br>27.8 | 27.8  | 8.4<br>8.5 | 8.5          | 27.3<br>27.3 | 27.3              | 130.7<br>133.2 | 132.0                   | 8.8<br>9.0   | 8.9  |                 | 1.9<br>1.7 | 1.8 |                         | 3.1<br>3.1 | 3.1 |     |
|          |                   |                 |               | Bottom    | 5                | 26.8<br>26.6 | 26.8  | 8.3<br>8.3 | 8.3          | 27.9<br>27.9 | 27.9              | 95.2<br>94.5   | 94.9                    | 6.5<br>6.5   | 6.5  |                 | 2.3<br>2.1 | 2.2 |                         | 5.4<br>5.5 | 5.5 |     |
| M2       | Sunny             | Moderate        | 10:51         | Surface   | 1                | 27.9<br>27.8 | 27.9  | 8.5<br>8.5 | 8.5          | 27.3<br>27.3 | 27.3              | 144.5<br>139.3 | 141.9                   | 9.7<br>9.4   | 9.6  | 7.2             | 1.6<br>1.7 | 1.7 | 2.5                     | 5.6<br>5.8 | 5.7 | 6.0 |
|          |                   |                 |               | Middle    | 6                | 25.6<br>25.6 | 25.6  | 8.2<br>8.2 | 8.2          | 29.3<br>29.3 | 29.3              | 66.2<br>69.6   | 67.9                    | 4.6<br>4.8   | 4.7  |                 | 2.0<br>2.0 | 2.0 |                         | 5.5<br>5.7 | 5.6 |     |
|          |                   |                 |               | Bottom    | 11               | 24.6<br>24.6 | 24.6  | 8.1<br>8.2 | 8.2          | 30.3<br>30.2 | 30.3              | 60.4<br>64.7   | 62.6                    | 4.2<br>4.5   | 4.4  |                 | 3.8<br>3.7 | 3.8 |                         | 6.6<br>6.7 | 6.7 |     |
| M3       | Sunny             | Moderate        | 11:25         | Surface   | 1                | 28.7<br>28.6 | 28.7  | 8.5<br>8.5 | 8.5          | 26.4<br>26.5 | 26.5              | 139.6<br>144.8 | 142.2                   | 9.3<br>9.7   | 9.5  | 8.3             | 1.3<br>1.2 | 1.3 | 2.0                     | 5.2<br>5.1 | 5.2 | 5.3 |
|          |                   |                 |               | Middle    | 4                | 27.1<br>27.0 | 27.1  | 8.3<br>8.3 | 8.3          | 27.9<br>28.0 | 28.0              | 103.1<br>102.6 | 102.9                   | 7.0<br>7.0   | 7.0  |                 | 1.9<br>2.2 | 2.1 |                         | 5.2<br>5.3 | 5.3 |     |
|          |                   |                 |               | Bottom    | 7                | 26.6<br>26.5 | 26.6  | 8.3<br>8.3 | 8.3          | 28.5<br>28.7 | 28.6              | 76.9<br>75.8   | 76.4                    | 5.3<br>5.2   | 5.3  |                 | 2.5<br>2.5 | 2.5 |                         | 5.6<br>5.3 | 5.5 |     |
| M4       | Sunny             | Moderate        | 10:43         | Surface   | 1                | 28.8<br>28.7 | 28.8  | 8.6<br>8.6 | 8.6          | 27.1<br>27.1 | 27.1              | 183.8<br>183.7 | 183.8                   | 12.2<br>12.2 | 12.2 | 11.7            | 1.0<br>1.2 | 1.1 | 1.6                     | 4.0<br>3.8 | 3.9 | 4.4 |
|          |                   |                 |               | Middle    | 5                | 28.1<br>28.1 | 28.1  | 8.6<br>8.6 | 8.6          | 27.2<br>27.2 | 27.2              | 165.0<br>166.4 | 165.7                   | 11.1<br>11.2 | 11.2 |                 | 1.5<br>1.5 | 1.5 |                         | 4.6<br>4.6 | 4.6 |     |
|          |                   |                 |               | Bottom    | 9                | 26.5<br>26.0 | 26.3  | 8.3<br>8.3 | 8.3          | 28.4<br>28.9 | 28.7              | 85.0<br>76.3   | 80.7                    | 5.8<br>5.3   | 5.6  |                 | 2.4<br>2.2 | 2.3 |                         | 4.8<br>4.8 | 4.8 |     |
| M5       | Sunny             | Moderate        | 11:45         | Surface   | 1                | 27.7<br>27.7 | 27.7  | 8.4<br>8.4 | 8.4          | 26.6<br>26.5 | 26.6              | 116.2<br>116.6 | 116.4                   | 7.9<br>7.9   | 7.9  | 7.4             | 2.1<br>1.9 | 2.0 | 2.6                     | 4.3<br>4.3 | 4.3 | 3.8 |
|          |                   |                 |               | Middle    | 5.5              | 27.0<br>27.6 | 27.3  | 8.3<br>8.4 | 8.4          | 27.7<br>27.0 | 27.4              | 98.7<br>100.1  | 99.4                    | 6.7<br>6.8   | 6.8  |                 | 2.6<br>2.3 | 2.5 |                         | 4.9<br>4.9 | 4.9 |     |
|          |                   |                 |               | Bottom    | 10               | 24.9<br>25.0 | 25.0  | 8.2<br>8.2 | 8.2          | 29.8<br>29.8 | 29.8              | 66.5<br>66.2   | 66.4                    | 4.6<br>4.6   | 4.6  |                 | 3.3<br>3.2 | 3.3 |                         | 2.2<br>2.1 | 2.2 |     |
| M6       | Sunny             | Moderate        | 11:38         | Surface   | -                | -            | -     | -          | -            | -            | -                 | -              | -                       | -            | 10.0 | -               | -          | 1.6 | -                       | -          | 2.0 |     |
|          |                   |                 |               | Middle    | 1.3              | 28.2<br>28.4 | 28.3  | 8.5<br>8.5 | 8.5          | 27.2<br>27.2 | 27.2              | 145.0<br>152.4 | 148.7                   | 9.7<br>10.2  |      | 10.0            | 1.6<br>1.5 |     | 1.6                     | 2.0<br>2.0 |     | 2.0 |
|          |                   |                 |               | Bottom    | -                | -            | -     | -          | -            | -            | -                 | -              | -                       | -            |      | -               | -          |     | -                       | -          |     | -   |

Remarks: \*DA: Depth-Averaged  
\*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough: White capped or rougher.

**Appendix I - Action and Limit Levels for Marine Water Quality on 27 June 2018 (Mid-Flood Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 9.1 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 9.9 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 5.5 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.0 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 5.5 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.0 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 8.0 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 8.7 mg/L</u>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction**  
**Water Quality Monitoring Results on 27 June 2018**

**(Mid-Flood Tide)**

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) | Temperature (°C) |              | pH    |            | Salinity ppt |              | DO Saturation (%) |                | Dissolved Oxygen (mg/L) |              |      | Turbidity (NTU) |            |     | Suspended Solids (mg/L) |            |     |     |            |     |
|----------|-------------------|-----------------|---------------|-----------|------------------|--------------|-------|------------|--------------|--------------|-------------------|----------------|-------------------------|--------------|------|-----------------|------------|-----|-------------------------|------------|-----|-----|------------|-----|
|          |                   |                 |               |           | Value            | Average      | Value | Average    | Value        | Average      | Value             | Average        | Value                   | Average      | DA*  | Value           | Average    | DA* | Value                   | Average    | DA* |     |            |     |
| C1       | Sunny             | Moderate        | 19:01         | Surface   | 1                | 27.5<br>27.7 | 27.6  | 8.4<br>8.4 | 8.4          | 26.8<br>26.7 | 26.8              | 111.0<br>118.5 | 114.8                   | 7.6<br>8.0   | 7.8  | 6.6             | 1.8<br>1.7 | 1.8 | 3.8                     | 4.5<br>4.7 | 4.6 | 6.1 |            |     |
|          |                   |                 |               | Middle    | 9                | 26.3<br>26.3 | 26.3  | 8.2<br>8.3 | 8.3          | 28.5<br>28.5 | 28.5              | 77.5<br>78.6   | 78.1                    | 5.3<br>5.4   | 5.4  |                 | 2.2<br>2.0 |     |                         | 2.1        |     |     | 7.0<br>7.1 | 7.1 |
|          |                   |                 |               | Bottom    | 17               | 23.8<br>23.7 | 23.8  | 8.1<br>8.1 | 8.1          | 30.8<br>30.8 | 30.8              | 60.7<br>60.3   | 60.5                    | 4.3<br>4.3   | 4.3  |                 | 7.7<br>7.4 |     |                         | 7.6        |     |     | 6.6<br>6.8 | 6.7 |
| C2       | Sunny             | Moderate        | 17:34         | Surface   | 1                | 28.4<br>28.5 | 28.5  | 8.5<br>8.5 | 8.5          | 26.8<br>26.8 | 26.8              | 152.9<br>153.5 | 153.2                   | 10.2<br>10.3 | 10.3 | 7.5             | 1.6<br>1.8 | 1.7 | 3.2                     | 5.5<br>5.4 | 5.5 | 3.7 |            |     |
|          |                   |                 |               | Middle    | 16.5             | 25.0<br>25.2 | 25.1  | 8.2<br>8.2 | 8.2          | 29.8<br>29.7 | 29.8              | 66.3<br>66.6   | 66.5                    | 4.6<br>4.6   | 4.6  |                 | 3.5<br>3.5 |     |                         | 3.5        |     |     | 3.1<br>3.1 | 3.1 |
|          |                   |                 |               | Bottom    | 32               | 24.9<br>24.8 | 24.9  | 8.2<br>8.1 | 8.2          | 30.0<br>30.1 | 30.1              | 64.3<br>62.7   | 63.5                    | 4.5<br>4.4   | 4.5  |                 | 4.3<br>4.4 |     |                         | 4.4        |     |     | 2.5<br>2.3 | 2.4 |
| G1       | Sunny             | Moderate        | 18:14         | Surface   | 1                | 28.5<br>28.5 | 28.5  | 8.5<br>8.5 | 8.5          | 27.2<br>27.1 | 27.2              | 161.6<br>160.0 | 160.8                   | 10.8<br>10.7 | 10.8 | 9.0             | 1.2<br>1.3 | 1.3 | 1.7                     | 4.6<br>4.6 | 4.6 | 3.8 |            |     |
|          |                   |                 |               | Middle    | 4                | 26.8<br>27.2 | 27.0  | 8.3<br>8.4 | 8.4          | 27.9<br>27.7 | 27.8              | 98.5<br>110.6  | 104.6                   | 6.7<br>7.5   | 7.1  |                 | 1.9<br>1.7 |     |                         | 1.8        |     |     | 3.6<br>3.8 | 3.7 |
|          |                   |                 |               | Bottom    | 7                | 26.2<br>26.3 | 26.3  | 8.2<br>8.2 | 8.2          | 28.4<br>28.4 | 28.4              | 74.0<br>76.0   | 75.0                    | 5.1<br>5.2   | 5.2  |                 | 2.1<br>2.1 |     |                         | 2.1        |     |     | 3.1<br>3.2 | 3.2 |
| G2       | Sunny             | Moderate        | 17:58         | Surface   | 1                | 27.8<br>27.8 | 27.8  | 8.5<br>8.5 | 8.5          | 27.3<br>27.2 | 27.3              | 138.0<br>136.8 | 137.4                   | 9.3<br>9.2   | 9.3  | 7.5             | 1.7<br>1.7 | 1.7 | 2.7                     | 5.2<br>5.0 | 5.1 | 4.3 |            |     |
|          |                   |                 |               | Middle    | 5                | 26.3<br>26.5 | 26.4  | 8.2<br>8.3 | 8.3          | 28.3<br>28.1 | 28.2              | 80.6<br>85.7   | 83.2                    | 5.5<br>5.9   | 5.7  |                 | 2.2<br>2.3 |     |                         | 2.3        |     |     | 3.8<br>3.8 | 3.8 |
|          |                   |                 |               | Bottom    | 9                | 25.1<br>25.2 | 25.2  | 8.2<br>8.2 | 8.2          | 29.8<br>29.8 | 29.8              | 66.3<br>66.7   | 66.5                    | 4.6<br>4.6   | 4.6  |                 | 4.2<br>4.2 |     |                         | 4.2        |     |     | 3.8<br>4.0 | 3.9 |
| G3       | Sunny             | Moderate        | 18:21         | Surface   | 1                | 28.7<br>28.7 | 28.7  | 8.6<br>8.5 | 8.6          | 26.7<br>26.0 | 26.4              | 161.3<br>149.7 | 155.5                   | 10.8<br>10.0 | 10.4 | 8.8             | 1.2<br>1.2 | 1.2 | 1.8                     | 4.6<br>4.4 | 4.5 | 5.1 |            |     |
|          |                   |                 |               | Middle    | 4                | 27.2<br>27.1 | 27.2  | 8.3<br>8.3 | 8.3          | 27.8<br>27.9 | 27.9              | 104.6<br>103.1 | 103.9                   | 7.1<br>7.0   | 7.1  |                 | 2.0<br>2.0 |     |                         | 2.0        |     |     | 7.3<br>7.5 | 7.4 |
|          |                   |                 |               | Bottom    | 7                | 26.2<br>26.2 | 26.2  | 8.2<br>8.2 | 8.2          | 28.5<br>28.6 | 28.6              | 77.0<br>75.4   | 76.2                    | 5.3<br>5.2   | 5.3  |                 | 2.4<br>2.2 |     |                         | 2.3        |     |     | 3.4<br>3.4 | 3.4 |
| G4       | Sunny             | Moderate        | 18:34         | Surface   | 1                | 28.5<br>28.0 | 28.2  | 8.5<br>8.5 | 8.5          | 27.2<br>27.2 | 27.2              | 153.0<br>146.4 | 149.7                   | 10.3<br>9.9  | 10.1 | 8.4             | 1.5<br>1.6 | 1.6 | 2.4                     | 2.2<br>2.3 | 2.3 | 4.9 |            |     |
|          |                   |                 |               | Middle    | 4                | 26.9<br>26.8 | 26.9  | 8.3<br>8.3 | 8.3          | 27.9<br>28.0 | 28.0              | 99.1<br>94.5   | 96.8                    | 6.8<br>6.5   | 6.7  |                 | 1.9<br>2.0 |     |                         | 2.0        |     |     | 5.8<br>5.7 | 5.8 |
|          |                   |                 |               | Bottom    | 7                | 25.8<br>25.8 | 25.8  | 8.2<br>8.2 | 8.2          | 29.0<br>29.0 | 29.0              | 62.2<br>63.4   | 62.8                    | 4.3<br>4.4   | 4.4  |                 | 3.6<br>3.6 |     |                         | 3.6        |     |     | 6.7<br>6.7 | 6.7 |
| M1       | Sunny             | Moderate        | 18:07         | Surface   | 1                | 28.2<br>28.3 | 28.3  | 8.5<br>8.5 | 8.5          | 27.2<br>27.2 | 27.2              | 149.0<br>154.0 | 151.5                   | 10.0<br>10.3 | 10.2 | 9.5             | 1.4<br>1.2 | 1.3 | 1.8                     | 3.6<br>3.7 | 3.7 | 4.6 |            |     |
|          |                   |                 |               | Middle    | 3                | 27.7<br>27.7 | 27.7  | 8.4<br>8.4 | 8.4          | 27.4<br>27.3 | 27.4              | 130.3<br>130.8 | 130.6                   | 8.8<br>8.8   | 8.8  |                 | 1.7<br>1.9 |     |                         | 1.8        |     |     | 4.6<br>4.3 | 4.5 |
|          |                   |                 |               | Bottom    | 5                | 26.8<br>26.8 | 26.8  | 8.3<br>8.3 | 8.3          | 27.8<br>27.9 | 27.9              | 94.6<br>94.3   | 94.5                    | 6.5<br>6.5   | 6.5  |                 | 2.2<br>2.1 |     |                         | 2.2        |     |     | 5.4<br>5.9 | 5.7 |
| M2       | Sunny             | Moderate        | 17:51         | Surface   | 1                | 28.0<br>27.8 | 27.9  | 8.5<br>8.5 | 8.5          | 27.3<br>27.3 | 27.3              | 148.5<br>140.4 | 144.5                   | 10.0<br>9.5  | 9.8  | 7.2             | 1.5<br>1.5 | 1.5 | 2.5                     | 5.6<br>5.4 | 5.5 | 4.7 |            |     |
|          |                   |                 |               | Middle    | 6                | 25.5<br>25.6 | 25.6  | 8.2<br>8.2 | 8.2          | 29.4<br>29.3 | 29.4              | 64.2<br>66.5   | 65.4                    | 4.5<br>4.6   | 4.6  |                 | 2.0<br>2.1 |     |                         | 2.1        |     |     | 3.0<br>3.0 | 3.0 |
|          |                   |                 |               | Bottom    | 11               | 24.6<br>24.6 | 24.6  | 8.1<br>8.1 | 8.1          | 30.2<br>30.2 | 30.2              | 62.0<br>63.1   | 62.6                    | 4.3<br>4.4   | 4.4  |                 | 3.9<br>3.6 |     |                         | 3.8        |     |     | 5.6<br>5.7 | 5.7 |
| M3       | Sunny             | Moderate        | 18:27         | Surface   | 1                | 28.6<br>28.6 | 28.6  | 8.5<br>8.5 | 8.5          | 26.5<br>26.4 | 26.5              | 145.8<br>148.5 | 147.2                   | 9.8<br>9.9   | 9.9  | 8.4             | 1.3<br>1.1 | 1.2 | 2.0                     | 4.5<br>4.2 | 4.4 | 3.8 |            |     |
|          |                   |                 |               | Middle    | 4                | 27.0<br>27.0 | 27.0  | 8.3<br>8.3 | 8.3          | 28.0<br>28.0 | 28.0              | 100.1<br>100.1 | 100.1                   | 6.8<br>6.8   | 6.8  |                 | 1.9<br>2.1 |     |                         | 2.0        |     |     | 4.3<br>4.2 | 4.3 |
|          |                   |                 |               | Bottom    | 7                | 26.4<br>26.4 | 26.4  | 8.2<br>8.2 | 8.2          | 28.7<br>28.7 | 28.7              | 75.2<br>74.2   | 74.7                    | 5.2<br>5.1   | 5.2  |                 | 2.8<br>2.9 |     |                         | 2.9        |     |     | 2.7<br>2.8 | 2.8 |
| M4       | Sunny             | Moderate        | 17:43         | Surface   | 1                | 28.8<br>28.7 | 28.8  | 8.6<br>8.6 | 8.6          | 27.1<br>27.1 | 27.1              | 183.8<br>184.4 | 184.1                   | 12.2<br>12.3 | 12.3 | 11.7            | 1.0<br>1.1 | 1.1 | 1.6                     | 4.7<br>4.3 | 4.5 | 5.2 |            |     |
|          |                   |                 |               | Middle    | 5                | 28.0<br>28.1 | 28.1  | 8.6<br>8.6 | 8.6          | 27.2<br>27.2 | 27.2              | 163.6<br>165.3 | 164.5                   | 11.0<br>11.1 | 11.1 |                 | 1.6<br>1.6 |     |                         | 1.6        |     |     | 5.6<br>5.6 | 5.6 |
|          |                   |                 |               | Bottom    | 9                | 26.3<br>26.1 | 26.2  | 8.3<br>8.2 | 8.3          | 28.5<br>28.8 | 28.7              | 78.6<br>77.0   | 77.8                    | 5.4<br>5.3   | 5.4  |                 | 2.3<br>2.1 |     |                         | 2.2        |     |     | 5.4<br>5.3 | 5.4 |
| M5       | Sunny             | Moderate        | 18:51         | Surface   | 1                | 27.6<br>27.8 | 27.7  | 8.4<br>8.4 | 8.4          | 26.7<br>26.2 | 26.5              | 115.2<br>118.9 | 117.1                   | 7.8<br>8.1   | 8.0  | 7.8             | 1.5<br>1.8 | 1.7 | 2.6                     | 5.2<br>5.0 | 5.1 | 4.7 |            |     |
|          |                   |                 |               | Middle    | 5.5              | 27.1<br>27.6 | 27.4  | 8.3<br>8.4 | 8.4          | 27.5<br>27.1 | 27.3              | 99.3<br>119.0  | 109.2                   | 6.8<br>8.1   | 7.5  |                 | 2.8<br>2.5 |     |                         | 2.7        |     |     | 4.8<br>4.8 | 4.8 |
|          |                   |                 |               | Bottom    | 10               | 24.9<br>25.0 | 25.0  | 8.2<br>8.2 | 8.2          | 29.8<br>29.7 | 29.8              | 66.3<br>66.8   | 66.6                    | 4.6<br>4.7   | 4.7  |                 | 3.2<br>3.4 |     |                         | 3.3        |     |     | 4.0<br>4.1 | 4.1 |
| M6       | Sunny             | Moderate        | 18:43         | Surface   | -                | -            | -     | -          | -            | -            | -                 | -              | -                       | -            | -    | 10.1            | -          | -   | 1.5                     | -          | -   | 4.3 |            |     |
|          |                   |                 |               | Middle    | 1.3              | 28.3<br>28.4 | 28.4  | 8.5<br>8.5 | 8.5          | 27.2<br>27.2 | 27.2              | 148.8<br>152.2 | 150.5                   | 10.0<br>10.2 | 10.1 |                 | 1.5<br>1.5 |     |                         | 1.5        |     |     | 4.3<br>4.2 | 4.3 |
|          |                   |                 |               | Bottom    | -                | -            | -     | -          | -            | -            | -                 | -              | -                       | -            | -    |                 | -          |     |                         | -          |     |     | -          | -   |

Remarks: \*DA: Depth-Averaged  
 \*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough: White capped or rougher.



**Appendix I - Action and Limit Levels for Marine Water Quality on 29 June 2018 (Mid-Ebb Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 6.0 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>C2: 6.5 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.2 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.8 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.2 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 6.8 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>C2: 8.2 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>C2: 8.8 mg/L</u>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.

**Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction**  
**Water Quality Monitoring Results on 29 June 2018**

**(Mid-Ebb Tide)**

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) |      | Temperature (°C) |             | pH         |              | Salinity ppt |                | DO Saturation (%) |            | Dissolved Oxygen (mg/L) |         |            | Turbidity (NTU) |         |            | Suspended Solids (mg/L) |         |     |
|----------|-------------------|-----------------|---------------|-----------|------|------------------|-------------|------------|--------------|--------------|----------------|-------------------|------------|-------------------------|---------|------------|-----------------|---------|------------|-------------------------|---------|-----|
|          |                   |                 |               |           |      | Value            | Average     | Value      | Average      | Value        | Average        | Value             | Average    | Value                   | Average | DA*        | Value           | Average | DA*        | Value                   | Average | DA* |
| C1       | Sunny             | Moderate        | 14:12         | Surface   | 1    | 26.8<br>26.7     | 26.8<br>7.8 | 7.8<br>7.8 | 29.4<br>29.5 | 29.5         | 86.3<br>84.8   | 85.6              | 5.9<br>5.8 | 5.9                     | 5.3     | 3.3<br>3.3 | 3.3             | 3.1     | 4.9<br>4.9 | 4.9                     | 5.0     |     |
|          |                   |                 |               | Middle    | 9.5  | 25.5<br>25.6     | 25.6<br>7.8 | 7.8<br>7.8 | 31.4<br>31.2 | 31.3         | 67.4<br>68.9   | 68.2              | 4.6<br>4.7 | 4.7                     |         | 3.1<br>3.2 | 3.2             |         | 5.0<br>5.1 | 5.1                     |         |     |
|          |                   |                 |               | Bottom    | 18   | 25.5<br>25.3     | 25.4<br>7.8 | 7.8<br>7.8 | 31.3<br>31.6 | 31.5         | 67.9<br>69.8   | 68.9              | 4.7<br>4.8 | 4.8                     |         | 3.0<br>2.8 | 2.9             |         | 5.1<br>5.0 | 5.1                     |         |     |
| C2       | Sunny             | Moderate        | 12:20         | Surface   | 1    | 27.6<br>27.6     | 27.6<br>7.8 | 7.9<br>7.9 | 28.6<br>28.5 | 28.6         | 102.1<br>103.5 | 102.8             | 6.9<br>7.0 | 7.0                     | 5.8     | 2.2<br>2.3 | 2.3             | 4.0     | 5.2<br>5.1 | 5.2                     | 6.1     |     |
|          |                   |                 |               | Middle    | 16.5 | 24.5<br>24.5     | 24.5<br>7.7 | 7.7<br>7.7 | 32.7<br>32.7 | 32.7         | 64.4<br>64.9   | 64.7              | 4.5<br>4.5 | 4.5                     |         | 5.1<br>4.4 | 4.8             |         | 6.4<br>6.2 | 6.3                     |         |     |
|          |                   |                 |               | Bottom    | 32   | 24.3<br>24.2     | 24.3<br>7.7 | 7.7<br>7.7 | 33.0<br>33.1 | 33.1         | 62.1<br>61.3   | 61.7              | 4.3<br>4.3 | 4.3                     |         | 5.2<br>4.8 | 5.0             |         | 6.7<br>6.9 | 6.8                     |         |     |
| G1       | Sunny             | Moderate        | 13:15         | Surface   | 1    | 26.8<br>27.1     | 27.0<br>8.0 | 8.0<br>8.0 | 30.7<br>30.6 | 30.7         | 119.5<br>120.2 | 119.9             | 8.0<br>8.1 | 8.1                     | 7.7     | 1.2<br>1.2 | 1.2             | 1.4     | 5.3<br>5.3 | 5.3                     | 5.1     |     |
|          |                   |                 |               | Middle    | 4    | 26.5<br>26.5     | 26.5<br>7.9 | 7.9<br>7.9 | 30.9<br>31.0 | 31.0         | 108.1<br>106.2 | 107.2             | 7.3<br>7.2 | 7.3                     |         | 1.0<br>1.0 | 1.0             |         | 5.4<br>5.3 | 5.4                     |         |     |
|          |                   |                 |               | Bottom    | 7    | 25.7<br>25.7     | 25.7<br>7.8 | 7.8<br>7.8 | 31.9<br>31.9 | 31.9         | 64.4<br>65.0   | 64.7              | 4.4<br>4.4 | 4.4                     |         | 2.0<br>1.8 | 1.9             |         | 4.7<br>4.6 | 4.7                     |         |     |
| G2       | Sunny             | Moderate        | 12:58         | Surface   | 1    | 27.7<br>27.6     | 27.7<br>8.0 | 8.0<br>8.0 | 30.1<br>30.1 | 30.1         | 136.1<br>136.0 | 136.1             | 9.1<br>9.1 | 9.1                     | 8.6     | 0.9<br>0.8 | 0.9             | 1.1     | 5.2<br>5.2 | 5.2                     | 6.6     |     |
|          |                   |                 |               | Middle    | 5    | 27.0<br>27.1     | 27.1<br>8.0 | 8.0<br>8.0 | 30.5<br>30.5 | 30.5         | 119.5<br>121.1 | 120.3             | 8.0<br>8.1 | 8.1                     |         | 0.9<br>0.9 | 0.9             |         | 8.4<br>8.3 | 8.4                     |         |     |
|          |                   |                 |               | Bottom    | 9    | 25.5<br>25.4     | 25.5<br>7.8 | 7.8<br>7.8 | 32.0<br>32.1 | 32.1         | 66.8<br>65.3   | 66.1              | 4.6<br>4.5 | 4.6                     |         | 1.5<br>1.5 | 1.5             |         | 6.3<br>6.1 | 6.2                     |         |     |
| G3       | Sunny             | Moderate        | 13:27         | Surface   | 1    | 27.2<br>27.3     | 27.3<br>7.8 | 7.8<br>7.8 | 30.7<br>30.6 | 30.7         | 92.6<br>91.6   | 92.1              | 6.2<br>6.1 | 6.2                     | 5.6     | 3.0<br>3.2 | 3.1             | 2.3     | 4.6<br>4.6 | 4.6                     | 4.7     |     |
|          |                   |                 |               | Middle    | 4    | 25.9<br>25.9     | 25.9<br>7.8 | 7.8<br>7.8 | 31.6<br>31.6 | 31.6         | 71.3<br>71.6   | 71.5              | 4.9<br>4.9 | 4.9                     |         | 1.9<br>1.9 | 1.9             |         | 5.0<br>4.8 | 4.9                     |         |     |
|          |                   |                 |               | Bottom    | 7    | 25.5<br>25.5     | 25.5<br>7.8 | 7.8<br>7.8 | 32.0<br>31.9 | 32.0         | 62.7<br>64.2   | 63.5              | 4.3<br>4.4 | 4.4                     |         | 1.8<br>1.7 | 1.8             |         | 4.6<br>4.6 | 4.6                     |         |     |
| G4       | Sunny             | Moderate        | 13:44         | Surface   | 1    | 26.8<br>26.9     | 26.9<br>8.0 | 8.0<br>8.0 | 30.4<br>30.4 | 30.4         | 115.1<br>116.3 | 115.7             | 7.8<br>7.8 | 7.8                     | 7.4     | 1.7<br>1.7 | 1.7             | 1.7     | 3.1<br>3.1 | 3.1                     | 5.0     |     |
|          |                   |                 |               | Middle    | 4    | 26.4<br>26.4     | 26.4<br>7.9 | 7.9<br>7.9 | 30.8<br>30.8 | 30.8         | 101.5<br>101.6 | 101.6             | 6.9<br>6.9 | 6.9                     |         | 1.8<br>1.9 | 1.9             |         | 5.1<br>5.1 | 5.1                     |         |     |
|          |                   |                 |               | Bottom    | 7    | 26.0<br>26.1     | 26.1<br>7.9 | 7.9<br>7.9 | 31.5<br>31.4 | 31.5         | 87.4<br>89.1   | 88.3              | 5.9<br>6.1 | 6.0                     |         | 1.4<br>1.3 | 1.4             |         | 6.8<br>6.5 | 6.7                     |         |     |
| M1       | Sunny             | Moderate        | 13:07         | Surface   | 1    | 27.6<br>27.6     | 27.6<br>7.9 | 7.9<br>7.9 | 30.3<br>30.3 | 30.3         | 115.9<br>116.8 | 116.4             | 7.7<br>7.8 | 7.8                     | 7.9     | 1.4<br>1.4 | 1.4             | 1.3     | 3.9<br>3.8 | 3.9                     | 5.3     |     |
|          |                   |                 |               | Middle    | 3    | 27.1<br>27.1     | 27.1<br>8.0 | 8.0<br>8.0 | 30.5<br>30.5 | 30.5         | 119.5<br>119.3 | 119.4             | 8.0<br>8.0 | 8.0                     |         | 1.3<br>1.3 | 1.3             |         | 5.2<br>5.3 | 5.3                     |         |     |
|          |                   |                 |               | Bottom    | 5    | 26.5<br>26.4     | 26.5<br>7.9 | 7.9<br>7.9 | 31.0<br>31.0 | 31.0         | 104.2<br>105.0 | 104.6             | 7.0<br>7.1 | 7.1                     |         | 1.3<br>1.2 | 1.3             |         | 6.8<br>6.6 | 6.7                     |         |     |
| M2       | Sunny             | Moderate        | 12:48         | Surface   | 1    | 27.6<br>27.6     | 27.6<br>8.0 | 8.0<br>8.0 | 30.0<br>30.0 | 30.0         | 134.2<br>134.1 | 134.2             | 9.0<br>8.9 | 9.0                     | 8.1     | 0.8<br>0.8 | 0.8             | 1.2     | 3.9<br>3.9 | 3.9                     | 3.5     |     |
|          |                   |                 |               | Middle    | 5.5  | 26.6<br>26.5     | 26.6<br>7.9 | 7.9<br>7.9 | 30.8<br>30.9 | 30.9         | 106.9<br>104.9 | 105.9             | 7.2<br>7.1 | 7.2                     |         | 1.1<br>1.2 | 1.2             |         | 3.0<br>3.1 | 3.1                     |         |     |
|          |                   |                 |               | Bottom    | 10   | 25.0<br>24.8     | 24.9<br>7.7 | 7.7<br>7.7 | 32.5<br>32.8 | 32.7         | 64.8<br>64.2   | 64.5              | 4.5<br>4.4 | 4.5                     |         | 1.7<br>1.6 | 1.7             |         | 3.5<br>3.4 | 3.5                     |         |     |
| M3       | Sunny             | Moderate        | 13:35         | Surface   | 1    | 27.1<br>27.1     | 27.1<br>7.8 | 7.8<br>7.8 | 30.8<br>30.8 | 30.8         | 81.9<br>86.4   | 84.2              | 5.5<br>5.8 | 5.7                     | 5.5     | 2.1<br>2.2 | 2.2             | 2.0     | 4.4<br>4.1 | 4.3                     | 4.5     |     |
|          |                   |                 |               | Middle    | 4    | 26.1<br>26.1     | 26.1<br>7.8 | 7.8<br>7.8 | 31.6<br>31.6 | 31.6         | 75.9<br>75.9   | 75.9              | 5.2<br>5.2 | 5.2                     |         | 1.7<br>1.8 | 1.8             |         | 3.9<br>3.5 | 3.7                     |         |     |
|          |                   |                 |               | Bottom    | 7    | 25.5<br>25.4     | 25.5<br>7.7 | 7.7<br>7.7 | 32.1<br>32.1 | 32.1         | 67.8<br>66.4   | 67.1              | 4.6<br>4.5 | 4.6                     |         | 1.9<br>2.0 | 2.0             |         | 5.5<br>5.6 | 5.6                     |         |     |
| M4       | Sunny             | Moderate        | 12:36         | Surface   | 1    | 27.9<br>27.9     | 27.9<br>8.0 | 8.0<br>8.0 | 30.2<br>30.2 | 30.2         | 128.7<br>131.3 | 130.0             | 8.5<br>8.7 | 8.6                     | 8.2     | 0.8<br>0.8 | 0.8             | 1.2     | 3.5<br>3.5 | 3.5                     | 4.4     |     |
|          |                   |                 |               | Middle    | 4.5  | 27.0<br>27.1     | 27.1<br>7.9 | 7.9<br>7.9 | 30.6<br>30.4 | 30.5         | 113.9<br>118.4 | 116.2             | 7.7<br>7.9 | 7.8                     |         | 1.3<br>1.1 | 1.2             |         | 3.5<br>3.4 | 3.5                     |         |     |
|          |                   |                 |               | Bottom    | 8    | 26.3<br>26.4     | 26.4<br>7.8 | 7.8<br>7.9 | 31.1<br>31.0 | 31.1         | 91.3<br>93.8   | 92.6              | 6.2<br>6.4 | 6.3                     |         | 1.4<br>1.6 | 1.5             |         | 6.3<br>6.3 | 6.3                     |         |     |
| M5       | Sunny             | Moderate        | 14:01         | Surface   | 1    | 26.7<br>26.7     | 26.7<br>7.9 | 7.9<br>7.9 | 29.9<br>29.9 | 29.9         | 92.9<br>92.5   | 92.7              | 6.3<br>6.3 | 6.3                     | 6.3     | 2.7<br>2.8 | 2.8             | 2.8     | 5.0<br>5.0 | 5.0                     | 5.2     |     |
|          |                   |                 |               | Middle    | 5    | 26.6<br>26.6     | 26.6<br>7.9 | 7.9<br>7.9 | 30.2<br>30.2 | 30.2         | 92.5<br>92.0   | 92.3              | 6.3<br>6.2 | 6.3                     |         | 2.7<br>2.7 | 2.7             |         | 5.1<br>5.2 | 5.2                     |         |     |
|          |                   |                 |               | Bottom    | 9    | 26.6<br>26.5     | 26.6<br>7.9 | 7.9<br>7.9 | 30.2<br>30.2 | 30.2         | 90.6<br>91.3   | 91.0              | 6.1<br>6.2 | 6.2                     |         | 2.7<br>2.8 | 2.8             |         | 5.4<br>5.4 | 5.4                     |         |     |
| M6       | Sunny             | Moderate        | 13:53         | Surface   | -    | -                | -           | -          | -            | -            | -              | -                 | -          | -                       | 7.3     | -          | -               | 1.6     | -          | -                       | 3.7     |     |
|          |                   |                 |               | Middle    | 2    | 26.6<br>26.6     | 26.6<br>7.9 | 7.9<br>7.9 | 30.6<br>30.6 | 30.6         | 107.8<br>107.2 | 107.5             | 7.3<br>7.2 | 7.3                     |         | 1.5<br>1.6 | 1.6             |         | 3.7<br>3.6 | 3.7                     |         |     |
|          |                   |                 |               | Bottom    | -    | -                | -           | -          | -            | -            | -              | -                 | -          | -                       |         | -          | -               |         | -          | -                       |         | -   |

Remarks: \*DA: Depth-Averaged  
\*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough: White capped or rougher.

**Appendix I - Action and Limit Levels for Marine Water Quality on 29 June 2018 (Mid-Flood Tide)**

| <b>Parameter<br/>(unit)</b>               | <b>Depth</b>                        | <b>Action Level</b>   | <b>Limit Level</b>  |
|---|-------------------------------------|---|---|
| DO in mg/L<br>(See Note 1 and 4)          | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Depth Average                       | <u>4.9 mg/L</u>   | <u>4.6 mg/L</u>   |
|   | Bottom                              | <u>4.2 mg/L</u>   | <u>3.6 mg/L</u>   |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>5.0 mg/L</u>   | <u>4.7 mg/L</u>   |
| Turbidity in<br>NTU<br>(See Note 2 and 4) | <b><u>Stations G1-G4, M1-M5</u></b> |   |   |
|   | Bottom                              | <u>19.3 NTU</u><br>or 120% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 4.7 NTU</u> | <u>22.2 NTU</u><br>or 130% of upstream control station's Turbidity at the same tide of the same day<br><u>CI: 5.1 NTU</u> |
|   | <b><u>Station M6</u></b>            |   |   |
|   | Intake Level                        | <u>19.0 NTU</u>   | <u>19.4 NTU</u>   |
|   | SS in mg/L<br>(See Note 2 and 4)    | <b><u>Stations G1-G4</u></b>  |   |
| Surface                                   |                                     | <u>6.0 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.6 mg/L</u>       | <u>6.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 7.2 mg/L</u>       |
| <b><u>Stations M1-M5</u></b>              |                                     |   |   |
| Surface                                   |                                     | <u>6.2 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 6.6 mg/L</u>       | <u>7.4 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 7.2 mg/L</u>       |
| <b><u>Stations G1-G4, M1-M5</u></b>       |                                     |   |   |
| Bottom                                    |                                     | <u>6.9 mg/L</u><br>or 120% of upstream control station's SS at the same tide of the same day<br><u>CI: 7.7 mg/L</u>       | <u>7.9 mg/L</u><br>or 130% of upstream control station's SS at the same tide of the same day<br><u>CI: 8.3 mg/L</u>       |
| <b><u>Station M6</u></b>                  |                                     |   |   |
| Intake Level                              | <u>8.3 mg/L</u>                     | <u>8.6 mg/L</u>   |   |

Notes:

1. For DO, non-compliance of the water quality limits occurs when monitoring result is lower than the limits.
2. For turbidity, SS, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.
3. All the figures given in the table are used for reference only and EPD may amend the figures whenever it is considered as necessary.
4. Action and limit values are derived based on baseline water quality monitoring results to show the actual baseline water quality condition.


Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction  
 Water Quality Monitoring Results on 29 June 2018

(Mid-Flood Tide)

| Location | Weather Condition | Sea Condition** | Sampling Time | Depth (m) |      | Temperature (°C) |         | pH         |         | Salinity ppt |         | DO Saturation (%) |            | Dissolved Oxygen (mg/L) |         |            | Turbidity (NTU) |         |            | Suspended Solids (mg/L) |         |     |
|----------|-------------------|-----------------|---------------|-----------|------|------------------|---------|------------|---------|--------------|---------|-------------------|------------|-------------------------|---------|------------|-----------------|---------|------------|-------------------------|---------|-----|
|          |                   |                 |               |           |      | Value            | Average | Value      | Average | Value        | Average | Value             | Average    | Value                   | Average | DA*        | Value           | Average | DA*        | Value                   | Average | DA* |
| C1       | Fine              | Moderate        | 21:10         | Surface   | 1    | 27.1<br>27.0     | 27.1    | 8.0<br>8.0 | 8.0     | 29.3<br>29.4 | 29.4    | 107.6             | 7.3<br>7.2 | 7.3                     | 6.0     | 1.2<br>1.2 | 1.2             | 2.4     | 5.4<br>5.6 | 5.5                     | 5.4     |     |
|          |                   |                 |               | Middle    | 9.5  | 24.8<br>24.8     | 24.8    | 7.8<br>7.8 | 7.8     | 32.5<br>32.5 | 32.5    | 68.4<br>68.2      | 68.3       | 4.7<br>4.7              |         | 4.7        | 2.0<br>1.9      |         | 2.0        | 4.4<br>4.4              |         | 4.4 |
|          |                   |                 |               | Bottom    | 18   | 23.4<br>23.4     | 23.4    | 7.8<br>7.8 | 7.8     | 33.8<br>33.8 | 33.8    | 62.3<br>62.3      | 62.3       | 4.4<br>4.4              |         | 4.4        | 3.8<br>3.9      |         | 3.9        | 6.2<br>6.5              |         | 6.4 |
| C2       | Fine              | Moderate        | 18:57         | Surface   | 1    | 27.3<br>27.3     | 27.3    | 8.0<br>8.0 | 8.0     | 29.7<br>29.7 | 29.7    | 123.0<br>124.1    | 123.6      | 8.3<br>8.3              | 8.3     | 7.1        | 1.8<br>1.8      | 1.8     | 1.8        | 2.8<br>2.8              | 2.8     | 3.5 |
|          |                   |                 |               | Middle    | 16.5 | 25.9<br>25.8     | 25.9    | 7.8<br>7.8 | 7.8     | 31.3<br>31.3 | 31.3    | 85.1<br>84.8      | 85.0       | 5.8<br>5.8              | 5.8     |            | 1.7<br>1.8      | 1.8     |            | 4.3<br>4.3              | 4.3     |     |
|          |                   |                 |               | Bottom    | 32   | 25.3<br>25.5     | 25.4    | 7.8<br>7.8 | 7.8     | 31.8<br>31.7 | 31.8    | 70.4<br>73.3      | 71.9       | 4.8<br>5.0              | 4.9     |            | 2.0<br>1.7      | 1.9     |            | 3.5<br>3.5              | 3.5     |     |
| G1       | Fine              | Moderate        | 20:00         | Surface   | 1    | 27.3<br>27.3     | 27.3    | 8.1<br>8.1 | 8.1     | 30.1<br>30.1 | 30.1    | 129.4<br>129.2    | 129.3      | 8.7<br>8.7              | 8.7     | 7.5        | 1.1<br>1.1      | 1.1     | 1.8        | 5.5<br>5.6              | 5.6     | 5.6 |
|          |                   |                 |               | Middle    | 4    | 26.3<br>26.3     | 26.3    | 7.9<br>7.9 | 7.9     | 31.0<br>31.0 | 31.0    | 88.0<br>93.2      | 90.6       | 6.0<br>6.3              | 6.2     |            | 2.1<br>2.1      | 2.1     |            | 5.5<br>5.5              | 5.5     |     |
|          |                   |                 |               | Bottom    | 7    | 24.6<br>24.6     | 24.6    | 7.8<br>7.8 | 7.8     | 32.6<br>32.6 | 32.6    | 68.2<br>67.6      | 67.9       | 4.7<br>4.7              | 4.7     |            | 2.2<br>2.2      | 2.2     |            | 5.7<br>5.7              | 5.7     |     |
| G2       | Fine              | Moderate        | 19:33         | Surface   | 1    | 27.3<br>27.3     | 27.3    | 8.1<br>8.0 | 8.1     | 30.3<br>30.3 | 30.3    | 128.6<br>127.8    | 128.2      | 8.6<br>8.6              | 8.6     | 7.0        | 1.2<br>1.2      | 1.2     | 2.4        | 4.1<br>4.1              | 4.1     | 5.4 |
|          |                   |                 |               | Middle    | 5    | 25.7<br>25.4     | 25.6    | 7.9<br>7.8 | 7.9     | 31.4<br>31.7 | 31.6    | 78.3<br>78.5      | 78.4       | 5.4<br>5.4              | 5.4     |            | 1.9<br>1.7      | 1.8     |            | 5.3<br>5.5              | 5.4     |     |
|          |                   |                 |               | Bottom    | 9    | 24.1<br>24.1     | 24.1    | 7.7<br>7.7 | 7.7     | 33.2<br>33.2 | 33.2    | 69.5<br>67.4      | 68.5       | 4.8<br>4.7              | 4.8     |            | 4.3<br>4.2      | 4.3     |            | 6.6<br>6.5              | 6.6     |     |
| G3       | Fine              | Moderate        | 20:13         | Surface   | 1    | 27.3<br>27.3     | 27.3    | 8.1<br>8.1 | 8.1     | 30.0<br>30.0 | 30.0    | 127.0<br>126.9    | 127.0      | 8.5<br>8.5              | 8.5     | 7.4        | 1.2<br>1.2      | 1.2     | 1.8        | 5.1<br>5.1              | 5.1     | 5.2 |
|          |                   |                 |               | Middle    | 4    | 26.5<br>26.3     | 26.4    | 7.9<br>7.9 | 7.9     | 30.9<br>31.0 | 31.0    | 91.7<br>91.0      | 91.4       | 6.2<br>6.2              | 6.2     |            | 2.3<br>2.2      | 2.3     |            | 4.7<br>4.7              | 4.7     |     |
|          |                   |                 |               | Bottom    | 7    | 24.6<br>24.5     | 24.6    | 7.8<br>7.8 | 7.8     | 32.6<br>32.6 | 32.6    | 66.3<br>65.9      | 66.1       | 4.6<br>4.6              | 4.6     |            | 1.8<br>2.0      | 1.9     |            | 5.8<br>5.8              | 5.8     |     |
| G4       | Fine              | Moderate        | 20:38         | Surface   | 1    | 27.3<br>27.3     | 27.3    | 8.1<br>8.1 | 8.1     | 30.1<br>30.1 | 30.1    | 127.6<br>127.5    | 127.6      | 8.6<br>8.5              | 8.6     | 7.2        | 1.1<br>1.1      | 1.1     | 2.5        | 5.4<br>5.5              | 5.5     | 5.7 |
|          |                   |                 |               | Middle    | 4    | 26.2<br>26.2     | 26.2    | 7.9<br>7.9 | 7.9     | 31.1<br>31.1 | 31.1    | 85.8<br>86.0      | 86.0       | 5.8<br>5.8              | 5.8     |            | 2.9<br>2.6      | 2.9     |            | 5.5<br>5.5              | 5.5     |     |
|          |                   |                 |               | Bottom    | 7    | 24.7<br>24.7     | 24.7    | 7.8<br>7.8 | 7.8     | 32.5<br>32.5 | 32.5    | 68.0<br>65.2      | 65.6       | 4.6<br>4.5              | 4.6     |            | 3.2<br>3.7      | 3.5     |            | 6.2<br>6.1              | 6.2     |     |
| M1       | Fine              | Moderate        | 19:50         | Surface   | 1    | 27.4<br>27.4     | 27.4    | 8.1<br>8.1 | 8.1     | 30.1<br>30.1 | 30.1    | 130.3<br>130.0    | 130.2      | 8.7<br>8.7              | 8.7     | 8.7        | 1.3<br>1.3      | 1.3     | 2.1        | 3.5<br>3.5              | 3.5     | 5.0 |
|          |                   |                 |               | Middle    | 3    | 27.4<br>27.4     | 27.4    | 8.1<br>8.1 | 8.1     | 30.3<br>30.3 | 30.3    | 129.1<br>129.4    | 129.3      | 8.6<br>8.7              | 8.7     |            | 1.4<br>1.4      | 1.4     |            | 7.4<br>7.7              | 7.6     |     |
|          |                   |                 |               | Bottom    | 5    | 25.5<br>25.5     | 25.5    | 7.8<br>7.8 | 7.8     | 31.7<br>31.7 | 31.7    | 79.8<br>79.7      | 79.8       | 5.5<br>5.5              | 5.5     |            | 3.5<br>3.9      | 3.7     |            | 3.7<br>3.8              | 3.8     |     |
| M2       | Fine              | Moderate        | 19:21         | Surface   | 1    | 27.5<br>27.4     | 27.5    | 8.1<br>8.1 | 8.1     | 30.2<br>30.2 | 30.2    | 146.1<br>144.2    | 145.2      | 9.8<br>9.6              | 9.7     | 7.1        | 0.9<br>0.9      | 0.9     | 2.5        | 3.3<br>3.4              | 3.4     | 5.0 |
|          |                   |                 |               | Middle    | 5.5  | 25.0<br>25.0     | 25.0    | 7.8<br>7.8 | 7.8     | 32.2<br>32.3 | 32.3    | 65.4<br>64.7      | 65.1       | 4.5<br>4.5              | 4.5     |            | 2.3<br>2.3      | 2.3     |            | 5.7<br>5.6              | 5.7     |     |
|          |                   |                 |               | Bottom    | 10   | 24.2<br>24.2     | 24.2    | 7.7<br>7.7 | 7.7     | 33.2<br>33.3 | 33.3    | 63.9<br>63.5      | 63.7       | 4.4<br>4.4              | 4.4     |            | 4.4<br>4.2      | 4.3     |            | 5.6<br>5.9              | 5.8     |     |
| M3       | Fine              | Moderate        | 20:23         | Surface   | 1    | 27.3<br>27.3     | 27.3    | 8.1<br>8.1 | 8.1     | 30.0<br>30.0 | 30.0    | 126.0<br>126.1    | 126.1      | 8.4<br>8.5              | 8.5     | 6.5        | 1.2<br>1.2      | 1.2     | 2.8        | 3.8<br>3.8              | 3.8     | 4.8 |
|          |                   |                 |               | Middle    | 4    | 25.4<br>25.4     | 25.4    | 7.8<br>7.8 | 7.8     | 31.9<br>31.9 | 31.9    | 63.6<br>63.5      | 63.6       | 4.4<br>4.4              | 4.4     |            | 5.0<br>4.9      | 5.0     |            | 4.5<br>4.6              | 4.6     |     |
|          |                   |                 |               | Bottom    | 7    | 24.5<br>24.5     | 24.5    | 7.8<br>7.8 | 7.8     | 32.7<br>32.7 | 32.7    | 64.8<br>64.4      | 64.6       | 4.5<br>4.5              | 4.5     |            | 2.1<br>2.3      | 2.2     |            | 5.9<br>5.9              | 5.9     |     |
| M4       | Fine              | Moderate        | 19:10         | Surface   | 1    | 27.5<br>27.4     | 27.5    | 8.1<br>8.1 | 8.1     | 30.3<br>30.3 | 30.3    | 144.9<br>141.3    | 143.1      | 9.7<br>9.4              | 9.6     | 8.5        | 0.9<br>1.0      | 1.0     | 1.8        | 4.5<br>4.4              | 4.5     | 4.7 |
|          |                   |                 |               | Middle    | 5    | 26.6<br>26.5     | 26.6    | 7.9<br>7.9 | 7.9     | 30.6<br>30.7 | 30.7    | 108.5<br>105.9    | 107.2      | 7.3<br>7.2              | 7.3     |            | 1.5<br>1.6      | 1.6     |            | 4.2<br>4.1              | 4.2     |     |
|          |                   |                 |               | Bottom    | 9    | 25.8<br>25.8     | 25.8    | 7.9<br>7.8 | 7.9     | 31.4<br>31.4 | 31.4    | 82.1<br>80.8      | 81.5       | 5.6<br>5.5              | 5.6     |            | 3.0<br>2.8      | 2.9     |            | 5.2<br>5.3              | 5.3     |     |
| M5       | Fine              | Moderate        | 20:57         | Surface   | 1    | 27.0<br>27.0     | 27.0    | 8.0<br>8.0 | 8.0     | 29.7<br>29.8 | 29.8    | 110.0<br>109.7    | 109.9      | 7.4<br>7.4              | 7.4     | 6.4        | 2.0<br>1.8      | 1.9     | 3.2        | 5.1<br>5.1              | 5.1     | 4.3 |
|          |                   |                 |               | Middle    | 5    | 25.7<br>25.9     | 25.8    | 7.8<br>7.9 | 7.9     | 31.6<br>31.4 | 31.5    | 75.9<br>77.4      | 76.7       | 5.2<br>5.3              | 5.3     |            | 3.3<br>3.3      | 3.3     |            | 4.1<br>4.2              | 4.2     |     |
|          |                   |                 |               | Bottom    | 9    | 24.2<br>24.2     | 24.2    | 7.8<br>7.8 | 7.8     | 33.0<br>33.0 | 33.0    | 63.1<br>62.5      | 62.8       | 4.4<br>4.3              | 4.4     |            | 4.2<br>4.4      | 4.3     |            | 3.6<br>3.5              | 3.6     |     |
| M6       | Fine              | Moderate        | 20:49         | Surface   | -    | -                | -       | -          | -       | -            | -       | -                 | -          | -                       | 8.4     | -          | -               | 1.1     | -          | -                       | 4.7     |     |
|          |                   |                 |               | Middle    | 2.1  | 27.2<br>27.2     | 27.2    | 8.1<br>8.1 | 8.1     | 30.0<br>30.0 | 30.0    | 125.0<br>124.9    | 125.0      | 8.4<br>8.4              |         | 8.4        | 1.2<br>1.0      |         | 1.1        | 4.7<br>4.7              |         | 4.7 |
|          |                   |                 |               | Bottom    | -    | -                | -       | -          | -       | -            | -       | -                 | -          | -                       |         | -          | -               |         | -          | -                       |         | -   |

Remarks: \*DA: Depth-Averaged  
 \*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

## Dissolved Oxygen (Depth-averaged) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Dissolved Oxygen (Depth-averaged) at Mid-Ebb Tide




**Title**  
 Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction  
 Graphical Presentation of Water Quality Monitoring Results

**Scale**  
 N.T.S  
**Date**  
 Jun 18

**Project No.**  
 MA16034  
**Appendix**  
 I



## Dissolved Oxygen (Depth-averaged) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Dissolved Oxygen (Depth-averaged) at Mid-Ebb Tide



**Title**  
 Agreement No. CE 59/2015(EP) Environmental Team for  
 Tseung Kwan O - Lam Tin Tunnel Design and Construction  
 Graphical Presentation of Water Quality Monitoring  
 Results


**Scale**  
 N.T.S  
**Date**  
 Jun 18

**Project No.**  
 MA16034  
**Appendix**  
 I





## Dissolved Oxygen (Depth-averaged) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Dissolved Oxygen (Depth-averaged) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S




Date Jun 18

Project No. MA16034

Appendix I



## Dissolved Oxygen (Depth-averaged) at Mid-Flood Tide




**Title**  
 Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction  
 Graphical Presentation of Water Quality Monitoring Results

**Scale**  
 N.T.S  
**Date**  
 Jun 18

**Project No.**  
 MA16034  
**Appendix**  
 I






## Dissolved Oxygen (Depth-averaged) at Mid-Flood Tide



|       |  |                |                        |                 |
|-------|--|----------------|------------------------|-----------------|
| Title | Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction | Scale<br>N.T.S | Project No.<br>MA16034 | <b>CINOTECH</b> |
|       | Graphical Presentation of Water Quality Monitoring Results   | Date<br>Jun 18 | Appendix<br>I          |                 |


## Dissolved Oxygen (Bottom) at Mid-Ebb Tide



|              |  |              |        |                    |         |
|--------------|--|--------------|--------|--------------------|---------|
| <b>Title</b> | Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction | <b>Scale</b> | N.T.S  | <b>Project No.</b> | MA16034 |
|              | Graphical Presentation of Water Quality Monitoring Results   | <b>Date</b>  | Jun 18 | <b>Appendix</b>    | I       |

CINOTECH

## Dissolved Oxygen (Bottom) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Dissolved Oxygen (Bottom) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Dissolved Oxygen (Bottom) at Mid-Ebb Tide



**Title**  
 Agreement No. CE 59/2015(EP) Environmental Team for  
 Tseung Kwan O - Lam Tin Tunnel Design and Construction  
 Graphical Presentation of Water Quality Monitoring  
 Results


**Scale**  
 N.T.S  
**Date**  
 Jun 18

**Project No.**  
 MA16034  
**Appendix**  
 I





## Dissolved Oxygen (Bottom) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Dissolved Oxygen (Bottom) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S




Date Jun 18

Project No. MA16034

Appendix I



## Dissolved Oxygen (Bottom) at Mid-Flood Tide



**Title**  
 Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

**Scale**  
 N.T.S


**Date**  
 Jun 18

**Project No.**  
 MA16034

**Appendix**  
 I



## Dissolved Oxygen (Bottom) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I




## Dissolved Oxygen (Intake Level of WSD Salt Water Intake) at Mid-Ebb Tide




|       |  |       |        |             |         |                 |
|-------|--|-------|--------|-------------|---------|-----------------|
| Title | Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction | Scale | N.T.S  | Project No. | MA16034 | <b>CINOTECH</b> |
|       | Graphical Presentation of Water Quality Monitoring Results   | Date  | Jun 18 | Appendix    | I       |                 |

## Dissolved Oxygen (Intake Level of WSD Salt Water Intake) at Mid-Flood Tide



|   |                |                        |          |
|---|----------------|------------------------|----------|
| Title<br>Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction<br><br>Graphical Presentation of Water Quality Monitoring Results | Scale<br>N.T.S | Project No.<br>MA16034 | CINOTECH |
|   | Date<br>Jun 18 | Appendix<br>I          |          |

## Turbidity (Depth-averaged) at Mid-Ebb Tide




**Title**  
 Agreement No. CE 59/2015(EP) Environmental Team for  
 Tseung Kwan O - Lam Tin Tunnel Design and Construction  
 Graphical Presentation of Water Quality Monitoring  
 Results

**Scale**  
 N.T.S  
**Date**  
 Jun 18

**Project No.**  
 MA16034  
**Appendix**  
 I



## Turbidity (Depth-averaged) at Mid-Ebb Tide



**Title**  
 Agreement No. CE 59/2015(EP) Environmental Team for  
 Tseung Kwan O - Lam Tin Tunnel Design and Construction  
 Graphical Presentation of Water Quality Monitoring  
 Results


**Scale**  
 N.T.S  
**Date**  
 Jun 18

**Project No.**  
 MA16034  
**Appendix**  
 I





## Turbidity (Depth-averaged) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I




### Turbidity (Depth-averaged) at Mid-Ebb Tide



|   |                |                        |                 |
|---|----------------|------------------------|-----------------|
| Title<br>Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction<br><br>Graphical Presentation of Water Quality Monitoring Results | Scale<br>N.T.S | Project No.<br>MA16034 | <b>CINOTECH</b> |
|   | Date<br>Jun 18 | Appendix<br>I          |                 |

## Turbidity (Depth-averaged) at Mid-Flood Tide




**Title**  
 Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction  
 Graphical Presentation of Water Quality Monitoring Results

**Scale**  
 N.T.S  
**Date**  
 Jun 18

**Project No.**  
 MA16034  
**Appendix**  
 I



## Turbidity (Depth-averaged) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Turbidity (Depth-averaged) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I




## Turbidity (Depth-averaged) at Mid-Flood Tide



|   |                |                        |  |
|---|----------------|------------------------|--|
| Title<br>Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction<br><br>Graphical Presentation of Water Quality Monitoring Results | Scale<br>N.T.S | Project No.<br>MA16034 |  |
|   | Date<br>Jun 18 | Appendix<br>I          |  |

## Turbidity (Bottom) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Turbidity (Bottom) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S

Date Jun 18


Project No. MA16034

Appendix I





## Turbidity (Bottom) at Mid-Ebb Tide




Title  
 Agreement No. CE 59/2015(EP) Environmental Team for  
 Tseung Kwan O - Lam Tin Tunnel Design and Construction  
 Graphical Presentation of Water Quality Monitoring  
 Results

Scale  
 N.T.S  
 Date  
 Jun 18

Project  
 No. MA16034  
 Appendix  
 I



## Turbidity (Bottom) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Turbidity (Bottom) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S




Date Jun 18

Project No. MA16034

Appendix I



## Turbidity (Bottom) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Turbidity (Bottom) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Turbidity (Bottom) at Mid-Flood Tide



Title

Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale

N.T.S

Date

Jun 18

Project No.


MA16034

Appendix

I

**CINOTECH**


## Turbidity (Intake Level of WSD Salt Water Intake) at Mid-Ebb Tide



|   |       |        |             |         |
|---|-------|--------|-------------|---------|
| Title<br>Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction<br><br>Graphical Presentation of Water Quality Monitoring Results | Scale | N.T.S  | Project No. | MA16034 |
|   | Date  | Jun 18 | Appendix    | I       |

CINOTECH


## Turbidity (Intake Level of WSD Salt Water Intake) at Mid-Flood Tide



|       |  |       |        |             |         |                 |
|-------|--|-------|--------|-------------|---------|-----------------|
| Title | Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction | Scale | N.T.S  | Project No. | MA16034 | <b>CINOTECH</b> |
|       | Graphical Presentation of Water Quality Monitoring Results   | Date  | Jun 18 | Appendix    | I       |                 |



## Suspended Solids (Depth-averaged) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Suspended Solids (Depth-averaged) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Suspended Solids (Depth-averaged) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I




## Suspended Solids (Depth-averaged) at Mid-Ebb Tide



|       |  |       |        |             |         |          |
|-------|--|-------|--------|-------------|---------|----------|
| Title | Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction | Scale | N.T.S  | Project No. | MA16034 | CINOTECH |
|       | Graphical Presentation of Water Quality Monitoring Results   | Date  | Jun 18 | Appendix    | I       |          |

## Suspended Solids (Depth-averaged) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Suspended Solids (Depth-averaged) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Suspended Solids (Depth-averaged) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Suspended Solids (Depth-averaged) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S

Date Jun 18


Project No. MA16034

Appendix I





## Suspended Solids (Surface) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S




Date Jun 18

Project No. MA16034

Appendix I



## Suspended Solids (Surface) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Suspended Solids (Surface) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Suspended Solids (Surface) at Mid-Ebb Tide



Title

Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale

N.T.S

Date

Jun 18

Project No.


MA16034

Appendix

I

**CINOTECH**

## Suspended Solids (Surface) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Suspended Solids (Surface) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Suspended Solids (Surface) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Suspended Solids (Surface) at Mid-Flood Tide



Title

Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale

N.T.S

Date

Jun 18

Project No.

MA16034




Appendix

I

**CINOTECH**



## Suspended Solids (Bottom) at Mid-Ebb Tide




**Title**  
 Agreement No. CE 59/2015(EP) Environmental Team for  
 Tseung Kwan O - Lam Tin Tunnel Design and Construction  
 Graphical Presentation of Water Quality Monitoring  
 Results

**Scale**  
 N.T.S  
**Date**  
 Jun 18

**Project No.**  
 MA16034  
**Appendix**  
 I



## Suspended Solids (Bottom) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Suspended Solids (Bottom) at Mid-Ebb Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S


Date Jun 18

Project No. MA16034

Appendix I



## Suspended Solids (Bottom) at Mid-Ebb Tide



Title

Agreement No. CE 59/2015(EP) Environmental Team for  
Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring  
Results

Scale

N.T.S

Date




Jun 18

Project  
No. MA16034

Appendix  
I

CINOTECH

## Suspended Solids (Bottom) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S




Date Jun 18

Project No. MA16034

Appendix I



## Suspended Solids (Bottom) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S




Date Jun 18

Project No. MA16034

Appendix I



## Suspended Solids (Bottom) at Mid-Flood Tide




Title  
 Agreement No. CE 59/2015(EP) Environmental Team for  
 Tseung Kwan O - Lam Tin Tunnel Design and Construction  
 Graphical Presentation of Water Quality Monitoring  
 Results

Scale  
 N.T.S  
 Date  
 Jun 18

Project  
 No. MA16034  
 Appendix  
 I



## Suspended Solids (Bottom) at Mid-Flood Tide



Title Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction

Graphical Presentation of Water Quality Monitoring Results

Scale N.T.S

Date Jun 18


Project No. MA16034

Appendix I






## Suspended Solids (Intake Level of WSD Salt Water Intake) at Mid-Ebb Tide



|   |                |                        |          |
|---|----------------|------------------------|----------|
| Title<br>Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction<br><br>Graphical Presentation of Water Quality Monitoring Results | Scale<br>N.T.S | Project No.<br>MA16034 | CINOTECH |
|   | Date<br>Jun 18 | Appendix<br>I          |          |

## Suspended Solids (Intake Level of WSD Salt Water Intake) at Mid-Flood Tide



|   |       |        |             |         |
|---|-------|--------|-------------|---------|
| Title<br>Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction<br><br>Graphical Presentation of Water Quality Monitoring Results | Scale | N.T.S  | Project No. | MA16034 |
|   | Date  | Jun 18 | Appendix    | I       |

CINOTECH

### Water Quality Monitoring Results at W1 - Mid-Ebb Tide

| Date      | Weather Condition | Sea Condition** | Sampling Time | Depth (m) |     | Temperature (°C) |         | pH         |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         |     |
|-----------|-------------------|-----------------|---------------|-----------|-----|------------------|---------|------------|---------|--------------|---------|-------------------|---------|-------------------------|---------|-----|
|           |                   |                 |               |           |     | Value            | Average | Value      | Average | Value        | Average | Value             | Average | Value                   | Average | DA* |
| 5-Jun-18  | Rainy             | Moderate        | 16:03         | Surface   | 1   | 27.4<br>27.4     | 27.4    | 8.1<br>8.1 | 8.1     | 31.4<br>31.4 | 31.4    | 86.3<br>86.3      | 86.3    | 5.7<br>5.7              | 5.7     | 5.7 |
|           |                   |                 |               | Middle    | -   | -                | -       | -          | -       | -            | -       | -                 | -       | -                       | -       |     |
|           |                   |                 |               | Bottom    | 3.1 | 27.4<br>27.4     | 27.4    | 8.1<br>8.2 | 8.2     | 31.4<br>31.5 | 31.5    | 86.0<br>85.3      | 85.7    | 5.7<br>5.7              | 5.7     |     |
| 12-Jun-18 | Cloudy            | Calm            | 12:18         | Surface   | 1   | 27.8<br>27.8     | 27.8    | 8.2<br>8.2 | 8.2     | 29.4<br>29.2 | 29.3    | 86.3<br>88.2      | 87.3    | 5.8<br>5.9              | 5.9     | 5.9 |
|           |                   |                 |               | Middle    | -   | -                | -       | -          | -       | -            | -       | -                 | -       | -                       |         |     |
|           |                   |                 |               | Bottom    | 2.1 | 27.8<br>27.8     | 27.8    | 8.2<br>8.2 | 8.2     | 29.4<br>29.4 | 29.4    | 84.9<br>85.0      | 85.0    | 5.7<br>5.7              | 5.7     |     |
| 20-Jun-18 | Sunny             | Calm            | 16:31         | Surface   | 1   | 29.0<br>29.0     | 29.0    | 8.2<br>8.2 | 8.2     | 30.2<br>30.2 | 30.2    | 98.1<br>98.5      | 98.3    | 6.4<br>6.4              | 6.4     | 6.4 |
|           |                   |                 |               | Middle    | -   | -                | -       | -          | -       | -            | -       | -                 | -       | -                       |         |     |
|           |                   |                 |               | Bottom    | 3.1 | 29.0<br>29.0     | 29.0    | 8.1<br>8.1 | 8.1     | 30.3<br>30.3 | 30.3    | 96.7<br>96.6      | 96.7    | 6.3<br>6.3              | 6.3     |     |
| 26-Jun-18 | Sunny             | Calm            | 11:58         | Surface   | 1   | 29.2<br>29.2     | 29.2    | 8.4<br>8.4 | 8.4     | 26.4<br>26.4 | 26.4    | 115.6<br>115.5    | 115.6   | 7.7<br>7.7              | 7.7     | 7.7 |
|           |                   |                 |               | Middle    | -   | -                | -       | -          | -       | -            | -       | -                 | -       | -                       |         |     |
|           |                   |                 |               | Bottom    | 2.9 | 28.7<br>28.7     | 28.7    | 8.3<br>8.3 | 8.3     | 27.0<br>27.0 | 27.0    | 95.0<br>94.5      | 94.8    | 6.3<br>6.3              | 6.3     |     |


### Water Quality Monitoring Results at W1 - Mid-Flood Tide

| Date      | Weather Condition | Sea Condition** | Sampling Time | Depth (m) |     | Temperature (°C) |         | pH         |         | Salinity ppt |         | DO Saturation (%) |         | Dissolved Oxygen (mg/L) |         |     |
|-----------|-------------------|-----------------|---------------|-----------|-----|------------------|---------|------------|---------|--------------|---------|-------------------|---------|-------------------------|---------|-----|
|           |                   |                 |               |           |     | Value            | Average | Value      | Average | Value        | Average | Value             | Average | Value                   | Average | DA* |
| 5-Jun-18  | Rainy             | Moderate        | 09:52         | Surface   | 1   | 27.4<br>27.4     | 27.4    | 8.1<br>8.1 | 8.1     | 31.4<br>31.2 | 31.3    | 86.3<br>86.4      | 86.4    | 5.7<br>5.7              | 5.7     | 5.7 |
|           |                   |                 |               | Middle    | -   | -                | -       | -          | -       | -            | -       | -                 | -       | -                       |         |     |
|           |                   |                 |               | Bottom    | 3.1 | 27.3<br>27.4     | 27.4    | 8.1<br>8.2 | 8.2     | 31.5<br>31.4 | 31.5    | 84.5<br>84.6      | 84.6    | 5.6<br>5.6              | 5.6     |     |
| 12-Jun-18 | Rainy             | Calm            | 16:21         | Surface   | 1   | 27.7<br>27.7     | 27.7    | 8.2<br>8.2 | 8.2     | 29.4<br>29.4 | 29.4    | 85.5<br>85.4      | 85.5    | 5.7<br>5.7              | 5.7     | 5.7 |
|           |                   |                 |               | Middle    | -   | -                | -       | -          | -       | -            | -       | -                 | -       | -                       |         |     |
|           |                   |                 |               | Bottom    | 2   | 27.7<br>27.7     | 27.7    | 8.2<br>8.2 | 8.2     | 29.4<br>29.4 | 29.4    | 84.4<br>84.6      | 84.5    | 5.6<br>5.7              | 5.7     |     |
| 20-Jun-18 | Sunny             | Calm            | 10:06         | Surface   | 1   | 28.7<br>28.7     | 28.7    | 8.2<br>8.2 | 8.2     | 30.3<br>30.2 | 30.3    | 97.2<br>97.7      | 97.5    | 6.3<br>6.4              | 6.4     | 6.4 |
|           |                   |                 |               | Middle    | -   | -                | -       | -          | -       | -            | -       | -                 | -       | -                       |         |     |
|           |                   |                 |               | Bottom    | 3.1 | 28.7<br>28.6     | 28.7    | 8.1<br>8.1 | 8.1     | 30.3<br>30.3 | 30.3    | 97.6<br>96.8      | 97.2    | 6.4<br>6.3              | 6.4     |     |
| 26-Jun-18 | Sunny             | Calm            | 17:30         | Surface   | 1   | 29.1<br>29.1     | 29.1    | 8.3<br>8.3 | 8.3     | 26.4<br>26.4 | 26.4    | 112.0<br>112.5    | 112.3   | 7.5<br>7.4              | 7.5     | 7.5 |
|           |                   |                 |               | Middle    | -   | -                | -       | -          | -       | -            | -       | -                 | -       | -                       |         |     |
|           |                   |                 |               | Bottom    | 3.1 | 29.0<br>28.9     | 29.0    | 8.3<br>8.3 | 8.3     | 26.6<br>26.7 | 26.7    | 96.8<br>95.4      | 96.1    | 6.4<br>6.3              | 6.4     |     |


Remarks: \*DA: Depth-Averaged

\*\*Calm: Small or no wave; Moderate: Between calm and rough; Rough : White capped or rougher.

### Dissolved Oxygen (Depth-Averaged) at Mid-Ebb Tide




### Dissolved Oxygen (Depth-Averaged) at Mid-Flood Tide




|       |  |       |        |             |         |                 |
|-------|--|-------|--------|-------------|---------|-----------------|
| Title | Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction | Scale | N.T.S  | Project No. | MA16034 | <b>CINOTECH</b> |
|       | Graphical Presentation of Additional Water Quality Monitoring Results                                      | Date  | Jun 18 | Appendix    | I       |                 |

### Dissolved Oxygen (Bottom) at Mid-Ebb Tide



### Dissolved Oxygen (Bottom) at Mid-Flood Tide



|       |  |       |        |             |         |                 |
|-------|--|-------|--------|-------------|---------|-----------------|
| Title | Agreement No. CE 59/2015(EP) Environmental Team for Tseung Kwan O - Lam Tin Tunnel Design and Construction | Scale | N.T.S  | Project No. | MA16034 | <b>CINOTECH</b> |
|       | Graphical Presentation of Additional Water Quality Monitoring Results                                      | Date  | Jun 18 | Appendix    | I       |                 |

---

---

**APPENDIX J  
QUALITY CONTROL REPORTS FOR  
LABORATORY ANALYSIS**

---

---

## TEST REPORT

**APPLICANT:** Cinotech Consultants Limited  
1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T.

|                 |            |
|-----------------|------------|
| Report No.:     | QC29033    |
| Date of Issue:  | 2018-06-14 |
| Date Received:  | 2018-06-05 |
| Date Tested:    | 2018-06-05 |
| Date Completed: | 2018-06-14 |

**ATTN:** Ms. Mei Ling Tang  
**QC report:**

Page: 1 of 2

### Method Blank

| Parameter                                     | MB 1  | Acceptance |
|---|-------|------------|
| Suspended Solids (SS) (mg/L)                  | <0.5  | <0.5       |
| Biochemical Oxygen Demand                     | N/A   | N/A        |
| Total Organic Carbon (mg-TOC/L)               | <0.2  | <0.2       |
| Nitrogen (Total Kjeldahl + nitrate + nitrite) | N/A   | N/A        |
| Ammonia (mg NH <sub>3</sub> -N/L)             | <0.01 | <0.01      |
| Total Phosphorus (mg-P/L)                     | <0.01 | <0.01      |

### Method QC

| Parameter  | MQC1 | Acceptance |
|--|------|------------|
| Suspended Solids (SS) (%)                        | 101  | 80-120     |
| Biochemical Oxygen Demand (mg O <sub>2</sub> /L) | 215  | 170-220    |
| Total Organic Carbon (%)                         | 108  | 80-120     |
| Nitrogen (Total Kjeldahl + nitrate + nitrite)    | N/A  | N/A        |
| Ammonia (%)                                      | 115  | 80-120     |
| Total Phosphorus (%)                             | 109  | 80-120     |

Remarks: 1) <= less than

2) N/A = Not applicable

3) This report is the summary of quality control data for report number 29033.

\*\*\*\*\*

*PREPARED AND CHECKED BY:*

For and On Behalf of **WELLAB Ltd.**

  
\_\_\_\_\_  
**PATRICK TSE**  
Laboratory Manager

## TEST REPORT

|                 |            |
|-----------------|------------|
| Report No.:     | QC29033    |
| Date of Issue:  | 2018-06-14 |
| Date Received:  | 2018-06-05 |
| Date Tested:    | 2018-06-05 |
| Date Completed: | 2018-06-14 |

Page: 2 of 2

### QC report:

#### Sample Duplicate

| Parameter                                     | 29033-3 chk | Acceptance     |
|---|-------------|----------------|
| Suspended Solids (SS) (%)                     | 2           | RPD $\leq$ 20% |
| Biochemical Oxygen Demand (%)                 | N/A         | RPD $\leq$ 20% |
| Total Organic Carbon (%)                      | 1           | RPD $\leq$ 20% |
| Nitrogen (Total Kjeldahl + nitrate + nitrite) | N/A         | N/A            |
| Ammonia (%)                                   | N/A         | RPD $\leq$ 20% |
| Total Phosphorus (%)                          | 3           | RPD $\leq$ 20% |

#### Sample Spike

| Parameter                                     | 29033-3 spk | Acceptance |
|---|-------------|------------|
| Suspended Solids (SS) (%)                     | N/A         | N/A        |
| Biochemical Oxygen Demand (%)                 | N/A         | N/A        |
| Total Organic Carbon (%)                      | 109         | 80-120     |
| Nitrogen (Total Kjeldahl + nitrate + nitrite) | N/A         | N/A        |
| Ammonia (%)                                   | 96          | 80-120     |
| Total Phosphorus (%)                          | 97          | 80-120     |

Remarks: 1)  $\leq$  less than

2) N/A = Not applicable

3) This report is the summary of quality control data for report number 29033.

\*\*\*\*\*END OF REPORT\*\*\*\*\*



**TEST REPORT**

**APPLICANT:** Cinotech Consultants Limited  
1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T.

|                 |            |
|-----------------|------------|
| Report No.:     | QC29129    |
| Date of Issue:  | 2018-06-29 |
| Date Received:  | 2018-06-20 |
| Date Tested:    | 2018-06-20 |
| Date Completed: | 2018-06-29 |

**ATTN:** Ms. Mei Ling Tang  
**QC report:**

Page: 1 of 2

**Method Blank**

| Parameter                                     | MB 1  | Acceptance |
|---|-------|------------|
| Suspended Solids (SS) (mg/L)                  | <0.5  | <0.5       |
| Biochemical Oxygen Demand                     | N/A   | N/A        |
| Total Organic Carbon (mg-TOC/L)               | <0.2  | <0.2       |
| Nitrogen (Total Kjeldahl + nitrate + nitrite) | N/A   | N/A        |
| Ammonia (mg NH <sub>3</sub> -N/L)             | <0.01 | <0.01      |
| Total Phosphorus (mg-P/L)                     | <0.01 | <0.01      |

**Method QC**

| Parameter  | MQC1 | Acceptance |
|--|------|------------|
| Suspended Solids (SS) (%)                        | 102  | 80-120     |
| Biochemical Oxygen Demand (mg O <sub>2</sub> /L) | 197  | 170-220    |
| Total Organic Carbon (%)                         | 98   | 80-120     |
| Nitrogen (Total Kjeldahl + nitrate + nitrite)    | N/A  | N/A        |
| Ammonia (%)                                      | 105  | 80-120     |
| Total Phosphorus (%)                             | 103  | 80-120     |

Remarks: 1) < = less than

2) N/A = Not applicable

3) This report is the summary of quality control data for report number 29129.

\*\*\*\*\*

*PREPARED AND CHECKED BY:*

For and On Behalf of **WELLAB Ltd.**

  
\_\_\_\_\_  
**PATRICK TSE**  
Laboratory Manager

## TEST REPORT

|                 |            |
|-----------------|------------|
| Report No.:     | QC29129    |
| Date of Issue:  | 2018-06-29 |
| Date Received:  | 2018-06-20 |
| Date Tested:    | 2018-06-20 |
| Date Completed: | 2018-06-29 |
| Page:           | 2 of 2     |

**QC report:**

**Sample Duplicate**

| Parameter                                     | 29129-3 chk | Acceptance     |
|---|-------------|----------------|
| Suspended Solids (SS) (%)                     | N/A         | RPD $\leq$ 20% |
| Biochemical Oxygen Demand (%)                 | N/A         | RPD $\leq$ 20% |
| Total Organic Carbon (%)                      | 2           | RPD $\leq$ 20% |
| Nitrogen (Total Kjeldahl + nitrate + nitrite) | N/A         | N/A            |
| Ammonia (%)                                   | N/A         | RPD $\leq$ 20% |
| Total Phosphorus (%)                          | 2           | RPD $\leq$ 20% |

**Sample Spike**

| Parameter                                     | 29129-3 spk | Acceptance |
|---|-------------|------------|
| Suspended Solids (SS) (%)                     | N/A         | N/A        |
| Biochemical Oxygen Demand (%)                 | N/A         | N/A        |
| Total Organic Carbon (%)                      | 96          | 80-120     |
| Nitrogen (Total Kjeldahl + nitrate + nitrite) | N/A         | N/A        |
| Ammonia (%)                                   | 96          | 80-120     |
| Total Phosphorus (%)                          | 102         | 80-120     |

Remarks: 1)  $\leq$  less than

2) N/A = Not applicable

3) This report is the summary of quality control data for report number 29129.

\*\*\*\*\*END OF REPORT\*\*\*\*\*

**TEST REPORT**

**QC REPORT**

**APPLICANT: Cinotech Consultants Limited**  
RM 1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T., Hong Kong

|                 |          |
|-----------------|----------|
| Report No.:     | 28991    |
| Date of Issue:  | 2018/6/4 |
| Date Received:  | 2018/6/1 |
| Date Tested:    | 2018/6/1 |
| Date Completed: | 2018/6/4 |

**ATTN: Ms. Mei Ling Tang**

Page: 1 of 1

Project Name: Enviromental Team for Tseung Kwan O - Lam Tin Tunnel -  
Design and Construction Agreement No. CE/59/2015 (EP)

Project No.: MA16034

Sampling Date: 2018/6/1

Number of Sample: 136

Custody No.: MA16034-CE/59/2015(EP)180601

\*\*\*\*\*

| Total Suspended Solids<br>Sampling Point | Duplicate Analysis |                  |                  | QC Recovery, % |
|--|--------------------|------------------|------------------|----------------|
|  | Trial 1, mg/L      | Trial 2,<br>mg/L | Difference,<br>% |                |
| M4se                                     | 5.8                | 5.7              | 3                | 98             |

\*\*\*\*\*END OF REPORT\*\*\*\*\*

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



**PATRICK TSE**

Laboratory Manager

**TEST REPORT**

**QC REPORT**

**APPLICANT: Cinotech Consultants Limited**  
RM 1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T., Hong Kong

|                 |          |
|-----------------|----------|
| Report No.:     | 29005    |
| Date of Issue:  | 2018/6/5 |
| Date Received:  | 2018/6/4 |
| Date Tested:    | 2018/6/4 |
| Date Completed: | 2018/6/5 |

**ATTN: Ms. Mei Ling Tang**

Page: 1 of 1

Project Name: Enviromental Team for Tseung Kwan O - Lam Tin Tunnel -  
Design and Construction Agreement No. CE/59/2015 (EP)

Project No.: MA16034

Sampling Date: 2018/6/4

Number of Sample: 136

Custody No.: MA16034-CE/59/2015(EP)180604

\*\*\*\*\*

| Total Suspended Solids<br>Sampling Point | Duplicate Analysis |                  |                  | QC Recovery, % |
|--|--------------------|------------------|------------------|----------------|
|  | Trial 1, mg/L      | Trial 2,<br>mg/L | Difference,<br>% |                |
| M4se                                     | 5.8                | 5.9              | 1                | 99             |

\*\*\*\*\*END OF REPORT\*\*\*\*\*

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



**PATRICK TSE**

Laboratory Manager

**TEST REPORT**

**QC REPORT**

**APPLICANT: Cinotech Consultants Limited**  
RM 1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T., Hong Kong

|                 |          |
|-----------------|----------|
| Report No.:     | 29020    |
| Date of Issue:  | 2018/6/7 |
| Date Received:  | 2018/6/6 |
| Date Tested:    | 2018/6/6 |
| Date Completed: | 2018/6/7 |

**ATTN: Ms. Mei Ling Tang**

Page: 1 of 1

Project Name: Environmental Team for Tseung Kwan O - Lam Tin Tunnel -  
Design and Construction Agreement No. CE/59/2015 (EP)

Project No.: MA16034

Sampling Date: 2018/6/6

Number of Sample: 136

Custody No.: MA16034-CE/59/2015(EP)180606

\*\*\*\*\*

| Total Suspended Solids<br>Sampling Point | Duplicate Analysis |                  |                  | QC Recovery, % |
|--|--------------------|------------------|------------------|----------------|
|  | Trial 1, mg/L      | Trial 2,<br>mg/L | Difference,<br>% |                |
| M4se                                     | 5.3                | 5.4              | 1                | 99             |

\*\*\*\*\*END OF REPORT\*\*\*\*\*

PREPARED AND CHECKED BY:  
For and On Behalf of **WELLAB Ltd.**



**PATRICK TSE**  
Laboratory Manager

**TEST REPORT**

**QC REPORT**

**APPLICANT: Cinotech Consultants Limited**  
RM 1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T., Hong Kong

|                 |           |
|-----------------|-----------|
| Report No.:     | 29041     |
| Date of Issue:  | 2018/6/11 |
| Date Received:  | 2018/6/9  |
| Date Tested:    | 2018/6/9  |
| Date Completed: | 2018/6/11 |

**ATTN: Ms. Mei Ling Tang**

Page: 1 of 1

Project Name: Enviromental Team for Tseung Kwan O - Lam Tin Tunnel -  
Design and Construction Agreement No. CE/59/2015 (EP)

Project No.: MA16034

Sampling Date: 2018/6/9

Number of Sample: 136

Custody No.: MA16034-CE/59/2015(EP)180609

\*\*\*\*\*

| Total Suspended Solids<br>Sampling Point | Duplicate Analysis |                  |                  | QC Recovery, % |
|--|--------------------|------------------|------------------|----------------|
|  | Trial 1, mg/L      | Trial 2,<br>mg/L | Difference,<br>% |                |
| M4se                                     | 3.9                | 4.0              | 2                | 101            |

\*\*\*\*\*END OF REPORT\*\*\*\*\*

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



**PATRICK TSE**

Laboratory Manager

**TEST REPORT**

**QC REPORT**

**APPLICANT: Cinotech Consultants Limited**  
RM 1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T., Hong Kong

|                 |           |
|-----------------|-----------|
| Report No.:     | 29056     |
| Date of Issue:  | 2018/6/12 |
| Date Received:  | 2018/6/11 |
| Date Tested:    | 2018/6/11 |
| Date Completed: | 2018/6/12 |

**ATTN: Ms. Mei Ling Tang**

Page: 1 of 1

Project Name: Environmental Team for Tseung Kwan O - Lam Tin Tunnel -  
Design and Construction Agreement No. CE/59/2015 (EP)

Project No.: MA16034

Sampling Date: 2018/6/11

Number of Sample: 136

Custody No.: MA16034-CE/59/2015(EP)180611

\*\*\*\*\*

| Total Suspended Solids<br>Sampling Point | Duplicate Analysis |                  |                  | QC Recovery, % |
|--|--------------------|------------------|------------------|----------------|
|  | Trial 1, mg/L      | Trial 2,<br>mg/L | Difference,<br>% |                |
| M4se                                     | 5.3                | 5.1              | 5                | 102            |

\*\*\*\*\*END OF REPORT\*\*\*\*\*

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



**PATRICK TSE**

Laboratory Manager

**TEST REPORT**

**QC REPORT**

**APPLICANT: Cinotech Consultants Limited**  
RM 1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T., Hong Kong

|                 |           |
|-----------------|-----------|
| Report No.:     | 29072     |
| Date of Issue:  | 2018/6/14 |
| Date Received:  | 2018/6/13 |
| Date Tested:    | 2018/6/13 |
| Date Completed: | 2018/6/14 |

**ATTN: Ms. Mei Ling Tang**

Page: 1 of 1

Project Name: Enviromental Team for Tseung Kwan O - Lam Tin Tunnel -  
Design and Construction Agreement No. CE/59/2015 (EP)

Project No.: MA16034

Sampling Date: 2018/6/13

Number of Sample: 136

Custody No.: MA16034-CE/59/2015(EP)180613

\*\*\*\*\*

| Total Suspended Solids<br>Sampling Point | Duplicate Analysis |                  |                  | QC Recovery, % |
|--|--------------------|------------------|------------------|----------------|
|  | Trial 1, mg/L      | Trial 2,<br>mg/L | Difference,<br>% |                |
| M4se                                     | 3.5                | 3.6              | 4                | 101            |

\*\*\*\*\*END OF REPORT\*\*\*\*\*

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



**PATRICK TSE**

Laboratory Manager



**TEST REPORT**

**QC REPORT**

**APPLICANT: Cinotech Consultants Limited**  
RM 1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T., Hong Kong

|                 |           |
|-----------------|-----------|
| Report No.:     | 29085     |
| Date of Issue:  | 2018/6/19 |
| Date Received:  | 2018/6/15 |
| Date Tested:    | 2018/6/15 |
| Date Completed: | 2018/6/19 |

**ATTN: Ms. Mei Ling Tang**

Page: 1 of 1

Project Name: Environmental Team for Tseung Kwan O - Lam Tin Tunnel -  
Design and Construction Agreement No. CE/59/2015 (EP)

Project No.: MA16034

Sampling Date: 2018/6/15

Number of Sample: 136

Custody No.: MA16034-CE/59/2015(EP)180615

\*\*\*\*\*

| Total Suspended Solids | Duplicate Analysis |               |               | QC Recovery, % |
|------------------------|--------------------|---------------|---------------|----------------|
| Sampling Point         | Trial 1, mg/L      | Trial 2, mg/L | Difference, % |                |
| M4se                   | 3.3                | 3.2           | 4             | 102            |

\*\*\*\*\*END OF REPORT\*\*\*\*\*

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



**PATRICK TSE**

Laboratory Manager

**TEST REPORT**

**QC REPORT**

**APPLICANT: Cinotech Consultants Limited**  
RM 1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T., Hong Kong

|                 |           |
|-----------------|-----------|
| Report No.:     | 29100     |
| Date of Issue:  | 2018/6/20 |
| Date Received:  | 2018/6/19 |
| Date Tested:    | 2018/6/19 |
| Date Completed: | 2018/6/20 |

**ATTN: Ms. Mei Ling Tang**

Page: 1 of 1

Project Name: Environmental Team for Tseung Kwan O - Lam Tin Tunnel -  
Design and Construction Agreement No. CE/59/2015 (EP)

Project No.: MA16034

Sampling Date: 2018/6/19

Number of Sample: 136

Custody No.: MA16034-CE/59/2015(EP)180619

\*\*\*\*\*

| Total Suspended Solids<br>Sampling Point | Duplicate Analysis |                  |                  | QC Recovery, % |
|--|--------------------|------------------|------------------|----------------|
|  | Trial 1, mg/L      | Trial 2,<br>mg/L | Difference,<br>% |                |
| M4se                                     | 2.7                | 2.6              | 2                | 98             |

\*\*\*\*\*END OF REPORT\*\*\*\*\*

PREPARED AND CHECKED BY:  
For and On Behalf of **WELLAB Ltd.**



**PATRICK TSE**  
Laboratory Manager

**TEST REPORT**

**QC REPORT**

**APPLICANT: Cinotech Consultants Limited**  
RM 1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T., Hong Kong

|                 |           |
|-----------------|-----------|
| Report No.:     | 29114     |
| Date of Issue:  | 2018/6/22 |
| Date Received:  | 2018/6/21 |
| Date Tested:    | 2018/6/21 |
| Date Completed: | 2018/6/22 |

**ATTN: Ms. Mei Ling Tang**

Page: 1 of 1

Project Name: Enviromental Team for Tseung Kwan O - Lam Tin Tunnel -  
Design and Construction Agreement No. CE/59/2015 (EP)

Project No.: MA16034

Sampling Date: 2018/6/21

Number of Sample: 136

Custody No.: MA16034-CE/59/2015(EP)180621

\*\*\*\*\*

| Total Suspended Solids<br>Sampling Point | Duplicate Analysis |                  |                  | QC Recovery, % |
|--|--------------------|------------------|------------------|----------------|
|  | Trial 1, mg/L      | Trial 2,<br>mg/L | Difference,<br>% |                |
| M4se                                     | 4.1                | 4.1              | 1                | 101            |

\*\*\*\*\*END OF REPORT\*\*\*\*\*

PREPARED AND CHECKED BY:  
For and On Behalf of **WELLAB Ltd.**



**PATRICK TSE**  
Laboratory Manager

**TEST REPORT**

**QC REPORT**

**APPLICANT: Cinotech Consultants Limited**  
RM 1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T., Hong Kong

|                 |           |
|-----------------|-----------|
| Report No.:     | 29131     |
| Date of Issue:  | 2018/6/25 |
| Date Received:  | 2018/6/23 |
| Date Tested:    | 2018/6/23 |
| Date Completed: | 2018/6/25 |

**ATTN: Ms. Mei Ling Tang**

Page: 1 of 1

Project Name: Enviromental Team for Tseung Kwan O - Lam Tin Tunnel -  
Design and Construction Agreement No. CE/59/2015 (EP)

Project No.: MA16034

Sampling Date: 2018/6/23

Number of Sample: 136

Custody No.: MA16034-CE/59/2015(EP)180623

\*\*\*\*\*

| Total Suspended Solids<br>Sampling Point | Duplicate Analysis |                  |                  | QC Recovery, % |
|--|--------------------|------------------|------------------|----------------|
|  | Trial 1, mg/L      | Trial 2,<br>mg/L | Difference,<br>% |                |
| M4se                                     | 3.0                | 3.1              | 2                | 98             |

\*\*\*\*\*END OF REPORT\*\*\*\*\*

PREPARED AND CHECKED BY:

For and On Behalf of **WELLAB Ltd.**



**PATRICK TSE**

Laboratory Manager

**TEST REPORT**

**QC REPORT**

**APPLICANT: Cinotech Consultants Limited**  
RM 1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T., Hong Kong

|                 |           |
|-----------------|-----------|
| Report No.:     | 29137     |
| Date of Issue:  | 2018/6/26 |
| Date Received:  | 2018/6/25 |
| Date Tested:    | 2018/6/25 |
| Date Completed: | 2018/6/26 |

**ATTN: Ms. Mei Ling Tang**

Page: 1 of 1

Project Name: Enviromental Team for Tseung Kwan O - Lam Tin Tunnel -  
Design and Construction Agreement No. CE/59/2015 (EP)  
Project No.: MA16034  
Sampling Date: 2018/6/25  
Number of Sample: 136  
Custody No.: MA16034-CE/59/2015(EP)180625

\*\*\*\*\*

| Total Suspended Solids<br>Sampling Point | Duplicate Analysis |                  |                  | QC Recovery, % |
|--|--------------------|------------------|------------------|----------------|
|  | Trial 1, mg/L      | Trial 2,<br>mg/L | Difference,<br>% |                |
| M4se                                     | 5.6                | 5.7              | 1                | 100            |

\*\*\*\*\*END OF REPORT\*\*\*\*\*

PREPARED AND CHECKED BY:  
For and On Behalf of **WELLAB Ltd.**



**PATRICK TSE**  
Laboratory Manager

**TEST REPORT**

**QC REPORT**

**APPLICANT: Cinotech Consultants Limited**  
RM 1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T., Hong Kong

|                 |           |
|-----------------|-----------|
| Report No.:     | 29155     |
| Date of Issue:  | 2018/6/28 |
| Date Received:  | 2018/6/27 |
| Date Tested:    | 2018/6/27 |
| Date Completed: | 2018/6/28 |

**ATTN: Ms. Mei Ling Tang**

Page: 1 of 1

Project Name: Enviromental Team for Tseung Kwan O - Lam Tin Tunnel -  
Design and Construction Agreement No. CE/59/2015 (EP)  
Project No.: MA16034  
Sampling Date: 2018/6/27  
Number of Sample: 136  
Custody No.: MA16034-CE/59/2015(EP)180627

\*\*\*\*\*

| Total Suspended Solids | Duplicate Analysis |               |               | QC Recovery, % |
|------------------------|--------------------|---------------|---------------|----------------|
| Sampling Point         | Trial 1, mg/L      | Trial 2, mg/L | Difference, % |                |
| M4se                   | 4.0                | 3.8           | 4             | 100            |

\*\*\*\*\*END OF REPORT\*\*\*\*\*

PREPARED AND CHECKED BY:  
For and On Behalf of **WELLAB Ltd.**



**PATRICK TSE**  
Laboratory Manager

**TEST REPORT**

**QC REPORT**

**APPLICANT: Cinotech Consultants Limited**  
RM 1710, Technology Park,  
18 On Lai Street,  
Shatin, N.T., Hong Kong

|                 |           |
|-----------------|-----------|
| Report No.:     | 29174     |
| Date of Issue:  | 2018/7/3  |
| Date Received:  | 2018/6/29 |
| Date Tested:    | 2018/6/29 |
| Date Completed: | 2018/7/3  |

**ATTN: Ms. Mei Ling Tang**

Page: 1 of 1

Project Name: Enviromental Team for Tseung Kwan O - Lam Tin Tunnel -  
Design and Construction Agreement No. CE/59/2015 (EP)  
Project No.: MA16034  
Sampling Date: 2018/6/29  
Number of Sample: 136  
Custody No.: MA16034-CE/59/2015(EP)180629

\*\*\*\*\*

| Total Suspended Solids<br>Sampling Point | Duplicate Analysis |                  |                  | QC Recovery, % |
|--|--------------------|------------------|------------------|----------------|
|  | Trial 1, mg/L      | Trial 2,<br>mg/L | Difference,<br>% |                |
| M4se                                     | 3.5                | 3.5              | 1                | 100            |

\*\*\*\*\*END OF REPORT\*\*\*\*\*

*PREPARED AND CHECKED BY:*  
For and On Behalf of **WELLAB Ltd.**



**PATRICK TSE**  
*Laboratory Manager*

---

---

**APPENDIX K  
SUMMARY OF EXCEEDANCE**

---

---



**Agreement No. CE 59/2015 (EP)**  
**Environmental Team for Tseung Kwan O - Lam Tin Tunnel –**  
**Design and Construction**

**Appendix K – Summary of Exceedance**

**Reporting Period: June 2018**

**(A) Exceedance Report for Air Quality**  
**(NIL in the reporting month)**

**(B) Exceedance Report for Construction Noise**

**Action Level for Construction Noise**

**(Four (4) Action Level exceedances were recorded due to the documented complaints received in this reporting month.)**

**Limit Level for Construction Noise**

**(12 Limit Level exceedances for nighttime construction noise monitoring were recorded in the reporting month. The limit level exceedances were considered not due to project)**

| <b>Date</b>  | <b>Monitoring Location</b> | <b>Measured Level (L<sub>eq</sub> dB(A))</b> | <b>Baseline Noise Level (L<sub>eq</sub> dB(A))</b> | <b>Construction Noise Level (L<sub>eq</sub> dB(A))</b> | <b>Limit Level</b> |
|--------------|----------------------------|--|--|--|--------------------|
| 8 June 2018  | CM1                        | 65.7   | 60.5<br>(54.4 – 69.8)                              | 64.1   | 55                 |
| 14 June 2018 |                            | 64.2   |  | 61.8   |                    |
| 20 June 2018 |                            | 62.3   |  | 57.6   |                    |
| 26 June 2018 |                            | 63.9   |  | 61.2   |                    |
| 8 June 2018  | CM2                        | 64.9   | 58.0<br>(50.8 – 66.8)                              | 63.9   |                    |
| 14 June 2018 |                            | 63.1   |  | 61.5   |                    |
| 20 June 2018 |                            | 61.1   |  | 58.2   |                    |
| 26 June 2018 |                            | 64.2   |  | 63.0   |                    |
| 8 June 2018  | CM3                        | 64.1   | 60.2<br>(53.0 – 67.4)                              | 61.8   |                    |
| 14 June 2018 |                            | 64.6   |  | 62.6   |                    |
| 20 June 2018 |                            | 62.9   |  | 59.6   |                    |
| 26 June 2018 |                            | 64.7   |  | 62.8   |                    |

**Agreement No. CE 59/2015 (EP)**  
**Environmental Team for Tseung Kwan O - Lam Tin Tunnel –**  
**Design and Construction**

**Appendix K – Summary of Exceedance**

**(C) Exceedance Report for Water Quality**

**(No exceedance for marine water quality monitoring in the reporting month)**

**(Fourteen (14) Limit Level exceedances in groundwater quality monitoring as followed:**

| <b>Date</b>  | <b>Monitoring Location</b> | <b>Monitoring Parameter</b> | <b>Monitoring Results</b> | <b>Action Level</b> | <b>Limit Level</b> |
|--------------|----------------------------|-----------------------------|---------------------------|---------------------|--------------------|
| 5 June 2018  | Stream 1                   | Turbidity (NTU)             | <u>7.6</u>                | 2.1                 | 2.3                |
|              |                            | Suspended Solid (mg/L)      | <u>39</u>                 | 7.6                 | 12.1               |
|              |                            | Total Nitrogen (mg/L)       | <u>2.2</u>                | 2.0                 | 2.1                |
|              |                            | Total Phosphate (mg-P/L)    | <u>0.11</u>               | 0.05                | 0.05               |
|              | Stream 2                   | Turbidity (NTU)             | <u>72.2</u>               | 2.1                 | 2.3                |
|              |                            | Suspended Solid (mg/L)      | <u>100</u>                | 7.6                 | 12.1               |
|              | Stream 3                   | Turbidity (NTU)             | <u>86.9</u>               | 2.1                 | 2.3                |
|              |                            | Suspended Solid (mg/L)      | <u>92</u>                 | 7.6                 | 12.1               |
|              |                            | Total Phosphate (mg-P/L)    | <u>0.06</u>               | 0.05                | 0.05               |
| 20 June 2018 | Stream 1                   | Turbidity (NTU)             | <u>3.7</u>                | 2.1                 | 2.3                |
|              | Stream 2                   |                             | <u>3.3</u>                |                     |                    |
|              | Stream 3                   |                             | <u>4.2</u>                |                     |                    |
|              | Stream 1                   | Dissolved Oxygen (mg/L)     | <u>7.4</u>                | 7.6                 | 7.6                |
|              | Stream 2                   | Dissolved Oxygen (mg/L)     | <u>7.5</u>                |                     |                    |

**(D) Exceedance Report for Ecology**  
**(NIL in the reporting month)**

**(E) Exceedance Report for Cultural Heritage**  
**(NIL in the reporting month)**

**(F) Exceedance Report for Landfill Gas**  
**(NIL in the reporting month)**

**Agreement No. CE 59/2015 (EP)**  
**Environmental Team for Tseung Kwan O – Lam Tin Tunnel**  
**- Notification of Exceedances**

NOE No. 180608\_noise (CM1-CM3) **Exceedance Level:** Limit

**Date of Measurement:** 8 June 2018 – 9 June 2018

**Time of Measurement:** 23:00-00:15


**Date of Noise Monitoring:** 8 June 2018 – 9 June 2018

**Part A – Exceedance Summary Tables**

**Table I: Parameter(s) – Construction Noise**

| Station | Location  | Time        | Measured Level (L <sub>eq</sub> dB(A)) | Baseline Noise Level (L <sub>eq</sub> dB(A)) | Construction Noise Level (L <sub>eq</sub> dB(A)) | Action Level                               | Limit Level (L <sub>eq</sub> dB(A)) | Level exceeded |
|---------|---|-------------|--|--|--|--|-------------------------------------|----------------|
| CM1     | Nga Lai House, Yau Lai Estate Phase 1, Yau Tong | 23:00-23:15 | 65.7                                   | 60.5 (54.4 – 69.8)                           | <b><u>64.1</u></b>                               | When one documented complaint is received. | <b>55.0</b>                         | Limit          |
| CM2     | Bik Lai House, Yau Lai Estate Phase 1, Yau Tong | 23:25-23:40 | 64.9                                   | 58.0 (50.8 – 66.8)                           | <b><u>63.9</u></b>                               |  |                                     |                |
| CM3     | Block S, Yau Lai Estate Phase 5, Yau Tong       | 00:00-00:15 | 64.1                                   | 60.2 (53.0 – 67.4)                           | <b><u>61.8</u></b>                               |  |                                     |                |

**Field Observation(s) and Conclusion**

|  |  |
|--|--|
| <p>(a) Statement of exceedance(s)<br/>Construction noise measured at CM1, CM2 &amp; CM3 exceeded the construction noise (night time) limit level.</p>  |  |
| <p>(b) Cause of exceedance(s)<br/>The exceedance was not considered related to the Project works:</p> <ul style="list-style-type: none"> <li>• According to our field observation, road traffic noise were identified as the dominant noise source. No noticeable noise from blasting / associated works was identified.</li> <li>• No major construction activity was observed in Lam Tin Interchange during monitoring (see photo).</li> <li>• As confirmed by RE, only construction works inside the tunnel were being conducted with the blast door closed.</li> </ul> |  |

**Part B – Conclusion:** The exceedances of night time noise limit level were not due to the Project.

**Part C – Recommendation:** No further action is required.

ETL Signature: 

Date: 13 June, 2018

**Agreement No. CE 59/2015 (EP) Environmental Team for Tseung Kwan O – Lam Tin Tunnel**

**- Notification of Exceedances**

**NOE No.** 180614\_noise (CM1-CM3) **Exceedance Level:** Limit

**Date of Measurement:** 14 June 2018 – 15 June 2018

**Time of Measurement:** 23:00-00:05


**Date of Noise Monitoring:** 14 June 2018 – 15 June 2018

**Part A – Exceedance Summary Tables**

**Table I: Parameter(s) – Construction Noise**


| Station | Location  | Time        | Measured Level (L <sub>eq</sub> dB(A)) | Baseline Noise Level (L <sub>eq</sub> dB(A)) | Construction Noise Level (L <sub>eq</sub> dB(A)) | Action Level                               | Limit Level (L <sub>eq</sub> dB(A)) | Level exceeded |
|---------|---|-------------|--|--|--|--|-------------------------------------|----------------|
| CM1     | Nga Lai House, Yau Lai Estate Phase 1, Yau Tong | 23:00-23:10 | 64.2                                   | 60.5 (54.4 – 69.8)                           | <u>61.8</u>                                      | When one documented complaint is received. | 55.0                                | Limit          |
| CM2     | Bik Lai House, Yau Lai Estate Phase 1, Yau Tong | 23:20-23:30 | 63.1                                   | 58.0 (50.8 – 66.8)                           | <u>61.5</u>                                      |  |                                     |                |
| CM3     | Block S, Yau Lai Estate Phase 5, Yau Tong       | 23:55-00:05 | 64.6                                   | 60.2 (53.0 – 67.4)                           | <u>62.6</u>                                      |  |                                     |                |

**Field Observation(s) and Conclusion**

|  |  |
|--|--|
| <p>(a) Statement of exceedance(s)<br/>Construction noise measured at CM1, CM2 &amp; CM3 exceeded the construction noise (night time) limit level.</p>  |  |
| <p>(b) Cause of exceedance(s)<br/>The exceedance was not considered related to the Project works:</p> <ul style="list-style-type: none"> <li>• According to our field observation, road traffic noise were identified as the dominant noise source. No noticeable noise from blasting / associated works was identified.</li> <li>• No major construction activity was observed in Lam Tin Interchange during monitoring (see photo).</li> <li>• As confirmed by RE, only construction works inside the tunnel were being conducted with the blast door closed.</li> </ul> |  |

**Part B – Conclusion:** The exceedances of night time noise limit level were not due to the Project.

**Part C – Recommendation:** No further action is required.

ETL Signature: 

Date: 15 June, 2018

**Agreement No. CE 59/2015 (EP) Environmental Team for Tseung Kwan O – Lam Tin Tunnel**

**- Notification of Exceedances**

**NOE No.** 180620\_noise (CM1-CM3) **Exceedance Level:** Limit

**Date of Measurement:** 20 June 2018 – 21 June 2018

**Time of Measurement:** 23:35-00:45


**Date of Noise Monitoring:** 20 June 2018 – 21 June 2018

**Part A – Exceedance Summary Tables**

**Table I: Parameter(s) – Construction Noise**


| Station | Location  | Time        | Measured Level (L <sub>eq</sub> dB(A)) | Baseline Noise Level (L <sub>eq</sub> dB(A)) | Construction Noise Level (L <sub>eq</sub> dB(A)) | Action Level                               | Limit Level (L <sub>eq</sub> dB(A)) | Level exceeded |
|---------|---|-------------|--|--|--|--|-------------------------------------|----------------|
| CM1     | Nga Lai House, Yau Lai Estate Phase 1, Yau Tong | 00:35-00:45 | 62.3                                   | 60.5<br>(54.4 – 69.8)                        | <u>57.6</u>                                      | When one documented complaint is received. | 55.0                                | Limit          |
| CM2     | Bik Lai House, Yau Lai Estate Phase 1, Yau Tong | 00:05-00:15 | 61.1                                   | 58.0<br>(50.8 – 66.8)                        | <u>58.2</u>                                      |  |                                     |                |
| CM3     | Block S, Yau Lai Estate Phase 5, Yau Tong       | 23:35-23:45 | 62.9                                   | 60.2<br>(53.0 – 67.4)                        | <u>59.6</u>                                      |  |                                     |                |

**Field Observation(s) and Conclusion**

|  |  |
|--|--|
| <p>(a) Statement of exceedance(s)<br/>Construction noise measured at CM1, CM2 &amp; CM3 exceeded the construction noise (night time) limit level.</p>  |  |
| <p>(b) Cause of exceedance(s)<br/>The exceedance was not considered related to the Project works:</p> <ul style="list-style-type: none"> <li>• According to our field observation, road traffic noise were identified as the dominant noise source. No noticeable noise from blasting / associated works was identified.</li> <li>• No major construction activity was observed in Lam Tin Interchange during monitoring (see photo).</li> <li>• As confirmed by RE, only construction works inside the tunnel were being conducted with the blast door closed.</li> </ul> |  |

**Part B – Conclusion:** The exceedances of night time noise limit level were not due to the Project.

**Part C – Recommendation:** No further action is required.

ETL Signature: 

Date: 21 June, 2018

**Agreement No. CE 59/2015 (EP) Environmental Team for Tseung Kwan O – Lam Tin Tunnel**

**- Notification of Exceedances**

**NOE No.** 180626\_noise (CM1-CM3) **Exceedance Level:** Limit

**Date of Measurement:** 26 June 2018 – 27 June 2018

**Time of Measurement:** 23:00-00:05


**Date of Noise Monitoring:** 26 June 2018 – 27 June 2018

**Part A – Exceedance Summary Tables**

**Table I: Parameter(s) – Construction Noise**

| Station | Location  | Time        | Measured Level (L <sub>eq</sub> dB(A)) | Baseline Noise Level (L <sub>eq</sub> dB(A)) | Construction Noise Level (L <sub>eq</sub> dB(A)) | Action Level                               | Limit Level (L <sub>eq</sub> dB(A)) | Level exceeded |
|---------|---|-------------|--|--|--|--|-------------------------------------|----------------|
| CM1     | Nga Lai House, Yau Lai Estate Phase 1, Yau Tong | 23:50-00:05 | 63.9                                   | 60.5<br>(54.4 – 69.8)                        | <u>61.2</u>                                      | When one documented complaint is received. | 55.0                                | Limit          |
| CM2     | Bik Lai House, Yau Lai Estate Phase 1, Yau Tong | 23:28-23:43 | 64.2                                   | 58.0<br>(50.8 – 66.8)                        | <u>63.0</u>                                      |  |                                     |                |
| CM3     | Block S, Yau Lai Estate Phase 5, Yau Tong       | 23:00-23:15 | 64.7                                   | 60.2<br>(53.0 – 67.4)                        | <u>62.8</u>                                      |  |                                     |                |

**Field Observation(s) and Conclusion**

|  |  |
|--|--|
| <p>(a) Statement of exceedance(s)<br/>Construction noise measured at CM1, CM2 &amp; CM3 exceeded the construction noise (night time) limit level.</p>  |  |
| <p>(b) Cause of exceedance(s)<br/>The exceedance was not considered related to the Project works:</p> <ul style="list-style-type: none"> <li>• According to our field observation, road traffic noise were identified as the dominant noise source. No noticeable noise from blasting / associated works was identified.</li> <li>• No major construction activity was observed in Lam Tin Interchange during monitoring (see photo).</li> <li>• As confirmed by RE, only construction works inside the tunnel were being conducted with the blast door closed.</li> </ul> |  |

**Part B – Conclusion:** The exceedances of night time noise limit level were not due to the Project.

**Part C – Recommendation:** No further action is required.

ETL Signature: 

Date: 28 June, 2018

Agreement No. CE 59/2015 (EP)  
 ET for Tseung Kwan O – Lam Tin Tunnel  
 Design and Construction

- Notification and Investigation Report for Environmental Quality Action & Limit Exceedances

Monitoring Parameter: Groundwater Quality

Date of Monitoring: 5 June 2018

**Part A – Summary of Exceedance Records**

| Date        | Monitoring Parameter     | Monitoring Location | Monitoring Results | Action Level | Limit Level | Justification* | Exceedance due to the Project |
|-------------|--------------------------|---------------------|--------------------|--------------|-------------|----------------|-------------------------------|
| 5 June 2018 | Turbidity (NTU)          | Stream 1            | <u>7.6</u>         | 2.1          | 2.3         | (2), (3)       | No                            |
|             |                          | Stream 2            | <u>72.2</u>        |              |             | (1), (3)       | No                            |
|             |                          | Stream 3            | <u>86.9</u>        |              |             | (1), (3)       | No                            |
|             | Suspended Solid (mg/L)   | Stream 1            | <u>39</u>          | 7.6          | 12.1        | (2), (3)       | No                            |
|             |                          | Stream 2            | <u>100</u>         |              |             | (1), (3)       | No                            |
|             |                          | Stream 3            | <u>92</u>          |              |             | (1), (3)       | No                            |
|             | Total Nitrogen (mg/L)    | Stream 1            | <u>2.2</u>         | 2.0          | 2.1         | (2), (3)       | No                            |
|             | Total Phosphate (mg-P/L) | Stream 1            | <u>0.11</u>        | 0.05         | 0.05        | (2), (3)       | No                            |
|             |                          | Stream 3            | <u>0.06</u>        |              |             | (1), (3)       | No                            |

Note: For Total Phosphate, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.  
**Bold Italic** means Action Level exceedance  
**Bold Italic with underline** means Limit Level exceedance

- \*Remarks
- (1) – The distance between the tunnel construction activities and monitoring station of Stream 2 and 3 are about 1000 meters.
  - (2) – The vertical distance between Stream 1 and the tunnel construction site is more than 44 meters. Therefore, Stream 1 will not be affected by any tunnel construction works as its elevation is above the tunnel construction site (Figure 1 & 2).
  - (3) – Other(s): Based on the information from HKO, Standby Signal No. 1 & Thunderstorm Warning were hoisted and rainfall of 28.2mm was recorded on 5 June 2018.

**Part B – Conclusions:**

1. Based on the justifications in the above table, the exceedances are considered due to adverse weather (i.e. heavy rainfall).
2. No increase in monitoring frequency for groundwater quality monitoring and no further action are required.


**Part C – Recommendations**

The monitoring of stream water is considered not representative to monitor the potential impacts on groundwater due to the Project after consideration of the location & elevation of the stream(s) and the non-project related factors (e.g. human activities etc.).

Therefore, ET recommend to terminate the water quality monitoring for the streams in accordance with the EM&A Manual, Section 4. For the details, please refer to the separate proposal for termination of monitoring for stream water.


Reviewed by: Dr. Priscilla Choy  
 (Environmental Team Leader)

Date: 10 August 2018

Signature: 

**FIGURE**






**LEGEND:**

|  |  |
|--|--|
|  | SITE BOUNDARY                              |
|  | STREAM                                     |
|  | SAMPLING LOCATIONS FOR GROUNDWATER QUALITY |
|  | SAMPLING LOCATIONS FOR GROUNDWATER LEVEL   |



Agreement No. CE/59/2015 (EP)  
 Environmental Team for Tseung Kwan O - Lam Tin Tunnel -  
 Design and Construction  
 Location of Streams for Groundwater Quality and Groundwater Level Monitoring

|         |              |            |          |     |
|---------|--------------|------------|----------|-----|
| SCALE   | 1:10000 @ A4 | DATE       | APR 2017 |     |
| CHECK   | JF           | DRAWN      | JW       |     |
| JOB No. | MA16034      | FIGURE NO. | 1        | REV |
|         |              |            |          | -   |



Title Agreement No. CE/59/2015 (EP)  
 Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction  
 Location of Stream 1 and the Main Tunnel Construction

|       |        |             |         |
|-------|--------|-------------|---------|
| Scale | N.T.S  | Project No. | MA16034 |
| Date  | May-18 | Figure      | 2       |



---

**APPENDIX A  
DAILY RAINFALL DISTRIBUTION  
EXTRACTED FROM HKO**

---


**Agreement No. CE 59/2015 (EP)**

**Environmental Team for Tseung Kwan O – Lam Tin Tunnel**

**Design and Construction - Investigation Report for Environmental Quality Action & Limit Exceedances**

**Daily Rainfall Distribution:**

Total rainfall on **5-Jun-2018** (based on raingauges and radar data)



| Rainfall recorded in Sai Kung region on <b>5 June 2018</b> |               |                      |                      |
|--|---------------|----------------------|----------------------|
| Time   | Rainfall (mm) | Standby Signal No. 1 | Thunderstorm Warning |
| 23:45-00:45  | 0-1mm         | -                    | ✓                    |
| 00:45-01:45  | 0-1mm         | -                    | ✓                    |
| 01:45-02:45  | 0-2mm         | -                    | ✓                    |
| 02:45-03:45  | 0-8mm         | -                    | ✓                    |
| 03:45-04:45  | -             | -                    | ✓                    |
| 04:45-05:45  | -             | -                    | ✓                    |
| 05:45-06:45  | -             | -                    | ✓                    |
| 06:45-07:45  | -             | -                    | ✓                    |
| 07:45-08:45  | -             | -                    | -                    |
| 08:45-09:45  | -             | -                    | -                    |
| 09:45-10:45  | -             | -                    | -                    |
| 10:45-11:45  | -             | ✓                    | -                    |
| 11:45-12:45  | 0-3mm         | ✓                    | ✓                    |
| 12:45-13:45  | 5-18mm        | -                    | ✓                    |
| 13:45-14:45  | 0-2mm         | -                    | ✓                    |
| 14:45-15:45  | 0-2mm         | -                    | ✓                    |
| 15:45-16:45  | -             | -                    | ✓                    |
| 16:45-17:45  | -             | -                    | -                    |
| 17:45-18:45  | -             | -                    | -                    |
| 18:45-19:45  | -             | -                    | ✓                    |
| 19:45-20:45  | 7-18mm        | -                    | ✓                    |
| 20:45-21:45  | -             | -                    | ✓                    |
| 21:45-22:45  | -             | -                    | -                    |
| 22:45-23:45  | 0-6mm         | -                    | -                    |

**Agreement No. CE 59/2015 (EP)**  
**ET for Tseung Kwan O – Lam Tin Tunnel**  
**Design and Construction**

**- Notification and Investigation Report for Environmental Quality Action & Limit Exceedances**

Monitoring Parameter: Groundwater Quality

Date of Monitoring: 20 June 2018

**Part A – Summary of Exceedance Records**

| Date         | Monitoring Parameter | Monitoring Location | Monitoring Results | Action Level | Limit Level | Justification* | Exceedance due to the Project |
|--------------|----------------------|---------------------|--------------------|--------------|-------------|----------------|-------------------------------|
| 20 June 2018 | Turbidity (NTU)      | Stream 1            | <u>3.7</u>         | 2.1          | 2.3         | (2), (3)       | No                            |
|              |                      | Stream 2            | <u>3.3</u>         |              |             | (1), (3)       | No                            |
|              |                      | Stream 3            | <u>4.2</u>         |              |             | (1), (3)       | No                            |
|              | Dissolved Oxygen     | Stream 1            | <u>7.4</u>         | 7.6          | 7.6         | (2), (3)       | No                            |
|              |                      | Stream 2            | <u>7.5</u>         |              |             | (1), (3)       | No                            |

Note: For Total Phosphate, non-compliance of the water quality limits occurs when monitoring result is higher than the limits.

**Bold Italic** means Action Level exceedance

**Bold Italic with underline** means Limit Level exceedance

- \*Remarks
- (1) –The distance between the tunnel construction activities and monitoring stations of stream 2 and 3 are about 1000 meters.
  - (2) –The vertical distance between Stream 1 and the tunnel construction site is more than 44 meters. Therefore, Stream 1 will not be affected by any tunnel construction works as its elevation is above the tunnel construction site (**Figure 1 & 2**).
  - (3) –Other(s): Based on the information from HKO, rainfall was recorded on 19 June 2018 (Ref: Daily Rainfall Distribution extracted from HKO).

**Part B – Conclusions:**

1. Based on the justifications in the above table, there is no direct evidence showing that the exceedances were due to Project. The exceedances are considered properly due to non-project related factor, such as, rainfall or domestic sewage (as observed and reported in the EIA report).
2. No increase in monitoring frequency for groundwater quality monitoring and no further action are required.

**Part C – Recommendations**


The monitoring of stream water is considered not representative to monitor the potential impacts on groundwater due to the Project after consideration of the location & elevation of the stream(s) and the non-project related factors (e.g. human activities etc.).

Therefore, ET recommend to terminate the water quality monitoring for the streams in accordance with the EM&A Manual, Section 4. For the details, please refer to the separate proposal for suspension of monitoring for stream water.


Reviewed by: Dr. Priscilla Choy  
 (Environmental Team Leader)

Date: 10 August 2018

Signature:



**FIGURE**




LEGEND:

|  |  |
|--|--|
|  | SITE BOUNDARY                              |
|  | STREAM                                     |
|  | SAMPLING LOCATIONS FOR GROUNDWATER QUALITY |
|  | SAMPLING LOCATIONS FOR GROUNDWATER LEVEL   |



Agreement No. CE/59/2015 (EP)  
 Environmental Team for Tseung Kwan O - Lam Tin Tunnel -  
 Design and Construction  
 Location of Streams for Groundwater Quality and Groundwater Level Monitoring

|         |              |            |          |     |
|---------|--------------|------------|----------|-----|
| SCALE   | 1:10000 @ A4 | DATE       | APR 2017 |     |
| CHECK   | JF           | DRAWN      | JW       |     |
| JOB No. | MA16034      | FIGURE NO. | 1        | REV |
|         |              |            |          | -   |



Title Agreement No. CE/59/2015 (EP)  
 Environmental Team for Tseung Kwan O - Lam Tin Tunnel - Design and Construction  
 Location of Stream 1 and the Main Tunnel Construction

|       |        |             |         |
|-------|--------|-------------|---------|
| Scale | N.T.S  | Project No. | MA16034 |
| Date  | May-18 | Figure      | 2       |





---

**APPENDIX A  
DAILY RAINFALL DISTRIBUTION  
EXTRACTED FROM HKO**

---


**Agreement No. CE 59/2015 (EP)**

**Environmental Team for Tseung Kwan O – Lam Tin Tunnel**

**Design and Construction - Investigation Report for Environmental Quality Action & Limit Exceedances**

**Daily Rainfall Distribution:**

Total rainfall on **19-Jun-2018** (based on raingauges and radar data)



| Rainfall recorded in Sai Kung region on <b>19 June 2018</b> |               |                      |                      |
|---|---------------|----------------------|----------------------|
| Time  | Rainfall (mm) | Standby Signal No. 1 | Thunderstorm Warning |
| 23:45-00:45   | -             | -                    | -                    |
| 00:45-01:45   | -             | -                    | -                    |
| 01:45-02:45   | -             | -                    | -                    |
| 02:45-03:45   | -             | -                    | -                    |
| 03:45-04:45   | -             | -                    | -                    |
| 04:45-05:45   | -             | -                    | -                    |
| 05:45-06:45   | -             | -                    | -                    |
| 06:45-07:45   | -             | -                    | -                    |
| 07:45-08:45   | -             | -                    | -                    |
| 08:45-09:45   | 0-1mm         | -                    | -                    |
| 09:45-10:45   | 0-1mm         | -                    | -                    |
| 10:45-11:45   | 0-1mm         | -                    | -                    |
| 11:45-12:45   | -             | -                    | -                    |
| 12:45-13:45   | -             | -                    | -                    |
| 13:45-14:45   | -             | -                    | -                    |
| 14:45-15:45   | 0-6mm         | -                    | -                    |
| 15:45-16:45   | 0-1mm         | -                    | -                    |
| 16:45-17:45   | -             | -                    | -                    |
| 17:45-18:45   | -             | -                    | -                    |
| 18:45-19:45   | -             | -                    | -                    |
| 19:45-20:45   | -             | -                    | -                    |
| 20:45-21:45   | -             | -                    | -                    |
| 21:45-22:45   | -             | -                    | -                    |
| 22:45-23:45   | -             | -                    | -                    |

---

---

**APPENDIX L**  
**SITE AUDIT SUMMARY**

---

---

**Agreement No. CE 59/2015 (EP)**  
**Environmental Team for Tseung Kwan O - Lam Tin Tunnel – Design and Construction**  
**Monthly EM&A Report**

**Appendix L - Site Audit Summary (June 2018)**

**Contract No. NE/2015/01**

*Tseung Kwan O - Lam Tin Tunnel - Main Tunnel and Associated Works*

| Items   | Date         | Status* | Follow up Action  |
|---|--------------|---------|---|
| <b><i>Water Quality</i></b>   |              |         |   |
| The Contractor was reminded to provide silt curtain in accordance with the silt curtain deployment plan at TKO side before the commencement of the construction work. | 13 June 2018 | ✗       | Item remarked on 20 June 2018.                            |
|   | 20 June 2018 | ✗       | Item remarked on 28 June 2018                             |
|   | 27 June 2018 | #       | Follow up action will be reported in next reporting month |
| <b><i>Noise</i></b>   |              |         |   |
| --  | --           | --      | --  |
| <b><i>Landscape and Visual</i></b>  |              |         |   |
| --  | --           | --      | --  |
| <b><i>Air Quality</i></b>   |              |         |   |
| Water spraying should be provided to exposed slope at LTI and TKO for dust suppression.   | 30 May 2018  | ✓       | Improved/rectified on 6 June 2018.                        |
| Used cement bags should be removed at Portion IVC (Lam Tin).  | 6 June 2018  | ✓       | Improved/rectified on 13 June 2018.                       |
| <b><i>Waste / Chemical Management</i></b>   |              |         |   |
| Construction material should be removed from drip tray at TKO marine platform.  | 30 May 2018  | ✓       | Improved/rectified on 6 June 2018.                        |
|   |              |         |   |
| <b><i>Impact on Cultural Heritage</i></b>   |              |         |   |
| --  | --           | --      | --  |
| <b><i>Permits / Licenses</i></b>  |              |         |   |
| --  | --           | --      | --  |

- ✓ Observation/reminder was made during site audit but improved/rectified by the contractor in the next site audit
- ✗ Observation/reminder was made during site audit but not yet improved/rectified by the contractor in the next site audit
- # Follow up action will be reported in next reporting month
- \* Non-compliance of mitigation measure
- Non-compliance but improved by the contractor

**Agreement No. CE 59/2015 (EP)**  
**Environmental Team for Tseung Kwan O - Lam Tin Tunnel – Design and Construction**  
**Monthly EM&A Report**

**Appendix L - Site Audit Summary (June 2018)**

**Contract No. NE/2015/02**

*Tseung Kwan O - Lam Tin Tunnel - Road P2 and Associated Works*

| Items  | Date         | Status* | Follow up Action  |
|--|--------------|---------|---|
| <b>Water Quality</b>   |              |         |   |
| To regularly maintain the wetsep in Work Area A and drainage system properly to prevent overflowing during rain events.  | 13 June 2018 | ✓       | Improved/rectified on 20 June 2018.   |
| The stockpile in Work Area A was observed uncovered and its level was much higher than the stone wall. The Contractor should improve the mitigation measures for dust and water quality impact in Work Area A.         | 20 June 2018 | ✗       | The stockpile was observed partially covered but its level was still over the concrete block. Item remarked on 27 June 2018.                                |
|  | 27 June 2018 | #       | Follow up action will be reported in next reporting month   |
| <b>Noise</b>   |              |         |   |
| To properly erect the acoustic mats without gaps for the derrick barge (Superich 206).   | 30 May 2018  | ✓       | Improved/rectified on 6 June 2018.  |
| Excessive impact noise was produced from the vibration hammer and pile in Portion 6. The Contractor should enhance noise mitigation measures for the piling works in Portion 6 to reduce noise nuisance to nearby NSR. | 27 June 2018 | #       | Follow up action will be reported in next reporting month   |
| <b>Landscape and Visual</b>  |              |         |   |
| --   | --           | --      | --  |
| <b>Air Quality</b>   |              |         |   |
| To wrap the drilling rig with impervious sheeting and retractable tube before start of pre-boring works in Portion 4.  | 6 June 2018  | ✓       | Improved/rectified on 13 June 2018.   |
| The stockpile in Work Area A was observed uncovered and its level was much higher than the stone wall. The Contractor should improve the mitigation measures for dust and water quality impact in Work Area A.         | 20 June 2018 | ✗       | The stockpile was observed partially covered but its level was still over the concrete block. Item remarked on 27 June 2018. Item remarked on 27 June 2018. |
|  | 27 June 2018 | #       | Follow up action will be reported in next reporting month   |
| <b>Waste / Chemical Management</b>   |              |         |   |
|  |              |         |   |
| <b>Impact on Cultural Heritage</b>   |              |         |   |
| --   | --           | --      | --  |
| <b>Permits / Licenses</b>  |              |         |   |
| --   | --           | --      | --  |

- ✓ Observation/reminder was made during site audit but improved/rectified by the contractor in the next site audit
- ✗ Observation/reminder was made during site audit but not yet improved/rectified by the contractor in the next site audit
- # Follow up action will be reported in next reporting month
- \* Non-compliance of mitigation measure
- Non-compliance but rectified by the contractor

**Agreement No. CE 59/2015 (EP)**  
**Environmental Team for Tseung Kwan O - Lam Tin Tunnel – Design and Construction**  
**Monthly EM&A Report**

**Appendix L - Site Audit Summary (June 2018)**

**Contract No. NE/2015/03**

*Tseung Kwan O - Lam Tin Tunnel - Northern Footbridge*

| Items   | Date         | Status* | Follow up Action                    |
|---|--------------|---------|-------------------------------------|
| <b>Water Quality</b>  |              |         |                                     |
| To regularly remove the sediment in the sedimentation tank in West Pier.  | 30 May 2018  | ✓       | Improved/rectified on 6 June 2018.  |
| Sand bunds along West Pier were observed damaged. The Contractor should ensure the integrity of sand bunds at all time.   | 13 June 2018 | ✓       | Improved/rectified on 20 June 2018. |
| <b>Noise</b>  |              |         |                                     |
| --  | --           | --      | --                                  |
| <b>Landscape and Visual</b>   |              |         |                                     |
| Chemical containers were observed next to the tree protection zone. The Contractor should improve tree protection measures, such as, to relocate the chemical containers away from the TPZ. | 20 June 2018 | ✓       | Improved/rectified on 27 June 2018. |
| <b>Air Quality</b>  |              |         |                                     |
| --  | --           | --      | --                                  |
| <b>Waste / Chemical Management</b>  |              |         |                                     |
| To provide drip tray to the chemical container in Portion 2 near East Pier.   | 30 May 2018  | ✓       | Improved/rectified on 6 June 2018.  |
| Oil stain was observed on the surface of the stagnant water in West Pier. The Contractor should remove the oil stain on the stagnant water.   | 13 June 2018 | ✓       | Improved/rectified on 20 June 2018. |
| <b>Impact on Cultural Heritage</b>  |              |         |                                     |
| --  | --           | --      | --                                  |
| <b>Permits / Licenses</b>   |              |         |                                     |
| --  | --           | --      | --                                  |

- ✓ Observation/reminder was made during site audit but improved/rectified by the contractor in the next site audit
- ✗ Observation/reminder was made during site audit but not yet improved/rectified by the contractor in the next site audit
- # Follow up action will be reported in next reporting month

- \* Non-compliance of mitigation measure
- Non-compliance but rectified by the contractor

**Agreement No. CE 59/2015 (EP)**  
**Environmental Team for Tseung Kwan O - Lam Tin Tunnel – Design and Construction**  
**Monthly EM&A Report**

**Appendix L - Site Audit Summary (June 2018)**

**Contract No. NE/2017/01**

*Tseung Kwan O - Lam Tin Tunnel – Tsueng Kwan O Interchange and Associated Works*

| Items  | Date         | Status* | Follow up Action  |
|--|--------------|---------|---|
| <b>Water Quality</b>   |              |         |   |
|  |              |         |   |
| <b>Noise</b>   |              |         |   |
| --   | --           | --      | --  |
| <b>Landscape and Visual</b>  |              |         |   |
| --   | --           | --      | --  |
| <b>Air Quality</b>   |              |         |   |
|  |              |         |   |
| <b>Waste / Chemical Management</b>   |              |         |   |
| The Contractor was reminded to remove the stagnant water inside the drip tray at flat top barge. | 13 June 2018 | ✓       | Improved/rectified on 20 June 2018.                       |
| Oil leakage should be avoided from the oil container and cleaned up on the derrick barge.        | 27 June 2018 | #       | Follow up action will be reported in next reporting month |
| <b>Impact on Cultural Heritage</b>   |              |         |   |
| --   | --           | --      | --  |
| <b>Permits / Licenses</b>  |              |         |   |
|  |              |         |   |

- ✓ Observation/reminder was made during site audit but improved/rectified by the contractor in the next site audit
- ✗ Observation/reminder was made during site audit but not yet improved/rectified by the contractor in the next site audit
- # Follow up action will be reported in next reporting month
- \* Non-compliance of mitigation measure
- Non-compliance but rectified by the contractor

**Agreement No. CE 59/2015 (EP)**  
**Environmental Team for Tseung Kwan O - Lam Tin Tunnel – Design and Construction**  
**Monthly EM&A Report**

**Appendix L - Site Audit Summary (June 2018)**

**Contract No. NE/2017/02**

*Tseung Kwan O - Lam Tin Tunnel – Road P2/D4 and Associated Works*

| Items  | Date         | Status* | Follow up Action                    |
|--|--------------|---------|-------------------------------------|
| <b><i>Water Quality</i></b>  |              |         |                                     |
| Stagnant water was observed in Portion I. The Contractor should remove the stagnant water frequently.                          | 13 June 2018 | ✓       | Improved/rectified on 20 June 2018. |
| <b><i>Noise</i></b>  |              |         |                                     |
| --   | --           | --      | --                                  |
| <b><i>Landscape and Visual</i></b>   |              |         |                                     |
| --   | --           | --      | --                                  |
| <b><i>Air Quality</i></b>  |              |         |                                     |
| Stockpile and dry surface were observed in Portion 1. The Contractor should improve the dust mitigation measures in Portion 1. | 20 June 2018 | ✓       | Improved/rectified on 27 June 2018. |
| <b><i>Waste / Chemical Management</i></b>  |              |         |                                     |
| --   | --           | --      | --                                  |
| <b><i>Impact on Cultural Heritage</i></b>  |              |         |                                     |
| --   | --           | --      | --                                  |
| <b><i>Permits / Licenses</i></b>   |              |         |                                     |
|  |              |         |                                     |

- ✓ Observation/reminder was made during site audit but improved/rectified by the contractor in the next site audit
- ✗ Observation/reminder was made during site audit but not yet improved/rectified by the contractor in the next site audit
- # Follow up action will be reported in next reporting month
- \* Non-compliance of mitigation measure
- Non-compliance but rectified by the contractor



---

---

**APPENDIX M**  
**EVENT AND ACTION PLANS**

---

---

### Event and Action Plan for Air Quality (Dust)

| EVENT   | ACTION  |   |  |   |
|---|---|---|--|---|
|   | ET  | IEC   | ER   | CONTRACTOR  |
| Action level being exceeded by one sampling                     | <ol style="list-style-type: none"> <li>1. Identify source, investigate the causes of complaint and propose remedial measures;</li> <li>2. Inform IEC and ER;</li> <li>3. Repeat measurement to confirm finding;</li> <li>4. Increase monitoring frequency to daily.</li> </ol>  | <ol style="list-style-type: none"> <li>1. Check monitoring data submitted by ET;</li> <li>2. Check Contractor's working method.</li> </ol>  | <ol style="list-style-type: none"> <li>1. Notify Contractor.</li> </ol>  | <ol style="list-style-type: none"> <li>1. Rectify any unacceptable practice;</li> <li>2. Amend working methods if appropriate.</li> </ol>   |
| Action level being exceeded by two or more consecutive sampling | <ol style="list-style-type: none"> <li>1. Identify source;</li> <li>2. Inform IEC and ER;</li> <li>3. Advise the ER on the effectiveness of the proposed remedial measures;</li> <li>4. Repeat measurements to confirm findings;</li> <li>5. Increase monitoring frequency to daily;</li> <li>6. Discuss with IEC and Contractor on remedial actions required;</li> <li>7. If exceedance continues, arrange meeting with IEC and ER;</li> </ol> | <ol style="list-style-type: none"> <li>1. Check monitoring data submitted by ET;</li> <li>2. Check Contractor's working method;</li> <li>3. Discuss with ET and Contractor on possible remedial measures;</li> <li>4. Advise the ET on the effectiveness of the proposed remedial measures;</li> <li>5. Supervise Implementation of remedial measures.</li> </ol> | <ol style="list-style-type: none"> <li>1. Confirm receipt of notification of exceedance in writing;</li> <li>2. Notify Contractor;</li> <li>3. Ensure remedial measures properly implemented.</li> </ol> | <ol style="list-style-type: none"> <li>1. Submit proposals for remedial actions to IEC within three working days of notification;</li> <li>2. Implement the agreed proposals;</li> <li>3. Amend proposal if appropriate.</li> </ol> |

| EVENT  | ACTION  |   |  |  |
|--|---|---|--|--|
|  | ET  | IEC   | ER   | CONTRACTOR   |
|  | 8. If exceedance stops, cease additional monitoring.  |   |  |  |
| Limit level being exceeded by one sampling                     | <ol style="list-style-type: none"> <li>1. Identify source, investigate the causes of exceedance and propose remedial measures;</li> <li>2. Inform Contractor ,IEC, ER, and EPD;</li> <li>3. Repeat measurement to confirm finding;</li> <li>4. Increase monitoring frequency to daily;</li> <li>5. Assess effectiveness of Contractor's remedial actions and keep IEC, EPD and ER informed of the results.</li> </ol> | <ol style="list-style-type: none"> <li>1. Check monitoring data submitted by ET;</li> <li>2. Check Contractor's working method;</li> <li>3. Discuss with ET and Contractor on possible remedial measures;</li> <li>4. Advise the ER on the effectiveness of the proposed remedial measures;</li> <li>5. Supervise implementation of remedial measures.</li> </ol> | <ol style="list-style-type: none"> <li>1. Confirm receipt of notification of exceedance in writing;</li> <li>2. Notify Contractor;</li> <li>3. Ensure remedial measures properly implemented.</li> </ol>   | <ol style="list-style-type: none"> <li>1. Take immediate action to avoid further exceedance;</li> <li>2. Submit proposals for remedial actions to IEC within three working days of notification;</li> <li>3. Implement the agreed proposals;</li> <li>4. Amend proposal if appropriate.</li> </ol> |
| Limit level being exceeded by two or more consecutive sampling | <ol style="list-style-type: none"> <li>1. Notify IEC, ER, Contractor and EPD;</li> <li>2. Identify source;</li> <li>3. Repeat measurement to confirm findings;</li> <li>4. Increase monitoring frequency to daily;</li> </ol>   | <ol style="list-style-type: none"> <li>1. Discuss amongst ER, ET, and Contractor on the potential remedial actions;</li> <li>2. Review Contractor's remedial actions whenever necessary to assure their effectiveness and advise the ER accordingly;</li> </ol>   | <ol style="list-style-type: none"> <li>1. Confirm receipt of notification of exceedance in writing;</li> <li>2. Notify Contractor;</li> <li>3. In consolidation with the IEC, agree with the Contractor on the remedial measures to be implemented;</li> </ol> | <ol style="list-style-type: none"> <li>1. Take immediate action to avoid further exceedance;</li> <li>2. Submit proposals for remedial actions to IEC within three working days of notification;</li> <li>3. Implement the agreed proposals;</li> </ol>  |

| EVENT | ACTION  |   |  |  |
|-------|---|---|--|--|
|       | ET  | IEC   | ER   | CONTRACTOR   |
|       | 5. Carry out analysis of Contractor’s working procedures to determine possible mitigation to be implemented;<br>6. Arrange meeting with IEC and ER to discuss the remedial actions to be taken;<br>7. Assess effectiveness of Contractor’s remedial actions and keep IEC, EPD and ER informed of the results;<br>8. If exceedance stops, cease additional monitoring. | 3. Supervise the implementation of remedial measures. | 4. Ensure remedial measures properly implemented;<br>5. If exceedance continues, consider what portion of the work is responsible and instruct the Contractor to stop that portion of work until the exceedance is abated. | 4. Resubmit proposals if problem still not under control;<br>5. Stop the relevant portion of works as determined by the ER until the exceedance is abated. |

### Event and Action Plan for Construction Noise

| EVENT        | ACTION   |   |  |   |
|--------------|--|---|--|---|
|              | ET   | IEC   | ER   | CONTRACTOR  |
| Action Level | <ol style="list-style-type: none"> <li>1. Notify IEC and Contractor;</li> <li>2. Carry out investigation;</li> <li>3. Report the results of investigation to the IEC, ER and Contractor;</li> <li>4. Discuss with the Contractor and formulate remedial measures;</li> <li>5. Increase monitoring frequency to check mitigation effectiveness.</li> </ol>  | <ol style="list-style-type: none"> <li>1. Review the analysed results submitted by the ET;</li> <li>2. Review the proposed remedial measures by the Contractor and advise the ER accordingly;</li> <li>3. Supervise the implementation of remedial measures.</li> </ol>   | <ol style="list-style-type: none"> <li>1. Confirm receipt of notification of failure in writing;</li> <li>2. Notify Contractor;</li> <li>3. Require Contractor to propose remedial measures for the analysed noise problem;</li> <li>4. Ensure remedial measures are properly implemented.</li> </ol>  | <ol style="list-style-type: none"> <li>1. Submit noise mitigation proposals to IEC;</li> <li>2. Implement noise mitigation proposals.</li> </ol>  |
| Limit Level  | <ol style="list-style-type: none"> <li>1. Identify source;</li> <li>2. Inform IEC, ER, EPD and Contractor;</li> <li>3. Repeat measurements to confirm findings;</li> <li>4. Increase monitoring frequency;</li> <li>5. Carry out analysis of Contractor's working procedures to determine possible mitigation to be implemented;</li> <li>6. Inform IEC, ER and EPD the causes and actions taken for the exceedances;</li> </ol> | <ol style="list-style-type: none"> <li>1. Discuss amongst ER, ET, and Contractor on the potential remedial actions;</li> <li>2. Review Contractors remedial actions whenever necessary to assure their effectiveness and advise the ER accordingly;</li> <li>3. Supervise the implementation of remedial measures.</li> </ol> | <ol style="list-style-type: none"> <li>1. Confirm receipt of notification of failure in writing;</li> <li>2. Notify Contractor;</li> <li>3. Require Contractor to propose remedial measures for the analysed noise problem;</li> <li>4. Ensure remedial measures properly implemented;</li> <li>5. If exceedance continues, consider what portion of the work is responsible and instruct the Contractor to stop that portion of work until the exceedance is abated.</li> </ol> | <ol style="list-style-type: none"> <li>1. Take immediate action to avoid further exceedance;</li> <li>2. Submit proposals for remedial actions to IEC within 3 working days of notification;</li> <li>3. Implement the agreed proposals;</li> <li>4. Resubmit proposals if problem still not under control;</li> <li>5. Stop the relevant portion of works as determined by the ER until the exceedance is abated.</li> </ol> |

| EVENT | ACTION   |     |    |            |
|-------|--|-----|----|------------|
|       | ET   | IEC | ER | CONTRACTOR |
|       | 7. Assess effectiveness of Contractor's remedial actions and keep IEC, EPD and ER informed of the results;<br>8. If exceedance stops, cease additional monitoring. |     |    |            |

**Event and Action Plan for Marine Water Quality**

| <b>Event</b>   | <b>Action</b>   |   |   |   |
|--|---|---|---|---|
|  | <b>ET</b>   | <b>IEC</b>  | <b>ER</b>   | <b>CONTRACTOR</b>   |
| Action level being exceeded by one sampling day at water sensitive receiver(s) | <ul style="list-style-type: none"> <li>Identify the source(s) of impact by comparing the results with those collected at the control stations as appropriate;</li> <li>If exceedance is found to be caused by the reclamation activities, repeat <i>in-situ</i> measurement to confirm findings;</li> <li>Inform IEC and contractor;</li> <li>Check monitoring data, all plant, equipment and Contractor's working methods;</li> <li>If exceedance occurs at WSD salt water intake, inform WSD;</li> <li>Discuss mitigation measures with IEC and Contractor;</li> <li>Repeat measurement on next day of exceedance.</li> </ul> | <ul style="list-style-type: none"> <li>Discuss with ET and Contractor on the mitigation measures;</li> <li>Review proposal on mitigation measures submitted by Contractor and advise the ER accordingly;</li> <li>Assess the effectiveness of the implemented mitigation measures.</li> </ul> | <ul style="list-style-type: none"> <li>Discuss with IEC on the proposed mitigation measures;</li> <li>Make agreement on the mitigation proposal.</li> </ul> | <ul style="list-style-type: none"> <li>Inform the ER and confirm notification of the non-compliance in writing;</li> <li>Rectify unacceptable practice;</li> <li>Check all plant and equipment;</li> <li>Amend working methods if appropriate;</li> <li>Discuss with ET and IEC and propose mitigation measures to IEC and ER;</li> <li>Implement the agree mitigation measures.</li> </ul> |
| Action level being exceeded by two or more consecutive                         | <ul style="list-style-type: none"> <li>Identify the source(s) of impact by comparing the results with those collected at the control stations as appropriate;</li> </ul>  | <ul style="list-style-type: none"> <li>Discuss with ET and Contractor on the mitigation measures;</li> </ul>  | <ul style="list-style-type: none"> <li>Discuss with IEC on the proposed mitigation measures;</li> <li>Make agreement on the mitigation proposal;</li> </ul> | <ul style="list-style-type: none"> <li>Inform the Engineer and confirm notification of the non-compliance in writing;</li> <li>Rectify unacceptable practice;</li> </ul>  |

| Event   | Action  |   |  |   |
|---|---|---|--|---|
|   | ET  | IEC   | ER   | CONTRACTOR  |
| sampling days at water sensitive receiver(s)                                  | <ul style="list-style-type: none"> <li>• If exceedance is found to be caused by the reclamation activities, repeat in-situ measurement to confirm findings;</li> <li>• Inform IEC and contractor;</li> <li>• Check monitoring data, all plant, equipment and Contractor's working methods;</li> <li>• Discuss mitigation measures with IEC and Contractor;</li> <li>• Ensure mitigation measures are implemented;</li> <li>• Prepare to increase the monitoring frequency to daily;</li> <li>• If exceedance occurs at WSD salt water intake, inform WSD;</li> <li>• Repeat measurement on next day of exceedance.</li> </ul> | <ul style="list-style-type: none"> <li>• Review proposal on mitigation measures submitted by Contractor and advise the ER accordingly;</li> <li>• Assess the effectiveness of the implemented mitigation measures.</li> </ul> | <ul style="list-style-type: none"> <li>• Assess the effectiveness of the implemented mitigation measures.</li> </ul>   | <ul style="list-style-type: none"> <li>• Check all plant and equipment and consider changes of working methods;</li> <li>• Discuss with ET, IEC and ER and propose mitigation measures to IEC and ER within 3 working days;</li> <li>• Implement the agreed mitigation measures.</li> </ul> |
| Limit level being exceeded by one sampling day at water sensitive receiver(s) | <ul style="list-style-type: none"> <li>• Identify the source(s) of impact by comparing the results with those collected at the control stations as appropriate;</li> </ul>  | <ul style="list-style-type: none"> <li>• Discuss with ET and Contractor on the mitigation measures;</li> <li>• Review proposal on mitigation measures submitted by Contractor and advise the ER accordingly;</li> </ul>       | <ul style="list-style-type: none"> <li>• Discuss with IEC, ET and Contractor on the proposed mitigation measures;</li> <li>• Request Contractor to critically review the working methods;</li> </ul> | <ul style="list-style-type: none"> <li>• Inform the ER and confirm notification of the non-compliance in writing;</li> <li>• Rectify unacceptable practice;</li> </ul>  |



| Event  | Action  |   |  |  |
|--|---|---|--|--|
|  | ET  | IEC   | ER   | CONTRACTOR   |
|  | <ul style="list-style-type: none"> <li>• If exceedance is found to be caused by the reclamation activities, repeat <i>in-situ</i> measurement to confirm findings;</li> <li>• Inform IEC, contractor, AFCD and EPD</li> <li>• Check monitoring data, all plant, equipment and Contractor's working methods;</li> <li>• Discuss mitigation measures with IEC, ER and Contractor;</li> <li>• Ensure mitigation measures are implemented;</li> <li>• Increase the monitoring frequency to daily until no exceedance of Limit level;</li> <li>• If exceedance occurs at WSD salt water intake, inform WSD.</li> </ul> | <ul style="list-style-type: none"> <li>• Assess the effectiveness of the implemented mitigation measures.</li> </ul>  | <ul style="list-style-type: none"> <li>• Make agreement on the mitigation measures to be implemented;</li> <li>• Assess the effectiveness of the implemented mitigation measures.</li> </ul>           | <ul style="list-style-type: none"> <li>• Check all plant and equipment and consider changes of working methods;</li> <li>• Discuss with ET, IEC and ER and submit proposal of mitigation measures to IEC and ER within 3 working days of notification;</li> <li>• Implement the agreed mitigation measures.</li> </ul> |
| Limit level being exceeded by two or more consecutive sampling days at | <ul style="list-style-type: none"> <li>• Identify the source(s) of impact by comparing the results with those collected at the control stations as appropriate;</li> </ul>  | <ul style="list-style-type: none"> <li>• Discuss with ET and Contractor on the mitigation measures;</li> <li>• Review proposal on mitigation measures submitted by Contractor and advise the ER accordingly;</li> </ul> | <ul style="list-style-type: none"> <li>• Discuss with IC(E), ET and Contractor on the proposed mitigation measures;</li> <li>• Request Contractor to critically review the working methods;</li> </ul> | <ul style="list-style-type: none"> <li>• Inform the ER and confirm notification of the non-compliance in writing;</li> <li>• Rectify unacceptable practice;</li> </ul>   |

| Event                       | Action   |  |  |  |
|-----------------------------|--|--|--|--|
|                             | ET   | IEC  | ER   | CONTRACTOR   |
| water sensitive receiver(s) | <ul style="list-style-type: none"> <li>• If exceedance is found to be caused by the reclamation activities, repeat in-situ measurement to confirm findings;</li> <li>• Inform IC(E), AFCD, contractor and EPD;</li> <li>• Check monitoring data, all plant, equipment and Contractor's working methods;</li> <li>• Discuss mitigation measures with IC(E), ER and Contractor;</li> <li>• Ensure mitigation measures are implemented;</li> <li>• Increase the monitoring frequency to daily until no exceedance of Limit level for two consecutive days;</li> <li>• If exceedance occurs at WSD salt water intake, inform WSD.</li> </ul> | <ul style="list-style-type: none"> <li>• Assess the effectiveness of the implemented mitigation measures.</li> </ul> | <ul style="list-style-type: none"> <li>• Make agreement on the mitigation measures to be implemented;</li> <li>• Assess the effectiveness of the implemented mitigation measures;</li> <li>• Consider and instruct, if necessary, the Contractor to slow down or to stop all or part of the marine work until no exceedance of Limit level.</li> </ul> | <ul style="list-style-type: none"> <li>• Check all plant and equipment and consider changes of working methods;</li> <li>• Discuss with ET, IC(E) and ER and submit proposal of mitigation measures to IC(E) and ER within 3 working days of notification;</li> <li>• Implement the agreed mitigation measures;</li> <li>• As directed by the Engineer, to slow down or to stop all or part of the construction activities.</li> </ul> |

**Limit Levels and Action Plan for Landfill Gas**

| Parameter      | Limit Level                      | Action   |
|----------------|----------------------------------|--|
| Oxygen         | <19%                             | <ul style="list-style-type: none"> <li>• Ventilate to restore oxygen to &gt;19%</li> </ul>   |
|                | <18%                             | <ul style="list-style-type: none"> <li>• Stop works</li> <li>• Evacuate personnel/prohibit entry</li> <li>• Increase ventilation to restore oxygen to &gt;19%</li> </ul>             |
| Methane        | >10% LEL (i.e. > 0.5% by volume) | <ul style="list-style-type: none"> <li>• Prohibit hot works</li> <li>• Ventilate to restore methane to &lt;10% LEL</li> </ul>  |
|                | >20% LEL (i.e. > 1% by volume)   | <ul style="list-style-type: none"> <li>• Stop works</li> <li>• Evacuate personnel / prohibit entry</li> <li>• Increase ventilation to restore methane to &lt;10% LEL</li> </ul>      |
| Carbon Dioxide | >0.5%                            | <ul style="list-style-type: none"> <li>• Ventilate to restore carbon dioxide to &lt; 0.5%</li> </ul>   |
|                | >1.5%                            | <ul style="list-style-type: none"> <li>• Stop works</li> <li>• Evacuate personnel / prohibit entry</li> <li>• Increase ventilation to restore carbon dioxide to &lt; 0.5%</li> </ul> |

**Event and Action Plan for Coral Post-Translocation Monitoring**

| <b>Event</b>                   | <b>Action</b>  |  |   |  |
|--------------------------------|--|--|---|--|
|                                | <b>ET Leader</b>   | <b>IEC</b>   | <b>ER</b>   | <b>Contractor</b>  |
| <b>Action Level Exceedance</b> | 1. Check monitoring data;<br>2. Inform the IEC, ER and Contractor of the findings;<br>3. Increase the monitoring to at least once a month to confirm findings;<br>4. Propose mitigation measures for consideration | 1. Discuss monitoring with the ET and the Contractor;<br>2. Review proposals for additional Monitoring and any other measures submitted by the Contractor and advise the ER accordingly. | 1. Discuss with the IEC additional monitoring requirements and any other measures proposed by the ET;<br>2. Make agreement on the measures to be implemented. | 1. Inform the ER and confirm notification of the non-compliance in writing;<br>2. Discuss with the ET and the IEC and propose measures to the IEC and the ER;<br>3. Implement the agreed measures. |
| <b>Limit Level Exceedance</b>  | Undertake Steps 1-4 as in the Action Level Exceedance. If further exceedance of Limit Level, suspend construction works until an effective solution is identified.   | 1. Discuss monitoring with the ET and the Contractor;<br>2. Review proposals for additional Monitoring and any other measures submitted by the Contractor and advise the ER accordingly. | 1. Discuss with the IEC additional monitoring requirements and any other measures proposed by the ET;<br>2. Make agreement on the measures to be implemented. | 1. Inform the ER and confirm notification of the non-compliance in writing;<br>2. Discuss with the ET and the IEC and propose measures to the IEC and the ER;<br>3. Implement the agreed measures. |

### Mitigation Measures for Vibration Monitoring

| Level       | Contingency Action   |
|-------------|--|
| Alert Level | <ul style="list-style-type: none"> <li>● The Engineer shall be informed immediately.</li> <li>● The Contractor shall submit an investigation report to describe works being undertaken. To review the instrument responses and to study the cause of undue response.</li> <li>● The Contractor shall review and increase the instrumentation monitoring and reporting frequency, if applicable.</li> <li>● The Contractor shall submit a detailed plan of action describing the measures to be taken should the concerned instrument reach the action level to the Engineer for approval.</li> </ul>   |
| Alarm Level | <ul style="list-style-type: none"> <li>● The Engineer shall be informed immediately.</li> <li>● The active construction works may require to be suspended subject to the Engineer's review of monitoring data.</li> <li>● The Contractor shall immediately implement the measures as defined in the detailed plan of action to prevent further ground movement and groundwater drawdown etc.</li> <li>● The Contractor shall prepare a detailed investigation report to study the cause of the exceedance</li> <li>● The Contractor shall propose a contingency plan for the Engineer's approval in the event that alarm value is reached or exceeded</li> <li>● The Contractor shall develop an emergency plan for the Engineer's approval in the event the applied contingency measures cannot control the situation.</li> <li>● The Contractor shall meet the Engineer to discuss the instrument response and review the effectiveness of the implemented measures.</li> <li>● The Contractor shall carry out design review of the works</li> </ul> |

|              |  |
|--------------|--|
| Action Level | <ul style="list-style-type: none"><li>● Consideration shall be given to suspend all active construction works and the Engineer shall be informed immediately</li><li>● The Contractor shall immediately implement the measures defined in the contingency plan</li><li>● The Contractor shall implement the measures defined in the emergency plan in the event that the applied contingency measures are found inadequate</li><li>● The Contractor shall provide a complete report to examine the construction method and review the response of the instruments with full history of the monitoring data and construction activities and necessary design update</li><li>● To resume the suspended activities, the Contractor shall demonstrate to the Engineer's satisfaction that it is safe to do so with approval from the Engineer.</li></ul> |
|--------------|--|

---

---

**APPENDIX N  
ENVIRONMENTAL MITIGATION  
IMPLEMENTATION SCHEDULE (EMIS)**

---

---

**Table I – Recommended Mitigation Measures stipulated in EM&A Manual of the Project**

(Further information on observations/reminders/non-compliance made during site audit should refer to Table II)

- Key:**
- ^ Mitigation measure was fully implemented.
  - \* Observation/reminder was made during site audit but improved/rectified by the contractor.
  - # Observation/reminder was made during site audit but not yet improved/rectified by the contractor.
  - X Non-compliance of mitigation measure
  - Non-compliance but rectified by the contractor
  - N/A Not Applicable

| EIA Ref. | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address | Who to implement the measures? | Location of the measures    | When to Implement the measures? | What requirements or standards for the measures to achieve?   | Status           |
|----------|--|---|--------------------------------|-----------------------------|---------------------------------|---|------------------|
| S3.8.1   | Watering eight times a day on active works areas, exposed areas and paved haul roads   | To minimize the dust impact                                       | Contractor                     | All Active Work Sites       | Construction phase              | APCO  | *(1)             |
| S3.8.1   | Enclosing the unloading process at barging point by a 3-sided screen with top tipping hall / mixing area in Work Area A, provision of water spraying and flexible dust curtains  | To minimize the dust impact                                       | Contractor                     | Barging Points              | Construction phase              | APCO  | ^                |
| S3.8.7   | Dust suppression measures stipulated in the Air Pollution Control (Construction Dust) Regulation and good site practices:<br><ul style="list-style-type: none"> <li>- Use of regular watering to reduce dust emissions from exposed site surfaces and unpaved roads, particularly during dry weather.</li> <li>- Use of frequent watering for particularly dusty construction areas and areas close to ASRs.</li> <li>- Side enclosure and covering of any aggregate or dusty material storage piles to</li> </ul> | To minimize the dust impact                                       | Contractor                     | All Construction Work Sites | Construction phase              | APCO and Air Pollution Control (Construction Dust) Regulation | *(1)<br><br>*(1) |



**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref. | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status   |
|----------|--|---|--------------------------------|--------------------------|---------------------------------|---|--|
|          | <p>reduce emissions. Where this is not practicable owing to frequent usage, watering shall be applied to aggregate fines.</p> <ul style="list-style-type: none"> <li>- Open stockpiles shall be avoided or covered. Where possible, prevent placing dusty material storage piles near ASRs.</li> <li>- Tarpaulin covering of all dusty vehicle loads transported to, from and between site locations.</li> <li>- Establishment and use of vehicle wheel and body washing facilities at the exit points of the site.</li> <li>- Provision of wind shield and dust extraction units or similar dust mitigation measures at the loading area of barging point, and use of water sprinklers at the loading area where dust generation is likely during the loading process of loose material, particularly in dry seasons/ periods.</li> <li>- Provision of not less than 2.4m high hoarding from ground level along site boundary where adjoins a road, streets or other accessible to the public except for a site entrance or exit.</li> <li>- Imposition of speed controls for vehicles on site haul roads.</li> <li>- Where possible, routing of vehicles and positioning of construction plant should be at the maximum possible distance from ASRs</li> <li>- Every stock of more than 20 bags of cement or dry pulverised fuel ash (PFA) should be covered entirely by impervious sheeting or placed in an area sheltered on the top and the 3 sides.</li> <li>- Instigation of an environmental monitoring and auditing program to monitor the</li> </ul> |   |                                |                          |                                 |   | <p>*(1)/#(1)</p> <p>^</p> <p>N/A</p> <p>*(1)/#(1)</p> <p>^</p> <p>^</p> <p>^</p> <p>^</p> <p>^</p> |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref.                                 | Recommended Mitigation Measures   | Objectives of the recommended Measures & Main Concerns to address                   | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status      |
|--|---|---|--------------------------------|--------------------------|---------------------------------|---|-------------|
|  | construction process in order to enforce controls and modify method of work if dusty conditions arise.  |   |                                |                          |                                 |   |             |
| /  | Emission from Vehicles and Plants <ul style="list-style-type: none"> <li>• All vehicles shall be shut down in intermittent use.</li> <li>• Only well-maintained plant should be operated on-site and plant should be serviced regularly to avoid emission of black smoke.</li> <li>• All diesel fuelled construction plant within the works areas shall be powered by ultra low sulphur diesel fuel (ULSD)</li> </ul>   | Reduce air pollution emission from construction vehicles and plants                 | Contractor                     | All construction sites   | Construction stage              | • APCO  | ^<br>^<br>^ |
| /  | Valid No-road Mobile Machinery (NRMM) labels should be provided to regulated machines   | Reduce air pollution emission from construction vehicles and plants                 | Contractor                     | All construction sites   | Construction stage              | • APCO  | *(2)        |
| <b>Noise Impact (Construction Phase)</b> |   |   |                                |                          |                                 |   |             |
| S4.8                                     | - Use of quiet PME. Use of movable noise barriers for Excavator, Lorry, Dump Truck, Mobile Crane, Compactor, Concrete Mixer Truck, Concrete Lorry Mixer, Breaker, Mobile Crusher, Backhoe, Vibratory Poker, Saw, Asphalt Paver, Vibratory Roller, Vibrolance, Hydraulic Vibratory Lance and Piling (Vibration Hammer). Use of full enclosure for Air Compressor, Compressor, Bar Bender, Generator, Drilling Rig, Chisel, Large Diameter Bore Piling, Grout Mixer & Pump and Concrete Pump. | To minimize construction noise impact arising from the Project at the affected NSRs | Contractor                     | Work Sites               | Construction phase              | EIAO-TM, NCO  | #(3)        |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref.              | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address                   | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status                     |
|-----------------------|--|---|--------------------------------|--------------------------|---------------------------------|---|----------------------------|
| Noise Mitigation Plan | Use of Temporary Noise Barriers or Full Enclosure for PME according to the approved Noise Mitigation Plan  | To minimize construction noise impact arising from the Project at the affected NSRs | Contractor                     | Work Sites               | Construction phase              | EIAO-TM, NCO  | *(2)                       |
| S4.9                  | <p>Good Site Practice</p> <ul style="list-style-type: none"> <li>- Only well-maintained plant should be operated on-site and plant should be serviced regularly during the construction program</li> <li>- Silencers or mufflers on construction equipment should be utilized and should be properly maintained during the construction program.</li> <li>- Mobile plant, if any, should be sited as far away from NSRs as possible.</li> <li>- Machines and plant (such as trucks) that may be in intermittent use should be shut down between works periods or should be throttled down to a minimum.</li> <li>- Plant known to emit noise strongly in one direction should, wherever possible, be orientated so that the noise is directed away from the nearby NSRs.</li> <li>- Material stockpiles and other structures should be effectively utilized, wherever practicable, in screening noise from on-site construction activities.</li> </ul> | To minimize construction noise impact arising from the Project at the affected NSRs | Project Proponent              | Work sites               | Construction Period             | EIAO-TM, NCO  | ^<br>^<br>^<br>^<br>^<br>^ |
| S4.9                  | Scheduling of Construction Works during School Examination Period  | To minimize construction noise impact arising from the                              | Contractor                     | Work site near school    | Construction phase              | EIAO-TM, NCO  | N/A                        |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref.   | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address | Who to implement the measures? | Location of the measures           | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status |
|--|--|---|--------------------------------|------------------------------------|---------------------------------|---|--------|
|  |  | Project at the affected NSRs                                      |                                |                                    |                                 |   |        |
| <b>Water Quality Impact (Construction Phase)</b> |  |   |                                |                                    |                                 |   |        |
| S5.6.24  | The dry density of filling material for the TKO-LT Tunnel reclamation should be 1,900kg/m <sup>3</sup> , with fine content of 25% or less  | Control potential impacts from filling activities                 | CEDD's Contractors             | Work site                          | Construction Phase              | EIAO-TM, WPCO   | N/A    |
| S5.8.1   | Non-dredged method by constructing steel cellular caisson structure with stone column shall be adopted for construction of seawall foundation. During the stone column installation (also including the installation of steel cellular caisson), silt curtain shall be employed around the active stone column installation points.  | Control potential impacts from filling activities                 | CEDD's Contractors             | Work site                          | Construction Phase              | EIAO-TM, WPCO   | N/A    |
| S5.8.2   | Formation of seawall enclosing the reclamation for Road P2 (notwithstanding an opening of about 50m for marine access) shall be completed prior to the filling activities. The seawall opening of about 50m wide for marine access shall be selected at a location as indicatively shown in Appendix 5.10. No more than 3 filling barge trips per day shall be made with a maximum daily rate of 3,000m <sup>3</sup> (i.e. 1,000 m <sup>3</sup> per trip) for the filling operation at the reclamation area for Road P2. All filling works shall be carried out behind the seawall with the use of single silt curtain at the marine access. | Control potential impacts from filling activities                 | CEDD's Contractors             | Work site                          | Construction Phase              | EIAO-TM, WPCO   | N/A    |
| Silt Curtain Deployment Plan                     | <ul style="list-style-type: none"> <li>- Silt curtains should be deployed properly to surround the works area.</li> <li>- Maintenance of silt curtain should be provided.</li> <li>- Sufficient stock of silt curtain should be provided on site.</li> </ul>   | Control potential impacts from marine works                       | Contractor                     | NE/2015/01, NE/2015/02, NE/2017/01 | Construction stage              | EIAO  | #4     |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref.                 | Recommended Mitigation Measures   | Objectives of the recommended Measures & Main Concerns to address | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status   |
|--------------------------|---|---|--------------------------------|--------------------------|---------------------------------|---|--|
| Sediment Management Plan | <ul style="list-style-type: none"> <li>- Loading of barges and hoppers will be controlled to prevent splashing of dredged materials into the surrounding water. Barges or hoppers will not be filled to a level that will cause the overflow of materials or pollute water during loading or transportation.</li> <li>- Bottom opening of barges shall be fitted with tight fitting seals to prevent leakage of material. Excess material shall be cleaned from the decks and exposed fittings of barges and hopper dredgers before the vessel is moved.</li> <li>- Monitoring of the barge loading shall be conducted to ensure that loss of material does not take during transportation.</li> <li>- Transport barges or vessels shall be equipped with automatic self-monitoring devices.</li> <li>- Vehicles containing any untreated / treated marine sediments will be suitably covered to limit potential dust emissions or potential contaminated wastewater run-off, and truck bodies and tailgates will be sealed to prevent any discharge during transport or wet conditions.</li> <li>- The leachate from the untreated marine sediment will be collected and treated in the mixing pool for cement s/s treatment.</li> <li>- A 300mm diameter U-channel will be constructed along the perimeter of the cement s/s treatment facility to collect the run-off, if any, shall be collected and discharged according to the Water Pollution Control Ordinance (WPCO). Cleaning for the u-channel and desilting pits shall be conducted on weekly basic.</li> </ul> | Control potential impacts from Cement s/s process                 | Contractor                     | NE/2015/02               | Construction stage              | EIAO, WPCO  | <p>^</p> <p>^</p> <p>^</p> <p>^</p> <p>^</p> <p>^</p> <p>^</p> |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref.      | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address                     | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status            |
|---------------|--|---|--------------------------------|--------------------------|---------------------------------|---|-------------------|
|               | <ul style="list-style-type: none"> <li>- The stockpile area of treated marine sediment will be surrounded by the perimeter concrete block walls with geotextile membranes installed at the inner face of the concrete block walls. The types of perimeter wall can be used interchangeably. The Structural Feasibility of the perimeter wall for the changes of height of the stockpile had been checked and certified by ICE.</li> <li>- The mixing areas will be completely paved or covered by linings in order to avoid contamination to underlying soil or groundwater and will be confined by partition concrete block walls for carrying out the mixing and temporary stockpile of treated sediment.</li> </ul> |   |                                |                          |                                 |   | <p>^</p> <p>^</p> |
| S5.8.4        | Site specific mitigation plan for reclamation areas using public fill materials should be submitted for EPD agreement before commencement of construction phase with due consideration of good site practices.   | Control potential impacts from filling activities and marine based construction       | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | N/A               |
| ERR<br>S5.6.1 | <p>To minimize water quality impact arising from the dredging and filling works for Reclamation for Road P2, the following mitigation measures shall be implemented:</p> <ul style="list-style-type: none"> <li>- Before carrying out any dredging and underwater filling works, a temporary barrier shall first be constructed to a height above the high water mark to completely enclose the works site (without any opening at the barrier wall)</li> <li>- The temporary barrier fully enclosing the dredging and underwater filling works site shall not be removed before completion of all dredging and underwater</li> </ul>  | Control potential impacts from dredging and filling works for Reclamation for Road P2 | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | <p>^</p> <p>^</p> |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref. | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address                   | Who to implement the measures? | Location of the measures | When to Implement the measures?     | What requirements or standards for the measures to achieve? | Status       |
|----------|--|---|--------------------------------|--------------------------|-------------------------------------|---|--------------|
|          | filling works.<br>- Water quality sampling and testing shall be carried out to demonstrate that the water quality inside the enclosed barrier is comparable to the ambient or baseline levels prior to the removal of the fully enclosed barrier.<br>- Silt curtains shall be deployed for the installation and removal of the temporary barrier and at the double water gates marine access opening during its operation. The general of arrangement of silt curtain is shown in Figure 7 of the existing Environmental Permit (No. EP-458/2013/C). |   |                                |                          |                                     |   | N/A<br><br>^ |
| S5.8.5   | It is important that appropriate measures are implemented to control runoff and drainage and prevent high loading of SS from entering the marine environment. Proper site management is essential to minimise surface water runoff, soil erosion and sewage effluents.   | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase                  | ProPECC PN 1/94, EIAOTM, WPCO                               | ^            |
| S5.8.6   | Any practical options for the diversion and realignment of drainage should comply with both engineering and environmental requirements in order to ensure adequate hydraulic capacity of all drains.   | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Design Stage and Construction Phase | ProPECC PN 1/94, EIAOTM, WPCO, TM-DSS                       | ^            |
| S5.8.7   | Construction site runoff and drainage should be prevented or minimised in accordance with the guidelines stipulated in the EPD's Practice Note for Professional Persons,   | Control potential impacts from  | CEDD's Contractors             | Work site                | Construction Phase                  | ProPECC PN 1/94, EIAOTM, WPCO, TM-DSS                       | *(5)/ #(5)   |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref. | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address                   | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status   |
|----------|--|---|--------------------------------|--------------------------|---------------------------------|---|----------|
|          | Construction Site Drainage (ProPECC PN 1/94). Good housekeeping and stormwater best management practices, as detailed in below, should be implemented to ensure that all construction runoff complies with WPCO standards and no unacceptable impact on the WSRs arises due to construction of the TKO-LT Tunnel. All discharges from the construction site should be controlled to comply with the standards for effluents discharged into the corresponding WCZ under the TM-DSS.  | construction site runoff and land-based construction                                |                                |                          |                                 |   |          |
| S5.8.8   | Exposed soil areas should be minimised to reduce the potential for increased siltation, contamination of runoff, and erosion. Construction runoff related impacts associated with the above ground construction activities can be readily controlled through the use of appropriate mitigation measures which include:<br>- use of sediment traps; and<br>- adequate maintenance of drainage systems to prevent flooding and overflow.   | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | N/A<br>^ |
| S5.8.9   | Construction site should be provided with adequately designed perimeter channel and pretreatment facilities and proper maintenance. The boundaries of critical areas of earthworks should be marked and surrounded by dykes or embankments for flood protection. Temporary ditches should be provided to facilitate runoff discharge into the appropriate watercourses, via a silt retention pond. Permanent drainage channels should incorporate sediment basins or traps and baffles to enhance deposition rates. The design of efficient silt removal facilities should be based on the guidelines in Appendix A1 of ProPECC PN 1/94. | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | ^        |
| S5.8.10  | Ideally, construction works should be programmed to minimise surface excavation works during the rainy season (April to September). All exposed earth areas should   | Control potential impacts from  | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | ^        |



**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref. | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address                   | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status |
|----------|--|---|--------------------------------|--------------------------|---------------------------------|---|--------|
|          | be completed as soon as possible after earthworks have been completed, or alternatively, within 14 days of the cessation of earthworks where practicable. If excavation of soil cannot be avoided during the rainy season, or at any time of year when rainstorms are likely, exposed slope surfaces should be covered by tarpaulin or other means.  | construction site runoff and land-based construction                                |                                |                          |                                 |   |        |
| S5.8.11  | Sedimentation tanks of sufficient capacity, constructed from pre-formed individual cells of approximately 6 to 8m <sup>3</sup> capacity, are recommended as a general mitigation measure which can be used for settling surface runoff prior to disposal. The system capacity is flexible and able to handle multiple inputs from a variety of sources and particularly suited to applications where the influent is pumped. | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO S5                            | *(6)   |
| S5.8.12  | Earthworks final surfaces should be well compacted and the subsequent permanent work or surface protection should be carried out immediately after the final surfaces are formed to prevent erosion caused by rainstorms. Appropriate drainage like intercepting channels should be provided where necessary.  | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO S5                            | ^      |
| S5.8.13  | Measures should be taken to minimize the ingress of rainwater into trenches. If excavation of trenches in wet seasons is necessary, they should be dug and backfilled in short sections. Rainwater pumped out from trenches or foundation excavations should be discharged into storm drains via silt removal facilities.  | Control potential impacts from construction site runoff and land-based              | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO S5                            | ^      |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref. | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address                   | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status |
|----------|--|---|--------------------------------|--------------------------|---------------------------------|---|--------|
|          |  | construction  |                                |                          |                                 |   |        |
| S5.8.14  | Open stockpiles of construction materials (for examples, aggregates, sand and fill material) of more than 50m <sup>3</sup> should be covered with tarpaulin or similar fabric during rainstorms. Measures should be taken to prevent the washing away of construction materials, soil, silt or debris into any drainage system.  | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | ^      |
| S5.8.15  | Manholes (including newly constructed ones) should always be adequately covered and temporarily sealed so as to prevent silt, construction materials or debris being washed into the drainage system and storm runoff being directed into foul sewers. Discharge of surface run-off into foul sewers must always be prevented in order not to unduly overload the foul sewerage system.    | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | ^      |
| S5.8.16  | Precautions to be taken at any time of year when rainstorms are likely, actions to be taken when a rainstorm is imminent or forecast, and actions to be taken during or after rainstorms are summarised in Appendix A2 of ProPECC PN 1/94. Particular attention should be paid to the control of silty surface runoff during storm events, especially for areas located near steep slopes. | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | ^      |
| S5.8.17  | Oil interceptors should be provided in the drainage system and regularly cleaned to prevent the release of oils and grease into the storm water drainage system after accidental spillages. The interceptor should have a bypass to prevent flushing   | Control potential impacts from construction site                                    | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | N/A    |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref. | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address                   | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status |
|----------|--|---|--------------------------------|--------------------------|---------------------------------|---|--------|
|          | during periods of heavy rain.  | runoff and land-based construction  |                                |                          |                                 |   |        |
| S5.8.18  | All vehicles and plant should be cleaned before leaving a construction site to ensure no earth, mud, debris and the like is deposited by them on roads. An adequately designed and located wheel washing bay should be provided at every site exit, and washwater should have sand and silt settled out and removed at least on a weekly basis to ensure the continued efficiency of the process. The section of access road leading to, and exiting from, the wheelwash bay to the public road should be paved with sufficient backfall toward the wheel-wash bay to prevent vehicle tracking of soil and silty water to public roads and drains. | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | ^      |
| S5.8.19  | Silt removal facilities, channels and manholes should be maintained and the deposited silt and grit should be removed regularly, at the onset of and after each rainstorm to ensure that these facilities are functioning properly at all times.   | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | ^      |
| S5.8.20  | It is recommended that on-site drainage system should be installed prior to the commencement of other construction activities. Sediment traps should be installed in order to minimise the sediment loading of the effluent prior to discharge into foul sewers. There shall be no direct discharge of effluent from the site into the sea.  | Control potential impacts from construction site runoff and land-based              | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | ^      |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref. | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address                   | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status |
|----------|--|---|--------------------------------|--------------------------|---------------------------------|---|--------|
|          |  | construction  |                                |                          |                                 |   |        |
| S5.8.21  | All temporary and permanent drainage pipes and culverts provided to facilitate runoff discharge should be adequately designed for the controlled release of storm flows. All sediment control measures should be regularly inspected and maintained to ensure proper and efficient operation at all times and particularly following rain storms. The temporarily diverted drainage should be reinstated to its original condition when the construction work has finished or the temporary diversion is no longer required. | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | ^      |
| S5.8.22  | All fuel tanks and storage areas should be provided with locks and be located on sealed areas, within bunds of a capacity equal to 110% of the storage capacity of the largest tank, to prevent spilled fuel oils from reaching the coastal waters.  | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | ^      |
| S5.8.23  | Minimum distances of 100m shall be maintained between the existing or planned stormwater discharges and the existing or planned seawater intakes during construction and operational phases  | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase              | EIAO-TM, WPCO, TMDSS  | ^      |
| S5.8.24  | Under normal circumstances, groundwater pumped out of wells, etc. for the lowering of ground water level in basement or foundation construction, and groundwater seepage pumped out of tunnels or caverns under construction should be discharged  | Control potential impacts from construction site                                    | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | ^      |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref.                       | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address                   | Who to implement the measures? | Location of the measures | When to Implement the measures?    | What requirements or standards for the measures to achieve? | Status |
|--------------------------------|--|---|--------------------------------|--------------------------|------------------------------------|---|--------|
|                                | into storm drains after the removal of silt in silt removal facilities.  | runoff and land-based construction  |                                |                          |                                    |   |        |
| S5.8.25 - S5.8.27 & Table 5.18 | Grouting would be adopted as measure to reduce the groundwater inflow into the tunnel. During the tunnel excavation, the inflow rate of groundwater into the tunnel will be measured during the excavation. The groundwater levels above the tunnel will also be monitored by piezometers. If the inflow rate exceeds the pre-determined groundwater control criteria or the groundwater drawdown exceeds the required limit, pre-excavation grouting will be required to reduce the groundwater inflow. No significant change of groundwater levels would therefore be expected. Any chemicals/foaming agents which would be entrained to the groundwater should be biodegradable and non-toxic throughout the tunnel construction. Potential groundwater quality impact would be minimal as the used material is non-toxic and biodegradable. No adverse groundwater quality would therefore be expected. Prescriptive measures in the form of an Action Plan with pre-emptive and re-active to preserve the groundwater levels at all times during the tunnel construction are set out in Table 5.18. | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase                 | ProPECC PN 1/94, EIAOTM, WPCO, Buildings Ordinance          | N/A    |
| S5.8.28                        | Water used in ground boring and drilling for site investigation or rock / soil anchoring should as far as practicable be recirculated after sedimentation. When there is a need for final disposal, the wastewater should be discharged into storm drains via silt removal facilities.   | Control potential impacts from construction site runoff and land-based              | CEDD's Contractors             | Work site                | Design Stage and Construction Phas | ProPECC PN 1/94, EIAOTM, WPCO                               | N/A    |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref.          | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address                   | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status |
|-------------------|--|---|--------------------------------|--------------------------|---------------------------------|---|--------|
|                   |  | construction  |                                |                          |                                 |   |        |
| S5.8.29 - S5.8.31 | Wastewater generated from the washing down of mixing trucks and drum mixers and similar equipment should whenever practicable be recycled. The discharge of wastewater should be kept to a minimum. To prevent pollution from wastewater overflow, the pump sump of any water recycling system should be provided with an online standby pump of adequate capacity and with automatic alternating devices. Under normal circumstances, surplus wastewater may be discharged into foul sewers after treatment in silt removal and pH adjustment facilities (to within the pH range of 6 to 10). Disposal of wastewater into storm drains will require more elaborate treatment. | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | ^      |
| S5.8.32           | All vehicles and plant should be cleaned before they leave a construction site to ensure no earth, mud, debris and the like is deposited by them on roads. A wheel washing bay should be provided at every site exit if practicable and wash-water should have sand and silt settled out or removed before discharging into storm drains. The section of construction road between the wheel washing bay and the public road should be paved with backfall to reduce vehicle tracking of soil and to prevent site run-off from entering public road drains.  | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | ^      |
| S5.8.33           | Bentonite slurries used in diaphragm wall and borepile construction should be reconditioned and reused wherever practicable. If the disposal of a certain residual quantity cannot be avoided, the used slurry may be disposed of at the marine spoil grounds subject to obtaining a marine dumping licence from EPD on a case-by-case basis.  | Control potential impacts from construction site runoff and land-based              | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | N/A    |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref. | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address                   | Who to implement the measures? | Location of the measures | When to Implement the measures?     | What requirements or standards for the measures to achieve? | Status |
|----------|--|---|--------------------------------|--------------------------|-------------------------------------|---|--------|
|          |  | construction  |                                |                          |                                     |   |        |
| S5.8.34  | If the used bentonite slurry is intended to be disposed of through the public drainage system, it should be treated to the respective effluent standards applicable to foul sewer, storm drains or the receiving waters as set out in the WPCO Technical Memorandum on Effluent Standards. | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase                  | ProPECC PN 1/94, EIAOTM, WPCO                               | N/A    |
| S5.8.35  | Water used in water testing to check leakage of structures and pipes should be reused for other purposes as far as practicable. Surplus unpolluted water could be discharged into storm drains.  | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase                  | ProPECC PN 1/94, EIAOTM, WPCO                               | N/A    |
| S5.8.36  | Sterilization is commonly accomplished by chlorination. Specific advice from EPD should be sought during the design stage of the works with regard to the disposal of the sterilizing water. The sterilizing water should be reused wherever practicable.                                  | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Design Stage and Construction Phase | ProPECC PN 1/94, EIAOTM, WPCO                               | N/A    |
| S5.8.37  | Before commencing any demolition works, all sewer and drainage connections should be sealed to prevent building debris, soil, sand etc. from entering public sewers/drains.  | Control potential impacts from construction site                                    | CEDD's Contractors             | Work site                | Construction Phase                  | ProPECC PN 1/94, EIAOTM, WPCO                               | N/A    |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref. | Recommended Mitigation Measures   | Objectives of the recommended Measures & Main Concerns to address                   | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status |
|----------|---|---|--------------------------------|--------------------------|---------------------------------|---|--------|
|          |   | runoff and land-based construction  |                                |                          |                                 |   |        |
| S5.8.38  | Wastewater generated from building construction activities including concreting, plastering, internal decoration, cleaning of works and similar activities should not be discharged into the stormwater drainage system. If the wastewater is to be discharged into foul sewers, it should undergo the removal of settleable solids in a silt removal facility, and pH adjustment as necessary            | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | ^      |
| S5.8.39  | Acidic wastewater generated from acid cleaning, etching, pickling and similar activities should be neutralized to within the pH range of 6 to 10 before discharging into foul sewers. If there is no public foul sewer in the vicinity, the neutralized wastewater should be tinkered off site for disposal into foul sewers or treated to a standard acceptable to storm drains and the receiving waters | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | ^      |
| S5.8.40  | Wastewater collected from canteen kitchens, including that from basins, sinks and floor drains, should be discharged into foul sewer via grease traps capable of providing at least 20 minutes retention during peak flow.  | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | N/A    |



**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref. | Recommended Mitigation Measures   | Objectives of the recommended Measures & Main Concerns to address                   | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status |
|----------|---|---|--------------------------------|--------------------------|---------------------------------|---|--------|
| S5.8.41  | Drainage serving an open oil filling point should be connected to storm drains via a petrol interceptor with peak storm bypass.   | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | ^      |
| S5.8.42  | Vehicle and plant servicing areas, vehicle wash bays and lubrication bays should as far as possible be located within roofed areas. The drainage in these covered areas should be connected to foul sewers via a petrol interceptor. Oil leakage or spillage should be contained and cleaned up immediately. Waste oil should be collected and stored for recycling or disposal in accordance with the Waste Disposal Ordinance.  | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | *(7)   |
| S5.8.43  | Construction work force sewage discharges on site are expected to be connected to the existing trunk sewer or sewage treatment facilities. The construction sewage may need to be handled by portable chemical toilets prior to the commission of the on-site sewer system. Appropriate numbers of portable toilets shall be provided by a licensed contractor to serve the large number of construction workers over the construction site. The Contractor shall also be responsible for waste disposal and maintenance practices. | Control potential impacts from construction site runoff and land-based construction | CEDD's Contractors             | Work site                | Construction Phase              | ProPECC PN 1/94, EIAOTM, WPCO                               | ^      |
| S5.8.44  | Contractor must register as a chemical waste producer if chemical wastes would be produced from the construction activities. The Waste Disposal Ordinance (Cap 354) and its subsidiary regulations in particular the Waste Disposal (Chemical Waste)  | Control potential impacts from accidental   | CEDD's Contractors             | Work site                | Construction Phase              | EIAO-TM, WPCO, WDO  | ^      |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref. | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status              |
|----------|--|---|--------------------------------|--------------------------|---------------------------------|---|---------------------|
|          | (General) Regulation should be observed and complied with for control of chemical wastes.  | spillage of chemicals   |                                |                          |                                 |   |                     |
| S5.8.45  | Any service shop and maintenance facilities should be located on hard standings within a bunded area, and sumps and oil interceptors should be provided. Maintenance of vehicles and equipment involving activities with potential for leakage and spillage should only be undertaken within the areas appropriately equipped to control these discharges.   | Control potential impacts from accidental spillage of chemicals   | CEDD's Contractors             | Work site                | Construction Phase              | EIAO-TM, WPCO   | *(8)/#(8)           |
| S5.8.46  | Disposal of chemical wastes should be carried out in compliance with the Waste Disposal Ordinance. The "Code of Practice on the Packaging, Labelling and Storage of Chemical Wastes" published under the Waste Disposal Ordinance details the requirements to deal with chemical wastes. General requirements are given as follows:<br><ul style="list-style-type: none"> <li>- suitable containers should be used to hold the chemical wastes to avoid leakage or spillage during storage, handling and transport;</li> <li>- chemical waste containers should be suitably labelled, to notify and warn the personnel who are handling the wastes, to avoid accidents; and</li> <li>- storage area should be selected at a safe location on site and adequate space should be allocated to the storage area.</li> </ul> | Control potential impacts from accidental spillage of chemicals   | CEDD's Contractors             | Work site                | Construction Phase              | EIAO-TM, WPCO, WDO  | ^<br><br>^<br><br>^ |
| S5.8.47  | Collection and removal of floating refuse should be performed at regular intervals on a daily basis. The contractor should be responsible for keeping the water within the site boundary and the neighbouring water free from rubbish.   | Control potential impacts from floating refuse and debris         | CEDD's Contractors             | Work site                | Construction Phase              | EIAO-TM, WPCO,  | ^                   |

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

June 2018

| EIA Ref.                 | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address  | Who to implement the measures?  | Location of the measures    | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status  |
|--------------------------|--|--|---------------------------------|-----------------------------|---------------------------------|---|---|
| <b>Ecological Impact</b> |  |  |                                 |                             |                                 |   |   |
| S6.8.4                   | <p><b>Measures to Minimize Disturbance</b></p> <ul style="list-style-type: none"> <li>- Use of Quiet Mechanical Plant during the construction phase should be adopted wherever possible.</li> <li>- Hoarding or fencing should be erected around the works area boundaries during the construction phase. The hoarding would screen adjacent habitats from construction phase activities, reduce noise disturbance to these habitats and also to restrict access to habitats adjacent to works areas by site workers;</li> <li>- Regular spraying of haul roads to minimize impacts of dust deposition on adjacent vegetation and habitats during the construction activities</li> </ul>   | <p>Minimize noise, human and traffic disturbance to terrestrial habitat and wildlife; and reduce dust generation</p> | <p>Design Team / Contractor</p> | <p>Land-based works are</p> | <p>Construction Phase</p>       | <p>N/A</p>  | <p>^<br/><br/>^<br/><br/>^</p>                                  |
| S6.8.5                   | <p><b>Standard Good Site Practice</b></p> <ul style="list-style-type: none"> <li>- Placement of equipment or stockpile in designated works areas and access routes selected on existing disturbed land to minimise disturbance to natural habitats.</li> <li>- Construction activities should be restricted to works areas that should be clearly demarcated. The works areas should be reinstated after completion of the works.</li> <li>- Waste skips should be provided to collect general refuse and construction wastes. The wastes should be properly disposed off-site in a timely manner.</li> <li>- General drainage arrangements should include sediment and oil traps to collect and control construction site run-off.</li> <li>- Open burning on works sites is illegal, and should be strictly prohibited.</li> </ul> | <p>Reduce disturbance to surrounding habitats</p>  | <p>Contractor</p>               | <p>Land-based works are</p> | <p>Construction Phase</p>       | <p>N/A</p>  | <p>^<br/><br/>^<br/><br/>^<br/><br/>^<br/><br/>^<br/><br/>^</p> |

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

June 2018

| EIA Ref. | Recommended Mitigation Measures   | Objectives of the recommended Measures & Main Concerns to address | Who to implement the measures?            | Location of the measures                    | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status                       |
|----------|---|---|---|---|---------------------------------|---|------------------------------|
|          | <ul style="list-style-type: none"> <li>- Measures should also be put into place so that litter, fuel and solvents do not enter the nearby watercourses.</li> </ul>  |   |   |   |                                 |   |                              |
| S6.8.6   | <p><b>Measure to Minimize Groundwater Inflow</b></p> <ul style="list-style-type: none"> <li>- The drained tunnel construction method with groundwater inflow control measures would generally be adopted.</li> <li>- During the tunnel excavation, pre-excavation grouting could be adopted to reduce the groundwater inflow and ensure that the tunnel would meet the long term water tightness requirements.</li> </ul>   | Minimize groundwater inflow                                       | Contractor                                | Tunnel                                      | Construction Phase              | N/A   | N/A<br><br>N/A               |
| S6.8.8   | <p><b>Measure to Minimize Impact on Corals</b></p> <p><u>Coral translocation</u></p> <ul style="list-style-type: none"> <li>- It is recommended to translocate the affected coral colonies, except the locally common <i>Oulastrea crispata</i>, within the reclamation area and bridge footprint to the other suitable locations as far as practicable.</li> <li>- The coral translocation should be conducted during the winter months (November-March) in order to avoid disturbance during their spawning period (i.e. July to October).</li> <li>- A detailed coral translocation plan with a description on the methodology for pretranslocation coral survey, translocation methodology, identification/proposal of coral recipient site, monitoring methodology for posttranslocation should be prepared during the detailed design stage.</li> </ul> | Minimize loss of coral  | Design team, contractor, project operator | Within reclamation areas and pier footprint | Prior construction              | N/A   | ^<br><br>^<br><br>^<br><br>^ |

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

June 2018

| EIA Ref.                     | Recommended Mitigation Measures   | Objectives of the recommended Measures & Main Concerns to address  | Who to implement the measures? | Location of the measures               | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status                                |
|------------------------------|---|--|--------------------------------|--|---------------------------------|---|---------------------------------------|
|                              | <ul style="list-style-type: none"> <li>- The coral translocation plan should be subject to approval by relevant authorities (e.g. EPD and AFCD) before commencement of the coral translocation. All the translocation exercises should be conducted by experienced marine ecologist(s) who is/are approved by AFCD prior to commencement of coral translocation.</li> </ul> <p><u>Post translocation Monitoring</u></p> <ul style="list-style-type: none"> <li>- A coral monitoring programme is recommended to assess any adverse and unacceptable impacts to the translocated coral communities</li> <li>- Information gathered during each posttranslocation monitoring survey should include observations on the presence, survival, health condition and growth of the translocated coral colonies. These parameters should then be compared with the baseline results collected from the pre-translocation survey.</li> </ul> |  |                                |  |                                 |   | <p>^</p> <p>^</p>                     |
| <p>S6.8.9</p> <p>S6.8.10</p> | <p><b>Measure to Control Water Quality Impact</b></p> <ul style="list-style-type: none"> <li>- Deployment of silt curtains around the active stone column installation points, opening of newly installed seawall and marine works area.</li> <li>- Diverting of the site runoff to silt trap facilities before discharging into storm drain;</li> <li>- Proper waste and dumping management; and</li> <li>- Standard good-site practice for land-based construction.</li> </ul>  | <p>Control water quality impact, especially on suspended solid level; minimize the contamination of wastewater discharge, accidental chemical spillage</p> | <p>Design Team, contractor</p> | <p>Marine and landbased works area</p> | <p>Construction phase</p>       | <p>WQO</p>  | <p>N/A</p> <p>^</p> <p>^</p> <p>^</p> |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref.                                     | Recommended Mitigation Measures   | Objectives of the recommended Measures & Main Concerns to address | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve?    | Status |
|--|---|---|--------------------------------|--------------------------|---------------------------------|--|--------|
|  |   | and construction site runoff to the receiving water bodies        |                                |                          |                                 |  |        |
| S6.8.11                                      | <p><b>Compensation for Vegetation Loss</b></p> <ul style="list-style-type: none"> <li>- Felling of mature trees should be compensated by planting of standard or heavy standard trees within or in vicinity of the affected area as far as practicable. Such compensatory planting for trees should be provided with at least a 1:1 ratio. In addition, vegetation at the temporarily affected area should be reinstated with species similar to the existing condition.</li> </ul> | Compensate for the vegetation loss                                | Design Team, contractor        | Land-based works area    | Construction phase              | N/A  | ^      |
| <b>Fisheries Impact</b>                      |   |   |                                |                          |                                 |  |        |
| S7.7.3                                       | <p><b>Measure to Control Water Quality Impact</b></p> <ul style="list-style-type: none"> <li>- Deployment of silt curtains around the active stone column installation points, opening of newly installed seawall and marine works area.</li> </ul>   | Control water quality impact, especially on suspended solid level | Design Team / Contractor       | Marine work area         | Construction phase              | WQO  | ^      |
| <b>Waste Management (Construction Phase)</b> |   |   |                                |                          |                                 |  |        |
| S8.6.3                                       | <p><b>Good Site Practices and Waste Reduction Measures</b></p> <ul style="list-style-type: none"> <li>- Nomination of an approved person, such as a site manager, to be responsible for good site practices, arrangements for collection and effective disposal to an appropriate facility, of all wastes generated at the site;</li> </ul>   | To reduce waste management impacts                                | Contractor                     | All work sites           | Construction Phase              | Waste Disposal Ordinance (Cap. 354)<br><br>Land (Miscellaneous | ^      |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref. | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve?                                    | Status                          |
|----------|--|---|--------------------------------|--------------------------|---------------------------------|--|---------------------------------|
|          | <ul style="list-style-type: none"> <li>- Training of site personnel in site cleanliness, proper waste management and chemical handling procedures;</li> <li>- Provision of sufficient waste disposal points and regular collection of waste;</li> <li>- Appropriate measures to minimize windblown litter and dust during transportation of waste by either covering trucks or by transporting wastes in enclosed containers; and</li> <li>- Regular cleaning and maintenance programme for drainage systems, sumps and oil interceptors.</li> </ul>   |   |                                |                          |                                 | Provisions) Ordinance (Cap. 28)  | ^<br><br>^<br><br>^<br><br>*(9) |
| S8.6.4   | <p><b><i>Good Site Practices and Waste Reduction Measures (con't)</i></b></p> <ul style="list-style-type: none"> <li>- Segregation and storage of different types of waste in different containers, skips or stockpiles to enhance reuse or recycling of materials and their proper disposal;</li> <li>- Encourage collection of aluminium cans by providing separate labelled bins to enable this waste to be segregated from other general refuse generated by the workforce;</li> <li>- Proper storage and site practices to minimize the potential for damage or contamination of construction materials; and</li> <li>- Plan and stock construction materials carefully to minimize amount of waste generated and avoid unnecessary generation of waste.</li> </ul> | To achieve waste reduction  | Contractor                     | All work sites           | Construction Phase              | Waste Disposal Ordinance (Cap. 354)<br><br>Land (Miscellaneous Provisions) Ordinance (Cap. 28) | ^<br><br>^<br><br>^<br><br>^    |
| S8.6.5   | <p><b><i>Good Site Practices and Waste Reduction Measures (con't)</i></b></p> <p>The Contractor shall prepare and implement a WMP as part of the EMP in accordance with ETWB TCW No. 19/2005 which describes the arrangements for</p>  | To achieve waste reduction  | Contractor                     | All work sites           | Construction Phase              | ETWB TCW No. 19/2005   | ^                               |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref. | Recommended Mitigation Measures   | Objectives of the recommended Measures & Main Concerns to address              | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status                       |
|----------|---|--|--------------------------------|--------------------------|---------------------------------|---|------------------------------|
|          | <p>avoidance, reuse, recovery, recycling, storage, collection, treatment and disposal of different categories of waste to be generated from the construction activities. Such a management plan should incorporate site specific factors, such as the designation of areas for segregation and temporary storage of reusable and recyclable materials.</p> <p>The EMP should be submitted to the Engineer for approval. The Contractor should implement the waste management practices in the EMP throughout the construction stage of the Project. The EMP should be reviewed regularly and updated by the Contractor.</p>   |  |                                |                          |                                 |   |                              |
| S8.6.6   | <p><b><i>Good Site Practices and Waste Reduction Measures (con't)</i></b></p> <ul style="list-style-type: none"> <li>- C&amp;D materials would be reused in the project and other local concurrent projects as far as possible.</li> </ul>  | To achieve waste reduction   | Contractor                     | All work sites           | Construction Phase              | ETWB TCW No. 19/2005  | ^                            |
| S8.6.7   | <p><b><i>Storage, Collection and Transportation of Waste</i></b></p> <p>Should any temporary storage or stockpiling of waste is required, recommendations to minimize the impacts include:</p> <ul style="list-style-type: none"> <li>- Waste, such as soil, should be handled and stored well to ensure secure containment, thus minimizing the potential of pollution;</li> <li>- Maintain and clean storage areas routinely;</li> <li>- Stockpiling area should be provided with covers and water spraying system to prevent materials from wind-blown or being washed away; and</li> <li>- Different locations should be designated to stockpile each material to enhance reuse.</li> </ul> | To minimize potential adverse environmental impacts arising from waste storage | Contractor                     | All work sites           | Construction Phase              | -   | ^<br><br>^<br><br>^<br><br>^ |
| S8.6.8 / | <p><b><i>Storage, Collection and Transportation of Waste (con't)</i></b></p>  | To minimize  | Contractor                     | All work                 | Construction                    |   |                              |



**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref.                             | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address                              | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve?                 | Status  |
|--------------------------------------|--|--|--------------------------------|--------------------------|---------------------------------|---|---|
| Waste Management Plan                | <ul style="list-style-type: none"> <li>- Remove waste in timely manner;</li> <li>- Waste collectors should only collect wastes prescribed by their permits;</li> <li>- Impacts during transportation, such as dust and odour, should be mitigated by the use of covered trucks or in enclosed containers;</li> <li>- Obtain relevant waste disposal permits from the appropriate authorities, in accordance with the Waste Disposal Ordinance (Cap. 354), Waste Disposal (Charges for Disposal of Construction Waste) Regulation (Cap. 345) and the Land (Miscellaneous Provisions) Ordinance (Cap. 28);</li> <li>- Waste should be disposed of at licensed waste disposal facilities; and</li> <li>- Maintain records of quantities of waste generated, recycled and disposed.</li> </ul> | potential adverse environmental impacts arising from waste collection and disposal             |                                | sites                    | Phase                           |   | <p>^</p> <p>^</p> <p>^</p> <p>^</p> <p>^</p> <p>^</p> |
| S8.6.9 / Waste Management Plan       | <p><b>Storage, Collection and Transportation of Waste (con't)</b></p> <ul style="list-style-type: none"> <li>- Implementation of trip ticket system with reference to DEVB TC(W) No. 6/2010, Trip Ticket System for Disposal of Construction &amp; Demolition Materials, to monitor disposal of waste and to control fly-tipping at PFRFs or landfills. A recording system for the amount of waste generated, recycled and disposed (including disposal sites) should be proposed.</li> </ul>  | To minimize potential adverse environmental impacts arising from waste collection and disposal | Contractor                     | All work sites           | Construction Phase              | DEVB TCW No. 6/2010   | ^   |
| S8.6.11 - S8.6.13 / Waste Management | <p><b>Sorting of C&amp;D Materials</b></p> <ul style="list-style-type: none"> <li>- Sorting to be performed to recover the inert materials, reusable and recyclable materials before disposal off-site.</li> <li>- Specific areas shall be provided by the Contractors for sorting and to provide temporary storage areas for the sorted materials.</li> </ul>   | To minimize potential adverse environmental  | Contractor                     | All work sites           | Construction Phase              | DEVB TCW No. 6/2010<br><br>ETWB TCW No. 33/2002<br><br>ETWB TCW No. 19/2005 | <p>^</p> <p>^</p>                                     |



App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

June 2018

| EIA Ref.                     | Recommended Mitigation Measures   | Objectives of the recommended Measures & Main Concerns to address | Who to implement the measures? | Location of the measures                      | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status |
|------------------------------|---|---|--------------------------------|---|---------------------------------|---|--------|
|                              | <p>3.95m) exceed RBRG for lead. While cement stabilization will immobilize metal contaminants, it is capable to treat the exceedance on lead. The stabilized material should comply with UTS of Lead and UCS. If the treated material do not comply with UTS or UCS, re-stabilization have to be undertaken to meet compliance of UTS and UCS before reusing the treated sediment as filling material. However, further agreement on final disposal/treatment on sediment under sample (TKO-EBH501 3-3.95m) has to be sought from DEP</p>   |   |                                |   |                                 |   |        |
| <p>S8.6.17 –<br/>S8.6.20</p> | <p><b>Sediments (con't)</b></p> <ul style="list-style-type: none"> <li>- Requirements of the Air Pollution Control (Construction Dust) Regulation, where relevant, shall be adhered to during boring, excavation, transportation and disposal of sediments or cement stabilization of sediment.</li> <li>- A treatment area should be confined for carrying out the cement stabilization mixing and temporary stockpile. The area should be designed to prevent leachate from entering the ground. Leachate, if any, should be collected and discharged according to the Water Pollution Control Ordinance (WPCO).</li> <li>- In order to minimise the potential odour / dust emissions during boring, excavation and transportation of the sediment, the excavated sediments should be kept wet during excavation/boring and should be properly covered when placed on barges/trucks. Loading of the excavated sediment to the barge should be controlled to avoid splashing and overflowing of the sediment slurry to the surrounding water.</li> <li>- In order to minimise the exposure to contaminated materials, workers should,</li> </ul> | <p>To determine the best handling and treatment of sediment</p>   | <p>Contractor</p>              | <p>All works areas with sediments concern</p> | <p>Construction Phase</p>       | <p>N/A<br/><br/>N/A<br/><br/>N/A<br/><br/>N/A</p>           |        |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref.                        | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address                | Who to implement the measures? | Location of the measures               | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status |
|---------------------------------|--|--|--------------------------------|--|---------------------------------|---|--------|
|                                 | when necessary, wear appropriate personal protective equipments (PPE) when handling contaminated sediments. Adequate washing and cleaning facilities should also be provided on site.  |  |                                |  |                                 |   |        |
| S8.6.21 / Waste Management Plan | <p><b>Sediments (con't)</b></p> <ul style="list-style-type: none"> <li>- Alternatively, excavated sediment can be treated with marine disposal. The basic requirements and procedures for excavated sediment disposal specified under ETWB TC(W) No. 34/2002 shall be followed. MFC is responsible for the provision and management of disposal capacity and facilities for the excavated sediment, while the permit of marine dumping is required under the Dumping at Sea Ordinance and is the responsibility of the DEP.</li> </ul>   | To ensure the sediment to be disposed of in an authorized and least impacted way | contractor                     | All works areas with sediments concern | Construction Phase              | ETWB TC(W) No. 34/2002 & Dumping at Sea Ordinance           | N/A    |
| S8.6.23                         | <p><b>Sediments (con't)</b></p> <ul style="list-style-type: none"> <li>- For allocation of sediment disposal sites and application of marine dumping permit, separate SSTP has to be submitted to EPD for agreement under DASO. Additional site investigation, based on the SSTP, maybe carried out in order to confirm the disposal arrangements for the proposed sediments removal. A Sediment Quality Report (SQR) shall then be required for EPD agreement under DASO prior to the tendering of the construction contract, discussing in details the site investigation, testing results as well as the delineation of each of the categories of excavated materials and the corresponding types of disposal.</li> </ul> | To determine the best handling and disposal option of sediment                   | Contractor                     | All works areas with sediments concern | Construction Phase              | ETWB TC(W) No. 34/2002 & Dumping at Sea Ordinance           | N/A    |
| S8.6.24 - S8.6.28 / Waste       | <p><b>Sediments (con't)</b></p> <ul style="list-style-type: none"> <li>- The excavated sediments is expected to be loaded onto the barge and transported to the designated disposal sites allocated by the MFC. The</li> </ul>   | To ensure handling of sediments are in   | Contractor                     | All works areas with sediments         | Construction Phase              | ETWB TC(W) No. 34/2002 & Dumping at Sea Ordinance           | N/A    |



**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref.                        | Recommended Mitigation Measures   | Objectives of the recommended Measures & Main Concerns to address | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve?   | Status |
|---------------------------------|---|---|--------------------------------|--------------------------|---------------------------------|---|--------|
|                                 | <p>ensure that loss of material does not take place during transportation. Transport barges or vessels shall be equipped with automatic self-monitoring devices as specified by the DEP.</p> <ul style="list-style-type: none"> <li>- In order to minimise the exposure to contaminated materials, workers should, when necessary, wear appropriate personal protective equipments (PPE) when handling contaminated sediments. Adequate washing and cleaning facilities should also be provided on site.</li> <li>- Another possible arrangement for Type 3 disposal is by geosynthetic containment. A geosynthetic containment method is a method whereby the sediments are sealed in geosynthetic containers and, at the disposal site, the containers would be dropped into the designated contaminated mud pit where they would be covered by further mud disposal and later by the mud pit capping, thereby meeting the requirements for fully confined mud disposal.</li> </ul> |   |                                |                          |                                 |   | N/A    |
| S8.6.26 / Waste Management Plan | <p><b>Chemical Wastes.</b></p> <ul style="list-style-type: none"> <li>- If chemical wastes are produced at the construction site, the Contractor would be required to register with the EPD as a Chemical Waste Producer and to follow the guidelines stated in the Code of Practice on the Packaging, Labelling and Storage of Chemical Wastes. Good quality containers compatible with the chemical wastes should be used, and incompatible chemicals should be stored separately. Appropriate labels should be securely attached on each chemical waste container indicating the corresponding chemical characteristics of the chemical waste, such as explosive, flammable, oxidizing, irritant, toxic, harmful,</li> </ul>   | To ensure proper management of chemical waste                     | Contractor                     | All works sites          | Construction Phase              | Code of Practice on the Packaging, Labelling and Storage of Chemical Wastes<br><br>Waste Disposal (Chemical Waste) (General) Regulation | ^      |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref.  | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status      |
|---|--|---|--------------------------------|--------------------------|---------------------------------|---|-------------|
|   | corrosive, etc. The Contractor shall use a licensed collector to transport and dispose of the chemical wastes, to either the Chemical Waste Treatment Centre at Tsing Yi, or other licensed facility, in accordance with the Waste Disposal (Chemical Waste) (General) Regulation.   |   |                                |                          |                                 |   |             |
| S8.6.27 / Waste Management Plan                         | <p><b>General Refuse</b></p> <ul style="list-style-type: none"> <li>- General refuse should be stored in enclosed bins or compaction units separate from C&amp;D material. A reputable waste collector should be employed by the contractor to remove general refuse from the site, separately from C&amp;D material. Preferably an enclosed and covered area should be provided to reduce the occurrence of 'wind blown' light material.</li> </ul> | To ensure proper management of general refuse                     | Contractor                     | All works sites          | Construction Phase              | Public Health and Municipal Services Ordinance (Cap. 132)   | ^           |
| <b>Impact on Cultural Heritage (Construction Phase)</b> |  |   |                                |                          |                                 |   |             |
| S9.6.4  | <p>Dust and visual impacts</p> <ul style="list-style-type: none"> <li>- Temporarily fenced off buffer zone with allowance for public access (minimum 1 m) should be provided;</li> <li>- The open yard in front of the temple should be kept as usual for annual Tin Hau festival;</li> <li>- Monitoring of vibration impacts should be conducted when the construction works are less than 100m from the temple.</li> </ul>                         | To prevent dust and visual impacts                                | Contractors                    | Work areas               | Construction Phase              | EIAO; GCHIA; AMO  | ^<br>^<br>^ |
| S9.6.4  | <p>Indirect vibration impact</p> <ul style="list-style-type: none"> <li>- Vibration level is suggest to be controlled within a peak particle velocity (ppv) limit of 5mm/s measured inside the historical buildings;</li> <li>- Monitoring of vibration should be carried out during construction phase.</li> </ul>  | To prevent indirect vibration impact                              | Contractors                    | Work areas               | Construction Phase              | Vibration Limits on Heritage Buildings by CEDD; GCHIA; AMO. | ^<br>^      |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref.   | Recommended Mitigation Measures   | Objectives of the recommended Measures & Main Concerns to address | Who to implement the measures? | Location of the measures | When to Implement the measures?                      | What requirements or standards for the measures to achieve? | Status                     |
|--|---|---|--------------------------------|--------------------------|--|---|----------------------------|
|  | <ul style="list-style-type: none"> <li>- Tilting and settlement monitoring should will be applied on the Cha Kwo Ling Tin Hau Temple as well.</li> <li>- A proposal with details for the mitigation measures and monitoring of impacts on built heritage shall be submitted to AMO for comments before commencement of work.</li> </ul>       |   |                                |                          |  |   | <p>^</p> <p>^</p>          |
| Built Heritage Mitigation Plan                                 | <ul style="list-style-type: none"> <li>- Established Alert, Alarm and Action Level for the monitoring parameters.</li> <li>- To increase the instrumentation monitoring and reporting frequency.</li> <li>- To propose detailed action plan or contingency plan for the Engineer's approval when AAA Level is reached or exceeded.</li> </ul> | To prevent vibration impacts                                      | NE/2015/01                     | Tin Hau Temple           | Construction Phase                                   | Vibration Limits on Heritage Buildings by CEDD; GCHIA; AMO. | <p>^</p> <p>^</p> <p>^</p> |
| <b><i>Landscape and Visual Impact (Construction Phase)</i></b> |   |   |                                |                          |  |   |                            |
| Table 10.8.1/ Landscape Mitigation Plan                        | CM1 - Construction area and contractor's temporary works areas to be minimised to avoid impacts on adjacent landscape.  | Avoid impact on adjacent landscape areas                          | CEDD (via Contractor)          | General                  | Construction planning and during construction period | N/A   | ^                          |
| Table 10.8.1/ Landscape Mitigation                             | CM2 - Reduction of construction period to practical minimum.  | Minimise duration of impact                                       | CEDD (via Contractor)          | N/A                      | Construction planning                                | N/A   | ^                          |



**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref.                                | Recommended Mitigation Measures   | Objectives of the recommended Measures & Main Concerns to address | Who to implement the measures? | Location of the measures                    | When to Implement the measures?                   | What requirements or standards for the measures to achieve?                    | Status |
|---|---|---|--------------------------------|---|---|--|--------|
| Plan                                    |   |   |                                |   |   |  |        |
| Table 10.8.1/ Landscape Mitigation Plan | <p>CM3 - Topsoil, where the soil material meets acceptable criteria and where practical, to be stripped and stored for re-use in the construction of the soft landscape works.</p> <p>The Contract Specification shall include storage and reuse of topsoil as appropriate.</p>   | To allow re-use of topsoil  | CEDD (via Contractor)          | General                                     | Site clearance                                    | As per the Particular Specification  | ^      |
| Table 10.8.1/ Landscape Mitigation Plan | <p>CM4 - Existing trees at boundary of site and retained trees within site boundary to be carefully protected during construction. Detailed Tree Protection Specification shall be provided in the Contract Specification, under which the Contractor shall be required to submit, for approval, a detailed working method statement for the protection of trees prior to undertaking any works adjacent to all retained trees, including trees in contractor's works areas. (Tree protection measures will be detailed at Tree Removal Application stage).</p> | To minimize tree loss   | CEDD (via Contractor)          | As per approved Tree Removal Application(s) | Site clearance and throughout construction period | ETWB TC 3/2006 and as per tree protection measures in Particular Specification | ^      |
| Table 10.8.1/ Landscape Mitigation Plan | <p>CM5 - Trees unavoidably affected by the works shall be transplanted where practicable. Where possible, trees should be transplanted direct to permanent locations rather than temporary holding nurseries. A detailed tree transplanting specification shall be provided in the Contract Specification and sufficient time for preparation shall be allowed in the construction programme.</p>   | To maximize preservation of existing trees                        | CEDD (via Contractor)          | As per approved Tree Removal Application(s) | Site clearance                                    | ETWB TC 3/2006 and as per tree protection measures in Particular Specification | ^      |
| Table 10.8.1/                           | <p>CM6 - Advance screen planting of fast growing tree and shrub species to noise barriers and hoardings. Trees shall be capable of reaching a height &gt;10m within 10</p>  | To maximize screening of the                                      | CEDD (via Contractor)          | At Lam Tin Interchange                      | Beginning of construction                         | N/A  | ^      |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref.                                | Recommended Mitigation Measures   | Objectives of the recommended Measures & Main Concerns to address | Who to implement the measures? | Location of the measures                | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status |
|---|---|---|--------------------------------|---|---------------------------------|---|--------|
| Landscape Mitigation Plan               | years.  | works   |                                | and edge of Road P2 landscape deck, TKO | period                          |   |        |
| Table 10.8.1/ Landscape Mitigation Plan | CM7 - Hydroseeding or sheeting of soil stockpiles with visually unobtrusive material                          | To reduce visual intrusion  | CEDD (via Contractor)          | General                                 | Throughout construction period  | As per Particular Specification                             | N/A    |
| Table 10.8.1/ Landscape Mitigation Plan | CM8 - Control of night-time lighting by hooding all lights and through minimisation of night working periods. | To reduce visual intrusion  | CEDD (via Contractor)          | General                                 | Throughout construction period  | N/A   | ^      |
| Table 10.8.1/ Landscape Mitigation Plan | CM9 - Screening of works areas with hoardings with appropriate colours compatible with the surrounding area   | Reduction of visual intrusion                                     | CEDD (via Contractor)          | Project site Boundary                   | Excretion of site hoarding      | N/A   | ^      |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref.                                   | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address | Who to implement the measures? | Location of the measures  | When to Implement the measures?              | What requirements or standards for the measures to achieve? | Status |
|--|--|---|--------------------------------|---|--|---|--------|
| Table 10.8.1/<br>Landscape Mitigation Plan | CM10 - Avoidance of excessive height and bulk of site buildings and structure                                    | Reduction of visual intrusion and integration with environment    | CEDD (via Contractor)          | Built structures  | Design and construction stage                | N/A   | ^      |
| Table 10.8.1/<br>Landscape Mitigation Plan | CM11 - Limitation of run-off into freshwater streams, ponds and sea areas  | Avoidance of contamination of water courses and water bodies      | CEDD (via Contractor)          | TKO reclamation, TKO tunnel portal, Cha Kwo Ling roadworks                                    | Throughout construction period               | N/A   | ^      |
| Table 10.8.1/<br>Landscape Mitigation Plan | CM12 - Minimise area of reclamation and design the edges sensitively to tie in with adjacent coastline character | Minimise loss of Junk Bay and integration with existing coastline | CEDD (via Contractor)          | Temporary reclamation for barging points at TKO and Lam Tin and permanent reclamation for TKO | Construction planning and reclamation stages | N/A   | N/A    |

| EIA Ref.   | Recommended Mitigation Measures   | Objectives of the recommended Measures & Main Concerns to address | Who to implement the measures? | Location of the measures  | When to Implement the measures? | What requirements or standards for the measures to achieve?  | Status              |
|--|---|---|--------------------------------|---|---------------------------------|--|---------------------|
|  |   |   |                                | Interchange slip roads and Road P2                              |                                 |  |                     |
| <b>Landfill Gas Hazard (Design and Construction Phase)</b> |   |   |                                |   |                                 |  |                     |
| S11.5.9  | <p>A Safety Officer, trained in the use of gas detection equipment and landfill gas-related hazards, should be present on site throughout the groundworks phase. The Safety Officer should be provided with an intrinsically safe portable instrument, which is appropriately calibrated and able to measure the following gases in the ranges indicated below:</p> <p>Methane 0-100% LEL and 0100% v/v<br/>                     Carbon dioxide 0-100%<br/>                     Oxygen 0-21%</p>  | Protect the workers from landfill gas hazards                     | Contractor                     | Project sites within the Sai Tso Wan Landfill Consultation Zone | Construction phase              | EPD's Landfill Gas Hazard Assessment Guidance Note   | ^                   |
| S11.5.10<br>S11.5.25                                       | <p><b>Safety Measures</b></p> <ul style="list-style-type: none"> <li>- For staff who work in, or have responsibility for “at risk” area, such as all excavation workers, supervisors and engineers working within the Consultation Zone, should receive appropriate training on working in areas susceptible to landfill gas, fire and explosion hazards.</li> <li>- An excavation procedure or code of practice to minimize landfill gas related risk should be devised and carried out.</li> <li>- No worker should be allowed to work alone at any time in or near to any</li> </ul> | Protect the workers from landfill gas hazards                     | Contractor                     | Project sites within the Sai Tso Wan Landfill Consultation Zone | Construction phase              | EPD's Landfill Gas Hazard Assessment Guidance Note<br>Labour Department's Code of Practice for Safety and Health at Work in Confined Space | ^<br><br>^<br><br>^ |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref. | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status                                       |
|----------|--|---|--------------------------------|--------------------------|---------------------------------|---|--|
|          | <p>excavation. At least one other worker should be available to assist with a rescue if needed.</p> <ul style="list-style-type: none"> <li>- Smoking, naked flames and all other sources of ignition should be prohibited within 15m of any excavation or ground-level confined space. “No smoking” and “No naked flame” notices should be posted prominently on the construction site and, if necessary, special areas should be designed for smoking.</li> <li>- Welding, flame-cutting or other hot works should be confined to open areas at least 15m from any trench or excavation.</li> <li>- Welding, flame-cutting or other hot works may only be carried out in trenches or confined spaces when controlled by a “permit to work” procedure, properly authorized by the Safety Officer (or, in the case of small developments, other appropriately qualified person).</li> <li>- The permit to work procedure should set down clearly the requirements for continuous monitoring for methane, carbon dioxide and oxygen throughout the period during which the hot works are in progress. The procedure should also require the presence of an appropriately qualified person, in attendance outside the 'confined area', who should be responsible for reviewing the gas measurements as they are made, and who should have executive responsibility for suspending the work in the event of unacceptable or hazardous conditions. Only those workers who are appropriately trained and fully aware of the potentially hazardous conditions which may arise should be permitted to carry</li> </ul> |   |                                |                          |                                 |   | <p>^</p> <p>^</p> <p>^</p> <p>^</p> <p>^</p> |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref. | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status  |
|----------|--|---|--------------------------------|--------------------------|---------------------------------|---|---|
|          | <p>out hot works in confined areas.</p> <ul style="list-style-type: none"> <li>- Where there are any temporary site offices, or any other buildings located within the Sai Tso Wan Landfill Consultation Zone which have enclosed spaces with the capacity to accumulate landfill gas, then they should either be located in an area which has been proven to be free of landfill gas (by survey using portable gas detectors); or be raised clear of the ground by a minimum of 500mm. This aims to create a clear void under the structure which is ventilated by natural air movement such that emission of gas from the ground are mixed and diluted by air.</li> <li>- Any electrical equipment, such as motors and extension cords, should be intrinsically safe. During piping assembly or conduiting construction, all valves/seals should be closed immediately after installation. As construction progresses, all valves/seals should be closed to prevent the migration of gases through the pipeline/conduit. All piping /conduiting should be capped at the end of each working day.</li> <li>- During construction, adequate fire extinguishing equipment, fire-resistant clothing and breathing apparatus (BA) sets should be made available on site.</li> <li>- Fire drills should be organized at not less than six monthly intervals.</li> <li>- The contractor should formulate a health and safety policy, standards and instructions for site personnel to follow.</li> <li>- All personnel who work on the site and all visitors to the site should be made aware of the possibility of ignition of gas in the vicinity of excavations. Safety</li> </ul> |   |                                |                          |                                 |   | <p style="text-align: center;">^</p> <p style="text-align: center;">^</p> <p style="text-align: center;">^</p> <p style="text-align: center;">^</p> <p style="text-align: center;">^</p> <p style="text-align: center;">^</p> |

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

June 2018

| EIA Ref.                                 | Recommended Mitigation Measures   | Objectives of the recommended Measures & Main Concerns to address | Who to implement the measures? | Location of the measures  | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status |
|--|---|---|--------------------------------|---|---------------------------------|---|--------|
|  | <p>notices (in Chinese and English) should be posted at prominent position around the site warning danger of the potential hazards.</p> <ul style="list-style-type: none"> <li>- Service runs within the Consultation Zone should be designated as “special routes”; utilities companies should be informed of this and precautionary measures should be implemented. Precautionary measures should include ensuring that staff members are aware of the potential hazards of working in confined spaces such as manholes and service chambers, and that appropriate monitoring procedures are in place to prevent hazards due to asphyxiating atmospheres in confined spaces. Detailed guidance on entry into confined spaces is given in Code of Practice on Safety and Health at Work in Confined Spaces (Labour Department, Hong Kong).</li> <li>- Periodically during ground-works construction within the 250m Consultation Zone, the works area should be monitored for methane, carbon dioxide and oxygen using appropriately calibrated portable gas detection equipment. The monitoring frequency and areas to be monitored should be set down prior to commencement of ground-works either by the Safety Officer or an approved and appropriately qualified person.</li> </ul> |   |                                |   |                                 |   | ^      |
| <p>S11.5.26</p> <p>-</p> <p>S11.5.31</p> | <p><b>Monitoring</b></p> <ul style="list-style-type: none"> <li>● Routine monitoring should be carried out in all excavations, manholes, chambers, relocation of monitoring wells and any other confined spaces that may have been created. All measurements in excavations should be made with the extended monitoring tube located not more than 10 mm from the</li> </ul>  | <p>Protect the workers from landfill gas hazards</p>              | <p>Contractor</p>              | <p>Project sites within the Sai Tso Wan Landfill Consultation</p> | <p>Construction phase</p>       | <p>EPD’s Landfill Gas Hazard Assessment Guidance Note</p>   | ^      |

App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES

June 2018

| EIA Ref. | Recommended Mitigation Measures   | Objectives of the recommended Measures & Main Concerns to address | Who to implement the measures? | Location of the measures | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status                                       |
|----------|---|---|--------------------------------|--------------------------|---------------------------------|---|--|
|          | <p>exposed ground surface. Monitoring should be performed properly to make sure that the area is free of landfill gas before any man enters into the area.</p> <ul style="list-style-type: none"> <li>● For excavations <b>deeper than 1m</b>, measurements should be carried out:                             <ul style="list-style-type: none"> <li>- at the ground surface before excavation commences;-</li> <li>- immediately before any worker enters the excavation;</li> <li>- at the beginning of each working day for the entire period the excavation remains open; and</li> <li>- periodically throughout the working day whilst workers are in the excavation.</li> </ul> </li> <li>● For excavations <b>between 300mm and 1m deep</b>, measurements should be carried out:                             <ul style="list-style-type: none"> <li>- directly after the excavation has been completed; and</li> <li>- periodically whilst the excavation remains open.</li> </ul> </li> <li>● For excavations less than 300mm deep, monitoring may be omitted, at the discretion of the Safety Officer or other appropriately qualified person.</li> <li>● Depending on the results of the measurements, actions required will vary and should be set down by the Safety Officer or other appropriately qualified person.</li> <li>● The exact frequency of monitoring should be determined prior to the commencement of works, but should be at least once per day, and be carried out by a suitably qualified or qualified person before starting the work of the day. Measurements shall be recorded and kept as a record of safe working conditions with copies of the site diary and submitted to the Engineer for</li> </ul> |   |                                | Zone                     |                                 |   | <p>^</p> <p>^</p> <p>^</p> <p>^</p> <p>^</p> |



**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| EIA Ref. | Recommended Mitigation Measures  | Objectives of the recommended Measures & Main Concerns to address                          | Who to implement the measures? | Location of the measures  | When to Implement the measures? | What requirements or standards for the measures to achieve? | Status |
|----------|--|--|--------------------------------|---|---------------------------------|---|--------|
|          | approval. The Contractor may elect to carry out monitoring via an automated monitoring system.   |  |                                |   |                                 |   |        |
| S11.5.32 | The hazards from landfill gas during the construction stage within the Sai Tso Wan Landfill Consultation Zone should be minimized by suitable precautionary measures recommended in Chapter 8 of the Landfill Gas Hazard Assessment Guidance Note. | construction stage within the Sai Tso Wan<br>Protect the workers from landfill gas hazards | Contractor                     | Project sites within the Sai Tso Wan Landfill Consultation Zone | Construction phase              | EPD's Landfill Gas Hazard Assessment Guidance Note          | N/A    |

**Table II - Observations/reminders/non-compliance made during Site Audit**

- Key:**
- \* Observation/reminder was made during site audit but improved/rectified by the contractor.
  - # Observation/reminder was made during site audit but not yet improved/rectified by the contractor.
  - X Non-compliance of mitigation measure
  - Non-compliance but rectified by the contractor

| Status / Remark           | EIA Ref. | Recommended Mitigation Measures  | Contract No. | Work Sites                                      | Details of Observation/Reminder  |
|---------------------------|----------|--|--------------|---|--|
| <b>Air Quality Impact</b> |          |  |              |   |  |
| * (1)                     | S3.8.1   | Watering eight times a day on active works areas, exposed areas and paved haul roads   | NE/2015/01   | Construction of Lam Tin Interchange/ TKO Portal | Water spraying should be provided to exposed slope at LTI and TKO for dust suppression.  |
|                           | S3.8.7   | Dust suppression measures stipulated in the Air Pollution Control (Construction Dust) Regulation and good site practices: <ul style="list-style-type: none"> <li>- Use of regular watering to reduce dust emissions from exposed site surfaces and unpaved roads, particularly during dry weather.</li> <li>- Use of frequent watering for particularly dusty construction areas and areas close to ASRs.</li> <li>- Provision of wind shield and dust extraction units or similar dust mitigation measures at the loading area of barging point, and use of water sprinklers at the loading area where dust generation is likely during the loading process of loose material, particularly in dry seasons/ periods.</li> <li>- Open stockpiles shall be avoided or covered. Where possible, prevent placing dusty material storage piles near ASRs.</li> </ul> | NE/2015/01   | Construction of Lam Tin Interchange/ TKO Portal | Used cement bags should be removed at Portion IVC (Lam Tin).   |
|                           |          |  | NE/2015/02   | Construction of Road P2                         | To wrap the drilling rig with impervious sheeting and retractable tube before start of pre-boring works in Portion 4.  |
|                           |          |  | NE/2017/02   | Construction of Road P2/D4                      | Stockpile and dry surface were observed in Portion 1. The Contractor should improve the dust mitigation measures in Portion 1.   |
| # (1)                     |          |  | NE/2015/02   | Construction of Road P2                         | The stockpile in Work Area A was observed uncovered and its level was much higher than the stone wall. The Contractor should improve the mitigation measures for dust and water quality impact in Work Area A. |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| Status / Remark                                  | EIA Ref.              | Recommended Mitigation Measures  | Contract No. | Work Sites                          | Details of Observation/Reminder  |
|--|-----------------------|--|--------------|-------------------------------------|--|
| <b>Noise Impact (Construction Phase)</b>         |                       |  |              |                                     |  |
| * (2)  | Noise Mitigation Plan | Use of Temporary Noise Barriers or Full Enclosure for PME according to the approved Noise Mitigation Plan  | NE/2015/02   | Construction of Road P2             | To properly erect the acoustic mats without gaps for the derrick barge (Superich 206).   |
| # (3)  | S4.8                  | - Use of quiet PME. Use of movable noise barriers for Excavator, Lorry, Dump Truck, Mobile Crane, Compactor, Concrete Mixer Truck, Concrete Lorry Mixer, Breaker, Mobile Crusher, Backhoe, Vibratory Poker, Saw, Asphalt Paver, Vibratory Roller, Vibrolance, Hydraulic Vibratory Lance and Piling (Vibration Hammer). Use of full enclosure for Air Compressor, Compressor, Bar Bender, Generator, Drilling Rig, Chisel, Large Diameter Bore Piling, Grout Mixer & Pump and Concrete Pump.  | NE/2015/02   | Construction of Road P2             | Excessive impact noise was produced from the vibration hammer and pile in Portion 6. The Contractor should enhance noise mitigation measures for the piling works in Portion 6 to reduce noise nuisance to nearby NSR. |
| <b>Water Quality Impact (Construction Phase)</b> |                       |  |              |                                     |  |
| # (4)  | S5.8.3                | Other good site practices should be undertaken during filling operations include:<br>- floating single silt curtain shall be employed for all marine works;  | NE/2015/01   | Construction of TKO Portal          | The Contractor was reminded to provide silt curtain in accordance with the silt curtain deployment plan at TKO side before the commencement of the construction work.  |
| * (5)  | S5.8.7                | Construction site runoff and drainage should be prevented or minimised in accordance with the guidelines stipulated in the EPD's Practice Note for Professional Persons, Construction Site Drainage (ProPECC PN 1/94). Good housekeeping and stormwater best management practices, as detailed in below, should be implemented to ensure that all construction runoff complies with WPCO standards and no unacceptable impact on the WSRs arises due to construction of the TKO-LT Tunnel. All discharges from the construction site should be controlled to comply with the standards for effluents discharged into the corresponding WCZ under the TM-DSS. | NE/2015/02   | Construction of Road P2             | To regularly maintain the wetsep in Work Area A and drainage system properly to prevent overflowing during rain events.  |
|  |                       |  | NE/2015/03   | Construction of Northern Footbridge | Sand bunds along West Pier were observed damaged. The Contractor should ensure the integrity of sand bunds at all time.  |
|  |                       |  | NE/2017/01   | Construction of TKO Interchange     | Stagnant water was observed in Portion I. The Contractor should remove the stagnant water frequently.  |

**App N - IMPLEMENTATION SCHEDULE AND RECOMMENDED MITIGATION MEASURES**

**June 2018**

| Status / Remark | EIA Ref. | Recommended Mitigation Measures  | Contract No. | Work Sites                          | Details of Observation/Reminder  |
|-----------------|----------|--|--------------|-------------------------------------|--|
| #(5)            |          |  | NE/2015/02   | Construction of Road P2             | The stockpile in Work Area A was observed uncovered and its level was much higher than the stone wall. The Contractor should improve the mitigation measures for dust and water quality impact in Work Area A. |
| * (6)           | S5.8.11  | Sedimentation tanks of sufficient capacity, constructed from pre-formed individual cells of approximately 6 to 8m <sup>3</sup> capacity, are recommended as a general mitigation measure which can be used for settling surface runoff prior to disposal. The system capacity is flexible and able to handle multiple inputs from a variety of sources and particularly suited to applications where the influent is pumped.     | NE/2015/02   | Construction of Road P2             | To regularly maintain the wetsep in Work Area A and drainage system properly to prevent overflowing during rain events.  |
|                 |          |  | NE/2015/03   | Construction of Northern Footbridge | To regularly remove the sediment in the sedimentation tank in West Pier.   |
| * (7)           | S5.8.42  | Vehicle and plant servicing areas, vehicle wash bays and lubrication bays should as far as possible be located within roofed areas. The drainage in these covered areas should be connected to foul sewers via a petrol interceptor. Oil leakage or spillage should be contained and cleaned up immediately. Waste oil should be collected and stored for recycling or disposal in accordance with the Waste Disposal Ordinance. | NE/2015/01   | Construction of TKO Portal          | Construction material should be removed from drip tray at TKO marine platform.   |
|                 |          |  | NE/2015/03   | Construction of Northern Footbridge | Oil stain was observed on the surface of the stagnant water in West Pier. The Contractor should remove the oil stain on the stagnant water   |
| * (8)           | S5.8.45  | Any service shop and maintenance facilities should be located on hard standings within a bunded area, and sumps and oil interceptors should be provided. Maintenance of vehicles and equipment involving activities with potential for leakage and spillage should only be undertaken within the areas appropriately equipped to control these discharges.   | NE/2015/01   | Construction of TKO Portal          | Construction material should be removed from drip tray at TKO marine platform.   |
|                 |          |  | NE/2015/03   | Construction of Northern Footbridge | To provide drip tray to the chemical container in Portion 2 near East Pier.  |
|                 |          |  | NE/2017/01   | Construction of TKO Interchange     | The Contractor was reminded to remove the stagnant water inside the drip tray at flat top barge.   |
| # (8)           |          |  | NE/2017/01   | Construction of TKO Interchange     | Oil leakage should be avoided from the oil container and cleaned up on the derrick barge.  |

---

---

**APPENDIX O  
SUMMARIES OF ENVIRONMENTAL  
COMPLAINT, WARNING, SUMMON  
AND NOTIFICATION OF SUCCESSFUL  
PROSECUTION**

---

---

**Appendix O - Cumulative Log for Complaints, Notifications of Summons and Successful Prosecutions****Cumulative Complaint Log for Tseung Kwan O - Lam Tin Tunnel**

| Complaint No. | Received Date              | Date/Location of Complaint  | Complainant                | Nature           | Details of Complaint   | Noise Action Level Exceedance (Y/N) | Investigation/ Mitigation Action                               | File Closed |
|---------------|----------------------------|---|----------------------------|------------------|--|-------------------------------------|--|-------------|
| 192           | 27 <sup>th</sup> June 2018 | 26 <sup>th</sup> and 27 <sup>th</sup> June 2018/<br>Construction of Lam Tin Interchange | Resident of Yau Lai Estate | Noise            | The complainant complained the construction noise at Lam Tin Interchange during night-time.  | Y                                   | Under Investigation  | On-going    |
| 191           | 25 <sup>th</sup> June 2018 | 23 <sup>rd</sup> June 2018/<br>Construction of Road P2                                  | Public                     | Air Quality      | The complainant complained the dark smoke emission from construction barge and the smell from welding works.   | N                                   | Under Investigation  | On-going    |
| 190           | 22 <sup>nd</sup> June 2018 | Not Specific/<br>Construction of Lam Tin Interchange                                    | Public                     | Waste Management | The complainant complaint about the housekeeping of the construction site.   | N                                   | Under Investigation  | On-going    |
| 189           | 20 <sup>th</sup> June 2018 | 28 <sup>th</sup> May 2018/<br>Construction of Road P2                                   | SKDC member                | Air Quality      | The complainant complained the dark smoke emission from the same construction vessel.  | N                                   | See Investigation / Mitigation Measures for Complaint No. 181. | Closed      |
| 188           | 20 <sup>th</sup> June 2018 | 20 <sup>th</sup> June 2018/<br>Construction of Lam Tin Interchange                      | Resident of Yau Lai Estate | Noise            | The complainant complained about construction noise starting from 6 am.  | Y                                   | Under Investigation  | On-going    |
| 187           | 7 <sup>th</sup> June 2018  | 7 <sup>th</sup> June 2018/<br>Construction of Road P2                                   | Resident of Ocean Shores   | Air Quality      | The complainant complained about the smell of machinery exhaust affecting the podium of Ocean Shores (swimming pool). The complainant suspected the exhaust was originated from the nearby barges. | N                                   | Under Investigation  | On-going    |

| Complaint No. | Received Date             | Date/Location of Complaint  | Complainant                                 | Nature      | Details of Complaint   | Noise Action Level Exceedance (Y/N) | Investigation/ Mitigation Action  | File Closed |
|---------------|---------------------------|---|---|-------------|--|-------------------------------------|---|-------------|
| 186           | 6 <sup>th</sup> June 2018 | 6 <sup>th</sup> June 2018/ Construction of Lam Tin Interchange                    | Resident of Chung Pak House, Hong Pak Court | Noise       | The complainant complained about the construction noise at Lam Tin Interchange.                          | Y                                   | Under Investigation   | On-going    |
| 185           | 6 <sup>th</sup> June 2018 | 30 <sup>th</sup> May and 30 <sup>th</sup> September 2017/ Construction of Road P2 | SKDC member                                 | Noise       | The complainant complained about the noise affecting nearby resident in early morning near Ocean Shores. | Y                                   | See Investigation / Mitigation Measures for Complaint No. 50 and 81.  | On-going    |
| 184           | 6 <sup>th</sup> June 2018 | / Construction of Road P2   | SKDC member                                 | Landscape   | The complainant complained about excessive tree felling near Ocean Shores.                               | N                                   | Under Investigation   | On-going    |
| 183           | 4 <sup>th</sup> June 2018 | 4 <sup>th</sup> June 2018/ Construction of Lam Tin Interchange                    | Resident of Hong Pak Court                  | N/A         | The complainant complained about the blasting works during night-time.                                   | N                                   | Under Investigation   | On-going    |
| 182           | 1 <sup>st</sup> June 2018 | Not specified/ Construction of Lam Tin Interchange                                | Sin Fat Road Tennis Court                   | Air Quality | The complainant complained about the dust  | N                                   | Under Investigation   | On-going    |
| 181           | 29 <sup>th</sup> May 2018 | Not specified/ Construction of Road P2  | Public                                      | Air Quality | The complainant complained about the black smoke emission from the construction vessel.                  | N                                   | <p>According to the information provided and confirmed by the Engineer, dredging and placing rock fill material were conducted during the time of complaint.</p> <p>The Contractors had implemented environmental mitigation measures to reduce construction nuisance from construction activities to the nearby sensitive receivers as follows:</p> <p><u>Air Quality:</u></p> <ul style="list-style-type: none"> <li>➤ As confirmed by the Engineer, the concerned barge was removed off site for further maintenance;</li> <li>➤ Additional water filter tank was adopted to reduce emission of dark smoke and exhaust.</li> </ul> <p>The Engineer and the Environmental Team have reminded the Contractor to properly implement mitigation measures to effectively minimize construction nuisance caused by the construction works to the nearby residents.</p> | Closed      |

| Complaint No. | Received Date             | Date/Location of Complaint   | Complainant                      | Nature      | Details of Complaint  | Noise Action Level Exceedance (Y/N) | Investigation/ Mitigation Action  | File Closed |
|---------------|---------------------------|--|----------------------------------|-------------|---|-------------------------------------|---|-------------|
| 180           | 25 <sup>th</sup> May 2018 | 24 <sup>th</sup> May 2018/<br>Construction of Road P2                            | SKDC member Mr. Cheung Chin Pang | Odour       | The complainant complained about smell of exhaust gas affecting high level residents (60/F and above) of Metrotown Tower 10.  | N                                   | <p>According to the information provided and confirmed by the Engineer, modification of temporary marine platform and welding works were conducted during the time of complaint.</p> <p>The Contractors had implemented environmental mitigation measures to reduce construction nuisance from construction activities to the nearby sensitive receivers as follows:<br/><u>Air Quality:</u></p> <ul style="list-style-type: none"> <li>➤ Additional water filter tank was adopted to reduce emission of dark smoke and exhaust.</li> </ul> <p>The Engineer and the Environmental Team have reminded the Contractor to properly implement mitigation measures to effectively minimize construction nuisance caused by the construction works to the nearby residents.</p>   | Closed      |
| 179           | 24 <sup>th</sup> May 2018 | 24 <sup>th</sup> May 2018/<br>Construction of Northern footbridge and Road P2/D4 | Public                           | Air Quality | The complainant complained construction dust generated from the CEDD construction works site between Tong Yin Street and Tiu Keng Leng Sport Centre (Po Yap Road) as a result of insufficient dust suppression measures | N                                   | <p>According to the information provided and confirmed by the Engineer, construction works including steel bar fixing, scaffolding, trimming formation level, compaction, and removal of road marking were conducted during the time of complaint.</p> <p>As shown in the Air Quality Monitoring Results, no Action/Limit Level Exceedance was recorded at Station AM5(A) and AM6(A) in May 2018. It is considered that no adverse construction dust impact was brought to the nearby sensitive receivers during the construction period of this Project</p> <p>The Contractors had implemented environmental mitigation measures to reduce construction nuisance from construction activities to the nearby sensitive receivers as follows:</p> <ul style="list-style-type: none"> <li>➤ Water spraying was provided at least 8 times a day;</li> <li>➤ Surface near public access was hard paved.</li> </ul> <p>The Engineer and the Environmental Team have reminded the Contractor to properly implement mitigation measures to</p> | On-going    |



| Complaint No. | Received Date             | Date/Location of Complaint                               | Complainant | Nature | Details of Complaint  | Noise Action Level Exceedance (Y/N) | Investigation/ Mitigation Action  | File Closed |
|---------------|---------------------------|--|-------------|--------|---|-------------------------------------|---|-------------|
|               |                           |  |             |        |   |                                     | effectively minimize construction nuisance caused by the construction works to the nearby residents.  |             |
| 178           | 23 <sup>rd</sup> May 2018 | 22 <sup>nd</sup> May 2018/<br>Construction of TKO Portal | Public      | N/A    | The complainant complained construction works was carried out on 22 May (which was a public holiday) around 1500 hour at the sea area near Ocean shore Block 2. | N                                   | <p>According to the information provided and confirmed by the Engineer, modification of temporary marine platform and welding works were conducted during the time of complaint.</p> <p>One valid Construction Noise Permit (CNP) (No. GE-RE0309-18) was granted to the Contractor (Leighton – China State Joint Venture) (Contract No. NE/2015/01) for the marine construction site near Ocean Shores. According to the CNP, Group O to T of the PME listed in condition 3.a. are allowed to operate during general holiday (including Sunday) from 0900 – 2300 hours.</p> <p>As confirmed by the Engineer, only a group of PME (listed in Group Q) was operated during the time of complaint. No welding machine was operated in Zone A. No derrick barge and flat top barge were operated beyond Zone C.</p> <p>The Contractors had implemented environmental mitigation measures to reduce construction nuisance from construction activities to the nearby sensitive receivers as follows:</p> <p><u>Noise:</u></p> <ul style="list-style-type: none"> <li>➤ Preinstalled speaker was used on derrick barge to minimize the noise disturbance from on-site communication.</li> </ul> <p>The Engineer and the Environmental Team have reminded the Contractor to properly implement mitigation measures to effectively minimize construction nuisance caused by the construction works to the nearby residents.</p> | Closed      |

| Complaint No. | Received Date             | Date/Location of Complaint                         | Complainant                | Nature              | Details of Complaint   | Noise Action Level Exceedance (Y/N) | Investigation/ Mitigation Action   | File Closed |
|---------------|---------------------------|--|----------------------------|---------------------|--|-------------------------------------|--|-------------|
| 177           | 22 <sup>nd</sup> May 2018 | Not specified/ Construction of Lam Tin Interchange | Resident of Yau Lai Estate | Air Quality & Noise | The complainant complained about the dust nuisance and construction noise at Lam Tin Interchange | Y                                   | <p>According to the Engineer's Site Diaries, the major construction activities performed in May 2018 included rock breaking, drilling and excavation at Lam Tin Interchange. Construction works for night-time included blasting and excavation.</p> <p>According to the EM&amp;A Manual of this Project, regular air quality monitoring has been carried out at Station AM2 – Sai Tso Wan Recreation Ground and AM3 – Yau Lai Estate, Bik Lai House. Based on the Air Quality Monitoring Results which conducted by ET, no Action or Limit Level Exceedance was recorded at Station AM2 and AM3. It is considered that no adverse air quality impact was brought to the nearby sensitive receivers during the time of complaint.</p> <p>The Contractor had implemented environmental mitigation measures in accordance with the "Implementation Schedule of Proposed Mitigation Measures" of EM&amp;A Manual as follows:</p> <p><u>Air Quality:</u></p> <ul style="list-style-type: none"> <li>➤ Frequent water spraying on unpaved area and haul roads at Lam Tin Interchange</li> </ul> <p><u>Noise:</u></p> <ul style="list-style-type: none"> <li>➤ Ensured blasting doors were closed while blasting associated works was undertaken in the tunnel;</li> <li>➤ Installed steel-type blasting door mounted with sound absorptive lining to absorb construction noise in the tunnel;</li> <li>➤ Erected movable cantilever noise barriers and the breaker head was wrapped with Silent Mat and TMD;</li> <li>➤ Powered mechanical equipment (PME) for rock breaking were equipped with TMD and SilentMat;</li> <li>➤ Drill rig was covered with Silent Mat and TMR</li> </ul> <p>The environmental conditions of the site and the control of works</p> | On-going    |

| Complaint No. | Received Date             | Date/Location of Complaint                            | Complainant                | Nature      | Details of Complaint   | Noise Action Level Exceedance (Y/N) | Investigation/ Mitigation Action   | File Closed |
|---------------|---------------------------|---|----------------------------|-------------|--|-------------------------------------|--|-------------|
|               |                           |   |                            |             |  |                                     | will be continuously reviewed and monitored by the Engineer and the Environmental Team.  |             |
| 176           | 21 <sup>st</sup> May 2018 | 21 <sup>st</sup> May 2018/<br>Construction of Road P2 | Public                     | Air Quality | The complainant complained about dust/dirt being brought onto Tong Yin Street by the vehicles travelling to and from TKO-LTT construction site, causing dust problem and air nuisance. | N                                   | <p>According to the information confirmed by the Engineer, all dump trucks were covered and wheel washed before leaving the works site on 21 May 2018.</p> <p>As shown in the Air Quality Monitoring Results, no Action/Limit Level Exceedance was recorded at Station AM5(A) and AM6(A) in May 2018. It is considered that no adverse construction dust impact was brought to the nearby sensitive receivers during the construction period of this Project</p> <p>The Contractors had implemented environmental mitigation measures to minimize the noise nuisance to the nearby noise sensitive receivers as follows:</p> <ul style="list-style-type: none"> <li>➤ Water spraying was provided at least 8 times a day.</li> <li>➤ Street washing truck would be provided once a week to clean the dust on the public street.</li> <li>➤ Additional notice would be set up to remind the truck driver to perform wheel-washing properly before leaving site.</li> <li>➤ Deployed staff at the access to check the dump trucks to ensure the dump truck are properly covered and wheel-washed before leaving site.</li> </ul> <p>The Engineer and the Environmental Team have reminded the Contractor to properly implement mitigation measures to effectively minimize construction nuisance caused by the construction works to the nearby residents.</p> | On-going    |
| 175           | 19 <sup>th</sup> May 2018 | Not specified/<br>Construction of Lam Tin             | Resident of Hong Nga Court | Noise       | The complainant complained the noise nuisance due to the   | Y                                   | See Investigation / Mitigation Measures for Complaint No. 160.   | On-going    |

| Complaint No. | Received Date             | Date/Location of Complaint                               | Complainant   | Nature | Details of Complaint   | Noise Action Level Exceedance (Y/N) | Investigation/ Mitigation Action                               | File Closed |
|---------------|---------------------------|--|---|--------|--|-------------------------------------|--|-------------|
|               |                           | Interchange  |   |        | construction work at Lam Tin Interchange during nighttime.   |                                     |  |             |
| 174           | 19 <sup>th</sup> May 2018 | Not specified/ Construction of Lam Tin Interchange       | Resident of Hong Pak Court                          | Noise  | The complainant complained the noise nuisance due to the construction work at Lam Tin Interchange during nighttime.                  | Y                                   | See Investigation / Mitigation Measures for Complaint No. 160. | On-going    |
| 173           | 16 <sup>th</sup> May 2018 | Not specified/ Construction of Lam Tin Interchange       | Resident of Hong Nga Court,                         | Noise  | The complainant complained the noise nuisance due to the construction work at Lam Tin Interchange during night-time.                 | Y                                   | See Investigation / Mitigation Measures for Complaint No. 160. | On-going    |
| 172           | 15 <sup>th</sup> May 2018 | Not specified/ Construction of Lam Tin Interchange       | Resident of Hong Pak Court                          | Noise  | The complainant complained the noise nuisance during night time blasting works at the Lam Tin Interchange.                           | Y                                   | See Investigation / Mitigation Measures for Complaint No. 160. | On-going    |
| 171           | 15 <sup>th</sup> May 2018 | Not specified/ Construction of Lam Tin Interchange       | Resident of Yau Lai Estate, Bik Lai Estate          | Noise  | The complainant complained the noise nuisance during night time blasting works at the Lam Tin Interchange.                           | Y                                   | See Investigation / Mitigation Measures for Complaint No. 160. | On-going    |
| 170           | 15 <sup>th</sup> May 2018 | Not specified/ Construction site near Cha Kwo Ling Tsuen | Anonymous   | Noise  | The complainant complained the noise nuisance due to the construction work near Cha Kwo Ling Tsuen during night-time.                | Y                                   | See Investigation / Mitigation Measures for Complaint No. 160. | On-going    |
| 169           | 14 <sup>th</sup> May 2018 | Not specified/ Construction of Lam Tin Interchange       | Kowloon East District Council Member Mr. Tam Man Ho | Noise  | The complainant complained the noise nuisance due to the construction work and night time blasting works at the Lam Tin Interchange. | Y                                   | See Investigation / Mitigation Measures for Complaint No. 160. | On-going    |

| Complaint No. | Received Date             | Date/Location of Complaint                                     | Complainant                                  | Nature | Details of Complaint   | Noise Action Level Exceedance (Y/N) | Investigation/ Mitigation Action                               | File Closed |
|---------------|---------------------------|--|--|--------|--|-------------------------------------|--|-------------|
| 168           | 14 <sup>th</sup> May 2018 | Not specified/ Construction of Lam Tin Interchange             | Resident of Yau Lai Estate, Yung Lai House   | Noise  | The complainant complained the noise nuisance due to the construction work at Lam Tin Interchange during night-time.                                   | Y                                   | See Investigation / Mitigation Measures for Complaint No. 160. | On-going    |
| 167           | 13 <sup>th</sup> May 2018 | Not specified/ Construction of Lam Tin Interchange             | Resident of Hong Nga Court, Chung Pak House  | Noise  | The complainant complained the noise nuisance due to the construction work on Sunday morning and night time blasting works at the Lam Tin Interchange. | Y                                   | See Investigation / Mitigation Measures for Complaint No. 160. | On-going    |
| 166           | 13 <sup>th</sup> May 2018 | Not specified/ Construction of Lam Tin Interchange             | Resident of Hong Pak Court                   | Noise  | The complainant complained the noise nuisance due to the construction work at around 5:00 am and night time blasting works at the Lam Tin Interchange. | Y                                   | See Investigation / Mitigation Measures for Complaint No. 160. | On-going    |
| 165           | 13 <sup>th</sup> May 2018 | 13 <sup>th</sup> May 2018/ Construction of Lam Tin Interchange | Property Management Office of Hong Nga Court | Noise  | The complainant complained the noise nuisance due to the construction work at Lam Tin Interchange on 13 <sup>th</sup> May 2018 (Sunday morning).       | Y                                   | See Investigation / Mitigation Measures for Complaint No. 160. | On-going    |
| 164           | 12 <sup>th</sup> May 2018 | 12 <sup>th</sup> May 2018/ Construction of Lam Tin Interchange | Resident of Hong Nga Court                   | Noise  | The complainant complained the noise nuisance during night time blasting works at the Lam Tin Interchange.   | Y                                   | See Investigation / Mitigation Measures for Complaint No. 160. | On-going    |
| 163           | 12 <sup>th</sup> May 2018 | Not specified/ Construction of Lam Tin Interchange             | Resident of Yau Lai Estate                   | Noise  | The complainant complained the noise nuisance due to the construction work at  | Y                                   | See Investigation / Mitigation Measures for Complaint No. 160. | On-going    |

| Complaint No. | Received Date             | Date/Location of Complaint                         | Complainant                | Nature      | Details of Complaint   | Noise Action Level Exceedance (Y/N) | Investigation/ Mitigation Action  | File Closed |
|---------------|---------------------------|--|----------------------------|-------------|--|-------------------------------------|---|-------------|
|               |                           |  |                            |             | Lam Tin Interchange.   |                                     |   |             |
| 162           | 11 <sup>th</sup> May 2018 | Not specified/ Construction of Lam Tin Interchange | Resident of Lung Pak House | Noise       | The complainant complained the noise nuisance during night time blasting works at the Lam Tin Interchange.                                   | Y                                   | See Investigation / Mitigation Measures for Complaint No. 160.  | On-going    |
| 161           | 9 <sup>th</sup> May 2018  | 9 <sup>th</sup> May 2018 / Construction of Road P2 | Resident of Ocean Shore    | Air Quality | The complainant complained about dark smoke emission from a barge working at the sea area under TKO-LTT project near Block 2 of Ocean Shore. | N                                   | <p>According to the information provided and confirmed by the Engineer, loading and unloading of marine sediment was conducted during the time of complaint</p> <p>The Contractors had implemented environmental mitigation measures to reduce construction nuisance from construction activities to the nearby sensitive receivers as follows:</p> <ul style="list-style-type: none"> <li>➤ Additional water filter tank was adopted to reduce emission of dark smoke and exhaust smell.</li> </ul> <p>The Engineer and the Environmental Team have reminded the Contractor to properly implement mitigation measures to effectively minimize construction nuisance caused by the construction works to the nearby residents.</p>  | Closed      |
| 160           | 4 <sup>th</sup> May 2018  | Not specified/ Construction of Lam Tin Interchange | Public                     | Noise       | The complainant complained the noise nuisance during night time blasting works at the Lam Tin Interchange.                                   | Y                                   | <p>According to the Engineer's Site Diaries, the major construction activities performed in May 2018 included rock breaking, drilling and excavation at Lam Tin Interchange. Construction works for night-time included blasting and excavation.</p> <p>A valid Construction Noise Permit (CNP) (No. GW-RE0084-18) was granted to the Contractor for the construction site at Lam Tin Interchange. According to the conditions in the CNP, only one group among Group A to H of the powered mechanical equipment is allowed to be operated during 0800-2300 hours on general holidays (including Sundays); and 1900-2300 hours on any day not being a general holiday. The number of excavators, dump trucks, craned lorry and breaker that were used during the day of complaint was covered by the CNP.</p> | On-going    |

| Complaint No. | Received Date | Date/Location of Complaint | Complainant | Nature | Details of Complaint | Noise Action Level Exceedance (Y/N) | Investigation/ Mitigation Action   | File Closed |
|---------------|---------------|----------------------------|-------------|--------|----------------------|-------------------------------------|--|-------------|
|               |               |                            |             |        |                      |                                     | <p>In addition, Group I to N of the powered mechanical equipment is allowed to be operated during 2300-0700 hours on any day. The operation of charging unit during the time of complaint was covered by the CNP. Therefore, no violation of CNP (No. GW-RE0048-18) conditions was observed during the time of complaint.</p> <p>The Contractor had implemented environmental mitigation measures in accordance with the “Implementation Schedule of Proposed Mitigation Measures” of EM&amp;A Manual as follows:</p> <p><u>Air Quality:</u></p> <ul style="list-style-type: none"> <li>➤ Frequent water spraying on unpaved area and haul roads at Lam Tin;</li> </ul> <p><u>Noise:</u></p> <ul style="list-style-type: none"> <li>➤ Ensured blasting doors were closed while blasting associated works was undertaken in the tunnel;</li> <li>➤ Installed steel-type blasting door mounted with sound absorptive lining to absorb construction noise in the tunnel;</li> <li>➤ Erected movable cantilever noise barriers and the breaker head was wrapped with Silent Mat and TMD;</li> <li>➤ Powered mechanical equipment (PME) for rock breaking were equipped with TMD and SilentMat;</li> <li>➤ Drill rig was covered with Silent Mat and TMR.</li> </ul> <p>As shown by the Noise Monitoring Results conducted by ET, no Limit Level Exceedance was recorded at Station CM1, CM2, CM3 and CM4. The summary of noise monitoring results which conducted by ETL in May 2018 at Station CM1, CM2, CM3 and CM4.</p> <p>With the implementation of environmental mitigation measures by Contractors on site, it is considered that air quality and noise nuisance by the works has been brought to a minimum level and no adverse impact was brought to the nearby sensitive receivers</p> |             |

| Complaint No. | Received Date               | Date/Location of Complaint   | Complainant | Nature        | Details of Complaint   | Noise Action Level Exceedance (Y/N) | Investigation/ Mitigation Action   | File Closed |
|---------------|-----------------------------|--|-------------|---------------|--|-------------------------------------|--|-------------|
|               |                             |  |             |               |  |                                     | during the construction of Lam Tin Interchange under this Project.<br><br>The environmental conditions of the site and the control of works will be continuously reviewed and monitored by the Engineer and the Environmental Team.  |             |
| 159           | 3 <sup>rd</sup> May 2018    | 2 <sup>nd</sup> and 3 <sup>rd</sup> May 2018 / Construction of Road P2 | Public      | Odour         | The complainant complained the odour nuisance from the construction vessel.                        | N                                   | According to the information provided and confirmed by the Engineer, major construction activity including dredging, loading and unloading of marine sediment was conducted during the time of complaint   | Closed      |
|               | 30 <sup>th</sup> April 2018 | Not specified / Construction of Road P2                                | Public      | Noise & Odour | The complainant complained the construction noise and odour nuisance from the construction vessel. | Y                                   | The use of dredger and derrick barge conformed to the proposed quantity and type of PME stated in the updated Construction Noise Assessment of CNMP.<br><br>Based on the noise monitoring results in April and May 2018, no Limit Level Exceedance was recorded at Station CM6(A) and CM7(A). It is considered that no adverse construction noise impact was brought to the nearby sensitive receivers during the construction.<br><br>The Contractors had implemented environmental mitigation measures to reduce construction nuisance from construction activities to the nearby sensitive receivers as follows:<br><u>Noise:</u> <ul style="list-style-type: none"> <li>➤ Noise source on the barge was covered with acoustic materials.</li> <li>➤ Additional sound absorptive blankets were used to reduce the nuisance from the engine of the barge.</li> <li>➤ Nylon rope was used instead of wire rope to reduce friction secure the barge in place.</li> <li>➤ Maintenance of barge including lubrication of moving parts was performed to minimized noise from worn or</li> </ul> |             |



| Complaint No. | Received Date               | Date/Location of Complaint                               | Complainant                                    | Nature | Details of Complaint   | Noise Action Level Exceedance (Y/N) | Investigation/ Mitigation Action   | File Closed |
|---------------|-----------------------------|--|--|--------|--|-------------------------------------|--|-------------|
|               |                             |  |  |        |  |                                     | <p>loose parts.</p> <p><u>Air Quality:</u></p> <ul style="list-style-type: none"> <li>➤ Additional water filter tank was adopted to reduce emission of dark smoke and exhaust smell.</li> </ul> <p>The Engineer and the Environmental Team have reminded the Contractor to properly implement mitigation measures to effectively minimize construction nuisance caused by the construction works to the nearby residents.</p>  |             |
| 158           | 30 <sup>th</sup> April 2018 | Not specified/ Construction of Lam Tin Interchange       | Property Management Office of Kwong Tin Estate | Noise  | The complainant complained the noise nuisance due to the breaking work at Lam Tin Interchange.   | Y                                   | See Investigation / Mitigation Measures for Complaint No. 145.   | On-going    |
| 157           | 26 <sup>th</sup> April 2018 | 26 <sup>th</sup> April 2018 / Construction of TKO portal | Resident of Laguna City                        | Light  | The complainant complained that two spotlights were used during daytime and nighttime causing light nuisance to the residents. She requested to direct the strong lighting toward the sea. | N                                   | <p>According to the information provided and confirmed by the Engineer, no major construction activity was conducted at the location of complaint on 26 April 2018.</p> <p>Upon the receipt of the complaint, as confirmed by the Engineer, the Contractor had taken initiatives to maintain the environmental conditions in the works area as shown below:</p> <ul style="list-style-type: none"> <li>➤ The spotlights at the Cha Kwo Ling Public Cargo Working Administrative Office were switched off during daytime; and</li> <li>➤ The illumination angle of spotlights was turned facing downwards to avoid light overspill</li> </ul> <p>The Engineer and the Environmental Team have reminded the Contractor to properly implement mitigation measures to effectively minimize construction nuisance caused by the construction works to the nearby residents.</p> | Closed      |

| Complaint No. | Received Date               | Date/Location of Complaint                            | Complainant                                | Nature | Details of Complaint   | Noise Action Level Exceedance (Y/N) | Investigation/ Mitigation Action  | File Closed |
|---------------|-----------------------------|---|--|--------|--|-------------------------------------|---|-------------|
| 156           | 25 <sup>th</sup> April 2018 | Not specified/ Construction of Lam Tin Interchange    | Resident of Yau Lai Estate, Yau Lai Estate | Noise  | The complainant complained the noise nuisance due to the breaking work at Lam Tin Interchange.   | Y                                   | See Investigation / Mitigation Measures for Complaint No. 145.  | On-going    |
| 155           | 23 <sup>th</sup> April 2018 | 23 <sup>th</sup> April 2018 / Construction of Road P2 | Public                                     | Noise  | The complainant complained about noise from construction activities at the sea area near Ocean Shore Block 6 starting 8:30-8:45am on 23 April 2018. She suspected the noise is from drilling/breaking works. | Y                                   | <p>According to the information provided and confirmed by the Engineer, construction works including excavation and pre-boring works in Portion IV were conducted on 23 April 2018. One unit of excavator and two units of mini backhoe were in operation for excavation works while two units of drill rigs were in operation for the pre-boring works in Portion IV.</p> <p>As confirmed by the Engineer, no breaking works were carried out during the time of complaint in Portion IV. Therefore, pre-boring works at Portion IV is regarded the source of noise nuisance.</p> <p>The Contractor had implemented environmental mitigation measures to minimize the noise nuisance to the nearby noise sensitive receivers as follows:</p> <ul style="list-style-type: none"> <li>➤ Acoustics barriers were provided to the drill rigs for pre-boring works (see photo 1).</li> <li>➤ Maintenance was provided to the rotary head of the drill rig to minimize noise nuisance from worn or loose parts.</li> <li>➤ Regular site checking would be performed to ensure the type and quantity of powered mechanical equipment are in order with the updated Construction Noise Assessment.</li> <li>➤ Acoustic box was utilized for breaking works to minimize noise nuisance</li> </ul> <p>The Engineer and the Environmental Team have reminded the Contractor to properly implement mitigation measures to effectively minimize construction nuisance caused by the construction works to the nearby residents.</p> | Closed      |

| Complaint No. | Received Date               | Date/Location of Complaint                         | Complainant  | Nature | Details of Complaint  | Noise Action Level Exceedance (Y/N) | Investigation/ Mitigation Action  | File Closed |
|---------------|-----------------------------|--|--|--------|---|-------------------------------------|---|-------------|
|               |                             |  |  |        |   |                                     | The use of excavator did not conform the proposed quantity of powered mechanical equipment stated in the CNMP. Therefore, it is regarded as a non-compliance.   |             |
| 154           | 23 <sup>th</sup> April 2018 | Not specified/ Construction of Lam Tin Interchange | Kwun Tong District Council Member Mr. Lai Shu Ho     | Noise  | The complainant complained the noise nuisance during night time blasting works at the Lam Tin Interchange.  | Y                                   | See Investigation / Mitigation Measures for Complaint No. 145.  | On-going    |
| 153           | 23 <sup>th</sup> April 2018 | Not specified/ Construction of Lam Tin Interchange | Resident of Yau Lai Estate                           | Noise  | The complainant complained the noisy breaking work from two breakers at Lam Tin Interchange. He requested the Contractor to review the noise mitigation measures on site. | Y                                   | See Investigation / Mitigation Measures for Complaint No. 145.  | On-going    |
| 152           | 20 <sup>th</sup> April 2018 | Not specified/ Construction of Lam Tin Interchange | Resident of Nga Lai Estate, Yau Lai Estate           | Noise  | The complainant complained the noise nuisance during night time blasting works at the Lam Tin Interchange.  | Y                                   | See Investigation / Mitigation Measures for Complaint No. 145.  | On-going    |
| 151           | 17 <sup>th</sup> April 2018 | Not specified/ Construction of Lam Tin Interchange | Property Management Office of Yau Lai Estate         | Noise  | The complainant complained the noise nuisance due to the construction work at Lam Tin Interchange.  | Y                                   | See Investigation / Mitigation Measures for Complaint No. 145.  |             |
| 150           | 17 <sup>th</sup> April 2018 | Not specified/ Construction of Lam Tin Interchange | Sham Shui Po District Council Member Mr. Ho Kai Ming | Noise  | The complainant complained the noise nuisance during night time blasting works at the Lam Tin Interchange.  | Y                                   | See Investigation / Mitigation Measures for Complaint No. 145.  |             |
| 149           | 16 <sup>th</sup> April 2018 | Not specified / Construction of Road P2            | Resident of Ocean Shore                              | Noise  | The complaint is about the noise generated from a poorly maintained excavator.  | Y                                   | According to the information provided and confirmed by the Engineer, two units of excavators were in operation for excavation works in Portion VI on 16 and 18 April 2018. Excessive sound from movement of the poorly maintained excavator is considered source of noise nuisance. |             |

| Complaint No. | Received Date               | Date/Location of Complaint                                       | Complainant                | Nature | Details of Complaint   | Noise Action Level Exceedance (Y/N) | Investigation/ Mitigation Action  | File Closed |
|---------------|-----------------------------|--|----------------------------|--------|--|-------------------------------------|---|-------------|
|               | 18 <sup>th</sup> April 2018 | Not specified / Construction of Road P2                          | Resident of Ocean Shore    | Noise  | The complaint is about the noise generated from a poorly maintained excavator.   | Y                                   | <p>The Contractor had implemented environmental mitigation measures to minimize the noise nuisance to the nearby noise sensitive receivers as follows:</p> <ul style="list-style-type: none"> <li>➤ As confirmed by the Engineer, the use of concerned excavator was stopped and it was replaced with a new excavator.</li> <li>➤ Regular site checking would be performed to ensure the type and quantity of PME are in order with the updated Construction Noise Assessment</li> </ul> <p>The Engineer and the Environmental Team have reminded the Contractor to properly implement mitigation measures to effectively minimize construction nuisance caused by the construction works to the nearby residents.</p> <p>The use of excavator did not conform the proposed quantity of powered mechanical equipment stated in the CNMP. Therefore, it is regarded as a non-compliance.</p> |             |
| 148           | 15 <sup>th</sup> April 2018 | Not specified/ Construction of Lam Tin Interchange               | Resident of Yau Lai Estate | Noise  | The complainant complained the noisy construction work at Lam Tin Interchange.   | Y                                   | According to the Engineer's Site Diary, the major construction activities performed in the reporting period included rock breaking and excavation at Lam Tin Interchange.   |             |
| 147           | 15 <sup>th</sup> April 2018 | Not specified/ Construction of Lam Tin Interchange               | Resident of Yau Lai Estate | Noise  | The complainant complained the noisy construction work at Lam Tin Interchange on public holiday.   | Y                                   | According to the latest CNMP of this Contract, the subgroups of work activities undertaken near noise sensitive receivers in the reporting period are as follows:   |             |
| 145           | 2 <sup>nd</sup> April 2018  | Public holiday/ Construction Works near Eastern Harbour Crossing | Resident of Yau Lai Estate | Noise  | The complainant complained the noise nuisance due to the construction work near Eastern Harbour Crossing tunnel portal on public holiday. (started | Y                                   | <p>- Construction of Lam Tin Interchange (LTI);</p> <p>The construction activities of Lam Tin Interchange (Work site No.101) on 17<sup>th</sup>, 23<sup>rd</sup> &amp; 25<sup>th</sup> of April possessed of 7 no. of breakers, which were consistent with the quantities of breakers in</p>  |             |

| Complaint No. | Received Date | Date/Location of Complaint | Complainant | Nature | Details of Complaint | Noise Action Level Exceedance (Y/N) | Investigation/ Mitigation Action  | File Closed |
|---------------|---------------|----------------------------|-------------|--------|----------------------|-------------------------------------|---|-------------|
|               |               | tunnel portal              |             |        | from 9:00 am)        |                                     | <p>the Construction Noise Mitigation Plan (Group 1.1.8)</p> <p>A valid Construction Noise Permit (CNP) (No. GW-RE0084-18) was granted to the Contractor for the construction site at Lam Tin Interchange. According to the conditions in the CNP, only one group among Group A to N of the powered mechanical equipment is allowed to be operated during 08:00 - 23:00 hours on general holiday (including Sunday). The operations on 2<sup>nd</sup> &amp; 15<sup>th</sup> of April involved 1 no. of excavator, 2 no. of dump trucks, which were covered by the CNP. Therefore, no violation of CNP (No. GW-RE0084-18) condition was identified during the time of complaints.</p> <p>The Contractor had implemented environmental mitigation measures in accordance with the “Implementation Schedule of Proposed Mitigation Measures” of EM&amp;A Manual as follows:</p> <ul style="list-style-type: none"> <li>➤ Powered mechanical equipment (PME) for rock breaking were equipped with TMD and SilentMat at Slope H in Lam Tin Interchange;</li> <li>➤ PMEs at Portion IVC were mounted and shielded with SilentMat;</li> <li>➤ Noise barriers were placed next to the breaker at Slope H in Lam Tin Interchange to reduce the noise nuisance to nearby NSRs;</li> <li>➤ Cantilevered noise barriers were erected next to breakers wrapped with TMD and SilentMat at Portion IVC;</li> <li>➤ Ensured blasting doors were closed while mucking out in the tunnel was undertaken; and</li> <li>➤ Installed steel-type blasting door mounted with sound absorptive lining to absorb noise due to construction works in the tunnel</li> </ul> <p>The Engineer and the Environmental Team have reminded the Contractor to properly implement mitigation measures to effectively minimize construction nuisance caused by the construction works to the nearby residents.</p> |             |

**Cumulative Complaint Log since commencement of Project**

| <b>Reporting Month</b> | <b>Number of Complaints in Reporting Month</b> | <b>Number of Summons in Reporting Month</b> | <b>Number of Prosecutions in Reporting Month</b> |
|------------------------|--|---|--|
| November 2016          | 0  | 0   | 0  |
| December 2016          | 11   | 0   | 0  |
| January 2017           | 15   | 0   | 0  |
| February 2017          | 4  | 0   | 0  |
| March 2017             | 6  | 0   | 0  |
| April 2017             | 1  | 0   | 0  |
| May 2017               | 10   | 0   | 0  |
| June 2017              | 8  | 0   | 0  |
| July 2017              | 3  | 0   | 0  |
| August 2017            | 8  | 0   | 0  |
| September 2017         | 14   | 0   | 0  |
| October 2017           | 8  | 0   | 0  |
| November 2017          | 12   | 0   | 0  |
| December 2017          | 10   | 1   | 0  |
| January 2018           | 11   | 0   | 0  |
| February 2018          | 6  | 0   | 0  |
| March 2018             | 17   | 0   | 0  |
| April 2018             | 15   | 0   | 0  |
| May 2018               | 22   | 0   | 0  |
| June 2018              | 11   | 0   | 0  |
| <b>Total</b>           | <b>192</b>                                     | <b>1</b>                                    | <b>0</b>   |

**Cumulative Log for Notifications of Summons**

| <b>Contract No.</b> | <b>Log Ref.</b>       | <b>Date/Location</b>                                     | <b>Subject</b>   | <b>Status</b>                   | <b>Total no. Received in this reporting month</b> | <b>Total no. Received since project commencement</b> |
|---------------------|-----------------------|--|--|---------------------------------|---|--|
| NE/2015/01          | --                    | --   | --   | --                              | --  | --   |
| NE/2015/02          | KTS2<br>4138/<br>2017 | 25 June 2017/<br>Marine construction<br>site at Junk Bay | Contrary to: Sections 6 (1) (b) and 6 (5),<br>Noise Control Ordinance, Cap.400 | First hearing on<br>29 Mar 2018 | 0   | 1  |
| NE/2015/03          | --                    | --   | --   | --                              | --  | --   |
| NE/2017/01          | --                    | --   | --   | --                              | --  | --   |
| NE/2017/02          | --                    | --   | --   | --                              | --  | --   |

**Cumulative Log for Successful Prosecutions**

| <b>Contract No.</b> | <b>Log Ref.</b>       | <b>Date/Location</b>                                     | <b>Subject</b>   | <b>Status</b>  | <b>Total no. Received in this reporting month</b> | <b>Total no. Received since project commencement</b> |
|---------------------|-----------------------|--|--|--|---|--|
| NE/2015/01          | --                    | --   | --   | --   | --  | --   |
| NE/2015/02          | KTS2<br>4138/<br>2017 | 25 June 2017/<br>Marine construction<br>site at Junk Bay | Contrary to: Sections 6 (1) (b) and 6 (5),<br>Noise Control Ordinance, Cap.400 | Successful<br>prosecution to the<br>subcontractor on 27<br>June 2018 | 1   | 1  |
| NE/2015/03          | --                    | --   | --   | --   | --  | --   |
| NE/2017/01          | --                    | --   | --   | --   | --  | --   |
| NE/2017/02          | --                    | --   | --   | --   | --  | --   |

**Cumulative Complaint Log since commencement of Project**

| <b>Reporting Month</b> | <b>Number of Complaints in Reporting Month</b> | <b>Number of Summons in Reporting Month</b> | <b>Number of Prosecutions in Reporting Month</b> |
|------------------------|--|---|--|
| November 2016          | 0  | 0   | 0  |
| December 2016          | 11   | 0   | 0  |
| January 2017           | 15   | 0   | 0  |
| February 2017          | 4  | 0   | 0  |
| March 2017             | 6  | 0   | 0  |
| April 2017             | 1  | 0   | 0  |
| May 2017               | 10   | 0   | 0  |
| June 2017              | 8  | 0   | 0  |
| July 2017              | 3  | 0   | 0  |
| August 2017            | 8  | 0   | 0  |
| September 2017         | 14   | 0   | 0  |
| October 2017           | 8  | 0   | 0  |
| November 2017          | 12   | 0   | 0  |
| December 2017          | 10   | 1   | 0  |
| January 2018           | 11   | 0   | 0  |
| February 2018          | 6  | 0   | 0  |
| March 2018             | 17   | 0   | 0  |
| April 2018             | 15   | 0   | 0  |
| May 2018               | 22   | 0   | 0  |
| June 2018              | 11   | 0   | 0  |
| <b>Total</b>           | <b>192</b>                                     | <b>1</b>                                    | <b>0</b>   |



**Cumulative Log for Notifications of Summons**

| <b>Contract No.</b> | <b>Log Ref.</b>       | <b>Date/Location</b>                                     | <b>Subject</b>   | <b>Status</b>                   | <b>Total no. Received in this reporting month</b> | <b>Total no. Received since project commencement</b> |
|---------------------|-----------------------|--|--|---------------------------------|---|--|
| NE/2015/01          | --                    | --   | --   | --                              | --  | --   |
| NE/2015/02          | KTS2<br>4138/<br>2017 | 25 June 2017/<br>Marine construction<br>site at Junk Bay | Contrary to: Sections 6 (1) (b) and 6 (5),<br>Noise Control Ordinance, Cap.400 | First hearing on<br>29 Mar 2018 | 0   | 1  |
| NE/2015/03          | --                    | --   | --   | --                              | --  | --   |
| NE/2017/01          | --                    | --   | --   | --                              | --  | --   |
| NE/2017/02          | --                    | --   | --   | --                              | --  | --   |

**Cumulative Log for Successful Prosecutions**

| <b>Contract No.</b> | <b>Log Ref.</b>       | <b>Date/Location</b>                                     | <b>Subject</b>   | <b>Status</b>  | <b>Total no. Received in this reporting month</b> | <b>Total no. Received since project commencement</b> |
|---------------------|-----------------------|--|--|--|---|--|
| NE/2015/01          | --                    | --   | --   | --   | --  | --   |
| NE/2015/02          | KTS2<br>4138/<br>2017 | 25 June 2017/<br>Marine construction<br>site at Junk Bay | Contrary to: Sections 6 (1) (b) and 6 (5),<br>Noise Control Ordinance, Cap.400 | Successful<br>prosecution to the<br>subcontractor on 27<br>June 2018 | 1   | 1  |
| NE/2015/03          | --                    | --   | --   | --   | --  | --   |
| NE/2017/01          | --                    | --   | --   | --   | --  | --   |
| NE/2017/02          | --                    | --   | --   | --   | --  | --   |

---

---

**APPENDIX P  
WASTE GENERATION IN THE  
REPORTING MONTH**

---

---



**Monthly Summary Waste Flow Table for 2018**

| Month     | Actual Quantities of Inert C&D Materials Generated Monthly |  |                           |                             |   |                          | Actual Quantities of C&D Wastes Generated Monthly |  |   |                   |                                |
|-----------|--|--|---------------------------|-----------------------------|---|--------------------------|---|--|---|-------------------|--------------------------------|
|           | a.Total Quantity Generated<br>(see Note 8)                 | b. Hard Rock and Large Broken Concrete | c. Reused in the Contract | d. Reused in Other Projects | e. Disposed as Public Fill<br>(see Note 10) | f. Imported Fill         | g. Metals<br>(see Note 5)                         | h. Paper / Cardboard Packaging<br>(see Note 5) | i. Plastics<br>(see Note 3)<br>(see Note 5) | j. Chemical Waste | k. Others, e.g. general refuse |
|           | (in '000m <sup>3</sup> )                                   | (in '000m <sup>3</sup> )               | (in '000m <sup>3</sup> )  | (in '000m <sup>3</sup> )    | (in '000m <sup>3</sup> )                    | (in '000m <sup>3</sup> ) | (in '000kg)                                       | (in '000kg)                                    | (in '000kg)                                 | (in '000kg)       | (in '000m <sup>3</sup> )       |
| January   | 118.887  | 44.216                                 | 25.727                    | 60.437                      | 32.723                                      | 0.000                    | 0.000   | 0.308  | 0.000                                       | 1.200             | 0.094                          |
| February  | 76.419   | 34.880                                 | 8.626                     | 54.212                      | 13.581                                      | 0.000                    | 0.000   | 0.000  | 0.000                                       | 0.800             | 0.046                          |
| March     | 140.974  | 31.352                                 | 57.578                    | 49.166                      | 34.230                                      | 0.000                    | 0.000   | 0.020  | 0.000                                       | 0.000             | 0.052                          |
| April     | 123.925  | 30.310                                 | 57.340                    | 42.266                      | 24.319                                      | 0.000                    | 0.000   | 0.368  | 0.000                                       | 1.200             | 0.058                          |
| May       | 113.094  | 32.375                                 | 0.000                     | 70.782                      | 42.312                                      | 0.000                    | 0.000   | 0.294  | 0.000                                       | 1.000             | 0.034                          |
| June      | 134.902  | 48.193                                 | 0.000                     | 117.435                     | 17.467                                      | 0.000                    | 0.000   | 0.000  | 0.000                                       | 1.322             | 0.096                          |
| Sub-total | 708.201  | 221.326                                | 149.271                   | 394.298                     | 164.632                                     | 0.000                    | 0.000   | 0.990  | 0.000                                       | 5.522             | 0.380                          |
| July      |  |  |                           |                             |   |                          |   |  |   |                   |                                |
| August    |  |  |                           |                             |   |                          |   |  |   |                   |                                |
| September |  |  |                           |                             |   |                          |   |  |   |                   |                                |
| October   |  |  |                           |                             |   |                          |   |  |   |                   |                                |
| November  |  |  |                           |                             |   |                          |   |  |   |                   |                                |
| December  |  |  |                           |                             |   |                          |   |  |   |                   |                                |
| Total     | 708.201  | 221.326                                | 149.271                   | 394.298                     | 164.632                                     | 0.000                    | 0.000   | 0.990  | 0.000                                       | 5.522             | 0.380                          |

Total inert C&D waste generated = c+d+e

Total inert C&D waste recycled = c+d

% of recycled inert C&D waste = Total C&D waste recycled / Total C&D waste generated

Name of Department: Civil Engineering Development Department

Contract No.: NE/2015/01



- Notes: (1) The performance target are given in PS Clause 6(14)
- (2) The waste flow table shall also include C&D materials that are specified in the Contract to be imported for use at the Site
- (3) Plastics refer to plastic bottles/containers, plastic sheets/foam from packaging material
- (4) The Contractor shall also submit the latest forecast of the amount of C&D materials expected to be generated from the Works, together with a break down of the nature where the total amount of C&D materials expected to be generated from the Works is equal to or exceeding 50,000m<sup>3</sup>. (PS Clause 1.105(4) refers)
- (5) All recyclable materials, including metals, paper / cardboard packaging, plastics, etc. will be collected by registered collector for recycling.
- (6) Conversion factors for reporting purpose:  
in-situ: rock = 2.5 tonnes/m<sup>3</sup>; soil = 2.0 tonnes/m<sup>3</sup>
- (7) excavated: rock = 2.0 tonnes/m<sup>3</sup>; soil = 1.8 tonnes/m<sup>3</sup>; broken concrete and bitumen = 2.4 tonnes/m<sup>3</sup>, soil and rock = 1.9 tonnes/m<sup>3</sup>
- (8) C&D Waste = 0.9 tonnes/m<sup>3</sup>; bentonite slurry = 2.8 tonnes/m<sup>3</sup>  
Diesel density: 0.8kg/l  
Numbers are rounded off to the nearest three decimal places  
The "Total Quantity Generated" equals to the sum of "Reuse in the Contract", "Reuse in Other Projects" and "Disposed as Public Fill"

**Monthly Summary Waste Flow Table for 2018 Year**

NE/2015/02

| Month            | Actual Quantities of Inert C&D Materials Generated Monthly |                                     |                          |                          |                          |                          | Actual Quantities of C&D Wastes Generated Monthly |                             |                       |                |                            |
|------------------|--|-------------------------------------|--------------------------|--------------------------|--------------------------|--------------------------|---|-----------------------------|-----------------------|----------------|----------------------------|
|                  | Total Quantity Generated                                   | Hard Rock and Large Borken Concrete | Reused in the Contract   | Reused in other Projects | Disposal as Public Fill  | Imported Fill            | Metals  | Paper / Cardboard Packaging | Plastics (See note 3) | Chemical Waste | Other, e.g. general refuse |
|                  | [in '000m <sup>3</sup> ]                                   | [in '000m <sup>3</sup> ]            | [in '000m <sup>3</sup> ] | [in '000m <sup>3</sup> ] | [in '000m <sup>3</sup> ] | [in '000m <sup>3</sup> ] | [in '000kg]                                       | [in '000kg]                 | [in '000kg]           | [in '000kg]    | [in '000m <sup>3</sup> ]   |
| Jan              | 0.30510  | 0.00000                             | 0.11060                  | 0.00000                  | 0.00850                  | 0.18600                  | 0.00000   | 0.00000                     | 0.00000               | 0.00000        | 0.07544                    |
| Feb              | 1.12247  | 0.00000                             | 0.01080                  | 0.00000                  | 1.08367                  | 0.02800                  | 32.04000  | 0.00000                     | 0.00000               | 0.00000        | 0.05240                    |
| Mar              | 6.50826  | 0.00000                             | 0.04500                  | 0.00000                  | 6.46326                  | 0.00000                  | 23.74000  | 0.00000                     | 0.00000               | 0.00000        | 0.04520                    |
| Apr              | 3.82690  | 0.00000                             | 0.00000                  | 0.00000                  | 3.82690                  | 0.00000                  | 26.37000  | 0.00000                     | 0.00000               | 0.00000        | 0.03010                    |
| May              | 11.03519   | 0.00000                             | 8.30510                  | 0.00000                  | 2.64644                  | 0.08365                  | 24.18000  | 0.00000                     | 0.00000               | 0.00000        | 0.06998                    |
| June             | 1.62394  | 0.00000                             | 0.00000                  | 0.00000                  | 1.58194                  | 0.04200                  | 11.32000  | 0.00000                     | 0.00000               | 0.00000        | 0.06814                    |
| <b>SUB-TOTAL</b> | <b>24.42186</b>  | <b>0.00000</b>                      | <b>8.47150</b>           | <b>0.00000</b>           | <b>15.61071</b>          | <b>0.33965</b>           | <b>117.65000</b>                                  | <b>0.00000</b>              | <b>0.00000</b>        | <b>0.00000</b> | <b>0.34126</b>             |
| Jul              |  |                                     |                          |                          |                          |                          |   |                             |                       |                |                            |
| Aug              |  |                                     |                          |                          |                          |                          |   |                             |                       |                |                            |
| Sep              |  |                                     |                          |                          |                          |                          |   |                             |                       |                |                            |
| Oct              |  |                                     |                          |                          |                          |                          |   |                             |                       |                |                            |
| Nov              |  |                                     |                          |                          |                          |                          |   |                             |                       |                |                            |
| Dec              |  |                                     |                          |                          |                          |                          |   |                             |                       |                |                            |
| <b>TOTAL</b>     | <b>24.42186</b>  | <b>0.00000</b>                      | <b>8.47150</b>           | <b>0.00000</b>           | <b>15.61071</b>          | <b>0.33965</b>           | <b>117.65000</b>                                  | <b>0.00000</b>              | <b>0.00000</b>        | <b>0.00000</b> | <b>0.34126</b>             |

Note: Conversion to 1000m<sup>3</sup> for general refuse is weight in 1000kg multiply by 0.002  
 Conversion to 1000m<sup>3</sup> for Inert C&D is weight in 1000kg multiply by 0.0005  
 Plastics refer to plastic bottles / containers, plastic sheets / foam from packaging material  
 Plastics refer to plastic bottles / containers, plastic sheets / foam from packaging material

Name of Department :  CEDD

Contract No. :  NE/2015/03

**Monthly Summary Waste Flow Table for 2018** (year)

| Month                 | Actual Quantities of Inert C&D Materials Generated Monthly |                                   |                           |                           |                           |                           | Actual Quantities of C&D Wastes Generated Monthly |                            |                       |                 |                             |
|-----------------------|--|-----------------------------------|---------------------------|---------------------------|---------------------------|---------------------------|---|----------------------------|-----------------------|-----------------|-----------------------------|
|                       | Total Quantity Generated                                   | Hard Rock & Large Broken Concrete | Reused in the Contract    | Reused in other Projects  | Disposed as Public Fill   | Imported Fill             | Metals  | Paper/ cardboard packaging | Plastics (see Note 3) | Chemicals Waste | Others, e.g. general refuse |
|                       | (in '000 m <sup>3</sup> )                                  | (in '000 m <sup>3</sup> )         | (in '000 m <sup>3</sup> ) | (in '000 m <sup>3</sup> ) | (in '000 m <sup>3</sup> ) | (in '000 m <sup>3</sup> ) | (in '000 kg)                                      | (in '000 kg)               | (in '000 kg)          | (in '000 kg)    | (in '000 m <sup>3</sup> )   |
| Accumulated From 2017 | 0.84697  | 0                                 | 0.175365                  | 0.290915                  | 0.350135                  | 0.03056                   | 0   | 0                          | 0                     | 0               | 0.03079                     |
| Jan                   | 0.2397525  | 0                                 | 0                         | 0.0642025                 | 0.17555                   | 0                         | 0   | 0                          | 0                     | 0               | 0.00614                     |
| Feb                   | 0.0722875  | 0                                 | 0                         | 0.0722875                 | 0                         | 0                         | 0   | 0                          | 0                     | 0               | 0                           |
| Mar                   | 0.05853  | 0                                 | 0                         | 0                         | 0.05853                   | 0                         | 0   | 0                          | 0                     | 0               | 0                           |
| Apr                   | 0.007575   | 0                                 | 0                         | 0                         | 0.007575                  | 0                         | 0   | 0                          | 0                     | 0               | 0                           |
| May                   | 0  | 0                                 | 0                         | 0                         | 0                         | 0                         | 0   | 0                          | 0                     | 0               | 0.001258                    |
| June                  | 0  | 0                                 | 0                         | 0                         | 0                         | 0                         | 0   | 0                          | 0                     | 0               | 0                           |
| Sub-total             |  |                                   |                           |                           |                           |                           |   |                            |                       |                 |                             |
| July                  |  |                                   |                           |                           |                           |                           |   |                            |                       |                 |                             |
| Aug                   |  |                                   |                           |                           |                           |                           |   |                            |                       |                 |                             |
| Sept                  |  |                                   |                           |                           |                           |                           |   |                            |                       |                 |                             |
| Oct                   |  |                                   |                           |                           |                           |                           |   |                            |                       |                 |                             |
| Nov                   |  |                                   |                           |                           |                           |                           |   |                            |                       |                 |                             |
| Dec                   |  |                                   |                           |                           |                           |                           |   |                            |                       |                 |                             |
| Total                 | 1.225109   | 0                                 | 0.175365                  | 0.427405                  | 0.59179                   | 0.03056                   | 0   | 0                          | 0                     | 0               | 0.038188                    |

- Notes:
- (1) The performance targets are given in PS Clause 6.14.
  - (2) The waste flow table shall also include C&D materials that are specified in the Contract to be imported for use at the Site.
  - (3) Plastics refer to plastic bottles/containers, plastic sheets/foam from packaging materials.
  - (4) The *Contractor* shall also submit the latest forecast of the total amount of C&D materials expected to be generated from the *works*, together with a breakdown of the nature where the total amount of C&D materials expected to be generated from the *works* is equal to or exceeding 50,000 ms.

Monthly Summary Waste Flow Table for 2018

Name of Department: Civil Engineering and Development Department

Contract No.: NE/2017/01

| Month     | Actual Quantities of Inert C&D Materials Generated Monthly |                                     |                          |                          |                          |                          | Actual Quantities of C&D Wastes Generated Monthly |                            |             |                |                             |
|-----------|--|-------------------------------------|--------------------------|--------------------------|--------------------------|--------------------------|---|----------------------------|-------------|----------------|-----------------------------|
|           | Total Quantity Generated                                   | Hard Rock and Large Broken Concrete | Reused in the Contract   | Reused in other Projects | Disposed as Public Fill  | Imported Fill            | Metals  | Paper/ cardboard packaging | Plastics    | Chemical Waste | Others, e.g. general refuse |
|           | (in '000m <sup>3</sup> )                                   | (in '000m <sup>3</sup> )            | (in '000m <sup>3</sup> ) | (in '000m <sup>3</sup> ) | (in '000m <sup>3</sup> ) | (in '000m <sup>3</sup> ) | (in '000kg)                                       | (in '000kg)                | (in '000kg) | (in '000kg)    | (in '000m <sup>3</sup> )    |
| Jan       | 0.0000   | 0.0000                              | 0.0000                   | 0.0000                   | 0.0000                   | 0.0000                   | 0.0000  | 0.0000                     | 0.0000      | 0.0000         | 0.0000                      |
| Feb       | 0.0000   | 0.0000                              | 0.0000                   | 0.0000                   | 0.0000                   | 0.0000                   | 0.0000  | 0.0000                     | 0.0000      | 0.0000         | 0.0000                      |
| Mar       | 0.0000   | 0.0000                              | 0.0000                   | 0.0000                   | 0.0000                   | 0.0000                   | 0.0000  | 0.0000                     | 0.0000      | 0.0000         | 0.0000                      |
| Apr       | 0.0000   | 0.0000                              | 0.0000                   | 0.0000                   | 0.0000                   | 0.0000                   | 0.0000  | 0.0000                     | 0.0000      | 0.0000         | 0.0000                      |
| May       | 0.0222   | 0.0060                              | 0.0000                   | 0.0000                   | 0.0162                   | 0.0000                   | 0.0000  | 0.0000                     | 0.0000      | 0.0000         | 0.0024                      |
| Jun       | 0.0078   | 0.0000                              | 0.0000                   | 0.0000                   | 0.0078                   | 0.0000                   | 0.0000  | 0.0000                     | 0.0000      | 0.0000         | 0.0055                      |
| Sub-total | 0.0300   | 0.0060                              | 0.0000                   | 0.0000                   | 0.0240                   | 0.0000                   | 0.0000  | 0.0000                     | 0.0000      | 0.0000         | 0.0079                      |
| Jul       |  |                                     |                          |                          |                          |                          |   |                            |             |                |                             |
| Aug       |  |                                     |                          |                          |                          |                          |   |                            |             |                |                             |
| Sep       |  |                                     |                          |                          |                          |                          |   |                            |             |                |                             |
| Oct       |  |                                     |                          |                          |                          |                          |   |                            |             |                |                             |
| Nov       |  |                                     |                          |                          |                          |                          |   |                            |             |                |                             |
| Dec       |  |                                     |                          |                          |                          |                          |   |                            |             |                |                             |
| Total     | 0.0300   | 0.0060                              | 0.0000                   | 0.0000                   | 0.0240                   | 0.0000                   | 0.0000  | 0.0000                     | 0.0000      | 0.0000         | 0.0079                      |

- Notes:
1. Assume the density of soil fill is 2 ton/m<sup>3</sup>.
  2. Assume the density of rock and broken concrete is 2.5 ton/m<sup>3</sup>.
  3. Assume the density of mixed rock and soil is 1.9 ton/m<sup>3</sup>.
  4. Assume the density of slurry and bentonite is 2.8 ton/m<sup>3</sup>.
  5. The slurry and bentonite are disposed at Tseung Kwan O Area 137 Fill Bank.
  6. Assume the density of C&D waste is 0.9 ton/m<sup>3</sup>.
  7. The non-inert C&D wastes are disposed at NENT.



### Monthly Summary of Waste Flow Table for 2018

Name of Person completing the Record: Ricky Hon

| Month            | Actual Quantities of Inert C&D Materials Generated Monthly |                          |                          |                          |                          | Actual Quantities of Non-inert C&D Wastes Generated Monthly |                            |                     |                |                             |
|------------------|--|--------------------------|--------------------------|--------------------------|--------------------------|---|----------------------------|---------------------|----------------|-----------------------------|
|                  | Total Quantity Generated                                   | Broken Concrete          | Reused in the Contract   | Reused in other Projects | Disposed as Public Fill  | Metals  | Paper/ cardboard packaging | Plastics            | Chemical Waste | Others, e.g. general refuse |
|                  |  | <i>(see Note 1)</i>      |                          |                          |                          |   |                            | <i>(see Note 2)</i> |                |                             |
|                  | (in '000m <sup>3</sup> )                                   | (in '000m <sup>3</sup> ) | (in '000m <sup>3</sup> ) | (in '000m <sup>3</sup> ) | (in '000m <sup>3</sup> ) | (in '000 Kg)  | (in '000 Kg)               | (in '000 Kg)        | (in '000 Kg)   | (in '000m <sup>3</sup> )    |
| Jan              | 0  | 0                        | 0                        | 0                        | 0                        | 0   | 0                          | 0                   | 0              | 0                           |
| Feb              | 0  | 0                        | 0                        | 0                        | 0                        | 0   | 0                          | 0                   | 0              | 0.143                       |
| Mar              | 0  | 0                        | 0                        | 0                        | 0                        | 0   | 0                          | 0                   | 0              | 0                           |
| Apr              | 0  | 0.039                    | 0                        | 0                        | 0                        | 0   | 0                          | 0                   | 0              | 0.0585                      |
| May              | 0  | 0                        | 0                        | 0                        | 0                        | 0   | 0                          | 0                   | 0              | 0.0325                      |
| Jun              | 0  | 1.5194                   | 0                        | 0                        | 0                        | 0   | 0                          | 0                   | 0              | 0.0455                      |
| <b>Sub-total</b> | <b>0</b>   | <b>1.5584</b>            | <b>0</b>                 | <b>0</b>                 | <b>0</b>                 | <b>0</b>  | <b>0</b>                   | <b>0</b>            | <b>0</b>       | <b>0.2795</b>               |
| Jul              |  |                          |                          |                          |                          |   |                            |                     |                |                             |
| Aug              |  |                          |                          |                          |                          |   |                            |                     |                |                             |
| Sept             |  |                          |                          |                          |                          |   |                            |                     |                |                             |
| Oct              |  |                          |                          |                          |                          |   |                            |                     |                |                             |
| Nov              |  |                          |                          |                          |                          |   |                            |                     |                |                             |
| Dec              |  |                          |                          |                          |                          |   |                            |                     |                |                             |
| <b>Total</b>     | <b>0</b>   | <b>1.5584</b>            | <b>0</b>                 | <b>0</b>                 | <b>0</b>                 | <b>0</b>  | <b>0</b>                   | <b>0</b>            | <b>0</b>       | <b>0.2795</b>               |

Notes:

- (1) Broken concrete for recycling into aggregates.
- (2) Plastics refer to plastic bottles/containers, plastic sheets/foam from packaging material.
- (3) Use the conversion factor: 1 full load of 24t / 30t dumping truck being equivalent to 6.5m<sup>3</sup> / 8.125 m<sup>3</sup> by volume.



---

---

**APPENDIX Q  
TENTATIVE CONSTRUCTION  
PROGRAMME**

---

---

### High Level 3 Months Look Ahead Programme

| Activities   | Jul-18 | Aug-18 | Sep-18 |
|--|--------|--------|--------|
| <b>Lam Tin Interchange</b>                           |        |        |        |
| EHC2 U-Trough  |        |        |        |
| Site Formation - Area 1G1 & 1G2 &5                   |        |        |        |
| Site Formation - Area 2                              |        |        |        |
| Site Formation - Area 3                              |        |        |        |
| Site Formation - Area 4                              |        |        |        |
| <b>Main Tunnel</b>                                   |        |        |        |
| MT Excavation  |        |        |        |
| <b>TKO Interchange</b>                               |        |        |        |
| Haul Road Construction, Site Formation & Slope Works |        |        |        |
| Steel Platform for Bridge Construction               |        |        |        |
| Cavern Excavation                                    |        |        |        |


| Activity ID  | Activity Name  | Calendar | Original Duration | Remaining Duration | Start       | Finish      | Total Float | Activity % Complete | TRA | Variance - BL1 | 2018 |     |     |     |     |  |  |
|--|--|----------|-------------------|--------------------|-------------|-------------|-------------|---------------------|-----|----------------|------|-----|-----|-----|-----|--|--|
|  |  |          |                   |                    |             |             |             |                     |     |                | Jun  | Jul | Aug | Sep | Oct |  |  |
| <b>NE/2015/02 Tseung Kwan O - Lam Tin Tunnel-Road P2 and Associated Works (Jun-18)</b>                       |  |          |                   |                    |             |             |             |                     |     |                |      |     |     |     |     |  |  |
| <b>Early Warning (EW)</b>  |  |          |                   |                    |             |             |             |                     |     |                |      |     |     |     |     |  |  |
| B31220   | EW no.085 Damages to Hopper Barge due to Non-Compliance of Material from C1                      | P2-Cal.A | 0                 | 0                  | 20-Jun-18 A | 20-Jun-18 A |             | 100%                |     | 0              |      |     |     |     |     |  |  |
| <b>Preliminaries, Submission, Contractor's Design Submission and Approval</b>                                |  |          |                   |                    |             |             |             |                     |     |                |      |     |     |     |     |  |  |
| <b>Preliminaries</b>   |  |          |                   |                    |             |             |             |                     |     |                |      |     |     |     |     |  |  |
| <b>Design Submission of Physical Model</b>   |  |          |                   |                    |             |             |             |                     |     |                |      |     |     |     |     |  |  |
| LC10242  | Design the Physical Model  | P2-Cal.A | 14                | 9                  | 02-Jun-18 A | 28-Jun-18   | 586         | 35.71%              |     | -13            |      |     |     |     |     |  |  |
| LC10244  | Review and Discuss the Physical Model  | P2-Cal.A | 21                | 21                 | 29-Jun-18   | 19-Jul-18   | 586         | 0%                  |     | 0              |      |     |     |     |     |  |  |
| LC10246  | Re-submission of Physical Model  | P2-Cal.A | 14                | 14                 | 20-Jul-18   | 02-Aug-18   | 586         | 0%                  |     | 0              |      |     |     |     |     |  |  |
| LC10248  | Approve the Physical Model   | P2-Cal.A | 21                | 21                 | 03-Aug-18   | 23-Aug-18   | 586         | 0%                  |     | 0              |      |     |     |     |     |  |  |
| LC10250  | Fabrication of Physical Model  | P2-Cal.A | 90                | 90                 | 24-Aug-18   | 21-Nov-18   | 586         | 0%                  |     | 0              |      |     |     |     |     |  |  |
| <b>General Submission and Acceptance</b>   |  |          |                   |                    |             |             |             |                     |     |                |      |     |     |     |     |  |  |
| S10240   | Prepare/Submit the Weather Protection Scheme   | P2-Cal.A | 30                | 20                 | 21-Aug-17 A | 09-Jul-18   | 721         | 33.33%              |     | -293           |      |     |     |     |     |  |  |
| <b>Contractor's Design Submission and Acceptance</b>   |  |          |                   |                    |             |             |             |                     |     |                |      |     |     |     |     |  |  |
| <b>Foundation Design</b>   |  |          |                   |                    |             |             |             |                     |     |                |      |     |     |     |     |  |  |
| <b>AIP Submission for Foundation of Road P2 Structure (Reclaimed Section) Zone 1 CT01 CH366.059-201.44</b>   |  |          |                   |                    |             |             |             |                     |     |                |      |     |     |     |     |  |  |
| S11260-03  | 3rd Resubmit AIP Submission for Foundation of Road P2 Structure (Reclaimed Section Zone 1)       | P2-Cal.A | 14                | 2                  | 01-Jun-18 A | 21-Jun-18   | -104        | 85.71%              |     | -7             |      |     |     |     |     |  |  |
| S11260-04  | Review and Accept AIP Submission for Foundation of Road P2 Structure (Reclaimed Section Zone 1)  | P2-Cal.A | 21                | 21                 | 22-Jun-18   | 12-Jul-18   | -104        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| <b>AIP Submission for Foundation of Road P2 Structure (Reclaimed Section) Zone 2 (S200 CH821 - P2 CH188)</b> |  |          |                   |                    |             |             |             |                     |     |                |      |     |     |     |     |  |  |
| S11270-01  | 3rd Resubmit AIP Submission for Foundation of Road P2 Structure (Reclaimed Section Zone 2)       | P2-Cal.A | 14                | 2                  | 01-Jun-18 A | 21-Jun-18   | -104        | 85.71%              |     | -7             |      |     |     |     |     |  |  |
| S11270-02  | Review and Accept AIP Submission for Foundation of Road P2 Structure (Reclaimed Section Zone 2)  | P2-Cal.A | 21                | 21                 | 22-Jun-18   | 12-Jul-18   | -104        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| <b>AIP Submission for Foundation of Road P2 Structure (Reclaimed Section) Zone 3 (P2 CH188 - CH278)</b>      |  |          |                   |                    |             |             |             |                     |     |                |      |     |     |     |     |  |  |
| S11279-01  | 3rd Resubmit AIP Submission for Foundation of Road P2 Structure (Reclaimed Section Zone 3)       | P2-Cal.A | 14                | 2                  | 01-Jun-18 A | 21-Jun-18   | -104        | 85.71%              |     | -7             |      |     |     |     |     |  |  |
| S11279-02  | Review and Accept AIP Submission for Foundation of Road P2 Structure (Reclaimed Section Zone 3)  | P2-Cal.A | 21                | 21                 | 22-Jun-18   | 12-Jul-18   | -104        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| <b>DDA Submission for Foundation of Road P2 Structure (Reclaimed Section) Zone 1 CT01 CH366.059-201.44</b>   |  |          |                   |                    |             |             |             |                     |     |                |      |     |     |     |     |  |  |
| S11360   | Prepare and Submit DDA Submission for Foundation of Road P2 Structure (Reclaimed Section Zone 1) | P2-Cal.A | 21                | 21                 | 13-Jul-18   | 02-Aug-18   | -104        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| S11380   | Review and Discuss DDA Submission for Foundation of Road P2 Structure (Reclaimed Section Zone 1) | P2-Cal.A | 21                | 21                 | 03-Aug-18   | 23-Aug-18   | -104        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| S11400   | Resubmit DDA Submission for Foundation of Road P2 Structure (Reclaimed Section Zone 1)           | P2-Cal.A | 14                | 14                 | 24-Aug-18   | 06-Sep-18   | -104        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| S11410   | Review and comment by GEO  | P2-Cal.A | 14                | 14                 | 07-Sep-18   | 20-Sep-18   | -104        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| <b>DDA Submission for Foundation of Road P2 Structure (Reclaimed Section) Zone 2 (S200 CH821 - P2 CH188)</b> |  |          |                   |                    |             |             |             |                     |     |                |      |     |     |     |     |  |  |
| S11422   | Prepare and Submit DDA Submission for Foundation of Road P2 Structure (Reclaimed Section Zone 2) | P2-Cal.A | 21                | 21                 | 13-Jul-18   | 02-Aug-18   | -104        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| S11424   | Review and Discuss DDA Submission for Foundation of Road P2 Structure (Reclaimed Section Zone 2) | P2-Cal.A | 21                | 21                 | 03-Aug-18   | 23-Aug-18   | -104        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| S11426   | Resubmit DDA Submission for Foundation of Road P2 Structure (Reclaimed Section Zone 2)           | P2-Cal.A | 14                | 14                 | 24-Aug-18   | 06-Sep-18   | -104        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| S11428   | Review and comment by GEO  | P2-Cal.A | 14                | 14                 | 07-Sep-18   | 20-Sep-18   | -104        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| <b>DDA Submission for Foundation of Road P2 Structure (Reclaimed Section) Zone 3 (P2 CH188 - CH278)</b>      |  |          |                   |                    |             |             |             |                     |     |                |      |     |     |     |     |  |  |
| S11432   | Prepare and Submit DDA Submission for Foundation of Road P2 Structure (Reclaimed Section Zone 3) | P2-Cal.A | 21                | 21                 | 13-Jul-18   | 02-Aug-18   | -104        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| S11434   | Review and Discuss DDA Submission for Foundation of Road P2 Structure (Reclaimed Section Zone 3) | P2-Cal.A | 21                | 21                 | 03-Aug-18   | 23-Aug-18   | -104        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| S11436   | Resubmit DDA Submission for Foundation of Road P2 Structure (Reclaimed Section Zone 3)           | P2-Cal.A | 14                | 14                 | 24-Aug-18   | 06-Sep-18   | -104        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| S11438   | Review and comment by GEO  | P2-Cal.A | 14                | 14                 | 07-Sep-18   | 20-Sep-18   | -104        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| <b>E&amp;M Design</b>  |  |          |                   |                    |             |             |             |                     |     |                |      |     |     |     |     |  |  |
| <b>Statutory Approval for E&amp;M Works</b>  |  |          |                   |                    |             |             |             |                     |     |                |      |     |     |     |     |  |  |
| S11570-11  | FSD Approval for Underpass GBP   | P2-Cal.A | 0                 | 0                  | 22-Aug-18   | 22-Aug-18   | 54          | 0%                  |     | 0              |      |     |     |     |     |  |  |
| S11570-12  | FSD Approval for Plant room GBP  | P2-Cal.A | 0                 | 0                  | 22-Aug-18   | 22-Aug-18   | 54          | 0%                  |     | 0              |      |     |     |     |     |  |  |

█ Primary Baseline    █ Critical Remaining Work  
█ Actual Work    ◆ Milestone  
█ Remaining Work    ▼ Summary

**NE/2015/02 Tseung Kwan O - Lam Tin Tunnel-Road P2 and Associated Works (Jun-18)**

3 Monthly Rolling Programme  
(Data Date : 20-Jun-2018)

| Date      | Revision | Checked | Approved |
|-----------|----------|---------|----------|
| 20-Jun-18 |          |         |          |



█ Primary Baseline    █ Critical Remaining Work  
█ Actual Work    ◆ Milestone  
█ Remaining Work    ▼ Summary

NE/2015/02 Tseung Kwan O - Lam Tin Tunnel-Road P2 and Associated Works (Jun-18)

3 Monthly Rolling Programme  
(Data Date : 20-Jun-2018)

Page : 2 of 13

| Date      | Revision | Checked | Approved |
|-----------|----------|---------|----------|
| 20-Jun-18 |          |         |          |

| Activity ID  | Activity Name   | Calendar | Original Duration | Remaining Duration | Start       | Finish    | Total Float | Activity % Complete | TRA | Variance - BL1 | 2018 |     |     |     |     |
|--|---|----------|-------------------|--------------------|-------------|-----------|-------------|---------------------|-----|----------------|------|-----|-----|-----|-----|
|  |   |          |                   |                    |             |           |             |                     |     |                | Jun  | Jul | Aug | Sep | Oct |
| S11665   | Design Coordination for EL Services   | P2-Cal.A | 60                | 15                 | 07-Mar-17 A | 04-Jul-18 | 84          | 75%                 |     | -425           |      |     |     |     |     |
| S11666   | 1st review by EMSD/HyD  | P2-Cal.A | 15                | 5                  | 10-May-18 A | 09-Jul-18 | 84          | 66.67%              |     | -46            |      |     |     |     |     |
| S11667   | Formal Submission to Supervisor   | P2-Cal.A | 7                 | 7                  | 10-Jul-18   | 16-Jul-18 | 84          | 0%                  |     | 0              |      |     |     |     |     |
| S11668   | Accept detail design by the Supervisor  | P2-Cal.A | 7                 | 7                  | 17-Jul-18   | 23-Jul-18 | 84          | 0%                  |     | 0              |      |     |     |     |     |
| <b>ELV And SCADA Detail Design</b>   |   | P2-Cal.A | 211               | 29                 | 12-Aug-17 A | 18-Jul-18 | 89          |                     |     | -130           |      |     |     |     |     |
| <b>Underpass</b>   |   | P2-Cal.A | 211               | 29                 | 12-Aug-17 A | 18-Jul-18 | 89          |                     |     | -130           |      |     |     |     |     |
| S11669-10  | Design Coordination for ELV & SCADA   | P2-Cal.A | 60                | 10                 | 12-Aug-17 A | 29-Jun-18 | 89          | 83.33%              |     | -262           |      |     |     |     |     |
| S11669-19  | 2nd review by HyD   | P2-Cal.A | 15                | 5                  | 04-May-18 A | 04-Jul-18 | 89          | 66.67%              |     | -47            |      |     |     |     |     |
| S11669-29  | Formal Submission to Supervisor   | P2-Cal.A | 7                 | 7                  | 05-Jul-18   | 11-Jul-18 | 89          | 0%                  |     | 0              |      |     |     |     |     |
| S11669-30  | Accept detail design by the Supervisor  | P2-Cal.A | 7                 | 7                  | 12-Jul-18   | 18-Jul-18 | 89          | 0%                  |     | 0              |      |     |     |     |     |
| <b>Plantroom</b>   |   | P2-Cal.A | 172               | 29                 | 12-Aug-17 A | 18-Jul-18 | 89          |                     |     | -169           |      |     |     |     |     |
| S11670-10  | Design Coordination for ELV & SCADA   | P2-Cal.A | 60                | 10                 | 12-Aug-17 A | 29-Jun-18 | 89          | 83.33%              |     | -262           |      |     |     |     |     |
| S11670-19  | 2nd review by HyD   | P2-Cal.A | 15                | 5                  | 04-May-18 A | 04-Jul-18 | 89          | 66.67%              |     | -47            |      |     |     |     |     |
| S11670-29  | Formal Submission to Supervisor   | P2-Cal.A | 7                 | 7                  | 05-Jul-18   | 11-Jul-18 | 89          | 0%                  |     | 0              |      |     |     |     |     |
| S11670-30  | Accept detail design by the Supervisor  | P2-Cal.A | 7                 | 7                  | 12-Jul-18   | 18-Jul-18 | 89          | 0%                  |     | 0              |      |     |     |     |     |
| <b>Design of Architectural Finishes for Internal Walls of U-Trough Structures</b>          |   | P2-Cal.A | 77                | 77                 | 25-Jun-18   | 09-Sep-18 | 151         |                     |     | 0              |      |     |     |     |     |
| S11675   | Prepare and Submit Design of Architectural Finishes for Internal Walls of U-Trough Structures (VE and PC Panel) | P2-Cal.A | 21                | 21                 | 25-Jun-18   | 15-Jul-18 | 151         | 0%                  |     | 0              |      |     |     |     |     |
| S11680   | Review and Discuss Design of Architectural Finishes for Internal Walls of U-Trough Structures (VE and PC Panel) | P2-Cal.A | 21                | 21                 | 16-Jul-18   | 05-Aug-18 | 151         | 0%                  |     | 0              |      |     |     |     |     |
| S11700   | Resubmit Design of Architectural Finishes for Internal Walls of U-Trough Structures (VE and PC Panel)           | P2-Cal.A | 14                | 14                 | 06-Aug-18   | 19-Aug-18 | 151         | 0%                  |     | 0              |      |     |     |     |     |
| S11720   | Review and Accept Design of Architectural Finishes for Internal Walls of U-Trough Structures (VE and PC Panel)  | P2-Cal.A | 21                | 21                 | 20-Aug-18   | 09-Sep-18 | 151         | 0%                  |     | 0              |      |     |     |     |     |
| <b>Irrigation System</b>   |   | P2-Cal.A | 98                | 98                 | 20-Jun-18   | 25-Sep-18 | 90          |                     |     | 0              |      |     |     |     |     |
| S11787-01  | 2nd review by LCSD/EMSD   | P2-Cal.A | 21                | 21                 | 20-Jun-18   | 10-Jul-18 | 90          | 0%                  |     | 0              |      |     |     |     |     |
| S11788   | Prepare & Submission of Form 542  | P2-Cal.A | 14                | 14                 | 11-Jul-18   | 24-Jul-18 | 90          | 0%                  |     | 0              |      |     |     |     |     |
| S11789   | Reviewed by WSD   | P2-Cal.A | 28                | 28                 | 25-Jul-18   | 21-Aug-18 | 90          | 0%                  |     | 0              |      |     |     |     |     |
| S11790   | Formal Submission to Supervisor   | P2-Cal.A | 14                | 14                 | 22-Aug-18   | 04-Sep-18 | 90          | 0%                  |     | 0              |      |     |     |     |     |
| S11800   | Review and Accept Submission for Waterpoints and associated elements  | P2-Cal.A | 21                | 21                 | 05-Sep-18   | 25-Sep-18 | 90          | 0%                  |     | 0              |      |     |     |     |     |
| <b>Contractor Cost Saving Design</b>   |   | P2-Cal.A | 132               | 101                | 07-May-18 A | 28-Sep-18 | 162         |                     |     | -13            |      |     |     |     |     |
| <b>AIP Submission for CSD2 of Reclaimed Section (S200 CH674 - CH755, S300 CH326-CH355)</b> |   | P2-Cal.A | 90                | 59                 | 07-May-18 A | 17-Aug-18 | 11          |                     |     | -13            |      |     |     |     |     |
| S11930   | Review and Discuss AIP Submission for CSD of Reclaimed Section (S200 CH674 - CH755, S300 CH326-CH355)           | P2-Cal.A | 21                | 3                  | 07-May-18 A | 22-Jun-18 | 11          | 85.71%              |     | -26            |      |     |     |     |     |
| S11940   | Resubmit AIP for CSD of Reclaimed Section (S200 CH674 - CH755, S300 CH326-CH355)                                | P2-Cal.A | 28                | 28                 | 23-Jun-18   | 20-Jul-18 | 11          | 0%                  |     | 0              |      |     |     |     |     |
| S11950   | Review and Accept AIP Submission for CSD of Reclaimed Section by CEDD (S200 CH674 - CH755, S300 CH326-CH355)    | P2-Cal.A | 21                | 21                 | 21-Jul-18   | 10-Aug-18 | 18          | 0%                  |     | 0              |      |     |     |     |     |
| S11960   | Review and Accept AIP Submission for CSD of Reclaimed Section by HYD (S200 CH674 - CH755, S300 CH326-CH355)     | P2-Cal.A | 28                | 28                 | 21-Jul-18   | 17-Aug-18 | 11          | 0%                  |     | 0              |      |     |     |     |     |
| <b>DDA Submission for CSD2 of Reclaimed Section (S200 CH674 - CH755, S300 CH326-CH355)</b> |   | P2-Cal.A | 42                | 42                 | 18-Aug-18   | 28-Sep-18 | 11          |                     |     | 0              |      |     |     |     |     |
| S11962   | Prepare and Submit DDA Submission for CSD of Reclaimed Section (S200 CH674 - CH755, S300 CH326-CH355)           | P2-Cal.A | 21                | 21                 | 18-Aug-18   | 07-Sep-18 | 11          | 0%                  |     | 0              |      |     |     |     |     |
| S11964   | Review and Discuss DDA Submission for CSD of Reclaimed Section (S200 CH674 - CH755, S300 CH326-CH355)           | P2-Cal.A | 21                | 21                 | 08-Sep-18   | 28-Sep-18 | 11          | 0%                  |     | 0              |      |     |     |     |     |
| <b>AIP Submission for CSD3 of Reclaimed Section (S200 CH821 - P2 CH305)</b>                |   | P2-Cal.A | 86                | 59                 | 07-May-18 A | 17-Aug-18 | 162         |                     |     | -17            |      |     |     |     |     |
| S11971   | Review and Discuss AIP Submission for CSD of Reclaimed Section (S200 CH821 - P2 CH305)                          | P2-Cal.A | 21                | 3                  | 07-May-18 A | 22-Jun-18 | 162         | 85.71%              |     | -26            |      |     |     |     |     |
| S11972   | Resubmit AIP Submission for CSD of Reclaimed Section (S200 CH821 - P2 CH305)                                    | P2-Cal.A | 28                | 28                 | 23-Jun-18   | 20-Jul-18 | 162         | 0%                  |     | 0              |      |     |     |     |     |
| S11973   | Review and Accept AIP Submission for CSD of Reclaimed Section by CEDD (S200 CH821 - P2 CH305)                   | P2-Cal.A | 21                | 21                 | 21-Jul-18   | 10-Aug-18 | 169         | 0%                  |     | 0              |      |     |     |     |     |
| S11974   | Review and Accept AIP Submission for CSD of Reclaimed Section by HyD (S200 CH821 - P2 CH305)                    | P2-Cal.A | 28                | 28                 | 21-Jul-18   | 17-Aug-18 | 162         | 0%                  |     | 0              |      |     |     |     |     |
| <b>DDA Submission for CSD3 of Reclaimed Section (S200 CH821 - P2 CH305)</b>                |   | P2-Cal.A | 42                | 42                 | 18-Aug-18   | 28-Sep-18 | 162         |                     |     | 0              |      |     |     |     |     |
| S11975   | Prepare and Submit DDA Submission for CSD of Reclaimed Section (S200 CH821 - P2 CH305)                          | P2-Cal.A | 21                | 21                 | 18-Aug-18   | 07-Sep-18 | 162         | 0%                  |     | 0              |      |     |     |     |     |
| S11976   | Review and Discuss DDA Submission for CSD of Reclaimed Section (S200 CH821 - P2 CH305)                          | P2-Cal.A | 21                | 21                 | 08-Sep-18   | 28-Sep-18 | 162         | 0%                  |     | 0              |      |     |     |     |     |

█ Primary Baseline    █ Critical Remaining Work  
█ Actual Work    ◆ Milestone  
█ Remaining Work    ▼ Summary

NE/2015/02 Tseung Kwan O - Lam Tin Tunnel-Road P2 and Associated Works (Jun-18)

3 Monthly Rolling Programme  
(Data Date : 20-Jun-2018)

Page : 3 of 13

| Date      | Revision | Checked | Approved |
|-----------|----------|---------|----------|
| 20-Jun-18 |          |         |          |

| Activity ID  | Activity Name  | Calendar | Original Duration | Remaining Duration | Start     | Finish    | Total Float | Activity % Complete | TRA | Variance - BL1 | 2018 |     |     |     |     |  |  |  |  |
|--|--|----------|-------------------|--------------------|-----------|-----------|-------------|---------------------|-----|----------------|------|-----|-----|-----|-----|--|--|--|--|
|  |  |          |                   |                    |           |           |             |                     |     |                | Jun  | Jul | Aug | Sep | Oct |  |  |  |  |
| <b>Major Temporary Works Design</b>                            |  |          |                   |                    |           |           |             |                     |     |                |      |     |     |     |     |  |  |  |  |
| <b>ELS Design for U-Trough C (CT01 CH 366.059- CH 177.156)</b> |  |          |                   |                    |           |           |             |                     |     |                |      |     |     |     |     |  |  |  |  |
| S12780   | Prepare and Submit ELS Design for U-Trough C (CT01 CH 366.059- CH 177.156)                 | P2-Cal.A | 18                | 18                 | 13-Sep-18 | 30-Sep-18 | 69          | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| <b>Design of Marine Survey Tower</b>                           |  |          |                   |                    |           |           |             |                     |     |                |      |     |     |     |     |  |  |  |  |
| S13100   | Prepare and Submit Marine Survey Tower   | P2-Cal.A | 18                | 18                 | 20-Jun-18 | 07-Jul-18 | -37         | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S13120   | Review and Discuss Marine Survey Tower   | P2-Cal.A | 21                | 21                 | 08-Jul-18 | 28-Jul-18 | -37         | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S13140   | Resubmit Temporary Marine Survey Tower   | P2-Cal.A | 14                | 14                 | 29-Jul-18 | 11-Aug-18 | -37         | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S13160   | Accept Temporary Marine Survey Tower   | P2-Cal.A | 21                | 21                 | 12-Aug-18 | 01-Sep-18 | -37         | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| <b>Major Construction Works Method Statement</b>               |  |          |                   |                    |           |           |             |                     |     |                |      |     |     |     |     |  |  |  |  |
| <b>Construction Road P2 Underpass Structure CH105-318</b>      |  |          |                   |                    |           |           |             |                     |     |                |      |     |     |     |     |  |  |  |  |
| S13190   | Prepare and Submit Method Statement for Construction Road P2 Underpass Structure           | P2-Cal.A | 18                | 18                 | 11-Aug-18 | 28-Aug-18 | 230         | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S13200   | Review and Discuss Method Statement for Construction Road P2 Underpass Structure           | P2-Cal.A | 21                | 21                 | 29-Aug-18 | 18-Sep-18 | 230         | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S13220   | Resubmit Method Statement for Construction Road P2 Underpass Structure                     | P2-Cal.A | 7                 | 7                  | 19-Sep-18 | 25-Sep-18 | 230         | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| <b>Installation of bored pile for construction of abutment</b> |  |          |                   |                    |           |           |             |                     |     |                |      |     |     |     |     |  |  |  |  |
| S13420   | Prepare and Submit Method Statement for Installation of bored piling                       | P2-Cal.A | 18                | 18                 | 18-Aug-18 | 04-Sep-18 | -36         | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S13440   | Review and Discuss Method Statement for Installation of bored piling                       | P2-Cal.A | 21                | 21                 | 05-Sep-18 | 25-Sep-18 | -36         | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| <b>Removal of Temporary Steel Cofferdam</b>                    |  |          |                   |                    |           |           |             |                     |     |                |      |     |     |     |     |  |  |  |  |
| S13810   | Prepare and Submit Method Statement for Removal of Temporary Steel Cofferdam (type 1)      | P2-Cal.A | 18                | 18                 | 20-Jun-18 | 07-Jul-18 | -100        | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S13811   | Review and Discuss Method Statement for Removal of Temporary Steel Cofferdam (type 1)      | P2-Cal.A | 21                | 21                 | 08-Jul-18 | 28-Jul-18 | -100        | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S13812   | Resubmit Method Statement for Removal of Temporary Steel Cofferdam (type 1)                | P2-Cal.A | 7                 | 7                  | 29-Jul-18 | 04-Aug-18 | -100        | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S13813   | Accept Method Statement for Removal of Temporary Steel Cofferdam (type 1)                  | P2-Cal.A | 21                | 21                 | 05-Aug-18 | 25-Aug-18 | -100        | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S13814   | Prepare and Submit Method Statement for Removal of Temporary Steel Cofferdam (type 2)      | P2-Cal.A | 18                | 18                 | 26-Aug-18 | 12-Sep-18 | -100        | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S13815   | Review and Discuss Method Statement for Removal of Temporary Steel Cofferdam (type 2)      | P2-Cal.A | 21                | 21                 | 13-Sep-18 | 03-Oct-18 | -100        | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| <b>Removal of Water Gate</b>                                   |  |          |                   |                    |           |           |             |                     |     |                |      |     |     |     |     |  |  |  |  |
| S13882   | Prepare and Submit Method Statement for Removal of Water Gate                              | P2-Cal.A | 18                | 18                 | 06-Aug-18 | 23-Aug-18 | 60          | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S13884   | Review and Discuss Method Statement for Removal of Water Gate                              | P2-Cal.A | 21                | 21                 | 24-Aug-18 | 13-Sep-18 | 60          | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S13886   | Resubmit Method Statement for Removal of Water Gate  | P2-Cal.A | 7                 | 7                  | 14-Sep-18 | 20-Sep-18 | 60          | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| <b>ELS of Underpass (P2 CH105-318)</b>                         |  |          |                   |                    |           |           |             |                     |     |                |      |     |     |     |     |  |  |  |  |
| S14056   | Prepare and Submit Method Statement for Excavation and ELS of Underpass (P2 CH105-318)     | P2-Cal.A | 18                | 18                 | 27-Jun-18 | 14-Jul-18 | 1           | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S14057   | 1st Review and Discuss Method Statement for Excavation and ELS of Underpass (P2 CH105-318) | P2-Cal.A | 21                | 21                 | 15-Jul-18 | 04-Aug-18 | 1           | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S14058   | Resubmit Method Statement for Excavation and ELS of Underpass (P2 CH105-318)               | P2-Cal.A | 7                 | 7                  | 05-Aug-18 | 11-Aug-18 | 1           | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S14059   | Accept Method Statement for Excavation and ELS of Underpass (P2 CH105-318)                 | P2-Cal.A | 21                | 21                 | 12-Aug-18 | 01-Sep-18 | 1           | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| <b>ELS of U-Troughs (P2 CH318-363)</b>                         |  |          |                   |                    |           |           |             |                     |     |                |      |     |     |     |     |  |  |  |  |
| S14060   | Prepare and Submit Method Statement for Excavation and ELS of U-Troughs (P2 CH318-363)     | P2-Cal.A | 18                | 18                 | 27-Jun-18 | 14-Jul-18 | -99         | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S14080   | 1st Review and Discuss Method Statement for Excavation and ELS of U-Troughs (P2 CH318-363) | P2-Cal.A | 21                | 21                 | 15-Jul-18 | 04-Aug-18 | -99         | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S14100   | Resubmit Method Statement for Excavation and ELS of U-Troughs (P2 CH318-363)               | P2-Cal.A | 7                 | 7                  | 05-Aug-18 | 11-Aug-18 | -99         | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S14120-01  | Accept Method Statement for Excavation and ELS of U-Troughs (P2 CH318-363)                 | P2-Cal.A | 21                | 21                 | 12-Aug-18 | 01-Sep-18 | -99         | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| <b>Construction of U-Troughs structure (P2 CH318-363)</b>      |  |          |                   |                    |           |           |             |                     |     |                |      |     |     |     |     |  |  |  |  |
| S14122   | Prepare and Submit Method Statement for Construction of U-Troughs Structure (P2 CH318-363) | P2-Cal.A | 18                | 18                 | 27-Jun-18 | 14-Jul-18 | 1369        | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S14124   | Review and Discuss Method Statement for Construction of U-Troughs Structure (P2 CH318-363) | P2-Cal.A | 21                | 21                 | 15-Jul-18 | 04-Aug-18 | 1369        | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S14126   | Resubmit Method Statement for Construction of U-Troughs Structure (P2 CH318-363)           | P2-Cal.A | 14                | 14                 | 05-Aug-18 | 18-Aug-18 | 1369        | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| S14128   | Accept Method Statement for Construction of U-Troughs Structure (P2 CH318-363)             | P2-Cal.A | 21                | 21                 | 11-Aug-18 | 08-Sep-18 | 1369        | 0%                  |     |                |      |     |     |     |     |  |  |  |  |
| <b>Treatment of Dredged Marine Sediment of Type 1</b>          |  |          |                   |                    |           |           |             |                     |     |                |      |     |     |     |     |  |  |  |  |
| Treatment of Dredged Marine Sediment of Type 1                 |  |          |                   |                    |           |           |             |                     |     |                |      |     |     |     |     |  |  |  |  |

█ Primary Baseline    █ Critical Remaining Work  
█ Actual Work    ◆ Milestone  
█ Remaining Work    ▼ Summary

NE/2015/02 Tseung Kwan O - Lam Tin Tunnel-Road P2 and Associated Works (Jun-18)

3 Monthly Rolling Programme  
(Data Date : 20-Jun-2018)

Page : 4 of 13

| Date      | Revision | Checked | Approved |
|-----------|----------|---------|----------|
| 20-Jun-18 |          |         |          |

| Activity ID   | Activity Name  | Calendar | Original Duration | Remaining Duration | Start       | Finish    | Total Float | Activity % Complete | TRA | Variance - BL1 | 2018 |     |     |     |     |  |
|---|--|----------|-------------------|--------------------|-------------|-----------|-------------|---------------------|-----|----------------|------|-----|-----|-----|-----|--|
|   |  |          |                   |                    |             |           |             |                     |     |                | Jun  | Jul | Aug | Sep | Oct |  |
| S14375-02   | Submit Method Statement for Treatment of Dredging Marine Sediment of Type 1                            | P2-Cal.A | 14                | 5                  | 11-Apr-18 A | 24-Jun-18 | -237        | 64.29%              |     | -61            |      |     |     |     |     |  |
| S14376  | Accept Method Statement for Treatment of Dredging Marine Sediment of Type 1                            | P2-Cal.A | 21                | 21                 | 25-Jun-18   | 15-Jul-18 | -237        | 0%                  |     | 0              |      |     |     |     |     |  |
| <b>Construction of Vertical Seawall</b>                               |  |          |                   |                    |             |           |             |                     |     |                |      |     |     |     |     |  |
| S14938  | Resubmit Method Statement for Construction of Vertical Seawall   | P2-Cal.A | 14                | 3                  | 12-Jun-18 A | 22-Jun-18 | -218        | 78.57%              |     | 3              |      |     |     |     |     |  |
| S14938-01   | Accept Method Statement for Construction of Vertical Seawall   | P2-Cal.A | 21                | 21                 | 23-Jun-18   | 13-Jul-18 | -218        | 0%                  |     | 0              |      |     |     |     |     |  |
| <b>Construction of Vertical Band Drain</b>                            |  |          |                   |                    |             |           |             |                     |     |                |      |     |     |     |     |  |
| S14939  | Prepare and Submit Method Statement for Construction of Vertical Band Drain                            | P2-Cal.A | 5                 | 5                  | 20-Jun-18   | 24-Jun-18 | -236        | 0%                  |     | 0              |      |     |     |     |     |  |
| S14941  | Review and Discuss Method Statement for Construction of Vertical Band Drain                            | P2-Cal.A | 21                | 21                 | 25-Jun-18   | 15-Jul-18 | -236        | 0%                  |     | 0              |      |     |     |     |     |  |
| S14945  | Resubmit Method Statement for Construction of Vertical Band Drain                                      | P2-Cal.A | 3                 | 3                  | 16-Jul-18   | 18-Jul-18 | -236        | 0%                  |     | 0              |      |     |     |     |     |  |
| S14947  | Accept Method Statement for Construction of Vertical Band Drain  | P2-Cal.A | 14                | 14                 | 19-Jul-18   | 01-Aug-18 | -236        | 0%                  |     | 0              |      |     |     |     |     |  |
| <b>Procurement of Major Material</b>                                  |  |          |                   |                    |             |           |             |                     |     |                |      |     |     |     |     |  |
| <b>Civil/Structural</b>   |  |          |                   |                    |             |           |             |                     |     |                |      |     |     |     |     |  |
| S14981  | Procurement and Delivery of Steel H-Pile   | P2-Cal.A | 800               | 329                | 31-Jan-17 A | 14-May-19 | -112        | 58.88%              |     | -34            |      |     |     |     |     |  |
| S14983  | Procurement and Delivery of ELS Walling & Struts Members   | P2-Cal.A | 1015              | 564                | 20-Jan-17 A | 04-Jan-20 | -25         | 44.43%              |     | -65            |      |     |     |     |     |  |
| S14985  | Offsite Fabrication of Pre-cast Seawall blocks   | P2-Cal.A | 40                | 16                 | 27-Mar-18 A | 05-Jul-18 | -247        | 60%                 |     | -61            |      |     |     |     |     |  |
| S14995  | Offsite Fabrication of Marine Survey Tower   | P2-Cal.A | 120               | 120                | 02-Sep-18   | 30-Dec-18 | -37         | 0%                  |     | 0              |      |     |     |     |     |  |
| <b>Subletting Package</b>   |  |          |                   |                    |             |           |             |                     |     |                |      |     |     |     |     |  |
| <b>V Panel and Precast Concrete Panel</b>                             |  |          |                   |                    |             |           |             |                     |     |                |      |     |     |     |     |  |
| S15160  | V Panel and Precast Concrete Panel Award   | P2-Cal.A | 0                 | 0                  | 24-Jun-18   | 24-Jun-18 | 151         | 0%                  |     | 0              |      |     |     |     |     |  |
| <b>Installation of Socketed H-Pile (Reclaimed Section)</b>            |  |          |                   |                    |             |           |             |                     |     |                |      |     |     |     |     |  |
| S16381  | Prepare Installation of Pre-bored Socketed H-Pile (Reclaimed Section) Tender for PM Acceptance         | P2-Cal.A | 7                 | 3                  | 16-Apr-18 A | 14-Oct-18 | -104        | 57.14%              |     | -175           |      |     |     |     |     |  |
| <b>ELS Works (Reclaimed Section)</b>                                  |  |          |                   |                    |             |           |             |                     |     |                |      |     |     |     |     |  |
| S16385  | Prepare Excavation and ELS Works (Reclaimed Section) Tender Document for PM Acceptance                 | P2-Cal.A | 7                 | 3                  | 07-Apr-18 A | 22-Jun-18 | 257         | 57.14%              |     | -70            |      |     |     |     |     |  |
| S16386  | Invitation, Submission and Opening of Tender for Excavation and ELS Works (Reclaimed Section)          | P2-Cal.A | 14                | 14                 | 23-Jun-18   | 06-Jul-18 | 257         | 0%                  |     | 0              |      |     |     |     |     |  |
| S16387  | Tender Interview and Recommendation to PM for Excavation and ELS Works (Reclaimed Section)             | P2-Cal.A | 21                | 21                 | 07-Jul-18   | 27-Jul-18 | 257         | 0%                  |     | 0              |      |     |     |     |     |  |
| S16388  | Excavation and ELS Works (Reclaimed Section) Award   | P2-Cal.A | 0                 | 0                  | 27-Jul-18   | 27-Jul-18 | 257         | 0%                  |     | 0              |      |     |     |     |     |  |
| <b>Structural Works for Retaining Wall (Reclaimed Section)</b>        |  |          |                   |                    |             |           |             |                     |     |                |      |     |     |     |     |  |
| S16390  | Invitation, Submission and Opening of Tender for Structural Works for Retaining Wall                   | P2-Cal.A | 14                | 7                  | 14-Mar-18 A | 26-Jun-18 | 349         | 50%                 |     | -91            |      |     |     |     |     |  |
| S16391  | Tender Interview and Recommendation to PM for Structural Works for Retaining Wall                      | P2-Cal.A | 21                | 21                 | 27-Jun-18   | 17-Jul-18 | 349         | 0%                  |     | 0              |      |     |     |     |     |  |
| S16392  | Structural Works for Retaining Wall Award  | P2-Cal.A | 0                 | 0                  | 17-Jul-18   | 17-Jul-18 | 349         | 0%                  |     | 0              |      |     |     |     |     |  |
| <b>Structural Works for U-Trough, Underpass and Abutment</b>          |  |          |                   |                    |             |           |             |                     |     |                |      |     |     |     |     |  |
| S16420  | Invitation, Submission and Opening of Tender for Structural Works for U-Trough, Underpass and Abutment | P2-Cal.A | 60                | 30                 | 14-Mar-18 A | 19-Jul-18 | 319         | 50%                 |     | -68            |      |     |     |     |     |  |
| S16440  | Tender Interview and Recommendation to PM for Structural Works for U-Trough, Underpass and Abutment    | P2-Cal.A | 30                | 30                 | 20-Jul-18   | 18-Aug-18 | 319         | 0%                  |     | 0              |      |     |     |     |     |  |
| S16460  | Structural Works for U-Trough, Underpass and Abutment Award  | P2-Cal.A | 0                 | 0                  | 18-Aug-18   | 18-Aug-18 | 319         | 0%                  |     | 0              |      |     |     |     |     |  |
| <b>Drainage and Sewerage Works (Existing Land) (At Grade Section)</b> |  |          |                   |                    |             |           |             |                     |     |                |      |     |     |     |     |  |
| S17104  | Submission and Opening of Tender for Drainage and Sewerage Works                                       | P2-Cal.A | 42                | 42                 | 27-Apr-17 A | 31-Jul-18 | 254         | 0%                  |     | -419           |      |     |     |     |     |  |
| S17106  | Tender Interview and Recommendation to PM for Drainage and Sewerage Works                              | P2-Cal.A | 21                | 21                 | 01-Aug-18   | 21-Aug-18 | 254         | 0%                  |     | 0              |      |     |     |     |     |  |
| S17108  | Drainage and Sewerage Works Award  | P2-Cal.A | 0                 | 0                  | 21-Aug-18   | 21-Aug-18 | 254         | 0%                  |     | 0              |      |     |     |     |     |  |
| <b>Water Works (To be Incorporated in Irrigation Package)</b>         |  |          |                   |                    |             |           |             |                     |     |                |      |     |     |     |     |  |
| S17120  | Prepare Water Works Tender Document for PM Acceptance  | P2-Cal.A | 30                | 5                  | 07-Aug-17 A | 24-Jun-18 | 254         | 83.33%              |     | -292           |      |     |     |     |     |  |
| S17140  | Submission and Opening of Tender for Water Works   | P2-Cal.A | 30                | 30                 | 25-Jun-18   | 24-Jul-18 | 353         | 0%                  |     | 0              |      |     |     |     |     |  |
| S17160  | Tender Interview and Recommendation to PM for Water Works  | P2-Cal.A | 21                | 21                 | 25-Jul-18   | 14-Aug-18 | 353         | 0%                  |     | 0              |      |     |     |     |     |  |
| S17180  | Water Works Award  | P2-Cal.A | 0                 | 0                  | 14-Aug-18   | 14-Aug-18 | 353         | 0%                  |     | 0              |      |     |     |     |     |  |


█ Primary Baseline    █ Critical Remaining Work  
█ Actual Work    ◆ Milestone  
█ Remaining Work    ▼ Summary

NE/2015/02 Tseung Kwan O - Lam Tin Tunnel-Road P2 and Associated Works (Jun-18)

3 Monthly Rolling Programme  
(Data Date : 20-Jun-2018)

Page : 5 of 13

| Date      | Revision | Checked | Approved |
|-----------|----------|---------|----------|
| 20-Jun-18 |          |         |          |



█ Primary Baseline    █ Critical Remaining Work  
█ Actual Work    ◆ Milestone  
█ Remaining Work    ▼ Summary


NE/2015/02 Tseung Kwan O - Lam Tin Tunnel-Road P2 and Associated Works (Jun-18)

3 Monthly Rolling Programme  
(Data Date : 20-Jun-2018)

Page : 6 of 13

| Date      | Revision | Checked | Approved |
|-----------|----------|---------|----------|
| 20-Jun-18 |          |         |          |





█ Primary Baseline    █ Critical Remaining Work  
█ Actual Work    ◆ Milestone  
█ Remaining Work    ▼ Summary

NE/2015/02 Tseung Kwan O - Lam Tin Tunnel-Road P2 and Associated Works (Jun-18)

3 Monthly Rolling Programme  
(Data Date : 20-Jun-2018)

Page : 7 of 13

| Date      | Revision | Checked | Approved |
|-----------|----------|---------|----------|
| 20-Jun-18 |          |         |          |

| Activity ID                          | Activity Name  | Calendar | Original Duration | Remaining Duration | Start       | Finish    | Total Float | Activity % Complete | TRA | Variance-BL1 | 2018 |     |     |     |     |  |  |  |  |
|--------------------------------------|--|----------|-------------------|--------------------|-------------|-----------|-------------|---------------------|-----|--------------|------|-----|-----|-----|-----|--|--|--|--|
|                                      |  |          |                   |                    |             |           |             |                     |     |              | Jun  | Jul | Aug | Sep | Oct |  |  |  |  |
| LC17666-01                           | Stage 9 -- Preboring for Dia. 2100 Drain Pipe (no.981-1003)(28 nos.@ 2nos./d)(CE 041)                  | P2-Cal.C | 14                | 14                 | 07-Jul-18   | 23-Jul-18 | -152        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17666-02                           | Stage 9 -- Preboring for Dia. 2100 Drain Pipe (no.854-917)(64 nos.@ 2nos./d)(CE 041)                   | P2-Cal.C | 32                | 14                 | 21-May-18 A | 06-Jul-18 | -152        | 56.25%              |     | -6           |      |     |     |     |     |  |  |  |  |
| <b>Rig 2</b>                         |  | P2-Cal.C | 52                | 21                 | 13-Apr-18 A | 14-Jul-18 | -146        |                     |     | -24          |      |     |     |     |     |  |  |  |  |
| LC17676                              | Stage 8 -- Preboring for Dia. 2100 Drain Pipe (no.1004-1128)(125nos.@ 2.4nos./d)(CE 041)               | P2-Cal.C | 52                | 21                 | 13-Apr-18 A | 14-Jul-18 | -146        | 59.62%              |     | -24          |      |     |     |     |     |  |  |  |  |
| <b>ELS</b>                           |  | P2-Cal.C | 34                | 34                 | 20-Jun-18   | 30-Jul-18 | -152        |                     |     | 0            |      |     |     |     |     |  |  |  |  |
| <b>Installation Sheet Pile - 24m</b> |  | P2-Cal.C | 34                | 34                 | 20-Jun-18   | 30-Jul-18 | -152        |                     |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17687                              | Stage 8 -- Sheet Pile installation 24m length for SMH9110 - 9109 (105 nos.@15pcs./d)                   | P2-Cal.C | 7                 | 7                  | 20-Jun-18   | 27-Jun-18 | -125        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17687-01                           | Stage 8 -- Sheet Pile installation 24m length for SMH9109 - 9108 (105 nos.@15pcs./d)                   | P2-Cal.C | 7                 | 7                  | 16-Jul-18   | 23-Jul-18 | -146        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17687-02                           | Stage 9 -- Sheet Pile installation 24m length for SMH9108 - 9107 (90 nos.@15pcs./d)                    | P2-Cal.C | 6                 | 6                  | 24-Jul-18   | 30-Jul-18 | -152        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17688                              | Stage 9 -- Sheet Pile installation 24m length for SMH9107 - 9106 (95 nos.@15pcs./d)                    | P2-Cal.C | 6                 | 6                  | 24-Jul-18   | 30-Jul-18 | -152        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| <b>Drainage works</b>                |  | P2-Cal.C | 91                | 89                 | 11-Jun-18 A | 04-Oct-18 | 90          |                     |     | -5           |      |     |     |     |     |  |  |  |  |
| <b>SMH9102-SMH9103</b>               |  | P2-Cal.C | 53                | 53                 | 20-Jul-18   | 19-Sep-18 | 101         |                     |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17689-06                           | Preboring and sheet pile installation for Dia. 900 Drain Pipe SMH9102 to SMH9103                       | P2-Cal.C | 20                | 20                 | 20-Jul-18   | 11-Aug-18 | 101         | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17689-07                           | Trench Excavation and Strut Installation for Construction of Dia. 900 Drain Pipe (SMH9102 to SMH9103)  | P2-Cal.C | 10                | 10                 | 13-Aug-18   | 23-Aug-18 | 101         | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17689-08                           | Bedding And Inspection   | P2-Cal.C | 3                 | 3                  | 24-Aug-18   | 27-Aug-18 | 101         | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17689-09                           | Manhole construction and Pipe Laying (SMH9102)   | P2-Cal.C | 20                | 20                 | 28-Aug-18   | 19-Sep-18 | 101         | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| <b>SMH9103-SMH9104</b>               |  | P2-Cal.C | 42                | 42                 | 11-Jun-18 A | 08-Aug-18 | -119        |                     |     | -7           |      |     |     |     |     |  |  |  |  |
| LC17690                              | Trench Excavation and Strut Installation for Construction of Dia. 2100 Drain Pipe (SMH9103 to SMH9104) | P2-Cal.C | 10                | 7                  | 11-Jun-18 A | 27-Jun-18 | -119        | 30%                 |     | -4           |      |     |     |     |     |  |  |  |  |
| LC17690-2                            | Bedding And Inspection   | P2-Cal.C | 3                 | 3                  | 28-Jun-18   | 30-Jun-18 | -119        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17690-3                            | Manhole construction and Pipe Laying (SMH9103 and SMH9104)   | P2-Cal.C | 20                | 20                 | 03-Jul-18   | 25-Jul-18 | -119        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17690-5                            | Inspection & Backfill  | P2-Cal.C | 14                | 14                 | 24-Jul-18   | 08-Aug-18 | -119        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| <b>SMH9104-SMH9105</b>               |  | P2-Cal.C | 43                | 41                 | 19-Jun-18 A | 07-Aug-18 | -118        |                     |     | 1            |      |     |     |     |     |  |  |  |  |
| LC17691                              | Trench Excavation and Strut Installation for Construction of Dia. 2100 Drain Pipe (SMH9104 to SMH9105) | P2-Cal.C | 10                | 10                 | 19-Jun-18 A | 30-Jun-18 | -118        | 0%                  |     | -1           |      |     |     |     |     |  |  |  |  |
| LC17691-2                            | Bedding And Inspection   | P2-Cal.C | 3                 | 3                  | 03-Jul-18   | 05-Jul-18 | -118        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17691-3                            | Manhole construction and Pipe Laying (SMH9105)   | P2-Cal.C | 16                | 16                 | 06-Jul-18   | 24-Jul-18 | -118        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17691-5                            | Inspection & Backfill  | P2-Cal.C | 14                | 14                 | 23-Jul-18   | 07-Aug-18 | -118        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| <b>SMH9105-SMH9106</b>               |  | P2-Cal.C | 41                | 41                 | 20-Jun-18   | 07-Aug-18 | -118        |                     |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17692                              | Trench Excavation and Strut Installation for Construction of Dia. 2100 Drain Pipe (SMH9105 to SMH9106) | P2-Cal.C | 10                | 10                 | 20-Jun-18   | 30-Jun-18 | -118        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17692-2                            | Bedding And Inspection   | P2-Cal.C | 3                 | 3                  | 03-Jul-18   | 05-Jul-18 | -118        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17692-3                            | Manhole construction and Pipe Laying (SMH9106)   | P2-Cal.C | 16                | 16                 | 06-Jul-18   | 24-Jul-18 | -118        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17692-5                            | Inspection & Backfill  | P2-Cal.C | 14                | 14                 | 23-Jul-18   | 07-Aug-18 | -118        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| <b>SMH9106-SMH9107</b>               |  | P2-Cal.C | 41                | 41                 | 31-Jul-18   | 15-Sep-18 | -152        |                     |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17693                              | Trench Excavation and Strut Installation for Construction of Dia. 2100 Drain Pipe (SMH9106 to SMH9107) | P2-Cal.C | 10                | 10                 | 31-Jul-18   | 10-Aug-18 | -152        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17693-2                            | Bedding And Inspection   | P2-Cal.C | 3                 | 3                  | 11-Aug-18   | 14-Aug-18 | -152        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17693-3                            | Manhole construction and Pipe Laying (SMH9107)   | P2-Cal.C | 16                | 16                 | 15-Aug-18   | 01-Sep-18 | -152        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17693-5                            | Inspection & Backfill  | P2-Cal.C | 14                | 14                 | 31-Aug-18   | 15-Sep-18 | -152        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| <b>SMH9107-SMH9108</b>               |  | P2-Cal.C | 41                | 41                 | 31-Jul-18   | 15-Sep-18 | -152        |                     |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17694                              | Trench Excavation and Strut Installation for Construction of Dia. 2100 Drain Pipe (SMH9107 to SMH9108) | P2-Cal.C | 10                | 10                 | 31-Jul-18   | 10-Aug-18 | -152        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17695                              | Bedding And Inspection   | P2-Cal.C | 3                 | 3                  | 11-Aug-18   | 14-Aug-18 | -152        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17696                              | Manhole construction and Pipe Laying (SMH9108 & 9108A)   | P2-Cal.C | 16                | 16                 | 15-Aug-18   | 01-Sep-18 | -152        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17698                              | Inspection & Backfill  | P2-Cal.C | 14                | 14                 | 31-Aug-18   | 15-Sep-18 | -152        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |
| <b>SMH9108-SMH9109</b>               |  | P2-Cal.C | 41                | 41                 | 24-Jul-18   | 08-Sep-18 | -146        |                     |     | 0            |      |     |     |     |     |  |  |  |  |
| LC17699                              | Trench Excavation and Strut Installation for Construction of Dia. 2100 Drain Pipe (SMH9108 to SMH9109) | P2-Cal.C | 10                | 10                 | 24-Jul-18   | 03-Aug-18 | -146        | 0%                  |     | 0            |      |     |     |     |     |  |  |  |  |

█ Primary Baseline    █ Critical Remaining Work  
█ Actual Work    ◆ Milestone  
█ Remaining Work    ▼ Summary

NE/2015/02 Tseung Kwan O - Lam Tin Tunnel-Road P2 and Associated Works (Jun-18)

3 Monthly Rolling Programme  
(Data Date : 20-Jun-2018)

Page : 8 of 13

| Date      | Revision | Checked | Approved |
|-----------|----------|---------|----------|
| 20-Jun-18 |          |         |          |

| Activity ID                           | Activity Name  | Calendar | Original Duration | Remaining Duration | Start       | Finish      | Total Float | Activity % Complete | TRA | Variance - BL1 | 2018 |     |     |     |     |  |  |
|---------------------------------------|--|----------|-------------------|--------------------|-------------|-------------|-------------|---------------------|-----|----------------|------|-----|-----|-----|-----|--|--|
|                                       |  |          |                   |                    |             |             |             |                     |     |                | Jun  | Jul | Aug | Sep | Oct |  |  |
| LC17701                               | Bedding And Inspection   | P2-Cal.C | 3                 | 3                  | 04-Aug-18   | 07-Aug-18   | -146        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| LC17702                               | Manhole construction and Pipe Laying (SMH9109)   | P2-Cal.C | 16                | 16                 | 08-Aug-18   | 25-Aug-18   | -146        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| LC17704                               | Inspection & Backfill  | P2-Cal.C | 14                | 14                 | 24-Aug-18   | 08-Sep-18   | -146        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| <b>SMH9109-SMH9110</b>                |  |          | P2-Cal.C          | 41                 | 41          | 28-Jun-18   | 15-Aug-18   | -125                |     | 0              |      |     |     |     |     |  |  |
| LC17705                               | Trench Excavation and Strut Installation for Construction of Dia. 2100 Drain Pipe (SMH9109-9110) | P2-Cal.C | 10                | 10                 | 28-Jun-18   | 10-Jul-18   | -125        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| LC17707                               | Bedding And Inspection   | P2-Cal.C | 3                 | 3                  | 11-Jul-18   | 13-Jul-18   | -125        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| LC17708                               | Manhole construction and Pipe Laying (SMH9110)   | P2-Cal.C | 16                | 16                 | 14-Jul-18   | 01-Aug-18   | -125        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| LC17710                               | Inspection & Backfill  | P2-Cal.C | 14                | 14                 | 31-Jul-18   | 15-Aug-18   | -125        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| <b>SMH9110-Outfall</b>                |  |          | P2-Cal.C          | 91                 | 89          | 11-Jun-18 A | 04-Oct-18   | -152                |     | -5             |      |     |     |     |     |  |  |
| LC17711                               | Fabrication of Precast Outfall   | P2-Cal.C | 21                | 14                 | 11-Jun-18 A | 06-Jul-18   | -152        | 33.33%              |     | 0              |      |     |     |     |     |  |  |
| LC17712                               | Removal of Existing Seawall and Trench Excavation  | P2-Cal.C | 21                | 21                 | 28-Jun-18   | 23-Jul-18   | -152        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| LC17713                               | Bedding And Inspection   | P2-Cal.C | 3                 | 3                  | 24-Jul-18   | 26-Jul-18   | -152        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| LC17714                               | Installation of Precast Outfall  | P2-Cal.C | 5                 | 5                  | 27-Jul-18   | 01-Aug-18   | -152        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| LC17715                               | Lay Dia. 2100 Drainage for Existing Outfalls along Existing Seawall (SMH9110- Outfall) (63m)     | P2-Cal.C | 10                | 10                 | 02-Aug-18   | 13-Aug-18   | -152        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| LC17716                               | Reinstatement of Seawall and Backfilling Works   | P2-Cal.C | 30                | 30                 | 13-Aug-18   | 15-Sep-18   | -152        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| LC17717                               | DSD Inspection and Permanent Diversion   | P2-Cal.C | 14                | 14                 | 17-Sep-18   | 04-Oct-18   | -152        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| <b>New Reclaimed Section</b>          |  |          |                   | 388                | 200         | 06-Jan-18 A | 05-Jan-19   | 48                  |     | 23             |      |     |     |     |     |  |  |
| <b>Marine Works</b>                   |  |          |                   | 388                | 200         | 06-Jan-18 A | 05-Jan-19   | 48                  |     | 23             |      |     |     |     |     |  |  |
| <b>Initial Works</b>                  |  |          | P2-Cal.C          | 66                 | 66          | 03-May-18 A | 05-Sep-18   | 19                  |     | -39            |      |     |     |     |     |  |  |
| MC10060                               | Installation of Piezometer/ O Well/ Extensometer (Type RB)                                       | P2-Cal.C | 7                 | 7                  | 13-Jul-18   | 20-Jul-18   | -166        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| MC10070                               | Baseline for Piezometer/ O Well/ Extensometer (Type RB)  | P2-Cal.C | 10                | 10                 | 21-Jul-18   | 01-Aug-18   | -166        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| MC10080                               | Installation of Type 1 Settlement Marker (Type RA/ RB)   | P2-Cal.C | 7                 | 7                  | 03-May-18 A | 01-Sep-18   | -144        | 0%                  |     | -95            |      |     |     |     |     |  |  |
| MC10120                               | Baseline for Type 1 Settlement Marker (Type RA/ RB)  | P2-Cal.C | 3                 | 3                  | 03-Sep-18   | 05-Sep-18   | -144        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| MC10156                               | Installation of Type 2 Settlement Marker (Type RA)   | P2-Cal.C | 7                 | 7                  | 20-Jun-18   | 27-Jun-18   | -175        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| MC10160                               | Baseline for Type 2 Settlement Marker (Type RA)  | P2-Cal.C | 3                 | 3                  | 28-Jun-18   | 30-Jun-18   | -175        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| MC10170                               | Installation of Type 2 Settlement Marker (Type RB)   | P2-Cal.C | 7                 | 7                  | 13-Jul-18   | 20-Jul-18   | -56         | 0%                  |     | 0              |      |     |     |     |     |  |  |
| MC10175                               | Baseline for Type 2 Settlement Marker (Type RB)  | P2-Cal.C | 3                 | 3                  | 21-Jul-18   | 24-Jul-18   | -56         | 0%                  |     | 0              |      |     |     |     |     |  |  |
| <b>Steel Cofferdam and Water Gate</b> |  |          | P2-Cal.C          | 60                 | 60          | 20-Jun-18   | 29-Aug-18   | 25                  |     | 0              |      |     |     |     |     |  |  |
| <b>Steel Cofferdam Installation</b>   |  |          | P2-Cal.C          | 60                 | 60          | 20-Jun-18   | 29-Aug-18   | 25                  |     | 0              |      |     |     |     |     |  |  |
| <b>Reinstatement works</b>            |  |          | P2-Cal.C          | 60                 | 60          | 20-Jun-18   | 29-Aug-18   | 25                  |     | 0              |      |     |     |     |     |  |  |
| <b>Type 1</b>                         |  |          | P2-Cal.C          | 60                 | 60          | 20-Jun-18   | 29-Aug-18   | 25                  |     | 0              |      |     |     |     |     |  |  |
| Removal of S/P at transition zone     |  |          | P2-Cal.C          | 60                 | 60          | 20-Jun-18   | 29-Aug-18   | 25                  |     | 0              |      |     |     |     |     |  |  |
| MC10304-02                            | Removal of Underwater S/P  | P2-Cal.C | 60                | 60                 | 20-Jun-18   | 29-Aug-18   | 25          | 0%                  |     | 0              |      |     |     |     |     |  |  |
| <b>Dredging Work</b>                  |  |          | P2-Cal.C          | 51                 | 51          | 16-Jun-18 A | 18-Aug-18   | -181                |     | -2             |      |     |     |     |     |  |  |
| MC10695                               | Dredge CH250-300 (Bottom) (6504m3)   | P2-Cal.C | 3                 | 1                  | 16-Jun-18 A | 20-Jun-18   | -197        | 66.67%              |     | 0              |      |     |     |     |     |  |  |
| MC10735                               | Dredge CH300-350 (Bottom) (6910m3)   | P2-Cal.C | 3                 | 2                  | 20-Jun-18 A | 22-Jun-18   | -187        | 33.33%              |     | 0              |      |     |     |     |     |  |  |
| MC10775                               | Dredge CH350-400 (Bottom) (7794m3)   | P2-Cal.C | 4                 | 4                  | 23-Jun-18   | 27-Jun-18   | -181        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| MC10815                               | Dredge CH400-450 (Bottom) (10120m3)  | P2-Cal.C | 5                 | 5                  | 28-Jun-18   | 04-Jul-18   | -181        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| MC10845                               | Dredge CH450-500 (Middle) (9500m3)   | P2-Cal.C | 4                 | 4                  | 05-Jul-18   | 09-Jul-18   | -181        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| MC10855                               | Dredge CH500-560 (Bottom) for treatment (23000m3)  | P2-Cal.C | 35                | 35                 | 10-Jul-18   | 18-Aug-18   | -181        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| <b>Bathymetric and Seismic Survey</b> |  |          | P2-Cal.C          | 52                 | 52          | 21-Jun-18   | 21-Aug-18   | -181                |     | 0              |      |     |     |     |     |  |  |
| MC10955                               | Survey CH270-330   | P2-Cal.C | 2                 | 2                  | 21-Jun-18   | 22-Jun-18   | -197        | 0%                  |     | 0              |      |     |     |     |     |  |  |
| MC10975                               | Survey CH330-400   | P2-Cal.C | 2                 | 2                  | 23-Jun-18   | 25-Jun-18   | -187        | 0%                  |     | 0              |      |     |     |     |     |  |  |

█ Primary Baseline    █ Critical Remaining Work  
█ Actual Work    ◆ Milestone  
█ Remaining Work     Summary

NE/2015/02 Tseung Kwan O - Lam Tin Tunnel-Road P2 and Associated Works (Jun-18)

3 Monthly Rolling Programme  
(Data Date : 20-Jun-2018)

Page : 9 of 13

| Date      | Revision | Checked | Approved |
|-----------|----------|---------|----------|
| 20-Jun-18 |          |         |          |

| Activity ID  | Activity Name   | Calendar | Original Duration | Remaining Duration | Start       | Finish    | Total Float | Activity % Complete | TRA | Variance - BL1 | 2018 |     |     |     |     |
|--|---|----------|-------------------|--------------------|-------------|-----------|-------------|---------------------|-----|----------------|------|-----|-----|-----|-----|
|  |   |          |                   |                    |             |           |             |                     |     |                | Jun  | Jul | Aug | Sep | Oct |
| MC1095   | Survey CH400-450  | P2-Cal.C | 2                 | 2                  | 28-Jun-18   | 29-Jun-18 | -178        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11015  | Survey CH450-500  | P2-Cal.C | 2                 | 2                  | 05-Jul-18   | 06-Jul-18 | -170        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11035  | Survey CH500-560  | P2-Cal.C | 2                 | 2                  | 20-Aug-18   | 21-Aug-18 | -181        | 0%                  | 0   | 0              |      |     |     |     |     |
| <b>Filling of Recycle G400 Rock at Dredged Trench</b>    |   | P2-Cal.C | 130               | 106                | 09-May-18 A | 25-Oct-18 | -199        |                     |     | -10            |      |     |     |     |     |
| MC11085  | Fill Recycle G400 at CH112-162 (12707m3) (NCE109)(EW078)                  | P2-Cal.C | 7                 | 2                  | 09-May-18 A | 21-Jun-18 | -207        | 71.43%              | 0   | -29            |      |     |     |     |     |
| MC11105  | Fill Recycle G400 at CH162-212 (20761m3) (EW078)(EW085)                   | P2-Cal.C | 10                | 3                  | 04-Jun-18 A | 25-Jun-18 | -199        | 70%                 | 0   | -8             |      |     |     |     |     |
| MC11125  | Fill Recycle G400 at CH212-262 (21729m3) (EW078)(EW085)                   | P2-Cal.C | 13                | 12                 | 16-Jun-18 A | 10-Jul-18 | -199        | 7.69%               | 0   | -6             |      |     |     |     |     |
| MC11145  | Fill Recycle G400 at CH262-312 (22016m3)                                  | P2-Cal.C | 13                | 13                 | 11-Jul-18   | 25-Jul-18 | -199        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11165  | Fill Recycle G400 at CH312-362 (22354m3)                                  | P2-Cal.C | 13                | 13                 | 26-Jul-18   | 09-Aug-18 | -199        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11185  | Fill Recycle G400 at CH362-412 (25473m3)                                  | P2-Cal.C | 12                | 12                 | 10-Aug-18   | 23-Aug-18 | -199        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11205  | Fill Recycle G400 at CH412-462 (33181m3)                                  | P2-Cal.C | 16                | 16                 | 24-Aug-18   | 11-Sep-18 | -199        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11225  | Fill Recycle G400 at CH462-512 (72995m3)                                  | P2-Cal.C | 35                | 35                 | 12-Sep-18   | 25-Oct-18 | -199        | 0%                  | 0   | 0              |      |     |     |     |     |
| <b>Construction of Seawall Foundation (Dredged Area)</b> |   | P2-Cal.C | 74                | 74                 | 20-Jun-18 A | 17-Sep-18 | -198        |                     |     | -2             |      |     |     |     |     |
| <b>Laying of Type A Rockfill (Base)</b>                  |   | P2-Cal.C | 55                | 55                 | 11-Jul-18   | 12-Sep-18 | -198        |                     |     | 0              |      |     |     |     |     |
| MC11265  | Type A Rockfill CH213-262 (797m3)   | P2-Cal.C | 1                 | 1                  | 11-Jul-18   | 11-Jul-18 | -187        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11275  | Type A Rockfill CH262-312 (952m3)   | P2-Cal.C | 2                 | 2                  | 26-Jul-18   | 27-Jul-18 | -192        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11285  | Type A Rockfill CH312-362 (860m3)   | P2-Cal.C | 1                 | 1                  | 10-Aug-18   | 10-Aug-18 | -198        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11295  | Type A Rockfill CH362-412 (917m3)   | P2-Cal.C | 1                 | 1                  | 24-Aug-18   | 24-Aug-18 | -195        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11305  | Type A Rockfill CH412-462 (1288m3)  | P2-Cal.C | 1                 | 1                  | 12-Sep-18   | 12-Sep-18 | -198        | 0%                  | 0   | 0              |      |     |     |     |     |
| <b>Laying of Geotextile Type A (Base)</b>                |   | P2-Cal.C | 72                | 72                 | 22-Jun-18   | 14-Sep-18 | -198        |                     |     | 0              |      |     |     |     |     |
| MC11335  | Geotextile Type A CH112-162 (889m2)                                       | P2-Cal.C | 1                 | 1                  | 22-Jun-18   | 22-Jun-18 | -207        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11345  | Geotextile Type A CH162-212 (915m2)                                       | P2-Cal.C | 1                 | 1                  | 26-Jun-18   | 26-Jun-18 | -180        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11355  | Geotextile Type A CH212-262 (929m2)                                       | P2-Cal.C | 1                 | 1                  | 12-Jul-18   | 12-Jul-18 | -187        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11365  | Geotextile Type A CH262-312 (1023m2)                                      | P2-Cal.C | 1                 | 1                  | 28-Jul-18   | 28-Jul-18 | -192        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11375  | Geotextile Type A CH312-362 (952m2)                                       | P2-Cal.C | 1                 | 1                  | 11-Aug-18   | 11-Aug-18 | -198        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11385  | Geotextile Type A CH362-412 (952m2)                                       | P2-Cal.C | 1                 | 1                  | 25-Aug-18   | 25-Aug-18 | -195        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11395  | Geotextile Type A CH412-462 (1122m2)                                      | P2-Cal.C | 2                 | 2                  | 13-Sep-18   | 14-Sep-18 | -198        | 0%                  | 0   | 0              |      |     |     |     |     |
| <b>Laying of Granular Filter (Base)</b>                  |   | P2-Cal.C | 73                | 74                 | 20-Jun-18 A | 17-Sep-18 | -198        |                     |     | -3             |      |     |     |     |     |
| MC11415  | Granular Filter CH75-112 (1382m3)   | P2-Cal.C | 2                 | 1                  | 20-Jun-18 A | 22-Jun-18 | -207        | 50%                 | 0   | -1             |      |     |     |     |     |
| MC11425  | Granular Filter CH112-162 (2051m3)  | P2-Cal.C | 3                 | 3                  | 23-Jun-18   | 26-Jun-18 | -207        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11435  | Granular Filter CH162-212 (2219m3)  | P2-Cal.C | 3                 | 3                  | 27-Jun-18   | 29-Jun-18 | -180        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11445  | Granular Filter CH212-262 (1665m3)  | P2-Cal.C | 2                 | 2                  | 13-Jul-18   | 14-Jul-18 | -187        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11455  | Granular Filter CH262-312 (1217m3)  | P2-Cal.C | 2                 | 2                  | 30-Jul-18   | 31-Jul-18 | -192        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11465  | Granular Filter CH312-362 (852m3)   | P2-Cal.C | 1                 | 1                  | 13-Aug-18   | 13-Aug-18 | -198        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11475  | Granular Filter CH362-412 (893m3)   | P2-Cal.C | 1                 | 1                  | 27-Aug-18   | 27-Aug-18 | -195        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC11485  | Granular Filter CH412-462 (1239m3)  | P2-Cal.C | 2                 | 2                  | 15-Sep-18   | 17-Sep-18 | -198        | 0%                  | 0   | 0              |      |     |     |     |     |
| <b>Laying Geotextile Type A (Ground Treatment)</b>       |   | P2-Cal.C | 75                | 75                 | 27-Jun-18   | 22-Sep-18 | -198        |                     |     | 0              |      |     |     |     |     |
| MC12015  | Geotextile Type A (Dredged Area) and Granular Filter CH95-162 (1292m2)    | P2-Cal.C | 3                 | 3                  | 27-Jun-18   | 29-Jun-18 | -207        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC12025  | Geotextile Type A (Dredged Area) and Granular Filter CH162-212 (1400m2)   | P2-Cal.C | 3                 | 3                  | 30-Jun-18   | 04-Jul-18 | -180        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC12035  | Geotextile Type A (Dredged Area) and Granular Filter CH212-CH262 (1796m2) | P2-Cal.C | 3                 | 3                  | 16-Jul-18   | 18-Jul-18 | -187        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC12045  | Geotextile Type A (No-Dredged Area) CH262-312 (2426m2)                    | P2-Cal.C | 4                 | 4                  | 01-Aug-18   | 04-Aug-18 | -192        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC12055  | Geotextile Type A (No-Dredged Area) CH312-362 (2606m2)                    | P2-Cal.C | 4                 | 4                  | 14-Aug-18   | 17-Aug-18 | -198        | 0%                  | 0   | 0              |      |     |     |     |     |
| MC12065  | Geotextile Type A (No-Dredged Area) CH362-412 (2566m2)                    | P2-Cal.C | 4                 | 4                  | 28-Aug-18   | 31-Aug-18 | -195        | 0%                  | 0   | 0              |      |     |     |     |     |

— Primary Baseline    ■ Critical Remaining Work  
— Actual Work    ◆ Milestone  
— Remaining Work    ▶ Summary

NE/2015/02 Tseung Kwan O - Lam Tin Tunnel-Road P2 and Associated Works (Jun-18)

3 Monthly Rolling Programme  
(Data Date : 20-Jun-2018)

Page : 10 of 13

| Date      | Revision | Checked | Approved |
|-----------|----------|---------|----------|
| 20-Jun-18 |          |         |          |



| Activity ID   | Activity Name  | Calendar | Original Duration | Remaining Duration | Start       | Finish    | Total Float | Activity % Complete | TRA | Variance - BL1 | 2018 |     |     |  |  |
|---|--|----------|-------------------|--------------------|-------------|-----------|-------------|---------------------|-----|----------------|------|-----|-----|--|--|
|   |  |          |                   |                    |             |           |             |                     |     |                | Jun  | Jul | Aug | Sep  | Oct  |
| MC11815   | Granular Filter CH115-165 (1061m3)                       | P2-Cal.C | 2                 | 2                  | 10-Aug-18   | 11-Aug-18 | -207        | 0%                  | 0   | 0              |      |     |     | ■ Granular Filter CH115-165 (1061m3)                       |  |
| MC11825   | Granular Filter CH165-215 (1112m3)                       | P2-Cal.C | 2                 | 2                  | 19-Sep-18   | 20-Sep-18 | -189        | 0%                  | 0   | 0              |      |     |     |  | ■ Granular Filter CH165-215 (1112m3)                       |
| <b>Construction of Vertical Seawall</b>                           |  | P2-Cal.C | 52                | 52                 | 14-Jul-18   | 12-Sep-18 | -189        |                     |     | 0              |      |     |     |  | Construction of Vertical Seawall                           |
| <b>Construction of Vertical Seawall (Type 2 &amp; 3)</b>          |  | P2-Cal.C | 14                | 14                 | 14-Jul-18   | 30-Jul-18 | -207        |                     |     | 0              |      |     |     |  | Construction of Vertical Seawall (Type 2 & 3)              |
| MC11905   | Installation of guidance rail for leveling stone         | P2-Cal.C | 2                 | 2                  | 14-Jul-18   | 16-Jul-18 | -207        | 0%                  | 0   | 0              |      |     |     | ■ Installation of guidance rail for leveling stone         |  |
| MC11915   | Seawall (Type 2 & 3) Laying of leveling stone Type 2 & 3 | P2-Cal.C | 3                 | 3                  | 17-Jul-18   | 19-Jul-18 | -207        | 0%                  | 0   | 0              |      |     |     | ■ Seawall (Type 2 & 3) Laying of leveling stone Type 2 & 3 |  |
| MC11925   | Seawall (Type 2 & 3) Laying of M9 (18 nos)               | P2-Cal.C | 2                 | 2                  | 20-Jul-18   | 21-Jul-18 | -207        | 0%                  | 0   | 0              |      |     |     | ■ Seawall (Type 2 & 3) Laying of M9 (18 nos)               |  |
| MC11935   | Seawall (Type 2 & 3) Laying 1st Layer (39 nos)           | P2-Cal.C | 4                 | 4                  | 23-Jul-18   | 26-Jul-18 | -207        | 0%                  | 0   | 0              |      |     |     | ■ Seawall (Type 2 & 3) Laying 1st Layer (39 nos)           |  |
| MC11945   | Seawall (Type 2 & 3) Laying 2nd Layer (32 nos)           | P2-Cal.C | 3                 | 3                  | 27-Jul-18   | 30-Jul-18 | -207        | 0%                  | 0   | 0              |      |     |     | ■ Seawall (Type 2 & 3) Laying 2nd Layer (32 nos)           |  |
| <b>Construction of Vertical Seawall (Type 1 &amp; 4)</b>          |  | P2-Cal.C | 36                | 36                 | 02-Aug-18   | 12-Sep-18 | -189        |                     |     | 0              |      |     |     |  | Construction of Vertical Seawall (Type 1 & 4)              |
| MC11955   | Installation of guidance rail for leveling stone         | P2-Cal.C | 2                 | 2                  | 02-Aug-18   | 03-Aug-18 | -189        | 0%                  | 0   | 0              |      |     |     | ■ Installation of guidance rail for leveling stone         |  |
| MC11965   | Seawall (Type 1 & 4) Laying of leveling stone Type 1 & 4 | P2-Cal.C | 5                 | 5                  | 04-Aug-18   | 09-Aug-18 | -189        | 0%                  | 0   | 0              |      |     |     | ■ Seawall (Type 1 & 4) Laying of leveling stone Type 1 & 4 |  |
| MC11975   | Seawall (Type 1 & 4) Laying of M9 (65 nos)               | P2-Cal.C | 7                 | 7                  | 10-Aug-18   | 17-Aug-18 | -189        | 0%                  | 0   | 0              |      |     |     | ■ Seawall (Type 1 & 4) Laying of M9 (65 nos)               |  |
| MC11985   | Seawall (Type 1 & 4) Laying 1st Layer (124 nos)          | P2-Cal.C | 12                | 12                 | 18-Aug-18   | 31-Aug-18 | -189        | 0%                  | 0   | 0              |      |     |     | ■ Seawall (Type 1 & 4) Laying 1st Layer (124 nos)          |  |
| MC11995   | Seawall (Type 1 & 4) Laying 2nd Layer (105 nos)          | P2-Cal.C | 10                | 10                 | 01-Sep-18   | 12-Sep-18 | -189        | 0%                  | 0   | 0              |      |     |     | ■ Seawall (Type 1 & 4) Laying 2nd Layer (105 nos)          |  |
| <b>Construction of Western Seawall Up to +1.3mPD</b>              |  | P2-Cal.C | 5                 | 5                  | 08-Sep-18   | 13-Sep-18 | -142        |                     |     | 0              |      |     |     |  | Construction of Western Seawall Up to +1.3mPD              |
| <b>Filling of G400 Rock as West Seawall Core (+1.3mPD)</b>        |  | P2-Cal.C | 2                 | 2                  | 08-Sep-18   | 10-Sep-18 | -142        |                     |     | 0              |      |     |     |  | Filling of G400 Rock as West Seawall Core (+1.3mPD)        |
| MC12495   | Fill G400 CH270-320 (4241m3)                             | P2-Cal.C | 2                 | 2                  | 08-Sep-18   | 10-Sep-18 | -142        | 0%                  | 0   | 0              |      |     |     | ■ Fill G400 CH270-320 (4241m3)                             |  |
| <b>Laying of Type A Rockfill as West Seawall Core (+1.3mPD)</b>   |  | P2-Cal.C | 1                 | 1                  | 11-Sep-18   | 11-Sep-18 | -142        |                     |     | 0              |      |     |     |  | Laying of Type A Rockfill as West Seawall Core (+1.3mPD)   |
| MC12535   | Type A Rockfill CH270-320 (511m3)                        | P2-Cal.C | 1                 | 1                  | 11-Sep-18   | 11-Sep-18 | -142        | 0%                  | 0   | 0              |      |     |     | ■ Type A Rockfill CH270-320 (511m3)                        |  |
| <b>Laying of Geotextile Type A as West Seawall Core (+1.3mPD)</b> |  | P2-Cal.C | 1                 | 1                  | 12-Sep-18   | 12-Sep-18 | -142        |                     |     | 0              |      |     |     |  | Laying of Geotextile Type A as West Seawall Core (+1.3mPD) |
| MC12575   | Geotextile Type A CH270-320 (807m2)                      | P2-Cal.C | 1                 | 1                  | 12-Sep-18   | 12-Sep-18 | -142        | 0%                  | 0   | 0              |      |     |     | ■ Geotextile Type A CH270-320 (807m2)                      |  |
| <b>Laying of Granular Filter as West Seawall Core (+1.3mPD)</b>   |  | P2-Cal.C | 1                 | 1                  | 13-Sep-18   | 13-Sep-18 | -142        |                     |     | 0              |      |     |     |  | Laying of Granular Filter as West Seawall Core (+1.3mPD)   |
| MC12615   | Granular Filter CH270-320 (533m3)                        | P2-Cal.C | 1                 | 1                  | 13-Sep-18   | 13-Sep-18 | -142        | 0%                  | 0   | 0              |      |     |     | ■ Granular Filter CH270-320 (533m3)                        |  |
| <b>Filling of Reclamation Fill to -2.0mPD</b>                     |  | P2-Cal.C | 3                 | 3                  | 13-Aug-18   | 15-Aug-18 | -207        |                     |     | 0              |      |     |     |  | Filling of Reclamation Fill to -2.0mPD                     |
| MC12665   | Reclamation Fill to -2.0mPD CH80-155 (4382m3)            | P2-Cal.C | 3                 | 3                  | 13-Aug-18   | 15-Aug-18 | -207        | 0%                  | 0   | 0              |      |     |     | ■ Reclamation Fill to -2.0mPD CH80-155 (4382m3)            |  |
| <b>Filling of Reclamation Fill -2.0 to +2.5mPD</b>                |  | P2-Cal.C | 74                | 52                 | 25-Apr-18 A | 20-Aug-18 | -207        |                     |     | -23            |      |     |     |  | Filling of Reclamation Fill -2.0 to +2.5mPD                |
| MC12883   | Reclamation Fill to +2.5mPD CH0-40 (7413m3) - Sandfill   | P2-Cal.C | 4                 | 2                  | 25-Apr-18 A | 21-Jun-18 | -192        | 50%                 | 0   | -43            |      |     |     | ■ Reclamation Fill to +2.5mPD CH0-40 (7413m3) - Sandfill   |  |
| MC12885   | Reclamation Fill to +2.5mPD CH40-80 (10195m3) - Sandfill | P2-Cal.C | 6                 | 6                  | 06-Jul-18   | 12-Jul-18 | -203        | 0%                  | 0   | 0              |      |     |     | ■ Reclamation Fill to +2.5mPD CH40-80 (10195m3) - Sandfill |  |
| MC12895   | Reclamation Fill to +2.5mPD CH80-150 (8362m3)            | P2-Cal.C | 4                 | 4                  | 16-Aug-18   | 20-Aug-18 | -207        | 0%                  | 0   | 0              |      |     |     | ■ Reclamation Fill to +2.5mPD CH80-150 (8362m3)            |  |
| <b>Filling of Compacted Fill +2.5 to +5.5mPD</b>                  |  | P2-Cal.C | 37                | 37                 | 27-Jul-18   | 07-Sep-18 | -183        |                     |     | 0              |      |     |     |  | Filling of Compacted Fill +2.5 to +5.5mPD                  |
| MC12950   | Compacted Fill to +5.5mPD CH0-40 (5773m3)                | P2-Cal.C | 6                 | 6                  | 27-Jul-18   | 02-Aug-18 | -203        | 0%                  | 0   | 0              |      |     |     | ■ Compacted Fill to +5.5mPD CH0-40 (5773m3)                |  |
| MC12955   | Compacted Fill to +5.5mPD CH40-90 (7216m3)               | P2-Cal.C | 7                 | 7                  | 25-Aug-18   | 01-Sep-18 | -207        | 0%                  | 0   | 0              |      |     |     | ■ Compacted Fill to +5.5mPD CH40-90 (7216m3)               |  |
| MC12965   | Compacted Fill to +5.5mPD CH90-140 (4468m3)              | P2-Cal.C | 5                 | 5                  | 03-Sep-18   | 07-Sep-18 | -183        | 0%                  | 0   | 0              |      |     |     | ■ Compacted Fill to +5.5mPD CH90-140 (4468m3)              |  |
| <b>Surcharge</b>  |  |          | 156               | 156                | 03-Aug-18   | 05-Jan-19 | -258        |                     |     | 0              |      |     |     |  |  |
| <b>Placing Surcharge</b>  |  | P2-Cal.C | 33                | 33                 | 03-Aug-18   | 10-Sep-18 | -183        |                     |     | 0              |      |     |     |  | Placing Surcharge  |
| MC13015   | Placing Surcharge Area 1a (CH0-30) (2990m3)              | P2-Cal.C | 3                 | 3                  | 03-Aug-18   | 06-Aug-18 | -203        | 0%                  | 0   | 0              |      |     |     | ■ Placing Surcharge Area 1a (CH0-30) (2990m3)              |  |
| MC13020   | Placing Surcharge Area 1b (CH30-86) (4852m3)             | P2-Cal.C | 5                 | 5                  | 03-Sep-18   | 07-Sep-18 | -207        | 0%                  | 0   | 0              |      |     |     | ■ Placing Surcharge Area 1b (CH30-86) (4852m3)             |  |
| MC13035   | Placing Surcharge Area 2a (CH86-135) (1173m3)            | P2-Cal.C | 2                 | 2                  | 08-Sep-18   | 10-Sep-18 | -183        | 0%                  | 0   | 0              |      |     |     | ■ Placing Surcharge Area 2a (CH86-135) (1173m3)            |  |
| <b>Surcharging</b>  |  | P2-Cal.A | 152               | 152                | 07-Aug-18   | 05-Jan-19 | -258        |                     |     | 0              |      |     |     |  |  |
| MC13155   | Surcharge Area 1a (CH0-30) (2990m3)                      | P2-Cal.A | 120               | 120                | 07-Aug-18   | 04-Dec-18 | -253        | 0%                  | 0   | 0              |      |     |     |  |  |
| MC13160   | Surcharge Area 1b (CH30-86) (4852m3)                     | P2-Cal.A | 120               | 120                | 08-Sep-18   | 05-Jan-19 | -258        | 0%                  | 0   | 0              |      |     |     |  |  |
| MC13175   | Surcharge Area 2a (CH86-135) (1173m3)                    | P2-Cal.A | 60                | 60                 | 11-Sep-18   | 09-Nov-18 | -227        | 0%                  | 0   | 0              |      |     |     |  |  |

▬ Primary Baseline    ■ Critical Remaining Work  
▬ Actual Work    ◆ Milestone  
▬ Remaining Work    ▾ Summary

NE/2015/02 Tseung Kwan O - Lam Tin Tunnel-Road P2 and Associated Works (Jun-18)

3 Monthly Rolling Programme  
(Data Date : 20-Jun-2018)

|           |          |         |          |
|-----------|----------|---------|----------|
| Date      | Revision | Checked | Approved |
| 20-Jun-18 |          |         |          |

| Activity ID   | Activity Name  | Calendar | Original Duration | Remaining Duration | Start       | Finish    | Total Float | Activity % Complete | TRA | Variance - BL1 | 2018 |     |     |     |     |
|---|--|----------|-------------------|--------------------|-------------|-----------|-------------|---------------------|-----|----------------|------|-----|-----|-----|-----|
|   |  |          |                   |                    |             |           |             |                     |     |                | Jun  | Jul | Aug | Sep | Oct |
| <b>Full-scale Treatment of Cement S/S of Marine Sediment</b>                  |  |          |                   |                    |             |           |             |                     |     |                |      |     |     |     |     |
| MC14075   | Treatment  | P2-Cal.C | 313               | 96                 | 06-Jan-18 A | 07-Nov-18 | 86          | 87.2%               |     | 65             |      |     |     |     |     |
| MC14080   | Curing, Stockpiling and Filling                                    | P2-Cal.C | 313               | 96                 | 06-Jan-18 A | 07-Nov-18 | 86          | 69.33%              |     | 65             |      |     |     |     |     |
| <b>Modification Works of Existing Seawall</b>                                 |  |          |                   |                    |             |           |             |                     |     |                |      |     |     |     |     |
| MC14145   | Excavation and Removal of existing seawall                         | P2-Cal.C | 45                | 45                 | 04-Aug-18   | 26-Sep-18 | 65          | 0%                  |     | 0              |      |     |     |     |     |
| MC14165   | Excavation down to -0.5mPD   | P2-Cal.C | 20                | 20                 | 22-Aug-18   | 13-Sep-18 | 65          | 0%                  |     | 0              |      |     |     |     |     |
| MC14185   | Installation of Guidance Rail                                      | P2-Cal.C | 4                 | 4                  | 14-Sep-18   | 18-Sep-18 | 65          | 0%                  |     | 0              |      |     |     |     |     |
| MC14205   | Installation of Leveling Stone (47nos.)                            | P2-Cal.C | 6                 | 6                  | 19-Sep-18   | 26-Sep-18 | 65          | 0%                  |     | 0              |      |     |     |     |     |
| <b>Land Works</b>   |  |          |                   |                    |             |           |             |                     |     |                |      |     |     |     |     |
| <b>Road P2 Underpass (CH105-CH318)</b>  |  |          |                   |                    |             |           |             |                     |     |                |      |     |     |     |     |
| <b>Underpass</b>  |  |          |                   |                    |             |           |             |                     |     |                |      |     |     |     |     |
| <b>Underpass P2 CH 105 - 318</b>  |  |          |                   |                    |             |           |             |                     |     |                |      |     |     |     |     |
| <b>Ground Investigation</b>   |  |          |                   |                    |             |           |             |                     |     |                |      |     |     |     |     |
| LC17780   | Pre-drilling Works (11 nos) for Area 2a1 (P2 CH160 - 202) - 4 Rigs | P2-Cal.C | 12                | 12                 | 11-Sep-18   | 24-Sep-18 | -123        | 0%                  |     | 0              |      |     |     |     |     |
| LC17784   | Pre-drilling Works (10 nos) for Area 1a (P2 CH264 - 318) - 4 Rigs  | P2-Cal.C | 12                | 12                 | 07-Aug-18   | 20-Aug-18 | -113        | 0%                  |     | 0              |      |     |     |     |     |
| LC17789   | Pre-drilling Works (27 nos) for Area 1b (P2 CH202 - 264) - 4 Rigs  | P2-Cal.C | 28                | 28                 | 08-Sep-18   | 12-Oct-18 | -137        | 0%                  |     | 0              |      |     |     |     |     |
| <b>Section 4 of the Works - Preservation and Protection of Existing Trees</b> |  |          |                   |                    |             |           |             |                     |     |                |      |     |     |     |     |
| LC25260   | Preservation and Protection of Existing Trees                      | P2-Cal.A | 1563              | 1085               | 12-Jan-17 A | 08-Jun-21 | -255        | 30.32%              |     | -46            |      |     |     |     |     |
| LC25280   | Nursery Transplanted Trees at the Contractor's holding nursery     | P2-Cal.A | 1177              | 1011               | 28-Apr-17 A | 26-Mar-21 | -181        | 14.1%               |     | -252           |      |     |     |     |     |

- Primary Baseline
- Critical Remaining Work
- █ Actual Work
- ◆ Milestone
- █ Remaining Work
- ▬ Summary

NE/2015/02 Tseung Kwan O - Lam Tin Tunnel-Road P2 and Associated Works (Jun-18)

3 Monthly Rolling Programme  
(Data Date : 20-Jun-2018)  
Page : 13 of 13

| Date      | Revision | Checked | Approved |
|-----------|----------|---------|----------|
| 20-Jun-18 |          |         |          |























NE/2015/03

| Subject: 3 Months Look Ahead Programme            |        |        |        |
|---|--------|--------|--------|
| Activities  | Jul-18 | Aug-18 | Sep-18 |
| Construction of lift shaft and sum pit            |        |        |        |
| Construction of main deck                         |        |        |        |
| Temporary works erection and bearing installation |        |        |        |

| Subject: Construction Programme (Jun, 2018) |     |     |     |     |
|---|-----|-----|-----|-----|
| Activities                                  | wk1 | wk2 | wk3 | wk4 |
| Construction of lift shaft and sum pit      |     |     |     |     |
| Construction of main deck                   |     |     |     |     |

| Activity ID  | Activity Name  | Original Duration | Start       | Finish      | June |    |    | July |    |    | August |    |    | September |    |    | October |    | November |    |    |    |
|--|--|-------------------|-------------|-------------|------|----|----|------|----|----|--------|----|----|-----------|----|----|---------|----|----------|----|----|----|
|  |  |                   |             |             | 10   | 17 | 24 | 01   | 08 | 15 | 22     | 29 | 05 | 12        | 19 | 26 | 02      | 09 | 16       | 23 | 30 | 07 |
| <b>Tseung Kwan O Lam Tin Tunnel - Tseung Kwan O Interchange and Associated Works</b> |  |                   |             |             |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| <b>Preliminary &amp; Pre-Construction Work</b>                                       |  |                   |             |             |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| <b>Pre-Construction Work</b>   |  |                   |             |             |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| <b>Site Accommodation</b>  |  |                   |             |             |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| <b>Site Accommodation (Construction Work)</b>  |  |                   |             |             |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| PRE-11790  | Maintenance CSA during Contract Period including the Furniture, Equipment, Personnel, Computer Facilities, Land Transport  | 1012              | 26-Feb-18 A | 27-Apr-21   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| PRE-11760  | Erection of Contractor's Site Accommodation (CSA) including the Furniture, Equipment, Personnel, Computer Facilities, etc. | 90                | 26-Feb-18 A | 20-Jul-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| PRE-11770  | Hoarding Erection  | 90                | 07-Mar-18 A | 04-Aug-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| PRE-11780  | Construction of Project Signboard  | 75                | 07-May-18 A | 31-Jul-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| <b>Construction Work</b>   |  |                   |             |             |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| <b>Pre-Drilling &amp; Piling Work</b>  |  |                   |             |             |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| <b>Temporary Platform erection for Pre-drilling &amp; Piling</b>                     |  |                   |             |             |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| <b>Bridge ML</b>   |  |                   |             |             |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10020  | Temporary Platform Erection & Silt Curtain Installation for Pier 1F-N & 1F-S   | 26                | 26-May-18 A | 05-Jun-18 A |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10030  | Temporary Platform Erection & Silt Curtain Installation for Pier 1G-N & 1G-S   | 5                 | 14-Jun-18 A | 20-Jun-18 A |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10040  | Temporary Platform Erection & Silt Curtain Installation for Pier 1H-N & 1H-S   | 15                | 07-Jul-18 A | 17-Jul-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10050  | Temporary Platform Erection & Silt Curtain Installation for Pier 1J-N & 1J-S   | 15                | 18-Jul-18   | 03-Aug-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10060  | Temporary Platform Erection & Silt Curtain Installation for Pier 1K-N & 1K-S   | 15                | 14-Aug-18   | 30-Aug-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| <b>Bridge S300</b>   |  |                   |             |             |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10070  | Temporary Platform Erection & Silt Curtain Installation for Pier 4A  | 8                 | 21-Jun-18 A | 23-Jun-18 A |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10080  | Temporary Platform Erection & Silt Curtain Installation for Pier 4E  | 8                 | 04-Aug-18   | 13-Aug-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10090  | Temporary Platform Erection & Silt Curtain Installation for Pier 4B  | 8                 | 29-Aug-18 A | 04-Sep-18 A |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10100  | Temporary Platform Erection & Silt Curtain Installation for Pier 4F  | 8                 | 10-Sep-18   | 18-Sep-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10110  | Temporary Platform Erection & Silt Curtain Installation for Pier 4C  | 8                 | 19-Sep-18   | 28-Sep-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10120  | Temporary Platform Erection & Silt Curtain Installation for Pier 4G  | 8                 | 29-Sep-18   | 09-Oct-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| <b>Bridge S200</b>   |  |                   |             |             |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10170  | Temporary Platform Erection & Silt Curtain Installation for Pier 2E  | 6                 | 07-Jun-18 A | 14-Jun-18 A |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10180  | Temporary Platform Erection & Silt Curtain Installation for Pier 2F  | 8                 | 25-Jun-18 A | 27-Jun-18 A |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10190  | Temporary Platform Erection & Silt Curtain Installation for Pier 2G  | 8                 | 31-Aug-18   | 08-Sep-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| <b>Pre-drilling</b>  |  |                   |             |             |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| <b>Bridge ML</b>   |  |                   |             |             |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10360  | Pre-drill 1F-N Including Plant Mobilisation and Demobilisation (2 nos./Team 4)   | 11                | 25-Jun-18 A | 14-Jul-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10350  | Pre-drill 1E-S Including Plant Mobilisation and Demobilisation (2 nos./Team 1)   | 11                | 28-May-18 A | 14-Jun-18 A |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10370  | Pre-drill 1F-S Including Plant Mobilisation and Demobilisation (2 nos./Team 3)   | 11                | 30-Jun-18 A | 16-Jul-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10340  | Pre-drill 1E-N Including Plant Mobilisation and Demobilisation (2 nos./Team 2)   | 11                | 15-Jun-18 A | 29-Jun-18 A |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10380  | Pre-drill 1G Including Plant Mobilisation and Demobilisation (2 nos./Team 1)   | 10                | 12-Jul-18   | 23-Jul-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10390  | Pre-drill 1H Including Plant Mobilisation and Demobilisation (2 nos./Team 1)   | 10                | 24-Jul-18   | 03-Aug-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10400  | Pre-drill 1J Including Plant Mobilisation and Demobilisation (2 nos./Team 3)   | 10                | 04-Aug-18   | 15-Aug-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10410  | Pre-drill 1K Including Plant Mobilisation and Demobilisation (2 nos./Team 2)   | 10                | 31-Aug-18   | 11-Sep-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| <b>Bridge S300</b>   |  |                   |             |             |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10420  | Pre-drill 4A Including Plant Mobilisation and Demobilisation (1 nos./Team 3)   | 6                 | 17-Jul-18   | 23-Jul-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10440  | Pre-drill 4B Including Plant Mobilisation and Demobilisation (2 nos./Team 4)   | 10                | 14-Aug-18   | 24-Aug-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10430  | Pre-drill 4E Including Plant Mobilisation and Demobilisation (2 nos./Team 2)   | 10                | 14-Aug-18   | 24-Aug-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10450  | Pre-drill 4F Including Plant Mobilisation and Demobilisation (2 nos./Team 3)   | 10                | 19-Sep-18   | 02-Oct-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10460  | Pre-drill 4C Including Plant Mobilisation and Demobilisation (2 nos./Team 4)   | 10                | 29-Sep-18   | 11-Oct-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| <b>Bridge S200</b>   |  |                   |             |             |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10520  | Pre-drill 2E Including Plant Mobilisation and Demobilisation (2 nos./Team 2)   | 10                | 04-Jul-18 A | 19-Jul-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10530  | Pre-drill 2F Including Plant Mobilisation and Demobilisation (2 nos./Team 4)   | 10                | 16-Jul-18   | 26-Jul-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10540  | Pre-drill 2G Including Plant Mobilisation and Demobilisation (2 nos./Team 1)   | 10                | 10-Sep-18   | 20-Sep-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| <b>Establishment of Bored Pile Machine</b>   |  |                   |             |             |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10631  | Establishment of Piling Plant for Bridge ML (1st Piling of the Bridge)   | 4                 | 27-Aug-18   | 30-Aug-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10632  | Establishment of Piling Plant for Bridge S300 (1st Piling of the Bridge)   | 4                 | 27-Aug-18   | 30-Aug-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| <b>Bored Pile Include Fabrication &amp; Delivery of Pile Cage and Casing</b>         |  |                   |             |             |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| <b>Bridge ML</b>   |  |                   |             |             |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10660  | Bored Pile 1F-N Including Plant Demobilisation (2 nos. Pile / Team 2)  | 74                | 31-Aug-18   | 28-Nov-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10670  | Bored Pile 1F-S Including Plant Demobilisation (2 nos. Pile / Team 3)  | 74                | 31-Aug-18   | 28-Nov-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10680  | Bored Pile 1G Including Plant Mobilisation and Demobilisation (2 nos. Pile / Team 1)                                       | 78                | 27-Aug-18   | 28-Nov-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| <b>Bridge S300</b>   |  |                   |             |             |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |
| CON-10720  | Bored Pile 4A Including Plant Demobilisation (1 nos. Pile / Team 4)  | 48                | 31-Aug-18   | 29-Oct-18   |      |    |    |      |    |    |        |    |    |           |    |    |         |    |          |    |    |    |

---

---

**APPENDIX R  
RECORD OF LANDFILL GAS  
MONITORING BY CONTRACTOR**


---

---


**APPENDIX R - RECORD OF LANDFILL GAS MONITORING BY THE CONTRACTOR**

| Location    | Date of Measurement | Sampling time | Weather Condition | Temperature (°C) | Methane (%) | Carbon dioxide (%) | Oxygen (%) |
|-------------|---------------------|---------------|-------------------|------------------|-------------|--------------------|------------|
| Portion III | 1-Jun-18            | 08:30         | Sunny             | 27               | 0           | 0                  | 20.9       |
|             | 1-Jun-18            | 13:03         | Sunny             | 35               | 0           | 0                  | 20.9       |
|             | 2-Jun-18            | 08:30         | Cloudy            | 27               | 0           | 0                  | 20.9       |
|             | 2-Jun-18            | 13:00         | Cloudy            | 33               | 0           | 0                  | 20.9       |
|             | 4-Jun-18            | 08:30         | Rainy             | 26               | 0           | 0                  | 20.9       |
|             | 4-Jun-18            | 13:02         | Rainy             | 31               | 0           | 0                  | 20.9       |
|             | 5-Jun-18            | 08:31         | Rainy             | 26               | 0           | 0                  | 20.9       |
|             | 5-Jun-18            | 13:00         | Rainy             | 30               | 0           | 0                  | 20.9       |
|             | 6-Jun-18            | 08:30         | Rainy             | 26               | 0           | 0                  | 20.9       |
|             | 6-Jun-18            | 13:05         | Rainy             | 29               | 0           | 0                  | 20.9       |
|             | 7-Jun-18            | 08:30         | Rainy             | 26               | 0           | 0                  | 20.9       |
|             | 7-Jun-18            | 13:02         | Rainy             | 29               | 0           | 0                  | 20.9       |
|             | 8-Jun-18            | 08:30         | Rainy             | 25               | 0           | 0                  | 20.9       |
|             | 8-Jun-18            | 13:02         | Rainy             | 30               | 0           | 0                  | 20.9       |
|             | 9-Jun-18            | 08:30         | Cloudy            | 28               | 0           | 0                  | 20.9       |
|             | 9-Jun-18            | 13:01         | Cloudy            | 30               | 0           | 0                  | 20.9       |
|             | 11-Jun-18           | 08:30         | Sunny             | 28               | 0           | 0                  | 20.9       |
|             | 11-Jun-18           | 13:02         | Sunny             | 34               | 0           | 0                  | 20.9       |
|             | 12-Jun-18           | 08:30         | Rainy             | 25               | 0           | 0                  | 20.9       |
|             | 12-Jun-18           | 13:00         | Rainy             | 30               | 0           | 0                  | 20.9       |
|             | 13-Jun-18           | 08:30         | Rainy             | 25               | 0           | 0                  | 20.9       |
|             | 13-Jun-18           | 13:00         | Rainy             | 29               | 0           | 0                  | 20.9       |
|             | 14-Jun-18           | 08:30         | Cloudy            | 25               | 0           | 0                  | 20.9       |
|             | 14-Jun-18           | 13:05         | Cloudy            | 28               | 0           | 0                  | 20.9       |
|             | 15-Jun-18           | 08:30         | Cloudy            | 25               | 0           | 0                  | 20.9       |
|             | 15-Jun-18           | 13:00         | Cloudy            | 29               | 0           | 0                  | 20.9       |
|             | 16-Jun-18           | 08:30         | Cloudy            | 26               | 0           | 0                  | 20.9       |
|             | 16-Jun-18           | 13:05         | Cloudy            | 31               | 0           | 0                  | 20.9       |
|             | 19-Jun-18           | 08:30         | Cloudy            | 28               | 0           | 0                  | 20.9       |
|             | 19-Jun-18           | 13:00         | Cloudy            | 31               | 0           | 0                  | 20.9       |
| 20-Jun-18   | 08:30               | Cloudy        | 28                | 0                | 0           | 20.9               |            |
| 20-Jun-18   | 13:03               | Cloudy        | 32                | 0                | 0           | 20.9               |            |
| 21-Jun-18   | 08:30               | Cloudy        | 28                | 0                | 0           | 20.9               |            |
| 21-Jun-18   | 13:01               | Cloudy        | 31                | 0                | 0           | 20.9               |            |
| 22-Jun-18   | 08:30               | Rainy         | 25                | 0                | 0           | 20.9               |            |
| 22-Jun-18   | 13:00               | Rainy         | 30                | 0                | 0           | 20.9               |            |
| 23-Jun-18   | 08:30               | Rainy         | 24                | 0                | 0           | 20.9               |            |
| 23-Jun-18   | 13:00               | Rainy         | 30                | 0                | 0           | 20.9               |            |
| 25-Jun-18   | 08:30               | Cloudy        | 26                | 0                | 0           | 20.9               |            |
| 25-Jun-18   | 13:00               | Cloudy        | 31                | 0                | 0           | 20.9               |            |
| 26-Jun-18   | 08:30               | Cloudy        | 25                | 0                | 0           | 20.9               |            |
| 26-Jun-18   | 13:00               | Cloudy        | 33                | 0                | 0           | 20.9               |            |
| 27-Jun-18   | 08:30               | Cloudy        | 27                | 0                | 0           | 20.9               |            |
| 27-Jun-18   | 13:04               | Cloudy        | 32                | 0                | 0           | 20.9               |            |
| 28-Jun-18   | 08:30               | Cloudy        | 27                | 0                | 0           | 20.9               |            |
| 28-Jun-18   | 13:00               | Cloudy        | 32                | 0                | 0           | 20.9               |            |
| 29-Jun-18   | 08:30               | Cloudy        | 28                | 0                | 0           | 20.9               |            |
| 29-Jun-18   | 13:02               | Cloudy        | 32                | 0                | 0           | 20.9               |            |
| 30-Jun-18   | 08:30               | Cloudy        | 28                | 0                | 0           | 20.9               |            |
| 30-Jun-18   | 13:02               | Cloudy        | 32                | 0                | 0           | 20.9               |            |


### Methane



### Carbon Dioxide



### Oxygen



|  |   |         |             |                 |
|--|---|---------|-------------|-----------------|
| Title  | Agreement No. CE 59/2015 (EP)   | Scale   | Project     | <b>CINOTECH</b> |
|  | Environmental Team for Tseung Kwan O - Lam Tin Tunnel – Design and Construction | N.T.S   | No. MA16034 |                 |
| Graphical Presentation of Landfill Gas Measurement | Date  | June 18 | Appendix R  |                 |

---

---

**APPENDIX S  
UPDATED CONSTRUCTION NOISE  
ASSESSMENT**

---

---

Our Ref: MA16034/Corres/Out/vc180608\_NMP\_Contract 2

**Civil Engineering and Development Department**  
New Territories East Development Office  
Branch 1  
Project Division (1)  
Suite 1213 Chinachem Golden Plaza,  
77 Mody Road,  
Tsim Sha Tsui East, Kowloon

By E-mail

**Attn: Mr. CHIANG Nin Tat, Eric**

8<sup>th</sup> June 2018

Dear Mr. Chiang,

**Agreement No. CE 59/2015 (EP)**  
**Environmental Team for Tseung Kwan O – Lam Tin Tunnel - Design and Construction**  
**(Environmental Permit (EP) No. EP-458/2013/C)**  
**Contract No. NE/2015/02 – Noise Mitigation Plan (Rev. 08)**


We refer to the Noise Mitigation Plan (Rev. 08) received from CRBC – Build King Joint Venture on 8<sup>th</sup> June 2018 via email.

We noted that only the plant list was updated and construction noise assessment was revised according to the updated plant list. We are pleased to inform you that we have no further comment on your plan with reference to the approved Noise Mitigation Plan in November 2017.

Should you have any queries, please contact our Ms. Vivian Choi at 2157 3881 or the undersigned at 2151 2089.

Yours faithfully,

For and on behalf of  
Cinotech Consultants Limited

  
Dr. Priscilla Choy  
Environmental Team Leader

c.c. AECOM  
ANewR  
CBJV

Mr. KY Chan  
Mr. Adi Lee  
Mr. Gary Fung

By E-mail  
By E-mail  
By E-mail

---

**NE/2015/02 - Noise Mitigation Plan Rev.8**

---

Hazel CHAN | ANewR &lt;hyychan@anewr.com&gt;

Thu, Jun 21, 2018 at 4:54 PM

To: Vivian Choi &lt;vivian.choi@cinotech.com.hk&gt;

Cc: "gary.fung@buildking.hk" <gary.fung@buildking.hk>, Nic LAM | ANewR <nhhlam@anewr.com>, "michael.lau@crbc.com.hk" <michael.lau@crbc.com.hk>, "Yeung Hon Man, Simon" <simon.hm.yeung@tko-ltt1-aecom.com>, "victor.yeung@crbc.com.hk" <victor.yeung@crbc.com.hk>, "Ng Wing Wah, Leo" <leo.ww.ng@tko-ltt1-aecom.com>, "Leung Yu Kin, Keith" <keith.yk.leung@tko-ltt1-aecom.com>, Leung Hon Chung <hc.leung@tko-ltt1-aecom.com>, "keiko.pun@crbc.com.hk" <keiko.pun@crbc.com.hk>, "Dr. Priscilla Choy" <Priscilla.Choy@cinotech.com.hk>, "ivy.tam" <ivy.tam@cinotech.com.hk>, Andy Chan <andy.chan@cinotech.com.hk>, Adi LEE | ANewR <aymlee@anewr.com>

Dear Vivian,

As the revised NMPs Rev.7 and Rev.8 submitted by the Contractor on 14 April 2018 and 8 June 2018 respectively have yet included the details of new NSR Capri, we reserve our comment and IEC verification for the NMP in these versions. For updates of plant inventory in NMPs Rev.7 and Rev.8, please be reminded that we have no comment on the plant inventory subject to RE's confirmation.

Regards,  
Hazel

On Thu, Jun 7, 2018 at 7:38 PM, Vivian Choi <vivian.choi@cinotech.com.hk> wrote:

Dear All,

Please note that EPD has some comments (extracted below) regarding the updated NMP in the Monthly EM&A Report (March 2018).

- Please state clearly in the NMP (preferably in Section 1) the reason for the update e.g. change in PME or mitigation measures, start of new works etc.
- Please state the reason for the update e.g. change in PME or mitigation measures, start of new works etc.
- It is noted that an updated Construction Noise Assessment / Noise Mitigation Plan has been inserted in this monthly report. While it forms part of the EP submission by itself, ET certification letter and **IEC verification letter** of the updated NMP are required and should be inserted in Appendix S. Please also confirm if the said NMP has been commented by our EAD colleagues

Dear Gary,

Further to EPD comments, please find our comments on the revised NMP:

1. General - For further update/ changes in the PME list, it is suggested to include a sentence saying that the construction noise assessment will be updated from time to time subject to construction work sequence and site condition.
2. General - Please incorporate the reason for any update/ changes in the NMP.
3. General - Please be reminded to strictly comply with the condition stated in the NMP Rev. 7 until the latest version is certified/ verified.

Dear IEC,

Further to EPD comment, please provide the IEC verification letter for the updated NMP for us to include in the EM&A report.

--

Best Regards,  
Vivian Choi

---

Cinotech Consultants Ltd.



SilentUp barrier at Portion IV and Portion V

According to Insertion Loss (IL) Measurement Report of Movable Noise Barrier for Drilling Rig, the noise insertion loss of the SilentUp barrier demonstrated that when a drilling rig is located 1.5m away from the sound barrier, noise level at the NSR (CM6) can be reduced by 11.7 dB(A) up to a height of 39m. For use of SilentUp barrier in Portion IV, the drill rig will be located at an angle of 45 degrees so that the distance from sound barrier will be approx. 5.1m (refer to schematic diagram in Appendix D).

For Portion V, when the drill rig is located 1.5m away from the sound barrier, noise reduction of 11.7 dB(A) can be covered up to a height of 102m of the NSR (CM6) (refer to schematic diagram in Appendix D).

Table 3.1 PME List with Proposed Mitigation Measures

| Location   | PME Type  | TM Ref. / Other Ref / BS5228 Ref | Type of Noise Mitigation Measures       | Noise Level Reduction dB(A) |
|--|---|----------------------------------|---|-----------------------------|
| <b>Portion III</b><br>(Demolition of DSD Transformer room)   | Breaker, excavator mounted (hydraulic)                | CNP 028                          | Noise Barrier                           | -5                          |
| <b>Portion IV</b><br>(Road P2 Underpass (Piling))            | Crane (62 kw)   | BS D7/114                        | Noise Barrier                           | -5                          |
|  | Drill Rig, Rotary Type (Diesel)                       | CNP 072                          | Noise Barrier (SilentUp)                | -11.7                       |
|  | Air Compressor  | CNP 002                          | Noise Barrier                           | -5                          |
|  | Excavator (73 kw)                                     | BS D8/13                         | Noise Barrier                           | -5                          |
|  | Concrete Lorry Mixer (6 m <sup>3</sup> )              | BS D6/33                         | Noise Barrier                           | -5                          |
|  | Water pump, submersible (electric)                    | CNP 283                          | Noise Barrier                           | -5                          |
|  | G. I. drilling rig                                    | BS C2/43                         | Noise Barrier                           | -5                          |
| <b>Portion IV</b><br>(Road P2 Underpass (ELS))               | Breaker, excavator mounted (hydraulic)                | CNP 028                          | Acoustic box / Noise Barrier (SilentUp) | -10 / -11.7                 |
|  | Crane (62 kw)   | BS D7/114                        | Noise Barrier                           | -5                          |
|  | Generator, Silenced, <=75 dB(A) at 7m                 | CNP102                           | Noise Barrier                           | -5                          |
|  | Piling, Vibration Hammer                              | CNP 172                          | Noise Barrier                           | -5                          |
|  | Power Pack (diesel)                                   | CNP 174                          | Noise Barrier                           | -5                          |
|  | Excavator (73 kw)                                     | BS D8/13                         | Noise Barrier                           | -5                          |
| <b>Portion IV</b><br>(Road & Drainage Works)                 | Water pump, submersible (electric)                    | CNP 283                          | Noise Barrier                           | -5                          |
|  | Excavator (73 kw)                                     | BS D8/13                         | Noise Barrier                           | -5                          |
|  | Roller, Vibratory (51 kw)                             | BS D8/30                         | Noise Barrier                           | -5                          |
|  | Concrete Lorry Mixer (6 m <sup>3</sup> )              | BS D6/33                         | Noise Barrier                           | -5                          |
|  | Light goods vehicle, gross vehicle weight < 5.5 tonne | CNP 143                          | Noise Barrier                           | -5                          |
|  | Water pump, submersible (electric)                    | CNP 283                          | Noise Barrier                           | -5                          |
|  | Dump Truck  | CNP 068                          | Noise Barrier                           | -5                          |
| <b>Portion V</b><br>(Road P2 Underpass (Piling))             | Road Roller   | CNP 185                          | Noise Barrier                           | -5                          |
|  | Drill Rig, Rotary Type (Diesel)                       | CNP 072                          | Noise Barrier                           | -5                          |
| <b>Portion V</b><br>(Road P2 Underpass (Piling))             | Breaker, excavator mounted (hydraulic)                | CNP 028                          | Acoustic box / Noise Barrier (SilentUp) | -10 / -11.7                 |
|  | Drill Rig, Rotary Type (Diesel)                       | CNP 072                          | Noise Barrier                           | -5                          |
| <b>Portion VI</b><br>(Road P2 Underpass (Piling))            | Drill Rig, Rotary Type (Diesel)                       | CNP 072                          | Noise Barrier                           | -5                          |
|  | Crane (62 kw)   | BS D7/114                        | Noise Barrier                           | -5                          |
|  | Drill Rig, Rotary Type (Diesel)                       | CNP 072                          | Noise Barrier                           | -5                          |
|  | Air Compressor  | CNP 002                          | Noise Barrier                           | -5                          |
| <b>Portion VII</b><br>(Road P2 Underpass, U Trough (Piling)) | Excavator (73 kw)                                     | BS D8/13                         | Noise Barrier                           | -5                          |

|   |   |           |   |             |
|---|---|-----------|---|-------------|
|   | Concrete Lorry Mixer (6 m <sup>3</sup> )                | BS D6/33  | Noise Barrier                           | -5          |
|   | Piling, Vibration Hammer                                | CNP 172   | Noise Barrier                           | -5          |
|   | Power pack (diesel)                                     | CNP 174   | Noise Barrier                           | -5          |
|   | Water pump, submersible (electric)                      | CNP 283   | Noise Barrier                           | -5          |
| <b>Portion VII</b><br>(Road P2 Underpass, U Trough (ELS))     | Crane (62 kw)   | BS D7/114 | Noise Barrier                           | -5          |
|   | Generator, Silenced, <=75 dB(A) at 7m                   | CNP102    | Noise Barrier                           | -5          |
|   | Breaker, excavator mounted (hydraulic)                  | CNP 028   | Acoustic box / Noise Barrier (SilentUp) | -10 / -11.7 |
|   | Piling, Vibration Hammer                                | CNP 172   | Noise Barrier                           | -5          |
|   | Power pack (diesel)                                     | CNP 174   | Noise Barrier                           | -5          |
|   | Excavator (73 kw)                                       | BS D8/13  | Noise Barrier                           | -5          |
|   | Dump Truck  | CNP 068   | Noise Barrier                           | -5          |
|   | Water pump, submersible (electric)                      | CNP 283   | Noise Barrier                           | -5          |
| <b>Portion VII</b><br>(Road & Drainage Works)                 | Excavator (73 kw)                                       | BS D8/13  | Noise Barrier                           | -5          |
|   | Roller, Vibratory (51 kw)                               | BS D8/30  | Noise Barrier                           | -5          |
|   | Concrete Lorry Mixer (6 m <sup>3</sup> )                | BS D6/33  | Noise Barrier                           | -5          |
|   | Light goods vehicle, gross vehicle weight < 5.5 tonne   | CNP 143   | Noise Barrier                           | -5          |
|   | Water pump, submersible (electric)                      | CNP 283   | Noise Barrier                           | -5          |
|   | Dump Truck  | CNP 068   | Noise Barrier                           | -5          |
|   | Road Roller   | CNP 185   | Noise Barrier                           | -5          |
| <b>Portion VIII</b><br>(Road P2 Underpass, U Trough (Piling)) | Drill Rig, Rotary Type (Diesel)                         | CNP 072   | Noise Barrier                           | -5          |
| <b>Portion VIII</b><br>(Road P2 Underpass, U Trough (ELS))    | Breaker, excavator mounted (hydraulic)                  | CNP 028   | Acoustic box / Noise Barrier (SilentUp) | -10 / -11.7 |
| <b>Portion IX</b><br>(Road P2 Underpass, U Trough (Piling))   | Drill Rig, Rotary Type (Diesel)                         | CNP 072   | Noise Barrier                           | -5          |
|   | Piling, Large Diameter Bored, Reverse Circulation Drill | CNP 166   | Noise Barrier                           | -5          |
| <b>Area A</b>   | Breaker, excavator mounted (hydraulic)                  | CNP 028   | Noise Barrier                           | -5          |

### 3.2 Proposed Mitigation Strategy and Noise Assessment Results

The air-borne construction noise impacts for the construction activities under Contract NE/2015/02 have been assessed and summarised in Table 3.2.

The detail assessment result for NE/2015/02 is presented in Appendix C. The proposed mitigation measures described above are included in the assessment and, as such only the mitigation scenario has been presented.

The predicted cumulative noise levels and the exceedances of the daytime construction noise criteria are summarised in the following Table 3.2.

From the calculation of construction noise assessment of using the SilentUp barrier at Portion IV shown that there will be no exceedance of 75 dB(A) up to 39m of the NSR (CM6). For the level of above 39m of the NSR (CM6), the calculation of construction noise assessment without using the SilentUp barrier shown that there is also no exceedance of 75 dB(A) of the NSR(CM6).

**CRBC - Build King Joint Venture**

Construction Noise Assessment

Period: 0700 to 1900 (except general holidays)

Noise Sensitive Receiver: CM6 (0-39m)

Mitigation Measures Scenario

Noise Criteria: 75dB(A)

| Portion                            | Activity                                | PME   | TM Ref. / other Ref.  | No. of plants                         | SWL       | Total SWL | On-time, % | Time Factor | Distance from Notional Sources, m | Distance Attenuation*, dB(A) | Barrier Correction, dB(A) | Façade Correction, dB(A) | Predicted Noise Level, dB(A) | Total Predicted Noise Level for each group, dB(A) |       |       |       |
|------------------------------------|---|---|---|---------------------------------------|-----------|-----------|------------|-------------|-----------------------------------|------------------------------|---------------------------|--------------------------|------------------------------|---|-------|-------|-------|
| IX                                 | U - Trough (Piling)                     | Crane (62 kw)   | BS D7/114   | 10                                    | 101       | 111       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 55.93                        | 70.39   |       |       |       |
|                                    |   | Drill Rig, Rotary Type (Diesel)                         | CNP 072   | 10                                    | 110       | 120       | 30         | -5          | 225                               | -55.10                       | -5                        | 3                        | 57.71                        |   |       |       |       |
|                                    |   | Generator, Silenced, <=75 dB(A) at 7m                   | CNP 102   | 10                                    | 100       | 110       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 54.93                        |   |       |       |       |
|                                    |   | Air Compressor  | CNP 002   | 10                                    | 102       | 112       | 30         | -5          | 225                               | -55.10                       | 0                         | 3                        | 54.71                        |   |       |       |       |
|                                    |   | Excavator (73 kw)                                       | BS D8/13  | 10                                    | 110       | 120       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 64.93                        |   |       |       |       |
|                                    |   | Concrete Lorry Mixer                                    | BS D6/33  | 10                                    | 96        | 106       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 50.93                        |   |       |       |       |
|                                    |   | Piling, Vibration Hammer                                | CNP 172   | 10                                    | 115       | 125       | 30         | -5          | 225                               | -55.10                       | 0                         | 3                        | 67.71                        |   |       |       |       |
|                                    |   | Power pack (diesel)                                     | CNP 174   | 10                                    | 100       | 110       | 30         | -5          | 225                               | -55.10                       | 0                         | 3                        | 52.71                        |   |       |       |       |
|                                    |   | Water pump, submersible (electric)                      | CNP 283   | 10                                    | 85        | 95        | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 39.93                        |   |       |       |       |
|                                    |   | Piling, large diameter bored, reverse circulation drill | CNP 166   | 3                                     | 100       | 105       | 30         | -5          | 225                               | -55.10                       | -5                        | 3                        | 42.49                        |   |       |       |       |
| IX                                 | U - Trough (ELS)                        | Crane (62 kw)   | BS D7/114   | 4                                     | 101       | 107       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 51.95                        | 67.98   |       |       |       |
|                                    |   | Generator, Silenced, <=75 dB(A) at 7m                   | CNP 102   | 8                                     | 100       | 109       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 53.96                        |   |       |       |       |
|                                    |   | Piling, Vibration Hammer                                | CNP 172   | 4                                     | 115       | 121       | 30         | -5          | 225                               | -55.10                       | 0                         | 3                        | 63.73                        |   |       |       |       |
|                                    |   | Power pack (diesel)                                     | CNP 174   | 4                                     | 100       | 106       | 30         | -5          | 225                               | -55.10                       | 0                         | 3                        | 48.73                        |   |       |       |       |
|                                    |   | Excavator (73 kw)                                       | BS D8/13  | 8                                     | 110       | 119       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 63.96                        |   |       |       |       |
|                                    |   | Dump Truck  | CNP 068   | 8                                     | 105       | 114       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 58.96                        |   |       |       |       |
|                                    |   | Water pump, submersible (electric)                      | CNP 283   | 4                                     | 85        | 91        | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 35.95                        |   |       |       |       |
|                                    |   | Derrick Barge   | CNP 061   | 2                                     | 104       | 107       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 51.94                        |   |       |       |       |
|                                    |   | Crane (62 kw)   | BS D7/114   | 2                                     | 101       | 104       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 48.94                        |   |       |       |       |
|                                    |   | Generator, Silenced, <=75 dB(A) at 7m                   | CNP 102   | 2                                     | 100       | 103       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 47.94                        |   |       |       |       |
| IX                                 | U - Trough (Structure)                  | Air Blower  | CNP 006   | 10                                    | 95        | 105       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 49.93                        | 67.59   |       |       |       |
|                                    |   | Saw, Circular Wood                                      | CNP 201   | 10                                    | 108       | 118       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 62.93                        |   |       |       |       |
|                                    |   | Concrete Lorry Mixer (6 m3)                             | BS D6/33  | 4                                     | 96        | 102       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 46.95                        |   |       |       |       |
|                                    |   | Concrete pump, stationary/lorry mounted                 | CNP 047   | 4                                     | 109       | 115       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 59.95                        |   |       |       |       |
|                                    |   | Poker, vibratory, hand-held                             | CNP 170   | 4                                     | 113       | 119       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 63.95                        |   |       |       |       |
|                                    |   | Water pump, submersible (electric)                      | CNP 283   | 12                                    | 85        | 96        | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 40.72                        |   |       |       |       |
|                                    |   | Excavator (73 kw)                                       | BS D8/13  | 1                                     | 110       | 110       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 54.93                        |   |       |       |       |
|                                    |   | Roller, Vibratory (51 kw)                               | BS D8/30  | 1                                     | 101       | 101       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 45.93                        |   |       |       |       |
|                                    |   | Concrete Lorry Mixer (6 m3)                             | BS D6/33  | 1                                     | 96        | 96        | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 40.93                        |   |       |       |       |
|                                    |   | Light goods vehicle, gross vehicle weight < 5.5 tonne   | CNP 143   | 1                                     | 101       | 101       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 45.93                        |   |       |       |       |
| IX                                 | U - Trough (Road and Drainage Works)    | Water pump, submersible (electric)                      | CNP 283   | 4                                     | 85        | 91        | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 35.95                        | 58.46   |       |       |       |
|                                    |   | Dump Truck  | CNP 068   | 1                                     | 105       | 105       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 49.93                        |   |       |       |       |
|                                    |   | Road Roller   | CNP 185   | 1                                     | 108       | 108       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 52.93                        |   |       |       |       |
|                                    |   | Crane (62 kw)   | BS D7/114   | 1                                     | 101       | 101       | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 48.77                        |   |       |       |       |
|                                    |   | Piling, large diameter bored, oscillator                | CNP 165   | 1                                     | 115       | 115       | 30         | -5          | 163                               | -52.20                       | 0                         | 3                        | 60.56                        |   |       |       |       |
|                                    |   | Excavator (73 kw)                                       | BS D8/13  | 1                                     | 110       | 110       | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 57.77                        |   |       |       |       |
|                                    |   | Water pump, submersible (electric)                      | CNP 283   | 2                                     | 85        | 88        | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 35.78                        |   |       |       |       |
|                                    |   | VI  | Road P2 Underpass, U-Trough (Removal of Existing Abandoned Box Culvert) | Crane (62 kw)                         | BS D7/114 | 1         | 101        | 101         | 50                                | -3                           | 163                       | -52.20                   | 0                            |   | 3     | 48.77 | 62.59 |
|                                    |   |   |   | Drill Rig, Rotary Type (Diesel)       | CNP 072   | 1         | 110        | 110         | 30                                | -5                           | 163                       | -52.20                   | -5                           |   | 3     | 50.56 |       |
|                                    |   |   |   | Generator, Silenced, <=75 dB(A) at 7m | CNP 102   | 1         | 100        | 100         | 50                                | -3                           | 163                       | -52.20                   | 0                            |   | 3     | 47.77 |       |
| Air Compressor                     | CNP 002                                 |   |   | 2                                     | 102       | 105       | 30         | -5          | 163                               | -52.20                       | 0                         | 3                        | 50.57                        |   |       |       |       |
| Excavator (73 kw)                  | BS D8/13                                |   |   | 1                                     | 110       | 110       | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 57.77                        |   |       |       |       |
| Concrete Lorry Mixer               | BS D6/33                                |   |   | 1                                     | 96        | 96        | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 43.77                        |   |       |       |       |
| Water pump, submersible (electric) | CNP 283                                 |   |   | 4                                     | 85        | 91        | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 38.79                        |   |       |       |       |
| VI                                 | Road P2 Underpass, U Trough (Piling)    |   |   | Dump Truck                            | CNP 068   | 1         | 105        | 105         | 50                                | -3                           | 163                       | -52.20                   | 0                            | 3   | 49.93 | 59.97 |       |
|                                    |   |   |   | Crane (62 kw)                         | BS D7/114 | 1         | 101        | 101         | 50                                | -3                           | 163                       | -52.20                   | 0                            | 3   | 48.77 |       |       |
|                                    |   |   |   | Generator, Silenced, <=75 dB(A) at 7m | CNP 102   | 1         | 100        | 100         | 50                                | -3                           | 163                       | -52.20                   | 0                            | 3   | 47.77 |       |       |
|                                    |   | Piling, Vibration Hammer                                | CNP 172   | 1                                     | 115       | 115       | 30         | -5          | 163                               | -52.20                       | 0                         | 3                        | 60.56                        |   |       |       |       |
|                                    |   | Power pack (diesel)                                     | CNP 174   | 1                                     | 100       | 100       | 30         | -5          | 163                               | -52.20                       | 0                         | 3                        | 45.56                        |   |       |       |       |
|                                    |   | Excavator (73 kw)                                       | BS D8/13  | 1                                     | 110       | 110       | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 57.77                        |   |       |       |       |
|                                    |   | Dump Truck  | CNP 068   | 1                                     | 105       | 105       | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 52.77                        |   |       |       |       |
|                                    |   | Water pump, submersible (electric)                      | CNP 283   | 4                                     | 85        | 91        | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 38.79                        |   |       |       |       |
|                                    |   | VI  | Road P2 Underpass, U Trough (ELS)                                       | Crane (62 kw)                         | BS D7/114 | 1         | 101        | 101         | 50                                | -3                           | 163                       | -52.20                   | 0                            | 3   | 48.77 |       | 63.23 |
|                                    |   |   |   | Generator, Silenced, <=75 dB(A) at 7m | CNP 102   | 1         | 100        | 100         | 50                                | -3                           | 163                       | -52.20                   | 0                            | 3   | 47.77 |       |       |
| Piling, Vibration Hammer           | CNP 172                                 |   |   | 1                                     | 115       | 115       | 30         | -5          | 163                               | -52.20                       | 0                         | 3                        | 60.56                        |   |       |       |       |
| Power pack (diesel)                | CNP 174                                 |   |   | 1                                     | 100       | 100       | 30         | -5          | 163                               | -52.20                       | 0                         | 3                        | 45.56                        |   |       |       |       |
| Excavator (73 kw)                  | BS D8/13                                |   |   | 1                                     | 110       | 110       | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 57.77                        |   |       |       |       |
| Dump Truck                         | CNP 068                                 |   |   | 1                                     | 105       | 105       | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 52.77                        |   |       |       |       |
| Water pump, submersible (electric) | CNP 283                                 |   |   | 4                                     | 85        | 91        | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 38.79                        |   |       |       |       |
| VI                                 | Road P2 Underpass, U Trough (Structure) |   |   | Crane (62 kw)                         | BS D7/114 | 2         | 101        | 104         | 50                                | -3                           | 163                       | -52.20                   | 0                            | 3   | 51.78 | 60.96 |       |
|                                    |   |   |   | Generator, Silenced, <=75 dB(A) at 7m | CNP 102   | 2         | 100        | 103         | 50                                | -3                           | 163                       | -52.20                   | 0                            | 3   | 50.78 |       |       |
|                                    |   |   |   | Air Compressor                        | CNP 002   | 2         | 102        | 105         | 50                                | -3                           | 163                       | -52.20                   | 0                            | 3   | 52.78 |       |       |
|                                    |   | Saw, Circular Wood                                      | CNP 201   | 2                                     | 108       | 111       | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 58.78                        |   |       |       |       |
|                                    |   | Concrete Lorry Mixer (6 m3)                             | BS D6/33  | 1                                     | 96        | 96        | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 43.77                        |   |       |       |       |
|                                    |   | Water pump, submersible (electric)                      | CNP 283   | 4                                     | 85        | 91        | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 38.79                        |   |       |       |       |
|                                    |   | VI  | Road and Drainage Works   | Crane (62 kw)                         | BS D7/114 | 1         | 101        | 101         | 50                                | -3                           | 163                       | -52.20                   | 0                            | 3   | 48.77 |       | 61.3  |
|                                    |   |   |   | Generator, Silenced, <=75 dB(A) at 7m | CNP 102   | 1         | 100        | 100         | 50                                | -3                           | 163                       | -52.20                   | 0                            | 3   | 47.77 |       |       |
|                                    |   |   |   | Piling, Vibration Hammer              | CNP 172   | 1         | 115        | 115         | 30                                | -5                           | 163                       | -52.20                   | 0                            | 3   | 60.56 |       |       |
|                                    |   |   |   | Power pack (diesel)                   | CNP 174   | 1         | 100        | 100         | 30                                | -5                           | 163                       | -52.20                   | 0                            | 3   | 45.56 |       |       |
| Excavator (73 kw)                  | BS D8/13                                |   |   | 1                                     | 110       | 110       | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 57.77                        |   |       |       |       |
| Dump Truck                         | CNP 068                                 |   |   | 1                                     | 105       | 105       | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 52.77                        |   |       |       |       |
| Water pump, submersible (electric) | CNP 283                                 |   |   | 4                                     | 85        | 91        | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 38.79                        |   |       |       |       |
| Excavator (73 kw)                  | BS D8/13                                |   |   | 1                                     | 110       | 110       | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 57.77                        |   |       |       |       |
| Roller, Vibratory (51 kw)          | BS D8/30                                |   |   | 1                                     | 101       | 101       | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 48.77                        |   |       |       |       |
| Concrete Lorry Mixer (6 m3)        | BS D6/33                                |   |   | 1                                     | 96        | 96        | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 43.77                        |   |       |       |       |
| VI                                 | Road and Drainage Works                 | Light goods vehicle, gross vehicle weight < 5.5 tonne   | CNP 143   | 1                                     | 101       | 101       | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 48.77                        | 61.3  |       |       |       |
|                                    |   | Water pump, submersible (electric)                      | CNP 283   | 4                                     | 85        | 91        | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 38.79                        |   |       |       |       |
|                                    |   | Dump Truck  | CNP 068   | 1                                     | 105       | 105       | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 52.77                        |   |       |       |       |
|                                    |   | Road Roller   | CNP 185   | 1                                     | 108       | 108       | 50         | -3          | 163                               | -52.20                       | 0                         | 3                        | 55.77                        |   |       |       |       |

Note: SPL = SWL + TF + DC + BC + FC, where

SPL = Predicted noise level in dB(A)

SWL = Sound Power Level in dB(A)

TF = Time factor in dB(A) = 10 log (P)

P = On-time percentage

DC = Distance attenuation correction in dB(A) = -(20 log D + 8)

D = Distance in m between the noise source and the receiver

BC = Barrier correction in dB(A)

FC = Façade correction in dB(A) = 3 dB(A)

CRBC - Build King Joint Venture

Construction Noise Assessment  
 Period: 0700 to 1900 (except general holidays)  
 Noise Sensitive Receiver: CM6 (0-39m)  
 Mitigation Measures Scenario

Noise Criteria: 75dB(A)

| Portion | Activity                                | PME  | TM Ref. / other Ref. | No. of plants | SWL | Total SWL | On-time, % | Time Factor | Distance from Notional Sources, m | Distance Attenuation*, dB(A) | Barrier Correction, dB(A) | Façade Correction, dB(A) | Predicted Noise Level, dB(A) | Total Predicted Noise Level for each group, dB(A) |
|---------|---|--|----------------------|---------------|-----|-----------|------------|-------------|-----------------------------------|------------------------------|---------------------------|--------------------------|------------------------------|---|
| I       | DSD Transformer Room                    | Generator, Silenced, <=75 dB(A) at 7m                      | CNP 102              | 1             | 100 | 100       | 50         | -3          | 213                               | -54.57                       | 0                         | 3                        | 45.42                        | 59.78   |
|         |   | Bar Bender and Cutter                                      | CNP 021              | 1             | 90  | 90        | 50         | -3          | 213                               | -54.57                       | 0                         | 3                        | 35.42                        |   |
|         |   | Breaker, hand-held, mass > 10kg < 20kg                     | CNP 024              | 1             | 108 | 108       | 50         | -3          | 213                               | -54.57                       | 0                         | 3                        | 53.42                        |   |
|         |   | Concrete Lorry Mixer (6 m3)                                | BS D6/33             | 1             | 96  | 96        | 50         | -3          | 213                               | -54.57                       | 0                         | 3                        | 41.42                        |   |
|         |   | Saw, Circular Wood   | CNP 201              | 1             | 108 | 108       | 50         | -3          | 213                               | -54.57                       | 0                         | 3                        | 53.42                        |   |
|         |   | Water pump, subsersible (electric)                         | CNP 283              | 2             | 85  | 88        | 50         | -3          | 213                               | -54.57                       | 0                         | 3                        | 33.43                        |   |
|         |   | Excavator (73 kw)  | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 213                               | -54.57                       | 0                         | 3                        | 55.42                        |   |
|         |   | Dump Truck   | CNP 068              | 1             | 105 | 105       | 50         | -3          | 213                               | -54.57                       | 0                         | 3                        | 50.42                        |   |
| IV      | Road P2 Underpass (Piling)              | Crane (62 kw)  | BS D7/114            | 3             | 101 | 106       | 50         | -3          | 47                                | -41.39                       | -5                        | 3                        | 59.37                        | 69.10   |
|         |   | Drill Rig, Rotary Type (Diesel)                            | CNP 072              | 3             | 110 | 115       | 30         | -5          | 47                                | -41.39                       | -11.7                     | 3                        | 59.46                        |   |
|         |   | Air Compressor   | CNP 002              | 6             | 102 | 110       | 30         | -5          | 47                                | -41.39                       | -5                        | 3                        | 61.17                        |   |
|         |   | Excavator (73 kw)  | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 47                                | -41.39                       | -5                        | 3                        | 63.60                        |   |
|         |   | Concrete Lorry Mixer (6 m3)                                | BS D6/33             | 1             | 96  | 96        | 50         | -3          | 47                                | -41.39                       | -5                        | 3                        | 49.60                        |   |
|         |   | Water pump, subsersible (electric)                         | CNP 283              | 4             | 85  | 91        | 50         | -3          | 47                                | -41.39                       | -5                        | 3                        | 44.62                        |   |
|         |   | G. 1. drilling rig   | BS C2/43             | 1             | 102 | 102       | 50         | -3          | 47                                | -41.39                       | -5                        | 3                        | 55.60                        |   |
|         |   | Breaker, excavator mounted (hydraulic)                     | CNP 028              | 1             | 122 | 122       | 10         | -10         | 47                                | -41.39                       | -10                       | 3                        | 63.61                        |   |
| IV      | Road P2 Underpass (ELS)                 | Crane (62 kw)  | BS D7/114            | 1             | 101 | 101       | 50         | -3          | 47                                | -41.39                       | -5                        | 3                        | 54.60                        | 70.72   |
|         |   | Generator, Silenced, <=75 dB(A) at 7m                      | CNP 102              | 1             | 100 | 100       | 50         | -3          | 47                                | -41.39                       | -5                        | 3                        | 53.60                        |   |
|         |   | Piling, Vibration Hammer                                   | CNP 172              | 2             | 115 | 118       | 30         | -5          | 47                                | -41.39                       | -5                        | 3                        | 69.39                        |   |
|         |   | Power pack (diesel)  | CNP 174              | 2             | 100 | 103       | 30         | -5          | 47                                | -41.39                       | -5                        | 3                        | 54.39                        |   |
|         |   | Excavator (73 kw)  | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 47                                | -41.39                       | -5                        | 3                        | 63.60                        |   |
|         |   | Water pump, subsersible (electric)                         | CNP 283              | 4             | 85  | 91        | 50         | -3          | 47                                | -41.39                       | -5                        | 3                        | 44.62                        |   |
| IV      | Road and Drainage Works                 | Excavator (73 kw)  | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 47                                | -41.39                       | -5                        | 3                        | 63.60                        | 67.13   |
|         |   | Roller, Vibratory (51 kw)                                  | BS D8/30             | 1             | 101 | 101       | 50         | -3          | 47                                | -41.39                       | -5                        | 3                        | 54.60                        |   |
|         |   | Concrete Lorry Mixer (6 m3)                                | BS D6/33             | 1             | 96  | 96        | 50         | -3          | 47                                | -41.39                       | -5                        | 3                        | 49.60                        |   |
|         |   | Light goods vehicle, gross vehicle weight < 5.5 tonne      | CNP 143              | 1             | 101 | 101       | 50         | -3          | 47                                | -41.39                       | -5                        | 3                        | 54.60                        |   |
|         |   | Water pump, subsersible (electric)                         | CNP 283              | 4             | 85  | 91        | 50         | -3          | 47                                | -41.39                       | -5                        | 3                        | 44.62                        |   |
|         |   | Dump Truck   | CNP 068              | 1             | 105 | 105       | 50         | -3          | 47                                | -41.39                       | -5                        | 3                        | 58.60                        |   |
|         |   | Road Roller  | CNP 185              | 1             | 108 | 108       | 50         | -3          | 47                                | -41.39                       | -5                        | 3                        | 61.60                        |   |
|         |   | Generator, Silenced, <=75 dB(A) at 7m                      | CNP 102              | 1             | 100 | 100       | 50         | -3          | 47                                | -41.39                       | -5                        | 3                        | 53.60                        |   |
| V       | Road P2 Underpass, U Trough (Piling)    | Crane (62 kw)  | BS D7/114            | 1             | 101 | 101       | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 49.73                        | 61.69   |
|         |   | Drill Rig, Rotary Type (Diesel)                            | CNP 072              | 1             | 110 | 110       | 30         | -5          | 146                               | -51.26                       | -5                        | 3                        | 51.51                        |   |
|         |   | Generator, Silenced, <=75 dB(A) at 7m                      | CNP 102              | 1             | 100 | 100       | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 48.73                        |   |
|         |   | Air Compressor   | CNP 002              | 2             | 102 | 105       | 30         | -5          | 146                               | -51.26                       | 0                         | 3                        | 51.52                        |   |
|         |   | Excavator (73 kw)  | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 58.73                        |   |
|         |   | Concrete Lorry Mixer                                       | BS D6/33             | 1             | 96  | 96        | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 44.73                        |   |
|         |   | Water pump, subsersible (electric)                         | CNP 283              | 4             | 85  | 91        | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 39.75                        |   |
|         |   | Breaker, excavator mounted (hydraulic)                     | CNP 028              | 1             | 122 | 122       | 10         | -10         | 146                               | -51.26                       | -10                       | 3                        | 53.74                        |   |
| V       | Road P2 Underpass, U Trough (ELS)       | Crane (62 kw)  | BS D7/114            | 1             | 101 | 101       | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 49.73                        | 64.19   |
|         |   | Generator, Silenced, <=75 dB(A) at 7m                      | CNP 102              | 1             | 100 | 100       | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 48.73                        |   |
|         |   | Piling, Vibration Hammer                                   | CNP 172              | 1             | 115 | 115       | 30         | -5          | 146                               | -51.26                       | 0                         | 3                        | 61.51                        |   |
|         |   | Power pack (diesel)  | CNP 174              | 1             | 100 | 100       | 30         | -5          | 146                               | -51.26                       | 0                         | 3                        | 48.51                        |   |
|         |   | Excavator (73 kw)  | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 58.73                        |   |
|         |   | Dump Truck   | CNP 068              | 1             | 105 | 105       | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 53.73                        |   |
|         |   | Water pump, subsersible (electric)                         | CNP 283              | 4             | 85  | 91        | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 39.75                        |   |
|         |   | Generator, Silenced, <=75 dB(A) at 7m                      | CNP 102              | 2             | 100 | 103       | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 51.74                        |   |
| V       | Road P2 Underpass, U Trough (Structure) | Generator, Silenced, <=75 dB(A) at 7m                      | CNP 102              | 2             | 100 | 103       | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 51.74                        | 61.65   |
|         |   | Air Compressor   | CNP 002              | 2             | 102 | 105       | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 53.74                        |   |
|         |   | Saw, Circular Wood   | CNP 201              | 2             | 108 | 111       | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 59.74                        |   |
|         |   | Concrete Lorry Mixer (6 m3)                                | BS D6/33             | 1             | 96  | 96        | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 44.73                        |   |
|         |   | Water pump, subsersible (electric)                         | CNP 283              | 4             | 85  | 91        | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 39.75                        |   |
|         |   | Excavator (73 kw)  | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 58.73                        |   |
|         |   | Roller, Vibratory (51 kw)                                  | BS D8/30             | 1             | 101 | 101       | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 49.73                        |   |
|         |   | Concrete Lorry Mixer (6 m3)                                | BS D6/33             | 1             | 96  | 96        | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 44.73                        |   |
| V       | Road and Drainage Works                 | Excavator (73 kw)  | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 58.73                        | 62.25   |
|         |   | Roller, Vibratory (51 kw)                                  | BS D8/30             | 1             | 101 | 101       | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 49.73                        |   |
|         |   | Concrete Lorry Mixer (6 m3)                                | BS D6/33             | 1             | 96  | 96        | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 44.73                        |   |
|         |   | Light goods vehicle, gross vehicle weight < 5.5 tonne      | CNP 143              | 1             | 101 | 101       | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 49.73                        |   |
|         |   | Water pump, subsersible (electric)                         | CNP 283              | 4             | 85  | 91        | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 39.75                        |   |
|         |   | Dump Truck   | CNP 068              | 1             | 105 | 105       | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 53.73                        |   |
|         |   | Road Roller  | CNP 185              | 1             | 108 | 108       | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 56.73                        |   |
|         |   | Generator, Silenced, <=75 dB(A) at 7m                      | CNP 102              | 1             | 100 | 100       | 50         | -3          | 146                               | -51.26                       | 0                         | 3                        | 48.73                        |   |
| VII     | Road P2 Underpass, U Trough (Piling)    | Crane (62 kw)  | BS D7/114            | 1             | 101 | 101       | 50         | -3          | 119                               | -49.50                       | -5                        | 3                        | 46.50                        | 58.45   |
|         |   | Drill Rig, Rotary Type (Diesel)                            | CNP 072              | 1             | 110 | 110       | 30         | -5          | 119                               | -49.50                       | -5                        | 3                        | 53.29                        |   |
|         |   | Air Compressor   | CNP 002              | 2             | 102 | 105       | 30         | -5          | 119                               | -49.50                       | -5                        | 3                        | 48.30                        |   |
|         |   | Excavator (73 kw)  | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 119                               | -49.50                       | -5                        | 3                        | 55.50                        |   |
|         |   | Concrete Lorry Mixer (6 m3)                                | BS D6/33             | 1             | 96  | 96        | 50         | -3          | 119                               | -49.50                       | -5                        | 3                        | 41.50                        |   |
|         |   | Water pump, subsersible (electric)                         | CNP 283              | 4             | 85  | 91        | 50         | -3          | 119                               | -49.50                       | -5                        | 3                        | 36.52                        |   |
|         |   | Generator, Silenced, <=75 dB(A) at 7m                      | CNP 102              | 1             | 100 | 100       | 50         | -3          | 119                               | -49.50                       | -5                        | 3                        | 45.50                        |   |
|         |   | Breaker, Excavator mounted (hydraulic)                     | CNP 028              | 1             | 122 | 122       | 10         | -10         | 119                               | -49.50                       | -10                       | 3                        | 55.51                        |   |
| VII     | Road P2 Underpass, U Trough (ELS)       | Piling, Vibration Hammer                                   | CNP 172              | 1             | 115 | 115       | 30         | -5          | 119                               | -49.50                       | -5                        | 3                        | 58.29                        | 62.05   |
|         |   | Power pack (diesel)  | CNP 174              | 1             | 100 | 100       | 30         | -5          | 119                               | -49.50                       | -5                        | 3                        | 43.29                        |   |
|         |   | Excavator (73 kw)  | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 119                               | -49.50                       | -5                        | 3                        | 55.50                        |   |
|         |   | Dump Truck   | CNP 068              | 1             | 105 | 105       | 50         | -3          | 119                               | -49.50                       | -5                        | 3                        | 50.50                        |   |
|         |   | Water pump, subsersible (electric)                         | CNP 283              | 4             | 85  | 91        | 50         | -3          | 119                               | -49.50                       | -5                        | 3                        | 36.52                        |   |
|         |   | Excavator (73 kw)  | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 119                               | -49.50                       | -5                        | 3                        | 55.50                        |   |
|         |   | Roller, Vibratory (51 kw)                                  | BS D8/30             | 1             | 101 | 101       | 50         | -3          | 119                               | -49.50                       | -5                        | 3                        | 46.50                        |   |
|         |   | Concrete Lorry Mixer (6 m3)                                | BS D6/33             | 1             | 96  | 96        | 50         | -3          | 119                               | -49.50                       | -5                        | 3                        | 41.50                        |   |
| VII     | Road and Drainage Works                 | Light goods vehicle, gross vehicle weight < 5.5 tonne      | CNP 143              | 1             | 101 | 101       | 50         | -3          | 119                               | -49.50                       | -5                        | 3                        | 46.50                        | 59.03   |
|         |   | Water pump, subsersible (electric)                         | CNP 283              | 4             | 85  | 91        | 50         | -3          | 119                               | -49.50                       | -5                        | 3                        | 36.52                        |   |
|         |   | Dump Truck   | CNP 068              | 1             | 105 | 105       | 50         | -3          | 119                               | -49.50                       | -5                        | 3                        | 50.50                        |   |
|         |   | Road Roller  | CNP 185              | 1             | 108 | 108       | 50         | -3          | 119                               | -49.50                       | -5                        | 3                        | 53.50                        |   |
|         |   | Dredger  | CNP 070              | 2             | 103 | 106       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 50.94                        |   |
|         |   | Derrick Barge  | CNP 061              | 4             | 104 | 110       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 54.95                        |   |
|         |   | Tug boat   | CNP 221              | 2             | 110 | 113       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 57.94                        |   |
|         |   | Water pump, subsersible (electric)                         | CNP 283              | 6             | 85  | 93        | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 37.71                        |   |
| IX      | Dredging and Reclamation                | Dump Truck   | CNP 068              | 6             | 105 | 113       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 57.71                        | 65.73   |
|         |   | Generator, Silenced, <=75 dB(A) at 7m                      | CNP 102              | 4             | 100 | 106       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 50.95                        |   |
|         |   | Winch (Electric)   | CNP 262              | 4             | 95  | 101       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 45.95                        |   |
|         |   | Excavator (73 kw)  | BS D8/13             | 3             | 110 | 115       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 59.70                        |   |
|         |   | Vibration Hammer   | CNP 172              | 1             | 115 | 115       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 59.93                        |   |
|         |   | Hopper barge   | -                    | 6             | -   | -         | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | -                            |   |
|         |   | Derrick Barge  | CNP 061              | 3             | 104 | 109       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 53.70                        |   |
|         |   | Tug boat   | CNP 221              | 2             | 110 | 113       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 57.94                        |   |
| IX      | Marine Ground Treatment                 | Band Drain Machine (hydraulic Vibratory lance starting up) | BS D4/107a           | 1             | 113 | 113       | 50         | -3          | 225                               | -55.10                       | 0                         | 3                        | 57.93                        | 57.93   |

Note: SPL = SWL + TF + DC + BC + FC, where

SPL = Predicted noise level in dB(A)

SWL = Sound Power Level in dB(A)

TF = Time factor in dB(A) = 10 log (P)

P = On-time percentage

DC = Distance attenuation correction in dB(A) = (-20 log D + 8)

D = Distance in m between the noise source and the receiver

BC = Barrier correction in dB(A)

FC = Façade correction in dB

**CRBC - Build King Joint Venture**

Construction Noise Assessment

Period: 0700 to 1900 (except general holidays)

Noise Sensitive Receiver: CM7

Mitigation Measures Scenario

Noise Criteria: 75dB(A)

| Portion                               | Activity  | PME   | TM Ref. / other Ref. | No. of plants         | SWL     | Total SWL | On-time, % | Time Factor | Distance from Notional Sources, m | Distance Attenuation*, dB(A) | Barrier Correction, dB(A) | Façade Correction, dB(A) | Predicted Noise Level, dB(A) | Total Predicted Noise Level for each group, dB(A) |   |
|---------------------------------------|---|---|----------------------|-----------------------|---------|-----------|------------|-------------|-----------------------------------|------------------------------|---------------------------|--------------------------|------------------------------|---|---|
| VI                                    | Road P2 Underpass, U-Trough (Removal of Existing Abandoned Box Culvert) | Crane (62 kw)   | BS D7/114            | 1                     | 101     | 101       | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 49.07                        | 60.46   |   |
|                                       |   | Piling, large diameter bored, oscillator              | CNP 165              | 1                     | 115     | 115       | 30         | -5          | 157                               | -51.92                       | -5                        | 3                        | 55.85                        |   |   |
|                                       |   | Excavator (73 kw)                                     | BS D8/13             | 1                     | 110     | 110       | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 58.07                        |   |   |
|                                       |   | Water pump, submersible (electric)                    | CNP 283              | 2                     | 85      | 88        | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 36.08                        |   |   |
| VI                                    | Road P2 Underpass, U Trough (Piling)                                    | Crane (62 kw)   | BS D7/114            | 1                     | 101     | 101       | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 49.07                        | 60.27   |   |
|                                       |   | Drill Rig, Rotary Type (Diesel)                       | CNP 072              | 1                     | 110     | 110       | 30         | -5          | 157                               | -51.92                       | -5                        | 3                        | 50.85                        |   |   |
|                                       |   | Generator, Silenced, <=75 dB(A) at 7m                 | CNP 102              | 1                     | 100     | 100       | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 48.07                        |   |   |
|                                       |   | Air Compressor  | CNP 002              | 2                     | 102     | 105       | 30         | -5          | 157                               | -51.92                       | 0                         | 3                        | 50.86                        |   |   |
|                                       |   | Excavator (73 kw)                                     | BS D8/13             | 1                     | 110     | 110       | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 58.07                        |   |   |
|                                       |   | Concrete Lorry Mixer                                  | BS D6/33             | 1                     | 96      | 96        | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 44.07                        |   |   |
|                                       |   | Water pump, submersible (electric)                    | CNP 283              | 4                     | 85      | 91        | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 39.09                        |   |   |
| VI                                    | Road P2 Underpass, U Trough (ELS)                                       | Crane (62 kw)   | BS D7/114            | 1                     | 101     | 101       | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 49.07                        | 63.53   |   |
|                                       |   | Generator, Silenced, <=75 dB(A) at 7m                 | CNP 102              | 1                     | 100     | 100       | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 48.07                        |   |   |
|                                       |   | Piling, Vibration Hammer                              | CNP 172              | 1                     | 115     | 115       | 30         | -5          | 157                               | -51.92                       | 0                         | 3                        | 60.85                        |   |   |
|                                       |   | Power pack (diesel)                                   | CNP 174              | 1                     | 100     | 100       | 30         | -5          | 157                               | -51.92                       | 0                         | 3                        | 45.85                        |   |   |
|                                       |   | Excavator (73 kw)                                     | BS D8/13             | 1                     | 110     | 110       | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 58.07                        |   |   |
|                                       |   | Dump Truck  | CNP 068              | 1                     | 105     | 105       | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 53.07                        |   |   |
|                                       |   | Water pump, submersible (electric)                    | CNP 283              | 4                     | 85      | 91        | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 39.09                        |   |   |
| VI                                    | Road P2 Underpass, U Trough (Structure)                                 | Crane (62 kw)   | BS D7/114            | 2                     | 101     | 104       | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 52.08                        | 61.26   |   |
|                                       |   | Generator, Silenced, <=75 dB(A) at 7m                 | CNP 102              | 2                     | 100     | 103       | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 51.08                        |   |   |
|                                       |   | Air Compressor  | CNP 002              | 2                     | 102     | 105       | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 53.08                        |   |   |
|                                       |   | Saw, Circular Wood                                    | CNP 201              | 2                     | 108     | 111       | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 59.08                        |   |   |
|                                       |   | Concrete Lorry Mixer (6 m3)                           | BS D6/33             | 1                     | 96      | 96        | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 44.07                        |   |   |
|                                       |   | Water pump, submersible (electric)                    | CNP 283              | 4                     | 85      | 91        | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 39.09                        |   |   |
| VI                                    | Road and Drainage Works   | Excavator (73 kw)                                     | BS D8/13             | 1                     | 110     | 110       | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 58.07                        | 61.6  |   |
|                                       |   | Roller, Vibratory (51 kw)                             | BS D8/30             | 1                     | 101     | 101       | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 49.07                        |   |   |
|                                       |   | Concrete Lorry Mixer (6 m3)                           | BS D6/33             | 1                     | 96      | 96        | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 44.07                        |   |   |
|                                       |   | Light goods vehicle, gross vehicle weight < 5.5 tonne | CNP 143              | 1                     | 101     | 101       | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 49.07                        |   |   |
|                                       |   | Water pump, submersible (electric)                    | CNP 283              | 4                     | 85      | 91        | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 39.09                        |   |   |
|                                       |   | Dump Truck  | CNP 068              | 1                     | 105     | 105       | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 53.07                        |   |   |
|                                       |   | Road Roller   | CNP 185              | 1                     | 108     | 108       | 50         | -3          | 157                               | -51.92                       | 0                         | 3                        | 56.07                        |   |   |
|                                       |   |   |                      |                       |         |           |            |             |                                   |                              |                           |                          |                              |   |   |
| VIII                                  | Road P2 Underpass, U Trough (Piling)                                    | Crane (62 kw)   | BS D7/114            | 2                     | 101     | 104       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 49.00                        | 62.95   |   |
|                                       |   | Generator, Silenced, <=75 dB(A) at 7m                 | CNP 102              | 4                     | 100     | 106       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 51.01                        |   |   |
|                                       |   | Air Compressor  | CNP 002              | 4                     | 102     | 108       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 53.01                        |   |   |
|                                       |   | Drill Rig, Rotary Type (Diesel)                       | CNP 072              | 2                     | 110     | 113       | 50         | -3          | 224                               | -55.00                       | -5                        | 3                        | 53.00                        |   |   |
|                                       |   | Excavator (73 kw)                                     | BS D8/13             | 1                     | 110     | 110       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 54.98                        |   |   |
|                                       |   | Concrete Lorry Mixer (6 m3)                           | BS D6/33             | 2                     | 96      | 99        | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 44.00                        |   |   |
|                                       |   | Piling, Vibration Hammer                              | CNP 172              | 1                     | 115     | 115       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 59.98                        |   |   |
|                                       |   | Power pack (diesel)                                   | CNP 174              | 1                     | 100     | 100       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 44.98                        |   |   |
|                                       |   | Water pump, submersible (electric)                    | CNP 283              | 2                     | 85      | 88        | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 33.00                        |   |   |
|                                       |   |   |                      |                       |         |           |            |             |                                   |                              |                           |                          |                              |   |   |
| VIII                                  | Road P2 Underpass, U Trough (ELS)                                       | Crane (62 kw)   | BS D7/114            | 2                     | 101     | 104       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 49.00                        | 66.47   |   |
|                                       |   | Generator, Silenced, <=75 dB(A) at 7m                 | CNP 102              | 4                     | 100     | 106       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 51.01                        |   |   |
|                                       |   | Air Compressor  | CNP 002              | 4                     | 102     | 108       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 53.01                        |   |   |
|                                       |   | Piling, Vibration Hammer                              | CNP 172              | 2                     | 115     | 118       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 63.00                        |   |   |
|                                       |   | Power pack (diesel)                                   | CNP 174              | 2                     | 100     | 103       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 48.00                        |   |   |
|                                       |   | Excavator (73 kw)                                     | BS D8/13             | 4                     | 110     | 116       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 61.01                        |   |   |
|                                       |   | Breaker, Excavator mounted (hydraulic)                | CNP 028              | 1                     | 122     | 122       | 50         | -3          | 224                               | -55.00                       | -10                       | 3                        | 56.98                        |   |   |
|                                       |   | Dump Truck  | CNP 068              | 2                     | 105     | 108       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 53.00                        |   |   |
|                                       |   | Water pump, submersible (electric)                    | CNP 283              | 16                    | 85      | 97        | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 42.03                        |   |   |
|                                       |   |   |                      |                       |         |           |            |             |                                   |                              |                           |                          |                              |   |   |
| VIII                                  | Road P2 Underpass, U Trough (Structure)                                 | Crane (62 kw)   | BS D7/114            | 2                     | 101     | 104       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 49.00                        | 58  |   |
|                                       |   | Generator, Silenced, <=75 dB(A) at 7m                 | CNP 102              | 2                     | 100     | 103       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 48.00                        |   |   |
|                                       |   | Air Compressor  | CNP 002              | 1                     | 102     | 102       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 46.98                        |   |   |
|                                       |   | Saw, Circular Wood                                    | CNP 201              | 2                     | 108     | 111       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 56.00                        |   |   |
|                                       |   | Concrete Lorry Mixer (6 m3)                           | BS D6/33             | 2                     | 96      | 99        | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 44.00                        |   |   |
|                                       |   | Water pump, submersible (electric)                    | CNP 283              | 16                    | 85      | 97        | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 42.03                        |   |   |
| VIII                                  | Road and Drainage Works   | Excavator (73 kw)                                     | BS D8/13             | 2                     | 110     | 113       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 58.00                        | 61.66   |   |
|                                       |   | Roller, Vibratory (51 kw)                             | BS D8/30             | 2                     | 101     | 104       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 49.00                        |   |   |
|                                       |   | Saw, Circular Wood                                    | CNP 201              | 2                     | 108     | 111       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 56.00                        |   |   |
|                                       |   | Asphalt Paver   | BS D8/24             | 1                     | 101     | 101       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 45.98                        |   |   |
|                                       |   | Dump Truck  | CNP 068              | 2                     | 105     | 108       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 53.00                        |   |   |
|                                       |   | Lorry   | BS D8/25             | 2                     | 96      | 99        | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 44.00                        |   |   |
|                                       |   | Crane (62 kw)   | BS D7/114            | 2                     | 101     | 104       | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 49.00                        |   |   |
|                                       |   | Water pump, submersible (electric)                    | CNP 283              | 16                    | 85      | 97        | 50         | -3          | 224                               | -55.00                       | 0                         | 3                        | 42.03                        |   |   |
|                                       |   |   |                      |                       |         |           |            |             |                                   |                              |                           |                          |                              |   |   |
|                                       |   | Area Y  |                      | Bar Bender and Cutter | CNP 021 | 4         | 90         | 96          | 50                                | -3                           | 180                       | -53.11                   | 0                            |   | 3 |
| Generator, Silenced, <=75 dB(A) at 7m | CNP 102   |   |                      | 2                     | 100     | 103       | 50         | -3          | 180                               | -53.11                       | 0                         | 3                        | 49.89                        |   |   |
| Water pump, submersible (electric)    | CNP 283   |   |                      | 4                     | 85      | 91        | 50         | -3          | 180                               | -53.11                       | 0                         | 3                        | 37.90                        |   |   |

Note: SPL = SWL + TF + DC + BC + FC, where

SPL = Predicted noise level in dB(A)

SWL = Sound Power Level in dB(A)

TF = Time factor in dB(A) = 10 log (P)

P = On-time percentage

DC = Distance attenuation correction in dB(A) = -(20 log D + 8)

D = Distance in m between the noise source and the receiver

BC = Barrier correction in dB(A)

FC = Façade correction in dB(A) = 3 dB(A)

**CRBC - Build King Joint Venture**

Construction Noise Assessment

Period: 0700 to 1900 (except general holidays)

Noise Sensitive Receiver: CM8

Noise Criteria: 75dB(A)

| Portion                             | Activity   | PME                                    | TM Ref. / other Ref. | No. of plants | SWL | Total SWL | On-time, % | Time Factor | Distance from Notional Sources, m | Distance Attenuation*, dB(A) | Barrier Correction, dB(A) | Façade Correction, dB(A) | Predicted Noise Level, dB(A) | Total Predicted Noise Level for each group, dB(A) | Total Predicted Noise Level Portion II dB(A) |
|-------------------------------------|--|--|----------------------|---------------|-----|-----------|------------|-------------|-----------------------------------|------------------------------|---------------------------|--------------------------|------------------------------|---|--|
| III                                 | Demolition of DSD Transformer Room   | Breaker, Excavator mounted (hydraulic) | CNP 028              | 1             | 122 | 122       | 50         | -3          | 116                               | -49.29                       | -5                        | 3                        | 67.70                        | 68.52   | 68.52  |
|                                     |  | Excavator (73 kw)                      | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 116                               | -49.29                       | 0                         | 3                        | 60.70                        |   |  |
|                                     |  | Lorry                                  | BS D8/25             | 1             | 96  | 96        | 50         | -3          | 116                               | -49.29                       | 0                         | 3                        | 46.70                        |   |  |
|                                     |  | Water pump, subersible (electric)      | CNP 283              | 2             | 85  | 88        | 50         | -3          | 116                               | -49.29                       | 0                         | 3                        | 38.71                        |   |  |
| II                                  | Retaining Wall   | Excavator (73 kw)                      | BS D8/13             | 2             | 110 | 113       | 50         | -3          | 257                               | -56.20                       | 0                         | 3                        | 56.80                        | 61.18   | 61.18  |
|                                     |  | Dump Truck                             | CNP 068              | 2             | 105 | 108       | 50         | -3          | 257                               | -56.20                       | 0                         | 3                        | 51.80                        |   |  |
|                                     |  | Saw, Circular Wood                     | CNP 201              | 4             | 108 | 114       | 50         | -3          | 257                               | -56.20                       | 0                         | 3                        | 57.81                        |   |  |
|                                     |  | Bar Bender and Cutter                  | CNP 021              | 4             | 90  | 96        | 50         | -3          | 257                               | -56.20                       | 0                         | 3                        | 39.81                        |   |  |
|                                     |  | Lorry                                  | BS D8/25             | 2             | 96  | 99        | 50         | -3          | 257                               | -56.20                       | 0                         | 3                        | 42.80                        |   |  |
|                                     |  | Water pump, subersible (electric)      | CNP 283              | 2             | 85  | 88        | 50         | -3          | 257                               | -56.20                       | 0                         | 3                        | 31.80                        |   |  |
|                                     |  | Concrete Lorry Mixer (6 m3)            | BS D6/33             | 2             | 96  | 99        | 50         | -3          | 257                               | -56.20                       | 0                         | 3                        | 42.80                        |   |  |
|                                     |  | Roller, Vibratory (51 kw)              | BS D8/30             | 1             | 101 | 101       | 50         | -3          | 257                               | -56.20                       | 0                         | 3                        | 44.79                        |   |  |
| Area A                              |  | Breaker, Excavator mounted (hydraulic) | CNP 028              | 1             | 122 | 122       | 50         | -3          | 217                               | -54.73                       | -5                        | 3                        | 62.26                        | 66.48   | 66.48  |
|                                     |  | Excavator (73 kw)                      | BS D8/13             | 6             | 110 | 118       | 50         | -3          | 217                               | -54.73                       | 0                         | 3                        | 63.04                        |   |  |
|                                     |  | Dump Truck                             | CNP 068              | 7             | 105 | 113       | 50         | -3          | 217                               | -54.73                       | 0                         | 3                        | 58.71                        |   |  |
|                                     |  | Water pump, subersible (electric)      | CNP 283              | 3             | 85  | 90        | 50         | -3          | 217                               | -54.73                       | 0                         | 3                        | 35.03                        |   |  |
| Construction of Northern Footbridge | Pre-drilling works (Near Tiu Keng Leng Sports Centre) Feb 17 to Mar, 17          | Drill Rig                              | CNP 072              | 1             | 110 | 110       | 20         | -7          | 60                                | -43.56                       | -5                        | 3                        | 57.45                        | 69.71   | 69.71  |
|                                     |  | Breaker, excavator mounted (hydraulic) | CNP 028              | 1             | 122 | 122       | 20         | -7          | 60                                | -43.56                       | -5                        | 3                        | 69.45                        |   |  |
| Construction of Northern Footbridge | Construction of soldier wall (Near Tiu Keng Leng Sports Centre) Apr 17 to Oct 17 | Air Compressor                         | CNP 002              | 1             | 102 | 102       | 20         | -7          | 60                                | -43.56                       | -5                        | 3                        | 49.45                        | 66.35   |  |
|                                     |  | Crane                                  | BS D7/114            | 1             | 101 | 101       | 20         | -7          | 60                                | -43.56                       | 0                         | 3                        | 53.45                        |   |  |
|                                     |  | Generator, Silenced, <=75 dB(A) at 7m  | CNP 102              | 1             | 100 | 100       | 40         | -4          | 60                                | -43.56                       | 0                         | 3                        | 55.46                        |   |  |
|                                     |  | Concrete Lorry Mixer                   | BS D6/33             | 2             | 96  | 99        | 20         | -7          | 60                                | -43.56                       | 0                         | 3                        | 51.46                        |   |  |
|                                     |  | Piling, Vibration Hammer               | CNP 172              | 1             | 115 | 115       | 20         | -7          | 60                                | -43.56                       | -5                        | 3                        | 62.45                        |   |  |
|                                     |  | Water Pump, Submersible (electric)     | CNP 283              | 1             | 85  | 85        | 10         | -10         | 60                                | -43.56                       | 0                         | 3                        | 34.44                        |   |  |
| Construction of Northern Footbridge | Pre-drilling & Piling works (Near Park Central Block 6) Aug 17 to Oct, 17        | Drill Rig                              | CNP 072              | 1             | 110 | 110       | 30         | -5          | 93                                | -47.37                       | -5                        | 3                        | 55.40                        | 68.83   | 70.78  |
|                                     |  | Breaker, excavator mounted (hydraulic) | CNP 028              | 1             | 122 | 122       | 30         | -5          | 93                                | -47.37                       | -5                        | 3                        | 67.40                        |   |  |
|                                     |  | Air Compressor                         | CNP 002              | 1             | 102 | 102       | 20         | -7          | 93                                | -47.37                       | -5                        | 3                        | 45.64                        |   |  |
|                                     |  | Crane                                  | BS D7/114            | 1             | 101 | 101       | 20         | -7          | 93                                | -47.37                       | 0                         | 3                        | 49.64                        |   |  |
|                                     |  | Generator, Silenced, <=75 dB(A) at 7m  | CNP 102              | 1             | 100 | 100       | 40         | -4          | 93                                | -47.37                       | 0                         | 3                        | 51.65                        |   |  |
|                                     |  | Concrete Lorry Mixer                   | BS D6/33             | 2             | 96  | 99        | 20         | -7          | 93                                | -47.37                       | 0                         | 3                        | 47.65                        |   |  |
|                                     |  | Piling, Vibration Hammer               | CNP 172              | 1             | 115 | 115       | 20         | -7          | 93                                | -47.37                       | -5                        | 3                        | 58.64                        |   |  |
|                                     |  | Water Pump, Submersible (electric)     | CNP 283              | 1             | 85  | 85        | 10         | -10         | 93                                | -47.37                       | 0                         | 3                        | 30.63                        |   |  |
| Construction of Northern Footbridge | Construction of Footbridge (Near Park Central Block 6) Nov 17 to Apr 19          | Excavator                              | BS D8/13             | 1             | 110 | 110       | 20         | -7          | 93                                | -47.37                       | 0                         | 3                        | 58.64                        | 67.79   |  |
|                                     |  | Crane                                  | BS D7/114            | 1             | 101 | 101       | 40         | -4          | 60                                | -43.56                       | 0                         | 3                        | 56.46                        |   |  |
|                                     |  | Dump Truck                             | BS D8/25             | 1             | 105 | 105       | 20         | -7          | 60                                | -43.56                       | 0                         | 3                        | 57.45                        |   |  |
|                                     |  | Generator, Silenced, <=75 dB(A) at 7m  | CNP 102              | 1             | 100 | 100       | 70         | -2          | 60                                | -43.56                       | 0                         | 3                        | 57.89                        |   |  |
|                                     |  | Concrete Lorry Mixer                   | BS D6/33             | 2             | 96  | 99        | 30         | -5          | 60                                | -43.56                       | 0                         | 3                        | 53.22                        |   |  |
|                                     |  | Saw, Circular Wood                     | CNP 201              | 4             | 108 | 114       | 60         | -2          | 60                                | -43.56                       | -5                        | 3                        | 66.22                        |   |  |
| Construction of Northern Footbridge | Construction of Footbridge (Near Tiu Keng Leng Sports Centre) Nov 17 to Apr 19   | Water Pump, Submersible (electric)     | CNP 283              | 1             | 85  | 85        | 20         | -7          | 60                                | -43.56                       | 0                         | 3                        | 37.45                        | 63.99   | 69.30  |
|                                     |  | Crane                                  | BS D7/114            | 1             | 101 | 101       | 40         | -4          | 93                                | -47.37                       | 0                         | 3                        | 52.65                        |   |  |
|                                     |  | Dump Truck                             | BS D8/25             | 1             | 105 | 105       | 20         | -7          | 93                                | -47.37                       | 0                         | 3                        | 53.64                        |   |  |
|                                     |  | Generator, Silenced, <=75 dB(A) at 7m  | CNP 102              | 1             | 100 | 100       | 70         | -2          | 93                                | -47.37                       | 0                         | 3                        | 54.08                        |   |  |
|                                     |  | Concrete Lorry Mixer                   | BS D6/33             | 2             | 96  | 99        | 30         | -5          | 93                                | -47.37                       | 0                         | 3                        | 49.41                        |   |  |
|                                     |  | Saw, Circular Wood                     | CNP 201              | 4             | 108 | 114       | 60         | -2          | 93                                | -47.37                       | -5                        | 3                        | 62.41                        |   |  |
|                                     |  | Water Pump, Submersible (electric)     | CNP 283              | 1             | 85  | 85        | 20         | -7          | 93                                | -47.37                       | 0                         | 3                        | 33.64                        |   |  |

Note: SPL = SWL + TF + DC + BC + FC, where

SPL = Predicted noise level in dB(A)

SWL = Sound Power Level in dB(A)

TF = Time factor in dB(A) = 10 log (P)

P = On-time percentage

DC = Distance attenuation correction in dB(A) = -(20 log D + 8)

D = Distance in m between the noise source and the receiver

BC = Barrier correction in dB(A)

FC = Façade correction in dB(A) = 3 dB(A)



**CRBC - Build King Joint Venture**

Construction Noise Assessment

Period: 0700 to 1900 (except general holidays)

Noise Sensitive Receiver: CM6 (Above 39m)

Mitigation Measures Scenario

Noise Criteria: 75dB(A)

| Portion | Activity  | PME   | TM Ref. / other Ref. | No. of plants | SWL | Total SWL | On-time, % | Time Factor | Distance from Notional Sources, m | Distance Attenuation*, dB(A) | Barrier Correction, dB(A) | Façade Correction, dB(A) | Predicted Noise Level, dB(A) | Total Predicted Noise Level for each group, dB(A) |
|---------|---|---|----------------------|---------------|-----|-----------|------------|-------------|-----------------------------------|------------------------------|---------------------------|--------------------------|------------------------------|---|
| IX      | U - Trough (Piling)   | Crane (62 kw)   | BS D7/114            | 10            | 101 | 111       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 55.82                        | 70.28   |
|         |   | Drill Rig, Rotary Type (Diesel)                         | CNP 072              | 10            | 110 | 120       | 30         | -5          | 228                               | -55.20                       | -5                        | 3                        | 57.60                        |   |
|         |   | Generator, Silenced, <=75 dB(A) at 7m                   | CNP 102              | 10            | 100 | 110       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 54.82                        |   |
|         |   | Air Compressor  | CNP 002              | 10            | 102 | 112       | 30         | -5          | 228                               | -55.20                       | 0                         | 3                        | 54.60                        |   |
|         |   | Excavator (73 kw)                                       | BS D8/13             | 10            | 110 | 120       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 64.82                        |   |
|         |   | Concrete Lorry Mixer                                    | BS D6/33             | 10            | 96  | 106       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 50.82                        |   |
|         |   | Piling, Vibration Hammer                                | CNP 172              | 10            | 115 | 125       | 30         | -5          | 228                               | -55.20                       | 0                         | 3                        | 67.60                        |   |
|         |   | Power pack (diesel)                                     | CNP 174              | 10            | 100 | 110       | 30         | -5          | 228                               | -55.20                       | 0                         | 3                        | 52.60                        |   |
|         |   | Water pump, submersible (electric)                      | CNP 283              | 10            | 85  | 95        | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 39.82                        |   |
|         |   | Piling, large diameter bored, reverse circulation drill | CNP 166              | 3             | 100 | 105       | 30         | -5          | 228                               | -55.20                       | -5                        | 3                        | 42.37                        |   |
| IX      | U - Trough (ELS)  | Crane (62 kw)   | BS D7/114            | 4             | 101 | 107       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 51.84                        | 67.87   |
|         |   | Generator, Silenced, <=75 dB(A) at 7m                   | CNP 102              | 8             | 100 | 109       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 53.85                        |   |
|         |   | Piling, Vibration Hammer                                | CNP 172              | 4             | 115 | 121       | 30         | -5          | 228                               | -55.20                       | 0                         | 3                        | 63.62                        |   |
|         |   | Power pack (diesel)                                     | CNP 174              | 4             | 100 | 106       | 30         | -5          | 228                               | -55.20                       | 0                         | 3                        | 48.62                        |   |
|         |   | Excavator (73 kw)                                       | BS D8/13             | 8             | 110 | 119       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 63.85                        |   |
|         |   | Dump Truck  | CNP 068              | 8             | 105 | 114       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 58.85                        |   |
|         |   | Water pump, submersible (electric)                      | CNP 283              | 4             | 85  | 91        | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 35.84                        |   |
|         |   | Derrick Barge   | CNP 061              | 2             | 104 | 107       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 51.83                        |   |
|         |   | Crane (62 kw)   | BS D7/114            | 2             | 101 | 104       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 48.83                        |   |
|         |   | Generator, Silenced, <=75 dB(A) at 7m                   | CNP 102              | 2             | 100 | 103       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 47.83                        |   |
| IX      | U - Trough (Structure)  | Air Blower  | CNP 006              | 10            | 95  | 105       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 49.82                        | 67.47   |
|         |   | Saw, Circular Wood                                      | CNP 201              | 10            | 108 | 118       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 62.82                        |   |
|         |   | Concrete Lorry Mixer (6 m3)                             | BS D6/33             | 4             | 96  | 102       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 46.84                        |   |
|         |   | Concrete pump, stationary/lorry mounted                 | CNP 047              | 4             | 109 | 115       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 59.84                        |   |
|         |   | Poker, vibratory, hand-held                             | CNP 170              | 4             | 113 | 119       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 63.84                        |   |
|         |   | Water pump, submersible (electric)                      | CNP 283              | 12            | 85  | 96        | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 40.61                        |   |
|         |   | Excavator (73 kw)                                       | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 54.82                        |   |
|         |   | Roller, Vibratory (51 kw)                               | BS D8/30             | 1             | 101 | 101       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 45.82                        |   |
|         |   | Concrete Lorry Mixer (6 m3)                             | BS D6/33             | 1             | 96  | 96        | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 40.82                        |   |
|         |   | Light goods vehicle, gross vehicle weight < 5.5 tonne   | CNP 143              | 1             | 101 | 101       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 45.82                        |   |
| IX      | U - Trough (Road and Drainage Works)                                    | Water pump, submersible (electric)                      | CNP 283              | 4             | 85  | 91        | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 35.84                        | 58.34   |
|         |   | Dump Truck  | CNP 068              | 1             | 105 | 105       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 49.82                        |   |
|         |   | Road Roller   | CNP 185              | 1             | 108 | 108       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 52.82                        |   |
|         |   | Crane (62 kw)   | BS D7/114            | 1             | 101 | 101       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 48.55                        |   |
|         |   | Piling, large diameter bored, oscillator                | CNP 165              | 1             | 115 | 115       | 30         | -5          | 167                               | -52.40                       | 0                         | 3                        | 60.34                        |   |
|         |   | Excavator (73 kw)                                       | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 57.55                        |   |
|         |   | Water pump, submersible (electric)                      | CNP 283              | 2             | 85  | 88        | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 35.57                        |   |
|         |   | Crane (62 kw)   | BS D7/114            | 1             | 101 | 101       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 48.55                        |   |
|         |   | Drill Rig, Rotary Type (Diesel)                         | CNP 072              | 1             | 110 | 110       | 30         | -5          | 167                               | -52.40                       | -5                        | 3                        | 50.34                        |   |
|         |   | Generator, Silenced, <=75 dB(A) at 7m                   | CNP 102              | 1             | 100 | 100       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 47.55                        |   |
| VI      | Road P2 Underpass, U-Trough (Removal of Existing Abandoned Box Culvert) | Air Compressor  | CNP 002              | 2             | 102 | 105       | 30         | -5          | 167                               | -52.40                       | 0                         | 3                        | 50.35                        | 62.37   |
|         |   | Excavator (73 kw)                                       | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 57.55                        |   |
|         |   | Concrete Lorry Mixer                                    | BS D6/33             | 1             | 96  | 96        | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 43.55                        |   |
|         |   | Water pump, submersible (electric)                      | CNP 283              | 4             | 85  | 91        | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 38.58                        |   |
|         |   | Crane (62 kw)   | BS D7/114            | 1             | 101 | 101       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 48.55                        |   |
|         |   | Generator, Silenced, <=75 dB(A) at 7m                   | CNP 102              | 1             | 100 | 100       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 47.55                        |   |
|         |   | Piling, Vibration Hammer                                | CNP 172              | 1             | 115 | 115       | 30         | -5          | 167                               | -52.40                       | 0                         | 3                        | 60.34                        |   |
|         |   | Power pack (diesel)                                     | CNP 174              | 1             | 100 | 100       | 30         | -5          | 167                               | -52.40                       | 0                         | 3                        | 45.34                        |   |
|         |   | Excavator (73 kw)                                       | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 57.55                        |   |
|         |   | Dump Truck  | CNP 068              | 1             | 105 | 105       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 52.55                        |   |
| VI      | Road P2 Underpass, U Trough (Piling)                                    | Water pump, submersible (electric)                      | CNP 283              | 4             | 85  | 91        | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 38.58                        | 59.75   |
|         |   | Crane (62 kw)   | BS D7/114            | 1             | 101 | 101       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 48.55                        |   |
|         |   | Drill Rig, Rotary Type (Diesel)                         | CNP 072              | 1             | 110 | 110       | 30         | -5          | 167                               | -52.40                       | -5                        | 3                        | 50.34                        |   |
|         |   | Generator, Silenced, <=75 dB(A) at 7m                   | CNP 102              | 1             | 100 | 100       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 47.55                        |   |
|         |   | Air Compressor  | CNP 002              | 2             | 102 | 105       | 30         | -5          | 167                               | -52.40                       | 0                         | 3                        | 50.35                        |   |
|         |   | Excavator (73 kw)                                       | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 57.55                        |   |
|         |   | Concrete Lorry Mixer                                    | BS D6/33             | 1             | 96  | 96        | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 43.55                        |   |
|         |   | Water pump, submersible (electric)                      | CNP 283              | 4             | 85  | 91        | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 38.58                        |   |
|         |   | Crane (62 kw)   | BS D7/114            | 1             | 101 | 101       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 48.55                        |   |
|         |   | Generator, Silenced, <=75 dB(A) at 7m                   | CNP 102              | 1             | 100 | 100       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 47.55                        |   |
| VI      | Road P2 Underpass, U Trough (ELS)                                       | Piling, Vibration Hammer                                | CNP 172              | 1             | 115 | 115       | 30         | -5          | 167                               | -52.40                       | 0                         | 3                        | 60.34                        | 63.01   |
|         |   | Power pack (diesel)                                     | CNP 174              | 1             | 100 | 100       | 30         | -5          | 167                               | -52.40                       | 0                         | 3                        | 45.34                        |   |
|         |   | Excavator (73 kw)                                       | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 57.55                        |   |
|         |   | Dump Truck  | CNP 068              | 1             | 105 | 105       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 52.55                        |   |
|         |   | Water pump, submersible (electric)                      | CNP 283              | 4             | 85  | 91        | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 38.58                        |   |
|         |   | Crane (62 kw)   | BS D7/114            | 1             | 101 | 101       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 48.55                        |   |
|         |   | Generator, Silenced, <=75 dB(A) at 7m                   | CNP 102              | 1             | 100 | 100       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 47.55                        |   |
|         |   | Piling, Vibration Hammer                                | CNP 172              | 1             | 115 | 115       | 30         | -5          | 167                               | -52.40                       | 0                         | 3                        | 60.34                        |   |
|         |   | Power pack (diesel)                                     | CNP 174              | 1             | 100 | 100       | 30         | -5          | 167                               | -52.40                       | 0                         | 3                        | 45.34                        |   |
|         |   | Excavator (73 kw)                                       | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 57.55                        |   |
| VI      | Road P2 Underpass, U Trough (Structure)                                 | Dump Truck  | CNP 068              | 1             | 105 | 105       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 52.55                        | 60.74   |
|         |   | Water pump, submersible (electric)                      | CNP 283              | 4             | 85  | 91        | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 38.58                        |   |
|         |   | Crane (62 kw)   | BS D7/114            | 2             | 101 | 104       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 51.57                        |   |
|         |   | Generator, Silenced, <=75 dB(A) at 7m                   | CNP 102              | 2             | 100 | 103       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 50.57                        |   |
|         |   | Air Compressor  | CNP 002              | 2             | 102 | 105       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 52.57                        |   |
|         |   | Saw, Circular Wood                                      | CNP 201              | 2             | 108 | 111       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 58.57                        |   |
|         |   | Concrete Lorry Mixer (6 m3)                             | BS D6/33             | 1             | 96  | 96        | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 43.55                        |   |
|         |   | Water pump, submersible (electric)                      | CNP 283              | 4             | 85  | 91        | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 38.58                        |   |
|         |   | Crane (62 kw)   | BS D7/114            | 1             | 101 | 101       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 48.55                        |   |
|         |   | Generator, Silenced, <=75 dB(A) at 7m                   | CNP 102              | 1             | 100 | 100       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 47.55                        |   |
| VI      | Road and Drainage Works   | Piling, Vibration Hammer                                | CNP 172              | 1             | 115 | 115       | 30         | -5          | 167                               | -52.40                       | 0                         | 3                        | 60.34                        | 61.08   |
|         |   | Power pack (diesel)                                     | CNP 174              | 1             | 100 | 100       | 30         | -5          | 167                               | -52.40                       | 0                         | 3                        | 45.34                        |   |
|         |   | Excavator (73 kw)                                       | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 57.55                        |   |
|         |   | Dump Truck  | CNP 068              | 1             | 105 | 105       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 52.55                        |   |
|         |   | Water pump, submersible (electric)                      | CNP 283              | 4             | 85  | 91        | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 38.58                        |   |
|         |   | Excavator (73 kw)                                       | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 57.55                        |   |
|         |   | Roller, Vibratory (51 kw)                               | BS D8/30             | 1             | 101 | 101       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 48.55                        |   |
|         |   | Concrete Lorry Mixer (6 m3)                             | BS D6/33             | 1             | 96  | 96        | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 43.55                        |   |
|         |   | Light goods vehicle, gross vehicle weight < 5.5 tonne   | CNP 143              | 1             | 101 | 101       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 48.55                        |   |
|         |   | Water pump, submersible (electric)                      | CNP 283              | 4             | 85  | 91        | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 38.58                        |   |
| VI      | Road and Drainage Works   | Dump Truck  | CNP 068              | 1             | 105 | 105       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 52.55                        | 61.08   |
|         |   | Road Roller   | CNP 185              | 1             | 108 | 108       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 55.55                        |   |
|         |   | Excavator (73 kw)                                       | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 57.55                        |   |
|         |   | Roller, Vibratory (51 kw)                               | BS D8/30             | 1             | 101 | 101       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 48.55                        |   |
|         |   | Concrete Lorry Mixer (6 m3)                             | BS D6/33             | 1             | 96  | 96        | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 43.55                        |   |
|         |   | Light goods vehicle, gross vehicle weight < 5.5 tonne   | CNP 143              | 1             | 101 | 101       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 48.55                        |   |
|         |   | Water pump, submersible (electric)                      | CNP 283              | 4             | 85  | 91        | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 38.58                        |   |
|         |   | Dump Truck  | CNP 068              | 1             | 105 | 105       | 50         | -3          | 167                               | -52.40                       | 0                         | 3                        | 52.55                        |   |
|         |   | Road Roller   | CNP 185              | 1             | 1   |           |            |             |                                   |                              |                           |                          |                              |   |



| Portion                                | Activity                          | PME  | TM Ref. / other Ref. | No. of plants | SWL | Total SWL | On-time, % | Time Factor | Distance from Notional Sources, m | Distance Attenuation*, dB(A) | Barrier Correction, dB(A) | Façade Correction, dB(A) | Predicted Noise Level, dB(A) | Total Predicted Noise Level for each group, dB(A) |       |
|--|-----------------------------------|--|----------------------|---------------|-----|-----------|------------|-------------|-----------------------------------|------------------------------|---------------------------|--------------------------|------------------------------|---|-------|
| I                                      | DSD Transformer Room              | Generator, Silenced, <=75 dB(A) at 7m                      | CNP 102              | 1             | 100 | 100       | 50         | -3          | 217                               | -54.70                       | 0                         | 3                        | 45.29                        | 59.65   |       |
|  |                                   | Bar Bender and Cutter                                      | CNP 021              | 1             | 90  | 90        | 50         | -3          | 217                               | -54.70                       | 0                         | 3                        | 35.29                        |   |       |
|  |                                   | Breaker, hand-held, mass > 10kg < 20kg                     | CNP 024              | 1             | 108 | 108       | 50         | -3          | 217                               | -54.70                       | 0                         | 3                        | 53.29                        |   |       |
|  |                                   | Concrete Lorry Mixer (6 m3)                                | BS D6/33             | 1             | 96  | 96        | 50         | -3          | 217                               | -54.70                       | 0                         | 3                        | 41.29                        |   |       |
|  |                                   | Saw, Circular Wood   | CNP 201              | 1             | 108 | 108       | 50         | -3          | 217                               | -54.70                       | 0                         | 3                        | 53.29                        |   |       |
|  |                                   | Water pump, subsersible (electric)                         | CNP 283              | 2             | 85  | 88        | 50         | -3          | 217                               | -54.70                       | 0                         | 3                        | 33.30                        |   |       |
|  |                                   | Excavator (73 kw)  | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 217                               | -54.70                       | 0                         | 3                        | 55.29                        |   |       |
|  |                                   | Dump Truck   | CNP 068              | 1             | 105 | 105       | 50         | -3          | 217                               | -54.70                       | 0                         | 3                        | 50.29                        |   |       |
| IV                                     | Road P2 Underpass (Piling)        | Crane (62 kw)  | BS D7/114            | 3             | 101 | 106       | 50         | -3          | 60                                | -43.50                       | -5                        | 3                        | 57.26                        | 70.96   |       |
|  |                                   | Drill Rig, Rotary Type (Diesel)                            | CNP 072              | 3             | 110 | 115       | 30         | -5          | 60                                | -43.50                       | 0                         | 3                        | 69.05                        |   |       |
|  |                                   | Air Compressor   | CNP 002              | 6             | 102 | 110       | 30         | -5          | 60                                | -43.50                       | -5                        | 3                        | 59.06                        |   |       |
|  |                                   | Excavator (73 kw)  | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 60                                | -43.50                       | -5                        | 3                        | 61.49                        |   |       |
|  |                                   | Concrete Lorry Mixer (6 m3)                                | BS D6/33             | 1             | 96  | 96        | 50         | -3          | 60                                | -43.50                       | -5                        | 3                        | 47.49                        |   |       |
|  |                                   | Water pump, subsersible (electric)                         | CNP 283              | 4             | 85  | 91        | 50         | -3          | 60                                | -43.50                       | -5                        | 3                        | 42.51                        |   |       |
|  |                                   | G. I. drilling rig   | BS C2/43             | 1             | 102 | 102       | 50         | -3          | 60                                | -43.50                       | -5                        | 3                        | 53.49                        |   |       |
|  |                                   | Breaker, excavator mounted (hydraulic)                     | CNP 028              | 1             | 122 | 122       | 10         | -10         | 60                                | -43.50                       | -10                       | 3                        | 61.50                        |   |       |
| IV                                     | Road P2 Underpass (ELS)           | Crane (62 kw)  | BS D7/114            | 1             | 101 | 101       | 50         | -3          | 60                                | -43.50                       | -5                        | 3                        | 52.49                        | 68.61   |       |
|  |                                   | Generator, Silenced, <=75 dB(A) at 7m                      | CNP 102              | 1             | 100 | 100       | 50         | -3          | 60                                | -43.50                       | -5                        | 3                        | 51.49                        |   |       |
|  |                                   | Piling, Vibration Hammer                                   | CNP 172              | 2             | 115 | 118       | 30         | -5          | 60                                | -43.50                       | -5                        | 3                        | 67.28                        |   |       |
|  |                                   | Power pack (diesel)  | CNP 174              | 2             | 100 | 103       | 30         | -5          | 60                                | -43.50                       | -5                        | 3                        | 52.28                        |   |       |
|  |                                   | Excavator (73 kw)  | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 60                                | -43.50                       | -5                        | 3                        | 61.49                        |   |       |
|  |                                   | Water pump, subsersible (electric)                         | CNP 283              | 4             | 85  | 91        | 50         | -3          | 60                                | -43.50                       | -5                        | 3                        | 42.51                        |   |       |
| IV                                     | Road and Drainage Works           | Excavator (73 kw)  | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 60                                | -43.50                       | -5                        | 3                        | 61.49                        | 65.02   |       |
|  |                                   | Roller, Vibratory (51 kw)                                  | BS D8/30             | 1             | 101 | 101       | 50         | -3          | 60                                | -43.50                       | -5                        | 3                        | 52.49                        |   |       |
|  |                                   | Concrete Lorry Mixer (6 m3)                                | BS D6/33             | 1             | 96  | 96        | 50         | -3          | 60                                | -43.50                       | -5                        | 3                        | 47.49                        |   |       |
|  |                                   | Light goods vehicle, gross vehicle weight < 5.5 tonne      | CNP 143              | 1             | 101 | 101       | 50         | -3          | 60                                | -43.50                       | -5                        | 3                        | 52.49                        |   |       |
|  |                                   | Water pump, subsersible (electric)                         | CNP 283              | 4             | 85  | 91        | 50         | -3          | 60                                | -43.50                       | -5                        | 3                        | 42.51                        |   |       |
|  |                                   | Dump Truck   | CNP 068              | 1             | 105 | 105       | 50         | -3          | 60                                | -43.50                       | -5                        | 3                        | 56.49                        |   |       |
|  |                                   | Road Roller  | CNP 185              | 1             | 108 | 108       | 50         | -3          | 60                                | -43.50                       | -5                        | 3                        | 59.49                        |   |       |
|  |                                   | Crane (62 kw)  | BS D7/114            | 1             | 101 | 101       | 50         | -3          | 150                               | -51.50                       | 0                         | 3                        | 49.46                        |   | 61.42 |
| Drill Rig, Rotary Type (Diesel)        | CNP 072                           | 1  | 110                  | 110           | 30  | -5        | 150        | -51.50      | -5                                | 3                            | 51.24                     |                          |                              |   |       |
| Generator, Silenced, <=75 dB(A) at 7m  | CNP 102                           | 1  | 100                  | 100           | 50  | -3        | 150        | -51.50      | 0                                 | 3                            | 48.46                     |                          |                              |   |       |
| Air Compressor                         | CNP 002                           | 2  | 102                  | 105           | 30  | -5        | 150        | -51.50      | 0                                 | 3                            | 51.25                     |                          |                              |   |       |
| Excavator (73 kw)                      | BS D8/13                          | 1  | 110                  | 110           | 50  | -3        | 150        | -51.50      | 0                                 | 3                            | 58.46                     |                          |                              |   |       |
| Concrete Lorry Mixer                   | BS D6/33                          | 1  | 96                   | 96            | 50  | -3        | 150        | -51.50      | 0                                 | 3                            | 44.46                     |                          |                              |   |       |
| Water pump, subsersible (electric)     | CNP 283                           | 4  | 85                   | 91            | 50  | -3        | 150        | -51.50      | 0                                 | 3                            | 39.48                     |                          |                              |   |       |
| Breaker, excavator mounted (hydraulic) | CNP 028                           | 1  | 122                  | 122           | 10  | -10       | 150        | -51.50      | -10                               | 3                            | 53.47                     |                          |                              |   |       |
| V                                      | Road P2 Underpass, U Trough (ELS) | Crane (62 kw)  | BS D7/114            | 1             | 101 | 101       | 50         | -3          | 150                               | -51.50                       | 0                         | 3                        | 49.46                        | 63.91   |       |
|  |                                   | Generator, Silenced, <=75 dB(A) at 7m                      | CNP 102              | 1             | 100 | 100       | 50         | -3          | 150                               | -51.50                       | 0                         | 3                        | 48.46                        |   |       |
|  |                                   | Piling, Vibration Hammer                                   | CNP 172              | 1             | 115 | 115       | 30         | -5          | 150                               | -51.50                       | 0                         | 3                        | 61.24                        |   |       |
|  |                                   | Power pack (diesel)  | CNP 174              | 1             | 100 | 100       | 30         | -5          | 150                               | -51.50                       | 0                         | 3                        | 46.24                        |   |       |
|  |                                   | Excavator (73 kw)  | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 150                               | -51.50                       | 0                         | 3                        | 58.46                        |   |       |
|  |                                   | Dump Truck   | CNP 068              | 1             | 105 | 105       | 50         | -3          | 150                               | -51.50                       | 0                         | 3                        | 53.46                        |   |       |
|  |                                   | Water pump, subsersible (electric)                         | CNP 283              | 4             | 85  | 91        | 50         | -3          | 150                               | -51.50                       | 0                         | 3                        | 39.48                        |   |       |
|  |                                   | Crane (62 kw)  | BS D7/114            | 1             | 101 | 101       | 50         | -3          | 150                               | -51.50                       | 0                         | 3                        | 49.46                        |   | 61.38 |
| Generator, Silenced, <=75 dB(A) at 7m  | CNP 102                           | 2  | 100                  | 103           | 50  | -3        | 150        | -51.50      | 0                                 | 3                            | 51.47                     |                          |                              |   |       |
| Air Compressor                         | CNP 002                           | 2  | 102                  | 105           | 50  | -3        | 150        | -51.50      | 0                                 | 3                            | 53.47                     |                          |                              |   |       |
| Saw, Circular Wood                     | CNP 201                           | 2  | 108                  | 111           | 50  | -3        | 150        | -51.50      | 0                                 | 3                            | 59.47                     |                          |                              |   |       |
| Concrete Lorry Mixer (6 m3)            | BS D6/33                          | 1  | 96                   | 96            | 50  | -3        | 150        | -51.50      | 0                                 | 3                            | 44.46                     |                          |                              |   |       |
| Water pump, subsersible (electric)     | CNP 283                           | 4  | 85                   | 91            | 50  | -3        | 150        | -51.50      | 0                                 | 3                            | 39.48                     |                          |                              |   |       |
| Excavator (73 kw)                      | BS D8/13                          | 1  | 110                  | 110           | 50  | -3        | 150        | -51.50      | 0                                 | 3                            | 58.46                     |                          |                              |   |       |
| Roller, Vibratory (51 kw)              | BS D8/30                          | 1  | 101                  | 101           | 50  | -3        | 150        | -51.50      | 0                                 | 3                            | 49.46                     |                          |                              |   |       |
| V                                      | Road and Drainage Works           | Concrete Lorry Mixer (6 m3)                                | BS D6/33             | 1             | 96  | 96        | 50         | -3          | 150                               | -51.50                       | 0                         | 3                        | 44.46                        | 61.98   |       |
|  |                                   | Light goods vehicle, gross vehicle weight < 5.5 tonne      | CNP 143              | 1             | 101 | 101       | 50         | -3          | 150                               | -51.50                       | 0                         | 3                        | 49.46                        |   |       |
|  |                                   | Water pump, subsersible (electric)                         | CNP 283              | 4             | 85  | 91        | 50         | -3          | 150                               | -51.50                       | 0                         | 3                        | 39.48                        |   |       |
|  |                                   | Dump Truck   | CNP 068              | 1             | 105 | 105       | 50         | -3          | 150                               | -51.50                       | 0                         | 3                        | 53.46                        |   |       |
|  |                                   | Road Roller  | CNP 185              | 1             | 108 | 108       | 50         | -3          | 150                               | -51.50                       | 0                         | 3                        | 56.46                        |   |       |
|  |                                   | Crane (62 kw)  | BS D7/114            | 1             | 101 | 101       | 50         | -3          | 124                               | -49.90                       | -5                        | 3                        | 46.10                        |   | 58.04 |
|  |                                   | Drill Rig, Rotary Type (Diesel)                            | CNP 072              | 1             | 110 | 110       | 30         | -5          | 124                               | -49.90                       | -5                        | 3                        | 52.88                        |   |       |
|  |                                   | Air Compressor   | CNP 002              | 2             | 102 | 105       | 30         | -5          | 124                               | -49.90                       | -5                        | 3                        | 47.89                        |   |       |
| Excavator (73 kw)                      | BS D8/13                          | 1  | 110                  | 110           | 50  | -3        | 124        | -49.90      | -5                                | 3                            | 55.10                     |                          |                              |   |       |
| Concrete Lorry Mixer (6 m3)            | BS D6/33                          | 1  | 96                   | 96            | 50  | -3        | 124        | -49.90      | -5                                | 3                            | 41.10                     |                          |                              |   |       |
| Water pump, subsersible (electric)     | CNP 283                           | 4  | 85                   | 91            | 50  | -3        | 124        | -49.90      | -5                                | 3                            | 36.12                     |                          |                              |   |       |
| Crane (62 kw)                          | BS D7/114                         | 1  | 101                  | 101           | 50  | -3        | 124        | -49.90      | -5                                | 3                            | 46.10                     | 61.65                    |                              |   |       |
| Generator, Silenced, <=75 dB(A) at 7m  | CNP 102                           | 1  | 100                  | 100           | 50  | -3        | 124        | -49.90      | -5                                | 3                            | 45.10                     |                          |                              |   |       |
| Breaker, Excavator mounted (hydraulic) | CNP 028                           | 1  | 122                  | 122           | 10  | -10       | 124        | -49.90      | -10                               | 3                            | 55.11                     |                          |                              |   |       |
| Piling, Vibration Hammer               | CNP 172                           | 1  | 115                  | 115           | 30  | -5        | 124        | -49.90      | -5                                | 3                            | 57.88                     |                          |                              |   |       |
| Power pack (diesel)                    | CNP 174                           | 1  | 100                  | 100           | 30  | -5        | 124        | -49.90      | -5                                | 3                            | 42.88                     |                          |                              |   |       |
| Excavator (73 kw)                      | BS D8/13                          | 1  | 110                  | 110           | 50  | -3        | 124        | -49.90      | -5                                | 3                            | 55.10                     |                          |                              |   |       |
| Dump Truck                             | CNP 068                           | 1  | 105                  | 105           | 50  | -3        | 124        | -49.90      | -5                                | 3                            | 50.10                     |                          |                              |   |       |
| Water pump, subsersible (electric)     | CNP 283                           | 4  | 85                   | 91            | 50  | -3        | 124        | -49.90      | -5                                | 3                            | 36.12                     |                          |                              |   |       |
| VII                                    | Road and Drainage Works           | Excavator (73 kw)  | BS D8/13             | 1             | 110 | 110       | 50         | -3          | 124                               | -49.90                       | -5                        | 3                        | 55.10                        | 58.63   |       |
|  |                                   | Roller, Vibratory (51 kw)                                  | BS D8/30             | 1             | 101 | 101       | 50         | -3          | 124                               | -49.90                       | -5                        | 3                        | 46.10                        |   |       |
|  |                                   | Concrete Lorry Mixer (6 m3)                                | BS D6/33             | 1             | 96  | 96        | 50         | -3          | 124                               | -49.90                       | -5                        | 3                        | 41.10                        |   |       |
|  |                                   | Light goods vehicle, gross vehicle weight < 5.5 tonne      | CNP 143              | 1             | 101 | 101       | 50         | -3          | 124                               | -49.90                       | -5                        | 3                        | 46.10                        |   |       |
|  |                                   | Water pump, subsersible (electric)                         | CNP 283              | 4             | 85  | 91        | 50         | -3          | 124                               | -49.90                       | -5                        | 3                        | 36.12                        |   |       |
|  |                                   | Dump Truck   | CNP 068              | 1             | 105 | 105       | 50         | -3          | 124                               | -49.90                       | -5                        | 3                        | 50.10                        |   |       |
|  |                                   | Road Roller  | CNP 185              | 1             | 108 | 108       | 50         | -3          | 124                               | -49.90                       | -5                        | 3                        | 53.10                        |   |       |
|  |                                   | Dredger  | CNP 070              | 2             | 103 | 106       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 50.83                        |   | 65.61 |
| Derrick Barge                          | CNP 061                           | 4  | 104                  | 110           | 50  | -3        | 228        | -55.20      | 0                                 | 3                            | 54.84                     |                          |                              |   |       |
| Tug boat                               | CNP 221                           | 2  | 110                  | 113           | 50  | -3        | 228        | -55.20      | 0                                 | 3                            | 57.83                     |                          |                              |   |       |
| Water pump, subsersible (electric)     | CNP 283                           | 6  | 85                   | 93            | 50  | -3        | 228        | -55.20      | 0                                 | 3                            | 37.60                     |                          |                              |   |       |
| Dump Truck                             | CNP 068                           | 6  | 105                  | 113           | 50  | -3        | 228        | -55.20      | 0                                 | 3                            | 57.60                     |                          |                              |   |       |
| Generator, Silenced, <=75 dB(A) at 7m  | CNP 102                           | 4  | 100                  | 106           | 50  | -3        | 228        | -55.20      | 0                                 | 3                            | 50.84                     |                          |                              |   |       |
| Winch (Electric)                       | CNP 262                           | 4  | 95                   | 101           | 50  | -3        | 228        | -55.20      | 0                                 | 3                            | 45.84                     |                          |                              |   |       |
| Excavator (73 kw)                      | BS D8/13                          | 3  | 110                  | 115           | 50  | -3        | 228        | -55.20      | 0                                 | 3                            | 59.59                     |                          |                              |   |       |
| Vibration Hammer                       | CNP 172                           | 1  | 115                  | 115           | 50  | -3        | 228        | -55.20      | 0                                 | 3                            | 59.82                     |                          |                              |   |       |
| IX                                     | Steel Cofferdam and Water Gate    | Hopper barge   | -                    | 6             | -   | -         | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | -                            | 59.22   |       |
|  |                                   | Derrick Barge  | CNP 061              | 3             | 104 | 109       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 53.59                        |   |       |
| IX                                     | Marine Ground Treatment           | Tug boat   | CNP 221              | 2             | 110 | 113       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 57.83                        | 57.82   |       |
|  |                                   | Band Drain Machine (hydraulic Vibratory lance starting up) | BS D4/107a           | 1             | 113 | 113       | 50         | -3          | 228                               | -55.20                       | 0                         | 3                        | 57.82                        |   |       |

Note: SPL = SWL + TF + DC + BC + FC, where  
 SPL = Predicted noise level in dB(A)  
 SWL = Sound Power Level in dB(A)  
 TF = Time factor in dB(A) = 10 log (P)  
 P = On-time percentage  
 DC = Distance attenuation correction in dB(A) = (-20 log D + 8)  
 D = Distance in m between the noise source and the receiver  
 BC = Barrier correction in dB(A)  
 FC = Façade correction in dB(A) = 3 dB(A)



---

---

**APPENDIX T  
CULTURAL HERITAGE MONITORING  
RESULTS**

---

---

**Appendix T – Cultural Heritage Monitoring Results**

| Date                | Time  | Tilting   |   |   | Settlement (mm)     |           |           | Vibration (mm/s)      |          |              |
|---------------------|-------|---|---|---|---------------------|-----------|-----------|-----------------------|----------|--------------|
|                     |       | Angle (deg) between<br>THT-BSP-1 &<br>THT-BSP-2 | Angle (deg) between<br>THT-BSP-1 &<br>THT-BSP-3 | Angle (deg) between<br>THT-BSP-2 &<br>THT-BSP-3 | THT-BSP-1           | THT-BSP-2 | THT-BSP-3 | Measurement Direction |          |              |
|                     |       |   |   |   |                     |           |           | Tran                  | Vertical | Longitudinal |
| 1-Jun-18            | 14:35 | 1 : 4597  | 1 : 7009  | -1 : 16901                                      | +3                  | +0        | +1        | 0.254                 | 0.254    | 0.254        |
| 2-Jun-18            | 14:38 | 1 : 4597  | 1 : 7009  | -1 : 16901                                      | +3                  | +1        | +1        | 0.127                 | 0.254    | 0.381        |
| 4-Jun-18            | 14:23 | 0   | 1 : 4673  | 1 : 5634  | +1                  | +1        | -2        | 0.254                 | 0.254    | 0.254        |
| 5-Jun-18            | 14:43 | -1 : 13792                                      | 0   | 1 : 16901                                       | +1                  | +2        | +1        | 0.254                 | 0.254    | 0.254        |
| 6-Jun-18            | 14:47 | Bad weather                                     |   |   | Bad weather         |           |           | 0.127                 | 0.254    | 0.254        |
| 7-Jun-18            | 14:50 | 1 : 13792                                       | 1 : 7009  | 1 : 16901                                       | +2                  | +1        | +0        | 0.127                 | 0.254    | 0.254        |
| 8-Jun-18            | 14:52 | Bad weather                                     |   |   | Bad weather         |           |           | 0.127                 | 0.254    | 0.127        |
| 9-Jun-18            | 14:56 | 1 : 13792                                       | 1 : 14018                                       | 0   | +2                  | +1        | +1        | 0.127                 | 0.254    | 0.127        |
| 11-Jun-18           | 15:00 | 1 : 4597  | 1 : 7009  | -1 : 16901                                      | +3                  | +0        | +1        | 0.254                 | 0.381    | 0.381        |
| 12-Jun-18           | 15:00 | 1 : 4597  | 1 : 4673  | 0   | +4                  | +1        | +1        | 0.127                 | 0.127    | 0.254        |
| 13-Jun-18           | 15:00 | 1 : 4597  | 1 : 7009  | -1 : 16901                                      | +3                  | +0        | +1        | 0.762                 | 0.889    | 1.016        |
| 14-Jun-18           | 15:04 | 0   | 1 : 7009  | 1 : 8451  | +1                  | +1        | -1        | 0.127                 | 0.254    | 0.127        |
| 15-Jun-18           | 15:04 | -1 : 13792                                      | 1 : 14018                                       | 1 : 8451  | +0                  | +1        | -1        | 0.127                 | 0.254    | 0.254        |
| 16-Jun-18           | 15:06 | Measurement missing                             |   |   | Measurement missing |           |           | 0.127                 | 0.254    | 0.254        |
| 19-Jun-18           | 15:07 | 1 : 4597  | 1 : 4673  | 0   | +3                  | +0        | +0        | 0.127                 | 0.254    | 0.254        |
| 20-Jun-18           | 15:09 | 1 : 6896  | 1 : 7009  | 0   | +2                  | +0        | +0        | 0.254                 | 0.254    | 0.127        |
| 21-Jun-18           | 17:21 | 1 : 6896  | 1 : 7009  | 0   | +2                  | +0        | +0        | 0.126                 | 0.134    | 0.158        |
| 22-Jun-18           | 15:10 | 1 : 4597  | 1 : 4673  | 0   | +3                  | +0        | +0        | 0.127                 | 0.254    | 0.127        |
| 23-Jun-18           | 15:10 | 1 : 4597  | 1 : 4673  | 0   | +3                  | +0        | +0        | 0.127                 | 0.254    | 0.381        |
| 25-Jun-18           | 16:16 | 1 : 13792                                       | 1 : 14018                                       | 0   | +3                  | +2        | +2        | 0.118                 | 0.071    | 0.189        |
| 26-Jun-18           | 15:11 | 1 : 3448  | 1 : 3505  | 0   | +4                  | +0        | +0        | 0.762                 | 1.016    | 0.889        |
| 27-Jun-18           | 15:11 | 1 : 4597  | 1 : 7009  | -1 : 16901                                      | +3                  | +0        | +1        | 0.254                 | 0.381    | 0.381        |
| 28-Jun-18           | 15:12 | 1 : 4597  | 1 : 7009  | -1 : 16901                                      | +2                  | -1        | +0        | 0.127                 | 0.254    | 0.254        |
| 29-Jun-18           | 15:24 | 1 : 6896  | 1 : 7009  | 0   | +3                  | +1        | +1        | 0.762                 | 0.889    | 0.889        |
| 30-Jun-18           | 15:24 | 1 : 4597  | 1 : 4673  | 0   | +3                  | +0        | +0        | 0.127                 | 0.254    | 0.254        |
| <b>Alert Level</b>  |       | 1:2000  |   |   | 6                   |           |           | 4.5                   |          |              |
| <b>Alarm Level</b>  |       | 1:1500  |   |   | 8                   |           |           | 4.8                   |          |              |
| <b>Action Level</b> |       | 1:1000  |   |   | 10                  |           |           | 5                     |          |              |

Note: **Bold** means Alert Level exceedance**Bold Italic** means Alarm Level exceedance**Bold Italic with underline** means Action Level exceedance

---

---

**APPENDIX U**  
**PIEZOMETER MONITORING RESULTS**

---

---

**Appendix U – Construction Phase Daily Piezometer Monitoring Results**

| Date      | Daily Piezometer Monitoring  |  |
|-----------|--|--|
|           | 38568-LDH1   | TKO-LBH907   |
| 1-Jun-18  | Construction phase daily piezometer monitoring by the Contactor was not carried out as the monitoring point was being blocked by heavy overgrown vegetation. | Tunnel construction activities are not within +/-50m of the piezometer gate in plan. |
| 2-Jun-18  |  |  |
| 3-Jun-18  |  |  |
| 4-Jun-18  |  |  |
| 5-Jun-18  |  |  |
| 6-Jun-18  |  |  |
| 7-Jun-18  |  |  |
| 8-Jun-18  |  |  |
| 9-Jun-18  |  |  |
| 10-Jun-18 |  |  |
| 11-Jun-18 |  |  |
| 12-Jun-18 |  |  |
| 13-Jun-18 |  |  |
| 14-Jun-18 |  |  |
| 15-Jun-18 |  |  |
| 16-Jun-18 |  |  |
| 17-Jun-18 |  |  |
| 18-Jun-18 |  |  |
| 19-Jun-18 |  |  |
| 20-Jun-18 |  |  |
| 21-Jun-18 |  |  |
| 22-Jun-18 |  |  |
| 23-Jun-18 |  |  |
| 24-Jun-18 |  |  |
| 25-Jun-18 |  |  |
| 26-Jun-18 |  |  |
| 27-Jun-18 |  |  |
| 28-Jun-18 |  |  |
| 29-Jun-18 | +87.65   |  |
| 30-Jun-18 | +87.55   |  |

| Date              | Daily Piezometer Monitoring |            |
|-------------------|-----------------------------|------------|
|                   | 38568-LDH1                  | TKO-LBH907 |
| Action Level(mpD) | +74.65                      | +17.59     |

Note: ***Bold Italic with underline*** means Action Level exceedance