



# **Ocean Park Tai Shue Wan Water World Project**

Quarterly EM&A Report for March – May 2018

August 2018

Mott MacDonald  
3/F Mapletree Bay Point  
348 Kwun Tong Road  
Kwun Tong  
Kowloon  
Hong Kong

T +852 2828 5757  
F +852 2827 1823  
mottmac.hk

# **Ocean Park Tai Shue Wan Water World Project**

Quarterly EM&A Report for March – May 2018

August 2018

This Quarterly EM&A Summary Report for March – May 2018 has been  
reviewed and certified by the Environmental Team Leader (ETL) and  
verified by the Independent Environmental Checker (IEC) as having  
complied with the requirements as set out in the  
**EM&A Manual Section 11.4.**

**Certified by:**



Gary Chow  
Environmental Team Leader (ETL)  
Mott MacDonald Hong Kong Limited

Date:

  
8 Aug 2018.

**Verified by:**

  
Gerald Kam  
Independent Environmental Checker (IEC)  
Ove Arup and Partners Hong Kong Limited

Date:

  
9 Aug 2018

# Issue and Revision Record

Revision	Date	Originator	Checker	Approver	Description
A	Jul 2018	Various	Gary Chow	Eric Ching	1 <sup>st</sup> Draft to client and IEC
B	Aug 2018	Various	Gary Chow	Eric Ching	Final to client and IEC

## Information class: Standard

---

This document is issued for the party which commissioned it and for specific purposes connected with the above-captioned project only. It should not be relied upon by any other party or used for any other purpose.

We accept no responsibility for the consequences of this document being relied upon by any other party, or being used for any other purpose, or containing any error or omission which is due to an error or omission in data supplied to us by other parties.

This document contains confidential information and proprietary intellectual property. It should not be shown to other parties without consent from us and from the party which commissioned it.

---

# Contents

<b>Executive Summary</b>	<b>1</b>
<b>1      Introduction</b>	<b>3</b>
1.1    Project Background	3
<b>2      Project Organization</b>	<b>4</b>
2.1    Project Organization	4
2.2    Construction Progress	6
2.3    Summary of Environmental Submissions	7
<b>3      Summary of Environmental Monitoring and Audit Requirements</b>	<b>9</b>
3.1    General	9
3.2    Monitoring Locations	10
3.3    Derivation of Action/Limit Levels	10
3.4    Meteorological Information	11
<b>4      Construction Noise Monitoring</b>	<b>12</b>
4.1    Monitoring Results	12
<b>5      Ecology Monitoring</b>	<b>15</b>
5.1    Inspection Findings	15
5.2    Conclusion	15
<b>6      Landscape and Visual Monitoring</b>	<b>17</b>
6.1    Inspection Findings	17
<b>7      Waste Management</b>	<b>18</b>
7.1    Record of Waste Quantities	18
<b>8      Site Inspection</b>	<b>19</b>
8.1    Inspection Findings	19
<b>9      Summary of Environmental Quality Performance Limits</b>	<b>20</b>
9.1    Record on Non-compliance of Action and Limit Levels	20
9.2    Record on Environmental Complaints Received	20

<b>10 Implementation Status of Mitigation Measures</b>	<b>22</b>
10.1 General Requirements	22
<b>11 Conclusions and Recommendations</b>	<b>24</b>
11.1 Conclusions	24
11.2 Recommendations	24
<b>Appendices</b>	<b>25</b>
A. Layout Plan of the Project	26
B. Project Organization	27
C. Designated Monitoring Locations as Recommended in the Approved EM&A Manual	28
D. Actual Locations of Impact Monitoring	29
E. Meteorological Data	30
F. Noise Monitoring Data	31
G. Graphical Plots of Noise Monitoring Data	32
H. Implementation Schedule for Environmental Mitigation Measures	33

## Tables

Table 1: Status of Environmental Licenses and Permits of the Project	7
Table 2: Summary of Impact EM&A Requirements	9
Table 3: Impact Monitoring Stations for Construction Noise	10
Table 4: Action and Limit Levels for Construction Noise	10
Table 5: Summary of Construction Noise Monitoring Results (Noise level for 30 minutes)	12
Table 6: Summary of Construction Noise Monitoring Results (Noise level for 15 minutes)	13
Table 7: Summary of Quantities of Inert C&D Materials	18
Table 8: Summary of Quantities of Non-inert C&D Materials	18
Table 9: Site Observations of the Project	19
Table 10: Environmental Mitigation Measures	22

# Executive Summary

Mott MacDonald Hong Kong Ltd. ("MMHK") has been commissioned by the Gammon Engineering & Construction Company Limited, to undertake the Environmental Team (ET) services to carry out environmental monitoring and audit (EM&A) for Ocean Park Tai Shue Wan Development Water World.

This is the 4<sup>th</sup> Quarterly EM&A Summary report for the Tai Shue Wan Development Water World under Section 11.4 of the EM&A Manual (Register No.: AEIAR-184/2014). This report summarises the findings on EM&A during the period from 1 March 2018 to 31 May 2018.

## Environmental Monitoring and Audit Activities

Environmental monitoring activities under the EM&A programme in the Reporting Period are summarized in the following table:

Environmental Aspect	Environmental Monitoring Parameters / Inspection	Total Occasions
Construction Noise	$L_{eq(30min)}$ Daytime	26
	$L_{eq(15min)}$ Addition monitoring	24
Ecology	Site Inspection	3
Landscape and Visual	Inspection of the mitigation measures implementation situation	6
Site Inspection / Audit	Environmental Team (ET), the Contractor and Project Management Representative (PMR) joint site inspection and auditing	13
	Independent Environmental Checker (IEC) joint site inspection and auditing	3

## Breaches of Action/Limit Levels

No exceedance of construction noise measurement and no Notifications of Exceedances (NOEs) were issued to the PMR, IEC and the Contractor. The statistics of environmental exceedance, NOE issued and investigation of exceedance are summarized in the following table:

Environmental Aspect	Monitoring Parameter	Action Level	Limit Level	Event & Action		
				NOE Issued	Investigation	Corrective Actions
Construction Noise	$L_{eq(30min)}$ Daytime	0	0	0	0	0

## Environmental Complaints

A total of two noise complaints were received in this Reporting Period regarding noise impact at night time.

On 3 March 2018, the complaint was about noise from the construction work and construction vehicles during restricted hours. This complaint is unlikely to be related to the construction

works on the project site due to no construction works was carried out during the incident period.

Other complaint on 16 March 2018 was about traffic noise by construction vehicles in Nam Long Sha Road from 1 a.m. to 4 a.m. This complaint is unlikely to be related to the construction works on the project site due to no construction vehicles were accessed from Nam Long Shan Road to Project Site since commencement of construction.

### **Notification of Summons and Successful Prosecutions**

There was no record of notification of summons and successful prosecution in the Reporting Period.

### **Reporting Changes**

There are no reporting changes.

### **Future Key Issues**

The contractor should pay attention to the following environmental issues and maintain relevant mitigation measures:

- Site formation for ride footing construction
- Cut soil slope and soil nail installation for Ride P1, P2, P3, P4 and P5
- Rock breaking and slope stabilization works for Ride P1 to P5
- Construction of drainage channels to slopes
- Mini pile construction
- Utilities diversion at A4
- Drainage works at PJD office and A4
- Backfilling at South Plant Room
- Main Building: Column and wall construction, L3 column to Roof construction, Steel Platform for Shell A construction, B1 underground manhole, drainage and on grade slab. Block works and ABWF in B1, L1 and L2 Secondary structure construction; Roof construction.
- South Transformer Room: ABWF
- South Plant Room: Construction of wall and plinths
- North Plant Room: Removal of falsework, waterproofing for double slab and ABWF
- Spiral Ramp: Falsework for the RC construction.
- External Area: Laying of underground utilities

# 1 Introduction

## 1.1 Project Background

On 27 August 2014, the Environment Impact Assessment (EIA) Report and Environmental Monitoring and Audit (EM&A) Manual (Register No.: AEIAR-184/2014) for the “Tai Shue Wan Development at Ocean Park” (the Project) was approved and an Environmental Permit (EP) (Permit No.: EP-487/2014) was issued to the Ocean Park Corporation (Project Proponent).

The current valid EP (Permit No.: EP-487/2014/A) was issued on 10 January 2018 based on the Variation of Environmental Permit No. VEP-539/2017 which comprise variation of project boundary, location of sump pit and size of rising main. The layout plan of the Project is indicated in **Appendix A**.

Mott MacDonald Hong Kong Ltd. (“MMHK”) has been commissioned by Gammon Engineering & Construction Company Limited to undertake the Environmental Team (ET) services to carry out environmental monitoring and audit for the Ocean Park Tai Shue Wan Water World Project.

As part of the EM&A program, baseline monitoring for the required parameters including background noise, landscape & visual baseline review and baseline ardeid inspection were carried out between 24 October 2014 and 10 December 2014 by the environmental consultants of Ocean Park Corporation. Furthermore, the baseline monitoring report which was verified by the previous IEC was submitted to EPD and endorsed in December 2014.

The previous contract (Contract No.: TSW-C004) of Site Formation and Foundation Works has been completed since 31 May 2017 and the next construction phase (Contract No.: TSW-C006) for the Ocean Park Tai Shue Wan Development was handed over to Gammon Engineering & Construction Company Limited on 31 May 2017.

This report summarizes the findings during the Reporting Period from 1 March to 31 May 2018.

## 2 Project Organization

### 2.1 Project Organization

The project organization is shown in **Appendix B**. The responsibilities of respective parties are as follows:

#### Ocean Park Corporation

Ocean Park Corporation is the Project Proponent and the Permit Holder of the EP for the development of the Project and will assume overall responsibility for the project. An Independent Environmental Checker (IEC) shall be employed by Ocean Park Corporation to audit the results of the EM&A works carried out by the ET.

#### Environmental Protection Department (EPD)

EPD is the statutory enforcement body for environmental protection matters in Hong Kong.

#### Project Management Representative (PMR) of Ocean Park Corporation

The PMR is responsible for overseeing the construction works and for ensuring that the works are undertaken by the Contractor in accordance with the specification and contract requirements. The duties and responsibilities of the ER with respect to EM&A are:

- Monitor the Contractors' compliance with contract specifications, including the implementation and operation of the environmental mitigation measures and their effectiveness
- Monitor Contractor's, ET's and IEC's compliance with the requirements in the Environmental Permit (EP) and EM&A Manual
- Facilitate ET's implementation of the EM&A programme
- Participate in joint site inspection by the ET and IEC
- Oversee the implementation of the agreed Event / Action Plan in the event of any exceedance
- Adhere to the procedures for carrying out complaint investigation
- Liaison with the related government departments, ET, IEC, the Contractor and the other Contractors of the Project discussing regarding the cumulative impact issues.

#### The Contractor

The duties and responsibilities of the Contractor are:

- Comply with the relevant contract conditions and specifications on environmental protection
- Employ an Environmental Team (ET) to undertake monitoring, and reporting of EM&A
- Facilitate ET's monitoring and site inspection activities
- Participate in the site inspections by the ET and IEC, and undertake any corrective actions
- Provide information / advice to the ET regarding works programme and activities which may contribute to the generation of adverse environmental impacts

- Submit proposals on mitigation measures in case of exceedances of Action and Limit levels in accordance with the Event / Action Plans
- Implement measures to reduce impact where Action and Limit levels are exceeded
- Adhere to the procedures for carrying out complaint investigation

**Environmental Team (ET)**

The ET should be employed by the Contractor to conduct the EM&A programme. The ET should be managed by the ET Leader. ET Leader should have relevant professional qualifications in environmental control and possess at least 7 years' experience in EM&A. Suitably qualified professional and technical staff should be included in the ET, and resources for the implementation of the EM&A programme should be allocated in the time under the Contract, to enable fulfilment of the Project's EM&A requirements as specified in the EM&A Manual during construction of the Project. The ET shall include qualified botanist/ecologist for the ecological service and a Registered Landscape Architect for review of implementation of landscape and visual mitigation measures. The ET should report to the OPC and the duties should include:

- to monitor and audit various environmental parameters as required in the Approved EM&A Manual;
- to analyze the EM&A data, review the success of EM&A programme and the adequacy of mitigation measures implemented, confirm the validity of the EIA predictions and identify any adverse environmental impacts arising;
- to monitor compliance with conditions in the EP, environmental protection, pollution prevention and control regulations and contract specifications;
- to audit environmental conditions on site;
- to report on the EM&A results to EPD, the ER, the IEC and Contractor or their delegated representatives;
- to recommend suitable mitigation measures to the Contractor in the case of exceedance of Action and Limit levels in accordance with the Event and Action Plans;
- to liaise with the IEC on all environmental performance matters, and ensure timely submission of all relevant EM&A pro forma for IEC's approval;
- to provide advice to the Contractor on environmental improvement, awareness and enhancement matters etc. on site;
- to adhere to the procedures for carrying out complaint investigation;
- to prepare reports on the environmental monitoring data and the site environmental conditions;
- to submit the EM&A report to Director of Environmental Protection (DEP) timely;
- to review proposals of mitigation measures from the Contractor in case of exceedance of Action and Limit levels, in accordance with the Event and Action Plan; and
- to carry out site inspection to investigate and audit the Contractor's site practice, equipment and work methodologies with respect to pollution control and mitigation measures.

**Independent Environmental Checker (IEC)**

- The IEC is empowered to audit the environmental performance of construction, but is independent from the management of construction works. As such, the IEC should not be in any way an associated body of the Contractor or the ET for the Project. The IEC should be employed by OPC prior to the commencement of the construction of the Project. The IEC

should be a person who has relevant professional qualifications in environmental control and at least 7 years' experience in EM&A and environmental management. The duties and responsibilities of the IEC are:

- to provide proactive advice to the ER and OPC on EM&A matters related to the project;
- to review and verify the monitoring data and all submissions in connection with the EP and EM&A Manual submitted by the ET;
- to arrange and conduct regular, at least monthly site inspections of the works during the construction phase, and to carry out ad hoc inspections if significant environmental problems are identified;
- to check compliance with the agreed Event and Action Plan in the event of any exceedance;
- to check compliance with the procedures for carrying out complaint investigation;
- to check the effectiveness of corrective measures;
- to feedback audit results to the ET by signing off relevant EM&A pro forma;
- to check that mitigation measures are effectively implemented;
- to report the works conducted, and the findings, recommendations and improvements of the site inspections, after reviewing ET's and Contractor's works, the ER and OPC on a monthly basis;
- to verify the investigation result of the environmental complaint cases and the effectiveness of corrective measures;
- to verify EM&A report that has been certified by ET leader; and
- to audit EIA recommendations and requirements against the status of implementation of environmental mitigation measures on site.

## 2.2 Construction Progress

During the Reporting Period, works of the Project undertaken include:

- Site formation for ride footing construction
- Cut soil slope and soil nail installation for Ride P1, P2, P3, P4 and P5
- Rock breaking and slope stabilization works for Ride P1 to P5
- Construction of drainage channels to slopes
- Mini pile construction
- Utilities diversion at A4
- Drainage works at PJD office and A4
- Backfilling at South Plant Room
- North Plant Room: Removal of falsework, waterproofing for double slab, concreting for high level slab and ABWF
- Main Building: L1 and L2 slab, column and wall construction, L3 column for Roof construction, Steel ramp for Platform construction, B1 underground manhole, drainage and on grade slab. Block works and ABWF in B1, L1 and L2 Secondary structure construction.
- South Transformer Room: Removal of falsework and ABWF
- South Plant Room: Construction of wall and plinths
- Spiral Ramp: On grade slab and Falsework for the RC construction

## 2.3 Summary of Environmental Submissions

Summaries of validity permits, licenses, and/or notifications on environmental protection for the Project are presented in **Table 1**.

**Table 1: Status of Environmental Licenses and Permits of the Project**

Type of Permit/ License	Submission Date	Reference/ License No.	Date of Issue	Date of Expiry	Status
Environmental Permit	/	EP-487/2014/A	10-Jan-18	N/A	Valid
Variation of Environmental Permit	18-Dec-17	VEP-539/2017	10-Jan-18	N/A	Valid
Environmental Permit	/	EP-487/2014	27-Aug-14	N/A	Superseded
Notification pursuant to Air Pollution Control (Construction Dust) Regulation	15-Mar-17	414651	N/A	N/A	Valid
Application for a Billing Account for Disposal of Construction Waste	14-Dec-16	Account No. 7026786	28-Dec-16	N/A	Valid
Discharge Licence under WPCO WT00028196-2017	15-Mar-17	414650	29-May-17	31-May-22	Valid
Registration as a Chemical Waste Producer (WPN: 5213-176- G2785-01)	21-Apr-17	415966	31-May-17	N/A	Completed
Construction Noise Permit under NCO GW-RS0439-17	26-Apr-17	416080	15-May-17	29-Dec-17	Superseded
Construction Noise Permit under NCO GW-RS0825-17	8-Sep-17	420985	22-Sep-17	21-Mar-18	Superseded
Renew Construction Noise Permit under NCO GW-RS1024-17	3-Nov-17	422922	21-Nov-17	16-May-18	Superseded
Renew Construction Noise Permit under NCO GW-RS0356-18	16-Apr-18	432628	30-Apr-18	16-Nov-18	Valid

According to the EP stipulation, the required documents have been submitted to EPD for retention as listed below:

- Project Layout Plans
- Management Organization of Main Construction Companies
- Detailed Vegetation Survey Report
- Woodland Compensation Plan

- Ardeid Inspection Report
- Short-nosed Fruit Bat Inspection Report
- Baseline Monitoring Report Revision A of the Project

# 3 Summary of Environmental Monitoring and Audit Requirements

## 3.1 General

As specified in the approved EM&A Manual, environmental monitoring of construction noise, ecology, landscape and visual impacts as well as waste management are required. A summary of the monitoring parameters is presented in **Table 2**.

**Table 2: Summary of Impact EM&A Requirements**

Parameters	Description	Locations	Frequency
Construction Noise	<ul style="list-style-type: none"> <li>● <math>L_{eq}</math> (30min) on normal working days</li> <li>● 3 sets of consecutive <math>L_{eq}</math>(5min) during restricted hours if construction is necessary</li> <li>● Supplementary information for data auditing, statistical results such as <math>L_{10}</math> and <math>L_{90}</math> shall also be obtained for reference</li> </ul>	NM1A and NM2	<p>Weekly Normal working days: (07:00-19:00 except public holiday)</p> <p>Restricted hours: 19:00 to 07:00 next day, and whole day of public holiday or Sunday only when construction is necessary</p>
Ecology	<ul style="list-style-type: none"> <li>● Monitoring of in-situ preservation of <i>Platycodon grandifloras</i></li> <li>● Inspection of ardeids nest during breeding season (April to July)</li> <li>● Monitoring for ardeid night roost (November to March)</li> <li>● Inspection of enhancement area for ardeid roosting</li> <li>● Monitoring on woodland compensation</li> </ul>	Project area and preservation area for <i>Platycodon grandifloras</i>	<p>Once per month</p> <p>An enhancement area provided as an alternative roosting site for ardeids should be developed during the first phase of the construction.</p> <p>Mitigation measures recommended in the approved Woodland Compensation Plan should be fully and properly implemented, including but not limited to the creation of 0.84 ha woodland compensation on-site and 0.78 ha on-site woodland reinstatement, to mitigate for permanent loss of woodland habitat.</p>

Parameters	Description	Locations	Frequency
Landscape & Visual Impact	<ul style="list-style-type: none"> <li>● Ensure no construction activities / storage are undertaken outside the project boundary</li> <li>● Ensure landscaping works are carried out in accordance with the specifications</li> <li>● Ensure new planting is carried out properly and during the right season</li> <li>● Review progress of engineering works on site to identify the earliest practical opportunities for landscape works</li> </ul>	Project site	Bi-weekly
Regular Site Inspection Air, water, waste management	To review the environmental situation, and monitor the implementation of proper environmental protection and pollution control measures for the Project	Project site	Weekly

### 3.2 Monitoring Locations

Two designated noise monitoring locations as established in the EM&A Manual are shown in **Appendix C**. After the baseline monitoring, alternative location NM1A was proposed by MMHK due to the rejection of the monitoring location set up at NM1. The proposal was verified and agreed by EPD in the Baseline Monitoring Report. The construction noise monitoring locations for the Project are shown in **Table 3** and **Appendix D**.

**Table 3: Impact Monitoring Stations for Construction Noise**

Monitoring location	Descriptions	Type of measurement
NM1A	Slope near Victoria Shanghai Academy (VSA) to replace NM1 of the VSA	Free field
NM2	Hong Kong Juvenile Care Centre (HKJCC)	Facade

### 3.3 Derivation of Action/Limit Levels

The baseline results formed the basis for determining the environmental acceptance criteria for impact monitoring. According to the approved EM&A Manual and baseline monitoring results, the following construction noise criterion, namely Action and Limit levels listed in **Table 4** were proposed:

**Table 4: Action and Limit Levels for Construction Noise**

Monitoring Location	Action Level	Limit Level in dB(A)
<b>Time Period: 0700-1900 hours on normal weekdays</b>		
NM1A and NM2	When one or more documented complaints are received	70 dB(A)*

Note: Acceptable Noise Levels for school should be reduced to 65 dB(A) during examination period. If works are to be carried out during restricted hours, the conditions stipulated in the construction noise permit issued by the NCA must be followed.

### 3.4 Meteorological Information

Meteorological information including humidity, wind speed, wind direction, temperature and total rainfall was extracted from “the Hong Kong Observatory Wong Chuk Hang Station” to provide background weather information. The meteorological data for the Reporting Period is summarized in **Appendix E**.

# 4 Construction Noise Monitoring

## 4.1 Monitoring Results

Construction noise monitoring was conducted 26 times at the two designated locations in the Reporting Period. As shown in the summary of noise monitoring results in **Table 5**, the noise monitoring measurement were below 65 dB(A) and 70 dB(A) during the examination period from 5 to 16 March 2018. No Limit Level exceedance was recorded during the school examination period.

A total of two noise complaints were received in this Reporting Period regarding noise impact at night time. On 3 March 2018, the complaint was about noise from the construction work and construction vehicles during restricted hours. The other complaint on 16 March 2018 was about traffic noise by construction vehicles in Nam Long Sha Road from 1 a.m. to 4 a.m.

No exceedance (Action/Limit Level) of construction noise was recorded in this period.

**Table 5: Summary of Construction Noise Monitoring Results (Noise level for 30 minutes)**

Monitoring Date	Time		Mean and range of noise levels, dB(A)		Limit Level for L <sub>eq</sub> (dB(A)) <sup>2</sup>
	Start	Finish	L <sub>eq</sub> (30min)	Corrected L <sub>eq</sub> (30min) <sup>1</sup>	
<b>NM1A</b>					
07-Mar-18	09:42	10:12	56.2	59.2	65
13-Mar-18	10:00	10:30	54.0	57.0	65
21-Mar-18	10:23	10:53	55.3	58.3	70
29-Mar-18	10:10	10:40	55.7	58.7	70
04-Apr-18	09:42	10:12	55.6	58.6	70
10-Apr-18	09:40	10:10	55.6	58.6	70
19-Apr-18	11:10	11:40	55.9	58.9	70
26-Apr-18	10:22	10:52	56.7	59.7	70
02-May-18	09:02	09:32	56.6	59.6	70
08-May-18	10:18	10:48	56.8	59.8	70
17-May-18	10:12	10:42	56.1	59.1	70
24-May-18	10:10	10:40	56.4	59.4	70
30-May-18	08:42	09:12	56.6	59.6	70
<b>NM2</b>					
07-Mar-18	10:50	11:20	53.1	-	65
13-Mar-18	09:20	09:50	51.8	-	65
21-Mar-18	09:42	10:12	53.4	-	70

Monitoring Date	Time		Mean and range of noise levels, dB(A)		Limit Level for L <sub>eq</sub> (dB(A)) <sup>2</sup>
	Start	Finish	L <sub>eq</sub> (30min)	Corrected L <sub>eq</sub> (30min) <sup>1</sup>	
29-Mar-18	09:30	10:00	52.5	-	70
04-Apr-18	09:21	09:51	52.2	-	70
10-Apr-18	10:30	11:00	52.1	-	70
19-Apr-18	10:30	11:00	51.2	-	70
26-Apr-18	09:40	10:10	51.7	-	70
02-May-18	10:35	11:05	51.6	-	70
08-May-18	09:40	10:10	53.0	-	70
17-May-18	09:30	10:00	52.1	-	70
24-May-18	09:30	10:00	53.5	-	70
30-May-18	10:30	11:00	51.4	-	70

Note: 1. A correction of +3 dB(A) was made to the free field measurement at monitoring station NM1A.

2. Acceptable Noise Levels for school should be reduced to 65 dB(A) during examination period.

As shown in **Table 6**, results of the additional noise monitoring measurement were below 70 dB(A). No exceedance (Action/Limit Level) of construction noise was thus recorded in this period.

**Table 6: Summary of Construction Noise Monitoring Results (Noise level for 15 minutes)**

Monitoring date	Time		Mean and range of noise levels, dB(A)		Limit Level for L <sub>eq</sub> (dB(A)) <sup>2</sup>
	Start	Finish	L <sub>eq</sub> (15min)	Corrected L <sub>eq</sub> (15min) <sup>1</sup>	
<b>NM1A</b>					
11-Mar-18	13:44	13:59	49.5	52.5	65
18-Mar-18	10:30	10:45	51.5	54.5	70
25-Mar-18	17:00	17:15	49.7	52.7	70
01-Apr-18	17:20	17:35	54.4	57.4	70
08-Apr-18	10:29	10:44	52.6	55.6	70
15-Apr-18	16:40	16:55	51.6	54.6	70
22-Apr-18	14:28	14:43	50.8	53.8	70
29-Apr-18	16:28	16:43	51.4	54.4	70
06-May-18	16:35	16:50	51.4	54.4	70
13-May-18	14:45	15:00	49.4	52.4	70
20-May-18	15:40	15:55	50.7	53.7	70
27-May-18	13:30	13:45	51.5	54.5	70
<b>NM2</b>					
11-Mar-18	13:13	13:28	48.8	-	65
18-Mar-18	10:00	10:15	45.2	-	65
25-Mar-18	16:35	16:50	45.4	-	65
01-Apr-18	16:52	17:07	49.3	-	65
08-Apr-18	10:01	10:16	48.7	-	65

Monitoring date	Time	Mean and range of noise levels, dB(A)		Limit Level for L <sub>eq</sub> (dB(A)) <sup>2</sup>		
		Start	Finish			
				L <sub>eq</sub> (15min)	Corrected L <sub>eq</sub> (15min) <sup>1</sup>	Limit Level for L <sub>eq</sub> (dB(A)) <sup>2</sup>
15-Apr-18	17:08	17:23		48.3	-	65
22-Apr-18	14:00	14:15		46.1	-	65
29-Apr-18	16:00	16:15		48.2	-	65
06-May-18	16:10	16:25		48.5	-	65
13-May-18	14:20	14:35		46.1	-	65
20-May-18	15:10	15:25		47.5	-	65
27-May-18	13:05	13:20		48.5	-	65

Note: 1. A correction of +3dB(A) was made to the free field measurement at monitoring station NM1A.  
 2. Technical memorandum on noise from construction work other than percussive piling – Section 4 Table 2.

A summary of data and the supplementary data auditing information are shown in **Appendix F**. Graphical plots of the monitoring data are shown in **Appendix G**.

## 5 Ecology Monitoring

### 5.1 Inspection Findings

The ecological inspections were undertaken on 16 March, 13 April, 11 May 2018 by the qualified ecologist. The inspection findings are presented below.

#### Plants of Conservation Interest (*Platycodon grandiflorus*)

*Platycodon grandiflorus* is a perennial herb up to 120 cm high. Stems erect and scarcely any branches. It is often found on sunny grassy hillslopes in brushes. Two groups of *Platycodon grandiflorus* were recorded in 2015's growing season within the fenced area.

On the other hand, the preventive mitigation measures, i.e., erecting of temporary protective fencing and sign post, were found to be effectively implemented for human disturbance, and there are no signs or evidence (e.g. dust coating of plant) to prove that the on-going construction activities within the project area has affected the health condition of the *Platycodon grandiflorus*.

#### Nesting Activities of Ardeids in Breeding Season

No signs or breeding (such as courtship, nest building, brooding, juveniles etc.) of ardeids were noted within the project area during the reporting period.

#### Roosting Activities of Ardeids in Peak Wintering Season

According to the Approved EM&A Manual, monitoring of roosting activities of Ardeids within the project area should perform once a month during peak wintering season (November to March) during the construction phase.

Monitoring of roosting activities of ardeids has been carried out by direct observation at the vantage point on 16 March 2018, and covered the evening from an hour before sunset to nightfall (17:40 to 19:40).

No ardeids were noted within or in the vicinity of the project area during the monitoring period.

#### Compensation for Ardeid roosting Site

To be implemented.

#### Compensation of Woodland Habitat

To be implemented.

### 5.2 Conclusion

The implementation of the mitigation measures for the plant species of conservation interest, i.e., erecting of temporary protective fencing and sign post during the Reporting Period was noted. The two groups of *Platycodon grandiflorus* within the fenced area were found to be vigorous and all new branches were in healthy condition.

On the other hand, no sighting of ardeids or signs of any breeding/nesting activities were noted within the project area during the monitoring.

Roosting activities of ardeids was not observed within the project area during the monitoring.

# 6 Landscape and Visual Monitoring

## 6.1 Inspection Findings

In the Reporting Period, bi-weekly landscape and visual site inspection were conducted on 9, 23 March, 6, 20 April and 4, 18 May 2018.

According to the bi-weekly site inspections, it was observed that the Contractor complied with the intended aims of the mitigation measures. For example, construction activities were not conducted and materials storage were not placed outside of the working site boundary. The Contractor was advised to improve and maintain the tree protection zone.

# 7 Waste Management

## 7.1 Record of Waste Quantities

The quantity of waste for disposal in this Reporting Period is summarized in **Table 7** and **Table 8**.

**Table 7: Summary of Quantities of Inert C&D Materials**

Type of Waste	Quantity (tonne)		
	Total Generated C&D Materials	Total Disposal as Public Fill	Total Reused
March 2018	5196.18	4526.18	670.00
April 2018	5322.94	4810.94	512.00
May 2018	3197.41	1897.41	1300.00
Total	13716.53	11234.53	2482.00

**Table 8: Summary of Quantities of Non-inert C&D Materials**

Type of Waste	Quantity (tonne)				
	Recycled Metal	Recycled Paper / Cardboard Packing	Recycled Plastic	Disposed Chemical Wastes	Disposed General Refuses
March 2018	100.00	271.00	0.00	0.00	234.16
April 2018	1000.00	231.00	0.00	0.00	163.40
May 2018	0	101.00	0.00	0.00	287.39
Total	1100.00	603.00	0.00	0.00	684.95

# 8 Site Inspection

## 8.1 Inspection Findings

In the Reporting Period, joint site inspections were undertaken by the PMR, ET and the Contractor on 2, 9, 16, 23 and 29 March, 6, 13, 20 and 27 April as well as 4, 11, 18 and 25 May 2018. Furthermore, site inspection and audit were performed by the IEC on 16 March, 13 April and 11 May 2018. During the site inspections, non-compliance was not observed by ET and IEC. The site observations for the Reporting Period is summarized in **Table 9**.

**Table 9: Site Observations of the Project**

Reporting Period	Findings / Deficiencies
March 2018	<ul style="list-style-type: none"> <li>● Chemical containers observed without drip tray.</li> <li>● Access road in Area 1 observed dry and dusty. Contractor was reminded to enhance dust suppression measures i.e. water spraying.</li> <li>● Flap door of air compressor should be closed when in use.</li> <li>● Oil / chemical containers observed without drip tray (L2 slab).</li> <li>● Contractor is reminded to improve dust suppression at Access Road near site office.</li> <li>● Oil containers observed without drip tray at EVA and B1 Area A.</li> <li>● Stagnant water filled with algae observed at the side of Level 1 haul road should be cleared.</li> </ul>
April 2018	<ul style="list-style-type: none"> <li>● Fugitive dust was observed, appropriate mitigation measures should be undertaken.</li> <li>● Chemical and oil containers observed without drip tray at L1 corridor next to EVA, at L2 next to EVA and L3.</li> <li>● Oil container observed without drip tray at L2 grout station</li> </ul>
May 2018	<ul style="list-style-type: none"> <li>● Mitigation measure for fugitive dust should be enhanced.</li> <li>● Chemical containers observed without drip tray at 10E4.</li> <li>● Some chemicals stored in water bottles were found in a drip tray on L3. Appropriate chemical containers should be provided for the chemicals.</li> <li>● Stagnant water was observed near the toilet at 1/F zone B and the contractor shall clear the stagnant water properly.</li> </ul>

# 9 Summary of Environmental Quality Performance Limits

## 9.1 Record on Non-compliance of Action and Limit Levels

No exceedances of Action level or Limit levels were observed for construction noise during the Reporting Period.

## 9.2 Record on Environmental Complaints Received

The complaints received in relation to the environmental impact during March 2018 was investigated as follows:

Case 1: The complaint was about noise generated by construction equipment and construction vehicles movement at midnight from the construction site of Ocean Park Tai Shue Wan Water World Project.

Result of investigation:

As informed by the Contractor:

- As Shum Wan Road, the only access to the construction site, experienced congested traffic during daytime, the planned concreting works had been extended beyond 19:00.
- Referring to the information provided by the site team, no works was carried out during the incident period.
- It is noted that the Contractor obtained a valid Construction Noise Permit (CNP No. CW-RS1024-17) permitting the use certain powered mechanical equipment (PME) including PME for concreting works during restricted hours between 23 November 2017 and 16 May 2018. The listed PME and no. of units have been strictly followed to CNP.

This complaint is unlikely to be related to the construction works on the project site due to no construction works was carried out during the incident period.

Case 2: The complaint was about traffic noise at Nam Long Shan Road related to Ocean Park night time operation.

According to the complainant, construction vehicles travelled along Nam Long Shan Road in the direction of Ocean Park for the past few years between the hours of 01:00 and 04:00.

Furthermore, the complaint suspect that some of the vehicles were garbage trucks but according to FEHD's reply, no garbage pick-up was conducted during this period.

Result of investigation:

As informed by the Contractor:

- No construction vehicles were accessed from Nam Long Shan Road to Project Site since the commencement of this contract (TSW-C006).

- The site entrance at Nam Long Shan Road leading to the upper part of the sewage rising main under this project. However, there are no night works for this area since the commencement of this contract (TSW-C006).

Based on the above information, the complaint is considered unlikely to be related to the construction works at the project site.

# 10 Implementation Status of Mitigation Measures

## 10.1 General Requirements

The environmental mitigation measures that were recommended in the Implementation Schedule for Environmental Mitigation Measures in the approved EM&A Manual covered the issues of dust, noise, water and waste and are presented in **Appendix H**.

Environmental mitigation measures generally implemented by the contractor are listed in **Table 10**.

**Table 10: Environmental Mitigation Measures**

Issues	Environmental Mitigation Measures
Construction Noise	<ul style="list-style-type: none"> <li>Construction equipment is shut down when not in use</li> </ul>
Ecology	<ul style="list-style-type: none"> <li>Wire fencing was provided for temporary protection of the identified flora species of conservation concern</li> <li>Site inspection of the flora species of conservation and the Ardeid breeding and nesting activities was undertaken</li> </ul>
Landscape & Visual	<ul style="list-style-type: none"> <li>Good site management</li> </ul>
Air Quality	<ul style="list-style-type: none"> <li>Good site management to reduce air quality impact</li> <li>Main temporary access road paved with concrete</li> <li>Prior to any loading or transfer operation, all dusty materials were sprayed with water to keep them wet</li> <li>All debris had been covered entirely by impervious sheeting</li> <li>Before debris was dumped into a chute, water was sprayed onto the debris to make them wet</li> <li>Vehicles were covered with tarpaulin during transport of dusty materials</li> <li>When vehicles were leaving the construction site, any vehicles loaded with dusty materials were covered with clean impervious sheeting to prevent fugitive dusty material emission</li> <li>The speed of the trucks passing site areas was controlled to below 10 km/hour</li> <li>Water spraying was provided for soil-nailing work</li> </ul>
Water Quality	<ul style="list-style-type: none"> <li>Portable chemical toilets were provided on site</li> <li>A licensed collector has been employed to collect effluent and off-site dispose.</li> </ul>
Waste and Chemical Management	<ul style="list-style-type: none"> <li>A temporary container located far away from sea shore and drainage channel was provided for chemical materials and waste storage</li> <li>Drip tray was provided for chemical materials at the working areas</li> </ul>

<b>Issues</b>	<b>Environmental Mitigation Measures</b>
General	<ul style="list-style-type: none"><li>● Waste skip was provided for general refuse disposal</li><li>● The site was generally kept tidy and clean</li></ul>

# 11 Conclusions and Recommendations

## 11.1 Conclusions

The EM&A programme as recommended in the EM&A manual has been undertaken in the Reporting Period.

Monitoring of construction noise, ecology, landscape and visual, as well as waste management for the Project were conducted as scheduled in the Reporting Period. Data collected during construction noise monitoring were checked against the established Action and Limit levels and no exceedances were recorded.

For ecological monitoring, the implementation of the mitigation measures for the plant species of conservation interest, i.e., erecting of temporary protective fencing and sign post during the Reporting Period was noted. The two groups of *Platycodon grandiflorus* within the fenced area were found to be vigorous and all new branches were in healthy condition.

No sighting of ardeids or signs of any breeding/nesting activities were noted within the project area during the monitoring.

Roosting activities of ardeids were not observed within the project area during the monitoring.

For landscape and visual monitoring, the Contractor was advised to maintain the tidiness, carry out regular weeding in the tree protection zone.

## 11.2 Recommendations


With considerations on the construction activities and environment, the following reminders and recommendations were provided:

- Dust mitigation measures for potential fugitive dust impact should be implemented.
- Noise mitigation measures, including the use of quiet plants, should be implemented in accordance with the EM&A requirement.
- Cleanliness and tidiness in construction site should be enhanced.

# Appendices


A. Layout Plan of the Project	26
B. Project Organization	27
C. Designated Monitoring Locations as Recommended in the Approved EM&A Manual	28
D. Actual Locations of Impact Monitoring	29
E. Meteorological Data	30
F. Noise Monitoring Data	31
G. Graphical Plots of Noise Monitoring Data	32
H. Implementation Schedule for Environmental Mitigation Measures	33

## A. Layout Plan of the Project



Notes													
Key to symbols													
Project Boundary 項目範圍													
Reference drawings													
<table border="1"> <thead> <tr> <th>Rev</th><th>Date</th><th>Drawn</th><th>Description</th><th>Chkd</th><th>Appd</th></tr> </thead> <tbody> <tr> <td>M</td><td>M</td><td>MOTT MACDONALD</td><td>20/F AIA Kowloon Tower Landmark East 100 How Ming Street Kwun Tong, Kowloon Hong Kong T +852 2828 5757 F +852 2827 1923 W mottmac.com</td><td></td><td></td></tr> </tbody> </table>		Rev	Date	Drawn	Description	Chkd	Appd	M	M	MOTT MACDONALD	20/F AIA Kowloon Tower Landmark East 100 How Ming Street Kwun Tong, Kowloon Hong Kong T +852 2828 5757 F +852 2827 1923 W mottmac.com		
Rev	Date	Drawn	Description	Chkd	Appd								
M	M	MOTT MACDONALD	20/F AIA Kowloon Tower Landmark East 100 How Ming Street Kwun Tong, Kowloon Hong Kong T +852 2828 5757 F +852 2827 1923 W mottmac.com										
Client													
Project													
<b>TAI SHUE WAN DEVELOPMENT AT OCEAN PARK</b>													
Title													
<b>PROJECT LOCATION</b>													
<table border="1"> <thead> <tr> <th>Designed</th><th>Eng check</th><th></th></tr> </thead> <tbody> <tr> <td>Drawn</td><td>Coordination</td><td></td></tr> <tr> <td>Dwg check</td><td>Approved</td><td></td></tr> <tr> <td>Scale at A1</td><td>Status</td><td>Rev</td></tr> </tbody> </table>		Designed	Eng check		Drawn	Coordination		Dwg check	Approved		Scale at A1	Status	Rev
Designed	Eng check												
Drawn	Coordination												
Dwg check	Approved												
Scale at A1	Status	Rev											
Drawing Number													
<b>APPENDIX A</b>													


## B. Project Organization




### Contact information:

Company / Department	Position	Name	Telephone / Fax No. Mobile	
Ocean Park Corporation	Project Management Representative	Mr Augustine Li	2870 6130	2814 0179
Ove Arup & Partners Hong Kong Ltd.	Independent Environmental Checker	Mr Gerald Kam	2268 3915	2268 3950
Mott MacDonald Hong Kong Ltd.	Environmental Team Leader	Mr Gary Chow	2828 5874	2827 1823
Mott MacDonald Hong Kong Ltd.	Qualified Ecologist	Mr Roy Hung	2828 5965	2827 1823
Gammon Engineering & Construction Company Limited	Construction Manager	Mr Paul Leaver	3690 9229	2148 2890
Gammon Engineering & Construction Company Limited	Environmental Officer	Ms Michelle Tang	-	2148 2890

## **C. Designated Monitoring Locations as Recommended in the Approved EM&A Manual**



## D. Actual Locations of Impact Monitoring



Notes																								
<b>Key to symbols</b>																								
<ul style="list-style-type: none"> <li>NOISE MONITORING STATION</li> <li>300m ASSESSMENT AREA</li> <li>REVISED PROJECT BOUNDARY</li> <li>ADDITIONAL WORKS AREA AT SHUM WAN ROAD</li> <li>EXISTING NOISE SENSITIVE RECEIVER</li> <li>PLANNED NOISE SENSITIVE RECEIVER</li> <li>NOTIONAL SOURCE POSITION</li> </ul>																								
<table border="1"> <thead> <tr> <th>NSRID</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td>VSA</td> <td>VICTORIA SHANGHAI ACADEMY</td> </tr> <tr> <td>HKJCC</td> <td>HONG KONG JUVENILE CARE CENTRE</td> </tr> <tr> <td>BC</td> <td>BROADVIEW COURT</td> </tr> <tr> <td>SWC</td> <td>SOUTH WAVE COURT</td> </tr> <tr> <td>WCH</td> <td>PLANNED DEVELOPMENT ON WONG CHUK HANG STATION DEPOT</td> </tr> <tr> <td>GG</td> <td>GRANDVIEW GARDEN</td> </tr> </tbody> </table>	NSRID	DESCRIPTION	VSA	VICTORIA SHANGHAI ACADEMY	HKJCC	HONG KONG JUVENILE CARE CENTRE	BC	BROADVIEW COURT	SWC	SOUTH WAVE COURT	WCH	PLANNED DEVELOPMENT ON WONG CHUK HANG STATION DEPOT	GG	GRANDVIEW GARDEN										
NSRID	DESCRIPTION																							
VSA	VICTORIA SHANGHAI ACADEMY																							
HKJCC	HONG KONG JUVENILE CARE CENTRE																							
BC	BROADVIEW COURT																							
SWC	SOUTH WAVE COURT																							
WCH	PLANNED DEVELOPMENT ON WONG CHUK HANG STATION DEPOT																							
GG	GRANDVIEW GARDEN																							
<b>Reference drawings</b>																								
<table border="1"> <tbody> <tr> <td>P4</td> <td>NOV 17</td> <td>MING</td> <td>FOURTH ISSUE</td> <td>HL</td> <td>EC</td> </tr> <tr> <td>P3</td> <td>NOV 17</td> <td>MING</td> <td>THIRD ISSUE</td> <td>HL</td> <td>EC</td> </tr> <tr> <td>P2</td> <td>AUG 17</td> <td>TSE</td> <td>SECOND ISSUE</td> <td>HL</td> <td>EC</td> </tr> <tr> <td>P1</td> <td>JUL 17</td> <td>TSE</td> <td>FIRST ISSUE</td> <td>HL</td> <td>EC</td> </tr> </tbody> </table> <p>Rev Date Drawn Description Chk'd App'd</p>	P4	NOV 17	MING	FOURTH ISSUE	HL	EC	P3	NOV 17	MING	THIRD ISSUE	HL	EC	P2	AUG 17	TSE	SECOND ISSUE	HL	EC	P1	JUL 17	TSE	FIRST ISSUE	HL	EC
P4	NOV 17	MING	FOURTH ISSUE	HL	EC																			
P3	NOV 17	MING	THIRD ISSUE	HL	EC																			
P2	AUG 17	TSE	SECOND ISSUE	HL	EC																			
P1	JUL 17	TSE	FIRST ISSUE	HL	EC																			
<b>M</b> MOTT MACDONALD 20/F AIA Kowloon Tower Landmark East 100 How Ming Street Kwun Tong, Kowloon Hong Kong T +852 3828 5757 F +852 2827 1823 W mottmac.com																								
<b>Client:</b> Ocean Park Hong Kong																								
<b>Project:</b> TAI SHUE WAN DEVELOPMENT AT OCEAN PARK																								
<b>Title:</b> ACTUAL LOCATION OF IMPACT MONITORING																								
<table border="1"> <thead> <tr> <th>Designed</th> <th>HL</th> <th>Eng check</th> <th>JC</th> </tr> </thead> <tbody> <tr> <td>Drawn</td> <td>MING</td> <td>Coordination</td> <td>HC</td> </tr> <tr> <td>Dwg check</td> <td>HL</td> <td>Approved</td> <td>EC</td> </tr> </tbody> </table>	Designed	HL	Eng check	JC	Drawn	MING	Coordination	HC	Dwg check	HL	Approved	EC												
Designed	HL	Eng check	JC																					
Drawn	MING	Coordination	HC																					
Dwg check	HL	Approved	EC																					
Scale at A1 1:4000 Status PRE Rev P4																								
Drawing Number APPENDIX E																								

## E. Meteorological Data

### Weather Conditions - March 2018

Date		Mean Air Temperature (°C)	Mean Relative Humidity (%)	Mean Wind Speed (km/h)	Prevailing Wind Direction (degrees)
Thu	01-Mar-18	20.8	85	4.4	110
Fri	02-Mar-18	22.1	76	6.1	120
Sat	03-Mar-18	23	85	3.9	120
Sun	04-Mar-18	23.6	89	4.2	100
Mon	05-Mar-18	24.4	86	2.9	110
Tue	06-Mar-18	19.3	82	9.7	40
Wed	07-Mar-18	19.6	76	7.3	70
Thu	08-Mar-18	14.7	75	9.4	350
Fri	09-Mar-18	13.9	60	7.5	340
Sat	10-Mar-18	16.1	62	7.2	80
Sun	11-Mar-18	18	65	7.6	70
Mon	12-Mar-18	19.4	68	4.8	130
Tue	13-Mar-18	20.6	77	4.3	120
Wed	14-Mar-18	20.8	82	5.8	70
Thu	15-Mar-18	21.4	85	2.8	110
Fri	16-Mar-18	21.4	83	2.5	50 <sup>#</sup>
Sat	17-Mar-18	19.5	81	14.5	80
Sun	18-Mar-18	21.5	78	5.8	50
Mon	19-Mar-18	22.9	84	4.7	120
Tue	20-Mar-18	21.2	67	8.2	340
Wed	21-Mar-18	17.8	48	8.6	350
Thu	22-Mar-18	18.6	53	6.8	60
Fri	23-Mar-18	19.9	62	6.5	70
Sat	24-Mar-18	21.3	72	10	70
Sun	25-Mar-18	21.6	66	10.8	70
Mon	26-Mar-18	21.9	71	4.7	140
Tue	27-Mar-18	21.6	75	3.5	130
Wed	28-Mar-18	21.9	76	5.7	60
Thu	29-Mar-18	22.5	74	5.3	120
Fri	30-Mar-18	23.2	71	7.6	120
Sat	31-Mar-18	23.2	61	10.5	70

# Incomplete data

\*\*\* Data unavailable

### Weather Conditions - April 2018

Date		Mean Air Temperature (°C)	Mean Relative Humidity (%)	Mean Wind Speed (km/h)	Prevailing Wind Direction (degrees)
Sun	01-Apr-18	22.7	69	5.1	130
Mon	02-Apr-18	22.3	74	4.4	130
Tue	03-Apr-18	23.0	77	4.3	120
Wed	04-Apr-18	23.4	79	5.5	120
Thu	05-Apr-18	23.5	78	5.2	130
Fri	06-Apr-18	21.7	70	9.3	360
Sat	07-Apr-18	17.8	36	11.3	110
Sun	08-Apr-18	18.7	51	5.1	130
Mon	09-Apr-18	21.3	74	5.8	120
Tue	10-Apr-18	22.9	77	5.1	120
Wed	11-Apr-18	24.0	82	5.0	130
Thu	12-Apr-18	24.9	82	5.4	120
Fri	13-Apr-18	25.7	82	7.3	110
Sat	14-Apr-18	25.8	82	4.8	120
Sun	15-Apr-18	21.4	80	5.8	320
Mon	16-Apr-18	18.7	83	3.8	330
Tue	17-Apr-18	20.0	78	3.5	60
Wed	18-Apr-18	22.2	75	5.9	70
Thu	19-Apr-18	23.0	70	6.5	60
Fri	20-Apr-18	23.4	79	10.3	80
Sat	21-Apr-18	24.8	77	9.3	80
Sun	22-Apr-18	25.4	81	6.3	120
Mon	23-Apr-18	25.7	81	5.2	120
Tue	24-Apr-18	24.4	88	2.0	120
Wed	25-Apr-18	23.1	81	5.3	60
Thu	26-Apr-18	23.4	79	6.6	70
Fri	27-Apr-18	25.1	75	3.6	160
Sat	28-Apr-18	24.4	81	8.0	70
Sun	29-Apr-18	25.5	78	6.1	120
Mon	30-Apr-18	26.1	82	6.0	120

# Incomplete data

\*\*\* Data unavailable

### Weather Conditions - May 2018

Date		Mean Air Temperature (°C)	Mean Relative Humidity (%)	Mean Wind Speed (km/h)	Prevailing Wind Direction (degrees)
Tue	01-May-18	26.4	83	4.7	120
Wed	02-May-18	27.1	79	4.4	210
Thu	03-May-18	26.0 <sup>#</sup>	83 <sup>#</sup>	9.8 <sup>#</sup>	80 <sup>#</sup>
Fri	04-May-18	23.9	78	14.4	80
Sat	05-May-18	25.6	79	9.7	80
Sun	06-May-18	26.6	84	6.5	110
Mon	07-May-18	27.1	87	6.7	20
Tue	08-May-18	24.7	91	3.3	210
Wed	09-May-18	24.6	85	13.6	80
Thu	10-May-18	23.2	85	18.7	80
Fri	11-May-18	24.4	80	10.0	80
Sat	12-May-18	26.0	80	4.9	130
Sun	13-May-18	26.5	84	3.9	220
Mon	14-May-18	27.6	83	4.9	220
Tue	15-May-18	27.8	81	7.1	110
Wed	16-May-18	27.6	77	6.3	120
Thu	17-May-18	28.2	80	4.1	230
Fri	18-May-18	28.9	79	3.8	210
Sat	19-May-18	29.0	78	4.5	210
Sun	20-May-18	29.0	77	4.3	210
Mon	21-May-18	28.6	78	4.7	120
Tue	22-May-18	28.9	73	4.6	130
Wed	23-May-18	29.6	72	5.0	220
Thu	24-May-18	29.1	74	6.8	120
Fri	25-May-18	28.9	74	5.0	120
Sat	26-May-18	29.9	74	5.5	230
Sun	27-May-18	29.5	77	5.7	220
Mon	28-May-18	29.8	71	5.6	280
Tue	29-May-18	30.6	71	5.8	220
Wed	30-May-18	30.5	72	5.7	220
Thu	31-May-18	30.2	71	5.9	220

# Incomplete data

\*\*\* Data unavailable

## F. Noise Monitoring Data

**Noise Monitoring Data - Summary of Construction Noise Monitoring Results, dB(A)**

<b>NM1A - Slope near the Victoria Shanghai Academy</b>						
Date	Time		Noise Levels, dB(A)			Limit Level for L <sub>eq</sub> (dB(A)) <sup>(2)</sup>
	Start	Finish	Corrected L <sub>eq</sub> (30min) <sup>(1)</sup>	Corrected L <sub>90</sub> <sup>(1)</sup>	Corrected L <sub>10</sub> <sup>(1)</sup>	
07-Mar-18	09:42	10:12	59.2	57.0	60.9	65
13-Mar-18	10:00	10:30	57.0	54.3	58.5	65
21-Mar-18	10:23	10:53	58.3	56.5	60.0	70
29-Mar-18	10:10	10:40	58.7	56.5	60.2	70
04-Apr-18	09:42	10:12	58.6	56.6	60.7	70
10-Apr-18	09:40	10:10	58.6	56.9	60.2	70
19-Apr-18	11:10	11:40	58.9	57.1	60.4	70
26-Apr-18	10:22	10:52	59.7	57.3	61.3	70
02-May-18	09:02	09:32	59.6	57.5	61.2	70
08-May-18	10:18	10:48	59.8	57.7	61.4	70
17-May-18	10:12	10:42	59.1	57.3	60.7	70
24-May-18	10:10	10:40	59.4	57.4	61.1	70
30-May-18	08:42	09:12	59.6	57.6	61.2	70

<b>NM2 - Hong Kong Juvenile Care Centre</b>						
Date	Time		Noise Levels, dB(A)			Limit Level for L <sub>eq</sub> (dB(A)) <sup>(2)</sup>
	Start	Finish	L <sub>eq</sub> (30min)	L <sub>90</sub>	L <sub>10</sub>	
07-Mar-18	10:50	11:20	53.1	51.5	54.6	65
13-Mar-18	09:20	09:50	51.8	48.4	54.0	65
21-Mar-18	09:42	10:12	53.4	51.9	54.9	70
29-Mar-18	09:30	10:00	52.5	51.1	54.0	70
04-Apr-18	09:21	09:51	52.2	48.3	54.7	70
10-Apr-18	10:30	11:00	52.1	50.6	53.7	70
19-Apr-18	10:30	11:00	51.2	49.5	52.7	70
26-Apr-18	09:40	10:10	51.7	50.0	53.2	70
02-May-18	10:35	11:05	51.6	50.3	53.1	70
08-May-18	09:40	10:10	53.0	51.5	54.5	70
17-May-18	09:30	10:00	52.1	50.4	53.6	70
24-May-18	09:30	10:00	53.5	52.0	55.1	70
30-May-18	10:30	11:00	51.4	50.0	53.0	70

**NM1A - Slope near the Victoria Shanghai Academy**

Date	Time		Noise Levels, dB(A)			Limit Level for $L_{eq}$ (dB(A)) <sup>(3)</sup>
	Start	Finish	Corrected $L_{eq}(15min)$ <sup>(1)</sup>	Corrected $L_{90}$ <sup>(1)</sup>	Corrected $L_{10}$ <sup>(1)</sup>	
11-Mar-18	13:44	13:59	52.5	50.0	53.6	70
18-Mar-18	10:30	10:45	54.5	50.2	57.7	70
25-Mar-18	17:00	17:15	52.7	48.9	53.8	70
01-Apr-18	17:20	17:35	57.4	53.3	59.1	70
08-Apr-18	10:29	10:44	55.6	50.4	58.5	70
15-Apr-18	16:40	16:55	54.6	49.9	57.6	70
22-Apr-18	14:28	14:43	53.8	49.8	56.4	70
29-Apr-18	16:28	16:43	54.4	50.4	56.7	70
06-May-18	16:35	16:50	54.4	49.7	56.2	70
13-May-18	14:45	15:00	52.4	49.9	54.3	70
20-May-18	15:40	15:55	53.7	49.1	56.6	70
27-May-18	13:30	13:45	54.5	49.9	55.8	70

**NM2 - Hong Kong Juvenile Care Centre**



Date	Noise Levels, dB(A)					Limit Level for $L_{eq}$ (dB(A)) <sup>(3)</sup>	
	Time	Start	Finish	$L_{eq}(15min)$	$L_{90}$	$L_{10}$	
11-Mar-18	13:13	13:28		48.8	46.7	50.5	65
18-Mar-18	10:00	10:15		45.2	41.0	48.2	65
25-Mar-18	16:35	16:50		45.4	41.9	46.8	65
01-Apr-18	16:52	17:07		49.3	47.4	50.1	65
08-Apr-18	10:01	10:16		48.7	50.3	45.5	65
15-Apr-18	17:08	17:23		48.3	42.5	50.7	65
22-Apr-18	14:00	14:15		46.1	42.2	48.2	65
29-Apr-18	16:00	16:15		48.2	43.9	49.3	65
06-May-18	16:10	16:25		48.5	44.6	49.8	65
13-May-18	14:20	14:35		46.1	43.8	48.0	65
20-May-18	15:10	15:25		47.5	45.9	48.6	65
27-May-18	13:05	13:20		48.5	44.9	49.8	65

**Notes:**

- (1) A free field correction of +3dB(A) has been made to these measurements as specified in the EM&A Manual and EPD guidelines.
- (2) Acceptable noise level should be reduced to 65dB(A) upon school examination period.
- (3) Acceptable noise level should be 65dB(A) according to Technical Memorandum on noise from construction works other than percussive piling.

## G. Graphical Plots of Noise Monitoring Data

## Graphical Plot for Noise Monitoring Data (March - May 2018)



Note: \*Acceptable Noise Levels for school should be reduced to 65 dB(A) during examination period.

## H. Implementation Schedule for Environmental Mitigation Measures

# Appendix C. Implementation Schedule for Environmental Mitigation Measures

EIA Ref.	EM&A Log Ref.	Environmental Protection Measures	Location / Duration of measures / Timing of completion of measures	Implementation Stage <sup>1</sup>						
				Des	Con	Op	Dec			
Cat.1 Key/specific proposed mitigation measure										
<b>Noise Impact (Construction)</b>										
5.7	3.2	<b>Selecting Quiet Plant</b> The actual SWL of quiet plant is less than the value specified in GW-TM for the same piece of equipment. It should be noted that the silenced PME taken from EPD's Quality Powered Mechanical Equipment (QPMЕ) Inventory.	Within Project area / Duration of the construction phase / Prior to commencement of operation	Contractor appointed by OPC		✓	EIAO and Noise Control Ordinance			
5.7	3.2	<b>Use of Movable Barriers</b> Movable noise barriers can be very effective in screening noise from particular items of plant when constructing the Project. Noise barriers located along the active works area close to the noise generating component of a PME could produce at least 10 dB(A) screening for stationary plant and 5 dB(A) for mobile plant provided that the direct line of sight between the PME and the NSRs is blocked.	Within Project area / Duration of the construction phase / Prior to commencement of operation	Contractor appointed by OPC	✓		EIAO and Noise Control Ordinance			
<b>Ecological Impact</b>										
10.7	8.3	<b>Inspection of Active Ardeid Nest</b> Prior to site clearance works at the planting area abandoned for ardeid breeding, the area around the boundary of the ardeids roosting site as indicatively shown in Figure 8.1 should be inspected to confirm no active ardeid nest is present. If any active ardeid nest is observed, suitably sized buffer area should be established to avoid human or machinery disturbance until the nest is abandoned.	Indicative boundary of the ardeids roosting site within Project construction site (location indicated in Figure 8.1) / For once / Before site clearance	Qualified ecologist appointed by OPC	✓		EIAO-TM; HK Ordinance Cap. 170			
10.7	8.3	<b>Inspection of Short-nosed Fruit Bat</b> As precautionary measure, prior to any proposed arboricultural works of the trees (particularly the Chinese Fan-palms), daytime	Project construction site / For once / Before arboricultural works of	ET appointed by OPC	✓	✓	EIAO-TM; HK Ordinance Cap. 170			

# Tai Shue Wan Development at Ocean Park Environmental Monitoring and Audit Manual

EIA Ref.	EM&A Log Ref.	Environmental Protection Measures	Location / Duration of measures / Timing of completion of measures	Implementation Stage <sup>1</sup>		Dec	Relevant Legislation & Guidelines
				Des	Con		
10.7	8.3	<b>In-situ Preservation of Plant Species of Conservation Interest</b> During construction phase, protective fence for the identified flora species of conservation concern shall be erected and maintained.	the trees				EIAO-TM
10.7	8.3	<b>Inspection of Ardeid Nest during breeding season</b> After commencement of construction phase, the Site should be monitored monthly in breeding season (April to July) to check for any potential breeding and nesting activities.	Project construction site / Throughout construction stage / Until completion of all construction activities	Contractor appointed by OPC	✓		EIAO-TM
10.7	8.2	<b>Timing of site clearance and tree felling works</b> Site clearance and tree felling works at the existing ardeid night roost location as shown in Figure 8.1 should be avoided during the peak wintering season of ardeids, i.e. between November and March.	Project construction site / Throughout construction stage / Until completion of all construction activities	Qualified ecologist appointed by OPC	✓		EIAO-TM
10.7	8.3	<b>Compensation for Ardeid Roosting Site</b> An enhancement area with following features should be provided as an alternative roosting site for ardeids. <ul style="list-style-type: none"><li>■ The location is at southern part of the Project area (location indicated in Figure 8.1)<ul style="list-style-type: none"><li>■ The enhancement area shall include a Flamingo Pond</li><li>■ Native tree species <i>Macaranga tanarius</i> and <i>Celtis sinensis</i> and tree species which was used by ardeids for roosting <i>Mallotus paniculatus</i>, <i>Ficus hispida</i> and <i>Cratoxylum cochinchinense</i> shall be considered in the plan.</li><li>■ Heavy standard sized trees shall be considered for planting to allow early establishment of the trees around the Flamingo</li></ul></li></ul>	Indicative boundary of the ardeids roosting site within Project construction site (location indicated in Figure 8.1) / Throughout construction stage / Until completion of site clearance and tree felling works within the boundary	Contractor appointed by OPC	✓		EIAO-TM
10.7	8.3		Southern part of Project construction site (location indicated in Figure 8.1) / Before and throughout construction stage / Until completion of Flamingo Pond construction and tree planting activities at that area	Qualified ecologist and Contractor appointed by OPC	✓	✓	EIAO-TM

# Tai Shue Wan Development at Ocean Park Environmental Monitoring and Audit Manual



EIA Ref.	EM&A Log Ref.	Environmental Protection Measures	Location / Duration of measures / Timing of completion of measures	Implementation Stage <sup>1</sup>				Relevant Legislation & Guidelines
				Implementation Agent	Des	Con	Op	
10.7	8.3	<b>Pond.</b>	<b>Compensation for Woodland Habitat</b>	Location of Woodland Compensation Area indicated in Figure 8.2/ Before and throughout construction stage / Until completion of all construction activities	Contractor appointed by OPC	✓	✓	EIAO-TM
			<ul style="list-style-type: none"> <li>▪ Provision of a Woodland Area of about 1.62 ha, which includes 0.84 ha woodland compensation on-site and 0.78 ha on-site woodland reinstatement, to mitigate for permanent loss of woodland habitat.</li> <li>▪ In the woodland compensation area, whips should be planted with predominately native tree species similar to the affected woodland, such as <i>Celtis sinensis</i>, <i>Cratoxylum cochinchinense</i>, <i>Polyspora axillaris</i> and <i>Sterculia lanceolata</i>.</li> </ul>					
			<b>Landscape and Visual Impact (Construction)</b>	Project construction site / Throughout construction stage / Until completion of all construction activities	Contractor appointed by OPC	✓	✓	EIAO-TM
Table 12.13 (CP07)	Table 9.1 (CP07)	<b>Temporary Tree Nurseries</b>	<p>Temporary tree nurseries may be set up within the Project area at an early stage to allow small trees to grow during the construction period. By the time these trees are needed for landscape planting at the end of the construction phase, they will have grown larger, require minimal pruning and suffer much less damage during transplanting, as the moving distance from an on-site rather than off-site nursery will be much smaller. The temporary tree nurseries can also temporarily hold the existing trees to be transplanted if direct transplantation from their original locations to the final recipient location is impracticable. The locations of the temporary tree nurseries should be carefully selected so that the trees can also act as screen planting to block the views of the Project area from the VSRs during the construction phase, if practicable.</p>					
Table 12.13 (CP08)	Table 9.1 (CP08)	<b>Advance Planting</b>	<p>Advance planting should be undertaken at the earliest possible stage of the construction phase of the project. Plant species, preferably native ones, should be carefully selected to blend in with the existing preserved vegetation. Landscape planting in movable planters should also be considered as a temporary greening measure for the Project area.</p>	Project construction site / Throughout construction stage / Until completion of all construction activities	Contractor appointed by OPC	✓	✓	EIAO-TM
		<b>Landscape and Visual Impact (Operation)</b>						
Table 12.14 (OP04)	Table 9.2 (OP04)	<b>Green Roofs and Vertical Greening</b>	Project building rooftops / During design stage / Throughout operation	Design Architect / Contractor appointed by OPC	✓	✓	✓	EIAO-TM

# Tai Shue Wan Development at Ocean Park Environmental Monitoring and Audit Manual



EIA Ref.	EM&A Log Ref.	Environmental Protection Measures	Location / Duration of measures / Timing of completion of measures	Implementation Stage <sup>1</sup>				Relevant Legislation & Guidelines
				Des	Con	Op	Dec	
Table 12.14 (OP05)	Table 9.2 (OP05)	building structures.	phase	Project area / During design stage / Throughout operation phase	Design Architect / Contractor appointed by OPC	✓	✓	EIAO-TM
Table 12.14 (OP07)	Table 9.2 (OP07)	<p><b>Reprovision of Flamingo Pond</b> A pond is recommended to replace the demolished Flamingo Pond as compensation for the loss of semi-natural ponds, where wildlife, such as birds, can utilise.</p> <p><b>Woodland Compensation</b> 1.53ha of affected woodland is recommended to be reinstated / compensated by 1.62ha of whip tree planting adjacent to the existing unaffected woodland and tall shrubland. Native species should be proposed as far as practicable to re-create a native landscape, restore the ecological habitats and blend in with the existing native vegetation.</p>	Project area / During design stage / Throughout operation phase	Design Architect / Contractor appointed by OPC	✓	✓	EIAO-TM	
<b>Cat. 2 Submission required post EIA stage</b>								
<b>Sewerage and Sewage Treatment Implications</b>								
7.7	5.2	<p><b>Detailed Sewerage Design Report</b> In order to prevent septicity problems during operation phase, a detailed sewerage design report should be submitted to DSD for approval prior to installation of the rising mains.</p>	Rising mains site / During design stage	Design Engineer	✓			Sewerage Manual Part 1
<b>Ecological Impact (Construction)</b>								
10.7	8.3	<p><b>Vegetation Survey for Plant Species of Conservation Interest</b> For precautionary purposes and to further ensure no flora species of conservation interest to be affected, a detailed vegetation survey need to conduct to the exact locations, number and condition of individuals of <i>Playcodon grandiflorus</i>.</p>	Project construction site / For once / Before site clearance	Qualified botanist/ecologist of the ET appointed by OPC	✓			EIAO-TM; Hong Kong Ordinance Cap. 96
10.7	8.3	<p><b>Woodland Compensation Plan</b> A Woodland Compensation Plan shall be prepared and submitted to AFCD for approval no later than one month prior to commencement of site clearance. The plan shall include but not limited to the following:</p> <ul style="list-style-type: none"> <li>▪ Timing of planting works</li> <li>▪ Planting location</li> <li>▪ Species, size and number of trees</li> <li>▪ Monitoring methodology</li> </ul>	Location of Woodland Compensation Area indicated in Figure 8.2/ Before construction stage / No later than one month prior to commencement of site clearance	Qualified botanist/ecologist of the ET appointed by OPC	✓			EIAO-TM

**Tai Shue Wan Development at Ocean Park  
Environmental Monitoring and Audit Manual**

EIA Ref.	EM&A Log Ref.	Environmental Protection Measures	Location / Duration of measures / Timing of completion of measures	Implementation Stage <sup>1</sup>				Relevant Legislation & Guidelines
				Des	Con	Op	Dec	
<b>Landscape and Visual Impact (Construction)</b>								
Table 12.13 (CP05)	Table 9.1 (CP05)	<b>Transplantation of Existing Trees</b>  Trees which are in direct conflict with the development proposals and suitable for transplantation should be transplanted as far as practicable. A tree transplantation proposal should be submitted together with the tree removal application. Trees proposed to be transplanted should preferably be transplanted from their original locations directly to their final recipient locations in one go. If this is infeasible, the trees should be held in a temporary tree nursery, preferably within the Project area, where the trees will be properly maintained.	Project construction site / Throughout construction stage / Until completion of all construction activities	Contractor appointed by OPC	✓	✓		EIAO-TM; LAO PN No. 07/2007
<b>Landscape and Visual Impact (Operation)</b>								
Table 12.14 (OP02)	Table 9.2 (OP02)	<b>Compensatory Tree Planting</b>  Existing trees to be felled should be compensated as far as practicable. Native species should be proposed as far as practicable to re-create a native landscape, restore the ecological habitats and blend in with the existing native vegetation. A compensatory tree planting proposal should be submitted together with the tree removal application for approval by relevant authorities in accordance with LAO Practice Note No. 7/2007. It is recommended that approximately 608 heavy standard trees and approximately 18,202 whip trees could be planted on-site. The availability of off-site compensatory tree planting area is still subject to further investigation and agreement with relevant authorities.	Project area / During design stage / Throughout operation phase	Design Architect / Contractor appointed by OPC	✓	✓		EIAO-TM; LAO PN No. 07/2007
<b>Cat. 3 Good site practice/housekeeping measures under EM&amp;A mechanism</b>								
<b>Air Quality Impact (Construction)</b>								
3.9.1	2.2	<b>Dust Control Measures</b>  To achieve compliance with the FSP, RSP and TSP criteria during the construction phase, good practices for dust control should be implemented to reduce dust impacts. The dust control measures are detailed as follows: <ul style="list-style-type: none"><li>▪ Use of regular water spraying (once every 2.5 hours or 4 times per day) to reduce dust emissions from heavy construction activities (including ground excavation, earth moving, etc.) at all active works area exposed site surfaces and unpaved</li></ul>	Project construction site / Duration of the construction phase / Prior to commencement of operation	Contractor appointed by OPC	✓			EIA Recommendation and Air Pollution Control (Construction Dust) Regulation



**Tai Shue Wan Development at Ocean Park  
Environmental Monitoring and Audit Manual**

EIA Ref.	EM&A Log Ref.	Environmental Protection Measures	Location / Duration of measures / Timing of completion of measures	Implementation Stage <sup>1</sup>			Relevant Legislation & Guidelines
				Des	Con	Op	
		<p>to keep the dusty material wet.</p> <p>Debris Handling</p> <ul style="list-style-type: none"> <li>▪ Any debris should be covered entirely by impervious sheeting or stored in a debris collection area sheltered on the top and the three sides.</li> <li>▪ Before debris is dumped into a chute, water should be sprayed onto the debris so that it remains wet when it is dumped.</li> </ul> <p>Transport of Dusty Materials</p> <ul style="list-style-type: none"> <li>▪ Vehicles used for transporting dusty materials/spoils should be covered with tarpulin or similar material. The cover should extend over the edges of the sides and tailboards.</li> </ul> <p>Wheel washing</p> <ul style="list-style-type: none"> <li>▪ Vehicle wheel washing facilities should be provided at each construction site exit. Immediately before leaving the construction site, every vehicle should be washed to remove any dusty materials from its body and wheels.</li> </ul> <p>Use of vehicles</p> <ul style="list-style-type: none"> <li>▪ The speed of the trucks within the site should be controlled to about 10 km/hour in order to reduce adverse dust impacts and secure the safe movement around the site.</li> <li>▪ Immediately before leaving the construction site, every vehicle should be washed to remove any dusty materials from its body and wheels.</li> <li>▪ Where a vehicle leaving the construction site is carrying a load of dusty materials, the load should be covered entirely by clean impervious sheeting to ensure that the dusty materials do not leak from the vehicle.</li> </ul> <p>Site hoarding</p> <ul style="list-style-type: none"> <li>▪ Where a site boundary adjoins a road, street, service lane or other area accessible to the public, hoarding of not less than 2.4 m high from ground level should be provided along the entire length of that portion of the site boundary except for a site entrance or exit</li> </ul>					

**Noise Impact (Construction)**

# Tai Shue Wan Development at Ocean Park

## Environmental Monitoring and Audit Manual



EIA Ref.	EM&A Log Ref.	Environmental Protection Measures	Location / Duration of measures / Timing of completion of measures	Implementation Stage <sup>1</sup>				Relevant Legislation & Guidelines
				Implementation Agent	Des	Con	Op	
5.7	3.2	<b>Good Site Practice</b> Good site practice and noise management can significantly reduce the impact of construction site activities on nearby NSRs. <ul style="list-style-type: none"><li>▪ only well-maintained plant to be operated on-site and plant should be serviced regularly during the construction works;</li><li>▪ machines and plant that may be in intermittent use to be shut down between work periods or should be throttled down to a minimum;</li><li>▪ plant known to emit noise strongly in one direction, should, where possible, be orientated to direct noise away from the NSRs;</li><li>▪ mobile plant should be sited as far away from NSRs as possible; and</li><li>▪ material stockpiles and other structures to be effectively utilised, where practicable, to screen noise from on-site construction activities.</li></ul>	Project construction site / Duration of the construction phase / Prior to commencement of operation	Contractor appointed by OPC		✓		EIAO and Noise Control Ordinance
5.7	3.3.2	<b>Noise Impact (Operation)</b> <b>Fixed Plant Noise</b> With the adoption of the proposed maximum allowable SWLs, all representative NSRs is expected to comply with the relevant noise criteria for the daytime and evening time periods. No adverse fixed plant noise impact is anticipated. It is also recommended that the following noise reduction measures should be considered as far as practicable during design stage: <ul style="list-style-type: none"><li>▪ choose quiet plant such as those which have been effectively silenced;</li><li>▪ include noise levels specification when ordering new plant (including chiller and E&amp;M equipment);</li><li>▪ locate fixed plant / louvre away from any NSRs as far as practicable;</li><li>▪ locate fixed plant in walled plant rooms or in specially designed enclosures;</li><li>▪ locate noisy machine in a basement or a completely separate building;</li></ul>	Within Project area / Prior to operation phase / Duration of the operation phase / Throughout operation phase	Design Architect / Contractor appointed by OPC	✓	✓	✓	EIAO and Noise Control Ordinance

# Tai Shue Wan Development at Ocean Park

## Environmental Monitoring and Audit Manual

EIA Ref.	EM&A Log Ref.	Environmental Protection Measures	Location / Duration of measures / Timing of completion of measures	Implementation Stage <sup>1</sup>				Relevant Legislation & Guidelines
				Des	Con	Op	Dec	
		<ul style="list-style-type: none"> <li>▪ install direct noise mitigation measures including silencers, acoustic louvres and acoustic enclosure where necessary; and</li> <li>▪ develop and implement a regularly scheduled plant maintenance programme so that equipment is properly operated and serviced in order to maintain a controlled level of noise.</li> </ul> <p>Prior to the operation of the Project, noise commissioning tests for all major fixed noise sources should be conducted.</p>					EIAO and Noise Control Ordinance	
5.7	3.3.2	<p><b>Open Air Entertainment Noise</b></p> <p>With the adoption of the proposed maximum allowable SWLs, all representative NSRs is expected to comply with the relevant noise criteria for the daytime and evening periods, the following measures should be considered as far as practicable during stage:</p> <ul style="list-style-type: none"> <li>▪ use small clusters of small power loudspeakers rather than a few large power loudspeakers; and</li> <li>▪ loudspeakers should be pointed away from nearby NSRs.</li> </ul>	Within Project area / Duration of the operation phase / Throughout operation phase	Design Architect / Contractor appointed by OPC	✓	✓		EIAO-TM;
6.7	4.2	<p><b>Water Quality Impact (Construction)</b></p> <p><b>Construction Site Runoff</b></p> <p>The site practices outlined in ProPECC Note PN 1/94 should be followed as far as practicable in order to minimise surface runoff and erosion. The following measures are recommended to protect water quality of the inland areas:</p> <ul style="list-style-type: none"> <li>▪ At the start of site establishment, perimeter cut-off drains to direct off-site water around the site should be constructed with internal drainage works and erosion and sedimentation control facilities implemented. Channels, earth bunds or sand bag barriers should be provided on site to direct storm water to silt removal facilities. The design of the temporary on-site drainage system should be undertaken by the Contractors prior to the commencement of construction;</li> <li>▪ Sand/ silt removal facilities such as sand/silt traps and sediment basins should be provided to remove sand/silt particles from runoff to meet the requirements of the TM standards under the WPCO. The design of efficient silt removal facilities should be based on the guidelines in</li> </ul>	Project construction site / Duration of the construction phase	Contractor appointed by OPC	✓			ProPECC Note PN 1/94; WPCO; TM-DSS

## Tai Shue Wan Development at Ocean Park Environmental Monitoring and Audit Manual



EIA Ref.	EM&A Log Ref.	Environmental Protection Measures	Location / Duration of measures / Timing of completion of measures	Implementation Agent	Implementation Stage <sup>1</sup>			
					Des	Con	Op	Dec
		<p>Appendix A1 of ProPECC Note PN 1/94. Sizes may vary depending upon the flow rate. The detailed design of the sand/silt traps should be undertaken by the Contractors prior to the commencement of construction;</p> <ul style="list-style-type: none"> <li>■ All drainage facilities and erosion and sediment control structures should be regularly inspected and maintained to ensure proper and efficient operation at all times and particularly during rainstorms. Deposited silt and grit should be regularly removed, at the onset of and after each rainstorm to ensure that these facilities are functioning properly at all times;</li> <li>■ Measures should be taken to minimise the ingress of site drainage into excavations. If excavation of trenches in wet periods is necessary, they should be dug and backfilled in short sections wherever practicable. Water pumped out from site formation excavations should be discharged into storm drains via silt removal facilities;</li> <li>■ All vehicles and plant should be cleaned before leaving a construction site to ensure no earth, mud, debris and the like is deposited by them on roads. An adequately designed and sited wheel washing facility should be provided at construction site exit where practicable. Wash-water should have sand and silt settled out and removed regularly to ensure the continued efficiency of the process. The section of access road leading to, and exiting from, the wheel-wash bay to the public road should be paved with sufficient backfall toward the wheel-wash bay to prevent vehicle tracking of soil and silty water to public roads and drains;</li> <li>■ Open stockpiles of construction materials or construction wastes on-site should be covered with tarpaulin or similar fabric during rainstorms. Measures should be taken to prevent the washing away of construction materials, soil, silt or debris into any drainage system;</li> <li>■ Manholes (including newly constructed ones) should be adequately covered and temporarily sealed so as to prevent silt, construction materials or debris being washed into the drainage system and stormwater runoff being directed into foul sewers;</li> <li>■ Precautions should be taken at any time of the year when</li> </ul>						



# Tai Shue Wan Development at Ocean Park Environmental Monitoring and Audit Manual



EIA Ref.	EM&A Log Ref.	Environmental Protection Measures	Location / Duration of measures / Timing of completion of measures	Implementation Stage <sup>1</sup>			Relevant Legislation & Guidelines
				Des	Con	Op	
6.7	4.2	<b>Construction of Sewage Sump Pit and Rising Mains</b>	Project construction site / Duration of the construction phase	Contractor appointed by OPC	✓		ProPECC Note PN 1/94
6.7	4.2	<b>Accidental Spillage</b>	Project construction site / Duration of the construction phase	Contractor appointed by OPC	✓		ProPECC Note PN 1/94; Waste Disposal Ordinance (Cap 354); Waste Disposal (Chemical Waste) (General) Regulation

# Tai Shue Wan Development at Ocean Park Environmental Monitoring and Audit Manual

EIA Ref.	EM&A Log Ref.	Environmental Protection Measures	Location / Duration of measures / Timing of completion of measures	Implementation Stage <sup>1</sup>				Relevant Legislation & Guidelines
				Des	Con	Op	Dec	
		<p>Disposal of chemical wastes should be carried out in compliance with the Waste Disposal Ordinance. The Code of Practice on the Packaging, Labelling and Storage of Chemical Wastes published under the Waste Disposal Ordinance details the requirements to deal with chemical wastes. General requirements are given as follows:</p> <ul style="list-style-type: none"> <li>▪ Suitable containers should be used to hold the chemical wastes to avoid leakage or spillage during storage, handling and transport.</li> <li>▪ Chemical waste containers should be suitably labelled, to notify and warn the personnel who are handling the wastes, to avoid accidents.</li> <li>▪ Storage areas should be selected at a safe location on site and adequate space should be allocated to the storage area.</li> </ul>						
6.7	4.2	<p><b>Sewage Effluent from the Construction Workforce</b></p> <p>The Contractor should provide temporary sanitary facilities, such as portable chemical toilets within the construction site to handle sewage from the workforce. The Contractor has the responsibility to ensure that chemical toilets are used and properly maintained, and that licensed Contractors are employed to collect and dispose of the waste off-site at approved locations.</p>	Project construction site / Duration of the construction phase	Contractor appointed by OPC	✓			ProPECC Note PN 1/94
<b>Water Quality Impact (Operation)</b>								
6.7	4.2	<p><b>Runoff from Road Surfaces</b></p> <p>Road drainage system design has already included silt traps in the gully inlets to remove silt and grit before the runoff enters the public storm water drainage system. Silt traps should be regularly checked and maintained to ensure efficient operation.</p>	Within Project area / During operation phase	OPC/Operator appointed by OPC			✓	EIAO-TM; WPCO
6.7	4.2	<p><b>Runoff from On-site Planting Area</b></p> <p>Watering of plants on site should always be performed before application of pesticides, herbicides and fertilizers. Regular training should also be provided to frontline staff on the appropriate treatment and disposal of pesticides, herbicides and fertilizers.</p>	Within Project area / During operation phase	OPC/Operator appointed by OPC			✓	EIAO-TM; WPCO; TM-DSS
<b>Waste Management Implications (Construction)</b>				Project construction site / Throughout construction	Contractor	✓		Waste Disposal Ordinance; Waste
8.5.1.1	6.2	<b>Good Site Practice</b>						

# Tai Shue Wan Development at Ocean Park Environmental Monitoring and Audit Manual



EIA Ref.	EM&A Log Ref.	Environmental Protection Measures	Location / Duration of measures / Timing of completion of measures	Implementation Stage <sup>1</sup>				Relevant Legislation & Guidelines
				Des	Con	Op	Dec	
		<p>Recommendations for good site practices during the construction activities include:</p> <ul style="list-style-type: none"> <li>▪ Nomination of an approved person, such as a site manager, to be responsible for good site practices, arrangements for collection and effective disposal to an appropriate facility, of all wastes generated at the site</li> <li>▪ Training of site personnel in proper waste management and chemical handling procedures</li> <li>▪ Provision of sufficient waste disposal points and regular collection of waste</li> <li>▪ Appropriate measures to minimise windblown litter and dust/odour during transportation of waste by either covering trucks or by transporting wastes in enclosed containers</li> <li>▪ Stockpiles of C&amp;D materials should be kept covered by impervious sheets to avoid wind-blown dust</li> <li>▪ All dusty materials including C&amp;D materials should be sprayed with water immediately prior to any loading transfer operation so as to keep the dusty material wet during material handling at the stockpile areas</li> <li>▪ Provision of wheel washing facilities before the trucks leaving the works area so as to minimise dust introduction to public roads</li> <li>▪ Well planned delivery programme for offsite disposal such that adverse environmental impact from transporting the inert or non-inert C&amp;D materials is not anticipated</li> </ul>	stage / Until completion of all construction activities	appointed by OPC				Disposal (Chemical Wastes) (General) Regulation; and ETWB Technical Circular (Works) No. 19/2005 Environmental Management on Construction Site
8.5.1.2	6.2	<b>Waste Reduction Measures</b> Good management and control can prevent the generation of a significant amount of waste. Waste reduction is best achieved at the planning and design stage, as well as by ensuring the implementation of good site practices. Recommendations to achieve waste reduction include: <ul style="list-style-type: none"> <li>▪ Sort inert C&amp;D materials to recover any recyclable portions such as metals</li> <li>▪ Segregation and storage of different types of waste in different containers or skips to enhance reuse or recycling of</li> </ul>	Project construction site / Throughout construction stage / Until completion of all construction activities	Contractor appointed by OPC	✓			Waste Disposal Ordinance



**Tai Shue Wan Development at Ocean Park  
Environmental Monitoring and Audit Manual**

EIA Ref.	EM&A Log Ref.	Environmental Protection Measures	Location / Duration of measures / Timing of completion of measures	Implementation Stage <sup>1</sup>				Relevant Legislation & Guidelines
				Des	Con	Op	Dec	
		Contractor will be required to register with the EPD as a chemical waste producer and to follow the guidelines stated in the "Code of Practice on the Packaging Labelling and Storage of Chemical Wastes". Good quality containers compatible with the chemical wastes should be used, and incompatible chemicals should be stored separately. Appropriate labels should be securely attached on each chemical waste container indicating the corresponding chemical characteristics of the chemical waste, such as explosive, flammable, oxidising, irritant, toxic, harmful, corrosive, etc. The Contractor should use a licensed collector to transport and dispose of the chemical wastes at the approved Chemical Waste Treatment Centre or other licensed recycling facilities, in accordance with the Waste Disposal (Chemical Waste) (General) Regulation.	stage / Until completion of all construction activities					Labelling and Storage of Chemical Wastes; Waste Disposal (Chemical Waste) (General) Regulation
8.5.1.5	6.2	Potential environmental impacts arising from the handling activities (including storage, collection, transportation and disposal of chemical waste) are expected to be minimal with the implementation of appropriate mitigation measures as recommended.	Project construction site / Throughout construction stage / Until completion of all construction activities	Contractor appointed by OPC			✓	Waste Disposal Ordinance and Public Health and Municipal Services Ordinance - Public Cleansing and Prevention of Nuisances Regulation
8.5.1.6	6.2	<b>General Refuse</b> General refuse should be stored in enclosed bins or compaction units separated from inert C&D materials. A reputable waste collector should be employed by the Contractor to remove general refuse from the site, separately from inert C&D materials. Preferably an enclosed and covered area should be provided to reduce the occurrence of 'wind blown' light material.	Project construction site / Throughout construction stage / Until completion of all construction activities	Contractor appointed by OPC			✓	Waste Disposal Ordinance
<b>Waste Management Implications (Operation)</b>					Project area / On a regular basis /	Contractor appointed by OPC	✓	Waste Disposal Ordinance
8.5.2.1	6.2	<b>General Refuse</b> General refuse should be collected on daily basis and delivered						

Tai Shue Wan Development at Ocean Park  
Environmental Monitoring and Audit Manual

EIA Ref.	EM&A Log Ref.	Environmental Protection Measures	Location / Duration of measures / Timing of completion of measures	Implementation Stage <sup>1</sup>				Relevant Legislation & Guidelines
				Des	Con	Op	Dec	
		to the refuse collection point accordingly. A reputable waste collector should be employed to remove general refuse regularly to avoid odour nuisance or pest/vermin problem. Sufficient recycling containers are recommended to be provided at suitable locations of the Project to encourage recycling of such waste as aluminium cans, plastics and waste paper.	Throughout operation stage					Code of Practice on the Packaging Labelling and Storage of Chemical Wastes; Waste Disposal (Chemical Waste) (General) Regulation
8.5.2.2	6.2	<b>Chemical Waste</b> If chemical wastes are expected to be produced during the operation phase, the Project Proponent should register with the EPD as a chemical waste producer and follow the guidelines stated in the "Code of Practice on the Packaging, Labelling and Storage of Chemical Wastes". Good quality containers compatible with the chemical wastes should be used, and incompatible chemicals should be stored separately. Appropriate labels should be securely attached on each chemical waste container indicating the corresponding chemical characteristics of the chemical waste, such as explosive, flammable, oxidising, irritant, toxic, harmful, corrosive, etc. Licensed collector should be deployed to transport and dispose of the chemical wastes at the approved Chemical Waste Treatment Centre or other licensed recycling facilities, in accordance with the Waste Disposal (Chemical Waste) (General) Regulation.	Project area / On a regular basis / Throughout operation stage	Contractor appointed by OPC	Contractor	✓	✓	Code of Practice on the Packaging Labelling and Storage of Chemical Wastes; Waste Disposal (Chemical Waste) (General) Regulation
8.5.2.3	6.2	<b>Floating Refuse</b> Regular inspection should be carried out along the artificial seawall of the Project boundary for any entrapment or accumulation of floating refuse. Where an appreciable amount of floating refuse is found on the artificial seawall during the inspection, the locations of such refuse will be recorded and arrangements with the project proponent will immediately be made to collect and clear the refuse from the seawall.	Project area / On a regular basis / Throughout operation stage	Contractor appointed by OPC	Contractor appointed by OPC	✓	✓	Waste Disposal Ordinance
9.6	7.2	In any case where contaminated soil is identified after the commencement of works, a Contamination Assessment Plan (CAP) is required to be prepared for EPD's endorsement prior to	Project construction site / Before construction stage	Project construction site / Before construction stage	Contractor appointed by OPC	✓		Guidance Note for Contaminated Land Assessment and Remediation

## Tai Shue Wan Development at Ocean Park Environmental Monitoring and Audit Manual

EIA Ref.	EM&A Log Ref.	Environmental Protection Measures	Location / Duration of measures / Timing of completion of measures	Implementation	Implementation Stage <sup>1</sup>			Dec	Dec	Relevant Legislation & Guidelines
					Des	Con	Op			
9.6	7.2	<p>the site investigation. The Contamination Assessment Report (CAR) and/ or Remediation Action Plan (RAP) should be prepared for EPD's approval after the site investigation. If land contamination is confirmed, remediation works should be carried out according to the approved RAP. A Remediation Report (RR) should also be prepared for EPD's endorsement to demonstrate that the clean-up of the contaminated land is completed. No construction work or development of site should be carried out before the approval of the RR.</p>	<p>Project construction site / Throughout construction stage / Until completion of all construction activities</p> <ul style="list-style-type: none"> <li>▪ If contaminated soil is identified, the following mitigation measures are for the excavation and transportation of contaminated materials (if any):           <ul style="list-style-type: none"> <li>■ To minimise the incidents of construction workers coming in contact with any contaminated materials, bulk earth-moving excavation equipment should be employed;</li> <li>■ Contact with contaminated materials can be minimised by wearing appropriate clothing and personal protective equipment such as gloves and masks (especially when working directly with contaminated material), provision of washing facilities and prohibition of smoking and eating on site;</li> <li>■ Stockpiling of contaminated excavated materials on site should be avoided as far as possible;</li> <li>■ The use of any contaminated soil for landscaping purpose should be avoided unless pre-treatment was carried out;</li> <li>■ Vehicles containing any excavated materials should be suitably covered to reduce dust emissions and/or release of contaminated wastewater;</li> <li>■ Truck bodies and tailgates should be sealed to prevent any discharge;           </li></ul> </li> </ul>	Contractor appointed by OPC	✓			Waste Disposal Ordinance (Cap 354) Waste Disposal (Chemical Waste) (General) Regulation (Cap 354)		

EIA Ref.	EM&A Log Ref.	Environmental Protection Measures	Location / Duration of measures / Timing of completion of measures	Implementation Stage <sup>1</sup>					
				Implementation Agent	Des	Con	Op	Dec	Relevant Legislation & Guidelines
		<ul style="list-style-type: none"> <li>▪ Speed control for trucks carrying contaminated materials should be exercised.</li> <li>▪ Observe all relevant regulations in relation to waste handling, such as Waste Disposal Ordinance (Cap 354), Waste Disposal (Chemical Waste) (General) Regulation (Cap 354) and obtain all necessary permits where required; and</li> <li>▪ Maintain records of waste generation and disposal quantities and disposal arrangements.</li> </ul>							
<b>Landscape and Visual Impact (Construction)</b>									
Table 12.13 (CP01)	Table 9.1 (CP01)	<b>Minimisation of Construction Period</b> The construction programme should be carefully designed to minimise the length of the construction period.	Project construction site / Throughout construction stage / Until completion of all construction activities	Contractor appointed by OPC	✓	✓	✓		EIAO-TM
Table 12.13 (CP02)	Table 9.1 (CP02)	<b>Minimisation of Works Areas</b> The footprint of the proposed hard structures as well as the extent of temporary works areas should be minimised as far as practicable.	Project construction site / Throughout construction stage / Until completion of all construction activities	Contractor appointed by OPC	✓	✓			EIAO-TM
Table 12.13 (CP03)	Table 9.1 (CP03)	<b>Construction Site Controls</b> Construction site controls should be enforced, where possible, to ensure that the landscape and visual impacts arising from the construction phase activities, such as the storage of materials, the location and appearance of site accommodation, etc. are minimised.	Project construction site / Throughout construction stage / Until completion of all construction activities	Contractor appointed by OPC	✓	✓			EIAO-TM
Table 12.13 (CP04)	Table 9.1 (CP04)	<b>Preservation of Existing Vegetation</b> The development proposal should avoid disturbance to existing vegetation as far as practicable. A formal tree removal application should be submitted for approval by relevant authorities in accordance with LAO PN No. 07/2007 "Tree Preservation and Tree Removal Application for Building Development in Private Projects" during the detailed design phase of the Project. Where possible, all trees which are not in direct conflict with the development proposals should be retained <i>in situ</i> .	Project construction site / Throughout construction stage / Until completion of all construction activities	Contractor appointed by OPC	✓	✓			EIAO-TM; LAO PN No. 07/2007
Table	Table	<b>No Intrusion Zones</b>	Project construction site /	Contractor	✓	✓			EIAO-TM

## Tai Shue Wan Development at Ocean Park Environmental Monitoring and Audit Manual



EIA Ref.	EM&A Log Ref.	Environmental Protection Measures	Location / Duration of measures / Timing of completion of measures	Implementation Stage <sup>1</sup>			Relevant Legislation & Guidelines
				Des	Con	Op	
12.13 (CP06)	9.1 (CP06)	Where practicable, "no intrusion zones" should be designated within the Project area for protection of existing vegetation. Durable boundary fences should be erected to clearly demarcate these "no intrusion zones". No construction activities, storage of materials and vehicular access will be allowed within the "no intrusion zones" to prevent potential damage to canopies and root zones of vegetation.	Throughout construction stage / Until completion of all construction activities	appointed by OPC			EIAO-TM
Table 12.13 (CP09)	Table 9.1 (CP09)	<b>Construction Site Hoardings</b> Two types of hoardings should be considered. One is used for areas in close contact with visitors and for areas where visual intrusion is a key concern. It should be graphical and thematic, and visually 'impermeable' to block the views of construction activities from the VSRs. The other is used for areas to be viewed at a distance. It should be subtle and camouflaged so that it blends in with the surrounding landscape.	Project construction site / Throughout construction stage / Until completion of all construction activities	Contractor appointed by OPC	✓	✓	EIAO-TM
Table 12.13 (CP10)	Table 9.1 (CP10)	<b>Dust and Erosion Control for Exposed Soil</b> Exposed soil shall be covered or "camouflaged" and watered frequently. Areas that are expected to be left with bare soil for a long period of time should be hydroseeded and / or covered with suitable protective fabrics.	Project construction site / Throughout construction stage / Until completion of all construction activities	Contractor appointed by OPC	✓		EIAO-TM
Table 12.13 (CP11)	Table 9.1 (CP11)	<b>Appearance of Construction Plant / Machinery</b> To minimise the visual intrusion of construction activities to visitors and other VSRs, a suitable colour scheme of construction machines and plants should be adopted where possible.	Project construction site / Throughout construction stage / Until completion of all construction activities	Contractor appointed by OPC	✓		EIAO-TM
Table 12.13 (CP12)	Table 9.1 (CP12)	<b>Construction Lighting Control</b> All security floodlights for construction sites should be equipped with adjustable shield, frosted diffusers and reflective covers, and be carefully controlled to minimise light pollution and night-time glare to the VSRs.	Project construction site / Throughout construction stage / Until completion of all construction activities	Contractor appointed by OPC	✓		EIAO-TM
Table 12.13 (CP13)	Table 9.1 (CP13)	<b>Appearance of Construction Workers</b> To protect Ocean Park's image, construction workers should be required to enter the park areas with their helmets and safety vests properly stored or carried in non-transparent bags. They should also dress properly and cleanly.	Project construction site / Throughout construction stage / Until completion of all construction activities	Contractor appointed by OPC	✓		EIAO-TM
<b>Landscape and Visual Impact (Operation)</b>							

# Tai Shue Wan Development at Ocean Park Environmental Monitoring and Audit Manual

EIA Ref.	EM&A Log Ref.	Environmental Protection Measures	Location / Duration of measures / Timing of completion of measures	Implementation Stage <sup>1</sup>				Relevant Legislation & Guidelines
				Des	Con	Op	Dec	
Table 12.14 (OP01)	Table 9.2 (OP01)	<b>Sensitive Design and Disposition</b>  All proposed hard structures should be sensitively designed in a manner that responds to the existing and planned landscape context, and minimises potential adverse landscape and visual impacts. The structural design should seek to reduce the apparent visual mass through the use of natural materials such as wooden frame and semi-transparent panels. Subdued tones should be considered for the colour palette with non-reflective finishes to reduce glare effect. Site specific measures, such as the disposition of the key structures closer to the northern slopes, the design of building forms as extension along the existing slope topography, the use of concave roof form and the location of ride platforms on or near the slopes to minimise structural support, should also be considered for better integration with the surroundings and minimisation of potential visual impacts.	Project buildings / During design stage / Throughout operation phase	Design Architect / Contractor appointed by OPC	✓	✓	✓	EIAO-TM
Table 12.14 (OP03)	Table 9.2 (OP03)	<b>Enhancement Planting</b>  Other than compensatory tree planting, additional trees, shrubs, groundcovers and lawn should also be considered to maximise greening within the redevelopment area.	Project area / During design stage / Throughout operation phase	Design Architect / Contractor appointed by OPC	✓	✓	✓	EIAO-TM
Table 12.14 (OP06)	Table 9.2 (OP06)	<b>Responsive Lighting Design</b>  Overall lighting design would carefully consider a reasonable level of functional and thematic lighting with due consideration of possible light pollution and night-time glare to the surroundings. Consideration shall be made by the lighting designers to the following measures: <ul style="list-style-type: none"><li>▪ Lighting shall be designed with due consideration of mounting height and direction of light fixtures so as not to point directly towards any sensitive receiver.</li><li>▪ Lighting shall be arranged with due consideration of reflectance so as to avoid glare effect.</li><li>▪ Lighting shall be regularly monitored during operation.</li><li>▪ Lights located adjacent or in proximity to neighbours shall be carefully designed to prevent possible light intrusion.</li><li>▪ Lighting operation schedule shall specify only lights necessary for security to be left on after business hours.</li><li>▪ Paving materials should be selected as necessary to reduce</li></ul>	Project area / During design stage / Throughout operation phase	Design Architect / Contractor appointed by OPC	✓	✓	✓	EIAO-TM

Tai Shue Wan Development at Ocean Park  
Environmental Monitoring and Audit Manual



EIA Ref.	EM&A Log Ref.	Environmental Protection Measures	Implementation Stage <sup>1</sup>				Relevant Legislation & Guidelines
			Des	Con	Op	Dec	
		<p>potential glare from surface reflectance.</p> <ul style="list-style-type: none"> <li>▪ Particular attention should be paid to the use of lighting having a high intensity or harsher tone (e.g. metal halide lamps).</li> <li>▪ Lights shall generally be models having precise cut-off range (such as full cut-off optics where available and practicable) and if necessary be fitted with adjustable anti-glare shields.</li> </ul>					

Remarks:

1. Des – Design Stage, Con – Construction Stage, Op – Operation, Dec - Decommissioning