



土木工程拓展署
Civil Engineering and
Development Department

Agreement No. CE 87/2001 (CE)

Further Development of Tseung Kwan O Feasibility Study

ENVIRONMENTAL MONITORING AND AUDIT MANUAL

July 2005

Document Ref. 94002_EIA16 (26/07/05)

MAUNSELL CONSULTANTS ASIA LTD

in association with:

Maunsell Environmental Management Consultants Ltd

Maunsell Geotechnical Services Ltd

Metcalf & Eddy Ltd

Urbis Ltd

BMT Asia Pacific Ltd

CB Richard Ellis Ltd

Agreement No. CE 87/2001 (CE)
FURTHER DEVELOPMENT OF TSEUNG KWAN O
FEASIBILITY STUDY
ENVIRONMENTAL MONITORING AND AUDIT MANUAL

LIST OF CONTENTS

	Page
1	INTRODUCTION..... 1-1
1.1	Project Description..... 1-1
1.2	Purpose of the Manual..... 1-2
1.3	Project Organisation..... 1-3
2	AIR QUALITY 2-1
2.1	Introduction..... 2-1
2.2	Air Quality Parameters..... 2-1
2.3	Monitoring Equipment..... 2-2
2.4	Laboratory Measurement / Analysis..... 2-3
2.5	Monitoring Locations..... 2-4
2.6	Baseline Monitoring..... 2-5
2.7	Impact Monitoring..... 2-5
2.8	Event and Action Plan..... 2-6
2.9	Mitigation Measures..... 2-8
3	NOISE 3-1
3.1	Introduction..... 3-1
3.2	Noise Parameters..... 3-1
3.3	Monitoring Equipment..... 3-2
3.4	Monitoring Locations..... 3-2
3.5	Baseline Monitoring..... 3-4
3.6	Impact Monitoring..... 3-5
3.7	Event and Action Plan..... 3-6
3.8	Mitigation Measures..... 3-8
4	WATER QUALITY 4-1
4.1	Introduction..... 4-1
4.2	Construction Phase Monitoring..... 4-1
4.3	Operational Phase Monitoring..... 4-4
4.4	Monitoring Equipment and Field Log..... 4-5
4.5	Laboratory Measurement / Analysis..... 4-7
4.6	Event and Action Plan..... 4-7
4.7	Mitigation Measures..... 4-11
5	TERRESTRIAL ECOLOGY 5-1
5.1	Introduction..... 5-1
5.2	Ecological Mitigation Measures and Monitoring..... 5-1
6	MARINE ECOLOGY 6-1
6.1	Introduction..... 6-1
6.2	Ecological Mitigation Measures and Monitoring..... 6-1
7	FISHERIES 7-1
7.1	Introduction..... 7-1
7.2	Ecological Mitigation Measures and Monitoring..... 7-1
8	LANDSCAPE AND VISUAL 8-1
8.1	Introduction..... 8-1

8.2	Monitoring Details	8-1
8.3	Baseline Monitoring	8-2
8.4	Event/Action Plan for Landscape and Visual Works	8-2
8.5	Mitigation Measures	8-4
9	WASTE MANAGEMENT	9-1
9.1	Introduction	9-1
9.2	Mitigation Measures	9-1
10	CULTURAL HERITAGE	10-1
10.1	Introduction	10-1
10.2	Cultural Heritage Mitigation Measures	10-1
10.3	Construction Phase Monitoring and Audit	10-1
11	LANDFILL GAS HAZARD	11-1
11.1	Landfill Gas Parameters	11-1
11.2	Monitoring Equipment	11-1
11.3	Monitoring Locations	11-2
11.4	Limit Levels and Event and Action Plan (EAP) for Landfill Gas	11-2
11.5	Mitigation Measures	11-3
12	SITE ENVIRONMENTAL AUDIT	12-1
12.1	Site Inspections	12-1
12.2	Compliance with Legal and Contractual Requirements	12-2
12.3	Environmental Complaints	12-2
13	REPORTING	13-1
13.1	General	13-1
13.2	Electronic Reporting of EM&A Information	13-1
13.3	Baseline Monitoring Report	13-1
13.4	Monthly EM&A Reports	13-2
13.5	Quarterly EM&A Summary Reports	13-7
13.6	Final EM&A Review Reports	13-8
13.7	Data Keeping	13-10
13.8	Interim Notifications of Environmental Quality Limit Exceedances	13-10

TABLES

Table 2.1	Proposed Air Quality Monitoring Stations
Table 2.2	Action and Limit Levels for Air Quality (Dust)
Table 2.3	Event and Action Plan for Air Quality (Dust)
Table 2.4	Design of WCR Ventilation Building at the Eastern Portal and Mid-Ventilation Building
Table 3.1	Proposed Construction Noise Monitoring Stations
Table 3.2	Proposed Traffic Noise Monitoring Stations
Table 3.3	Proposed Fixed Noise Monitoring Station
Table 3.4	Action and Limit Levels for Construction Noise
Table 3.5	Event and Action Plan for Construction Noise
Table 4.1	Proposed Marine Water Quality Stations for Baseline and Construction Phase Monitoring
Table 4.2	Proposed Marine Water Quality Monitoring Frequency and Parameters at Stations C1, C2, CM1 to CM5
Table 4.3	Proposed Marine Water Quality Stations for Operational Phase Monitoring
Table 4.4	Analytical Methods to be applied to Marine Water Quality Samples
Table 4.5	Action and Limit Levels for Marine Water Quality
Table 4.6	Event and Action Plan for Marine Water Quality During Marine Construction Period
Table 4.7	Event and Action Plan for Marine Water Quality During DCM Field Trial
Table 4.8	Event and Action Plan for Marine Water Quality During Operational Phase
Table 6.1	Action and Limit Level for Coral Monitoring
Table 6.2	Action and Limit Level Exceedance Procedures for Construction Phase Coral Monitoring
Table 6.3a	Tier 1 benthic attribute categories
Table 6.3b	Tier I ordinal ranks of percentage cover of benthic attributes
Table 6.4	Taxonomic resolution of inventory
Table 6.5	Ordinal ranks of taxon abundance
Table 11.1	Limit Levels and Action Plan for Landfill Gas

FIGURES

Figure 1.1	Elements of the Project
Figure 1.2	Project Organisation
Figure 2.1a	Locations of Construction Dust Monitoring Stations (Kowloon Area)
Figure 2.1b	Locations of Construction Dust Monitoring Stations (TKO Area)
Figure 3.1a	Locations of Construction Noise Monitoring Stations (Kowloon Area)
Figure 3.1b	Locations of Construction Noise Monitoring Stations (TKO Area)
Figure 3.2a	Locations of Operational Traffic Noise Monitoring Stations (Kowloon Area)
Figure 3.2b	Locations of Operational Traffic Noise Monitoring Stations (TKO Area)
Figure 3.3	Location of Fixed Noise Monitoring Station
Figure 4.1	Locations of Marine Water Quality Monitoring Station
Figure 6.1	Coral Monitoring Locations
Figure 10.1	Location of Identified Anomaly
Figure 12.1	Complaint Response Procedures

APPENDICIES

Appendix A	Construction Programme
Appendix B	Sample Record Sheet
Appendix C	Implementation Schedule of Proposed Mitigation Measures
Appendix D	Sample Template for the Interim Notification

