

**Agreement No. CE 67/98
Yuen Long, Kam Tin, Ngau Tam Mei &
Tin Shui Wai Drainage Improvement
Stage 1, Phase 2B – Kam Tin
Secondary Drainage Channel KT13**

**Environmental Monitoring and Audit (EM&A) Manual
[382047/E/EMA/Issue 5]**

May 2006

Report Authorized For
Issue By:

.....
For and on Behalf of
Black & Veatch Hong Kong Limited

**Black & Veatch Hong Kong Limited
Room 1201-11, Millennium City 5
418 Kwun tong Road
Kowloon
Hong Kong**

**Drainage Services Department
Project Management Division
42/F, Revenue Tower
5 Gloucester Road
Wan Chai
Hong Kong**

CONTENTS

		Page
1.	ENVIRONMENTAL MONITORING AND AUDIT REQUIREMENTS	1-1
1.1	Introduction	1-1
1.2	Location of Designated Project and Existing Environment	1-2
1.3	Secondary Drainage Channel KT13	1-3
1.4	Design and Construction Programme	1-3
1.5	Mitigation Measures listed in the Environmental Impact Assessment Report	1-3
1.6	Project Organization	1-4
1.7	Approved EIA Report and Environmental Permit	1-9
2.	AIR QUALITY	2-1
2.1	Introduction	2-1
2.2	Air Quality Parameters	2-1
2.3	Monitoring Equipment	2-1
2.4	Laboratory Measurement/Analysis	2-3
2.5	Monitoring Locations	2-4
2.6	Baseline Monitoring	2-5
2.7	Impact Monitoring	2-6
2.8	Event and Action Plan for Air Quality	2-7
2.9	Mitigation Measures	2-9
3.	NOISE	3-1
3.1	Introduction	3-1
3.2	Noise Parameters	3-1
3.3	Monitoring Equipment	3-1
3.4	Monitoring Locations	3-2
3.5	Baseline Monitoring	3-3
3.6	Impact Monitoring	3-4
3.7	Event and Action Plan for Construction Noise	3-4
3.8	Construction Noise Mitigation Measures	3-4

	Name	Signature	Date
Prepared	Various compiled by M. Chua		
Checked	K.I. Lo		
Reviewed	N.F. Lau		

CONTENTS
(cont'd)

	Page
4. WATER QUALITY	4-1
4.1 Introduction	4-1
4.2 Water Quality Parameters	4-1
4.3 Sampling Procedures and Monitoring Equipment	4-1
4.4 Laboratory Measurement/Analysis	4-3
4.5 Monitoring Locations	4-4
4.6 Baseline Monitoring	4-5
4.7 Impact Monitoring	4-6
4.8 Event and Action Plan for Water Quality	4-6
4.9 Water Quality Mitigation Measures	4-9
5. WASTE MANAGEMENT	5-1
5.1 General Requirements	5-1
5.2 Waste Management Measures	5-1
5.3 Potential for Recycling or Reuse of Construction Wastes	5-7
5.4 Responsibilities for Construction Waste Management	5-9
6. ECOLOGY	6-1
6.1 Introduction	6-1
6.2 Monitoring Parameters	6-1
6.3 Equipment	6-1
6.4 Monitoring Areas	6-1
6.5 Baseline Monitoring	6-2
6.6 Impact Monitoring	6-2
6.7 Event and Action Plan for Ecology	6-5
7. CULTURAL HERITAGE	7-1
7.1 Introduction	7-1
7.2 Staff	7-1
7.3 Methodology and Approach	7-1
7.4 Location of Structure to be Monitored	7-1
7.5 Action and Limit Levels	7-1
7.6 Event and Action Plan for Cultural Heritage Resources	7-2

CONTENTS
(cont'd)

	Page
8. LANDSCAPE AND VISUAL	8-1
8.1 Introduction	8-1
8.2 Baseline Monitoring	8-1
8.3 Construction Phase Audit	8-1
8.4 Event and Action Plan	8-2
8.5 Landscape and Visual Impact Mitigation Measures	8-3
9. SITE ENVIRONMENTAL AUDIT	9-1
9.1 Site Inspections	9-1
9.2 Compliance with Legal and Contractual Requirements	9-2
9.3 Environmental Complaints	9-3
10. REPORTING	10-1
10.1 General	10-1
10.2 Documentation	10-1
10.3 Baseline Monitoring Report	10-1
10.4 Monthly EM&A Reports	10-2
10.5 Quarterly EM&A Summary Reports	10-7
10.6 Final EM&A Summary Report	10-8
10.7 Data Keeping	10-11
10.8 Interim Notifications of Environmental Quality Limit Exceedances	10-11
10.9 Sample Templates	10-11

END OF TEXT

APPENDICES

- Appendix A Mitigation Measures Implementation Schedule
Appendix B Proforma for EM&A Programme

CONTENTS
(cont'd)

LIST OF TABLES

Table 2.1	Air Quality Monitoring Stations
Table 2.2	Air Quality Monitoring Locations, Parameters, Frequency and Duration for Baseline
Table 2.3	Action and Limit Levels for Air Quality
Table 2.4	Event/Action Plan for Air Quality
Table 3.1	Noise Monitoring Stations for Baseline and Construction Monitoring
Table 3.2	Action and Limit Levels for Construction Noise
Table 3.3	Event/Action Plan for Construction Noise Monitoring
Table 4.1	Proposed Monitoring Locations for Water Quality
Table 4.2	Water Quality Monitoring Locations, Parameter, Frequency and Duration for Baseline
Table 4.3	Locations, Parameters, Frequencies and Durations during Construction Phases
Table 4.4	Action and Limit Levels for Water Quality
Table 4.5	Event and Action Plans for Water Quality
Table 4.6	Summary of Mitigation Measures for Construction Impacts
Table 5.1	Construction Wastes Generated by Proposed Works
Table 5.2	Construction Wastes Types and their Potential for Recycling or Re-use
Table 5.3	Responsibilities for Waste Collection, Recycling and Disposal during the Construction Phase
Table 6.1	Action and Limit Levels for Ecology
Table 6.2	Event and Action Plan for Ecology
Table 7.1	Action and Limit Levels for Cultural Heritage Resources
Table 7.2	Event and Action Plan for Cultural Heritage
Table 8.1	Event and Action Plan for Landscape and Visual Impact – Construction Phase

LIST OF FIGURES

Figure 1.1	Construction Phase Environmental Monitoring & Audit Procedures
Figure 1.2	KT13 and its relation with catchments in Northwest New Territories
Figure 1.3a	Ma On Kong Channel KT13 Proposed Layout Plan
Figure 1.3b	Ma On Kong Channel KT13 Proposed Layout Plan
Figure 1.4	Project Organisation and Lines of Authorities for EM&A
Figure 1.5	Lines of Communication for Reporting Function for the EM&A

CONTENTS
(cont'd)

Figure 2.1	Proposed Air Monitoring Locations and Representative Air Sensitive Receivers
Figure 3.1	Proposed Noise Monitoring Locations and Representative Noise Sensitive Receivers
Figure 3.2	Locations of Proposed Temporary Noise Barriers
Figure 4.1a	Recommended Water Quality and Sediment Quality Monitoring
Figure 4.1b	Recommended Water Quality and Sediment Quality Monitoring
Figure 6.1	Ecology Monitoring Areas Recommended for Construction Phase and Operation Phase
Figure 7.1	Location of Cultural Heritage Resources Monitoring
Figure 9.1	Complaint Response Procedures