

LANDSCAPE AND VISUAL MITIGATION MEASURES


- 1 CULTIVATION OF AREAS COMPACTED DURING CONSTRUCTION**
Areas compacted during the construction phase that are not required during the operations phase, are to be cultivated to a depth of 300mm in accordance with the future Landscape Specification.
- 2 SOIL STABILISATION AND EMBANKMENT PLANTING**
During the design process a soil stabilisation and embankment planting strategy should ensure that land affected by slope excavation can be replanted. Soil preparation and the selection and provision of suitable growing medium is to be completed in accordance with the relevant best practice guidelines.
Refer to Landscape Details 1,2,3 & 4.
- 3 TREE AND SHRUB PLANTING**
Planting of trees and shrubs is to be carried out in accordance with the Landscape Details and the relevant best practice guidelines. Plant densities are to be provided in future detailed design documents and are to be selected so as to achieve a finished landscape which matches the surrounding, undisturbed, equivalent landscape types.
Refer to Landscape Details 1, 2, 3 & 4.

Note: Soil stabilisation and embankment planting along with tree and shrub planting are to provide a minimum compensatory planting area of 0.74ha of Shrubland.


- 4 UTILISING NATURAL ROCK FOR RECLAMATION.**
The reclamation areas shall utilise natural rocks for the engineered sea-walls.
- 5 CUT STABILISATION**
Areas of cut to be stabilized for operational requirements. Materials and finishes of stabilization to be selected to complement the surrounding landscape where technically feasible.
- 6 BENCH PLANTINGS**
Cut Slopes to have benches created to allow for plantings. Plantings will include Shrubs and climbers to minimise the visual impact of the slope and mitigate impact on vegetation.
Refer to Landscape Detail 4

- 1 VMM1 DESIGN OF STRUCTURES**
Where possible, built structures will utilise appropriate designs to complement the surrounding landscape. Materials and finishes will also be considered during detailed design.
- 2 VMM2 COLOURS**
Colours for the terminal can be used to complement the surrounding area. Lighter colours such as shades of light grey and light brown may be utilised where technically feasible to reduce the visibility of the terminal.
- 3 VMM3 PLANTINGS**
In addition to the landscape mitigation plantings proposed in Section 11.10 of this report, appropriate new plantings will be installed where possible, to help integrate the new structures into the surrounding landscape.

- D1 DESIGN MEASURES**
Reduce tank height to be reduced from 70mPD to 61m PD.




Scale 1:5000 (A3)



BLACK POINT Fig 11.13 Landscape And Visual Mitigation Plan

Landscape Architecture
& Urban Design
21 / F Lincoln House
979 Kings Road
Taikoo Place
Island East, Hong Kong



Project No. 0018180
June 2006

ERM
ENVIRONMENTAL RESOURCES MANAGEMENT LTD