

TABLE OF CONTENT

1.	INTRODUCTION	4
	Project Description	4
	Purpose of this Manual	4
	Project Implementation	5
	Environmental Monitoring and Audit Requirements	5
	Project Organization	5
2.	CONSTRUCTION NOISE	9
	Introduction	9
	Methodology and Criteria	9
	Monitoring Equipment	9
	Monitoring Locations	10
	Baseline Monitoring	11
	Impact Monitoring	11
	Event and Action Plan	11
	Mitigation Measures	14
3.	AIR QUALITY	16
	Introduction	16
	Site Inspection	16
	Air Quality Mitigation Measures	16
4.	WATER QUALITY	17
	Introduction	17
	Site Inspection	17
	Water Quality Mitigation Measures	17
	Water Quality Monitoring in Shuen Wan Marsh and Wai Ha River	19
	Monitoring of Hydrological Characteristics of Shuen Wan Marsh	25
5.	WASTE MANAGEMENT IMPLICATIONS	30
	Introduction	30
	Waste Control and Mitigation Measures	30
6.	ECOLOGICAL IMPACT	33
	Introduction	33
	Ecological Mitigation Measures	33
	Ecological Monitoring and Audit Requirements	37
7.	LANDSCAPE AND VISUAL	43
	Introduction	43
	Monitoring Requirement	43
	Mitigation Measures	43

ET's Response to EPD Comments on Review EM&A Programme (Letter dated 1 December 2010)

Item No.	EPD's comments	ET/Ecologist's Responses (7 December 2010)
1	Nil.	Nil.

ET's Response to EPD Comments on Updated EM&A Manual

Item No.	EPD's comments	ET/Ecologist's Responses (7 December 2010)
1	<p><u>Section 1:</u> It appears that the project programme presented in Table 1.1 was already outdated. Please update the table according to the latest programme.</p>	Noted and Table 1.1 is updated accordingly.
2	<p><u>Section 2 – Construction Noise:</u> In principle, we have no objection to the applicant's suggestion of replacing the noise monitoring station "M2" by the alternative noise monitoring station "AL1" for Contract 1. However, during Contract 2, "M2" is much closer to the work site under Contract 2 than "AL1". Therefore, we consider it appropriate to resume noise monitoring at "M2" upon completion of construction works of domestic development at the location as indicated by the applicant. Amendment to Paragraph 2.14 to include "M2" is required. Table 2.4 should also include "M2" with a note that "noise monitoring at M2 would be carried out when the construction works of the nearby domestic development, affecting the noise measurement, has completed".</p>	Noted and section 2.14 and Table 2.4 is modified to resume monitoring station "M2" when the domestic development is completed.
3	<p><u>Section 4 – Water Quality:</u> Appendix A: Under water quality section, with reference to ProPECC PN 1/94, "as far as practicable" in the fifth bullet and "of more than 50m³" in the last bullet should be removed.</p>	Noted and Appendix A – Water Quality section is amended accordingly.

8.	ENVIRONMENTAL AUDIT	45
	Site Inspection	45
	Compliance with Legal and Contractual Requirements	45
	Environmental Complaints	46
9.	REPORTING	47
	General	47
	Baseline Monitoring Report	47
	Monthly EM&A Reports	48
	Quarterly EM&A Summary Reports	51
	Final EM&A Review Report	52
	Data Keeping	53
	Interim Notifications of Environmental Quality Limit Exceedances	53

Appendices

Appendix A	Implementation Schedule of Mitigation Measures
Appendix B	Construction Stage Noise Monitoring Field Record Sheet
Appendix C	Incident Report on Action Level or Limit Level Non-compliance
Appendix D	Water Quality Monitoring Data Record Sheet
Appendix E	Figure 5 & Section 5.5.4 of HCP
Appendix F	Hydrological Characteristics Monitoring Data Record Sheet

List of Tables

Table 1.1	Preliminary Project Programme
Table 2.1	Acceptable Noise Levels (ANLs)
Table 2.2	Noise Monitoring Stations during Construction Phase
Table 2.3	Alternative Noise Monitoring Stations during Construction Phase
Table 2.4	Action and Limit Levels for Construction Noise
Table 2.5	Event / Action Plan for Construction Noise
Table 2.6	Quieter PME Recommended for Adoption during Construction Phase
Table 2.7	Plant Inventory for the Low Impact Method
Table 4.1	Methods and Detection Limits for Laboratory Analysis
Table 4.2	Construction Phase Water Quality Monitoring Locations for Contract 1
Table 4.3	Construction Phase Water Quality Monitoring Locations for Contract 2
Table 4.4	Water Quality Monitoring Frequency in Construction Phase
Table 4.5	Action and Limit Levels for Water Quality Monitoring
Table 4.6	Event and Action Plan for Water Quality
Table 4.7	Construction Phase Hydrological Characteristics Monitoring Locations for Contract 1
Table 4.8	Construction Phase Hydrological Characteristics Monitoring Locations for Contract 2
Table 4.9	Event and Action Plan for Hydrological Characteristics
Table 6.1	Construction and Establishment Phase Ecological Monitoring by the Contractor's Ecologist for the ECA
Table 6.2	Proposed Contingency Plan for Monitoring and Maintaining the ECA
Table 6.3	Maintenance and Management Schedule for the ECA during the Post-establishment Phase
Table 6.4	Pre-construction, Construction and Operation Phase Ecological Monitoring by the Contractor's Ecologist for Areas under Contract 2

List of Figures

Figure 1.1	Location of the Project
Figure 1.2	Project Organization for Environmental Management
Figure 2.1	Location of Construction Noise Monitoring Station

Agreement No. CE 50/2001
Drainage Improvement in Sha Tin and Tai Po
Design and Construction
Updated Environmental Monitoring and Audit Manual

Figure 2.2	Typical Section of Proposed Temporary Barrier
Figure 2.3	Typical Design of Noise Enclosure
Figure 4.0	Location of Channel Link between Wai Ha River & ECA
Figure 4.1	Location of Water Quality Monitoring Station
Figure 4.2	Location of Hydrological Characteristics Monitoring Station
Figure 6.1	Ecological Monitoring Area for Contract 2 of the Project

1. INTRODUCTION

Project Description

- 1.1 The Sha Tin and Tai Po Drainage Master Plan (DMP) Study, completed in October 1999, indicated that certain stormwater drains and natural rivers/streamcourses in the Sha Tin and Tai Po areas did not have the required hydraulic capacity to meet the flow requirements. To minimize the risks of flooding and to cope with future developments as identified in the DMP Study, construction of river channels, upgrading of existing stormwater drains, construction of flood pumping stations in the low-lying areas and other minor drainage facilities were recommended.
- 1.2 Upon completion of the DMP Study, Drainage Services Department (DSD) of Hong Kong SAR Government commissioned Maunsell Consultants Asia Ltd. (MCAL) to undertake Agreement No. CE50/2001 (DS) Drainage Improvement in Sha Tin and Tai Po – Design and Construction (hereinafter referred to as “the Assignment”), for implementing the drainage improvement works at various locations as recommended by the DMP study to alleviate the potential flooding problems in Sha Tin and Tai Po districts.
- 1.3 This manual presents the environmental monitoring and auditing requirements associated with the proposed drainage improvement works in Shuen Wan (the Project), which comprises the following five works items:
 - Construction of a 1000m long 3m x 2.5m twin-cell box culvert along Tung Tsz Road
 - Replacement of existing gates by automatic mechanical gates at the mouth of Wai Ha River
 - Construction of a 280m long 1200dia. drainage pipe near Wai Ha Village
 - Construction of a 260m long 2100dia. flood relief drain along Ting Kok Road
 - Construction of a floodwater pumping station at Shuen Wan
- 1.4 An Environmental Impact Assessment (EIA) study was conducted to provide information on the nature and extent of potential environmental impacts pertinent to the construction and operation of the Project. The findings are presented in a separate EIA report.
- 1.5 **Figure 1.1** shows the location of the Project.

Purpose of this Manual

- 1.6 As part of the EIA study, the purpose of this Environmental Monitoring and Audit (EM&A) Manual is to provide guidelines for the setting up of an EM&A programme to check on compliance with the environmental protection conditions, EIA Report recommendations, assess the effectiveness of the recommended mitigation measures, and identify any need for additional mitigation measures or remedial action. This Manual also outlines the monitoring and audit programme for the construction and operation phases of the works proposed under the Project.
- 1.7 The EM&A Manual has been prepared in accordance with the requirements stipulated in Annex 21 of the Technical Memorandum on the EIA Process (EIAO TM).
- 1.8 This Manual contains the following information:
 - Responsibilities of the Contractor, the Engineer or Engineer's Representative (ER), Environmental Team (ET) and Independent Environmental Checker (IEC) with respect to the EM&A requirements during the implementation of the Project.
 - Information on the project organization and programming of construction activities.

- Project construction schedule and necessary environmental monitoring and audit programme to track environmental impacts.
- Requirements for the review of pollution sources and working procedures in the event of non-compliance of the project's environmental performance criteria.
- Environmental monitoring protocols and their technical requirements.
- Environmental auditing procedures.
- Requirements for the documentation of environmental monitoring and audit data, and appropriate reporting procedures.
- Complaint resolution procedures.

1.9 For the purpose of this Manual, the ET leader, who should be responsible for and in charge of the ET, should refer to the person or party delegated the role of executing the respective EM&A requirements.

Project Implementation

1.10 The project will be implemented under two works contracts, which comprises the following works:-

Contract 1

- Construction of a floodwater pumping station
- Construction of a flood relief drain along Ting Kok Road
- Construction of a twin-cell box culvert from the pumping station passing underneath Ting Kok Road and Tung Tsz Nursery and connect to twin cell box culvert (to be constructed under Contract 2)
- Installation of Auto mechanical gates at the mouth of Wai Ha River

Contract 2

- Construction of a twin-cell box culvert along Tung Tsz Road
- Construction of a drainage pipe near Wai Ha Village

The project programme for this Project is presented in **Table 1.1**.

Table 1.1 Project Programme

Task Description	Tentative/Actual Completion Date
Selection of the Scheme	May 2005
Detailed Design of Works	February 2007
Commencement of Contract 1	February 2010 (Construction in January 2011)
Commencement of Contract 2	May 2011
Completion of Contract 1	August 2013
Completion of Contract 2	March 2014

Environmental Monitoring and Audit Requirements

1.11 The construction and operational phase environmental impacts of the Project were assessed, and are presented in the EIA report on Drainage Improvement in Sha Tin and Tai Po – Design and Construction. The EIA report has identified the recommended environmental mitigation measures to minimize the potential adverse environmental impacts identified. An implementation schedule of the recommended mitigation measures is also prepared as part of the EIA study and is provided in **Appendix A** of this Manual.

Project Organisation

1.12 The proposed project organisation and lines of communication with respect to environmental protection works are shown in **Figure 1.2**.

1.13 The general duties/responsibilities of various parties comprise the following:

Engineer or Engineer's Representative (ER)

1.14 The term ER, refers to the organisation responsible for overseeing the construction works or operation of the Project undertaken by various Contractors, and for ensuring that the construction works are undertaken by the Contractors in accordance with the specification and requirements in the Contract. The ER should:

- Monitor the Contractors' compliance with contract specifications, including Environmental Permit (EP) conditions, and the implementation and operation of the environmental mitigation measures.
- Follow the requirements in the agreed Event / Action Plan in the event of any exceedance.
- Provide assistance to the ET as necessary in the implementation of the EM&A programme.
- Engage IEC services to audit EM&A works carried out by the ET.
- Require the Contractor to follow the agreed protocols or those in the contract specifications in the event of exceedance or complaints.

The Contractor

1.15 The term "Contractor" should be taken to mean all construction contractors and sub-contractors, working on site at any one time. Besides reporting to the ER, the Contractor should:

- Work within the scope of the relevant requirements in the contract and EP.
- Participate in site inspections undertaken by the ET and undertake any corrective actions as necessary.
- Provide information / advice to the ET regarding works activities which may contribute to the generation of adverse environmental conditions.
- Implement measures to reduce impact where Action and Limit levels are exceeded.
- Submit proposals on mitigation measures in case of exceedances of Action and Limit levels in accordance with the Event / Action Plans.
- Follow the procedures for carrying out complaint investigation.

Independent Environmental Checker (IEC)

1.16 The IEC should advise the ER on environmental issues related to the Project, and should be empowered to audit the environmental performance of construction.

1.17 The IEC should have at least 7 years' local experience in EM&A and ecology, and one year of which should be relevant to recent ecological survey / monitoring work in the Shuen Wan area. The IEC should also have relevant professional qualifications, which should include being an Accredited Monitoring Professional of the Hong Kong Institute of Environmental Impact Assessment (HKIEIA), and have relevant project management experience. The appointment of the IEC is subject to the approval of the ER. The IEC should be employed prior to the commencement of the construction of the Project.

1.18 The main duty of the IEC is to carry out environmental audit of the project; this should include, inter alia, the following:

- Review and audit all aspects of the EM&A programme.

- Validate and confirm the accuracy of monitoring results, monitoring equipment, monitoring locations, monitoring procedures and locations of sensitive receivers.
- Carry out random sample check and audit on monitoring data and sampling procedures.
- Conduct random site inspection.
- Audit the EIA recommendations and requirements against the status of implementation of environmental protection measures on site.
- Review the effectiveness of environmental mitigation measures and project environmental performance.
- On a need basis, verify and certify the environmental acceptability of the Contractor's construction methodology (both temporary and permanent works), relevant design plans and submissions under the EP. Where necessary, the IEC should seek the least impact alternative in consultation with ET leader and the Contractor.
- Verify the investigation results of complaint cases and the effectiveness of corrective measures.
- Verify EM&A report that has been certified by the ET leader.
- Feedback audit results to ET according to Event and Action Plan in the manual.
- Verify the results of the ecological monitoring of the compensatory ecological habitats. Details of the monitoring requirements are set out in **Section 6.16** of this Manual.

Environmental Team (ET)

- 1.19 The ET leader and the ET should be employed to conduct the EM&A programme and check the Contractor's compliance with the Project's environmental performance requirements during construction. The ET should be led and managed by the ET leader.
- 1.20 The ET leader should be an independent party from the Contractor and should possess at least 7 years' local experience of EM&A and have relevant professional qualifications, which should include being an Accredited Monitoring Professional of the Hong Kong Institute of Environmental Impact Assessment (HKIEIA). The ET leader should have at least 3 years of experience in ecological monitoring given ecological impact would be the key environmental issue of this Project. The appointment of the ET is subject to the approval of the ER and the Director of Environmental Protection.
- 1.21 Suitably qualified staff should be included in the ET, and resources for the implementation of the EM&A programme should be allocated in time under the Contract, to enable fulfilment of the requirements as specified in the EM&A Manual during construction and operation of the Project.
- 1.22 Duties of the ET are:
- Conduct sampling, analysis and statistical evaluation of monitoring parameters with reference to the EIA study recommendations and requirements.
 - Conduct environmental site surveillance.
 - Audit of compliance with environmental protection, and pollution prevention and control regulations.
 - Monitor the implementation of environmental mitigation measures.
 - Monitor compliance with the environmental protection clauses/specifications in the Contract.
 - Review construction programme and comment as necessary.
 - Review construction methodology and comment as necessary.

Agreement No. CE 50/2001
Drainage Improvement in Sha Tin and Tai Po
Design and Construction
Updated Environmental Monitoring and Audit Manual

- Conduct complaint investigation, evaluation and identification of corrective measures.
- Liaise with IEC on all environmental performance matters, and timely submit all relevant EM&A proforma for IEC's approval.
- Provide advice to the Contractor on environmental improvement, awareness, enhancement matters, etc. on site.
- Submit EM&A report timely to the Project Proponent and the Director of Environmental Protection.

1.23 Sufficient and suitably qualified professional and technical staff should be employed by the respective parties to confirm full compliance with their duties and responsibilities, as required under the EM&A programme for the duration of the Project.

2. CONSTRUCTION NOISE

Introduction

- 2.1 In this section, the requirements, methodology, equipment, monitoring locations, criteria and protocols for the monitoring and audit of noise impacts during the construction phase of the Project are presented.

Methodology and Criteria

- 2.2 The construction noise level should be measured in terms of the A-weighted equivalent continuous sound pressure level (L_{eq}). L_{eq} (30 minutes) should be used as the monitoring parameter for the time period between 0700 and 1900 hours on normal weekdays. For all other time periods, L_{eq} (5 minutes) should be employed for comparison with the Noise Control Ordinance (NCO) criteria.
- 2.3 Supplementary information for data auditing, statistical results such as L_{10} and L_{90} should also be obtained for reference. A sample data record sheet is shown in **Appendix B** for reference.
- 2.4 Whilst the Noise Control Ordinance (NCO) does not provide for the statutory control of construction activities occurring on weekdays during normal working hours (i.e. Monday to Saturday inclusive 0700-1900 hours), a daytime standard of $L_{Aeq}(30 \text{ minute})$ 75dB stipulated in *Annex 5 of the Technical Memorandum on Environmental Impact Assessment Process* is used as the appropriate criterion for all residential dwellings; while a daytime standard of $L_{Aeq}(30 \text{ minute})$ 70dB was adopted for all educational institutions during normal school days and L_{Aeq} (30 minute) 65dB during examination periods.
- 2.5 The NCO provides statutory controls on general construction works during restricted hours (i.e. 1900-0700 hours Monday to Saturday and at any time on Sundays and public holidays). The ANLs for evenings and holidays and for night-time are dependent on the Area Sensitivity Rating at the NSR. The relevant ANLs are provided in Table 2.1.

Table 2.1 Acceptable Noise Levels (ANLs)

Time Period	Area Sensitivity Rating		
	A	B	C
All days during the evening (1900-2300 hours) and general holidays (including Sundays) during the day and evening (0700-2300 hours)	60	65	70
All days during the night-time (2300-0700)	45	50	55

Monitoring Equipment

- 2.6 As referred to in the Technical Memorandum (TM) issued under the NCO, sound level meters in compliance with the International Electrotechnical Commission Publications 651: 1979 (Type 1) and 804: 1985 (Type 1) specifications should be used for carrying out the noise monitoring. Immediately prior to and following each noise measurement the accuracy of the sound level meter should be checked using an acoustic calibrator generating a known sound pressure level at a known frequency. Measurements may be accepted as valid only if the calibration level from before and after the noise measurement agree to within 1.0 dB.
- 2.7 Noise measurements should not be made in the presence of fog, rain, wind with a steady speed exceeding 5ms^{-1} or wind with gusts exceeding 10ms^{-1} . The wind speed should be checked with a portable wind speed meter capable of measuring the wind speed in m/s.
- 2.8 The ET is responsible for the provision of the monitoring equipment. He should confirm that sufficient noise measuring equipment and associated instrumentation are available for carrying out

the baseline monitoring, regular impact monitoring and ad hoc monitoring. All the equipment and associated instrumentation should be clearly labelled.

Monitoring Locations

2.9 Based on the EIA study, four worst affected locations are designated for construction noise monitoring as listed in Table 2.2 and illustrated in **Figure 2.1**. The status and location of noise sensitive receivers may change after issuing this manual. If such cases exist, the ET Leader should propose updated monitoring locations and seek approval from ER and agreement from the IEC and EPD on the proposal.

Table 2.2 Noise Monitoring Stations during Construction Phase

Noise Monitoring Station	Noise Monitoring Location
M1	14, Shuen Wan Chim Uk
M2	150, San Tau Kok
M3	31, Wai Ha
M4	Block 15, Treasure Spot Garden

2.10 When alternative monitoring locations are proposed, the monitoring locations should be chosen based on the following criteria:

- Monitoring at sensitive receivers close to the major site activities which are likely to have noise impacts;
- Monitoring at the noise sensitive receivers as defined in the Technical Memorandum;
- Assurance of minimal disturbance to the occupants during monitoring.

2.11 The monitoring station should normally be at a point 1 m from the exterior of the noise sensitive facade and be at a position 1.2 m above ground. If there is a problem with access to the normal monitoring position, an alternative position should be chosen, and a correction to the measurements should be made. For reference, a correction of +3 dB(A) should be made to the free field measurements. The ET should agree with the IEC and EPD on the monitoring position and the corrections adopted. Once the positions for the monitoring stations are chosen, the baseline monitoring and the impact monitoring should be carried out at the same positions.

Alternative Noise Monitoring Locations for Contract 1

2.12 Although the Contractor has taken the possession of Area L, no construction activities will be carried out in Area L under Contract 1. Therefore, the Environmental Team Leader propose to omit noise monitoring station M4 from Contract 1. Furthermore, Noise Monitoring station M3 is more than 300 meters away from any major activities of Contract 1, so they will not be monitored in Contract 1.

2.13 Due to a domestic development on Tung Tze Road potentially affecting the reliability of noise monitoring data collected at M2, alternative noise monitoring location, AL1 is proposed by the ET Leader. The monitoring station AL1, which is situated at the Joint Village Office for Villages in Shuen Wan, Tai Po, can capture construction noise produced from Areas A and B. Many populated village houses are located adjacent to the Joint Village Office, hence the ET Leader sees this location as a suitable replacement for M2. The proposed locations are listed in Table 2.3.

Table 2.3 Alternative Noise Monitoring Stations during Construction Phase

Noise Monitoring Station	Noise Monitoring Location
M1	14, Shuen Wan Chim Uk
AL1	Joint Village Office for Villages in Shuen Wan, Tai Po

Noise Monitoring Locations for Contract 2

- 2.14 Due to the change of monitoring locations for Contract 1, the monitoring locations for Contract 2 are also changed and they are listed in Table 2.4. In the case of the domestic development completes before the completion of Contract 2, monitoring station M2 will be resumed.

Table 2.4 Noise Monitoring Stations during Construction Phase for Contract 2

Noise Monitoring Station	Noise Monitoring Location
M1	14, Shuen Wan Chim Uk
AL1	Joint Village Office for Villages in Shuen Wan, Tai Po
M2*	150, San Tau Kok
M3	31, Wai Ha
M4	Block 15, Treasure Spot Garden

*Monitoring station M2 will be resumed when the construction works of the nearby domestic development, affecting the noise measurement, has completed.

Baseline Monitoring

- 2.15 The ET should carry out baseline noise monitoring prior to the commencement of the construction works. The baseline monitoring should be measured for a continuous period of at least 14 consecutive days at a minimum logging interval of 30 minutes (as six consecutive $L_{Aeq, 5min}$ readings) for daytime and 15 minutes (as three consecutive $L_{Aeq, 5min}$ readings) for evening time and night time. The L_{eq} , L_{10} and L_{90} should be recorded at the specified interval. A schedule on the baseline monitoring should be submitted to the IEC and EPD for approval before the monitoring starts.
- 2.16 There should not be any construction activities in the vicinity of the stations during the baseline monitoring. Any non-project related construction activities in the vicinity of the stations during the baseline monitoring should be noted and the source and location recorded.
- 2.16 In exceptional cases, when insufficient baseline monitoring data or questionable results are obtained, the ET should liaise with the EPD to agree on an appropriate set of data to be used as a baseline reference and submit to the ER for approval.

Impact Monitoring

- 2.18 Noise monitoring should be carried out at all the designated monitoring stations. The monitoring frequency should depend on the scale of the construction activities. The following is an initial guide on the regular monitoring frequency for each station on a weekly basis when noise-generating activities are underway:

- one set of measurements between 0700 and 1900 hours on normal weekdays.

- 2.19 In case of non-compliance with the construction noise criteria, more frequent monitoring, as specified in the Action Plan in **Table 2.5**, should be carried out. This additional monitoring should be continued until the recorded noise levels are rectified or proved to be irrelevant to the construction activities.

Event and Action Plan

- 2.20 The Action and Limit levels for construction noise are defined in **Table 2.5**. Should non-compliance of the criteria occur, action in accordance with the Action Plan in **Table 2.6** should be carried out.

Table 2.5 Action and Limit Levels for Construction Noise

Agreement No. CE 50/2001
Drainage Improvement in Sha Tin and Tai Po
Design and Construction
Updated Environmental Monitoring and Audit Manual

Time Period	Action Level	Limit Level
0700 – 1900 hours on normal weekdays	When one documented complaint is received	75 dB(A)

*Acceptable Noise Levels for Area Sensitivity Rating of A/B/C.

Table 2.6 Event / Action Plan for Construction Noise

EVENT	ACTION			
	ET Leader	IEC	ER	CONTRACTOR
Action Level	<ol style="list-style-type: none"> 1. Notify IEC and Contractor. 2. Carry out investigation. 3. Report the results of investigation to the IEC, ER and Contractor. 4. Discuss with the Contractor and formulate remedial measures. 5. Increase monitoring frequency to check mitigation effectiveness. 	<ol style="list-style-type: none"> 1. Review the analysed results submitted by the ET. 2. Review the proposed remedial measures by the Contractor and advise the ER accordingly. 3. Supervise the implementation of remedial measures. 	<ol style="list-style-type: none"> 1. Confirm receipt of notification of failure in writing. 2. Notify Contractor. 3. Require Contractor to propose remedial measures for the analysed noise problem; 4. Check remedial measures are properly implemented. 	<ol style="list-style-type: none"> 1. Submit noise mitigation proposals to IEC. 2. Implement noise mitigation proposals.
Limit Level	<ol style="list-style-type: none"> 1. Notify IEC, ER, EPD and Contractor. 2. Identify source. 3. Repeat measurements to confirm findings. 4. Increase monitoring frequency. 5. Carry out analysis of Contractor's working procedures to determine possible mitigation to be implemented. 6. Inform IEC, ER and EPD the causes and actions taken for the exceedances. 7. Assess effectiveness of Contractor's remedial actions and keep IEC, EPD and ER informed of the results. 8. If exceedance stops, cease additional monitoring. 	<ol style="list-style-type: none"> 1. Discuss amongst ER, ET, and Contractor on the potential remedial actions. 2. Review Contractor's remedial actions whenever necessary to assure their effectiveness and advise the ER accordingly. 3. Supervise the implementation of remedial measures. 	<ol style="list-style-type: none"> 1. Confirm receipt of notification of failure in writing. 2. Notify Contractor. 3. Require Contractor to propose remedial measures for the analysed noise problem. 4. Check remedial measures properly implemented. 5. If exceedance continues, consider what portion of the work is responsible and instruct the Contractor to stop that portion of work until the exceedance is abated. 	<ol style="list-style-type: none"> 1. Take immediate action to avoid further exceedance. 2. Submit proposals for remedial actions to IEC within 3 working days of notification. 3. Implement the agreed proposals. 4. Resubmit proposals if problem still not under control. 5. Stop the relevant portion of works as determined by the ER until the exceedance is abated.

Mitigation Measures

Good Site Practice

2.21 The following good site practices were recommended in the EIA study:

- Only well-maintained plant should be operated on-site and plant should be serviced regularly during the construction program;
- Silencers or mufflers on construction equipment should be utilized and should be properly maintained during the construction program;
- Mobile plant, if any, should be sited as far from NSRs as possible;
- Machines and plant (such as trucks) that may be in intermittent use should be shut down between work periods or should be throttled down to a minimum;
- Plant known to emit noise strongly in one direction should, wherever possible, be orientated so that the noise is directed away from the nearby NSRs; and
- Material stockpiles and other structures should be effectively utilized, wherever practicable, in screening noise from on-site construction activities.

Adoption of Quieter PME

2.22 The EIA study recommended the use of quieter plants for the construction tasks proposed for the Project. The quieter plants recommended are listed in the table below.

Table 2.7 Quieter PME Recommended for Adoption during Construction Phase

PME	Reference	SWL
Excavator / Loader	BS C3/97	105
Dump Truck	BS C9/39	103
Concrete Lorry Mixer	BS C6/23	100
Vibratory Poker	BS C6/32	100
Breaker, Excavator Mounted (Hydraulic)	BS C8/12	106
Vibratory Roller	Noise data of Quality PME from EPD Website	101

Use of Temporary Noise Barrier

2.23 Temporary noise barriers of about 3.5m high have been recommended in the EIA study for screening of noise from the PMEs used for the construction of box culvert and site clearance. This can achieve a 5 dB(A) reduction for movable plants and 10dB(A) for stationary plant, depending on the line of sight that could be blocked by the barriers when viewed from the NSR.

2.24 **Figure 2.2** shows the typical section of the proposed temporary noise barriers. The barriers should be made of material of surface mass in excess of 7kg/m² to achieve the predicted screening effect.

Use of Quieter Alternative Construction Method

2.25 Quieter alternative construction method (hereinafter referred to as “the Low Impact Method”) has been proposed in the EIA study. This method involves using PMEs with lower impact and generally smaller in size, making it possible to be enclosed by noise enclosure which can further reduce the noise emission levels. **Table 2.7** presents the proposed PME for the Low Impact Method.

Table 2.8 Plant Inventory for the Low Impact Method

Construction Sub-task	PME	Reference	SWL
Pipe laying at Wai Ha			
Excavation	Hand-held breaker	CNP024	108
	Air compressor	CNP002	102
	Mini backhoe	CNP082	94
Pipe Laying	Mini backhoe	CNP082	94
	Vibratory poker	BSC6/32	100
Backfilling	Vibratory poker	BSC6/32	100
	Vibratory roller	EPD Website: Quality PME	101

Noise Enclosures and Temporary Noise Barriers

- 2.26 Noise enclosure has been proposed in the EIA study to alleviate the construction noise impact. It can be used for enclosing the PMEs (except mini backhoe) as listed in **Table 2.7**. For mini backhoe, the roof panels of the noise enclosure should be removed when it is in use and the side panels would form a temporary noise barrier (as illustrated in **Figure 2.2**) along the periphery of the works area. The conceptual design of the noise enclosure is shown in **Figures 2.3**.
- 2.27 The noise enclosure should be made of materials with a surface mass of not less than 10kg/m² to achieve the maximum screening effect. Openings should be provided at the side of the noise enclosure facing towards the natural hillside and away from the NSRs for ventilation. The noise enclosure should be designed to achieve at least 15dB(A) noise reduction for PME.
- 2.28 The implementation schedule for the recommended mitigation measures is presented in **Appendix A**.

3. AIR QUALITY

Introduction

- 3.1 This section presents the requirements, methodology, equipment, monitoring locations, criteria and protocols for the audit of air quality impacts during the construction phase of the Project.
- 3.2 According to the EIA study, significant dust emission arising from the construction activities would not be expected. With the implementation of mitigation measures as stipulated in the *Air Pollution Control (Construction Dust) Regulation*, it would be unlikely that the Project would result in adverse air quality impact on the representative ASRs.
- 3.3 Therefore, no air quality monitoring would be required during construction of the drainage improvement works. It is recommended that auditing works during construction phase be carried out to check that the Contractor has implemented the recommended mitigation measures to minimize the construction dust impact.

Site Inspection

- 3.4 Weekly site audits should be carried out to inspect the construction activities and works areas in order to confirm the recommended dust control mitigation measures are implemented and are working effectively. The Contractor should be responsible for the implementation of the *Air Pollution Control (Construction Dust) Regulation* and good site practices

Air Quality Mitigation Measures

- 3.5 Mitigation measures have been proposed in the EIA study, including the implementation of the *Air Pollution Control (Construction Dust) Regulation* and good site practices. The practical measures are summarized as below:
- Use of regular watering to reduce dust emissions from exposed site surfaces and unpaved road, with complete coverage, particularly during dry weather;
 - Use of frequent watering for particularly dusty static construction areas and areas close to ASRs;
 - Tarpaulin covering of all dusty vehicle loads transported to, from and between site location;
 - Establishment and use of vehicle wheel and body washing facilities at the exit points of the site;
 - Routing of vehicles and positioning of construction plant should be at the maximum possible distance from ASRs;
 - Stockpiled excavated materials should be covered with tarpaulin, and should be removed off-site within 24 hours to avoid any odour nuisance arising.
- 3.6 Upon receipt of an environmental complaint, or as part of the environmental audit, the Contractor should liaise with the ET on some other mitigation measures, propose to ER for approval, and implement the mitigation measures.

4. WATER QUALITY

Introduction

- 4.1 The water quality assessment in the EIA study identified that no adverse impact would occur during the construction and operation of the Project provided the recommended mitigation measures were properly implemented. It is recommended that regular site inspections (at least weekly) be undertaken to audit the construction activities and works areas in order to check the recommended mitigation measures are properly implemented.

Site Inspection

- 4.2 Site inspection should be conducted at least weekly to inspect the construction activities and works areas in order to check the recommended mitigation measures are properly implemented

Water Quality Mitigation Measures

- 4.3 Mitigation measures recommended for the construction and operation phases of the Project are summarized below. The implementation schedule of the recommended water quality mitigation measures is presented in **Appendix A**.

Construction Phase

Construction Run-off and Drainage

- 4.4 Mitigation measures should be implemented to control construction site runoff and drainage from the works areas, and to prevent runoff and drainage water with high levels of suspended solids from entering the Wai Ha River, fishponds and the receiving water body of Tolo Harbour. The construction phase discharges should comply with the WPCO requirements.
- 4.5 The site practices outlined in ProPECC PN 1/94 "Construction Site Drainage" should be followed during the drainage improvement works in order to minimise surface runoff and to control erosion, and also to retain and reduce any suspended solids prior to discharge. These practices include the following items and should be implemented as an erosion control plan during the construction phase:
- Before commencing any site formation work, all sewer and drainage connections should be sealed to prevent debris, soil, sand etc. from entering public sewers/drains.
 - Temporary ditches should be provided to facilitate run-off discharge into appropriate watercourses, via a silt retention pond. No site run-off should enter the fishponds at Shuen Wan.
 - Sand/silt removal facilities such as sand traps, silt traps and sediment basins should be provided to remove sand/silt particles from runoff to meet the requirements of the Technical Memorandum standard under the Water Pollution Control Ordinance. The design of silt removal facilities should be based on the guidelines provided in ProPECC PN 1/94. All drainage facilities and erosion and sediment control structures should be inspected monthly and maintained to attain proper and efficient operation at all times and particularly during rainstorms.
 - Water pumped out from excavated pits should be discharged into silt removal facilities.
 - During rainstorms, exposed slope/soil surfaces should be covered by a tarpaulin or other means. Other measures that need to be implemented before, during, and after rainstorms are summarized in ProPECC PN 1/94.
 - Exposed soil areas should be minimized to reduce potential for increased siltation and contamination of runoff.

- Earthwork final surfaces should be well compacted and subsequent permanent work or surface protection should be immediately performed to reduce the potential of soil erosion.
- Open stockpiles of construction materials or construction wastes on-site should be covered with tarpaulin or similar fabric during rainstorms.

4.6 With standard water pollution control measures set out in ProPECC PN1/94 in place, it is anticipated that the construction phase discharges would comply with the WPCO requirements.

4.7 In addition, precautionary measures for controlling potential water quality impact due to the proposed works close to the Conservation Area should be required in order to safeguard the known sites of high ecological value during the construction phase, particularly during the rainy season as there is a risk that intense rainfall events may result in discharge of turbid drainage water. The contractor should implement the following mitigation measures:

- For the construction of the box culvert next to the existing channel of the Wai Ha River, sand bags should be deployed around the boundary of the works trench to prevent muddy water ingress into the adjacent CA or Wai Ha River. As an effective measure, sand bags should be used to surround the excavated trench. Generally, the sand bags will be placed up to a height of 300mm to provide adequate allowance for the built-up water level during rainstorm event. With sand bags in place, unpolluted surface runoff will be intercepted and flow to Wai Ha River or collected by the existing drainage system as usual.
- For the construction of the box culvert in the extreme northeast corner of Shuen Wan Marsh Conservation Area sand bags should be deployed along the limit of the works area to prevent muddy water ingress into the CA. Sand bags should be placed to a height of at least 300mm from ground level and +2.5 mPD (whichever is greater) to provide adequate allowance for the built-up water level during rainstorm events. Unpolluted surface runoff within the works area should then be collected and directed into the existing drainage system.
- Sheet-piles, which would be installed around the works trench near the Conservation Area, would be extended above ground level for about 2m to serve as hoardings to isolate the works site.
- Tarpaulin sheets would be used to cover the excavation areas during heavy rainstorms. This would prevent the ingress of rainwater into the trench minimising the risk of muddy water getting into Wai Ha River and the adjacent Conservation Area.
- Any concrete washing water would be contained inside the works site surrounded by the extended sheet piles. A pump sump at the bottom of the trench would be provided to pump any excess water during concrete washing.
- Stockpiling the excavated materials adjacent to the Conservation Area would not be allowed. The excavated materials would be either removed off site immediately after excavation, or stockpile at location(s) away from the Conservation Area. The stockpile locations should be approved by the site engineer.

General Construction Activities

4.8 Debris and refuse generated on-site should be collected, handled and disposed of properly to avoid entering the Wai Ha River and fish ponds at Shuen Wan. Stockpiles of cement and other construction materials should be kept covered when not being used.

4.9 Oils and fuels should only be used and stored in designated areas which have pollution prevention facilities. To prevent spillage of fuels and solvents to nearby water bodies, all fuel tanks and storage areas should be provided with locks and be sited on sealed areas, within bunds of a capacity equal to 110% of the storage capacity of the largest tank. The bund should be drained of rainwater after a rain event.

Sewage from Construction Workforce

- 4.10 Temporary sanitary facilities, such as portable chemical toilets, should be employed on-site. A licensed contractor would be responsible for appropriate disposal and maintenance of these facilities.

River Channel Excavation Works

- 4.11 The excavation works within the upstream end of the existing river channel of the Wai Ha River for the construction of the proposed box culvert should be carried out in a dry condition. Containment measures such as bunds and barriers should be used within the affected length of the river channel and the excavation works restricted to within an enclosed dry section of the channel. The excavation works should be restricted to the period from October to April.
- 4.12 Creation of the Ecological Compensatory Area (ECA) as shown in Figure 7.2 of the EIA Report and as detailed in the Habitat Compensatory Plan (HCP) will involve the formation of a channel link to the Wai Ha River in order to divert water into (ECA). The formation of the channel link should be undertaken during the period from October to April and all excavation work should be carried out from the landward (ECA) side. Prior to actually establishing the connection a temporary sandbag barrier should be placed in the channel during low tide (tide height less than +1.5 mPD) to isolate the section of bank which is to be removed to form the channel. Once the bank has been lowered to the required height and the required works to stabilize the channel floor and sides have been undertaken, the temporary sandbag barrier will be removed. The removal of temporary sandbag barrier will effect water quality and water flow of Wai Ha River. The water quality and water flow will be monitored by the respective water quality and hydrological characteristics monitoring stated out in the following sections. Water pollution control measures set out in ProPECC PN1/94 shall be strictly followed, such that construction phase discharges would comply with the WPCO requirements.
- 4.13 The location of the channel link is shown in Figure 4.0. For details on the formation of channel link, please refer to the Figure 5 and Section 5.5.4 of the HCP in **Appendix E**.

Water Quality Monitoring in Shuen Wan Marsh and Wai Ha River

- 4.14 The EIA study, Section 5.16, indicates the construction of penstock and ECA shall not significantly affect the water quality of the water sensitive receivers within Tolo Harbour, namely the fish ponds at Shuen Wan, Wai Ha River. However, the construction of ECA for Contract 1 and box culvert for Contract 2 include excavation at sections adjacent to the Wai Ha River, so a water quality monitoring scheme for construction phase was determined to be necessary.
- 4.15 The water quality parameters which need to be monitored include dissolved oxygen (DO), dissolved oxygen saturation, temperature, turbidity, suspended solids (SS) and pH. In association to the water quality parameters, relevant data including location/position, time, weather conditions, and any other special phenomena and work underway at the construction site shall also be recorded. A sample of data collection sheet is presented in **Appendix D**.

Monitoring Equipment

- 4.16 Monitoring equipment such as the DO and temperature measuring equipment, turbidity measurement instrument, water sampler and pH indicator shall be supplied by the ET and approved by the IEC and the Engineer for water quality monitoring.
- 4.17 Dissolved Oxygen, Dissolved Oxygen Saturation, Temperature, Turbidity and pH Measurement
- 4.17.1 The instrument shall a portable and weatherproof multimeter complete with cable and use a DC power source. The instrument is capable of measuring:
- A turbidity between 0-800NTU;
 - A dissolved Oxygen level in the range of 0-20mg/L and 0-200% saturation;
 - A temperature of 0-45°C;
 - pH in the range of 0-14.

- 4.17.2 Should any of the measuring parameters not be built-in in the multimeter, ET shall supply specifications of monitoring equipments to IEC and Engineer for approval.
- 4.18 Water Sampler
- 4.18.1 A water sampler is required. It shall comprise a transparent PVC cylinder, with a capacity of not less than 2 litres, which can be effectively sealed with latex cups at both ends. The sampler shall have a positive latching system to keep it open and prevent premature closure until released by a messenger when the sampler is at the selected water depth.
- 4.18.2 In case the water depth is less than 500mm, a water bucket can be used as a water sampler to minimize the possibility of the latching system disturbing sediment during water sampling.
- 4.19 Water Depth Detector
- 4.19.1 A portable, battery-operated echo sounder shall be used for the determination of water depth at each designated monitoring station.
- 4.20 Suspended Solids
- 4.20.1 A water sample of at least 2.5L in capacity shall be collected. Samples should be submitted to HOKLAS accredited laboratory as soon as possible for gravimetric analysis for suspended solids determination.
- 4.21 Positioning Device
- 4.21.1 The locations of water monitoring points should be located using a hand-held or boat fixed digital Global Positioning System (GPS) or other equivalent instrument of similar accuracy. This is to ensure that the water sampling locations are correct during the water quality monitoring work.
- 4.22 Laboratory Analysis
- 4.22.1 All laboratory work shall be carried out in a HOKLAS accredited laboratory. Water samples of about 1,000 ml shall be collected at the monitoring and control stations for carrying out the laboratory determinations. The determination work shall start within 24 hours after collection of the water samples. The analyses shall follow the standard methods according to APHA Standard Methods for the Examination of Water and Wastewater, 20th Edition, or an equivalent method approved by EPD.

Table 4.1 Methods and Detection Limits for Laboratory Analysis

Parameter	Recommended Method	Detection Limit
Suspended Solids	APHA 2540D	2 mg/L

- 4.22.2 For each of the testing methods, details shall be submitted to the Director of Environmental Protection (DEP) or his representatives for approval prior to the commencement of the monitoring programme. The submitted information should include pre-treatment procedures, instrument use, Quality Assurance/Quality Control (QA/QC) details (such as blank, spike recovery, number of duplicate samples per-batch etc), detection limits and accuracy. The QA/QC details shall be in accordance with requirements of HOKLAS or another internationally accredited scheme. The QA/QC results shall be reported. EPD may request the laboratory to carry out analysis of known standards provided by EPD for inter-laboratory calibration. Remaining samples after analysis shall be kept by the laboratory for 3 months in case repeat analysis is required. If in-house or non-standard methods are proposed, details of method verification should, if required, be submitted to the EPD. In any case, sample testing shall have comprehensive quality assurance and quality control programmes. The laboratory shall be prepared to demonstrate the quality control programmes to the EPD or their representative if and when required.

- 4.23 All *in-situ* monitoring instruments should be checked, calibrated and certified by a laboratory accredited under HOKLAS or any other international accreditation scheme before use, and subsequently re-calibrated at 3 monthly intervals throughout all stages of the water quality monitoring. Responses of sensors and electrodes should be checked with certified standard solutions before each use. Wet bulb calibration for a DO meter should be carried out before measurement at each monitoring.
- 4.24 The monitoring locations (**Figure 4.1**) are summarized in **Table 4.2** and **4.3**. Water quality monitoring station W1 will act as a control point for Contract 1 and W3 for Contract 2 to compare the water quality from potentially impacted sites with the ambient water quality. When alternative monitoring locations are proposed, they shall be chosen based on the following criteria:
- at locations close to and preferably at the boundary of the mixing zone of the major site activities as indicated in the EIA final report, which are likely to have water quality impacts;
 - close to the sensitive receptors which are directly or likely to be affected;
 - for monitoring locations located in the vicinity of the sensitive receptors, care shall be taken to cause minimal disturbance during monitoring;
 - one upstream control station is selected for Contract 1 (Station Number W1), and one upstream control station is selected for Contract 2 (Station Number W3) and they are at locations representative of the project site in its undisturbed condition. These control stations will act as control stations for their respective works area for the entire project period. Control stations shall be located, as far as if practicable, both upstream and down stream of the works area.

Table 4.2 Construction Phase Water Quality Monitoring Locations for Contract 1

Station Number	Location	Coordinates
W1	Between the Shuen Wan Marsh and ECA (<u>Control Station</u>)	E: 839301 N: 836386
W2	Between Tolo Harbour and Proposed Penstock	E: 839542 N: 836184

Table 4.3 Construction Phase Water Quality Monitoring Locations after commencement of Contract 2

Station Number	Location	Coordinates
W1	Between the Shuen Wan Marsh and ECA (Control Station for works under Contract 1)	E: 839301 N: 836386
W2	Between Tolo Harbour and Proposed Penstock	E: 839542 N: 836184
W3	Upstream of Tung Tze Shan Road (<u>Control Station</u> for works under Contract 2)	E: 838760 N: 836714
W4	Wai Ha Village 29D	E: 838865 N: 836621

- 4.25 Measurements shall be taken at 3 water depths, namely, 1m below water surface, mid-depth and 1m above river bed, except where the water depth less than 6m, the mid-depth station may be omitted. Should the water depth be less than 3m, only the mid-depth station will be monitored.
- 4.26 Baseline monitoring shall be performed and baseline conditions shall be established prior to commencement of works on the ECA. Measurements shall be taken at all designated monitoring locations, 3 days per week, for a period of 4 weeks prior to commencement of works of the channel link between the Wai Ha River and ECA for Contract 1 and the box culvert for Contract 2. The interval between 2 sets monitoring shall not be less than 36 hours.
- 4.27 During the construction phase, impact monitoring shall be undertaken on all designated monitoring locations 3 times per week.

Table 4.4 Water Quality Monitoring Frequency in Construction Phase

Monitoring Phase	Frequency
Baseline monitoring	Three times per week
Impact monitoring	Three times per week

4.28 The water quality criteria, namely Action and Limit levels, are shown in **Table 4.4**. Should the water quality parameters monitoring results at any designated monitoring station exceed the water quality criteria, actions in accordance with the Event and Action Plain in **Table 4.5** shall be carried out.

Table 4.5 Action and Limit Levels for Water Quality Monitoring

Parameters	Action	Limit
DO in mg L ⁻¹	5 percentile of baseline data	4 mg/L or 1%-ile of baseline data
pH	N/A	6.0 – 9.0
SS in mg L ⁻¹	95 percentile of baseline data or 120% of upstream control station's SS	99 percentile of baseline data or 130% of upstream control station's SS
Turbidity in NTU	95 percentile of baseline data or 120% of upstream control station's Turbidity	99 percentile of baseline data or 130% of upstream control station's Turbidity

Notes:

- For DO, non-compliance of water quality limits occurs when monitoring result is lower than the limits.
- For SS and Turbidity, non-compliance of water quality limits occurs when monitoring result is higher than the limits.

Table 4.6 Event and Action Plan for Water Quality

Event	ET Leader	IEC	ER	Contractor
ACTION LEVEL				
Action level being exceeded by one sampling day	<ol style="list-style-type: none"> 1. Repeat in-situ measurements to confirm findings; 2. Identify reasons for non-compliance and source(s) of impact; 3. Inform IEC, Contractor and Engineer; 4. Check monitoring data, all plant, equipment and Contractor's working methods; 5. Discuss mitigation measures with IEC, Engineer and Contractor; 6. Ensure mitigation measures are implemented. 7. Repeat measurement on next day of exceedance. 	<ol style="list-style-type: none"> 1. Discuss mitigation measures with ET, Engineer and Contractor; 2. Review proposals on mitigation measures submitted by Contractor and advise the Engineer accordingly; 3. Assess effectiveness of implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Discuss proposed mitigation measures with IEC, ET and Contractor; 2. Make agreement on mitigation measures to be implemented; 3. Assess effectiveness of implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Inform Engineer and confirm in writing notification of the non-compliance; 2. Rectify unacceptable practice; 3. Check all plant and equipment; 4. Consider changes in working methods; 5. Discuss with ET, IEC and Engineer and propose mitigation measures to IEC and Engineer within three working days; 6. Implement agreed mitigation measures.
Action level being exceeded by more than two consecutive sampling days	<ol style="list-style-type: none"> 1. Repeat in-situ measurements to confirm findings; 2. Identify reasons for non-compliance and source(s) of impact; 3. Inform IEC, Contractor and Engineer; 4. Check monitoring data, all plant, equipment and Contractor's working methods; 5. Discuss mitigation measures with IEC, Engineer and Contractor; 	<ol style="list-style-type: none"> 1. Discuss mitigation measures with ET, Engineer and Contractor; 2. Review proposals on mitigation measures submitted by Contractor and advise the Engineer accordingly; 3. Assess effectiveness of implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Discuss proposed mitigation measures with IEC, ET and Contractor; 2. Make agreement on mitigation measures to be implemented; 3. Assess effectiveness of implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Inform Engineer and confirm in writing notification of the non-compliance; 2. Rectify unacceptable practice; 3. Check all plant and equipment; 4. Consider changes in working methods; 5. Discuss with ET, IEC and Engineer and propose

	<ol style="list-style-type: none"> 6. Ensure mitigation measures are implemented. 7. Prepare to increase the monitoring frequency to daily; 8. Repeat measurement on next day of exceedance. 			<p>mitigation measures to IEC and Engineer within three working days;</p> <p>6. Implement agreed mitigation measures.</p>
LIMIT LEVEL				
Limit level being exceeded by one sampling day	<ol style="list-style-type: none"> 1. Repeat in-situ measurements to confirm findings; 2. Identify reasons for non-compliance and source(s) of impact; 3. Inform EPD, IEC, Contractor and Engineer; 4. Check monitoring data, all plant, equipment and Contractor's working methods; 5. Discuss mitigation measures with IEC, Engineer and Contractor; 6. Ensure mitigation measures are implemented; 7. Increase the monitoring frequency to daily until no exceedance of Limit level. 	<ol style="list-style-type: none"> 1. Discuss mitigation measures with ET, Engineer and Contractor; 2. Review proposals on mitigation measures submitted by Contractor and advise the Engineer accordingly; 3. Assess effectiveness of implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Discuss proposed mitigation measures with IEC, ET and Contractor; 2. Request Contractor to critically review the working methods; 3. Make agreement on mitigation measures to be implemented; 4. Assess effectiveness of implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Inform Engineer and confirm in writing notification of the non-compliance; 2. Rectify unacceptable practice; 3. Check all plant and equipment; 4. Consider changes in working methods; 5. Discuss with ET, IEC and Engineer and propose mitigation measures to IEC and Engineer within three working days; 6. Implement agreed mitigation measures.
Limit level being exceeded by more than two consecutive sampling days	<ol style="list-style-type: none"> 1. Repeat in-situ measurements to confirm findings; 2. Identify reasons for non-compliance and source(s) of impact; 3. Inform EPD, IEC, Contractor and Engineer; 4. Check monitoring data, all plant, 	<ol style="list-style-type: none"> 1. Discuss mitigation measures with ET, Engineer and Contractor; 2. Review proposals on mitigation measures submitted by Contractor and advise the Engineer 	<ol style="list-style-type: none"> 1. Discuss proposed mitigation measures with IEC, ET and Contractor; 2. Request Contractor to critically review the working methods; 	<ol style="list-style-type: none"> 1. Inform Engineer and confirm in writing notification of the non-compliance; 2. Rectify unacceptable practice; 3. Check all plant and equipment; 4. Consider

	<p>equipment and Contractor's working methods;</p> <p>5. Discuss mitigation measures with IEC, Engineer and Contractor;</p> <p>6. Ensure mitigation measures are implemented.</p> <p>7. Increase the monitoring frequency to daily until no exceedance of Limit level for two consecutive days.</p>	<p>accordingly;</p> <p>3. Assess effectiveness of implemented mitigation measures.</p>	<p>3. Make agreement on mitigation measures to be implemented;</p> <p>4. Assess effectiveness of implemented mitigation measures;</p> <p>5. Consider and if necessary instruct Contractor to slow down or to stop all or part of the construction activities until no exceedance of Limit Level.</p>	<p>changes in working methods;</p> <p>5. Discuss with ET, IEC and Engineer and propose mitigation measures to IEC and Engineer within three working days;</p> <p>6. Implement agreed mitigation measures;</p> <p>7. As directed by the Engineer, slow down or stop all or part of the construction activities until no exceedance of Limit level.</p>
--	---	--	--	---

Monitoring of Hydrological Characteristics of Shuen Wan Marsh

- 4.29 A specific monitoring programme of Wai Ha River through the Shuen Wan Marsh is recommended. The hydrological monitoring is to ensure the works along Wai Ha River will not affect the water flow into the Shuen Wan Marsh. A sample template for the Hydrological Characteristics Monitoring Data Record Sheet is presented in Appendix F.
- 4.30 Monitoring locations should be situated on the upper and lower stream of Shuen Wan Marsh. **Figure 4.2** and **Table 4.7 & 4.8** summarized the locations of monitoring stations. H3 and H4 are proposed to monitor if there is any change in the hydrological characteristics of Wai Ha River that may subsequently affect the Shuen Wan Marsh caused by the works involved in Contract 2.

Table 4.7 Construction and Operation Phase Hydrological Characteristics Monitoring Locations for Contract 1

Station Number	Location	Coordinates
H1	Between the Shuen Wan Marsh and ECA	E: 839306 N: 836379
H2	Route to Sam Kung Temple	E: 839163 N: 836433

Table 4.8 Construction and Operation Phase Hydrological Characteristics Monitoring Locations after commencement of Contract 2

Station Number	Location	Coordinates
H1	Between the Shuen Wan Marsh and ECA	E: 839306 N: 836379
H2	Route to Sam Kung Temple	E: 839163 N: 836433

H3	Upstream of Tung Tze Shan Road	E: 838760 N: 836714
H4	Wai Ha Village 29D	E: 838865 N: 836621

- 4.31 Baseline data should be collected on a consecutive of 4 weeks, at mid-flood and mid-ebb tides, for once a week before commencement of any major site activities involving the Wai Ha River, namely the construction of channel link between the Wai Ha River and ECA for Contract 1 and the box culvert for Contract 2.
- 4.32 Construction and operation phase monitoring shall be conducted on a weekly basis, at mid-flood and mid-ebb tides. The hydrological monitoring will be carried out for 1 year after the construction is complete as operation phase monitoring. After this monitoring period, DSD will review the need for extending the operation phase monitoring. The review results will be submitted to the EPD and AFCD for agreement.
- 4.33 The monitoring parameters shall include:
- Water flow rate
 - Water depth
- 4.34 The action/limit level for the hydrological monitoring shall be determined after the baseline data is collected.

Monitoring Equipment

- 4.35 Water Depth Detector
- 4.35.1 A portable, battery-operated echo sounder shall be used for the determination of water depth at each designated monitoring station.
- 4.36 Flow Rate Meter
- 4.36.1 A portable, battery-operated flow meter should be used for the determination of water depth at each designated monitoring location and record in m³/s.
- 4.37 The water quality criteria, namely Action and Limit levels shall be determined once the baseline monitoring is complete. Should the water quality parameters monitoring results at any designated monitoring station exceed the water quality criteria, actions in accordance with the Event and Action Plain in **Table 4.9** shall be carried out.

Table 4.9 Event and Action Plan for Monitoring of Hydrological Characteristics

Event	ET Leader	IEC	ER	Contractor
ACTION LEVEL				
Action level being exceeded by one sampling day	1. Repeat in-situ measurements to confirm findings; 2. Identify reasons for non-compliance and source(s) of impact; 3. Inform IEC, Contractor	1. Discuss mitigation measures with ET, Engineer and Contractor; 2. Review proposals on mitigation measures submitted by Contractor and	1. Discuss proposed mitigation measures with IEC, ET and Contractor; 2. Make agreement on mitigation	1. Inform Engineer and confirm in writing notification of the non-compliance; 2. Rectify unacceptable practice;

	<p>and Engineer;</p> <ol style="list-style-type: none"> 4. Check monitoring data, Contractor's working methods and any excavation works or dewatering processes; 5. Discuss mitigation measures with IEC, Engineer and Contractor; 6. Ensure mitigation measures are implemented. 7. Repeat measurement on next day of exceedance. 	<p>advise the Engineer accordingly;</p> <ol style="list-style-type: none"> 3. Assess effectiveness of implemented mitigation measures. 	<p>measures to be implemented;</p> <ol style="list-style-type: none"> 3. Assess effectiveness of implemented mitigation measures. 	<ol style="list-style-type: none"> 3. Check working methods and any excavation works or dewatering processes; 4. Consider changes in working methods and plans; 5. Discuss with ET, IEC and Engineer and propose mitigation measures to IEC and Engineer within three working days; 6. Implement agreed mitigation measures.
<p>Action level being exceeded by more than two consecutive sampling days</p>	<ol style="list-style-type: none"> 1. Repeat in-situ measurements to confirm findings; 2. Identify reasons for non-compliance and source(s) of impact; 3. Inform IEC, Contractor and Engineer; 4. Check monitoring data, Contractor's working methods and any excavation works or dewatering processes; 5. Discuss mitigation measures with IEC, Engineer and Contractor; 6. Ensure mitigation measures are implemented. 7. Prepare to increase the monitoring frequency to daily; 8. Repeat measurement on next day of exceedance. 	<ol style="list-style-type: none"> 1. Discuss mitigation measures with ET, Engineer and Contractor; 2. Review proposals on mitigation measures submitted by Contractor and advise the Engineer accordingly; 3. Assess effectiveness of implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Discuss proposed mitigation measures with IEC, ET and Contractor; 2. Make agreement on mitigation measures to be implemented; 3. Assess effectiveness of implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Inform Engineer and confirm in writing notification of the non-compliance; 2. Rectify unacceptable practice; 3. Check working methods and any excavation works or dewatering processes; 4. Consider changes in working methods and plans; 5. Discuss with ET, IEC and Engineer and propose mitigation measures to IEC and Engineer within three working days; 6. Implement agreed mitigation measures.
LIMIT LEVEL				

<p>Limit level being exceeded by one sampling day</p>	<ol style="list-style-type: none"> 1. Repeat in-situ measurements to confirm findings; 2. Identify reasons for non-compliance and source(s) of impact; 3. Inform AFCD, IEC, Contractor and Engineer; 4. Check monitoring data, and Contractor's working methods and any excavation works or dewatering processes; 5. Discuss mitigation measures with IEC, Engineer and Contractor; 6. Ensure mitigation measures are implemented; 7. Increase the monitoring frequency to daily until no exceedance of Limit level. 	<ol style="list-style-type: none"> 1. Discuss mitigation measures with ET, Engineer and Contractor; 2. Review proposals on mitigation measures submitted by Contractor and advise the Engineer accordingly; 3. Assess effectiveness of implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Discuss proposed mitigation measures with IEC, ET and Contractor; 2. Request Contractor to critically review the working methods; 3. Make agreement on mitigation measures to be implemented; 4. Assess effectiveness of implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Inform Engineer and confirm in writing notification of the non-compliance; 2. Rectify unacceptable practice; 3. Check working methods and any excavation works or dewatering processes; 4. Consider changes in working methods and plans; 5. Discuss with ET, IEC and Engineer and propose mitigation measures to IEC and Engineer within three working days; 6. Implement agreed mitigation measures.
<p>Limit level being exceeded by more than two consecutive sampling days</p>	<ol style="list-style-type: none"> 1. Repeat in-situ measurements to confirm findings; 2. Identify reasons for non-compliance and source(s) of impact; 3. Inform AFCD, IEC, Contractor and Engineer; 4. Check monitoring data, and Contractor's working methods and any excavation works or dewatering processes; 5. Discuss mitigation measures with IEC, Engineer and Contractor; 6. Ensure mitigation measures are 	<ol style="list-style-type: none"> 1. Discuss mitigation measures with ET, Engineer and Contractor; 2. Review proposals on mitigation measures submitted by Contractor and advise the Engineer accordingly; 3. Assess effectiveness of implemented mitigation measures. 	<ol style="list-style-type: none"> 1. Discuss proposed mitigation measures with IEC, ET and Contractor; 2. Request Contractor to critically review the working methods; 3. Make agreement on mitigation measures to be implemented; 4. Assess effectiveness of implemented mitigation measures; 5. Consider and if 	<ol style="list-style-type: none"> 1. Inform Engineer and confirm in writing notification of the non-compliance; 2. Rectify unacceptable practice; 3. Check working methods and any excavation works or dewatering processes; 4. Consider changes in working methods and plans; 5. Discuss with ET, IEC and Engineer and propose mitigation measures to IEC

	<p>implemented.</p> <p>7. Increase the monitoring frequency to daily until no exceedance of Limit level for two consecutive days.</p>		<p>necessary instruct Contractor to slow down or to stop all or part of the construction activities until no exceedance of Limit Level.</p>	<p>and Engineer within three working days;</p> <p>6. Implement agreed mitigation measures;</p> <p>7. As directed by the Engineer, slow down or stop all or part of the construction activities until no exceedance of Limit level.</p>
--	---	--	---	--

5. WASTE MANAGEMENT IMPLICATIONS

Introduction

- 5.1 Waste management should be the contractor's responsibility to confirm that all wastes produced during the construction phase for the drainage improvement works are handled, stored and disposed of in accordance with good waste management practices and EPD's regulations and requirements. The recommended mitigation measures should form the basis of the Waste Management Plan to be developed by the Contractor.
- 5.2 Waste materials generated during construction activities, such as construction and demolition (C&D) material, chemical wastes and general refuse, are recommended to be audited at regular intervals (at least quarterly) to check that proper storage, transportation and disposal practices are being implemented. The Contractor should be responsible for the implementation of any mitigation measures to minimise waste or redress problems arising from the waste materials.

Waste Control and Mitigation Measures

- 5.3 Mitigation measures for waste management are summarised below. With the appropriate handling, storage and removal of waste arisings during the construction works as defined below, the potential to cause adverse environmental impacts would be minimised. The implementation schedule of the recommended mitigation measures is presented in **Appendix A**. During the site inspections, the ET should pay special attention to the issues relating to waste management and check whether the Contractor has implemented the recommended good site practices and other mitigation measures.

Good Site Practices

- 5.4 Appropriate waste handling, transportation and disposal methods for all waste generated during the construction works should be implemented such that construction wastes do not enter the river channels and coastal waters of Inner Tolo Harbour, and to minimize potential impacts where works areas are located close to ecological sensitive receivers.
- 5.5 It is not anticipated that adverse waste management related impacts would arise, provided that good site practices are strictly followed. Recommendations for good site practices during the construction activities include:
- Nomination of approved personnel, such as a site manager, to be responsible for good site practices and making arrangements for collection of all wastes generated at the site and effective disposal to an appropriate facility.
 - Training of site personnel in proper waste management and chemical waste handling procedures.
 - Provision of sufficient waste disposal points and regular collection for disposal.
 - Appropriate measures to minimise windblown litter and dust during transportation of waste by either covering trucks or by transporting wastes in enclosed containers.
 - Separation of chemical wastes for special handling and appropriate treatment at the Chemical Waste Treatment Facility.
 - Regular cleaning and maintenance programme for drainage systems, sumps and oil interceptors.
 - A recording system for the amount of waste generated, recycled and disposal (including the disposal sites) should be proposed.
 - A Waste Management Plan should be prepared and submitted to the Engineer for approval. One may make reference to ETWB TCW No. 19/2005 for details.

- 5.6 In order to monitor the disposal of C&D material at landfills and public filling areas, as appropriate, and to control fly tipping, a trip-ticket system should be included as one of the contractual requirements. One may make reference to ETWB TCW No. 31/2004 for details. The use of a trip-ticket system should be required to avoid any illegal or unplanned dumping of waste generated by the Project, particularly at works areas close to ecologically sensitive receivers.

Waste Reduction Measures

- 5.7 Good management and control can prevent the generation of significant amounts of waste. Waste reduction is best achieved at the planning and design stage, as well as by ensuring the implementation of good site practices. Recommendations to achieve waste reduction include:
- Segregation and storage of different types of waste in different containers, skips or stockpiles to enhance reuse or recycling of materials and their proper disposal.
 - To encourage collection of aluminium cans by individual collectors, separate labelled bins should be provided to segregate this waste from other general refuse generated by the work force.
 - Any unused chemicals or those with remaining functional capacity should be recycled.
 - Maximising the use of reusable steel formwork to reduce the amount of C&D material.
 - Prior to disposal of C&D waste, it is recommended that wood, steel and other metals should be separated for re-use and / or recycling to minimise the quantity of waste to be disposed of to landfill.
 - Proper storage and site practices to minimise the potential for damage or contamination of construction materials.
 - Plan and stock construction materials carefully to minimise amount of waste generated and avoid unnecessary generation of waste.
- 5.8 In addition to the above good site practices and waste reduction measures, specific mitigation measures are recommended below for the identified waste arisings to minimise environmental impacts during handling, transportation and disposal of these wastes.

Construction and Demolition Material

- 5.9 To minimize the environmental impacts during the collection and transportation of C&D material, the following mitigation measures are recommended:
- The excavated material with suitable characteristics/size should be reused on-site as fill material as far as practicable, such as for backfilling of the box culvert and drainage pipe works, to minimise off-site disposal of C&D material.
 - Suitable areas should be designated within the works site boundaries for temporary stockpiling of C&D material.
 - Within stockpile areas, the following measures should be taken to control potential environmental impacts or nuisance:
 - covering material during heavy rainfall;
 - locating stockpiles to minimise potential visual impacts; and
 - minimizing land intake of stockpile areas as far as possible
 - When disposing C&D material at a public filling area, the material should only consist of soil,

rock, concrete, brick, cement plaster/mortar, inert building debris, aggregates and asphalt. The material should be free from marine mud, household refuse, plastic, metals, industrial and chemical waste, animal and vegetable matter, and other material considered to be unsuitable by the Filling Supervisor.

Chemical Wastes

- 5.10 If chemical wastes are produced at the construction site, the following mitigation measures should be implemented to minimize the environmental impacts associated with the handling, transportation and disposal of chemical waste:
- Contractor should be required to register with the EPD as a Chemical Waste Producer and to follow the guidelines stated in the Code of Practice on the Packaging, Labelling and Storage of Chemical Wastes.
 - Good quality containers compatible with the chemical wastes should be used, and incompatible chemicals should be stored separately.
 - Appropriate labels should be securely attached on each chemical waste container indicating the corresponding chemical characteristics of the chemical waste, such as explosives, flammable, oxidizing, irritant, toxic, harmful, corrosive, etc.
 - The Contractor should use a licensed collector to transport and dispose of the chemical wastes generated at the Chemical Waste Treatment Centre at Tsing Yi, or other licensed facility, in accordance with the Waste Disposal (Chemical Waste) (General) Regulation.

General Refuse

- 5.11 The recommended mitigation measures for the handling of general refuse are as below:
- General refuse should be stored in enclosed bins or compaction units separate from C&D material.
 - A reputable waste collector should be employed by the contractor to remove general refuse from the site, separately from C&D material.
 - An enclosed and covered area is preferred to reduce the occurrence of 'wind blown' light material.

6. ECOLOGICAL IMPACT

Introduction

- 6.1 The ecological impact assessment in the EIA Report identified that ecological impacts resulting from the proposed drainage improvement works are anticipated to be very minor in scale. Nevertheless, measures were identified in the EIA Report that would minimise any potential ecological impact. Ecological mitigation measures are detailed in the following sections.

Ecological Mitigation Measures

- 6.2 Following *EIAOTM Annex 16* guidelines, mitigation measures are proposed in this section to avoid, minimise and compensate for identified ecological impacts.

Avoidance/ Minimisation

- 6.3 Wherever possible, proposed drainage improvement works have been designed to avoid or minimise direct impacts to areas of recognised conservation importance in the Assessment Area including Conservation Area (CA), Coastal Protection Area (CPA), and Site of Special Scientific Interest (SSSI).
- 6.4 The following measures should be implemented to minimise identified ecological impacts during the construction and operation phase.

Construction Phase

- 6.5 The proposed twin cell box-culvert constructed partially underneath Tung Tsz Road has been designed to reduce the footprint of the proposed works from 0.35ha to 0.3ha, thereby minimising direct impacts to marsh habitat and the CA.
- 6.6 During the construction of the proposed twin cell box-culvert, the following measures are recommended to be implemented:
- Sheet-pilings, which will be installed around the trench of excavation, should be extended above ground level for ~2m to act as hoarding to isolate the works site.
 - The trenching works for the construction of the proposed box culvert should be carried out in phases, with a trench length of not more than 120m in each phase. The trench should be backfilled and compacted with suitable materials upon completion of each phase of the construction works.
 - The construction of intercept point of twin cell box culvert at the upstream of Wai Ha River should be confined to only one side of the river bank.
 - Construction works of box culvert should be conducted in the existing artificially modified channel as far as practicable which lined with masonry wall in order to minimised impact to natural stream section.
 - To restore and enhance the ecological value of the stream, any affected river bank should be reinstated to its original condition or lined with rock-filled gabion.
 - Planting pits will be provided in any gabion bank to allow the re-establishment of riparian vegetation.
 - The existing natural riverbed and substrates should be retained and the natural pool-riffle sequence should be re-created in the new channel bed.

6.7 Concerning the excavation works, the following measures should be implemented:

- All works conducted within or close to water bodies should be carried out from October to April, with construction making use of land-based plant.
- Works within river/stream channels should be restricted to an enclosed dry section of the river, with containment measures such as bunds and barriers used within the river to minimize the impacts upon the downstream water body.
- Site runoff should be directed towards regularly cleaned and maintained silt traps and oil/grease separators to minimise the risk of sedimentation and pollution of river water. The silt and oil/grease separators should be appropriately designed for the local drainage and ground conditions.
- To minimize leakage and loss of sediments during excavation in narrow channels, tightly sealed closed grab excavators should be deployed where material to be handled is wet.
- For the construction of the box culvert along the north side of Shuen Wan Marsh Conservation Area, sand bags should be deployed along the limit of the works area to prevent muddy water ingress into the CA. Sand bags should be placed to a height of at least 300mm from ground level and +2.5 mPD (whichever is greater) to provide adequate allowance for the built-up water level during rainstorm events. Surface within the works area runoff should then be collected and directed into the existing drainage system

6.8 During the construction of the ecological compensatory area (ECA), the following monitoring should be implemented:

- Monthly check of planted, retained and transplanted trees and shrubs, and other planted vegetation (including wetland vegetation, shrubs and trees once planting of these has commenced).
- Monthly monitoring *in situ* of water quality of the ECA once connection to the river has been made.
- Weekly inspection of the construction and planting of the ECA.

6.9 Since the identified ecological impacts resulting from the proposed drainage improvement work are very minor in scale, ecological monitoring is conducted to ensure that the proposed construction would produce no adverse ecological impacts on the floral and faunal characteristics on-site and in the adjacent habitats. During the pre-construction and construction phases of the stormwater pumping station and twin-cell box-culvert under Contract 1, the following monitoring should be implemented:

- During the pre-construction phase, ecological baseline monitoring updating the habitat map, floristic and faunal characteristics (including bird, mammal, herpetofauna, butterfly, dragonfly) within the works boundary and areas within 100m of the works boundary under Contract 1. Since the proposed construction area under Contract 1 is adjacent to the downstream of Wai Ha River, aquatic stream survey (including fish and macroinvertebrates) in this downstream portion will be conducted.
- Bi-monthly monitoring of the faunal groups (same faunal groups as for the pre-construction phase monitoring) during the construction.
- Bi-monthly check of retained and transplanted trees and shrubs within the work boundary and riparian vegetation adjacent to construction site and wetland vegetation (mainly mangrove and mangrove-associated vegetation) during the construction.

No ecological monitoring on the marine habitat is required as no ecological impacts on marine ecosystem resulting from the proposed construction of stormwater pumping station under Contract 1 was identified by the approved EIA report.

6.10 During the pre-construction and construction phases of the twin-cell box-culvert under Contract 2, the following monitoring should be implemented:

- During the pre-construction phase, ecological baseline monitoring updating the habitat map, floristic and faunal characteristics (including bird, mammal, herpetofauna, butterfly, dragonfly, and fish and macroinvertebrates in Wai Ha River) within the works boundary and areas within 100m of the works boundary under Contract 2.
- Bi-monthly monitoring of the faunal groups (same faunal groups as for the pre-construction phase monitoring) during the construction.
- Bi-monthly check of retained and transplanted trees and shrubs within the work boundary, riparian vegetation adjacent to construction site and wetland vegetation (mainly mangrove and mangrove-associated vegetation) during the construction.

6.11 It has been identified in the EIA report that a plant species of conservation interest (Hong Kong Pavetta, *Pavetta hongkongensis*) would be potentially affected by the construction of the proposed box-culvert. In view of this, specific mitigation measures have been recommended for this species:

- The affected individuals are to be transplanted to a suitable wooded habitat in the ECA prior to the construction phase of the second contract of the Project.
- A detailed vegetation survey of the affected species of conservation interest should be conducted by a suitably qualified botanist/ecologist to identify the number and location of the affected individuals. A detailed transplantation methodology should be formulated before the commencement of transplantation.
- Transplantation should be supervised by a suitably qualified botanist/horticulturalist/arborist.
- Monitoring of the transplanted saplings will cover a period of 12 months after the transplant. The monitoring will be conducted once a week in the first 3 months and once in each following month in the remaining monitoring period. Health condition and growth of each transplanted sapling will be assessed and reported.

6.12 To minimise disturbance to habitats adjacent to the works areas, noise mitigation measures as listed below should be implemented:

- Quieter construction plant should be used during the construction phase.
- Temporary noise barriers should be used during the construction of the box-culvert along Tung Tsz Road, the floodwater pumping station, the mechanical gate, and drainage pipe to minimise potential construction phase disturbance to ardeids that may breed in Shuen Wan Egretty SSSI, and avifauna foraging in marsh habitat.
- Noise generating construction works within 100m of any nests in the Shuen Wan Egretty SSSI should be avoided as far as practicable during the breeding season (March to June) of the ardeids. Works near the SSSI (i.e. installation of mechanical gate) could be restricted to be executed outside the breeding season by provision of special conditions in the contract document.
- To further minimise construction noise impact to the marshland and prevent tipping, storage of

construction material and encroachment of personnel into the marshland area, hoardings with minimum height of 2m should be set up along the south side of the proposed box culvert works area adjacent to the marsh, extending at least 20m at both ends, throughout the construction period.

- 6.13 Standard good site practice measures should be implemented throughout the construction phase. The measures should include:
- Placement of equipment or stockpile in designated works areas and access routes selected on existing disturbed land to minimise disturbance to natural or moderate-high ecological value habitats.
 - Construction activities should be restricted to work areas that should be clearly demarcated. The work areas should be reinstated after completion of the works.
 - Waste skips should be provided to collect general refuse and construction wastes. The wastes should be disposed of timely and properly off-site.
 - General drainage arrangements should include sediment and oil traps to collect and control construction site run-off.
 - Open burning on works sites is illegal, and should be strictly prohibited.

Operation Phase

- 6.14 Potential operational phase activities in newly box-culvert would be limited to regular maintenance such as de-silting. Impacts to aquatic communities in the nearby water channel resulting from these activities are expected to be minor. Nevertheless, the following measures are recommended to minimise potential impacts resulting from operational phase activities:
- To minimise sedimentation, de-silting should be limited to the dry season.
 - Waste material produced during de-silting should be disposed of in a timely and appropriate manner.

Compensation

- 6.15 Compensatory planting as listed below would be required due to the unavoidable loss of trees and vegetations.
- Planting of trees should be provided within the ECA to compensate for the unavoidable loss of approximately 0.08ha of secondary woodland habitat that would be affected by the drainage improvement works.
 - Planting of trees and other vegetation within project area along the banks of Wai Ha River and Tung Tsz Road should also provide compensation for unavoidable tree-felling and loss of riparian vegetation resulting from the proposed works.
 - Planting of trees and shrubs of appropriate separation and density should be provided in area falling within the Shuen Wan Conservation Area to compensate for the loss of tree and other wetland vegetation (such as mangrove and mangrove-associated vegetation).
 - The compensatory planting should make use of native plant species with flowers/fruits attractive to wildlife.
- 6.16 As there will be loss of a small area of marsh habitat (about 0.30ha) within the CA resulting from the construction of the box-culvert along Tung Tsz Road, a total of about 1.12 ha of area is proposed as ECA to compensate the loss of marsh and secondary habitats. Wetland habitats, including open water, intertidal mudflat, mangrove and brackish marsh, of approximately 0.75 ha will be proposed,

while about 0.37 ha of land will be planted with trees and shrubs or as a receptor site for any transplanted trees under the Project. The compensation should includes the following:

- The ECA will make use of an existing low ecological value recreational fishpond on government land adjacent to the marsh.
- The above-mentioned pond should be enhanced by removing boardwalks around the existing pond, and restoring vegetation along the pond bunds. It should also be re-profiled to provide areas of shallow water (approximately 15-50cm deep), creating a suitable foraging habitat for wildlife.
- Screen planting of shrubs and trees along the south-eastern bund of the pond should be implemented to minimise disturbance to avifauna and other wildlife from the adjacent recreational fishpond.

Ecological Monitoring and Audit Requirements

6.17 The proper implementation of mitigation measures during construction and operation phase recommended in Section 6.3 to 6.15 should be monitored and audited. Ecological monitoring (including flora establishment and fauna utilization) of the ECA will be carried out by qualified ecologists employed by the Contractor during the 1-year wetland establishment period of the ECA. During the post establishment period, ecological monitoring and maintenance of the ECA will be undertaken by Agriculture, Fisheries and Conservation Department (AFCD) for the first 5 years upon completion of the wetland habitat. Monitoring during the post-establishment phase will only involve measures to monitor the vegetation health, fauna utilization of the ECA and maintain the engineering stability of the bunds and created wetland of the ECA. The need for extension of the maintenance of the ECA would be subject to further review.

6.18 A specific monitoring programme of the compensatory habitats of the ECA is required. The programme should provide data on the establishment of marsh communities, and allow an assessment of the relative success of mitigation measures to be made. The ecological monitoring will be conducted by qualified ecologists employed by the Contractor in accordance with the approved ecological monitoring programme and requirements detailed in the Habitat Compensatory Plan (HCP) pursuant to Condition 2.5 of the Environmental Permit No. EP-303/2008 and approved by EPD on 24 September 2010. Ecological monitoring of the ECA during its construction and establishment phases is recommended in Table 6.1. Table 6.2 describes the action and limit levels and the action plan for the ecological monitoring of the ECA during establishment phase. Methodology is also applicable as a management plan after the establishment phase monitoring. Ecological monitoring results of the ECA should be submitted to the Environmental Team Leader for inclusion in the Monthly EM&A Reports and verified by IEC before submission to EPD.

Table 6.1 Construction and Establishment Phase Ecological Monitoring by the Contractor’s ecologist for the ECA

	Construction Phase Ecological Monitoring	Establishment Phase Ecological Monitoring
Habitat types	Not required.	At six monthly intervals at the end of the wet season (i.e. September 2011) and the end of the dry season (i.e. March 2012) when tide height is <1.5 mPD.

	Construction Phase Ecological Monitoring	Establishment Phase Ecological Monitoring
Vegetation cover	Not required.	At six monthly intervals at the end of the wet season (i.e. September 2011) and the end of the dry season (i.e. March 2012) when tide height is <1.5 mPD.
Vegetation health	Monthly check of planted, retained and transplanted trees and shrubs, and planting (once planting has commenced).	Monthly check of planted, retained and transplanted trees and shrubs.
Water Quality	Following filling with water monthly for <i>in situ</i> water quality.	Monthly for <i>in situ</i> water quality.
Intertidal fauna	Not required.	At six monthly intervals in wet season (August 2011) and dry season (February 2012).
Other fauna (include avifauna, herpetofauna, fish, odonate and butterfly)	Not required.	At six monthly intervals in wet season (August 2011) and dry season (February 2010).
Site Inspections	Weekly.	Twice per month.

Table 6.2 Proposed Contingency Plan for Monitoring and Maintaining the ECA

Parameters	Action Level	Limit Level	Action
Flooding/storm damage	N.A.	N.A.	Review damage in conjunction with short-term weather forecast. Review damage (e.g. vegetation condition) and determine severity and undertake repairs/modifications to the design.
Area of water in the open water pond at tide height of < 1.5 mPD	< 70%	< 60 %	Action level exceedance: double the monitoring frequency, identify and review the problem. If the problem persists, the action plan for limit level exceedance should be implemented. Limit level exceedance: re-profiling as required.
Emergent or floating vegetation in the open water pond at tide height of < 1.5 mPD(although it	> 10 %	> 20 %	Action level exceedance: double the monitoring frequency, identify and review the problem. If the problem persists, the action plan for limit level exceedance should be implemented. Limit level exceedance: manual or

Parameters	Action Level	Limit Level	Action
is not proposed to plant emergent or floating vegetation as part of the restoration process, it is to be expected that these will colonise the wetland over time)			mechanical vegetation clearance.
Woodland area with a mixture of planted trees and shrubs; wooded area with retained and/or (trans)planted trees	< 80%	< 70%	Action level exceedance: review tree status and growth. If the problem (such as dead trees, shrubs or >50% diseased leaves in tree canopy) persists, the action plan for limit level exceedance should be implemented. Limit level exceedance: undertake supplemental tree and/or shrub planting.
Emergent, mangrove propagules or unwanted vegetation in the intertidal mudflat (it is expected that such vegetation will colonize the wetland over time)	> 20%	> 30%	Action level exceedance: double the monitoring frequency, identify and review the problem. If the problem persists, the action plan for limit level exceedance should be implemented. Limit level exceedance: manual or mechanical vegetation clearance.
Brackish marsh vegetation cover	< 80%	< 70%	Action level exceedance: double the monitoring frequency, identify and review the problem. If the problem (such as dead plants or invasion of undesirable plant species) persists, the action plan for limit level exceedance should be implemented. Limit level exceedance: carry out weeding or planting.
Undesirable plant species (all wetland) including unwanted terrestrial	> 10% of vegetation in the ECA	> 20% of vegetation in ECA	Action level exceedance: removal by weeding. Limit level exceedance: removal by weeding, if problem persists or further deterioration occurs, review design

Parameters	Action Level	Limit Level	Action
species and exotics (including but not limited to exotic, invasive climbers <i>Mikania micrantha</i> , <i>Ipomoea aquatica</i> , <i>Ipomoea cairica</i> , <i>Eichhornia crassipes</i> and <i>Typha angustilia</i> .			and management regime.
Undesirable fauna including invasive/exotic aquatic invertebrates (including but not limited to Red Imported Fire Ant)	Presence	Negatively impacting wetland function	Action level exceedance: treatment or removal (or other method if suitable). Limit level exceedance: increase frequency of treatment or removal (or other method if suitable), review management protocols and design.

6.19 Ecological monitoring during post-establishment phase should be undertaken by AFCD to maintain the wetland health and engineering stability of the created wetland (**Table 6.3**). Monitoring results should be reported to Environmental Protection Department (EPD) on a quarterly basis.

Table 6.3 Maintenance and Management Schedule for the ECA during the Post-establishment Phase

Action	Frequency	Notes
Structural maintenance		
Inspect condition of bunds and repair / maintain as necessary	Annual inspection.	Also after any flood events/ typhoons. Repair/maintenance of bunds will only be carried out if necessary.
Vegetation management		
Supplemental planting	Requirement to be assessed annually.	Depending upon health status of the wetland vegetation, trees and shrubs during the bi-annual monitoring. Planting to be restricted to the wet season; monthly inspection on any newly planted vegetation should be conducted in the first three months to monitor their survival

Action	Frequency	Notes
		and establishment rates in early planting period.
Monitoring the health of trees and shrubs, vegetation cover, pruning and removal	Bi-annual monitoring of vegetation cover and health; Annual pruning of trees and shrubs if necessary in the whole ECA.	Annual pruning of trees and shrubs will be conducted only if necessary.
Removal of exotic / undesirable invasive plants (including algae, unwanted terrestrial species and exotics) (weeding)	Quarterly checking of unwanted vegetation in particular wetland habitats (i.e. open water, intertidal mudflat, brackish marsh and mangrove) with removal to be scheduled in subsequent 30 days.	Aggressive exotics such as floating herb <i>Eichhornia crassipes</i> and emergent herb <i>Typha angustifolia</i> to be removed immediately. Any significant number of established mangrove seedlings in intertidal mudflat and open water to be removed immediately.
Control of excessive colonization of brackish marsh in the adjacent intertidal mudflat	Quarterly checking of any excessive colonization of brackish marsh vegetation with removal to be scheduled for subsequent 30 days.	Removal of excessive colonization of brackish marsh will be conducted on a case-by-case basis.
Monitoring of intertidal fauna, avifauna, herpetofauna, fish, odonate and butterfly	Bi-annually.	
Pest control	Quarterly check for presence of pests.	Review and consider appropriate treatment on a case-by-case basis.

6.20 For other areas of ecological importance, baseline ecological survey should be conducted in pre-construction phases of Contracts 1 and 2 to update the floristic composition and faunal characteristics of the adjacent ecologically sensitive habitats (such as Wai Ha River and marsh in Shuen Wan Conservation Area) (**Figure 6.1**). The baseline survey should cover areas within the works boundaries (Contracts 1 and 2) and areas within 100m from the boundaries of Contracts 1 and 2. Bi-monthly and quarterly ecological monitoring should be carried out during the construction and operation phases (12 months) of the stormwater pumping station, twin-cell box-culvert and drainage pipe (**Table 6.4**). The construction and operation phases ecological monitoring should be conducted by qualified local ecologist(s) of the Independent Environmental Checker (IEC) for the Project with at least 7 years relevant ecology and EM&A experience. The IEC should submit reports on the findings of each monitoring trip, and a final report summarising the monitoring results over the entire monitoring period to AFCD and Environmental Protection Department (EPD).

Table 6.4 Pre-construction, Construction and Operation Phase Ecological Monitoring for areas under Contracts 1 and 2

	Pre-construction Phase Ecological	Construction Phase Ecological	Establishment Phase Ecological
--	-----------------------------------	-------------------------------	--------------------------------

	Monitoring	Monitoring	Monitoring
Habitat map	Once before the commencement of construction of Contracts 1 and 2	Not required.	Not required.
Vegetation	Once before the commencement of construction of Contracts 1 and 2	Bi-monthly check on the retained and transplanted trees and shrubs within and in proximity to the works boundary.	Quarterly check on the retained, transplanted and planted trees and shrubs within and in proximity to the works boundary.
Fauna (includes avifauna, herpetofauna, odonate and butterfly)	Once before the commencement of construction of Contracts 1 and 2	Bi-monthly monitoring on faunal groups in any ecologically sensitive area within 100m of the works boundary.	Quarterly monitoring on faunal groups in any ecologically sensitive area within 100m of the works boundary.
Stream (includes fish and macroinvertebrates)	Once before the commencement of construction of Contracts 1 and 2	Bi-monthly monitoring on stream fauna along Wai Ha River.	Quarterly monitoring on stream fauna along Wai Ha River.

- 6.21 Following transplantation, the health and condition of individuals of the plant species of conservation interest, *Pavetta hongkongensis*, affected by the proposed works should be monitored by a qualified botanist/ecologist. Monitoring should cover 12-month period following transplantation, and be conducted once a week in the first 3 months and at least once per month in the remaining of monitoring period. Health and growth condition of trees planted for compensating the tree loss of the Project (for both Contracts 1 and 2) should be monitored by a qualified botanist/ecologist during the 1-year establishment period. Monitoring results of these transplanted saplings of *Pavetta hongkongensis* and trees should be included in the EM&A reports of the Project for updating the conditions of these plants after transplantation.

7. LANDSCAPE AND VISUAL

Introduction

- 7.1 Landscape and Visual Impact Assessment in the EIA Report has identified the key issues and the possible impacts due to the proposed work. It has also recommended mitigation measures for minimizing the impacts and for improving overall landscape and visual quality. The Contractor of the Project should be responsible for the implementation of mitigation measures.

Monitoring Requirement

- 7.2 A Registered Landscape Architect (RLA) as a member of the ET, with local construction site experience should be responsible for conducting the baseline review and monitoring the design, implementation and maintenance of landscape and visual mitigation measures during construction and operational phases in accordance with the EIA Report.

Construction Phase

Baseline Review

- 7.3 A baseline review should be undertaken at the commencement of the construction contracts. The purpose of the review is:
- to check the status of the landscape resources within, and immediately adjacent to, the construction sites and works areas.
 - to determine whether any change has occurred to the status of the landscape resources since the EIA.
 - to determine whether amendments in the design of the landscape and visual mitigation measures are required for those changes.
 - to recommend any necessary amendments to the design of the landscape and visual mitigation measures.

Landscape and Visual Monitoring

- 7.4 The design, implementation and maintenance of landscape and visual mitigation measures should be checked bi-weekly to check that they are fully realised. Any potential conflicts between the proposed landscape measures and any other project works or operational requirements should also be recorded for the Contractor to resolve in early stage, without compromising the intention of the mitigation measures.

Operational Phase

Landscape and Visual Monitoring

- 7.5 All landscape and visual mitigation measures should be monitored quarterly during the first year of the Operational Phase to check on the effectiveness of the mitigations.

Mitigation Measures

Construction Phase

- 7.6 A number of landscape and visual mitigation measures during the construction phase have been proposed in the EIA report, and are summarized as below:

- Use of hoardings as visual screens for the construction in the works areas.
- Use of temporary barriers, covers and drainage provision around the construction works as contaminant / sediment control to prevent the contaminants and sediments from entering the sensitive water-based habitats.
- Implementation of pollution control measures to minimise any adverse environmental impacts to the surrounding habitats.
- Liaison with the nursery operator as necessary to minimise any adverse impact to the daily operation and plant holding capacity of the nursery.
- Maintenance and protection of the existing trees, especially their crowns, trunks and roots, within work sites.
- Provision of construction light should be controlled at night to avoid excessive glare to the surrounding villages and to Plover Cove.

Operation Phase

- 7.7 Landscape and visual mitigation measures during the operation phase as listed below should be implemented to minimize the potential impacts:
- Viewing area formation by planting with shrubs, grasses and benches along the area.
 - Architectural design of the pump house will help it fit into the existing suburban, natural to semi-natural surroundings.
 - Landscape design of pump house by providing sufficient planting around its boundary fence,
 - Enhancement planting along Tung Tsz Road with shrubs / trees of suitable species to help protect the stream and marshes.
 - Construction of box culvert should be with at least 1.0m soil depth for enhancement planting.
 - Transplanting of existing affected trees to adjacent locations should be carried out.
 - Preparation for transplanting is needed to allow sufficient time for root pruning and rootball preparation prior to transplanting.
 - Reinstatement of affected area should be carried out to check that the works areas are properly reinstated.
- 7.8 The implementation for the recommended landscape and visual impact mitigation measures is presented in **Appendix A**.

8. ENVIRONMENTAL AUDIT

Site Inspection

- 8.1 Site inspection provides a direct means to assess and check the project's environmental protection and pollution control measures are in compliance with relevant statutory requirements. Site inspection should be undertaken regularly and routinely by the ET to inspect construction activities in order to check that appropriate environmental protection and pollution control mitigation measures are implemented in accordance with EIA recommendations. With well defined pollution control and impact mitigation specifications and an established efficient and remedial action reporting system, site inspection is an effective tool to verify the acceptable environmental performance on the construction site.
- 8.2 The ET leader should be responsible for formulation of the environmental site inspection, deficiency and remedial action reporting system, and for carrying out site inspection works. He should in consultation with the IEC, prepare a procedure for the site inspection, deficiency and remedial action reporting requirements, and submit to the Contractor for agreement, and to the ER for approval, within 21 days of commencement of the construction contract.
- 8.3 Regular site inspections should be carried out at least once per week for all works areas. The inspections should cover the environmental situation, pollution control and mitigation measures within the works areas; they should also review the environmental situation outside the works areas which is likely to be affected, directly or indirectly, by the site activities. The ET leader should make reference to the following information in conducting the inspection:
- i. The EIA recommendations and requirements on environmental protection and pollution control mitigation measures.
 - ii. Works progress, programme, site/aerial photos and site plans.
 - iii. Individual works methodology proposals (which should include proposal on associated pollution control measures).
 - iv. Contract specifications on environmental protection and pollution prevent control.
 - v. Relevant environmental protection and pollution control laws, ProPECC Notes.
 - vi. Previous site inspection results.
- 8.4 The Contractor should update the ET leader with all relevant information of the construction contract necessary for him to carry out site inspections. Inspection results and associated recommendations for improvements in the Project's environmental performance should be submitted to the IEC and the Contractor within 24 hours for reference and for taking immediate remedial action. The Contractor should follow the procedures and time-frame as stipulated in the environmental site inspection, deficiency and remedial action reporting system (formulated by the ET leader), to report on any remedial measures subsequent to the site inspections.
- 8.5 The ET and/or IEC should also carry out ad hoc site inspections if major unacceptable or unforeseen environmental problems are identified. Inspections may also be required subsequent to receipt of an environmental complaint, or as part of the investigation work, as specified in the Action Plan for environmental monitoring and audit.

Compliance with Legal and Contractual Requirements

- 8.6 There are contractual environmental protection and pollution control requirements as well as environmental protection and pollution control laws in Hong Kong with which construction activities should comply.
- 8.7 The ET leader should also review the progress and programme of the works to check that relevant environmental laws have not been violated, and that any foreseeable potential for violating laws can be prevented.
- 8.8 The Contractor should regularly copy relevant documents to the ET leader so that the checking of

the Project's environmental performance can be carried out effectively. Documents to be submitted by the Contractor should include at least the updated Works Progress Reports, Works Programme, application for any necessary licence / permits under relevant environmental protection laws, and all the valid licence / permits received to date. The site diary should also be available for the ET leader's inspection upon his request.

- 8.9 After reviewing the documents, the ET leader should advise the Contractor and inform the IEC of any non-compliance with the project contractual and legislative requirements on environmental protection and pollution control. The Contractor should take follow-up and appropriate remedial actions. If the ET leader's review concludes that the current status of licence / permit application and any planned environmental protection and pollution control works may not cope with the works programme, or potential violation of environmental protection and pollution control requirements may arise, he should advise the Contractor and ER accordingly. The review should be copied to IEC for any follow-up action.
- 8.10 Upon receipt of the advice, the Contractor should undertake immediate action to remedy the situation. The ER should follow up to check that appropriate action has been taken by the Contractor to satisfy Project's environmental protection and pollution control requirements

Environmental Complaints

- 8.11 Complaints should be referred to the ET leader for carrying out complaint investigation procedures. The ET leader should undertake the following procedures upon receipt of any complaint:
- (i) Log complaint and date of receipt onto the complaint database and inform the IEC immediately.
 - (ii) Investigate the complaint to determine its validity, and assess whether the source of the problem is due to works activities.
 - (iii) Identify mitigation measures in consultation with the IEC if a complaint is valid and due to works.
 - (iv) Advise the Contractor accordingly if mitigation measures are required.
 - (v) Review the Contractor's response to identified and required mitigation measures, and the current situation.
 - (vi) If the complaint is transferred from the EPD, submit interim report to the EPD on the status of the complaint investigation and follow-up action within the time frame assigned by the EPD.
 - (vii) Undertake additional monitoring and audit to verify the situation if necessary, and check that any valid reason for complaint does not recur through the proposed amendments to work methods, procedures, machines and/or equipment, etc.
 - (viii) Report investigation results and subsequent actions to complainant (if the source of complaint is EPD, the results should be reported within the timeframe assigned by the EPD).
 - (ix) Log a record of the complaint, investigation, the subsequent actions and the results in the monthly EM&A reports.
- 8.12 During the complaint investigation work, the Contractor and ER should cooperate with the ET leader in providing all necessary information and assistance for completion of the investigation. If mitigation measures (in consultation with the IEC) are required following the investigation, the Contractor should promptly carry out the measures. The ER should check that the measures have been carried out by the Contractor.

9. REPORTING

General

- 9.1 Reports can be provided in an electronic medium upon agreeing the format with EPD. This would enable a transition from a paper / historic and reactive approach to an electronic / real time proactive approach. All the monitoring data (baseline and impact) should also be submitted on diskettes. The format for noise monitoring data to be submitted on diskette is shown in **Appendix B**.
- 9.2 Types of reports that the ET leader should prepare and submit include baseline monitoring report, monthly EM&A report, quarterly EM&A summary report and final EM&A review report. In accordance with Annex 21 of the EIAO-TM, a copy of the monthly, quarterly summary and final review EM&A reports should be made available to the Director of Environmental Protection.

Baseline Monitoring Report

- 9.3 The ET leader should prepare and submit a Baseline Environmental Monitoring Report within 10 working days of completion of the baseline monitoring. Copies of the Baseline Environmental Monitoring Report should be submitted to the Contractor, the IEC, the ER and the EPD. The ET leader should liaise with the relevant parties on the exact number of copies they require. The report format and baseline monitoring data format should be agreed with the EPD prior to submission.
- 9.4 The baseline monitoring report should include at least the following:
- (i) Up to half a page executive summary.
 - (ii) Brief project background information.
 - (iii) Drawings showing locations of the baseline monitoring stations.
 - (iv) Monitoring results (in both hard and diskette copies) together with the following information:
 - Monitoring methodology.
 - Types of equipment used and calibration details.
 - Parameters monitored.
 - Monitoring locations.
 - Monitoring date, time, frequency and duration.
 - Quality assurance (QA) / quality control (QC) results and detection limits.
 - (v) Details of influencing factors, including:
 - Major activities, if any, being carried out on the site during the period.
 - Weather conditions during the period.
 - Other factors which might affect results.
 - (vi) Determination of the Action and Limit Levels for each monitoring parameter and statistical analysis of the baseline data, the analysis should conclude if there is any significant difference between control and impact stations for the parameters monitored.
 - (vii) Revisions for inclusion in the EM&A Manual.

- (viii) Comments, recommendations and conclusions.

Monthly EM&A Reports

- 9.5 The results and findings of all EM&A work required in the Manual should be recorded in the monthly EM&A reports prepared by the ET leader. The EM&A report should be prepared and submitted within 10 working days of the end of each reporting month, with the first report due the month after construction commences. Each monthly EM&A report should be submitted to the following parties: the Contractor, the IEC, the ER and the EPD. Before submission of the first EM&A report, the ET leader should liaise with the parties on the required number of copies and format of the monthly reports in both hard copy and electronic medium.
- 9.6 The ET leader should review the number and location of monitoring stations and parameters every six months, or on as needed basis, in order to cater for any changes in the surrounding environment and the nature of works in progress.

First Monthly EM&A Report

- 9.7 The first monthly EM&A report should include at least the following:
- (i) Executive summary (1-2 pages):
- Breaches of Action and Limit levels.
 - Complaint log.
 - Notifications of any summons and successful prosecutions.
 - Reporting changes.
 - Future key issues.
- (ii) Basic project information:
- Project organization including key personnel contact names and telephone numbers.
 - Construction programme.
 - Management structure, and
 - Works undertaken during the month.
- (iii) Environmental status:
- Works undertaken during the month with illustrations (such as location of works).
 - Drawings showing the project area, any environmental sensitive receivers and the locations of the monitoring and control stations (with co-ordinates of the monitoring locations).
- (iv) A brief summary of EM&A requirements including:
- All monitoring parameters.
 - Environmental quality performance limits (Action and Limit levels).
 - Event-Action Plans.

- Environmental mitigation measures, as recommended in the project EIA study final report.
 - Environmental requirements in contract documents.
- (v) Implementation status:
- Advice on the implementation status of environmental protection and pollution control / mitigation measures, as recommended in the project EIA.
- (vi) Monitoring results (in both hard and diskette copies) together with the following information:
- Monitoring methodology.
 - Name of types of equipment used and calibration details.
 - Parameters monitored.
 - Monitoring locations.
 - Monitoring date, time, frequency, and duration.
 - Weather conditions during the period.
 - Any other factors which might affect the monitoring results.
 - QA/QC results and detection limits.
- (vii) Report on non-compliance, complaints, and notifications of summons and successful prosecutions:
- Record of all non-compliance (exceedances) of the environmental quality performance limits (Action and Limit levels).
 - Record of all complaints received (written or verbal) for each media, including locations and nature of complaints investigation, liaison and consultation undertaken, actions and follow-up procedures taken, results and summary.
 - Record of all notification of summons and successful prosecutions for breaches of current environmental protection / pollution control legislation, including locations and nature of the breaches, investigation, follow-up actions taken, results and summary.
 - Review of the reasons for and the implications of non-compliance, complaints, summons and prosecutions including review of pollution sources and working procedures.
 - Description of the actions taken in the event of non-compliance and deficiency reporting and any follow-up procedures related to earlier non-compliance.
- (viii) Others
- An account of the future key issues as reviewed from the works programme and work method statements.

- Advice on the solid and liquid waste management status.
- Comments (for examples, effectiveness and efficiency of the mitigation measures), recommendations (for example, any improvement in the EM&A programme) and conclusions.

Subsequent Monthly EM&A Reports

9.8 Subsequent monthly EM&A reports should include the following:

- (i) Executive summary (1 - 2 pages):
 - Breaches of Action and Limit levels.
 - Complaints log.
 - Notifications of any summons and successful prosecutions.
 - Reporting changes.
 - Future key issues.
- (ii) Environmental status:
 - Works undertaken during the month with illustrations (such as location of works etc.).
 - Drawing showing the project area, any environmental sensitive receivers and the locations of the monitoring and control stations.
- (iii) Implementation status:
 - Advice on the implementation status of environmental protection and pollution control / mitigation measures, as recommended in the project EIA.
- (iv) Monitoring results (in both hard and diskette copies) together with the following information:
 - Monitoring methodology.
 - Name of types of equipment used and calibration details.
 - Parameters monitored.
 - Monitoring locations.
 - Monitoring date, time, frequency, and duration.
 - Weather conditions during the period.
 - Any other factors which might affect the monitoring results.
 - QA / QC results and detection limits.
- (v) Report on non-compliance, complaints, and notifications of summons and successful prosecutions:
 - Record of all non-compliance (exceedances) of the environmental quality performance limits (Action and Limit levels).
 - Record of all complaints received (written or verbal) for each media, including locations and nature of complaints investigation, liaison and consultation undertaken, actions and follow-up procedures taken, results and summary.
 - Record of all notification of summons and successful prosecutions for breaches of current environmental protection / pollution control legislation, including locations and

nature of the breaches, investigation, follow-up actions taken, results and summary.

- Review of the reasons for and the implications of non-compliance, complaints, summons and prosecutions including review of pollution sources and working procedures.
 - Description of the actions taken in the event of non-compliance and deficiency reporting and any follow-up procedures related to earlier non-compliance.
- (vi) Others
- An account of the future key issues as reviewed from the works programme and work method statements.
 - Advice on the solid and liquid waste management status.
 - Comments (for examples, effectiveness and efficiency of the mitigation measures), recommendations (for example, any improvement in the EM&A programme) and conclusions.
- (vii) Appendix
- Action and Limit levels.
 - Graphical plots of trends of monitored parameters at key stations over the past four reporting periods for representative monitoring stations annotated against the following:
 - major activities being carried out on site during the period.
 - weather conditions during the period.
 - any other factors that might affect the monitoring results.
 - Monitoring schedule for the present and next reporting period.
 - Cumulative statistics on complaints, notifications of summons and successful prosecutions.
 - Outstanding issues and deficiencies.

Quarterly EM&A Summary Reports

9.9 A quarterly EM&A summary report of around five pages should be produced and should contain at least the following information.

- (i) Up to half a page executive summary.
- (ii) Basic project information including a synopsis of the project organisation, programme, contacts of key management, and a synopsis of works undertaken during the quarter.
- (iii) A brief summary of EM&A requirements including:
 - Monitoring parameters.
 - Environmental quality performance limits (Action and Limit levels).
 - Environmental mitigation measures, as recommended in the project EIA Final Report.
- (iv) Advice on the implementation status of environmental protection and pollution control / mitigation measures, as recommended in the project EIA Final Report, summarised in the updated implementation schedule.
- (v) Drawings showing the project area, any environmental sensitive receivers and the locations of

the monitoring and control stations.

- (vi) Graphical plots of any trends in monitored parameters over the past four months (the last month of the previous quarter and the present quarter) for representative monitoring stations annotated against:
 - Major activities being carried out on site during the period.
 - Weather conditions during the period.
 - Any other factors which might affect the monitoring results.
- (vii) Advice on the solid and liquid waste management status.
- (viii) A summary of non-compliance (exceedances) of the environmental quality performance limits (Action and Limit levels).
- (ix) A brief review of the reasons for and the implications of any non-compliance, including a review of pollution sources and working procedures.
- (x) A summary description of actions taken in the event of non-compliance and any follow-up procedures related to any earlier non-compliance.
- (xi) A summarised record of all complaints received (written or verbal) for each media, liaison and consultation undertaken, actions and follow-up procedures taken.
- (xii) Comments (for examples, a review of the effectiveness and efficiency of the mitigation measures), recommendations (for example, any improvement in the EM&A programme) and conclusions for the quarter.
- (xiii) Proponents' contacts and any hotline telephone number for the public to make enquiries.

Final EM&A Review Report

9.10 The final EM&A report should include, inter alia, the following information:

- (i) An executive summary.
- (ii) Drawings showing the project area, any environmental sensitive receivers and the locations of the monitoring and control stations.
- (iii) Basic project information including a synopsis of the project organisation, contacts of key management, and a synopsis of work undertaken during the entire construction period.
- (iv) A brief summary of EM&A requirements including:
 - Monitoring parameters.
 - Environmental quality performance limits (Action and Limit levels).
 - Environmental mitigation measures, as recommended in the project EIA study final report.
 - Event-Action Plans.
- (v) A summary of the implementation status of environmental protection and pollution control/mitigation measures, as recommended in the project EIA Report, summarised in the updated implementation schedule.
- (vi) Graphical plots of the trends of monitored parameters over the construction period for representative monitoring stations, including the post-project monitoring annotated against:

- The major activities being carried out on site during the period.
 - Weather conditions during the period.
 - Any other factors which might affect the monitoring results.
- (vii) A summary of non-compliance (exceedances) of the environmental quality performance limits (Action and Limit levels).
- (xi) A brief review of the reasons for and the implications of non-compliance including review of pollution sources and working procedures as appropriate.
- (xii) A summary description of the actions taken in the event of non-compliance and any follow-up procedures related to earlier non-compliance.
- (xiii) A summary record of all complaints received (written or verbal) for each media, liaison and consultation undertaken, actions and follow-up procedures taken.
- (xiv) A summary record of notifications of summons and successful prosecutions for breaches of the current environmental protection/pollution control legislations, locations and nature of the breaches, investigation, follow-up actions taken and results.
- (xii) A review of the validity of EIA predictions and identification of shortcomings in EIA recommendations.
- (xiii) Comments (for examples, a review of the effectiveness and efficiency of the mitigation measures and of the performance of the environmental management system, that is, of the overall EM&A programme).
- (xiv) Recommendations and conclusions (for example, a review of success of the overall EM&A programme to cost-effectively identify deterioration and to initiate prompt effective mitigatory action when necessary).

Data Keeping

- 9.11 No site-based documents (such as monitoring field records, laboratory analysis records, site inspection forms, etc.) are required to be included in the monthly EM&A reports. However, any such document should be well kept by the ET leader and be ready for inspection upon request. All relevant information should be clearly and systematically recorded in the document. Monitoring data should also be recorded in magnetic media form, and the software copy must be available upon request. Data format should be agreed with EPD. All documents and data should be kept for at least one year following completion of the construction contract.

Interim Notifications of Environmental Quality Limit Exceedances

- 9.12 With reference to the Event and Action Plan, when the environmental quality performance limits are exceeded, the ET leader should immediately notify the IEC and EPD, as appropriate. The notification should be followed up with advice to IEC and EPD on the results of the investigation, proposed actions and success of the actions taken, with any necessary follow-up proposals. A sample template for the interim notifications is presented in Appendix C.