

PTW - North Point
Tree Assessment Schedule

Date of Survey: 8 & 24 Nov 2006

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T001	<i>Delonix regia</i>	鳳凰木	0.160	10.0	2.4	Fair	Poor	Low	Medium	Forked	Retain	No conflict with proposed works	LCSD
T002	<i>Delonix regia</i>	鳳凰木	0.350	12.0	10.0	Fair	Poor	Low	Medium	Curved trunk	Retain	No conflict with proposed works	LCSD
T003	<i>Nerium oleander</i>	夾竹桃	0.140	4.0	2.0	Fair	Poor	Low	Medium	Leaning	Retain	No conflict with proposed works	LCSD
T006	<i>Casuarina equisetifolia</i>	木麻黃	0.200	13.0	3.0	Fair	Poor	Low	Medium	Broken branch	Retain	No conflict with proposed works	LCSD
T009	Dead tree	死樹	0.140	2.0	0.4	-	Retain	No conflict with proposed works	LCSD
T010	Dead tree	死樹	0.110	4.0	3.0	-	Retain	No conflict with proposed works	LCSD
T011	Dead tree	死樹	0.120	6.0	4.0	-	Retain	No conflict with proposed works	LCSD
T013	<i>Melaleuca quinquenervia</i>	白千層	0.250	8.0	4.0	Poor	Poor	Low	Low	Broken trunk, forked, densely grown with bamboo	Retain	No conflict with proposed works	LCSD
T015	<i>Melaleuca quinquenervia</i>	白千層	0.300	7.0	3.0	Fair	Poor	Low	Medium	Densely grown with bamboo	Retain	No conflict with proposed works	LCSD
T016	Dead tree	死樹	0.100	5.0	2.0	-	Retain	No conflict with proposed works	LCSD
T018	Dead tree	死樹	0.120	5.0	3.0	-	Fell	Dead tree	LCSD
T019	<i>Melaleuca quinquenervia</i>	白千層	0.270	12.0	3.0	Fair	Poor	Low	Medium	Broken branch	Transplant	Falls within proposed work area	LCSD
T020	<i>Hibiscus tiliaceus</i>	黃槿	0.300	10.0	4.0	Fair	Poor	Low	Medium	Curved trunk	Transplant	Falls within proposed work area	LCSD
T021	<i>Melaleuca quinquenervia</i>	白千層	0.180	6.0	3.0	Poor	Poor	Low	Low	Leaning, dead branch	Transplant	Falls within proposed work area	LCSD
T022	<i>Casuarina equisetifolia</i>	木麻黃	0.140	6.0	2.0	Poor	Poor	Low	Low	Leaning, shoot and branch grown with climber	Transplant	Falls within footprint of proposed works	LCSD
T025	<i>Ficus elastica</i>	印度榕	0.300	6.0	4.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within footprint of proposed works	LCSD
T026	<i>Leucaena leucocephala</i>	銀合歡	0.150	7.0	4.0	Fair	Poor	Low	Medium	Leaning	Fell	Falls within footprint of proposed works	LCSD
T027	<i>Leucaena leucocephala</i>	銀合歡	0.150	8.0	3.0	Fair	Poor	Low	Medium	Leaning	Fell	Falls within footprint of proposed works	LCSD
T028	Dead tree	死樹	0.120	8.0	5.0	-	Fell	Dead tree	LCSD
T030	<i>Macaranga tanarius</i>	血桐	0.100	8.0	2.0	Poor	Poor	Low	Low	Forked, leaning	Transplant	Falls within footprint of proposed works	LCSD
T031	<i>Hibiscus tiliaceus</i>	黃槿	0.220	9.0	5.0	Fair	Poor	Low	Medium	Forked, curved trunk	Transplant	Falls within footprint of proposed works	LCSD
T032	<i>Macaranga tanarius</i>	血桐	0.120	7.0	4.0	Fair	Poor	Low	medium	Leaning, forked, broken branch	Transplant	Falls within footprint of proposed works	LCSD
T034	<i>Nerium oleander</i>	夾竹桃	0.120	6.0	4.0	Fair	Poor	Low	Medium	Leaning	Transplant	Falls within footprint of proposed works	LCSD
T035	<i>Nerium oleander</i>	夾竹桃	0.100	4.0	3.0	Fair	Poor	Low	Medium	Curved trunk	Transplant	Falls within footprint of proposed works	LCSD
T036	<i>Delonix regia</i>	鳳凰木	0.300	12.0	10.0	Fair	Poor	Low	Medium	Curved trunk	Transplant	Falls within footprint of proposed works	LCSD
T037	<i>Casuarina equisetifolia</i>	木麻黃	0.200	11.0	3.0	Fair	Poor	Low	Medium	Curved trunk	Transplant	Falls within footprint of proposed works	LCSD
T038	<i>Ilex rotunda</i>	鐵冬青	0.100	6.0	2.0	Fair	Poor	Low	Medium	Curved trunk	Transplant	Falls within footprint of proposed works	LCSD
T039	<i>Macaranga tanarius</i>	血桐	0.180	10.0	2.0	Fair	Poor	Low	Medium	Broken branch, leaning	Transplant	Falls within footprint of proposed works	LCSD

PTW - North Point
Tree Assessment Schedule

Date of Survey: 8 & 24 Nov 2006

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T041	<i>Hibiscus tiliaceus</i>	黃種	0.500	6.0	5.0	Fair	Poor	Low	Medium	Multi-trunk	Transplant	Falls within footprint of proposed works	LCSD
T042	<i>Hibiscus tiliaceus</i>	黃種	0.120	6.0	5.0	Fair	Poor	Low	Medium	Leaning, curved trunk	Transplant	Falls within footprint of proposed works	LCSD
T045	<i>Ficus elastica</i>	印度榕	0.400	8.0	8.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within footprint of proposed works	LCSD
T046	<i>Leucaena leucocephala</i>	銀合歡	0.150	8.0	3.0	Fair	Poor	Low	Medium	Curved trunk	Fell	Falls within footprint of proposed works	LCSD
T047	<i>Casuarina equisetifolia</i>	木麻黃	0.330	6.0	10.0	Fair	Poor	Low	Medium	Curved trunk	Transplant	Falls within footprint of proposed works	LCSD
T048	<i>Eucalyptus torelliana</i>	毛葉桉	0.250	6.0	1.0	Fair	Poor	Low	Medium	Curved trunk, densely grown with bamboo	Transplant	Falls within footprint of proposed works	LCSD
T052	<i>Artocarpus macrocarpon</i>	波羅蜜	0.110	5.0	2.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within footprint of proposed works	LCSD
T053	<i>Macaranga tanarius</i>	血桐	0.280	5.0	7.0	Fair	Poor	Low	Medium	Forked, densely grown with bamboo	Transplant	Falls within footprint of proposed works	LCSD
T055	<i>Eucalyptus torelliana</i>	毛葉桉	0.500	15.0	4.0	Fair	Fair	Low	Medium	Forked	Retain	No conflict with proposed works	LCSD
T056	<i>Ilex rotunda</i>	鐵冬青	0.300	10.0	6.0	Fair	Poor	Low	Medium	Forked, curved trunk	Retain	No conflict with proposed works	LCSD
T057	<i>Casuarina equisetifolia</i>	木麻黃	0.280	11.0	5.0	Fair	Fair	Medium	Medium	-	Retain	No conflict with proposed works	LCSD
T058	Dead tree	死樹	0.100	1.8	0.7	-	-	-	-	-	Retain	No conflict with proposed works	LCSD
T059	<i>Carica papaya</i>	番木瓜	0.100	6.0	5.0	Fair	Poor	Low	Medium	-	Retain	No conflict with proposed works	LCSD
T060	<i>Carica papaya</i>	番木瓜	0.100	7.0	2.0	Fair	Poor	Low	Medium	-	Retain	No conflict with proposed works	LCSD
T061	<i>Aleurites moluccana</i>	石栗	0.130	7.0	3.0	Fair	Poor	Low	Medium	Deformed crown	Retain	No conflict with proposed works	LCSD
T064	<i>Macaranga tanarius</i>	血桐	0.200	5.0	4.0	Fair	Poor	Low	Medium	Leaning	Transplant	Falls within footprint of proposed works	LCSD
T066	<i>Morus alba</i>	桑	0.100	5.0	4.0	Fair	Poor	Low	Medium	Leaning	Transplant	Falls within footprint of proposed works	LCSD
T067	<i>Nerium oleander</i>	夾竹桃	0.100	3.0	2.0	Poor	Poor	Low	Low	Broken and dead branch	Transplant	Falls within footprint of proposed works	LCSD
T068	<i>Ficus elastica</i>	印度榕	0.400	7.0	6.0	Fair	Poor	Low	Medium	Deformed crown	Transplant	Falls within footprint of proposed works	LCSD
T069	<i>Ficus elastica</i>	印度榕	0.300	5.0	2.0	Poor	Poor	Low	Low	Broken branch	Transplant	Falls within footprint of proposed works	LCSD
T070	<i>Ficus elastica</i>	印度榕	0.100	3.7	3.0	Fair	Poor	Low	Medium	Leaning, broken branch	Transplant	Falls within footprint of proposed works	LCSD
T071	<i>Ficus elastica</i>	印度榕	0.200	6.0	5.0	Poor	Poor	Low	Low	Broken trunk, leaning	Transplant	Falls within footprint of proposed works	LCSD
T072	<i>Ficus elastica</i>	印度榕	0.100	4.0	3.0	Fair	Poor	Low	Medium	Dead branch	Transplant	Falls within footprint of proposed works	LCSD
T074	<i>Aleurites moluccana</i>	石栗	0.300	11.0	4.0	Fair	Poor	Low	Medium	Forked	Transplant	Falls within footprint of proposed works	LCSD
T075	<i>Eucalyptus torelliana</i>	毛葉桉	0.350	11.0	4.0	Fair	Poor	Low	Medium	Forked, leaning, dead branch	Transplant	Falls within footprint of proposed works	LCSD
T076	<i>Ficus hispida</i>	對葉榕	0.100	3.0	2.0	Poor	Poor	Low	Low	Dead branch, leaning	Transplant	Falls within footprint of proposed works	LCSD
T077	<i>Acacia confusa</i>	臺灣相思	0.250	10.0	3.0	Fair	Poor	Low	Medium	Curved trunk, dead branch	Transplant	Falls within footprint of proposed works	LCSD
T079	Dead tree	死樹	0.100	5.0	2.0	-	-	-	-	-	Fell	Dead tree	LCSD

PTW - North Point
Tree Assessment Schedule

Date of Survey: 8 & 24 Nov 2006

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T083	<i>Melaleuca quinquenervia</i>	白千層	0.100	4.0	2.0	Fair	Poor	Low	Medium	Leaning, yellow leaves	Transplant	Falls within footprint of proposed works	LCSD
T084	<i>Melaleuca quinquenervia</i>	白千層	0.250	8.0	3.0	Fair	Poor	Low	Medium	Curved trunk	Transplant	Falls within footprint of proposed works	LCSD
T086	<i>Macaranga tanarius</i>	血桐	0.200	8.0	5.0	Fair	Poor	Low	Medium	Forked, curved trunk	Transplant	Falls within footprint of proposed works	LCSD
T087	<i>Cassia siamea</i>	鐵刀木	0.300	7.0	7.0	Fair	Poor	Low	Medium	Curved trunk	Transplant	Falls within footprint of proposed works	LCSD
T088	<i>Delonix regia</i>	鳳凰木	0.300	7.0	7.0	Fair	Poor	Low	Medium	Curved trunk, broken branch	Transplant	Falls within footprint of proposed works	LCSD
T090	<i>Delonix regia</i>	鳳凰木	0.400	11.0	10.0	Fair	Poor	Low	Medium	Curved trunk, dead branch	Transplant	Falls within footprint of proposed works	LCSD
T092	<i>Ficus elastica</i>	印度榕	0.150	5.0	6.0	Fair	Poor	Low	Medium	Leaning, dead and broken branch	Transplant	Falls within footprint of proposed works	LCSD
T093	<i>Cassia siamea</i>	鐵刀木	0.300	10.0	6.0	Fair	Poor	Low	Medium	Leaning, curved and broken branch	Transplant	Falls within footprint of proposed works	LCSD
T095	<i>Melaleuca quinquenervia</i>	白千層	0.120	7.0	2.5	Fair	Fair	Low	Medium	-	Retain	No conflict with proposed works	LCSD
T096	<i>Melaleuca quinquenervia</i>	白千層	0.150	6.0	2.5	Fair	Fair	Low	Medium	-	Retain	No conflict with proposed works	LCSD
T097	<i>Melaleuca quinquenervia</i>	白千層	0.120	8.0	2.0	Fair	Fair	Low	Medium	-	Retain	No conflict with proposed works	LCSD
T098	<i>Melaleuca quinquenervia</i>	白千層	0.200	8.0	3.0	Fair	Fair	low	Medium	-	Retain	No conflict with proposed works	LCSD
T102	<i>Nerium oleander</i>	夾竹桃	0.120	4.0	5.0	Fair	Poor	Low	Medium	Yellow leaves, multi-trunk, dead branch	Retain	Falls within proposed work area	LCSD
T103	<i>Casuarina equisetifolia</i>	木麻黃	0.300	12.0	7.0	Fair	Poor	Low	Medium	Leaning, curved trunk, broken branch, forked	Retain	Falls within proposed work area	LCSD
T104	<i>Delonix regia</i>	鳳凰木	0.200	10.0	10.0	Fair	Poor	Low	Medium	Forked	Retain	Falls within proposed work area	LCSD
T106	<i>Delonix regia</i>	鳳凰木	0.300	11.0	10.0	Fair	Poor	Low	Medium	Dead branch	Retain	Falls within proposed work area	LCSD
T107	<i>Delonix regia</i>	鳳凰木	0.150	10.0	6.0	Fair	Poor	Low	Medium	Forked	Transplant	Falls within footprint of proposed works	LCSD
T109	<i>Delonix regia</i>	鳳凰木	0.250	10.0	8.0	Fair	Fair	Medium	Medium	Forked	Transplant	Falls within footprint of proposed works	LCSD
T110	<i>Nerium oleander</i>	夾竹桃	0.150	6.0	3.0	Fair	Poor	Low	Medium	Leaning, densely grown with bamboo	Transplant	Falls within footprint of proposed works	LCSD
T111	<i>Delonix regia</i>	鳳凰木	0.350	12.0	12.0	Fair	Fair	Medium	Medium	Broken branch, leaning	Transplant	Falls within footprint of proposed works	LCSD
T113	<i>Nerium oleander</i>	夾竹桃	0.170	6.0	2.0	Poor	Poor	Low	Medium	Broken trunk, densely grown with bamboo	Transplant	Falls within footprint of proposed works	LCSD
T114	<i>Delonix regia</i>	鳳凰木	0.350	11.0	10.0	Fair	Fair	Low	Medium	Dead branch	Retain	No conflict with proposed works	LCSD
T115	<i>Delonix regia</i>	鳳凰木	0.320	12.0	12.0	Fair	Poor	Low	Medium	Broken branch, curved branch	Retain	No conflict with proposed works	LCSD
T119	<i>Macaranga tanarius</i>	血桐	0.150	5.0	4.0	Fair	Poor	Low	Medium	Forked	Retain	No conflict with proposed works	LCSD
T120	<i>Delonix regia</i>	鳳凰木	0.350	12.0	10.0	Fair	Poor	Low	Medium	Curved trunk, leaning, broken branch	Retain	No conflict with proposed works	LCSD
T121	<i>Delonix regia</i>	鳳凰木	0.250	12.0	6.0	Fair	Poor	Low	Medium	Curved trunk, leaning	Retain	No conflict with proposed works	LCSD
T123	<i>Delonix regia</i>	鳳凰木	0.300	11.0	6.0	Fair	Poor	Low	Medium	Forked, broken branch	Retain	No conflict with proposed works	LCSD
T125	<i>Macaranga tanarius</i>	血桐	0.250	8.0	5.0	Fair	Poor	Low	Medium	Forked, dead branch	Retain	No conflict with proposed works	LCSD
T126	<i>Delonix regia</i>	鳳凰木	0.260	9.0	6.0	Fair	Poor	Low	Medium	Forked, dead branch	Retain	No conflict with proposed works	LCSD

PTW - North Point
Tree Assessment Schedule

Date of Survey: 8 & 24 Nov 2006

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T127	<i>Macaranga tanarius</i>	血桐	0.200	4.0	4.0	Fair	Poor	Low	Medium	Leaning, forked, curved trunk	Retain	No conflict with proposed works	LCSD
T129	<i>Delonix regia</i>	鳳凰木	0.400	12.0	8.0	Fair	Poor	Low	Medium	Broken branch	Retain	No conflict with proposed works	LCSD
T132	<i>Ficus virens</i>	黃葛樹	0.600	12.0	10.0	Fair	Fair	Medium	Medium	Yellow leaves	Retain	No conflict with proposed works	LCSD
T134	<i>Mallotus paniculatus</i>	白楸	0.100	5.0	6.0	Fair	Fair	Low	Medium	Leaning, damage on bark	Retain	No conflict with proposed works	LCSD
T135	<i>Acacia confusa</i>	臺灣相思	0.450	10.0	6.0	Fair	Poor	Low	Medium	Damage on bark, broken trunk and branch, curved trunk	Retain	No conflict with proposed works	LCSD
T138	Dead tree	死樹	0.100	3.0	3.0	-	-	-	-	-	Retain	No conflict with proposed works	LCSD
T139	<i>Delonix regia</i>	鳳凰木	0.350	12.0	10.0	Fair	Fair	Medium	Medium	Forked	Retain	No conflict with proposed works	LCSD
T140	<i>Delonix regia</i>	鳳凰木	0.150	12.0	3.0	Poor	Poor	Low	Low	Damage on bark	Retain	No conflict with proposed works	LCSD
T141	<i>Macaranga tanarius</i>	血桐	0.250	11.0	6.0	Fair	Poor	Low	Medium	Leaning	Retain	No conflict with proposed works	LCSD
T142	<i>Macaranga tanarius</i>	血桐	0.150	10.0	8.0	Fair	Poor	Low	Medium	Curved trunk, leaning	Retain	No conflict with proposed works	LCSD
T144	<i>Delonix regia</i>	鳳凰木	0.200	9.0	5.0	Fair	Poor	Low	Medium	Angled trunk	Retain	No conflict with proposed works	LCSD
T146	<i>Delonix regia</i>	鳳凰木	0.300	12.0	6.0	Fair	Poor	Low	Medium	Angled trunk	Transplant	Falls within footprint of proposed works	LCSD
T147	<i>Aleurites moluccana</i>	石栗	0.300	12.0	5.0	Fair	Poor	Low	Medium	Dead branch	Transplant	Falls within footprint of proposed works	LCSD
T148	<i>Aleurites moluccana</i>	石栗	0.160	11.0	3.0	Fair	Poor	Low	Medium	-	Transplant	Falls within footprint of proposed works	LCSD
T152	<i>Celtis sinensis</i>	朴樹	0.200	8.0	5.0	Fair	Fair	Low	Medium	Leaning, curved trunk	Retain	No conflict with proposed works	LCSD
T154	<i>Ficus microcarpa</i>	細葉榕	0.100	4.0	3.0	Fair	Fair	Low	Medium	Leaning	Retain	No conflict with proposed works	LCSD

* LCSD - Leisure and Cultural Services Department

PTW - Wan Chai East
Tree Assessment Schedule

Date of Survey: 12 Oct & 6 Dec 2006

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T012	<i>Bauhinia</i> sp.	羊蹄甲屬	0.130	4.0	3.0	Poor	Poor	Low	Low	Dead leading shoot, deformed crown	Retain	No conflict with proposed works	LCSD
T013	<i>Bauhinia</i> sp.	羊蹄甲屬	0.150	5.0	4.0	Poor	Poor	Low	Low	Dead leading shoot	Retain	No conflict with proposed works	LCSD
T014	<i>Bauhinia</i> sp.	羊蹄甲屬	0.150	4.0	3.0	Poor	Poor	Low	Low	Climber overgrown, suppressed growth	Transplant	Falls within proposed work area	LCSD
T015	<i>Melia azedarach</i>	苦楝	0.200	6.0	2.0	Fair	Poor	Low	Medium	Angled trunk	Transplant	Falls within proposed work area	LCSD
T016	<i>Macaranga tanarius</i>	血桐	0.280	5.0	5.0	Fair	Poor	Low	Medium	Leaning trunk, dead branches	Transplant	Falls within proposed work area	LCSD
T017	<i>Spathodea campanulata</i>	火焰木	0.130	4.0	3.0	Poor	Poor	Low	Low	Suppressed growth, deformed crown	Transplant	Falls within proposed work area	LCSD
T018	<i>Delonix regia</i>	鳳凰木	0.250	6.0	4.0	Fair	Poor	Low	Low	Topped leading shoot	Transplant	Falls within proposed work area	LCSD
T019	<i>Delonix regia</i>	鳳凰木	0.140	4.0	1.5	Fair	Poor	Low	Medium	Deformed crown	Transplant	Falls within proposed work area	LCSD
T020	<i>Broussonetia papyrifera</i>	構樹	0.200	7.0	3.0	Poor	Poor	Low	Low	Bark damage	Transplant	Falls within proposed work area	LCSD
T021	<i>Delonix regia</i>	鳳凰木	0.300	7.0	4.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
T022	<i>Cassia siamea</i>	鐵刀木	0.270	8.0	4.0	Fair	Poor	Low	Medium	Curved trunk	Transplant	Falls within proposed work area	LCSD
T023	<i>Broussonetia papyrifera</i>	構樹	0.300	4.0	4.0	Poor	Poor	Low	Low	Multi-trunk, bark damage	Transplant	Falls within proposed work area	LCSD
T024	<i>Cassia siamea</i>	鐵刀木	0.350	8.0	6.0	Fair	Poor	Low	Medium	Leaning trunk	Transplant	Falls within proposed work area	LCSD
T025	<i>Broussonetia papyrifera</i>	構樹	0.200	4.0	3.0	Poor	Poor	Low	Low	Bark damage	Transplant	Falls within proposed work area	LCSD
T026	<i>Cassia siamea</i>	鐵刀木	0.200	7.0	3.0	Fair	Fair	Medium	Medium	Bark damage	Transplant	Falls within proposed work area	LCSD
T027	<i>Cassia siamea</i>	鐵刀木	0.200	7.0	2.0	Fair	Fair	Medium	Medium	Topped leading shoot, some climber grown on tree	Transplant	Falls within proposed work area	LCSD
T028	<i>Delonix regia</i>	鳳凰木	0.300	10.0	6.0	Fair	Poor	Low	Medium	Curved trunk	Transplant	Falls within proposed work area	LCSD
T029	<i>Cassia siamea</i>	鐵刀木	0.200	9.0	4.0	Fair	Fair	Medium	Medium	Some climber grown on tree	Transplant	Falls within proposed work area	LCSD
T031	<i>Delonix regia</i>	鳳凰木	0.200	7.0	3.0	Fair	Poor	Low	Medium	Curved trunk	Transplant	Falls within proposed work area	LCSD
T032	<i>Cassia siamea</i>	鐵刀木	0.300	8.0	4.0	Fair	Poor	Low	Medium	Bark damage, curve trunk	Transplant	Falls within proposed work area	LCSD
T033	<i>Hibiscus tiliaceus</i>	黃槿	3x0.120	6.0	3.0	Fair	Poor	Low	Medium	Multi-trunk	Transplant	Falls within proposed work area	LCSD
T034	<i>Cassia siamea</i>	鐵刀木	0.170	7.0	2.5	Fair	Poor	Low	Medium	Bark damage, some climber grown on tree	Transplant	No conflict with proposed works	LCSD
T035	<i>Melia azedarach</i>	苦楝	3x0.140	5.0	3.0	Fair	Fair	Medium	Medium	Bark damage, multi-trunk	Transplant	Falls within proposed work area	LCSD
T036	<i>Delonix regia</i>	鳳凰木	0.200	6.0	3.0	Fair	Fair	Low	Medium	-	Transplant	Falls within proposed work area	LCSD
T037	<i>Ficus microcarpa</i>	細葉榕	0.200	3.5	3.5	Good	Good	High	High	-	Transplant	Falls within proposed work area	LCSD
T038	<i>Delonix regia</i>	鳳凰木	0.350	6.0	4.0	Fair	Poor	Low	Medium	Leaning	Transplant	Falls within proposed work area	LCSD
T040	<i>Cassia siamea</i>	鐵刀木	0.250	7.0	3.5	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
T042	<i>Celtis sinensis</i>	朴樹	0.130	4.0	3.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
T044	<i>Delonix regia</i>	鳳凰木	0.300	7.0	4.0	Fair	Poor	Low	Medium	Some bark damage	Transplant	Falls within proposed work area	LCSD

PTW - Wan Chai East
Tree Assessment Schedule

Date of Survey: 12 Oct & 6 Dec 2006

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T045	<i>Celtis sinensis</i>	朴樹	0.120	5.0	2.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
T046	<i>Celtis sinensis</i>	朴樹	0.150	5.0	3.0	Fair	Poor	Low	Medium	leaning, some climber grown on tree	Transplant	Falls within proposed work area	LCSD
T048	<i>Aleurites moluccana</i>	石栗	0.200	7.0	2.0	Poor	Poor	Low	Low	Bark damage, topped leading shoot	Transplant	Falls within proposed work area	LCSD
T049	<i>Aleurites moluccana</i>	石栗	0.200	7.0	2.0	Fair	Poor	Low	Medium	Deformed crown	Transplant	Falls within proposed work area	LCSD
T050	Dead tree	死樹	0.120	2.5	0.5	-	-	-	-	-	Fell	Dead	LCSD
T051	<i>Ficus microcarpa</i>	細葉榕	0.140	5.0	2.0	Fair	Poor	Low	Medium	Deformed crown	Transplant	Falls within proposed work area	LCSD
T053	<i>Ficus superba</i>	筆管榕	0.100	5.0	2.0	Fair	Poor	Low	Medium	Curved trunk	Retain	No conflict with proposed works	LCSD
T055	<i>Aleurites moluccana</i>	石栗	0.130	6.0	2.0	Fair	Poor	Low	Medium	Curved trunk	Retain	No conflict with proposed works	LCSD
T057	<i>Ficus elastica</i>	印度榕	0.120	2.0	0.5	Poor	Poor	Low	Low	Broken trunk	Retain	No conflict with proposed works	LCSD
T059	<i>Aleurites moluccana</i>	石栗	0.160	6.0	2.0	Fair	Poor	Low	Medium	Deformed crown	Retain	No conflict with proposed works	LCSD
T063	<i>Ilex rotunda</i> Thunb.	鐵冬青	0.130	3.0	2.0	Fair	Poor	Low	Medium	Cut trunk	Retain	No conflict with proposed works	LCSD
T064	<i>Artocarpus macrocarpon</i>	菠蘿蜜	0.100	4.0	2.5	Good	Fair	Medium	High	Dead branch	Retain	No conflict with proposed works	LCSD
T065	<i>Artocarpus macrocarpon</i>	菠蘿蜜	0.120	5.0	2.5	Good	Good	High	High	-	Retain	No conflict with proposed works	LCSD
T067	<i>Artocarpus macrocarpon</i>	菠蘿蜜	0.100	4.0	2.0	Fair	Fair	Low	High	Leaning	Retain	No conflict with proposed works	LCSD
T068	<i>Delonix regia</i>	鳳凰木	0.250	7.0	5.0	Fair	Poor	Low	Medium	Curved trunk, deformed crown	Retain	No conflict with proposed works	LCSD
T069	<i>Delonix regia</i>	鳳凰木	0.300	8.0	6.0	Fair	Poor	Low	Medium	Curved trunk	Retain	No conflict with proposed works	LCSD
T070	<i>Delonix regia</i>	鳳凰木	0.350	7.0	5.0	Fair	Poor	Low	Medium	Forked	Retain	No conflict with proposed works	LCSD
T071	<i>Delonix regia</i>	鳳凰木	0.160	6.0	4.0	Fair	Poor	Low	Medium	Curved trunk	Retain	No conflict with proposed works	LCSD
T072	<i>Delonix regia</i>	鳳凰木	0.180	8.0	3.0	Fair	Poor	Low	Medium	Curved trunk	Retain	No conflict with proposed works	LCSD
T073	<i>Delonix regia</i>	鳳凰木	0.200	8.0	3.0	Fair	Poor	Low	Medium	Curved trunk	Retain	No conflict with proposed works	LCSD
T074	<i>Araucaria heterophylla</i>	南洋杉	0.100	4.0	2.0	Fair	Fair	Low	High	Curved trunk	Retain	No conflict with proposed works	LCSD
T075	<i>Araucaria heterophylla</i>	南洋杉	0.100	4.0	2.0	Fair	Poor	Low	High	Curved trunk	Retain	No conflict with proposed works	LCSD
T076	<i>Delonix regia</i>	鳳凰木	0.300	7.0	7.0	Fair	Poor	Low	Medium	Curved trunk, leaning	Retain	No conflict with proposed works	LCSD
T077	<i>Araucaria heterophylla</i>	南洋杉	0.100	4.0	2.0	Fair	Fair	Low	High	Curved trunk	Retain	No conflict with proposed works	LCSD
T078	<i>Araucaria heterophylla</i>	南洋杉	0.120	5.0	2.0	Fair	Fair	Low	High	Curved trunk	Retain	No conflict with proposed works	LCSD
T079	<i>Delonix regia</i>	鳳凰木	0.300	7.0	6.0	Fair	Fair	Low	Medium	Forked	Retain	No conflict with proposed works	LCSD
T081	<i>Araucaria heterophylla</i>	南洋杉	0.100	4.0	2.0	Fair	Fair	Low	High	Curved trunk	Retain	No conflict with proposed works	LCSD
T084	<i>Delonix regia</i>	鳳凰木	0.350	7.0	6.0	Fair	Poor	Low	Medium	Curved trunk, forked, dead branch	Retain	No conflict with proposed works	LCSD
T086	<i>Delonix regia</i>	鳳凰木	0.300	7.0	6.0	Fair	Poor	Low	Medium	Forked, cut trunk	Retain	No conflict with proposed works	LCSD

PTW - Wan Chai East
Tree Assessment Schedule

Date of Survey: 12 Oct & 6 Dec 2006

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T090	<i>Araucaria heterophylla</i>	南洋杉	0.100	4.0	2.0	Fair	Fair	Low	High	Curved trunk	Retain	No conflict with proposed works	LCSD
T093	<i>Araucaria heterophylla</i>	南洋杉	0.100	4.0	2.0	Fair	Fair	Low	Medium	Curved trunk	Retain	No conflict with proposed works	LCSD
T094	<i>Delonix regia</i>	鳳凰木	0.400	8.0	7.0	Fair	Poor	Low	Medium	Curved trunk, forked, dead branch	Retain	No conflict with proposed works	LCSD
T101	<i>Araucaria heterophylla</i>	南洋杉	0.100	4.0	2.0	Fair	Fair	Low	High	Leaning	Retain	No conflict with proposed works	LCSD
T102	<i>Araucaria heterophylla</i>	南洋杉	0.100	4.0	2.0	Fair	Fair	Low	High	Curved trunk	Retain	No conflict with proposed works	LCSD
T114	<i>Livistona chinensis</i> R. Br.	蒲葵	0.200	6.0	3.5	Fair	Poor	Low	High	Leaning	Retain	No conflict with proposed works	LCSD
T115	<i>Acacia confusa</i>	臺灣相思	0.300	8.0	6.0	Fair	Poor	Low	Medium	Leaning, forked	Retain	No conflict with proposed works	LCSD
T116	<i>Acacia confusa</i>	臺灣相思	0.250	7.0	5.0	Fair	Poor	Low	Medium	Leaning, forked	Retain	No conflict with proposed works	LCSD
T117	<i>Macaranga tanarius</i>	血桐	0.100	3.0	4.0	Fair	Fair	Low	Medium	Curved trunk, broken branch	Retain	No conflict with proposed works	LCSD
T118	<i>Acacia confusa</i>	臺灣相思	0.250	8.0	5.0	Fair	Fair	Low	Medium	Broken bark	Retain	No conflict with proposed works	LCSD
T119	<i>Leucaena leucocephala</i>	銀合歡	0.240	6.0	4.0	Fair	Fair	Low	Medium	Multi-trunk, leaning, dead branch	Retain	No conflict with proposed works	LCSD
T120	<i>Phoenix roebelenii</i> O' Brien	日本葵	0.100	2.5	2.0	Fair	Poor	Low	High	Curved trunk	Retain	No conflict with proposed works	LCSD
T121	<i>Phoenix roebelenii</i> O' Brien	日本葵	0.100	2.5	2.0	Fair	Poor	Low	High	Curved trunk	Retain	No conflict with proposed works	LCSD
T122	<i>Phoenix roebelenii</i> O' Brien	日本葵	0.100	2.0	2.0	Fair	Poor	Low	High	Curved trunk	Retain	No conflict with proposed works	LCSD
T123	<i>Phoenix roebelenii</i> O' Brien	日本葵	0.100	3.0	2.0	Fair	Poor	Low	High	Leaning	Retain	No conflict with proposed works	LCSD
T124	<i>Phoenix roebelenii</i> O' Brien	日本葵	0.100	2.5	2.0	Fair	Poor	Low	High	Curved trunk, leaning	Retain	No conflict with proposed works	LCSD
T126	<i>Ficus microcarpa</i>	細葉榕	0.100	4.0	3.0	Fair	Fair	Medium	Medium	-	Retain	No conflict with proposed works	LCSD
T128	<i>Eucalyptus robusta</i>	大葉桉	0.100	4.0	2.0	Fair	Fair	Medium	Medium	-	Retain	No conflict with proposed works	LCSD

* LCSD - Leisure and Cultural Services Department

PTW - Central
Tree Assessment Schedule

Date of Survey: 17-Oct-06

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T001	<i>Bombax ceiba</i>	木棉	0.400	10.0	8.0	Fair	Fair	Medium	Medium	Broken branches	Retain	No conflict with proposed works	LCSD
T002	<i>Macaranga tanarius</i>	血桐	0.300	6.0	7.0	Poor	Poor	Low	Low	Bark and trunk damages	Retain	No conflict with proposed works	LCSD
T003	<i>Macaranga tanarius</i>	血桐	0.280	6.5	7.0	Fair	Poor	Low	Medium	Deformed crown	Retain	No conflict with proposed works	LCSD
T004	<i>Musa x paradisiaca</i>	大蕉, 甘蔗	3x0.130	3.2	2.0	Poor	Poor	Low	Low	Yellow leaves, many dead branches, multi-trunk	Retain	No conflict with proposed works	LCSD
T005	<i>Musa x paradisiaca</i>	大蕉, 甘蔗	2x0.120	3.2	1.0	Poor	Poor	Low	Low	Yellow leaves, multi-trunk	Retain	No conflict with proposed works	LCSD
T006	<i>Musa x paradisiaca</i>	大蕉, 甘蔗	7x0.150	3.2	3.0	Poor	Poor	Low	Low	Yellow leaves, multi-trunk	Retain	No conflict with proposed works	LCSD
T007	<i>Macaranga tanarius</i>	血桐	3x0.100	5.0	5.0	Fair	Poor	Low	Medium	Bark damage	Retain	No conflict with proposed works	LCSD
T008	<i>Macaranga tanarius</i>	血桐	0.120	5.5	3.5	Fair	Poor	Low	Medium	Angled trunk, deformed crown	Retain	No conflict with proposed works	LCSD
T009	<i>Macaranga tanarius</i>	血桐	0.150	6.0	4.5	Fair	Fair	Low	Medium	Curved trunk	Retain	No conflict with proposed works	LCSD
T010	<i>Macaranga tanarius</i>	血桐	0.150	5.0	5.0	Poor	Poor	Low	Low	Leaning, bark damages	Retain	No conflict with proposed works	LCSD
T012	<i>Celtis sinensis</i>	朴樹	0.120	5.0	2.5	Poor	Poor	Low	Low	Deformed crown, dead leading shoot	Retain	No conflict with proposed works	LCSD
T013	<i>Celtis sinensis</i>	朴樹	0.350	8.5	5.5	Fair	Poor	Low	Medium	Forked, deformed crown	Retain	No conflict with proposed works	LCSD
T014	<i>Macaranga tanarius</i>	血桐	0.100	2.5	4.0	Fair	Fair	Low	Medium	-	Retain	No conflict with proposed works	LCSD
T016	<i>Celtis sinensis</i>	朴樹	2x0.200	9.5	8.0	Fair	Poor	Low	Medium	Forked, broken branches, bark damage	Retain	No conflict with proposed works	LCSD
T018	<i>Macaranga tanarius</i>	血桐	0.270	7.2	7.0	Fair	Poor	Low	Medium	Leaning, forked	Transplant	Falls within proposed work area	LCSD
T019	<i>Psidium guajava</i>	番石榴	0.120	6.0	4.3	Poor	Poor	Low	Low	Leaning, Deformed crown, dead branches	Transplant	Falls within proposed work area	LCSD
T020	<i>Clausena lansium</i>	黃皮	2x0.150	5.5	4.0	Fair	Fair	Medium	Medium	Dead branches	Transplant	No conflict with proposed works	LCSD

* LCSD - Leisure and Cultural Services Department

PTW - Sandy Bay
Tree Assessment Schedule

Date of Survey: 17 Oct & 10 Nov 2006

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T002	<i>Psidium guajava</i>	番石榴	0.100	3.3	4.0	Poor	Poor	Low	Low	Forked, suppressed growth	Transplant	Falls within footprint of proposed works	LCSD
T003	<i>Ficus elastica</i>	印度榕	0.600	10.0	6.5	Good	Good	High	Medium	-	Transplant	Falls within footprint of proposed works	LCSD
T004	<i>Psidium guajava</i>	番石榴	0.100	3.6	3.5	Fair	Poor	Low	Medium	-	Transplant	Falls within footprint of proposed works	DSD
T005	<i>Psidium guajava</i>	番石榴	0.100	4.7	3.5	Fair	Poor	Low	Medium	Leaning	Transplant	Falls within footprint of proposed works	DSD
T006	<i>Ficus elastica</i>	印度榕	0.500	9.5	6.5	Good	Good	High	Medium	-	Transplant	Falls within footprint of proposed works	LCSD
T007	Unidentified tree	-	0.300	12.0	6.0	Fair	Fair	Medium	Medium	Bark damage, dead branches	Transplant	Falls within footprint of proposed works	LCSD
T008	Unidentified tree	-	0.200	11.0	4.5	Good	Good	High	High	-	Transplant	Falls within footprint of proposed works	LCSD
T009	Unidentified tree	-	0.300	11.0	7.6	Good	Good	High	High	-	Transplant	Falls within footprint of proposed works	LCSD
T010	Unidentified tree	-	0.220	8.5	3.6	Fair	Fair	Medium	Medium	Bark damage	Transplant	Falls within footprint of proposed works	LCSD
T011	Unidentified tree	-	0.250	8.5	5.7	Fair	Fair	Medium	Medium	-	Transplant	Falls within footprint of proposed works	LCSD
T012	Unidentified tree	-	0.280	12.0	8.0	Fair	Good	High	Medium	Bark damage	Transplant	Falls within footprint of proposed works	LCSD
T013	Unidentified tree	-	0.250	12.0	5.8	Fair	Fair	Medium	Medium	Dead branches	Transplant	Falls within footprint of proposed works	LCSD
T014	Unidentified tree	-	0.200	11.5	6.0	Poor	Poor	Low	Low	Bark damage, deformed crown	Transplant	Falls within footprint of proposed works	DSD
T015	Unidentified tree	-	0.270	12.0	5.5	Fair	Fair	Medium	Medium	-	Transplant	Falls within footprint of proposed works	LCSD
T016	<i>Lagerstroemia speciosa</i>	大花紫薇	0.120	7.0	6.5	Fair	Fair	Medium	High	-	Transplant	Falls within footprint of proposed works	LCSD
T062	<i>Macaranga tanarius</i>	血桐	0.150	5.0	6.0	Fair	Fair	Low	Medium	Broken bark	Retain	No conflict with proposed works	LCSD
T063	<i>Macaranga tanarius</i>	血桐	0.120	5.0	5.0	Fair	Poor	Low	Medium	Broken bark & broken branch	Retain	No conflict with proposed works	LCSD
T064	<i>Delonix regia</i>	鳳凰木	0.400	12.0	10.0	Fair	Poor	Low	High	Curved trunk	Retain	No conflict with proposed works	LCSD
T065	<i>Delonix regia</i>	鳳凰木	0.200	10.0	8.0	Fair	Poor	Low	Medium	Curved trunk & broken branch	Retain	No conflict with proposed works	LCSD
T066	<i>Bombax ceiba</i>	木棉	0.300	14.0	6.0	Fair	Fair	Medium	Medium	Yellow leaves	Retain	No conflict with proposed works	LCSD
T067	<i>Macaranga tanarius</i>	血桐	0.280	6.0	9.0	Fair	Poor	Low	Medium	Broken branch	Retain	No conflict with proposed works	LCSD
T068	<i>Terminalia catappa</i>	欖仁樹	0.500	6.0	8.0	Fair	Poor	Low	Medium	Leaning, yellow leaves	Retain	No conflict with proposed works	LCSD
T069	<i>Acacia confusa</i>	臺灣相思	0.380	8.0	7.0	Fair	Poor	Low	Medium	Leaning, broken branch	Retain	No conflict with proposed works	LCSD

* LCSD - Leisure and Cultural Services Department

PTW - Cyberport
Tree Assessment Schedule

Date of Survey: 12 Oct 2006 &
25 Jan 2007

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T008	<i>Lagerstroemia speciosa</i>	大花紫薇	0.900	3.5	2.5	Fair	Poor	Low	Medium	Leaning	Transplant	Falls within footprint of proposed works	LCSD
T015	<i>Archontophoenix alexandrae</i>	假檳榔	0.150	4.5	1.8	Fair	Fair	Low	Medium	-	Transplant	Falls within footprint of proposed works	LCSD
T016	<i>Archontophoenix alexandrae</i>	假檳榔	0.150	5.0	1.8	Fair	Fair	Low	Medium	-	Transplant	Falls within footprint of proposed works	LCSD
T017	<i>Archontophoenix alexandrae</i>	假檳榔	0.150	4.8	1.6	Fair	Fair	Low	Medium	-	Transplant	Falls within footprint of proposed works	LCSD
T048	<i>Mangifera indica</i>	芒果	0.100	4.0	2.2	Good	Fair	Medium	High	-	Transplant	Falls within proposed work area	LCSD
T049	<i>Terminalia boivinii</i>	細葉欖仁	0.180	8.0	4.0	Fair	Fair	Medium	Medium	Cut branch	Transplant	Falls within proposed work area	LCSD
T050	<i>Terminalia boivinii</i>	細葉欖仁	0.200	8.0	3.0	Poor	Fair	Medium	Low	-	Transplant	Falls within proposed work area	LCSD
T051	<i>Terminalia boivinii</i>	細葉欖仁	0.250	8.0	4.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
T052	<i>Terminalia boivinii</i>	細葉欖仁	0.200	8.0	4.0	Fair	Poor	Low	Medium	Leaning, cut branch	Transplant	Falls within proposed work area	LCSD
T053	<i>Terminalia boivinii</i>	細葉欖仁	0.250	7.0	4.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
T054	<i>Terminalia boivinii</i>	細葉欖仁	0.210	9.0	5.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
T055	<i>Terminalia boivinii</i>	細葉欖仁	0.190	8.5	4.0	Fair	Fair	Medium	Medium	Cut branch	Transplant	Falls within proposed work area	LCSD
T056	<i>Terminalia boivinii</i>	細葉欖仁	0.210	8.5	4.0	Fair	Fair	Medium	Medium	Cut branch	Transplant	Falls within proposed work area	LCSD
T057	<i>Terminalia boivinii</i>	細葉欖仁	0.210	9.0	4.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
T058	<i>Terminalia boivinii</i>	細葉欖仁	0.180	7.5	4.0	Fair	Poor	Low	Medium	Curved trunk	Transplant	Falls within proposed work area	LCSD
T059	<i>Terminalia boivinii</i>	細葉欖仁	0.170	8.5	3.0	Fair	Fair	Medium	Medium	Yellow leaves, cut branch	Transplant	Falls within proposed work area	LCSD
T060	<i>Terminalia boivinii</i>	細葉欖仁	0.220	8.5	3.5	Fair	Fair	Medium	Medium	Cut branch	Transplant	Falls within proposed work area	LCSD
T061	<i>Terminalia boivinii</i>	細葉欖仁	0.230	8.5	4.0	Fair	Fair	Medium	Medium	Cut branch	Transplant	Falls within proposed work area	LCSD
T062	<i>Terminalia boivinii</i>	細葉欖仁	0.220	8.5	3.5	Fair	Fair	Medium	Medium	Cut branch	Transplant	Falls within proposed work area	LCSD

* LCSD - Leisure and Cultural Services Department

PTW - Wah Fu
Tree Assessment Schedule

Date of Survey: 17-Oct-06

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T001	<i>Ficus elastica</i>	印度榕	0.900	17.0	14.0	Fair	Fair	Medium	Medium	-	Retain	No conflict with proposed works but branches spread into PTW boundary will be pruned	LCSD
T002	<i>Citrus maxima</i>	柚	0.120	4.5	2.5	Fair	Fair	Medium	High	Potted Plant	Retain	No conflict with proposed works	LCSD
T003	<i>Macaranga tanarius</i>	血桐	0.120	7.0	5.0	Poor	Poor	Low	Low	Deformed crown, leaning, dead branches	Retain	No conflict with proposed works	LCSD
T004	<i>Ficus elastica</i>	印度榕	0.900	18.0	17.0	Fair	Fair	Medium	Low	Broken branches, forked, roots grown on concrete	Retain	No conflict with proposed works	LCSD

* LCSD - Leisure and Cultural Services Department

PTW - Aberdeen
Tree Assessment Schedule

Date of Survey: 17-Oct-06

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T001	<i>Acacia confusa</i>	臺灣相思	0.500	10.0	10.0	Fair	Fair	Medium	Medium	Bark damage, broken branches, forked	Transplant	Falls within proposed work area	LCSD
T002	<i>Acacia confusa</i>	臺灣相思	0.200	5.1	5.5	Poor	Poor	Low	Low	Broken leading shoot, suppressed growth	Transplant	Falls within proposed work area	LCSD
T003	<i>Ficus microcarpa</i>	細葉榕	0.700	8.0	6.0	Fair	Poor	Low	Medium	Forked, deformed crown	Transplant	Falls within footprint of proposed works	LCSD
T004	<i>Psidium guajava</i>	番石榴	0.400	6.0	2.5	Poor	Fair	Low	Low	Yellow leaves	Transplant	Falls within footprint of proposed works	LCSD
T005	<i>Michelia alba</i>	白蘭	0.200	7.0	3.0	Fair	Fair	Low	Medium	Broken branches, densely grown with T004	Transplant	Falls within footprint of proposed works	LCSD
T008	<i>Macaranga tanarius</i>	血桐	0.200	4.0	3.0	Poor	Poor	Low	Low	Bark damage, deformed crown	Transplant	Falls within footprint of proposed works	LCSD
T009	<i>Dimocarpus longan</i>	龍眼	0.200	4.6	3.3	Fair	Fair	Medium	Medium	Forked	Transplant	Falls within footprint of proposed works	LCSD
T010	<i>Acacia confusa</i>	臺灣相思	0.500	10.5	6.0	Fair	Poor	Low	Medium	Deformed crown	Retain	No conflict with proposed works	LCSD
T011	<i>Acacia confusa</i>	臺灣相思	0.400	12.0	4.0	Fair	Poor	Low	Medium	Forked, curved trunk, bark damage	Retain	No conflict with proposed works	LCSD
T012	<i>Ficus elastica</i>	印度榕	0.400	3.3	2.7	Poor	Poor	Low	Low	Bark damage, deformed crown	Retain	No conflict with proposed works	LCSD
T013	<i>Acacia confusa</i>	臺灣相思	0.300	6.5	2.0	Poor	Poor	Low	Low	Almost dead	Retain	No conflict with proposed works	LCSD
T014	<i>Acacia confusa</i>	臺灣相思	0.300	7.5	3.0	Fair	Poor	Low	Medium	Curved trunk	Retain	No conflict with proposed works	LCSD
T015	<i>Acacia confusa</i>	臺灣相思	0.350	10.0	4.0	Poor	Poor	Low	Low	Leaning, bark damage	Retain	No conflict with proposed works	LCSD
T016	<i>Acacia confusa</i>	臺灣相思	0.300	9.0	2.5	Fair	Poor	Low	Medium	Deformed crown	Retain	No conflict with proposed works	LCSD
T017	<i>Acacia confusa</i>	臺灣相思	0.350	8.5	5.0	Poor	Fair	Low	Low	Bark damage, broken branches	Retain	No conflict with proposed works	LCSD
T018	<i>Artocarpus macrocarpon</i>	菠蘿蜜	0.350	5.0	2.0	Good	Fair	Medium	High	-	Transplant	Falls within footprint of proposed works	LCSD
T023	<i>Ficus microcarpa</i>	細葉榕	0.950	11.0	6.0	Fair	Poor	Low	Medium	Leaning	Transplant	Falls within footprint of proposed works	LCSD
T026	<i>Ficus microcarpa</i>	細葉榕	1.500	12.0	14.0	Good	Good	High	Medium	-	Transplant	Falls within footprint of proposed works	LCSD
T029	<i>Michelia alba</i>	白蘭	0.150	7.0	3.0	Fair	Fair	Medium	Medium	Broken branches	Transplant	Falls within footprint of proposed works	LCSD
T030	<i>Caryota ochlandra</i>	魚尾葵	0.150	4.0	2.5	Poor	Poor	Low	Low	Yellow leaves	Transplant	Falls within footprint of proposed works	LCSD
T031	<i>Caryota ochlandra</i>	魚尾葵	0.150	5.0	2.0	Poor	Poor	Low	Low	Suppressed growth	Transplant	Falls within footprint of proposed works	LCSD
T032	<i>Caryota ochlandra</i>	魚尾葵	0.150	6.0	3.0	Fair	Fair	Low	High	-	Transplant	Falls within footprint of proposed works	LCSD
T036	<i>Caryota ochlandra</i>	魚尾葵	0.200	6.0	3.0	Poor	Fair	Low	Low	Yellow leaves	Transplant	Falls within footprint of proposed works	LCSD
T037	<i>Araucaria heterophylla</i>	南洋杉	0.150	6.0	3.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within footprint of proposed works	LCSD
T038	<i>Araucaria heterophylla</i>	南洋杉	0.150	5.5	2.5	Fair	Poor	Low	Medium	Leaning	Transplant	Falls within footprint of proposed works	LCSD
T039	<i>Araucaria heterophylla</i>	南洋杉	0.150	6.0	2.5	Fair	Good	Medium	Medium	-	Transplant	Falls within footprint of proposed works	LCSD
T040	<i>Araucaria heterophylla</i>	南洋杉	0.120	6.0	2.0	Poor	Poor	Low	Low	Suppressed growth	Transplant	Falls within footprint of proposed works	LCSD
T041	<i>Araucaria heterophylla</i>	南洋杉	0.120	6.0	2.0	Poor	Poor	Low	Low	Suppressed growth	Transplant	Falls within footprint of proposed works	LCSD
T042	<i>Ficus microcarpa</i>	細葉榕	0.150	3.5	3.0	Fair	Poor	Low	Medium	Grown on seawall, deformed crown	Retain	No conflict with proposed works	LCSD

PTW - Aberdeen
Tree Assessment Schedule

Date of Survey: 17-Oct-06

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T043	<i>Ficus microcarpa</i>	細葉榕	0.400	4.0	8.0	Fair	Poor	Low	Medium	Grown on seawall, deformed crown, multi-trunk	Retain	No conflict with proposed works	LCSD
T044	<i>Ficus microcarpa</i>	細葉榕	0.200	2.5	3.0	Fair	Poor	Low	Medium	Grown on seawall, multi-trunk	Retain	No conflict with proposed works	LCSD
T045	<i>Ficus microcarpa</i>	細葉榕	0.300	2.5	3.0	Fair	Poor	Low	Medium	Grown on seawall, multi-trunk	Retain	No conflict with proposed works	LCSD
T050	<i>Leucaena leucocephala</i>	銀合歡	0.110	6.0	3.0	Poor	Poor	Low	Low	Deformed crown	Retain	No conflict with proposed works	LCSD
T051	<i>Macaranga tanarius</i>	血桐	0.100	4.0	4.0	Fair	Fair	Low	Medium	Multi-trunk	Retain	No conflict with proposed works	LCSD
T056	<i>Leucaena leucocephala</i>	銀合歡	0.250	6.0	6.0	Poor	Poor	Low	Low	Forked, dead branches	Retain	No conflict with proposed works	LCSD
T057	<i>Leucaena leucocephala</i>	銀合歡	0.150	6.0	5.0	Poor	Poor	Low	Low	Leaning	Retain	No conflict with proposed works	LCSD
T058	<i>Broussonetia papyrifera</i>	構樹	0.500	8.0	6.0	Fair	Poor	Low	Medium	Multi-trunk, crossing branches	Retain	No conflict with proposed works	LCSD
T059	<i>Leucaena leucocephala</i>	銀合歡	0.100	6.0	4.0	Poor	Poor	Low	Low	Leaning	Retain	No conflict with proposed works	LCSD
T061	<i>Leucaena leucocephala</i>	銀合歡	0.100	6.0	3.0	Fair	Poor	Low	Medium	Deformed crown	Retain	No conflict with proposed works	LCSD
T070	<i>Leucaena leucocephala</i>	銀合歡	0.100	5.0	3.0	Fair	Fair	Low	Medium	-	Retain	No conflict with proposed works	LCSD
T074	<i>Macaranga tanarius</i>	血桐	0.150	3.0	2.0	Poor	Poor	Low	Low	Climber grown on tree	Retain	No conflict with proposed works	LCSD
T076	<i>Leucaena leucocephala</i>	銀合歡	0.100	4.0	3.0	Poor	Poor	Low	Low	Climber grown on tree	Retain	No conflict with proposed works	LCSD
T082	<i>Caryota ochlandra</i>	魚尾葵	0.150	2.5	1.0	Fair	Fair	Low	High	-	Transplant	Falls within footprint of proposed works	LCSD
T083	<i>Caryota ochlandra</i>	魚尾葵	0.150	6.0	3.0	Poor	Poor	Low	Low	Dead branches	Transplant	Falls within footprint of proposed works	LCSD
T084	<i>Caryota ochlandra</i>	魚尾葵	0.100	6.0	2.0	Fair	Fair	Low	High	-	Transplant	Falls within footprint of proposed works	LCSD
T085	<i>Caryota ochlandra</i>	魚尾葵	0.100	4.5	2.0	Fair	Fair	Low	High	-	Transplant	Falls within footprint of proposed works	LCSD
T086	<i>Caryota ochlandra</i>	魚尾葵	0.200	5.0	3.0	Poor	Poor	Low	Low	Climber overgrown, deformed crown	Transplant	Falls within footprint of proposed works	LCSD
T087	<i>Caryota ochlandra</i>	魚尾葵	0.150	5.0	1.5	Fair	Fair	Low	High	-	Transplant	Falls within footprint of proposed works	LCSD
T088	<i>Caryota ochlandra</i>	魚尾葵	0.500	1.1	1.0	Poor	Poor	Low	Low	Dead leading shoot	Transplant	Falls within footprint of proposed works	LCSD
T089	<i>Caryota ochlandra</i>	魚尾葵	0.400	1.6	0.8	Poor	Poor	Low	Low	Very poor health condition	Transplant	Falls within footprint of proposed works	LCSD
T090	<i>Caryota ochlandra</i>	魚尾葵	0.150	3.0	2.0	Fair	Poor	Low	Medium	Some dead leaves, densely grow with other trees	Transplant	Falls within footprint of proposed works	LCSD
T091	<i>Caryota ochlandra</i>	魚尾葵	0.150	8.0	3.0	Fair	Poor	Low	Medium	Some dead leaves, densely grow with other trees	Transplant	Falls within footprint of proposed works	LCSD
T092	<i>Caryota ochlandra</i>	魚尾葵	0.100	5.0	2.0	Fair	Poor	Low	Medium	Some dead leaves, densely grow with other trees	Transplant	Falls within footprint of proposed works	LCSD

* LCSD - Leisure and Cultural Services Department

PTW - Ap Lei Chau
Tree Assessment Schedule

Date of Survey: 17-Oct-06

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T001	<i>Plumeria rubra</i>	紅雞蛋花	0.350	5.0	4.5	Fair	Fair	Medium	Medium	Forked	Transplant	Falls within footprint of proposed works	LCSD
T003	<i>Archontophoenix alexandrae</i>	假檳榔	0.100	3.0	2.0	Fair	Fair	Low	High	-	Transplant	Falls within footprint of proposed works	LCSD
T004	<i>Archontophoenix alexandrae</i>	假檳榔	0.120	3.0	2.0	Fair	Fair	Low	High	-	Transplant	Falls within footprint of proposed works	LCSD
T005	<i>Archontophoenix alexandrae</i>	假檳榔	0.120	3.0	2.0	Fair	Fair	Low	High	-	Transplant	Falls within footprint of proposed works	LCSD
T006	<i>Archontophoenix alexandrae</i>	假檳榔	0.100	2.5	2.0	Fair	Fair	Low	High	-	Transplant	Falls within footprint of proposed works	LCSD

* LCSD - Leisure and Cultural Services Department

SCISTW
Tree Assessment Schedule

20-21 &
Date of Survey: 24 Nov 2006

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
SCT001	<i>Araucaria heterophylla</i>	南洋杉	0.120	7.0	1.5	Fair	Fair	Low	High	Curved trunk	Retain	No conflict with proposed works	LCSD
SCT002	<i>Araucaria heterophylla</i>	南洋杉	0.150	7.0	2.0	Fair	Fair	Low	High	Leaning	Retain	No conflict with proposed works	LCSD
SCT003	<i>Araucaria heterophylla</i>	南洋杉	0.130	7.0	2.0	Good	Good	Medium	High	-	Retain	No conflict with proposed works	LCSD
SCT004	<i>Araucaria heterophylla</i>	南洋杉	0.150	7.0	1.5	Fair	Fair	Low	High	-	Retain	No conflict with proposed works	LCSD
SCT005	<i>Araucaria heterophylla</i>	南洋杉	0.140	7.0	1.5	Fair	Fair	Low	High	-	Retain	No conflict with proposed works	LCSD
SCT006	<i>Araucaria heterophylla</i>	南洋杉	0.150	7.0	2.0	Fair	Fair	Low	High	Leaning	Retain	No conflict with proposed works	LCSD
SCT007	<i>Araucaria heterophylla</i>	南洋杉	0.160	7.0	2.0	Fair	Fair	Medium	High	-	Retain	No conflict with proposed works	LCSD
SCT008	<i>Araucaria heterophylla</i>	南洋杉	0.150	7.0	1.8	Fair	Fair	Low	High	-	Retain	No conflict with proposed works	LCSD
SCT019	<i>Bauhinia blakeana</i>	洋紫荆	0.130	4.5	3.0	Fair	Fair	Low	Medium	Forked, yellow leaves	Retain	No conflict with proposed works	LCSD
SCT020	<i>Bauhinia blakeana</i>	洋紫荆	0.180	9.0	5.0	Fair	Fair	Low	Medium	Forked, yellow leaves	Retain	No conflict with proposed works	LCSD
SCT021	<i>Bauhinia blakeana</i>	洋紫荆	0.140	7.0	3.0	Fair	Poor	Low	Medium	Curved trunk	Retain	No conflict with proposed works	LCSD
SCT022	<i>Bauhinia blakeana</i>	洋紫荆	0.140	4.5	3.0	Poor	Poor	Low	Low	Yellow leaves, leaning	Retain	No conflict with proposed works	LCSD
SCT023	<i>Aleurites moluccana</i>	石栗	0.200	8.0	6.0	Good	Poor	Low	High	Forked, broken branch	Retain	No conflict with proposed works	LCSD
SCT024	<i>Aleurites moluccana</i>	石栗	0.200	7.8	5.0	Fair	Poor	Low	Medium	Dead branch	Retain	No conflict with proposed works	LCSD
SCT025	<i>Cassia siamea</i>	鐵刀木	0.160	5.5	5.0	Fair	Fair	Low	Medium	Leaning, dead branch	Retain	No conflict with proposed works	LCSD
SCT026	<i>Cassia siamea</i>	鐵刀木	0.290	9.0	6.0	Fair	poor	Low	Medium	Curved trunk	Retain	No conflict with proposed works	LCSD
SCT027	<i>Cassia siamea</i>	鐵刀木	0.250	9.0	6.0	Fair	Fair	Low	Medium	Curved trunk, dead branch	Retain	No conflict with proposed works	LCSD
SCT028	<i>Cassia siamea</i>	鐵刀木	0.280	7.0	6.0	Fair	Poor	Low	Medium	Forked, broken branch, leaning	Retain	No conflict with proposed works	LCSD
SCT029	<i>Cassia siamea</i>	鐵刀木	0.190	7.0	6.0	Fair	Poor	Low	Medium	Curved trunk, broken branch	Retain	No conflict with proposed works	LCSD
SCT030	<i>Ficus microcarpa</i>	細葉榕	0.260	4.0	4.0	Fair	Fair	Medium	Medium	-	Retain	No conflict with proposed works	LCSD
SCT031	<i>Terminalia boivinii</i>	細葉欖仁	0.200	10.0	6.0	Good	Good	High	Medium	-	Retain	No conflict with proposed works	LCSD
SCT032	<i>Aleurites moluccana</i>	石栗	0.190	9.0	5.0	Fair	Fair	Low	Medium	Broken branch, forked	Retain	No conflict with proposed works	LCSD
SCT033	<i>Aleurites moluccana</i>	石栗	0.240	9.0	5.0	Good	Fair	Medium	Medium	Broken branch	Retain	No conflict with proposed works	LCSD
SCT034	<i>Aleurites moluccana</i>	石栗	0.220	9.0	5.0	Fair	Poor	Low	Medium	Dead and broken branch, forked	Retain	No conflict with proposed works	LCSD
SCT035	<i>Ficus microcarpa</i>	細葉榕	0.400	10.0	6.0	Good	Good	High	Medium	-	Retain	No conflict with proposed works	LCSD
SCT036	<i>Ficus microcarpa</i>	細葉榕	0.300	10.0	6.0	Good	Fair	Medium	Medium	Broken branch	Retain	No conflict with proposed works	LCSD

SCISTW
Tree Assessment Schedule

20-21 &
Date of Survey: 24 Nov 2006

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
SCT037	<i>Ficus microcarpa</i>	細葉榕	0.290	10.0	7.0	Good	Good	High	High	-	Transplant	Falls within footprint of proposed works	LCSD
SCT038	<i>Ficus microcarpa</i>	細葉榕	0.220	10.0	7.0	Good	Fair	Medium	High	-	Transplant	Falls within footprint of proposed works	LCSD
SCT039	<i>Ficus microcarpa</i>	細葉榕	0.300	10.0	7.0	Good	Fair	Medium	High	Cut trunk	Transplant	Falls within footprint of proposed works	LCSD
SCT040	<i>Mangifera indica</i>	芒果	0.110	5.0	3.0	Fair	Fair	Medium	High	Curved trunk	Retain	No conflict with proposed works	LCSD
SCT041	<i>Mangifera indica</i>	芒果	0.110	5.5	3.5	Good	Good	High	High	-	Retain	No conflict with proposed works	LCSD
SCT042	<i>Mangifera indica</i>	芒果	0.110	5.5	3.5	Good	Good	High	High	-	Retain	No conflict with proposed works	LCSD
SCT043	<i>Mangifera indica</i>	芒果	0.110	5.5	3.5	Fair	Fair	Medium	High	-	Retain	No conflict with proposed works	LCSD
SCT044	<i>Mangifera indica</i>	芒果	0.110	5.5	3.5	Good	Good	High	High	-	Retain	No conflict with proposed works	LCSD
SCT045	<i>Mangifera indica</i>	芒果	0.110	5.5	3.0	Good	Good	High	High	-	Retain	No conflict with proposed works	LCSD
SCT047	<i>Mangifera indica</i>	芒果	0.110	5.0	3.0	Good	Good	High	High	-	Retain	No conflict with proposed works	LCSD
SCT048	<i>Mangifera indica</i>	芒果	0.110	3.0	3.0	Fair	Fair	Medium	High	-	Retain	No conflict with proposed works	LCSD
SCT051	<i>Mangifera indica</i>	芒果	0.110	3.5	3.5	Good	Fair	Medium	High	-	Retain	No conflict with proposed works	LCSD
SCT053	<i>Ficus microcarpa</i>	細葉榕	0.290	4.0	4.5	Fair	Fair	Medium	Medium	-	Retain	No conflict with proposed works	LCSD
SCT054	<i>Ficus microcarpa</i>	細葉榕	0.190	4.5	4.5	Fair	Fair	Medium	Medium	Yellow leaves	Retain	No conflict with proposed works	LCSD
SCT055	<i>Ficus microcarpa</i>	細葉榕	0.250	5.0	4.5	Good	Good	High	Medium	-	Retain	No conflict with proposed works	LCSD
SCT056	<i>Bauhinia blakeana</i>	洋紫荊	0.240	7.0	6.0	Fair	Poor	Low	Medium	Dead branch, yellow leaves, leaning	Retain	No conflict with proposed works	LCSD
SCT057	<i>Bauhinia blakeana</i>	洋紫荊	0.170	8.0	7.0	Fair	Fair	Low	Medium	Broken branch, forked, yellow leaves	Retain	No conflict with proposed works	LCSD
SCT058	<i>Ficus microcarpa</i>	細葉榕	0.250	5.0	5.0	Good	Good	High	High	-	Transplant	Falls within footprint of proposed works	LCSD
SCT059	<i>Ficus microcarpa</i>	細葉榕	0.394	6.0	5.0	Good	Good	High	High	-	Transplant	Falls within footprint of proposed works	LCSD
SCT060	<i>Celtis sinensis</i>	朴樹	0.180	5.5	6.0	Poor	Fair	Low	Low	Yellow leaves	Transplant	Falls within footprint of proposed works	LCSD
SCT061	<i>Celtis sinensis</i>	朴樹	0.220	6.0	5.0	Poor	Fair	Low	Low	Yellow leaves	Transplant	Falls within footprint of proposed works	LCSD
SCT062	<i>Celtis sinensis</i>	朴樹	0.200	6.5	6.0	Poor	Fair	Low	Low	Yellow leaves	Transplant	Falls within footprint of proposed works	LCSD
SCT063	<i>Celtis sinensis</i>	朴樹	0.200	6.5	6.0	Poor	Fair	Low	Low	Yellow leaves	Transplant	Falls within footprint of proposed works	LCSD
SCT064	<i>Aleurites moluccana</i>	石栗	0.180	6.5	5.0	Fair	Poor	Low	Medium	Deformed crown	Retain	No conflict with proposed works	LCSD
SCT065	<i>Aleurites moluccana</i>	石栗	0.180	7.0	6.0	Fair	Fair	Medium	Medium	-	Retain	No conflict with proposed works	LCSD
SCT066	<i>Aleurites moluccana</i>	石栗	0.130	7.0	5.0	Fair	Fair	Low	Medium	-	Retain	No conflict with proposed works	LCSD
SCT067	<i>Aleurites moluccana</i>	石栗	0.180	7.5	5.0	Fair	Fair	Low	Medium	Dead branch	Retain	No conflict with proposed works	LCSD
SCT068	<i>Acacia confusa</i>	臺灣相思	0.095	5.5	3.0	Fair	Poor	Low	Medium	Curved trunk	Transplant	Falls within proposed work area	LCSD
SCT069	<i>Acacia confusa</i>	臺灣相思	0.095	5.5	4.0	Fair	Poor	Low	Medium	Curved trunk	Transplant	Falls within proposed work area	LCSD

SCISTW
Tree Assessment Schedule

20-21 &
Date of Survey: 24 Nov 2006

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
SCT070	<i>Acacia confusa</i>	臺灣相思	0.100	5.0	3.0	Fair	Fair	Medium	Medium	Forked	Transplant	Falls within proposed work area	LCSD
SCT071	<i>Acacia confusa</i>	臺灣相思	0.100	5.0	3.0	Fair	Fair	Medium	Medium	Forked	Transplant	Falls within proposed work area	LCSD
SCT072	<i>Acacia confusa</i>	臺灣相思	0.095	4.7	3.0	Fair	Fair	Medium	Medium	Forked	Transplant	Falls within proposed work area	LCSD
SCT073	<i>Acacia confusa</i>	臺灣相思	0.100	5.0	3.0	Fair	Fair	Medium	Medium	Forked, dead branch	Transplant	Falls within proposed work area	LCSD
SCT074	<i>Acacia confusa</i>	臺灣相思	0.100	4.5	3.0	Fair	Fair	Medium	Medium	Forked, dead branch	Transplant	Falls within proposed work area	LCSD
SCT075	<i>Acacia confusa</i>	臺灣相思	0.100	4.5	3.0	Fair	Poor	Low	Medium	Forked, dead branch, leaning	Transplant	Falls within proposed work area	LCSD
SCT076	<i>Acacia confusa</i>	臺灣相思	0.110	5.0	3.0	Fair	Poor	Low	Medium	Curved trunk	Transplant	Falls within proposed work area	LCSD
SCT077	<i>Acacia confusa</i>	臺灣相思	0.100	5.0	3.0	Fair	Fair	Medium	Medium	Forked	Transplant	Falls within proposed work area	LCSD
SCT078	<i>Acacia confusa</i>	臺灣相思	0.095	4.5	4.0	Fair	Fair	Medium	Medium	Forked, dead branch	Transplant	Falls within proposed work area	LCSD
SCT079	<i>Acacia confusa</i>	臺灣相思	0.100	5.0	3.5	Fair	Fair	Medium	Medium	Forked	Transplant	Falls within proposed work area	LCSD
SCT080	<i>Acacia confusa</i>	臺灣相思	0.120	5.5	4.5	Fair	poor	Low	Medium	Leaning	Transplant	Falls within proposed work area	LCSD
SCT081	<i>Acacia confusa</i>	臺灣相思	0.140	5.0	3.0	Fair	Fair	Low	Medium	Forked, leaning	Transplant	Falls within proposed work area	LCSD
SCT082	<i>Acacia confusa</i>	臺灣相思	0.130	6.0	4.0	Fair	Fair	Low	Medium	Forked	Transplant	Falls within proposed work area	LCSD
SCT083	<i>Acacia confusa</i>	臺灣相思	0.130	6.0	4.0	Fair	Poor	Low	Medium	Forked, curved trunk	Transplant	Falls within proposed work area	LCSD
SCT084	<i>Acacia confusa</i>	臺灣相思	0.095	5.0	2.0	Fair	Fair	Medium	Medium	Forked	Transplant	Falls within proposed work area	LCSD
SCT085	<i>Acacia confusa</i>	臺灣相思	0.120	5.0	4.0	Fair	Poor	Low	Medium	Angled trunk	Transplant	Falls within proposed work area	LCSD
SCT086	<i>Acacia confusa</i>	臺灣相思	0.100	4.8	3.0	Fair	Fair	Medium	Medium	Leaning	Transplant	Falls within proposed work area	LCSD
SCT087	<i>Acacia confusa</i>	臺灣相思	0.100	4.5	2.5	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT088	<i>Acacia confusa</i>	臺灣相思	0.120	5.5	4.5	Fair	Fair	Medium	Medium	Curved trunk	Transplant	Falls within proposed work area	LCSD
SCT089	<i>Acacia confusa</i>	臺灣相思	0.110	5.5	4.0	Fair	Fair	Medium	Medium	Forked	Transplant	Falls within proposed work area	LCSD
SCT090	<i>Acacia confusa</i>	臺灣相思	0.100	5.0	4.0	Fair	Fair	Medium	Medium	Forked	Transplant	Falls within proposed work area	LCSD
SCT091	<i>Acacia confusa</i>	臺灣相思	0.095	5.0	2.5	Fair	Poor	Low	Medium	Forked	Transplant	Falls within proposed work area	LCSD
SCT092	<i>Hibiscus tiliaceus</i>	黃槿	0.190	5.0	6.0	Fair	Fair	Low	Medium	Leaning	Transplant	Falls within proposed work area	LCSD
SCT093	<i>Acacia confusa</i>	臺灣相思	0.095	4.5	2.5	Fair	Fair	Medium	Medium	Curved trunk	Transplant	Falls within proposed work area	LCSD
SCT094	<i>Ficus virens</i>	黃葛樹	0.238	6.0	5.0	Fair	Poor	Low	Medium	Forked	Transplant	Falls within proposed work area	LCSD
SCT095	<i>Ficus virens</i>	黃葛樹	0.403	5.0	7.0	Fair	Poor	Low	Medium	Multi-trunk	Transplant	Falls within proposed work area	LCSD
SCT096	<i>Ficus microcarpa</i>	細葉榕	0.286	5.0	5.0	Fair	Fair	Low	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT097	<i>Ficus virens</i>	黃葛樹	0.120	4.5	4.0	Fair	poor	Low	Medium	Forked, leaning	Transplant	Falls within proposed work area	LCSD
SCT098	<i>Ficus virens</i>	黃葛樹	0.214	4.5	5.0	Fair	Fair	Low	Medium	Forked	Transplant	Falls within proposed work area	LCSD

SCISTW
Tree Assessment Schedule

20-21 &
Date of Survey: 24 Nov 2006

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
SCT099	<i>Ficus microcarpa</i>	細葉榕	0.552	5.0	4.0	Fair	Fair	Low	Medium	multi-trunk	Transplant	Falls within proposed work area	LCSD
SCT100	<i>Ficus virens</i>	黃葛樹	0.176	4.0	5.0	Fair	poor	Low	Medium	forked	Transplant	Falls within proposed work area	LCSD
SCT101	<i>Cinnamomum camphora</i>	樟	0.200	5.3	6.0	Fair	Fair	Low	Medium	leaning	Retain	No conflict with proposed works	LCSD
SCT102	<i>Aleurites moluccana</i>	石栗	0.220	8.0	6.0	Good	Fair	Medium	Medium	-	Retain	No conflict with proposed works	LCSD
SCT103	<i>Aleurites moluccana</i>	石栗	0.230	7.2	6.0	Good	Fair	Low	Medium	forked	Retain	No conflict with proposed works	LCSD
SCT104	<i>Aleurites moluccana</i>	石栗	0.220	8.1	6.0	Good	Poor	Low	Medium	forked	Retain	No conflict with proposed works	LCSD
SCT105	<i>Aleurites moluccana</i>	石栗	0.230	7.4	8.0	Good	Fair	Medium	Medium	-	Retain	No conflict with proposed works	LCSD
SCT106	<i>Aleurites moluccana</i>	石栗	0.180	5.8	6.0	Good	Fair	Medium	Medium	leaning	Retain	No conflict with proposed works	LCSD
SCT107	<i>Cinnamomum burmannii</i>	陰香	0.220	7.5	6.0	Good	Fair	Medium	Medium	-	Retain	No conflict with proposed works	LCSD
SCT108	<i>Aleurites moluccana</i>	石栗	0.220	8.5	6.0	Good	Fair	Low	Medium	forked	Retain	No conflict with proposed works	LCSD
SCT109	<i>Aleurites moluccana</i>	石栗	0.150	6.6	5.0	Good	Fair	Low	Medium	forked	Retain	No conflict with proposed works	LCSD
SCT110	<i>Cinnamomum camphora</i>	樟	0.150	6.1	5.0	Fair	Fair	Low	Medium	leaning	Retain	No conflict with proposed works	LCSD
SCT111	<i>Cinnamomum burmannii</i>	陰香	0.150	4.6	4.0	Fair	Fair	Medium	Medium	-	Retain	No conflict with proposed works	LCSD
SCT112	<i>Cinnamomum camphora</i>	樟	0.180	5.6	5.0	Fair	Fair	Medium	Medium	curved trunk	Retain	No conflict with proposed works	LCSD
SCT113	<i>Cinnamomum burmannii</i>	陰香	0.150	5.3	4.0	Fair	Good	High	Medium	-	Transplant	Falls within footprint of proposed works	LCSD
SCT114	<i>Cinnamomum camphora</i>	樟	0.150	4.6	4.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within footprint of proposed works	LCSD
SCT115	<i>Albizia lebbek</i>	大葉合歡	0.190	6.9	4.0	Poor	Fair	Low	Low	dead branch	Transplant	Falls within footprint of proposed works	LCSD
SCT116	<i>Albizia lebbek</i>	大葉合歡	0.200	8.9	13.0	Fair	Poor	Low	Medium	leaning	Transplant	Falls within footprint of proposed works	LCSD
SCT117	<i>Bauhinia blakeana</i>	洋紫荊	0.170	5.8	6.0	Fair	Poor	Low	Medium	broken branch, curved trunk	Transplant	Falls within footprint of proposed works	LCSD
SCT118	<i>Bauhinia blakeana</i>	洋紫荊	0.180	6.5	6.0	Fair	Poor	Low	Medium	broken branch, curved trunk	Transplant	Falls within footprint of proposed works	LCSD
SCT119	<i>Albizia lebbek</i>	大葉合歡	0.280	8.8	10.0	Fair	Fair	Medium	Medium	broken branch	Transplant	Falls within footprint of proposed works	LCSD
SCT120	<i>Albizia lebbek</i>	大葉合歡	0.220	12.5	12.0	Fair	Fair	Medium	Medium	broken branch	Transplant	Falls within footprint of proposed works	LCSD
SCT121	<i>Albizia lebbek</i>	大葉合歡	0.180	8.4	8.0	Fair	poor	Low	Medium	broken branch	Retain	No conflict with proposed works	LCSD
SCT122	<i>Albizia lebbek</i>	大葉合歡	0.230	8.7	9.0	Fair	Fair	Low	Medium	broken branch	Retain	No conflict with proposed works	LCSD
SCT123	<i>Ficus microcarpa</i>	細葉榕	0.280	6.2	6.0	Good	Good	High	High	-	Retain	No conflict with proposed works	LCSD
SCT124	<i>Cinnamomum camphora</i>	樟	0.120	4.9	4.0	Fair	Fair	Medium	Medium	-	Retain	No conflict with proposed works	LCSD
SCT125	<i>Cinnamomum camphora</i>	樟	0.200	6.4	6.0	Fair	Fair	Medium	Medium	-	Retain	No conflict with proposed works	LCSD
SCT126	<i>Cinnamomum burmannii</i>	陰香	0.230	6.6	6.0	Good	Fair	Medium	Medium	-	Retain	No conflict with proposed works	LCSD
SCT127	<i>Cinnamomum camphora</i>	樟	0.130	5.1	6.0	Fair	Fair	Medium	Medium	-	Retain	No conflict with proposed works	LCSD

SCISTW
Tree Assessment Schedule

20-21 &
Date of Survey: 24 Nov 2006

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
SCT128	<i>Ficus microcarpa</i>	細葉榕	0.250	5.9	7.0	Fair	Good	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT129	<i>Ficus microcarpa</i>	細葉榕	0.240	4.9	6.0	Fair	Good	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT130	<i>Ficus microcarpa</i>	細葉榕	0.250	4.7	6.0	Fair	Good	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT131	<i>Celtis sinensis</i>	朴樹	0.100	5.3	4.0	Fair	Poor	Low	Medium	curved trunk, yellow leaves	Transplant	Falls within proposed work area	LCSD
SCT132	<i>Ficus microcarpa</i>	細葉榕	0.220	5.7	5.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT133	<i>Cassia siamea</i>	鐵刀木	0.150	4.3	5.0	Fair	Poor	Low	Medium	curved trunk, leaning	Transplant	Falls within proposed work area	LCSD
SCT134	<i>Cassia siamea</i>	鐵刀木	0.150	4.9	6.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT135	<i>Ficus microcarpa</i>	細葉榕	0.250	6.4	7.0	Good	Good	High	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT136	<i>Ficus microcarpa</i>	細葉榕	0.350	6.6	8.0	Good	Good	High	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT137	<i>Ficus microcarpa</i>	細葉榕	0.120	6.6	4.0	Fair	Fair	low	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT138	<i>Ficus microcarpa</i>	細葉榕	0.250	7.0	5.0	Good	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT139	<i>Cassia siamea</i>	鐵刀木	0.230	8.0	6.0	Fair	Poor	Low	Medium	curved trunk	Transplant	Falls within proposed work area	LCSD
SCT140	<i>Ficus microcarpa</i>	細葉榕	0.230	8.2	5.0	Good	Good	High	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT141	<i>Ficus microcarpa</i>	細葉榕	0.150	7.4	4.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT165	<i>Casuarina equisetifolia</i>	木麻黃	0.170	6.0	2.0	Fair	Poor	Low	Medium	broken branch	Transplant	Falls within proposed work area	LCSD
SCT166	<i>Casuarina equisetifolia</i>	木麻黃	0.140	6.0	2.0	Fair	Poor	Low	Medium	curved trunk, forked	Transplant	Falls within proposed work area	LCSD
SCT167	<i>Casuarina equisetifolia</i>	木麻黃	0.100	5.0	2.0	Fair	Poor	Low	Medium	curved trunk	Transplant	Falls within proposed work area	LCSD
SCT168	<i>Casuarina equisetifolia</i>	木麻黃	0.150	6.0	3.0	Fair	Poor	Low	Medium	curved trunk	Transplant	Falls within proposed work area	LCSD
SCT169	<i>Casuarina equisetifolia</i>	木麻黃	0.130	7.0	3.0	Fair	Poor	Low	Medium	forked	Transplant	Falls within proposed work area	LCSD
SCT170	<i>Casuarina equisetifolia</i>	木麻黃	0.170	7.0	3.0	Fair	Poor	Low	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT171	<i>Casuarina equisetifolia</i>	木麻黃	0.210	10.0	4.0	Fair	Poor	Low	Medium	deformed crown	Transplant	Falls within proposed work area	LCSD
SCT172	<i>Casuarina equisetifolia</i>	木麻黃	0.200	8.0	5.0	Fair	Poor	Low	Medium	broken branch	Transplant	Falls within proposed work area	LCSD
SCT173	<i>Casuarina equisetifolia</i>	木麻黃	0.180	7.0	5.0	Fair	Poor	Low	Medium	broken branch	Transplant	Falls within proposed work area	LCSD
SCT174	<i>Casuarina equisetifolia</i>	木麻黃	0.220	8.0	4.0	Fair	Poor	Low	Medium	leaning	Transplant	Falls within proposed work area	LCSD
SCT175	<i>Casuarina equisetifolia</i>	木麻黃	0.150	7.0	4.0	Fair	Poor	Low	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT176	<i>Casuarina equisetifolia</i>	木麻黃	0.180	7.0	4.0	Fair	Poor	Low	Medium	curved trunk	Transplant	Falls within proposed work area	LCSD
SCT177	<i>Ficus microcarpa</i>	細葉榕	0.160	3.0	2.0	Fair	Fair	Low	Medium	multi-trunk	Transplant	Falls within proposed work area	LCSD
SCT178	<i>Celtis sinensis</i>	朴樹	0.220	6.0	4.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT179	<i>Celtis sinensis</i>	朴樹	0.220	5.0	5.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD

SCISTW
Tree Assessment Schedule

Jurisdiction
Date of Survey: 20-21 &
24 Nov 2006

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
SCT180	<i>Celtis sinensis</i>	朴樹	0.200	5.0	4.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT182	<i>Cassia siamea</i>	鐵刀木	0.190	7.0	4.0	Fair	Poor	Low	Medium	broken branch	Transplant	Falls within proposed work area	LCSD
SCT183	<i>Cassia siamea</i>	鐵刀木	0.150	7.0	4.0	Fair	Poor	Low	Medium	curved trunk, forked	Transplant	Falls within proposed work area	LCSD
SCT185	<i>Acacia confusa</i>	臺灣相思	0.200	7.0	4.0	Fair	Poor	Low	Medium	forked	Transplant	Falls within proposed work area	LCSD
SCT186	<i>Acacia confusa</i>	臺灣相思	0.200	7.0	4.0	Fair	Poor	Low	Medium	leaning	Transplant	Falls within proposed work area	LCSD
SCT187	<i>Cassia siamea</i>	鐵刀木	0.250	9.0	5.0	Fair	Poor	Low	Medium	forked	Transplant	Falls within proposed work area	LCSD
SCT188	<i>Acacia confusa</i>	臺灣相思	0.150	4.0	3.0	Fair	Poor	Low	Medium	forked	Transplant	Falls within proposed work area	LCSD
SCT190	<i>Cassia siamea</i>	鐵刀木	0.250	9.0	5.0	Fair	Poor	Low	Medium	forked, dead branch	Transplant	Falls within proposed work area	LCSD
SCT192	<i>Acacia confusa</i>	臺灣相思	0.100	4.0	2.0	Fair	Poor	Low	Medium	leaning	Transplant	Falls within proposed work area	LCSD
SCT193	<i>Acacia confusa</i>	臺灣相思	0.170	6.0	3.0	Fair	Poor	Low	Medium	broken branch	Transplant	Falls within proposed work area	LCSD
SCT194	<i>Cassia siamea</i>	鐵刀木	0.160	6.0	3.0	Fair	Poor	Low	Medium	curved and broken branch	Transplant	Falls within proposed work area	LCSD
SCT195	<i>Acacia confusa</i>	臺灣相思	0.150	5.0	3.0	Fair	Poor	Low	Medium	forked, leaning	Transplant	Falls within proposed work area	LCSD
SCT196	<i>Hibiscus tiliaceus</i>	黃槿	0.180	5.0	4.0	Fair	Poor	Low	Medium	curved trunk	Transplant	Falls within proposed work area	LCSD
SCT197	<i>Hibiscus tiliaceus</i>	黃槿	0.150	5.0	4.0	Fair	Poor	Low	Medium	forked, broken bark	Transplant	Falls within proposed work area	LCSD
SCT198	<i>Hibiscus tiliaceus</i>	黃槿	0.150	6.0	5.0	Fair	poor	Low	Medium	broken branch, leaning	Transplant	Falls within proposed work area	LCSD
SCT199	<i>Hibiscus tiliaceus</i>	黃槿	0.200	7.0	5.0	Fair	Poor	Low	Medium	forked	Transplant	Falls within proposed work area	LCSD
SCT200	<i>Hibiscus tiliaceus</i>	黃槿	0.150	7.0	6.0	Fair	Poor	Low	Medium	curved trunk	Transplant	Falls within proposed work area	LCSD
SCT201	<i>Hibiscus tiliaceus</i>	黃槿	0.150	7.0	5.0	Fair	Poor	Low	Medium	forked, broken branch	Transplant	Falls within proposed work area	LCSD
SCT202	<i>Hibiscus tiliaceus</i>	黃槿	0.160	6.0	4.0	Fair	Poor	Low	Medium	forked, broken branch	Transplant	Falls within proposed work area	LCSD
SCT203	<i>Ficus microcarpa</i>	細葉榕	0.300	3.0	3.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT204	<i>Hibiscus tiliaceus</i>	黃槿	0.200	7.0	4.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT205	<i>Hibiscus tiliaceus</i>	黃槿	0.250	7.0	5.0	Fair	Poor	Low	Medium	leaning	Transplant	Falls within proposed work area	LCSD
SCT206	<i>Hibiscus tiliaceus</i>	黃槿	0.200	6.0	4.0	Fair	Poor	Low	Medium	curved trunk, forked	Transplant	Falls within proposed work area	LCSD
SCT207	<i>Hibiscus tiliaceus</i>	黃槿	0.200	7.0	5.0	Fair	Poor	Low	Medium	curved trunk	Transplant	Falls within proposed work area	LCSD
SCT208	<i>Hibiscus tiliaceus</i>	黃槿	0.150	6.0	4.0	Fair	Poor	Low	Medium	curved trunk	Transplant	Falls within proposed work area	LCSD
SCT209	<i>Hibiscus tiliaceus</i>	黃槿	0.180	6.0	4.0	Fair	Poor	Low	Medium	broken branch, leaning	Transplant	Falls within proposed work area	LCSD
SCT210	<i>Hibiscus tiliaceus</i>	黃槿	0.250	5.0	5.0	Fair	Poor	Low	Medium	forked, curved trunk	Transplant	Falls within proposed work area	LCSD
SCT211	<i>Aleurites moluccana</i>	石栗	0.180	5.3	5.0	Fair	Fair	Medium	Medium	branch was cut	Transplant	Falls within proposed work area	LCSD
SCT212	<i>Aleurites moluccana</i>	石栗	0.230	6.7	6.0	Fair	Fair	Medium	Medium	forked, cut branch	Transplant	Falls within proposed work area	LCSD

SCISTW
Tree Assessment Schedule

20-21 &
Date of Survey: 24 Nov 2006

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
SCT213	<i>Aleurites moluccana</i>	石栗	0.250	6.5	7.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT214	<i>Acacia confusa</i>	臺灣相思	0.200	7.3	8.0	Fair	Fair	Medium	Medium	leaning	Transplant	Falls within proposed work area	LCSD
SCT215	<i>Acacia confusa</i>	臺灣相思	0.160	6.9	5.0	Fair	Poor	Low	Medium	curved trunk	Transplant	Falls within proposed work area	LCSD
SCT216	<i>Ficus microcarpa</i>	細葉榕	0.300	6.3	8.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT217	<i>Acacia confusa</i>	臺灣相思	0.220	5.0	6.0	Fair	Fair	Low	Medium	leaning, cut trunk	Transplant	Falls within proposed work area	LCSD
SCT218	<i>Aleurites moluccana</i>	石栗	0.230	8.1	8.0	Good	Fair	Medium	Medium	forked	Transplant	Falls within proposed work area	LCSD
SCT219	<i>Aleurites moluccana</i>	石栗	0.200	7.3	6.0	Fair	Fair	Medium	Medium	cut trunk	Transplant	Falls within proposed work area	LCSD
SCT220	<i>Aleurites moluccana</i>	石栗	0.240	8.0	8.0	Fair	Good	High	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT221	<i>Bauhinia blakeana</i>	洋紫荊	0.180	5.8	5.0	Poor	Poor	Low	Low	dead branch, yellow leaves, leaning	Transplant	Falls within proposed work area	LCSD
SCT222	<i>Bauhinia blakeana</i>	洋紫荊	0.180	6.5	6.0	Poor	Poor	Low	Low	dead branch, yellow leaves, leaning	Transplant	Falls within proposed work area	LCSD
SCT223	<i>Bauhinia blakeana</i>	洋紫荊	0.180	5.7	6.0	Poor	Poor	Low	Low	dead branch, yellow leaves, leaning	Transplant	Falls within proposed work area	LCSD
SCT228	<i>Bauhinia blakeana</i>	洋紫荊	0.095	5.2	4.0	Poor	Poor	Low	Low	curved trunk, pest on leaves	Transplant	Falls within proposed work area	LCSD
SCT229	<i>Bauhinia blakeana</i>	洋紫荊	0.110	3.8	4.0	Poor	Poor	Low	Low	curve trunk, pest on leaves	Transplant	Falls within proposed work area	LCSD
SCT230	<i>Bauhinia blakeana</i>	洋紫荊	0.110	4.5	5.0	Poor	Poor	Low	Low	forked, pest on leaves	Transplant	Falls within proposed work area	LCSD
SCT231	<i>Bauhinia blakeana</i>	洋紫荊	0.110	4.1	5.0	Poor	Poor	Low	Low	curved trunk, pest on leaves	Transplant	Falls within proposed work area	LCSD
SCT232	<i>Bauhinia blakeana</i>	洋紫荊	0.110	4.9	5.0	Poor	Poor	Low	Low	curved trunk, pest on leaves	Transplant	Falls within proposed work area	LCSD
SCT233	<i>Cassia siamea</i>	鐵刀木	0.110	5.3	6.0	Fair	Poor	Low	Medium	curved trunk, forked	Transplant	Falls within proposed work area	LCSD
SCT234	<i>Cassia siamea</i>	鐵刀木	0.110	4.0	6.0	Fair	Poor	Low	Medium	forked	Transplant	Falls within proposed work area	LCSD
SCT235	<i>Cassia siamea</i>	鐵刀木	0.110	5.8	6.0	Fair	Fair	Low	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT236	<i>Cassia siamea</i>	鐵刀木	0.140	6.9	6.0	Fair	Fair	Low	Medium	curved trunk	Transplant	Falls within proposed work area	LCSD
SCT238	<i>Celtis sinensis</i>	朴樹	0.095	3.0	3.0	Poor	Poor	Low	Low	yellow leaves, pest on leaves	Transplant	Falls within proposed work area	LCSD
SCT239	<i>Celtis sinensis</i>	朴樹	0.095	3.4	3.0	Poor	Fair	Low	Low	yellow leaves, pest on leaves	Transplant	Falls within proposed work area	LCSD
SCT240	<i>Albizia lebbek</i>	大葉合歡	0.180	6.1	6.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT241	<i>Albizia lebbek</i>	大葉合歡	0.130	5.5	5.0	Poor	Fair	Low	Low	dead branch	Transplant	Falls within proposed work area	LCSD
SCT242	<i>Albizia lebbek</i>	大葉合歡	0.110	4.5	5.0	Fair	Poor	Low	Medium	forked, leaning	Transplant	Falls within proposed work area	LCSD
SCT243	<i>Albizia lebbek</i>	大葉合歡	0.100	4.8	5.0	Poor	Poor	Low	Low	dead branch	Transplant	Falls within proposed work area	LCSD
SCT244	<i>Albizia lebbek</i>	大葉合歡	0.130	4.7	5.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT245	<i>Albizia lebbek</i>	大葉合歡	0.220	5.9	6.0	Fair	Fair	Medium	Medium	curved trunk	Transplant	Falls within proposed work area	LCSD
SCT246	<i>Litsea glutinosa</i>	潺槁樹	0.110	5.4	6.0	Fair	Poor	Low	Medium	curved trunk, broken branch	Transplant	Falls within proposed work area	LCSD

SCISTW
Tree Assessment Schedule

Jurisdiction
Date of Survey: 20-21 &
24 Nov 2006

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
SCT247	<i>Ficus microcarpa</i>	細葉榕	0.250	5.5	4.0	Fair	Fair	Medium	Medium	forked	Transplant	Falls within proposed work area	LCSD
SCT248	<i>Litsea glutinosa</i>	潺樟樹	0.100	6.3	5.0	Fair	Poor	Low	Medium	curved trunk, forked	Transplant	Falls within proposed work area	LCSD
SCT249	<i>Ficus microcarpa</i>	細葉榕	0.120	6.2	6.0	Fair	Poor	Low	Medium	forked	Transplant	Falls within proposed work area	LCSD
SCT250	<i>Ficus microcarpa</i>	細葉榕	0.100	5.5	5.0	Fair	Poor	Low	Medium	forked, dead branch	Transplant	Falls within proposed work area	LCSD
SCT251	<i>Ficus microcarpa</i>	細葉榕	0.110	5.9	5.0	Fair	Poor	Low	Medium	forked	Transplant	Falls within proposed work area	LCSD
SCT252	<i>Ficus microcarpa</i>	細葉榕	0.110	5.6	5.0	Fair	Poor	Low	Medium	forked	Transplant	Falls within proposed work area	LCSD
SCT253	<i>Ficus microcarpa</i>	細葉榕	0.130	7.0	5.0	Fair	Poor	Low	Medium	forked	Transplant	Falls within proposed work area	LCSD
SCT254	<i>Ficus microcarpa</i>	細葉榕	0.290	7.8	8.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT255	<i>Ficus microcarpa</i>	細葉榕	0.300	9.5	9.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT256	<i>Ficus microcarpa</i>	細葉榕	0.180	5.8	6.0	Fair	Fair	Low	Medium	forked	Transplant	Falls within proposed work area	LCSD
SCT257	<i>Celtis sinensis</i>	朴樹	0.200	6.7	8.0	Fair	Fair	Low	Medium	forked, curved trunk, pest on leaves	Transplant	Falls within proposed work area	LCSD
SCT258	<i>Ficus microcarpa</i>	細葉榕	0.150	7.2	6.0	Fair	Poor	Low	Medium	forked	Transplant	Falls within proposed work area	LCSD
SCT259	<i>Ficus microcarpa</i>	細葉榕	0.095	6.9	5.0	Fair	Poor	Low	Medium	leaning	Transplant	Falls within proposed work area	LCSD
SCT260	<i>Litsea glutinosa</i>	潺樟樹	0.095	6.5	5.0	Fair	Poor	Low	Medium	curved trunk	Transplant	Falls within proposed work area	LCSD
SCT261	<i>Ficus microcarpa</i>	細葉榕	0.190	8.2	5.0	Fair	Fair	Low	Medium	forked	Transplant	Falls within proposed work area	LCSD
SCT262	<i>Cassia siamea</i>	鐵刀木	0.300	11.8	10.0	Fair	Fair	Medium	Medium	curved trunk, leaning	Transplant	Falls within proposed work area	LCSD
SCT263	<i>Ficus microcarpa</i>	細葉榕	0.500	9.0	12.0	Fair	Good	High	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT264	<i>Cassia siamea</i>	鐵刀木	0.450	9.9	10.0	Fair	Poor	Low	Medium	forked, leaning	Transplant	Falls within proposed work area	LCSD
SCT265	<i>Ficus microcarpa</i>	細葉榕	0.230	5.9	8.0	Good	Good	High	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT266	<i>Ficus microcarpa</i>	細葉榕	0.400	6.2	8.0	Good	Good	High	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT267	<i>Ficus microcarpa</i>	細葉榕	0.400	6.5	8.0	Good	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT268	<i>Ficus microcarpa</i>	細葉榕	0.400	8.9	9.0	Good	Good	High	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT269	<i>Ficus microcarpa</i>	細葉榕	0.300	9.0	8.0	Good	Fair	High	Medium	leaning	Transplant	Falls within proposed work area	LCSD
SCT270	<i>Ficus microcarpa</i>	細葉榕	0.450	9.0	10.0	Good	Good	High	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT271	<i>Ficus microcarpa</i>	細葉榕	0.400	8.9	10.0	Good	Good	High	Medium	-	Transplant	Falls within proposed work area	LCSD
SCT272	<i>Ficus microcarpa</i>	細葉榕	0.500	10.5	10.0	Good	Good	High	Medium	cut branch	Transplant	Falls within proposed work area	LCSD
SCT273	<i>Ficus microcarpa</i>	細葉榕	0.120	5.5	4.0	Fair	Poor	Low	Medium	forked	Transplant	Falls within proposed work area	LCSD
SCT274	<i>Aleurites moluccana</i>	石栗	0.120	5.0	1.5	Fair	Poor	Low	Medium	forked	Transplant	Falls within proposed work area	LCSD
SCT275	<i>Aleurites moluccana</i>	石栗	0.110	5.0	2.4	Fair	Poor	Low	Medium	forked	Transplant	Falls within proposed work area	LCSD

SCISTW
Tree Assessment Schedule

Date of Survey: 20-21 &
24 Nov 2006

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
SCT277	<i>Ficus elastica</i>	印度榕	0.269	5.5	6.0	Fair	Poor	Low	Medium	curved trunk, leaning, trunk was cut	Retain	No conflict with proposed works	LCSD
SCT278	<i>Ficus elastica</i>	印度榕	0.472	8.0	10.0	Fair	Fair	Low	Medium	forked, trunk was cut	Retain	No conflict with proposed works	LCSD
SCT279	<i>Ficus elastica</i>	印度榕	0.206	5.0	8.0	Fair	Fair	Low	Medium	forked, trunk was cut	Retain	No conflict with proposed works	LCSD
SCT280	<i>Ficus elastica</i>	印度榕	0.436	10.0	10.0	Fair	Fair	Low	Medium	trunk was cut	Retain	No conflict with proposed works	LCSD
SCT281	<i>Ficus microcarpa</i>	細葉榕	0.442	5.0	8.0	Fair	Good	High	Medium	-	Retain	No conflict with proposed works	LCSD
SCT282	<i>Leucaena leucocephala</i>	銀合歡	0.323	5.5	3.5	Fair	Poor	Low	Medium	suppressed growth, dead branch	Fell	Falls within footprint of proposed works	LCSD
SCT283	<i>Leucaena leucocephala</i>	銀合歡	0.100	5.0	2.5	Fair	Poor	Low	Medium	leaning, dead branch	Fell	Falls within footprint of proposed works	LCSD
SCT287	<i>Leucaena leucocephala</i>	銀合歡	0.100	6.0	3.5	Fair	Poor	Low	Medium	leaning, dead branch	Fell	Falls within footprint of proposed works	LCSD
SCT288	<i>Leucaena leucocephala</i>	銀合歡	0.180	6.5	5.0	Fair	Poor	Low	Medium	forked, leaning, broken branch	Fell	Falls within footprint of proposed works	LCSD
SCT290	<i>Leucaena leucocephala</i>	銀合歡	0.131	6.5	3.5	Fair	Poor	Low	Medium	curved trunk, forked	Fell	Falls within footprint of proposed works	LCSD
SCT291	<i>Leucaena leucocephala</i>	銀合歡	0.100	5.5	3.5	Fair	Poor	Low	Medium	leaning, forked, dead branch	Fell	Falls within footprint of proposed works	LCSD
SCT293	<i>Leucaena leucocephala</i>	銀合歡	0.120	5.0	3.5	Fair	Poor	Low	Medium	curved trunk	Fell	Falls within footprint of proposed works	LCSD
SCT295	<i>Leucaena leucocephala</i>	銀合歡	0.229	7.5	5.0	Fair	Poor	Low	Medium	forked, suppress growth, dead branch	Fell	Falls within footprint of proposed works	LCSD
SCT296	<i>Leucaena leucocephala</i>	銀合歡	0.100	6.0	3.5	Fair	Poor	Low	Medium	leaning, forked	Fell	Falls within footprint of proposed works	LCSD
SCT297	<i>Leucaena leucocephala</i>	銀合歡	0.119	5.0	2.5	Fair	Poor	Low	Medium	curved trunk, forked	Fell	Falls within footprint of proposed works	LCSD
SCT298	<i>Acacia farnesiana</i>	金合歡	0.250	6.0	6.0	Fair	Good	Medium	Medium	dead branch	Transplant	Falls within footprint of proposed works	LCSD
SCT299	<i>Leucaena leucocephala</i>	銀合歡	0.140	6.0	4.0	Fair	Poor	Low	Medium	leaning, forked, dead branch	Fell	Falls within footprint of proposed works	LCSD
SCT300	<i>Leucaena leucocephala</i>	銀合歡	0.240	6.0	4.0	Poor	Poor	Low	Low	leaning, root exposed, dead and broken b	Fell	Falls within footprint of proposed works	LCSD

* LCSD - Leisure and Cultural Services Department

SCS Work - North Point (NP-viii)
Tree Assessment Schedule

Date of Survey: 15-Jan-07

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T038	<i>Cinnamomum burmannii</i>	陰香	0.120	3.5	3.4	Good	Fair	Medium	Medium	-	Retain	No conflict with proposed works	LCSD
T039	<i>Cinnamomum burmannii</i>	陰香	0.150	5.0	4.3	Good	Fair	Medium	High	-	Retain	No conflict with proposed works	LCSD
T040	<i>Cinnamomum burmannii</i>	陰香	0.120	4.0	3.8	Poor	Fair	Low	Low	Dead branch, yellow leaves	Retain	No conflict with proposed works	LCSD
T041	<i>Cinnamomum burmannii</i>	陰香	0.180	4.0	3.2	Poor	Fair	Low	Low	Forked, yellow leaves	Retain	No conflict with proposed works	LCSD
T042	<i>Cinnamomum burmannii</i>	陰香	0.180	4.0	4.1	Good	Fair	Medium	High	-	Retain	No conflict with proposed works	LCSD
T043	<i>Cinnamomum burmannii</i>	陰香	0.150	3.5	2.8	Fair	Fair	Medium	Medium	-	Retain	No conflict with proposed works	LCSD
T044	<i>Cinnamomum burmannii</i>	陰香	0.150	4.5	3.5	Fair	Fair	Medium	Medium	-	Retain	No conflict with proposed works	LCSD
T045	<i>Cinnamomum burmannii</i>	陰香	0.220	5.0	6.9	Good	Fair	Medium	High	-	Retain	No conflict with proposed works	LCSD

* LCSD - Leisure and Cultural Services Department

SCS Works - Wan Chai East (WCE-i)
Tree Assessment Schedule

Date of Survey: 6 Dec 2006 & 17 Apr 2007

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T001	<i>Macaranga tanarius</i>	血桐	0.150	5.0	4.0	Poor	Fair	Low	Low	Leaning, leaves attacked by pest	Retain	No conflict with proposed works	LCSD
T002	<i>Macaranga tanarius</i>	血桐	0.150	5.0	5.0	Fair	Poor	Low	Medium	Forked, broken branch	Retain	No conflict with proposed works	LCSD
T003	Dead tree	死樹	0.100	3.0	1.0	-	-	-	-	-	Retain	No conflict with proposed works	LCSD
T004	<i>Macaranga tanarius</i>	血桐	2x0.150	6.0	5.0	Fair	Poor	Low	Medium	Multi-trunk, leaning	Retain	No conflict with proposed works	LCSD
T005	<i>Mangifera indica</i>	芒果	0.400	9.0	6.0	Fair	Fair	Medium	Medium	Cut branch, broken bark, deformed crown	Transplant	Falls within footprint of proposed works	LCSD
T006	<i>Ficus virens</i>	黃葛樹	1.700	13.0	10.0	Fair	Fair	Medium	Medium	Multi-trunk, broken branch	Retain	No conflict with proposed works	LCSD
T007	<i>Melia azedarach</i>	苦楝	0.400	9.0	4.0	Fair	Fair	Medium	Medium	Leaning, broken branch	Transplant	Falls within footprint of proposed works	LCSD
T008	<i>Citrus maxima</i>	柚	0.120	6.5	3.0	Fair	Poor	Low	Medium	Curved trunk, leaning, broken bark, dead branch	Retain	No conflict with proposed works	LCSD
T009	<i>Macaranga tanarius</i>	血桐	0.300	7.0	6.0	Fair	Poor	Low	Medium	Leaning, broken branch	Retain	No conflict with proposed works	LCSD
T010	<i>Bauhinia sp.</i>	羊蹄甲屬	0.400	9.5	7.0	Fair	Fair	Low	Medium	Multi-trunk, dead branch	Retain	No conflict with proposed works	LCSD
T011	<i>Delonix regia</i>	鳳凰木	0.700	10.0	8.0	Fell down on 17 Sept 2007 and cut down on 18 Sept 2007 with the approval of DLO							
T012	<i>Macaranga tanarius</i>	血桐	0.090	3.5	3.0	Fair	Fair	Low	Medium	-	Transplant	Falls within proposed work area	LCSD
T013	<i>Ficus microcarpa</i>	細葉榕	0.130	4.0	3.0	Fair	Fair	Low	Medium	Leaning	Transplant	Falls within proposed work area	LCSD
T014	<i>Celtis sinensis</i>	朴樹	0.110	4.5	3.0	Fair	Fair	Low	Medium	Leaning	Transplant	Falls within proposed work area	LCSD
T015	<i>Aleurites moluccana</i>	石栗	0.580	14.0	8.0	Fair	Fair	Medium	Medium	-	Transplant	Falls within proposed work area	LCSD
T016	<i>Macaranga tanarius</i>	血桐	0.110	3.5	4.0	Fair	Fair	Low	Medium	Leaning	Retain	No conflict with proposed works	LCSD
T017	<i>Macaranga tanarius</i>	血桐	0.170	4.0	5.0	Fair	Fair	Low	Medium	Leaning	Retain	No conflict with proposed works	LCSD

* LCSD - Leisure and Cultural Services Department

SCS Works - Sandy Bay (SB-I & SB-PS)
Tree Assessment Schedule

Date of Survey: 10-Nov-06

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T017	<i>Bauhinia</i> spp.	洋蹄甲屬	0.170	4.0	6.0	Fair	Poor	Low	Medium	multi-trunk, yellow leaves	Transplant	Falls within footprint of proposed works	LCSD
T018	<i>Ficus hispida</i>	對葉榕	0.100	4.5	3.0	Fair	Poor	Low	Medium	yellow leaves, leaning	Transplant	Falls within footprint of proposed works	LCSD
T019	<i>Acacia confusa</i>	臺灣相思	0.140	3.5	4.0	Fair	Poor	Low	Medium	forked	Transplant	Falls within footprint of proposed works	LCSD
T020	<i>Macaranga tanarius</i>	血桐	0.130	6.0	5.0	Fair	Poor	Low	Medium	curved trunk	Transplant	Falls within footprint of proposed works	LCSD
T021	<i>Macaranga tanarius</i>	血桐	0.130	8.0	5.0	Fair	Poor	Low	Medium	broken branch, forked	Transplant	Falls within footprint of proposed works	LCSD
T022	<i>Leucaena leucocephala</i>	銀合歡	0.120	11.0	6.0	Fair	Poor	Low	Medium	forked	Fell	Falls within footprint of proposed works	LCSD
T023	<i>Leucaena leucocephala</i>	銀合歡	0.100	11.0	5.0	Fair	Poor	Low	Medium	forked	Fell	Falls within footprint of proposed works	LCSD
T026	<i>Leucaena leucocephala</i>	銀合歡	0.100	9.0	6.0	Fair	Poor	Low	Medium	leaning, broken trunk	Fell	Falls within footprint of proposed works	LCSD
T027	<i>Broussonetia papyrifera</i>	構樹	0.170	10.0	5.0	Fair	Poor	Low	Medium	broken branch	Transplant	Falls within footprint of proposed works	LCSD
T028	<i>Broussonetia papyrifera</i>	構樹	0.110	9.0	4.0	Fair	Poor	Low	Medium	leaning	Transplant	Falls within footprint of proposed works	LCSD
T029	<i>Leucaena leucocephala</i>	銀合歡	0.120	10.0	8.0	Fair	Poor	Low	Medium	forked, leaning	Fell	Falls within footprint of proposed works	LCSD
T030	<i>Leucaena leucocephala</i>	銀合歡	0.130	11.0	7.0	Fair	Poor	Low	Medium	forked, broken branch	Fell	Falls within footprint of proposed works	LCSD
T031	<i>Leucaena leucocephala</i>	銀合歡	0.100	8.0	5.0	Fair	Poor	Low	Medium	leaning, forked	Fell	Falls within footprint of proposed works	LCSD
T032	<i>Leucaena leucocephala</i>	銀合歡	0.110	8.0	2.0	Fair	Poor	Low	Medium	curved trunk	Fell	Falls within footprint of proposed works	LCSD
T034	<i>Leucaena leucocephala</i>	銀合歡	0.110	9.0	6.0	Fair	Poor	Low	Medium	curved trunk	Fell	Falls within footprint of proposed works	LCSD
T035	<i>Leucaena leucocephala</i>	銀合歡	0.120	10.0	6.0	Fair	Poor	Low	Medium	forked	Fell	Falls within footprint of proposed works	LCSD
T036	<i>Macaranga tanarius</i>	血桐	0.100	6.0	4.0	Fair	Poor	Low	Medium	leaning, broken branch	Transplant	Falls within footprint of proposed works	LCSD
T037	<i>Macaranga tanarius</i>	血桐	0.210	6.0	7.0	Fair	Poor	Low	Medium	multi-trunk, broken branch	Transplant	Falls within footprint of proposed works	LCSD
T038	<i>Macaranga tanarius</i>	血桐	0.120	5.0	4.0	Fair	Poor	Low	Medium	curved trunk	Retain	no conflict with proposed works	LCSD
T039	<i>Macaranga tanarius</i>	血桐	0.220	4.0	6.0	Fair	Poor	Low	Medium	leaning, broken branch	Retain	no conflict with proposed works	LCSD
T040	<i>Macaranga tanarius</i>	血桐	0.240	7.0	6.0	Fair	Poor	Low	Medium	branched trunk, broken branch	Retain	no conflict with proposed works	LCSD
T041	<i>Macaranga tanarius</i>	血桐	0.180	7.0	5.0	Fair	Poor	Low	Medium	curved trunk, broken bark	Retain	no conflict with proposed works	LCSD
T042	<i>Macaranga tanarius</i>	血桐	0.160	7.0	5.0	Fair	Poor	Low	Medium	broken branch	Retain	no conflict with proposed works	LCSD
T043	<i>Macaranga tanarius</i>	血桐	0.180	6.0	6.0	Fair	Poor	Low	Medium	curved trunk, broken branch	Retain	no conflict with proposed works	LCSD
T044	<i>Macaranga tanarius</i>	血桐	0.140	7.0	4.0	Fair	Fair	Low	Medium	broken bark & broken branch	Retain	no conflict with proposed works	LCSD
T045	<i>Macaranga tanarius</i>	血桐	0.400	6.0	7.0	Fair	Fair	Low	Medium	broken bark & broken branch	Retain	no conflict with proposed works	LCSD

SCS Works - Sandy Bay (SB-I & SB-PS)
Tree Assessment Schedule

Date of Survey: 10-Nov-06

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T046	<i>Aleurites moluccana</i>	石栗	0.480	15.0	10.0	Good	Good	High	Medium	-	Retain	no conflict with proposed works	LCSD
T047	<i>Macaranga tanarius</i>	血桐	0.150	7.0	5.0	Fair	Fair	Low	High	broken branch	Retain	no conflict with proposed works	LCSD

SCS Works - Sandy Bay (SB-I & SB-PS)
Tree Assessment Schedule

Date of Survey: 10-Nov-06

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T048	<i>Macaranga tanarius</i>	血桐	0.120	6.0	5.0	Fair	Poor	Low	Medium	broken bark & broken branch	Retain	no conflict with proposed works	LCSD
T049	<i>Aleurites moluccana</i>	石栗	0.170	12.0	5.0	Fair	Poor	Low	Medium	-	Retain	no conflict with proposed works	LCSD
T050	<i>Leucaena leucocephala</i>	銀合歡	0.100	7.0	6.0	Fair	Poor	Low	Medium	leaning, covered by climber	Retain	no conflict with proposed works	LCSD
T051	<i>Aleurites moluccana</i>	石栗	0.220	10.0	5.0	Fair	Fair	medium	Medium	-	Retain	no conflict with proposed works	LCSD
T052	<i>Macaranga tanarius</i>	血桐	0.230	8.0	8.0	Fair	Fair	Low	Medium	broken branch	Retain	no conflict with proposed works	LCSD
T053	<i>Macaranga tanarius</i>	血桐	0.300	8.0	9.0	Fair	Fair	Low	Medium	broken branch	Retain	no conflict with proposed works	LCSD
T054	<i>Leucaena leucocephala</i>	銀合歡	0.190	9.0	4.0	Fair	Poor	Low	Medium	Forked, suppressed growth	Retain	no conflict with proposed works	LCSD
T055	<i>Leucaena leucocephala</i>	銀合歡	0.100	9.0	3.0	Fair	Poor	Low	Medium	curved trunk	Retain	no conflict with proposed works	LCSD
T056	<i>Macaranga tanarius</i>	血桐	0.130	9.0	6.0	Fair	Poor	Low	Medium	leaning	Retain	no conflict with proposed works	LCSD
T057	<i>Macaranga tanarius</i>	血桐	0.120	9.0	4.0	Fair	Poor	Low	Medium	leaning, broken bark	Retain	no conflict with proposed works	LCSD
T058	<i>Macaranga tanarius</i>	血桐	0.120	9.0	4.0	Fair	Poor	Low	Medium	bark damage & broken branch	Retain	no conflict with proposed works	LCSD
T059	<i>Macaranga tanarius</i>	血桐	0.210	5.0	5.0	Fair	Poor	Low	Medium	forked, curved trunk	Retain	no conflict with proposed works	LCSD
T060	<i>Leucaena leucocephala</i>	銀合歡	0.160	10.0	8.0	Fair	Poor	low	Medium	forked, broken branch	Retain	no conflict with proposed works	LCSD
T061	<i>Macaranga tanarius</i>	血桐	0.100	5.0	4.0	Fair	Poor	Low	Medium	curved trunk	Transplant	Falls within proposed work area	LCSD

* LCSD - Leisure and Cultural Services Department

SCS Work - Cyberport (CP-iv)
Tree Assessment Schedule

Date of Survey: 25-Jan-07

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T065	<i>Hibiscus tiliaceus</i>	黃槿	0.160	4.5	3.0	Poor	Poor	Low	Low	-	Retain	No conflict with proposed works	LCSD
T066	<i>Hibiscus tiliaceus</i>	黃槿	0.130	3.5	2.5	Poor	Poor	Low	Low	Cut branch	Retain	No conflict with proposed works	LCSD
T067	<i>Hibiscus tiliaceus</i>	黃槿	0.100	3.5	2.5	Poor	Poor	Low	Low	Cut branch	Retain	No conflict with proposed works	LCSD
T068	<i>Hibiscus tiliaceus</i>	黃槿	0.140	4.0	2.5	Poor	Poor	Low	Low	Cut branch	Retain	No conflict with proposed works	LCSD
T072	<i>Hibiscus tiliaceus</i>	黃槿	0.110	4.0	3.0	Poor	Poor	Low	Low	Cut branch	Retain	No conflict with proposed works	LCSD
T074	<i>Ficus microcarpa</i>	細葉榕	0.150	5.0	3.0	Poor	Poor	Low	Low	Broken branch	Retain	No conflict with proposed works	LCSD
T075	<i>Acacia auriculliformis</i>	耳果相思	0.110	4.5	3.5	Fair	Poor	Low	Medium	Leaning	Retain	No conflict with proposed works	LCSD

* LCSD - Leisure and Cultural Services Department

SCS Works - Aberdeen (Abd-i & Abd-iii)
Tree Assessment Schedule

Date of Survey: 5 Dec 06 & 8 Feb 07

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T001	<i>Leucaena leucocephala</i>	銀合歡	0.120	3.0	4.0	Fair	Poor	Low	Medium	Forked trunk, dead branch	Retain	No conflict with proposed work	LCSD
T002	<i>Celtis sinensis</i>	朴樹	0.320	3.5	5.0	Fair	Fair	Low	Medium	Yellow leaves, dead branch, forked trunk	Retain	No conflict with proposed work	LCSD
T003	<i>Leucaena leucocephala</i>	銀合歡	0.190	5.5	5.0	Fair	Fair	Low	Medium	Curved trunk, dead branch	Retain	No conflict with proposed work	LCSD
T004	<i>Leucaena leucocephala</i>	銀合歡	0.160	3.5	4.5	Fair	Fair	Low	Medium	Forked trunk, dead branch	Retain	No conflict with proposed work	LCSD
T005	<i>Leucaena leucocephala</i>	銀合歡	0.100	4.0	3.5	Fair	Fair	Low	Medium	Dead branch	Retain	No conflict with proposed work	LCSD
T006	<i>Leucaena leucocephala</i>	銀合歡	0.130	5.0	5.0	Fair	Fair	Low	Medium	Forked trunk, dead branch	Retain	No conflict with proposed work	LCSD
T007	<i>Leucaena leucocephala</i>	銀合歡	0.140	5.0	5.0	Fair	Fair	Low	Medium	Curved trunk, dead branch	Retain	No conflict with proposed work	LCSD
T008	<i>Leucaena leucocephala</i>	銀合歡	0.180	5.0	5.0	Fair	Fair	Low	Medium	Broken branch, covered with climber, dead branch	Retain	No conflict with proposed work	LCSD
T076	<i>Macaranga tanarius</i>	血桐	0.120	5.0	3.0	Poor	Poor	Low	Low	Leaning, broken branch	Transplant	Falls within proposed work area	LCSD
T078	<i>Macaranga tanarius</i>	血桐	0.110	5.0	3.5	Poor	Poor	Low	Low	Leaning, cut branch	Transplant	Falls within proposed work area	LCSD
T079	<i>Macaranga tanarius</i>	血桐	0.140	5.0	4.0	Poor	Poor	Low	Low	Leaning, cut branch	Transplant	Falls within proposed work area	LCSD
T080	<i>Macaranga tanarius</i>	血桐	0.180	5.0	4.0	Poor	Poor	Low	Low	Leaning, broken & cut branch	Transplant	Falls within proposed work area	LCSD
T081	<i>Ficus Superba</i>	筆管榕	0.410	8.0	5.0	Fair	Fair	Medium	Medium	Broken branch	Transplant	Falls within proposed work area	LCSD
T082	<i>Macaranga tanarius</i>	血桐	0.230	5.5	5.0	Poor	Poor	Low	Low	Leaning, dead branch	Transplant	Falls within proposed work area	LCSD
T083	<i>Macaranga tanarius</i>	血桐	0.190	5.0	4.0	Poor	Poor	Low	Low	Curved trunk, cut branch	Transplant	Falls within proposed work area	LCSD
T084	<i>Macaranga tanarius</i>	血桐	0.240	5.5	6.5	Fair	Poor	Low	Medium	Leaning	Transplant	Falls within proposed work area	LCSD

* LCSD - Leisure and Cultural Services Department

SCS Work - Ap Lei Chau (ALC-iv & ALC-i)
Tree Assessment Schedule

Date of Survey: 11-Dec-06

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T001	<i>Eucalyptus robusta</i>	大葉桉	0.130	5.0	2.0	Fair	Fair	Low	Medium	Forked	Retain	No conflict with proposed works	LCSD
T002	<i>Thevetia peruviana</i>	黃花夾竹桃	0.150	3.0	3.0	Poor	Poor	Low	Low	Multi-trunk, curved trunk, dead branch	Retain	No conflict with proposed works	LCSD
T004	<i>Eucalyptus robusta</i>	大葉桉	0.120	4.0	2.0	Poor	Poor	Low	Low	Leaning, dead branch	Retain	No conflict with proposed works	LCSD
T005	<i>Eucalyptus robusta</i>	大葉桉	0.140	5.0	4.0	Poor	Poor	Low	Low	Dead branch, deformed crown	Retain	No conflict with proposed works	LCSD
T006	<i>Eucalyptus robusta</i>	大葉桉	0.140	5.0	3.5	Fair	Fair	Low	Medium	Dead branch, leaning	Retain	No conflict with proposed works	LCSD
T007	<i>Thevetia peruviana</i>	黃花夾竹桃	0.117	4.0	3.0	Poor	Poor	Low	Low	Multi-trunk, curved trunk	Retain	No conflict with proposed works	LCSD
T008	<i>Thevetia peruviana</i>	黃花夾竹桃	0.100	3.0	2.0	Poor	Poor	Low	Low	Forked, curved trunk	Retain	No conflict with proposed works	LCSD
T009	<i>Eucalyptus robusta</i>	大葉桉	0.140	4.0	3.0	Poor	Poor	Low	Low	Leaning, dead branch	Retain	No conflict with proposed works	LCSD
T010	<i>Ficus microcarpa</i>	細葉榕	0.130	5.0	4.0	Poor	Fair	Low	Low	Dead branch	Retain	No conflict with proposed works	LCSD
T011	<i>Ficus microcarpa</i>	細葉榕	0.130	4.0	4.0	Fair	Fair	Medium	Medium	Dead branch	Retain	No conflict with proposed works	LCSD
T012	<i>Ficus microcarpa</i>	細葉榕	0.130	4.5	4.0	Fair	Poor	Medium	Medium	Forked, curved trunk	Retain	No conflict with proposed works	LCSD
T013	<i>Ficus microcarpa</i>	細葉榕	0.135	5.0	4.5	Fair	Fair	Medium	Medium	-	Retain	No conflict with proposed works	LCSD
T014	<i>Ficus microcarpa</i>	細葉榕	0.125	4.5	4.0	Fair	Fair	Low	Medium	-	Retain	No conflict with proposed works	LCSD
T015	<i>Ficus microcarpa</i>	細葉榕	0.145	4.0	4.0	Fair	Fair	Medium	Medium	-	Retain	No conflict with proposed works	LCSD
T016	<i>Ficus microcarpa</i>	細葉榕	0.140	4.5	4.0	Fair	Fair	Medium	Medium	-	Retain	No conflict with proposed works	LCSD
T017	<i>Ficus microcarpa</i>	細葉榕	0.206	5.0	4.5	Fair	Poor	Low	Medium	Dead branch, multi-trunk	Retain	No conflict with proposed works	LCSD
T018	<i>Ficus microcarpa</i>	細葉榕	0.120	4.0	4.5	Fair	Fair	Low	Medium	Dead branch	Retain	No conflict with proposed works	LCSD
T019	<i>Thevetia peruviana</i>	黃花夾竹桃	0.133	3.0	2.5	Poor	Poor	Low	Low	Forked, curved trunk, dead branch	Retain	No conflict with proposed works	LCSD
T020	<i>Eucalyptus robusta</i>	大葉桉	0.130	4.5	1.0	Fair	Fair	Low	Medium	Leaning	Retain	No conflict with proposed works	LCSD
T021	<i>Eucalyptus robusta</i>	大葉桉	0.140	5.5	2.5	Fair	Fair	Low	Medium	Dead branch, broken branch	Retain	No conflict with proposed works	LCSD
T022	<i>Eucalyptus robusta</i>	大葉桉	0.145	4.0	1.0	Poor	Poor	Low	Low	Dead branch	Retain	No conflict with proposed works	LCSD
T023	<i>Eucalyptus robusta</i>	大葉桉	0.140	4.0	1.5	Poor	Poor	Low	Low	Leaning, dead branch	Retain	No conflict with proposed works	LCSD
T024	<i>Eucalyptus robusta</i>	大葉桉	0.150	5.5	2.5	Fair	Fair	Low	Medium	-	Retain	No conflict with proposed works	LCSD
T025	<i>Thevetia peruviana</i>	黃花夾竹桃	0.131	3.0	2.5	Poor	Poor	Low	Low	Forked, curved trunk	Retain	No conflict with proposed works	LCSD
T026	<i>Ficus microcarpa</i>	細葉榕	0.120	4.5	3.0	Fair	Fair	Low	Medium	Dead branch	Retain	No conflict with proposed works	LCSD
T028	<i>Ficus microcarpa</i>	細葉榕	0.140	3.5	2.5	Fair	Fair	Low	Medium	Dead branch	Retain	No conflict with proposed works	LCSD
T029	<i>Thevetia peruviana</i>	黃花夾竹桃	0.110	3.5	2.0	Poor	Poor	Low	Low	Curved trunk, leaning, dead branch	Retain	No conflict with proposed works	LCSD
T030	<i>Acacia confusa</i>	臺灣相思	0.145	5.5	4.0	Fair	Poor	Low	Medium	Curved trunk, branch covered by climber	Retain	No conflict with proposed works	LCSD

SCS Work - Ap Lei Chau (ALC-iv & ALC-i)
Tree Assessment Schedule

Date of Survey: 11-Dec-06

Tree No.	Botanical Name	Chinese Name	Trunk Diameter (m)	Overall Height (m)	Crown Spread (m)	Health (Good/Fair/Poor)	Form (Good/Fair/Poor)	Amenity Value (High/Medium/Low)	Survival Rate after Transplanting (High/Medium/Low)	Remarks	Recommendation	Justification	Jurisdiction of Tree Preservation *
T031	<i>Macaranga tanarius</i>	血桐	0.095	3.5	3.0	Fair	Poor	Low	Medium	Leaning, curved trunk	Transplant	Falls within proposed work area	LCSD
T033	<i>Macaranga tanarius</i>	血桐	0.180	4.6	5.0	Fair	Poor	Low	Medium	Leaning, damage on bark	Transplant	Falls within proposed work area	LCSD
T034	<i>Macaranga tanarius</i>	血桐	0.152	2.5	2.5	Fair	Poor	Low	Medium	Multi-trunk, branch covered by climber	Transplant	Falls within proposed work area	LCSD
T035	<i>Leucaena leucocephala</i>	銀合歡	0.120	4.0	4.0	Fair	Poor	Low	High	Forked	Retain	No conflict with proposed works	LCSD
T037	<i>Carica papaya</i>	番木瓜	0.180	4.5	2.0	Fair	Fair	Low	High	-	Retain	No conflict with proposed works	LCSD

* LCSD - Leisure and Cultural Services Department