

Consultancy Agreement No. NEX/2213

Environmental Impact Assessment (EIA) Study for the Shatin to Central Link Protection Works at Causeway Bay Typhoon Shelter





MTR Corporation Limited

Consultancy Agreement No. NEX/2213

**Environmental Impact Assessment
(EIA) Study for Shatin to Central Link
Protection Works at
Causeway Bay Typhoon Shelter****Final Environmental Monitoring and Audit
Manual**

November 2010

	Name	Signature
Prepared & Checked:	Joanne Tsoi	
Reviewed & Approved:	Freeman Cheung	

Version: B

Date: 29 November 2010

Disclaimer

This Environmental Impact Assessment (EIA) Report is prepared for MTR Corporation Limited and is given for its sole benefit in relation to and pursuant to EIA Study for Shatin to Central Link Protection Works at Causeway Bay Typhoon Shelter under Agreement No. NEX/2213 and may not be disclosed to, quoted to or relied upon by any person other than MTR Corporation Limited without our prior written consent. No person (other than MTR Corporation Limited) into whose possession a copy of this EIA report comes may rely on this EIA report without our express written consent and MTR Corporation Limited may not rely on it for any purpose other than as described above.

AECOM Asia Co. Ltd.

11/F, Grand Central Plaza, Tower 2, 138 Shatin Rural Committee Road, Shatin, NT, Hong Kong
Tel: (852) 3105 8686 Fax: (852) 2317 7609 www.aecom.com

TABLE OF CONTENTS

		Page
1.	INTRODUCTION	1-1
	Project Background.....	1-1
	Project Scope.....	1-1
	Purpose of the Manual.....	1-2
	Project Organisation	1-3
	Structure of the EM&A Manual.....	1-4
2.	WATER QUALITY	2-1
	Water Quality Parameters.....	2-1
	Monitoring Equipment for Marine Water Quality Monitoring.....	2-1
	Laboratory Measurement / Analysis for Marine Water.....	2-2
	Marine Water Monitoring Locations	2-3
	Baseline Marine Water Monitoring.....	2-3
	Impact Marine Water Monitoring.....	2-3
	Post-construction Marine Water Monitoring.....	2-4
	Field Log for Marine Water Monitoring	2-4
	Construction Site Audits.....	2-5
	Event and Action Plan for Construction Water Quality	2-5
	Mitigation of Adverse Environmental Impacts.....	2-6
3.	NOISE	3-1
	Introduction	3-1
	Noise Parameters	3-1
	Monitoring Equipment and Methodology	3-1
	Noise Monitoring Locations	3-1
	Baseline Monitoring	3-2
	Impact Monitoring	3-2
	Event and Action Plan.....	3-2
	Mitigation Measures.....	3-5
4.	AIR QUALITY	4-1
	Introduction	4-1
	Objectives of Dust Monitoring.....	4-1
	Monitoring Parameters and Equipment	4-1
	Proposed Dust Monitoring Stations	4-2
	Baseline Monitoring	4-3
	Impact Monitoring	4-4
	Compliance Assessment.....	4-5
	Event and Action Plan.....	4-5
	Mitigation Measures.....	4-8
5.	WASTE MANAGEMENT IMPLICATIONS	5-1
	Introduction	5-1
	Mitigation Measures.....	5-1
6.	SITE ENVIRONMENTAL AUDIT	6-1
	Site Inspection	6-1
	Compliance with Legal and Contractual Requirements.....	6-1
	Environmental Complaints	6-2
7.	REPORTING	7-1
	Introduction	7-1
	Baseline Monitoring Report	7-1
	Monthly EM&A Reports.....	7-2

First Monthly EM&A Report	7-2
Subsequent Monthly EM&A Reports	7-3
Quarterly EM&A Summary Reports	7-5
Final EM&A Review Report	7-6
Data Keeping	7-7
Interim Notifications of Environmental Quality Limit Exceedances.....	7-7

List of Tables

Table 2.1	Analytical Methods to be applied to Marine Water Quality Samples
Table 2.2	Proposed Marine Water Quality Stations for Baseline and Impact Monitoring
Table 2.3	Proposed Marine Water Quality Monitoring Frequency and Parameters
Table 2.4	Action and Limit Levels for Marine Water Quality at Seawater Intakes
Table 2.5	Event and Action Plan for Marine Water Quality
Table 3.1	Noise Monitoring Stations during Construction Phase
Table 3.2	Action and Limit Levels for Construction Noise
Table 3.3	Event and Action Plan for Construction Noise Monitoring
Table 4.1	Proposed Dust Monitoring Locations
Table 4.2	Summary of Dust Monitoring Programme
Table 4.3	Proposed Action and Limit Levels for Impact Monitoring
Table 4.4	Event and Action Plan for Construction Dust Monitoring

List of Figures

NEX2213/C/331/ENS/M50/501	Project Site Plan
NEX2213/C/331/ENS/M50/502	General Layout Plan (Sheet 1 of 2)
NEX2213/C/331/ENS/M50/503	General Layout Plan (Sheet 2 of 2)
NEX2213/C/331/ENS/M62/501	Project Organisation
NEX2213/C/331/ENS/M62/510	Locations of Water Quality Monitoring Stations
NEX2213/C/331/ENS/M62/520	Locations of Noise Monitoring Stations
NEX2213/C/331/ENS/M62/530	Locations of Dust Monitoring Stations

List of Appendices

Appendix A	Implementation Schedule and Recommended Mitigation Measures
Appendix B1	Water Quality Monitoring Data Record Sheet
Appendix B2	Construction Noise Monitoring Field Record Sheet
Appendix B3	Data Record Sheet for TSP Monitoring
Appendix C	Sample of the Interim Notification