

Appendix 10.7 Calculation of Cumulative Construction Ground-borne Noise

From PME

NSR No. **HH9**
Name **Harbourfront Horizon**

Calculation of construction ground-borne noise arising from SCL (HUH - ADM) works in Hung Hom area

PME Hydraulic Breaker								Assumption
Item	Description	16	31.5	63	125	250	500	Hz
	Octave Band Frequency							
	rms velocity	0.06	0.07	0.06	0.05	0.062	0.12	mm/s
1	Vibration Velocity, ref 10 ⁻⁶ mm/s	95	97	96	94	96	102	dB(V)
2	Ro	5.5	5.5	5.5	5.5	5.5	5.5	m
	R	220	220	220	220	220	220	m
	Distance Attenuation	-32	-32	-32	-32	-32	-32	dB
3	Soil / Rock Damping	0	0	0	0	0	0	dB
4	Building Coupling Loss	0	0	0	0	0	0	dB
5	Floor to Floor Attenuation	-2	-2	-2	-2	-2	-2	dB
6	Conversion from Vibration to Noise	-27	-27	-27	-27	-27	-27	dB
7	Conversion to A-weighted Noise	-57	-39	-26	-16	-8.6	-3.2	dB(A)
	Individual Groundborne Noise	-22	-4	9	17	26	37	dB(A)
	Predicted Groundborne Noise for ONE Hydraulic Breaker Operation							38 dB(A)

Note:
The modified rig is mainly used for excavation of soil during construction of diaphragm wall. However, it would also be used in minor rock chiselling in order to toe in the diaphragm wall into the the rock. In view of similar nature of rock chiseling by modified rig and rock breaking by hydraulic breaker, the rms velocity for hydraulic breaker, that has been used in KSL EIA (Appendix 7-1), is adopted for assessment.

PME Drill Rig				Assumption
	Using the calculated hydraulic breaker noise to correct to Rock Drill Noise	5.1	dB(A)	20log(0.536/0.298) Site measurement in KSL EIA Appendix 7-1
	Predicted Groundborne Noise for ONE drill rig operation	43	dB(A)	

PME Hand-held Breaker				Assumption
	Using the calculated hydraulic breaker noise to correct to Hand-held Breaker Noise	-0.6	dB(A)	20log(0.279/0.298) Site measurement in KSL EIA Appendix 7-1
	Predicted Groundborne Noise for ONE Hand-held breaker operation	37	dB(A)	

Calculation of construction ground-borne noise arising from South Approach Tunnel & related works of SCL (MKK - HUH)

PME Hydraulic Breaker								Assumption
Item	Description	16	31.5	63	125	250	500	Hz
	Octave Band Frequency							
	rms velocity	0.06	0.07	0.06	0.05	0.062	0.12	mm/s
1	Vibration Velocity, ref 10 ⁻⁶ mm/s	95	97	96	94	96	102	dB(V)
2	Ro	5.5	5.5	5.5	5.5	5.5	5.5	m
	R	220	220	220	220	220	220	m
	Distance Attenuation	-32	-32	-32	-32	-32	-32	dB
3	Soil / Rock Damping	0	0	0	0	0	0	dB
4	Building Coupling Loss	0	0	0	0	0	0	dB
5	Floor to Floor Attenuation	-2	-2	-2	-2	-2	-2	dB
6	Conversion from Vibration to Noise	-27	-27	-27	-27	-27	-27	dB
7	Conversion to A-weighted Noise	-57	-39	-26	-16	-8.6	-3.2	dB(A)
	Individual Groundborne Noise	-22	-4	9	17	26	37	dB(A)
	Predicted Groundborne Noise for ONE Hydraulic Breaker Operation							38 dB(A)

Note:
The modified rig is mainly used for excavation of soil during construction of diaphragm wall. However, it would also be used in minor rock chiselling in order to toe in the diaphragm wall into the the rock. In view of similar nature of rock chiseling by modified rig and rock breaking by hydraulic breaker, the rms velocity for hydraulic breaker, that has been used in KSL EIA (Appendix 7-1), is adopted for assessment.

PME Drill Rig				Assumption
	Using the calculated hydraulic breaker noise to correct to Rock Drill Noise	5.1	dB(A)	20log(0.536/0.298) Site measurement in KSL EIA Appendix 7-1
	Predicted Groundborne Noise for ONE drill rig operation	43	dB(A)	

PME Hand-held Breaker				Assumption
	Using the calculated hydraulic breaker noise to correct to Hand-held Breaker Noise	-0.6	dB(A)	20log(0.279/0.298) Site measurement in KSL EIA Appendix 7-1
	Predicted Groundborne Noise for ONE Hand-held breaker operation	37	dB(A)	

PME Pile Rig				Assumption
	Using the calculated hydraulic breaker noise to correct to pipepile noise	6.6	dB(A)	20log(0.638/0.298) Site measurement in KSL EIA Appendix 7-1
	Predicted Groundborne Noise for ONE pile rig operation	44	dB(A)	

Cumulative Construction Ground-borne Noise Level at HH9

Period: Nov-2014

Project	Construction activities	Type of PME	No. of PME	Predicted Ground-borne Noise Level	Cumulative Ground-borne Noise Level
SCL (HUH ADM)	Demolition of freight building	Hydraulic Breaker	2	41	43
SCL (MKK HUH)	Demolition of existing columns at Area H2	Hydraulic Breaker	1	38	

Period: Jan-2015

Project	Construction activities	Type of PME	No. of PME	Predicted Ground-borne Noise Level	Cumulative Ground-borne Noise Level
SCL (HUH ADM)	Demolition of freight building and construction of cofferdam wall	Hydraulic Breaker	2	45	49
		Drill Rig	1		
SCL (MKK HUH)	Construction of diaphragm wall at Area H1 and excavation works at Area H3	Modified Rig	2	46	
		Piling Rig	1		

Period: Feb - Aug 2015

Project	Construction activities	Type of PME	No. of PME	Predicted Ground-borne Noise Level	Cumulative Ground-borne Noise Level
SCL (HUH ADM)	Construction of cofferdam wall for HUH Landfall	Drill Rig	1	43	45
SCL (MKK HUH)	Construction of diaphragm wall at Area H1	Modified Rig	2	41	

Period: Sep-2015

Project	Construction activities	Type of PME	No. of PME	Predicted Ground-borne Noise Level	Cumulative Ground-borne Noise Level
SCL (HUH ADM)	Construction of cofferdam wall for HUH Landfall	Drill Rig	1	43	48
SCL (MKK HUH)	Demolition of IMC and construction of diaphragm wall	Hydraulic Breaker	1	47	
		Drill Rig	2		

Period: Oct-2015

Project	Construction activities	Type of PME	No. of PME	Predicted Ground-borne Noise Level	Cumulative Ground-borne Noise Level
SCL (HUH ADM)	Excavation at HUH Landfall	Hydraulic Breaker	1	41	48
		Hand-held Breaker	1		
SCL (MKK HUH)	Demolition of IMC and construction of diaphragm wall	Hydraulic Breaker	1	47	
		Drill Rig	2		

Period: Nov - Dec 2015

Project	Construction activities	Type of PME	No. of PME	Predicted Ground-borne Noise Level	Cumulative Ground-borne Noise Level
SCL (HUH ADM)	Excavation at HUH Landfall	Hydraulic Breaker	5	49	49
		Hand-held Breaker	11		
SCL (MKK HUH)	Demolition of IMC / Modification to existing EVA structures	Hydraulic Breaker	1	38	

Period: Jan - Feb 2016

Project	Construction activities	Type of PME	No. of PME	Predicted Ground-borne Noise Level	Cumulative Ground-borne Noise Level
SCL (HUH ADM)	Excavation at HUH Landfall	Hydraulic Breaker	4	49	49
		Hand-held Breaker	10		
SCL (MKK HUH)	Modification to existing EVA structures	Hydraulic Breaker	1	38	