

Appendix 5.7D

Unmitigated Construction Noise Impacts (East Portion)

Project : Central Kowloon Route

Title : Construction Noise Calculation

Scenario : Unmitigated Scenario

Subtitle: East Portion

Activities	2015												2016												2017																		
	Jan	Feb	March	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec	Jan	Feb	March	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec	Jan	Feb	March	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec							
Cut and Cover Tunnel Worksite S1 3001 Decant Disused Vehicular Pier Elevated Structure (PTI Phase 1)	125	125	125	125	125	125																																					
Cut and Cover Tunnel Worksite S2 3002 Construction of Noise Enclosure (PTI Phase 2) 3003 Shaft Excavation							118	118	118																																		
Cut and Cover Tunnel Worksite S3a 3101 Diaphragm walls (PTI Phase 3)							118	118	118	118	118	118																															
Cut and Cover Tunnel Worksite S3b 3101 Diaphragm walls (PTI Phase 3)							118	118	118	118	118	118																															
Cut and Cover Tunnel Worksite S3c 3102 Excavation and Structures (PTI Phase 3) 3102.1 Tunnel Box (Phase 1) 3102.2 Backfill and Restoration (Phase 1)													124	124	124	124	124	124	124						122	122	122	122	122	122	122	122	120	120	120								
Cut and Cover Tunnel Worksite S4a 3103 Diaphragm Walls (PTI Phase 4)																																											
Cut and Cover Tunnel Worksite S4b 3103 Diaphragm Walls (PTI Phase 4)																																											
Cut and Cover Tunnel Worksite S4c 3104 Excavation and Structures (PTI Phase 4) 3104.1 Tunnel Box (Phase 2) 3104.2 Backfill and Restoration (Phase 2)																																											
Cut and Cover Tunnel Worksite S4d 3104 Excavation and Structures (PTI Phase 4) 3104.1 Tunnel Box (Phase 2) 3104.2 Backfill and Restoration (Phase 2)																																											
Cut and Cover Tunnel Worksite S5 3105 Excavation and Structures (PTI Phase 5-remaining C&C Tunnel construction at Access Shaft) 3105.1 Tunnel Box (Phase 3) 3105.2 Backfill and Restoration (Phase 3)																																											
Construction of Landing Step S6 Construction of Landing Step	122	122	122	122	122	122	122	122	122																																		
Underwater Tunnel Worksite S7 Underwater Tunnel (Phase 1) - Stone Columns Construction	120	120	120	120	120	120																																					
Underwater Tunnel Worksite S8 Underwater Tunnel (Phase 1) - Seawall Construction	123	123	123	123	123	123																																					
Underwater Tunnel Worksite S9 Underwater Tunnel (Phase 1) - Temporary Reclamation							122	122																																			
Underwater Tunnel Worksite S10 Underwater Tunnel (Phase 1) - Diaphragm Walls									122	122	122	122	122																														
Underwater Tunnel Worksite S11 Underwater Tunnel (Phase 1) - Excavation Underwater Tunnel (Phase 1) - Tunnel Box Underwater Tunnel (Phase 1) - Backfill													120	120	120	120	120	120						122	122	122	122	122															
Underwater Tunnel Worksite S12a Underwater Tunnel (Phase 1) - Restoration																																											
Underwater Tunnel Worksite S12b Underwater Tunnel (Phase 1) - Restoration																																											
Underwater Tunnel Worksite S13 3206 Demolish Ma Tau Kok Public Pier 3206 Staged handover of Temporary PTI	122	122	122																																								
Underwater Tunnel Worksite S14a Underwater Tunnel (Phase 1) - Dredging																									114	114																	
Underwater Tunnel Worksite S14b Underwater Tunnel (Phase 1) - Dredging																									114	114																	
Underwater Tunnel Worksite S15a Underwater Tunnel (Phase 2) - Stone Columns Construction																																											
Underwater Tunnel Worksite S15b Underwater Tunnel (Phase 2) - Stone Columns Construction																																											
Underwater Tunnel Worksite S16 Underwater Tunnel (Phase 2) - Seawall Construction																																											
Underwater Tunnel Worksite S17 Underwater Tunnel (Phase 2) - Seawall Construction																																											
Underwater Tunnel Worksite S18 Underwater Tunnel (Phase 2) - Temporary Reclamation																																											
Underwater Tunnel Worksite S19a Underwater Tunnel (Phase 2) - Diaphragm Walls																																											
Underwater Tunnel Worksite S19b Underwater Tunnel (Phase 2) - Diaphragm Walls																																											

Project : Central Kowloon Route

Title : Construction Noise Calculation

Scenario : Unmitigated Scenario

Subtitle: East Portion

Activities	2015												2016												2017											
	Jan	Feb	March	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec	Jan	Feb	March	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec	Jan	Feb	March	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec
Underwater Tunnel Worksite S20 Underwater Tunnel (Phase 2) - Excavation Underwater Tunnel (Phase 2) - Tunnel Box Underwater Tunnel (Phase 2) - Backfill																																				
Underwater Tunnel Worksite S21 Underwater Tunnel (Phase 2) - Restoration																																				
Depressed Road Worksite S22 3301 Diaphragm wall	118	118	118	118	118	118	118	118	118	118	118	118																								
Depressed Road Worksite S23 3301 Site Formation, Levelling and Excavation Works	118	118	118	118	118	118	118	118	118	118	118	118																								
Depressed Road Worksite S24 3302 Site Formation, levelling & excavation works 3302 Construction & Paving Works	124	124	124	124	124	124	124																													
Depressed Road Worksite S25 3303 Site Formation, levelling & excavation works 3303 Construction & Paving Works													122	122	122	122	122	122																		
Depressed Road Worksite S26 3303 Site Formation, levelling & excavation works 3303 Construction & Paving Works													122	122	122	122	122	122																		
Connecting Road and Flyover Worksite S27 3401 Site Formation, levelling & Excavation works 3401 Construction & Paving Works 3401 Fitting Works	124	124																																		
Connecting Road and Flyover Worksite S28 3402 Site Formation, levelling & Excavation works 3402 Construction & Paving Works 3402 Fitting Works	124	124																																		
Connecting Road and Flyover Worksite S29 (Slip Road S1, S2,S7, S8, S9) 3403 Site Formation, levelling & Excavation works 3403 Construction & Paving Works 3403 Fitting Works																																				
Connecting Road and Flyover Worksite S30 (Slip Road S3) 3404 Site Formation, levelling & Excavation works 3404 Construction & Paving Works 3404 Fitting Works																																				
Connecting Road and Flyover Worksite S31 3405 Decant of Fire Station	125	125	125																																	
Connecting Road and Flyover Worksite S32 (ring road) 3405 Site Formation, levelling & Excavation works 3405 Construction & Paving Works 3405 Fitting Works																																				
Connecting Road and Flyover Worksite S33 (Slip Road S4) 3405 Site Formation, levelling & Excavation works 3405 Construction & Paving Works 3405 Fitting Works																																				
Connecting Road and Flyover Worksite S34 3406 Foundation Works for Admin/ Ventilation Building in Kai Tak 3406 Construction of Admin and Ventilation Building																																				
Connecting Road and Flyover Worksite S35 3406 Foundation Works for Admin/ Ventilation Building in Kai Tak 3406 Construction of Admin and Ventilation Building																																				
Connecting Road and Flyover Worksite S36 3406 Construction of Ventilation Duct																																				
Connecting Road and Flyover Worksite S37 3407 Site Formation, levelling & Excavation works 3407 Construction & Paving Works 3407 Fitting Works																																				
Connecting Road and Flyover Worksite S38 3408 Site Formation, levelling & Excavation works 3408 Construction & Paving Works 3408 Fitting Works																																				
PTI Landscape Deck Worksite S39 Construct Landscape Deck and Finishing Works																																				

Project : Central Kowloon Route

Title : Construction Noise Calculation

Scenario : Unmitigated Scenario

Subtitle: East Portion

Activities	2015												2016												2017																
	Jan	Feb	March	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec	Jan	Feb	March	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec	Jan	Feb	March	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec					
Summary of SWLs																																									
Cut and Cover Tunnel Worksite S1	125	125	125	125	125	125	0	0	118	118	118	124	124	124	124	124	124	124	124	124	124	124	124	124	124	124	124	124	124	124	124	124	124	124	124						
Cut and Cover Tunnel Worksite S2	0	0	0	0	0	0	0	0	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118					
Cut and Cover Tunnel Worksite S3a	0	0	0	0	0	0	0	0	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118					
Cut and Cover Tunnel Worksite S3b	0	0	0	0	0	0	0	0	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118					
Cut and Cover Tunnel Worksite S3c	0	0	0	0	0	0	0	0	0	0	0	0	0	0	124	124	124	124	124	124	124	124	124	124	124	124	124	124	124	124	124	124	124	124	124	124					
Cut and Cover Tunnel Worksite S4a	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
Cut and Cover Tunnel Worksite S4b	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
Cut and Cover Tunnel Worksite S4c	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
Cut and Cover Tunnel Worksite S4d	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
Cut and Cover Tunnel Worksite S5	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
Construction of Landing Step S6	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122				
Underwater Tunnel Worksite S7	120	120	120	120	120	120	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
Underwater Tunnel Worksite S8	123	123	123	123	123	123	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
Underwater Tunnel Worksite S9	0	0	0	0	0	0	0	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122				
Underwater Tunnel Worksite S10	0	0	0	0	0	0	0	0	0	0	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122				
Underwater Tunnel Worksite S11	0	0	0	0	0	0	0	0	0	0	0	0	0	120	120	120	120	120	124	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122					
Underwater Tunnel Worksite S12a	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
Underwater Tunnel Worksite S12b	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Underwater Tunnel Worksite S13	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122			
Underwater Tunnel Worksite S14a	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Underwater Tunnel Worksite S14b	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Underwater Tunnel Worksite S15a	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Underwater Tunnel Worksite S15b	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Underwater Tunnel Worksite S16	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Underwater Tunnel Worksite S17	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Underwater Tunnel Worksite S18	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Underwater Tunnel Worksite S19a	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Underwater Tunnel Worksite S19b	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Underwater Tunnel Worksite S20	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Underwater Tunnel Worksite S21	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Depressed Road Worksite S22	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118			
Depressed Road Worksite S23	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118	118		
Depressed Road Worksite S24	124	124	124	124	124	124	124	124	123	123	123	123	123	123	123	123	123	123	123	123	123	123	123	123	123	123	123	123	123	123	123	123	123	123	123	123	123	123			
Depressed Road Worksite S25	0	0	0	0	0	0	0	0	0	0	0	0	0	0	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122	122			
Depressed Road Worksite S26	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Connecting Road and Flyover Worksite S27	124	124	123	123	119	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Connecting Road and Flyover Worksite S28	124	124	123	123	123	119	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Connecting Road and Flyover Worksite S29 (Slip Road S1, S2,S7, S8, S9)	0	0	0	0	0	0	124	124	124	123	123	123	123	123	119	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Connecting Road and Flyover Worksite S30 (Slip Road S3)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Connecting Road and Flyover Worksite S31	125	125	125	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Connecting Road and Flyover Worksite S32 (ring road)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Connecting Road and Flyover Worksite S33 (Slip Road S4)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Connecting Road and Flyover Worksite S34	0																																								

Project : Central Kowloon Route

Title : Construction Noise Calculation

Scenario : Unmitigated Scenario

Subtitle: East Portion

Activities	2018												2019												2020													
	Jan	Feb	March	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec	Jan	Feb	March	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec	Jan	Feb	March	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec		
Cut and Cover Tunnel Worksite S1 3001 Decant Disused Vehicular Pier Elevated Structure (PTI Phase 1)																																						
Cut and Cover Tunnel Worksite S2 3002 Construction of Noise Enclosure (PTI Phase 2)																																						
3003 Shaft Excavation	124	124	124	124	124	124	124	124	124	124	124	124	124	124	124																							
Cut and Cover Tunnel Worksite S3a 3101 Diaphragm walls (PTI Phase 3)																																						
Cut and Cover Tunnel Worksite S3b 3101 Diaphragm walls (PTI Phase 3)																																						
Cut and Cover Tunnel Worksite S3c 3102 Excavation and Structures (PTI Phase 3) 3102.1 Tunnel Box (Phase 1) 3102.2 Backfill and Restoration (Phase 1)																																						
Cut and Cover Tunnel Worksite S4a 3103 Diaphragm Walls (PTI Phase 4)																																						
Cut and Cover Tunnel Worksite S4b 3103 Diaphragm Walls (PTI Phase 4)																																						
Cut and Cover Tunnel Worksite S4c 3104 Excavation and Structures (PTI Phase 4) 3104.1 Tunnel Box (Phase 2) 3104.2 Backfill and Restoration (Phase 2)	124	124																																				
Cut and Cover Tunnel Worksite S5 3105 Excavation and Structures (PTI Phase 5-remaining C&C Tunnel construction at Access Shaft) 3105.1 Tunnel Box (Phase 3) 3105.2 Backfill and Restoration (Phase 3)																124	124	124																				
Construction of Landing Step S6 Construction of Landing Step																																						
Underwater Tunnel Worksite S7 Underwater Tunnel (Phase 1) - Stone Columns Construction																																						
Underwater Tunnel Worksite S8 Underwater Tunnel (Phase 1) - Seawall Construction																																						
Underwater Tunnel Worksite S9 Underwater Tunnel (Phase 1) - Temporary Reclamation																																						
Underwater Tunnel Worksite S10 Underwater Tunnel (Phase 1) - Diaphragm Walls																																						
Underwater Tunnel Worksite S11 Underwater Tunnel (Phase 1) - Excavation Underwater Tunnel (Phase 1) - Tunnel Box Underwater Tunnel (Phase 1) - Backfill																																						
Underwater Tunnel Worksite S12a Underwater Tunnel (Phase 1) - Restoration																																						
Underwater Tunnel Worksite S12b Underwater Tunnel (Phase 1) - Restoration																																						
Underwater Tunnel Worksite S13 3206 Demolish Ma Tau Kok Public Pier 3206 Staged handover of Temporary PTI																																						
Underwater Tunnel Worksite S14a Underwater Tunnel (Phase 1) - Dredging																																						
Underwater Tunnel Worksite S14b Underwater Tunnel (Phase 1) - Dredging																																						
Underwater Tunnel Worksite S15a Underwater Tunnel (Phase 2) - Stone Columns Construction																																						
Underwater Tunnel Worksite S15b Underwater Tunnel (Phase 2) - Stone Columns Construction																																						
Underwater Tunnel Worksite S16 Underwater Tunnel (Phase 2) - Seawall Construction																																						
Underwater Tunnel Worksite S17 Underwater Tunnel (Phase 2) - Seawall Construction																																						
Underwater Tunnel Worksite S18 Underwater Tunnel (Phase 2) - Temporary Reclamation																																						
Underwater Tunnel Worksite S19a Underwater Tunnel (Phase 2) - Diaphragm Walls	120	120	120	120																																		
Underwater Tunnel Worksite S19b Underwater Tunnel (Phase 2) - Diaphragm Walls	120	120	120	120																																		

Project : Central Kowloon Route

Title : Construction Noise Calculation

Scenario : Unmitigated Scenario

Subtitle: East Portion

Activities	2018												2019												2020											
	Jan	Feb	March	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec	Jan	Feb	March	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec	Jan	Feb	March	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec
Underwater Tunnel Worksite S20																																				
Underwater Tunnel (Phase 2) - Excavation			120	120	120	120	120	120																												
Underwater Tunnel (Phase 2) - Tunnel Box								122	122	122	122	122																								
Underwater Tunnel (Phase 2) - Backfill													122	122																						
Underwater Tunnel Worksite S21																																				
Underwater Tunnel (Phase 2) - Restoration														128	128	128																				
Depressed Road Worksite S22																																				
3301 Diaphragm wall																																				
Depressed Road Worksite S23																																				
3301 Site Formation, Levelling and Excavation Works																																				
Depressed Road Worksite S24																																				
3302 Site Formation, levelling & excavation works																																				
3302 Construction & Paving Works																																				
Depressed Road Worksite S25																																				
3303 Site Formation, levelling & excavation works																																				
3303 Construction & Paving Works																																				
Depressed Road Worksite S26																																				
3303 Site Formation, levelling & excavation works																																				
3303 Construction & Paving Works																																				
Connecting Road and Flyover Worksite S27																																				
3401 Site Formation, levelling & Excavation works																																				
3401 Construction & Paving Works																																				
3401 Fitting Works																																				
Connecting Road and Flyover Worksite S28																																				
3402 Site Formation, levelling & Excavation works																																				
3402 Construction & Paving Works																																				
3402 Fitting Works																																				
Connecting Road and Flyover Worksite S29 (Slip Road S1, S2,S7, S8, S9)																																				
3403 Site Formation, levelling & Excavation works																																				
3403 Construction & Paving Works																																				
3403 Fitting Works																																				
Connecting Road and Flyover Worksite S30 (Slip Road S3)																																				
3404 Site Formation, levelling & Excavation works																																				
3404 Construction & Paving Works																																				
3404 Fitting Works																																				
Connecting Road and Flyover Worksite S31																																				
3405 Decant of Fire Station																																				
Connecting Road and Flyover Worksite S32 (ring road)																																				
3405 Site Formation, levelling & Excavation works																																				
3405 Construction & Paving Works																																				
3405 Fitting Works																																				
Connecting Road and Flyover Worksite S33 (Slip Road S4)																																				
3405 Site Formation, levelling & Excavation works																																				
3405 Construction & Paving Works																																				
3405 Fitting Works																																				
Connecting Road and Flyover Worksite S34																																				
3406 Foundation Works for Admin/ Ventilation Building in Kai Tak																																				
3406 Construction of Admin and Ventilation Building																																				
Connecting Road and Flyover Worksite S35																																				
3406 Foundation Works for Admin/ Ventilation Building in Kai Tak																																				
3406 Construction of Admin and Ventilation Building																																				
Connecting Road and Flyover Worksite S36																																				
3406 Construction of Ventilation Duct			120	120																																
Connecting Road and Flyover Worksite S37																																				
3407 Site Formation, levelling & Excavation works																																				
3407 Construction & Paving Works																																				
3407 Fitting Works																																				
Connecting Road and Flyover Worksite S38																																				
3408 Site Formation, levelling & Excavation works																																				
3408 Construction & Paving Works																																				
3408 Fitting Works																																				
PTI Landscape Deck Worksite S39																																				
Construct Landscape Deck and Finishing Works																																				
																									123	123	123	123	123	123	123	123	123	123	123	123

