

Appendix 5.8A

**SWL of Construction Activities
(Barging Point)**

Project : Central Kowloon Route
Title : Plant Inventory
Subtitle: Barging Point

CKR- Construction of Barging Point				SWL of Single PME	Total SWL
Worksite S1					
Activity	Months	PME	Units	Unmitigated	Unmitigated
Mobilization / Site Clearance & Site Office	Jan 2015 - Feb 2015	Air Compressor (CNP002) (100%)	1	102	102
		Hand Held Breaker (CNP024) (100%)	2	108	111
		Dump Truck (CNP067) (100%)	1	117	117
		Excavator/Loader, Wheeled/Tracked (CNP081) (100%)	2	112	115
		Saw, Circular Wood (CNP201) (100%)	1	108	108
Construction of Conveyor Belt	Feb 2015- Mar 2015	Air Compressor (CNP002) (50%)	1	99	99
		Concrete Lorry Mixer (CNP044) (50%)	1	106	106
		Crane Mobile (CNP048) (50%)	1	109	109
		Dump Truck (CNP067) (80%)	1	116	116
		Poker, Vibratory, Hand Held (CNP170) (100%)	2	113	116
Operation (Barge)	Apr 2015 - Aug 2019	Derrick Barge (CNP061) (100%)	2	104	107
		Tug boat (CNP221) (100%)	2	110	113
Operation (Other Plants)	Apr 2015 - Aug 2019	Excavator/Loader, Wheeled/Tracked (CNP081) (100%)	1	112	112
		Conveyor (CNP041) (100%)	1	90	90
		Crane Mobile (CNP048) (100%)	1	112	112
		Dump Truck (CNP067) (100%)	2	117	120
Demolition of Barging Point	Sep 2019	Concrete Lorry Mixer (CNP044) (100%)	1	109	109
		Crane Mobile (CNP048) (100%)	1	112	112
		Excavator/Loader, Wheeled/Tracked (CNP081) (100%)	1	112	112
		Lorry, Crane/Grab (CNP145) (100%)	1	105	105