

Appendix 4.8E

**Summary of Mitigated
Construction Noise Level of the
Project**

Appendix 4.8E - Mitigated Construction Noise Level from the Project

NSR	Noise Criteria, dB(A)	Max	SPL (dB(A))																							
			2014												2015											
			Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
IHV	75	68	52	52	66	66	67	67	68	68	68	68	63	61	61	61	61	61	61	61	61	61	61	0	0	
FR	75	67	51	51	65	65	66	66	67	67	67	67	62	60	60	60	60	60	60	60	60	60	60	0	0	
PAV	75	68	53	53	67	67	68	68	68	68	68	68	64	62	62	62	62	62	62	62	62	62	62	0	0	
CG	75	67	54	54	64	65	66	66	67	66	66	66	63	62	62	62	62	62	62	62	62	62	62	0	0	
LKPC	70	65	54	54	62	64	65	65	65	65	65	65	62	61	61	61	61	61	61	61	61	62	62	0	0	
YCS	70	64	53	53	62	63	64	64	64	64	64	64	61	60	60	60	60	60	60	60	60	61	61	0	0	
SRT	75	73	65	65	65	72	72	72	73	73	73	73	73	73	73	68	68	68	68	68	68	72	72	0	0	
CLS	75	74	69	69	69	72	72	72	74	74	74	74	74	74	74	68	68	68	68	68	68	72	72	0	0	
ASD1	75	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	68	68	68	68	68	68	
ASD2	75	75	74	74	74	74	74	74	75	75	75	75	75	75	75	75	75	75	73	73	73	73	73	73	73	
FSDO	75	62	62	62	62	62	62	62	62	62	62	62	62	62	62	62	62	62	60	60	60	60	60	60	60	
ASC	75	69	69	69	69	69	69	69	69	69	69	69	69	69	69	69	69	69	68	68	68	68	68	68	68	
LCMS	70	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	59	59	59	59	59	59	59	
VT	75	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	61	60	60	60	60	60	60	60	
GB	75	64	64	64	64	64	64	64	64	64	64	64	64	64	64	64	64	64	62	62	62	62	62	62	62	
YTB	75	72	72	72	72	72	72	72	72	72	72	72	72	72	72	72	72	72	71	71	71	71	71	71	71	