EIA Report (September 2013)

Appendix 4.9A
Plant List of the Concurrent
Projects

Appendix 4.9A - Sound Power Level of the Concurrent Projects

Trenchless Cable Duct Crossings at Nga Cheung Road

Stage 1

PME	CNP Code	SWL, dB(A)	No. of Plant	% on time	Sub-toal, dB(A)	Total SWL, dB(A)
Dump truck, 5.5 tonne < gross vehicle weight <38 tonne	CNP 068	105	1	50%	102	
Lorry	CNP 141	112	1	50%	109	115
Generator, standard	CNP 101	108	1	80%	107	115
Excavator, mini-robot mounted	CNP 082	94	2	50%	94	
Breaker, hand-held, mass>35 kg	CNP 026	114	1	60%	112	

Stage 2

PME	CNP Code	SWL,	No. of	% on time	Sub-toal,	Total SWL,
FIVIE	CIVIF Code	dB(A)	Plant	70 OII tIIIIE	dB(A)	dB(A)
Generator, silenced	CNP 102	100	1	80%	99	
Asphalt Paver	CNP 004	109	1	50%	106	110
Road Roller	CNP 185	108	1	50%	105	110
Power Rammer (petrol)	CNP 169	108	1	50%	105	



BLACK & VEATCH HONG KONG LIMITED

25/F, Millennium City 6, 392 Kwun Tong Road, Hong Kong 博威工程顧問有限公司香港九龍觀塘道 392 號創紀之城第六期 25 樓 Tel 電話 +852 2601 1000 • Fax 傳真 +852 2601 3988 Email 電郵 bvhk@bv.com

OUR REF

382706-1732

YOUR REF

DATE

27 August 2012

C0473324

Receives U AUG 2012
File (EDMS) 2512064R - GN
Reywords
Scanned: Y / N
Name Action Info
Return to Archive
Rescan Y / N

DWG/CD KEPTBY(

Distribution List

Dear Sirs,

Outline Agreement No. 4600003274
Transmission Cable Route Selection Consultancy Services
Feasibility Study of Trenchless Cable Duct Crossings at Nga Cheung Road
[Project No.12270]

We have been commissioned by CLP Power Hong Kong Limited to carry out a feasibility study for construction of three cable duct crossings by trenchless method along the northbound lane of Nga Cheung Road. The cable duct crossings are used to house new 132kV cable circuits which form parts of electricity supply for the development of West Kowloon Cultural District. The construction works are scheduled to commence in the second quarter of 2013 and expected to be complete by mid 2015.

As requested by Urban Region (Kowloon), Highways Department, we are pleased to enclose for your comment a copy of Drawings regarding the optimum alignment and sectional profile of the proposed cable duct crossings.

Due to tight project programme for the study, we shall be grateful for your provision of comments on the proposed cable duct crossing by **14 September 2012**. Your early reply will be much appreciated. Should you have any queries, please do not hesitate to contact our Mr. K. L. Tse or Mr. Jeremy Wong at 2601 1000.

Yours faithfully, for and on behalf of BLACK & VEATCH HONG KONG LIMITED

ANDY Y. KWOK PROJECT MANAGER

Encl.

cc:

CLP Power/EPD - Attn: Messrs. L. T. Chow / K.P. Lau







Member of the Association of Consulting Engineers of Hong Kong



OUR REF

382706-1732

YOUR REF

DATE

27 August 2012

| PAGE 2

Distribution List

West Harbour Tunnel Company Limited Administration Building, Western Harbour Crossing, Yau Ma Tei, Kowloon

For the attention of Mr. Keith Kong

Parsons Brinckerhoff (Asia) Limited
7/F, One Kowloon
1 Wang Yuen Street,
Kowloon Bay,
Kowloon
(Consultant of Agreement No. CE44/2011(HY))

Likely Powered Mechanical Equipment for Construction of the CSBCSPS, DWFI compound and associated facilities [Mitigation 1- Quiet Plant]

Sheet Piling

	TM Code / Other	Number of	SWL,	Assume Percentage	Summation	Total SWL,
Type of PME	reference	Equipment	dB(A)	of On-time Usage	of SWL, dB(A)	dB(A)
Piling, vibrating hammer	*	1	115	80%	114	114

Excavation

	TM Code / Other	Number of	SWL,	Assume Percentage	Summation	Total SWL,
Type of PME	reference	Equipment	dB(A)	of On-time Usage	of SWL, dB(A)	dB(A)
Excavator/loader, wheeled/tracked	*	1	94	80%	93	104
Dump truck [1]	*	1	105	80%	104	

Modification Works for Existing Box Culvert (Only for DWFI compound and associated facilities)

		K .				
	TM Code / Other	Number of	SWL,	Assume Percentage	Summation	Total SWL,
Type of PME	reference	Equipment	dB(A)	of On-time Usage	of SWL, dB(A)	dB(A)
Saw/Groover, Concrete (petrol)	203	1	115	80%	114	114
Water pumps, submersible (electric)	283	1	85	80%	84	

Construction of Substructure/Structure

	TM Code / Other	Number of	SWL,	Assume Percentage	Summation	Total SWL,
Type of PME	reference	Equipment	dB(A)	of On-time Usage	of SWL, dB(A)	dB(A)
Crane, mobile/barge mounted (diesel)	QPME-EPD-01058	1	107	80%	106	110
Concrete lorry mixer	044	1	109	60%	107	
Poker, vibratory, hand-held	*	1	102	80%	101	

Backfilling and Extraction of Piles

, , ,						
	TM Code / Other	Number of	SWL,	Assume Percentage	Summation	Total SWL,
Type of PME	reference	Equipment	dB(A)	of On-time Usage	of SWL, dB(A)	dB(A)
Excavator/loader, wheeled/tracked	*	1	94	75%	93	109
Dump truck [1]	*	1	105	80%	104	
Compactor, vibratory	050	1	105	80%	104	
Crane, mobile/barge mounted (diesel)	QPME-EPD-01058	1	107	70%	105	
Piling, diaphragm wall, hydraulic extractor	163	1	90	80%	89	

E&M Installations

	TM Code / Other	Number of	SWL,	Assume Percentage	Summation	Total SWL,
Type of PME	reference	Equipment	dB(A)	of On-time Usage	of SWL, dB(A)	dB(A)
Crane, mobile/barge mounted (diesel)	QPME-EPD-01058	1	107	90%	107	109
Lorry [2]	*	1	105	85%	104	

Finishing and Landscaping Works

	TM Code / Other	Number of	SWL,	Assume Percentage	Summation	Total SWL,
Type of PME	reference	Equipment	dB(A)	of On-time Usage	of SWL, dB(A)	dB(A)
Excavator/loader, wheeled/tracked	081	1	112	50%	109	111
Crane, mobile/barge mounted (diesel)	QPME-EPD-01058	1	107	60%	105	
Lorry [2]	*	1	105	80%	104	

Notes:

SWL = Sound Power Level of a Powered Mechanical Equipment (PME)

TM = Technical Memorandum on Noise from Construction Work other than Percussive Piling

* = Sound Power Levels of Other Commonly Used PME (Source: Guidance Notes for Licence Application in EPD website)

QPME = Quality Powered Mechanical Equipment (Source: An Administrative System on the Use of QPME in EPD website)

[1] = Dump truck, with grab (5.5 tonne < gross vehicle weight < 38 tonne)

[2] = Lorry with crane/grab (5.5 tonne < gross vehicle weight < 38 tonne)

Agreement No. CE1/2012(DS) - Construction of Dry Weather Flow Interceptor at Cherry Street Box Culvert and Other Works - Investigation, Design and Construction Construction Programme

							20	14											20	15					
Stage	Activities	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Designate	d Project (CSBCSPS)																								
1	Sheet Piling																								
2	Excavation																								
3	Construction of Substructure																								
4	Backfilling and Extraction of Piles																								
5	E&M Installations																								
6	Finishing and Landscaping Works																								
Non- deisg	nated Project (CSBC DWFI)																								
1	Sheet Piling																								
2	Excavation																								
3	Modification Works for Existing Box Culvert																								
4	Construction of Structure																								
5	Backfilling and Extraction of Piles																								
6	E&M Installations																								
7	Finishing and Landscaping Works						·															·	·		

Agreement No. CE1/2012(DS) - Construction of Dry Weather Flow Construction Programme

							20	16											20	17					
Stage	Activities	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Designated	Project (CSBCSPS)																								
1	Sheet Piling																							1	
2	Excavation																								
3	Construction of Substructure																							1	
4	Backfilling and Extraction of Piles																							1	
5	E&M Installations																						,	1	
6	Finishing and Landscaping Works																							1	
																								1	
Non- deisg	nated Project (CSBC DWFI)																							1	
1	Sheet Piling																								
2	Excavation																							1	
3	Modification Works for Existing Box Culvert																								
4	Construction of Structure																							1	
5	Backfilling and Extraction of Piles																								
6	E&M Installations																								
7	Finishing and Landscaping Works										-														

Agreement No. CE1/2012(DS) - Construction of Dry Weather Flow Construction Programme

							20	18					
Stage	Activities	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Designate	ed Project (CSBCSPS)												
1	Sheet Piling												
2	Excavation												
3	Construction of Substructure												
4	Backfilling and Extraction of Piles												
5	E&M Installations												
6	Finishing and Landscaping Works												
Non- deis	gnated Project (CSBC DWFI)												
1	Sheet Piling												
2	Excavation												
3	Modification Works for Existing Box Culvert												
4	Construction of Structure												
5	Backfilling and Extraction of Piles												
6	E&M Installations												
7	Finishing and Landscaping Works												