

**Appendix 4.9F**  
**Summary of Mitigated  
Cumulative Construction Noise  
Level**

---

**Appendix 4.9F - Cumulative Construction Noise Level (Mitigated + Con-Current Projects)**

NSR	Noise Criteria, dB(A)	Max	SPL (dB(A))																							
			2014												2015											
			Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
IHV	75	71	68	68	70	70	71	71	68	68	68	70	68	68	68	68	69	69	69	69	69	69	69	68	68	
FR	75	68	64	64	68	68	68	68	67	67	67	68	65	65	65	65	65	65	65	65	65	65	65	64	64	
PAV	75	70	65	66	70	70	70	70	68	68	68	69	67	66	66	66	67	67	67	67	67	67	67	65	65	
CG	75	67	54	54	64	65	66	66	67	66	66	66	63	63	63	63	63	63	64	64	63	63	63	57	57	
LKPC	70	65	54	54	62	64	65	65	65	65	65	65	62	62	62	62	62	62	63	63	62	63	63	57	57	
YCS	70	67	57	57	63	64	65	65	65	65	64	64	61	65	65	66	66	66	67	67	65	65	65	62	62	
SRT	75	74	69	69	69	73	73	73	74	74	74	74	74	74	74	71	71	71	71	68	68	72	72	0	0	
CLS	75	74	70	70	70	73	73	73	74	74	74	74	74	74	74	69	69	69	69	68	68	72	72	0	0	
ASD1	75	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	68	68	68	68	68	68	
ASD2	75	75	74	74	74	74	74	74	75	75	75	75	75	75	75	75	75	75	73	73	73	73	73	73	73	
FSDO	75	74	72	72	73	73	74	74	74	72	72	72	70	69	69	69	68	68	68	68	68	68	68	69	69	
ASC	75	70	70	69	69	69	69	69	69	69	69	69	69	69	69	69	69	69	68	68	68	68	68	68	68	
LCMS	70	69	68	68	68	68	69	69	69	68	67	68	66	66	66	66	65	66	65	65	65	65	65	65	65	
VT	75	71	70	70	71	71	71	71	71	70	69	69	68	67	67	67	66	66	66	65	65	65	65	65	65	
GB	75	69	69	69	69	69	69	69	69	69	68	68	68	68	68	68	67	67	66	65	65	65	65	65	65	
YTB	75	73	73	73	73	73	73	73	73	73	72	72	72	72	72	72	72	72	71	71	71	71	71	71	71	