Project: Tung Chung New Town Extension

Project no.: 219844-70

Title: Measured SEL at Ta Pang Po

Event	Direction	Mic location	Measured SEL, dB(A)	Measurement Distance from Track, m	Train Length [1], m	Speed, km/h	Correction for SEL dB(A)			
							Distance	Speed	Measured SEL (8 cars) at standard condition, dB(A)	Measured SEL (8 cars) adjusted to 1 car at standard condition, dB(A)
AEL	To Hong Kong Station	1	84.5	25	185.0	131	0.0	0.3	84.8	75.8
		2	81.5	50			3.0	0.3	84.8	75.8
		3	79.3	70			4.5	0.3	84.1	75.0
		1	84.9	25	185.0	126	0.0	0.6	85.5	76.5
		2	81.9	50			3.0	0.6	85.5	76.5
		3	79.7	70			4.5	0.6	84.8	75.7
		1	83.8	25	185.0	129	0.0	0.4	84.2	75.2
		2	81.2	50			3.0	0.4	84.6	75.6
		3	79.0	70			4.5	0.4	83.9	74.8
	To Airport	1	81.7	29	185.0	129	0.6	0.4	82.8	73.7
		2	79.6	54			3.3	0.4	83.4	74.3
		3	77.9	74			4.7	0.4	83.0	74.0
		1	81.1	29	185.0	128	0.6	0.5	82.2	73.2
		2	79.1	54			3.3	0.5	82.9	73.9
		3	77.7	74			4.7	0.5	82.9	73.9
		1	80.9	29	185.0	128	0.6	0.5	82.0	73.0
		2	78.9	54			3.3	0.5	82.7	73.7
		3	77.1	74			4.7	0.5	82.3	73.3
TCL	To Hong Kong Station	1	87.3	25	185.0	129	0.0	0.4	87.7	78.7
		2	83.7	50			3.0	0.4	87.1	78.1
		3	81.4	70			4.5	0.4	86.3	77.2
		1	87.1	25	185.0	123	0.0	0.8	87.9	78.9
		2	84.2	50			3.0	0.8	88.0	79.0
		3	82.0	70			4.5	0.8	87.3	78.2
		1	86.8	25	185.0	123	0.0	0.8	87.6	78.6
		2	84.0	50			3.0	0.8	87.8	78.8
		3	81.6	70			4.5	0.8	86.9	77.8
	To Tung Chung	1	84.8	29	185.0	126	0.6	0.6	86.0	77.0
		2	82.4	54			3.3	0.6	86.3	77.3
		3	80.3	74			4.7	0.6	85.6	76.6
		1	84.1	29	185.0	132	0.6	0.2	85.0	75.9
		2	81.7	54			3.3	0.2	85.3	76.2
		3	80.0	74			4.7	0.2	84.9	75.9
		1	84.2	29	185.0	126	0.6	0.6	85.4	76.4
		2	81.6	54			3.3	0.6	85.5	76.5
		3	79.7	74			4.7	0.6	85.0	76.0
		1	82.6	29	185.0	124	0.6	0.7	84.0	75.0
		2	80.3	54			3.3	0.7	84.4	75.4
		3	77.9	74			4.7	0.7	83.3	74.3
		1	82.2	29	185.0	125	0.6	0.7	83.5	74.5
		2	79.5	54			3.3	0.7	83.5	74.5
		3	77.8	74			4.7	0.7	83.2	74.2
							·	Max	88.0	79.0
Source Term in	-	-	86	25.0	185.0	135	0.0	0.0	92.9	83.9
MTRC LAR EIA	-	-	86	25.0	225.0	135	0.0	0.0	93.9	

Notes:

There is no screening structure between the track and the measurement locations.

^[1] Current (Nov 2013) LAR and AEL trains are with 8 cars and are 185m in length

The measurement has been taken in free field condition near a straight ballast track section whereas the measurements data contain both AEL and TCL trains.

