



**Appendix 4.9a Construction Noise Assessment (Mitigated Scenario)**

**Location:** Kowloon

**NAP ID:** MC1

Assessment Floor 3/F

Floor mP.D. 84.9

Construction Activity	SWL, dB(A)	Distance, m [1]	Distance Correction, dB(A)	Screening Correction, dB(A)	Façade Correction, dB(A)	2028				2029				2030				2031																							
						S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A
						45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80
<b>Lion Rock Tunnel Road Widening</b>																																									
<b>Work Zone 8 - Kowloon Side</b>																																									
Site Clearance, tree felling / transplant, utilities diversion	106	88	-46.9	0	3	62	62	62																																	
<b>Road Widening</b>																																									
Pipe Pile Wall / L-Shape Retaining Wall Installation	108	88	-46.9	0	3				64	64																															
Slope Formation Works	108	88	-46.9	0	3														64	64																					
Demolition of Existing K7A Vehicular Bridge/Footbridge	111	146	-51.3	0	3				63	63																															
Construction of K7A Concrete Upstand Bridge	111	146	-51.3	0	3																																				
<b>Road works</b>																																									
Roadworks (Flexible Pavement & Low Noise Road Surfacing), Signage, Drainage	109	88	-46.9	0	3																																				
<b>Landscaping Works</b>																																									
Landscape Works	100	88	-46.9	0	3																																56	56			
Predicted Noise Level, Leq (30mins), dB(A)						62	62	62	67	67	67	67	67	67	67	67	67	67	67	67	67	67	67	67	67	68	65	65	65	65	65	65	65	65	65	65	56	56			

[1] The distances refer to the horizontal distances between the notional source positions in work zones and the concerned NSRs

## Appendix 4.9a Construction Noise Assessment (Mitigated Scenario)

Location: Kowloon

NAP ID: PH2

Assessment Floor: 1/F

Floor mP.D.: 76.7

Construction Activity	SWL, dB(A)	Distance, m [1]	Distance Correction, dB(A)	Screening Correction, dB(A)	Façade Correction, dB(A)	2028				2029				2030				2031																				
						S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A									
						45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77
<b>Lion Rock Tunnel Road Widening</b> <b>Work Zone 8 - Kowloon Side</b> Site Clearance, tree felling / transplant, utilities diversion <b>Road Widening</b> Pipe Pile Wall / L-Shape Retaining Wall Installation Slope Formation Works Demolition of Existing K7A Vehicular Bridge/Footbridge Construction of K7A Concrete Upstand Bridge <b>Road works</b> Roadworks (Flexible Pavement & Low Noise Road Surfacing), Signage, Drainage <b>Landscaping Works</b> Landscape Works Predicted Noise Level, Leq (30mins), dB(A)																																						
106	52	-42.3	0	3		66	66	66																														
108	52	-42.3	0	3						69	69	69	69	69	69	69	69	69	69																			
108	52	-42.3	0	3													68	68	68	68	68	68	68															
111	172	-52.7	0	3				61	61																													
111	172	-52.7	0	3						61	61	61	61	61	61	61	61	61	61	61	61	61	61															
109	52	-42.3	0	3																				70	70	70	70	70	70	70	70	70	70	70	70	70	70	70
100	52	-42.3	0	3																															61	61		
Predicted Noise Level, Leq (30mins), dB(A)						66	66	66	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70		

[1] The distances refer to the horizontal distances between the notional source positions in work zones and the concerned NSRs





Appendix 4.9a Construction Noise Assessment (Mitigated Scenario)

Location: Shatin  
 NAP ID: STTNV1  
 Assessment Floor: G/F  
 Floor mP.D.: 35.2

Construction Activity	SWL, dB(A)	Distance, m [1]	Distance Correction, dB(A)	Screening Correction, dB(A)	Façade Correction, dB(A)	2028				2029				2030				2031				2032				2033																																			
						S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D																
Shatin Side																																																													
<u>Work Zone 1</u>																																																													
<u>Preparatory works</u>																																																													
Site Clearance and Tree felling / transplant	106	45	-41	0	3					68	68	68	68	68																																															
<u>Reprovisioning of Footbridge NF74</u>																																																													
Construction of temporary footbridge	107	96	-47.6	0	3					62	62	62	62	62																																															
Demolition of existing footbridge	102	96	-47.6	0	3										57	57	57			57	57																																								
Construction of new footbridge (including demolition of temporary footbridge)	107	96	-47.6	0	3															62	62	62	62	62	62	62	62	62	62	62	62	62	62	62	62	62	62																								
<u>Road Widening and Installation of Noise Barrier</u>																																																													
<u>Widening works at north bound</u>																																																													
Slope Formation / Upgrading Works	108	45	-41	0	3																																																								
Foundation of Noise Barrier	107	45	-41	0	3																																																								
Pile Cap, L-retaining Wall and Formation of new road	107	45	-41	0	3																																																								
Utilities Diversion	104	45	-41	0	3																																																								
Erection of structural steel post for noise barrier	100	45	-41	0	3																																																								
<u>Widening works at central divider</u>																																																													
Foundation of Noise Barrier	107	45	-41	0	3																																																								
Pile Cap and Footing	107	45	-41	0	3																																																								
Erection of structural steel post for noise barrier	100	45	-41	0	3																																																								
<u>Widening works at south bound</u>																																																													
Slope Formation / Upgrading Works	108	45	-41	0	3																																																								
Foundation of Noise Barrier	107	45	-41	0	3																																																								
Pile Cap and Formation of new road	107	45	-41	0	3																																																								
Utilities Diversion	104	45	-41	0	3																																																								
Erection of structural steel post for noise barrier	100	45	-41	0	3																																																								
<u>Installation of steel member and noise barrier panel</u>																																																													
Erection of steel member and noise barrier panel at north bound	100	45	-41	0	3																																																								
Erection of steel member and noise barrier panel at south bound	100	45	-41	0	3																																																								
<u>Roadworks</u>																																																													
<u>Roadworks at north bound</u>																																																													
Road Drainage	103	45	-41	0	3																																																								
Road Surfacing	109	45	-41	0	3																																																								
Roadlighting and E&M works	96	45	-41	0	3																																																								
<u>Roadworks at south bound</u>																																																													
Road Drainage	103	45	-41	0	3																																																								
Road Surfacing	109	45	-41	0	3																																																								
Roadlighting and E&M works	96	45	-41	0	3																																																								
<u>Landscaping Works</u>																																																													
Landscaping works at north bound	100	45	-41	0	3																																																								
Landscaping works at south bound	100	45	-41	0	3																																																								
Predicted Noise Level, Leq (30mins), dB(A)						69	69	69	69	69	71	71	71	71	70	70	70	70	69	69	72	72	73	73	73	73	73	73	71	71	71	71	71	71	71	71	71	70	73	73	74	74	73	73	73	71	71	69	69	72	72	72	72	70	70	69	73	73	69	73	72

[1] The distances refer to the horizontal distances between the notional source positions in work zones and the concerned NSRs

**Appendix 4.9a Construction Noise Assessment (Mitigated Scenario)**

Location: Shatin

NAP ID: STTNV2

Assessment Floor: G/F

Floor mP.D.: 44

Construction Activity	SWL, dB(A)	Distance, m [1]	Distance Correction, dB(A)	Screening Correction, dB(A)	Façade Correction, dB(A)	2028				2029				2030				2031				2032				2033																																			
						S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D				
<b>Shatin Side</b>																																																													
<b>Work Zone 1</b>																																																													
<b>Preparatory works</b>																																																													
Site Clearance and Tree felling / transplant	106	32	-38.1	0	3	71	71	71	71	71																																																			
<b>Reprovisioning of Footbridge NF74</b>																																																													
Construction of temporary footbridge	107	67	-44.5	0	3	65	65	65	65	65	65	65	65																																																
Demolition of existing footbridge	102	67	-44.5	0	3									61	61	61	61																																												
Construction of new footbridge (including demolition of temporary footbridge)	107	67	-44.5	0	3													65	65	65	65	65	65	65	65	65	65	65	65																																
<b>Road Widening and Installation of Noise Barrier</b>																																																													
<b>Widening works at north bound</b>																																																													
Slope Formation / Upgrading Works	108	32	-38.1	0	3					73	73	73	73																																																
Foundation of Noise Barrier	107	32	-38.1	0	3									73	73	73	73																																												
Pile Cap, L-retaining Wall and Formation of new road	107	32	-38.1	0	3									72	72	72	72	72	72	72	72	72	72	72	72	72	72	72	72																																
Utilities Diversion	104	32	-38.1	0	3													69	69	69	69	69	69	69	69	69	69	69	69																																
Erection of structural steel post for noise barrier	100	32	-38.1	0	3													65	65	65	65	65	65	65	65																																				
<b>Widening works at central divider</b>																																																													
Foundation of Noise Barrier	107	32	-38.1	0	3																					72	72	72	72	72	72	72	72																												
Pile Cap and Footing	107	32	-38.1	0	3																					72	72	72	72	72	72	72	72																												
Erection of structural steel post for noise barrier	100	32	-38.1	0	3																					65	65	65	65	65	65	65	65																												
<b>Widening works at south bound</b>																																																													
Slope Formation / Upgrading Works	108	32	-38.1	0	3									73	73	73	73	73	73	73	73	73	73	73	73	73	73	73	73																																
Foundation of Noise Barrier	107	32	-38.1	0	3													72	72	72	72	72	72	72	72	72	72	72	72																																
Pile Cap and Formation of new road	107	32	-38.1	0	3													72	72	72	72	72	72	72	72	72	72	72	72	72	72	72	72																												
Utilities Diversion	104	32	-38.1	0	3													69	69	69	69	69	69	69	69	69	69	69	69																																
Erection of structural steel post for noise barrier	100	32	-38.1	0	3													65	65	65	65	65	65	65	65	65	65	65	65																																
<b>Installation of steel member and noise barrier panel</b>																																																													
Erection of steel member and noise barrier panel at north bound	100	32	-38.1	0	3																									65	65	65	65	65	65	65	65																								
Erection of steel member and noise barrier panel at south bound	100	32	-38.1	0	3																									65	65	65	65	65	65	65	65																								
<b>Roadworks</b>																																																													
<b>Roadworks at north bound</b>																																																													
Road Drainage	103	32	-38.1	0	3																													68	68																										
Road Surfacing	109	32	-38.1	0	3																													74	74																										
Roadlighting and E&M works	96	32	-38.1	0	3																													61	61																										
<b>Roadworks at south bound</b>																																																													
Road Drainage	103	32	-38.1	0	3																																	68	68																						
Road Surfacing	109	32	-38.1	0	3																																	74	74																						
Roadlighting and E&M works	96	32	-38.1	0	3																																	61	61																						
<b>Landscaping Works</b>																																																													
Landscaping works at north bound	100	32	-38.1	0	3																																	65	65	65																					
Landscaping works at south bound	100	32	-38.1	0	3																																	65	65	65																					
Predicted Noise Level, Leq (30mins), dB(A)						72	72	72	72	72	74	74	74	74	73	73	73	73	72	72	75	75	76	76	76	76	76	76	74	74	74	74	74	74	74	74	74	73	76	76	77	77	76	76	76	74	74	72	72	75	75	75	75	73	73	72	76	76	72	76	75

[1] The distances refer to the horizontal distances between the notional source positions in work zones and the concerned NSRs











**Appendix 4.9a Construction Noise Assessment (Mitigated Scenario)**

**Location:** Shatin

**NAP ID:** KTV2

Assessment Floor G/F  
Floor mP.D. 21.6

Construction Activity	SWL, dB(A)	Distance, m [1]	Distance Correction, dB(A)	Screening Correction, dB(A)	Façade Correction, dB(A)	2028				2029				2030				2031				2032				2033																																							
						S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D																				
<b>Shatin Side</b>																																																																	
<b>Work Zone 1</b>																																																																	
<b>Preparatory works</b>																																																																	
Site Clearance and Tree felling / transplant	106	130	-50.3	0	3					58	58	58	58	58																																																			
<b>Road Widening and Installation of Noise Barrier</b>																																																																	
<b>Widening works at north bound</b>																																																																	
Slope Formation / Upgrading Works	108	130	-50.3	0	3									61	61	61		61	61	61	61																																												
Foundation of Noise Barrier	107	130	-50.3	0	3													60	60	60		60	60	60																																									
Pile Cap, L-retaining Wall and Formation of new road	107	130	-50.3	0	3																	60	60	60																																									
Utilities Diversion	104	130	-50.3	0	3																	57	57	57																																									
Erection of structural steel post for noise barrier	100	130	-50.3	0	3																																																												
<b>Widening works at central divider</b>																																																																	
Foundation of Noise Barrier	107	130	-50.3	0	3																																																												
Pile Cap and Footing	107	130	-50.3	0	3																																																												
Erection of structural steel post for noise barrier	100	130	-50.3	0	3																																																												
<b>Widening works at south bound</b>																																																																	
Slope Formation / Upgrading Works	108	130	-50.3	0	3																																																												
Foundation of Noise Barrier	107	130	-50.3	0	3																																																												
Pile Cap and Formation of new road	107	130	-50.3	0	3																																																												
Utilities Diversion	104	130	-50.3	0	3																																																												
Erection of structural steel post for noise barrier	100	130	-50.3	0	3																																																												
<b>Installation of steel member and noise barrier panel</b>																																																																	
Erection of steel member and noise barrier panel at north bound	100	130	-50.3	0	3																																																												
Erection of steel member and noise barrier panel at south bound	100	130	-50.3	0	3																																																												
<b>Roadworks</b>																																																																	
<b>Roadworks at north bound</b>																																																																	
Road Drainage	103	130	-50.3	0	3																																																												
Road Surfacing	109	130	-50.3	0	3																																																												
Roadlighting and E&M works	96	130	-50.3	0	3																																																												
<b>Roadworks at south bound</b>																																																																	
Road Drainage	103	130	-50.3	0	3																																																												
Road Surfacing	109	130	-50.3	0	3																																																												
Roadlighting and E&M works	96	130	-50.3	0	3																																																												
<b>Landscaping Works</b>																																																																	
Landscaping works at north bound	100	130	-50.3	0	3																																																												
Landscaping works at south bound	100	130	-50.3	0	3																																																												
<b>Work Zone 2</b>																																																																	
<b>Preparatory works</b>																																																																	
Site Clearance and Tree felling / transplant	106	83	-46.4	0	3																																																												
<b>Road Widening and Installation of Noise Barrier</b>																																																																	
<b>Widening works at north bound</b>																																																																	
Slope Formation / Upgrading Works	108	83	-46.4	0	3																																																												
Foundation of Noise Barrier	106	83	-46.4	0	3																																																												
Pile Cap and Formation of new road	107	83	-46.4	0	3																																																												
Utilities Diversion	104	83	-46.4	0	3																																																												
Erection of structural steel post for noise barrier	100	83	-46.4	0	3																																																												
<b>Widening works at south bound</b>																																																																	
Slope Formation / Upgrading Works	108	83	-46.4	0	3																																																												
<b>Roadworks</b>																																																																	
<b>Roadworks at north bound</b>																																																																	
Road Drainage	106	83	-46.4	0	3																																																												
Road Surfacing	109	83	-46.4	0	3																																																												
Roadlighting and E&M works	96	83	-46.4	0	3																																																												
<b>Roadworks at south bound</b>																																																																	
Road Drainage	106	83	-46.4	0	3																																																												
Road Surfacing	109	83	-46.4	0	3																																																												
Roadlighting and E&M works	96	83	-46.4	0	3																																																												
<b>Landscaping Works</b>																																																																	
Landscaping works at north bound	100	83	-46.4	0	3																																																												
Predicted Noise Level, Leq (30mins), dB(A)						58	58	58	58	58	61	61	61	61	61	61	61	61	60	60	63	63	64	64	64	66	66	66	65	65	65	66	66	66	66	66	66	65	65	68	68	68	69	68	69	68	67	67	67	66	66	65	65	66	69	69	67	61	65	68	69	68	62	65	64

[1] The distances refer to the horizontal distances between the notional source positions in work zones and the concerned NSRs

### Appendix 4.9a Construction Noise Assessment (Mitigated Scenario)

Location: Shatin  
 NAP ID: MWG1  
 Assessment Floor: 3/F  
 Floor mP.D.: 31.6

Construction Activity	SWL, dB(A)	Distance, m [1]	Distance Correction, dB(A)	Screening Correction, dB(A)	Façade Correction, dB(A)	2030				2031				2032				2033																											
						S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D												
<b>Shatin Side</b>																																													
<b>Work Zone 2</b>																																													
<b>Preparatory works</b>																																													
Site Clearance and Tree felling / transplant	106	62	-43.8	0	3	65	65	65	65	65	65																																		
<b>Road Widening and Installation of Noise Barrier</b>																																													
<u>Widening works at north bound</u>																																													
Slope Formation / Upgrading Works	108	62	-43.8	0	3					67	67	67	67	67																															
Foundation of Noise Barrier	106	62	-43.8	0	3									65	65	65	65	65	65																										
Pile Cap and Formation of new road	107	62	-43.8	0	3											66	66	66	66	66	66																								
Utilities Diversion	104	62	-43.8	0	3													64	64	64	64																								
Erection of structural steel post for noise barrier	100	62	-43.8	0	3													59	59	59																									
<u>Widening works at south bound</u>																																													
Slope Formation / Upgrading Works	108	62	-43.8	0	3													67	67	67	67	67	67	67	67																				
<b>Roadworks</b>																																													
<u>Roadworks at north bound</u>																																													
Road Drainage	106	62	-43.8	0	3																	65	65	65																					
Road Surfacing	109	62	-43.8	0	3																	68	68	68																					
Roadlighting and E&M works	96	62	-43.8	0	3																	55	55	55																					
<u>Roadworks at south bound</u>																																													
Road Drainage	106	62	-43.8	0	3																					65	65	65																	
Road Surfacing	109	62	-43.8	0	3																					68	68	68	68																
Roadlighting and E&M works	96	62	-43.8	0	3																					55	55	55	55																
<b>Landscaping Works</b>																																													
Landscaping works at north bound	100	62	-43.8	0	3																																								
Predicted Noise Level, Leq (30mins), dB(A)						65	65	65	65	65	65	67	67	67	67	67	67	65	65	69	69	70	70	69	69	67	67	67	67	67	67	67	67	65	70	70	68	55	65	70	70	68	60	59	59

[1] The distances refer to the horizontal distances between the notional source positions in work zones and the concerned NSRs



















