Wan Bao Construction Limited

Environmental Management Plan

for

Construction of Green Park at Stanley Bay

Contract No. : *CV*/2006/EMP-01

Revision No. : 1

Date : *1 – 1 – 2006*

Prepared by :	K.K. Lai	Date :	1 – 1 – 2006
	(Project Manager)		
Approved by :	K.T. Wong	Date :	1 – 1 – 2006

(General Manager)

Revision History

Revision Date	Description	Sections Affected	Revised By	Approved By
1-1-2006	First issue	-	-	KT Wong

Section

Title

Contents

Page No.

1.0	Ba	ckground	1
	1.1	Project Description	1
	1.2	Requirements for an Environmental Management Plan (EMP)	1
	1.3	Objectives of the EMP	1
2.0	Pol	licy Statement	2
3.0		ganisation Structure and Responsibilities	
	3.1	Site Organisation Diagram	3
	3.2	Environmental Team Structure	3
4.0	Pro	pmoting Environmental Awareness	3
	4.1	Reporting and Communication Procedures	4
5.0	Lis	t of Legal and Other Requirements	5
6.0		t of Significant Environmental Aspects	
7.0		vironmental Control Procedures and Mitigation Measures	
8.0		vironmental Emergency Procedures	
9.0		vironmental Inspection, Monitoring, Auditing and Corrective Actions	6
10.0	Env	vironmental Records	6

List of Tables

Table 1	An Outline of Training Requirement for all Relevant Staff(s)
Table 2	Summary of Communication Means & Actions
Table 3	A list of environmental procedure(s) / instruction(s) for site staff and subcontractors' staff
Table 4	Example of Environmental Records

List of Appendices

Appendix A	Site Maps
Appendix B	List of Sensitive Receivers

1.0 Background

1.1 **Project Description**

One of the Government Departments of the Hong Kong Special Administrative Region (hereafter referred as 'the Client') intends to construct a Green Park in Stanley Bay of South Hong Kong Island and its essential associated infrastructure (hereafter referred as the Project). Proposed facilities will include the Green Park, entertainment, retail and dining outlets, resort hotel with 100 rooms, and essential supporting services. New roads, public transport interchange, vehicle parking areas, and associated stations will provide direct transport links to the proposed park.

Wan Bao Construction Limited (WBC) has been awarded the Contract CV/2006/EMP-01 for Stanley Bay's Development Contract by Client. The construction work is scheduled to commence in Jan 2006 and will be completed tentatively by Dec 2008. The contract include the following designated projects:

Western Storm water Drainage Channel at Stanley Bay;

• Construction and operation of drainage channel which discharges into an area, where is 800 m away from the St. Stephen's Beach;

Chung Hom Kok Link Road;

• Construction of the site formation for about 1.5 km of a road, which is an expressway.

A site-map showing the site boundary is shown in Appendix A.

1.2 Requirements for an Environmental Management Plan (EMP)

This Environmental Management Plan (EMP) sets out in detail the approach of WBC to be adopted in managing and controlling potential environmental impacts from our work activities at the Project, for meeting all relevant legal and contractual environmental requirements. Where necessary, this EMP will be revised to include recommended changes made by the Environmental Consultant appointed by the Project Proponent. Any amendment to the approved EMP shall require subsequent approval by the Client.

ABC Environmental Services and Consulting (ABC) has been commissioned by WBC to undertake environmental management and monitoring works in compliance with the legal and contractual requirements for the Contract CV/2006/EMP-01 of Infrastructure for Stanley Bay's development

1.3 Objectives of the EMP

This EMP sets out in detail the approach, which WBC will adopt in dealing with the potential environmental impacts from various different construction activities throughout the construction of the Contracts. It provides systematic procedures for minimising environmental impacts from that may arise from the construction work.

The main objectives of the EMP are to:

- 1. Make reference to statutory environmental requirements and obligations;
- 2. Clarify responsibilities of various parties involved;
- 3. Address all potential significant environmental impacts;
- 4. Set out environmental management approach;
- 5. Initiate and implement mitigation measures;
- 6. Set out housekeeping practices; and
- 7. Set out emergency procedures.

2.0 Policy Statement

The commitment from top management is important to drive the staff for implementing the environmental management system, thus an environmental management policy is communicated to all staff and given as below:

Environmental Management Policy for Contract No. CV/2006/EMP-01

Wan Bao Construction Limited (WBC) undertakes the design, construction, operation, maintenance and project management of building and civil engineering works in both public and private sectors.

Protecting the environment is the responsibility of every staff in the organization. WBC is committed to sustainable construction and minimise any adverse impact on the environment resulting from our business activities.

We are committed to delivering services with minimal impact to the environment through the following principles: -

- ★ Focus on prevention of pollution, waste minimization and resource conservation as critical considerations within our core management processes.
- ★ Compliance with all applicable local legislation and other relevant requirements.
- ★ Regular performance reviews to ensure that environmental objectives and the requirements of Interested Parties are met.
- ★ Provision of staff training to ensure understanding, implementation and development of these principles throughout our business.
- ★ Continual improvement

All staff will follow the requirements of the Environmental Management System in the performance of their tasks and will ensure this policy is supported and maintained. This policy will be communicated to our customers, suppliers, and subcontractors. It will also be made available to the public whenever requested.


Endorsed by

1

K, T. Wong General Manager of Wan Bao Construction Limited 1/1/2006

3.0 Organisation Structure and Responsibilities

3.1 Site Organisation Diagram



3.2 Environmental Team Structure

Refer to EMS Manual (EM - 01) and Waste Management Plan (WMP - CV/2006/EMP-01) for details on roles and environmental responsibilities of project key staff.

4.0 **Promoting Environmental Awareness**

Briefing and instruction will be given to site staff as well as subcontractors to increase awareness and draw attention to environmental management issues. Table 1 shows the outline of training requirements for all relevant staff. An outline of the training requirements will also be distributed to relevant site staff and subcontractors etc. (EMS procedure EP-03 - EMS Training). Details of training procedure are given in:

Table 1 – An Outline of Training Requirement for all Relevant Staff

Staff	Training Needs	Schedule / Frequency
Project Manager / Environmental Manager	Distribution of Environmental Management Plan	Beginning of Work
Relevant site supervisors / foremen identified by Environmental Manager	Mitigation and management measures specific to their scope of work	Before the staff commences the particular work
All site worker (including sub-contractor site staff)	General environmental management instructions / procedures, including site house keeping, waste reduction, noise control, dust control, environmental management policy, targets, measures for subcontractor performance etc	Induction for the workers

In general, the training sessions will be conducted by the EM / Project Environmental Engineer (PEE) on a regular basis or where it is deemed necessary. In order to establish a better community relationship, EM / PEE is responsible to organise meetings and establish communicate channels to convey WBC's environmental commitment and performance to the nearby community.

4.1 Reporting and Communication Procedures

Effective 2-way communications will be developed to initiate the flow of environmental information among different parties. The communication is mainly achieved through the site environmental logbook, site meeting, environmental briefing, site inspection, etc. and environmental awareness promotion activities between WBC and site works and sub-contractors. The major channels of communications are summarised in the following Table 2.

Means	Frequency	Purpose/Action	Responsible Party
Site Environmental Log Book	Continually	Written record of what has been observed and done related to environmental issues, including implementation status of mitigation measures.	PEE.
Site meeting	Monthly	Face-to-face communications between construction and client.	PEE
Environmental briefing / training session	Monthly	Briefing or Training on environmental issues to key site staff and staff of subcontractors.	PEE
Environmental Complaint Log	When necessary	To handle and respond environmental complaints.	PEE
Site Inspection	Continually	Promote awareness of environmental procedures among workers and sub- contractors via continual and casual conversations.	PEE.

Table 2 – Summary of Communication Means & Actions

Refer to EP-07 Enquiry / Complaint / Nonconformity Handling

5.0 List of Legal and Other Requirements

Refer to Legal Register and Other Requirements (LR - 01)

6.0 List of Significant Environmental Aspects

PM and EM shall ensure that all environmental aspects that may pose significant impacts to the environment are under control. A list of environmental aspects of this project can be referred to EAR-01. A list of Sensitive Receivers is shown in Appendix B.

7.0 Environmental Control Procedures and Mitigation Measures

All operations and activities associated with the significant aspects will be properly controlled, through the adoption of operational control procedures, which include Environmental Procedures (EPs) and Environmental Instructions (EIs). These procedures and instructions will be communicated to personnel whose tasks may result in significant environmental aspects.

A list of environmental procedures and instructions for site staff and subcontractors' staff is shown in Table 1.

Document No.	Title of document
EM-01	Environmental Management System Manual
EP-01	Identification of Environmental Aspects and Significance Evaluation
EP-02	Review of Legal and Other Requirements
EP-03	Training
EP-04	Control of Documents
EP-05	Environmental Emergency Preparedness and Response
EP-06	Environmental Monitoring and Evaluation of Compliance
EP-07	Enquiry / Complaints / Nonconformity Handling
EP-08	Control of Records
EP-09	Internal Audit
ÆI-01	Environmental Management Plan
ÆI-02	Waste Management Plan
EI-03	Environmental Instruction for Building and Civil Engineering Design
EI-04	Best Practices for Construction Activities
ÆI-05	Selection and Control of Contractors Regarding Environmental Performance
£I-06	Green Purchasing for Office
£I-07	Environmental Office Practices
£I-08	Environmental Practices for Using Company's Car

Table 3 - A list of environmental procedure(s) / instruction(s) for site staff and subcontractors' staff.

8.0 Environmental Emergency Procedures

Refer to EI-04 Section H, which sets out instructions for Potential Accidents and Emergency Situations

9.0 Environmental Inspection, Monitoring, Auditing and Corrective Actions

Environmental audit will be carried out on a monthly basis with the attendance of the PEE, Environmental Team (ET) and the Agent. The areas of audit will cover difference aspects, such as air, noise, water and waste, and their pollution controls and mitigation measures for both within and outside the site area.

Detail of auditing requirements can refer to EP-09; if found any nonconformity items, refer to EP-07 for more details of corrective action procedure.

10.0 Environmental Records

Apart from the regular reviews / audits or inspections, there are some typical environmental records are shown in the following Table 4 which they should be necessary to maintain during the construction periods.

<i>Table 4 – Example</i>	of Environmental Records

Category	Environmental Record	Responsible Personnel	Retention
General	 Environmental training records Monthly environmental audit results and/or reports (i.e. completed environmental checklist) Equipment maintenance/repair records Monitoring of noise, air quality or effluent discharge as required by the EPD Copies of all plans, reports, applications, 	Project Manager	1 year after project completion
	 etc. submitted to the project Proponent and the EPD Correspondence with EPD, Project Proponent and other parties in relation to environmental matters Minutes of monthly environmental review meeting 		
Air Pollution Control	 Notification to EPD in accordance with the Air Pollution Control (Construction Dust) Regulation Records on maintenance/cleaning of wheel washing facility Specific Process Licence 	Project Manager	1 year after project completion
Noise Control	 Construction Noise Permits Noise Emission Labels for hand-held percussive breakers and air compressors 	Project Manager	1 year after project completion
Water Pollution Control	 Effluent Discharge Licenses Construction site drainage plans	Project Manager	1 year after project

WBC


Environmental Management Plan *Construction of Green Park at Stanley Bay*

Revision Number : 1 Date : 1-1-2006

Form Number : EF-EI01-01

Category	Environmental Record	Responsible Personnel	Retention
	• Records on maintenance/cleaning of wastewater treatment plant		completion
	• Records on toilet sewage disposal		
	 Chemical Waste Producer Registration Chemical waste collection and disposal records 	Project Manager	1 year after project completion
	• Trip tickets and documentation for collection and tipping of waste and waste removal		
	• Dumping licences		
Waste Management	• Copies of relevant licenses of the waste haulers and waste collectors		
эманицетенг	• Records on quantities of waste reused/recycled		
	• Records on quantities of excavated material transferred to other construction sites for use		
	• Records on quantities of excavated material transferred to public filling areas		
	Waste disposal records		
	Material Safety Data Sheets	Project	1 year after
Chemical Storage	• A log of chemicals inventories	Manager	project completion
	Environmental complaint records	Project	1 year after
Complaints	• Correspondence with relevant parties	Manager	project completion
Environmental Emergency	Emergency Incident Reports	Project Manager	1 year after project completion
Non-compliance	Non-compliance Reports	Project	1 year after
	• Non-compliance Reports Logbook	Manager	project completion
Environmental Costs and Savings	Table of Environmental Costs and Savings	Project Manager	1 year after project completion

Refer to EI-04 Best Practices for Construction for list of environmental records.



Appendix B – List of Sensitive Receivers(s)

Air Sensitive Receivers No.	Fig. No.	Description	Air Sensitive Receivers	Horizontal Distance to Worksite (m)
1	Appendix A	Stanley Bay Estate – Block 1	X	60
2	As above	Stanley Bay Estate – Block 2	X	70
3	As above	Stanley Bay Estate – Block 3	X	80
4	As above	Stanley Bay Estate – Block 4	X	120
5	As above	Stanley Bay Estate – Block 5	X	130
6	As above	Stanley Bay Estate – Block 6	X	85
7	As above	Stanley Bay Estate – Block 7	X	90
5	As above	Local school	X	65
6	As above	Local shopping arcade	X	65

Noise Sensitive Receivers No.	Fig. No.	Description	Noise Sensitive Receivers	Horizontal Distance to Worksite (m)
1	Appendix A	Stanley Bay Estate – Block 1	X	60
2	As above	Stanley Bay Estate – Block 2	X	70
3	As above	Stanley Bay Estate – Block 3	X	80
4	As above	Stanley Bay Estate – Block 4	X	120
5	As above	Stanley Bay Estate – Block 5	X	130
6	As above	Stanley Bay Estate – Block 6	X	85
7	As above	Stanley Bay Estate – Block 7	X	90
5	As above	Local school	X	65
6	As above	Local shopping arcade	X	65

Water Sensitive Receivers No.	Fig. No.	Description	Water Sensitive Receivers (Stream, River and Sea)	Horizontal Distance to Worksite (m)
<i>N/А</i>	N/A	N/A	N/A	N/A